

# GOEMANS APPLIANCES

1-877-463-6267

HST # 105167993

WWW.GOEMANS.COM

Find us on Facebook at [www.facebook.com/GoemansAppliances](http://www.facebook.com/GoemansAppliances)

## PACKING SLIP

# HB00016424-1

Salesperson: JASON NG  
Purchase Date: 10/14/17  
Invoice Finished Date:  
Delivery/Pickup Date: Apr 02, 2018  
Invoice Type: VBL  
Date Printed: Oct 14, 2017  
Page: 1

### ONLINE BANKING ACCOUNT

**BILL TO:** 4168372530

TUGAMBAYEVA & MOUKHAMEDIROV, TATYANA &  
RINAT

226 INVERNESS WAY

LOT # 119

BRADFORD, ON L3Z 0W6

TEL# (416) 837-2530

BUS# (416) 356-5917

**SHIP TO:** 4168372530

TUGAMBAYEVA & MOUKHAMEDIROV, TATYANA &  
RINAT

226 INVERNESS WAY

LOT # 119

BRADFORD, ON L3Z 0W6

TEL# (416) 837-2530

BUS# (416) 356-5917

Directions: 6TH LINE & SIMCOE ROAD - ANDY MINATEL AT 416-697-1593 OR TRAILER AT 905-551-1181

QTY	LOC	MODEL #	SERIAL #	COLOUR	BRAND - DESCRIPTION
1		JGRP436WP			
-1		P-CJEN-1710-10P			
		This special order product requires a 50% deposit & is considered FINAL SALE. x _____ PLEASE ALLOW UP TO 4-12 WEEKS FOR DELIVERY OF THIS PIECE.			
1		JXW9036WP			
-1		P-CJEN-1710-10P			
1		JPk36BNXEPS			
		This special order product requires a 50% deposit & is considered FINAL SALE. x _____ PLEASE ALLOW UP TO 4-12 WEEKS FOR DELIVERY OF THIS PIECE.			
1		JDTSS244GP			
-1		P-CJEN-1710-10P			
1		WM4370HKA		Black Stain	LGE, WAFL: WASHER, FRONT LOAD, LARGE CAPA 5.2 CUFT,STEAM,14 CYC/11 OPTS,HEATER,1200RPM,NFC
		MUST PURCHASE OPTIONAL HOSES			
1		DLEX4370K		Black Stain	LGE, DREFL: DRYER, ELECTRIC - TO MATCH LAR 7.4 CUFT,TRUESTEAM,RACK,NEVERUST DRUM,14 CYC,10 OP
1		HOSE KIT WS5SS-ST			REL, ALAU: ACCESSORY, LAUNDRY
1		HOSE LNDRY 6FT 48			HOSE-KIT,FOR STEAM DRYER,ALSO INCLUDES 1 WSHR HOSE
1		VHOOD3WM	UNASSIGNED INSTALLER		REL, AWA: ACCESSORY WASHER 1X 6 FT WASH HOSE, 3/4,STAINLESS STEEL BRAID
		Mounting of hood to wall, and vent connection up to 4ft in length. No hole cutting.			

- All products remain the property of Goemans until paid in full.
- Removal of old appliances at owner's risk and must be disconnected.
- Please refer to delivery/installation brochures for important details.
- All authorized returned products will be subject to a restocking charge.
- Interest of 18% per annum will be charged on overdue accounts.
- Upon delivery customer agrees to accept service in accordance with manufacturer's warranty.
- This sales invoice is based on delivery within 12 months from date of purchase. After 12 months (or if market conditions adversely change) Goemans reserves the right to review pricing/delivery on this order and offer our customers options to accommodate these changes. Any & all date sensitive supplier promotions are exempt from the 12 month price guarantee and must be taken by the promotional delivery deadline.

WHITE CUSTOMER COPY

PINK GOEMANS COPY

# GOEMANS APPLIANCES

1-877-463-6267

HST # 105167993

WWW.GOEMANS.COM

Find us on Facebook at [www.facebook.com/GoemansAppliances](http://www.facebook.com/GoemansAppliances)

## PACKING SLIP

# HB00016424-1

Salesperson: JASON NG  
Purchase Date: 10/14/17  
Invoice Finished Date:  
Delivery/Pickup Date: Apr 02, 2018  
Invoice Type: VBL  
Date Printed: Oct 14, 2017  
Page: 2

### ONLINE BANKING ACCOUNT

**BILL TO:** 4168372530

TUGAMBAYEVA & MOUKHAMEDAROV, TATYANA &  
RINAT  
226 INVERNESS WAY  
LOT # 119

BRADFORD, ON L3Z 0W6 BUS# (416) 356-5917  
TEL# (416) 837-2530

**SHIP TO:** 4168372530

TUGAMBAYEVA & MOUKHAMEDAROV, TATYANA &  
RINAT  
226 INVERNESS WAY  
LOT # 119

BRADFORD, ON L3Z 0W6 BUS# (416) 356-5917  
TEL# (416) 837-2530

Directions: 6TH LINE & SIMCOE ROAD - ANDY MINATEL AT 416-697-1593 OR TRAILER AT 905-551-1181

QTY	LOC	MODEL #	SERIAL #	COLOUR	BRAND - DESCRIPTION
1		P-DELIVERY \$2,500-4,999			
-1		SALES DELIVERY ALLOWANCE Payment			MASTER CARD

- All products remain the property of Goemans until paid in full.
- Removal of old appliances at owner's risk and must be disconnected.
- Please refer to delivery/installation brochures for important details.
- All authorized returned products will be subject to a restocking charge.
- Interest of 18% per annum will be charged on overdue accounts.
- Upon delivery customer agrees to accept service in accordance with manufacturer's warranty.
- This sales invoice is based on delivery within 12 months from date of purchase. After 12 months (or if market conditions adversely change) Goemans reserves the right to review pricing/delivery on this order and offer our customers options to accommodate these changes. Any & all date sensitive supplier promotions are exempt from the 12 month price guarantee and must be taken by the promotional delivery deadline.


WHITE CUSTOMER COPY

PINK GOEMANS COPY

## 36" PRO-STYLE® GAS RANGES


JGRP536WP, JLRP536WP, **JGRP436WP**, JLRP436WP – 35<sup>7</sup>/<sub>8</sub>" x 38<sup>3</sup>/<sub>4</sub>" x 29<sup>1</sup>/<sub>4</sub>"

## PRODUCT DIMENSIONS



FRONT VIEW

MODEL #		JGRP536WP JLRP536WP <b>JGRP436WP</b> JLRP436WP	
		in	cm
<b>A</b>	Overall width	35 <sup>7</sup> / <sub>8</sub>	91.1
<b>B</b>	Height of island trim backsplash	3	7.6
<b>C</b>	Height of bullnose	2 <sup>1</sup> / <sub>4</sub>	5.5
<b>D</b>	Height of control panel	5 <sup>3</sup> / <sub>8</sub>	13.5
<b>E</b>	Space between door and control panel	<sup>7</sup> / <sub>8</sub>	2.0
<b>F</b>	Height of door	20 <sup>3</sup> / <sub>4</sub>	52.5
<b>G</b>	Height to top of handle	19 <sup>3</sup> / <sub>8</sub>	49.0
<b>H</b>	Space between door and lower panel	1	2.5
<b>I</b>	Height of lower panel	5 <sup>1</sup> / <sub>2</sub>	14.0
<b>J</b>	Depth with control panel overhang	27 <sup>3</sup> / <sub>8</sub>	69.5
<b>K</b>	Depth with handle	29 <sup>1</sup> / <sub>4</sub>	74.2
<b>L</b>	Depth with door fully open	45 <sup>3</sup> / <sub>4</sub>	116.2



TOP VIEW


**IMPORTANT:** Dimensional specifications are provided for planning purposes only.Do not make any cutouts based on this information. Refer to the Installation Guide *before* selecting cabinetry, verifying electrical/gas connections, making cutouts or beginning installation.

All Jenn-Air® appliances are appropriately UL, CUL or CSA approved.

## 36" PRO-STYLE® GAS RANGES

JGRP536WP, JLRP536WP, JGRP436WP, JLRP436WP – 35<sup>7</sup>/<sub>8</sub>" x 38<sup>3</sup>/<sub>4</sub>" x 29<sup>1</sup>/<sub>4</sub>"

## DIMENSIONS AS INSTALLED



MODEL #		JGRP536WP JLRP536WP JGRP436WP JLRP436WP	
		in	cm
<b>A*</b>	Height to top of grates (min.)	36 <sup>3</sup> / <sub>4</sub>	93.3
<b>B*</b>	Height to top of cooking surface (min.)	35 <sup>3</sup> / <sub>4</sub>	90.8
<b>C*</b>	Height to top of door (min.)	27 <sup>3</sup> / <sub>8</sub>	69.5
<b>D*</b>	Height to top of handle (min.)	25 <sup>7</sup> / <sub>8</sub>	65.7
<b>E*</b>	Height to top of lower panel (min.)	5 <sup>7</sup> / <sub>8</sub>	14.9
<b>F</b>	Depth with door fully open	45 <sup>3</sup> / <sub>4</sub>	116.2
<b>G</b>	Depth with handle	29 <sup>1</sup> / <sub>4</sub>	74.2
<b>H</b>	Depth with control panel overhang	27 <sup>3</sup> / <sub>8</sub>	69.5
<b>I</b>	Depth without control panel	23 <sup>1</sup> / <sub>2</sub>	59.5
<b>J</b>	Depth of island trim backsplash	2 <sup>1</sup> / <sub>4</sub>	5.7
<b>K</b>	Depth without door	24 <sup>5</sup> / <sub>8</sub>	62.5
<b>L</b>	Depth with door	26 <sup>3</sup> / <sub>4</sub>	68.0
<b>M*</b>	Height to top of island trim backsplash (min.)	38 <sup>3</sup> / <sub>4</sub>	98.4


\*Add 1<sup>3</sup>/<sub>4</sub>" (4.4 cm) to the height dimension when leveling legs are fully extended.

**IMPORTANT:** Dimensional specifications are provided for planning purposes only.  
**Do not make any cutouts based on this information.** Refer to the Installation Guide *before* selecting cabinetry, verifying electrical/gas connections, making cutouts or beginning installation.  
 All Jenn-Air® appliances are appropriately UL, CUL or CSA approved.


## 36" PRO-STYLE® GAS RANGES

JGRP536WP, JLRP536WP, JGRP436WP, JLRP436WP – 35<sup>7</sup>/<sub>8</sub>" x 38<sup>3</sup>/<sub>4</sub>" x 29<sup>1</sup>/<sub>4</sub>"


## OPENING/CLEARANCE DIMENSIONS



FRONT VIEW



SIDE VIEW



BACK VIEW

MODEL #	JGRP536WP JLRP536WP JGRP436WP JLRP436WP	
	in	cm
<b>A</b>	Width of combustable area above cooking surface (min.)	36 91.4
<b>B</b>	Width from range to fixed wall or other combustable material (min.)	6 15.2
<b>C</b>	Width of opening (min.)	36 <sup>1</sup> / <sub>4</sub> 92.1
<b>D</b>	Width of electrical installation area	28 71.1
<b>E</b>	Width of gas installation area	14 35.5
<b>F</b>	Width from side cabinet to gas installation area	6 15.2
<b>G*</b>	Height to bottom of uncovered wood or metal cabinet above cooking surface (min.)	42 106.7
<b>H</b>	Height to bottom of uncovered wood or metal cabinet (min.)	18 45.7
<b>I</b>	Height of electrical installation area	15 38.1
<b>J</b>	Depth of electrical and gas installation area	5 12.7
<b>K</b>	Height of gas installation area	3 7.6
<b>L</b>	Depth of upper cabinet (max.)	13 33.0
<b>M**</b>	Depth to wall (min.)	6 15.2
<b>N</b>	Width to electrical conduit	9 <sup>1</sup> / <sub>8</sub> 23.0
<b>O</b>	Width to gas inlet	14 <sup>3</sup> / <sub>8</sub> 36.5
<b>e</b>	Recommended electrical access location	
<b>g</b>	Recommended gas supply line location	

\*If installing a hood or hood liner above the range, follow the hood or hood liner instructions for dimensional clearances above the cooking surface.

\*\*If back wall is constructed of a combustable material and a backsplash is not installed, a 6" (15.2 cm) minimum clearance is required.

**ELECTRICAL REQUIREMENTS**

120 volt, 60 Hz, AC only, 15-amp fused, grounded circuit is required. A dedicated circuit is recommended.

**IMPORTANT:** Dimensional specifications are provided for planning purposes only.


**Do not make any cutouts based on this information.** Refer to the Installation Guide *before* selecting cabinetry, verifying electrical/gas connections, making cutouts or beginning installation.

All Jenn-Air® appliances are appropriately UL, CUL or CSA approved.


## 48"/36"/30" PRO-STYLE™ WALL-MOUNT HOODS

~~JXW9048WP – 48" x 19<sup>3</sup>/<sub>8</sub>" x 25"~~**JXW9036WP – 36" x 19<sup>3</sup>/<sub>8</sub>" x 25"**~~JXW9030WP – 30" x 19<sup>3</sup>/<sub>8</sub>" x 25"~~

## PRODUCT DIMENSIONS




FRONT VIEW



SIDE VIEW

(shown with optional duct cover)



TOP VIEW

MODEL #		<del>JXW9048WP</del>		<b>JXW9036WP</b>		<del>JXW9030WP</del>	
		in	cm	in	cm	in	cm
<b>A</b>	Overall width	<del>48</del>	<del>121.9</del>	36	91.4	<del>30</del>	<del>76.2</del>
<b>B</b>	Height without trim	<del>15<sup>3</sup>/<sub>4</sub></del>	<del>40.0</del>	15 <sup>3</sup> / <sub>4</sub>	40.0	<del>15<sup>3</sup>/<sub>4</sub></del>	<del>40.0</del>
<b>C</b>	Height of trim	<del>2<sup>1</sup>/<sub>4</sub></del>	<del>5.7</del>	2 <sup>1</sup> / <sub>4</sub>	5.7	<del>2<sup>1</sup>/<sub>4</sub></del>	<del>5.7</del>
<b>D</b>	Height without controls	<del>18</del>	<del>45.7</del>	18	45.7	<del>18</del>	<del>45.7</del>
<b>E</b>	Height with controls	<del>19<sup>3</sup>/<sub>8</sub></del>	<del>49.1</del>	19 <sup>3</sup> / <sub>8</sub>	49.1	<del>19<sup>3</sup>/<sub>8</sub></del>	<del>49.1</del>
<b>F</b>	Height of optional duct cover	<del>12</del>	<del>30.5</del>	12	30.5	<del>12</del>	<del>30.5</del>
<b>G</b>	Depth of optional duct cover	<del>12</del>	<del>30.5</del>	12	30.5	<del>12</del>	<del>30.5</del>
<b>H</b>	Depth of hood	<del>25</del>	<del>63.5</del>	25	63.5	<del>25</del>	<del>63.5</del>
<b>I</b>	<b>Vent collar diameter</b>	<del>9<sup>7</sup>/<sub>8</sub></del>	<del>25.1</del>	<b>9<sup>7</sup>/<sub>8</sub></b>	<b>25.1</b>	<del>9<sup>7</sup>/<sub>8</sub></del>	<del>25.1</del>


**IMPORTANT:** Dimensional specifications are provided for planning purposes only.Do not make any cutouts based on this information. Refer to the Installation Guide *before* selecting cabinetry, verifying electrical/gas connections, making cutouts or beginning installation.

All Jenn-Air® appliances are appropriately UL, CUL or CSA approved.

## 48"/36"/30" PRO-STYLE™ WALL-MOUNT HOODS

JXW9048WP – 48" x 19<sup>3</sup>/<sub>8</sub>" x 25"JXW9036WP – 36" x 19<sup>3</sup>/<sub>8</sub>" x 25"JXW9030WP – 30" x 19<sup>3</sup>/<sub>8</sub>" x 25"

## OPENING/CLEARANCE DIMENSIONS



FRONT VIEW

## ELECTRICAL REQUIREMENTS

120 volt, 60 Hz, AC only, 15-amp fused, electrical circuit is required. The knockout into the back of the terminal box is located on the right side.

## VENTING REQUIREMENTS

The hood is factory set for venting through the roof or wall. Do not terminate the vent in an attic or other enclosed area.

## LOCATION REQUIREMENTS

The minimum height from the floor to the top of the vent hood is 7' (2.1 m). The minimum height from the floor to the top of the optional duct cover is 8' (2.4 m).


MODEL #		JXW9048WP		JXW9036WP		JXW9030WP	
		in	cm	in	cm	in	cm
A	Width of vent entry location – ceiling option	12	30.5	12	30.5	12	30.5
B	Width of vent entry location – wall option	12	30.5	12	30.5	12	30.5
C	Width of cabinet opening (min.)	48	121.9	36	91.4	30	76.2
D	Height from vent entry location to ceiling – wall option (min.)	2	5.1	2	5.1	2	5.1
E	Height from hood to vent entry location – wall option (min.)	24	61.0	24	61.0	24	61.0
F	Height from hood to cooking surface (min.-max.)	30-36	76.2-91.4	30-36	76.2-91.4	30-36	76.2-91.4
G	Height from upper cabinet to countertop (min.)	18	45.7	18	45.7	18	45.7
H	Depth of vent entry location – ceiling option	12	30.5	12	30.5	12	30.5
v	Recommended vent entry location						

**IMPORTANT:** Dimensional specifications are provided for planning purposes only.


**Do not make any cutouts based on this information.** Refer to the Installation Guide *before* selecting cabinetry, verifying electrical/gas connections, making cutouts or beginning installation.

All Jenn-Air® appliances are appropriately UL, CUL or CSA approved.

## Product and Cabinet Opening Dimensions




For 4" (100 mm) toe kick, height of cabinet opening is 34 <sup>1</sup>/<sub>2</sub>" (863 mm).



- A. Insulation may be compressed (not used on all models).
- B. For panel-ready models, dishwasher depth is 24" (610 mm), not including the 3/4" (19 mm) custom door panel.
- C. Door handles may protrude forward of the face of the dishwasher, varies by model.

Check that all surfaces have no protrusions that would prohibit dishwasher installation.



- D. Measured from the lowest point on the underside of the countertop. May be reduced to 33 <sup>1</sup>/<sub>2</sub>" (851 mm) by removing the wheels and perforated area of insulation (blanket) on dishwasher.
- E. Minimum, measured from narrowest point of opening




## DRAIN REQUIREMENTS

- A new drain hose is supplied with your dishwasher. If drain hose is not long enough, use a new drain hose with a maximum length of 12 ft (3.7 m) that meets all current AHAM/IAPMO test standards, is resistant to heat and detergent, and fits the 1" (25 mm) drain connector of the dishwasher. See the "Tools and Parts" section at the front of the guide for part details and orders.

**NOTE:** Do not connect multiple drain hoses together.

- Make sure to connect drain hose to waste tee or disposer inlet above drain trap in house plumbing and 20" (508 mm) minimum above the floor. It is recommended that the drain hose either be looped up and securely fastened to the underside of the counter or be connected to an air gap.
- Make sure to use an air gap if the drain hose is connected to house plumbing lower than 20" (508 mm) above subfloor or floor.



- If required, the air gap should be installed in accordance with the air gap installation instructions. When you are connecting the air gap, a rubber hose (not provided) will be needed to connect to the waste tee or disposer inlet.
- Use 1/2" minimum I.D. drain line fittings.

## WATER SUPPLY REQUIREMENTS

- This dishwasher has a water heating feature and also requires a connection to a hot water supply line.
- A hot water line with 20 to 120 psi (138 to 862 kPa) water pressure can be verified by a licensed plumber.
- 120°F (49°C) water at dishwasher
- 3/8" O.D. copper tubing with compression fitting or flexible braided water supply line. See the "Tools and Parts" section at the front of the guide for part details and orders.

**NOTE:** 1/2" minimum plastic tubing is not recommended.

- A 90° elbow with 3/4" hose connection with rubber washer. See the "Tools and Parts" section at the front of the guide for part details and orders.
- Do not solder within 6" (152 mm) of the water inlet valve.
- If installed in new construction, make sure the house water supply lines have been flushed prior to connecting the dishwasher to remove any debris that may exist in the supply line.

**NOTE:** If replacing an existing dishwasher, it is recommended to install a new water line (see the "Tools and Parts" section at the front of the guide for part details) and drain hose (supplied) with the new dishwasher.

## ELECTRICAL REQUIREMENTS

Be sure that the electrical connection and wire size are adequate and in conformance with the National Electrical Code, ANSI/NFPA 70 - latest edition, and all local codes and ordinances.

A copy of the above code standards can be obtained from:

National Fire Protection Association  
1 Batterymarch Park  
Quincy, MA 02169-7471

### You Must Have:


- 120-volt, 60 Hz, AC-only, 15- or 20-amp, fused electrical supply
- Copper wire only
- A maximum of 2 field wiring supply conductors (12 AWG largest size) plus 1 grounding conductor are permitted in the terminal box.

### We Recommend:

- A time-delay fuse or circuit breaker
- A separate circuit

### If Connecting Dishwasher with a Power Cord:

- Use UL Listed power cord kit marked for use with dishwasher. See the "Tools and Parts" section at the front of the guide for part details and orders.
- Plug into a grounded 3 prong outlet. Outlet must meet all local codes and ordinances.



### If Connecting Dishwasher with Direct Wiring:

- Use flexible, armored, or nonmetallic sheathed copper wire with grounding wire that meets the wiring requirements for your home and local codes and ordinances.
- Use a UL Listed/CSA Approved metallic strain relief. See the "Tools and Parts" section at the front of the guide for part details and orders.

