

Schedule 1: Designer Information

Use one form for each individual who reviews and takes responsibility for design activities with respect to the project.

A. Project Information			
Building number, street name		Unit no.	Lot/con.
Municipality INNISFIL	Postal code	Plan number/ other description	
B. Individual who reviews and takes responsibility for design activities			
Name MICHAEL O'ROURKE		Firm HVAC DESIGNS LTD.	
Street address 375 FINLEY AVE		Unit no. 202	Lot/con. N/A
Municipality AJAX	Postal code L1S 2E2	Province ONTARIO	E-mail info@hvacdesigns.ca
Telephone number (905) 619-2300	Fax number (905) 619-2375	Cell number ()	
C. Design activities undertaken by individual identified in Section B. [Building Code Table 3.5.2.1 OF Division C]			
☐ House ☐ Small Buildings ☐ Large Buildings ☐ Complex Buildings ☒ HVAC – House ☐ Building Services ☐ Detection, Lighting and Power ☐ Fire Protection ☐ Building Structural ☐ Plumbing – House ☐ Plumbing – All Buildings ☐ On-site Sewage Systems			
Description of designer's work HEAT LOSS / GAIN CALCULATIONS DUCT SIZING RESIDENTIAL MECHANICAL VENTILATION DESIGN SUMMARY RESIDENTIAL SYSTEM DESIGN per CSA-F280-12		Model: 32-2-12 Project: ALCONA	
D. Declaration of Designer			
I <u>MICHAEL O'ROURKE</u> (print name)		declare that (choose one as appropriate):	
☐ I review and take responsibility for the design work on behalf of a firm registered under subsection 3.2.4. of Division C, of the Building Code. I am qualified, and the firm is registered, in the appropriate classes/categories. Individual BCIN: _____ Firm BCIN: _____			
☒ I review and take responsibility for the design and am qualified in the appropriate category as an "other designer" under subsection 3.2.5. of Division C, of the Building Code. Individual BCIN: <u>19669</u> Basis for exemption from registration and qualification: <u>O.B.C SENTENCE 3.2.4.1 (4)</u>			
☐ The design work is exempt from the registration and qualification requirements of the Building Code. Basis for exemption from registration and qualification: _____			
I certify that:			
1. The information contained in this schedule is true to the best of my knowledge. 2. I have submitted this application with the knowledge and consent of the firm.			
June 21, 2017 Date		 Signature of Designer	

NOTE:

- For the purposes of this form, "individual" means the "person" referred to in Clause 3.2.4.7(1) d) of Division C, Article 3.2.5.1. of Division C, and all other persons who are exempt from qualification under Subsections 3.2.4. and 3.2.5. of Division C.
- Schedule 1 is not required to be completed by a holder of a license, temporary license, or a certificate of authorization, issued by the Ontario Association of Architects. Schedule 1 is also not required to be completed by a holder of a license to practise, a limited license to practise, or a certificate of authorization, issued by the Association of Professional Engineers of Ontario.

Town of Innisfil Certified Model
04/01/2018 2:02:19 PM kgervais

SITE NAME: ALCONA		BUILDER: BAYVIEW WELLINGTON		TYPE: 32-2-12				GFA: 2070		DATE: Jun-17		WINTER NATURAL AIR CHANGE RATE 0.332		HEAT LOSS ΔT °F. 83		CSA-F280-12 SB-12 PACKAGE A1	
ROOM USE	EXP. WALL CLG. HT.	MBR	ENS	WIC	BED-2	BED-3	BED-4	LO# 74577	BATH	SUMMER NATURAL AIR CHANGE RATE 0.087	HEAT GAIN ΔT °F. 12						
GRS.WALL AREA	FACTORS	270	198	54	228	333	153		72								
	LOSS GAIN	LOSS GAIN	LOSS GAIN	LOSS GAIN	LOSS GAIN	LOSS GAIN	LOSS GAIN	LOSS GAIN	LOSS GAIN								
	NORTH	0 0 0	0 0 0	0 0 0	0 0 0	0 0 0	0 0 0	0 0 0	0 0 0								
	EAST	0 0 0	0 0 0	0 0 0	28 652 1159	33 769 1366	0 0 0	0 0 0	0 0 0								
	SOUTH	0 0 0	0 0 0	0 0 0	0 0 0	0 0 0	28 652 692	7 163 173									
	WEST	28 652 1159	13 303 538	0 0 0	0 0 0	0 0 0	0 0 0	0 0 0	0 0 0								
	SKYL.T.	40.8 101.3	0 0 0	0 0 0	0 0 0	0 0 0	0 0 0	0 0 0	0 0 0								
	DOORS	27.6 4.1	0 0 0	0 0 0	0 0 0	0 0 0	0 0 0	0 0 0	0 0 0								
	NET EXPOSED WALL	4.9 0.7	242 1182 173	185 904 133	54 264 39	200 977 143	300 1463 215	125 611 90	65 318 47								
	NET EXPOSED BSMT WALL ABOVE GR	3.9 0.6	0 0 0	0 0 0	0 0 0	0 0 0	0 0 0	0 0 0	0 0 0								
EXPOSED CLG	1.4 0.6	224 315 129	121 170 70	96 135 55	124 174 72	145 204 84	187 263 108	128 180 74									
NO ATTIC EXPOSED CLG	3.0 1.2	0 0 0	0 0 0	0 0 0	30 90 37	30 90 37	0 0 0	0 0 0									
EXPOSED FLOOR	2.8 0.4	0 0 0	0 0 0	0 0 0	154 430 63	0 0 0	0 0 0	0 0 0									
BASEMENT/CRAWL HEAT LOSS		0	0	0	0	0	0	0	0								
SLAB ON GRADE HEAT LOSS		0	0	0	0	0	0	0	0								
SUBTOTAL HT LOSS		2149	1377	399	2324	2526	1526		660								
SUB TOTAL HT GAIN		1461	740	94	1474	1701	890		294								
LEVEL FACTOR / MULTIPLIER		0.20 0.24	0.20 0.24	0.20 0.24	0.20 0.24	0.20 0.24	0.20 0.24		0.20 0.24								
AIR CHANGE HEAT LOSS		512	328	95	553	601	363		157								
AIR CHANGE HEAT GAIN		102	52	7	103	119	62		21								
DUCT LOSS		0	0	0	288	0	0		0								
DUCT GAIN		0	0	0	240	0	0		0								
HEAT GAIN PEOPLE	240	2	480	0	1	240	1		0								
HEAT GAIN APPLIANCES/LIGHTS		582	582	0	582	582	582		582								
TOTAL HT LOSS BTU/H		2661	1704	494	3165	3127	1889		818								
TOTAL HT GAIN x 1.3 BTU/H		3413	1030	131	3430	3434	2306		408								

ROOM USE	EXP. WALL CLG. HT.	GRT	FACTORS	WIC-2	LAUN	WIR	FOY	MUD	WOD	BAS
GRS.WALL AREA	FACTORS	410	410	120	63	40	189	160	324	1116
GLAZING	LOSS GAIN	LOSS GAIN	LOSS GAIN	LOSS GAIN	LOSS GAIN	LOSS GAIN	LOSS GAIN	LOSS GAIN	LOSS GAIN	LOSS GAIN
NORTH	23.3 15.8	0 0 0	0 0 0	0 0 0	0 0 0	0 0 0	0 0 0	0 0 0	23 536 364	6 140 95
EAST	23.3 41.4	0 0 0	0 0 0	12 280 497	0 0 0	0 0 0	6 140 248	0 0 0	0 0 0	0 0 0
SOUTH	23.3 24.7	48 1118 1187	0 0 0	0 0 0	0 0 0	0 0 0	0 0 0	0 0 0	0 0 0	0 0 0
WEST	23.3 41.4	0 0 0	83 1934 3435	0 0 0	0 0 0	0 0 0	0 0 0	0 0 0	0 0 0	0 0 0
SKYL.T.	40.8 101.3	0 0 0	0 0 0	0 0 0	0 0 0	0 0 0	0 0 0	0 0 0	0 0 0	0 0 0
DOORS	27.6 4.1	0 0 0	0 0 0	0 0 0	0 0 0	0 0 0	40 1106 162	20 553 81	0 0 0	20 553 81
NET EXPOSED WALL	4.9 0.7	362 1789 259	517 2526 370	108 528 77	63 308 45	40 195 29	143 699 102	140 684 100	193 760 111	234 922 135
NET EXPOSED BSMT WALL ABOVE GR	3.9 0.6	0 0 0	0 0 0	0 0 0	0 0 0	0 0 0	0 0 0	0 0 0	0 0 0	0 0 0
EXPOSED CLG	1.4 0.6	0 0 0	0 0 0	0 0 0	105 148 61	0 0 0	0 0 0	0 0 0	0 0 0	0 0 0
NO ATTIC EXPOSED CLG	3.0 1.2	0 0 0	0 0 0	0 0 0	0 0 0	0 0 0	0 0 0	0 0 0	0 0 0	0 0 0
EXPOSED FLOOR	2.8 0.4	0 0 0	0 0 0	0 0 0	54 151 22	0 0 0	0 0 0	0 0 0	0 0 0	0 0 0
BASEMENT/CRAWL HEAT LOSS		0	0	0	0	0	0	0	0	5186
SLAB ON GRADE HEAT LOSS		0	0	0	0	0	0	0	0	6800
SUB TOTAL HT LOSS		2887	3805	807	606	195	1944	1237	1296	6800
SUB TOTAL HT GAIN		1446	574	128	128	29	513	181	475	311
LEVEL FACTOR / MULTIPLIER		0.30 0.36	0.30 0.36	0.30 0.36	0.20 0.24	0.30 0.36	0.30 0.36	0.30 0.36	0.30 0.36	0.50 0.85
AIR CHANGE HEAT LOSS		1034	1597	289	144	70	696	443	475	6882
AIR CHANGE HEAT GAIN		101	266	40	9	2	36	13	0	55
DUCT LOSS		0	0	0	75	0	0	0	0	0
DUCT GAIN		0	0	0	72	0	0	0	0	0
HEAT GAIN PEOPLE	240	0	0	0	0	0	0	0	0	0
HEAT GAIN APPLIANCES/LIGHTS		582	582	582	582	0	0	582	0	582
TOTAL HT LOSS BTU/H		3921	6056	6049	825	265	2640	1880	1296	13682
TOTAL HT GAIN x 1.3 BTU/H		2768	798	1028	1028	40	713	1009	618	1232

SITE NAME: ALCONA

BUILDER: BAYVIEW WELLINGTON

DATE: Jun-17

GFA: 2070 LO# 74577

TYPE: 32-2-12

furnace pressure
furnace filter
a/c coil pressure
available pressure
for s/a & r/a0.6
0.05
0.2
0.35plenum pressure s/a
max s/a dif press. loss
min adjusted pressure s/a0.18
0.02
0.16r/a pressure
r/a grille press. Loss
adjusted pressure r/a0.17
0.02
0.15HEATING CFM 995
TOTAL HEAT LOSS 45,320
AIR FLOW RATE CFM 21.96COOLING CFM 995
TOTAL HEAT GAIN 28,406
AIR FLOW RATE CFM 35.03ARUE = 96 %
INPUT (BTU/H) = 66,000
OUTPUT (BTU/H) = 64,000^LENNOX
EL296UH070XE36B 70
FAN SPEED
LOW
MEDIUM
HIGHDESIGN CFM = 995
CH-M @ 8" E.S.P.

RUN COUNT	4th	3rd	2nd	1st	Bas
S/A	0	0	11	9	4
R/A	0	0	4	2	1

All S/A diffusers 4"x10" unless noted otherwise on layout.

All S/A runs 5'Ø unless noted otherwise on layout.

RUN #	1	2	3	4	5	6	7	8	9	10	11	12	13	14	15	16	17	18	19	20	21	22	23	24
ROOM NAME	MBR	ENS	WIC	BED-2	BED-3	BED-4	BATH	BED-2	BED-3	MBR	WIC-2	GRT	GRT	KIT	KIT	KIT	LAUN	W/R	FOY	MUD	BAS	BAS	BAS	BAS
RM LOSS MBH	1.33	1.70	0.49	1.58	1.56	1.89	0.82	1.58	1.56	1.33	1.10	1.96	1.96	2.02	2.02	2.02	2.02	0.83	2.64	1.88	3.74	3.74	3.74	3.74
CFM PER RUN HEAT	29	37	11	35	34	41	18	35	34	29	24	43	44	44	44	44	18	6	58	37	82	82	82	82
RM GAIN MBH	1.71	1.03	0.13	1.71	1.72	2.31	0.41	1.71	1.72	1.71	0.80	1.38	1.38	2.02	2.02	2.02	1.03	0.04	0.71	1.01	0.46	0.46	0.46	0.46
CFM PER RUN COOLING	60	36	5	60	60	81	14	60	60	60	28	48	48	71	71	71	36	1	25	35	16	16	16	16
ADJUSTED PRESSURE	0.17	0.17	0.17	0.17	0.17	0.16	0.17	0.17	0.17	0.17	0.17	0.17	0.17	0.17	0.17	0.17	0.17	0.17	0.17	0.17	0.16	0.16	0.16	0.16
ACTUAL DUCT LGH	62	81	36	37	54	41	58	42	63	56	41	24	33	33	37	35	30	26	31	19	38	28	25	34
EQUIVALENT LENGTH	140	150	120	190	120	140	160	180	140	150	120	130	140	110	120	120	170	110	90	140	90	110	150	120
TOTAL EFFECTIVE LENGTH	202	231	156	227	174	181	218	222	203	206	161	154	173	143	157	125	200	136	121	159	128	138	175	154
ADJUSTED PRESSURE	0.09	0.07	0.11	0.08	0.1	0.09	0.08	0.08	0.08	0.08	0.11	0.11	0.1	0.12	0.11	0.11	0.09	0.13	0.14	0.11	0.13	0.12	0.09	0.11
ROUND DUCT SIZE	5	4	4	5	5	5	4	5	5	5	4	4	4	5	5	5	4	4	4	5	5	5	5	5
HEATING VELOCITY (ft/min)	213	424	126	257	250	301	207	257	250	213	275	493	493	521	521	323	207	69	665	424	602	602	602	602
COOLING VELOCITY (ft/min)	441	413	57	441	441	595	161	441	441	441	321	551	551	521	521	521	407	11	287	402	117	117	117	117
OUTLET GRILL SIZE	3X10	3X10	3X10	3X10	3X10	3X10	3X10	3X10	3X10	3X10	3X10	3X10	3X10	3X10	3X10	3X10	3X10	3X10	3X10	3X10	3X10	3X10	3X10	3X10
TRUNK	B	B	C	C	D	C	D	C	D	B	D	C	D	A	B	B	C	C	D	C	A	A	D	D

RUN #	ROOM NAME	RM LOSS MBH	CFM PER RUN HEAT	RM GAIN MBH	ADJUSTED PRESSURE	ACTUAL DUCT LGH	EQUIVALENT LENGTH	TOTAL EFFECTIVE LENGTH	ADJUSTED PRESSURE	ROUND DUCT SIZE	HEATING VELOCITY (ft/min)	COOLING VELOCITY (ft/min)	OUTLET GRILL SIZE	TRUNK
TRUNK A	208	0.12	7	6	8	624	0	0.00	0	0.00	0	0	0	0
TRUNK B	183	0.07	7.7	8	8	412	0	0.00	0	0.00	0	0	0	0
TRUNK C	617	0.07	12.1	18	8	617	0	0.00	0	0.00	0	0	0	0
TRUNK D	375	0.08	9.7	12	8	563	0	0.00	0	0.00	0	0	0	0
TRUNK E	995	0.07	14.5	24	8	746	0	0.00	0	0.00	0	0	0	0
TRUNK F	0	0.00	0	0	8	0	0	0.00	0	0.00	0	0	0	0

SUPPLY AIR TRUNK SIZE	TRUNK CFM	STATIC PRESS.	ROUND DUCT	RECT DUCT	VELOCITY (ft/min)	TRUNK CFM	STATIC PRESS.	ROUND DUCT	RECT DUCT	VELOCITY (ft/min)	RETURN AIR TRUNK SIZE	TRUNK CFM	STATIC PRESS.	ROUND DUCT	RECT DUCT	VELOCITY (ft/min)
TRUNK A	208	0.12	7	6	8	624	0	0.00	0	0	TRUNK O	0	0.07	0	0	8
TRUNK B	183	0.07	7.7	8	8	412	0	0.00	0	0	TRUNK P	0	0.07	0	0	8
TRUNK C	617	0.07	12.1	18	8	617	0	0.00	0	0	TRUNK Q	0	0.07	0	0	8
TRUNK D	375	0.08	9.7	12	8	563	0	0.00	0	0	TRUNK R	0	0.07	0	0	8
TRUNK E	995	0.07	14.5	24	8	746	0	0.00	0	0	TRUNK S	0	0.07	0	0	8
TRUNK F	0	0.00	0	0	8	0	0	0.00	0	0	TRUNK T	0	0.07	0	0	8
											TRUNK U	0	0.07	0	0	8
											TRUNK V	0	0.07	0	0	8
											TRUNK W	0	0.07	0	0	8
											TRUNK X	995	0.07	14.5	26	8
											TRUNK Y	0	0.07	0	0	8
											TRUNK Z	0	0.07	0	0	8
											DROP	995	0.07	14.5	24	10
																597

RETURN AIR #	1	2	3	4	5	6	7	8	9	10	11	12	13	14	15	16	17	18	19	20	21	22	23	24
AIR VOLUME	120	120	120	120	360	0.15	0.15	0.15	0.15	0.15	0.15	0.15	0.15	0.15	0.15	0.15	0.15	0.15	0.15	0.15	0.15	0.15	0.15	0.15
PLENUM PRESSURE	55	36	42	47	27	1	1	1	1	1	1	1	1	1	1	1	1	1	1	1	1	1	1	1
ACTUAL DUCT LGH	145	150	145	145	185	0	0	0	0	0	0	0	0	0	0	0	0	0	0	0	0	0	0	0
EQUIVALENT LENGTH	200	186	187	192	212	1	1	1	1	1	1	1	1	1	1	1	1	1	1	1	1	1	1	1
TOTAL EFFECTIVE LH	0.07	0.08	0.08	0.08	0.07	14.80	14.80	14.80	14.80	14.80	14.80	14.80	14.80	14.80	14.80	14.80	14.80	14.80	14.80	14.80	14.80	14.80	14.80	14.80
ADJUSTED PRESSURE	6.6	6.3	6.3	6.3	9.9	0	0	0	0	0	0	0	0	0	0	0	0	0	0	0	0	0	0	0
ROUND DUCT SIZE	8	8	8	8	8	0	0	0	0	0	0	0	0	0	0	0	0	0	0	0	0	0	0	0
INLET GRILL SIZE	X	X	X	X	X	X	X	X	X	X	X	X	X	X	X	X	X	X	X	X	X	X	X	X
INLET GRILL SIZE	14	14	14	14	30	0	0	0	0	0	0	0	0	0	0	0	0	0	0	0	0	0	0	0

REVIEW AND TAKE RESPONSIBILITY FOR THE DESIGN WORK AND AMOUNT HEREIN IN THE APPROPRIATE CATEGORY AS AN "OTHER DESIGNER" UNDER DIVISION C 3 2 5 OF THE BUILDING CODE



MICHAEL J. SPENCE
INDIVIDUAL PCIN: 19669

TYPE: 32-2-12
SITE NAME: ALCONA

LO # 74577

RESIDENTIAL MECHANICAL VENTILATION DESIGN SUMMARY

COMBUSTION APPLIANCES		9.32.3.1(1)
a)	☒ Direct vent (sealed combustion) only	
b)	☐ Positive venting induced draft (except fireplaces)	
c)	☐ Natural draft, B-vent or induced draft gas fireplace	
d)	☐ Solid Fuel (including fireplaces)	
e)	☐ No Combustion Appliances	

HEATING SYSTEM	
☒ Forced Air	☐ Non Forced Air
☐ Electric Space Heat	

HOUSE TYPE		9.32.1(2)
☒ I	Type a) or b) appliance only, no solid fuel	
☐ II	Type I except with solid fuel (including fireplaces)	
☐ III	Any Type c) appliance	
☐ IV	Type I, or II with electric space heat	
☐	Other: Type I, II or IV no forced air	

SYSTEM DESIGN OPTIONS		O.N.H.W.P.
☐ 1	Exhaust only/Forced Air System	
☐ 2	HRV with Ducting/Forced Air System	
☒ 3	HRV Simplified/connected to forced air system	
☐ 4	HRV with Ducting/non forced air system	
☐	Part 6 Design	

TOTAL VENTILATION CAPACITY		9.32.3.3(1)
Basement + Master Bedroom	<u>2</u> @ 21.2 cfm	<u>42.4</u> cfm
Other Bedrooms	<u>3</u> @ 10.6 cfm	<u>31.8</u> cfm
Kitchen & Bathrooms	<u>4</u> @ 10.6 cfm	<u>42.4</u> cfm
Other Rooms	<u>5</u> @ 10.6 cfm	<u>53.0</u> cfm
Table 9.32.3.A. TOTAL		<u>169.6</u> cfm

PRINCIPAL VENTILATION CAPACITY REQUIRED		9.32.3.4.(1)
1 Bedroom	31.8	cfm
2 Bedroom	47.7	cfm
3 Bedroom	63.6	cfm
4 Bedroom	79.5	cfm
5 Bedroom	95.4	cfm
TOTAL		<u>79.5</u> cfm

SUPPLEMENTAL VENTILATION CAPACITY		9.32.3.5.
Total Ventilation Capacity	<u>169.6</u>	cfm
Less Principal Ventil. Capacity	<u>139</u>	cfm
Required Supplemental Capacity	<u>30.6</u>	cfm

PRINCIPAL EXHAUST FAN CAPACITY	
Model:	VANEE 60H-V+
Location:	BSMT
<u>139.0</u> cfm	<u>3.0</u> sones
☒ HVI Approved	

PRINCIPAL EXHAUST HEAT LOSS CALCULATION				
CFM	ΔT °F	FACTOR	% LOSS	
139.0 CFM	X 83 F	X 1.08	X	0.25

SUPPLEMENTAL FANS		NUTONE		
Location	Model	cfm	HVI	Sones
ENS	QTXEN050C	50	☒	0.3
BATH	QTXEN050C	50	☒	0.3
W/R	QTXEN050C	50	☒	0.3

HEAT RECOVERY VENTILATOR		9.32.3.11.
Model:	VANEE 60H-V+	
<u>139</u> cfm high	<u>50</u> cfm low	
<u>75</u> % Sensible Efficiency	☒ HVI Approved	
@ 32 deg F (0 deg C)		

LOCATION OF INSTALLATION	
Lot:	Concession
Township	Plan:
Address	
Roll #	Building Permit #

BUILDER:		BAYVIEW WELLINGTON
Name:		
Address:		
City:		
Telephone #:	Fax #:	

INSTALLING CONTRACTOR	
Name:	
Address:	
City:	
Telephone #:	Fax #:

DESIGNER CERTIFICATION	
I hereby certify that this ventilation system has been designed in accordance with the Ontario Building Code.	
Name:	HVAC Designs Ltd.
Signature:	
HRAI #	001820
Date:	June-17

HEAT LOSS AND GAIN SUMMARY SHEET**MODEL:** 32-2-12**BUILDER:** BAYVIEW WELLINGTON**SFQT:** 2070**LO#** 74577**SITE:** ALCONA**DESIGN ASSUMPTIONS**

HEATING	°F	COOLING	°F
OUTDOOR DESIGN TEMP.	-11	OUTDOOR DESIGN TEMP.	84
INDOOR DESIGN TEMP.	72	INDOOR DESIGN TEMP. (MAX 75°F)	72

BUILDING DATA

ATTACHMENT:	DETACHED	# OF STORIES (+BASEMENT):	3
FRONT FACES:	EAST	ASSUMED (Y/N):	Y
AIR CHANGES PER HOUR:	3.57	ASSUMED (Y/N):	Y
AIR TIGHTNESS CATEGORY:	AVERAGE	ASSUMED (Y/N):	Y
WIND EXPOSURE:	SHELTERED	ASSUMED (Y/N):	Y
HOUSE VOLUME (ft³):	27850.0	ASSUMED (Y/N):	Y
INTERNAL SHADING:	BLINDS/CURTAINS	ASSUMED OCCUPANTS:	5
INTERIOR LIGHTING LOAD (Btu/h/ft²):	1.75	DC BRUSHLESS MOTOR (Y/N):	Y
FOUNDATION CONFIGURATION	BCIN_1	DEPTH BELOW GRADE:	6.0 ft
LENGTH: 48.0 ft	WIDTH: 27.0 ft	EXPOSED PERIMETER:	150.0 ft

2012 OBC - COMPLIANCE PACKAGE

Component	Compliance Package A1	
	Nominal	Min. Eff.
Ceiling with Attic Space Minimum RSI (R)-Value	60	59.22
Ceiling Without Attic Space Minimum RSI (R)-Value	31	27.65
Exposed Floor Minimum RSI (R)-Value	31	29.8
Walls Above Grade Minimum RSI (R)-Value	22	17.03
Basement Walls Minimum RSI (R)-Value	20 ci	21.12
Below Grade Slab Entire surface > 600 mm below grade Minimum RSI (R)-Value	-	-
Edge of Below Grade Slab ≤ 600 mm Below Grade Minimum RSI (R)-Value	10	10
Heated Slab or Slab ≤ 600 mm below grade Minimum RSI (R)-Value	10	11.13
Windows and Sliding Glass Doors Maximum U-Value	0.28	-
Skylights Maximum U-Value	0.49	-
Space Heating Equipment Minimum AFUE	0.96	-
HRV Minimum Efficiency	75%	-
Domestic Hot Water Heater Minimum EF	0.8	-


INDIVIDUAL BCIN: 19669

MICHAEL O'ROURKE



Residential Foundation Thermal Load Calculator

Supplemental tool for CAN/CSA-F280

Weather Station Description		
Province:	Ontario	
Region:	Barrie	
Site Description		
Soil Conductivity:	Normal conductivity: dry sand, loam, clay	
Water Table:	Normal (7-10 m, 23-33 ft)	
Foundation Dimensions		
Floor Length (m):	14.6	 Insulation Configuration
Floor Width (m):	8.2	
Exposed Perimeter (m):	0.0	
Wall Height (m):	2.7	
Depth Below Grade (m):	1.83	
Window Area (m ²):	2.7	
Door Area (m ²):	1.9	
Radiant Slab		
Heated Fraction of the Slab:	0	
Fluid Temperature (°C):	33	
Design Months		
Heating Month	1	
Foundation Loads		
Heating Load (Watts):		1519

TYPE: 32-2-12

LO# 74577


Air Infiltration Residential Load Calculator

Supplemental tool for CAN/CSA-F280


Weather Station Description				
Province:	Ontario			
Region:	Barrie			
Weather Station Location:	Open flat terrain, grass			
Anemometer height (m):	10			
Local Shielding				
Building Site:	Suburban, forest			
Walls:	Heavy			
Flue:	Heavy			
Highest Ceiling Height (m):	6.71			
Building Configuration				
Type:	Detached			
Number of Stories:	Two			
Foundation:	Full			
House Volume (m ³):	788.6			
Air Leakage/Ventilation				
Air Tightness Type:	Present (1961-) (3.57 ACH)			
Custom BDT Data:	ELA @ 10 Pa.	1051.3 cm ²		
	3.57	ACH @ 50 Pa		
Mechanical Ventilation (L/s):	Total Supply	Total Exhaust		
	65.6	65.6		
Flue Size				
Flue #:	#1	#2	#3	#4
Diameter (mm):	0	0	0	0
Natural Infiltration Rates				
Heating Air Leakage Rate (ACH/H):	0.332			
Cooling Air Leakage Rate (ACH/H):	0.087			

TYPE: 32-2-12


LO# 74577



GROUND FLOOR PLAN 'B'
10'0" GARAGE



PARTIAL STD. GROUND FLOOR PLAN 'A' & 'B'
W.O.D. 9R AND MORE COND.



GROUND FLOOR PLAN 'A' AND 'B'

Town of Innisfil Certified Model
04/01/2018 2:02:42 PM kgervais



I MICHAEL O'ROURKE HAVE REVIEWED AND TAKE RESPONSIBILITY FOR THE DESIGN WORK AND AM QUALIFIED UNDER DIVISION C, 3.2.5 OF THE BUILDING CODE.
Michael O'Rourke
Michael O'Rourke, BCIN# 19669
HVAC DESIGNS LTD.

CSA-F280-12
PACKAGE A1

HVAC LEGEND								3.		
SYMBOL	DESCRIPTION	SYMBOL	DESCRIPTION	SYMBOL	DESCRIPTION	SYMBOL	DESCRIPTION	2.		
	FLOOR SUPPLY AIR GRILLE		6" SUPPLY AIR BOOT ABOVE		14"x8" RETURN AIR GRILLE		RETURN AIR STACK ABOVE	1.		
	FLOOR SUPPLY AIR GRILLE 6" BOOT		SUPPLY AIR STACK FROM 2nd FLOOR		30"x8" RETURN AIR GRILLE		RETURN AIR STACK 2nd FLOOR	No.	Description	Date
	SUPPLY AIR BOOT ABOVE		6" SUPPLY AIR STACK 2nd FLOOR		FRA- FLOOR RETURN AIR GRILLE		REDUCER	REVISIONS		

ALL DRAWINGS, CALCULATIONS AND SPECIFICATIONS ARE THE PROPERTY OF HVAC DESIGNS LTD.© AND MAY NOT BE REPRODUCED, MODIFIED OR ALTERED WITHOUT EXPRESSED WRITTEN CONSENT. THE DRAWINGS ARE DATED AND USE OF THESE DRAWINGS AFTER ONE YEAR FROM THE DATED NOTED IS NOT AUTHORIZED. CONTRACTOR SHALL CHECK ALL CONDITIONS BEFORE PROCEEDING WITH WORK. LATEST MUNICIPAL APPROVED DRAWINGS ONLY TO BE USED DURING INSTALLATION OF HEATING SYSTEM. HVAC DESIGNS LTD. IS NOT LIABLE FOR ANY CLAIMS ARISING FROM UNAUTHORIZED USE OF THE DRAWINGS OR FROM ANY CHANGES TO ACCEPTED STANDARDS AND/OR THE ONTARIO BUILDING CODE.

Client BAYVIEW WELLINGTON		 375 Finley Ave - Suite 202 - Ajax, Ontario L1S 2E2 Tel. 905.619.2300 - 905.420.5300 Fax 905.619.2375 Email: info@hvacdesigns.ca Web: www.hvacdesigns.ca Specializing in Residential Mechanical Design Services Installation to comply with the latest Ontario Building Code. All supply branch outlets shall be equipped with a manual balancing damper. Ductwork which passes through the garage or unheated spaces shall be adequately insulated and be gas-proofed.	Sheet Title FIRST FLOOR HEATING LAYOUT	
Project Name ALCONA INNISFIL, ONTARIO			Date JUNE/2017	
32-2-12			Scale 3/16" = 1'-0"	
2070 sqft			BCIN# 19669	
			LO# 74577	



Town of Innisfil Certified Model
04/01/2018 2:02:45 PM kgervais

I MICHAEL O'ROURKE HAVE REVIEW
AND TAKE RESPONSIBILITY FOR THE
DESIGN WORK AND AM QUALIFIED
UNDER DIVISION C, 3.2.5 OF THE
BUILDING CODE.
Michael O'Rourke
Michael O'Rourke, BCIN# 19669
HVAC DESIGNS LTD.

CSA-F280-12
PACKAGE A1

HVAC LEGEND								3.		
SYMBOL	DESCRIPTION	SYMBOL	DESCRIPTION	SYMBOL	DESCRIPTION	SYMBOL	DESCRIPTION	2.		
	FLOOR SUPPLY AIR GRILLE		6" SUPPLY AIR BOOT ABOVE		14"x8" RETURN AIR GRILLE		RETURN AIR STACK ABOVE	1.		
	FLOOR SUPPLY AIR GRILLE 6" BOOT		SUPPLY AIR STACK FROM 2nd FLOOR		30"x8" RETURN AIR GRILLE		RETURN AIR STACK 2nd FLOOR	No.	Description	Date
	SUPPLY AIR BOOT ABOVE		6" SUPPLY AIR STACK 2nd FLOOR		FRA- FLOOR RETURN AIR GRILLE		REDUCER	REVISIONS		

ALL DRAWINGS, CALCULATIONS AND SPECIFICATIONS ARE THE PROPERTY OF HVAC DESIGNS LTD.© AND MAY NOT BE REPRODUCED, MODIFIED OR ALTERED WITHOUT EXPRESSED WRITTEN CONSENT. THE DRAWINGS ARE DATED AND USE OF THESE DRAWINGS AFTER ONE YEAR FROM THE DATED NOTED IS NOT AUTHORIZED. CONTRACTOR SHALL CHECK ALL CONDITIONS BEFORE PROCEEDING WITH WORK. LATEST MUNICIPAL APPROVED DRAWINGS ONLY TO BE USED DURING INSTALLATION OF HEATING SYSTEM. HVAC DESIGNS LTD. IS NOT LIABLE FOR ANY CLAIMS ARISING FROM UNAUTHORIZED USE OF THE DRAWINGS OR FROM ANY CHANGES TO ACCEPTED STANDARDS AND/OR THE ONTARIO BUILDING CODE.

Client BAYVIEW WELLINGTON		 375 Finley Ave - Suite 202 - Ajax, Ontario L1S 2E2 Tel. 905.619.2300 - 905.420.5300 Fax 905.619.2375 Email: info@hvacdesigns.ca Web: www.hvacdesigns.ca Specializing in Residential Mechanical Design Services Installation to comply with the latest Ontario Building Code. All supply branch outlets shall be equipped with a manual balancing damper. Ductwork which passes through the garage or unheated spaces shall be adequately insulated and be gas-proofed.	Sheet Title SECOND FLOOR HEATING LAYOUT	
Project Name ALCONA INNISFIL, ONTARIO			Date JUNE/2017	
32-2-12			Scale 3/16" = 1'-0"	
2070 sqft			BCIN# 19669	
			LO# 74577	