

See attached sealed span charts
for all uniformly loaded beams.
*ALL JOISTS UNDER TILED APPLICATIONS
SHALL CONFORM TO OBC 9.30.06"

DESIGN ASSUMPTIONS
=====

Floor Loads:

T/C Live: 40 psf B/C Live: 0 psf
T/C Dead: 15 psf B/C Dead: 0 psf

Load Case: Live

Deflection Criteria: L/360 Live L/240 Total
Building Code: OBC-2012 (Limit States Design)

Building Type: Residential Importance Category: Normal(Part 9)
Design assumes continuous lateral bracing for both edges.
Joist Design Includes CCMC Vibration Check
Subfloor: 5/8" Canadian softwood plywood/Glued and Nailed
Ceiling: (None)
Blocking: (As Shown)

Reported Reactions are UN-FACTORED Loads

----- Connector List -----		
ID#	Model	Number

H1	HUS1.81/10	
H2	LT251188	
H3	LT251188	

----- JOIST MATERIALS -----		
Type	Product	Length

J1	11 7/8" NI-20	14' 0"
J2	v v	12' 0"
J3	v v	10' 0"
J4	11 7/8" NI-40x	20' 0"

----- FLUSH GIRDERS -----		
Type	Product	Length

G1	1 3/4"x11 7/8" 2.0E Microllam LVL	4' 0"
G2	v v	4' 0"
G3	11 7/8" NI-20	2' 0"
G4	v v	2' 0"
G5	1 3/4"x11 7/8" 2.0E Microllam LVL	4' 0"
G6	v v	20' 0"
G7	v v	14' 0"
G8	11 7/8" NI-40x	20' 0"
G9	v v	20' 0"
G10	v v	20' 0"

----- RIMBOARD & RIMJOISTS -----		
Type	Product	Length

R1	1-1/8" x 11-7/8" Rimboard	12' 0"

----- BLOCKING -----		
Type	Product	Length

E1	11 7/8" NI-40x	4' 0"

All product names are trademarks of their respective owners.

GENERAL NOTES

- The building design professional is responsible for the overall structural stability of the structure.
- Minimum required bearings for joists is 1.75" 3.5" for intermediate bearings
- Minimum required bearings for LVL shall be 3" or the minimum required length indicated on the individual beam/girder member ~~minimum design~~ ^{whichever is greater}. Each ply of the member shall be supported for the full member width for the full required minimum length of the bearing.
- Unless otherwise noted, continuous lateral support must be provided to the compression edge of all joist/girder/beam members. Full support is considered to be a maximum unbraced length of 24". This restraint is normally provided by sheathing and/or framing members which must be adequately anchored to the member and supporting structure.
- Provide lateral support to all joist/girder/beam member components at all bearing locations to prevent lateral displacement and rotation.
- All joist/girder/beam member components shall be used in a dry, well ventilated environment where the moisture content will not exceed 18% - such as in most covered structure
- Point loads from above shall be solidly blocked (squash blocks) to solid bearing below.
- All floor sheathing must be attached (as indicated - nailed only or nailed and glued) for the entire length of the joist.
- Blocking required over all interior supports under load bearing walls or when floor joists are not continuous over support, for cantilevered joists or when indicated on the Iavo
- All lengths and quantities must be verified prior to installation.

- — — — — Represents Wall Above
◇ Represents Load From Above

Job: A15-085

Scale: 3/16" = 1'


Keybuild 1.102.1 [Build 4]



DWG. NO.
Main FL L-5

Esquire Homes
Riverrun
Ajax, Ontario
The Dogwood
Elev. A, B & B Mod

Argo Lumber Inc.
10275 Keele Street
Maple ON L6A 1S7
Tel: 905-832-2251
Drawn By: Scott Sostar



DESIGN ASSUMPTIONS

Floor Loads:

T/C Live: 40 psf B/C Live: 0 psf
T/C Dead: 15 psf B/C Dead: 0 psf

Load Case: Live

Deflection Criteria: L/360 Live L/240 Total
Building Code: OBC-2012 (Limit States Design)

Building Type: Residential Importance Category: Normal(Part 9)
Design assumes continuous lateral bracing for both edges.
Joist Design Includes CCMC Vibration Check
Subfloor: 5/8" Canadian softwood plywood/Glued and Nailed
Ceiling: 1/2" gypsum
Blocking: (As Shown)

Reported Reactions are UN-FACTORED Loads

See attached sealed span charts
for all uniformly loaded beams.
"ALL JOISTS UNDER TILED APPLICATIONS
SHALL CONFORM TO OBC 9.30.06"

Connector List	
ID#	Model Number
H1	HUS1.81/10
H2	LT251188

JOIST MATERIALS		
Type	Product	Length
J1	11 7/8" NI-20	16' 0"
J2	v v	12' 0"
J3	11 7/8" NI-40x	20' 0"

FLUSH GIRDERS		
Type	Product	Length
G1	1 3/4"x11 7/8" 2.0E Microllam LVL	4' 0"
G2	v v	4' 0"
G3	v v	12' 0"
G4	v v	20' 0"

RIMBOARD & RIMJOISTS		
Type	Product	Length
R1	1-1/8" x 11-7/8" Rimboard	12' 0"

BLOCKING		
Type	Product	Length
E1	11 7/8" NI-40x	4' 0"

All product names are trademarks of their respective owners.

GENERAL NOTES

- The building design professional is responsible for the overall structural stability of the structure.
- Minimum required bearings for joists is 1.75" 3.5" for intermediate bearings
- Minimum required bearings for LVL shall be 3" or the minimum required length indicated on the individual beam/girder member component design, whichever is greater. Each ply of the member shall be supported for the full member width for the full required minimum length of the bearing.
- Unless otherwise noted, continuous lateral support must be provided to the compression edge of all joist/girder/beam members. Full support is considered to be a maximum unbraced length of 24". This restraint is normally provided by sheathing and/or framing members which must be adequately anchored to the member and supporting structure.
- Provide lateral support to all joist/girder/beam member components at all bearing locations to prevent lateral displacement and rotation.
- All joist/girder/beam member components shall be used in a dry, well ventilated environment where the moisture content will not exceed 16% - such as in most covered structure
- Point loads from above shall be solidly blocked (squash blocks) to solid bearing below.
- All floor sheathing must be attached (as indicated - nailed only or nailed and glued) for the entire length of the joist.
- Blocking required over all interior supports under load bearing walls or when floor joists are not continuous over support, for cantilevered joists or when indicated on the layo
- All lengths and quantities must be verified prior to installation.

— — — — — Represents Wall Above
◇ Represents Load From Above

Job: A15-085

Scale: 3/16" = 1'


Keybuild 1.102.1 [Build 4]



DWG. NO.
Second FL L-10

Esquire Homes
Riverrun
Ajax, Ontario
The Dogwood
Elev. A, B & B Mod

Argo Lumber Inc.
10275 Keele Street
Maple ON L6A 1S7
Tel: 905-832-2251
Drawn By: Scott Sostar



See attached sealed span charts
for all uniformly loaded beams.
"ALL JOISTS UNDER TILED APPLICATIONS
SHALL CONFORM TO OBC 9.30.06"

DESIGN ASSUMPTIONS

=====

Floor Loads:

T/C Live: 40 psf B/C Live: 0 psf
T/C Dead: 15 psf B/C Dead: 0 psf

Load Case: Live

Deflection Criteria: L/360 Live L/240 Total
Building Code: OBC-2012 (Limit States Design)

Building Type: Residential Importance Category: Normal(Part 9)
Design assumes continuous lateral bracing for both edges.
Joist Design Includes CCMC Vibration Check
Subfloor: 5/8" Canadian softwood plywood/Glued and Nailed
Ceiling: (None)
Blocking: (As Shown)

Reported Reactions are UN-FACTORED Loads

----- Connector List -----

ID#	Model Number
H1	HUS1.81/10
H2	LT251188
H3	LT251188

----- JOIST MATERIALS -----

Type	Product	Length
J1	11 7/8" NI-20	14' 0"
J2	v v	12' 0"
J3	v v	10' 0"
J4	11 7/8" NI-40x	22' 0"
J5	v v	20' 0"

----- FLUSH GIRDERS -----

Type	Product	Length
G1	1 3/4"x11 7/8" 2.0E Microllam LVL	4' 0"
G2	v v	4' 0"
G3	11 7/8" NI-20	2' 0"
G4	v v	2' 0"
G5	v v	4' 0"
G6	v v	4' 0"
G7	1 3/4"x11 7/8" 2.0E Microllam LVL	22' 0"
G8	v v	14' 0"
G9	11 7/8" NI-40x	20' 0"
G10	v v	20' 0"
G11	v v	20' 0"
G12	v v	20' 0"

----- RIMBOARD & RIMJOISTS -----

Type	Product	Length
R1	1-1/8" x 11-7/8" Rimboard	12' 0"

----- BLOCKING -----

Type	Product	Length
E1	11 7/8" NI-40x	4' 0"

All product names are trademarks of their respective owners.

GENERAL NOTES

1. The building design professional is responsible for the overall structural stability of the structure.
2. Minimum required bearings for joists is 1.75" 3.5" for intermediate bearings
3. Minimum required bearings for LVL shall be 3" or the minimum required length indicated on the individual beam/girder member ~~minimum design~~ ^{whichever is greater}. Each ply of the member shall be supported for the full member width for the full required minimum length of the bearing.
4. Unless otherwise noted, continuous lateral support must be provided to the compression edge of all joist/girder/beam members. Full support is considered to be a maximum unbraced length of 24". This restraint is normally provided by sheathing and/or framing members which must be adequately anchored to the member and supporting structure.
5. Provide lateral support to all joist/girder/beam member components at all bearing locations to prevent lateral displacement and rotation.
6. All joist/girder/beam member components shall be used in a dry, well ventilated environment where the moisture content will not exceed 18% - such as in most covered structure
7. Point loads from above shall be solidly blocked (squash blocks) to solid bearing below.
8. All floor sheathing must be attached (as indicated - nailed only or nailed and glued) for the entire length of the joist.
9. Blocking required over all interior supports under load bearing walls or when floor joists are not continuous over support, for cantilevered joists or when indicated on the Iavo
10. All lengths and quantities must be verified prior to installation.

— — — — — Represents Wall Above

◇ Represents Load From Above

Job: A15-085

Scale: 3/16" = 1'

Keybuild 1.102.1 [Build 4]



DWG. NO.

Main FL L-5

Esquire Homes
Riverrun
Ajax, Ontario
The Dogwood
Elev. A Upgrade

Argo Lumber Inc.
10275 Keele Street
Maple ON L6A 1S7
Tel: 905-832-2251
Drawn By: Scott Sostar

See attached sealed span charts
for all uniformly loaded beams.
"ALL JOISTS UNDER TILED APPLICATIONS
SHALL CONFORM TO OBC 9.30.06"

GENERAL NOTES

1. The building design professional is responsible for the overall structural stability of the structure.
2. Minimum required bearings for joists is 1.75" 3.5" for intermediate bearings
3. Minimum required bearings for LVL shall be 3" or the minimum required length indicated on the individual beam/girder member component design, whichever is greater. Each ply of the member shall be supported for the full member width for the full required minimum length of the bearing.
4. Unless otherwise noted, continuous lateral support must be provided to the compression edge of all joist/girder/beam members. Full support is considered to be a maximum unbraced length of 24". This restraint is normally provided by sheathing and/or framing members which must be adequately anchored to the member and supporting structure.
5. Provide lateral support to all joist/girder/beam member components at all bearing locations to prevent lateral displacement and rotation.
6. All joist/girder/beam member components shall be used in a dry, well ventilated environment where the moisture content will not exceed 16% - such as in most covered structure
7. Point loads from above shall be solidly blocked (squash blocks) to solid bearing below.
8. All floor sheathing must be attached (as indicated - nailed only or nailed and glued) for the entire length of the joist.
9. Blocking required over all interior supports under load bearing walls or when floor joists are not continuous over support, for cantilevered joists or when indicated on the layo
10. All lengths and quantities must be verified prior to installation.

— — — — — Represents Wall Above
◇ Represents Load From Above

Job: A15-085

Scale: 3/16" = 1'

Keybuild 1.102.1 [Build 4]



DWG. NO.

Second FL L-10

Argo Lumber Inc.
10275 Keele Street
Maple ON L6A 1S7
Tel: 905-832-2251
Drawn By: Scott Sostar

Esquire Homes
Riverrun
Ajax, Ontario
The Dogwood
Elev. A Upgrade

DESIGN ASSUMPTIONS
=====

Floor Loads:

T/C Live: 40 psf B/C Live: 0 psf
T/C Dead: 15 psf B/C Dead: 0 psf

Load Case: Live

Deflection Criteria: L/360 Live L/240 Total
Building Code: OBC-2012 (Limit States Design)

Building Type: Residential Importance Category: Normal(Part 9)
Design assumes continuous lateral bracing for both edges.
Joist Design Includes CCMC Vibration Check
Subfloor: 5/8" Canadian softwood plywood/Glued and Nailed
Ceiling: 1/2" gypsum
Blocking: (As Shown)

Reported Reactions are UN-FACTORED Loads

----- Connector List -----		
ID#	Model	Number
H1	HHUS410	
H2	HUS1.81/10	
H3	LT251188	
H4	LT251188	


----- JOIST MATERIALS -----		
Type	Product	Length
J1	11 7/8" NI-20	16' 0"
J2	v v	12' 0"
J3	11 7/8" NI-40x	20' 0"
----- FLUSH GIRDERS -----		

Type	Product	Length
G1	1 3/4"x11 7/8" 2.0E Microllam LVL	4' 0"
G2	v v	4' 0"
G3	v v	12' 0"
G4	v v	20' 0"
G5	v v	10' 0"

----- RIMBOARD & RIMJOISTS -----		
Type	Product	Length
R1	1-1/8" x 11-7/8" Rimboard	12' 0"

----- BLOCKING -----		
Type	Product	Length
E1	11 7/8" NI-40x	4' 0"

All product names are trademarks of their respective owners.



D:\00\Jobs\ 2015 Argo\A15-085\Floor\Dogwood Upgrade.LAY