

MODEL: UNIT 4201 - EL.A
+OPT. LOGGIA

Second Floor Framing
Do not scale - refer to architectural plans for dimensions

Products			
PlotID	Length	Product	Plies Net Qty
J1	18-00-00	11 7/8" N-20	1 5
J2	15-00-00	11 7/8" N-20	1 16
J3	13-00-00	11 7/8" N-20	1 10
J4	10-00-00	11 7/8" N-20	1 4
J5	2-00-00	11 7/8" N-20	1 1
B5	18-00-00	VERSALAM-12.2.OE	2 2
B9	16-00-00	VERSALAM-12.2.OE	2 2
B6	14-00-00	VERSALAM-12.2.OE	2 2
B8	13-00-00	VERSALAM-12.2.OE	2 2
B3	10-00-00	VERSALAM-12.2.OE	1 1
B1	6-00-00	VERSALAM-12.2.OE	1 1
B4	6-00-00	VERSALAM-12.2.OE	1 1
B2	5-00-00	VERSALAM-12.2.OE	2 2
B7	4-00-00	VERSALAM-12.2.OE	2 2

HANGER SCHEDULE	
H1	17251188 (TM)
H2	HUS1.8110(FM)
H3	HUS410(FM)
H4	HUS4(FM)
H5	LSSU410(FM)

NOTE:
TM-----TOP MOUNT HANGERS
FM-----FACE MOUNT HANGERS

RIMBOARD
1- 1/8" X 11 7/8" O.S.B.
SUBFLOOR - 5/8" NAILED & GLUED
APP - AS PER PLAN
BBO - BEAM BY OTHERS

Ceramic tile application as per O.B.C. 9.30.6
1-2X6 SPF#2 Squash Block req'd on one side of each joist under interior load bearing wall. Multiple Squash Blocks are req'd under concentrated loads.



JT/PL: 45147/98839

Builder: Gold Park

Location: Vaughan

Designer: NL

Alpha Roof Trusses Inc.

Salesperson: Derek

LI: 299725(290678)

Project: Pine Valley

Date: November 20, 2017


Sheet: 1 of 4

Maple, Ontario

Home Lumber

201004-CLD-00-04

70-03-00



Products				
PileID	Length	Product	Piles	Net Qty
J1	6-00-00	9 1/2" NI-20	1	8
J2	16-00-00	11 7/8" NI-20	1	17
J3	15-00-00	11 7/8" NI-20	1	10
J4	14-00-00	11 7/8" NI-20	1	25
J5	14-00-00	11 7/8" NI-20	2	4
J6	11-00-00	11 7/8" NI-20	1	8
J7	10-00-00	11 7/8" NI-20	1	11
J8	8-00-00	11 7/8" NI-20	1	7
J9	3-00-00	11 7/8" NI-20	1	2
J10	20-00-00	11 7/8" NI-40x	1	19
J11	20-00-00	11 7/8" NI-40x	2	4
B12	16-00-00	VERSALAM-12 2.0E	2	2
B11	14-00-00	VERSALAM-12 2.0E	2	2
B14	11-00-00	VERSALAM-12 2.0E	1	1
B13	10-00-00	VERSALAM-12 2.0E	1	1
B15	10-00-00	VERSALAM-12 2.0E	2	2
B18	9-00-00	VERSALAM-10 2.0E	1	2
B10	9-00-00	VERSALAM-12 2.0E	1	1
B16	6-00-00	VERSALAM-10 2.0E	1	1
B17	6-00-00	VERSALAM-10 2.0E	2	2

HANGER SCHEDULE				
H1	LT251188 (TM)			
H2	HUS18110(FM)			
H3	HUS410(FM)			
H5	LT259(TM)			
NOTE: TOP MOUNT HANGERS				
FM-----FACE MOUNT HANGERS				

RIMBOARD				
1	1-1/8" X 9 1/2" O.S.B.			
1	1-1/8" X 11 7/8" O.S.B.			
SUBFLOOR - 5/8" NAILED & GLUED				
APP - AS PER PLAN				
BBO - BEAM BY OTHERS				

Ceramic tile application as per O.B.C. 9.30.6
1-2X6 SPF#2 Squash Block req'd on one side of each joist under interior load bearing wall. Multiple Squash Blocks are req'd under concentrated loads.

First Floor Framing

Do not scale - refer to architectural plans for dimensions

1 1/2" BLOCKING
TOTAL LENGTH: 7'1"

REVISION: June 29, 2018
MODEL: UNIT 4201 - EL.A

70-03-00

Products				
PileID	Length	Product	Piles	Net Qty
J1	18-00-00	11 7/8" NI-20	1	5
J3	13-00-00	11 7/8" NI-20	1	26
J4	10-00-00	11 7/8" NI-20	1	4
J5	2-00-00	11 7/8" NI-20	1	1
B5	18-00-00	VERSALAM-12.2.0E	2	2
B9	16-00-00	VERSALAM-12.2.0E	2	2
B6	14-00-00	VERSALAM-12.2.0E	2	2
B8	13-00-00	VERSALAM-12.2.0E	2	2
B3	10-00-00	VERSALAM-12.2.0E	1	1
B1	6-00-00	VERSALAM-12.2.0E	1	1
B4	6-00-00	VERSALAM-12.2.0E	1	1
B2	5-00-00	VERSALAM-12.2.0E	2	2
B7	4-00-00	VERSALAM-12.2.0E	2	2

HANGER SCHEDULE

H1-----LT261198 (TM)
H2-----HUST1.8110(FM)
H3-----HGUS410(FM)
H4-----HUBX(FM)
H6-----LSSU410(FM)

NOTE:
TM-----TOP MOUNT HANGERS
FM-----FACE MOUNT HANGERS

RIMBOARD

1- 1/8" X 11 7/8" O.S.B.
SUBFLOOR - 3/4" NAILED & GLUED
APP - AS PER PLAN
BBO - BEAM BY OTHERS

Ceramic Tile


Ceramic tile application as per O.B.C. 9.30.6
1-2X6 SPF#2 Squash Block req'd on one side of each joist under interior load bearing wall. Multiple Squash Blocks are req'd under concentrated loads.

Second Floor Framing


Do not scale - refer to architectural plans for dimensions

MODEL: UNIT 4201 - EL.B
+OPT. LOGGIA

REVISION: June 29, 2018



JT/PL: 45147/98839 Builder: Gold Park Location: Vaughan Designer: NL Alpha Roof Trusses Inc. Salesperson: Derek
LI: 299725(290678) Project: Pine Valley Date: November 20, 2017 Sheet: 3 of 4 Maple, Ontario Home Lumber



Products				
ProdID	Length	Product	Pieces	Net Qty
J1	6-00-00	9 1/2" NI-20	1	8
J2	16-00-00	11 7/8" NI-20	1	17
J3	15-00-00	11 7/8" NI-20	1	10
J4	14-00-00	11 7/8" NI-20	1	25
J5	14-00-00	11 7/8" NI-20	2	4
J6	11-00-00	11 7/8" NI-20	1	8
J7	10-00-00	11 7/8" NI-20	1	11
J8	8-00-00	11 7/8" NI-20	1	7
J9	3-00-00	11 7/8" NI-20	1	2
J10	20-00-00	11 7/8" NI-40x	1	19
J11	20-00-00	11 7/8" NI-40x	2	4
B12	16-00-00	VERSALAM-12 2.0E	2	2
B11	14-00-00	VERSALAM-12 2.0E	2	2
B14	11-00-00	VERSALAM-12 2.0E	1	1
B13	10-00-00	VERSALAM-12 2.0E	1	1
B15	10-00-00	VERSALAM-12 2.0E	2	2
B18	9-00-00	VERSALAM-10 2.0E	1	2
B10	9-00-00	VERSALAM-12 2.0E	1	1
B16	6-00-00	VERSALAM-10 2.0E	1	1
B17	6-00-00	VERSALAM-10 2.0E	2	2

HANGER SCHEDULE

H1-----LT261188 (TM)

H2-----HUST1810(FM)

H3-----HGUS410(FM)

H5-----LT259(TM)

NOTE:

TM-----TOP MOUNT HANGERS

FM-----FACE MOUNT HANGERS

RIMBOARD

1-1/8" X 9 1/2" O.S.B.

1-1/8" X 11 7/8" O.S.B.

SUBFLOOR - 3/4" NAILED & GLUED

APP - AS PER PLAN

BBO - BEAM BY OTHERS

Ceramic tile application as per O.B.C. 9.30.6

1-2X6 SPF#2 Squash Block req'd on one side of each joist under interior load bearing wall. Multiple Squash Blocks are req'd under concentrated loads.

First Floor Framing

REVISION: June 29, 2018

MODEL: UNIT 4201 - E.L.B

Do not scale - refer to architectural plans for dimensions


11 7/8" BLOCKING

TOTAL LENGTH: 71'

JT/PL: 45147/98839 Builder: Gold Park Location: Vaughan Designer: NL Alpa Roof Trusses Inc. Salesperson: Derek

LI: 299725(290678) Project: Pine Valley Date: November 20, 2017 Sheet: 4 of 4 Maple, Ontario Home Lumber

70-03-00



Products				
PileID	Length	Product	Piles	Net Qty
J1	6-00-00	9 1/2" NI-20	1	8
J2	16-00-00	11 7/8" NI-20	1	17
J3	15-00-00	11 7/8" NI-20	1	10
J4	14-00-00	11 7/8" NI-20	1	25
J5	14-00-00	11 7/8" NI-20	2	4
J6	11-00-00	11 7/8" NI-20	1	8
J7	10-00-00	11 7/8" NI-20	1	11
J8	8-00-00	11 7/8" NI-20	1	7
J9	3-00-00	11 7/8" NI-20	1	2
J10	20-00-00	11 7/8" NI-40x	1	19
J11	20-00-00	11 7/8" NI-40x	2	4
B12	16-00-00	VERSALAM-12.2 OE	2	2
B11	14-00-00	VERSALAM-12.2 OE	2	2
B14	11-00-00	VERSALAM-12.2 OE	1	1
B13	10-00-00	VERSALAM-12.2 OE	1	1
B15	10-00-00	VERSALAM-12.2 OE	2	2
B18	9-00-00	VERSALAM-10.2 OE	1	1
B10	9-00-00	VERSALAM-12.2 OE	1	1
B16	6-00-00	VERSALAM-10.2 OE	1	1
B17	6-00-00	VERSALAM-10.2 OE	2	2

HANGER SCHEDULE	
H1	LT251188 (TM)
H2	HUS1.81/10(FM)
H3	HUS410(FM)
H5	LT259(TM)
NOTE:	
TM	TOP MOUNT HANGERS
FM	FACE MOUNT HANGERS

RIMBOARD	
1- 1/8" X 9 1/2" O.S.B.	
1- 1/8" X 11 7/8" O.S.B.	
SUBFLOOR - 3/4" NAILED & GLUED	
APP - AS PER PLAN	
BBO - BEAM BY OTHERS	

Ceramic tile application as per O.B.C. 9.30.6
1-2X6 SPF#2 Squash Block req'd on one side of each joist under interior load bearing wall. Multiple Squash Blocks are req'd under concentrated loads.

REVISION: June 29, 2018
MODEL: UNIT 4201 - EL.B
- OPT. LOGGIA

First Floor Framing
Do not scale - refer to architectural plans for dimensions

11 7/8" BLOCKING
TOTAL LENGTH: 71'

JT/PL: 45147/98839 Builder: Gold Park Location: Vaughan Designer: NL Alpha Roof Trusses Inc. Salesperson: Derek
LI: 299725(290678) Project: Pine Valley Date: December 18, 2017 Sheet: 4a of 4 Maple, Ontario Home Lumber



Single 1-3/4" x 11-7/8" VERSA-LAM® 2.0 3100 SP

Floor Beam\B01

Dry | 1 span | No cantilevers | 0/12 slope (deg)


November 20, 2017 15:37:52

BC CALC® Design Report



Build 6080
Job Name: 45147 (4201)
Address: Pine Valley
City, Province, Postal Code: Vaughan, ON
Customer: Gold Park
Code reports: CCMC 12472-R

File Name: 290678.bcc
Description: Second Floor Framing
Specifier:
Designer: NL
Company: Alpa Roof Trusses
Misc:



Reaction Summary (Down / Uplift) (lbs)

Bearing	Live	Dead	Snow	Wind
B0, 3-1/2"	777 / 0	308 / 0		
B1, 3-1/2"	1,223 / 0	476 / 0		

Load Summary

Tag	Description	Load Type	Ref.	Start	End	Live	Dead	Snow	Wind	Trib.
1		Unf. Area (lb/ft^2)	L	00-00-00	05-06-00	40	15			05-00-00
2		Conc. Pt. (lbs)	L	04-00-00	04-00-00	900	338			n/a

Controls Summary

	Factored Demand	Factored Resistance	Demand / Resistance	Load Case	Location
Pos. Moment	2,651 ft-lbs	17,696 ft-lbs	15%	1	03-10-07
End Shear	1,915 lbs	7,232 lbs	26.5%	1	04-02-10
Total Load Defl.	L/999 (0.017")	n/a	n/a	4	02-10-12
Live Load Defl.	L/999 (0.012")	n/a	n/a	5	02-10-12
Max Defl.	0.017"	n/a	n/a	4	02-10-12
Span / Depth	5.1	n/a	n/a		00-00-00
Squash Blocks	Valid				

Bearing Supports

	Dim. (L x W)	Demand	Demand/ Resistance Support	Demand/ Resistance Member	Material
B0 Wall/Plate	3-1/2" x 1-3/4"	1,551 lbs	41.2%	20.8%	Spruce Pine Fir
B1 Wall/Plate	3-1/2" x 1-3/4"	2,429 lbs	64.5%	32.5%	Spruce Pine Fir

Notes

Design meets Code minimum (L/240) Total load deflection criteria.
Design meets Code minimum (L/360) Live load deflection criteria.
Design meets User specified (1") Maximum Total load deflection criteria.
Calculations assume member is fully braced.
Resistance Factor phi has been applied to all presented results per CSA O86.
BC CALC® analysis is based on Canadian Limit States Design, as per NBCC 2010 and CSA O86.
Design based on Dry Service Condition.
Importance Factor : Normal Part code : Part 4

Disclosure

Completeness and accuracy of input must be verified by anyone who would rely on output as evidence of suitability for particular application. Output here based on building code-accepted design properties and analysis methods. Installation of Boise Cascade engineered wood products must be in accordance with current Installation Guide and applicable building codes. To obtain Installation Guide or ask questions, please call 1-800-964-6999 before installation.

BC CALC®, BC FRAMER®, AJS™, ALLJOIST®, BC RIM BOARD™, BCI®, BOISE GLULAM™, SIMPLE FRAMING SYSTEM®, VERSA-LAM®, VERSA-RIM PLUS®, VERSA-RIM®, VERSA-STRAND®, VERSA-STUD® are trademarks of Boise Cascade Wood Products L.L.C.





Double 1-3/4" x 11-7/8" VERSA-LAM® 2.0 3100 SP

Floor Beam\B02

Dry | 1 span | No cantilevers | 0/12 slope (deg)

November 20, 2017 13:50:18

BC CALC® Design Report



Build 6080

Job Name:

45147 (4201)

Address:

Pine Valley

City, Province, Postal Code: Vaughan, ON

Customer:

Gold Park

Code reports:

CCMC 12472-R

File Name: 290678.bcc


Description: Second Floor Framing

Specifier:

Designer: NL

Company: Alpa Roof Trusses

Misc:



Reaction Summary (Down / Uplift) (lbs)

Bearing	Live	Dead	Snow	Wind
B0, 3-1/2"	236 / 0	119 / 0		
B1, 3-1/2"	164 / 0	91 / 0		

Load Summary

Tag	Description	Load Type	Ref.	Start	End	Live 1.00	Dead 0.65	Snow 1.00	Wind 1.15	Trib.
1		Unf. Area (lb/ft^2)	L	00-00-00	05-00-00	40	15			01-00-00
2		Trapezoidal (lb/ft)	L	00-00-00	05-00-00	80	30			n/a
						0	0			n/a

Controls Summary

	Factored Demand	Factored Resistance	Demand / Resistance	Load Case	Location
Pos. Moment	447 ft-lbs	35,392 ft-lbs	1.3%	1	02-04-03
End Shear	338 lbs	14,464 lbs	2.3%	1	01-03-06
Total Load Defl.	L/999 (0.001")	n/a	n/a	4	02-05-09
Live Load Defl.	L/999 (0.001")	n/a	n/a	5	02-05-09
Max Defl.	0.001"	n/a	n/a	4	02-05-09
Span / Depth	4.6	n/a	n/a		00-00-00
Squash Blocks	Valid				

Bearing Supports

Bearing Support		Dim. (L x W)	Demand	Demand / Resistance Support	Demand / Resistance Member	Material
B0	Wall/Plate	3-1/2" x 3-1/2"	503 lbs	6.7%	3.4%	Spruce Pine Fir
B1	Wall/Plate	3-1/2" x 3-1/2"	360 lbs	4.8%	2.4%	Spruce Pine Fir

Notes

Design meets Code minimum (L/240) Total load deflection criteria.
 Design meets Code minimum (L/360) Live load deflection criteria.
 Design meets User specified (1") Maximum Total load deflection criteria.
 Calculations assume member is fully braced.
 Resistance Factor phi has been applied to all presented results per CSA O86.
 BC CALC® analysis is based on Canadian Limit States Design, as per NBCC 2010 and CSA O86.
 Design based on Dry Service Condition.
 Importance Factor : Normal Part code : Part 4

Nail one ply to another with
 3 1/2" spiral nails @ 12"
 o.c, staggered in 2 rows



S.152391



Single 1-3/4" x 11-7/8" VERSA-LAM® 2.0 3100 SP

Floor Beam\B03

Dry | 1 span | No cantilevers | 0/12 slope (deg)


November 20, 2017 14:50:12

BC CALC® Design Report



Build 6080
 Job Name: 45147 (4201)
 Address: Pine Valley
 City, Province, Postal Code: Vaughan, ON
 Customer: Gold Park
 Code reports: CCMC 12472-R

File Name: 290678.bcc
 Description: Second Floor Framing
 Specifier:
 Designer: NL
 Company: Alpha Roof Trusses
 Misc:



Total Horizontal Product Length = 09-08-00

Reaction Summary (Down / Uplift) (lbs)

Bearing	Live	Dead	Snow	Wind
B0, 3-1/2"	203 / 0	134 / 0		
B1, 3-1/2"	362 / 0	202 / 0		

Load Summary

Tag	Description	Load Type	Ref.	Start	End	Live 1.00	Dead 0.65	Snow 1.00	Wind 1.15	Trib.
1		Unf. Lin. (lb/ft)	L	00-00-00	09-08-00	27	14			n/a
2		Trapezoidal (lb/ft)	L	06-02-00	09-08-00	0	0			n/a
3		Conc. Pt. (lbs)	L	06-02-00	06-02-00	164	91			n/a

Controls Summary

	Factored Demand	Factored Resistance	Demand / Resistance	Load Case	Location
Pos. Moment	1,564 ft-lbs	17,696 ft-lbs	8.8%	1	06-02-00
End Shear	668 lbs	7,232 lbs	9.2%	1	08-04-10
Total Load Defl.	L/999 (0.032")	n/a	n/a	4	05-01-03
Live Load Defl.	L/999 (0.02")	n/a	n/a	5	05-01-03
Max Defl.	0.032"	n/a	n/a	4	05-01-03
Span / Depth	9.3	n/a	n/a		00-00-00
Squash Blocks	Valid				

Bearing Supports

	Dim. (L x W)	Demand	Demand/Resistance Support	Demand/Resistance Member	Material
B0 Wall/Plate	3-1/2" x 1-3/4"	473 lbs	12.6%	6.3%	Spruce Pine Fir
B1 Wall/Plate	3-1/2" x 1-3/4"	796 lbs	21.1%	10.6%	Spruce Pine Fir

Notes

Design meets Code minimum (L/240) Total load deflection criteria.
 Design meets Code minimum (L/360) Live load deflection criteria.
 Design meets User specified (1") Maximum Total load deflection criteria.
 Calculations assume member is fully braced.
 Resistance Factor phi has been applied to all presented results per CSA O86.
 BC CALC® analysis is based on Canadian Limit States Design, as per NBCC 2010 and CSA O86.
 Design based on Dry Service Condition.
 Importance Factor : Normal Part code : Part 4

Disclosure

Completeness and accuracy of input must be verified by anyone who would rely on output as evidence of suitability for particular application. Output here based on building code-accepted design properties and analysis methods. Installation of Boise Cascade engineered wood products must be in accordance with current Installation Guide and applicable building codes. To obtain Installation Guide or ask questions, please call 1-800-964-6999 before installation.

BC CALC®, BC FRAMER®, AJS™, ALLJOIST®, BC RIM BOARD™, BCI®, BOISE GLULAM™, SIMPLE FRAMING SYSTEM®, VERSA-LAM®, VERSA-RIM PLUS®, VERSA-RIM®, VERSA-STRAND®, VERSA-STUD® are trademarks of Boise Cascade Wood Products Ltd.



S 152392

BC CALC® Design Report




Dry | 1 span | No cantilevers | 0/12 slope (deg)

November 20, 2017 13:51:30

Build 6080
Job Name: 45147 (4201)
Address: Pine Valley
City, Province, Postal Code: Vaughan, ON
Customer: Gold Park
Code reports: CCMC 12472-R

File Name: 290678.bcc
Description: Second Floor Framing
Specifier:
Designer: NL
Company: Alpa Roof Trusses
Misc:



Total Horizontal Product Length = 05-10-00

Reaction Summary (Down / Uplift) (lbs)

Bearing	Live	Dead	Snow	Wind
B0, 3-1/2"	1,050 / 0	718 / 0		
B1, 3-1/2"	1,050 / 0	718 / 0		

Load Summary

Tag	Description	Load Type	Ref.	Start	End	Live	Dead	Snow	Wind	Trib.
1		Unf. Area (lb/ft²)	L	00-00-00	05-10-00	40	20			09-00-00
2		Unf. Lin. (lb/ft)	L	00-00-00	05-10-00		60			n/a

Controls Summary

	Factored Demand	Factored Resistance	Demand / Resistance	Load Case	Location
Pos. Moment	3,061 ft-lbs	17,696 ft-lbs	17.3%	1	02-11-00
End Shear	1,386 lbs	7,232 lbs	19.2%	1	01-03-06
Total Load Defl.	L/999 (0.023")	n/a	n/a	4	02-11-00
Live Load Defl.	L/999 (0.014")	n/a	n/a	5	02-11-00
Max Defl.	0.023"	n/a	n/a	4	02-11-00
Span / Depth	5.4	n/a	n/a		00-00-00
Squash Blocks	Valid				

Disclosure


Completeness and accuracy of input must be verified by anyone who would rely on output as evidence of suitability for particular application. Output here based on building code-accepted design properties and analysis methods. Installation of Boise Cascade engineered wood products must be in accordance with current Installation Guide and applicable building codes. To obtain Installation Guide or ask questions, please call 1-800-964-6999 before installation.

Bearing Supports

	Dim. (L x W)	Demand	Demand/ Resistance Support	Demand/ Resistance Member	Material
B0 Wall/Plate	3-1/2" x 1-3/4"	2,472 lbs	65.6%	33.1%	Spruce Pine Fir
B1 Wall/Plate	3-1/2" x 1-3/4"	2,472 lbs	65.6%	33.1%	Spruce Pine Fir

Notes

Design meets Code minimum (L/240) Total load deflection criteria.
Design meets Code minimum (L/360) Live load deflection criteria.
Design meets User specified (1") Maximum Total load deflection criteria.
Calculations assume member is fully braced.
Resistance Factor phi has been applied to all presented results per CSA O86.
BC CALC® analysis is based on Canadian Limit States Design, as per NBCC 2010 and CSA O86.
Design based on Dry Service Condition.
Importance Factor : Normal Part code : Part 4



BC CALC® Design Report



Dry | 2 spans | Left cantilever | 0/12 slope (deg)

November 20, 2017 13:53:40

Build 6080

Job Name:

45147 (4201)

Address:

Pine Valley

City, Province, Postal Code:

Vaughan, ON

Customer:

Gold Park

Code reports:

CCMC 12472-R

File Name: 290678.bcc


Description: Second Floor Framing

Specifier:

Designer: NL

Company: Alpa Roof Trusses

Misc:



Reaction Summary (Down / Uplift) (lbs)

Bearing	Live	Dead	Snow	Wind
B1, 3-1/2"	1,748 / 0	1,821 / 0		
B2, 3-1/2"	1,312 / 159	1,048 / 0		

Load Summary

Tag	Description	Load Type	Ref.	Start	End	Live 1.00	Dead 0.65	Snow 1.00	Wind 1.15	Trib.
1		Unf. Lin. (lb/ft)	L	00-00-00	17-09-00	27	74			n/a
2		Unf. Lin. (lb/ft)	L	11-00-00	14-04-00	27	14			n/a
3		Unf. Area (lb/ft^2)	L	14-04-00	17-09-00	40	15			05-00-00
4		Conc. Pt. (lbs)	L	00-00-00	00-00-00	1,050	718			n/a
5		Conc. Pt. (lbs)	L	11-00-00	11-00-00	236	119			n/a
6		Conc. Pt. (lbs)	L	14-04-00	14-04-00	362	202			n/a

Controls Summary

	Factored Demand	Factored Resistance	Demand / Resistance	Load Case	Location
Pos. Moment	8,267 ft-lbs	35,392 ft-lbs	23.4%	3	11-02-08
Neg. Moment	-5,937 ft-lbs	-35,392 ft-lbs	16.8%	2	02-03-00
End Shear	2,584 lbs	14,464 lbs	17.9%	3	16-05-10
Cont. Shear	2,638 lbs	14,464 lbs	18.2%	2	01-01-06
Total Load Defl.	L/781 (0.235")	0.764"	30.7%	10	10-06-04
Live Load Defl.	L/1,436 (0.128")	0.509"	25.1%	13	10-06-04
Total Neg. Defl.	2xL/1,998 (-0.081")	n/a	n/a	10	00-00-00
Max Defl.	0.235"	1"	23.5%	10	10-06-04
Cant. Max Defl.	-0.081"	n/a	n/a	10	00-00-00
Span / Depth	15.4	n/a	n/a		00-00-00
Squash Blocks	Valid				

Bearing Supports

B1	Wall/Plate	3-1/2" x 3-1/2"	4,898 lbs	65%	32.8%	Spruce Pine Fir
B2	Wall/Plate	3-1/2" x 3-1/2"	3,278 lbs	43.5%	21.9%	Spruce Pine Fir

Notes

Nail one ply to another with
3 1/2" spiral nails @ 12"
o.c., staggered in 2 rows




S-152394

BC CALC® Design Report



Build 6080
Job Name: 45147 (4201)
Address: Pine Valley
City, Province, Postal Code: Vaughan, ON
Customer: Gold Park
Code reports: CCMC 12472-R

File Name: 290678.bcc
Description: Second Floor Framing
Specifier:
Designer: NL
Company: Alpa Roof Trusses
Misc:



Total Horizontal Product Length = 14-00-00

Reaction Summary (Down / Uplift) (lbs)

Bearing	Live	Dead	Snow	Wind
B0, 3"	163 / 0	619 / 0	7 / 0	
B1, 3"	948 / 0	1,189 / 0	88 / 0	

Load Summary

Tag	Description	Load Type	Ref.	Start	End	Live 1.00	Dead 0.65	Snow 1.00	Wind 1.15	Trib.
1		Unf. Lin. (lb/ft)	L	00-00-00	14-00-00		60			n/a
2		Unf. Lin. (lb/ft)	L	11-09-00	14-00-00	27	14			n/a
3		Unf. Area (lb/ft^2)	L	11-09-00	14-00-00		11	21		02-00-00
4		Conc. Pt. (lbs)	L	11-09-00	11-09-00	1,050	718			n/a

Controls Summary

	Factored Demand	Factored Resistance	Demand / Resistance	Load Case	Location
Pos. Moment	5,603 ft-lbs	35,392 ft-lbs	15.8%	1	11-05-01
End Shear	2,708 lbs	14,464 lbs	18.7%	1	12-09-02
Total Load Defl.	L/1,218 (0.134")	0.681"	19.7%	11	07-05-12
Live Load Defl.	L/999 (0.046")	n/a	n/a	15	07-11-11
Max Defl.	0.134"	1"	13.4%	11	07-05-12
Span / Depth	13.8	n/a	n/a		00-00-00
Squash Blocks	Valid				

Bearing Supports

	Dim. (L x W)	Demand	Demand/Resistance Support	Demand/Resistance Member	Material
B0	Wall/Plate 3" x 3-1/2"	866 lbs	20.6%	10.4%	Spruce Pine Fir
B1	Wall/Plate 3" x 3-1/2"	2,951 lbs	45.7%	23%	Spruce Pine Fir

Notes

Design meets Code minimum (L/240) Total load deflection criteria.
Design meets Code minimum (L/360) Live load deflection criteria.
Design meets User specified (1") Maximum Total load deflection criteria.
Calculations assume member is fully braced.
Resistance Factor phi has been applied to all presented results per CSA O86.
BC CALC® analysis is based on Canadian Limit States Design, as per NBCC 2010 and CSA O86.
Design based on Dry Service Condition.
Importance Factor : Normal Part code : Part 4

Nail one ply to another with
3 1/2" spiral nails @ 12"
o.c, staggered in 2 rows



BC CALC® Design Report



Dry | 1 span | No cantilevers | 0/12 slope (deg)

November 20, 2017 16:01:59

Build 6080

File Name: 290678.bcc

Job Name: 45147 (4201)

Description: Second Floor Framing

Address: Pine Valley

Specifier:

City, Province, Postal Code: Vaughan, ON


Designer: NL

Customer: Gold Park

Company: Alpa Roof Trusses

Code reports: CCMC 12472-R

Misc:



Total Horizontal Product Length = 03-10-00

Reaction Summary (Down / Uplift) (lbs)

Bearing	Live	Dead	Snow	Wind
B0, 3-1/2"		182 / 0	81 / 0	
B1, 3"		178 / 0	80 / 0	

Load Summary

Tag	Description	Load Type	Ref.	Start	End	Live 1.00	Dead 0.65	Snow 1.00	Wind 1.15	Trib.
1		Unf. Lin. (lb/ft)	L	00-00-00	03-10-00		60			n/a
2		Unf. Area (lb/ft^2)	L	00-00-00	03-10-00		11	21		02-00-00

Controls Summary

	Factored Demand	Factored Resistance	Demand / Resistance	Load Case	Location
Pos. Moment	192 ft-lbs	23,005 ft-lbs	0.8%	0	01-11-04
End Shear	86 lbs	9,401 lbs	0.9%	0	01-03-06
Total Load Defl.	L/999 (0")	n/a	n/a	4	01-11-04
Live Load Defl.	L/999 (0")	n/a	n/a	5	01-11-04
Max Defl.	0"	n/a	n/a	4	01-11-04
Span / Depth	3.5	n/a	n/a		00-00-00
Squash Blocks	Valid				

Bearing Supports

			Demand/ Resistance Support	Demand/ Resistance Member	Material
Bearing Supports	Dim. (L x W)	Demand			
B0	Wall/Plate	3-1/2" x 3-1/2"	255 lbs	5.2%	2.6%
B1	Wall/Plate	3" x 3-1/2"	250 lbs	5.9%	3%
					Spruce Pine Fir
					Spruce Pine Fir

Notes

Design meets Code minimum (L/240) Total load deflection criteria.
Design meets Code minimum (L/360) Live load deflection criteria.
Design meets User specified (1") Maximum Total load deflection criteria.
Calculations assume member is fully braced.
Resistance Factor phi has been applied to all presented results per CSA O86.
BC CALC® analysis is based on Canadian Limit States Design, as per NBCC 2010 and CSA O86.
Design based on Dry Service Condition.
Importance Factor : Normal Part code : Part 4

Nail one ply to another with
3 1/2" spiral nails @ 12"
o.c, staggered in 2 rows





Build 6080

Job Name: 45147 (4201)

Address: Pine Valley

City, Province, Postal Code: Vaughan, ON

Customer: Gold Park

Code reports: CCMC 12472-R

File Name: 290678.bcc


Description: Second Floor Framing

Specifier:

Designer: NL

Company: Alpha Roof Trusses

Misc:



Reaction Summary (Down / Uplift) (lbs)

Bearing	Live	Dead	Snow	Wind
B0, 3-1/2"	1,690 / 0	2,246 / 0	2,184 / 0	
B1, 3-1/2"	1,690 / 0	2,246 / 0	2,184 / 0	

Load Summary

Tag	Description	Load Type	Ref.	Start	End	Live 1.00	Dead 0.65	Snow 1.00	Wind 1.15	Trib.
1		Unf. Area (lb/ft²)	L	00-00-00	13-00-00	40	15			06-06-00
2		Unf. Lin. (lb/ft)	L	00-00-00	13-00-00		60			n/a
3		Unf. Area (lb/ft²)	L	00-00-00	13-00-00		11	21		16-00-00

Controls Summary

	Factored Demand	Factored Resistance	Demand / Resistance	Load Case	Location
Pos. Moment	20,958 ft-lbs	35,392 ft-lbs	59.2%	5	06-06-00
End Shear	5,563 lbs	14,464 lbs	38.5%	5	01-03-06
Total Load Defl.	L/339 (0.443")	0.627"	70.7%	13	06-06-00
Live Load Defl.	L/611 (0.246")	0.418"	58.9%	17	06-06-00
Max Defl.	0.443"	1"	44.3%	13	06-06-00
Span / Depth	12.7	n/a	n/a		00-00-00
Squash Blocks	Valid				

Bearing Supports

	Dim. (L x W)	Demand	Demand / Resistance Support	Demand / Resistance Member	Material
B0	Wall/Plate 3-1/2" x 3-1/2"	6,928 lbs	91.9%	46.4%	Spruce Pine Fir
B1	Wall/Plate 3-1/2" x 3-1/2"	6,928 lbs	91.9%	46.4%	Spruce Pine Fir

Notes

Design meets Code minimum (L/240) Total load deflection criteria.
 Design meets Code minimum (L/360) Live load deflection criteria.
 Design meets User specified (1") Maximum Total load deflection criteria.
 Calculations assume member is fully braced.
 Resistance Factor phi has been applied to all presented results per CSA O86.
 BC CALC® analysis is based on Canadian Limit States Design, as per NBCC 2010 and CSA O86.
 Design based on Dry Service Condition.
 Importance Factor : Normal Part code : Part 4

Nail one ply to another with
 3 1/2" spiral nails @ 12"
 o.c, staggered in 2 rows




BC CALC® Design Report



Build 6080
Job Name: 45147 (4201)
Address: Pine Valley
City, Province, Postal Code: Vaughan, ON
Customer: Gold Park
Code reports: CCMC 12472-R

File Name: 290678.bcc
Description: Second Floor Framing
Specifier:
Designer: NL
Company: Alpa Roof Trusses
Misc:



Total Horizontal Product Length = 15-06-00

Reaction Summary (Down / Uplift) (lbs)

Bearing	Live	Dead	Snow	Wind
B0, 3"	1,752 / 0	2,653 / 0	1,919 / 0	
B1, 3-1/2"	701 / 0	1,160 / 0	380 / 0	

Load Summary

Tag	Description	Load Type	Ref.	Start	End	Live 1.00	Dead 0.65	Snow 1.00	Wind 1.15	Trib.
1		Unf. Lin. (lb/ft)	L	00-00-00	15-06-00	27	74			n/a
2		Unf. Area (lb/ft^2)	L	00-00-00	02-09-00		11	21		02-00-00
3		Unf. Lin. (lb/ft)	L	02-09-00	15-06-00	27	14			n/a
4		Conc. Pt. (lbs)	L	02-09-00	02-09-00	1,690	2,240	2,184		n/a

Controls Summary

	Factored Demand	Factored Resistance	Demand / Resistance	Load Case	Location
Pos. Moment	17,324 ft-lbs	35,392 ft-lbs	48.9%	5	02-09-00
End Shear	6,809 lbs	14,464 lbs	47.1%	5	01-02-14
Total Load Defl.	L/368 (0.492")	0.754"	65.2%	11	07-00-10
Live Load Defl.	L/781 (0.232")	0.503"	46.1%	15	07-00-10
Max Defl.	0.492"	1"	49.2%	11	07-00-10
Span / Depth	15.2	n/a	n/a		00-00-00
Squash Blocks	Valid				

Bearing Supports	Dim. (L x W)	Demand	Demand/Resistance Support	Demand/Resistance Member	Material
B0 Post	3" x 3-1/2"	7,071 lbs	38.8%	55.2%	Spruce Pine Fir
B1 Wall/Plate	3-1/2" x 3-1/2"	2,691 lbs	35.7%	18%	Spruce Pine Fir

Notes


Design meets Code minimum (L/240) Total load deflection criteria.
Design meets Code minimum (L/360) Live load deflection criteria.
Design meets User specified (1") Maximum Total load deflection criteria.
Calculations assume member is fully braced.
Resistance Factor phi has been applied to all presented results per CSA O86.
BC CALC® analysis is based on Canadian Limit States Design, as per NBCC 2010 and CSA O86.

Design based on Dry Service Condition.
Importance Factor : Normal Part code : Part 4

Nail one ply to another with
3 1/2" spiral nails @ 12"
o.c., staggered in 2 rows



BC CALC® Design Report




Dry | 1 span | No cantilevers | 0/12 slope (deg)

November 20, 2017 16:08:14

Build 6080
 Job Name: 45147 (4201)
 Address: Pine Valley
 City, Province, Postal Code: Vaughan, ON
 Customer: Gold Park
 Code reports: CCMC 12472-R

File Name: 290678.bcc
 Description: First Floor Framing
 Specifier:
 Designer: NL
 Company: Alpa Roof Trusses
 Misc:



Total Horizontal Product Length = 09-00-00

Reaction Summary (Down / Uplift) (lbs)

Bearing	Live	Dead	Snow	Wind
B0, 3-1/2"	720 / 0	657 / 0		
B1, 3-1/2"	720 / 0	657 / 0		

Load Summary

Tag	Description	Load Type	Ref.	Start	End	Live 1.00	Dead 0.65	Snow 1.00	Wind 1.15	Trib.
1		Unf. Area (lb/ft²)	L	00-00-00	09-00-00	40	20			04-00-00
2		Unf. Lin. (lb/ft)	L	00-00-00	09-00-00		60			n/a

Controls Summary

	Factored Demand	Factored Resistance	Demand / Resistance	Load Case	Location
Pos. Moment	3,853 ft-lbs	17,696 ft-lbs	21.8%	1	04-06-00
End Shear	1,360 lbs	7,232 lbs	18.8%	1	01-03-06
Total Load Defl.	L/999 (0.075")	n/a	n/a	4	04-06-00
Live Load Defl.	L/999 (0.039")	n/a	n/a	5	04-06-00
Max Defl.	0.075"	n/a	n/a	4	04-06-00
Span / Depth	8.6	n/a	n/a		00-00-00
Squash Blocks	Valid				

Disclosure

Completeness and accuracy of input must be verified by anyone who would rely on output as evidence of suitability for particular application. Output here based on building code-accepted design properties and analysis methods. Installation of Boise Cascade engineered wood products must be in accordance with current Installation Guide and applicable building codes. To obtain Installation Guide or ask questions, please call 1-800-964-6999 before installation.

Bearing Supports

	Dim. (L x W)	Demand	Demand/Resistance Support	Demand/Resistance Member	Material
B0	Wall/Plate 3-1/2" x 1-3/4"	1,901 lbs	50.5%	25.4%	Spruce Pine Fir
B1	Wall/Plate 3-1/2" x 1-3/4"	1,901 lbs	50.5%	25.4%	Spruce Pine Fir

Notes

Design meets Code minimum (L/240) Total load deflection criteria.
 Design meets Code minimum (L/360) Live load deflection criteria.
 Design meets User specified (1") Maximum Total load deflection criteria.
 Calculations assume member is fully braced.
 Resistance Factor phi has been applied to all presented results per CSA O86.
 BC CALC® analysis is based on Canadian Limit States Design, as per NBCC 2010 and CSA O86.
 Design based on Dry Service Condition.
 Importance Factor : Normal Part code : Part 4



BC CALC® Design Report



Dry | 1 span | No cantilevers | 0/12 slope (deg)

November 20, 2017 16:08:20

Build 6080

Job Name:

45147 (4201)

Address:

Pine Valley

City, Province, Postal Code:

Vaughan, ON

Customer:

Gold Park

Code reports:

CCMC 12472-R

File Name: 290678.bcc


Description: First Floor Framing

Specifier:

Designer: NL

Company: Alpa Roof Trusses

Misc:



Total Horizontal Product Length = 14-00-00

Reaction Summary (Down / Uplift) (lbs)

Bearing	Live	Dead	Snow	Wind
B0, 3-1/2"	3,204 / 0	1,972 / 0		
B1, 3-1/2"	2,898 / 0	1,816 / 0		

Load Summary

Tag	Description	Load Type	Ref.	Start	End	Live 1.00	Dead 0.65	Snow 1.00	Wind 1.15	Trib.
1		Unf. Area (lb/ft^2)	L	00-00-00	14-00-00	40	15			07-06-00
2		Unf. Lin. (lb/ft)	L	00-00-00	14-00-00		60			n/a
3		Unf. Lin. (lb/ft)	L	06-06-00	14-00-00	27	14			n/a
4		Conc. Pt. (lbs)	L	06-06-00	06-06-00	720	657			n/a
5		Conc. Pt. (lbs)	L	04-07-00	04-07-00	777	308			n/a
6		Conc. Pt. (lbs)	L	04-07-00	04-07-00	203	134			n/a

Controls Summary


	Factored Demand	Factored Resistance	Demand / Resistance	Load Case	Location
Pos. Moment	27,356 ft-lbs	35,392 ft-lbs	77.3%	1	06-06-00
End Shear	6,399 lbs	14,464 lbs	44.2%	1	01-03-06
Total Load Defl.	L/259 (0.627")	0.677"	92.5%	4	06-10-11
Live Load Defl.	L/423 (0.384")	0.451"	85.1%	5	06-10-11
Max Defl.	0.627"	1"	62.7%	4	06-10-11
Span / Depth	13.7	n/a	n/a		00-00-00
Squash Blocks	Valid				

Bearing Supports

B0	Wall/Plate	3-1/2" x 3-1/2"	7,271 lbs	96.5%	48.7%	Spruce Pine Fir
B1	Wall/Plate	3-1/2" x 3-1/2"	6,617 lbs	87.8%	44.3%	Spruce Pine Fir

Notes

Nail one ply to another with
3 1/2" spiral nails @ 12"
o.c., staggered in 2 rows





Double 1-3/4" x 11-7/8" VERSA-LAM® 2.0 3100 SP

Floor Beam\B12

Dry | 1 span | No cantilevers | 0/12 slope (deg)

November 20, 2017 16:08:24

BC CALC® Design Report



Build 6080

Job Name:

45147 (4201)

Address:

Pine Valley

City, Province, Postal Code: Vaughan, ON

Customer:

Gold Park

Code reports:

CCMC 12472-R

File Name: 290678.bcc


Description: First Floor Framing

Specifier:

Designer: NL

Company: Alpa Roof Trusses

Misc:



Total Horizontal Product Length = 15-08-00

Reaction Summary (Down / Uplift) (lbs)

Bearing	Live	Dead	Snow	Wind
B0, 3-1/2"	563 / 0	869 / 0		
B1, 4"	3,314 / 0	2,560 / 0		

Load Summary

Tag	Description	Load Type	Ref.	Start	End	Live 1.00	Dead 0.65	Snow 1.00	Wind 1.15	Trib.
1		Unf. Lin. (lb/ft)	L	00-00-00	15-08-00	27	74			n/a
2		Unf. Lin. (lb/ft)	L	00-00-00	14-08-00	27	14			n/a
3		Unf. Area (lb/ft^2)	L	14-08-00	15-08-00	40	15			04-00-00
4		Conc. Pt. (lbs)	L	14-08-00	14-08-00	2,898	1,816			n/a

Controls Summary

	Factored Demand	Factored Resistance	Demand / Resistance	Load Case	Location
Pos. Moment	8,617 ft-lbs	35,392 ft-lbs	24.3%	1	09-05-05
End Shear	5,710 lbs	14,464 lbs	39.5%	1	14-04-02
Total Load Defl.	L/658 (0.277")	0.758"	36.5%	4	08-02-10
Live Load Defl.	L/999 (0.121")	n/a	n/a	5	08-02-10
Max Defl.	0.277"	1"	27.7%	4	08-02-10
Span / Depth	15.3	n/a	n/a		00-00-00
Squash Blocks	Valid				

Bearing Supports	Dim. (L x W)	Demand	Demand/Resistance Support	Demand/Resistance Member	Material
B0 Wall/Plate	3-1/2" x 3-1/2"	1,932 lbs	25.6%	12.9%	Spruce Pine Fir
B1 Wall/Plate	4" x 3-1/2"	8,170 lbs	94.9%	47.8%	Spruce Pine Fir

Notes

Design meets Code minimum (L/240) Total load deflection criteria.
 Design meets Code minimum (L/360) Live load deflection criteria.
 Design meets User specified (1") Maximum Total load deflection criteria.
 Calculations assume member is fully braced.
 Resistance Factor phi has been applied to all presented results per CSA O86.
 BC CALC® analysis is based on Canadian Limit States Design, as per NBCC 2010 and CSA O86.
 Design based on Dry Service Condition.
 Importance Factor : Normal Part code : Part 4

Nail one ply to another with
 3 1/2" spiral nails @ 12"
 o.c., staggered in 2 rows





Single 1-3/4" x 11-7/8" VERSA-LAM® 2.0 3100 SP

Floor Beam\B13

BC CALC® Design Report




Dry | 1 span | No cantilevers | 0/12 slope (deg)

November 20, 2017 16:08:28

Build 6080
Job Name: 45147 (4201)
Address: Pine Valley
City, Province, Postal Code: Vaughan, ON
Customer: Gold Park
Code reports: CCMC 12472-R

File Name: 290678.bcc
Description: First Floor Framing
Specifier:
Designer: NL
Company: Alpa Roof Trusses
Misc:



Total Horizontal Product Length = 10-00-00

Reaction Summary (Down / Uplift) (lbs)

Bearing	Live	Dead	Snow	Wind
B0, 3-1/2"	790 / 0	666 / 0		
B1, 3-1/2"	411 / 0	301 / 0		

Load Summary

Tag	Description	Load Type	Ref.	Start	End	Live	Dead	Snow	Wind	Trib.
1		Unf. Lin. (lb/ft)	L	00-00-00	10-00-00	27	14			n/a
2		Unf. Lin. (lb/ft)	L	02-02-00	10-00-00	27	14			n/a
3		Conc. Pt. (lbs)	L	02-02-00	02-02-00	720	657			n/a

Controls Summary

	Factored Demand	Factored Resistance	Demand / Resistance	Load Case	Location
Pos. Moment	3,760 ft-lbs	17,696 ft-lbs	21.2%	1	02-02-00
End Shear	1,934 lbs	7,232 lbs	26.7%	1	01-03-06
Total Load Defl.	L/999 (0.083")	n/a	n/a	4	04-07-08
Live Load Defl.	L/999 (0.046")	n/a	n/a	5	04-07-08
Max Defl.	0.083"	n/a	n/a	4	04-07-08
Span / Depth	9.6	n/a	n/a		00-00-00
Squash Blocks	Valid				

Disclosure

Completeness and accuracy of input must be verified by anyone who would rely on output as evidence of suitability for particular application. Output here based on building code-accepted design properties and analysis methods. Installation of Boise Cascade engineered wood products must be in accordance with current Installation Guide and applicable building codes. To obtain Installation Guide or ask questions, please call 1-800-964-6999 before installation.

Bearing Supports

	Dim. (L x W)	Demand	Demand/ Resistance Support	Demand/ Resistance Member	Material
B0 Wall/Plate	3-1/2" x 1-3/4"	2,018 lbs	53.6%	27%	Spruce Pine Fir
B1 Wall/Plate	3-1/2" x 1-3/4"	993 lbs	26.3%	13.3%	Spruce Pine Fir

Notes

Design meets Code minimum (L/240) Total load deflection criteria.
Design meets Code minimum (L/360) Live load deflection criteria.
Design meets User specified (1") Maximum Total load deflection criteria.
Calculations assume member is fully braced.
Resistance Factor phi has been applied to all presented results per CSA O86.
BC CALC® analysis is based on Canadian Limit States Design, as per NBCC 2010 and CSA O86.
Design based on Dry Service Condition.
Importance Factor : Normal Part code : Part 4



S152402



Single 1-3/4" x 11-7/8" VERSA-LAM® 2.0 3100 SP

Floor Beam\B14

BC CALC® Design Report




Dry | 1 span | No cantilevers | 0/12 slope (deg)

November 20, 2017 16:08:33

Build 6080
Job Name: 45147 (4201)
Address: Pine Valley
City, Province, Postal Code: Vaughan, ON
Customer: Gold Park
Code reports: CCMC 12472-R

File Name: 290678.bcc
Description: First Floor Framing
Specifier:
Designer: NL
Company: Alpa Roof Trusses
Misc:



Total Horizontal Product Length = 11-00-00

Reaction Summary (Down / Uplift) (lbs)

Bearing	Live	Dead	Snow	Wind
B0, 3-1/2"	1,538 / 0	751 / 0		
B1, 3-11/16"	1,885 / 0	896 / 0		

Load Summary

Tag	Description	Load Type	Ref.	Start	End	Live	Dead	Snow	Wind	Trib.
1		Unf. Area (lb/ft^2)	L	00-00-00	06-08-00	40	20			05-00-00
2		Unf. Area (lb/ft^2)	L	06-08-00	11-00-00	40	20			06-00-00
3		Conc. Pt. (lbs)	L	06-08-00	06-08-00	1,050	394			n/a

Controls Summary

	Factored Demand	Factored Resistance	Demand / Resistance	Load Case	Location
Pos. Moment	11,294 ft-lbs	17,696 ft-lbs	63.8%	1	06-08-00
End Shear	3,276 lbs	7,232 lbs	45.3%	1	09-08-07
Total Load Defl.	L/421 (0.3")	0.526"	57%	4	05-07-14
Live Load Defl.	L/617 (0.205")	0.351"	58.3%	5	05-07-14
Max Defl.	0.3"	1"	30%	4	05-07-14
Span / Depth	10.6	n/a	n/a		00-00-00
Squash Blocks	Valid				

Disclosure

Completeness and accuracy of input must be verified by anyone who would rely on output as evidence of suitability for particular application. Output here based on building code-accepted design properties and analysis methods. Installation of Boise Cascade engineered wood products must be in accordance with current Installation Guide and applicable building codes. To obtain Installation Guide or ask questions, please call 1-800-964-6999 before installation.


Bearing Supports

	Dim. (L x W)	Demand	Demand / Resistance Support	Demand / Resistance Member	Material
B0	Wall/Plate 3-1/2" x 1-3/4"	3,246 lbs	86.1%	43.4%	Spruce Pine Fir
B1	Wall/Plate 3-11/16" x 1-3/4"	3,948 lbs	99.1%	50%	Spruce Pine Fir

Notes

Design meets Code minimum (L/240) Total load deflection criteria.
Design meets Code minimum (L/360) Live load deflection criteria.
Design meets User specified (1") Maximum Total load deflection criteria.
Calculations assume member is fully braced.
Resistance Factor phi has been applied to all presented results per CSA O86.
BC CALC® analysis is based on Canadian Limit States Design, as per NBCC 2010 and CSA O86.
Design based on Dry Service Condition.
Importance Factor : Normal Part code : Part 4

BC CALC®, BC FRAMER®, AJST™, ALLJOIST®, BC RIM BOARD™, BCI®, BOISE GLULAM™, SIMPLE FRAMING SYSTEM®, VERSA-LAM®, VERSA-RIM PLUS®, VERSA-RIM®, VERSA-STRAND®, VERSA-STUD® are trademarks of Boise Cascade Wood Products L.L.C.



S.152403



Double 1-3/4" x 11-7/8" VERSA-LAM® 2.0 3100 SP

Floor Beam\B15

Dry | 1 span | No cantilevers | 0/12 slope (deg)

November 20, 2017 16:08:40

BC CALC® Design Report



Build 6080

Job Name:

45147 (4201)

Address:

Pine Valley

City, Province, Postal Code: Vaughan, ON

Customer:

Gold Park

Code reports:

CCMC 12472-R

File Name: 290678.bcc


Description: First Floor Framing

Specifier:

Designer: NL

Company: Alpa Roof Trusses

Misc:



Total Horizontal Product Length = 10-00-00

Reaction Summary (Down / Uplift) (lbs)

Bearing	Live	Dead	Snow	Wind
B0, 3-1/2"	200 / 0	848 / 0	903 / 0	
B1, 3-1/2"	200 / 0	226 / 0	104 / 0	

Load Summary

Tag	Description	Load Type	Ref.	Start	End	Live 1.00	Dead 0.65	Snow 1.00	Wind 1.15	Trib.
1		Unf. Area (lb/ft^2)	L	00-00-00	10-00-00	40	20			01-00-00
2		Unf. Lin. (lb/ft)	L	00-00-00	01-05-00		160			n/a
3		Conc. Pt. (lbs)	L	01-05-00	01-05-00		372	709		n/a
4		Unf. Area (lb/ft^2)	L	00-00-00	01-05-00		11	21		10-00-00

Controls Summary

	Factored Demand	Factored Resistance	Demand / Resistance	Load Case	Location
Pos. Moment	2,290 ft-lbs	35,392 ft-lbs	6.5%	5	01-05-00
End Shear	1,602 lbs	14,464 lbs	11.1%	5	01-03-06
Total Load Defl.	L/999 (0.025")	n/a	n/a	13	04-07-05
Live Load Defl.	L/999 (0.013")	n/a	n/a	17	04-06-00
Max Defl.	0.025"	n/a	n/a	13	04-07-05
Span / Depth	9.6	n/a	n/a		00-00-00
Squash Blocks	Valid				

Bearing Supports

	Dim. (L x W)	Demand	Demand/Resistance Support	Demand/Resistance Member	Material
B0 Wall/Plate	3-1/2" x 3-1/2"	2,515 lbs	33.4%	16.8%	Spruce Pine Fir
B1 Wall/Plate	3-1/2" x 3-1/2"	635 lbs	8.4%	4.2%	Spruce Pine Fir

Notes

Design meets Code minimum (L/240) Total load deflection criteria.
 Design meets Code minimum (L/360) Live load deflection criteria.
 Design meets User specified (1") Maximum Total load deflection criteria.
 Calculations assume member is fully braced.
 Resistance Factor phi has been applied to all presented results per CSA O86.
 BC CALC® analysis is based on Canadian Limit States Design, as per NBCC 2010 and CSA O86.
 Design based on Dry Service Condition.
 Importance Factor : Normal Part code : Part 4
 Nail one ply to another with
 3 1/2" spiral nails @ 12"
 o.c, staggered in 2 rows




5152404



Build 6080
 Job Name: 45147 (4201)
 Address: Pine Valley
 City, Province, Postal Code: Vaughan, ON
 Customer: Gold Park
 Code reports: CCMC 12472-R

File Name: 290678.bcc
 Description: First Floor Framing
 Specifier:
 Designer: NL
 Company: Alpa Roof Trusses
 Misc:



Total Horizontal Product Length = 06-00-00

Reaction Summary (Down / Uplift) (lbs)

Bearing	Live	Dead	Snow	Wind
B0, 3-1/2"	516 / 0	428 / 0		
B1, 3-1/2"	1,031 / 0	628 / 0		

Load Summary

Tag	Description	Load Type	Ref.	Start	End	Live 1.00	Dead 0.65	Snow 1.00	Wind 1.15	Trib.
1		Unf. Lin. (lb/ft)	L	00-00-00	06-00-00	54	87			n/a
2		Conc. Pt. (lbs)	L	04-02-00	04-02-00	1,223	476			n/a

Controls Summary

	Factored Demand	Factored Resistance	Demand / Resistance	Load Case	Location
Pos. Moment	3,407 ft-lbs	23,220 ft-lbs	14.7%	1	04-02-00
End Shear	2,113 lbs	11,571 lbs	18.3%	1	04-11-00
Total Load Defl.	L/999 (0.023")	n/a	n/a	4	03-02-07
Live Load Defl.	L/999 (0.014")	n/a	n/a	5	03-02-07
Max Defl.	0.023"	n/a	n/a	4	03-02-07
Span / Depth	7	n/a	n/a		00-00-00
Squash Blocks	Valid				

Bearing Supports

	Dim. (L x W)	Demand	Demand/Resistance Support	Demand/Resistance Member	Material
B0 Wall/Plate	3-1/2" x 3-1/2"	1,309 lbs	17.4%	8.8%	Spruce Pine Fir
B1 Wall/Plate	3-1/2" x 3-1/2"	2,331 lbs	30.9%	15.6%	Spruce Pine Fir

Notes

Design meets Code minimum (L/240) Total load deflection criteria.
 Design meets Code minimum (L/360) Live load deflection criteria.
 Design meets User specified (1") Maximum Total load deflection criteria.
 Calculations assume member is fully braced.
 Resistance Factor phi has been applied to all presented results per CSA O86.
 BC CALC® analysis is based on Canadian Limit States Design, as per NBCC 2010 and CSA O86.
 Design based on Dry Service Condition.
 Importance Factor : Normal Part code : Part 4

Nail one ply to another with
 3 1/2" spiral nails @ 12"
 o.c, staggered in 2 rows





Single 1-3/4" x 9-1/2" VERSA-LAM® 2.0 3100 SP

Floor Beam\B18

BC CALC® Design Report




Dry | 1 span | No cantilevers | 0/12 slope (deg)

November 20, 2017 16:08:54

Build 6080
Job Name: 45147 (4201)
Address: Pine Valley
City, Province, Postal Code: Vaughan, ON
Customer: Gold Park
Code reports: CCMC 12472-R

File Name: 290678.bcc
Description: First Floor Framing
Specifier:
Designer: NL
Company: Alpa Roof Trusses
Misc:



Total Horizontal Product Length = 08-06-00

Reaction Summary (Down / Uplift) (lbs)

Bearing	Live	Dead	Snow	Wind
B0, 3-1/2"	961 / 0	805 / 0		
B1, 3-1/2"	1,090 / 0	884 / 0		

Load Summary

Tag	Description	Load Type	Ref.	Start	End	Live	Dead	Snow	Wind	Trib.
1		Unf. Area (lb/ft²)	L	00-00-00	08-06-00	40	20			03-00-00
2		Unf. Lin. (lb/ft)	L	00-00-00	08-06-00		60			n/a
3		Conc. Pt. (lbs)	L	04-09-00	04-09-00	1,031	628			n/a

Controls Summary

	Factored Demand	Factored Resistance	Demand / Resistance	Load Case	Location
Pos. Moment	7,289 ft-lbs	11,610 ft-lbs	62.8%	1	04-09-00
End Shear	2,375 lbs	5,785 lbs	41%	1	07-05-00
Total Load Defl.	L/452 (0.214")	0.402"	53.1%	4	04-03-08
Live Load Defl.	L/999 (0.121")	n/a	n/a	5	04-04-14
Max Defl.	0.214"	1"	21.4%	4	04-03-08
Span / Depth	10.2	n/a	n/a		00-00-00
Squash Blocks	Valid				

Disclosure

Completeness and accuracy of input must be verified by anyone who would rely on output as evidence of suitability for particular application. Output here based on building code-accepted design properties and analysis methods. Installation of Boise Cascade engineered wood products must be in accordance with current Installation Guide and applicable building codes. To obtain Installation Guide or ask questions, please call 1-800-964-6999 before installation.

Bearing Supports



	Dim. (L x W)	Demand	Demand / Resistance Support	Demand / Resistance Member	Material
B0 Wall/Plate	3-1/2" x 1-3/4"	2,449 lbs	65%	32.8%	Spruce Pine Fir
B1 Wall/Plate	3-1/2" x 1-3/4"	2,739 lbs	72.7%	36.7%	Spruce Pine Fir

Notes

Design meets Code minimum (L/240) Total load deflection criteria.
Design meets Code minimum (L/360) Live load deflection criteria.
Design meets User specified (1") Maximum Total load deflection criteria.
Calculations assume member is fully braced.
Resistance Factor phi has been applied to all presented results per CSA O86.
BC CALC® analysis is based on Canadian Limit States Design, as per NBCC 2010 and CSA O86.
Design based on Dry Service Condition.
Importance Factor : Normal Part code : Part 4



S.152407




Maximum Floor Spans

Live Load = 40 psf, Dead Load = 15 psf
Simple Spans, L/360 Deflection Limit
3/4" OSB G&N Sheathing

Depth	Series	Bare				1/2" Gypsum Ceiling			
		On Centre Spacing				On Centre Spacing			
		12"	16"	19.2"	24"	12"	16"	19.2"	24"
9-1/2"	NI-20	15'-10"	15'-0"	14'-5"	13'-5"	16'-4"	15'-5"	14'-6"	13'-5"
	NI-40x	17'-0"	16'-0"	15'-5"	14'-9"	17'-5"	16'-5"	15'-10"	15'-2"
	NI-60	17'-2"	16'-2"	15'-7"	14'-11"	17'-6"	16'-7"	15'-11"	15'-3"
	NI-70	18'-0"	16'-11"	16'-3"	15'-7"	18'-5"	17'-3"	16'-7"	15'-11"
	NI-80	18'-3"	17'-1"	16'-5"	15'-9"	18'-8"	17'-5"	16'-9"	16'-1"
11-7/8"	NI-20	17'-10"	16'-10"	16'-2"	15'-6"	18'-6"	17'-4"	16'-9"	16'-1"
	NI-40x	19'-4"	17'-11"	17'-3"	16'-6"	19'-11"	18'-6"	17'-9"	17'-0"
	NI-60	19'-7"	18'-2"	17'-5"	16'-9"	20'-2"	18'-9"	17'-11"	17'-2"
	NI-70	20'-9"	19'-2"	18'-3"	17'-5"	21'-4"	19'-9"	18'-10"	17'-10"
	NI-80	21'-1"	19'-5"	18'-6"	17'-7"	21'-7"	20'-0"	19'-0"	18'-0"
14"	NI-90x	21'-8"	20'-0"	19'-1"	18'-0"	22'-2"	20'-6"	19'-6"	18'-6"
	NI-40x	21'-5"	19'-10"	18'-11"	17'-11"	22'-1"	20'-6"	19'-7"	18'-7"
	NI-60	21'-10"	20'-2"	19'-3"	18'-2"	22'-5"	20'-10"	19'-11"	18'-10"
	NI-70	23'-0"	21'-3"	20'-3"	19'-2"	23'-8"	21'-11"	20'-10"	19'-9"
	NI-80	23'-5"	21'-7"	20'-7"	19'-5"	24'-0"	22'-3"	21'-2"	20'-0"
16"	NI-90x	24'-1"	22'-3"	21'-2"	20'-0"	24'-8"	22'-10"	21'-9"	20'-7"
	NI-60	23'-9"	22'-0"	20'-11"	19'-10"	24'-6"	22'-9"	21'-8"	20'-6"
	NI-70	25'-1"	23'-2"	22'-0"	20'-10"	25'-9"	23'-10"	22'-9"	21'-6"
	NI-80	25'-6"	23'-6"	22'-4"	21'-2"	26'-1"	24'-2"	23'-1"	21'-10"
	NI-90x	26'-4"	24'-3"	23'-1"	21'-10"	26'-11"	24'-11"	23'-8"	22'-5"

Depth	Series	Mid-Span Blocking				Mid-Span Blocking and 1/2" Gypsum Ceiling			
		On Centre Spacing				On Centre Spacing			
		12"	16"	19.2"	24"	12"	16"	19.2"	24"
9-1/2"	NI-20	17'-1"	15'-5"	14'-6"	13'-5"	17'-1"	15'-5"	14'-6"	13'-5"
	NI-40x	18'-8"	17'-6"	16'-7"	15'-3"	19'-2"	17'-8"	16'-7"	15'-3"
	NI-60	18'-11"	17'-8"	16'-10"	15'-7"	19'-4"	18'-0"	16'-10"	15'-7"
	NI-70	20'-0"	18'-7"	17'-9"	17'-0"	20'-5"	19'-0"	18'-2"	17'-0"
	NI-80	20'-3"	18'-10"	17'-11"	17'-2"	20'-8"	19'-3"	18'-4"	17'-5"
11-7/8"	NI-20	20'-2"	18'-8"	17'-6"	16'-2"	20'-7"	18'-8"	17'-6"	16'-2"
	NI-40x	21'-10"	20'-4"	19'-5"	17'-8"	22'-5"	20'-11"	19'-9"	17'-8"
	NI-60	22'-1"	20'-7"	19'-7"	18'-7"	22'-8"	21'-2"	20'-3"	18'-8"
	NI-70	23'-4"	21'-8"	20'-8"	19'-7"	23'-10"	22'-3"	21'-3"	20'-1"
	NI-80	23'-7"	21'-11"	20'-11"	19'-9"	24'-1"	22'-6"	21'-5"	20'-4"
14"	NI-90x	24'-3"	22'-6"	21'-6"	20'-4"	24'-8"	23'-0"	22'-0"	20'-9"
	NI-40x	24'-5"	22'-9"	21'-8"	19'-5"	25'-1"	23'-6"	21'-9"	19'-5"
	NI-60	24'-10"	23'-1"	22'-0"	20'-10"	25'-6"	23'-10"	22'-9"	21'-4"
	NI-70	26'-1"	24'-3"	23'-2"	21'-10"	26'-8"	24'-11"	23'-9"	22'-6"
	NI-80	26'-6"	24'-7"	23'-5"	22'-2"	27'-1"	25'-3"	24'-1"	22'-9"
16"	NI-90x	27'-3"	25'-4"	24'-1"	22'-9"	27'-9"	25'-11"	24'-8"	23'-4"
	NI-60	27'-3"	25'-5"	24'-2"	22'-10"	28'-0"	26'-2"	25'-0"	23'-8"
	NI-70	28'-8"	26'-8"	25'-4"	23'-11"	29'-3"	27'-4"	26'-1"	24'-8"
	NI-80	29'-1"	27'-0"	25'-9"	24'-4"	29'-8"	27'-9"	26'-5"	25'-0"
	NI-90x	29'-11"	27'-10"	26'-6"	25'-0"	30'-6"	28'-5"	27'-2"	25'-8"

- Maximum clear span applicable to simple-span residential floor construction with a design live load of 40 psf and dead load of 15 psf. The ultimate limit states are based on the factored loads of 1.50L + 1.25D. The serviceability limit states include the consideration for floor vibration, a live load deflection limit of L/360 and a total load deflection limit of L/240.
- Spans are based on a composite floor with glued-nailed oriented strand board (OSB) sheathing with a minimum thickness of 3/4 inch for a joist spacing of 24 inches or less. The composite floor may include 1/2 inch gypsum ceiling and/or one row of blocking at mid-span with strapping. Strapping shall be minimum 1x4 inch strap applied to underside of joists at blocking line or 1/2 inch gypsum ceiling attached to joists.
- Minimum bearing length shall be 1-3/4 inches for the end bearings.
- Bearing stiffeners are not required when I-joists are used with the spans and spacings given in this table, except as required for hangers.
- This span chart is based on uniform loads. For applications with other than uniformly distributed loads, an engineering analysis may be required based on the use of the design properties. Tables are based on Limit States Design per CSA O86-09, NBC 2010, and OBC 2012.
- Joists shall be laterally supported at supports and continuously along the compression edge. Refer to technical documentation for installation guidelines and construction details. Nordic I-joists are listed in CCMC evaluation report 13032-R and APA Product Report PR-L274C.



	NI-20	NI-40x	NI-60	NI-70	NI-80	NI-90	NI-90x
S-RF No.2	1950f MSR	2100f MSR	1950f MSR	2100f MSR	2400f MSR	2400f MSR	NPG Lumber
33 pieces per unit	33 pieces per unit	33 pieces per unit	23 pieces per unit	23 pieces per unit	23 pieces per unit	23 pieces per unit	23 pieces per unit

Refer to the Installation Guide for Residential Floors for additional information.
CMC EVALUATION REPORT 13032-R

WEB HOLE SPECIFICATIONS

RULES FOR CUTTING HOLES AND DUCT CHASE OPENINGS:

- The distance between the inside edge of the support and the centreline of any hole or duct chase opening shall be in compliance with the requirements of Table 1 or 2, respectively.
- I-joist top and bottom flanges must NEVER be cut, notched, or otherwise modified.
- Whenever possible, field-cut holes should be centred on the middle of the web.
- The maximum size hole or the maximum depth of a duct chase opening that can be cut into an I-joist web shall equal the clear distance between the flanges of the I-joist minus 1/4 inch. A minimum of 1/8 inch should always be maintained between the top or bottom of the hole or opening and the adjacent I-joist flange.

- The sides of square holes or longest sides of rectangular holes should not exceed 3/4 of the diameter of the maximum round hole permitted at that location.
- Where more than one hole is necessary, the distance between adjacent hole edges shall exceed twice the diameter of the largest round hole or twice the size of the largest square hole (or twice the length of the longest side of the longest rectangular hole or duct chase opening) and each hole and duct chase opening shall be sized and located in compliance with the requirements of Tables 1 and 2, respectively.
- A knockout is not considered a hole, may be utilized anywhere it occurs, and may be ignored for purposes of calculating minimum distances between holes and/or duct chase openings.
- Holes measuring 1-1/2 inches or smaller are permitted anywhere in a cantilevered section of a joist. Holes of greater size may be permitted subject to verification.

- A 1-1/2 inch hole or smaller can be placed anywhere in the web provided that it meets the requirements of rule number 6 above.
- All holes and duct chase openings shall be cut in a workman-like manner in accordance with the restrictions listed above and as illustrated in Figure 7.
- Limit three maximum size holes per span, of which one may be a duct chase opening.
- A group of round holes at approximately the same location shall be permitted if they meet the requirements for a single round hole circumscribed around them.

TABLE 1
LOCATION OF CIRCULAR HOLES IN JOIST WEBS

Simple or Multiple Span for Dead Loads up to 15 psf and Live Loads up to 40 psf

Joist Depth	Joist Series	Minimum Distance from Inside Face of Any Support to Centre of Hole (ft - in.)											
		Round Hole Diameter (in.)											
		2	3	4	5	6	6-1/4	7	8	8-5/8	9	10	10-3/4
9-1/2"	NI-20	0-7"	1-6"	2-10"	4-3"	5-8"	6-10"	---	---	---	---	---	---
	NI-40x	0-7"	1-6"	3-0"	4-4"	6-0"	6-4"	---	---	---	---	---	---
	NI-60	1-3"	2-6"	4-0"	5-4"	7-0"	7-5"	---	---	---	---	---	---
	NI-70	2-0"	3-4"	4-9"	6-3"	8-0"	8-4"	---	---	---	---	---	---
	NI-80	2-3"	3-6"	5-0"	6-6"	8-2"	8-8"	---	---	---	---	---	---
11-7/8"	NI-20	0-7"	0-8"	1-0"	2-4"	3-8"	4-0"	5-0"	6-6"	7-9"	---	---	---
	NI-40x	0-7"	0-8"	1-3"	2-8"	4-0"	4-4"	5-5"	7-0"	8-4"	---	---	---
	NI-60	0-7"	1-8"	3-0"	4-3"	5-9"	6-0"	7-3"	8-10"	10-0"	---	---	---
	NI-70	1-3"	2-6"	4-0"	5-4"	6-9"	7-2"	8-4"	10-0"	11-4"	---	---	---
	NI-80	1-6"	2-10"	4-2"	5-6"	7-0"	7-5"	8-6"	10-3"	11-4"	---	---	---
14"	NI-20	0-7"	0-8"	1-5"	3-2"	4-10"	5-4"	6-9"	8-9"	10-2"	---	---	---
	NI-40x	0-7"	0-8"	0-9"	2-5"	4-4"	4-9"	6-3"	---	---	---	---	---
	NI-60	0-7"	0-8"	1-0"	2-4"	3-8"	4-0"	5-0"	6-6"	7-9"	---	---	---
	NI-70	0-7"	0-8"	1-8"	3-0"	4-3"	4-8"	5-8"	7-2"	8-0"	8-8"	10-4"	11-9"
	NI-80	0-7"	0-8"	1-10"	3-0"	4-5"	5-10"	6-2"	7-3"	8-9"	9-9"	10-4"	12-0"
16"	NI-20	0-7"	0-8"	1-6"	3-2"	4-10"	5-4"	6-9"	8-9"	10-2"	---	---	---
	NI-40x	0-7"	0-8"	1-0"	2-4"	3-8"	4-0"	5-0"	6-6"	7-9"	---	---	---
	NI-60	0-7"	0-8"	1-8"	3-0"	4-3"	4-8"	5-8"	7-2"	8-0"	8-8"	10-4"	11-9"
	NI-70	0-7"	0-8"	1-10"	3-0"	4-5"	5-10"	6-2"	7-3"	8-9"	9-9"	10-4"	12-0"
	NI-80	0-7"	0-8"	1-12"	3-0"	4-5"	5-10"	6-2"	7-3"	8-9"	9-9"	10-4"	12-0"



- Above table may be used for I-joist spacing of 24 inches on centre or less.
- Hole location distance is measured from inside face of supports to centre of hole.
- Distances in this chart are based on uniformly loaded joists.
- The above table is based on the I-joists being used at their maximum spans. The minimum distance as given above may be reduced for shorter spans; contact your local distributor.

TABLE 2
DUCT CHASE OPENING SIZES AND LOCATIONS
Simple Span Only

Joist Depth	Joist Series	Minimum distance from inside face of supports to centre of opening (ft - in.)											
		Duct Chase Length (in.)											
		8	10	12	14	16	18	20	22	24	26	28	30
9-1/2"	NI-20	4-1"	4-5"	4-10"	5-4"	5-8"	6-1"	6-6"	7-1"	7-5"	---	---	---
	NI-40x	5-3"	5-8"	6-0"	6-5"	6-10"	7-3"	7-8"	8-2"	8-6"	---	---	---
	NI-60	5-4"	5-9"	6-2"	6-7"	7-1"	7-5"	8-0"	8-3"	8-9"	---	---	---
	NI-70	5-1"	5-5"	5-10"	6-3"	6-7"	7-1"	7-6"	8-1"	8-4"	---	---	---
	NI-80	5-3"	5-8"	6-0"	6-5"	6-10"	7-3"	7-8"	8-2"	8-6"	---	---	---
11-7/8"	NI-20	5-9"	6-2"	6-6"	7-1"	7-5"	7-9"	8-3"	8-9"	9-4"	---	---	---
	NI-40x	6-8"	7-2"	7-6"	8-1"	8-6"	9-1"	9-6"	10-1"	10-9"	---	---	---
	NI-60	7-3"	7-8"	8-0"	8-6"	9-0"	9-3"	9-9"	10-3"	11-0"	---	---	---
	NI-70	7-1"	7-4"	7-9"	8-3"	8-7"	9-1"	9-6"	10-1"	10-4"	---	---	---
	NI-80	7-2"	7-7"	8-0"	8-5"	8-10"	9-3"	9-8"	10-2"	10-8"	---	---	---
14"	NI-20	7-6"	7-11"	8-4"	8-9"	9-2"	9-7"	10-1"	10-7"	10-11"	---	---	---
	NI-40x	7-7"	8-1"	8-5"	8-10"	9-4"	9-8"	10-2"	10-8"	11-2"	---	---	---
	NI-60	8-1"	8-7"	9-0"	9-6"	10-1"	10-7"	11-2"	12-0"	12-8"	---	---	---
	NI-70	8-9"	9-3"	9-8"	10-1"	10-6"	11-1"	11-6"	12-3"	13-0"	---	---	---
	NI-80	8-7"	9-1"	9-5"	9-10"	10-4"	10-8"	11-2"	11-7"	12-3"	---	---	---
16"	NI-20	9-0"	9-3"	9-9"	10-2"	10-7"	11-1"	11-6"	12-1"	12-6"	---	---	---
	NI-40x	9-2"	9-8"	10-0"	10-6"	11-1"	11-5"	11-9"	12-4"	12-11"	---	---	---
	NI-60	9-4"	9-9"	10-3"	10-7"	11-1"	11-7"	12-1"	12-7"	13-2"	---	---	---
	NI-70	10-3"	10-8"	11-2"	11-6"	12-1"	12-6"	13-2"	14-1"	14-10"	---	---	---
	NI-80	10-1"	10-5"	11-0"	11-4"	11-10"	12-3"	12-8"	13-3"	14-0"	---	---	---

- Above table may be used for I-joist spacing of 24 inches on centre or less.
- Duct chase opening location distance is measured from inside face of supports to centre of opening.
- The above table is based on simple-span joists only. For other applications, contact your local distributor.
- Distances are based on uniformly loaded floor joists that meet the span requirements for a design live load of 40 psf and dead load of 15 psf, and a live load deflection limit of L/480.
- The above table is based on the I-joists being used at their maximum spans. The minimum distance as given above may be reduced for shorter spans; contact your local distributor.

FIGURE 7 FIELD-CUT HOLE LOCATOR



Knockouts are precut holes provided for the contractor's convenience to install electrical or small plumbing lines. They are 1-1/2 inches in diameter, and are spaced 15 inches on centre along the length of the I-joist. Where possible, it is preferable to use knockouts instead of field-cut holes.

Never drill, cut or notch the flange, or over-cut the web.


Holes in webs should be cut with a sharp saw.

For rectangular holes, avoid over-cutting the corners, as this can cause unnecessary stress concentrations. Slightly rounding the corners is recommended. Starting the rectangular hole by drilling a 1-inch diameter hole in each of the four corners and then making the cuts between the holes is another good method to minimize damage to the I-joist.

SAFETY AND CONSTRUCTION PRECAUTIONS



Do not walk on I-joists until fully fastened and braced, or serious injuries can result.



Never stack building materials over unheated I-joists. Once sheathed, do not over-stress I-joists with concentrated loads from building materials.

WARNING: I-joists are not stable until completely installed, and will not carry any load until fully braced and sheathed.

AVOID ACCIDENTS BY FOLLOWING THESE IMPORTANT GUIDELINES:

- Brace and nail each I-joist as it is installed, using hangers, blocking panels, rim board, and/or cross-bracing at joist ends. When I-joists are applied continuous over interior supports and a load-bearing wall is planned at that location, blocking will be required at the interior support.
- When the building is completed, the floor sheathing will provide lateral support for the top flanges of the I-joists. Until this sheathing is applied, temporary bracing, often called struts, or temporary sheathing must be applied to prevent I-joist rollover or buckling.
 - Temporary bracing or struts must be 1x4 inch minimum, at least 8 feet long and spaced no more than 8 feet on centre, and must be secured with a minimum of two 2-1/2" nails fastened to the top surface of each I-joist. Nail the bracing to a lateral restraint at the end of each bay. Lay ends of adjoining bracing over at least two I-joists.
 - Or, sheathing (temporary or permanent) can be nailed to the top flange of the first 4 feet of I-joists at the end of the bay.
- For cantilevered I-joists, brace top and bottom flanges, and brace ends with closure panels, rim board, or cross-bracing.
- Install and fully nail permanent sheathing to each I-joist before placing loads on the floor system. Then, stack building materials over beams or walls only.
- Never install a damaged I-joist.


Improper storage or installation, failure to follow applicable building codes, failure to follow span ratings for Nordic I-joists, failure to follow allowable hole sizes and locations, or failure to use web stiffeners when required can result in serious accidents. Follow these installation guidelines carefully.



PRODUCT WARRANTY

Chantiers Chibougamau guarantees that, in accordance with our specifications, Nordic products are free from manufacturing defects in material and workmanship.


Furthermore, Chantiers Chibougamau warrants that our products, when utilized in accordance with our handling and installation instructions, will meet or exceed our specifications for the lifetime of the structure.



Blocking Panel or Rim Joist	Maximum Factored Uniform Vertical Load* (plf)
Ni Joists	3,300

*The uniform vertical load is limited to a joist depth of 16 inches or less and is based on standard term load duration. It shall not be used in the design of a bending member, such as joist, header, or rafter. For concentrated vertical load transfer, see detail 1d.

2-1/2" nails at 6" o.c. to top plate (when used for lateral shear transfer, nail to bearing plate with same nailing as required for decking)



Blocking Panel or Rim Joist	Maximum Factored Uniform Vertical Load* (plf)
1-1/8" Rim Board Plus	8,090

*The uniform vertical load is limited to a rim board depth of 16 inches or less and is based on standard term load duration. It shall not be used in the design of a bending member, such as joist, header, or rafter. For concentrated vertical load transfer, see detail 1d.

One 2-1/2" face nail at each side of bearing


One 2-1/2" wire or spiral nail at top and bottom flange

Attach rim board to top plate using 2-1/2" wire or spiral toe-nails at 6" o.c.

To avoid splitting flange, start nails at least 1-1/2" from end of I-joist.

Nails may be driven at an angle to avoid splitting of bearing plate.



Minimum bearing length shall be 1-3/4" for the end bearings, and 3-1/2" for the intermediate bearings when applicable.



Pair of Squash Blocks	Maximum Factored Vertical Load per Pair of Squash Blocks (lbs)
2x Lumber	5,500
1-1/8" Rim Board Plus	4,300

3-1/2" wide 5-1/2" wide


Provide lateral bracing per detail 1a or 1b



Load bearing wall above shall align vertically with the bearing below. Other conditions, such as offset bearing walls, are not covered by this detail.

Blocking required over all interior supports under load-bearing walls or when floor joists are not continuous over support

Ni blocking panel per detail 1a




BACKER BLOCKS (Blocks must be long enough to permit required nailing without splitting)

Flange Width	Material Thickness Required*	Minimum Depth**
2-1/2"	1"	5-1/2"
3-1/2"	1-1/2"	7-1/4"

* Minimum grade for backer block material shall be S-P-F No. 2 or better for solid sawn lumber and wood structural panels conforming to CAN/CSA-O325 or CAN/CSA-O437 Standard.


** For face-mount hangers use net joist depth minus 3-1/4" for joists with 1-1/2" thick flanges. For 2" thick flanges use net depth minus 4-1/4".







NOTE: Unless hanger sides laterally support the top flange, bearing stiffeners shall be used.

Backer block required (both sides for face-mount hangers)


For hanger capacity see hanger manufacturer's recommendations. Verify double I-joist capacity to support concentrated loads.



NOTE: Unless hanger sides laterally support the top flange, bearing stiffeners shall be used.




1p FILLER BLOCK REQUIREMENTS FOR DOUBLE I-JOIST CONSTRUCTION



- NOTES:
- Support back of I-joist web during nailing to prevent damage to web/flange connection.
 - Leave a 1/8 to 1/4-inch gap between top of filler block and bottom of top I-joist flange.
 - Filler block is required between joists for full length of span.
 - Nail joists together with two rows of 3" nails at 12 inches o.c. (clinch when possible) on each side of the double I-joist. Total of four nails per foot required. If nails can be clinched, only two nails per foot are required.
 - The maximum factored load that may be applied to one side of the double joist using this detail is 860 lb/ft. Verify double I-joist capacity.

Flange Size	Net Depth	Filler Block Size
2-1/2" x 1-1/2"	9-1/2"	2-1/8" x 6"
	11-7/8"	2-1/8" x 8"
	14"	2-1/8" x 10"
	16"	2-1/8" x 12"
3-1/2" x 1-1/2"	9-1/2"	3" x 6"
	11-7/8"	3" x 8"
	14"	3" x 10"
	16"	3" x 12"
3-1/2" x 2"	11-7/8"	3" x 7"
	14"	3" x 9"
	16"	3" x 11"



NOTES:

- In some local codes, blocking is prescriptively required in the first joist space (or first and second joist space) next to the starter joist. Where required, see local code requirements for spacing of the blocking.
- All nails are common spiral in this detail.


All nails shown in the above details are assumed to be common wire nails unless otherwise noted. 3" (0.122" dia.) common spiral nails may be substituted for 2-1/2" (0.128" dia.) common wire nails. Framing lumber assumed to be Spruce-Pine-Fir No. 2 or better. Individual components not shown to scale for clarity.

WEB STIFFENERS

RECOMMENDATIONS:

- A bearing stiffener is required in all engineered applications with factored reactions greater than shown in the I-joist properties table found in the I-joist Construction Guide (C101). The gap between the stiffener and the flange is at the top.
- A bearing stiffener is required when the I-joist is supported in a hanger and the sides of the hanger do not extend up to, and support, the top flange. The gap between the stiffener and flange is at the top.
- A load stiffener is required at locations where a factored concentrated load greater than 2,370 lbs is applied to the top flange between supports, or in the case of a cantilever, anywhere between the cantilever tip and the support. These values are for standard term load duration, and may be adjusted for other load durations as permitted by the code. The gap between the stiffener and the flange is at the bottom.


FIGURE 2 WEB STIFFENER INSTALLATION DETAILS




Flange Width	Web Stiffener Size Each Side of Web
2-1/2"	1" x 2-5/16" minimum width
3-1/2"	1-1/2" x 2-5/16" minimum width

CANTILEVER DETAILS FOR VERTICAL BUILDING OFFSET

4a Method 1 — SHEATHING REINFORCEMENT ONE SIDE




Method 2 — SHEATHING REINFORCEMENT TWO SIDES



NOTE: Canadian softwood plywood sheathing or equivalent (minimum thickness 3/4") required on sides of joist. Depth shall match the full height of the joist. Nail with 2-1/2" nails at 6" o.c., top and bottom flange. Install with face grain horizontal. Attach I-joist to plate at all supports per detail 1b. Verify reinforced I-joist capacity.


RIM BOARD INSTALLATION DETAILS

8a ATTACHMENT DETAILS WHERE RIM BOARDS ABUT



CANTILEVER DETAILS FOR BALCONIES (NO WALL LOAD)


3a I-JOIST CANTILEVER DETAIL FOR BALCONIES (No Wall Load)



CAUTION: Cantilevers formed this way must be carefully detailed to prevent moisture intrusion into the structure and potential decay of untreated I-joist extensions.

Note: This detail is applicable to cantilevers supporting a maximum specified uniform live load of 60 psf.


3b LUMBER CANTILEVER DETAIL FOR BALCONIES (No Wall Load)



Note: This detail is applicable to cantilevers supporting a maximum specified uniform live load of 60 psf.

CANTILEVER DETAILS FOR VERTICAL BUILDING OFFSET (CONCENTRATED WALL LOAD)

4a Method 1 — SHEATHING REINFORCEMENT ONE SIDE




Method 2 — SHEATHING REINFORCEMENT TWO SIDES

- Use same installation as Method 1 but reinforce both sides of I-joist with sheathing.
- Use nailing pattern shown for Method 1 with opposite face nailing offset by 3\".

Note: Canadian softwood plywood sheathing or equivalent (minimum thickness 3/4\" required on sides of joist. Depth shall match the full height of the joist. Nail with 2-1/2\" nails at 6\" o.c., top and bottom flange. Install with face grain horizontal. Attach I-joist to plate at all supports per detail 1b. Verify reinforced I-joist capacity.


4b Alternate Method 2 — DOUBLE I-JOIST



Block I-joists together with filler blocks for the full length of the reinforcement. For I-joist flange widths greater than 3 inches place an additional row of 3\" nails along the centreline of the reinforcing panel from each side. Clinch when possible.

FIGURE 4 (continued)

See table below for NI reinforcement requirements at cantilever.




CANTILEVER REINFORCEMENT METHODS ALLOWED

JOIST DEPTH (in.)	ROOF TRUSS SPAN (ft.)	ROOF LOADING (UNFACTORED)											
		LL = 30 psf, DL = 15 psf				LL = 40 psf, DL = 15 psf				LL = 50 psf, DL = 15 psf			
		JOIST SPACING (in.)				JOIST SPACING (in.)				JOIST SPACING (in.)			
		12	16	19.2	24	12	16	19.2	24	12	16	19.2	24
9-1/2"	24	N	N	N	N	N	N	N	N	N	N	N	N
	28	N	N	N	N	N	N	N	N	N	N	N	N
	30	N	N	N	N	N	N	N	N	N	N	N	N
	32	N	N	N	N	N	N	N	N	N	N	N	N
	34	N	N	N	N	N	N	N	N	N	N	N	N
11-7/8"	24	N	N	N	N	N	N	N	N	N	N	N	N
	28	N	N	N	N	N	N	N	N	N	N	N	N
	30	N	N	N	N	N	N	N	N	N	N	N	N
	32	N	N	N	N	N	N	N	N	N	N	N	N
	34	N	N	N	N	N	N	N	N	N	N	N	N
14"	24	N	N	N	N	N	N	N	N	N	N	N	N
	28	N	N	N	N	N	N	N	N	N	N	N	N
	30	N	N	N	N	N	N	N	N	N	N	N	N
	32	N	N	N	N	N	N	N	N	N	N	N	N
	34	N	N	N	N	N	N	N	N	N	N	N	N
16"	24	N	N	N	N	N	N	N	N	N	N	N	N
	28	N	N	N	N	N	N	N	N	N	N	N	N
	30	N	N	N	N	N	N	N	N	N	N	N	N
	32	N	N	N	N	N	N	N	N	N	N	N	N
	34	N	N	N	N	N	N	N	N	N	N	N	N

- N = No reinforcement required.
- 1 = NI reinforced with 3/4\" wood structural panel on one side only.
- 2 = NI reinforced with 3/4\" wood structural panel on both sides, or double I-joist.
- X = Try a deeper joist or closer spacing.
- Maximum design load shall be: 15 psf roof dead load, 55 psf floor total load, and 80 psf wall load. Wall load is based on 3'-0\" maximum width window or door openings.
- For larger openings, or multiple 3'-0\" wide openings spaced less than 6'-0\" o.c., additional joists beneath the opening's cripple studs may be required.
- Table applies to joists 12\" to 24\" o.c. that meet the floor span requirements for a design live load of 40 psf and dead load of 15 psf, and a live load deflection limit of L/480. Use 12\" o.c. requirements for lesser spacing.
- For conventional roof construction using a ridge beam, the Roof Truss Span column above is equivalent to the distance between the supporting wall and the ridge beam. When the roof is framed using a ridge board, the Roof Truss Span is equivalent to the distance between the supporting walls as if a truss is used.
- Cantilevered joists supporting girder trusses or roof beams may require additional reinforcing.


BRICK CANTILEVER DETAILS FOR VERTICAL BUILDING OFFSET (CONCENTRATED WALL LOAD)

5a SHEATHING REINFORCEMENT



Note: Canadian softwood plywood sheathing or equivalent (minimum thickness 3/4\" required on sides of joist. Depth shall match the full height of the joist. Nail with 2-1/2\" nails at 6\" o.c., top and bottom flange. Install with face grain horizontal. Attach I-joist to plate at all supports per detail 1b. Verify reinforced I-joist capacity.


5b SET-BACK DETAIL



Notes:

- Provide full depth blocking between joists over support (not shown for clarity).
- Attach I-joist to plate at all supports per detail 1b.
- 3-1/2\" minimum I-joist bearing required.

5c SET-BACK CONNECTION




Notes:

- Verify girder joist capacity if the back span exceeds the joist spacing.
- Attach double I-joist per detail 1p, if required.

FIGURE 5 (continued)

See table below for NI reinforcement requirements at cantilever.



BRICK CANTILEVER REINFORCEMENT METHODS ALLOWED

JOIST DEPTH (in.)	ROOF TRUSS SPAN (ft.)	ROOF LOADING (UNFACTORED)											
		LL = 30 psf, DL = 15 psf				LL = 40 psf, DL = 15 psf				LL = 50 psf, DL = 15 psf			
		JOIST SPACING (in.)				JOIST SPACING (in.)				JOIST SPACING (in.)			
		12	16	19.2	24	12	16	19.2	24	12	16	19.2	24
9-1/2"	24	N	N	N	N	N	N	N	N	N	N	N	N
	28	N	N	N	N	N	N	N	N	N	N	N	N
	30	N	N	N	N	N	N	N	N	N	N	N	N
	32	N	N	N	N	N	N	N	N	N	N	N	N
	34	N	N	N	N	N	N	N	N	N	N	N	N
11-7/8"	24	N	N	N	N	N	N	N	N	N	N	N	N
	28	N	N	N	N	N	N	N	N	N	N	N	N
	30	N	N	N	N	N	N	N	N	N	N	N	N
	32	N	N	N	N	N	N	N	N	N	N	N	N
	34	N	N	N	N	N	N	N	N	N	N	N	N
14"	24	N	N	N	N	N	N	N	N	N	N	N	N
	28	N	N	N	N	N	N	N	N	N	N	N	N
	30	N	N	N	N	N	N	N	N	N	N	N	N
	32	N	N	N	N	N	N	N	N	N	N	N	N
	34	N	N	N	N	N	N	N	N	N	N	N	N
16"	24	N	N	N	N	N	N	N	N	N	N	N	N
	28	N	N	N	N	N	N	N	N	N	N	N	N
	30	N	N	N	N	N	N	N	N	N	N	N	N
	32	N	N	N	N	N	N	N	N	N	N	N	N
	34	N	N	N	N	N	N	N	N	N	N	N	N


- N = No reinforcement required.
- 1 = NI reinforced with 3/4\" wood structural panel on one side only.
- 2 = NI reinforced with 3/4\" wood structural panel on both sides, or double I-joist.
- X = Try a deeper joist or closer spacing.
- Maximum design load shall be: 15 psf roof dead load, 55 psf floor total load, and 80 psf wall load. Wall load is based on 3'-0\" maximum width window or door openings.
- For larger openings, or multiple 3'-0\" wide openings spaced less than 6'-0\" o.c., additional joists beneath the opening's cripple studs may be required.
- Table applies to joists 12\" to 24\" o.c. that meet the floor span requirements for a design live load of 40 psf and dead load of 15 psf, and a live load deflection limit of L/480. Use 12\" o.c. requirements for lesser spacing.
- For conventional roof construction using a ridge beam, the Roof Truss Span column above is equivalent to the distance between the supporting wall and the ridge beam. When the roof is framed using a ridge board, the Roof Truss Span is equivalent to the distance between the supporting walls as if a truss is used.
- Cantilevered joists supporting girder trusses or roof beams may require additional reinforcing.

WEB HOLES

RULES FOR CUTTING HOLES AND DUCT CHASE OPENINGS:

- The distance between the inside edge of the support and the centreline of any hole or duct chase opening shall be in compliance with the requirements of Table 1 or 2, respectively.
- I-joist top and bottom flanges must NEVER be cut, notched, or otherwise modified.
- Whenever possible, field-cut holes should be centred on the middle of the web.
- The maximum size hole or the maximum depth of a duct chase opening that can be cut into an I-joist web shall equal the clear distance between the flanges of the I-joist minus 1/4 inch. A minimum of 1/8 inch should always be maintained between the top or bottom of the hole or opening and the adjacent I-joist flange.
- The sides of square holes or longest sides of rectangular holes should not exceed 3/4 of the diameter of the maximum round hole permitted at that location.
- Where more than one hole is necessary, the distance between adjacent hole edges shall exceed twice the diameter of the largest round hole or twice the size of the largest square hole (or twice the length of the longest side of the longest rectangular hole or duct chase opening) and each hole and duct chase opening shall be sized and located in compliance with the requirements of Tables 1 and 2, respectively.
- A knockout is not considered a hole, may be utilized anywhere it occurs, and may be ignored for purposes of calculating minimum distances between holes and/or duct chase openings.
- Holes measuring 1-1/2 inches or smaller shall be permitted anywhere in a cantilevered section of a joist. Holes of greater size may be permitted subject to verification.
- A 1-1/2 inch hole or smaller can be placed anywhere in the web provided that it meets the requirements of rule number 6 above.
- All holes and duct chase openings shall be cut in a workman-like manner in accordance with the restrictions listed above and as illustrated in Figure 7.
- Limit three maximum size holes per span, of which one may be a duct chase opening.
- A group of round holes at approximately the same location shall be permitted if they meet the requirements for a single round hole circumscribed around them.

FIGURE 7
FIELD-CUT HOLE LOCATOR



A knockout is NOT considered a hole, may be utilized wherever it occurs and may be ignored for purposes of calculating minimum distances between holes.

Knockouts are pre-scored holes provided for the contractor's convenience to install electrical or small plumbing lines. They are 1-1/2 inches in diameter, and are spaced 15 inches on centre along the length of the joist. Where possible, it is preferable to use knockouts instead of field-cut holes.

Never drill, cut or notch the flange, or over-cut the web.

Holes in webs should be cut with a sharp saw.

For rectangular holes, avoid over-cutting the corners, as this can cause unnecessary stress concentrations. Slightly rounding the corners is recommended. Starting the rectangular hole by drilling a 1-inch diameter hole in each of the four corners and then making the cuts between the holes is another good method to minimize damage to the I-joist.

TABLE 1
LOCATION OF CIRCULAR HOLES IN JOIST WEBS
Simple or Multiple Span for Dead Loads up to 15 psf and Live Loads up to 40 psf

Joist Depth	Joist Series	Minimum distance from inside face of any support to centre of hole (in.)												Span adjustment Factor		
		Round hole diameter (in.)														
		2	3	4	5	6	6-1/4	7	8	8-5/8	9	10	10-3/4		11	12
9-1/2"	N-10	0.7	1.0	1.3	1.6	1.9	2.2	2.5	2.8	3.1	3.4	3.7	4.0	4.3	4.6	4.9
	N-12	0.7	1.0	1.3	1.6	1.9	2.2	2.5	2.8	3.1	3.4	3.7	4.0	4.3	4.6	4.9
	N-14	0.7	1.0	1.3	1.6	1.9	2.2	2.5	2.8	3.1	3.4	3.7	4.0	4.3	4.6	4.9
	N-16	0.7	1.0	1.3	1.6	1.9	2.2	2.5	2.8	3.1	3.4	3.7	4.0	4.3	4.6	4.9
11-7/8"	N-10	0.7	1.0	1.3	1.6	1.9	2.2	2.5	2.8	3.1	3.4	3.7	4.0	4.3	4.6	4.9
	N-12	0.7	1.0	1.3	1.6	1.9	2.2	2.5	2.8	3.1	3.4	3.7	4.0	4.3	4.6	4.9
	N-14	0.7	1.0	1.3	1.6	1.9	2.2	2.5	2.8	3.1	3.4	3.7	4.0	4.3	4.6	4.9
	N-16	0.7	1.0	1.3	1.6	1.9	2.2	2.5	2.8	3.1	3.4	3.7	4.0	4.3	4.6	4.9
14"	N-10	0.7	1.0	1.3	1.6	1.9	2.2	2.5	2.8	3.1	3.4	3.7	4.0	4.3	4.6	4.9
	N-12	0.7	1.0	1.3	1.6	1.9	2.2	2.5	2.8	3.1	3.4	3.7	4.0	4.3	4.6	4.9
	N-14	0.7	1.0	1.3	1.6	1.9	2.2	2.5	2.8	3.1	3.4	3.7	4.0	4.3	4.6	4.9
	N-16	0.7	1.0	1.3	1.6	1.9	2.2	2.5	2.8	3.1	3.4	3.7	4.0	4.3	4.6	4.9
16"	N-10	0.7	1.0	1.3	1.6	1.9	2.2	2.5	2.8	3.1	3.4	3.7	4.0	4.3	4.6	4.9
	N-12	0.7	1.0	1.3	1.6	1.9	2.2	2.5	2.8	3.1	3.4	3.7	4.0	4.3	4.6	4.9
	N-14	0.7	1.0	1.3	1.6	1.9	2.2	2.5	2.8	3.1	3.4	3.7	4.0	4.3	4.6	4.9
	N-16	0.7	1.0	1.3	1.6	1.9	2.2	2.5	2.8	3.1	3.4	3.7	4.0	4.3	4.6	4.9

- Above table may be used for I-joist spacing of 24 inches on centre or less.
- Hole location distance is measured from inside face of supports to centre of hole.
- Distances in this chart are based on uniformly loaded joists.

OPTIONAL:

The above table is based on the I-joists used at their maximum span. If the I-joists are placed or less than their full maximum span (see Maximum Span Table), the minimum distance from the centreline of the hole to the face of any support (D) as given above may be reduced as follows:

$$D_{\text{reduced}} = \frac{L_{\text{actual}}}{L_{\text{max}}} \times D$$

Where:

- D_{reduced} = Distance from the inside face of any support to centre of hole, reduced for less than maximum span applications.
- L_{actual} = The actual measured span distance between the inside faces of supports (ft).
- L_{max} = Span Adjustment Factor given in this table.
- D = The minimum distance from the inside face of any support to centre of hole from this table.

TABLE 2
DUCT CHASE OPENING SIZES AND LOCATIONS — Simple Span Only

Joist Depth	Joist Series	Minimum distance from inside face of any support to centre of opening (in.)											
		8	10	12	14	16	18	20	22	24	26	28	30
9-1/2"	N-10	4.1	4.5	4.9	5.3	5.7	6.1	6.5	6.9	7.3	7.7	8.1	8.5
	N-12	4.1	4.5	4.9	5.3	5.7	6.1	6.5	6.9	7.3	7.7	8.1	8.5
	N-14	4.1	4.5	4.9	5.3	5.7	6.1	6.5	6.9	7.3	7.7	8.1	8.5
	N-16	4.1	4.5	4.9	5.3	5.7	6.1	6.5	6.9	7.3	7.7	8.1	8.5
11-7/8"	N-10	4.1	4.5	4.9	5.3	5.7	6.1	6.5	6.9	7.3	7.7	8.1	8.5
	N-12	4.1	4.5	4.9	5.3	5.7	6.1	6.5	6.9	7.3	7.7	8.1	8.5
	N-14	4.1	4.5	4.9	5.3	5.7	6.1	6.5	6.9	7.3	7.7	8.1	8.5
	N-16	4.1	4.5	4.9	5.3	5.7	6.1	6.5	6.9	7.3	7.7	8.1	8.5
14"	N-10	4.1	4.5	4.9	5.3	5.7	6.1	6.5	6.9	7.3	7.7	8.1	8.5
	N-12	4.1	4.5	4.9	5.3	5.7	6.1	6.5	6.9	7.3	7.7	8.1	8.5
	N-14	4.1	4.5	4.9	5.3	5.7	6.1	6.5	6.9	7.3	7.7	8.1	8.5
	N-16	4.1	4.5	4.9	5.3	5.7	6.1	6.5	6.9	7.3	7.7	8.1	8.5
16"	N-10	4.1	4.5	4.9	5.3	5.7	6.1	6.5	6.9	7.3	7.7	8.1	8.5
	N-12	4.1	4.5	4.9	5.3	5.7	6.1	6.5	6.9	7.3	7.7	8.1	8.5
	N-14	4.1	4.5	4.9	5.3	5.7	6.1	6.5	6.9	7.3	7.7	8.1	8.5
	N-16	4.1	4.5	4.9	5.3	5.7	6.1	6.5	6.9	7.3	7.7	8.1	8.5

- Above table may be used for I-joist spacing of 24 inches on centre or less.
- Duct chase opening location distance is measured from inside face of supports to centre of opening.
- The above table is based on simple-span joists only. For other applications, contact your local distributor.
- Distances are based on uniformly loaded floor joists that meet the span requirements for a design live load of 40 psf and dead load of 15 psf, and a live load deflection limit of L/480. For other applications, contact your local distributor.

INSTALLING THE GLUED FLOOR SYSTEM

- Wipe any mud, dirt, water, or ice from I-joist flanges before gluing.
- Snap a chalk line across the I-joists four feet from the wall for panel edge alignment and as a boundary for spreading glue.
- Spread only enough glue to lay one or two panels at a time, or follow specific recommendations from the glue manufacturer.
- Lay the first panel with tongue side to the wall, and nail in place. This protects the tongue of the next panel from damage when tapped into place with a block and sledgehammer.
- Apply a continuous line of glue (about 1/4-inch diameter) to the top flange of a single I-joist. Apply glue in a winding pattern on wide areas, such as with double I-joists.
- Apply two lines of glue on I-joists where panel ends butt to assure proper gluing of each end.
- After the first row of panels is in place, spread glue in the groove of one or two panels at a time before laying the next row. Glue line may be continuous or spaced, but avoid squeeze-out by applying a thinner line (1/8 inch) than used on I-joist flanges.
- Tap the second row of panels into place, using a block to protect groove edges.
- Stagger end joints in each succeeding row of panels. A 1/8-inch space between all end joints and 1/8-inch at all edges, including T&G edges, is recommended. (Use a spacer tool or an 1/8" common nail to assure accurate and consistent spacing.)
- Complete all nailing of each panel before glue sets. Check the manufacturer's recommendations for cure time. (Warm weather accelerates glue setting.) Use 2" ring- or screw-shank nails for panels 3/4-inch thick or less, and 2-1/2" ring- or screw-shank nails for thicker panels. Space nails per the table below. Closer nail spacing may be required by some codes, or for diaphragm construction. The finished deck can be walked on right away and will carry construction loads without damage to the glue bond.

FASTENERS FOR SHEATHING AND SUBFLOORING(1)

Maximum End Spacing (in.)	Minimum Panel Thickness (in.)	Common Wire or Spiral Nails	Ring Thread Nails or Screws	Shank	Maximum Spacing of Fasteners	Interior Supports
16	5/8	2"	1-3/4"	2"	6"	12"
20	5/8	2"	1-3/4"	2"	6"	12"
24	3/4	2"	1-3/4"	2"	6"	12"

- Fasteners of sheathing and subflooring shall conform to the above table.
- Staples shall not be less than 1/16-inch in diameter or thickness, with not less than a 3/8-inch crown driven with the crown parallel to framing.
- Flooring screws shall not be less than 1/8-inch in diameter.
- Special conditions may impose heavy traffic and concentrated loads that require construction in excess of the minimums shown.
- Use only adhesives conforming to CAN/CGSB-71.26 Standard, Adhesives for Field-Gluing Plywood to Lumber Framing for Floor System, applied in accordance with the manufacturer's recommendations. If OSB panels with sealed surfaces and edges are to be used, use only solvent-based glues; check with panel manufacturer.


Ref: NRC-CNRC, National Building Code of Canada 2010, Table 9.23.3.5.

IMPORTANT NOTE:


Floor sheathing must be field glued to the I-joist flanges in order to achieve the maximum spans shown in this document. If sheathing is nailed only, I-joist spans must be verified with your local distributor.

RIM BOARD INSTALLATION DETAILS


8a ATTACHMENT DETAILS WHERE RIM BOARDS ABUT



8b TOE-NAIL CONNECTION AT RIM BOARD



8c 2X LEDGER TO RIM BOARD ATTACHMENT DETAIL



2x ledger board (preservative-treated) must be greater than or equal to the depth of the deck joist




2015-04-16




PRODUCT WARRANTY

OSB Products warrants that, in accordance with our specifications, OSB products are free from manufacturing defects in material and workmanship.

Furthermore, OSB Products warrants that our products, when utilized in accordance with our handling and installation instructions, will meet or exceed our specifications for the lifetime of the structure.





N-CDD / November 2014

SAFETY AND CONSTRUCTION PRECAUTIONS

WARNING

I-joists are not stable until completely installed, and will not carry any load until fully braced and sheathed.


Avoid Accidents by Following these Important Guidelines:

1. Brace and nail each I-joist as it is installed, using hangers, blocking panels, rim board, and/or cross-bridging at joist ends. When I-joists are applied continuously over interior supports and a load-bearing wall is planned at that location, blocking will be required at the interior support.
2. When the building is completed, the floor sheathing will provide lateral support for the top flanges of the I-joists. Until this sheathing is applied, temporary bracing, often called struts, or temporary sheathing must be applied to prevent I-joist rollover or buckling.
 - Temporary bracing or struts must be 1x4 inch minimum, at least 8 feet long and spaced no more than 8 feet on center, and must be secured with a minimum of two 2-1/2" nails fastened to the top surface of each I-joist. Nail the bracing to a lateral restraint at the end of each bay. Lap ends of adjoining bracing over at least two I-joists.
 - Or, sheathing (temporary or permanent) can be nailed to the top flange of the first 4 feet of I-joists at the end of the bay.
3. For cantilevered I-joists, brace top and bottom flanges, and brace ends with closure panels, rim board, or cross-bridging.
4. Install and fully nail permanent sheathing to each I-joist before placing loads on the floor system. Then, stack building materials over beams or walls only.
5. Never install a damaged I-joist.

Improper storage or installation, failure to follow applicable building codes, failure to follow span ratings for Nordic I-joists, failure to follow allowable hole sizes and locations, or failure to use web stiffeners when required can result in serious accidents. Follow these installation guidelines carefully.

STORAGE AND HANDLING GUIDELINES


1. Bundle wrap can be slippery when wet. Avoid walking on wrapped bundles.
2. Store, stack, and handle I-joists vertically and level only.
3. Always stack and handle I-joists in the upright position only.
4. Do not store I-joists in direct contact with the ground and/or flatwise.
5. Protect I-joists from weather, and use spacers to separate bundles.
6. Bundled units should be kept intact until time of installation.
7. When handling I-joists with a crane on the job site, take a few simple precautions to prevent damage to the I-joists and injury to your work crew.
 - Pick I-joists in bundles as shipped by the supplier.
 - Orient the bundles so that the webs of the I-joists are vertical.
 - Pick the bundles at the 5th points, using a spreader bar if necessary.
8. Do not handle I-joists in a horizontal orientation.
9. NEVER USE OR TRY TO REPAIR A DAMAGED I-JOIST.




INSTALLING NORDIC I-JOISTS

1. Before laying out floor system components, verify that I-joist flange widths match hanger widths. If not, contact supplier.
2. Except for cutting to length, I-joist flanges should never be cut, drilled, or notched.
3. Install I-joists so that top and bottom flanges are within 1/2 inch of true vertical alignment.
4. I-joists must be anchored securely to supports before floor sheathing is attached, and supports for multiple-span joists must be level.
5. Minimum bearing lengths: 1-3/4 inches for end bearings and 3-1/2 inches for intermediate bearings.
6. When using hangers, seat I-joists firmly in hanger bottoms to minimize settlement.
7. Leave a 1/16-inch gap between the I-joist end and a header.
8. Concentrated loads greater than those that can normally be expected in residential construction should only be applied to the top surface of the top flange. Normal concentrated loads include track lighting fixtures, audio equipment and security cameras. Never suspend unusual or heavy loads from the I-joist's bottom flange. Whenever possible, suspend all concentrated loads from the top of the I-joist. Or, attach the load to blocking that has been securely fastened to the I-joist webs.
9. Never install I-joists where they will be permanently exposed to weather, or where they will remain in direct contact with concrete or masonry.
10. Restrain ends of floor joists to prevent rollover. Use rim board, rim joists or I-joist blocking panels.
11. For I-joists installed over and beneath bearing walls, use full depth blocking panels, rim board, or squash blocks (triple members) to transfer gravity loads through the floor system to the wall or foundation below.
12. Due to shrinkage, common framing lumber set on edge may never be used as blocking or rim boards. I-joist blocking panels or other engineered wood products – such as rim board – must be cut to fit between the I-joists, and on I-joist-compatible depth selected.
13. Provide permanent lateral support of the bottom flange of all I-joists at interior supports of multiple-span joists. Similarly, support the bottom flange of all cantilevered I-joists at the end support next to the cantilever extension. In the completed structure, the gypsum wallboard ceiling provides this lateral support. Until the final finished ceiling is applied, temporary bracing or struts must be used.
14. If square-edge panels are used, edges must be supported between I-joists with 2x4 blocking. Glue panels to blocking to minimize squeaks. Blocking is not required under structural finish flooring, such as wood strip flooring, or if a separate underlayment layer is installed.
15. Nail spacing: Space nails installed to the flange's top face in accordance with the applicable building code requirements or approved building plans.


FIGURE 1
TYPICAL NORDIC I-JOIST FLOOR FRAMING AND CONSTRUCTION DETAILS




All nails shown in the above details are assumed to be common wire nails unless otherwise noted. 3" (0.122" dia.) common spiral nails may be substituted for 2-1/2" (0.128" dia.) common wire nails. Framing lumber assumed to be Spruce-Pine-Fir No. 2 or better. Individual components not shown to scale for clarity.




*The uniform vertical load is limited to a joist depth of 16 inches or less and is based on standard term load duration. It shall not be used in the design of a bending member, such as joist, header, or rafter. For concentrated vertical load transfer, see detail 1d.



*The uniform vertical load is limited to a rim board depth of 16 inches or less and is based on standard term load duration. It shall not be used in the design of a bending member, such as joist, header, or rafter. For concentrated vertical load transfer, see detail 1d.



Minimum 1-3/4" bearing required



Provide lateral bracing per detail 1a, 1b, or 1c

MAXIMUM FLOOR SPANS

- Maximum clear spans applicable to simple-span or multiple-span residential floor construction with a design live load of 40 psf and dead load of 15 psf. The ultimate limit states are based on the factored loads of 1.50L + 1.25D. The serviceability limit states include the consideration for floor vibration and a live load deflection limit of L/480. For multiple-span applications, the end spans shall be 40% or more of the adjacent span.
- Spans are based on a composite floor with glued-nailed oriented strand board (OSB) sheathing with a minimum thickness of 5/8 inch for a joist spacing of 19.2 inches or less, or 3/4 inch for joist spacing of 24 inches. Adhesive shall meet the requirements given in CGS-71.26 Standard. No concrete topping or bridging element was assumed. Increased spans may be achieved with the use of gypsum and/or a row of blocking at mid-span.
- Minimum bearing length shall be 1-3/4 inches for the end bearings, and 3-1/2 inches for the intermediate bearings.
- Bearing stiffeners are not required when I-joists are used with the spans and spacings given in this table, except as required for hangers.
- This span chart is based on uniform loads. For applications with other than uniform loads, an engineering analysis may be required based on the use of five design properties.
- Tables are based on Limit States Design per CAN/CSA C08-09 Standard, and NBC 2010.
- SI units conversion: 1 inch = 25.4 mm
1 foot = 0.305 m


MAXIMUM FLOOR SPANS FOR NORDIC I-JOISTS SIMPLE AND MULTIPLE SPANS

Joist Depth	Joist Series	Simple spans				Multiple spans			
		On centre spacing				On centre spacing			
		12"	16"	19.2"	24"	12"	16"	19.2"	24"
9-1/2"	Ni-20	15-11"	14-2"	13-9"	12-5"	16-3"	15-4"	14-10"	14-7"
	Ni-40	16-11"	15-2"	14-8"	14-9"	17-5"	16-5"	15-10"	15-5"
	Ni-60	16-5"	15-4"	14-10"	14-11"	17-2"	16-7"	16-0"	16-11"
	Ni-70	17-1"	16-11"	15-6"	15-9"	18-7"	17-4"	16-9"	16-10"
	Ni-80	17-3"	16-3"	15-8"	15-9"	18-10"	17-5"	16-11"	17-9"
11-7/8"	Ni-20	16-11"	16-0"	15-5"	15-6"	18-4"	17-3"	16-8"	16-7"
	Ni-40	18-1"	17-2"	16-5"	16-6"	20-2"	18-6"	17-9"	17-7"
	Ni-60	18-4"	17-3"	16-9"	16-9"	20-3"	18-9"	18-0"	18-11"
	Ni-70	19-2"	18-0"	17-4"	17-5"	21-6"	19-11"	19-0"	19-11"
	Ni-80	19-9"	18-5"	17-6"	17-7"	21-9"	20-2"	19-3"	19-4"
14"	Ni-20	20-2"	19-7"	19-10"	19-11"	22-3"	20-7"	19-8"	19-9"
	Ni-40	20-4"	19-9"	19-11"	19-11"	22-5"	20-9"	19-10"	19-11"
	Ni-60	20-5"	19-11"	19-11"	19-11"	22-6"	21-0"	20-11"	20-11"
	Ni-70	21-7"	20-5"	19-11"	19-11"	23-10"	22-11"	21-11"	21-12"
	Ni-80	21-11"	20-5"	19-11"	19-11"	24-5"	22-6"	21-5"	21-6"
16"	Ni-20	22-5"	20-8"	19-9"	19-10"	24-9"	22-10"	21-10"	21-10"
	Ni-40	22-7"	20-11"	19-11"	19-11"	25-0"	23-1"	22-0"	22-2"
	Ni-60	22-8"	20-8"	19-9"	19-10"	25-1"	23-2"	22-1"	22-1"
	Ni-70	23-4"	21-5"	20-9"	20-10"	26-5"	24-5"	23-5"	23-6"
	Ni-80	23-11"	22-1"	21-1"	21-2"	26-8"	24-8"	23-8"	23-9"
18"	Ni-20	24-5"	22-6"	21-5"	21-6"	26-11"	24-10"	23-9"	23-9"
	Ni-40	24-9"	22-9"	21-9"	21-10"	27-5"	25-2"	24-0"	24-11"
	Ni-60	25-1"	23-1"	22-1"	22-2"	28-0"	25-6"	24-5"	24-6"
	Ni-70	25-5"	23-5"	22-5"	22-6"	28-4"	26-0"	25-0"	25-1"
	Ni-80	25-9"	23-9"	22-9"	23-0"	28-8"	26-4"	25-4"	25-5"

CEMC EVALUATION REPORT 13032-R

1-JOIST HANGERS

- Hangers shown illustrate the three most commonly used metal hangers to support I-joists.
- All nailing must meet the hanger manufacturer's recommendations.
- Hangers should be selected based on the joist depth, flange width and load capacity based on the maximum spans.
- Web stiffeners are required when the sides of the hangers do not laterally brace the top flange of the I-joist.




WEB STIFFENERS

RECOMMENDATIONS:

- A bearing stiffener is required in all engineered applications with factored reactions greater than shown in the I-joist properties table found in the I-joist Construction Guide (C101). The gap between the stiffener and the flange is at the top.
- A bearing stiffener is required when the I-joist is supported in a hanger end and the sides of the hanger do not extend up to, and support, the top flange. The gap between the stiffener and flange is at the top.
- A load stiffener is required at locations where a factored concentrated load greater than 2,370 lbs is applied to the top flange between supports, or in the case of a cantilever, anywhere between the cantilever tip and the support. These values are for standard term load duration, and may be adjusted for other load durations as permitted by the code. The gap between the stiffener and the flange is at the bottom.

SI units conversion: 1 inch = 25.4 mm

FIGURE 2
WEB STIFFENER INSTALLATION DETAILS



See table below for web stiffener size requirements

STIFFENER SIZE REQUIREMENTS











Flange Width	Web Stiffener Size Each Side of Web
2-1/2"	1" x 2-5/16" minimum width
3-1/2"	1-1/2" x 2-5/16" minimum width

NORDIC I-JOIST SERIES

Series	Flange Width	Material Thickness	Minimum Depth
Ni-20	2-1/2"	1"	5-1/2"
Ni-40	3-1/2"	1-1/2"	7-1/4"
Ni-60	3-1/2"	1-1/2"	7-1/4"
Ni-70	3-1/2"	1-1/2"	7-1/4"
Ni-80	3-1/2"	1-1/2"	7-1/4"
Ni-90	3-1/2"	1-1/2"	7-1/4"
Ni-92s	3-1/2"	1-1/2"	7-1/4"

Chantiers Chibougamau Ltd. harvests its own trees, which enables Nordic products to adhere to strict quality control procedures throughout the manufacturing process. Every phase of the operation, from harvest to the finished product, reflects our commitment to quality.

Nordic Engineered Wood I-joists use only finger-jointed lumber in their flanges, ensuring consistent quality, superior strength and longer span carrying capacity.



- Notes:
- Support back of I-joist web during nailing to prevent damage to web/flange connections.
 - Leave a 1/8 to 1/4-inch gap between top of filler block and bottom of top I-joist flange.
 - Filler block is required between joists for full length of span.
 - Nail joists together with two rows of 3" nails at 12 inches o.c. (clinched when possible) on each side of the double I-joist. Total of four nails per foot required. If nails can be clinched, only two nails per foot are required.
 - The maximum factored load that may be applied to one side of the double I-joist using this detail is 860 lb/ft. Verify double I-joist capacity.

FILLER BLOCK REQUIREMENTS FOR DOUBLE I-JOIST CONSTRUCTION

Flange Size	Joist Depth	Filler Block Size
2-1/2" x 1-1/2"	9-1/2"	2-1/8" x 6"
	11-7/8"	2-1/8" x 8"
	14"	2-1/8" x 10"
	16"	2-1/8" x 12"
3-1/2" x 1-1/2"	9-1/2"	3" x 6"
	11-7/8"	3" x 8"
	14"	3" x 10"
	16"	3" x 12"
3-1/2" x 2"	11-7/8"	3" x 7"
	14"	3" x 9"
	16"	3" x 11"

