



CONSTRUCTION SUMMARY

Lot: 34
Model: 40.04 A DALERIDGE
Project/Phase: Pine Valley Forevergreen / 1

APPLIANCES


Invoice	Qty.	Description
2709	1	APPLIANCE SPECIFICATIONS ATTACHED - SIGNED COPY
14Apr21 NoCat		

PV- #34
April 1/2021
EY Jan


JENN-AIR® DETAILED PLANNING DIMENSIONS

30" INDUCTION RANGE
JIS1450D - 29⁷/₈" x 36" x 28³/₈"

PRODUCT DIMENSIONS



FRONT VIEW



TOP VIEW

MODEL #	JIS1450D	
	in	cm
A Overall width	29 ⁷ / ₈	75.9
B Width of door/drawer	29 ⁷ / ₈	75.9
C Height from cooktop to top of vent	1 ³ / ₈	2.0
D Space between door and control panel	1 ³ / ₈	2.1
E Height to top of handle		
Pro-Style® Stainless	22 ⁷ / ₈	58.1
Euro-Style Stainless	22 ⁷ / ₈	58.1
F Height of door	23 ¹ / ₄	59.0
G* Height to top of cooktop edge	36	91.4
H Height of warming drawer	6 ⁷ / ₈	16.0
I Space between door and warming drawer	1 ³ / ₈	2.0
J Depth from front of console to back of range (max.)	27 ¹ / ₄	70.7
K Depth from handle to back of range (max.)		
Pro-Style® Stainless	28 ³ / ₈	73.5
Euro-Style Stainless	28 ³ / ₈	71.9

* With leveling legs screwed all the way in. Range can be raised approximately 1" (2.5 cm) by adjusting the leveling legs.

IMPORTANT: Dimensional specifications are provided for planning purposes only. Do not make your estimate based on this information. Refer to the Installation or User Guide.



April 1, 2021
PV-34

[Handwritten signature]


JENN-AIR® DETAILED PLANNING DIMENSIONS

2 of 3

30" INDUCTION RANGE

JIS1450D – 29⁷/₈" x 36" x 28⁵/₁₆"


DIMENSIONS AS INSTALLED



SIDE VIEW

MODEL #	JIS1450D
A* Height to top of cooking surface (min.)	35 ¹ / ₄ 90.2
B* Height to top of door (min.)	30 ¹ / ₁₆ 78.0
C* Height to top of handle (min.)	
Pro-Style® Stainless	30 ¹ / ₂ 77.5
Euro-Style Stainless	30 ¹ / ₄ 77.5
D* Height to top of warming drawer (min.)	6 ⁷ / ₈ 17.5
E* Height to top of countertop (min.)	35 ¹ / ₂ 91.0
F Depth with door fully open	50 ¹ / ₁₆ 128.5
Depth with handle	
Pro-Style® Stainless	28 ³ / ₁₆ 73.5
Euro-Style Stainless	28 ³ / ₁₆ 71.9
H Depth without handle	27 ¹ / ₂ 70.7
I Depth without door	25 63.5
J Depth with door	26 ¹ / ₁₆ 66.8
K Height of countertop channel	1 ¹ / ₁₆ 4.6
L Depth to countertop channel	1 ³ / ₁₆ 3.0

* With leveling legs screwed all the way in. Range can be raised approximately 1" (2.5 cm) by adjusting the leveling legs.



SIDE VIEW – COUNTERTOP CHANNEL DETAIL

IMPORTANT: Dimensional specifications are provided for planning purposes only. Do not make any estimate based on this information. Refer to the installation or User's Guide.

PV-34

April 1, 2021

[Signature]


JENN-AIR® DETAILED PLANNING DIMENSIONS

3 of 3

30" INDUCTION RANGE

JIS1450D – 29¹¹/₁₆" x 36" x 28⁵/₁₆"

OPENING/CLEARANCE DIMENSIONS






MODEL #	JIS1450D
A	Width of combustible area above cooking surface (min.)
B	Width from cooltop to fixed wall or other combustible material (min.)
C	Width from electrical installation area to cabinet (min.)
D*	Height to bottom of uncovered wood or metal cabinet above cooking surface (min.)
E	Height to bottom of uncovered wood or metal cabinet (min.)
F	Height of electrical installation area (max.)
G	Depth of electrical installation area (max.)
H	Depth of upper cabinet (recommended)
I	Width of cutout
J	Width to power cord
e	Recommended junction box location

*Dimension can be reduced by 6" (15.2 cm) when bottom of wood or metal cabinet is covered by not less than 1/2" (0.6 cm) flame retardant millboard covered with not less than No. 28 MSG sheet metal, 0.015" (0.4 mm) stainless steel, 0.024" (0.6 mm) aluminum or 0.020" (0.5 mm) copper.

If installing a hood or microwave hood combination above the range, follow the hood or microwave hood combination instructions for dimensional clearances above the cooking surface.

ELECTRICAL REQUIREMENTS

240 volt, 60 Hz, AC only, 40-amp fused, grounded circuit is required.
A dedicated circuit is recommended. Minimum length of power cord is 48" (121.9 cm).



SIDE VIEW

TOP VIEW – CUTOUT


BACK VIEW

IMPORTANT: Dimensional specifications are provided for planning purposes only. Do not make any alterations based on this information. Refer to the installation or User's Guide.




1-11

Product and Cabinet Opening Dimensions




For 4" (100 mm) toe kick, height of cabinet opening is 34 $\frac{1}{2}$ " (863 mm).



- A. Insulation may be compressed (not used on all models).
- B. For panel-ready models, dishwasher depth is 24" (610 mm), not including the 3/4" (19 mm) custom door panel.
- C. Door handles may protrude forward of the face of the dishwasher, varies by model.

Check that all surfaces have no protrusions that would prohibit dishwasher installation.



NOTE: Shaded areas of cabinet walls show where utility connections may be installed.

- D. Measured from the lowest point on the underside of the countertop. May be reduced to 33 1/2" (851 mm) by removing the wheels and perforated area of insulation (blanket) on dishwasher.
- E. Minimum, measured from narrowest point of opening

PV-#34
April 11/2021




72" COUNTER DEPTH FRENCH DOOR REFRIGERATOR WITH EXTERNAL JENNAIR DISPENSER


DETAILED PLANNING DIMENSIONS GUIDE

JFFCC72EH - 35 3/4" (W) x 71 1/2" (H) x 32 1/2" (depth with handles)

PRODUCT DIMENSIONS



FRONT VIEW



TOP VIEW

DIMENSION	DESCRIPTION	JFFCC72EH
A	Width of each door	17" / " (45 cm)
B	Space between doors	3/8" (9 mm)
C	Overall width	35 3/4" (90.5 cm)
D	Height of door handles (RISE™)	32 1/2" (82.9 cm)
E	Height to top of door handles (RISE™)	38 1/2" (98.2 cm)
F	Height of doors	46 1/2" (118.2 cm)
G	Space between doors and drawer	12" (12 cm)
H	Depth with doors open 90°	44" (111.7 cm)
I	Height of drawer	23" (58.4 cm)
J	Height of grille	1 1/2" (3.9 cm)
K	Width from side of refrigerator to handle - door fully open 135° (RISE™)	14" (35.5 cm)
L	Width from side of refrigerator to handle - door open 90° (RISE™)	4 1/2" (11 cm)

Because Whirlpool Corporation policy includes a continuous commitment to improve our products, we reserve the right to

Dimensions are for planning purposes only. For complete details, see installation instructions packed with product. Specifications

PV-34

April 1, 2021


[Signature]



72" COUNTER DEPTH REFRIGERATOR WITH EXTERNAL DISPENSER

DETAILED PLANNING DIMENSIONS GUIDE

JFFCC72EH - 35 3/4" (W) x 71 1/2" (H) x 32 1/2" (depth with handles)



SIDE VIEW

DIMENSION	DESCRIPTION	JFFCC72EH
A*	Height to top of drawer (m in.)	24 / " (63.3 cm)
B*	Height to top of drawer handle (m in.)	23 / " (60.4 cm)
C*	Height of recessed refrigerator (m in.)	70 / " (180.1 cm)
D*	Height to top of hinges (m in.)	71 / " (182.7 cm)
E	Depth with drawer fully open including drawer handle (m in.)	46 / " (118.8 cm)
F	Depth with handles (m in.)	32 / " (83.1 cm)
G	Depth with doors (m in.)	29 / " (74.4 cm)
H	Depth without doors (m in.)	24 / " (62.6 cm)
I	Depth to back of hinges (m in.)	16 / " (42.6 cm)

*Add 3/4" (19 cm) to the height dimension when leveling legs are fully extended.

Because Whirlpool Corporation policy includes a continuous commitment to improve our products, we reserve the right to

Dimensions are for planning purposes only. For complete details, see installation instructions packed with product. Specifications

PV-34
April 1, 2021


ty Jan

72" COUNTER DEPTH REFRIGERATOR WITH EXTERNAL JENNAIR DISPENSER


DETAILED PLANNING DIMENSIONS GUIDE

JFFCC72EH - 35 3/4" (W) x 71" (H) x 32 1/2" (depth with handles)

OPENING CLEARANCE DIMENSIONS



FRONT VIEW



BACK VIEW

DIMENSION	DESCRIPTION	JFFCC72EH
A	Width (min.)	36" / " (93.3 cm)
B	Minimum width from side of refrigerator to fixed wall - door open 90°	3" / " (9.5 cm)
	Minimum width from side of refrigerator to fixed wall - door open approx. 135°	12" (30.5 cm)
C	Width of recommended electrical/water installation area	35" / " (90.2 cm)
D	Height (min.)	72" / " (184 cm)
E	Height of recommended electrical installation area	Min. 24" (61 cm) Max. 36" (91.4 cm)
F	Height of recommended water installation area	12" (30.5 cm)
G	Depth of recommended water installation area	1" (2.5 cm)
H	Water line location - distance from side	2" / " (6.4 cm)
I	Water line location - distance from bottom	7" (17.8 cm)
E	Recommended electrical connection location	
	Recommended water connection location	

Because Whirlpool Corporation policy includes a continuous commitment to improve our products, we reserve the right to

Dimensions are for planning purposes only. For complete details, see installation instructions packed with product. Specifications

PV-34
April 1, 2021

[Signature]

ELECTRICAL REQUIREMENTS

⚠ WARNING 
Electrical Shock Hazard
Plug into a grounded 3 prong outlet.
Do not remove ground prong.
Do not use an adapter.
Do not use an extension cord.
Failure to follow these instructions can result in death, fire, or electrical shock.

115 V, 60 Hz, AC only, 15 A or 20 A fused, grounded circuit is required. A dedicated circuit is recommended. Use an outlet that cannot be turned off by a switch. Minimum length of power cord is 60" (152.0 cm). Do not use an extension cord.

WATER PRESSURE REQUIREMENTS

A cold water supply with water pressure between 30 psi and 120 psi (207 kPa and 827 kPa) is required to operate the ice maker. Call a licensed, qualified plumber with any questions about the water pressure.

Reverse Osmosis Water Supply

IMPORTANT: The pressure of the water coming out of a reverse osmosis system going to the water inlet valve of the refrigerator needs to be between 30 psi and 120 psi (207 kPa and 827 kPa).

If a reverse osmosis water filtration system is connected to the cold water supply, the water pressure to the reverse osmosis system needs to be a minimum of 40 psi to 60 psi (276 kPa to 414 kPa).

LOCATION REQUIREMENTS

⚠ WARNING 
Explosion Hazard
Keep flammable materials and vapors, such as gasoline, away from refrigerator.
Failure to do so can result in death, explosion, or fire.

To ensure proper ventilation for your refrigerator, allow for a minimum 3/16" (0.48 cm) of space on each side and 1/4" (0.64 cm) at the top. Allow for a minimum 1" (2.54 cm) space behind the refrigerator.


PV-#34

Microwave

April 1/2021 *by [signature]*

Interior Dimensions

15"W x 9"H x 15.4"D




PV - #34

April 1/2021

dy gem


microwave

Width	23 1/2"
Height	16 1/8"
Depth (Thickness)	3/4"



PV-34

April 1, 2021



Width	23 1/2"
Height	16 1/8"
Depth (Thickness)	3/4"

