



FLANKAGE ELEVATION

FRONT ELEVATION

(LOTS 72, 101)

## UNIT 5011-CORNER-UPG-TIMBERLAND

## SB-12 ENERGY EFFICIENCY DESIGN MATRIX

PRESCRIPTIVE COMPLIANCE

SB-12 (SECTION 3.1.1) TABLE 3.1.1.2.A

SPACE HEATING FUEL

GAS

GAS

ELECTRIC

PROPANE

EARTH

SOLID FUEL

| BUILDING COMPONENT  | REQUIRED    | PROPOSED    |
|---|-------------|-------------|
| INSULATION RSI (R) VALUE  |             |             |
| CEILING W/ ATTIC SPACE  | 10.56 (R60) | 10.56 (R60) |
| CEILING W/O ATTIC SPACE   | 5.46 (R31)  | 5.46 (R31)  |
| EXPOSED FLOOR   | 5.46 (R31)  | 5.46 (R31)  |
| WALLS ABOVE GRADE   | 3.87 (R22)  | 3.87 (R22)  |
| BASEMENT WALLS  | 3.52 ci     | 3.52 ci     |
| * PROPOSED VALUES MAY BE SUBSTITUTED W/ 2.11+1.76ci (R12+R10ci) | (R20 ci) *  | (R20 ci) *  |
| BELOW GRADE SLAB ENTIRE SURFACE > 600mm BELOW GRADE             | -           | -           |
| EDGE OF BELOW GRADE SLAB ≤ 600mm BELOW GRADE                    | 1.76 (R10)  | 1.76 (R10)  |
| HEATED SLAB OR SLAB ≤ 600mm BELOW GRADE                         | 1.76 (R10)  | 1.76 (R10)  |
| WINDOWS & DOORS   |             |             |
| WINDOWS/SLIDING GLASS DOORS (MAX U-VALUE)                       | 1.6         | 1.6         |
| SKYLIGHTS (MAX. U-VALUE)  | 2.8         | 2.8         |
| APPLIANCE EFFICIENCY  |             |             |
| SPACE HEATING EQUIP. (AFUE%)                                    | 96%         | 96%         |
| HRV EFFICIENCY (%)  | 75%         | 75%         |
| DHW HEATER (EF)   | 0.8         | 0.8         |

1 - TITLE PAGE

- 2 BASEMENT PLAN, EL. 'A'
- 3 GROUND FLOOR PLAN, EL. 'A' 4 - SECOND FLOOR PLAN, EL. 'A'
- 5 BASEMENT PLAN, EL. 'A'
- 6 UPGRADED LEFT SIDE ELEVATION 'A'
- 7 RIGHT SIDE ELEVATION 'A'
- 8 UPGRADED REAR ELEVATION 'A'
- 9 UPGRADED REAR ELEVATION 'A'
- 10 CONSTRUCTION NOTES

GOLDPARK WORTH MORE

AREA CALCULATIONS

GROUND FLOOR AREA

SECOND FLOOR AREA

DEDUCT ALL OPEN AREAS

TOTAL NET AREA

FINISHED BASEMENT AREA

SUBTOTAL

COVERAGE W/OUT PORCH

COVERAGE W/ PORCH

COVERAGE W/ OPT. LOGGIA

CALCULATIONS

GROSS WALL AREA

GROSS WINDOW AREA (INCL GLASS DOORS & SKYLIGHTS)

TOTAL WINDOW %

WINDOW / WALL AREA

**EL. 'A'** STD. PLAN 2114.67 sq. ft.

(196.46 sq. m.)

2700.50 sq. ft. (250.88 sq. m.)

4815 sq. ft. (447.34 sq. m.) 41.16 sq. ft.

(3.82 sq. m.) 4774 sq. ft.

(443.52 sq. m.)

186.10 sq. ft. (17.29 sq. m.) 2743.41 sq. ft.

(254.87 sq. m.)

2857.08 sq. ft. (265.43 sq. m.)

0 sq. ft. (0.00 sq. m.)

EL. 'A'

STD. PLAN 5265.23 sq. ft.

(489.16 sq. m.) 655.72 sq. ft.

12.45 %



| 7. | -   | -                 | -  |
|----|---|-------------------|----|
| 6. | ISSUED FOR PERMIT                                   | -                 | -  |
| 5. | REVISED PER STURCT. ENG. COMMENTS                   | 2022.08.18        | WT |
| 4. | CO-ORD. W/ FLOOR & TRUSS LAYOUTS                    | 2022.07.27        | WT |
| 3. | REVISED JOIST DIRECTION OVER LIBRARY, FOYER, DINING | 2022.06.16        | AW |
| 2. | REVISED PER CLIENT DESIGN CHANGES                   | 2022.06.09        | WT |
| 1. | ISSUED FOR CLIENT REVIEW                            | 2022.05.16        | AW |
|    | REVISIONS   | DATE (YYYY/MM/DD) | BY |

THE UNDERSIGNED HAS REVIEWED AND TAKES RESPONSIBILITY FOR THIS DESIGN AND HAS THE GOULE/CATIONS AND MEETS THE REQUIREMENTS SET OUT IN THE ONTARIO BUILDING CODE TO BE A DESIGNER.

QUALIFICATION INFORMATION

Allan Whiting

23177

BCIN

DESIGN ASSOCIATES INC.

BOSO

WWW.-burntdesign.ca

B966 Woodbline Ave, Markham, ON L3R 0J7

T 905.737.73266

TITLE PAGE

GOLDPARK HOMES - 221081 UNIT 5011-COR-UPG-TIMBERLAND

PINE VALLEY, PH.2 VAUGHAN ONT.


REV.2022.08.18


AWW 3/16"=1"-0" 221081WS5011-COR-UPG-TIMBERLAND.dwg 1 of 10


WWW.-burntdesign.ca

B966 Woodbline Ave, Markham, ON L3R 0J7

T 905.737.5133 F 905.737.73266
















It is the builder's complete responsibility to ensure that all plans submitted for approval fully comply with the Architectural Guidelines and all applicable regulations and requirements including zoning provisions and any provisions in the subdivision agreement. The Control Architect is not responsible in any way for examining or approving site (lotting) plans or working drawings with respect to any zoning or building code or permit matter or that any house can be properly built or located on its lot.

This is to certify that these plans comply with the applicable Architectural Design Guidelines approved by the City of VAUGHAN.

JOHN G. WILLIAMS LTD., ARCHITECT
ARCHITECTURAL CONTROL REVIEW
AND APPROVAL

APPROVED BY:

DATE: AUG 24, 2022

This stamp certifies compliance with the applicable Design Guidelines only and bears no further professional responsibility.

THE UNDERSIGNED HAS REVIEWED AND TAKES RESPONSIBILITY FOR THIS DESIGN AND HAS THE COURT FINE DESIGN AND HAS THE COURT FINE OF THE RECOURS HERE FOR THIS DESIGN AND HAS THE RECOURS HERE FOR THE RECOUR



PROVIDE ICE AND WATER SHIELD IN THE AREAS INDICATED. THE ICE AND WATER SHIELD SHALL BE A SELF ADHERING AND SELF SEALING MEMBRANE. SIDE LAPS MUST BE A MINIMUM 3 1/2" (90) AND END LAPS A MINIMUM 6" (152). AND TO EXTEND UP DORMER WALLS A MINIMUM 12" (305).

1B PROFILED ROOF TRUSSES

ROOF TRUSSES SHALL BE PROFILED AND/OR STEPPED AT RAISED COFFER/TRAY CEILINGS. ANGLED TRAY CEILINGS WILL BE SHEATHED W/ 3/8" (9.5) PLYWOOD. SIDING WALL CONSTRUCTION (2'x6')

SIDING MATERIAL AS PER ELEVATION ATTACHED TO FRAMING MEMBERS, FURRING MEMBERS OR BLOCKING BETWEEN THE FRAMING MEMBERS ON APPROVED SHEATHING PAPER ON 3/8" (9.5) EXT. GRADE SHEATHING ON STUDS CONFORMING TO 0.6.C (9.23.10.1.) & SECTION 1.1., INSULATION, APPROVED 6 MIL POLYETYLENE AIR/VAPOUR BARRIER, ON 1/2" (12.7) GYPSUM WALLBOARD INT. FIN. (GYPSUM SHEATHING, RIGID INSULATION, AND FIBERBOARD SHALL NOT BE USED FOR THE ATTACLIMENT OF SIDING 10.25 A 1.2 DEFENDENT OF SERVING SERVING. FOR THE ATTACHMENT OF SIDING (9.23.16.3.(1.)) (REFER TO 35 NOTE AS REQ.)

 $\langle {
m 2A} \rangle$  SIDING WALL CONSTRUCTION (2\*x6\*) W/ CONTIN. INSULATION SIDING MATERIAL AS PER ELEVATION ATTACHED TO FURRING MEMBERS ON APPROVED AIR/WATER BARRIER AS PER O.B.C. 9.27.3. ON EXTERIOR TYPE RIGID INSULATION (JOINTS UNTAPED) MECHANICALLY FASTENED AS PER MANUFACTURER'S SPECIFICATIONS ON 3/8" (9.5) EXT. GRADE SHEATHING ON STUDS CONFORMING TO O.B.C (9.23.10.1.) & SECTION 1.1., INSULATION, APPROVED 6 MIL POLYETHYLENE AIR/VAPOUR BARRIER, ON 1/2" (12.7) GYPSUM WALLBOARD INT. FIN. (GYPSUM SHEATHING, RIGID INSULATION, AND FIBERBOARD SHALL NOT BE USED FOR THE ATTACHMENT OF SIDING (9.23.16.3.(1,)) (REFER TO 35 NOTE AS REQ.)

2B SIDING WALL @ GARAGE CONSTRUCTION SIDING MATERIAL AS PER ELEVATION ATTACHED TO FRAMING MEMBERS, FURRING MEMBERS OR BLOCKING BETWEEN THE FRAMING MEMBERS ON APPROVED SHEATHING PAPER ON 3/8" (9.5) EXTERIOR TYPE SHEATHING ON STUDS CONFORMING TO O.B.C (9.23.10.1.) & SECTION 1.1.,1/2" (12.7) GYPSUM WALLBOARD INTERIOR FINISH. (GYPSUM SHEATHING, RIGID INSULATION AND (9.23.16.3.(1,)) (REFER TO 35 NOTE AS REQ.)

BRICK VENEER WALL CONSTRUCTION (2"x6") 3 1/2" (90) BRICK VENEER 1" (25) AIR SPACE, 7/8"x7"x0.03" (22x180x0.76) GALV. METAL @ 16" (400) O.C. HORIZ. 24" (600) O.C. VERT. BONDING AND FASTENING FOR TIES TO CONFORM WITH 9.20.9. ON APPROVED SHEATHING PAPER, 3/8" (9.5) EXTERIOR TYP SHEATHING, STUDS CONFORMING TO O.B.C (9.23.10.1.) & SECTION 1.1., INSULATION AND 6 mil POLYETHYLENE VAPOUR BARRIER WITH APPROVED CONTIN. AIR BARRIER. (12.7) GYPSUM WALLBOARD INTERIOR FINISH. PROVIDE WEEP HOLES @ 32° (800) O.C BOTTOM COURSE AND OVER OPENINGS. PROVIDE BASE FLASHING UP MIN. 6" (150) BEHIND BUILDING PAPER (9.20.13.6.) (REFER TO 35 NOTE AS REQUIRED)

3A BRICK VENEER WALL CONSTRUCTION (2"x6") W/ CONTIN. INSULATION 2" (90) BRICK VENEER 1" (25) AIR SPACE, 7/8"x7"x0.03" (22x180x0.76) GALV. META S @ 16" (400) O.C. HORIZ. 24" (600) O.C. VERT. BONDING AND FASTENING FOR S TO CONFORM WITH 9.20.9. ON APPROVED AIR/WATER BARRIER AS PER O.B.C .27.3. ON EXTERIOR TYPE RIGID INSULATION (JOINTS UNTAPED) MECHANICALL 9.27.3. ON EATERIOR THE RIGID INSCALATION (DOINS OWNED) METER DISCRETE THE SECTION S. ON 3/8" (9.5) EXTERIOR TYPE SHEATHING, STUDS CONFORMING TO O.B.C (9.23.10.1.) & SECTION 1.1., INSULATION AND 6 mil POLYETHYLENE VAPOUR BARRIER WITH APPROVED CONTIN. AIR BARRIER. 1/2" (12.7) GYPSUM WALLBOARD INTERIOR FINISH. PROVIDE WEEP HOLES @ 32" (800) O.C. BOTTOM COURSE AND OVER OPENINGS. PROVIDE BASE FLASHING UP MIN. 6" 150) OVER RIGID INSULATION (9.20.13.6.) (REFER TO 35 NOTE AS REQUIRED)

3B BRICK VENEER WALL @ GARAGE CONSTRUCTION 3 1/2" (90) BRICK VENEER, MIN. 1" (25) AIR SPACE, 7/8"x7"x0.03" (22x180x0.76) GALV. METAL TIES @ 16" (400) O.C. HORIZ. 24" (600) O.C. VERT. BONDING AND FASTENING FOR TIES TO CONFORM WITH 9.20.9. ON APPROVED SHEATHING PAPER, 3/8" (9.5) EXTERIOR TYPE SHEATHING ON STUDS CONFORMING TO O.B.C (9.23.1) SECTION 1.1., 1/2" (12.7) GYPSUM WALLBOARD INTERIOR FINISH, PROVIDE WEEP HOLES @ 32" (800) O.C. AT BOTTOM COURSE AND OVER OPENINGS, PROVIDE BASE FLASHING UP 6" (150) MIN. BEHIND BUILDING PAPER (9.20.13.6.) (REFER TO

INTERIOR STUD PARTITIONS (9.23.9.8., 9.23.10) BEARING PARTITIONS SHALL BE A MINIMUM 2"x4" (38x89) @ 16" (406) O.C. FOR 2 STOREY AND 12" (305) O.C. FOR 3 STOREY, NON-BEARING PARTITIONS 2"x4" (38x89) @ 24" (610) O.C. PROVIDE 2"x4" (38x89) BOTTOM PLATE AND 2-2"x4" (2-38x89) TOP PLATE. 1/2" (12.7) INT. DRYWALL BOTH SIDES OF STUDS, PROVIDE 2'x6" (38x140) STUDS WHERE NOTED. PROVIDE 2"x4" (38x89) @ 24" (610) O.C. LADDER FRAMING WHERE WALLS INTERSECT PERPENDICULAR TO ONE ANOTHER. PROVIDE 2 X<sup>4</sup> (38x89) WOOD BLOCKING ON FLAT @ 3-11" (1194) O.C. MAX. BETWEEN FLOOR JOISTS WHEN NON-LOADBEARING WALLS ARE PARALLEL TO FLOOR JOISTS.

(4A) EXT. LOFT WALL CONSTRUCTION (2"x6") - NO CLADDING 3/8" (9.5) EXTERIOR TYPE SHEATHING, STUDS CONFORMING TO O.B.C (9.23.10.1.) & SECTION 1.1., INSULATION AND 6 mil POLYETHYLENE VAPOUR BARRIER WITH APPROVED CONT. AIR BARRIER. 1/2" (12.7) GYPSUM WALLBOARD INT. FINISH. (9.23.)

4B EXT. LOFT WALL CONSTRUCTION (2"x6")
NO CLADDING W/ CONTINUOUS INSULATION
APPROVED AIRWATER BARRIER AS PER O.B.C. 9.27.3. ON EXTERIOR TYPE RIGID
INSULATION (JOINTS UNTAPED) MECHANICALLY FASTENED AS PER
INSULATION (JOINTS UNTAPED) ACCOUNT OF THE PROPERTY OF THE PROPERT MANUFACTURER'S SPECIFICATIONS, ON 3/8" (9.5) EXTERIOR TYPE SHEATHING, STUDS CONFORMING TO O.B.C (9.23.10.1.) & SECTION 1.1., INSULATION AND 6 mil POLYETHYLENE VAPOUR BARRIER WITH APPROVED CONT. AIR BARRIER. 1/2" 12.7) GYPSUM WALLBOARD INT. FINISH. (9.23.)

FOUNDATION WALL/FOOTINGS

POURED CONC. FOUNDATION WALL AS PER CHART BELOW ON CONTINUOUS KEYED CONC. FOONDATION WALL AS PER CHART BELOW ON CONTINUOUS KEYED CONCRETE FOOTING, FOUNDATION WALLS SHALL EXTEND NOT LESS THAN 6" (150) ABOVE FINISHED GRADE. THE OUTSIDE OF THE FOUNDATION SHALL BE DAMPROOFED FROM THE TOP OF THE FOOTING TO FINISHED GRADE AND BRUSH COAT FROM THE TOP TO 2" BELOW GRADE. PROWDE A DRAINAGE LAYER ON THE OUTSIDE OF THE FOUNDATION WALL. SEAL THE DRAINAGE LAYER I THE TOP, THE TOP OF THE CONC. FOOTING SHALL BE DAMPRODED CONCRETE FOOTINGS SUPPORTING JOIST SPANS GREATER THAN 16'-1" (4900' SHALL BE SIZED IN ACCORDANCE WITH 9.15.3.4 (1),(2) OF THE O.B.C. (REFER TO CHART BELOW FOR RESPECTIVE SIZE). BRACE FOUNDATION WALL PRIOR TO BACKFILLING. ALL FOOTINGS SHALL REST ON NATURAL UNDISTURBED SOIL OF 125KPa S.L.S. OR COMPACTED ENGINEERED FILL WITH MIN. BEARING CAPACITY OF 125KPA S.L.S. IF SOIL BEARING DOES NOT MEET MINIMUM CAPACITY, ENGINEERED FOOTINGS ARE REQUIRED. ACTUAL SOIL BEARING CAPACITY TO BE VERIFIED WITH SOIL ENGINEERING REPORT. REFER TO CONSTRUCTION DRAWINGS AND DETAILS FOR FOUNDATION

WALL STRENGTH AND THICKNESS AND 9.15.4. FOUNDATION WALLS SHALL NOT EXCEED 9-10" (3.0m) IN UNSUPPORTED HEIGHT UNLESS OTHERWISE NOTED. [9.15.4.2.(1.)]

|  |          | UNRE        | INFORCED SOLI  | D CONCRETE FO    | DUNDAT <mark>I</mark> ON WAL | LS (9.15.4.2.) |  |
|--|----------|-------------|----------------|------------------|------------------------------|----------------|--|
|  | STRENGTH | SS          | MAX            | . HEIGHT FROM    | FIN. SLAB TO GR              | ADE            |  |
|  |          | THICKNESS   | UNSUPPORTED    | SUPPORTED AT TOP |                              |                |  |
|  | STF      | 崖           | AT TOP         | ≤2.5m            | >2.5m & ≤2.75m               | >2.75m & ≤3.0m |  |
|  | 15 MPa   | <b>*</b> 8" | 3'-11" (1.20m) | 7'-0" (2.15m)    | 7'-0" (2.15m)                | 6'-10" (2.10m) |  |
|  |          | 10"         | 4'-7" (1.40m)  | 7'-6" (2.30m)    | 8'-6" (2.60m)                | 8'-2" (2.50m)  |  |
|  |          | 12"         | 4'-11" (1.50m) | 7'-6" (2.30m)    | 8'-6" (2.60m)                | 9'-3" (2.85m)  |  |
|  | 20 MPa   | <b>*</b> 8" | 3'-11" (1.20m) | 7'-6" (2.30m)    | 7'-6" (2.30m)                | 7'-2" (2.20m)  |  |
|  |          | 10"         | 4'-7" (1.40m)  | 7'-6" (2.30m)    | 8'-6" (2.60m)                | 9'-3" (2.85m)  |  |
|  |          | 12"         | 4'-11" (1.50m) | 7'-6" (2.30m)    | 8'-6" (2.60m)                | 9'-3" (2.85m)  |  |
| * 9" MIN. THICK FOUNDATION WALL IS REQUIRED FOR MASONRY VENEER |          |             |                |                  |                              | NRY VENEER     |  |
|  | TIME     | CHED        | EVTEDIOD WALL  | LIMITIMOO LITIMA | IOLIC INICI II ATIO          | N CONDITION TO |  |

PROVIDE MIN. BEARING FOR SILL PLATES, BEAMS AND FLOOR JOIST AS PER

| 9.23.7.2., 9.23.8.1., & 9.23.9.1. OF THE O.B.C. |                                     |   |                         |  |  |
|---|-------------------------------------|---|-------------------------|--|--|
|   | MINIMUM STRIP FO<br>UNLESS NOTED OT | OTING SIZES (9.15.3<br>HERWISE ON PLANS | .)                      |  |  |
| NUMBER FLOORS<br>SUPPORTED                      |                                     |   | SUPPORTING<br>PARTYWALL |  |  |
| 1   | 16' WIDE x 6" THICK                 | 16" WIDE x 6" THICK                     | 16" WIDE x 6" THICK     |  |  |
| 2   | 24' WIDE x 8" THICK                 | 20" WIDE x 6" THICK                     | 24" WIDE x 8" THICK     |  |  |
| 3   | 36" WIDE x 14" THICK                | 26" WIDE x 9" THICK                     | 36" WIDE x 14" THICK    |  |  |

REFER TO SB-12 ENERGY EFFICIENCY DESIGN MATRIX ON THE TITLE PAGE FOR ALL VALUES AS REQUIRED PER 3.1.1., 3.1.2., 3.1.3. OF THE OBC.

FOUNDATION REDUCTION IN THICKNESS FOR MASONRY THE FOUNDATION WALL IS REDUCED IN THICKNESS. SECTION SHALL BE NOT LESS THAN 3 1/2" (90) THICK. THE BRICK VENEER SHALL BE TIED TO THE FOUNDATION WALL WITH CORROSION RESISTANT METAL TIES (9 7 7/8" (200) VERTICAL AND 2-11" (889) HORIZONTAL. FILL VOID WITH MORTAR BETWEEN WALL AND BRICK VENEER (9.15.4.7(2)(3) & 9.20.9.4(3))

FOUNDATION REDUCTION IN THICKNESS FOR JOISTS WHERE THE TOP OF THE FOUNDATION WALL IS REDUCED IN THICKNESS TO PERMIT THE INSTALLATION OF FLOOR JOISTS. THE REDUCED SECTION SHALL F NOT MORE THAN 13 3/4" (350) HIGH & NOT LESS THAN 3 1/2" (90) THICK (9.15.4.7(1)) WEEPING TILE (9.14.3.)

" (100) Ø WEEPING TILE W/ FILTER CLOTH WRAP & 6" (152) CRUSHED STONE COVER **BASEMENT SLAB OR SLAB ON GRADE** (9.16.4.) (9.13.)

3" (80) MIN. 25MPa (3600psi) CONC. SLAB ON 4" (100) COARSE GRANULAR FILL, OR 20MPa (2900psi) CONC. WITH DAMPPROOFING BELOW SLAB. PROVIDE 1/2" (12.7) IMPERVIOUS BOARD FOR BOND BREAK AT EDGE. WHERE A BASEMENT SLAB IS WITHIN 24" (610) OF THE EXTERIOR GRADE PROVIDE RIGID INSUL. AROUND THE PERIMETER EXTENDING MIN. 24" (610) BELOW GRADE. FOR SLAB ON GRADE CONDITIONS RIGID INSULATION SHALL BE APPLIED TO THE UNDERSIDE OF THE ENTIRE SLAB. ([SB-12] 3.1.1.7.(5) & (6))

**EXPOSED FLOOR TO EXTERIOR** (9.10.17.10, & CAN/ULC-S705.2) PROVIDE SPRAY FOAM INSULATION BETWEEN CANT. JOIST AND INSTALL OSB CONFIRMING TO 9.29.9. FIN. SOFFIT OR CLADDING AS PER ELEVATION TO U/S OF EXPOSED CANT. JOIST.

EXPOSED CEILING TO EXTERIOR w/ ATTIC (9.25.2.4) INSULATION, 6 mil POLYETHYLENE VAPOUR BARRIER, 1/2" (12.7) GYPSUM BOARD INTERIOR FINISH OR APPROVED FO.

EXPOSED CEILING TO EXTERIOR W/o ATTIC JOISTS/TRUSSES AS PER PLANS W/ 2"x2" (38x38) PURLINS @ 16" (406) O.C. PERPENDICULAR TO JOISTS (PURLINS NOT REQ. W/ SPRAY FOAM OR ROOF TRUSSES), W/INSULATION BETWEEN JOIST, 6 mil POLYETHYLENE VAPOUR BARRIER, 1/2" (12.7) GYPSUM BOARD INT. FINISH OR APPROVED EQ. (CAN/ULC-S705.2, 9.19.1, 9.10.17.10)

**ALL STAIRS/EXTERIOR STAIRS** (9.8.1.2., 9.8.2., 9.8.4.)

PUBLIC 2"-11" (900) MIN. RUN 5 7/8" (150) MIN. AVG. RUN 11" (280)

RAGE RUN OF TAPERED TREAD MEASURED AT A POINT 300mm FROM THE CENTERLINE OF INSIDE HANDRAIL, (9.8.4.3.) \* HEIGHT OVER STAIRS (HEADROOM) IS MEASURED VERTICALLY ACROSS WIDTH OF

REQUIRED LANDING IN GARAGE - O.B.C. 9.8.6.2.(3.)
FOR AN EXTERIOR STAIR SERVING A GARAGE W/ MORE THAN 3 RISERS. GUARDS, HANDRAILS & STEPS AS PER CONSTRUCTION HEX NOTE 10 & 11.

**GUARDS/RAILINGS** (9.8.7., 9.8.8.) GUARDS TO BE DESIGNED NOT TO FACILITATE CLIMBING AND PROVIDING MAX. OPENING CONFORMING TO O.B.C. 9.8.8.5. & 9.8.8.6. AND BE ABLE TO RESIST LOADS AS PER TABLE 9.8.8.2.

GUARD HEIGHTS - O.B.C. 9.8.8. INTERIOR GUARDS: 2-11" (900) MIN.

EXTERIOR GUARDS: 2-11" (900) MIN. (LESS THAN 5-11" (1800) TO GRADE)

3-6" (1070) MIN. (MORE THAN 5-11" (1800) TO GRADE)

GUARDS FOR EXIT STAIRS: 3-6" (1070) MIN.

GUARDS FOR LANDINGS @ EXIT STAIRS: 3'-6" (1070) MIN.
GUARDS FOR FLOORS & RAMPS IN GARAGES (SERVICE STAIRS)
FLOOR OR RAMP W/O EXTERIOR WALLS THAT IS 23 5/8" (600) OR MORE ABOVE ADJACENT SURFACE REQUIRES CONT. CURB MIN. 6" (150) HIGH, AND GUARD MIN. 3'-6" (1070) HIGH. TWEEN WALKING SURFACE & ADJACENT SURFACE WITH A DIFFERENCE IN

ELEVATION MORE THAN 23 5/8" (600) OR ADJACENT SURFACE WITHIN 3-11" (1200) & WALKING SURFACE W/ A SLOPE MORE THAN 1 IN 12 SHALL BE PROTECTED WITH GUARDS PER CONSTRUCTION HEX NOTE 11 HANDRAIL HEIGHTS - O.B.C. 9.8.7. - REQUIRED AS PER 9.8.7.1.(3)
MIN. HEIGHT AT STAIRS, RAMP AND LANDINGS: 2'-10" (865)

SILL PLATES

2"x4" (38x89) SILL PLATE WITH 1/2" (12.7)Ø ANCHOR BOLTS 8" (200) LONG, EMBEDDED MIN. 4" (100) INTO CONC. @ 4'-0" (1220) O.C., CAULKING OR GASKET BETWEEN PLATE AND TOP OF FOUNDATION WALL. USE NON-SHRINK GROUT TO LEVEL SILL PLATE WHEN REQUIRED (9.23.7.)

**BASEMENT INSULATION** ([SB-12] 3.1.1.7.) PROVIDE CONTINUOUS BLANKET INSULATION W/ BUILT IN 6 mil POLYETHYLENE VAPOUR BARRIER. INSULATION TO EXTEND NO MORE THAN 8" (200) ABOVE FINISHED BASEMENT FLOOR. DAMPROOFED WITH BUILDING PAPER BETWEEN THE FOUNDATION WALL AND INSULATION UP TO GRADE LEVEL.

BEARING STUD PARTITION IN BASEMENT (9.15.3.6., 9.23.10.1.) 2"x4" (38x89) STUDS @ 16" (406) O.C., 2"x4" (38x89) SILL PLATE (2"x6" (38x140) AS REQUIRED) ON DAMPPROOFING MATERIAL OR 2 mil POLYETHYLENE FILM, 1/2" (12.7) Ø ANCHOR BOLTS 8" (200) LONG, EMBEDDED 4" (100) MIN. INTO CONC. @ 7-10" (2390) O.C. 4" (100) HIGH CONC. CURB ON CONC. FOOTING, FOR SIZE REFER TO HEX NOTE 5. ADD HORIZ. BLOCKING AT MID-HEIGHT IF WALL IS UNFINISHED.

**ADJUSTABLE STEEL BASEMENT COLUMN** (9.15.3.4.) 9'-10" (3000) MAX. SPAN BETWEEN COLUMNS. 3 1/2" (90)Ø SINGLE TUBE ADJUSTABLE STEEL COLUMN CONFORMING TO CAN/CGSB-7.2M, AND WITH COLUMN CONNECTION. POURED CONCRETE FOOTING ON NATURAL UNDISTURBED SOIL OF 125KPa S.L.S. OR COMPACTED ENGINEERED FILL WITH MIN. BEARING CAPACITY OF 125KPA S.L.S. AS PER SOILS REPORT. SUPPORTING 2 STOREY FLR. LOAD PROVIDE 34"x34"x16" (870x870x410) CONC. FOOTING

SUPPORTING 3 STOREY FLR. LOAD PROVIDE 40"x40"x19" (1060x1060x480) CONC. FOOTING

15A) NON-ADJUSTABLE STEEL BASEMENT COLUMN STEEL PLATE TOP & BOTTOM. BOTTOM PLATE C.W 2 1/2"/Ø X 12" LONGX2" HOOK ANCHORS. FIELD WELD BASEMENT COLUMN CONNECTION. POURED CONCRETE FOOTING ON NATURAL UNDISTURBED SOIL OF 125KPA S.L.S. OR COMPACTED ENGINEERED FILL WITH MIN. BEARING CAPACITY OF 125KPA S.L.S. AS PER SOILS REPORT. SUPPORTING 2 STOREY FUR LOAD PROVIDE 42"x42"x18" (1070x1070x460) CONC. FOOTING SUPPORTING 3 STOREY FLR. LOAD PROVIDE 48"x48"x24" (1220x1220x610) CONC. FOOTING

NON-ADJUSTABLE STL. COLUMN AT FOUNDATION WALL 3 1/2" (90)Ø x 0.188" (4.78) NON-ADJUSTABLE STEEL COLUMN WITH 6"x6"x3/8" (152x152x9.5) STEEL TOP PLATE & 6"x4"x3/8" (152x100x9.5) BOTTOM PLATE. BASE PLATE 4-1/2'x10'x1/2' (120x250x12.7) WTH 2- 1/2''Ø x 12''LONG x 2'' HOOK ANCHORS (2- 12.7Øx305x50). FIELD WELD COLUMN TO BASE PLATE & STEEL BM.

STEEL BEAM BEARING AT FOUNDATION WALL (9.23.8.1.) BEAM POCKET OR 8"x8" (200x200) POURED CONC. NIB WALLS, MIN. BEARING 3 1/2" (90). CONC. NIB WALLS TO HAVE EXTENDED FOOTINGS

**WOOD STRAPPING AT STEEL BEAMS** (9.23.4.3.(3.), 9.23.9.3.) 1"x3" (19x64) CONTIN. WOOD STRAPPING BOTH SIDES OF STEEL BEAM.

(9.16., 9.35.)

(18) GARAGE SLAB (9.16., 9.35.) 4" (100) 32MPa (4640psi) CONC. SLAB WITH 5-8% AIR ENTRAINMENT ON OPT. 4" (100) COARSE GRANULAR FILL WITH COMPACTED SUB-BASE OR COMPACTED NATIVE FILL. SLOPE TO FRONT @ 1% MIN.

GARAGE TO HOUSE WALLS/CEILING (9.10.9.16.) 1/2" (12.7) GYPSUM BOARD ON WALL AND CEILING BETWEEN HOUSE AND GARAGE, PLUS REQUIRED INSULATION IN WALLS AND SPRAY FOAM FOR CEILINGS. TAPE AND SEAL ALL JOINTS GAS TIGHT. (9.10.17.10, CAN/ULC-S705.2

GARAGE TO HOUSE WALLS/CEILING W/ CONTIN. INSULATION 1/2" (12.7) GYPSUM BOARD ON CEILING AND ON WALLS INSTALLED OVER EXTERIOR TYPE RIGID INSULATION (JOINTS UNTAPED) MECHANICALLY FASTENED AS PER MANUFACTURER'S SPECIFICATIONS ON 3/8" EXTERIOR GRADE SHEATHING ON STUDS BETWEEN HOUSE AND GARAGE, PLUS REQUIRED INSULATION IN WALLS & SPRAY FOAM FOR CEILINGS. TAPE AND SEAL ALL JOINTS GAS TIGHT. (9.10.9.16., 9.10.17.10, CAN/ULC-S705.2)

**GARAGE DOOR TO HOUSE** (9.10.9.16., 9.10.13.10., 9.10.13.15.) AS-PROOF DOOR AND FRAME. DOOR EQUIPPED WITH SELF CLOSING DEVICE AND WEATHER STRIPPING.

EXTERIOR AND GARAGE STEPS

PRECAST CONC. STEP OR WOOD STEP WHERE NOT EXPOSED TO WEATHER. MAX RISE 7 7/8" (200), MIN. TREAD 9 1/4" (235). FOR THE REQUIRED NUMBER OF STEPS REFER TO SITING AND GRADING DRAWINGS. EXTERIOR CONCRETE FOUNDATION AS REQUIRED BY ARTICLE 9.8.9.2. OR SHALL BE CANTILEVERED AS PER SUBSECTION 9.8.10.

DRYER EXHAUST

CAPPED DRYER EXHAUST VENTED TO EXT. CONFORMING TO PART 6, OBC 9.32. **ATTIC ACCESS** (9.19.2.1.)

ATTIC ACCESS HATCH WITH MIN. AREA OF 0.32m2 AND NO DIM. LESS THAN 21 1/2" (545) WITH WEATHER STRIPPING, HATCHWAYS TO THE ATTIC OR ROOF SPACE WILL BE FITTED WITH DOORS OR COVERS AND WILL BE INSULATED WITH MIN. R20 (RSI 3.52) ([SB-12] 3.1.1.8.(1))

FIREPLACE CHIMNEYS (9.21.)

TOP OF FIREPLACE CHIMNEY SHALL BE 2'-11" (889) ABOVE THE HIGHEST POINT AT WHICH IT COMES IN CONTACT WITH THE ROOF AND 2'-0" (610) ABOVE THE ROOF SURFACE WITHIN A HORIZ. DISTANCE OF 10'-0" (3048) FROM THE CHIMNEY

LINEN CLOSET PROVIDE 4 SHELVES MIN. 14" (356) DEEP.

MECHANICAL VENTILATION (9.32.1.3.) MECHANICAL EXHAUST FAN, VENTED TO EXTERIOR, TO PROVIDE AT LEAST ONE AIR CHANGE PER HOUR. SEE GENERAL NOTE 2.3.

PARTY WALL BEARING (9.23.8)

12"x12"x5/8" (305x305x15.9) STEEL PLATE FOR STEEL BEAMS AND 12"x12"x1/2" (305x305x12.7) STEEL PLATE FOR WOOD BEAMS BEARING (MIN. 3-1/2" (89)) ON CONC. BLOCK PARTY WALL, ANCHORED WITH 2-3/4" (2-19) x 8" (200) LONG GALV. ANCHORS WITHIN SOLID BLOCK COURSE. LEVEL W/ NON-SHRINK GROUT. REFER TO NOTE SOLID BEARING (SECTION 3.0) FOR WD. STUD PARTY WALL.

WOOD FRAMING IN CONTACT TO CONCRETE WOOD BEARING WALLS, THE UNDERSIDE OF BUILT-UP WOOD POSTS AND SILLS SHALL BE WRAPPED WITH 2 mil POLY. STRIP FOOTINGS SUPPORTING

THE FOUNDATION WALL SHALL BE WIDENED  $6^{\rm w}$  (152) BELOW THE BEARING WALL AND/OR WOOD POST. (9.17.4.3.) 29) BUILT-UP WOOD POST AND FOOTING (9.17.4.1., 9.15.3.7.) 3-2"x6" (3-38x140) BUILT-UP WOOD POST (UNLESS OTHERWSE NOTED) ON METAL BASE SHOE ANCHORED TO CONC. WITH 1/2" (12.7) Ø BOLT, 24"x24"x12 (610x610x305) CONC. FOOTING OR AS PROVIDED ON PLAN. REFER TO NOTE 28

**STEP FOOTINGS** (9.15.3.9.) MIN. HORIZ. STEP = 23 5/8" (600). MAX. VERT. STEP = 23 5/8" (600).

CONC. PORCH SLAB (9.16.4.) MIN. 4" (100) CONCRETE SLAB ON GRADE ON 4" (100) COARSE GRANULAR FILL, REINFORCED WITH 6x6xW2.9xW2.9 MESH PLACED NEAR MID-DEPTH O SLAB. CONC. STRENGTH 32MPa (4640psi) WITH 5-8% AIR ENTRAINMENT ON COMPACTED SUB-GRADE.

**FURNACE VENTING** (9.32.) DIRECT VENT FURNACE TERMINAL MIN. 3'-0" (915) FROM A GAS REGULATOR. MIN. 12" (305) ABOVE FIN. GRADE, FROM ALL OPENINGS, EXHAUST AND INTAKE VENTS. HRV INTAKE TO BE A MIN. OF 6'-0" (1830) FROM ALL EXHAUST TERMINALS. REFER TO GAS UTILIZATION CODE.

FIREPLACE VENTING (9.32.3.) DIRECT VENT GAS FIREPLACE VENT TO BE A MIN. 12" (305) FROM AN OPENING AND ABOVE FIN. GRADE. REFER TO GAS UTILIZÁTION CODE.

**FLOOR FRAMING** (9.23.3.5., 9.23.9.4., 9.23.14.) T&G SUBFLOOR ON WOOD FLOOR JOISTS. FOR CERAMIC TILE APPLICATION SEE O.B.C. 9.30.6. ALL JOISTS WHERE REQUIRED TO BE BRIDGED WITH 2"X2" (38x38) CROSS BRACING OR SOLID BLOCKING @ 6'-11" (2108) O.C. MAX. ALL JOISTS TO BE STRAPPED WITH 1"X2" (19x64) @ 6'-11" (2108) O.C. UNLESS A PANEL TYPE CEILING FINISH IS APPLIED.

HEADER CONSTRUCTION

PROVIDE CONTINUOUS APPROVED AIR/VAPOUR BARRIER (HEADER WRAP) UNDER THE SILL PLATE, AROUND THE RIM BOARD AND UNDER THE BOTTOM PLATE. THE HEADER WRAP SHALL EXTEND 6" (152) BELOW THE TOM POF FOUNDATION WALL AND WILL BE SEALED TO THE CONCRETE FOUNDATION WALL AND WILL BE SEALED TO THE CONCRETE FOUNDATION WALL. EXTEND HEADER WRAP 6" (152) UP THE INTERIOR SIDE OF THE STUD WALL AND OVERLAP WITH THE VAPOUR BARRIER AND SEAL THE STUD WALL AND OVERLAP WITH THE VAPOUR BARRIER AND SEAL THE JOINT. ALL EDGES/JOINTS MUST BE MECHANICALLY CLAMPED.

EXPOSED BUILDING FACE w/ LIMITING DISTANCE <= 3'-11" (1.20m) WALL ASSEMBLY CONTAINS INSULATION CONFORMING TO CANVULC-S702 & HAVING A MASS OF NOT LESS THAN 1.22 KG/M2 OF WALL SURFACE AND 1/2" (12.7) TYPE X GYPSUM WALLBOARD INTERIOR FINISH. EXTERIOR CLADDING MUST BE NON-COMBUSTIBLE WHEN LIMITING DISTANCE IS 23 5/8" (0.60m) OR LESS. WALL ASSEMBLY REQUIRES TO HAVE A FIRE RESISTANCE RATING OF NOT LESS THAN 45 MINUTES & CONFORMING TO 0.B.C. (9.10.14. OR 9.10.15.). REFER TO DETAILS FOR TYPE & SPECS. \*\* AN OPENING IN AN EXPOSING BUILDING FACE NOT MORE THAN 20 in² (130cm²) SHALL NOT BE CONSIDERED AN UNPROTECTED OPENING AS PER 9.10.14.6.

COLD CELLAR PORCH SLAB (9.39.) FOR MAX. 8'-2" (2500) PORCH DEPTH, 5" (127) 32 MPa (4640psi) CONC. SLAB W/5-8% AIR ENTRAINMENT. REINF. WITH 10M BARS @ 7 7/8" (200) O.C. EACH DIRECTION, W 1 1/4" (32) CLEAR COVER FROM BOTTOM OF SLAB TO FIRST LAYER OF BARS & SECOND LAYER OF BARS LAID DIRECTLY ON TOP OF LOWER LAYER IN OPPOSITE DIR. 24"x24" (610x610) 10M DOWELS @ 23 5/8" (600) O.C.,

ANCHORED IN PERIMETER FND. WALLS. ŚLOPE SLAB 1.0% FROM DOOR. **RANGE HOODS AND RANGE-TOP FANS** 

COOKING APPLIANCE EXHAUST FANS VENTED TO EXTERIOR MUST CONFORM TO OBC 9.10.22, 9.32.3.9. & 9.32.3.10.

**CONVENTIONAL ROOF FRAMING** (9.23.13., 9.23.15.) 2"x6" (38x140) RAFTERS @ 16" (406) O.C., 2"x8" (38x184) RIDGE BOARD. 2"x4" (38x89) COLLAR TIES AT MID-SPAN. CEILING JOISTS TO BE 2"x4" (38x89) @ 16" (406) O.C. FOR MAX. 9-3" (2819) SPAN & 2"x6" (38x140) @ 16" (406) .C. FÒR MAX. SPAN 14'-7" (4450). RAFTERS FOR BUILT UP ROOF OVER PRE-ENGINEERED ROOF TRUSSES AND OR CONVENTIONAL FRAMING TO BE 2"x4" (38x89) @ 24" (610) O.C. UNLESS OTHERWISE SPECIFIED.



FOR STRUCTURAL ONLY. EXCLUDING ENGINEERED ROOF TRUSS, FLOOR JOIST, AND FLOOR LVL BEAM DESIGN. cont. SECTION 1.0. CONSTRUCTION NOTES

**TWO STOREY VOLUME SPACES** (9.23.10.1., 9.23.11., 9.23.16.) 
 WALL ASSEMBLY
 WIND LOADS

 EXTERIOR
 STUDS
 <= 0.5 kPA (q50)</td>
 > 0.5 kPa (q50)

 SPACING
 MAX HEIGHT
 SPACING
 MAX HEIGHT

 BRICK
 2-2"x6"
 12" (305) O.C.
 18-4" (5588)
 8" (200) O.C.
 18-4" (5588)
 SIDING (2-38×140) SPR.#2 16" (406) O.C. 18'-4" (5588) 12" (305) O.C. 18'-4" (5588) BRICK 2-2"x8" 12" (305) O.C. 21'-0" (6400) 12" (305) O.C. 21'-0" (6400) SPR.#2 16" (406) O.C. 21'-0" (6400) 16" (406) O.C. 21'-0" (6400) \*\* STUD SIZE & SPACING TO BE VERIFIED BY STRUCTURAL ENGINEER \* STUDS ARE TO BE CONTINUOUS, C/W 3/8" (9.5) THICK EXTERIOR PLYWOOD SHEATHING. PROVIDE SOLID WOOD BLOCKING BETWEEN WOOD STUDS @ 4'-0" (1220) O.C. VERTICALLY.

- FOR HORIZ. DISTANCES LESS THAN 9'-6' (2896) PROVIDE 2"x6' (38x140) STUDS @
16" (406) O.C. WITH CONTIN. 2-2"x6" (2-38x140) TOP PLATE + 1-2"x6" (1-38x140)
BOTTOM PLATE & MIN. OF 3-2"x8" (3-38x184) CONT. HEADER AT GROUND FLOOR CEILING LEVEL TOE-NAILED & GLUED AT TOP, BOTTOM PLATES & HEADERS

1 HR. PARTY WALL (CONC. BLOCK) ([SB-3] WALL TYPE 'B6e' & 'B1b') /2" (12.7) GYPSUM SHEATHING ON EACH SIDE ON 2"x2" (38x38) VERTICAL WD STRAPPING @ 24" (610) O.C. ON 8" (200) CONC. BLOCK FILL STRAPPING CAVITY EACH SIDE WITH AT LEAST 90% OF ABSORPTIVE MATERIAL PROCESSED FROM ROCK, SLAG OR GLASS. TAPE, FILL & SAND ALL GYPSUM JOINTS. EXPOSED BLOCK MUST BE SEALED W/ 2 COATS OF PAINT OR FURRED WITH 2"x2" (38x38) WD. STRAPPING & 1/2" (12.7) GYPSUM SHEATHING.

40 1 HR. PARTY WALL (DOUBLE STUD) ([SB-3] WALL TYPE 'W13c') 5/8" (15.9) TYPE 'X' GYPSUM SHEATHING ON EXTERIOR SIDE OF 2 ROWS OF 2"x4" (38x89) STUDS @ 16" (406) O.C., MIN. 1" (25) APART ON SEPARATE 2"x-(38x89) SILL PLATES. (2"x6" (38x140) AS REQUIRED) FILL ONE SIDE OF STUD CAVITY WITH AT LEAST 90% OF ABSORPTIVE MATERIAL PROCESSED FROM ROCK, SLAG OR GLASS. TAPE FILL AND SAND ALL GYPSUM JOINTS.

40A) 2 HR. FIREWALL ([SB-3] WALL TYPE 'B6e' & 'B1b') 1/2" (12.7) GYPSUM SHEATHING ON EACH SIDE ON 2"X2" (38x38) VERTICAL WOOD STRAPPING @ 24" (610) O.C ON 8" (200) CONC. BLOCK 75% SOUID. FILL STRAPPING CAVITY EACH SIDE WITH AT LEAST 90% OF ABSORPTIVE MATERIAL PROCESSED FROM ROCK, SLAG OR GLASS. TAPE, FILL & SAND ALL GYPSUM JOINTS. AT UNFINISHED AREAS, EXTERIOR FACE OF CONC. BLOCK TO BE SEALED WITH 2 COATS OF PAINT. GYPSUM SHEATHING TO BE ATTACHED TO CONC. BLOCK, (REFER TO DETAILS)

41 STUCCO WALL CONSTRUCTION (2'x6') STUCCO FINISH CONFORMING TO O.B.C. SECTION 9.28. AND APPLIED PER MANUFACTURERS SPECIFICATIONS OVER 1 1/2" (38) E.I.F.S. (MINIMUM) ON APPROVED DRAINAGE MAT ON 1/2" (12.7) DENSGLASS GOLD GYPSUM BOART ON STUDS CONFORMING TO O.B.C (9.23.10.1.) & SECTION 1.1., INSULATION, APPROVED 6 MIL. POLYETHYLENE VÅPOUR BARRIER. 1/ WALLBOARD INT. FINISH. (REFER TO 35 NOTE AS REQUIRED)

(41A) STUCCO WALL CONSTRUCTION (2'x6") W/ CONTIN. INSUL. STUCCO FINISH CONFORMING TO O.B.C. SECTION 9.28. AND APPLIED PERMANUFACTURERS SPECIFICATIONS OVER 1 1/2" (38) E.I.F.S. (MINIMUM) ON APPROVED DRAINAGE MAI ON APPROVED AIR/WALLER DARRIER AS FED OLD C. 9.27.3. ON EXTERIOR TYPE RIGID INSULATION (JOINTS UNTAPED) MECHANICAL FASTENED AS PER MANUFACTURER'S SPECIFICATIONS, ON 7/16" EXTERIOR TY SHEATHING ON STUDS CONFORMING TO O.B.C (9.23.10.1.) & SECTION 1.1., INSULATION, APPROVED 6 MILL POLYETHYLENE VAPOUR BARRIER, 1/2" (12.7) GYPSUM WALLBOARD INT. FINISH. (REFER TO 35 NOTE AS REQUIRED) 41B STUCCO WALL @ GARAGE CONST.

STUCCO FINISH CONFORMING TO O.B.C. SECTION 9.28. AND APPLIED PER MANUFACTURERS SPECIFICATIONS OVER 1 1/2" (38) E.F.I.S (MINIMUM) ON APPROVED DRAINAGE MAT ON 1/2" (12.7) DENSGLASS GOLD GYPSUM BRD. ON STUDS CONFORMING TO O.B.C (9.23.10.1.) & SECTION 1.1., 1/2" (12.7) GYPSUM WALLBOARD INT. FINISH. (REFER TO 35 NOTE AS REQ.) \*\* FOR DWELLINGS USING CONTIN. INSULATION CONSTRUCTION PROVIDE APPROVED DRAINAGE MAT ON 7/16" (11) EXTERIOR TYPE SHEATHING OVER FURRING (AS REQ.) AND STUDS IN LIEU OF 1 1/2" (38) E.F.I.S (MINIMUM) ON APPROVED DRAINAGE MAT ON 1/2" (12.7) DENSGLASS GOLD GYPSUM BRD **UNSUPPORTED FOUNDATION WALLS** (9.15.4.2.)

REINFORCING AT STAIRS AND SUNKEN FLOOR AREAS 2-20M BARS IN TOP PORTION OF WALL (UP TO 8-0" OPENING) 3-20M BARS IN TOP PORTION OF WALL (8-0" TO 10-0" OPENING) 4-20M BARS IN TOP PORTION OF WALL (10'-0" TO 15'-0" OPENING - BARS STACKED VERTICALLY AT INTERIOR FACE OF WALL @ 6" O.C REINFORCING AT BASEMENT WINDOWS 2-15M HORIZ. REINFORCING ON THE INSIDE AND OUTSIDE FACE OF THE FOUNDATION WALL BELOW THE WIN. SILL. EXTEND BARS 24" (610) BEYOND THE OPENING. 2-15M VERTICAL REINFORCING ON THE INSIDE AND OUTSIDE

FACE OF THE FOUNDATION WALL ON EACH SIDE OF THE WINDOW OPENING - BARS TO HAVE MIN. 1" (25) CONC. COVER - BARS TO EXTEND 2"-0" (610) BEYOND BOTH SIDES OF OPENING 43 STUD WALL REINFORCEMENT

PROVIDE STUD WALL REINFORCEMENT IN MAIN BATHROOM CONFORMING TO O.B.C. (9.5.2.3.(1)) (REFER TO DETAILS) WINDOW WELLS

WHERE A WINDOW OPENS INTO A WINDOW WELL, A CLEARANCE OF NOT LESS THAN 21 5/8" (550) SHALL BE PROVIDED IN FRONT OF THE WINDOW. EVERY WINDOW WELL SHALL BE DRAINED TO THE FOOTING LEVEL OR OTHER SUITABLE LOCATION WITH A 4" (100) WEEPING TILE C/W A FILTER CLOTH WRAP AND FILLED WITH CRUSHED STONE. (9.9.10.1.(5), 9.14.6.3.) SLOPED CEILING CONSTRUCTION ([SB-12] 3.1.1.8., 9.23.4.2.)

SURFACE OF EXTERIOR WALLS SHALL NOT BE LESS THAN R20 (3.52 RSI). FLAT ROOF/BALCONY CONSTRUCTION WATERPROOFING MEMBRANE (9.26.11, 9.26.15, 9.26.16) FULLY ADHERED TO 5 (15.9) T&G EXTERIOR GRADE PLYWOOD SHEATHING ON 2"x2" (38x38) PURLINS

(10.9) TAG EXTERIOR GRADE TET WOOD STEATHING ON 2.2. (29.30) FORLING ANGLED TOWARDS SCUPPER @ 2% MINIMUM LAID PERPENDICULAR TO 2:x8" (38x184) FLOOR JOISTS @ 16" (406) O.C. (UNLESS OTHERWISE NOTED). BUILT CURB TO BE 4" (100) MIN. ABOVE FINISHED BALCONY FLOOR. CONTINUOUS 'L TRIM DRIP EDGE TO BE PROVIDED ON OUTSIDE FACE OF CURB. SCUPPER DRA TO BE LOCATED 24" (610) MIN. AWAY FROM HOUSE. PREFINISHED ALUMINUM O PANEL FOR UNDERSIDE OF SOFFIT (9.23.2.3). REMOVE CURB WHERE REQ. **BALCONY CONDITION** 

SEE FLAT ROOF/BALCONY CONSTRUCTION NOTE. INCLUDE 2"x4" (38x89) PT. DECKING W/ 1/4" (6.4) GAPS LAID FLAT PARALLEL TO JOISTS ON 2"x4" (38x89) PT. SLEEPERS @ 12" (305) O.C. LAID FLAT PERPENDICULAR TO JOISTS BALCONY OVER HEATED SPACE CONDITION SEE FLAT ROOF/BALCONY CONSTRUCTION NOTE FOR ASSEMBLY, REFER TO PLANS FOR FLOOR JOIST SIZE & REFER TO HEX NOTE 9 FOR INSULATION AND

BARREL VAULT CONSTRUCTION

LINDERSIGNED HAS REVIEWED AND TAKES RESPONSIBILITY FOR THIS DESIGN AND HA

DDE TO BE A DESIGNER.

CANTILEVERED 2"X4" (38x89) SPACERS LAID FLAT ON 2"X10" (38x235) SPR. #2 ROOF JOIST NAILED TO BUILT-UP 3-3/4" (19) PLYWOOD HEADER PROFILED FOR BARREL. SPRAY FOAM INSULATION BETWEEN JOISTS W/ GYPSUM BOARD. INTERIOR FIN. (REFER TO DETAILS)

REFER TO SB-12 ENERGY EFFICIENCY DESIGN MATRIX ON THE TITLE PAGE FOR ALL VALUES AS REQUIRED PER 3.1.1., 3.1.2., 3.1.3. OF THE OBC.

**SECTION 1.1. WALL STUDS** 

- REFER TO THIS CHART FOR STUD SIZE & SPACING AS REQUIRED FOR EXTERIOR WALLS ONLY. REFER TO SITING & GRADING PLAN OF THIS UNIT FOR CONFIRMATION OF TOP OF FOUNDATION WALL AND ADDITIONAL INFORMATION.

| TIEVIEW ED AND ALT HOVED DE ENGINEEN. |   |                |                |                 |  |  |
|---------------------------------------|---|----------------|----------------|-----------------|--|--|
| SIZE                                  | ZE & SPACING OF STUDS: (OBC REFERENCE - TABLE 9.23.10.1.) |                |                |                 |  |  |
| MIN.                                  |   | SUPPORTED LO   | , ,            |                 |  |  |
| STUD                                  | ROOF w/ OR  | ROOF w/ OR w/o | ROOF w/ OR w/o | ROOF w/ OR w/o  |  |  |
| SIZE.                                 |   |                |                | ATTIC & 3 FLOOR |  |  |
| in (mm)                               | MAX. STUD SPACING, in (mm) O.C.                           |                |                |                 |  |  |
| 111 (111111)                          | MAX. UNSUPPORTED HGT., ft-in (m)                          |                |                |                 |  |  |
| 2"x4"                                 | 24" (610)   | 16" (405)      | 12" (305)      | N/A             |  |  |
| (38x89)                               | 9'-10" (3.0)  | 9'-10" (3.0)   | 9'-10" (3.0)   | N/A             |  |  |
| 2"x6"                                 | -   | 24" (610)      | 16" (406)      | 12" (305)       |  |  |
| (38x140)                              | 5'-11" (1.8)  |                |                |                 |  |  |

## **SECTION 2.0. GENERAL NOTES**

2.1. WINDOWS EXCEPT WHERE A DOOR ON THE SAME FLOOR LEVEL AS THE BEDROOM PROVIDE: DIRECT ACCESS TO THE EXTERIOR, EVERY FLOOR LEVEL CONTAINING A BEDROOM IS TO HAVE AT LEAST ONE OUTSIDE WINDOW W/ MIN. 0.35m2 UNOBSTRUCTED OPEN ORTION W/ NO DIMENSION LESS THAN 1'-3" (380). CAPABLE OF MAINTAINING THE OPENING WITHOUT THE NEED FOR ADDITIONAL SUPPORT, CONFORMING TO 9.9.10. 2) WINDOW GUARDS: A GUARD OR A WINDOW WITH A MAXIMUM RESTRICTED OPENING WIDTH OF 4" (100) IS REQUIRED WHERE THE TOP OF THE WINDOW SILL IS LOCATED LESS THAN 1'-7" (480) ABOVE FIN. FLOOR AND THE DISTANCE FROM THE INISHED FLOOR TO THE ADJACENT GRADE IS GREATER THAN 5'-11" (1800). (9.8.8.1 3) WINDOWS IN EXIT STAIRWAYS THAT EXTEND TO LESS THAN 2-11" (900) [3-6" (1070) FOR ALL OTHER BUILDINGS] SHALL BE PROTECTED BY GUARDS IN ACCORDANCE WITH NOTE #2 (ABOVE). OR THE WINDOW SHALL BE NON-OPERABLE AND DESIGNED TO WITHSTAND THE SPECIFIED LOADS FOR BALCONY GUARDS AS PROVIDED IN

4) REFER TO TITLE PAGE FOR MAX. U-VALUE REQUIREMENTS

2.2. CEILING HEIGHTS

4.1.5.15 OR 9.8.8.2

|  | THE CEILING HEIGHTS OF ROOMS AND SPACES SHALL CONFORM TO TABLE 9.5.3.1. |  |  |  |  |  |  |
|--|---|--|--|--|--|--|--|
|  | ROOM OR SPACE   | MINIMUM HEIGHTS  |  |  |  |  |  |
|  | LIVING ROOM, DINING<br>ROOM AND KITCHEN                                 | 7'-7" OVER 75% OF REQUIRED FLOOR AREA WITH A<br>CLEAR HEIGHT OF 6'-11" AT ANY POINT  |  |  |  |  |  |
|  | BEDROOM   | 7'-7" OVER 50% OF REQUIRED FLOOR AREA OR 6'-11"<br>OVER ALL OF THE REQUIRED FLOOR AREA.  |  |  |  |  |  |
|  | BASEMENT  | 6'-11" OVER AT LEAST 75% OF THE BASEMENT AREA<br>EXCEPT THAT UNDER BEAMS AND DUCTS THE<br>CLEARANCE IS PERMITTED TO BE REDUCED TO 6'-5". |  |  |  |  |  |
|  | BATHROOM, LAUNDRY<br>AREA ABOVE GRADE                                   | 6'-11" IN ANY AREA WHERE A PERSON WOULD<br>NORMALLY BE STANDING  |  |  |  |  |  |
|  | FINISHED ROOM NOT<br>MENTIONED ABOVE                                    | 6'-11"   |  |  |  |  |  |
|  | MEZZANINES  | 6'-11" ABOVE & BELOW FLOOR ASSEMBLY (9.5.3.2.)   |  |  |  |  |  |
|  | STORAGE GARAGE  | 6'-7" (9.5.3.3.)   |  |  |  |  |  |

2.3. MECHANICAL / PLUMBING

1) MECHANICAL VENTILATION IS REQUIRED TO PROVIDE 0.7 AIR CHANGE PER HOUR IF NOT AIR CONDITIONED 1 PER HOUR IF AIR CONDITIONED AVERAGED OVER 24 IOURS. WHEN A VENTILATION FAN (PRINCIPAL EXHAUST) IS REQUIRED, CONFORM O OBC 9.32.3.4. WHEN A HRV IS REQUIRED, CONFORM TO 9.32.3.11. REFER TO MECHAN**I**CAL DRAW**I**NGS.

2) REFER TO HOT WATER TANK MANUFACTURER SPECS. CONFORM TO OBC 9.31.6. 3) REFER TO TITLE PAGE FOR SPACE HEATING EQUIPMENT, HRV AND DOMESTIC HOT WATER HEATER MINIMUM EFFICIENCIES.

4) DRAIN WATER HEAT RECOVERY UNIT(S) WILL BE INSTALLED CONFORMING TO THE REQUIREMENTS OF SB12 - 3.1.1.12. OF THE O.B.C. L LUMBER SHALL BE SPRUCE No.2 GRADE OR BETTER, UNLESS NOTED OTHERWISE. 2) STUDS SHALL BE STUD GRADE SPRUCE, UNLESS NOTED OTHERWISE.

3) LUMBER EXPOSED TO THE EXTERIOR TO BE SPRUCE No. 2 GRADE PRESSURE TREATED OR CEDAR, UNLESS NOTED OTHERWISE. 4) ALL LAMINATED VENEER LUMBER (LVL) BEAMS, GIRDER TRUSSES, AND METAL HANGER CONNECTIONS SUPPORTING ROOF FRAMING TO BE DESIGNED & CERTIFIED BY FLOOR AND ROOF TRUSS MANUFACTURER.

5) JOIST HANGERS: PROVIDE APPROVED METAL HANGERS FOR ALL JOISTS AND BUILT-UP WOOD MEMBERS INTERSECTING WITH FLUSH BUILT-UP WOOD MEMBERS. 6) WOOD FRAMING NOT TREATED WITH A WOOD PRESERVATIVE, IN CONTACT WITH CONCRETE, SHALL BE SEPARATED FROM THE CONC. BY AT LEAST 2 mil POLYETHYLET FILM, No.50 (45lbs) ROLL ROOFING OR OTHER DAMPPROOFING MATERIAL, EXCEPT HERE THE WOOD MEMBER IS AT LEAST 6" (152) ABOVE THE GROUND.

1) STRUCTURAL STEEL SHALL CONFORM TO CAN/CSA-G40-21 GRADE 350W. HOLLOW STRUCT. SECTIONS SHALL CONFORM TO CAN/CSA-G40-21 GRADE 350W CLASS "H". 2) REINFORCING STEEL SHALL CONFORM TO CSA-G30-18M GRADE 400R.

2.6. FLAT ARCHES 1) FOR 8-0" (2440) CEILINGS, FLAT ARCHES SHALL BE 6'-10" (2080) A.F.F. 2) FOR 9'-0" (2740) CEILINGS, FLAT ARCHES SHALL BE 7'-10" (2400) A.F.F. 3) FOR 10'-0" (3040) CEILINGS, FLAT ARCHES SHALL BE 8'-6" (2600) A.F.F.

**2.7. ROOF OVERHANGS**1) ALL ROOF OVERHANGS SHALL BE 1'-0" (305). UNLESS NOTED OTHERWISE. **2.8. FLASHING** (9.20.13., 9.26.4. & 9.27.3.)

FLASHING MATERIALS & INSTALLATION SHALL CONFORM TO O.B.C 2.9. GRADING
1) THE BUILDING SHALL BE LOCATED OR THE BUILDING SITE GRADED SO THE WATER WILL NOT ACCUMULATE AT OR NEAR THE BUILDING AND WILL NOT ADVERSELY AFFECT ADJACENT PROPERTIES. CONFORM TO 9.14.6.

2.10. ULC SPECIFIED ASSEMBLIES
ALL REQUIRED INDIVIDUAL COMPONENTS THAT FORM PART OF ANY 'ULC LISTED ASSEMBLY', SPECIFIED WITHIN THESE DRAWINGS, CANNOT BE ALTERED OR SUBSTITUTED FOR ANY OTHER MATERIAL/PRODUCT OR SPECIFIED MANUFACTURER THAT IS IDENTIFIED IN THAT 'SPECIFIED ULC LISTING'. THERE SHALL BE NO DEVIATIONS UNDER ANY CIRCUMSTANCES IN ANY 'ULC LISTED ASSEMBLY' IDENTIFIED IN THESE DRAWINGS.

**SECTION 3.0. LEGEND** 

3.1. WOOD LINTELS AND BUILT-UP WOOD (DIVISION B PART 9. TABLES AS TO A10 AND A12, A15 & A16)

|  | FORMING PART OF SENTENCE 9.23.4.2.(3), 9.23.4.2.(4), 9.23.12.3.(1),(3), 9.23.13.8.(2), 9.37.3.1.(1) |   |                      |                     |                  |                     |  |
|--|---|---|----------------------|---------------------|------------------|---------------------|--|
|  | 2"x8" SPRUCE #2   |   | 2"x10" SPRUCE #2     |                     | 2"x12" SPRUCE #2 |                     |  |
| D  | L1  | 2/2"x8" (2/38x184)                      | L3                   | 2/2"x10" (2/38x235) | L5               | 2/2"x12" (2/38x286) |  |
|  | B1  | 3/2"x8" (3/38x184)                      | ВЗ                   | 3/2"x10" (3/38x235) | B5               | 3/2"x12" (3/38x286) |  |
|  | B2  | 4/2"x8" (4/38x184)                      | B4                   | 4/2"x10" (4/38x235) | B6               | 4/2"x12" (4/38x286) |  |
|  | B7  | 5/2"x8" (5/38x184)                      | B8                   | 5/2"x10" (5/38x235) | B9               | 5/2"x12" (5/38x286) |  |
| )R   | ENGINEERED LUMBER SCHEDULE - GRADE 2.0E (UNLESS NOTE OTHERWISE)                                     |   |                      |                     |                  |                     |  |
|  | 1 3/4" x 9 1/2" LVL   |   | 1 3/4" x 11 7/8" LVL |                     | 1 3/4" x 14" LVL |                     |  |
|  | LVL2  | 1-1 3/4"x9 1/2"                         | LVL3                 | 1-1 3/4"x11 7/8"    | LVL10            | 1-1 3/4"x14"        |  |
|  | LVL4  | 2-1 3/4"x9 1/2"                         | LVL6                 | 2-1 3/4"x11 7/8"    | LVL11            | 2-1 3/4"x14"        |  |
|  | LVL5  | 3-1 3/4"x9 1/2"                         | LVL7                 | 3-1 3/4"x11 7/8"    | LVL12            | 3-1 3/4"x14"        |  |
|  | LVL8  | 4-1 3/4"x9 1/2"                         | LVL9                 | 4-1 3/4"x11 7/8"    | LVL13            | 4-1 3/4"x14"        |  |
| 3.2. STEEL LINTELS SUPPORTING MASONRY VENEER |   |   |                      |                     |                  |                     |  |
|  |   | /////////////////////////////////////// | 1NI E                | DADTO TADIE 0.20    | ヽ゠っ              | D 1                 |  |

|      | (DIVISION B PART 9. TABLE 9.20.5.2.B.) FORMING PART OF SENTENCE 9.20.5.2.(2) & 9.20.5.2.(3) |                 |                |  |  |  |
|------|---|-----------------|----------------|--|--|--|
| CODE | SIZE  | BRICK           | STONE          |  |  |  |
| L7   | 3 1/2" x 3 1/2" x 1/4" (89 x 89 x 6.4)  | 8'-1" (2.47m)   | 7'-6" (2.30m)  |  |  |  |
| L8   | 4" x 3 1/2" x 1/4" (102 x 89 x 6.4)   | 8'-9" (2.66m)   | 8'-1" (2.48m)  |  |  |  |
| L9   | 4 7/8" x 3 1/2" x 5/16" (127 x 89 x 7.9)  | 10'-10" (3.31m) | 10'-1" (3.03m) |  |  |  |
| L10  | 4 7/8" x 3 1/2" x 3/8" (127 x 89 x 11)  | 11'-5" (3.48m)  | 10'-7" (3.24m) |  |  |  |
| L11  | 5 7/8" x 3 1/2" x 3/8" (152 x 89 x 11)  | 12'-6" (3.82m)  | 11'-7" (3.54m) |  |  |  |
| L12  | 7 1/8" x 4" x 3/8" (178 x 102 x 11)   | 14'-1" (4.30m)  | 13'-1" (3.99m) |  |  |  |

CONFORMING TO SECTIONS 9.5.11, 9.6., 9.7.2.1, 9.7.5.2, & 9.10.13.10 EXTERIOR | 2'-8" x 6'-8" x 1-3/4" (815 x 2030 x 45) INSULATED MIN. R4 (RSI 0.7) EXTERIOR | 2'-10" x 6'-8" x 1-3/4" (865 x 2030 x 45) INSULATED MIN. R4 (RSI 0.7) EXTERIOR | 3'-0" x 6'-8" x 1-3/4" (915 x 2030 x 45) INSULATED MIN. R4 (RSI 0.7) XTERIOR | 2'-6" x 6'-8" x 1-3/4" (760 x 2030 x 45) INSULATED MIN. R4 (RSI 0.7) EXTERIOR | 2"-8" x 6"-8" x 1-3/4" (815 x 2030 x 45) INS. MIN. R4 (RSI 0.7) (SEE HEX NOTE 20 E | EXTERIOR | 3'-0" x 8'-0" x 1-3/4" (915 x 2440 x 45) INSULATED MIN. R4 (RSI 0.7). EXTERIOR | 2'-8" x 8'-0" x 1-3/4" (815 x 2440 x 45) INSULATED MIN. R4 (RSI 0.7) EXTERIOR | 2-8" x 6-8" x 1-3/4" (815 x 2030 x 45) 20 MIN. F.R.P. DOOR/FRAME WITH APP. SELF CLOSING DEVIC INTERIOR | 2'-8" x 6'-8" x 1-3/8" (815 x 2030 x 35) INTERIOR | 2'-6" x 6'-8" x 1-3/8" (760 x 2030 x 35) INTERIOR | 2'-4" x 6'-8" x 1-3/8" (710 x 2030 x 35) INTERIOR DOORS FOR ALL 10' CEILING INTERIOR | 2'-0" x 6'-8" x 1-3/8" (610 x 2030 x 35) CONDITIONS A | INTERIOR | 2'-2" x 6'-8" x 1-3/8" (660 x 2030 x 35) INTERIOR | 1'-6" x 6'-8" x 1-3/8" (460 x 2030 x 35)

T.IST JOIST BFM | BEAM BY FLOOR MANUFACTURER | LIN | LINEN CLOSET BG | FIXED GLASS W/ BLACK BACKING | LVL | LAMINATED VENEER LUMBER BM BEAM OTB/A OPEN TO BELOW/ABOVE RMI BEAM BY ROOF MANUFACTURER PL | POINT LOAD CONVENTIONAL ROOF FRAMING PRESSURE TREATED TJ| DOUBLE JOIST/ TRIPLE JOIST D | PAINTED DO DO OVER WD | POWDER ROOM RWL RAIN WATER LEADER RP | DROPPEI NG ENGINEEREI SB | SOLID BEARING WOOD POS EST | ESTIMATED SBFA SB FROM ABOVE FA | FLAT ARCH SJ | SINGLE JOIS FLOOR DRAIN SPR SPRUCE FIXED GLASS T/O TOP OF FLR | FLOOR TYP TYPICAL GT | GIRDER TRUSS U/S UNDERSIDE HB HOSE BIB WD WOOD RV | HEAT RETURN VENTILATION UNIT | WIC | WALK IN CLOSET WP WEATHER PROOF WT | HOT WATER TANK

LL ELECTRICAL FACILITIES SHALL BE INSTALLED IN ACCORDANCE WITH SECTION 9.34 S EXHAUST VENT CLASS 'B' VENT → DUPLEX OUTLET (12" HIGH) DUPLEX OUTLET (HEIGHT AS NOTED A. → \$ SWITCH (2/3/4 WAY) HEAVY DUTY OUTLET POT LIGHT LIGHT FIXTURE (CEILING MOUNTE □GHT FIXTURE (PULL CHAIN) LIGHT FIXTURE (WALL MOUNTED) TELEPHONE JACK CABLE T.V. JACK CHANDELIER (CEILING MOUNTE CENTRAL VACUUM OUTLET SMOKE ALARM (9.10.19.)

PROVIDE ONE PER FLOOR, NEAR THE STAIRS CONNECTING THE FLOOR LEVEL. ALARMS ARE TO BE INSTALLED IN EACH SLEEPING ROOM AND IN A LOCATION BETWEEN SLEEPING ROOMS AND CONNECTING HALLWAYS AND WIRED TO BE INTERCONNECTED TO ACTIVATE ALL ALARMS IF ONE SOUNDS. ALARMS ARE TO BE CONNECTED TO AN ECTRICAL CIRCUIT AND WITH A BATTERY BACKUP. ALARM SIGNAL SHALL MEET MPORAL SOUND PATTERNS MIN. ALARMS SHALL HAVE A VISUAL SIGNALLING OMPONENT AS PER THE "NATIONAL FIRE ALARM AND SIGNALING CODE 72".

CMD CARBON MONOXIDE ALARM (9.33.4.) CONFORMING TO CAN/CGA-6.19 SHALL BE INSTALLED ON OR NEAR THE CEILING IN EACH DWELLING UNIT ADJACENT TO EACH SLEEPING AREA. CARBON MONOXIDE ALARM(S) SHALL BE PERMANENTLY WIRED WITH NO DISCONNECT SWITCH, WITH AN ALARM THAT IS

SB SOLID BEARING (BUILT-UP WOOD COLUMNS AND STUD POSTS)

SOLID BEARING (BUILT-UP WOOD COLUMNS AND THE WIDTH OF A WOOD COLUMN SHALL NOT BE LESS THAN THAN THE WIDTH OF SUPPORTED MEMBER. BUILT-UP WOOD COLUMNS SHALL BE NAILED TOGETHER WITH NOT LESS THAN 3" (76) NAILS SPACED NOT MORE THAN 11 3/4" (300) O.C. THE NUMBER OF STUDS IN A WALL DIRECTLY BELOW A GIRDER TRUSS OR ROOF BEAM SHALL CONFORM TO TABLES A-34 TO A-37. (9.17.4., 9.23.10.7.)

AUDIBLE WITHIN SLEEPING ROOMS WHEN THE INTERVENING DOORS ARE CLOSED.

TWO STOREY VOLUME SPACE. SEE CONSTRUCTION NOTE 39.

WARYING PLATES, BUILT-OUT FLOORS, BEARING WALLS, ICE & WATER SHIELI EXPOSED BUILDING FACE -O.B.C. 9.10.14, OR 9.10.15.

REFER TO HEX NOTE 35. & DETAILS FOR TYPE AND SPECIFICATIONS.

1 HR. PARTY WALL
REFER TO HEX NOTE 40.

2 HR. FIREWALL
REFER TO HEX NOTE 40A.

**SECTION 4.0. CLIMATIC DATA** 

DESIGN SNOW LOAD (9.4.2.2.) 1.01 **kPa** WIND PRESSURE (q50) (SB-1.2.): 0.44 **kPa** 

NSTRUCTION NOTE REVISION DATE: **DECEMBER 15, 2021** 

**CONSTRUCTION NOTES** GOLDPARK HOMES - 221081 UNIT 5011-COR-UPG-TIMBERLAND PINE VALLEY, PH.2 VAUGHAN ONT.

3/16"=1'-0" 221081WS5011-COR-UPG-TIMBERLAND.dwg 10 of 1 WT AW 8966 Woodbine Ave, Markham, ON L3R 0J7 T 905.737.5133 F 905.737.7326

HUNT LU aw Allan Whiting STRATION INFORMATION HUNT DESIGN ASSOCIATES INC

www.huntdesign.ca