


1000 Trusses 18-331269 000 0044

For conventional framing roof/ceilings
framing shall conform to OBC.9.2.3



THIS CERTIFICATION IS FOR THE ENGINEERING REVIEW OF STRUCTURAL COMPONENTS SHOWN ON THIS DRAWING AND IS LIMITED TO THE COMPONENTS SUPPLIED BY KOTT LUMBER FOR THE LOADS AND CONDITIONS SHOWN ON THE CALCULATION PAGE OF EACH COMPONENT. THE PLACEMENT OF THESE COMPONENTS ON THIS LAYOUT IS SHOWN FOR REFERENCE ONLY. ROOF TRUSSES MUST BE INSTALLED ACCORDING TO MANUFACTURER'S GUIDELINES AT 24" C/C UNLESS NOTED OTHERWISE. CONVENTIONAL FRAMING SHOWN ON THE LAYOUT MUST BE DESIGNED AND APPROVED BY THE PROJECT ENGINEER. TEMPORARY AND PERMANENT BRACINGS OF THE ROOF AND BUILDING ARE THE RESPONSIBILITY OF THE PROJECT ENGINEER AND TO CONFORM TO BCSI GUIDELINES.



CITY OF BRAMPTON
BUILDING DIVISION
REVIEWED
DEC 7 2018
MARK DERKSEN

All work shall conform to the Ontario
Building Code O. Reg. 332/12 as amended

18-331269 000 00 P2

READ ALL NOTES ON THIS PAGE AND ON
ENGINEERING NOTE PAGE ENP-1. THIS
NOTE PAGE IS AN INTEGRAL PART OF
THIS DRAWING AS IT CONTAINS
SPECIFICATIONS AND CRITERIA USED IN
THE DESIGN OF THIS COMPONENT.

Architectural Drawing Info:
Date: JULY 26, 2018
Project number: 18-24
Model: GRANDBROOKE 1



CONVENTIONAL
FRAMING BY OTHERS

ALL CONVENTIONAL FRAMING TO CONFORM WITH
PART 9 OF THE O.B.C.
ROOF RAFTERS THAT CROSS MEET OVER TRUSSES
TO BE 2x4 S.P.F. @ 24" O/C WITH A 2x4 VERTICAL
POST TO THE TRUSS UNDERNEATH EACH CROSS
POINT. VERTICAL POST LONGER THAN 6' TO HAVE
LATERAL BRACING SO THAT THE DISTANCE BETWEEN
END POINT AND BETWEEN ROWS OF BRACING
DOES NOT EXCEED 6'.

SIZE AND LOCATION OF CONVENTIONAL FRAMING
IS APPROXIMATE. ALL AREAS MAY NOT BE SHOWN.
REFER TO ARCHITECTURAL PLANS FOR DETAILS.

HANGER LEGEND:

- ▼ LUS24
- LJS26DS
- HGUS26
- ✕ HGUS26-2

DESIGN CRITERIA
SPECIFIED LOADS:
TOP CH. LL = 23.3 PSF
DL = 3 PSF
BOT CH. LL = 0 PSF
DL = 7 PSF
TOTAL LOAD = 33.3 PSF

SPACING = 24" O/C.

THIS TRUSS IS DESIGNED FOR RESIDENTIAL OR
SMALL BUILDING REQUIREMENTS OF PART 9, NBCC 2010

THIS DESIGN COMPLIES WITH:
- PART 9 OF OBC 2012, BCBC 2012, ABC 2014
- CSA 088-08
- TPIC 2011

Model: **GRANDBROOKE 1 EL 1**
Customer: GREENPARK
Project: MINNISALE HOMES
Location: BRAMPTON
Date: 6/22/2018 Drawn by: BB
Lot 14



ENGINEERING NOTE PAGE (ENP-1)
PLEASE READ PRIOR TO INSTALLATION

NE0818-060

GREENPARK-MINNISLAE HOMES-GRANDBROOKE 1 EL 1 - LOT 14

RESPONSIBILITIES

THIS DESIGN IS FOR AN INDIVIDUAL BUILDING COMPONENT AND HAS BEEN BASED ON INFORMATION PROVIDED BY THE DESIGN OFFICE OF KOTT LUMBER. THE UNDERSIGNED ENGINEER DISCLAIMS ANY RESPONSIBILITY FOR DAMAGES AS A RESULT OF FAULTY OR INCORRECT INFORMATION, SPECIFICATION AND/OR DESIGNS FURNISHED TO THE ENGINEER. THE UNDERSIGNED ENGINEER IS ONLY RESPONSIBLE FOR THE STRUCTURAL INTEGRITY OF THIS BUILDING COMPONENT FOR THE CONDITIONS AND LOADS SHOWN ON THIS DRAWING. THE STRUCTURAL INTEGRITY OF THE BUILDING AND THE VERIFICATION OF THE DIMENSIONS AND THE DESIGN LOADS USED ARE THE RESPONSIBILITY OF THE BUILDING DESIGNER.

TRUSSES ARE DESIGNED IN CONFORMANCE WITH THE RELEVANT SECTIONS OF THE NATIONAL BUILDING CODE OF CANADA OR THE CANADIAN CODE FOR FARM BUILDINGS, WHICHEVER APPLIES TO THE BUILDING TYPE INDICATED ON THE DRAWING

IT IS THE RESPONSIBILITY OF KOTT LUMBER TO ENSURE THAT TRUSSES ARE MANUFACTURED IN CONFORMANCE WITH THESE DESIGNS AND WITH THE SPECIFICATIONS OUTLINED BELOW. THE UNDERSIGNED ENGINEER IS NOT RESPONSIBLE FOR QUALITY CONTROL IN THE TRUSS MANUFACTURING PLANT.

USE AND OCCUPANCY

- The building is of the type indicated on the drawing

LOADING

- The truss loading intensity and distribution as well as load transfer mechanism is that indicated on the drawing
- No buildings, trees, parapets or other projections higher than the roof for which the trusses are used are located within a distance less than ten (10) times the difference in height, or five metres (16 ft) whichever is greater, unless the drawing indicates that the snow drifting has been taken into account

HANDLING, INSTALLATION AND BRACING


- The trusses must be handled and installed by a qualified professional as per the supplied document titled *Information for Truss Installers* and the BCSI-B1 and BCSI-B3 Summary Sheets
- The compression chords are laterally braced by continuous rigid diaphragm sheathing or as specified on the drawing
- Temporary and permanent bracing must be installed as indicated on the truss drawing and according to the BCSI-B1 and BCSI-B3 Summary Sheets. Bracing for the lateral stability of the truss is to be provided by the building designer
- **It is recommended that a Professional Engineer's advice be obtained for the bracing of trusses spanning more than 12.37m (40'-7")**

SUPPORTS

- The trusses are to be supported at the bearing points indicated and anchored to the supports where considered necessary by the designer of the overall structure
- Bearing sizes shown are the minimum required to prevent crushing of the truss members and do not necessarily take into account stability of the overall building structure
- Elevation of bearings must be carefully checked and shimmed to alignment for solid bearings
- Adequate wood truss bearing is the responsibility of the building designer.

DIMENSIONS

- Geometry of the truss and dimensions indicated on the drawing are identical to those of the installed truss.



THIS CERTIFICATION IS FOR THE ENGINEERING REVIEW OF STRUCTURAL COMPONENTS SHOWN ON THIS DRAWING AND IS LIMITED TO THE COMPONENTS SUPPLIED BY KOTT LUMBER FOR THE LOADS AND CONDITIONS SHOWN ON THE CALCULATION PAGE OF EACH COMPONENT. THE PLACEMENT OF THESE COMPONENTS ON THIS LAYOUT IS SHOWN FOR REFERENCE ONLY. ROOF TRUSSES MUST BE INSTALLED ACCORDING TO MANUFACTURER'S GUIDELINES AT 24" C/C UNLESS NOTED OTHERWISE. CONVENTIONAL FRAMING SHOWN ON THE LAYOUT MUST BE DESIGNED AND APPROVED BY THE PROJECT ENGINEER. TEMPORARY AND PERMANENT BRACINGS OF THE ROOF AND BUILDING ARE THE RESPONSIBILITY OF THE PROJECT ENGINEER AND TO CONFORM TO BCSI GUIDELINES.

READ ALL NOTES ON THIS PAGE AND ON ENGINEERING NOTE PAGE ENP-1. THIS NOTE PAGE IS AN INTEGRAL PART OF THIS DRAWING AS IT CONTAINS SPECIFICATIONS AND CRITERIA USED IN THE DESIGN OF THIS COMPONENT.

Architectural Drawing Info:
Date: JULY 26, 2018
Project number: 18-24
Model: GRANDBROOKE 1



CONVENTIONAL FRAMING BY OTHERS

ALL CONVENTIONAL FRAMING TO CONFORM WITH PART 9 OF THE O.B.C. ROOF RAFTERS THAT CROSS MEET OVER TRUSSES TO BE 2x4 S.P.F. @ 24"OC WITH A 2x4 VERTICAL POST TO THE TRUSS UNDER EACH CROSS POINT. VERTICAL POST LONGER THAN 8' TO HAVE LATERAL BRACING SO THAT THE DISTANCE BETWEEN END POINT AND BETWEEN ROWS OF BRACING DOES NOT EXCEED 8'.

SIZE AND LOCATION OF CONVENTIONAL FRAMING IS APPROXIMATE. ALL AREAS MAY NOT BE SHOWN. REFER TO ARCHITECTURAL PLANS FOR DETAILS.

HANGER LEGEND:

▼ LUS24
■ LJS26DS
■ HGUS26
X HGUS26-2

DESIGN CRITERIA
SPECIFIED LOADS:
TOP CH. LL = 25.3 PSF
DL = 3 PSF
BOT CH. LL = 3 PSF
DL = 7 PSF
TOTAL LOAD = 35.3 PSF

SPACING = 24" O.C.
THIS TRUSS IS DESIGNED FOR RESIDENTIAL OR SMALL BUILDING REQUIREMENTS OF PART 9, NBC 2010
THIS DESIGN COMPLIES WITH
- PART 9 OF CBC 2012, BCSI 2012, ABC 2014
- CSA 084-08
- IBC 2011

Model: GRANDBROOKE 1 EL 1
Customer: GREENPARK
Project: MINNISALE HOMES
Location: BRAMPTON
Date: 6/22/2018 Drawn by: BB

JOB NAME	TRUSS NAME	QUANTITY	PLY	JOB DESC.	DRWG NO.
NE0818-060	G01	1	1	GREENPARK-MINNISLAE HOMES-GRANDBROOKE 1 EL 1	
				TRUSS DESC.	

Version 8.210 S Mar 12 2018 MiTek Industries, Inc. Mon Aug 13 08:50:53 2018 Page 2
ID:w_6JogZnfv1q7BUYX2Ki0Uz3oDL-4UMWliE4IFIBk?bBDGa6kF8mm7ZLYC8rljYrFfyoKDG

PLATE PLACEMENT TOL. = 0.250 inches

PLATE ROTATION TOL. = 5.0 Deg.

JSI GRIP= 0.90 (12) (INPUT = 0.90)

JSI METAL= 0.68 (9) (INPUT = 1.00)




READ ALL NOTES ON THIS PAGE AND ON
ENGINEERING NOTE PAGE ENP-1. THIS
NOTE PAGE IS AN INTEGRAL PART OF
THIS DRAWING AS IT CONTAINS
SPECIFICATIONS AND CRITERIA USED IN
THE DESIGN OF THIS COMPONENT.



JOB NAME	TRUSS NAME	QUANTITY	PLY	JOB DESC.	DRWG NO.
NE0818-060	G02	1	1	GREENPARK-MINNISLAE HOMES-GRANDBROOKE 1 EL 1	

Version 8.210 S Mar 12 2018 MiTek Industries, Inc. Mon Aug 13 08:50:54 2018 Page 1
ID:w_6JogZnfv1q7BUYX2Ki0Uz3oDL-YgwwW2Fi3YQ1L9AnN_5LGShtkXxWhhe?WNlOn5yoKDf

-1-3-8 0-0 3-2-7 3-2-7 4-3-2 7-5-10 4-3-2 11-8-12 5-0-6 16-9-2 5-0-6 21-9-9 3-2-7 25-0-0 1-3-8 26-3-8
Scale = 1:43.2



TOTAL WEIGHT = 118 lb
[M]

LUMBER				
N. L. G. A. RULES				
CHORDS	SIZE	LUMBER		DESCR
1 - 3	2x4	DRY	No.2	SPF
3 - 6	2x4	DRY	No.2	SPF
6 - 8	2x4	DRY	No.2	SPF
8 - 10	2x4	DRY	No.2	SPF
10 - 12	2x6	DRY	No.2	SPF
12 - 14	2x6	DRY	No.2	SPF
14 - 16	2x6	DRY	No.2	SPF
16 - 18	2x6	DRY	No.2	SPF
18 - 20	2x6	DRY	No.2	SPF
20 - 22	2x6	DRY	No.2	SPF
22 - 24	2x6	DRY	No.2	SPF
24 - 26	2x6	DRY	No.2	SPF
26 - 28	2x6	DRY	No.2	SPF
28 - 30	2x6	DRY	No.2	SPF
30 - 32	2x6	DRY	No.2	SPF
32 - 34	2x6	DRY	No.2	SPF
34 - 36	2x6	DRY	No.2	SPF
36 - 38	2x6	DRY	No.2	SPF
38 - 40	2x6	DRY	No.2	SPF
40 - 42	2x6	DRY	No.2	SPF
42 - 44	2x6	DRY	No.2	SPF
44 - 46	2x6	DRY	No.2	SPF
46 - 48	2x6	DRY	No.2	SPF
48 - 50	2x6	DRY	No.2	SPF
50 - 52	2x6	DRY	No.2	SPF
52 - 54	2x6	DRY	No.2	SPF
54 - 56	2x6	DRY	No.2	SPF
56 - 58	2x6	DRY	No.2	SPF
58 - 60	2x6	DRY	No.2	SPF
60 - 62	2x6	DRY	No.2	SPF
62 - 64	2x6	DRY	No.2	SPF
64 - 66	2x6	DRY	No.2	SPF
66 - 68	2x6	DRY	No.2	SPF
68 - 70	2x6	DRY	No.2	SPF
70 - 72	2x6	DRY	No.2	SPF
72 - 74	2x6	DRY	No.2	SPF
74 - 76	2x6	DRY	No.2	SPF
76 - 78	2x6	DRY	No.2	SPF
78 - 80	2x6	DRY	No.2	SPF
80 - 82	2x6	DRY	No.2	SPF
82 - 84	2x6	DRY	No.2	SPF
84 - 86	2x6	DRY	No.2	SPF
86 - 88	2x6	DRY	No.2	SPF
88 - 90	2x6	DRY	No.2	SPF
90 - 92	2x6	DRY	No.2	SPF
92 - 94	2x6	DRY	No.2	SPF
94 - 96	2x6	DRY	No.2	SPF
96 - 98	2x6	DRY	No.2	SPF
98 - 100	2x6	DRY	No.2	SPF
100 - 102	2x6	DRY	No.2	SPF
102 - 104	2x6	DRY	No.2	SPF
104 - 106	2x6	DRY	No.2	SPF
106 - 108	2x6	DRY	No.2	SPF
108 - 110	2x6	DRY	No.2	SPF
110 - 112	2x6	DRY	No.2	SPF
112 - 114	2x6	DRY	No.2	SPF
114 - 116	2x6	DRY	No.2	SPF
116 - 118	2x6	DRY	No.2	SPF
118 - 120	2x6	DRY	No.2	SPF
120 - 122	2x6	DRY	No.2	SPF
122 - 124	2x6	DRY	No.2	SPF
124 - 126	2x6	DRY	No.2	SPF
126 - 128	2x6	DRY	No.2	SPF
128 - 130	2x6	DRY	No.2	SPF
130 - 132	2x6	DRY	No.2	SPF
132 - 134	2x6	DRY	No.2	SPF
134 - 136	2x6	DRY	No.2	SPF
136 - 138	2x6	DRY	No.2	SPF
138 - 140	2x6	DRY	No.2	SPF
140 - 142	2x6	DRY	No.2	SPF
142 - 144	2x6	DRY	No.2	SPF
144 - 146	2x6	DRY	No.2	SPF
146 - 148	2x6	DRY	No.2	SPF
148 - 150	2x6	DRY	No.2	SPF
150 - 152	2x6	DRY	No.2	SPF
152 - 154	2x6	DRY	No.2	SPF
154 - 156	2x6	DRY	No.2	SPF
156 - 158	2x6	DRY	No.2	SPF
158 - 160	2x6	DRY	No.2	SPF
160 - 162	2x6	DRY	No.2	SPF
162 - 164	2x6	DRY	No.2	SPF
164 - 166	2x6	DRY	No.2	SPF
166 - 168	2x6	DRY	No.2	SPF
168 - 170	2x6	DRY	No.2	SPF
170 - 172	2x6	DRY	No.2	SPF
172 - 174	2x6	DRY	No.2	SPF
174 - 176	2x6	DRY	No.2	SPF
176 - 178	2x6	DRY	No.2	SPF
178 - 180	2x6	DRY	No.2	SPF
180 - 182	2x6	DRY	No.2	SPF
182 - 184	2x6	DRY	No.2	SPF
184 - 186	2x6	DRY	No.2	SPF
186 - 188	2x6	DRY	No.2	SPF
188 - 190	2x6	DRY	No.2	SPF
190 - 192	2x6	DRY	No.2	SPF
192 - 194	2x6	DRY	No.2	SPF
194 - 196	2x6	DRY	No.2	SPF
196 - 198	2x6	DRY	No.2	SPF
198 - 200	2x6	DRY	No.2	SPF
200 - 202	2x6	DRY	No.2	SPF
202 - 204	2x6	DRY	No.2	SPF
204 - 206	2x6	DRY	No.2	SPF
206 - 208	2x6	DRY	No.2	SPF
208 - 210	2x6	DRY	No.2	SPF
210 - 212	2x6	DRY	No.2	SPF
212 - 214	2x6	DRY	No.2	SPF
214 - 216	2x6	DRY	No.2	SPF
216 - 218	2x6	DRY	No.2	SPF
218 - 220	2x6	DRY	No.2	SPF
220 - 222	2x6	DRY	No.2	SPF
222 - 224	2x6	DRY	No.2	SPF
224 - 226	2x6	DRY	No.2	SPF
226 - 228	2x6	DRY	No.2	SPF
228 - 230	2x6	DRY	No.2	SPF
230 - 232	2x6	DRY	No.2	SPF
232 - 234	2x6	DRY	No.2	SPF
234 - 236	2x6	DRY	No.2	SPF
236 - 238	2x6	DRY	No.2	SPF
238 - 240	2x6	DRY	No.2	SPF
240 - 242	2x6	DRY	No.2	SPF
242 - 244	2x6	DRY	No.2	SPF
244 - 246	2x6	DRY	No.2	SPF
246 - 248	2x6	DRY	No.2	SPF
248 - 250	2x6	DRY	No.2	SPF
250 - 252	2x6	DRY	No.2	SPF
252 - 254	2x6	DRY	No.2	SPF
254 - 256	2x6	DRY	No.2	SPF
256 - 258	2x6	DRY	No.2	SPF
258 - 260	2x6	DRY	No.2	SPF
260 - 262	2x6	DRY	No.2	SPF
262 - 264	2x6	DRY	No.2	SPF
264 - 266	2x6	DRY	No.2	SPF
266 - 268	2x6	DRY	No.2	SPF
268 - 270	2x6	DRY	No.2	SPF
270 - 272	2x6	DRY	No.2	SPF
272 - 274	2x6	DRY	No.2	SPF
274 - 276	2x6	DRY	No.2	SPF
276 - 278	2x6	DRY	No.2	SPF
278 - 280	2x6	DRY	No.2	SPF
280 - 282	2x6	DRY	No.2	SPF
282 - 284	2x6	DRY	No.2	SPF
284 - 286	2x6	DRY	No.2	SPF
286 - 288	2x6	DRY	No.2	SPF
288 - 290	2x6	DRY	No.2	SPF
290 - 292	2x6	DRY	No.2	SPF
292 - 294	2x6	DRY	No.2	SPF
294 - 296	2x6	DRY	No.2	SPF
296 - 298	2x6	DRY	No.2	SPF
298 - 300	2x6	DRY	No.2	SPF
300 - 302	2x6	DRY	No.2	SPF
302 - 304	2x6	DRY	No.2	SPF
304 - 306	2x6	DRY	No.2	SPF
306 - 308	2x6	DRY	No.2	SPF
308 - 310	2x6	DRY	No.2	SPF
310 - 312	2x6	DRY	No.2	SPF
312 - 314	2x6	DRY	No.2	SPF
314 - 316	2x6	DRY	No.2	SPF
316 - 318	2x6	DRY	No.2	SPF
318 - 320	2x6	DRY	No.2	SPF
320 - 322	2x6	DRY	No.2	SPF
322 - 324	2x6	DRY	No.2	SPF
324 - 326	2x6	DRY	No.2	SPF
326 - 328	2x6	DRY	No.2	SPF
328 - 330	2x6	DRY	No.2	SPF
330 - 332	2x6	DRY	No.2	SPF
332 - 334	2x6	DRY	No.2	SPF
334 - 336	2x6	DRY	No.2	SPF
336 - 338	2x6	DRY	No.2	SPF
338 - 340	2x6	DRY	No.2	SPF
340 - 342	2x6	DRY	No.2	SPF
342 - 344	2x6	DRY	No.2	SPF
344 - 346	2x6	DRY	No.2	SPF
346 - 348	2x6	DRY	No.2	SPF
348 - 350	2x6	DRY	No.2	SPF
350 - 352	2x6	DRY	No.2	SPF
352 - 354	2x6	DRY	No.2	SPF
354 - 356	2x6	DRY	No.2	SPF
356 - 358	2x6	DRY	No.2	SPF
358 - 360	2x6	DRY	No.2	SPF
360 - 362	2x6	DRY	No.2	SPF
362 - 364	2x6	DRY	No.2	SPF
364 - 366	2x6	DRY	No.2	SPF
366 - 368	2x6	DRY	No.2	SPF
368 - 370	2x6	DRY	No.2	SPF
370 - 372	2x6	DRY	No.2	SPF
372 - 374	2x6	DRY	No.2	SPF
374 - 376	2x6	DRY	No.2	SPF
376 - 378	2x6	DRY	No.2	SPF
378 - 380	2x6	DRY	No.2	SPF
380 - 382	2x6	DRY	No.2	SPF
382 - 384	2x6	DRY	No.2	SPF
384 - 386	2x6	DRY	No.2	SPF
386 - 388	2x6	DRY	No.2	SPF
388 - 390	2x6	DRY	No.2	SPF
390 - 392	2x6	DRY	No.2	SPF
392 - 394	2x6	DRY	No.2	SPF
394 - 396	2x6	DRY	No.2	SPF
396 - 398	2x6	DRY	No.2	SPF
398 - 400	2x6	DRY	No.2	SPF
400 - 402	2x6	DRY	No.2	SPF
402 - 404	2x6	DRY	No.2	SPF
404 - 406	2x6	DRY	No.2	SPF
406 - 408	2x6	DRY	No.2	SPF
408 - 410	2x6	DRY	No.2	SPF
410 - 412	2x6	DRY	No.2	SPF
412 - 414	2x6	DRY	No.2	SPF
414 - 416	2x6	DRY	No.2	SPF
416 - 418	2x6	DRY	No.2	SPF
418 - 420	2x6	DRY	No.2	SPF
420 - 422	2x6	DRY	No.2	SPF
422 - 424	2x6	DRY	No.2	SPF
424 - 426	2x6	DRY	No.2	SPF
426 - 428	2x6	DRY	No.2	SPF
428 - 430	2x6	DRY	No.2	SPF
430 - 432	2x6	DRY	No.2	SPF
432 - 434	2x6	DRY	No.2	SPF
434 - 436	2x6	DRY	No.2	SPF
436 - 438	2x6	DRY	No.2	SPF
438 - 440	2x6	DRY	No.2	SPF
440 - 442	2x6	DRY	No.2	SPF
442 - 444	2x6	DRY	No.2	SPF
444 - 446	2x6	DRY	No.2	SPF
446 - 448	2x6	DRY	No.2	SPF
448 - 450	2x6	DRY	No.2	SPF
450 - 452	2x6	DRY	No.2	SPF
452 - 454	2x6	DRY	No.2	SPF
454 - 456	2x6	DRY	No.2	SPF
456 - 458	2x6	DRY	No.2	SPF
458 - 460	2x6	DRY	No.2	SPF
460 - 462	2x6	DRY	No.2	SPF
462 - 464	2x6	DRY	No.2	SPF
464 - 466	2x6	DRY	No.2	SPF
466 - 468	2x6	DRY	No.2	SPF
468 - 470	2x6	DRY	No.2	SPF
470 - 472	2x6	DRY	No.2	SPF
472 - 474	2x6	DRY	No.2	SPF
474 - 476	2x6	DRY	No.2	SPF
476 - 478	2x6	DRY	No.2	SPF
478 - 480	2x6	DRY	No.2	SPF
480 - 482	2x6	DRY	No.2	SPF
482 - 484	2x6	DRY	No.2	SPF
484 - 486	2x6	DRY	No.2	SPF
486 - 488	2x6	DRY	No.2	SPF
488 - 490	2x6	DRY	No.2	SPF
490 - 492	2x6	DRY	No.2	SPF
492 - 494	2x6	DRY	No.2	SPF
494 - 496	2x6	DRY	No.2	SPF
496 - 498	2x6	DRY	No.2	SPF
498 - 500	2x6	DRY	No.2	SPF
ALL WEBS 2x3 DRY No.2 SPF				
EXCEPT				
DRY: SEASONED LUMBER.				

JOB NAME	TRUSS NAME	QUANTITY	PLY	JOB DESC.	DRWG NO.
NE0818-060	G02	1	1	GREENPARK-MINNISLAE HOMES-GRANDBROOKE 1 EL 1	

Version 8.210 S Mar 12 2018 MiTek Industries, Inc. Mon Aug 13 08:50:54 2018 Page 2
ID:w_6JogZnfv1q7BUYX2Ki0Uz3oDL-YgwwW2Fi3YQ1L9ANn_5LGShwkXxWhhe?WNlOn5yoKDf

TRUSS PLATE MANUFACTURER IS NOT
RESPONSIBLE FOR QUALITY CONTROL IN
THE TRUSS MANUFACTURING PLANT .

NAIL VALUES

PLATE	GRIP(DRY)	SHEAR	SECTION
	(PSI)	(PLI)	(PLI)
	MAX	MIN	MAX
MT20	618	354	1667
	822	2284	1656

PLATE PLACEMENT TOL. = 0.250 inches

PLATE ROTATION TOL. = 5.0 Deg.

JSI GRIP= 0.90 (3) (INPUT = 0.90)
JSI METAL= 0.65 (14) (INPUT = 1.00)




READ ALL NOTES ON THIS PAGE AND ON
ENGINEERING NOTE PAGE ENP-1. THIS
NOTE PAGE IS AN INTEGRAL PART OF
THIS DRAWING AS IT CONTAINS
SPECIFICATIONS AND CRITERIA USED IN
THE DESIGN OF THIS COMPONENT.



JOB NAME	TRUSS NAME	QUANTITY	PLY	JOB DESC.	DRWG NO.
NE0818-060	G03	1	1	GREENPARK-MINNISLAE HOMES-GRANDBROOKE 1 EL 1	

Version 8.210 S Mar 12 2018 MiTek Industries, Inc. Mon Aug 13 08:50:54 2018 Page 1
ID:w_6JogZnfv1q7BUYX2Ki0Uz3oDL-YgwwW2F3YQ1L9ANn_5LGSh08X_FhoW?WNIOn5yoKDF



Scale = 1:22.6

TOTAL WEIGHT = 24 lb

LUMBER				DIMENSIONS, SUPPORTS AND LOADINGS SPECIFIED BY FABRICATOR TO BE VERIFIED BY BUILDING DESIGNER				DESIGN CRITERIA			
N. L. G. A. RULES	CHORDS	SIZE	LUMBER	DESCR.	SPF	FACTORED	MAXIMUM FACTORED	INPUT	REQD	SPECIFIED LOADS:	
4 - 1	2x4	DRY	No.2	SPF		GROSS REACTION	GROSS REACTION	BRG	BRG	TOP CH. LL = 23.3 PSF	
1 - 2	2x4	DRY	No.2	SPF		VERT	HORZ	DOWN	HORZ	DL = 3.0 PSF	
3 - 2	2x4	DRY	No.2	SPF		4	791 0	791 0	0 0	BOT CH. LL = 0.0 PSF	
4 - 3	2x8	DRY	No.2	SPF		3	791 0	791 0	0 0	DL = 7.0 PSF	
ALL WEBS	2x3	DRY	No.2	SPF						TOTAL LOAD = 33.3 PSF	
DRY: SEASONED LUMBER.											

PLATES (table is in inches)

JT	TYPE	PLATES	W	LEN	Y	X
1	TMVW-t	MT20	3.0	5.0	1.50	2.00
2	TMV+p	MT20	2.0	4.0		
3	BMVW1-t	MT20	4.0	4.0		
4	BMV1+p	MT20	2.0	4.0		

UNFACTORED REACTIONS

JT	1ST LCASE	MAX/MIN. COMPONENT REACTIONS						
4	COMBINED	SNOW	LIVE	PERM.LIVE	WIND	DEAD	SOIL	
4	555	388 / 0	0 / 0	0 / 0	0 / 0	167 / 0	0 / 0	
3	555	388 / 0	0 / 0	0 / 0	0 / 0	167 / 0	0 / 0	

BEARING MATERIAL TO BE SPF NO.2 OR BETTER AT JOINT(S) 4

BRACING

TOP CHORD TO BE SHEATHED OR MAX. PURLIN SPACING = 10.00 FT.
MAX. UNBRACED BOTTOM CHORD LENGTH = 10.00 FT OR RIGID CEILING DIRECTLY APPLIED.

ALL PITCH BREAKS AND PERIMETER CORNER JOINTS MUST BE Laterally RESTRAINED.

LOADING

TOTAL LOAD CASES: (4)

CHORDS				WEBS			
MEMB.	FORCE	FACTORED		MEMB.	FORCE	FACTORED	
	(LBS)	VERT. LOAD	LC1 MAX		(LBS)	MAX. FACTORED	
		(PLF)	CSI (LC)			MAX. FACTORED	
FR-TO		FROM TO		FR-TO			
4-1	-175 / 0	0.0	0.0 0.02 (1)	1-3	0 / 0	0.00 (1)	
1-2	0 / 0	-77.4	-77.4 0.30 (1)				
3-2	-175 / 0	0.0	0.0 0.04 (1)				
4-3	0 / 0	-272.4	-272.4 0.34 (1)				

GIRDER TYPE: CStdGirder

START DISTANCE = 0-0
START SPAN CARRIED = 13-2-8
END DISTANCE = 4-6-4
END SPAN CARRIED = 13-2-8
END WALL WIDTH = 5-8
APPLIED TO FRONT SIDE OF BOTTOM CHORD.
- ADDTL LOADS BASED ON 55 % OF GSL.

THIS TRUSS IS DESIGNED FOR RESIDENTIAL OR SMALL BUILDING REQUIREMENTS OF PART 9, NBCC 2010

THIS DESIGN COMPLIES WITH:
- PART 9 OF OBC 2012, CBC 2012, ABC 2014
- CSA 086-09
- TPIC 2011

(55 % OF 27.2 P.S.F. G.S.L. PLUS 8.4 P.S.F. RAIN LOAD) EQUALS 23.3 P.S.F. SPECIFIED ROOF LIVE LOAD

ALLOWABLE DEFL.(LL)= L/360 (0.19")
CALCULATED VERT. DEFL.(LL) = L/999 (0.02")
ALLOWABLE DEFL.(TL)= L/360 (0.19")
CALCULATED VERT. DEFL.(TL) = L/999 (0.03")

CSI: TC=0.30/1.00 (1-2-1), BC=0.34/1.00 (3-4-1), WB=0.00/1.00 (1-3-1), SSI=0.36/1.00 (3-4-1)

DOL LUMBER=1.00 NAIL=1.00 LS BEND=1.00
COMP=1.00 SHEAR=1.00 TENS= 1.00

COMPANION LIVE LOAD FACTOR = 0.50

TRUSS PLATE MANUFACTURER IS NOT RESPONSIBLE FOR QUALITY CONTROL IN THE TRUSS MANUFACTURING PLANT.

NAIL VALUES
PLATE GRIP(DRY) SHEAR SECTION
(PSI) (PLI) (PLI)
MAX MIN MAX MIN MAX MIN
MT20 618 354 1667 822 2284 1656

PLATE PLACEMENT TOL. = 0.250 inches

PLATE ROTATION TOL. = 5.0 Deg.

CONTINUED ON PAGE 2



READ ALL NOTES ON THIS PAGE AND ON ENGINEERING NOTE PAGE ENP-1. THIS NOTE PAGE IS AN INTEGRAL PART OF THIS DRAWING AS IT CONTAINS SPECIFICATIONS AND CRITERIA USED IN THE DESIGN OF THIS COMPONENT.



JOB NAME	TRUSS NAME	QUANTITY	PLY	JOB DESC.	GREENPARK-MINNISLAE HOMES-GRANDBROOKE 1 EL 1	DRWG NO.
NE0818-060	G03	1	1	TRUSS DESC.		

Version 8.210 S Mar 12 2018 MiTek Industries, Inc. Mon Aug 13 08:50:54 2018 Page 2
ID:w_6JogZnfv1q7BUYX2Ki0Uz3oDL-YgwwW2Fi3YQ1L9ANn_5LGSh08X_FhoW?WNIOn5yoKDF

JSI GRIP= 0.15 (1) (INPUT = 0.90)
JSI METAL= 0.04 (2) (INPUT = 1.00)




READ ALL NOTES ON THIS PAGE AND ON
ENGINEERING NOTE PAGE ENP-1. THIS
NOTE PAGE IS AN INTEGRAL PART OF
THIS DRAWING AS IT CONTAINS
SPECIFICATIONS AND CRITERIA USED IN
THE DESIGN OF THIS COMPONENT.



JOB NAME	TRUSS NAME	QUANTITY	PLY	JOB DESC.	DRWG NO.
NE0818-060	J01	2	1	GREENPARK-MINNISLAE HOMES-GRANDBROOKE 1 EL 1	
TRUSS DESC.					

Version 8.210 S Mar 12 2018 MiTek Industries, Inc. Mon Aug 13 08:50:55 2018 Page 1
ID:w_6JogZnfv1q7BUYX2Ki0Uz3oDL-0sTHjOFKqsYuzJlaLhcagpDCNxBpQFm8l11xJXyoKD



TOTAL WEIGHT = 2 X 10 = 21 lb

LUMBER

N. L. G. A. RULES

CHORDS	SIZE	LUMBER
5 - 2	2x4	DRY No.2
1 - 3	2x4	DRY No.2
5 - 4	2x4	DRY No.2

DRY: SEASONED LUMBER.

DESCR.
SPF
SPF
SPF

DIMENSIONS, SUPPORTS AND LOADINGS SPECIFIED BY FABRICATOR TO BE VERIFIED BY BUILDING DESIGNER

BEARINGS

JT	FACTORED GROSS REACTION		MAXIMUM FACTORED GROSS REACTION		INPUT BRG	REQRD BRG
	VERT	HORZ	DOWN	HORZ	UPLIFT IN-SX	IN-SX
5	314	0	314	0	0	5-8
3	114	0	114	0	0	1-8
4	16	0	18	0	0	1-8

SEE MITEK STANDARD DETAIL B37579H FOR CONNECTION TO JOINT(S) 3, 4

UNFACTORED REACTIONS

JT	1ST LCASE	MAX./MIN. COMPONENT REACTIONS					
	COMBINED	SNOW	LIVE	PERM.LIVE	WIND	DEAD	SOIL
5	216	177 / 0	0 / 0	0 / 0	0 / 0	38 / 0	0 / 0
3	77	68 / 0	0 / 0	0 / 0	0 / 0	9 / 0	0 / 0
4	13	0 / 0	0 / 0	0 / 0	0 / 0	13 / 0	0 / 0

BEARING MATERIAL TO BE SPF NO.2 OR BETTER AT JOINT(S) 5

BRACING

TOP CHORD TO BE SHEATHED OR MAX. PURLIN SPACING = 6.25 FT.
MAX. UNBRACED BOTTOM CHORD LENGTH = 10.00 FT OR RIGID CEILING DIRECTLY APPLIED.

ALL PITCH BREAKS AND PERIMETER CORNER JOINTS MUST BE Laterally RESTRAINED.

LOADING

TOTAL LOAD CASES: (5)

CHORDS				WEBS			
MEMB.	MAX. FACTORED FORCE (LBS)	FACTORED VERT. LOAD (PLF)	LC1 MAX CSI (LC)	MAX. UNBRAC LENGTH	MEMB.	MAX. FACTORED FORCE (LBS)	MAX CSI (LC)
FR-TO		FROM	TO		FR-TO		
5-2	-295 / 0	0.0	0.0	0.01 (4)	7.81		
1-2	0 / 27	-77.4	-77.4	0.10 (1)	10.00		
2-3	-19 / 0	-77.4	-77.4	0.20 (1)	6.25		
5-4	0 / 0	-17.5	-17.5	0.02 (4)	10.00		

CANTILEVER ANALYSIS HAS BEEN CONSIDERED IN THIS DESIGN

DESIGN CRITERIA

SPECIFIED LOADS:

TOP CH.	LL =	23.3	PSF
	DL =	3.0	PSF
BOT CH.	LL =	0.0	PSF
	DL =	7.0	PSF
TOTAL LOAD	=	33.3	PSF

SPACING = 24.0 IN. C/C

THIS TRUSS IS DESIGNED FOR RESIDENTIAL OR SMALL BUILDING REQUIREMENTS OF PART 9, NBCC 2010

THIS DESIGN COMPLIES WITH:
- PART 9 OF OBC 2012, BCBC 2012, ABC 2014
- CSA 086-09
- TPIC 2011

DESIGN ASSUMPTIONS

- OVERHANG NOT TO BE ALTERED OR CUT OFF.

(55% OF 27.2 P.S.F. G.S.L. PLUS 8.4 P.S.F. RAIN LOAD) EQUALS 23.3 P.S.F. SPECIFIED ROOF LIVE LOAD

ALLOWABLE DEFL.(LL)= L/360 (0.19")
CALCULATED VERT. DEFL.(LL)= L/999 (0.00")
ALLOWABLE DEFL.(TL)= L/360 (0.19")
CALCULATED VERT. DEFL.(TL)= L/999 (0.00")

CSI: TC=0.20/1.00 (2-3:1), BC=0.02/1.00 (4-5:4), WB=0.00/1.00 (n/a:0), SSI=0.13/1.00 (2-3:1)

DOL LUMBER=1.00 NAIL=1.00 LS BEND=1.10
COMP=1.10 SHEAR=1.10 TENS=1.10

COMPANION LIVE LOAD FACTOR = 0.50

TRUSS PLATE MANUFACTURER IS NOT RESPONSIBLE FOR QUALITY CONTROL IN THE TRUSS MANUFACTURING PLANT.

NAIL VALUES

PLATE	GRIP(DRY)	SHEAR (PSI)	SECTION (PLI)
MT20	618	354	1667
	822	2284	1656

PLATE PLACEMENT TOL. = 0.250 inches


PLATE ROTATION TOL. = 5.0 Deg.


JSI GRIP= 0.18 (2) (INPUT = 0.90)
JSI METAL= 0.07 (2) (INPUT = 1.00)



READ ALL NOTES ON THIS PAGE AND ON ENGINEERING NOTE PAGE ENP-1. THIS NOTE PAGE IS AN INTEGRAL PART OF THIS DRAWING AS IT CONTAINS SPECIFICATIONS AND CRITERIA USED IN THE DESIGN OF THIS COMPONENT.




KOTT



TOTAL WEIGHT = $2 \times 15 = 30$ lb

DRY-SEASONED LUMBER.

[illegible]

BEARINGS

SEE MITEK STANDARD DETAIL B37579H FOR CONNECTION TO JOINT(S) 3, 4

1ST LCASE MAX/JMIN. COMPONENT REACTIONS

BEARING MATERIAL TO BE SPF NO.2 OR BETTER AT JOINT(S) 5, 3

TOP CHORD TO BE SHEATHED OR MAX. PURLIN SPACING = 6.25 FT.
MAX. UNBRACED BOTTOM CHORD LENGTH = 10.00 FT OR RIGID CEILING DIRECTLY
APPLIED.

ALL PITCH BREAKS AND PERIMETER CORNER JOINTS MUST BE LATERALLY RESTRAINED.

TOTAL LOAD CASES: (4)

WERS

SPECIFIED LOADS:			
TOP CH.	LL =	23.3	PSF
	DL =	3.0	PSF
BOT CH.	LL =	0.0	PSF
	DL =	7.0	PSF
TOTAL LOAD		= 33.3	PSF

SPACING = 24.0 IN. C/C

THIS TRUSS IS DESIGNED FOR RESIDENTIAL
OR SMALL BUILDING REQUIREMENTS OF
PART 9, NBCC 2010

THIS DESIGN COMPLIES WITH:
- PART 9 OF OBC 2012 , BCBC 2012 , ABC 2014
- CSA 086-09
- TPIG 2011

-OVERHANG NOT TO BE ALTERED OR CUT OFF

(55 % OF 27.2 P.S.F. G.S.L. PLUS 8.4 P.S.F. RAIN LOAD) EQUALS 23.3 P.S.F. SPECIFIED ROOF LIVE LOAD

ALLOWABLE DEFL.(LL)= $L/360$ (0.20")
 CALCULATED VERT. DEFL.(LL) = $L/999$ (0.00")
 ALLOWABLE DEFL.(TL)= $L/360$ (0.20")
 CALCULATED VERT. DEFL.(TL) = $L/999$ (0.03")

CSI: TC=0.20/1.00 (2-3:1), BC=0.13/1.00 (4-5:4),
WB=0.00/1.00 (n/a:0), SSI=0.13/1.00 (2-3:1)

DOL LUMBER=1.00 NAIL=1.00 LS BEND=1.10
COMP=1.10 SHEAR=1.10 TENS= 1.10

COMPANION LIVE LOAD FACTOR = 0.50


TRUSS PLATE MANUFACTURER IS NOT RESPONSIBLE FOR QUALITY CONTROL IN THE TRUSS MANUFACTURING PLANT.

PLATE	GRIP(DRY)		SHEAR		SECTION	
	(PSI)		(PLI)		(PLI)	
	MAX	MIN	MAX	MIN	MAX	MIN
MT20	618	354	1667	822	2284	1656

PLATE PLACEMENT TOL. = 0.250 inches


PLATE ROTATION TOL. = 5.0 Deg.

JSI GRIP= 0.18 (2) (INPUT = 0.90)
JSI METAL= 0.07 (2) (INPUT = 1.00)



JOB NAME	TRUSS NAME	QUANTITY	PLY	JOB DESC.	GREENPARK-MINNISLAE HOMES-GRANDBROOKE 1 EL 1	DRWG NO.
NE0818-060	J05	8	1	TRUSS DESC.		

Version 8.210 6 Mar 12 2018 MiTek Industries, Inc. Mon Aug 13 08:50:56 2018 Page 1
ID:w_6JogZnf1q7BUYX2Ki0Uz3oDL-U21fxkGybAg1bTJmvp7pLtmJrLj59i0H_hnVs_yoKDD



Scale = 1:26.7

TOTAL WEIGHT = 8 X 18 = 141 lb [M]

LUMBER

N. L. G. A. RULES	CHORDS	SIZE	LUMBER	DESCR.
5 - 2	2x4	DRY	No.2	SPF
1 - 3	2x4	DRY	No.2	SPF
5 - 4	2x4	DRY	No.2	SPF

DRY: SEASONED LUMBER.

PLATES (table is in inches)

JT	TYPE	PLATES	W	LEN	Y	X
2	TMV+p	MT20	2.0	4.0		
5	BMV1+p	MT20	2.0	4.0		

DIMENSIONS, SUPPORTS AND LOADINGS SPECIFIED BY FABRICATOR TO BE VERIFIED BY BUILDING DESIGNER

BEARINGS							
JT	FACTORED GROSS REACTION		MAXIMUM FACTORED GROSS REACTION		INPUT BRG	REQRD BRG	
	VERT	HORZ	DOWN	HORZ	UPLIFT IN-SX	IN-SX	
5	457	0	457	0	0	5-8	5-8
3	174	0	174	0	0	1-8	1-8
4	44	0	49	0	0	1-8	1-8

SEE MITEK STANDARD DETAIL B37579H FOR CONNECTION TO JOINT(S) 3, 4

UNFACTORED REACTIONS

JT	1ST LCASE		MAX/MIN. COMPONENT REACTIONS		WIND	DEAD	SOIL
	COMBINED	SNOW	LIVE	PERM. LIVE			
5	318	238 / 0	0 / 0	0 / 0	0 / 0	80 / 0	0 / 0
3	118	105 / 0	0 / 0	0 / 0	0 / 0	14 / 0	0 / 0
4	35	0 / 0	0 / 0	0 / 0	0 / 0	35 / 0	0 / 0

BEARING MATERIAL TO BE SPF NO.2 OR BETTER AT JOINT(S) 5

BRACING

TOP CHORD TO BE SHEATHED OR MAX. PURLIN SPACING = 6.25 FT.
MAX. UNBRACED BOTTOM CHORD LENGTH = 10.00 FT OR RIGID CEILING DIRECTLY APPLIED.

ALL PITCH BREAKS AND PERIMETER CORNER JOINTS MUST BE Laterally RESTRAINED.

LOADING

TOTAL LOAD CASES: (4)

MEMB.	CHORDS		FACTORED		WEBS		FACTORED	
	MAX. FORCE (LBS)	VERT. LOAD (PLF)	LC1 MAX (LC)	MAX. UNBRAC LENGTH	MEMB. FORCE (LBS)	MAX. UNBRAC LENGTH	MAX. FORCE (LBS)	MAX. UNBRAC LENGTH
FR-TO		FROM TO						
5-2	-396 / 0	0.0	0.0	0.12 (4)	7.81			
1-2	0 / 27	-77.4	-77.4	0.10 (1)	10.00			
2-3	-29 / 0	-77.4	-77.4	0.47 (1)	6.25			
5-4	0 / 0	-17.5	-17.5	0.13 (4)	10.00			

DESIGN CRITERIA

SPECIFIED LOADS:

TOP CH.	LL =	23.3	PSF
	DL =	3.0	PSF
BOT CH.	LL =	0.0	PSF
	DL =	7.0	PSF
TOTAL LOAD	=	33.3	PSF

SPACING = 24.0 IN. C/C

THIS TRUSS IS DESIGNED FOR RESIDENTIAL OR SMALL BUILDING REQUIREMENTS OF PART 9, NBCC 2010

THIS DESIGN COMPLIES WITH:
- PART 9 OF OBC 2012, BCBC 2012, ABC 2014
- CSA 086-09
- TPIC 2011

DESIGN ASSUMPTIONS

-OVERHANG NOT TO BE ALTERED OR CUT OFF.

(55 % OF 27.2 P.S.F. G.S.L. PLUS 8.4 P.S.F. RAIN LOAD) EQUALS 23.3 P.S.F. SPECIFIED ROOF LIVE LOAD

ALLOWABLE DEFL.(LL)= L/360 (0.20")
CALCULATED VERT. DEFL.(LL)= L/999 (0.00")
ALLOWABLE DEFL.(TL)= L/360 (0.20")
CALCULATED VERT. DEFL.(TL)= L/999 (0.03")

CSI: TC=0.47/1.00 (2-3:1), BC=0.13/1.00 (4-5:4), WB=0.00/1.00 (n/a:0), SSI=0.20/1.00 (2-3:1)

DOL LUMBER=1.00 NAIL=1.00 LS BEND=1.10 COMP=1.10 SHEAR=1.10 TENS= 1.10

COMPANION LIVE LOAD FACTOR = 0.50

TRUSS PLATE MANUFACTURER IS NOT RESPONSIBLE FOR QUALITY CONTROL IN THE TRUSS MANUFACTURING PLANT.

NAIL VALUES

PLATE	GRIP(DRY)	SHEAR	SECTION
	(PSI)	(PLI)	(PLI)
MT20	618	354	1667
	822	2284	1656

PLATE PLACEMENT TOL. = 0.250 inches

PLATE ROTATION TOL. = 5.0 Deg.

JSI GRIP= 0.24 (2) (INPUT = 0.90)
JSI METAL= 0.09 (2) (INPUT = 1.00)




READ ALL NOTES ON THIS PAGE AND ON ENGINEERING NOTE PAGE ENP-1. THIS NOTE PAGE IS AN INTEGRAL PART OF THIS DRAWING AS IT CONTAINS SPECIFICATIONS AND CRITERIA USED IN THE DESIGN OF THIS COMPONENT.



JOB NAME	TRUSS NAME	QUANTITY	PLY	JOB DESC.	GREENPARK-MINNISLAKE HOMES-GRANDBROOKE 1 EL 1	DRWG NO.
NE0818-060	J06	5	1	TRUSS DESC.		

Version 8.210 5 Mar 12 2018 MiTek Industries, Inc. Mon Aug 13 08:50:57 2018 Page 1
ID:w_6JogZnfv1q7BUYX2Ki0Uz3oDL-zFb184HbMTocCduyS6f2u5IXpk38u9FRDLW2OQyoKDC



Scale = 1:22.6

TOTAL WEIGHT = 5 X 14 = 70 lb

LUMBER

N. L. G. A. RULES	CHORDS	SIZE	LUMBER	DESCR.
5 - 2	2x4	DRY	No.2	SPF
1 - 3	2x4	DRY	No.2	SPF
5 - 4	2x4	DRY	No.2	SPF

DRY: SEASONED LUMBER.

PLATES (table is in inches)

JT	TYPE	PLATES	W	LEN	Y	X
2	TMV+p	MT20	2.0	4.0		
5	BMV1+p	MT20	2.0	4.0		

DIMENSIONS, SUPPORTS AND LOADINGS SPECIFIED BY FABRICATOR TO BE VERIFIED BY BUILDING DESIGNER

BEARINGS							
JT	FACTORED GROSS REACTION		MAXIMUM FACTORED GROSS REACTION			INPUT BRG	REQRD BRG
	VERT	HORZ	DOWN	HORZ	UPLIFT	IN-SX	IN-SX
5	370	0	370	0	0	5-8	5-8
3	131	0	131	0	0	1-8	1-8
4	34	0	38	0	0	1-8	1-8

SEE MITEK STANDARD DETAIL B37579H FOR CONNECTION TO JOINT(S) 3, 4

UNFACTORED REACTIONS

JT	1ST LCASE	MAX./MIN. COMPONENT REACTIONS					
	COMBINED	SNOW	LIVE	PERM.LIVE	WIND	DEAD	SOIL
5	257	195 / 0	0 / 0	0 / 0	0 / 0	62 / 0	0 / 0
3	89	79 / 0	0 / 0	0 / 0	0 / 0	10 / 0	0 / 0
4	27	0 / 0	0 / 0	0 / 0	0 / 0	27 / 0	0 / 0

BEARING MATERIAL TO BE SPF NO.2 OR BETTER AT JOINT(S) 5

BRACING

TOP CHORD TO BE SHEATHED OR MAX. PURLIN SPACING = 6.25 FT.
MAX. UNBRACED BOTTOM CHORD LENGTH = 10.00 FT OR RIGID CEILING DIRECTLY APPLIED.

ALL PITCH BREAKS AND PERIMETER CORNER JOINTS MUST BE Laterally RESTRAINED.

LOADING

TOTAL LOAD CASES: (4)

CHORDS					WEBS				
MEMB.	MAX. FACTORED FORCE (LBS)	FACTORED VERT. LOAD (PLF)	LOAD LC1	MAX CSI (LC)	MAX. UNBRACED LENGTH	MEMB.	MAX. FACTORED FORCE (LBS)	MAX CSI (LC)	
FR-TO		FROM	TO			FR-TO			
5-2	-324 / 0	0.0	0.0	0.06 (4)	7.81				
1-2	0 / 27	-77.4	-77.4	0.10 (1)	10.00				
2-3	-22 / 0	-77.4	-77.4	0.27 (1)	6.25				
5-4	0 / 0	-17.5	-17.5	0.08 (4)	10.00				

DESIGN CRITERIA

SPECIFIED LOADS:

TOP CH.	LL =	23.3	PSF
	DL =	3.0	PSF
BOT CH.	LL =	0.0	PSF
	DL =	7.0	PSF
TOTAL LOAD	=	33.3	PSF

SPACING = 24.0 IN. C/C

THIS TRUSS IS DESIGNED FOR RESIDENTIAL OR SMALL BUILDING REQUIREMENTS OF PART 9, NBCC 2010

THIS DESIGN COMPLIES WITH:
- PART 9 OF OBC 2012, BCBC 2012, ABC 2014
- CSA 086-09
- TPIC 2011

DESIGN ASSUMPTIONS

-OVERHANG NOT TO BE ALTERED OR CUT OFF.

(55 % OF 27.2 P.S.F. G.S.L. PLUS 8.4 P.S.F. RAIN LOAD) EQUALS 23.3 P.S.F. SPECIFIED ROOF LIVE LOAD

ALLOWABLE DEFL.(LL)= L/360 (0.19")
CALCULATED VERT. DEFL.(LL) = L/999 (0.00")
ALLOWABLE DEFL.(TL)= L/360 (0.19")
CALCULATED VERT. DEFL.(TL) = L/999 (0.01")

CSI: TC=0.27/1.00 (2-3:1), BC=0.08/1.00 (4-5:4), WB=0.00/1.00 (n/a:0), SSI=0.15/1.00 (2-3:1)

DOL LUMBER=1.00 NAIL=1.00 L.S BEND=1.10
COMP=1.10 SHEAR=1.10 TENS= 1.10

COMPANION LIVE LOAD FACTOR = 0.50

TRUSS PLATE MANUFACTURER IS NOT RESPONSIBLE FOR QUALITY CONTROL IN THE TRUSS MANUFACTURING PLANT.

NAIL VALUES

PLATE	GRIP(DRY)	SHEAR	SECTION
	(FSI)	(PLI)	(PLI)
MT20	618	354	1667
	822	2284	1656

PLATE PLACEMENT TOL. = 0.250 inches


PLATE ROTATION TOL. = 5.0 Deg.

JSI GRIP= 0.20 (2) (INPUT = 0.90)
JSI METAL= 0.08 (2) (INPUT = 1.00)



READ ALL NOTES ON THIS PAGE AND ON ENGINEERING NOTE PAGE ENP-1. THIS NOTE PAGE IS AN INTEGRAL PART OF THIS DRAWING AS IT CONTAINS SPECIFICATIONS AND CRITERIA USED IN THE DESIGN OF THIS COMPONENT.





LUMBER					DIMENSIONS, SUPPORTS AND LOADINGS SPECIFIED BY FABRICATOR TO BE VERIFIED BY BUILDING DESIGNER										DESIGN CRITERIA									
N. L. G. A. RULES																								
CHORDS					LUMBER					DESCR.														
1 - 4					2x4					DRY					No.2					SPF				
4 - 6					2x4					DRY					No.2					SPF				
6 - 9					2x4					DRY					No.2					SPF				
15 - 2					2x4					DRY					No.2					SPF				
10 - 8					2x4					DRY					No.2					SPF				
15 - 12					2x4					DRY					No.2					SPF				
12 - 10					2x4					DRY					No.2					SPF				
ALL WEBS EXCEPT					2x3					DRY					No.2					SPF				
DRY: SEASONED LUMBER.																								
PLATES (table is in inches)																								




READ ALL NOTES ON THIS PAGE AND ON ENGINEERING NOTE PAGE ENP-1. THIS NOTE PAGE IS AN INTEGRAL PART OF THIS DRAWING AS IT CONTAINS SPECIFICATIONS AND CRITERIA USED IN THE DESIGN OF THIS COMPONENT.



JOB NAME	TRUSS NAME	QUANTITY	PLY	JOB DESC.	DRWG NO.
NE0818-060	T02	1	1	GREENPARK-MINNISLAE HOMES-GRANDBROOKE 1 EL 1	

Version 8.210 S Mar 12 2018 MiTek Industries, Inc. Mon Aug 13 08:50:58 2018 Page 1
ID:w_6JogZnf1q7BUYX2Ki0Uz3oDL-RR9PMPID7nxTqmT80pAHRInT8NbdYvar?GcwsyoKDB



LUMBER N. L. G. A. RULES **CHORDS** **SIZE** **LUMBER** **DESCR.** **BEARINGS** **FACTORED** **MAXIMUM FACTORED** **INPUT** **REQRD** **DESIGN CRITERIA** **SPECIFIED LOADS:** **TOP CH.** **LL = 23.3 PSF** **BOT CH.** **LL = 0.0 PSF** **DL = 7.0 PSF** **TOTAL LOAD = 33.3 PSF** **SPACING = 24.0 IN. C/C** **LOADING IN FLAT SECTION BASED ON A SLOPE OF 2.00/12 MINIMUM** **THIS TRUSS IS DESIGNED FOR RESIDENTIAL OR SMALL BUILDING REQUIREMENTS OF PART 9, NBCC 2010** **THIS DESIGN COMPLIES WITH:** **- PART 9 OF OBC 2012, BCBC 2012, ABC 2014 - CSA 086-09 - TPIC 2011** **(55% OF 27.2 P.S.F. G.S.L. PLUS 8.4 P.S.F. RAIN LOAD) EQUALS 23.3 P.S.F. SPECIFIED ROOF LIVE LOAD** **ALLOWABLE DEFL.(LL) = L/360 (0.83")** **CALCULATED VERT. DEFL.(LL) = L/999 (0.05")** **ALLOWABLE DEFL.(TL) = L/360 (0.83")** **CALCULATED VERT. DEFL.(TL) = L/999 (0.09")** **CSI: TC=0.27/1.00 (2-3:1), BC=0.25/1.00 (10-12:1), WB=0.29/1.00 (2-14:1), SSI=0.16/1.00 (6-7:1)** **DOL LUMBER=1.00 NAIL=1.00 L.S BEND=1.10 COMP=1.10 SHEAR=1.10 TENS=1.10** **COMPANION LIVE LOAD FACTOR = 0.50** **TRUSS PLATE MANUFACTURER IS NOT RESPONSIBLE FOR QUALITY CONTROL IN THE TRUSS MANUFACTURING PLANT.** **NAIL VALUES** **PLATE GRIP(DRY) SHEAR SECTION (PSI) (PLI) (PLI)** **MAX MIN MAX MIN MAX MIN** **MT20 618 354 1667 822 2284 1656** **PLATE PLACEMENT TOL. = 0.250 inches** **PLATE ROTATION TOL. = 5.0 Deg.** **JSI GRIP= 0.89 (14) (INPUT = 0.90)** **JSI METAL= 0.48 (14) (INPUT = 1.00)**

CHORDS	SIZE	LUMBER	DESCR.
1 - 4	2x4	DRY	No.2
4 - 5	2x4	DRY	No.2
5 - 8	2x4	DRY	No.2
15 - 2	2x4	DRY	No.2
9 - 7	2x4	DRY	No.2
15 - 11	2x4	DRY	No.2
11 - 9	2x4	DRY	No.2
ALL WEBS	2x3	DRY	No.2
EXCEPT			

DRY: SEASONED LUMBER.

PLATES (table is in inches)

JT	TYPE	PLATES	W	LEN	Y	X
2	TMVW-I	MT20	4.0	6.0	2.00	3.00
3	TMVW-I	MT20	3.0	4.0	1.50	1.75
4	TTWW-m	MT20	4.0	6.0	1.75	2.25
5	TTWW-p	MT20	3.0	4.0	2.50	1.50
6	TMVW-I	MT20	3.0	4.0	1.50	1.75
7	TMVW-I	MT20	4.0	6.0	2.00	3.00
9	BMV1-p	MT20	2.0	4.0		
10	BMVW-I	MT20	4.0	4.0	1.75	1.50
11	BS-I	MT20	3.0	6.0		
12	BMVWW-I	MT20	3.0	6.0		
13	BMVW-I	MT20	3.0	4.0		
14	BMVW-I	MT20	4.0	4.0	1.75	1.50
15	BMV1-p	MT20	2.0	4.0		

DIMENSIONS, SUPPORTS AND LOADINGS SPECIFIED BY FABRICATOR TO BE VERIFIED BY BUILDING DESIGNER

JT	VERT	HORZ	DOWN	HORZ	UPLIFT	IN-SX	IN-SX
15	1291	0	1291	0	0	5-8	5-8
9	1291	0	1291	0	0	5-8	5-8

UNFACTORED REACTIONS

JT	COMBINED	SNOW	LIVE	PERM.LIVE	WIND	DEAD	SOIL
15	904	646 / 0	0 / 0	0 / 0	0 / 0	258 / 0	0 / 0
9	904	646 / 0	0 / 0	0 / 0	0 / 0	258 / 0	0 / 0

BEARING MATERIAL TO BE SPF NO.2 OR BETTER AT JOINT(S) 15, 9

BRACING

TOP CHORD TO BE SHEATHED OR MAX. PURLIN SPACING = 5.13 FT.
MAX. UNBRACED BOTTOM CHORD LENGTH = 10.00 FT OR RIGID CEILING DIRECTLY APPLIED.

ALL PITCH BREAKS AND PERIMETER CORNER JOINTS MUST BE Laterally RESTRAINED.

LOADING

TOTAL LOAD CASES: (4)

MEMB.	MAX. FACTORED FORCE (LBS)	FACTORED VERT. LOAD (PLF)	MAX. LOAD LC1 (LC)	MAX. UNBRACED LENGTH (FT)	MEMB.	MAX. FACTORED FORCE (LBS)	MAX. UNBRACED LENGTH (FT)
FR-TO					FR-TO		
1-2	0 / 27	-77.4	-77.4 0.10 (1)	10.00	14-3	-150 / 39	0.04 (1)
2-3	-1466 / 0	-77.4	-77.4 0.27 (1)	5.13	3-13	-307 / 0	0.22 (1)
3-4	-1234 / 0	-77.4	-77.4 0.26 (1)	5.49	13-4	0 / 275	0.06 (1)
4-5	-1049 / 0	-77.4	-77.4 0.26 (1)	5.83	4-12	0 / 0	0.00 (1)
5-6	-1235 / 0	-77.4	-77.4 0.26 (1)	5.49	12-5	0 / 276	0.06 (1)
6-7	-1468 / 0	-77.4	-77.4 0.27 (1)	5.13	12-6	-306 / 0	0.22 (1)
7-8	0 / 27	-77.4	-77.4 0.10 (1)	10.00	10-6	-151 / 39	0.04 (1)
15-2	-1253 / 0	0.0	0.0 0.13 (1)	7.18	2-14	0 / 1309	0.29 (1)
9-7	-1253 / 0	0.0	0.0 0.13 (1)	7.19	10-7	0 / 1308	0.29 (1)
15-14	0 / 0	-17.5	-17.5 0.10 (4)	10.00			
14-13	0 / 1285	-17.5	-17.5 0.25 (1)	10.00			
13-12	0 / 1049	-17.5	-17.5 0.22 (1)	10.00			
12-11	0 / 1285	-17.5	-17.5 0.25 (1)	10.00			
11-10	0 / 1285	-17.5	-17.5 0.25 (1)	10.00			
10-9	0 / 0	-17.5	-17.5 0.10 (4)	10.00			




READ ALL NOTES ON THIS PAGE AND ON ENGINEERING NOTE PAGE ENP-1. THIS NOTE PAGE IS AN INTEGRAL PART OF THIS DRAWING AS IT CONTAINS SPECIFICATIONS AND CRITERIA USED IN THE DESIGN OF THIS COMPONENT.



JOB NAME	TRUSS NAME	QUANTITY	PLY	JOB DESC.	GREENPARK-MINNISLAE HOMES-GRANDBROOKE 1 EL 1	DRWG NO.
NE0818-060	T03	1	1	TRUSS DESC.		

Version 8.210 S Mar 12 2018 MiTek Industries, Inc. Mon Aug 13 08:50:59 2018 Page 1
ID:w_6JogZnf1q7BUYX2Ki0Uz3oDL-vdjoZilru53KSw2LaXhWzWOr8YiHMxdkgf?9SJyoKDA



LUMBER

N. L. G. A. RULES	CHORDS	SIZE	LUMBER	DESCR.
1 - 4	2x4	DRY	No.2	SPF
4 - 5	2x4	DRY	No.2	SPF
5 - 8	2x4	DRY	No.2	SPF
15 - 2	2x4	DRY	No.2	SPF
9 - 7	2x4	DRY	No.2	SPF
11 - 11	2x4	DRY	No.2	SPF
11 - 9	2x4	DRY	No.2	SPF

ALL WEBS 2x3 DRY No.2 SPF
EXCEPT

DRY: SEASONED LUMBER.

PLATES (table is in inches)

JT	TYPE	PLATES	W	LEN	Y	X
2	TMVW-t	MT20	4.0	6.0	2.00	3.00
3	TMWW-t	MT20	3.0	4.0	1.50	1.75
4	TTWW+m	MT20	5.0	5.0	2.50	1.25
5	TTW+m	MT20	3.0	4.0	2.00	1.25
6	TMWW-t	MT20	3.0	4.0	1.50	1.75
7	TMVW-t	MT20	4.0	6.0	2.00	3.00
9	BMV1+p	MT20	2.0	4.0		
10	BMVW-t	MT20	4.0	4.0	1.75	1.50
11	BS-t	MT20	3.0	6.0		
12	BMWW-t	MT20	3.0	8.0		
13	BMWW-t	MT20	3.0	4.0		
14	BMWW-t	MT20	4.0	4.0	1.75	1.50
15	BMV1+p	MT20	2.0	4.0		

DIMENSIONS, SUPPORTS AND LOADINGS SPECIFIED BY FABRICATOR TO BE VERIFIED BY

BUILDING DESIGNER

BEARINGS

	FACTORED GROSS REACTION	MAXIMUM FACTORED GROSS REACTION	INPUT BRG	REQRD BRG
JT	VERT	HORZ	DOWN	HORZ
15	1291	0	1291	0
9	1291	0	1291	0

UNFACTORED REACTIONS

1ST LCASE	COMBINED	SNOW	LIVE	PERM.LIVE	WIND	DEAD	SOIL
JT	904	646 / 0	0 / 0	0 / 0	0 / 0	258 / 0	0 / 0
9	904	646 / 0	0 / 0	0 / 0	0 / 0	258 / 0	0 / 0

BEARING MATERIAL TO BE SPF NO.2 OR BETTER AT JOINT(S) 15, 9

BRACING

TOP CHORD TO BE SHEATHED OR MAX. PURLIN SPACING = 4.95 FT.
MAX. UNBRACED BOTTOM CHORD LENGTH = 10.00 FT OR RIGID CEILING DIRECTLY APPLIED.

ALL PITCH BREAKS AND PERIMETER CORNER JOINTS MUST BE Laterally RESTRAINED.

LOADING

TOTAL LOAD CASES: (4)

CHORDS				WEBS			
MEMB.	MAX. FACTORED FORCE (LBS)	FACTORED VERT. LOAD (PLF)	MAX. LC1 MAX CSI (LC)	MEMB.	MAX. FACTORED FORCE (LBS)	MAX. UNBRACED LENGTH	MAX. FACTORED CSI (LC)
FR-TO		FROM TO		FR-TO			
1-2	0 / 27	-77.4	-77.4 0.10 (1)	10.00	14-3	-85 / 77	0.03 (1)
2-3	-1470 / 0	-77.4	-77.4 0.41 (1)	4.95	3-13	-461 / 0	0.52 (1)
3-4	-1102 / 0	-77.4	-77.4 0.38 (1)	5.56	13-4	0 / 297	0.07 (1)
4-5	-934 / 0	-77.4	-77.4 0.02 (1)	6.25	4-12	0 / 35	0.01 (1)
5-6	-1106 / 0	-77.4	-77.4 0.38 (1)	5.55	12-5	0 / 334	0.08 (1)
6-7	-1469 / 0	-77.4	-77.4 0.41 (1)	4.96	12-6	-455 / 0	0.51 (1)
7-8	0 / 27	-77.4	-77.4 0.10 (1)	10.00	10-6	-92 / 74	0.03 (1)
15-2	-1248 / 0	0.0	0.0 0.13 (1)	7.19	2-14	0 / 1310	0.29 (1)
9-7	-1247 / 0	0.0	0.0 0.13 (1)	7.19	10-7	0 / 1309	0.29 (1)
15-14	0 / 0	-17.5	-17.5 0.16 (4)	10.00			
14-13	0 / 1294	-17.5	-17.5 0.29 (1)	10.00			
13-12	0 / 930	-17.5	-17.5 0.22 (1)	10.00			
12-11	0 / 1292	-17.5	-17.5 0.28 (1)	10.00			
11-10	0 / 1292	-17.5	-17.5 0.28 (1)	10.00			
10-9	0 / 0	-17.5	-17.5 0.15 (4)	10.00			

DESIGN CRITERIA

SPECIFIED LOADS:

TOP CH.	LL = 23.3	PSF
DL = 3.0	PSF	
BOT CH.	LL = 0.0	PSF
DL = 7.0	PSF	
TOTAL LOAD = 33.3	PSF	

SPACING = 24.0 IN. C/C

LOADING IN FLAT SECTION BASED ON A SLOPE OF 2.00/12 MINIMUM

THIS TRUSS IS DESIGNED FOR RESIDENTIAL OR SMALL BUILDING REQUIREMENTS OF PART 9, NBCC 2010

THIS DESIGN COMPLIES WITH:
- PART 9 OF OBC 2012, CBC 2012, ABC 2014
- CSA 086-09
- TPIC 2011

(55% OF 27.2 P.S.F. G.S.L. PLUS 8.4 P.S.F. RAIN LOAD) EQUALS 23.3 P.S.F. SPECIFIED ROOF LIVE LOAD

ALLOWABLE DEFL.(LL)= L/360 (0.83")
CALCULATED VERT. DEFL.(LL)= L/999 (0.05")
ALLOWABLE DEFL.(TL)= L/360 (0.83")
CALCULATED VERT. DEFL.(TL)= L/999 (0.10")

CSI: TC=0.41/1.00 (2-3:1), BC=0.29/1.00 (13-14:1), WB=0.52/1.00 (3-13:1), SSI=0.20/1.00 (2-3:1)

DOL LUMBER=1.00 NAIL=1.00 LS BEND=1.10
COMP=1.10 SHEAR=1.10 TENS=1.10

COMPANION LIVE LOAD FACTOR = 0.50

TRUSS PLATE MANUFACTURER IS NOT RESPONSIBLE FOR QUALITY CONTROL IN THE TRUSS MANUFACTURING PLANT.

NAIL VALUES
PLATE GRIP(DRY) SHEAR SECTION (PSI) (PLI)
MAX MIN MAX MIN MAX MIN
MT20 618 354 1667 822 2284 1656

PLATE PLACEMENT TOL. = 0.250 inches

PLATE ROTATION TOL. = 5.0 Deg.

JSI GRIP= 0.87 (14) (INPUT = 0.90)
JSI METAL= 0.48 (14) (INPUT = 1.00)




READ ALL NOTES ON THIS PAGE AND ON ENGINEERING NOTE PAGE ENP-1. THIS NOTE PAGE IS AN INTEGRAL PART OF THIS DRAWING AS IT CONTAINS SPECIFICATIONS AND CRITERIA USED IN THE DESIGN OF THIS COMPONENT.



JOB NAME	TRUSS NAME	QUANTITY	PLY	JOB DESC.	DRWG NO.
NE0818-060	T04	8	1	GREENPARK-MINNISLAE HOMES-GRANDBROOKE 1 EL 1	

Version 8.210 S Mar 12 2018 MiTek Industries, Inc. Mon Aug 13 08:51:00 2018 Page 1
ID:w_6JogZnfv1q7BUYX2Ki0Uz3oDL-NqHAm5JTtOB34dX8ECiVjw0ly2X5NktvJli?lyoKD9
Scale = 1:50.8



LUMBER	N. L. G. A. RULES	SIZE	LUMBER	DESCR.
CHORDS				
1 - 4	2x4	DRY	No.2	SPF
4 - 5	2x4	DRY	No.2	SPF
5 - 6	2x4	DRY	No.2	SPF
6 - 9	2x4	DRY	No.2	SPF
15 - 2	2x4	DRY	No.2	SPF
10 - 8	2x4	DRY	No.2	SPF
15 - 12	2x4	DRY	No.2	SPF
12 - 10	2x4	DRY	No.2	SPF
ALL WEBS EXCEPT	2x3	DRY	No.2	SPF

DRY: SEASONED LUMBER.

PLATES (table is in inches)	JT	TYPE	PLATES	W	LEN	Y	X
1 - 4	2	TMVW-t	MT20	4.0	6.0	2.00	3.00
4 - 5	3	TMWW-t	MT20	3.0	4.0	1.50	1.75
5 - 6	4	TS-t	MT20	3.0	6.0		
6 - 9	5	TTW+p	MT20	3.0	4.0	2.25	1.50
15 - 2	6	TS-t	MT20	3.0	6.0		
10 - 8	7	TMVW-t	MT20	3.0	4.0	1.50	1.75
15 - 12	8	TMVW-t	MT20	4.0	6.0	2.00	3.00
12 - 10	10	BMV1+p	MT20	2.0	4.0		
	11	BMWW-t	MT20	4.0	4.0	1.75	1.50
	12	BS-t	MT20	3.0	6.0		
	13	BMWW-t	MT20	4.0	4.0		
	14	BMWW-t	MT20	4.0	4.0	1.75	1.50
	15	BMV1+p	MT20	2.0	4.0		

DIMENSIONS, SUPPORTS AND LOADINGS SPECIFIED BY FABRICATOR TO BE VERIFIED BY BUILDING DESIGNER

BEARINGS	FACTORED GROSS REACTION	MAXIMUM FACTORED GROSS REACTION	INPUT BRG	REQRD BRG
JT	VERT	HORZ	DOWN	HORZ
15	1291	0	1291	0
10	1291	0	1291	0

UNFACTORED REACTIONS	1ST LCASE	MAX/MIN	COMPONENT REACTIONS
JT	COMBINED	SNOW	LIVE
15	904	646 / 0	0 / 0
10	904	646 / 0	0 / 0

BEARING MATERIAL TO BE SPF NO.2 OR BETTER AT JOINT(S) 15, 10

BRACING
TOP CHORD TO BE SHEATHED OR MAX. PURLIN SPACING = 4.91 FT.
MAX. UNBRACED BOTTOM CHORD LENGTH = 10.00 FT OR RIGID CEILING DIRECTLY APPLIED.

ALL PITCH BREAKS AND PERIMETER CORNER JOINTS MUST BE LATERALLY RESTRAINED.

LOADING
TOTAL LOAD CASES: (4)

CHORDS	MEMB.	MAX. FACTORED FORCE (LBS)	FACTORED VERT. LOAD (PLF)	LC1	MAX. UNBRACED LENGTH	WEBS	MEMB.	MAX. FACTORED FORCE (LBS)	MAX. UNBRACED LENGTH
FR-TO						FR-TO			
1-2	0 / 27	-77.4	-77.4	0.10 (1)	10.00	13-5	0 / 696	0.16 (1)	10.00
2-3	-1466 / 0	-77.4	-77.4	0.44 (1)	4.91	13-7	-489 / 0	0.59 (1)	10.00
3-4	-1075 / 0	-77.4	-77.4	0.41 (1)	5.56	11-7	-77 / 81	0.03 (1)	10.00
4-5	-1075 / 0	-77.4	-77.4	0.41 (1)	5.56	3-13	-489 / 0	0.59 (1)	10.00
5-6	-1075 / 0	-77.4	-77.4	0.41 (1)	5.56	14-3	-77 / 81	0.03 (1)	10.00
6-7	-1075 / 0	-77.4	-77.4	0.41 (1)	5.56	2-14	0 / 1307	0.29 (1)	10.00
7-8	-1466 / 0	-77.4	-77.4	0.44 (1)	4.91	11-8	0 / 1307	0.29 (1)	10.00
8-9	0 / 27	-77.4	-77.4	0.10 (1)	10.00				
15-2	-1245 / 0	0.0	0.0	0.13 (1)	7.20				
10-8	-1245 / 0	0.0	0.0	0.13 (1)	7.20				
15-14	0 / 0	-17.5	-17.5	0.16 (4)	10.00				
14-13	0 / 1292	-17.5	-17.5	0.29 (1)	10.00				
13-12	0 / 1292	-17.5	-17.5	0.29 (1)	10.00				
12-11	0 / 1292	-17.5	-17.5	0.29 (1)	10.00				
11-10	0 / 0	-17.5	-17.5	0.16 (4)	10.00				

DESIGN CRITERIA

SPECIFIED LOADS:
TOP CH. LL = 23.3 PSF
DL = 3.0 PSF
BOT CH. LL = 0.0 PSF
DL = 7.0 PSF
TOTAL LOAD = 33.3 PSF

SPACING = 24.0 IN. C/C

THIS TRUSS IS DESIGNED FOR RESIDENTIAL OR SMALL BUILDING REQUIREMENTS OF PART 9, NBC 2010

THIS DESIGN COMPLIES WITH:
- PART 9 OF OBC 2012, BCBC 2012, ABC 2014
- CSA 086-09
- TPIC 2011

(55 % OF 27.2 P.S.F. G.S.L. PLUS 8.4 P.S.F. RAIN LOAD) EQUALS 23.3 P.S.F. SPECIFIED ROOF LIVE LOAD

ALLOWABLE DEFL.(LL) = L/360 (0.83")
CALCULATED VERT. DEFL.(LL) = L/999 (0.05")
ALLOWABLE DEFL.(TL) = L/360 (0.83")
CALCULATED VERT. DEFL.(TL) = L/999 (0.10")

CSI: TC=0.44/1.00 (7-8:1), BC=0.29/1.00 (11-13:1), WB=0.59/1.00 (7-13:1), SSI=0.20/1.00 (7-8:1)

DOL LUMBER=1.00 NAIL=1.00 LS BEND=1.10 COMP=1.10 SHEAR=1.10 TENS=1.10

COMPANION LIVE LOAD FACTOR = 0.50

TRUSS PLATE MANUFACTURER IS NOT RESPONSIBLE FOR QUALITY CONTROL IN THE TRUSS MANUFACTURING PLANT.

NAIL VALUES	PLATE	GRIP(DRY)	SHEAR	SECTION
	(PSI)	(PLI)	(PLI)	(PLI)
	MAX MIN	MAX MIN	MAX MIN	MAX MIN
MT20	618	354	1667	822
	2284	1656		

PLATE PLACEMENT TOL. = 0.250 inches


PLATE ROTATION TOL. = 5.0 Deg.

JSI GRIP= 0.88 (5) (INPUT = 0.90)
JSI METAL= 0.48 (14) (INPUT = 1.00)



READ ALL NOTES ON THIS PAGE AND ON ENGINEERING NOTE PAGE ENP-1. THIS NOTE PAGE IS AN INTEGRAL PART OF THIS DRAWING AS IT CONTAINS SPECIFICATIONS AND CRITERIA USED IN THE DESIGN OF THIS COMPONENT.





TOTAL WEIGHT = 105 lb

LUMBER			
N. L. G. A. RULES			
CHORDS	SIZE	LUMBER	DESCR.
1 - 3	2x4	DRY	No.2
3 - 6	2x4	DRY	No.2
6 - 8	2x4	DRY	No.2
14 - 2	2x4	DRY	No.2
9 - 7	2x4	DRY	No.2
14 - 11	2x4	DRY	No.2
11 - 9	2x4	DRY	No.2

ALL WEBS	2x3	DRY	No.2	SPF
EXCEPT				

DRY: SEASONED LUMBER.

PLATES (table is in inches)						
JT	TYPE	PLATES	W	LEN	Y	X
2	TMVW-t	MT20	4.0	5.0	1.75	2.00
3	TTWW+m	MT20	5.0	6.0	2.25	1.50
4	TMW+w	MT20	2.0	4.0		
5	TMWW-t	MT20	3.0	4.0		
6	TTWW+m	MT20	5.0	6.0	2.25	1.50
7	TMVW-t	MT20	4.0	5.0	1.75	2.00
9	BMV1+p	MT20	2.0	4.0		
10	BMWW-t	MT20	3.0	5.0	1.50	2.00
11	BSWW+l	MT20	4.0	6.0	Edge	1.75
12	BMWWW-t	MT20	3.0	8.0		
13	BMWW-t	MT20	3.0	5.0	1.50	2.00
14	BMV1+p	MT20	2.0	4.0		

Edge - INDICATES REFERENCE CORNER OF PLATE TOUCHES EDGE OF CHORD.

DIMENSIONS, SUPPORTS AND LOADINGS SPECIFIED BY FABRICATOR TO BE VERIFIED BY BUILDING DESIGNER

BEARINGS		FACTORED	MAXIMUM FACTORED	INPUT	REQRD
		GROSS REACTION	GROSS REACTION	BRG	BRG
JT	VERT	HORZ	DOWN	HORZ	IN-SX
14	1292	0	1292	0	5-8
9	1292	0	1292	0	5-8

UNFACTORED REACTIONS

1ST LCASE		MAX./MIN. COMPONENT REACTIONS					
JT	COMBINED	SNOW	LIVE	PERM.LIVE	WIND	DEAD	SOIL
14	905	646 / 0	0 / 0	0 / 0	0 / 0	258 / 0	0 / 0
9	905	646 / 0	0 / 0	0 / 0	0 / 0	258 / 0	0 / 0

BEARING MATERIAL TO BE SPF NO.2 OR BETTER AT JOINT(S) 14, 9

BRACING

TOP CHORD TO BE SHEATHED OR MAX. PURLIN SPACING = 4.96 FT.
MAX. UNBRACED BOTTOM CHORD LENGTH = 10.00 FT OR RIGID CEILING DIRECTLY APPLIED.

ALL PITCH BREAKS AND PERIMETER CORNER JOINTS MUST BE Laterally RESTRAINED.

LOADING

TOTAL LOAD CASES: (4)

CHORDS				WEBS			
MEMB.	MAX. FACTORED FORCE (LBS)	FACTORED VERT. LOAD (PLF)	MAX LC1 (LC)	MEMB.	MAX. FACTORED FORCE (LBS)	MAX LC1 (LC)	UNBRACED LENGTH (LC)
FR-TO				FR-TO			
1-2	0 / 32	-77.4	-77.4 0.11 (1)	10.00	13-3	-138 / 38	0.05 (1)
2-3	-1213 / 0	-77.4	-77.4 0.35 (1)	5.39	3-12	0 / 761	0.17 (1)
3-4	-1526 / 0	-77.4	-77.4 0.32 (1)	4.97	12-4	-429 / 0	0.16 (1)
4-5	-1526 / 0	-77.4	-77.4 0.32 (1)	4.96	12-5	-2 / 0	0.00 (1)
5-6	-1527 / 0	-77.4	-77.4 0.32 (1)	4.96	11-5	-430 / 0	0.16 (1)
6-7	-1213 / 0	-77.4	-77.4 0.35 (1)	5.39	11-6	0 / 763	0.17 (1)
7-8	0 / 32	-77.4	-77.4 0.11 (1)	10.00	10-6	-139 / 38	0.05 (1)
14-2	-1259 / 0	0.0	0.0 0.13 (1)	7.17	2-13	0 / 998	0.22 (1)
9-7	-1259 / 0	0.0	0.0 0.13 (1)	7.17	10-7	0 / 997	0.22 (1)
14-13	0 / 0	-17.5	-17.5 0.10 (4)	10.00			
13-12	0 / 966	-17.5	-17.5 0.21 (1)	10.00			
12-11	0 / 1527	-17.5	-17.5 0.29 (1)	10.00			
11-10	0 / 966	-17.5	-17.5 0.21 (1)	10.00			
10-9	0 / 0	-17.5	-17.5 0.10 (4)	10.00			

DESIGN CRITERIA

SPECIFIED LOADS:

TOP CH.	LL	=	23.3	PSF
	DL	=	3.0	PSF
BOT CH.	LL	=	0.0	PSF
	DL	=	7.0	PSF
TOTAL LOAD	=	33.3	PSF	

SPACING = 24.0 IN. C/C

LOADING IN FLAT SECTION BASED ON A SLOPE OF 2.00/12 MINIMUM

THIS TRUSS IS DESIGNED FOR RESIDENTIAL OR SMALL BUILDING REQUIREMENTS OF PART 9, NBCC 2010

THIS DESIGN COMPLIES WITH:

- PART 9 OF OBC 2012, BCBC 2012, ABC 2014
- CSA 086-09
- TPIC 2011

(55 % OF 27.2 P.S.F. G.S.L. PLUS 8.4 P.S.F. RAIN LOAD) EQUALS 23.3 P.S.F. SPECIFIED ROOF LIVE LOAD

ALLOWABLE DEFL.(LL)= L/360 (0.83")
CALCULATED VERT. DEFL.(LL) = L/999 (0.06")
ALLOWABLE DEFL.(TL)= L/360 (0.83")
CALCULATED VERT. DEFL.(TL) = L/999 (0.11")

CSI: TC=0.35/1.00 (2-3:1), BC=0.29/1.00 (11-12:1), WB=0.22/1.00 (2-13:1), SSI=0.19/1.00 (5-6:1)

DOL LUMBER=1.00 NAIL=1.00 LS BEND=1.10
COMP=1.10 SHEAR=1.10 TENS= 1.10

COMPANION LIVE LOAD FACTOR = 0.50

TRUSS PLATE MANUFACTURER IS NOT RESPONSIBLE FOR QUALITY CONTROL IN THE TRUSS MANUFACTURING PLANT .

NAIL VALUES

PLATE	GRIP(DRY)	SHEAR	SECTION
	(PSI)	(PLI)	(PLI)
	MAX	MIN	MAX MIN
MT20	618	354	1667 822 2284 1656

PLATE PLACEMENT TOL. = 0.250 inches

PLATE ROTATION TOL. = 5.0 Deg.


JSI GRIP= 0.88 (11) (INPUT = 0.90)
JSI METAL= 0.42 (2) (INPUT = 1.00)

READ ALL NOTES ON THIS PAGE AND ON ENGINEERING NOTE PAGE ENP-1. THIS NOTE PAGE IS AN INTEGRAL PART OF THIS DRAWING AS IT CONTAINS SPECIFICATIONS AND CRITERIA USED IN THE DESIGN OF THIS COMPONENT.



READ ALL NOTES ON THIS PAGE AND ON ENGINEERING NOTE PAGE ENP-1. THIS NOTE PAGE IS AN INTEGRAL PART OF THIS DRAWING AS IT CONTAINS SPECIFICATIONS AND CRITERIA USED IN THE DESIGN OF THIS COMPONENT.





TOTAL WEIGHT = 104 lb [M/JF]

LUMBER				DIMENSIONS, SUPPORTS AND LOADINGS SPECIFIED BY FABRICATOR TO BE VERIFIED BY BUILDING DESIGNER			
N. L. G. A. RULES	CHORDS	SIZE	DESCR.	BEARINGS			
1 - 3	2x4	DRY	No.2	FACTORED	MAXIMUM FACTORED	INPUT	REQD
3 - 5	2x4	DRY	No.2	GROSS REACTION	GROSS REACTION	BRG	BRG
5 - 7	2x4	DRY	No.2	JT VERT	DOWN	UPLIFT	IN-SX
13 - 2	2x4	DRY	No.2	13 1292 0	1292 0	0	5-8
8 - 6	2x4	DRY	No.2	8 1292 0	1292 0	0	5-8
13 - 10	2x4	DRY	No.2				
10 - 8	2x4	DRY	No.2				
ALL WEBS EXCEPT	2x3	DRY	No.2	UNFACTORED REACTIONS			
DRY: SEASONED LUMBER.				1ST LCASE	MAX/MIN	COMPONENT REACTIONS	
				JT COMBINED	SNOW	LIVE	PERM.LIVE
				13 905	646 / 0	0 / 0	0 / 0
				8 905	646 / 0	0 / 0	0 / 0

BEARING MATERIAL TO BE SPF NO.2 OR BETTER AT JOINT(S) 13, 8

BRACING
TOP CHORD TO BE SHEATHED OR MAX. PURLIN SPACING = 5.16 FT.
MAX. UNBRACED BOTTOM CHORD LENGTH = 10.00 FT OR RIGID CEILING DIRECTLY APPLIED.

ALL PITCH BREAKS AND PERIMETER CORNER JOINTS MUST BE LATERALLY RESTRAINED.

LOADING
TOTAL LOAD CASES: (4)

CHORDS				WEBS			
MEMB.	MAX. FACTORED	FACTORED	MAX. FACTORED	MEMB.	MAX. FACTORED	FACTORED	MAX. FACTORED
FORCE (LBS)	VERT. LOAD (LBS)	LC1 MAX (PLF)	MAX. UNBRACED LENGTH (LC)	FORCE (LBS)	MAX. UNBRACED LENGTH (LC)	MAX. UNBRACED LENGTH (LC)	MAX. UNBRACED LENGTH (LC)
FR-TO	FR-TO	FR-TO	FR-TO	FR-TO	FR-TO	FR-TO	FR-TO
1-2	0 / 32	-77.4	-77.4 0.11 (1)	10.00	12-3	-51 / 87	0.03 (1)
2-3	-1195 / 0	-77.4	-77.4 0.44 (1)	5.32	3-11	0 / 491	0.11 (1)
3-4	-1308 / 0	-77.4	-77.4 0.41 (1)	5.16	11-4	-586 / 0	0.37 (1)
4-5	-1308 / 0	-77.4	-77.4 0.41 (1)	5.16	11-5	0 / 491	0.11 (1)
5-6	-1195 / 0	-77.4	-77.4 0.44 (1)	5.32	9-5	-51 / 87	0.03 (1)
6-7	0 / 32	-77.4	-77.4 0.11 (1)	10.00	2-12	0 / 971	0.22 (1)
13-2	-1247 / 0	0.0	0.0 0.13 (1)	7.19	9-6	0 / 971	0.22 (1)
8-6	-1247 / 0	0.0	0.0 0.13 (1)	7.19			
13-12	0 / 0	-17.5	-17.5 0.17 (4)	10.00			
12-11	0 / 954	-17.5	-17.5 0.25 (1)	10.00			
11-10	0 / 954	-17.5	-17.5 0.25 (1)	10.00			
10-9	0 / 954	-17.5	-17.5 0.25 (1)	10.00			
9-8	0 / 0	-17.5	-17.5 0.17 (4)	10.00			

DESIGN CRITERIA

SPECIFIED LOADS:
TOP CH. LL = 23.3 PSF
DL = 3.0 PSF
BOT CH. LL = 0.0 PSF
DL = 7.0 PSF
TOTAL LOAD = 33.3 PSF

SPACING = 24.0 IN. C/C

LOADING IN FLAT SECTION BASED ON A SLOPE OF 2.00/12 MINIMUM

THIS TRUSS IS DESIGNED FOR RESIDENTIAL OR SMALL BUILDING REQUIREMENTS OF PART 9, NBCC 2010

THIS DESIGN COMPLIES WITH:
- PART 9 OF OBC 2012, BCBC 2012, ABC 2014
- CSA 086-09
- TPIC 2011

(55 % OF 27.2 P.S.F. G.S.L. PLUS 8.4 P.S.F. RAIN LOAD) EQUALS 23.3 P.S.F. SPECIFIED ROOF LIVE LOAD

ALLOWABLE DEFL.(LL)= L/360 (0.83")
CALCULATED VERT. DEFL.(LL)= L/999 (0.05")
ALLOWABLE DEFL.(TL)= L/360 (0.83")
CALCULATED VERT. DEFL.(TL)= L/999 (0.08")

CSI: TC=0.44/1.00 (5-6:1), BC=0.25/1.00 (9-11:1), WB=0.37/1.00 (4-11:1), SSI=0.23/1.00 (4-5:1)

DOL LUMBER=1.00 NAIL=1.00 LS BEND=1.10
COMP=1.10 SHEAR=1.10 TENS= 1.10

COMPANION LIVE LOAD FACTOR = 0.50


TRUSS PLATE MANUFACTURER IS NOT RESPONSIBLE FOR QUALITY CONTROL IN THE TRUSS MANUFACTURING PLANT.

READ ALL NOTES ON THIS PAGE AND ON ENGINEERING NOTE PAGE ENP-1. THIS NOTE PAGE IS AN INTEGRAL PART OF THIS DRAWING AS IT CONTAINS SPECIFICATIONS AND CRITERIA USED IN THE DESIGN OF THIS COMPONENT.



JOB NAME	TRUSS NAME	QUANTITY	PLY	JOB DESC.	DRWG NO.
NE0818-060	T12	1	1	GREENPARK-MINNISLAE HOMES-GRANDBROOKE 1 EL 1	

Version 8.210 S Mar 12 2018 MiTek Industries, Inc. Mon Aug 13 08:51:02 2018 Page 1
ID:w_6JogZnfv1q7BUYX2Ki0Uz3oDL-r0rY_RK5QiJ2hECjhyj_2xTEZMOMqod17zUGXAyoKD8



TOTAL WEIGHT = 116 lb [MJF]

LUMBER	N. L. G. A. RULES	CHORDS	SIZE	LUMBER	DESCR.
1 - 4	2x4	DRY	No.2	SPF	
4 - 6	2x4	DRY	No.2	SPF	
6 - 9	2x4	DRY	No.2	SPF	
15 - 2	2x4	DRY	No.2	SPF	
10 - 8	2x4	DRY	No.2	SPF	
15 - 12	2x4	DRY	No.2	SPF	
12 - 10	2x4	DRY	No.2	SPF	
ALL WEBS EXCEPT	2x3	DRY	No.2	SPF	

DRY: SEASONED LUMBER.

PLATES (table is in inches)	JT	TYPE	PLATES	W	LEN	Y	X
2 TMV+p	MT20	2.0	4.0				
4 TMWW-l	MT20	4.0	4.0	1.75	1.50		
6 TTWW+m	MT20	5.0	5.0	2.25	1.50		
5 TMW+w	MT20	2.0	4.0				
6 TTWW+m	MT20	5.0	5.0	2.25	1.50		
7 TMWW-l	MT20	4.0	4.0	1.75	1.50		
8 TMV+p	MT20	2.0	4.0				
10 BMVW1-l	MT20	4.0	4.0	1.75	1.75		
11 BMWW-l	MT20	3.0	4.0				
12 BS-l	MT20	3.0	6.0				
13 BMWW-l	MT20	3.0	6.0				
14 BMWW-l	MT20	3.0	4.0				
15 BMVW1-l	MT20	4.0	4.0	1.75	1.75		

DIMENSIONS, SUPPORTS AND LOADINGS SPECIFIED BY FABRICATOR TO BE VERIFIED BY BUILDING DESIGNER

FACTORED		GROSS REACTION		MAXIMUM FACTORED		INPUT		REQRD	
JT	VERT	HORZ	DOWN	HORZ	UPLIFT	IN-SX	IN-SX	BRG	BRG
15	1292	0	1292	0	0	5-8	5-8		
10	1292	0	1292	0	0	5-8	5-8		

UNFACTORED REACTIONS		MAX/MIN. COMPONENT REACTIONS		1ST LCASE		MAX/MIN. COMPONENT REACTIONS	
JT	COMBINED	SNOW	LIVE	PERM.LIVE	WIND	DEAD	SOIL
15	905	646 / 0	0 / 0	0 / 0	0 / 0	258 / 0	0 / 0
10	905	646 / 0	0 / 0	0 / 0	0 / 0	258 / 0	0 / 0

BEARING MATERIAL TO BE SPF NO.2 OR BETTER AT JOINT(S) 15, 10

BRACING
TOP CHORD TO BE SHEATHED OR MAX. PURLIN SPACING = 5.75 FT.
MAX. UNBRACED BOTTOM CHORD LENGTH = 10.00 FT OR RIGID CEILING DIRECTLY APPLIED.

ALL PITCH BREAKS AND PERIMETER CORNER JOINTS MUST BE Laterally RESTRAINED.

LOADING

TOTAL LOAD CASES: (4)

CHORDS				WEBS			
MEMB.	MAX. FACTORED FORCE (LBS)	FACTORED VERT. LOAD (PLF)	MAX. FACTORED VERT. LOAD (LC1) (1)	MEMB.	MAX. FACTORED FORCE (LBS)	MAX. FACTORED VERT. LOAD (LC1) (1)	MAX. FACTORED VERT. LOAD (LC1) (1)
FR-TO		FROM TO		FR-TO		FROM TO	
1-2	0 / 32	-77.4	-77.4 0.11 (1)	10.00	3-14	-68 / 31	0.04 (1)
2-3	0 / 21	-77.4	-77.4 0.19 (1)	10.00	14-4	0 / 195	0.05 (4)
3-4	-1162 / 0	-77.4	-77.4 0.16 (1)	5.75	4-13	0 / 277	0.06 (1)
4-5	-1065 / 0	-77.4	-77.4 0.22 (1)	5.85	13-5	-434 / 0	0.43 (1)
5-6	-1065 / 0	-77.4	-77.4 0.22 (1)	5.85	13-6	0 / 277	0.06 (1)
6-7	-1162 / 0	-77.4	-77.4 0.16 (1)	5.75	11-6	0 / 195	0.05 (4)
7-8	0 / 21	-77.4	-77.4 0.19 (1)	10.00	11-7	-68 / 31	0.04 (1)
8-9	0 / 32	-77.4	-77.4 0.11 (1)	10.00	15-3	-1394 / 0	0.74 (1)
15-2	-224 / 0	0.0	0.0 0.02 (1)	7.81	7-10	-1394 / 0	0.74 (1)
10-8	-224 / 0	0.0	0.0 0.02 (1)	7.81			
15-14	0 / 959	-17.5	-17.5 0.31 (4)	10.00			
14-13	0 / 914	-17.5	-17.5 0.31 (4)	10.00			
13-12	0 / 914	-17.5	-17.5 0.31 (4)	10.00			
12-11	0 / 914	-17.5	-17.5 0.31 (4)	10.00			
11-10	0 / 959	-17.5	-17.5 0.31 (4)	10.00			

DESIGN CRITERIA

SPECIFIED LOADS:
TOP CH. LL = 23.3 PSF
DL = 3.0 PSF
BOT CH. LL = 0.0 PSF
DL = 7.0 PSF
TOTAL LOAD = 33.3 PSF

SPACING = 24.0 IN. C/C

LOADING IN FLAT SECTION BASED ON A SLOPE OF 2.00/12 MINIMUM

THIS TRUSS IS DESIGNED FOR RESIDENTIAL OR SMALL BUILDING REQUIREMENTS OF PART 9, NBCC 2010

THIS DESIGN COMPLIES WITH:
- PART 9 OF OBC 2012, BCBC 2012, ABC 2014
- CSA 086-09
- TPIC 2011

(55% OF 27.2 P.S.F. G.S.L. PLUS 8.4 P.S.F. RAIN LOAD) EQUALS 23.3 P.S.F. SPECIFIED ROOF LIVE LOAD

ALLOWABLE DEFL.(LL)= L/360 (0.83")
CALCULATED VERT. DEFL.(LL)= L/999 (0.04")
ALLOWABLE DEFL.(TL)= L/360 (0.83")
CALCULATED VERT. DEFL.(TL)= L/999 (0.13")

CSI: TC=0.22/1.00 (4-5:1), BC=0.31/1.00 (11-13:4), WB=0.74/1.00 (7-10:1), SSI=0.17/1.00 (4-5:1)

DOL LUMBER=1.00 NAIL=1.00 LS BEND=1.10 COMP=1.10 SHEAR=1.10 TENS=1.10

COMPANION LIVE LOAD FACTOR = 0.50

TRUSS PLATE MANUFACTURER IS NOT RESPONSIBLE FOR QUALITY CONTROL IN THE TRUSS MANUFACTURING PLANT.

NAIL VALUES	PLATE	GRIP(DRY)	SHEAR	SECTION
(PSI)	(PSI)	(PLI)	(PLI)	(PLI)
	MAX	MIN	MAX	MIN
MT20	618	354	1667	822 2284 1656

PLATE PLACEMENT TOL. = 0.250 inches

PLATE ROTATION TOL. = 5.0 Deg.

JSI GRIP= 0.86 (13) (INPUT = 0.90)
JSI METAL= 0.51 (7) (INPUT = 1.00)




READ ALL NOTES ON THIS PAGE AND ON ENGINEERING NOTE PAGE ENP-1. THIS NOTE PAGE IS AN INTEGRAL PART OF THIS DRAWING AS IT CONTAINS SPECIFICATIONS AND CRITERIA USED IN THE DESIGN OF THIS COMPONENT.



JOB NAME	TRUSS NAME	QUANTITY	PLY	JOB DESC.	DRWG NO.
NE0818-060	T13	1	1	GREENPARK-MINNISLAE HOMES-GRANDBROOKE 1 EL 1	

Version 8.210 S Mar 12 2018 MITek Industries, Inc. Mon Aug 13 08:51:02 2018 Page 1
ID:w_6JogZnfv1q7BUYX2Ki0Uz3oDL~JCPwBnLjB0RvJOnwFFEDb80MjIIOZNSAMdEp3dyoKD



LUMBER N. L. G. A. RULES CHORDS SIZE LUMBER DESCR. DIMENSIONS, SUPPORTS AND LOADINGS SPECIFIED BY FABRICATOR TO BE VERIFIED BY BUILDING DESIGNER BEARINGS

CHORDS	SIZE	LUMBER	DESCR.
1 - 4	2x4	DRY No.2	SPF
4 - 5	2x4	DRY No.2	SPF
5 - 8	2x4	DRY No.2	SPF
14 - 2	2x4	DRY No.2	SPF
9 - 7	2x4	DRY No.2	SPF
14 - 11	2x4	DRY No.2	SPF
11 - 9	2x4	DRY No.2	SPF
ALL WEBS	2x3	DRY No.2	SPF
EXCEPT			

DRY: SEASONED LUMBER.

PLATES (table is in inches)

JT	TYPE	PLATES	W	LEN	Y	X
2	TMVW-t	MT20	4.0	5.0	1.75	2.00
3	TMWW-t	MT20	3.0	4.0	1.50	1.50
4	TTWW+m	MT20	5.0	5.0	2.25	1.50
5	TTW+m	MT20	3.0	4.0	2.00	1.25
6	TMWW-t	MT20	3.0	4.0	1.50	1.50
7	TMVW-t	MT20	4.0	5.0	1.75	2.00
9	BMV1+p	MT20	2.0	4.0		
10	BMWW-t	MT20	3.0	5.0	1.50	2.00
11	BSWWW-t	MT20	5.0	6.0	3.00	3.00
12	BMWW-t	MT20	3.0	4.0		
13	BMWW-t	MT20	3.0	5.0	1.50	2.00
14	BMV1+p	MT20	2.0	4.0		

UNFACTORED REACTIONS

FACTORED GROSS REACTION			MAXIMUM FACTORED GROSS REACTION		INPUT BRG	REORD BRG	
JT	VERT	HORZ	DOWN	HORZ	UPLIFT	IN-SX	IN-SX
14	1292	0	1292	0	0	5-8	5-8
9	1292	0	1292	0	0	5-8	5-8

UNFACTORED REACTIONS							
JT	1ST LCASE	MAX./MIN. COMPONENT REACTIONS					
	COMBINED	SNOW	LIVE	PERM.LIVE	WIND	DEAD	SOIL
14	905	646 / 0	0 / 0	0 / 0	0 / 0	258 / 0	0 / 0
9	905	646 / 0	0 / 0	0 / 0	0 / 0	258 / 0	0 / 0

BEARING MATERIAL TO BE SPF NO.2 OR BETTER AT JOINT(S) 14, 9

BRACING

TOP CHORD TO BE SHEATHED OR MAX. PURLIN SPACING = 5.52 FT.
MAX. UNBRACED BOTTOM CHORD LENGTH = 10.00 FT OR RIGID CEILING DIRECTLY APPLIED.

ALL PITCH BREAKS AND PERIMETER CORNER JOINTS MUST BE Laterally RESTRAINED.

LOADING

TOTAL LOAD CASES: (4)

CHORDS				WEBS			
MEMB.	MAX. FACTORED FORCE (LBS)	FACTORED VERT. LOAD (PLF)	LC1 MAX (LC)	MEMB.	MAX. FACTORED FORCE (LBS)	FACTORED VERT. LOAD (PLF)	LC1 MAX (LC)
FR-TO		FROM	TO	FR-TO		FROM	TO
1-2	0 / 32	-77.4	-77.4 0.11 (1)	10.00	13-3	-163 / 27	0.06 (1)
2-3	-1235 / 0	-77.4	-77.4 0.24 (1)	5.52	3-12	-235 / 0	0.20 (1)
3-4	-1083 / 0	-77.4	-77.4 0.23 (1)	5.80	12-4	0 / 264	0.06 (1)
4-5	-847 / 0	-77.4	-77.4 0.39 (1)	6.10	4-11	0 / 0	0.00 (1)
5-6	-1084 / 0	-77.4	-77.4 0.23 (1)	5.80	11-5	0 / 265	0.06 (1)
6-7	-1234 / 0	-77.4	-77.4 0.24 (1)	5.52	11-6	-235 / 0	0.20 (1)
7-8	0 / 32	-77.4	-77.4 0.11 (1)	10.00	10-6	-164 / 26	0.06 (1)
14-2	-1256 / 0	0.0	0.0 0.13 (1)	7.17	2-13	0 / 1039	0.23 (1)
9-7	-1256 / 0	0.0	0.0 0.13 (1)	7.17	10-7	0 / 1038	0.23 (1)
14-13	0 / 0	-17.5	-17.5 0.08 (4)	10.00			
13-12	0 / 1008	-17.5	-17.5 0.22 (1)	10.00			
12-11	0 / 847	-17.5	-17.5 0.20 (1)	10.00			
11-10	0 / 1008	-17.5	-17.5 0.22 (1)	10.00			
10-9	0 / 0	-17.5	-17.5 0.08 (4)	10.00			

DESIGN CRITERIA

SPECIFIED LOADS:
TOP CH. LL = 23.3 PSF
DL = 3.0 PSF
BOT CH. LL = 0.0 PSF
DL = 7.0 PSF
TOTAL LOAD = 33.3 PSF

SPACING = 24.0 IN. C/C

LOADING IN FLAT SECTION BASED ON A SLOPE OF 2.00/12 MINIMUM

THIS TRUSS IS DESIGNED FOR RESIDENTIAL OR SMALL BUILDING REQUIREMENTS OF PART 9, NBCC 2010

THIS DESIGN COMPLIES WITH:
- PART 9 OF OBC 2012, BCBC 2012, ABC 2014
- CSA 086-09
- TPIC 2011

(55% OF 27.2 P.S.F. G.S.L. PLUS 8.4 P.S.F. RAIN LOAD) EQUALS 23.3 P.S.F. SPECIFIED ROOF LIVE LOAD

ALLOWABLE DEFL.(LL)= L/360 (0.83")
CALCULATED VERT. DEFL.(LL) = L/999 (0.03")
ALLOWABLE DEFL.(TL)= L/360 (0.83")
CALCULATED VERT. DEFL.(TL) = L/999 (0.08")

CSI: TC=0.39/1.00 (4-5:1), BC=0.22/1.00 (10-11:1), WB=0.23/1.00 (2-13:1), SSI=0.19/1.00 (4-5:1)

DOL LUMBER=1.00 NAIL=1.00 LS BEND=1.10 COMP=1.10 SHEAR=1.10 TENS=1.10

COMPANION LIVE LOAD FACTOR = 0.50

TRUSS PLATE MANUFACTURER IS NOT RESPONSIBLE FOR QUALITY CONTROL IN THE TRUSS MANUFACTURING PLANT.

NAIL VALUES
PLATE GRIP(DRY) SHEAR SECTION (PSI) (PLI) (PLI)
MAX MIN MAX MIN MAX MIN
MT20 618 354 1667 822 2284 1656

PLATE PLACEMENT TOL. = 0.250 inches

PLATE ROTATION TOL. = 5.0 Deg.

JSI GRIP= 0.89 (5) (INPUT = 0.90)
JSI METAL= 0.42 (2) (INPUT = 1.00)




READ ALL NOTES ON THIS PAGE AND ON ENGINEERING NOTE PAGE ENP-1. THIS NOTE PAGE IS AN INTEGRAL PART OF THIS DRAWING AS IT CONTAINS SPECIFICATIONS AND CRITERIA USED IN THE DESIGN OF THIS COMPONENT.



JOB NAME	TRUSS NAME	QUANTITY	PLY	JOB DESC.	DRWG NO.
NE0818-060	T14	1	1	GREENPARK-MINNISLAE HOMES-GRANDBROOKE 1 EL 1	

Version 8.210 S Mar 12 2018 MiTek Industries, Inc. Mon Aug 13 08:51:03 2018 Page 1
ID:w_6JogZnf1q7BUYX2Ki0Uz3oDL-nPyIP7MLyJZmwYM6pNIS8LYYG944InJbGzMb4yoKD6



Scale = 1:55.7

TOTAL WEIGHT = 122 lb
[M/JF]

LUMBER

N. L. G. A. RULES	CHORDS	SIZE	LUMBER	DESCR.
1 - 4	2x4	DRY	No.2	SPF
4 - 5	2x4	DRY	No.2	SPF
5 - 8	2x4	DRY	No.2	SPF
15 - 2	2x4	DRY	No.2	SPF
9 - 7	2x4	DRY	No.2	SPF
15 - 11	2x4	DRY	No.2	SPF
11 - 9	2x4	DRY	No.2	SPF

ALL WEBS 2x3 DRY No.2 SPF
EXCEPT

DRY: SEASONED LUMBER.

PLATES (table is in inches)

JT	TYPE	PLATES	W	LEN	Y	X
2	TMVW-t	MT20	4.0	5.0	1.75	2.00
3	TMVW-t	MT20	3.0	4.0	1.50	1.50
4	TTWW+m	MT20	4.0	6.0	2.25	1.00
5	TTW+m	MT20	3.0	4.0	2.00	1.25
6	TMVW-t	MT20	3.0	4.0	1.50	1.50
7	TMVW-t	MT20	4.0	5.0	1.75	2.00
9	BMV1+p	MT20	2.0	4.0		
10	BMVW-t	MT20	4.0	4.0	2.00	1.50
11	BS-t	MT20	3.0	6.0		
12	BMVW-t	MT20	4.0	6.0		
13	BMVW-t	MT20	3.0	4.0		
14	BMVW-t	MT20	4.0	4.0	2.00	1.50
15	BMV1+p	MT20	2.0	4.0		

DIMENSIONS, SUPPORTS AND LOADINGS SPECIFIED BY FABRICATOR TO BE VERIFIED BY BUILDING DESIGNER

JT	FACTORED GROSS REACTION		MAXIMUM FACTORED GROSS REACTION		INPUT BRG	REQRD IN-SX
	VERT	HORZ	DOWN	HORZ		
15	1292	0	1292	0	5-8	5-8
9	1292	0	1292	0	5-8	5-8

UNFACTORED REACTIONS

JT	1ST LCASE		MAX/MIN. COMPONENT REACTIONS		WIND	DEAD	SOIL
	COMBINED	SNOW	LIVE	PERM.LIVE			
15	905	646 / 0	0 / 0	0 / 0	0 / 0	258 / 0	0 / 0
9	905	646 / 0	0 / 0	0 / 0	0 / 0	258 / 0	0 / 0

BEARING MATERIAL TO BE SPF NO.2 OR BETTER AT JOINT(S) 15, 9

BRACING

TOP CHORD TO BE SHEATHED OR MAX. PURLIN SPACING = 5.39 FT.
MAX. UNBRACED BOTTOM CHORD LENGTH = 10.00 FT OR RIGID CEILING DIRECTLY APPLIED.

ALL PITCH BREAKS AND PERIMETER CORNER JOINTS MUST BE Laterally RESTRAINED.

LOADING

TOTAL LOAD CASES: (4)

CHORDS				WEBS			
MEMB.	FORCE (LBS)	FACTORED VERT. LOAD (PLF)	FACTORED LC1 MAX CSI (LC)	MEMB.	FORCE (LBS)	FACTORED VERT. LOAD (PLF)	FACTORED LC1 MAX CSI (LC)
FR-TO		FROM	TO	FR-TO		FROM	TO
1-2	0 / 32	-77.4	-77.4 0.11 (1)	10.00	14-3	-105 / 64	0.05 (1)
2-3	-1242 / 0	-77.4	-77.4 0.33 (1)	5.39	3-13	-344 / 0	0.41 (1)
3-4	-998 / 0	-77.4	-77.4 0.32 (1)	5.87	13-4	0 / 305	0.07 (1)
4-5	-776 / 0	-77.4	-77.4 0.10 (1)	6.25	4-12	0 / 4	0.00 (1)
5-6	-999 / 0	-77.4	-77.4 0.32 (1)	5.86	12-5	0 / 309	0.07 (1)
6-7	-1241 / 0	-77.4	-77.4 0.33 (1)	5.39	12-6	-342 / 0	0.41 (1)
7-8	0 / 32	-77.4	-77.4 0.11 (1)	10.00	10-6	-108 / 62	0.05 (1)
15-2	-1253 / 0	0.0	0.0 0.13 (1)	7.19	2-14	0 / 1040	0.23 (1)
9-7	-1252 / 0	0.0	0.0 0.13 (1)	7.19	10-7	0 / 1040	0.23 (1)
15-14	0 / 0	-17.5	-17.5 0.14 (4)	10.00			
14-13	0 / 1017	-17.5	-17.5 0.23 (1)	10.00			
13-12	0 / 775	-17.5	-17.5 0.17 (1)	10.00			
12-11	0 / 1017	-17.5	-17.5 0.23 (1)	10.00			
11-10	0 / 1017	-17.5	-17.5 0.23 (1)	10.00			
10-9	0 / 0	-17.5	-17.5 0.13 (4)	10.00			

DESIGN CRITERIA

SPECIFIED LOADS:

TOP CH. LL	=	23.3 PSF
DL	=	3.0 PSF
BOT CH. LL	=	0.0 PSF
DL	=	7.0 PSF
TOTAL LOAD	=	33.3 PSF

SPACING = 24.0 IN. C/C

LOADING IN FLAT SECTION BASED ON A SLOPE OF 2.00/12 MINIMUM

THIS TRUSS IS DESIGNED FOR RESIDENTIAL OR SMALL BUILDING REQUIREMENTS OF PART 9, NBCC 2010

THIS DESIGN COMPLIES WITH:

- PART 9 OF OBC 2012, BCBC 2012, ABC 2014
- CSA 086-09
- TPIC 2011

(55% OF 27.2 P.S.F. G.S.I. PLUS 8.4 P.S.F. RAIN LOAD) EQUALS 23.3 P.S.F. SPECIFIED ROOF LIVE LOAD

ALLOWABLE DEFL.(LL)= L/360 (0.83")
CALCULATED VERT. DEFL.(LL) = L/999 (0.04")
ALLOWABLE DEFL.(TL)= L/360 (0.83")
CALCULATED VERT. DEFL.(TL) = L/999 (0.07")

CSI: TC=0.33/1.00 (2-3:1), BC=0.23/1.00 (13-14:1), WB=0.41/1.00 (3-13:1), SSI=0.17/1.00 (2-3:1)

DOL LUMBER=1.00 NAIL=1.00 LS BEND=1.10
COMP=1.10 SHEAR=1.10 TENS=1.10

COMPANION LIVE LOAD FACTOR = 0.50

TRUSS PLATE MANUFACTURER IS NOT RESPONSIBLE FOR QUALITY CONTROL IN THE TRUSS MANUFACTURING PLANT.

NAIL VALUES

PLATE	GRIP(DRY)	SHEAR	SECTION
(PSI)	(PLI)	(PLI)	(PLI)
MAX MIN	MAX MIN	MAX MIN	MAX MIN
MT20	618	354	1667 822 2284 1656

PLATE PLACEMENT TOL. = 0.250 inches

PLATE ROTATION TOL. = 5.0 Deg.

JSI GRIP= 0.89 (5) (INPUT = 0.90)

JSI METAL= 0.43 (2) (INPUT = 1.00)




READ ALL NOTES ON THIS PAGE AND ON ENGINEERING NOTE PAGE ENP-1. THIS NOTE PAGE IS AN INTEGRAL PART OF THIS DRAWING AS IT CONTAINS SPECIFICATIONS AND CRITERIA USED IN THE DESIGN OF THIS COMPONENT.



JOB NAME	TRUSS NAME	QUANTITY	PLY	JOB DESC.	DRWG NO.
NE0818-060	T16	1	1	GREENPARK-MINNISLAE HOMES-GRANDBROOKE 1 EL 1	

Version 8.210 S Mar 12 2018 MiTek Industries, Inc. Mon Aug 13 08:51:04 2018 Page 1
ID:w_6JogZnfv1q7BUYX2Ki0Uz3oDL-FbWhcTM_jdhdyhxiN4HhgZ5nSZRL1HxTqwjw8WyoKD5



TOTAL WEIGHT = 66 lb
[M][F]

LUMBER	N. L. G. A. RULES	CHORDS	SIZE	LUMBER	DESCR.
1 - 4	2x4	DRY	No.2	SPF	
4 - 6	2x4	DRY	No.2	SPF	
11 - 2	2x4	DRY	No.2	SPF	
7 - 6	2x4	DRY	No.2	SPF	
11 - 9	2x4	DRY	No.2	SPF	
9 - 7	2x4	DRY	No.2	SPF	
ALL WEBS EXCEPT	2x3	DRY	No.2	SPF	
ALL GABLE WEBS	2x3	DRY	No.2	SPF	
DRY: SEASONED LUMBER.					
GABLE STUDS SPACED AT	2'-0.0	OC.			

DIMENSIONS, SUPPORTS AND LOADINGS SPECIFIED BY FABRICATOR TO BE VERIFIED BY BUILDING DESIGNER

BEARINGS	FACTORED GROSS REACTION	MAXIMUM FACTORED GROSS REACTION	INPUT BRG	REQD BRG
JT	VERT	HORZ	DOWN	HORZ
11	755	0	755	0
7	648	0	648	0

UNFACTORED REACTIONS

1ST LCASE	MAX/MIN.	COMPONENT REACTIONS	WIND	DEAD	SOIL
JT	COMBINED	SNOW	LIVE	PERM.LIVE	
11	527	382 / 0	0 / 0	0 / 0	145 / 0
7	455	318 / 0	0 / 0	0 / 0	137 / 0

BEARING MATERIAL TO BE SPF NO.2 OR BETTER AT JOINT(S) 11, 7

BRACING

TOP CHORD TO BE SHEATHED OR MAX. PURLIN SPACING = 6.20 FT.
MAX. UNBRACED BOTTOM CHORD LENGTH = 10.00 FT OR RIGID CEILING DIRECTLY APPLIED.

ALL PITCH BREAKS AND PERIMETER CORNER JOINTS MUST BE Laterally RESTRAINED.

LOADING

TOTAL LOAD CASES: (4)

CHORDS				WEBS			
MEMB.	MAX. FACTORED FORCE (LBS)	FACTORED VERT. LOAD (PLF)	FACTORED LC1 MAX CSI (LC)	MEMB.	MAX. FACTORED FORCE (LBS)	FACTORED VERT. LOAD (PLF)	FACTORED LC1 MAX CSI (LC)
FR-TO		FROM	TO	FR-TO		FROM	TO
1-2	0 / 32	-77.4	-77.4 0.11 (1)	10.00	9-4	0 / 869	0.20 (1)
2-3	-969 / 0	-77.4	-77.4 0.11 (1)	6.20	9-5	-78 / 0	0.02 (1)
3-4	-907 / 0	-77.4	-77.4 0.11 (1)	6.25	8-5	-248 / 0	0.04 (1)
4-5	-907 / 0	-77.4	-77.4 0.11 (1)	6.25	3-9	-78 / 0	0.02 (1)
5-6	-969 / 0	-77.4	-77.4 0.11 (1)	6.20	10-3	-248 / 0	0.04 (1)
11-2	-727 / 0	0.0	0.0 0.08 (1)	7.81	2-10	0 / 792	0.18 (1)
7-6	-620 / 0	0.0	0.0 0.07 (1)	7.81	8-6	0 / 792	0.18 (1)
11-10	0 / 3	-17.5	-17.5 0.05 (4)	10.00			
10-9	0 / 880	-17.5	-17.5 0.17 (1)	10.00			
9-8	0 / 880	-17.5	-17.5 0.17 (1)	10.00			
8-7	0 / 3	-17.5	-17.5 0.05 (4)	10.00			

DESIGN CRITERIA

SPECIFIED LOADS:
TOP CH. LL = 23.3 PSF
DL = 3.0 PSF
BOT CH. LL = 0.0 PSF
DL = 7.0 PSF
TOTAL LOAD = 33.3 PSF

SPACING = 24.0 IN. C/C

THIS TRUSS IS DESIGNED FOR RESIDENTIAL OR SMALL BUILDING REQUIREMENTS OF PART 9, NBCC 2010

THIS DESIGN COMPLIES WITH:
- PART 9 OF OBC 2012, BCBC 2012, ABC 2014
- CSA 086-09
- TPIC 2011

(55% OF 27.2 P.S.F. G.S.L. PLUS 8.4 P.S.F. RAIN LOAD) EQUALS 23.3 P.S.F. SPECIFIED ROOF LIVE LOAD

ALLOWABLE DEFL.(LL)= L/360 (0.46")
CALCULATED VERT. DEFL.(LL)= L/999 (0.03")
ALLOWABLE DEFL.(TL)= L/360 (0.46")
CALCULATED VERT. DEFL.(TL)= L/999 (0.05")

CSI: TC=0.11/1.00 (5-6:1), BC=0.17/1.00 (9-10:1), WB=0.20/1.00 (4-9:1), SSI=0.10/1.00 (2-3:1)

DOL LUMBER=1.00 NAIL=1.00 LS BEND=1.10 COMP=1.10 SHEAR=1.10 TENS=1.10

COMPANION LIVE LOAD FACTOR = 0.50

TRUSS PLATE MANUFACTURER IS NOT RESPONSIBLE FOR QUALITY CONTROL IN THE TRUSS MANUFACTURING PLANT.

NAIL VALUES
PLATE GRIP(DRY) SHEAR SECTION
(PSI) (PLI) (PLI)
MAX MIN MAX MIN MAX MIN
MT20 618 354 1667 822 2284 1656

PLATE PLACEMENT TOL. = 0.250 inches

PLATE ROTATION TOL. = 5.0 Deg.

JSI GRIP= 0.74 (8) (INPUT = 0.90)
JSI METAL= 0.28 (6) (INPUT = 1.00)

PLATES (table is in inches)

JT	TYPE	PLATES	W	LEN	Y	X
2	TMVW-I	MT20	3.0	6.0	1.50	2.75
3	TMVW-I	MT20	3.0	4.0	1.50	1.50
4	TTW+p	MT20	3.0	5.0		
5	TMVW-I	MT20	3.0	4.0	1.50	1.50
6	TMVW-I	MT20	3.0	6.0	1.50	Edge
7	BMV1+p	MT20	2.0	4.0		
8	BMVW-I	MT20	3.0	5.0		
9	BBVW-p	MT20	5.0	6.0		
10	BMVW-I	MT20	3.0	5.0		
11	BMV1+p	MT20	2.0	4.0		
12	NP-p	MT20	2.0	8.0	0.75	1.50
12, 13, 14, 15, 16, 17, 18, 19, 20, 21, 22, 23, 24, 25						
12	NP+w	MT20	2.0	4.0		
21	NP-p	MT20	2.0	8.0	0.75	1.50

Edge - INDICATES REFERENCE CORNER OF PLATE TOUCHES EDGE OF CHORD.




READ ALL NOTES ON THIS PAGE AND ON ENGINEERING NOTE PAGE ENP-1. THIS NOTE PAGE IS AN INTEGRAL PART OF THIS DRAWING AS IT CONTAINS SPECIFICATIONS AND CRITERIA USED IN THE DESIGN OF THIS COMPONENT.





JOB NAME	TRUSS NAME	QUANTITY	PLY	JOB DESC.	DRWG NO.
NE0818-060	T18	1	1	GREENPARK-MINNISLAE HOMES-GRANDBROOKE 1 EL 1	

Version 8.210 S Mar 12 2018 MiTek Industries, Inc. Mon Aug 13 08:51:05 2018 Page 1
ID:w_6JogZnfv1q7BUYX2Ki0Uz3oDL-kn43qpNcTxpUArWVvnowDmexmzmKmj7c2aSTgyyoKD



Scale = 1:39.8

TOTAL WEIGHT = 59 lb
(M)F

LUMBER	N. L. G. A. RULES	CHORDS	SIZE	LUMBER	DESCR.
1 - 4	2x4	DRY	No.2	SPF	
4 - 6	2x4	DRY	No.2	SPF	
9 - 2	2x4	DRY	No.2	SPF	
7 - 6	2x4	DRY	No.2	SPF	
9 - 7	2x4	DRY	No.2	SPF	
ALL WEBS EXCEPT	2x3	DRY	No.2	SPF	

DRY: SEASONED LUMBER.

PLATES (table is in inches)

JT	TYPE	PLATES	W	LEN	Y	X
2	TMV+p	MT20	2.0	4.0		
3	TMWW-1	MT20	3.0	4.0	1.50	1.50
4	TTW+p	MT20	3.0	4.0	2.25	1.50
5	TMWW-1	MT20	3.0	4.0		
6	TMV+p	MT20	2.0	4.0		
7	BMWW-1	MT20	3.0	4.0		
8	BMWW-1	MT20	3.0	6.0		
9	BMWW-1	MT20	3.0	4.0		

DIMENSIONS, SUPPORTS AND LOADINGS SPECIFIED BY FABRICATOR TO BE VERIFIED BY BUILDING DESIGNER

BEARINGS	FACTORED	MAXIMUM FACTORED	INPUT	REQD
	GROSS REACTION	GROSS REACTION	BRG	BRG
JT	VERT	HORZ	DOWN	HORZ
9	733	0	733	0
7	626	0	626	0

A SUITABLE MECHANICAL CONNECTION IS REQUIRED AT JOINT 7 TO RESIST THE MAX FACTORED REACTIONS.

UNFACTORED REACTIONS

JT	1ST LCASE	MAX/MIN	COMPONENT REACTIONS	
	COMBINED	SNOW	LIVE	PERM.LIVE
9	512	372 / 0	0 / 0	0 / 0
7	440	308 / 0	0 / 0	0 / 0

BEARING MATERIAL TO BE SPF NO.2 OR BETTER AT JOINT(S) 9

BRACING

TOP CHORD TO BE SHEATHED OR MAX. PURLIN SPACING = 6.25 FT.
MAX. UNBRACED BOTTOM CHORD LENGTH = 10.00 FT OR RIGID CEILING DIRECTLY APPLIED.

ALL PITCH BREAKS AND PERIMETER CORNER JOINTS MUST BE Laterally RESTRAINED.

LOADING

TOTAL LOAD CASES: (4)

CHORDS	MEMB.	MAX. FACTORED	FACTORED	WEBS	MEMB.	MAX. FACTORED	FACTORED
		FORCE (LBS)	VERT. LOAD (PLF)			FORCE (LBS)	MAX. FACTORED
			LC1 MAX				CS1 (LC)
FR-TO			FROM TO	LENGTH	FR-TO		
1-2	0 / 32	-77.4	-77.4	0.11 (1)	10.00	3-8	-138 / 4
2-3	0 / 18	-77.4	-77.4	0.14 (1)	10.00	8-4	0 / 314
3-4	-444 / 0	-77.4	-77.4	0.11 (1)	6.25	8-5	-89 / 15
4-5	-443 / 0	-77.4	-77.4	0.09 (1)	6.25	9-3	-847 / 0
5-6	0 / 16	-77.4	-77.4	0.12 (1)	10.00	5-7	-629 / 0
9-2	-208 / 0	0.0	0.0	0.02 (1)	7.81		
7-6	-96 / 0	0.0	0.0	0.01 (1)	7.81		
9-8	0 / 435	-17.5	-17.5	0.25 (4)	10.00		
8-7	0 / 397	-17.5	-17.5	0.25 (4)	10.00		

DESIGN CRITERIA

SPECIFIED LOADS:

TOP CH.	LL	=	23.3	PSF
	DL	=	3.0	PSF
BOT CH.	LL	=	0.0	PSF
	DL	=	7.0	PSF
TOTAL LOAD		=	33.3	PSF

SPACING = 24.0 IN. C/C

THIS TRUSS IS DESIGNED FOR RESIDENTIAL OR SMALL BUILDING REQUIREMENTS OF PART 9, NBCC 2010

THIS DESIGN COMPLIES WITH:

- PART 9 OF OBC 2012, BCBC 2012, ABC 2014
- CSA 086-09
- TPIC 2011

(55 % OF 27.2 P.S.F. G.S.L. PLUS 8.4 P.S.F. RAIN LOAD) EQUALS 23.3 P.S.F. SPECIFIED ROOF LIVE LOAD

ALLOWABLE DEFL.(LL) = L/360 (0.44")
CALCULATED VERT. DEFL.(LL) = L/999 (0.01")
ALLOWABLE DEFL.(TL) = L/360 (0.44")
CALCULATED VERT. DEFL.(TL) = L/999 (0.05")

CSI: TC=0.14/1.00 (2-3:1), BC=0.25/1.00 (8-9:4), WB=0.26/1.00 (3-9:1), SSI=0.10/1.00 (3-4:1)

DOL LUMBER=1.00 NAIL=1.00 LS BEND=1.10
COMP=1.10 SHEAR=1.10 TENS= 1.10

COMPANION LIVE LOAD FACTOR = 0.50

TRUSS PLATE MANUFACTURER IS NOT RESPONSIBLE FOR QUALITY CONTROL IN THE TRUSS MANUFACTURING PLANT.

NAIL VALUES

PLATE	GRIP(DRY)	SHEAR	SECTION
	(PSI)	(PLI)	(PLI)
MT20	618	354	1667
	822	2284	1658

PLATE PLACEMENT TOL. = 0.250 inches

PLATE ROTATION TOL. = 5.0 Deg.

JSI GRIP= 0.88 (5) (INPUT = 0.90)
JSI METAL= 0.23 (3) (INPUT = 1.00)




READ ALL NOTES ON THIS PAGE AND ON ENGINEERING NOTE PAGE ENP-1. THIS NOTE PAGE IS AN INTEGRAL PART OF THIS DRAWING AS IT CONTAINS SPECIFICATIONS AND CRITERIA USED IN THE DESIGN OF THIS COMPONENT.



JOB NAME	TRUSS NAME	QUANTITY	PLY	JOB DESC.	GREENPARK-MINNISLAE HOMES-GRANDBROOKE 1 EL 1	DRWG NO.
NE0818-060	T19	7	1	TRUSS DESC.		

Version 8.210 S Mar 12 2018 MiTek Industries, Inc. Mon Aug 13 08:51:05 2018 Page 1
ID:w_6JogZnfv1q7BUYX2Ki0Uz3oDL-kn43qpNcTxpUArWVwnowDmeuizIWmnEc2aSTgyyoKD4



TOTAL WEIGHT = 7 X 17 = 121 lb
(M)(F)

LUMBER

N. L. G. A. RULES	CHORDS	SIZE	LUMBER	DESCR.
1 - 3	2x4	DRY	No.2	SPF
5 - 3	2x4	DRY	No.2	SPF
2 - 4	2x4	DRY	No.2	SPF

DRY: SEASONED LUMBER.

PLATES (table is in inches)

JT TYPE	PLATES	W	LEN	Y	X
2 TMB1-I	MT20	3.0	4.0		
3 TMBV+p	MT20	2.0	4.0		
5 BMV+p	MT20	2.0	4.0		

DIMENSIONS, SUPPORTS AND LOADINGS SPECIFIED BY FABRICATOR TO BE VERIFIED BY BUILDING DESIGNER

BEARINGS	FACTORED	MAXIMUM FACTORED	INPUT	REQRD
GROSS REACTION	GROSS REACTION	BRG	BRG	
JT VERT HORZ	JT VERT HORZ	UPLIFT	IN-SX	IN-SX
2 402 0	402 0	0	3-0	3-0
4 237 0	237 0	0	1-8	1-8

UNFACTORED REACTIONS

1ST CASE	MAX/MIN	COMPONENT REACTIONS
JT	COMBINED	SNOW LIVE PERM.LIVE WIND DEAD SOIL
2	280	209 / 0 0 / 0 0 / 0 0 / 0 71 / 0 0 / 0
4	168	110 / 0 0 / 0 0 / 0 0 / 0 58 / 0 0 / 0

BEARING MATERIAL TO BE SPF NO.2 OR BETTER AT JOINT(S) 2, 4

BRACING

TOP CHORD TO BE SHEATHED OR MAX. PURLIN SPACING = 6.25 FT.
MAX. UNBRACED BOTTOM CHORD LENGTH = 10.00 FT OR RIGID CEILING DIRECTLY APPLIED.

ALL PITCH BREAKS AND PERIMETER CORNER JOINTS MUST BE Laterally RESTRAINED.

LOADING

TOTAL LOAD CASES: (4)

CHORDS	MAX. FACTORED	FACTORED	WEBS	MAX. FACTORED
MEMB.	FORCE	VERT. LOAD LC1 MAX	MEMB.	FORCE
FR-TO	(LBS)	FROM TO	UNBRAC	MAX
1-2	0 / 16	-77.4 -77.4 0.10 (1)	10.00	6-7 -135 / 71 0.00 (1)
2-7	-30 / 0	-77.4 -77.4 0.08 (4)	6.25	
7-3	0 / 3	-77.4 -77.4 0.34 (1)	10.00	
5-3	-196 / 0	0.0 0.0 0.02 (1)	7.81	
2-6	0 / 0	-17.5 -17.5 0.17 (1)	10.00	
6-5	0 / 0	-17.5 -17.5 0.30 (1)	10.00	
5-4	0 / 0	-17.5 -17.5 0.27 (1)	10.00	

DESIGN CRITERIA

SPECIFIED LOADS:
TOP CH. LL = 23.3 PSF
DL = 3.0 PSF
BOT CH. LL = 0.0 PSF
DL = 7.0 PSF
TOTAL LOAD = 33.3 PSF

SPACING = 24.0 IN. C/C

THIS TRUSS IS DESIGNED FOR RESIDENTIAL OR SMALL BUILDING REQUIREMENTS OF PART 9, NBCC 2010

THIS DESIGN COMPLIES WITH:
- PART 9 OF OBC 2012, BCBC 2012, ABC 2014
- CSA 086-09
- TPIC 2011

(55 % OF 27.2 P.S.F. G.S.L. PLUS 8.4 P.S.F. RAIN LOAD) EQUALS 23.3 P.S.F. SPECIFIED ROOF LIVE LOAD

ALLOWABLE DEFL.(LL)= L/360 (0.21")
CALCULATED VERT. DEFL.(LL) = L/737 (0.10")
ALLOWABLE DEFL.(TL)= L/360 (0.21")
CALCULATED VERT. DEFL.(TL) = L/381 (0.20")

CSI: TC=0.34/1.00 (3-7:1), BC=0.30/1.00 (5-6:1), WB=0.00/1.00 (6-7:1), SSI=0.19/1.00 (4-5:1)

DOL LUMBER=1.00 NAIL=1.00 LS BEND=1.10 COMP=1.10 SHEAR=1.10 TENS= 1.10

COMPANION LIVE LOAD FACTOR = 0.50

TRUSS PLATE MANUFACTURER IS NOT RESPONSIBLE FOR QUALITY CONTROL IN THE TRUSS MANUFACTURING PLANT.

NAIL VALUES
PLATE GRIP(DRY) SHEAR SECTION
(PSI) (PLI) (PLI)
MAX MIN MAX MIN MAX MIN
MT20 618 354 1667 822 2284 1656

PLATE PLACEMENT TOL. = 0.250 inches

PLATE ROTATION TOL. = 5.0 Deg.

JSI GRIP= 0.21 (2) (INPUT = 0.90)
JSI METAL= 0.06 (2) (INPUT = 1.00)




READ ALL NOTES ON THIS PAGE AND ON ENGINEERING NOTE PAGE ENP-1. THIS NOTE PAGE IS AN INTEGRAL PART OF THIS DRAWING AS IT CONTAINS SPECIFICATIONS AND CRITERIA USED IN THE DESIGN OF THIS COMPONENT.



JOB NAME	TRUSS NAME	QUANTITY	PLY	JOB DESC.	DRWG NO.
NE0818-060	T21	1	1	GREENPARK-MINNISLAE HOMES-GRANDBROOKE 1 EL 1	

Version 8.210 S Mar 12 2018 Mittek Industries, Inc. Mon Aug 13 08:51:06 2018 Page 1
ID: w_6JogZnfv1q7BUYX2Ki0Uz3oDL-C_eR180EEExKo?4hUVJ9l_A4ZN6QV8kmHEC1CPyoKD8



TOTAL WEIGHT = 120 lb
[M/F]

LUMBER

N. L. G. A. RULES	CHORDS	SIZE	LUMBER	DESCR.
1 - 4	2x4	DRY	No.2	SPF
4 - 6	2x4	DRY	No.2	SPF
6 - 9	2x4	DRY	No.2	SPF
17 - 2	2x4	DRY	No.2	SPF
10 - 8	2x4	DRY	No.2	SPF
17 - 13	2x4	DRY	No.2	SPF
13 - 10	2x4	DRY	No.2	SPF
ALL WEBS EXCEPT	2x3	DRY	No.2	SPF

DRY: SEASONED LUMBER.

PLATES (table is in inches)

JT	TYPE	PLATES	W	LEN	Y	X
2	TMVW-t	MT20	4.0	5.0	1.75	2.00
3	TMWW-t	MT20	3.0	4.0	1.50	1.50
4	TTWW+m	MT20	5.0	5.0	2.25	1.50
5	TMW-w	MT20	2.0	4.0		
6	TTWW+m	MT20	5.0	5.0	2.25	1.50
7	TMWW-t	MT20	3.0	4.0	1.50	1.50
8	TMVW-t	MT20	4.0	5.0	1.75	2.00
10	BMV1+p	MT20	2.0	4.0		
11	BMWW-t	MT20	3.0	5.0	1.50	2.00
12	BMWW-t	MT20	3.0	4.0		
13	BS-t	MT20	3.0	6.0		
14	BMWW-t	MT20	3.0	6.0		
15	BMWW-t	MT20	3.0	4.0		
16	BMWW-t	MT20	3.0	5.0	1.50	2.00
17	BMV1+p	MT20	2.0	4.0		

DIMENSIONS, SUPPORTS AND LOADINGS SPECIFIED BY FABRICATOR TO BE VERIFIED BY BUILDING DESIGNER

BEARINGS

JT	FACTORED GROSS REACTION	MAXIMUM FACTORED GROSS REACTION	INPUT BRG	REQRD BRG
17	1292 0	1292 0	5-8	5-8
10	1292 0	1292 0	5-8	5-8

UNFACTORED REACTIONS

JT	1ST LCASE COMBINED	MAX/MIN. COMPONENT REACTIONS	SNOW	LIVE	PERM.LIVE	WIND	DEAD	SOIL
17	905	646 / 0	0 / 0	0 / 0	0 / 0	0 / 0	258 / 0	0 / 0
10	905	646 / 0	0 / 0	0 / 0	0 / 0	0 / 0	258 / 0	0 / 0

BEARING MATERIAL TO BE SPF NO.2 OR BETTER AT JOINT(S) 17, 10

BRACING

TOP CHORD TO BE SHEATHED OR MAX. PURLIN SPACING = 5.63 FT.
MAX. UNBRACED BOTTOM CHORD LENGTH = 10.00 FT OR RIGID CEILING DIRECTLY APPLIED.

ALL PITCH BREAKS AND PERIMETER CORNER JOINTS MUST BE Laterally RESTRAINED.

LOADING

TOTAL LOAD CASES: (4)

CHORDS				WEBS			
MEMB.	MAX. FACTORED FORCE (LBS)	FACTORED VERT. LOAD (PLF)	LC1 MAX CSI (LC)	MAX. UNBRAC LENGTH FR-TO	MEMB.	MAX. FACTORED FORCE (LBS)	MAX. FACTORED CSI (LC)
1-2	0 / 32	-77.4	-77.4 0.11 (1)	10.00	16-3	-212 / 4	0.07 (1)
2-3	-1218 / 0	-77.4	-77.4 0.17 (1)	5.63	3-15	-142 / 0	0.08 (1)
3-4	-1143 / 0	-77.4	-77.4 0.17 (1)	5.77	15-4	0 / 178	0.04 (1)
4-5	-1048 / 0	-77.4	-77.4 0.20 (1)	5.91	4-14	0 / 289	0.06 (1)
5-6	-1048 / 0	-77.4	-77.4 0.20 (1)	5.91	14-5	-417 / 0	0.43 (1)
6-7	-1143 / 0	-77.4	-77.4 0.17 (1)	5.77	14-6	0 / 289	0.06 (1)
7-8	-1218 / 0	-77.4	-77.4 0.17 (1)	5.63	12-6	0 / 178	0.04 (1)
8-9	0 / 32	-77.4	-77.4 0.11 (1)	10.00	12-7	-142 / 0	0.08 (1)
17-2	-1261 / 0	0.0	0.0 0.13 (1)	7.16	11-7	-212 / 4	0.07 (1)
10-8	-1261 / 0	0.0	0.0 0.13 (1)	7.16	2-16	0 / 1032	0.23 (1)
17-16	0 / 0	-17.5	-17.5 0.06 (4)	10.00	11-8	0 / 1032	0.23 (1)
16-15	0 / 991	-17.5	-17.5 0.19 (1)	10.00			
15-14	0 / 897	-17.5	-17.5 0.18 (1)	10.00			
14-13	0 / 897	-17.5	-17.5 0.18 (1)	10.00			
13-12	0 / 897	-17.5	-17.5 0.18 (1)	10.00			
12-11	0 / 991	-17.5	-17.5 0.19 (1)	10.00			
11-10	0 / 0	-17.5	-17.5 0.06 (4)	10.00			

DESIGN CRITERIA

SPECIFIED LOADS:

TOP CH.	LL	=	23.3	PSF
	DL	=	3.0	PSF
BOT CH.	LL	=	0.0	PSF
	DL	=	7.0	PSF
TOTAL LOAD		=	33.3	PSF

SPACING = 24.0 IN. C/C

LOADING IN FLAT SECTION BASED ON A SLOPE OF 2.00/12 MINIMUM

THIS TRUSS IS DESIGNED FOR RESIDENTIAL OR SMALL BUILDING REQUIREMENTS OF PART 9, NBCC 2010

THIS DESIGN COMPLIES WITH:
- PART 9 OF OBC 2012, CBC 2012, ABC 2014
- CSA 086-09
- TPIC 2011

(55% OF 27.2 P.S.F. G.S.L. PLUS 8.4 P.S.F. RAIN LOAD) EQUALS 23.3 P.S.F. SPECIFIED ROOF LIVE LOAD

ALLOWABLE DEFL.(LL) = $L/360$ (0.83")
CALCULATED VERT. DEFL.(LL) = $L/999$ (0.04")
ALLOWABLE DEFL.(TL) = $L/360$ (0.83")
CALCULATED VERT. DEFL.(TL) = $L/999$ (0.06")

CSI: TC=0.20/1.00 (4-5:1), BC=0.19/1.00 (11-12:1), WB=0.43/1.00 (5-14:1), SSI=0.17/1.00 (5-6:1)

DOL LUMBER=1.00 NAIL=1.00 LS BEND=1.10
COMP=1.10 SHEAR=1.10 TENS=1.10

COMPANION LIVE LOAD FACTOR = 0.50

TRUSS PLATE MANUFACTURER IS NOT RESPONSIBLE FOR QUALITY CONTROL IN THE TRUSS MANUFACTURING PLANT.

NAIL VALUES
PLATE GRIP(DRY) SHEAR SECTION
(PSI) (PLI) (PLI)
MAX MIN MAX MIN MAX MIN
MT20 618 354 1667 822 2284 1656

PLATE PLACEMENT TOL. = 0.250 inches

PLATE ROTATION TOL. = 5.0 Deg.

JSI GRIP= 0.86 (14) (INPUT = 0.90)
JSI METAL= 0.41 (8) (INPUT = 1.00)




READ ALL NOTES ON THIS PAGE AND ON ENGINEERING NOTE PAGE ENP-1. THIS NOTE PAGE IS AN INTEGRAL PART OF THIS DRAWING AS IT CONTAINS SPECIFICATIONS AND CRITERIA USED IN THE DESIGN OF THIS COMPONENT.



JOB NAME	TRUSS NAME	QUANTITY	PLY	JOB DESC.	GREENPARK-MINNISLAKE HOMES-GRANDBROOKE 1 EL 1	DRWG NO.
NE0818-060	T22	1	1	TRUSS DESC.		

Version 8.210 S Mar 12 2018 MiTek Industries, Inc. Mon Aug 13 08:51:07 2018 Page 1
ID:w_6JogZnf1q7BUYX2Ki0Uz3oDL-gACpEUPs?Y3BP9f2Cq0IBjD7mSGEe5vWuxakryoKD2



TOTAL WEIGHT = 116 lb

LUMBER N. L. G. A. RULES **CHORDS** **SIZE** **LUMBER** **DESCR.** **SPF** **FACTORED** **MAXIMUM FACTORED** **INPUT** **REQRD** **DESIGN CRITERIA**

CHORDS	SIZE	LUMBER	DESCR.	SPF	FACTORED	MAXIMUM FACTORED	INPUT	REQRD	DESIGN CRITERIA
1 - 4	2x4	DRY	No.2	SPF	GROSS REACTION	GROSS REACTION	BRG	BRG	SPECIFIED LOADS:
4 - 5	2x4	DRY	No.2	SPF	JT VERT	DOWN	HORZ	UPLIFT	TOP CH. LL = 23.3 PSF
5 - 8	2x4	DRY	No.2	SPF	14 1292 0	1292 0	0 0	5-8 5-8	DL = 3.0 PSF
14 - 2	2x4	DRY	No.2	SPF	9 1292 0	1292 0	0 0	5-8 5-8	BOT CH. LL = 0.0 PSF
9 - 7	2x4	DRY	No.2	SPF					DL = 7.0 PSF
14 - 11	2x4	DRY	No.2	SPF					TOTAL LOAD = 33.3 PSF
11 - 9	2x4	DRY	No.2	SPF					

ALL WEBS 2x3 DRY No.2 SPF UNFACTORED REACTIONS 1ST LCASE MAX./MIN. COMPONENT REACTIONS

JT	COMBINED	SNOW	LIVE	PERM.LIVE	WIND	DEAD	SOIL
14	905	646 / 0	0 / 0	0 / 0	0 / 0	258 / 0	0 / 0
9	905	646 / 0	0 / 0	0 / 0	0 / 0	258 / 0	0 / 0

BEARING MATERIAL TO BE SPF NO.2 OR BETTER AT JOINT(S) 14, 9

BRACING

TOP CHORD TO BE SHEATHED OR MAX. PURLIN SPACING = 5.51 FT.
MAX. UNBRACED BOTTOM CHORD LENGTH = 10.00 FT OR RIGID CEILING DIRECTLY APPLIED.

ALL PITCH BREAKS AND PERIMETER CORNER JOINTS MUST BE Laterally RESTRAINED.

LOADING

TOTAL LOAD CASES: (4)

CHORDS	MEMB.	MAX. FACTORED	FORCE	VERT. LOAD	LC1	MAX	CS1 (LC)	UNBRAC	LENGTH	FR-TO	MEMB.	MAX. FACTORED	FORCE	MAX	CS1 (LC)
1-2		0 / 32		-77.4	-77.4	0.11 (1)	10.00	13-3	-156 / 32	0.06 (1)					
2-3		-1236 / 0		-77.4	-77.4	0.25 (1)	5.51	3-12	-249 / 0	0.22 (1)					
3-4		-1073 / 0		-77.4	-77.4	0.24 (1)	5.81	12-4	0 / 269	0.06 (1)					
4-5		-839 / 0		-77.4	-77.4	0.34 (1)	6.20	4-11	0 / 0	0.00 (1)					
5-6		-1074 / 0		-77.4	-77.4	0.24 (1)	5.81	11-5	0 / 270	0.06 (1)					
6-7		-1236 / 0		-77.4	-77.4	0.25 (1)	5.51	11-6	-248 / 0	0.22 (1)					
7-8		0 / 32		-77.4	-77.4	0.11 (1)	10.00	10-6	-157 / 31	0.06 (1)					
14-2		-1256 / 0		0.0	0.0	0.13 (1)	7.17	2-13	0 / 1039	0.23 (1)					
9-7		-1256 / 0		0.0	0.0	0.13 (1)	7.17	10-7	0 / 1039	0.23 (1)					
14-13		0 / 0		-17.5	-17.5	0.09 (4)	10.00								
13-12		0 / 1010		-17.5	-17.5	0.21 (1)	10.00								
12-11		0 / 839		-17.5	-17.5	0.19 (1)	10.00								
11-10		0 / 1010		-17.5	-17.5	0.22 (1)	10.00								
10-9		0 / 0		-17.5	-17.5	0.09 (4)	10.00								

ALLOWABLE DEFL.(LL) = L/360 (0.83")
CALCULATED VERT. DEFL.(LL) = L/999 (0.03")
ALLOWABLE DEFL.(TL) = L/360 (0.83")
CALCULATED VERT. DEFL.(TL) = L/999 (0.07")

CSI: TC=0.34/1.00 (4-5:1), BC=0.22/1.00 (10-11:1)
WB=0.23/1.00 (2-13:1), SSI=0.17/1.00 (4-5:1)

DOL LUMBER=1.00 NAIL=1.00 LS BEND=1.10
COMP=1.10 SHEAR=1.10 TENS=1.10

COMPANION LIVE LOAD FACTOR = 0.50

TRUSS PLATE MANUFACTURER IS NOT RESPONSIBLE FOR QUALITY CONTROL IN THE TRUSS MANUFACTURING PLANT.

NAIL VALUES
PLATE GRIP(DRY) SHEAR SECTION
(PSI) (PLI) (PLI)
MAX MIN MAX MIN MAX MIN
MT20 618 354 1667 822 2284 1656

PLATE PLACEMENT TOL. = 0.250 inches

PLATE ROTATION TOL. = 5.0 Deg.

JSI GRIP= 0.89 (5) (INPUT = 0.90)
JSI METAL= 0.42 (2) (INPUT = 1.00)



READ ALL NOTES ON THIS PAGE AND ON ENGINEERING NOTE PAGE ENP-1. THIS NOTE PAGE IS AN INTEGRAL PART OF THIS DRAWING AS IT CONTAINS SPECIFICATIONS AND CRITERIA USED IN THE DESIGN OF THIS COMPONENT.




BEARING ANCHORAGE BY TOE-NAILS FOR LATERAL CAPACITY

B37579H1

NAIL TYPE	LENGTH (IN)	DIAMETER (IN)	NAIL LATERAL CAPACITY (LB)	
			S-P-F	D. FIR
COMMON WIRE	3.00	0.144	132	147
	3.25	0.144	132	147
	3.50	0.160	159	177

NOTES:

1. Rafter and ceiling members may be anchored to top and bottom chords of girder truss by toe-nailing rafter and ceiling members to girder chords provided the reaction does not exceed the lateral capacities in the table. Hangers (specified by others) are required for reactions higher than the maximum toe-nail capacity. Reactions are based on factored loads.
2. Toe nail capacities shown in the table are for **one** toe-nail. For additional toe-nails multiply values in table by the number of toe-nails used. Toe-nail capacities take into account toe-nailing factor J_A in CSA O86-09, section 10.9.4.1.
3. For 9- 3/4 gauge 3.25" common wire gun nails (diameter = 0.120") use 3" common spiral nail values.
4. Maximum number of toe-nails allowed depends on the lumber size & species to be toe-nailed to supporting member and nail diameter, as shown in tables below.
5. Nail values in table are based on the following relative lumber densities: $G = 0.42$ (SPF), $G = 0.49$ (D. Fir).
6. Toe-nails shall be driven at approximately 1/3 the nail length from the edge of the joist/truss chord and driven at an angle of 30° to the grain of the member (See next page for nailing on bearing plate).
7. For loads due to **wind** the nail lateral capacity in this table may be multiplied by 1.15 (K_D factor).
8. Lumber must be dry (< 19% moisture content) at the time of nail installation.
9. Nail values in this table comply with CSA O86-09, section 10.9.4
10. This design is not valid after April 30, 2019.



Nail type	Common wire	Common spiral	Common wire
Nail dia. (in)	0.160	0.152	0.144
	(3.5" nail)		(3" and 3.25" nail)
LUMBER SIZE	MAXIMUM NUMBER OF TOE-NAILS		
2X4 SPF	2	2	3
2X4 D. Fir	2	2	2
2X6 SPF	4	4	4
2X6 D. Fir	3	3	3



MiTek Canada Inc
100 Industrial Rd.
Bradford, Ontario L3Z 3G7

PEO
Certificate No. 10889485



April 26, 2017

BEARING ANCHORAGE BY TOE-NAILS FOR WIND LOADING

B37579H2



NAIL TYPE	LENGTH (IN)	DIAMETER (IN)	NAIL WITHDRAWAL CAPACITY (LB)	
			S-P-F	D. FIR
COMMON WIRE	3.00	0.144	30	42
	3.25	0.144	32	45
	3.50	0.160	38	52

Note: If using truss with D. Fir lumber and S-P-F bearing plate, use values in table for S-P-F.



NOTES:

1. Truss chord, rafter, or ceiling members may be anchored to bearing plate by toe-nails, provided that the actual factored uplift force due to **wind or earthquake** load does not exceed the withdrawal capacities in the table. Hangers (specified by others) are required for uplift forces that are higher than the maximum toe-nail withdrawal capacity.
2. Toe nail capacities shown in the table are for **one** toe-nail. For additional toe-nails multiply values in table by the number of toe-nails used. Toe-nail capacities take into account toe-nailing factor J_A in CSA O86-09, section 10.9.5.2.
3. For 9- 3/4 gauge 3.25" common wire gun nails (diameter = 0.120") use 3" common spiral nail values.
4. Maximum number of toe-nails allowed depends on the lumber size & species to be toe-nailed to supporting member and nail diameter, as shown in table above.
5. Nail values in table are based on the following relative lumber densities: $G = 0.42$ (SPF), $G = 0.49$ (D. Fir).
6. Toe-nails shall be driven at approximately 1/3 the nail length from the edge of the joist/truss chord and driven at an angle of 30° to the grain of the member (See drawing on detail B37579H1).
7. Lumber must be dry (< 19% moisture content) at the time of nail installation.
8. Nail values in this table comply with CSA O86-09, section 10.9.5
9. This design is not valid after April 30, 2019

Toe-nailing on 2x6 Bearing Plate



Toe-nailing on 2x4 Bearing Plate



MiTek Canada Inc
100 Industrial Rd.
Bradford, Ontario L3Z 3G7

PEO
Certificate No. 10889485



April 26, 2017