

ENGINEERING NOTE PAGE (ENP-1)
PLEASE READ PRIOR TO INSTALLATION

NE0818-100
GREENPARK-MINNISALE
HOMES-HEMLOCK 4 EL 1

LOT 35 L.

RESPONSIBILITIES

THIS DESIGN IS FOR AN INDIVIDUAL BUILDING COMPONENT AND HAS BEEN BASED ON INFORMATION PROVIDED BY THE DESIGN OFFICE OF KOTT LUMBER. THE UNDERSIGNED ENGINEER DISCLAIMS ANY RESPONSIBILITY FOR DAMAGES AS A RESULT OF FAULTY OR INCORRECT INFORMATION, SPECIFICATION AND/OR DESIGNS FURNISHED TO THE ENGINEER. THE UNDERSIGNED ENGINEER IS ONLY RESPONSIBLE FOR THE STRUCTURAL INTEGRITY OF THIS BUILDING COMPONENT FOR THE CONDITIONS AND LOADS SHOWN ON THIS DRAWING. THE STRUCTURAL INTEGRITY OF THE BUILDING AND THE VERIFICATION OF THE DIMENSIONS AND THE DESIGN LOADS USED ARE THE RESPONSIBILITY OF THE BUILDING DESIGNER.

TRUSSES ARE DESIGNED IN CONFORMANCE WITH THE RELEVANT SECTIONS OF THE NATIONAL BUILDING CODE OF CANADA OR THE CANADIAN CODE FOR FARM BUILDINGS, WHICHEVER APPLIES TO THE BUILDING TYPE INDICATED ON THE DRAWING

IT IS THE RESPONSIBILITY OF KOTT LUMBER TO ENSURE THAT TRUSSES ARE MANUFACTURED IN CONFORMANCE WITH THESE DESIGNS AND WITH THE SPECIFICATIONS OUTLINED BELOW. THE UNDERSIGNED ENGINEER IS NOT RESPONSIBLE FOR QUALITY CONTROL IN THE TRUSS MANUFACTURING PLANT.

USE AND OCCUPANCY

- The building is of the type indicated on the drawing

LOADING

- The truss loading intensity and distribution as well as load transfer mechanism is that indicated on the drawing
- No buildings, trees, parapets or other projections higher than the roof for which the trusses are used are located within a distance less than ten (10) times the difference in height, or five metres (16 ft) whichever is greater, unless the drawing indicates that the snow drifting has been taken into account

HANDLING, INSTALLATION AND BRACING

- The trusses must be handled and installed by a qualified professional as per the supplied document titled *Information for Truss Installers* and the BCSI-B1 and BCSI-B3 Summary Sheets
- The compression chords are laterally braced by continuous rigid diaphragm sheathing or as specified on the drawing
- Temporary and permanent bracing must be installed as indicated on the truss drawing and according to the BCSI-B1 and BCSI-B3 Summary Sheets. Bracing for the lateral stability of the truss is to be provided by the building designer
- It is recommended that a Professional Engineer's advice be obtained for the bracing of trusses spanning more than 12.37m (40'-7")


SUPPORTS

- The trusses are to be supported at the bearing points indicated and anchored to the supports where considered necessary by the designer of the overall structure
- Bearing sizes shown are the minimum required to prevent crushing of the truss members and do not necessarily take into account stability of the overall building structure
- Elevation of bearings must be carefully checked and shimmed to alignment for solid bearings
- Adequate wood truss bearing is the responsibility of the building designer.

DIMENSIONS

- Geometry of the truss and dimensions indicated on the drawing are identical to those of the installed truss.

READ ALL NOTES ON THIS PAGE AND ON
ENGINEERING NOTE PAGE ENP-1. THIS
NOTE PAGE IS AN INTEGRAL PART OF
THIS DRAWING AS IT CONTAINS
SPECIFICATIONS AND CRITERIA USED IN
THE DESIGN OF THIS COMPONENT.



see attached layout

THIS CERTIFICATION IS FOR THE ENGINEERING REVIEW OF
STRUCTURAL COMPONENTS SHOWN ON THIS DRAWING
AND IS LIMITED TO THE COMPONENTS SUPPLIED BY KOTT
LUMBER FOR THE LOADS AND CONDITIONS SHOWN ON
THE CALCULATION PAGE OF EACH COMPONENT. THE
PLACEMENT OF THESE COMPONENTS ON THIS LAYOUT IS
SHOWN FOR REFERENCE ONLY. ROOF TRUSSES MUST BE
INSTALLED ACCORDING TO MANUFACTURER'S GUIDELINES
AT 24" C/C UNLESS NOTED OTHERWISE. CONVENTIONAL
FRAMING SHOWN ON THE LAYOUT MUST BE DESIGNED
AND APPROVED BY THE PROJECT ENGINEER. TEMPORARY
AND PERMANENT BRACINGS OF THE ROOF AND BUILDING
ARE THE RESPONSIBILITY OF THE PROJECT ENGINEER
AND TO CONFORM TO BCSI GUIDELINES.

Architectural Drawing Info:
Date: JULY 23, 2016
Project number: 18012
Model: HEMLOCK 4



CONVENTIONAL FRAMING BY OTHERS

ALL CONVENTIONAL FRAMING TO CONFORM WITH
PART 8 OF THE C.B.C.
ROOF RAFTERS THAT CROSS MEET OVER TRUSSES
TO BE 2x6 S.F.P. @ 24"OC WITH A 2x4 VERTICAL
POST TO THE TRUSS' UNDERWEATH EACH CROSS
POINT. VERTICAL POST LONGER THAN 8' TO HAVE
LATERAL BRACING SO THAT THE DISTANCE BETWEEN
END POINT AND BETWEEN ROWS OF BRACING
DOES NOT EXCEED 8'.

SIZE AND LOCATION OF CONVENTIONAL FRAMING
IS APPROXIMATE. ALL AREAS MAY NOT BE SHOWN.
REFER TO ARCHITECTURAL PLANS FOR DETAILS.


HANGER LEGEND:

- ▼ LUS24
- LUS26DS
- HGUS26
- ✕ HGUS26-2

DESIGN CRITERIA
SPECIFIED LOADS:
TOP CH. LL = 25.3 PSF
BOT CH. LL = 0.75 PSF
TOTAL LOAD = 26.05 PSF
SPACING = 24" OC.

THIS TRUSS IS DESIGNED FOR RESIDENTIAL OR
SMALL BUILDING REQUIREMENTS OF PART 8, MISC 2016
THIS DESIGN COMPLETES WITH:
- PART 8 OF CBC 2012, CBC 2012, ASH 2014
- CANADIAN
- TYP 2011

Model: HEMLOCK 4 EL 1
Customer: GREENPARK
Project: MINNISALE HOMES
Location: BRAMPTON
Date: 6/20/2018 Drawn by: BB



LUMBER

N. L. G. A. RULES

CHORDS	SIZE	DRY	LUMBER	DESCR.
1 - 3	2x4	DRY	No.2	SPF
3 - 6	2x4	DRY	No.2	SPF
6 - 8	2x4	DRY	No.2	SPF
15 - 2	2x4	DRY	No.2	SPF
9 - 7	2x4	DRY	No.2	SPF
15 - 11	2x4	DRY	No.2	SPF
11 - 9	2x4	DRY	No.2	SPF
ALL WEBS	2x3	DRY	No.2	SPF

EXCEPT

DRY: SEASONED LUMBER.

PLATES (table is in inches)

JT	TYPE	PLATES	W	LEN	Y	X
2	TMVW-t	MT20	5.0	6.0	1.75	3.00
3	TTWW+m	MT20	6.0	6.0	2.25	2.00
4	TMW+w	MT20	2.0	4.0		
5	TMWW-t	MT20	3.0	4.0		
6	TTWW+m	MT20	6.0	6.0	2.25	2.00
7	TMVW-t	MT20	5.0	6.0	1.75	3.00
9	BMV1+p	MT20	2.0	4.0	2.25	1.00
10	BMWW-t	MT20	3.0	8.0	1.50	3.25
11	BS-t	MT20	3.0	6.0		
12	BMWW-t	MT20	4.0	4.0	1.75	1.75
13	BMWW-t	MT20	5.0	6.0	2.25	2.00
14	BMWW-t	MT20	3.0	8.0	1.50	3.25
15	BMV1+p	MT20	2.0	4.0	2.25	1.00

HANGERS NOTES

1) SPECIAL HANGER(S) OR CONNECTION(S) REQUIRED TO SUPPORT CONCENTRATED LOAD(S) 267.4 lbs FACTORED DOWN AT 17-5-11, AND 267.4 lbs FACTORED DOWN AT 4-7-5 ON TOP CHORD. DESIGN FOR UNSPECIFIED CONNECTION(S) IS DELEGATED TO THE BUILDING DESIGNER.

DIMENSIONS, SUPPORTS AND LOADINGS SPECIFIED BY FABRICATOR TO BE VERIFIED BY BUILDING DESIGNER

BEARINGS

JT	FACTORED GROSS REACTION		MAXIMUM FACTORED GROSS REACTION		INPUT BRG	REQD BRG
	VERT	HORZ	DOWN	HORZ		
15	2033	0	2033	0	5-8	5-8
9	2033	0	2033	0	5-8	5-8

UNFACTORED REACTIONS							
JT	1ST LCASE	MAX./MIN. COMPONENT REACTIONS					
	COMBINED	SNOW	LIVE	PERM.LIVE	WIND	DEAD	SOIL
15	1425	1004 / 0	0 / 0	0 / 0	0 / 0	421 / 0	0 / 0
9	1425	1004 / 0	0 / 0	0 / 0	0 / 0	421 / 0	0 / 0

BEARING MATERIAL TO BE SPF NO.2 OR BETTER AT JOINT(S) 15, 9

BRACING
TOP CHORD TO BE SHEATHED OR MAX. PURLIN SPACING = 3.61 FT.
MAX. UNBRACED BOTTOM CHORD LENGTH = 10.00 FT OR RIGID CEILING DIRECTLY APPLIED.

ALL PITCH BREAKS AND PERIMETER CORNER JOINTS MUST BE Laterally RESTRAINED.

LOADING
TOTAL LOAD CASES: (4)

CHORDS				WEBS			
MEMB.	MAX. FACTORED FORCE (LBS)	FACTORED VERT. LOAD (PLF)	MAX LC1 (LC)	MAX. UNBRAC LENGTH	MEMB.	MAX. FACTORED FORCE (LBS)	MAX LC1 (LC)
FR-TO		FROM TO			FR-TO		
1-2	0 / 29	-77.4 -77.4	0.11 (1)	10.00	14-3	-259 / 65	0.08 (1)
2-3	-2255 / 0	-77.4 -77.4	0.45 (1)	4.08	3-13	0 / 1152	0.29 (1)
3-4	-2697 / 0	-145.9 -145.9	0.51 (1)	3.63	13-4	-669 / 0	0.21 (1)
4-5	-2697 / 0	-145.9 -145.9	0.52 (1)	3.62	13-5	-4 / 0	0.00 (1)
5-6	-2700 / 0	-145.9 -145.9	0.52 (1)	3.61	12-5	-670 / 0	0.21 (1)
6-7	-2255 / 0	-77.4 -77.4	0.45 (1)	4.08	12-6	0 / 1157	0.29 (1)
7-8	0 / 29	-77.4 -77.4	0.11 (1)	10.00	10-6	-261 / 65	0.08 (1)
15-2	-1969 / 0	0.0 0.0	0.22 (1)	5.95	2-14	0 / 1922	0.48 (1)
9-7	-1968 / 0	0.0 0.0	0.22 (1)	5.96	10-7	0 / 1922	0.48 (1)
15-14	0 / 0	-33.0 -33.0	0.18 (4)	10.00			
14-13	0 / 1867	-33.0 -33.0	0.43 (1)	10.00			
13-12	0 / 2700	-33.0 -33.0	0.55 (1)	10.00			
12-11	0 / 1867	-33.0 -33.0	0.43 (1)	10.00			
11-10	0 / 1867	-33.0 -33.0	0.43 (1)	10.00			
10-9	0 / 0	-33.0 -33.0	0.18 (4)	10.00			

FACTORED CONCENTRATED LOADS (LBS)

JT	LOC.	LC1	MAX-	MAX+	FACE	DIR.	TYPE
3	4-7-5	-267	-267	---	FRONT	VERT	TOTAL
6	17-5-11	-267	-267	---	FRONT	VERT	TOTAL

DESIGN CRITERIA

SPECIFIED LOADS:
TOP CH. LL = 23.3 PSF
DL = 3.0 PSF
BOT CH. LL = 0.0 PSF
DL = 7.0 PSF
TOTAL LOAD = 33.3 PSF

SPACING = 24.0 IN. C/C

LOADING IN FLAT SECTION BASED ON A SLOPE OF 2.00/12 MINIMUM

GIRDER TYPE: CPrimeHip
SIDE SETBACK = 4-7-5
END SETBACK = 6-0-0
END WALL WIDTH = 5-8
CORNER FRAMING TYPE: CONVENTIONAL
END JACK TYPE: CONVENTIONAL
APPLIED TO FRONT SIDE
- ADDTL LOADS BASED ON 55 % OF GSL.

THIS TRUSS IS DESIGNED FOR RESIDENTIAL OR SMALL BUILDING REQUIREMENTS OF PART 9, NBCC 2010

THIS DESIGN COMPLIES WITH:
- PART 9 OF OBC 2012, BCBC 2012, ABC 2014
- CSA 086-09
- TPIC 2011

(55 % OF 27.2 P.S.F. G.S.L. PLUS 8.4 P.S.F. RAIN LOAD) EQUALS 23.3 P.S.F. SPECIFIED ROOF LIVE LOAD

ALLOWABLE DEFL.(LL)= L/360 (0.74")
CALCULATED VERT. DEFL.(LL)= L/999 (0.09")
ALLOWABLE DEFL.(TL)= L/360 (0.74")
CALCULATED VERT. DEFL.(TL)= L/999 (0.17")

CSI: TC=0.52/1.00 (5-6-1), BC=0.55/1.00 (12-13-1), WB=0.48/1.00 (2-14-1), SSI=0.32/1.00 (5-6-1)

DOL LUMBER=1.00 NAIL=1.00 LS BEND=1.00
COMP=1.00 SHEAR=1.00 TENS=1.00

COMPANION LIVE LOAD FACTOR = 0.50

TRUSS PLATE MANUFACTURER IS NOT RESPONSIBLE FOR QUALITY CONTROL IN THE TRUSS MANUFACTURING PLANT .

NAIL VALUES
PLATE GRIP(DRY) SHEAR SECTION
(PSI) (PLI) (PLI)
MAX MIN MAX MIN MAX MIN
MT20 618 354 1667 822 2284 1656

CONTINUED ON PAGE 2



READ ALL NOTES ON THIS PAGE AND ON ENGINEERING NOTE PAGE ENP-1. THIS NOTE PAGE IS AN INTEGRAL PART OF THIS DRAWING AS IT CONTAINS SPECIFICATIONS AND CRITERIA USED IN THE DESIGN OF THIS COMPONENT.


JOB NAME	TRUSS NAME	QUANTITY	PLY	JOB DESC.	GREENPARK-MINNISALE HOMES-HEMLOCK 4 EL 1	DRWG NO.
NE0818-100	G01	1	1	TRUSS DESC.		PAGE 4 OF 31

Version 8.210 S Mar 12 2018 MiTek Industries, Inc. Thu Aug 16 13:39:15 2018 Page 2
ID:eu6n2?latr9jLP2IXToTi6z4Q5d-Cwhh0KT4hVemyRZf2dCrAw00nmKRrRoWqzr5_AynGiv

PLATE PLACEMENT TOL. = 0.250 inches
PLATE ROTATION TOL. = 5.0 Deg.
JSI GRIP= 0.89 (14) (INPUT = 0.90)
JSI METAL= 0.60 (2) (INPUT = 1.00)

READ ALL NOTES ON THIS PAGE AND ON
ENGINEERING NOTE PAGE ENP-1. THIS
NOTE PAGE IS AN INTEGRAL PART OF
THIS DRAWING AS IT CONTAINS
SPECIFICATIONS AND CRITERIA USED IN
THE DESIGN OF THIS COMPONENT.





LUMBER

N. L. G. A. RULES

CHORDS

SIZE

LUMBER

DESCR.

SPF

DRY: SEASONED LUMBER.

ALL WEBS EXCEPT

2x3

DRY

No.2

SPF

FACTORED CONCENTRATED LOADS (LBS)

JT

LOC.

LC1

MAX-

MAX+

FACE

DIR.

TYPE

TOTAL

11

5-10-12

-556

-556

-

FRONT

VERT

DIMENSIONS, SUPPORTS AND LOADINGS SPECIFIED BY FABRICATOR TO BE VERIFIED BY BUILDING DESIGNER

BEARINGS

FACTORED

GROSS REACTION

VERT

HORZ

MAXIMUM FACTORED

GROSS REACTION

DOWN

HORZ

UPLIFT

IN-SX

REQD

BRG

IN-SX

JT

13

1992

0

1992

0

0

5-8

5-8

8

1613

0

1613

0

0

5-8

5-8

UNFACTORED REACTIONS

1ST LCASE

MAX/MIN. COMPONENT REACTIONS

JT

13

1396

990 / 0

0 / 0

0 / 0

0 / 0

406 / 0

0 / 0

8

1132

792 / 0

0 / 0

0 / 0

0 / 0

340 / 0

0 / 0

BEARING MATERIAL TO BE SPF NO.2 OR BETTER AT JOINT(S) 13, 8

BRACING

TOP CHORD TO BE SHEATHED OR MAX. PURLIN SPACING = 4.64 FT.

MAX. UNBRACED BOTTOM CHORD LENGTH = 10.00 FT OR RIGID CEILING DIRECTLY APPLIED.

ALL PITCH BREAKS AND PERIMETER CORNER JOINTS MUST BE Laterally RESTRAINED.

LOADING

TOTAL LOAD CASES: (4)

CHORDS

MEMB.

MAX. FACTORED

FORCE

(LBS)

FACTORED

VERT. LOAD

LC1

MAX

CS1 (LC)

WEBS

MEMB.

MAX. FACTORED

FORCE

(LBS)

MAX

CS1 (LC)

FR-TO

1-2

0 / 29

-77.4

-77.4

0.11 (1)

10.00

12-3

-151 / 32

0.03 (1)

2-3

-1900 / 0

-116.8

-116.8

0.21 (1)

4.64

3-11

-233 / 0

0.07 (1)

3-4

-1747 / 0

-116.8

-116.8

0.20 (1)

4.82

11-4

0 / 957

0.24 (1)

4-5

-1322 / 0

-77.4

-77.4

0.14 (1)

5.44

4-10

-272 / 0

0.15 (1)

5-6

-1588 / 0

-77.4

-77.4

0.13 (1)

5.08

10-5

0 / 678

0.17 (1)

6-7

-1642 / 0

-77.4

-77.4

0.14 (1)

5.02

10-6

-98 / 0

0.03 (1)

13-2

-1832 / 0

0.0

0.0

0.20 (1)

6.13

9-6

-166 / 0

0.03 (1)

8-7

-1459 / 0

0.0

0.0

0.16 (1)

6.73

2-12

0 / 1677

0.42 (1)

9-7

0 / 1446

0.36 (1)

13-12

0 / 0

-110.4

-110.4

0.09 (1)

10.00

12-11

0 / 1597

-110.4

-110.4

0.29 (1)

10.00

11-10

0 / 1454

-101.5

-101.5

0.27 (1)

10.00

10-9

0 / 1376

-101.5

-101.5

0.26 (1)

10.00

9-8

0 / 0

-101.5

-101.5

0.09 (1)

10.00

DESIGN CRITERIA

*** SPECIAL LOADS ANALYSIS ***

GEOMETRY AND/OR BASIC LOADS CHANGED BY USER.

LOADS WERE DERIVED FROM USER INPUT NO FURTHER MODIFICATIONS WERE MADE

SPECIFIED LOADS:

TOP CH. LL = 23.3 PSF

DL = 3.0 PSF

BOT CH. LL = 0.0 PSF

DL = 7.0 PSF

TOTAL LOAD = 33.3 PSF

SPACING = 24.0 IN. C/C

LOADING IN FLAT SECTION BASED ON A SLOPE OF 2.00/12 MINIMUM

GIRDER TYPE: CPrimeHlp

SIDE SETBACK = 0-0

END SETBACK = 4-6-0

END WALL WIDTH = 5-8

CORNER FRAMING TYPE: CONVENTIONAL

END JACK TYPE: CONVENTIONAL

APPLIED TO FRONT SIDE

- ADDTL LOADS BASED ON 55 % OF GSL.

LOADS APPLIED TO FIRST 5-10-12 OF SPAN MEASURED FROM THE LEFT.

GIRDER TYPE: CStdGirder

START DISTANCE = 0-0

START SPAN CARRIED = 5-6-8

END DISTANCE = 14-10-0

END SPAN CARRIED = 5-6-8

END WALL WIDTH = 0-0

APPLIED TO BACK SIDE OF BOTTOM CHORD.

- ADDTL LOADS BASED ON 55 % OF GSL.

*** NON STANDARD GIRDER ***

ADDTL USER-DEFINED LOADS APPLIED TO ALL LOAD CASES.

THIS TRUSS IS DESIGNED FOR RESIDENTIAL OR SMALL BUILDING REQUIREMENTS OF PART 9, NBCC 2010

THIS DESIGN COMPLIES WITH:

- PART 9 OF OBC 2012, BCBC 2012, ABC 2014

- CSA 086-09

- TPIC 2011

(55 % OF 27.2 P.S.F. G.S.L. PLUS 8.4 P.S.F. RAIN LOAD) EQUALS 23.3 P.S.F. SPECIFIED ROOF LIVE LOAD

ALLOWABLE DEFL.(LL)= L/360 (0.49")

CALCULATED VERT. DEFL.(LL) = L/999 (0.03")

ALLOWABLE DEFL.(TL)= L/360 (0.49")

CALCULATED VERT. DEFL.(TL) = L/999 (0.06")

CONTINUED ON PAGE 2

READ ALL NOTES ON THIS PAGE AND ON ENGINEERING NOTE PAGE ENP-1. THIS NOTE PAGE IS AN INTEGRAL PART OF THIS DRAWING AS IT CONTAINS SPECIFICATIONS AND CRITERIA USED IN THE DESIGN OF THIS COMPONENT.

LICENSED PROFESSIONAL ENGINEER

N.A. EL-MASRI

Aug 16, 2018

KOTT

JOB NAME	TRUSS NAME	QUANTITY	PLY	JOB DESC.	DRWG NO.
NE0818-100	G02	1	1	GREENPARK-MINNISALE HOMES-HEMLOCK 4 EL 1	PAGE 6 OF 31
TRUSS DESC.					

Version 8.210 S Mar 12 2018 MiTek Industries, Inc. Thu Aug 16 13:39:16 2018 Page 2
ID:eu6n27latr9jLP2IXToTi6z4Q5d-g6F3DgTiSomdab8rclJ4j8ZGMAkdavzg3dafWdynGiv

CSI: TC=0.21/1.00 (2-3:1) , BC=0.29/1.00 (11-12:1)
, WB=0.42/1.00 (2-12:1) , SSI=0.15/1.00 (2-3:1)

DOL LUMBER=1.00 NAIL=1.00 LS BEND=1.00
COMP=1.00 SHEAR=1.00 TENS= 1.00

COMPANION LIVE LOAD FACTOR = 0.50

TRUSS PLATE MANUFACTURER IS NOT
RESPONSIBLE FOR QUALITY CONTROL IN
THE TRUSS MANUFACTURING PLANT .

NAIL VALUES

PLATE	GRIP(DRY)	SHEAR	SECTION
	(PSI)	(PLI)	(PLI)
	MAX MIN	MAX MIN	MAX MIN
MT20	618 354	1667 822	2284 1656


PLATE PLACEMENT TOL. = 0.250 inches

PLATE ROTATION TOL. = 5.0 Deg.

JSI GRIP= 0.90 (2) (INPUT = 0.90)
JSI METAL= 0.48 (12) (INPUT = 1.00)

READ ALL NOTES ON THIS PAGE AND ON
ENGINEERING NOTE PAGE ENP-1. THIS
NOTE PAGE IS AN INTEGRAL PART OF
THIS DRAWING AS IT CONTAINS
SPECIFICATIONS AND CRITERIA USED IN
THE DESIGN OF THIS COMPONENT.





TOTAL WEIGHT = 26 lb [M]

LUMBER	N. L. G. A. RULES	CHORDS	SIZE	LUMBER	DESCR.
1 - 3	2x4	DRY	No.2	SPF	
4 - 3	2x4	DRY	No.2	SPF	
6 - 1	2x4	DRY	No.2	SPF	
6 - 4	2x4	DRY	No.2	SPF	
ALL WEBS EXCEPT	2x3	DRY	No.2	SPF	

DRY: SEASONED LUMBER.

PLATES (table is in inches)

JT	TYPE	PLATES	W	LEN	Y	X
1	TMVW-1	MT20	3.0	5.0	1.50	1.75
2	TMVW-1	MT20	3.0	4.0	1.50	1.25
3	TMV+p	MT20	2.0	4.0		
4	BMVW1-1	MT20	3.0	4.0		
5	BMVW-1	MT20	3.0	4.0		
6	BMV1+p	MT20	2.0	4.0		

DIMENSIONS, SUPPORTS AND LOADINGS SPECIFIED BY FABRICATOR TO BE VERIFIED BY BUILDING DESIGNER

BEARINGS		FACTORED		MAXIMUM FACTORED			INPUT	REQRD
	GROSS REACTION		GROSS REACTION			BRG	BRG	
JT	VERT	HORZ	DOWN	HORZ	UPLIFT	IN-SX	IN-SX	
4	556	0	556	0	0	MECHANICAL		
6	556	0	556	0	0	5-8	5-8	

A SUITABLE MECHANICAL CONNECTION IS REQUIRED AT JOINT 4 TO RESIST THE MAX FACTORED REACTIONS.

UNFACTORED REACTIONS

1ST LCASE		MAX./MIN. COMPONENT REACTIONS					
JT	COMBINED	SNOW	LIVE	PERM.LIVE	WIND	DEAD	SOIL
4	390	273 / 0	0 / 0	0 / 0	0 / 0	117 / 0	0 / 0
6	390	273 / 0	0 / 0	0 / 0	0 / 0	117 / 0	0 / 0

BEARING MATERIAL TO BE SPF NO.2 OR BETTER AT JOINT(S) 6

BRACING

TOP CHORD TO BE SHEATHED OR MAX. PURLIN SPACING = 6.25 FT.
MAX. UNBRACED BOTTOM CHORD LENGTH = 10.00 FT OR RIGID CEILING DIRECTLY APPLIED.

ALL PITCH BREAKS AND PERIMETER CORNER JOINTS MUST BE Laterally RESTRAINED.

LOADING

TOTAL LOAD CASES: (4)

CHORDS	MAX. FACTORED MEMB. FORCE (LBS)	FACTORED VERT. LOAD (PLF)	MAX. FACTORED VERT. LOAD (LC) (1)	MAX. FACTORED VERT. LOAD (LC) (2)	MAX. FACTORED VERT. LOAD (LC) (3)	MAX. FACTORED VERT. LOAD (LC) (4)	MAX. FACTORED VERT. LOAD (LC) (5)
FR-TO		FROM	TO	UNBRACED LENGTH	FR-TO		
1-2	-296 / 0	-77.4	-77.4	0.07 (1)	6.25	5-2	0 / 329
2-3	-13 / 0	-77.4	-77.4	0.07 (1)	6.25	2-4	-418 / 0
4-3	-65 / 0	0.0	0.0	0.03 (1)	7.81	1-5	0 / 272
6-1	-401 / 0	0.0	0.0	0.05 (1)	7.81		
6-5	0 / 0	-169.7	-169.7	0.14 (1)	10.00		
5-4	0 / 236	-169.7	-169.7	0.18 (1)	10.00		

DESIGN CRITERIA

SPECIFIED LOADS:
TOP CH. LL = 23.3 PSF
DL = 3.0 PSF
BOT CH. LL = 0.0 PSF
DL = 7.0 PSF
TOTAL LOAD = 33.3 PSF

SPACING = 24.0 IN. C/C

GIRDER TYPE: CSldGirder
START DISTANCE = 0-0
START SPAN CARRIED = 8-10-8
END DISTANCE = 4-6-0
END SPAN CARRIED = 8-10-8
END WALL WIDTH = 5-8
APPLIED TO FRONT SIDE OF BOTTOM CHORD.
- ADD'L LOADS BASED ON 55% OF GSL.

THIS TRUSS IS DESIGNED FOR RESIDENTIAL OR SMALL BUILDING REQUIREMENTS OF PART 9, NBCC 2010

THIS DESIGN COMPLIES WITH:
- PART 9 OF OBC 2012, BCBC 2012, ABC 2014
- CSA 086-09
- TPIC 2011

(55% OF 27.2 P.S.F. G.S.L. PLUS 8.4 P.S.F. RAIN LOAD) EQUALS 23.3 P.S.F. SPECIFIED ROOF LIVE LOAD

ALLOWABLE DEFL.(LL)= L/360 (0.19")
CALCULATED VERT. DEFL.(LL)= L/999 (0.00")
ALLOWABLE DEFL.(TL)= L/360 (0.19")
CALCULATED VERT. DEFL.(TL)= L/999 (0.01")

CSI: TC=0.07/1.00 (1-2:1), BC=0.18/1.00 (4-5:1), WB=0.11/1.00 (2-4:1), SSI=0.20/1.00 (5-6:1)

DOL LUMBER=1.00 NAIL=1.00 LS BEND=1.00
COMP=1.00 SHEAR=1.00 TENS=1.00

COMPANION LIVE LOAD FACTOR = 0.50

TRUSS PLATE MANUFACTURER IS NOT RESPONSIBLE FOR QUALITY CONTROL IN THE TRUSS MANUFACTURING PLANT.

NAIL VALUES	PLATE GRIP(DRY)	SHEAR (PSI)	SECTION (PLI)
	MAX	MIN	MAX
MT20	618	354	1667

PLATE PLACEMENT TOL. = 0.250 inches

PLATE ROTATION TOL. = 5.0 Deg.

CONTINUED ON PAGE 2



READ ALL NOTES ON THIS PAGE AND ON ENGINEERING NOTE PAGE ENP-1. THIS NOTE PAGE IS AN INTEGRAL PART OF THIS DRAWING AS IT CONTAINS SPECIFICATIONS AND CRITERIA USED IN THE DESIGN OF THIS COMPONENT.



JOB NAME	TRUSS NAME	QUANTITY	PLY	JOB DESC.	GREENPARK-MINNISALE HOMES-HEMLOCK 4 EL 1	DRWG NO.
NE0818-100	G03	1	1	TRUSS DESC.		PAGE 8 OF 31


Version 8.210 S Mar 12 2018 MiTek Industries, Inc. Thu Aug 16 13:39:16 2018 Page 2
ID:eu6n2?latr9jLP2lXToTi6z4Q5d-g6F3DgTiSomdab8rcLj4j8ZleAmQa_jg3dafWdynGiv

JSI GRIP= 0.66 (5) (INPUT = 0.90)
JSI METAL= 0.12 (5) (INPUT = 1.00)

READ ALL NOTES ON THIS PAGE AND ON
ENGINEERING NOTE PAGE ENP-1. THIS
NOTE PAGE IS AN INTEGRAL PART OF
THIS DRAWING AS IT CONTAINS
SPECIFICATIONS AND CRITERIA USED IN
THE DESIGN OF THIS COMPONENT.



-1-3-8 0-0 4-7-5 4-7-5 4-3-14 8-11-3 4-2-10 13-1-13 4-3-14 17-5-11 4-7-5 22-1-0 1-3-8 23-4-8
Scale = 1:38.6



TOTAL WEIGHT = 92 lb [M]

LUMBER				N. L. G. A. RULES	
CHORDS	SIZE	LUMBER	DESCR.	SPF	SPF
1 - 3	2x4	DRY	No.2	SPF	SPF
3 - 6	2x4	DRY	No.2	SPF	SPF
6 - 8	2x4	DRY	No.2	SPF	SPF
15 - 2	2x4	DRY	No.2	SPF	SPF
9 - 7	2x4	DRY	No.2	SPF	SPF
15 - 11	2x4	DRY	No.2	SPF	SPF
11 - 9	2x4	DRY	No.2	SPF	SPF
ALL WEBS EXCEPT	2x3	DRY	No.2	SPF	SPF

DRY: SEASONED LUMBER.

PLATES (table is in inches)

JT	TYPE	PLATES	W	LEN	Y	X
2	TMVW-t	MT20	5.0	6.0	1.75	3.00
3	TTWW+m	MT20	6.0	6.0	2.25	2.00
4	TMW+w	MT20	2.0	4.0		
5	TMWW-t	MT20	3.0	4.0		
6	TTWW+m	MT20	6.0	6.0	2.25	2.00
7	TMVW-t	MT20	5.0	6.0	1.75	3.00
9	BMV1+p	MT20	2.0	4.0	2.25	1.00
10	BMWW-t	MT20	3.0	8.0	1.50	3.25
11	BS-t	MT20	3.0	6.0		
12	BMWW-t	MT20	4.0	4.0	1.75	1.75
13	BMWW-t	MT20	5.0	6.0	2.25	2.00
14	BMWW-t	MT20	3.0	8.0	1.50	3.25
15	BMV1+p	MT20	2.0	4.0	2.25	1.00

HANGERS NOTES

- SPECIAL HANGER(S) OR CONNECTION(S) REQUIRED TO SUPPORT CONCENTRATED LOAD(S) 267.4 lbs FACTORED DOWN AT 17-5-11, AND 267.4 lbs FACTORED DOWN AT 4-7-5 ON TOP CHORD. DESIGN FOR UNSPECIFIED CONNECTION(S) IS DELEGATED TO THE BUILDING DESIGNER.

DIMENSIONS, SUPPORTS AND LOADINGS SPECIFIED BY FABRICATOR TO BE VERIFIED BY BUILDING DESIGNER

BEARINGS				FACTORED				MAXIMUM FACTORED				INPUT				REQRD			
JT	VERT	HORZ	DOWN	HORZ	UPLIFT	IN-SX	IN-SX	BRG	BRG	BRG	BRG	BRG	BRG	BRG	BRG	BRG	BRG	BRG	BRG
15	2033	0	2033	0	0	5-8	5-8												
9	2033	0	2033	0	0	5-8	5-8												

UNFACTORED REACTIONS

1ST LCASE		MAX./MIN. COMPONENT REACTIONS					
JT	COMBINED	SNOW	LIVE	PERM.LIVE	WIND	DEAD	SOIL
15	1425	1004 / 0	0 / 0	0 / 0	0 / 0	421 / 0	0 / 0
9	1425	1004 / 0	0 / 0	0 / 0	0 / 0	421 / 0	0 / 0

BEARING MATERIAL TO BE SPF NO.2 OR BETTER AT JOINT(S) 15, 9

BRACING

TOP CHORD TO BE SHEATHED OR MAX. PURLIN SPACING = 3.61 FT.
MAX. UNBRACED BOTTOM CHORD LENGTH = 10.00 FT OR RIGID CEILING DIRECTLY APPLIED.

ALL PITCH BREAKS AND PERIMETER CORNER JOINTS MUST BE Laterally RESTRAINED.

LOADING

TOTAL LOAD CASES: (4)

CHORDS				WEBS			
MEMB.	MAX. FACTORED FORCE (LBS)	FACTORED VERT. LOAD (PLF)	MAX. FACTORED CSI (LC)	MEMB.	MAX. FACTORED FORCE (LBS)	MAX. FACTORED CSI (LC)	
FR-TO		FROM TO		FR-TO			
1-2	0 / 29	-77.4 -77.4 0.11 (1)	10.00	14-3	-259 / 65	0.08 (1)	
2-3	-2255 / 0	-77.4 -77.4 0.45 (1)	4.08	3-13	0 / 1152	0.29 (1)	
3-4	-2697 / 0	-145.9 -145.9 0.51 (1)	3.63	13-4	-669 / 0	0.21 (1)	
4-5	-2697 / 0	-145.9 -145.9 0.52 (1)	3.62	13-5	-4 / 0	0.00 (1)	
5-6	-2700 / 0	-145.9 -145.9 0.52 (1)	3.61	12-5	-670 / 0	0.21 (1)	
6-7	-2255 / 0	-77.4 -77.4 0.45 (1)	4.08	12-6	0 / 1157	0.29 (1)	
7-8	0 / 29	-77.4 -77.4 0.11 (1)	10.00	10-6	-261 / 65	0.08 (1)	
15-2	-1969 / 0	0.0 0.0 0.22 (1)	5.95	2-14	0 / 1922	0.48 (1)	
9-7	-1968 / 0	0.0 0.0 0.22 (1)	5.96	10-7	0 / 1922	0.48 (1)	
15-14	0 / 0	-33.0 -33.0 0.18 (4)	10.00				
14-13	0 / 1867	-33.0 -33.0 0.43 (1)	10.00				
13-12	0 / 2700	-33.0 -33.0 0.55 (1)	10.00				
12-11	0 / 1867	-33.0 -33.0 0.43 (1)	10.00				
11-10	0 / 1867	-33.0 -33.0 0.43 (1)	10.00				
10-9	0 / 0	-33.0 -33.0 0.18 (4)	10.00				

FACTORED CONCENTRATED LOADS (LBS)

JT	LOC.	LC1	MAX-	MAX+	FACE	DIR.	TYPE
3	4-7-5	-267	-267	---	FRONT	VERT	TOTAL
6	17-5-11	-267	-267	---	FRONT	VERT	TOTAL

DESIGN CRITERIA

SPECIFIED LOADS:

TOP CH.	LL = 23.3	PSF
	DL = 3.0	PSF
BOT CH.	LL = 0.0	PSF
	DL = 7.0	PSF
TOTAL LOAD	= 33.3	PSF

SPACING = 24.0 IN. C/C

LOADING IN FLAT SECTION BASED ON A SLOPE OF 2.00/12 MINIMUM

GIRDER TYPE: CPrimeHip
SIDE SETBACK = 4-7-5
END SETBACK = 6-0-0
END WALL WIDTH = 5-8
CORNER FRAMING TYPE: CONVENTIONAL
END JACK TYPE: CONVENTIONAL
APPLIED TO FRONT SIDE
- ADDTL LOADS BASED ON 55 % OF GSL.

THIS TRUSS IS DESIGNED FOR RESIDENTIAL OR SMALL BUILDING REQUIREMENTS OF PART 9, NBCC 2010

THIS DESIGN COMPLIES WITH:
- PART 9 OF OBC 2012, BCBC 2012, ABC 2014
- CSA 086-09
- TPIC 2011

(55 % OF 27.2 P.S.F. G.S.L. PLUS 8.4 P.S.F. RAIN LOAD) EQUALS 23.3 P.S.F. SPECIFIED ROOF LIVE LOAD

ALLOWABLE DEFL.(LL)= L/360 (0.74")
CALCULATED VERT. DEFL.(LL) = L/ 999 (0.09")
ALLOWABLE DEFL.(TL)= L/360 (0.74")
CALCULATED VERT. DEFL.(TL) = L/ 999 (0.17")

CSI: TC=0.52/1.00 (5-6:1), BC=0.55/1.00 (12-13:1)

, WB=0.48/1.00 (2-14:1), SSI=0.32/1.00 (5-6:1)

DOL LUMBER=1.00 NAIL=1.00 LS BEND=1.00
COMP=1.00 SHEAR=1.00 TENS= 1.00

COMPANION LIVE LOAD FACTOR = 0.50

TRUSS PLATE MANUFACTURER IS NOT RESPONSIBLE FOR QUALITY CONTROL IN THE TRUSS MANUFACTURING PLANT .

NAIL VALUES
PLATE GRIP(DRY) SHEAR SECTION
(PSI) (PLI) (PLI)
MAX MIN MAX MIN MAX MIN
MT20 618 354 1667 822 2284 1656

CONTINUED ON PAGE 2



READ ALL NOTES ON THIS PAGE AND ON ENGINEERING NOTE PAGE ENP-1. THIS NOTE PAGE IS AN INTEGRAL PART OF THIS DRAWING AS IT CONTAINS SPECIFICATIONS AND CRITERIA USED IN THE DESIGN OF THIS COMPONENT.




JOB NAME	TRUSS NAME	QUANTITY	PLY	JOB DESC.	DRWG NO.
NE0818-100	G04	1	1	GREENPARK-MINNISALE HOMES-HEMLOCK 4 EL 1	PAGE 10 OF 31
TRUSS DESC.					

Version 8.210 S Mar 12 2018 MITek Industries, Inc. Thu Aug 16 13:39:17 2018 Page 2
ID:eu6n2?lattr9jLP2lXTToTi6z4Q5d-8JoRR0UKD6uUBkj292FJFL5MGZ0vJLHpIHKC23ynGi

PLATE PLACEMENT TOL. = 0.250 inches
PLATE ROTATION TOL. = 5.0 Deg.
JSI GRIP= 0.89 (14) (INPUT = 0.90)
JSI METAL= 0.60 (2) (INPUT = 1.00)

READ ALL NOTES ON THIS PAGE AND ON
ENGINEERING NOTE PAGE ENP-1. THIS
NOTE PAGE IS AN INTEGRAL PART OF
THIS DRAWING AS IT CONTAINS
SPECIFICATIONS AND CRITERIA USED IN
THE DESIGN OF THIS COMPONENT.





TOTAL WEIGHT = 39 lb (M)

LUMBER					
N. L. G. A.	RULES			LUMBER	DESCR.
CHORDS	SIZE				
16 - 2	2x4	DRY	No.2		SPF
1 - 5	2x4	DRY	No.2		SPF
5 - 9	2x4	DRY	No.2		SPF
10 - 8	2x4	DRY	No.2		SPF
16 - 10	2x4	DRY	No.2		SPF
ALL WEBS	2x3	DRY	No.2		SPF
ALL GABLE WEBS					
	2x3	DRY	No.2		SPF
DRY: SEASONED LUMBER.					
GABLE STUDS SPACED AT 2'-0" OC.					

PLATES (table is in inches)

JT	TYPE	PLATES	W	LEN	Y	X
2	TMV+p	MT20	2.0	4.0		
3, 4, 6, 7						
3	TMW+w	MT20	2.0	4.0		
5	TTW+p	MT20	3.0	4.0	2.25	1.50
8	TMV+p	MT20	2.0	4.0		
10	BMV1+p	MT20	2.0	4.0		
11, 12, 13, 14, 15						
11	BMW1+w	MT20	2.0	4.0		
16	BMV1+p	MT20	2.0	4.0		

DIMENSIONS, SUPPORTS AND LOADINGS SPECIFIED BY FABRICATOR TO BE VERIFIED BY BUILDING DESIGNER

BEARINGS
THIS TRUSS DESIGNED FOR CONTINUOUS BEARINGS.
THIS TRUSS REQUIRES RIGID SHEATHING ON EXPOSED FACE.
BEARING MATERIAL TO BE SPF NO.2 OR BETTER AT JOINT(S)

BRACING
TOP CHORD TO BE SHEATHED OR MAX. PURLIN SPACING = 6.25 FT.
MAX. UNBRACED BOTTOM CHORD LENGTH = 6.25 FT OR RIGID CEILING DIRECTLY APPLIED.
ALL PITCH BREAKS AND PERIMETER CORNER JOINTS MUST BE Laterally RESTRAINED.

LOADING
TOTAL LOAD CASES: (4)

CHORDS				WEBS			
MEMB.	MAX. FACTORED FORCE (LBS)	FACTORED VERT. LOAD (PLF)	MAX. UNBRACED LENGTH (LC)	MEMB.	MAX. FACTORED FORCE (LBS)	MAX. UNBRACED LENGTH (LC)	
FR-TO		FROM TO		FR-TO			
16-2	-176 / 0	0.0 0.0 0.03 (1)	7.81	13-5	-189 / 0	0.06 (1)	
1-2	0 / 29	-77.4 -77.4 0.10 (1)	10.00	14-4	-164 / 0	0.03 (1)	
2-3	-11 / 0	-77.4 -77.4 0.07 (1)	6.25	15-3	-33 / 0	0.00 (1)	
3-4	0 / 27	-77.4 -77.4 0.04 (1)	10.00	12-6	-164 / 0	0.03 (1)	
4-5	0 / 28	-77.4 -77.4 0.04 (1)	10.00	11-7	-33 / 0	0.00 (1)	
5-6	0 / 28	-77.4 -77.4 0.04 (1)	10.00				
6-7	0 / 27	-77.4 -77.4 0.04 (1)	10.00				
7-8	-11 / 0	-77.4 -77.4 0.07 (1)	6.25				
8-9	0 / 29	-77.4 -77.4 0.10 (1)	10.00				
10-8	-176 / 0	0.0 0.0 0.03 (1)	7.81				
16-15	-18 / 0	-17.5 -17.5 0.01 (4)	6.25				
15-14	-20 / 0	-17.5 -17.5 0.01 (4)	6.25				
14-13	-24 / 0	-17.5 -17.5 0.01 (4)	6.25				
13-12	-24 / 0	-17.5 -17.5 0.01 (4)	6.25				
12-11	-20 / 0	-17.5 -17.5 0.01 (4)	6.25				
11-10	-18 / 0	-17.5 -17.5 0.01 (4)	6.25				

DESIGN CRITERIA

SPECIFIED LOADS:
TOP CH. LL = 23.3 PSF
DL = 3.0 PSF
BOT CH. LL = 0.0 PSF
DL = 7.0 PSF
TOTAL LOAD = 33.3 PSF

SPACING = 24.0 IN. C/C

THIS TRUSS IS DESIGNED FOR RESIDENTIAL OR SMALL BUILDING REQUIREMENTS OF PART 9, NBCC 2010

THIS DESIGN COMPLIES WITH:
- PART 9 OF OBC 2012, BCBC 2012, ABC 2014
- CSA 088-09
- TPIC 2011

DESIGN ASSUMPTIONS
- OVERHANG NOT TO BE ALTERED OR CUT OFF.
(55% OF 27.2 P.S.F. G.S.L. PLUS 8.4 P.S.F. RAIN LOAD) EQUALS 23.3 P.S.F. SPECIFIED ROOF LIVE LOAD

CSI: TC=0.10/1.00 (8-9:1), BC=0.01/1.00 (13-14:4), WB=0.06/1.00 (5-13:1), SSI=0.07/1.00 (8-9:1)
DOL LUMBER=1.00 NAIL=1.00 LS BEND=1.10
COMP=1.10 SHEAR=1.10 TENS=1.10

COMPANION LIVE LOAD FACTOR = 0.50

TRUSS PLATE MANUFACTURER IS NOT RESPONSIBLE FOR QUALITY CONTROL IN THE TRUSS MANUFACTURING PLANT.


NAIL VALUES
PLATE GRIP(DRY) SHEAR SECTION (PSI) (PLI) (PLI)
MAX MIN MAX MIN MAX MIN
MT20 618 354 1667 822 2284 1656

PLATE PLACEMENT TOL. = 0.250 inches
PLATE ROTATION TOL. = 5.0 Deg.
JSI GRIP= 0.13 (5) (INPUT = 0.90)
JSI METAL= 0.06 (5) (INPUT = 1.00)



READ ALL NOTES ON THIS PAGE AND ON ENGINEERING NOTE PAGE ENP-1. THIS NOTE PAGE IS AN INTEGRAL PART OF THIS DRAWING AS IT CONTAINS SPECIFICATIONS AND CRITERIA USED IN THE DESIGN OF THIS COMPONENT.





TOTAL WEIGHT = 21 lb [M]

LUMBER

N. L. G. A. RULES	CHORDS	SIZE	LUMBER	DESCR.
11- 2	2x4	DRY	No.2	SPF
1 - 4	2x4	DRY	No.2	SPF
4 - 6	2x4	DRY	No.2	SPF
7 - 6	2x4	DRY	No.2	SPF
11- 7	2x4	DRY	No.2	SPF
ALL WEBS	2x3	DRY	No.2	SPF
ALL GABLE WEBS	2x3	DRY	No.2	SPF
DRY: SEASONED LUMBER.				
GABLE STUDS SPACED AT 2-0-0 OC.				

PLATES (table is in inches)

JT	TYPE	PLATES	W	LEN	Y	X
2	TMV+p	MT20	2.0	4.0		
3	TMW+w	MT20	2.0	4.0		
4	TTW+p	MT20	3.0	4.0	2.25	1.50
5	TMW+w	MT20	2.0	4.0		
6	TMV+p	MT20	2.0	4.0		
7	BMV1+p	MT20	2.0	4.0		
8, 9, 10						
8	BMW1+w	MT20	2.0	4.0		
11	BMV1+p	MT20	2.0	4.0		

DIMENSIONS, SUPPORTS AND LOADINGS SPECIFIED BY FABRICATOR TO BE VERIFIED BY BUILDING DESIGNER

BEARINGS

THIS TRUSS DESIGNED FOR CONTINUOUS BEARINGS.
THIS TRUSS REQUIRES RIGID SHEATHING ON EXPOSED FACE.

PROVIDE ANCHORAGE AT BEARING JOINT 7 FOR 150 LBS. FACTORED UPLIFT BEARING MATERIAL TO BE SPF NO.2 OR BETTER AT JOINT(S).

BRACING

TOP CHORD TO BE SHEATHED OR MAX. PURLIN SPACING = 6.25 FT.
MAX. UNBRACED BOTTOM CHORD LENGTH = 6.25 FT. OR RIGID CEILING DIRECTLY APPLIED.

ALL PITCH BREAKS AND PERIMETER CORNER JOINTS MUST BE Laterally RESTRAINED.

LOADING

TOTAL LOAD CASES: (4)

CHORDS				WEBS			
MEMB.	MAX. FACTORED FORCE (LBS)	FACTORED VERT. LOAD (PLF)	MAX. UNBRACED LENGTH (LC)	MEMB.	MAX. FACTORED FORCE (LBS)	MAX. UNBRACED LENGTH (LC)	
FR-TO		FROM TO		FR-TO			
11-2	-182 / 0	0.0	0.0 0.03 (1)	7-8	-190 / 0	0.03 (1)	
1-2	0 / 27	-77.4	-77.4 0.11 (1)	10-3	-52 / 0	0.01 (1)	
2-3	-11 / 0	-77.4	-77.4 0.07 (1)	6-25	8-5	-130 / 0	0.02 (1)
3-4	0 / 21	-77.4	-77.4 0.05 (1)	10.00			
4-5	0 / 20	-77.4	-77.4 0.04 (1)	10.00			
5-6	0 / 22	-77.4	-77.4 0.03 (1)	10.00			
7-6	0 / 0	0.0	0.0 0.00 (1)	10.00			
11-10	-11 / 0	-17.5	-17.5 0.02 (1)	6.25			
10-9	-15 / 0	-17.5	-17.5 0.02 (4)	6.25			
9-8	-15 / 0	-17.5	-17.5 0.02 (4)	6.25			
8-7	-7 / 0	-17.5	-17.5 0.01 (4)	10.00			

DESIGN CRITERIA

SPECIFIED LOADS:
TOP CH. LL = 23.3 PSF
DL = 3.0 PSF
BOT CH. LL = 0.0 PSF
DL = 7.0 PSF
TOTAL LOAD = 33.3 PSF

SPACING = 24.0 IN. C/C

THIS TRUSS IS DESIGNED FOR RESIDENTIAL OR SMALL BUILDING REQUIREMENTS OF PART 9, NBCC 2010

THIS DESIGN COMPLIES WITH:
- PART 9 OF OBC 2012, BCBC 2012, ABC 2014
- CSA 086-09
- TPIC 2011

DESIGN ASSUMPTIONS
- OVERHANG NOT TO BE ALTERED OR CUT OFF.

(55% OF 27.2 P.S.F. G.S.L. PLUS 8.4 P.S.F. RAIN LOAD) EQUALS 23.3 P.S.F. SPECIFIED ROOF LIVE LOAD

CSI: TC=0.11/1.00 (1-2:1), BC=0.02/1.00 (10-11:1), WB=0.03/1.00 (4-9:1), SSI=0.07/1.00 (1-2:1)

DOL LUMBER=1.00 NAIL=1.00 LS BEND=1.10 COMP=1.10 SHEAR=1.10 TENS=1.10

COMPANION LIVE LOAD FACTOR = 0.50

TRUSS PLATE MANUFACTURER IS NOT RESPONSIBLE FOR QUALITY CONTROL IN THE TRUSS MANUFACTURING PLANT.

NAIL VALUES	PLATE GRIP(DRY)	SHEAR (PSI)	SECTION (PLI)
	MAX MIN	MAX MIN	MAX MIN
MT20	618 354	1667 822	2284 1656

PLATE PLACEMENT TOL. = 0.250 inches

PLATE ROTATION TOL. = 5.0 Deg.

JSI GRIP= 0.12 (4) (INPUT = 0.90)
JSI METAL= 0.07 (4) (INPUT = 1.00)




READ ALL NOTES ON THIS PAGE AND ON ENGINEERING NOTE PAGE ENP-1. THIS NOTE PAGE IS AN INTEGRAL PART OF THIS DRAWING AS IT CONTAINS SPECIFICATIONS AND CRITERIA USED IN THE DESIGN OF THIS COMPONENT.



DESCR

SPF

SPF



TOTAL LOAD CASES: (4)

WEB

CONTINUED ON PAGE 2




LOADING

TOTAL LOAD CASES: (4)

CHORDS				WEBS			
MEMB.	MAX. FACTORED FORCE (LBS)	FACTORED VERT. LOAD (PLF)	LC1 MAX CSI (LC)	MAX. UNBRAC LENGTH	MEMB.	MAX. FACTORED FORCE (LBS)	FACTORED MAX CSI (LC)
FR-TO		FROM TO			FR-TO		
42-41	-4 / 0	-17.5	-17.5 0.01 (4)	10.00			
41-40	-3 / 0	-17.5	-17.5 0.01 (4)	10.00			
40-39	-2 / 1	-17.5	-17.5 0.01 (4)	10.00			
39-38	0 / 1	-17.5	-17.5 0.01 (4)	10.00			
38-37	0 / 1	-17.5	-17.5 0.01 (4)	10.00			
37-36	0 / 4	-17.5	-17.5 0.01 (4)	10.00			
36-35	0 / 6	-17.5	-17.5 0.01 (4)	10.00			
35-34	0 / 8	-17.5	-17.5 0.01 (4)	10.00			
33-34	-40 / 7	0.0	0.0 0.01 (1)	7.81			
34-23	-65 / 0	0.0	0.0 0.01 (1)	7.81			
33-32	0 / 8	-17.5	-17.5 0.01 (4)	10.00			
32-31	0 / 11	-17.5	-17.5 0.02 (4)	10.00			
31-30	0 / 16	-17.5	-17.5 0.02 (4)	10.00			
30-29	0 / 16	-17.5	-17.5 0.03 (1)	10.00			

READ ALL NOTES ON THIS PAGE AND ON
ENGINEERING NOTE PAGE ENP-1. THIS
NOTE PAGE IS AN INTEGRAL PART OF
THIS DRAWING AS IT CONTAINS
SPECIFICATIONS AND CRITERIA USED IN
THE DESIGN OF THIS COMPONENT.





Scale = 1:25.1

TOTAL WEIGHT = 13 X 17 = 225 lb [M]

LUMBER				DESCR.
N.L.G.A. RULES	CHORDS	SIZE	LUMBER	
5 - 2	2x4	DRY	No.2	SPF
1 - 3	2x4	DRY	No.2	SPF
5 - 4	2x4	DRY	No.2	SPF

DRY: SEASONED LUMBER.

PLATES (table is in inches)					
JT	TYPE	PLATES	W	LEN	Y X
2	TMV+p	MT20	2.0	4.0	
5	BMV1+p	MT20	2.0	4.0	

DIMENSIONS, SUPPORTS AND LOADINGS SPECIFIED BY FABRICATOR TO BE VERIFIED BY BUILDING DESIGNER

JT	FACTORED GROSS REACTION		MAXIMUM FACTORED GROSS REACTION		INPUT BRG		REQD BRG	
	VERT	HORZ	DOWN	HORZ	IN-SX	IN-SX	IN-SX	IN-SX
5	457	0	457	0	5-8	5-8	5-8	5-8
3	174	0	174	0	1-8	1-8	1-8	1-8
4	43	0	49	0	1-8	1-8	1-8	1-8

SEE MITTEK STANDARD DETAIL B3759H FOR CONNECTION TO JOINT(S) 3, 4

UNFACTORED REACTIONS

JT	1ST LCASE		MAX/MIN		COMPONENT REACTIONS		DEAD	SOIL
	COMBINED	SNOW	LIVE	PERM.LIVE	WIND			
5	318	238 / 0	0 / 0	0 / 0	0 / 0	80 / 0	0 / 0	0 / 0
3	118	105 / 0	0 / 0	0 / 0	0 / 0	14 / 0	0 / 0	0 / 0
4	35	0 / 0	0 / 0	0 / 0	0 / 0	35 / 0	0 / 0	0 / 0

BEARING MATERIAL TO BE SPF NO.2 OR BETTER AT JOINT(S) 5

BRACING

TOP CHORD TO BE SHEATHED OR MAX. PURLIN SPACING = 6.25 FT.
MAX. UNBRACED BOTTOM CHORD LENGTH = 10.00 FT OR RIGID CEILING DIRECTLY APPLIED.

ALL PITCH BREAKS AND PERIMETER CORNER JOINTS MUST BE Laterally RESTRAINED.

LOADING

TOTAL LOAD CASES: (4)

MEMB.	CHORDS		FACTORED		WEBS		FACTORED	
	MAX. FORCE (LBS)	VERT. LOAD (PLF)	LC1 MAX (LC)	MAX. UNBRACED LENGTH	MEMB. FORCE (LBS)	MAX. FACTORED (LBS)	MAX. UNBRACED LENGTH	MEMB. FORCE (LBS)
FR-TO								
5-2	-395 / 0	0.0	0.0	0.13 (4)	7.81			
1-2	0 / 25	-77.4	-77.4	0.10 (1)	10.00			
2-3	-28 / 0	-77.4	-77.4	0.47 (1)	6.25			
5-4	0 / 0	-17.5	-17.5	0.13 (4)	10.00			

DESIGN CRITERIA

SPECIFIED LOADS:

TOP CH.	LL = 23.3	PSF
	DL = 3.0	PSF
BOT CH.	LL = 0.0	PSF
	DL = 7.0	PSF
TOTAL LOAD	= 33.3	PSF

SPACING = 24.0 IN./C

THIS TRUSS IS DESIGNED FOR RESIDENTIAL OR SMALL BUILDING REQUIREMENTS OF PART 9, NBCC 2010

THIS DESIGN COMPLIES WITH:

- PART 9 OF OBC 2012, BCBC 2012, ABC 2014
- CSA 086-09
- TPIC 2011

DESIGN ASSUMPTIONS

- OVERHANG NOT TO BE ALTERED OR CUT OFF.

(55 % OF 27.2 P.S.F. G.S.L. PLUS 8.4 P.S.F. RAIN LOAD) EQUALS 23.3 P.S.F. SPECIFIED ROOF LIVE LOAD

ALLOWABLE DEFL.(LL)= L/360 (0.20")
CALCULATED VERT. DEFL.(LL) = L/999 (0.00")
ALLOWABLE DEFL.(TL)= L/360 (0.20")
CALCULATED VERT. DEFL.(TL) = L/999 (0.03")

CSI: TC=0.47/1.00 (2-3:1), BC=0.13/1.00 (4-5:4), WB=0.00/1.00 (n/a:0), SSI=0.20/1.00 (2-3:1)

DOL LUMBER=1.00 NAIL=1.00 LS BEND=1.10
COMP=1.10 SHEAR=1.10 TENS= 1.10

COMPANION LIVE LOAD FACTOR = 0.50

TRUSS PLATE MANUFACTURER IS NOT RESPONSIBLE FOR QUALITY CONTROL IN THE TRUSS MANUFACTURING PLANT.

NAIL VALUES

PLATE	GRIP(DRY)	SHEAR	SECTION
(PSI)	(PLI)	(PLI)	(PLI)
MT20	618	354	1667
	822	2284	1656

PLATE PLACEMENT TOL. = 0.250 inches


PLATE ROTATION TOL. = 5.0 Deg.

JSI GRIP= 0.23 (2) (INPUT = 0.90)
JSI METAL= 0.09 (2) (INPUT = 1.00)



READ ALL NOTES ON THIS PAGE AND ON ENGINEERING NOTE PAGE ENP-1. THIS NOTE PAGE IS AN INTEGRAL PART OF THIS DRAWING AS IT CONTAINS SPECIFICATIONS AND CRITERIA USED IN THE DESIGN OF THIS COMPONENT.





Scale = 1:25.2

TOTAL WEIGHT = 7 X 15 = 104 lb [M][F]

LUMBER				
N. L. G. A. RULES	CHORDS	SIZE	LUMBER	DESCR.
4 - 1	2x4	DRY	No.2	SPF
1 - 2	2x4	DRY	No.2	SPF
4 - 3	2x4	DRY	No.2	SPF

DRY: SEASONED LUMBER.

PLATES (table is in inches)					
JT	TYPE	PLATES	W	LEN	Y X
1	TMV+p	MT20	2.0	4.0	
4	BMV1+p	MT20	2.0	4.0	

DIMENSIONS, SUPPORTS AND LOADINGS SPECIFIED BY FABRICATOR TO BE VERIFIED BY BUILDING DESIGNER

JT	FACTORED GROSS REACTION		MAXIMUM FACTORED GROSS REACTION		INPUT BRG	REQRD BRG
	VERT	HORZ	DOWN	HORZ		
4	263	0	263	0	0	0
2	197	0	197	0	1-8	1-8
3	66	0	66	0	1-8	1-8

A SUITABLE MECHANICAL CONNECTION IS REQUIRED AT JOINT 4 TO RESIST THE MAX FACTORED REACTIONS.

SEE MITEK STANDARD DETAIL B37579H FOR CONNECTION TO JOINT(S) 2, 3

UNFACTORED REACTIONS

JT	1ST LCASE COMBINED		MAX/MIN. SNOW		LIVE		PERM.LIVE		WIND		DEAD		SOIL	
	FROM	TO	FROM	TO	FROM	TO	FROM	TO	FROM	TO	FROM	TO	FROM	TO
4	184	129/0	0/0	0/0	0/0	0/0	0/0	0/0	55/0	0/0	0/0	0/0	0/0	0/0
2	134	116/0	0/0	0/0	0/0	0/0	0/0	0/0	18/0	0/0	0/0	0/0	0/0	0/0
3	50	13/0	0/0	0/0	0/0	0/0	0/0	0/0	37/0	0/0	0/0	0/0	0/0	0/0

BRACING

TOP CHORD TO BE SHEATHED OR MAX. PURLIN SPACING = 10.00 FT.
MAX. UNBRACED BOTTOM CHORD LENGTH = 10.00 FT OR RIGID CEILING DIRECTLY APPLIED.

ALL PITCH BREAKS AND PERIMETER CORNER JOINTS MUST BE Laterally RESTRAINED.

LOADING

TOTAL LOAD CASES: (4)

FR-TO	CHORDS		FACTORED		WEBS		FACTORED	
	MEMB.	FORCE (LBS)	VERT. LOAD (PLF)	LC1 MAX (LC)	MEMB.	FORCE (LBS)	MAX. UNBRAC LENGTH (LC)	MAX. (LC)
4-1	-232/0	0.0	0.0	0.12 (1)	7.61			
1-2	-8/1	-77.4	-77.4	0.34 (1)	10.00			
4-3	0/0	-17.5	-17.5	0.17 (1)	10.00			

DESIGN CRITERIA

SPECIFIED LOADS:

TOP CH.	LL =	23.3	PSF
	DL =	3.0	PSF
BOT CH.	LL =	0.0	PSF
	DL =	7.0	PSF
TOTAL LOAD	=	33.3	PSF

SPACING = 24.0 IN./C

THIS TRUSS IS DESIGNED FOR RESIDENTIAL OR SMALL BUILDING REQUIREMENTS OF PART 9, NBCC 2010

THIS DESIGN COMPLIES WITH:

- PART 9 OF OBC 2012, BCBC 2012, ABC 2014
- CSA 086-09
- TPIC 2011

(55 % OF 27.2 P.S.F. G.S.L. PLUS 8.4 P.S.F. RAIN LOAD) EQUALS 23.3 P.S.F. SPECIFIED ROOF LIVE LOAD

ALLOWABLE DEFL.(LL)= L/360 (0.19")
CALCULATED VERT. DEFL.(LL)= L/999 (0.03")
ALLOWABLE DEFL.(TL)= L/360 (0.19")
CALCULATED VERT. DEFL.(TL)= L/829 (0.08")

CSI: TC=0.34/1.00 (1-2:1), BC=0.17/1.00 (3-4:1), WB=0.00/1.00 (n/a:0), SSI=0.16/1.00 (1-2:1)

DOL LUMBER=1.00 NAIL=1.00 LS BEND=1.10 COMP=1.10 SHEAR=1.10 TENS= 1.10

COMPANION LIVE LOAD FACTOR = 0.50

TRUSS PLATE MANUFACTURER IS NOT RESPONSIBLE FOR QUALITY CONTROL IN THE TRUSS MANUFACTURING PLANT.

NAIL VALUES

PLATE	GRIP(DRY) (PSI)	SHEAR (PLI)	SECTION (PLI)
MT20	618	354	1667
	822	2284	1656

PLATE PLACEMENT TOL. = 0.250 inches

PLATE ROTATION TOL. = 5.0 Deg.


JSI GRIP= 0.14 (1) (INPUT = 0.90)
JSI METAL= 0.05 (1) (INPUT = 1.00)



READ ALL NOTES ON THIS PAGE AND ON ENGINEERING NOTE PAGE ENP-1. THIS NOTE PAGE IS AN INTEGRAL PART OF THIS DRAWING AS IT CONTAINS SPECIFICATIONS AND CRITERIA USED IN THE DESIGN OF THIS COMPONENT.



Version 8.210 S Mar 12 2018 MiTek Industries, Inc. Thu Aug 16 13:39:21 2018 Page 1
ID:eu6n27latr9jLP2iXToTi6z4Q5d-042yGNXrHLOWgM0pOuJFQBG5FBU9FGiPCviQBqynGig



TOTAL WEIGHT = 2 X 15 = 31 lb [M]

LUMBER				
N. L. G. A. RULES	SIZE	LUMBER	DESCR.	SPF
5 - 2	2x4	No.2	SPF	
1 - 3	2x4	No.2	SPF	
5 - 4	2x4	No.2	SPF	

DRY: SEASONED LUMBER.

PLATES (table is in inches)

JT	TYPE	PLATES	W	LEN	Y	X
2	TMV+p	MT20	2.0	4.0		
5	BMV1+p	MT20	2.0	4.0		

DIMENSIONS, SUPPORTS AND LOADINGS SPECIFIED BY FABRICATOR TO BE VERIFIED BY BUILDING DESIGNER

FACTORED GROSS REACTION		MAXIMUM FACTORED GROSS REACTION		INPUT BRG		REQRD BRG	
JT	VERT	HORZ	DOWN	HORZ	UPLIFT	IN-SX	IN-SX
5	369	0	369	0	0	5-8	5-8
3	131	0	131	0	0	1-8	1-8
4	34	0	38	0	0	1-8	1-8

SEE MITTEK STANDARD DETAIL B37579H FOR CONNECTION TO JOINT(S) 3, 4

UNFACTORED REACTIONS

1ST LCASE		MAX./MIN. COMPONENT REACTIONS		LIVE		PERM. LIVE		WIND		DEAD		SOIL	
JT	COMBINED	SNOW											
5	256	195 / 0	0 / 0	0 / 0	0 / 0	0 / 0	0 / 0	61 / 0	0 / 0	0 / 0	0 / 0	0 / 0	0 / 0
3	89	79 / 0	0 / 0	0 / 0	0 / 0	0 / 0	0 / 0	10 / 0	0 / 0	0 / 0	0 / 0	0 / 0	0 / 0
4	27	0 / 0	0 / 0	0 / 0	0 / 0	0 / 0	0 / 0	27 / 0	0 / 0	0 / 0	0 / 0	0 / 0	0 / 0

BEARING MATERIAL TO BE SPF NO.2 OR BETTER AT JOINT(S) 5, 3

BRACING

TOP CHORD TO BE SHEATHED OR MAX. PURLIN SPACING = 6.25 FT.
MAX. UNBRACED BOTTOM CHORD LENGTH = 10.00 FT OR RIGID CEILING DIRECTLY APPLIED.

ALL PITCH BREAKS AND PERIMETER CORNER JOINTS MUST BE Laterally RESTRAINED.

LOADING

TOTAL LOAD CASES: (4)

CHORDS		FACTORED		WEBS		FACTORED	
MEMB.	FORCE (LBS)	VERT. LOAD (PLF)	LC1 MAX (LC)	MEMB.	FORCE (LBS)	MAX. UNBRAC LENGTH (LC)	MAX. (LC)
FR-TO		FROM TO		FR-TO			
5-2	-325 / 0	0.0	0.0 0.06 (4)	7.81			
1-2	0 / 34	-77.4	-77.4 0.11 (1)	10.00			
2-3	-28 / 0	-77.4	-77.4 0.27 (1)	6.25			
5-4	0 / 0	-17.5	-17.5 0.08 (4)	10.00			

DESIGN CRITERIA

SPECIFIED LOADS:
TOP CH. LL = 23.3 PSF
DL = 3.0 PSF
BOT CH. LL = 0.0 PSF
DL = 7.0 PSF
TOTAL LOAD = 33.3 PSF

SPACING = 24.0 IN. C/C

THIS TRUSS IS DESIGNED FOR RESIDENTIAL OR SMALL BUILDING REQUIREMENTS OF PART 9, NBCC 2010

THIS DESIGN COMPLIES WITH:
- PART 9 OF OBC 2012, BCBC 2012, ABC 2014
- CSA 086-09
- TPIC 2011

DESIGN ASSUMPTIONS
- OVERHANG NOT TO BE ALTERED OR CUT OFF.

(55 % OF 27.2 P.S.F. G.S.L. PLUS 8.4 P.S.F. RAIN LOAD) EQUALS 23.3 P.S.F. SPECIFIED ROOF LIVE LOAD

ALLOWABLE DEFL.(LL) = $L/360$ (0.19")
CALCULATED VERT. DEFL.(LL) = $L/999$ (0.00")
ALLOWABLE DEFL.(TL) = $L/360$ (0.19")
CALCULATED VERT. DEFL.(TL) = $L/999$ (0.01")

CSI: TC=0.27/1.00 (2-3:1), BC=0.08/1.00 (4-5:4), WB=0.00/1.00 (n/a:0), SS=0.13/1.00 (2-3:1)

DOL LUMBER=1.00 NAIL=1.00 LS BEND=1.10 COMP=1.10 SHEAR=1.10 TENS=1.10

COMPANION LIVE LOAD FACTOR = 0.50

TRUSS PLATE MANUFACTURER IS NOT RESPONSIBLE FOR QUALITY CONTROL IN THE TRUSS MANUFACTURING PLANT.

NAIL VALUES		PLATE GRIP(DRY) SHEAR		SECTION	
(PSI)	(PL)	(PSI)	(PL)	(PL)	(PL)
MAX MIN	MAX MIN	MAX MIN	MAX MIN	MAX MIN	MAX MIN
MT20	618 354	1667 822	2284 1656		

PLATE PLACEMENT TOL. = 0.250 inches

PLATE ROTATION TOL. = 5.0 Deg.


JSI GRIP= 0.23 (2) (INPUT = 0.90)
JSI METAL= 0.09 (2) (INPUT = 1.00)



READ ALL NOTES ON THIS PAGE AND ON ENGINEERING NOTE PAGE ENP-1. THIS NOTE PAGE IS AN INTEGRAL PART OF THIS DRAWING AS IT CONTAINS SPECIFICATIONS AND CRITERIA USED IN THE DESIGN OF THIS COMPONENT.



Version 8.210 S Mar 12 2018 MiTek Industries, Inc. Thu Aug 16 13:39:22 2018 Page 1
ID: eu6n2?latr9JLP2IXToTi6z4Q5d-UGcKUjYT2eWnlWb?ybyqUyPpEgao_gfYRZ1zjGynG



LUMBER
N. L. G. A. RULES

CHORDS	SIZE	DRY	LUMBER	DESCR.
1 - 3	2x4	DRY	No.2	SPF
3 - 5	2x4	DRY	No.2	SPF
5 - 7	2x4	DRY	No.2	SPF
13 - 2	2x4	DRY	No.2	SPF
8 - 6	2x4	DRY	No.2	SPF
13 - 10	2x4	DRY	No.2	SPF
10 - 8	2x4	DRY	No.2	SPF
ALL WEBS EXCEPT	2x3	DRY	No.2	SPF

DRY: SEASONED LUMBER.

PLATES (table is in inches)

JT	TYPE	PLATES	W	LEN	Y	X
2	TMVW-t	MT20	4.0	5.0	1.75	2.00
3	TTWW-m	MT20	4.0	6.0	1.75	2.00
4	TMVW-w	MT20	2.0	4.0		
5	TTWW-m	MT20	4.0	6.0	1.75	2.00
6	TMVW-t	MT20	4.0	5.0	1.75	2.00
8	BMV1+p	MT20	2.0	4.0		
9	BMWW-t	MT20	3.0	5.0	1.50	1.75
10	BS-t	MT20	3.0	6.0		
11	BMWW-t	MT20	3.0	6.0		
12	BMWW-t	MT20	3.0	5.0	1.50	1.75
13	BMV1+p	MT20	2.0	4.0		

DIMENSIONS, SUPPORTS AND LOADINGS SPECIFIED BY FABRICATOR TO BE VERIFIED BY BUILDING DESIGNER

BEARINGS

JT	FACTORED GROSS REACTION		MAXIMUM FACTORED GROSS REACTION		INPUT BRG	REQD BRG
	VERT	HORZ	DOWN	UP/LIFT		
13	1154	0	1154	0	5-8	5-8
8	1154	0	1154	0	5-8	5-8

UNFACTORED REACTIONS

JT	1ST LCASE		MAX/MIN. COMPONENT REACTIONS				
	COMBINED	SNOW	LIVE	PERM. LIVE	WIND	DEAD	SOIL
13	807	578 / 0	0 / 0	0 / 0	0 / 0	229 / 0	0 / 0
8	807	578 / 0	0 / 0	0 / 0	0 / 0	229 / 0	0 / 0

BEARING MATERIAL TO BE SPF NO.2 OR BETTER AT JOINT(S) 13, 8

BRACING
TOP CHORD TO BE SHEATHED OR MAX. PURLIN SPACING = 5.53 FT.
MAX. UNBRACED BOTTOM CHORD LENGTH = 10.00 FT OR RIGID CEILING DIRECTLY APPLIED.

ALL PITCH BREAKS AND PERIMETER CORNER JOINTS MUST BE Laterally RESTRAINED.

LOADING
TOTAL LOAD CASES: (4)

CHORDS				WEBS			
MEMB.	MAX. FACTORED FORCE (LBS)	FACTORED VERT. LOAD (PLF)	MAX. FACTORED CSI (LC)	MEMB.	MAX. FACTORED FORCE (LBS)	MAX. FACTORED CSI (LC)	
FR-TO		FROM TO		FR-TO			
1-2	0 / 29	-77.4 -77.4	0.10 (1)	10.00	12-3	-36 / 85	0.03 (4)
2-3	-1090 / 0	-77.4 -77.4	0.42 (1)	5.53	3-11	0 / 347	0.08 (1)
3-4	-1140 / 0	-77.4 -77.4	0.24 (1)	5.68	11-4	-453 / 0	0.21 (1)
4-5	-1140 / 0	-77.4 -77.4	0.24 (1)	5.68	11-5	0 / 347	0.08 (1)
5-6	-1090 / 0	-77.4 -77.4	0.42 (1)	5.53	9-5	-36 / 85	0.03 (4)
6-7	0 / 29	-77.4 -77.4	0.10 (1)	10.00	2-12	0 / 919	0.21 (1)
13-2	-1108 / 0	0.0 0.0	0.11 (1)	7.52	9-6	0 / 919	0.21 (1)
8-6	-1108 / 0	0.0 0.0	0.11 (1)	7.52			
13-12	0 / 0	-17.5 -17.5	0.15 (4)	10.00			
12-11	0 / 906	-17.5 -17.5	0.23 (1)	10.00			
11-10	0 / 906	-17.5 -17.5	0.23 (1)	10.00			
10-9	0 / 906	-17.5 -17.5	0.23 (1)	10.00			
9-8	0 / 0	-17.5 -17.5	0.15 (4)	10.00			

DESIGN CRITERIA

SPECIFIED LOADS:
TOP CH. LL = 23.3 PSF
DL = 3.0 PSF
BOT CH. LL = 0.0 PSF
DL = 7.0 PSF
TOTAL LOAD = 33.3 PSF

SPACING = 24.0 IN. C/C

LOADING IN FLAT SECTION BASED ON A SLOPE OF 2.00/12 MINIMUM

THIS TRUSS IS DESIGNED FOR RESIDENTIAL OR SMALL BUILDING REQUIREMENTS OF PART 9, NBCC 2010

THIS DESIGN COMPLIES WITH:
- PART 9 OF OBC 2012, BCBC 2012, ABC 2014
- CSA 086-09
- TPIC 2011

(55% OF 27.2 P.S.F. G.S.L. PLUS 8.4 P.S.F. RAIN LOAD) EQUALS 23.3 P.S.F. SPECIFIED ROOF LIVE LOAD

ALLOWABLE DEFL.(LL)= L/360 (0.74")
CALCULATED VERT. DEFL.(LL) = L/999 (0.04")
ALLOWABLE DEFL.(TL)= L/360 (0.74")
CALCULATED VERT. DEFL.(TL) = L/999 (0.07")

CSI: TC=0.42/1.00 (2-3:1), BC=0.23/1.00 (11-12:1), WB=0.21/1.00 (4-11:1), SSI=0.18/1.00 (3-4:1)

DOL LUMBER=1.00 NAIL=1.00 LS BEND=1.10 COMP=1.10 SHEAR=1.10 TENS=1.10

COMPANION LIVE LOAD FACTOR = 0.50

TRUSS PLATE MANUFACTURER IS NOT RESPONSIBLE FOR QUALITY CONTROL IN THE TRUSS MANUFACTURING PLANT.

NAIL VALUES

PLATE	GRIP(DRY) (PSI)	SHEAR (PLI)	SECTION (PLI)
MT20	618	354	1667
	822	2284	1656

PLATE PLACEMENT TOL. = 0.250 inches


PLATE ROTATION TOL. = 5.0 Deg.

JSI GRIP= 0.90 (12) (INPUT = 0.90)
JSI METAL= 0.38 (2) (INPUT = 1.00)



READ ALL NOTES ON THIS PAGE AND ON ENGINEERING NOTE PAGE ENP-1. THIS NOTE PAGE IS AN INTEGRAL PART OF THIS DRAWING AS IT CONTAINS SPECIFICATIONS AND CRITERIA USED IN THE DESIGN OF THIS COMPONENT.





TOTAL WEIGHT = 2 X 94 = 187 lb
(M)F

LUMBER	N. L. G. A. RULES	CHORDS	SIZE	LUMBER	DESCR.
1 - 4	2x4	DRY	No.2	SPF	
4 - 5	2x4	DRY	No.2	SPF	
5 - 8	2x4	DRY	No.2	SPF	
13 - 2	2x4	DRY	No.2	SPF	
9 - 7	2x4	DRY	No.2	SPF	
13 - 10	2x4	DRY	No.2	SPF	
10 - 9	2x4	DRY	No.2	SPF	
ALL WEBS EXCEPT	2x3	DRY	No.2	SPF	

DRY: SEASONED LUMBER.

PLATES (table is in inches)	JT	TYPE	PLATES	W	LEN	Y	X
2	TMV+p	MT20	2.0	4.0			
3	TMWW-t	MT20	4.0	4.0	1.75	2.00	
4	TTW+m	MT20	3.0	4.0	2.00	1.25	
5	TTWW-m	MT20	4.0	5.0	1.75	1.50	
6	TMWW-t	MT20	4.0	4.0	1.75	2.00	
7	TMV+p	MT20	2.0	4.0			
9	BMVW1-t	MT20	4.0	4.0	1.75	1.75	
10	BS-t	MT20	3.0	6.0			
11	BMWW-t	MT20	3.0	4.0			
12	BMVWW-t	MT20	3.0	6.0			
13	BMVW1-t	MT20	4.0	4.0	1.75	1.75	

DIMENSIONS, SUPPORTS AND LOADINGS SPECIFIED BY FABRICATOR TO BE VERIFIED BY BUILDING DESIGNER

BEARINGS			FACTORED		MAXIMUM FACTORED		INPUT	REQRD
JT	GROSS REACTION		GROSS REACTION			BRG	BRG	
	VERT	HORZ	DOWN	HORZ	UPLIFT	IN-SX	IN-SX	
13	1154	0	1154	0	0	5-8	5-8	
9	1154	0	1154	0	0	5-8	5-8	

UNFACTORED REACTIONS

JT	COMBINED	SNOW	LIVE	PERM. LIVE	WIND	DEAD	SOIL
13	807	578 / 0	0 / 0	0 / 0	0 / 0	229 / 0	0 / 0
9	807	578 / 0	0 / 0	0 / 0	0 / 0	229 / 0	0 / 0

BEARING MATERIAL TO BE SPF NO.2 OR BETTER AT JOINT(S) 13, 9

BRACING

TOP CHORD TO BE SHEATHED OR MAX. PURLIN SPACING = 5.99 FT.
MAX. UNBRACED BOTTOM CHORD LENGTH = 10.00 FT OR RIGID CEILING DIRECTLY APPLIED.

ALL PITCH BREAKS AND PERIMETER CORNER JOINTS MUST BE Laterally RESTRAINED.

LOADING

TOTAL LOAD CASES: (4)

CHORDS				WEBS			
MEMB.	MAX. FACTORED FORCE (LBS)	FACTORED VERT. LOAD (PLF)	MAX. CS1 (LC)	MEMB.	MAX. FACTORED FORCE (LBS)	MAX. CS1 (LC)	
FR-TO		FROM	TO	FR-TO		FROM	TO
1-2	0 / 29	-77.4	-77.4 0.10 (1)	10.00	3-12	-103 / 23	0.05 (1)
2-3	0 / 19	-77.4	-77.4 0.19 (1)	10.00	12-4	0 / 204	0.05 (4)
3-4	-1041 / 0	-77.4	-77.4 0.15 (1)	5.99	12-5	0 / 0	0.00 (1)
4-5	-852 / 0	-77.4	-77.4 0.41 (1)	6.04	11-5	0 / 204	0.05 (4)
5-6	-1040 / 0	-77.4	-77.4 0.15 (1)	5.99	11-6	-103 / 23	0.05 (1)
6-7	0 / 19	-77.4	-77.4 0.19 (1)	10.00	13-3	-1271 / 0	0.60 (1)
7-8	0 / 29	-77.4	-77.4 0.10 (1)	10.00	6-9	-1270 / 0	0.60 (1)
13-2	-224 / 0	0.0	0.0 0.02 (1)	7.81			
9-7	-224 / 0	0.0	0.0 0.02 (1)	7.81			
13-12	0 / 925	-17.5	-17.5 0.29 (4)	10.00			
12-11	0 / 852	-17.5	-17.5 0.28 (4)	10.00			
11-10	0 / 925	-17.5	-17.5 0.29 (4)	10.00			
10-9	0 / 925	-17.5	-17.5 0.29 (4)	10.00			

DESIGN CRITERIA

SPECIFIED LOADS:

TOP CH.	LL = 23.3	PSF
DL = 3.0	PSF	
BOT CH.	LL = 0.0	PSF
DL = 7.0	PSF	
TOTAL LOAD = 33.3	PSF	

SPACING = 24.0 IN. C/C

LOADING IN FLAT SECTION BASED ON A SLOPE OF 2.00/12 MINIMUM

THIS TRUSS IS DESIGNED FOR RESIDENTIAL OR SMALL BUILDING REQUIREMENTS OF PART 9, NBCC 2010

THIS DESIGN COMPLIES WITH:
- PART 9 OF OBC 2012, BCBC 2012, ABC 2014
- CSA 086-09
- TPIC 2011

(55% OF 27.2 P.S.F. G.S.L. PLUS 8.4 P.S.F. RAIN LOAD) EQUALS 23.3 P.S.F. SPECIFIED ROOF LIVE LOAD

ALLOWABLE DEFL.(LL) = L/360 (0.74")
CALCULATED VERT. DEFL.(LL) = L/999 (0.03")
ALLOWABLE DEFL.(TL) = L/360 (0.74")
CALCULATED VERT. DEFL.(TL) = L/999 (0.13")

CSI: TC=0.41/1.00 (4-5:1), BC=0.29/1.00 (9-11:4),
WB=0.60/1.00 (3-13:1), SSI=0.19/1.00 (4-5:1)

DOL LUMBER=1.00 NAIL=1.00 LS BEND=1.10
COMP=1.10 SHEAR=1.10 TENS=1.10

COMPANION LIVE LOAD FACTOR = 0.50

TRUSS PLATE MANUFACTURER IS NOT RESPONSIBLE FOR QUALITY CONTROL IN THE TRUSS MANUFACTURING PLANT.

NAIL VALUES	PLATE GRIP(DRY) SHEAR (PSI)	SECTION (PLI)	SECTION (PLI)
MT20	618	354	1667
	822	2284	1656

PLATE PLACEMENT TOL. = 0.250 inches


PLATE ROTATION TOL. = 5.0 Deg.

JSI GRIP= 0.89 (3) (INPUT = 0.90)
JSI METAL= 0.46 (3) (INPUT = 1.00)



READ ALL NOTES ON THIS PAGE AND ON ENGINEERING NOTE PAGE ENP-1. THIS NOTE PAGE IS AN INTEGRAL PART OF THIS DRAWING AS IT CONTAINS SPECIFICATIONS AND CRITERIA USED IN THE DESIGN OF THIS COMPONENT.





LUMBER	N. L. G. A. RULES	CHORDS	SIZE	LUMBER	DESCR.
1 - 4	2x4	DRY	No.2	SPF	
4 - 5	2x4	DRY	No.2	SPF	
5 - 8	2x4	DRY	No.2	SPF	
15 - 2	2x4	DRY	No.2	SPF	
9 - 7	2x4	DRY	No.2	SPF	
15 - 11	2x4	DRY	No.2	SPF	
11 - 9	2x4	DRY	No.2	SPF	
ALL WEBS EXCEPT	2x3	DRY	No.2	SPF	

DRY: SEASONED LUMBER.

PLATES (table is in inches)						
JT	TYPE	PLATES	W	LEN	Y	X
2	TMVW-t	MT20	4.0	5.0	1.75	2.00
3	TMWW-t	MT20	3.0	4.0	1.50	1.50
4	TTWW-m	MT20	4.0	5.0	1.75	1.50
5	TTW+m	MT20	3.0	4.0	2.00	1.25
6	TMWW-t	MT20	3.0	4.0	1.50	1.50
7	TMVW-t	MT20	4.0	5.0	1.75	2.00
9	BMV1+p	MT20	2.0	4.0		
10	BMWW-t	MT20	3.0	5.0	1.50	2.00
11	BS-t	MT20	3.0	6.0		
12	BMWWW-t	MT20	4.0	6.0		
13	BMWW-t	MT20	3.0	4.0		
14	BMWW-t	MT20	3.0	5.0	1.50	2.00
15	BMV1+p	MT20	2.0	4.0		

DIMENSIONS, SUPPORTS AND LOADINGS SPECIFIED BY FABRICATOR TO BE VERIFIED BY BUILDING DESIGNER

JT	FACTORED GROSS REACTION		MAXIMUM FACTORED GROSS REACTION		INPUT BRG		REQRD BRG	
	VERT	HORZ	DOWN	HORZ	IN-SX	IN-SX	IN-SX	IN-SX
15	1154	0	1154	0	0	5-8	5-8	
9	1154	0	1154	0	0	5-8	5-8	

UNFACTORED REACTIONS

JT	1ST LCASE		MAX/MIN. COMPONENT REACTIONS		WIND	DEAD	SOIL
	COMBINED	SNOW	LIVE	PERM.LIVE			
15	807	578 / 0	0 / 0	0 / 0	0 / 0	229 / 0	0 / 0
9	807	578 / 0	0 / 0	0 / 0	0 / 0	229 / 0	0 / 0

BEARING MATERIAL TO BE SPF NO.2 OR BETTER AT JOINT(S) 15, 9

BRACING

TOP CHORD TO BE SHEATHED OR MAX. PURLIN SPACING = 5.67 FT.
MAX. UNBRACED BOTTOM CHORD LENGTH = 10.00 FT OR RIGID CEILING DIRECTLY APPLIED.

ALL PITCH BREAKS AND PERIMETER CORNER JOINTS MUST BE Laterally RESTRAINED.

LOADING

TOTAL LOAD CASES: (4)

CHORDS				WEBS			
MEMB.	MAX. FACTORED FORCE (LBS)	FACTORED VERT. LOAD (PLF)	LC1 MAX CSI (LC)	MEMB.	MAX. FACTORED FORCE (LBS)	MAX. FACTORED VERT. LOAD (PLF)	LC1 MAX CSI (LC)
FR-TO		FROM TO		FR-TO		FROM TO	
1-2	0 / 29	-77.4	-77.4 0.10 (1)	10.00	14-3	-123 / 45	0.04 (1)
2-3	-1148 / 0	-77.4	-77.4 0.24 (1)	5.67	3-13	-286 / 0	0.21 (1)
3-4	-943 / 0	-77.4	-77.4 0.23 (1)	6.11	13-4	0 / 254	0.06 (1)
4-5	-768 / 0	-77.4	-77.4 0.10 (1)	6.25	4-12	0 / 3	0.00 (1)
5-6	-944 / 0	-77.4	-77.4 0.23 (1)	6.11	12-5	0 / 257	0.06 (1)
6-7	-1148 / 0	-77.4	-77.4 0.24 (1)	5.68	12-6	-285 / 0	0.21 (1)
7-8	0 / 29	-77.4	-77.4 0.10 (1)	10.00	10-6	-125 / 44	0.04 (1)
15-2	-1118 / 0	0.0	0.0 0.12 (1)	7.49	2-14	0 / 999	0.22 (1)
9-7	-1118 / 0	0.0	0.0 0.12 (1)	7.50	10-7	0 / 999	0.22 (1)
15-14	0 / 0	-17.5	-17.5 0.10 (4)	10.00			
14-13	0 / 975	-17.5	-17.5 0.20 (1)	10.00			
13-12	0 / 767	-17.5	-17.5 0.16 (1)	10.00			
12-11	0 / 975	-17.5	-17.5 0.20 (1)	10.00			
11-10	0 / 975	-17.5	-17.5 0.20 (1)	10.00			
10-9	0 / 0	-17.5	-17.5 0.10 (4)	10.00			

DESIGN CRITERIA

SPECIFIED LOADS:
TOP CH. LL = 23.3 PSF
DL = 3.0 PSF
BOT CH. LL = 0.0 PSF
DL = 7.0 PSF
TOTAL LOAD = 33.3 PSF

SPACING = 24.0 IN. C/C

LOADING IN FLAT SECTION BASED ON A SLOPE OF 2.00/12 MINIMUM

THIS TRUSS IS DESIGNED FOR RESIDENTIAL OR SMALL BUILDING REQUIREMENTS OF PART 9, NBCC 2010

THIS DESIGN COMPLIES WITH:
- PART 9 OF OBC 2012, BCBC 2012, ABC 2014
- CSA 086-09
- TPIC 2011

(55% OF 27.2 P.S.F. G.S.L. PLUS 8.4 P.S.F. RAIN LOAD) EQUALS 23.3 P.S.F. SPECIFIED ROOF LIVE LOAD

ALLOWABLE DEFL.(LL)= L/360 (0.74")
CALCULATED VERT. DEFL.(LL)= L/999 (0.03")
ALLOWABLE DEFL.(TL)= L/360 (0.74")
CALCULATED VERT. DEFL.(TL)= L/999 (0.06")

CSI: TC=0.24/1.00 (2-3:1), BC=0.20/1.00 (13-14:1), WB=0.22/1.00 (2-14:1), SSI=0.15/1.00 (2-3:1)

DOL LUMBER=1.00 NAIL=1.00 LS BEND=1.10 COMP=1.10 SHEAR=1.10 TENS=1.10

COMPANION LIVE LOAD FACTOR = 0.50

TRUSS PLATE MANUFACTURER IS NOT RESPONSIBLE FOR QUALITY CONTROL IN THE TRUSS MANUFACTURING PLANT.

NAIL VALUES	PLATE GRIP(DRY) SHEAR (PSI)	SECTION (PLI)	MAX MIN	MAX MIN	MAX MIN
MT20	618	354	1667	822	2284 1656

PLATE PLACEMENT TOL. = 0.250 inches


PLATE ROTATION TOL. = 5.0 Deg.

JSI GRIP= 0.87 (5) (INPUT = 0.90)
JSI METAL= 0.39 (2) (INPUT = 1.00)



READ ALL NOTES ON THIS PAGE AND ON ENGINEERING NOTE PAGE ENP-1. THIS NOTE PAGE IS AN INTEGRAL PART OF THIS DRAWING AS IT CONTAINS SPECIFICATIONS AND CRITERIA USED IN THE DESIGN OF THIS COMPONENT.





TOTAL WEIGHT = 5 X 96 = 478 lb [M][F]

LUMBER			
N. L. G. A. RULES	CHORDS	SIZE	DESCR.
1 - 4	2x4	DRY	No.2
4 - 7	2x4	DRY	No.2
13 - 2	2x4	DRY	No.2
8 - 6	2x4	DRY	No.2
13 - 10	2x4	DRY	No.2
10 - 8	2x4	DRY	No.2
ALL WEBS	2x3	DRY	No.2
EXCEPT			
DRY: SEASONED LUMBER.			

DIMENSIONS, SUPPORTS AND LOADINGS SPECIFIED BY FABRICATOR TO BE VERIFIED BY BUILDING DESIGNER

BEARINGS		FACTORED		MAXIMUM FACTORED		INPUT		REQRD	
JT	VERT	GROSS REACTION	HORZ	JT	VERT	GROSS REACTION	HORZ	BRG	IN-SX
13	1154	0	1154	0	0	5-8	5-8		
8	1154	0	1154	0	0	5-8	5-8		

UNFACTORED REACTIONS							
JT	COMBINED	SNOW	LIVE	PERM. LIVE	WIND	DEAD	SOIL
13	807	578 / 0	0 / 0	0 / 0	0 / 0	229 / 0	0 / 0
8	807	578 / 0	0 / 0	0 / 0	0 / 0	229 / 0	0 / 0

BEARING MATERIAL TO BE SPF NO.2 OR BETTER AT JOINT(S) 13, 8

BRACING
TOP CHORD TO BE SHEATHED OR MAX. PURLIN SPACING = 5.55 FT.
MAX. UNBRACED BOTTOM CHORD LENGTH = 10.00 FT OR RIGID CEILING DIRECTLY APPLIED.

ALL PITCH BREAKS AND PERIMETER CORNER JOINTS MUST BE Laterally RESTRAINED.

LOADING			
TOTAL LOAD CASES: (4)			
CHORDS		FACTORED	
MEMB.	FORCE (LBS)	VERT. LOAD (PLF)	MAX. CSI (LC)
FR-TO	FROM	TO	LENGTH
1-2	0 / 29	-77.4	-77.4 0.10 (1)
2-3	-1147 / 0	-77.4	-77.4 0.33 (1)
3-4	-858 / 0	-77.4	-77.4 0.31 (1)
4-5	-858 / 0	-77.4	-77.4 0.31 (1)
5-6	-1147 / 0	-77.4	-77.4 0.33 (1)
6-7	0 / 29	-77.4	-77.4 0.10 (1)
13-2	-1113 / 0	0.0	0.0 0.11 (1)
8-6	-1113 / 0	0.0	0.0 0.11 (1)
13-12	0 / 0	-17.5	-17.5 0.13 (4)
12-11	0 / 977	-17.5	-17.5 0.22 (1)
11-10	0 / 977	-17.5	-17.5 0.22 (1)
10-9	0 / 977	-17.5	-17.5 0.22 (1)
9-8	0 / 0	-17.5	-17.5 0.13 (4)

DESIGN CRITERIA			
SPECIFIED LOADS:			
TOP CH.	LL =	23.3	PSF
	DL =	3.0	PSF
BOT CH.	LL =	0.0	PSF
	DL =	7.0	PSF
TOTAL LOAD = 33.3 PSF			
SPACING = 24.0 IN. C/C			

THIS TRUSS IS DESIGNED FOR RESIDENTIAL OR SMALL BUILDING REQUIREMENTS OF PART 9, NBC 2010

THIS DESIGN COMPLIES WITH:
- PART 9 OF OBC 2012, BCBC 2012, ABC 2014
- CSA 086-09
- TPIC 2011

(55% OF 27.2 P.S.F. G.S.L. PLUS 8.4 P.S.F. RAIN LOAD) EQUALS 23.3 P.S.F. SPECIFIED ROOF LIVE LOAD

ALLOWABLE DEFL. (LL) = $L/360$ (0.74")
CALCULATED VERT. DEFL. (LL) = $L/999$ (0.03")
ALLOWABLE DEFL. (TL) = $L/360$ (0.74")
CALCULATED VERT. DEFL. (TL) = $L/999$ (0.07")

CSI: TC=0.33/1.00 (2-3:1), BC=0.22/1.00 (11-12:1), WB=0.39/1.00 (3-11:1), SSI=0.17/1.00 (2-3:1)

DOL LUMBER=1.00 NAIL=1.00 LS BEND=1.10 COMP=1.10 SHEAR=1.10 TENS=1.10

COMPANION LIVE LOAD FACTOR = 0.50

TRUSS PLATE MANUFACTURER IS NOT RESPONSIBLE FOR QUALITY CONTROL IN THE TRUSS MANUFACTURING PLANT.

NAIL VALUES			
PLATE	GRIP(DRY)	SHEAR	SECTION
(PSI)	(PLI)	(PLI)	(PLI)
MAX	MIN	MAX	MIN
MT20	618	354	1667
	822	2284	1656

PLATE PLACEMENT TOL. = 0.250 inches

PLATE ROTATION TOL. = 5.0 Deg.


JSI GRIP= 0.82 (9) (INPUT = 0.90)
JSI METAL= 0.40 (6) (INPUT = 1.00)

PLATES (table is in inches)					
JT	TYPE	PLATES	W	LEN	Y X
2	TMVW-I	MT20	4.0	5.0	1.75 2.00
3	TMWW-I	MT20	3.0	4.0	1.50 1.50
4	TTW+p	MT20	3.0	4.0	2.25 1.50
5	TMWW-I	MT20	3.0	4.0	1.50 1.50
6	TMVW-I	MT20	4.0	5.0	1.75 2.00
8	BMV1+p	MT20	2.0	4.0	
9	BMWW-I	MT20	4.0	4.0	2.00 1.50
10	BS-I	MT20	3.0	6.0	
11	BMWW-I	MT20	4.0	4.0	
12	BMWW-I	MT20	4.0	4.0	2.00 1.50
13	BMV1+p	MT20	2.0	4.0	



READ ALL NOTES ON THIS PAGE AND ON ENGINEERING NOTE PAGE ENP-1. THIS NOTE PAGE IS AN INTEGRAL PART OF THIS DRAWING AS IT CONTAINS SPECIFICATIONS AND CRITERIA USED IN THE DESIGN OF THIS COMPONENT.





TOTAL WEIGHT = 4 X 40 = 159 lb
(M/F)

LUMBER

N. L. G. A. RULES				
CHORDS	SIZE		LUMBER	DESCR
1 - 3	2x4	DRY	No.2	SPF
3 - 5	2x4	DRY	No.2	SPF
8 - 2	2x4	DRY	No.2	SPF
6 - 4	2x4	DRY	No.2	SPF
8 - 6	2x4	DRY	No.2	SPF
ALL WEBS EXCEPT	2x3	DRY	No.2	SPF

DRY: SEASONED LUMBER.

PLATES (table is in inches)

JT	TYPE	PLATES	W	LEN	Y	X
2	TMVW-t	MT20	3.0	5.0	1.50	2.00
3	TTW+p	MT20	3.0	4.0	2.25	1.50
4	TMVW-t	MT20	3.0	5.0	1.50	2.00
6	BMV1+p	MT20	2.0	4.0		
7	BMVWW-t	MT20	3.0	6.0		
8	BMV1+p	MT20	2.0	4.0		

DIMENSIONS, SUPPORTS AND LOADINGS SPECIFIED BY FABRICATOR TO BE VERIFIED BY BUILDING DESIGNER

JT	FACTORED GROSS REACTION		MAXIMUM FACTORED GROSS REACTION		INPUT BRG	REQRD BRG
	VERT	HORZ	DOWN	HORZ UPLIFT		
8	549	0	549	0	5-8	5-8
6	549	0	549	0	5-8	5-8

UNFACTORED REACTIONS

JT	1ST LCASE		MAX/MIN. COMPONENT REACTIONS		WIND	DEAD	SOIL
	COMBINED	SNOW	LIVE	PERM. LIVE			
8	383	281 / 0	0 / 0	0 / 0	0 / 0	102 / 0	0 / 0
6	383	281 / 0	0 / 0	0 / 0	0 / 0	102 / 0	0 / 0

BEARING MATERIAL TO BE SPF NO.2 OR BETTER AT JOINT(S) 8, 6

BRACING

TOP CHORD TO BE SHEATHED OR MAX. PURLIN SPACING = 6.25 FT.
MAX. UNBRACED BOTTOM CHORD LENGTH = 10.00 FT OR RIGID CEILING DIRECTLY APPLIED.

ALL PITCH BREAKS AND PERIMETER CORNER JOINTS MUST BE Laterally RESTRAINED.

LOADING

TOTAL LOAD CASES: (4)

CHORDS					WEBS				
MEMB.	MAX. FACTORED FORCE (LBS)	FACTORED VERT. LOAD (PLF)	LC1 MAX. CSI (LC)	MAX. UNBRACED LENGTH	MEMB.	MAX. FACTORED FORCE (LBS)	MAX. CSI (LC)		
FR-TO		FROM TO			FR-TO				
1-2	0 / 29	-77.4	-77.4	0.10 (1)	10.00	7-3	-19 / 74	0.03 (4)	
2-3	-309 / 0	-77.4	-77.4	0.22 (1)	6.25	2-7	0 / 263	0.06 (1)	
3-4	-309 / 0	-77.4	-77.4	0.22 (1)	6.25	7-4	0 / 263	0.06 (1)	
4-5	0 / 29	-77.4	-77.4	0.10 (1)	10.00				
8-2	-517 / 0	0.0	0.0	0.05 (1)	7.81				
6-4	-517 / 0	0.0	0.0	0.05 (1)	7.81				
8-7	0 / 0	-17.5	-17.5	0.11 (4)	10.00				
7-6	0 / 0	-17.5	-17.5	0.11 (4)	10.00				

DESIGN CRITERIA

SPECIFIED LOADS:
TOP CH. LL = 23.3 PSF
DL = 3.0 PSF
BOT CH. LL = 0.0 PSF
DL = 7.0 PSF
TOTAL LOAD = 33.3 PSF

SPACING = 24.0 IN. C/C

THIS TRUSS IS DESIGNED FOR RESIDENTIAL OR SMALL BUILDING REQUIREMENTS OF PART 9, NBC 2010

THIS DESIGN COMPLIES WITH:
- PART 9 OF OBC 2012, BCBC 2012, ABC 2014
- CSA 086-09
- TPIC 2011

(55% OF 27.2 P.S.F. G.S.L. PLUS 8.4 P.S.F. RAIN LOAD) EQUALS 23.3 P.S.F. SPECIFIED ROOF LIVE LOAD

ALLOWABLE DEFL.(LL) = L/360 (0.31")
CALCULATED VERT. DEFL.(LL) = L/999 (0.00")
ALLOWABLE DEFL.(TL) = L/360 (0.31")
CALCULATED VERT. DEFL.(TL) = L/999 (0.01")

CSI: TC=0.22/1.00 (2-3:1), BC=0.11/1.00 (7-8:4), WB=0.06/1.00 (2-7:1), SSI=0.12/1.00 (2-3:1)

DOL LUMBER=1.00 NAIL=1.00 LS BEND=1.10
COMP=1.10 SHEAR=1.10 TENS= 1.10

COMPANION LIVE LOAD FACTOR = 0.50

TRUSS PLATE MANUFACTURER IS NOT RESPONSIBLE FOR QUALITY CONTROL IN THE TRUSS MANUFACTURING PLANT .

NAIL VALUES
PLATE GRIP(DRY) SHEAR SECTION
(PSI) (PLI) (PLI)
MAX MIN MAX MIN MAX MIN
MT20 618 354 1667 822 2284 1656

PLATE PLACEMENT TOL. = 0.250 inches


PLATE ROTATION TOL. = 5.0 Deg.

JSI GRIP= 0.48 (7) (INPUT = 0.90)
JSI METAL= 0.14 (4) (INPUT = 1.00)



READ ALL NOTES ON THIS PAGE AND ON ENGINEERING NOTE PAGE ENP-1. THIS NOTE PAGE IS AN INTEGRAL PART OF THIS DRAWING AS IT CONTAINS SPECIFICATIONS AND CRITERIA USED IN THE DESIGN OF THIS COMPONENT.





TOTAL WEIGHT = 2 X 37 = 74 lb
[M][F]

LUMBER			
N. L. G. A. RULES	SIZE	LUMBER	DESCR.
CHORDS			
1 - 3	2x4	DRY	No.2
3 - 4	2x4	DRY	No.2
7 - 2	2x4	DRY	No.2
5 - 4	2x4	DRY	No.2
7 - 5	2x4	DRY	No.2
ALL WEBS	2x3	DRY	No.2
EXCEPT			
DRY: SEASONED LUMBER.			

PLATES (table is in inches)						
JT	TYPE	PLATES	W	LEN	Y	X
2	TMVW-t	MT20	3.0	5.0	1.50	2.00
3	TTW+p	MT20	3.0	4.0	2.25	1.50
4	TMVW-t	MT20	3.0	4.0	1.50	1.00
5	BMV1+p	MT20	2.0	4.0		
6	BMWWW-t	MT20	3.0	6.0		
7	BMV1+p	MT20	2.0	4.0		

DIMENSIONS, SUPPORTS AND LOADINGS SPECIFIED BY FABRICATOR TO BE VERIFIED BY BUILDING DESIGNER

BEARINGS							
FACTORED		MAXIMUM FACTORED		INPUT		REQRD	
GROSS REACTION		GROSS REACTION		BRG		BRG	
JT	VERT	HORZ	DOWN	HORZ	UPLIFT	IN-SX	IN-SX
7	527	0	527	0	0	5-8	5-8
5	421	0	421	0	0	MECHANICAL	

A SUITABLE MECHANICAL CONNECTION IS REQUIRED AT JOINT 5 TO RESIST THE MAX FACTORED REACTIONS.

UNFACTORED REACTIONS

1ST LCASE		MAX./MIN. COMPONENT REACTIONS					
JT	COMBINED	SNOW	LIVE	PERM.LIVE	WIND	DEAD	SOIL
7	368	271 / 0	0 / 0	0 / 0	0 / 0	97 / 0	0 / 0
5	295	207 / 0	0 / 0	0 / 0	0 / 0	89 / 0	0 / 0

BEARING MATERIAL TO BE SPF NO.2 OR BETTER AT JOINT(S) 7

BRACING

TOP CHORD TO BE SHEATHED OR MAX. PURLIN SPACING = 6.25 FT.
MAX. UNBRACED BOTTOM CHORD LENGTH = 10.00 FT OR RIGID CEILING DIRECTLY APPLIED.

ALL PITCH BREAKS AND PERIMETER CORNER JOINTS MUST BE Laterally RESTRAINED.

LOADING

TOTAL LOAD CASES: (4)

CHORDS					WEBS				
MEMB.	MAX. FACTORED FORCE (LBS)	FACTORED VERT. LOAD (PLF)	LC1 MAX	MAX. CS1 (LC)	MEMB.	MAX. FACTORED FORCE (LBS)	MAX. CS1 (LC)		
FR-TO		FROM TO			FR-TO				
1-2	0 / 29	-77.4	-77.4	0.10 (1)	10.00	6-3	-35 / 65	0.02 (4)	
2-3	-278 / 0	-77.4	-77.4	0.22 (1)	6.25	2-6	0 / 238	0.05 (1)	
3-4	-278 / 0	-77.4	-77.4	0.18 (1)	6.25	6-4	0 / 244	0.05 (1)	
7-2	-495 / 0	0.0	0.0	0.05 (1)	7.81				
5-4	-393 / 0	0.0	0.0	0.04 (1)	7.81				
7-6	0 / 0	-17.5	-17.5	0.10 (4)	10.00				
6-5	0 / 0	-17.5	-17.5	0.10 (4)	10.00				

DESIGN CRITERIA

SPECIFIED LOADS:
TOP CH. LL = 23.3 PSF
DL = 3.0 PSF
BOT CH. LL = 0.0 PSF
DL = 7.0 PSF
TOTAL LOAD = 33.3 PSF

SPACING = 24.0 IN. C/C

THIS TRUSS IS DESIGNED FOR RESIDENTIAL OR SMALL BUILDING REQUIREMENTS OF PART 9, NBC 2010

THIS DESIGN COMPLIES WITH:
- PART 9 OF OBC 2012, BCBC 2012, ABC 2014
- CSA 086-09
- TPIC 2011

(55 % OF 27.2 P.S.F. G.S.L. PLUS 8.4 P.S.F. RAIN LOAD) EQUALS 23.3 P.S.F. SPECIFIED ROOF LIVE LOAD

ALLOWABLE DEFL.(LL) = L/360 (0.30")
CALCULATED VERT. DEFL.(LL) = L/999 (0.00")
ALLOWABLE DEFL.(TL) = L/360 (0.30")
CALCULATED VERT. DEFL.(TL) = L/999 (0.01")

CSI: TC=0.22/1.00 (2-3:1), BC=0.10/1.00 (5-6:4), WB=0.05/1.00 (4-6:1), SSI=0.12/1.00 (2-3:1)

DOL LUMBER=1.00 NAIL=1.00 LS BEND=1.10
COMP=1.10 SHEAR=1.10 TENS= 1.10

COMPANION LIVE LOAD FACTOR = 0.50

TRUSS PLATE MANUFACTURER IS NOT RESPONSIBLE FOR QUALITY CONTROL IN THE TRUSS MANUFACTURING PLANT.

NAIL VALUES					
PLATE	GRIP(DRY)	SHEAR	SECTION		
(PSI)	(PLI)	(PLI)	(PLI)		
	MAX	MIN	MAX	MIN	MAX
MT20	618	354	1667	822	2284

PLATE PLACEMENT TOL. = 0.250 inches


PLATE ROTATION TOL. = 5.0 Deg.

JSI GRIP= 0.79 (4) (INPUT = 0.90)
JSI METAL= 0.14 (4) (INPUT = 1.00)



READ ALL NOTES ON THIS PAGE AND ON ENGINEERING NOTE PAGE ENP-1. THIS NOTE PAGE IS AN INTEGRAL PART OF THIS DRAWING AS IT CONTAINS SPECIFICATIONS AND CRITERIA USED IN THE DESIGN OF THIS COMPONENT.





LUMBER				DESCR.	
N. L. G. A. RULES					
CHORDS	SIZE	LUMBER			
1 - 3	2x4	DRY	No.2	SPF	
3 - 4	2x4	DRY	No.2	SPF	
7 - 2	2x4	DRY	No.2	SPF	
5 - 4	2x4	DRY	No.2	SPF	
7 - 5	2x4	DRY	No.2	SPF	
ALL WEBS	2x3	DRY	No.2	SPF	
EXCEPT					

DRY: SEASONED LUMBER.

PLATES (table is in inches)						
JT	TYPE	PLATES	W	LEN	Y	X
2	TMVW-l	MT20	3.0	5.0	1.50	2.00
3	TTW+p	MT20	3.0	4.0	2.25	1.50
4	TMVW-l	MT20	3.0	5.0	1.50	2.00
5	BMV1+p	MT20	2.0	4.0		
6	BMVWW-l	MT20	3.0	6.0		
7	BMV1+p	MT20	2.0	4.0		

READ ALL NOTES ON THIS PAGE AND ON ENGINEERING NOTE PAGE ENP-1. THIS NOTE PAGE IS AN INTEGRAL PART OF THIS DRAWING AS IT CONTAINS SPECIFICATIONS AND CRITERIA USED IN THE DESIGN OF THIS COMPONENT.

DIMENSIONS, SUPPORTS AND LOADINGS SPECIFIED BY FABRICATOR TO BE VERIFIED BY BUILDING DESIGNER									
BEARINGS									
JT	FACTORED GROSS REACTION	MAXIMUM FACTORED GROSS REACTION	INPUT BRG	REQRD BRG					
VERT	HORZ	DOWN	HORZ	UPLIFT	IN-SX				
7	382	0	382	0	0	3-0	3-0		
5	273	0	273	0	0	3-0	3-0		

UNFACTORED REACTIONS									
JT	1ST LCASE	MAX./MIN. COMPONENT REACTIONS							
COMBINED	SNOW	LIVE	PERM.LIVE	WIND	DEAD	SOIL			
7	265	199 / 0	0 / 0	0 / 0	0 / 0	66 / 0	0 / 0		
5	191	134 / 0	0 / 0	0 / 0	0 / 0	57 / 0	0 / 0		

BEARING MATERIAL TO BE SPF NO.2 OR BETTER AT JOINT(S) 7, 5

BRACING
 TOP CHORD TO BE SHEATHED OR MAX. PURLIN SPACING = 6.25 FT.
 MAX. UNBRACED BOTTOM CHORD LENGTH = 10.00 FT OR RIGID CEILING DIRECTLY APPLIED.
 ALL PITCH BREAKS AND PERIMETER CORNER JOINTS MUST BE Laterally RESTRAINED.

LOADING									
TOTAL LOAD CASES: (4)									
CHORDS					WEBS				
MEMB.	MAX. FACTORED FORCE (LBS)	FACTORED VERT. LOAD (PLF)	LC1 MAX CSI (LC)	MAX. UNBRACED LENGTH	MEMB.	MAX. FACTORED FORCE (LBS)	MAX CSI (LC)		
FR-TO		FROM	TO		FR-TO				
1-2	0 / 27	-77.4	-77.4	0.11 (1)	10.00	6-3	-22 / 42	0.01 (4)	
2-3	-199 / 0	-77.4	-77.4	0.11 (1)	6.25	2-6	0 / 177	0.04 (1)	
3-4	-199 / 0	-77.4	-77.4	0.11 (1)	6.25	6-4	0 / 177	0.04 (1)	
7-2	-361 / 0	0.0	0.0	0.04 (1)	7.81				
5-4	-252 / 0	0.0	0.0	0.03 (1)	7.81				
7-6	0 / 0	-17.5	-17.5	0.04 (4)	10.00				
6-5	0 / 0	-17.5	-17.5	0.04 (4)	10.00				

DESIGN CRITERIA
 SPECIFIED LOADS:
 TOP CH. LL = 23.3 PSF
 DL = 3.0 PSF
 BOT CH. LL = 0.0 PSF
 DL = 7.0 PSF
 TOTAL LOAD = 33.3 PSF
 SPACING = 24.0 IN. C/C
 THIS TRUSS IS DESIGNED FOR RESIDENTIAL OR SMALL BUILDING REQUIREMENTS OF PART 9, NBCC 2010
 THIS DESIGN COMPLIES WITH:
 - PART 9 OF OBC 2012, BCBC 2012, ABC 2014
 - CSA 086-09
 - TPIC 2011
 (55 % OF 27.2 P.S.F. G.S.L. PLUS 8.4 P.S.F. RAIN LOAD) EQUALS 23.3 P.S.F. SPECIFIED ROOF LIVE LOAD
 ALLOWABLE DEFL.(LL)= L/360 (0.19")
 CALCULATED VERT. DEFL.(LL) = L/ 999 (0.00")
 ALLOWABLE DEFL.(TL)= L/360 (0.19")
 CALCULATED VERT. DEFL.(TL) = L/ 999 (0.00")
 CSI: TC=0.11/1.00 (2-3:1), BC=0.04/1.00 (5-6:4), WB=0.04/1.00 (4-6:1), SSI=0.07/1.00 (2-3:1)
 DOL LUMBER=1.00 NAIL=1.00 LS BEND=1.10
 COMP=1.10 SHEAR=1.10 TENS= 1.10
 COMPANION LIVE LOAD FACTOR = 0.50
 TRUSS PLATE MANUFACTURER IS NOT RESPONSIBLE FOR QUALITY CONTROL IN THE TRUSS MANUFACTURING PLANT .
 NAIL VALUES


PLATE	GRIP(DRY)	SHEAR	SECTION
	(PSI)	(PLI)	(PLI)
	MAX MIN	MAX MIN	MAX MIN
MT20	618 354	1667 822	2284 1656

 PLATE PLACEMENT TOL. = 0.250 inches
 PLATE ROTATION TOL. = 5.0 Deg.
 JSI GRIP= 0.33 (6) (INPUT = 0.90)
 JSI METAL= 0.09 (4) (INPUT = 1.00)



READ ALL NOTES ON THIS PAGE AND ON ENGINEERING NOTE PAGE ENP-1. THIS NOTE PAGE IS AN INTEGRAL PART OF THIS DRAWING AS IT CONTAINS SPECIFICATIONS AND CRITERIA USED IN THE DESIGN OF THIS COMPONENT.





TOTAL WEIGHT = 3 X 23 = 68 lb (M)

LUMBER	N. L. G. A. RULES	CHORDS	SIZE	LUMBER	DESCR.
1 - 3	2x4	DRY	No.2	SPF	
3 - 4	2x4	DRY	No.2	SPF	
8 - 2	2x4	DRY	No.2	SPF	
6 - 4	2x4	DRY	No.2	SPF	
8 - 5	2x4	DRY	No.2	SPF	

ALL WEBS 2x3 DRY No.2 SPF

EXCEPT

DRY: SEASONED LUMBER.

PLATES (table is in inches)

JT	TYPE	PLATES	W	LEN	Y	X
2	TMVW-t	MT20	3.0	5.0	1.50	2.00
3	TTW+p	MT20	3.0	4.0	2.25	1.50
4	TMVW-t	MT20	3.0	4.0	1.50	1.00
6	BMV+p	MT20	2.0	4.0		
7	BMVWW-t	MT20	3.0	6.0		
8	BMV1+p	MT20	2.0	4.0		

DIMENSIONS, SUPPORTS AND LOADINGS SPECIFIED BY FABRICATOR TO BE VERIFIED BY BUILDING DESIGNER

BEARINGS		FACTORED		MAXIMUM FACTORED		INPUT		REQ'D	
JT	VERT	GROSS REACTION	GROSS REACTION	DOWN	HORIZ	UPLIFT	IN-SX	BRG	IN-SX
8	389	0	389	0	0	3-0	3-0	3-0	3-0
5	281	0	281	0	0	1-8	1-8	1-8	1-8

UNFACTORED REACTIONS

JT	1ST LCASE	SNOW	LIVE	PERM.LIVE	WIND	DEAD	SOIL
8	271	203 / 0	0 / 0	0 / 0	0 / 0	68 / 0	0 / 0
5	197	138 / 0	0 / 0	0 / 0	0 / 0	59 / 0	0 / 0

BEARING MATERIAL TO BE SPF NO.2 OR BETTER AT JOINT(S) 8, 5

BRACING

TOP CHORD TO BE SHEATHED OR MAX. PURLIN SPACING = 6.25 FT.
MAX. UNBRACED BOTTOM CHORD LENGTH = 10.00 FT OR RIGID CEILING DIRECTLY APPLIED.

ALL PITCH BREAKS AND PERIMETER CORNER JOINTS MUST BE Laterally RESTRAINED.

LOADING

TOTAL LOAD CASES: (4)

CHORDS				WEBS			
MEMB.	MAX. FACTORED FORCE (LBS)	FACTORED VERT. LOAD (PLF)	MAX. UNBRACED LENGTH (LC)	MEMB.	MAX. FACTORED FORCE (LBS)	MAX. UNBRACED LENGTH (LC)	
FR-TO		FROM TO		FR-TO			
1-2	0 / 27	-77.4 -77.4	0.11 (1)	10.00	7-3	0 / 53	0.02 (4)
2-3	-230 / 0	-77.4 -77.4	0.11 (1)	6.25	2-7	0 / 204	0.05 (1)
3-4	-230 / 0	-77.4 -77.4	0.06 (1)	6.25	7-4	0 / 222	0.05 (1)
8-2	-383 / 0	0.0 0.0	0.04 (1)	7.81			
6-4	-300 / 0	0.0 0.0	0.03 (1)	7.81			
8-7	0 / 0	-17.5 -17.5	0.07 (1)	10.00			
7-6	0 / 0	-17.5 -17.5	0.28 (1)	10.00			
6-5	0 / 0	-94.9 -94.9	0.28 (1)	10.00			

DESIGN CRITERIA

SPECIFIED LOADS:
TOP CH. LL = 23.3 PSF
DL = 3.0 PSF
BOT CH. LL = 0.0 PSF
DL = 7.0 PSF
TOTAL LOAD = 33.3 PSF

SPACING = 24.0 IN. C/C

THIS TRUSS IS DESIGNED FOR RESIDENTIAL OR SMALL BUILDING REQUIREMENTS OF PART 9, NBC 2010

THIS DESIGN COMPLIES WITH:
- PART 9 OF OBC 2012, BCBC 2012, ABC 2014
- CSA 086-09
- TPIC 2011

(55% OF 27.2 P.S.F. G.S.L. PLUS 8.4 P.S.F. RAIN LOAD) EQUALS 23.3 P.S.F. SPECIFIED ROOF LIVE LOAD

ALLOWABLE DEFL.(LL)= L/360 (0.20")
CALCULATED VERT. DEFL.(LL) = L/999 (0.02")
ALLOWABLE DEFL.(TL)= L/360 (0.20")
CALCULATED VERT. DEFL.(TL) = L/999 (0.04")

CSI: TC=0.11/1.00 (2-3:1), BC=0.28/1.00 (6-7:1), WB=0.05/1.00 (4-7:1), SSI=0.22/1.00 (5-6:1)

DOL LUMBER=1.00 NAIL=1.00 LS BEND=1.10
COMP=1.10 SHEAR=1.10 TENS=1.10

COMPANION LIVE LOAD FACTOR = 0.50

TRUSS PLATE MANUFACTURER IS NOT RESPONSIBLE FOR QUALITY CONTROL IN THE TRUSS MANUFACTURING PLANT.

NAIL VALUES
PLATE GRIP(DRY) SHEAR SECTION (PSI) (PLI) (PLI)
MAX MIN MAX MIN MAX MIN
MT20 618 354 1667 822 2284 1656

PLATE PLACEMENT TOL. = 0.250 inches


PLATE ROTATION TOL. = 5.0 Deg.

JSI GRIP= 0.76 (4) (INPUT = 0.90)
JSI METAL= 0.10 (2) (INPUT = 1.00)



READ ALL NOTES ON THIS PAGE AND ON ENGINEERING NOTE PAGE ENP-1. THIS NOTE PAGE IS AN INTEGRAL PART OF THIS DRAWING AS IT CONTAINS SPECIFICATIONS AND CRITERIA USED IN THE DESIGN OF THIS COMPONENT.





Scale = 1:22.9

TOTAL WEIGHT = 2 X 23 = 47 lb [M]

LUMBER	N. L. G. A. RULES	CHORDS	SIZE	LUMBER	DESCR.
1 - 3	2x4	DRY	No.2	SPF	
5 - 3	2x4	DRY	No.2	SPF	
6 - 2	2x4	DRY	No.2	SPF	
6 - 4	2x4	DRY	No.2	SPF	
ALL WEBS	2x3	DRY	No.2	SPF	
DRY: SEASONED LUMBER.					

PLATES (table is in inches)

JT	TYPE	PLATES	W	LEN	Y	X
2	TMVW-1	MT20	3.0	5.0	1.50	2.00
3	TMV+p	MT20	2.0	4.0		
5	BMVW-1	MT20	3.0	4.0		
6	BMV1+p	MT20	2.0	4.0		

DIMENSIONS, SUPPORTS AND LOADINGS SPECIFIED BY FABRICATOR TO BE VERIFIED BY BUILDING DESIGNER

BEARINGS		FACTORED GROSS REACTION		MAXIMUM FACTORED GROSS REACTION		INPUT BRG		REQRD BRG	
JT		VERT	HORZ	DOWN	HORZ	IN-SX		IN-SX	
6		384	0	384	0	3-0		3-0	
4		218	0	218	0	1-8		1-8	

UNFACTORED REACTIONS

1ST LCASE		MAX/MIN. COMPONENT REACTIONS						
JT	COMBINED	SNOW	LIVE	PERM. LIVE	WIND	DEAD	SOIL	
6	268	200 / 0	0 / 0	0 / 0	0 / 0	67 / 0	0 / 0	
4	154	100 / 0	0 / 0	0 / 0	0 / 0	54 / 0	0 / 0	

BEARING MATERIAL TO BE SPF NO.2 OR BETTER AT JOINT(S) 6, 4

BRACING

TOP CHORD TO BE SHEATHED OR MAX. PURLIN SPACING = 10.00 FT.
MAX. UNBRACED BOTTOM CHORD LENGTH = 10.00 FT OR RIGID CEILING DIRECTLY APPLIED.

ALL PITCH BREAKS AND PERIMETER CORNER JOINTS MUST BE Laterally RESTRAINED.

LOADING

TOTAL LOAD CASES: (4)

CHORDS				WEBS			
MEMB.	MAX. FACTORED FORCE (LBS)	FACTORED VERT. LOAD (PLF)	LC1 MAX	MEMB.	MAX. FACTORED FORCE (LBS)	MAX	LC
FR-TO		FROM TO	CSI (LC)	LENGTH FR-TO			
1-2	0 / 27	-77.4	-77.4 0.11 (1)	10.00	2-5	0 / 0	0.00 (1)
2-3	0 / 0	-77.4	-77.4 0.33 (1)	10.00			
5-3	-195 / 0	0.0	0.0 0.05 (1)	7.81			
6-2	-304 / 0	0.0	0.0 0.03 (1)	7.81			
6-5	0 / 0	-17.5	-17.5 0.25 (1)	10.00			
5-4	0 / 0	-17.5	-17.5 0.25 (1)	10.00			

DESIGN CRITERIA

SPECIFIED LOADS:

TOP CH.	LL = 23.3	PSF
	DL = 3.0	PSF
BOT CH.	LL = 0.0	PSF
	DL = 7.0	PSF
TOTAL LOAD	= 33.3	PSF

SPACING = 24.0 IN. C/C

THIS TRUSS IS DESIGNED FOR RESIDENTIAL OR SMALL BUILDING REQUIREMENTS OF PART 9, NBCC 2010

THIS DESIGN COMPLIES WITH:

- PART 9 OF OBC 2012, BCBC 2012, ABC 2014
- CSA 086-09
- TPIC 2011

(55 % OF 27.2 P.S.F. G.S.L. PLUS 8.4 P.S.F. RAIN LOAD) EQUALS 23.3 P.S.F. SPECIFIED ROOF LIVE LOAD

ALLOWABLE DEFL.(LL)= L/360 (0.20")
CALCULATED VERT. DEFL.(LL)= L/999 (0.05")
ALLOWABLE DEFL.(TL)= L/360 (0.20")
CALCULATED VERT. DEFL.(TL)= L/555 (0.13")

CSI: TC=0.33/1.00 (2-3:1), BC=0.25/1.00 (5-6:1), WB=0.00/1.00 (2-5:1), SSI=0.17/1.00 (4-5:1)

DOL LUMBER=1.00 NAIL=1.00 LS BEND=1.10 COMP=1.10 SHEAR=1.10 TENS= 1.10

COMPANION LIVE LOAD FACTOR = 0.50

TRUSS PLATE MANUFACTURER IS NOT RESPONSIBLE FOR QUALITY CONTROL IN THE TRUSS MANUFACTURING PLANT.

NAIL VALUES

PLATE	GRIP(DRY)	SHEAR	SECTION
	(PSI)	(PLI)	(PLI)
MAX MIN	MAX MIN	MAX MIN	MAX MIN
MT20	618 354	1667 822	2284 1656

PLATE PLACEMENT TOL. = 0.250 inches


PLATE ROTATION TOL. = 5.0 Deg.

JSI GRIP= 0.26 (2) (INPUT = 0.90)
JSI METAL= 0.06 (6) (INPUT = 1.00)



READ ALL NOTES ON THIS PAGE AND ON ENGINEERING NOTE PAGE ENP-1. THIS NOTE PAGE IS AN INTEGRAL PART OF THIS DRAWING AS IT CONTAINS SPECIFICATIONS AND CRITERIA USED IN THE DESIGN OF THIS COMPONENT.





TOTAL WEIGHT = 5 X 20 = 100 lb (M)

LUMBER	N. L. G. A. RULES	CHORDS	SIZE	DRY	LUMBER	DESCR.
1 - 3	2x4	DRY	No.2	SPF		
5 - 3	2x4	DRY	No.2	SPF		
2 - 4	2x4	DRY	No.2	SPF		
REINFORCING MEMBERS						
HW1	2x4	DRY	No.2	SPF		

DRY: SEASONED LUMBER.

PLATES (table is in inches)

JT	TYPE	PLATES	W	LEN	Y	X
2	TMBMW1-I	MT20	4.0	5.0	2.00	1.50
3	TMV+p	MT20	2.0	4.0		
5	BMVW-I	MT20	4.0	4.0		

DIMENSIONS, SUPPORTS AND LOADINGS SPECIFIED BY FABRICATOR TO BE VERIFIED BY BUILDING DESIGNER

<u>BEARINGS</u>		FACTORED		MAXIMUM FACTORED		INPUT	REQRD
	GROSS REACTION		GROSS REACTION			BRG	BRG
JT	VERT	HORZ	DOWN	HORZ	UPLIFT	IN-SX	IN-SX
2	358	0	358	0	0	3-0	3-0
4	195	0	195	0	0	1-8	1-8

UNFACTORED REACTIONS

JT	1ST LCASE	MAX/MIN. COMPONENT REACTIONS	SNOW	LIVE	PERM. LIVE	WIND	DEAD	SOIL
2	249	187 / 0	0 / 0	0 / 0	0 / 0	0 / 0	62 / 0	0 / 0
4	138	89 / 0	0 / 0	0 / 0	0 / 0	0 / 0	49 / 0	0 / 0

BEARING MATERIAL TO BE SPF NO.2 OR BETTER AT JOINT(S) 2, 4

BRACING

TOP CHORD TO BE SHEATHED OR MAX. PURLIN SPACING = 6.25 FT.
MAX. UNBRACED BOTTOM CHORD LENGTH = 10.00 FT OR RIGID CEILING DIRECTLY APPLIED.

ALL PITCH BREAKS AND PERIMETER CORNER JOINTS MUST BE Laterally RESTRAINED.

LOADING

TOTAL LOAD CASES: (4)

CHORDS		FACTORED		WEBS		FACTORED	
MEMB.	FORCE (LBS)	VERT. LOAD	LC1 MAX	MAX. MEMB.	FORCE (LBS)	MAX. MEMB.	FORCE (LBS)
FR-TO		FROM TO	CSI (LC)	UNBRAC	FR-TO		CSI (LC)
1-2	0 / 5	-77.4	-77.4 0.10 (1)	10.00	5-7	-550 / 0	0.11 (1)
2-7	-617 / 0	-77.4	-77.4 0.12 (1)	6.25	6-7	0 / 209	0.00 (1)
7-3	0 / 4	-77.4	-77.4 0.15 (1)	10.00			
5-3	-135 / 0	0.0	0.0 0.02 (1)	7.81			
2-6	0 / 535	-17.5	-17.5 0.17 (1)	10.00			
6-5	0 / 535	-17.5	-17.5 0.34 (1)	10.00			
5-4	0 / 0	-17.5	-17.5 0.26 (1)	10.00			

DESIGN CRITERIA

SPECIFIED LOADS:

TOP CH.	LL = 23.3	PSF
DL = 3.0	PSF	
BOT CH.	LL = 0.0	PSF
DL = 7.0	PSF	
TOTAL LOAD = 33.3	PSF	

SPACING = 24.0 IN. C/C

THIS TRUSS IS DESIGNED FOR RESIDENTIAL OR SMALL BUILDING REQUIREMENTS OF PART 9, NBCC 2010

THIS DESIGN COMPLIES WITH:
- PART 9 OF OBC 2012, BCBC 2012, ABC 2014
- CSA 086-09
- TPIC 2011

(55 % OF 27.2 P.S.F. G.S.L. PLUS 8.4 P.S.F. RAIN LOAD) EQUALS 23.3 P.S.F. SPECIFIED ROOF LIVE LOAD

ALLOWABLE DEFL.(LL) = $L/360$ (0.19")
CALCULATED VERT. DEFL.(LL) = $L/999$ (0.04")
ALLOWABLE DEFL.(TL) = $L/360$ (0.19")
CALCULATED VERT. DEFL.(TL) = $L/882$ (0.07")

CSI: TC=0.15/1.00 (3-7:1), BC=0.34/1.00 (5-6:1), WB=0.11/1.00 (5-7:1), SSI=0.15/1.00 (4-5:1)

DOL LUMBER=1.00 NAIL=1.00 LS BEND=1.10
COMP=1.10 SHEAR=1.10 TENS=1.10

COMPANION LIVE LOAD FACTOR = 0.50

TRUSS PLATE MANUFACTURER IS NOT RESPONSIBLE FOR QUALITY CONTROL IN THE TRUSS MANUFACTURING PLANT.

NAIL VALUES	PLATE	GRIP(DRY)	SHEAR	SECTION
	(PSI)	(PLI)	(PLI)	(PLI)
	MAX MIN	MAX MIN	MAX MIN	MAX MIN
MT20	618 354	1667 822	2284 1656	

PLATE PLACEMENT TOL. = 0.250 inches

PLATE ROTATION TOL. = 5.0 Deg.

JSI GRIP= 0.53 (5) (INPUT = 0.90)
JSI METAL= 0.20 (5) (INPUT = 1.00)




READ ALL NOTES ON THIS PAGE AND ON ENGINEERING NOTE PAGE ENP-1. THIS NOTE PAGE IS AN INTEGRAL PART OF THIS DRAWING AS IT CONTAINS SPECIFICATIONS AND CRITERIA USED IN THE DESIGN OF THIS COMPONENT.






DRY: SEASONED LUMBER.

JSI GRIP= 0.89 (18) (INPUT = 0.90)
JSI METAL= 0.82 (24) (INPUT = 1.00)





TOTAL WEIGHT = 4 X 27 = 107 lb [M]F

LUMBER
N. L. G. A. RULES
CHORDS SIZE LUMBER DESCR.
1 - 4 2x4 DRY No.2 SPF
2 - 4 2x4 DRY No.2 SPF
8 - 2 2x4 DRY No.2 SPF
8 - 5 2x4 DRY No.2 SPF
ALL WEBS 2x3 DRY No.2 SPF
EXCEPT
DRY: SEASONED LUMBER.

PLATES (table is in inches)

JT	TYPE	PLATES	W	LEN	Y	X
2	TMVW-t	MT20	3.0	4.0	1.50	1.50
3	TMVW-t	MT20	3.0	4.0		
4	TMV+p	MT20	2.0	4.0		
6	BMVW-t	MT20	3.0	4.0		
7	BMVW-t	MT20	3.0	4.0		
8	BMV1+p	MT20	2.0	4.0		

DIMENSIONS, SUPPORTS AND LOADINGS SPECIFIED BY FABRICATOR TO BE VERIFIED BY BUILDING DESIGNER

BEARINGS

JT	FACTORED GROSS REACTION		MAXIMUM FACTORED GROSS REACTION		INPUT BRG	REQRD BRG
	VERT	HORZ	DOWN	HORZ		
8	441	0	441	0	3-8	3-8
5	278	0	278	0	1-8	1-8

UNFACTORED REACTIONS

JT	1ST LCASE COMBINED	MAX./MIN. COMPONENT REACTIONS					
		SNOW	LIVE	PERM. LIVE	WIND	DEAD	SOIL
8	307	228 / 0	0 / 0	0 / 0	0 / 0	80 / 0	0 / 0
5	197	130 / 0	0 / 0	0 / 0	0 / 0	67 / 0	0 / 0

BEARING MATERIAL TO BE SPF NO.2 OR BETTER AT JOINT(S) 8, 5

BRACING
TOP CHORD TO BE SHEATHED OR MAX. PURLIN SPACING = 6.25 FT.
MAX. UNBRACED BOTTOM CHORD LENGTH = 10.00 FT OR RIGID CEILING DIRECTLY APPLIED.

ALL PITCH BREAKS AND PERIMETER CORNER JOINTS MUST BE Laterally RESTRAINED.

LOADING
TOTAL LOAD CASES: (4)

CHORDS					WEBS				
MEMB.	MAX. FACTORED FORCE (LBS)	FACTORED VERT. LOAD (PLF)	LC1 MAX	MAX. UNBRACED LENGTH	MEMB.	MAX. FACTORED FORCE (LBS)	MAX. UNBRACED LENGTH	MAX. FACTORED FORCE (LBS)	
FR-TO		FROM TO			FR-TO				
1-2	0 / 16	-77.4	-77.4	0.10 (1)	10.00	7-3	0 / 83	0.03 (4)	
2-3	-455 / 0	-77.4	-77.4	0.09 (1)	6.25	3-6	-498 / 0	0.11 (1)	
3-4	-8 / 0	-77.4	-77.4	0.09 (1)	10.00	2-7	0 / 448	0.10 (1)	
6-4	-96 / 0	0.0	0.0	0.01 (1)	7.81				
8-2	-434 / 0	0.0	0.0	0.04 (1)	7.81				
8-7	0 / 0	-17.5	-17.5	0.09 (1)	10.00				
7-6	0 / 439	-17.5	-17.5	0.39 (1)	10.00				
6-5	0 / 0	-17.5	-17.5	0.32 (1)	10.00				

DESIGN CRITERIA

SPECIFIED LOADS:
TOP CH. LL = 23.3 PSF
DL = 3.0 PSF
BOT CH. LL = 0.0 PSF
DL = 7.0 PSF
TOTAL LOAD = 33.3 PSF

SPACING = 24.0 IN. C/C

THIS TRUSS IS DESIGNED FOR RESIDENTIAL OR SMALL BUILDING REQUIREMENTS OF PART 9, NBCC 2010

THIS DESIGN COMPLIES WITH:
- PART 9 OF OBC 2012, BCBC 2012, ABC 2014
- CSA 086-09
- TPIC 2011

(55% OF 27.2 P.S.F. G.S.L. PLUS 8.4 P.S.F. RAIN LOAD) EQUALS 23.3 P.S.F. SPECIFIED ROOF LIVE LOAD

ALLOWABLE DEFL.(LL)= L/360 (0.24")
CALCULATED VERT. DEFL.(LL) = L/999 (0.04")
ALLOWABLE DEFL.(TL)= L/360 (0.24")
CALCULATED VERT. DEFL.(TL) = L/999 (0.07")

CSI: TC=0.10/1.00 (1-2:1), BC=0.39/1.00 (6-7:1), WB=0.11/1.00 (3-6:1), SSI=0.22/1.00 (5-6:1)

DOL LUMBER=1.00 NAIL=1.00 LS BEND=1.10 COMP=1.10 SHEAR=1.10 TENS=1.10

COMPANION LIVE LOAD FACTOR = 0.50

TRUSS PLATE MANUFACTURER IS NOT RESPONSIBLE FOR QUALITY CONTROL IN THE TRUSS MANUFACTURING PLANT.

NAIL VALUES

PLATE	GRIP(DRY)	SHEAR (PSI)	SECTION (PLI)
MT20	618	354	1667
	822	2284	1658

PLATE PLACEMENT TOL. = 0.250 inches

PLATE ROTATION TOL. = 5.0 Deg.

JSI GRIP= 0.88 (2) (INPUT = 0.90)
JSI METAL= 0.20 (2) (INPUT = 1.00)



READ ALL NOTES ON THIS PAGE AND ON ENGINEERING NOTE PAGE ENP-1. THIS NOTE PAGE IS AN INTEGRAL PART OF THIS DRAWING AS IT CONTAINS SPECIFICATIONS AND CRITERIA USED IN THE DESIGN OF THIS COMPONENT.




BEARING ANCHORAGE BY TOE-NAILS FOR LATERAL CAPACITY

B37579H1

NAIL TYPE	LENGTH (IN)	DIAMETER (IN)	NAIL LATERAL CAPACITY (LB)	
			S-P-F	D. FIR
COMMON WIRE	3.00	0.144	132	147
	3.25	0.144	132	147
	3.50	0.160	159	177

NOTES:

1. Rafter and ceiling members may be anchored to top and bottom chords of girder truss by toe-nailing rafter and ceiling members to girder chords provided the reaction does not exceed the lateral capacities in the table. Hangers (specified by others) are required for reactions higher than the maximum toe-nail capacity. Reactions are based on factored loads.
2. Toe nail capacities shown in the table are for one toe-nail. For additional toe-nails multiply values in table by the number of toe-nails used. Toe-nail capacities take into account toe-nailing factor J_A in CSA O86-09, section 10.9.4.1.
3. For 9- 3/4 gauge 3.25" common wire gun nails (diameter = 0.120") use 3" common spiral nail values.
4. Maximum number of toe-nails allowed depends on the lumber size & species to be toe-nailed to supporting member and nail diameter, as shown in tables below.
5. Nail values in table are based on the following relative lumber densities: $G = 0.42$ (SPF), $G = 0.49$ (D. Fir).
6. Toe-nails shall be driven at approximately 1/3 the nail length from the edge of the joist/truss chord and driven at an angle of 30° to the grain of the member (See next page for nailing on bearing plate).
7. For loads due to wind the nail lateral capacity in this table may be multiplied by 1.15 (K_D factor).
8. Lumber must be dry ($< 19\%$ moisture content) at the time of nail installation.
9. Nail values in this table comply with CSA O86-09, section 10.9.4
10. This design is not valid after April 30, 2019.



Nail type	Common wire	Common spiral	Common wire
Nail dia. (in)	0.160	0.152	0.144
	(3.5" nail)		(3" and 3.25" nail)
LUMBER SIZE	MAXIMUM NUMBER OF TOE-NAILS		
2X4 SPF	2	2	3
2X4 D. Fir	2	2	2
2X6 SPF	4	4	4
2X6 D. Fir	3	3	3



MiTek Canada Inc
100 Industrial Rd.
Bradford, Ontario L3Z 3G7

PEO
Certificate No. 10889485



April 26, 2017

BEARING ANCHORAGE BY TOE-NAILS FOR WIND LOADING

B37579H2



NAIL TYPE	LENGTH (IN)	DIAMETER (IN)	NAIL WITHDRAWAL CAPACITY (LB)	
			S-P-F	D. FIR
COMMON WIRE	3.00	0.144	30	42
	3.25	0.144	32	45
	3.50	0.160	38	52

Note: If using truss with D. Fir lumber and S-P-F bearing plate, use values in table for S-P-F.



NOTES:

1. Truss chord, rafter, or ceiling members may be anchored to bearing plate by toe-nails, provided that the actual factored uplift force due to **wind or earthquake** load does not exceed the withdrawal capacities in the table. Hangers (specified by others) are required for uplift forces that are higher than the maximum toe-nail withdrawal capacity.
2. Toe nail capacities shown in the table are for **one** toe-nail. For additional toe-nails multiply values in table by the number of toe-nails used. Toe-nail capacities take into account toe-nailing factor J_A in CSA O86-09, section 10.9.5.2.
3. For 9- 3/4 gauge 3.25" common wire gun nails (diameter = 0.120") use 3" common spiral nail values.
4. Maximum number of toe-nails allowed depends on the lumber size & species to be toe-nailed to supporting member and nail diameter, as shown in table above.
5. Nail values in table are based on the following relative lumber densities: $G = 0.42$ (SPF), $G = 0.49$ (D. Fir).
6. Toe-nails shall be driven at approximately 1/3 the nail length from the edge of the joist/truss chord and driven at an angle of 30° to the grain of the member (See drawing on detail B37579H1).
7. Lumber must be dry (< 19% moisture content) at the time of nail installation.
8. Nail values in this table comply with CSA O86-09, section 10.9.5
9. This design is not valid after April 30, 2019

Toe-nailing on 2x6 Bearing Plate



Toe-nailing on 2x4 Bearing Plate




MiTek Canada Inc
100 Industrial Rd.
Bradford, Ontario L3Z 3G7

PEO
Certificate No. 10889485



April 26, 2017

READ ALL NOTES ON THIS PAGE AND ON
ENGINEERING NOTE PAGE ENP-1. THIS
NOTE PAGE IS AN INTEGRAL PART OF
THIS DRAWING AS IT CONTAINS
SPECIFICATIONS AND CRITERIA USED IN
THE DESIGN OF THIS COMPONENT.



THIS CERTIFICATION IS FOR THE ENGINEERING REVIEW OF
STRUCTURAL COMPONENTS SHOWN ON THIS DRAWING
AND IS LIMITED TO THE COMPONENTS SUPPLIED BY KOTT
LUMBER FOR THE LOADS AND CONDITIONS SHOWN ON
THE CALCULATION PAGE OF EACH COMPONENT. THE
PLACEMENT OF THESE COMPONENTS ON THIS LAYOUT IS
SHOWN FOR REFERENCE ONLY. ROOF TRUSSES MUST BE
INSTALLED ACCORDING TO MANUFACTURER'S GUIDELINES
AT 24" C/C UNLESS NOTED OTHERWISE. CONVENTIONAL
FRAMING SHOWN ON THE LAYOUT MUST BE DESIGNED
AND APPROVED BY THE PROJECT ENGINEER. TEMPORARY
AND PERMANENT BRACINGS OF THE ROOF AND BUILDING
ARE THE RESPONSIBILITY OF THE PROJECT ENGINEER
AND TO CONFORM TO BCSI GUIDELINES.

CITY OF BRAMPTON
BUILDING DIVISION
REVIEWED
JAN 08 2019
BY
MARY FENETTE

All work shall conform to the Ontario
Building Code O. Reg. 332/12 as amended

For conventional framing roof / ceilings
framing shall conform to OBC.9.23

18-413520-000-02, RF

Architectural Drawing Info:
Date: JULY 23, 2018
Project number: 18012
Model: HEMLOCK 4

LOT 35L



CONVENTIONAL
FRAMING BY OTHERS

ALL CONVENTIONAL FRAMING TO CONFORM WITH
PART 9 OF THE O.B.C.
ROOF RAFTERS THAT CROSS MEET OVER TRUSSES
TO BE 2x4 S.P.F. @ 24" O/C WITH A 2x4 VERTICAL
POST TO THE TRUSS UNDERNEATH EACH CROSS
POINT. VERTICAL POST LONGER THAN 6' TO HAVE
LATERAL BRACING SO THAT THE DISTANCE BETWEEN
END POINT AND BETWEEN ROWS OF BRACING
DOES NOT EXCEED 6'.

SIZE AND LOCATION OF CONVENTIONAL FRAMING
IS APPROXIMATE. ALL AREAS MAY NOT BE SHOWN.
REFER TO ARCHITECTURAL PLANS FOR DETAILS.

HANGER LEGEND:

- ▼ LUS24
- LJS26DS
- HGUS26
- ✕ HGUS26-2

DESIGN CRITERIA
SPECIFIED LOADS:
TOP CH. LL = 23.3 PSF
DL = 3 PSF
BOT CH. LL = 0 PSF
DL = 7 PSF
TOTAL LOAD = 35.3 PSF

SPACING = 24" O.C.

THIS TRUSS IS DESIGNED FOR RESIDENTIAL OR
SMALL BUILDING REQUIREMENTS OF PART 9, NBCC 2010

THIS DESIGN COMPLIES WITH:
- PART 9 OF OBC 2012, BCBC 2012, ABC 2014
- CSA 086-09
- TPC 2011

Model: **HEMLOCK 4 EL 1**
Customer: GREENPARK
Project: MINNISALE HOMES
Location: BRAMPTON
Date: 6/20/2018 Drawn by: BB