

FROM PLAN DATED: OCT 2017

BUILDER: GREEN PARK HOMES

SITE: SECONDO VALES ESTATES

MODEL: NEWBERRY 6A

ELEVATION: 1

LOT:

CITY: EAST GWILLIMBURY

SALESMAN: M D

DESIGNER: CF

REVISION: lbv

NOTES:

REFER TO THE **NORDIC INSTALLATION** GUIDE FOR PROPER STORAGE AND INSTALLATION.

SQUASH BLOCKS OF 2x4, 2x6, 2x8 #2 S.P.F REQ'D UNDER INTERIOR UNIFORM LOAD BEARING WALLS. **MULTIPLE SQUASH BLOCKS** REQ'D UNDER CONCENTRATED LOADS. SEE FIGURE 1. **CANTILEVERED JOISTS** INCLUDING **CANT' OVER BRICK** REQ. I-JOIST BLOCKING ALONG BEARING AND RIMBOARD CLOSURE AT ENDS. SEE FIGURES 4 & 5 FOR REINFORCEMENT REQUIREMENTS. FOR **HOLES** INCLUDING **DUCT CHASE** AND **FIELD CUT OPENINGS** SEE FIGURE 7, TABLES 1 & 2. **CERAMIC TILE** APPLICATION AS PER O.B.C 9.30.6.

LOADING:

DESIGN LOADS: L/480.000

LIVE LOAD: 40.0 lb/ft²


DEAD LOAD: 15.0 lb/ft²

TILED AREAS: 20 lb/ft


SUBFLOOR: 3/4" GLUED AND NAILED

DATE: 2018-01-05

1st FLOOR



Products					Connector Summary		
PlotID	Length	Product	Plies	Net Qty	Qty	Manuf	Product
J1	14-00-00	9 1/2" NI-40x	1	18	14	H1	IUS2.56/9.5
J1DJ	14-00-00	9 1/2" NI-40x	2	4	4	H1	IUS2.56/9.5
J2	12-00-00	9 1/2" NI-40x	1	30	4	H1	IUS2.56/9.5
J1DJ	12-00-00	9 1/2" NI-40x	2	4	8	H1	IUS2.56/9.5
J3	10-00-00	9 1/2" NI-40x	1	20	5	H1	IUS2.56/9.5
J4	8-00-00	9 1/2" NI-40x	1	3	1	H3	HUS1.81/10
J5	6-00-00	9 1/2" NI-40x	1	7	1	H5	HGUS5.50/10
J6	4-00-00	9 1/2" NI-40x	1	6			
J7	2-00-00	9 1/2" NI-40x	1	2			
B3	10-00-00	1-3/4" x 9-1/2" VERSA-LAM® 2.0 3100 SP	1	1			
B4	10-00-00	1-3/4" x 9-1/2" VERSA-LAM® 2.0 3100 SP	1	1			
B6	10-00-00	1-3/4" x 9-1/2" VERSA-LAM® 2.0 3100 SP	1	1			
B1	8-00-00	1-3/4" x 9-1/2" VERSA-LAM® 2.0 3100 SP	3	3			
B2	6-00-00	1-3/4" x 9-1/2" VERSA-LAM® 2.0 3100 SP	1	1			
B7	6-00-00	1-3/4" x 9-1/2" VERSA-LAM® 2.0 3100 SP	2	2			
B5	4-00-00	1-3/4" x 9-1/2" VERSA-LAM® 2.0 3100 SP	1	1			



FROM PLAN DATED: OCT 2017

BUILDER: GREEN PARK HOMES

SITE: SECONDO VALES ESTATES

MODEL: NEWBERRY 6A

ELEVATION: 1

LOT:

CITY: EAST GWILLIMBURY

SALESMAN: M D

DESIGNER: CF


REVISION: lbv

NOTES:
REFER TO THE NORDIC **INSTALLATION GUIDE** FOR PROPER STORAGE AND INSTALLATION. **SQUASH BLOCKS** OF 2x4, 2x6, 2x8 #2 S.P.F. REQ'D UNDER INTERIOR UNIFORM LOAD BEARING WALLS. **MULTIPLE SQUASH BLOCKS** REQ'D UNDER CONCENTRATED LOADS. SEE FIGURE 1. **CANTILEVERED JOISTS** INCLUDING **CANT' OVER BRICK** REQ. I-JOIST BLOCKING ALONG BEARING AND RIMBOARD CLOSURE AT ENDS. SEE FIGURE 7 TABLES 4 & 5 FOR REINFORCEMENT REQUIREMENTS. FOR **HOLES** INCLUDING **DUCT CHASE** AND **FIELD CUT OPENINGS** SEE FIGURE 7 TABLES 1 & 2 OF THE INSTALLATION GUIDE. **CERAMIC TILE** APPLICATION AS PER O.B.C. 9.30.6


LOADING:
DESIGN LOADS: L/480.000
LIVE LOAD: 40.0 lb/ft²
DEAD LOAD: 15.0 lb/ft²
TILED AREAS: 20 lb/ft²
SUBFLOOR: 5/8" GLUED AND NAILED

DATE: 2018-01-05

2nd FLOOR



Products					Connector Summary		
PlotID	Length	Product	Plies	Net Qty	Qty	Manuf	Product
J1	14-00-00	9 1/2" NI-40x	1	19	25	H1	IUS2.56/9.5
J2	12-00-00	9 1/2" NI-40x	1	50	1	H4	HGUS410
J3	10-00-00	9 1/2" NI-40x	1	20			
J4	8-00-00	9 1/2" NI-40x	1	7			
J5	2-00-00	9 1/2" NI-40x	1	2			
J6	18-00-00	9 1/2" NI-80	1	18			
B10	12-00-00	1-3/4" x 9-1/2" VERSA-LAM® 2.0 3100 SP	2	2			
B14	12-00-00	1-3/4" x 9-1/2" VERSA-LAM® 2.0 3100 SP	2	2			
B8	10-00-00	1-3/4" x 9-1/2" VERSA-LAM® 2.0 3100 SP	1	1			
B9DR	8-00-00	1-3/4" x 9-1/2" VERSA-LAM® 2.0 3100 SP	2	2			
B11	6-00-00	1-3/4" x 9-1/2" VERSA-LAM® 2.0 3100 SP	2	2			
B13DR	6-00-00	1-3/4" x 9-1/2" VERSA-LAM® 2.0 3100 SP	2	2			
B15	2-00-00	1-3/4" x 9-1/2" VERSA-LAM® 2.0 3100 SP	2	2			
B12DR	16-00-00	1-3/4" x 11-7/8" VERSA-LAM® 2.0 3100 SP	3	3			



FROM PLAN DATED: OCT 2017

BUILDER: GREEN PARK HOMES

SITE: SECONDO VALES ESTATES

MODEL: NEWBERRY 6A

ELEVATION: 2

LOT:

CITY: EAST GWILLIMBURY

SALESMAN: M D

DESIGNER: CF


REVISION: lbv

NOTES:
REFER TO THE **NORDIC INSTALLATION** GUIDE FOR PROPER STORAGE AND INSTALLATION.
SQUASH BLOCKS OF 2x4, 2x6, 2x8 #2 S.P.F REQ'D UNDER INTERIOR UNIFORM LOAD BEARING WALLS. **MULTIPLE SQUASH BLOCKS** REQ'D UNDER CONCENTRATED LOADS. SEE FIGURE 1. **CANTILEVERED JOISTS** INCLUDING **CANT' OVER BRICK** REQ. I-JOIST BLOCKING ALONG BEARING AND RIMBOARD CLOSURE AT ENDS. SEE FIGURES 4 & 5 FOR REINFORCEMENT REQUIREMENTS. FOR **HOLES** INCLUDING **DUCT CHASE** AND **FIELD CUT OPENINGS** SEE FIGURE 7, TABLES 1 & 2. **CERAMIC TILE** APPLICATION AS PER O.B.C 9.30.6.


LOADING:
DESIGN LOADS: L/480.000
LIVE LOAD: 40.0 lb/ft²
DEAD LOAD: 15.0 lb/ft²
TILED AREAS: 20 lb/ft²
SUBFLOOR: 3/4" GLUED AND NAILED

DATE: 2018-01-05

1st FLOOR



Products					Connector Summary		
PlotID	Length	Product	Plies	Net Qty	Qty	Manuf	Product
J1	14-00-00	9 1/2" NI-40x	1	18	14	H1	IUS2.56/9.5
J1DJ	14-00-00	9 1/2" NI-40x	2	4	4	H1	IUS2.56/9.5
J2	12-00-00	9 1/2" NI-40x	1	30	4	H1	IUS2.56/9.5
J1DJ	12-00-00	9 1/2" NI-40x	2	4	8	H1	IUS2.56/9.5
J3	10-00-00	9 1/2" NI-40x	1	20	5	H1	IUS2.56/9.5
J4	8-00-00	9 1/2" NI-40x	1	3	1	H3	HUS1.81/10
J5	6-00-00	9 1/2" NI-40x	1	7	1	H5	HGUS5.50/10
J6	4-00-00	9 1/2" NI-40x	1	6			
J7	2-00-00	9 1/2" NI-40x	1	2			
B3	10-00-00	1-3/4" x 9-1/2" VERSA-LAM® 2.0 3100 SP	1	1			
B4	10-00-00	1-3/4" x 9-1/2" VERSA-LAM® 2.0 3100 SP	1	1			
B6	10-00-00	1-3/4" x 9-1/2" VERSA-LAM® 2.0 3100 SP	1	1			
B1	8-00-00	1-3/4" x 9-1/2" VERSA-LAM® 2.0 3100 SP	3	3			
B2	6-00-00	1-3/4" x 9-1/2" VERSA-LAM® 2.0 3100 SP	1	1			
B7	6-00-00	1-3/4" x 9-1/2" VERSA-LAM® 2.0 3100 SP	2	2			
B5	4-00-00	1-3/4" x 9-1/2" VERSA-LAM® 2.0 3100 SP	1	1			



FROM PLAN DATED: OCT 2017

BUILDER: GREEN PARK HOMES

SITE: SECONDO VALES ESTATES

MODEL: NEWBERRY 6A

ELEVATION: 2

LOT:

CITY: EAST GWILLIMBURY

SALESMAN: M D

DESIGNER: CF

REVISION: lbv

NOTES:

REFER TO THE NORDIC **INSTALLATION GUIDE** FOR PROPER STORAGE AND INSTALLATION. **SQUASH BLOCKS** OF 2x4, 2x6, 2x8 #2 S.P.F. REQ'D UNDER INTERIOR UNIFORM LOAD BEARING WALLS. **MULTIPLE SQUASH BLOCKS** REQ'D UNDER CONCENTRATED LOADS. SEE FIGURE 1. **CANTILEVERED JOISTS** INCLUDING **CANT' OVER BRICK** REQ. I-JOIST BLOCKING ALONG BEARING AND RIMBOARD CLOSURE AT ENDS. SEE FIGURE 7 TABLES 4 & 5 FOR REINFORCEMENT REQUIREMENTS. FOR **HOLES** INCLUDING **DUCT CHASE** AND **FIELD CUT OPENINGS** SEE FIGURE 7 TABLES 1 & 2 OF THE INSTALLATION GUIDE. **CERAMIC TILE** APPLICATION AS PER O.B.C. 9.30.6

LOADING:

DESIGN LOADS: L/480.000

LIVE LOAD: 40.0 lb/ft²


DEAD LOAD: 15.0 lb/ft²

TILED AREAS: 20 lb/ft

SUBFLOOR: 5/8" GLUED AND NAILED

DATE: 2018-01-05

2nd FLOOR



Products					Connector Summary		
PlotID	Length	Product	Plies	Net Qty	Qty	Manuf	Product
J1	14-00-00	9 1/2" NI-40x	1	19	25	H1	IUS2.56/9.5
J2	12-00-00	9 1/2" NI-40x	1	50			
J3	10-00-00	9 1/2" NI-40x	1	19	1	H4	HGUS410
J4	8-00-00	9 1/2" NI-40x	1	7			
J5	6-00-00	9 1/2" NI-40x	1	1			
J6	2-00-00	9 1/2" NI-40x	1	2			
J7	18-00-00	9 1/2" NI-80	1	18			
B10	12-00-00	1-3/4" x 9-1/2" VERSA-LAM® 2.0 3100 SP	2	2			
B14	12-00-00	1-3/4" x 9-1/2" VERSA-LAM® 2.0 3100 SP	2	2			
B8	10-00-00	1-3/4" x 9-1/2" VERSA-LAM® 2.0 3100 SP	1	1			
B9DR	8-00-00	1-3/4" x 9-1/2" VERSA-LAM® 2.0 3100 SP	2	2			
B11	6-00-00	1-3/4" x 9-1/2" VERSA-LAM® 2.0 3100 SP	2	2			
B13DR	6-00-00	1-3/4" x 9-1/2" VERSA-LAM® 2.0 3100 SP	2	2			
B16	2-00-00	1-3/4" x 9-1/2" VERSA-LAM® 2.0 3100 SP	2	2			
B12DR	16-00-00	1-3/4" x 11-7/8" VERSA-LAM® 2.0 3100 SP	3	3			

FROM PLAN DATED: OCT 2017

BUILDER: GREEN PARK HOMES

SITE: SECONDO VALES ESTATES

MODEL: NEWBERRY 6A

ELEVATION: 3

LOT:

CITY: EAST GWILLIMBURY

SALESMAN: M D

DESIGNER: CF

REVISION: lbv

NOTES:

REFER TO THE **NORDIC INSTALLATION**
GUIDE FOR PROPER STORAGE AND
INSTALLATION.

SQUASH BLOCKS OF 2x4, 2x6, 2x8 #2 S.P.F REQ'D UNDER INTERIOR UNIFORM LOAD BEARING WALLS. **MULTIPLE SQUASH BLOCKS** REQ'D UNDER CONCENTRATED LOADS. SEE FIGURE 1. **CANTILEVERED JOISTS** INCLUDING **CANT' OVER BRICK** REQ. I-JOIST BLOCKING ALONG BEARING AND RIMBOARD CLOSURE AT ENDS. SEE FIGURES 4 & 5 FOR REINFORCEMENT REQUIREMENTS. FOR **HOLES** INCLUDING **DUCT CHASE** AND **FIELD CUT OPENINGS** SEE FIGURE 7, TABLES 1 & 2. **CERAMIC TILE** APPLICATION AS PER O.B.C 9.30.6.

LOADING:

DESIGN LOADS: L/480.000


LIVE LOAD: 40.0 lb/ft²

DEAD LOAD: 15.0 lb/ft²

TILED AREAS: 20 lb/ft²


SUBFLOOR: 3/4" GLUED AND NAILED

DATE: 2018-01-05



Products					Connector Summary		
PlotID	Length	Product	Plies	Net Qty	Qty	Manuf	Product
J1	14-00-00	9 1/2" NI-40x	1	18	14	H1	IUS2.56/9.5
J1DJ	14-00-00	9 1/2" NI-40x	2	4	4	H1	IUS2.56/9.5
J2	12-00-00	9 1/2" NI-40x	1	30	4	H1	IUS2.56/9.5
J1DJ	12-00-00	9 1/2" NI-40x	2	4	8	H1	IUS2.56/9.5
J3	10-00-00	9 1/2" NI-40x	1	20	5	H1	IUS2.56/9.5
J4	8-00-00	9 1/2" NI-40x	1	3	1	H3	HUS1.81/10
J5	6-00-00	9 1/2" NI-40x	1	7	1	H5	HGUS5.50/10
J6	4-00-00	9 1/2" NI-40x	1	6			
J7	2-00-00	9 1/2" NI-40x	1	2			
B3	10-00-00	1-3/4" x 9-1/2" VERSA-LAM® 2.0 3100 SP	1	1			
B4	10-00-00	1-3/4" x 9-1/2" VERSA-LAM® 2.0 3100 SP	1	1			
B6	10-00-00	1-3/4" x 9-1/2" VERSA-LAM® 2.0 3100 SP	1	1			
B1	8-00-00	1-3/4" x 9-1/2" VERSA-LAM® 2.0 3100 SP	3	3			
B2	6-00-00	1-3/4" x 9-1/2" VERSA-LAM® 2.0 3100 SP	1	1			
B7	6-00-00	1-3/4" x 9-1/2" VERSA-LAM® 2.0 3100 SP	2	2			
B5	4-00-00	1-3/4" x 9-1/2" VERSA-LAM® 2.0 3100 SP	1	1			

1st FLOOR



FROM PLAN DATED: OCT 2017

BUILDER: GREEN PARK HOMES

SITE: SECONDO VALES ESTATES

MODEL: NEWBERRY 6A

ELEVATION: 3

LOT:

CITY: EAST GWILLIMBURY

SALESMAN: M D

DESIGNER: CF


REVISION: lbv

NOTES:
REFER TO THE NORDIC **INSTALLATION GUIDE** FOR PROPER STORAGE AND INSTALLATION. **SQUASH BLOCKS** OF 2x4, 2x6, 2x8 #2 S.P.F. REQ'D UNDER INTERIOR UNIFORM LOAD BEARING WALLS. **MULTIPLE SQUASH BLOCKS** REQ'D UNDER CONCENTRATED LOADS. SEE FIGURE 1. **CANTILEVERED JOISTS** INCLUDING **CANT' OVER BRICK** REQ. I-JOIST BLOCKING ALONG BEARING AND RIMBOARD CLOSURE AT ENDS. SEE FIGURE 7 TABLES 4 & 5 FOR REINFORCEMENT REQUIREMENTS. FOR **HOLES** INCLUDING **DUCT CHASE** AND **FIELD CUT OPENINGS** SEE FIGURE 7 TABLES 1 & 2 OF THE INSTALLATION GUIDE. **CERAMIC TILE** APPLICATION AS PER O.B.C. 9.30.6

LOADING:
DESIGN LOADS: L/480.000
LIVE LOAD: 40.0 lb/ft²
DEAD LOAD: 15.0 lb/ft²
TILED AREAS: 20 lb/ft²

SUBFLOOR: 5/8" GLUED AND NAILED

DATE: 2018-01-05



Products					Connector Summary		
PlotID	Length	Product	Plies	Net Qty	Qty	Manuf	Product
J1	14-00-00	9 1/2" NI-40x	1	19	25	H1	IUS2.56/9.5
J2	12-00-00	9 1/2" NI-40x	1	50			
J3	10-00-00	9 1/2" NI-40x	1	19	1	H4	HGUS410
J4	8-00-00	9 1/2" NI-40x	1	7			
J5	6-00-00	9 1/2" NI-40x	1	1			
J6	2-00-00	9 1/2" NI-40x	1	2			
J7	18-00-00	9 1/2" NI-80	1	18			
B10	12-00-00	1-3/4" x 9-1/2" VERSA-LAM® 2.0 3100 SP	2	2			
B14	12-00-00	1-3/4" x 9-1/2" VERSA-LAM® 2.0 3100 SP	2	2			
B8	10-00-00	1-3/4" x 9-1/2" VERSA-LAM® 2.0 3100 SP	1	1			
B9DR	8-00-00	1-3/4" x 9-1/2" VERSA-LAM® 2.0 3100 SP	2	2			
B11	6-00-00	1-3/4" x 9-1/2" VERSA-LAM® 2.0 3100 SP	2	2			
B13DR	6-00-00	1-3/4" x 9-1/2" VERSA-LAM® 2.0 3100 SP	2	2			
B16	2-00-00	1-3/4" x 9-1/2" VERSA-LAM® 2.0 3100 SP	2	2			
B12DR	16-00-00	1-3/4" x 11-7/8" VERSA-LAM® 2.0 3100 SP	3	3			

2nd FLOOR



Triple 1-3/4" x 9-1/2" VERSA-LAM® 2.0 3100 SP Basement\Flush Beams\B1(i2883)

Dry | 1 span | No cantilevers | 0/12 slope (deg)

October 26, 2017 16:55:48

BC CALC® Design Report



Build 5033

Job Name:

Address:

City, Province, Postal Code: EAST GWILLIMBURY,

Customer:

Code reports: CCMC 12472-R

File Name: NEWBERRY 6A.mmdl


Description: Designs\Flush Beams\Basement\Flush Beams\B1(i2883)

Specifier:

Designer: CF

Company:

Misc:



Total Horizontal Product Length = 06-00-02

Reaction Summary (Down / Uplift) (lbs)

Bearing	Live	Dead	Snow	Wind
B0	2,589 / 0	1,425 / 0		
B1, 5-3/8"	6,201 / 0	3,377 / 0		

Load Summary

Tag	Description	Load Type	Ref.	Start	End	Live 1.00	Dead 0.65	Snow 1.00	Wind 1.15	Trib.
0	20(i1091)	Unf. Lin. (lb/ft)	L	00-01-02	00-09-06		101			n/a
1	Smoothed Load	Unf. Lin. (lb/ft)	L	01-05-06	05-05-06	498	249			n/a
2	10(i197)	Unf. Lin. (lb/ft)	L	05-04-06	06-00-02	387	294			n/a
3	-	Conc. Pt. (lbs)	L	00-08-11	00-08-11	1,973	1,012			n/a
4	10(i197)	Conc. Pt. (lbs)	L	05-05-06	05-05-06	1,090	570			n/a
5	10(i197)	Conc. Pt. (lbs)	L	05-11-06	05-11-06	3,470	1,870			n/a

Controls Summary

	Factored Demand	Factored Resistance	Demand / Resistance	Load Case	Location
Pos. Moment	5,265 ft-lbs	39,636 ft-lbs	13.3%	1	02-01-06
End Shear	4,369 lbs	17,356 lbs	25.2%	1	00-11-08
Total Load Defl.	L/999 (0.028")	n/a	n/a	4	02-09-06
Live Load Defl.	L/999 (0.018")	n/a	n/a	5	02-09-06
Max Defl.	0.028"	n/a	n/a	4	02-09-06
Span / Depth	7	n/a	n/a		00-00-00

Bearing Supports

	Dim. (L x W)	Demand	Demand / Resistance Support	Demand / Resistance Member	Material
B0 Hanger	2" x 5-1/4"	5,665 lbs	n/a	44.2%	HGUS5.50/10
B1 Beam	5-3/8" x 5-1/4"	13,523 lbs	89.7%	39.3%	Unspecified

Notes



DWG NO. TAM 60307-17
STRUCTURAL
COMPONENT ONLY



Triple 1-3/4" x 9-1/2" VERSA-LAM® 2.0 3100 SP Basement\Flush Beams\B1(i2883)

Dry | 1 span | No cantilevers | 0/12 slope (deg)

October 26, 2017 16:55:48

BC CALC® Design Report



Build 5033

Job Name:

Address:

City, Province, Postal Code: EAST GWILLIMBURY,

Customer:

Code reports: CCMC 12472-R

File Name: NEWBERRY 6A.mmdl

Description: Designs\Flush Beams\Basement\Flush Beams\B1(i2883)

Specifier:

Designer: CF

Company:

Misc:

Design meets Code minimum (L/240) Total load deflection criteria.

Design meets Code minimum (L/360) Live load deflection criteria.

Calculations assume member is fully braced.

Hanger Manufacturer: Unassigned

Resistance Factor phi has been applied to all presented results per CSA O86.


BC CALC® analysis is based on Canadian Limit States Design, as per NBCC 2010 and CSA O86.

CONFORMS TO OBC 2012

Design based on Dry Service Condition.

Importance Factor: Normal Part code: Part 9

Connection Diagram



a minimum = 2"

c = 2-1/4"

b minimum = 3"

d = 3"

e minimum = 3"

Calculated Side Load = 480.6 lb/ft

Connection design assumes point load is top-loaded. For connection design of side-loaded point loads, please consult a technical representative or professional of Record.

Nailing schedule applies to both sides of the member.

Connectors are: 16d Nails

3 1/2" ARDOX SPIRAL

Disclosure

Completeness and accuracy of input must be verified by anyone who would rely on output as evidence of suitability for particular application. Output here based on building code-accepted design properties and analysis methods. Installation of Boise Cascade engineered wood products must be in accordance with current Installation Guide and applicable building codes. To obtain Installation Guide or ask questions, please call 1-800-964-6999 before installation.

BC CALO®, BC FRAMER®, AJS™, ALLJOIST®, BC RIM BOARD™, BCI®, BOISE GLULAM™, SIMPLE FRAMING SYSTEM®, VERSA-LAM®, VERSA-RIM PLUS®, VERSA-RIM®, VERSA-STRAND®, VERSA-STUD® are trademarks of Boise Cascade Wood Products L.L.C.



DWG NO. TAM 60307-17
STRUCTURAL
COMPONENT ONLY



Single 1-3/4" x 9-1/2" VERSA-LAM® 2.0 3100 SP 1st Floor\Flush Beams\B8(i2798)

Dry | 1 span | No cantilevers | 0/12 slope (deg)

October 26, 2017 16:55:37

BC CALC® Design Report



Build 5033

Job Name:

Address:

City, Province, Postal Code: EAST GWILLIMBURY,

Customer:

Code reports: CCMC 12472-R

File Name: NEWBERRY 6A.mmdl


Description: Designs\Flush Beams\1st Floor\Flush Beams\B8(i2798)

Specifier:

Designer: CF

Company:

Misc:



Total Horizontal Product Length = 08-03-12

Reaction Summary (Down / Uplift) (lbs)

Bearing	Live	Dead	Snow	Wind
B0, 5-1/2"	175 / 0	118 / 0		
B1, 2-3/4"	628 / 0	377 / 0		

Load Summary

Tag	Description	Load Type	Ref.	Start	End	Live 1.00	Dead 0.65	Snow 1.00	Wind 1.15	Trib.
0	FC3 Floor Material	Unf. Lin. (lb/ft)	L	00-00-00	06-06-08	9	5			n/a
1	FC3 Floor Material	Unf. Lin. (lb/ft)	L	06-06-08	08-03-12	13	7			n/a
2	B10(i2839)	Conc. Pt. (lbs)	L	06-08-04	06-08-04	720	414			n/a

Controls Summary

	Factored Demand	Factored Resistance	Demand / Resistance	Load Case	Location
Pos. Moment	2,016 ft-lbs	12,704 ft-lbs	15.9%	1	06-08-04
End Shear	1,379 lbs	5,785 lbs	23.8%	1	07-03-08
Total Load Defl.	L/999 (0.048")	n/a	n/a	4	04-08-11
Live Load Defl.	L/999 (0.03")	n/a	n/a	5	04-08-11
Max Defl.	0.048"	n/a	n/a	4	04-08-11
Span / Depth	9.8	n/a	n/a		00-00-00

Disclosure

Completeness and accuracy of input must be verified by anyone who would rely on output as evidence of suitability for particular application. Output here based on building code-accepted design properties and analysis methods. Installation of Boise Cascade engineered wood products must be in accordance with current Installation Guide and applicable building codes. To obtain Installation Guide or ask questions, please call 1-800-964-6999 before installation.

Bearing Supports

B0	Wall/Plate	5-1/2" x 1-3/4"	411 lbs	8%	3.5%	Unspecified
B1	Wall/Plate	2-3/4" x 1-3/4"	1,414 lbs	55%	24.1%	Unspecified

Notes

Design meets Code minimum (L/240) Total load deflection criteria.

Design meets Code minimum (L/360) Live load deflection criteria.

Calculations assume member is fully braced.

Resistance Factor phi has been applied to all presented results per CSA O86.


BC CALC® analysis is based on Canadian Limit States Design, as per NBCC 2010 and CSA O86.

Design based on Dry Service Condition.

Importance Factor : Normal Part code : Part 9

CONFORMS TO QBC 2012

BC CALC®, BC FRAMER®, AJS™, ALLJOIST®, BC RIM BOARD™, BCI®, BOISE GLULAM™, SIMPLE FRAMING SYSTEM®, VERSA-LAM®, VERSA-RIM PLUS®, VERSA-RIM®, VERSA-STRAND®, VERSA-STUD® are trademarks of Boise Cascade Wood Products L.L.C.





Build 5033

Job Name:

Address:

City, Province, Postal Code: EAST GWILLIMBURY,

Customer:

Code reports:

CCMC 12472-R

File Name: NEWBERRY6A EL 1.mmdl


Description: Designs\Flush Beams\1st Floor\Flush Beams\B11(i2971)

Specifier:

Designer: CF

Company:

Misc:



Total Horizontal Product Length = 04-05-00

Reaction Summary (Down / Uplift) (lbs)

Bearing	Live	Dead	Snow	Wind
B0, 3-1/2"	716 / 0	379 / 0		
B1, 5-1/2"	838 / 0	441 / 0		

Load Summary

Tag	Description	Load Type	Ref.	Start	End	Live 1.00	Dead 0.65	Snow 1.00	Wind 1.15	Trib.
0	Smoothed Load	Unf. Lin. (lb/ft)	L	00-05-08	04-05-00	130	64			n/a
1	J2(i2962)	Conc. Pt. (lbs)	L	00-05-08	00-05-08	231	116			n/a
2	J2(i2984)	Conc. Pt. (lbs)	L	01-05-08	01-05-08	231	116			n/a
3	J2(i3055)	Conc. Pt. (lbs)	L	02-05-08	02-05-08	270	135			n/a
4	J2(i2983)	Conc. Pt. (lbs)	L	03-09-08	03-09-08	308	154			n/a

Controls Summary

	Factored Demand	Factored Resistance	Demand / Resistance	Load Case	Location
Pos. Moment	1,451 ft-lbs	25,408 ft-lbs	5.7%	1	02-05-08
End Shear	1,146 lbs	11,571 lbs	9.9%	1	01-01-00
Total Load Defl.	L/999 (0.005")	n/a	n/a	4	02-01-12
Live Load Defl.	L/999 (0.003")	n/a	n/a	5	02-01-12
Max Defl.	0.005"	n/a	n/a	4	02-01-12
Span / Depth	4.8	n/a	n/a		00-00-00

Bearing Supports

	Dim. (L x W)	Demand	Demand / Resistance Support	Demand / Resistance Member	Material
B0 Wall/Plate	3-1/2" x 3-1/2"	1,547 lbs	23.7%	10.4%	Unspecified
B1 Wall/Plate	5-1/2" x 3-1/2"	1,809 lbs	17.6%	7.7%	Unspecified

Notes

Design meets Code minimum (L/240) Total load deflection criteria.

Design meets Code minimum (L/360) Live load deflection criteria.

Calculations assume member is fully braced.

Resistance Factor phi has been applied to all presented results per CSA O86.

BC CALC® analysis is based on Canadian Limit States Design, as per NBCC 2010 and CSA O86.

Design based on Dry Service Condition.

Importance Factor : Normal Part code : Part 9

CONFORMS TO OBC 2012



DWG NO. TAM 60309-17
STRUCTURAL
COMPONENT ONLY



Double 1-3/4" x 9-1/2" VERSA-LAM® 2.0 3100 SP 1st Floor\...\B11(i2971)

Dry | 1 span | No cantilevers | 0/12 slope (deg)

October 27, 2017 11:16:47

BC CALC® Design Report



Build 5033

Job Name:

Address:

City, Province, Postal Code: EAST GWILLIMBURY,

Customer:

Code reports: CCMC 12472-R

File Name: NEWBERRY 6A EL 1.mmdl

Description: Designs\Flush Beams\1st Floor\Flush Beams\B11(i2971)


Specifier:

Designer: CF

Company:

Misc:

Connection Diagram



a minimum = 2" c = 2-3/4"
b minimum = 3" d = 3"

Calculated Side Load = 500.7 lb/ft

Connection design assumes point load is top-loaded. For connection design of side-loaded point loads, please consult a technical representative or professional of Record.

Connectors are: 16d Nails

3 1/2" ARDOX SPIRAL

Disclosure

Completeness and accuracy of input must be verified by anyone who would rely on output as evidence of suitability for particular application. Output here based on building code-accepted design properties and analysis methods. Installation of Boise Cascade engineered wood products must be in accordance with current Installation Guide and applicable building codes. To obtain Installation Guide or ask questions, please call 1-800-964-6999 before installation.

BC CALC®, BC FRAMER®, AJS™, ALLJOIST®, BC RIM BOARD™, BCI®, BOISE GLULAM™, SIMPLE FRAMING SYSTEM®, VERSA-LAM®, VERSA-RIM PLUS®, VERSA-RIM®, VERSA-STRAND®, VERSA-STUD® are trademarks of Boise Cascade Wood Products L.L.C.



DWG NO. TAM 60309-17
STRUCTURAL
COMPONENT ONLY



Single 1-3/4" x 9-1/2" VERSA-LAM® 2.0 3100 SP Basement\Flush Beams\B6(i2955)

Dry | 1 span | No cantilevers | 0/12 slope (deg)

October 27, 2017 11:16:49

BC CALC® Design Report



Build 5033

Job Name:

Address:

City, Province, Postal Code: EAST GWILLIMBURY,

Customer:

Code reports: CCMC 12472-R

File Name: NEWBERRY6A EL 1.mmdl


Description: Designs\Flush Beams\Basement\Flush Beams\B6(i2955)

Specifier:

Designer: CF

Company:

Msc:



Total Horizontal Product Length = 08-06-08

Reaction Summary (Down / Uplift) (lbs)

Bearing	Live	Dead	Snow	Wind
B0, 3-1/2"	137 / 0	89 / 0		
B1, 3-1/2"	135 / 0	103 / 0		

Load Summary

Tag	Description	Load Type	Ref.	Start	End	Live 1.00	Dead 0.65	Snow 1.00	Wind 1.15	Trib.
0	FC1 Floor Material	Unf. Lin. (lb/ft)	L	00-00-00	08-06-08	32	16			n/a
1	E9(i5)	Conc. Pt. (lbs)	L	08-03-12	08-03-12		15			n/a

Controls Summary

	Factored Demand	Factored Resistance	Demand / Resistance	Load Case	Location
Pos. Moment	599 ft-lbs	12,704 ft-lbs	4.7%	1	04-03-04
End Shear	234 lbs	5,785 lbs	4%	1	01-01-00
Total Load Defl.	L/999 (0.02")	n/a	n/a	4	04-03-04
Live Load Defl.	L/999 (0.012")	n/a	n/a	5	04-03-04
Max Defl.	0.02"	n/a	n/a	4	04-03-04
Span / Depth	10.2	n/a	n/a		00-00-00

Disclosure

Completeness and accuracy of input must be verified by anyone who would rely on output as evidence of suitability for particular application. Output here based on building code-accepted design properties and analysis methods. Installation of Boise Cascade engineered wood products must be in accordance with current Installation Guide and applicable building codes. To obtain Installation Guide or ask questions, please call 1-800-964-6999 before installation.

Bearing Supports

	Dim. (L x W)	Demand	Demand / Resistance Support	Demand / Resistance Member	Material
B0 Post	3-1/2" x 1-3/4"	316 lbs	6.4%	4.2%	Unspecified
B1 Wall/Plate	3-1/2" x 1-3/4"	332 lbs	10.1%	4.4%	Unspecified

Notes

Design meets Code minimum (L/240) Total load deflection criteria.

Design meets Code minimum (L/360) Live load deflection criteria.

Calculations assume member is fully braced.

Resistance Factor phi has been applied to all presented results per CSA O86.


BC CALC® analysis is based on Canadian Limit States Design, as per NBCC 2010 and CSA O86.

Design based on Dry Service Condition.

Importance Factor: Normal Part code: Part 9

CONFORMS TO OBC 2012

BC CALC®, BC FRAMER®, AJST™, ALLJOIST®, BC RIM BOARD™, BCI®, BOISE GLULAM™, SIMPLE FRAMING SYSTEM®, VERSA-LAM®, VERSA-RIM PLUS®, VERSA-RIM®, VERSA-STRAND®, VERSA-STUD® are trademarks of Boise Cascade Wood Products L.L.C.



DWG NO. TAM 60310-17
STRUCTURAL
COMPONENT ONLY



Double 1-3/4" x 9-1/2" VERSA-LAM® 2.0 3100 SP 1st Floor\...\B10(i2839)

Dry | 1 span | No cantilevers | 0/12 slope (deg)

October 26, 2017 16:55:42

BC CALC® Design Report



Build 5033

Job Name:

Address:

City, Province, Postal Code: EAST GWILLIMBURY,

Customer:

Code reports: CCMC 12472-R

File Name: NEWBERRY 6A.mmdl


Description: Designs\Flush Beams\1st Floor\Flush Beams\B10(i2839;

Specifier:

Designer: CF

Company:

Misc:



Total Horizontal Product Length = 11-03-08

Reaction Summary (Down / Uplift) (lbs)

Bearing	Live	Dead	Snow	Wind
B0, 3-1/2"	1,435 / 0	772 / 0		
B1	723 / 0	416 / 0		

Load Summary

Tag Description	Load Type	Ref.	Start	End	Live 1.00	Dead 0.65	Snow 1.00	Wind 1.15	Trib.
0 FC3 Floor Material	Unf. Lin. (lb/ft)	L	00-03-08	00-09-00	126	63			n/a
1 J5(i2049)	Conc. Pt. (lbs)	L	00-09-00	00-09-00	381	190			n/a
2 J5(i2021)	Conc. Pt. (lbs)	L	02-01-00	02-01-00	499	249			n/a
3 J5(i1997)	Conc. Pt. (lbs)	L	03-05-00	03-05-00	416	208			n/a
4 J5(i1996)	Conc. Pt. (lbs)	L	04-09-00	04-09-00	192	96			n/a
5 J5(i285)	Conc. Pt. (lbs)	L	06-01-00	06-01-00	181	91			n/a
6 J5(i285)	Conc. Pt. (lbs)	L	07-05-00	07-05-00	181	91			n/a
7 J5(i2760)	Conc. Pt. (lbs)	L	08-09-00	08-09-00	171	85			n/a
8 J6(i2872)	Conc. Pt. (lbs)	L	09-09-00	09-09-00	45	23			n/a
9 J6(i2774)	Conc. Pt. (lbs)	L	11-01-00	11-01-00	31	16			n/a

Controls Summary	Factored Demand	Factored Resistance	Demand / Resistance	Load Case	Location
Pos. Moment	6,173 ft-lbs	25,408 ft-lbs	24.3%	1	04-09-00
End Shear	2,758 lbs	11,571 lbs	23.8%	1	01-01-00
Total Load Defl.	L/703 (0.187")	0.548"	34.1%	4	05-05-00
Live Load Defl.	L/999 (0.121")	n/a	n/a	5	05-05-00
Max Defl.	0.187"	n/a	n/a	4	05-05-00
Span / Depth	13.8	n/a	n/a		00-00-00

Bearing Supports	Dim. (L x W)	Demand	Demand / Resistance Support	Demand / Resistance Member	Material
B0 Beam	3-1/2" x 3-1/2"	3,117 lbs	23.3%	20.9%	Unspecified
B1 Hanger	2" x 3-1/2"	1,604 lbs	n/a	18.8%	HGUS410

Notes



DWG NO. TAM60311-17
STRUCTURAL
COMPONENT ONLY

BC CALC® Design Report



Build 5033

Job Name:

Address:

City, Province, Postal Code: EAST GWILLIMBURY,

Customer:

Code reports: CCMC 12472-R

File Name: NEWBERRY 6A.mmdl

Description: Designs\Flush Beams\1st Floor\Flush Beams\B10(i2839

Specifier:

Designer: CF

Company:

Msc:

Design meets Code minimum (L/240) Total load deflection criteria.

Design meets Code minimum (L/360) Live load deflection criteria.

Calculations assume member is fully braced.

Hanger Manufacturer: Unassigned

Resistance Factor phi has been applied to all presented results per CSA O86.


BC CALC® analysis is based on Canadian Limit States Design, as per NBCC 2010 and CSA O86.

Design based on Dry Service Condition.

Importance Factor: Normal Part code: Part 9

CONFORMS TO OBC 2012

Connection Diagram



a minimum = 2" c = 1-1/2"
b minimum = 3" d = 6"

Calculated Side Load = 394.7 lb/ft

Connection design assumes point load is top-loaded. For connection design of side-loaded point loads, please consult a technical representative or professional of Record.

Connectors are: 16d 16d Nails

3 1/2" ARDQX SPIRAL

Disclosure

Completeness and accuracy of input must be verified by anyone who would rely on output as evidence of suitability for particular application. Output here based on building code-accepted design properties and analysis methods. Installation of Boise Cascade engineered wood products must be in accordance with current Installation Guide and applicable building codes. To obtain Installation Guide or ask questions, please call 1-800-964-6999 before installation.

BC CALO®, BC FRAMER®, AJS™, ALLJOIST®, BC RIM BOARD™, BC®, BOISE GLULAM™, SIMPLE FRAMING SYSTEM®, VERSA-LAM®, VERSA-RIM PLUS®, VERSA-RIM®, VERSA-STRAND®, VERSA-STUD® are trademarks of Boise Cascade Wood Products L.L.C.



DWG NO. TAM 60311-17
STRUCTURAL
COMPONENT ONLY



Double 1-3/4" x 9-1/2" VERSA-LAM® 2.0 3100 SP 1st Floor\Flush Beams\B14(i122)

Dry | 1 span | No cantilevers | 0/12 slope (deg)

October 26, 2017 16:55:44

BC CALC® Design Report



Build 5033

Job Name:

Address:

City, Province, Postal Code: EAST GWILLIMBURY,

Customer:

Code reports:

CCMC 12472-R

File Name: NEWBERRY 6A.mmdl


Description: Designs\Flush Beams\1st Floor\Flush Beams\B14(i122)

Specifier:

Designer: CF

Company:

Misc:



Total Horizontal Product Length = 11-10-00

Reaction Summary (Down / Uplift) (lbs)

Bearing	Live	Dead	Snow	Wind
B0, 3-1/2"	1,443 / 49	751 / 0		
B1, 5-1/2"	925 / 185	427 / 0		

Load Summary

Tag	Description	Load Type	Ref.	Start	End	Live 1.00	Dead 0.65	Snow 1.00	Wind 1.15	Trib.
0	Smoothed Load	Unf. Lin. (lb/ft)	L	00-00-00	06-07-00	254	127			n/a
1	FC3 Floor Material	Unf. Lin. (lb/ft)	L	00-00-08	11-10-00	22	11			n/a
2	Smoothed Load	Unf. Lin. (lb/ft)	L	06-07-00	10-07-00	86	20			n/a
3	J2(i342)	Conc. Pt. (lbs)	L	07-03-00	07-03-00	-63				n/a
4	J2(i339)	Conc. Pt. (lbs)	L	08-07-00	08-07-00	-63				n/a
5	J2(i293)	Conc. Pt. (lbs)	L	09-11-00	09-11-00	-63				n/a
6	J2(i234)	Conc. Pt. (lbs)	L	11-03-00	11-03-00	83	19			n/a
7	J2(i234)	Conc. Pt. (lbs)	L	11-03-00	11-03-00	-45				n/a


Controls Summary

	Factored Demand	Factored Resistance	Demand / Resistance	Load Case	Location
Pos. Moment	7,207 ft-lbs	25,408 ft-lbs	28.4%	1	04-07-00
End Shear	2,592 lbs	11,571 lbs	22.4%	1	01-01-00
Total Load Defl.	L/604 (0.223")	0.56"	39.7%	6	05-07-00
Live Load Defl.	L/907 (0.148")	0.374"	39.7%	8	05-07-00
Max Defl.	0.223"	n/a	n/a	6	05-07-00
Span / Depth	14.2	n/a	n/a		00-00-00

Bearing Supports

	Dim. (L x W)	Demand	Demand / Resistance Support	Demand / Resistance Member	Material
B0 Wall/Plate	3-1/2" x 3-1/2"	3,104 lbs	47.5%	20.8%	Unspecified
B1 Wall/Plate	5-1/2" x 3-1/2"	1,922 lbs	18.7%	8.2%	Unspecified

Notes



DWG NO. TAM 603/12-17
STRUCTURAL
COMPONENT ONLY



Boise Cascade

Double 1-3/4" x 9-1/2" VERSA-LAM® 2.0 3100 SP 1st Floor\Flush Beams\B14(i122)

Dry | 1 span | No cantilevers | 0/12 slope (deg)

October 26, 2017 16:55:44

BC CALC® Design Report



Build 5033

Job Name:

Address:

City, Province, Postal Code: EAST GWILLIMBURY,

Customer:

Code reports: CCMC 12472-R

File Name: NEWBERRY6A.mmdl

Description: Designs\Flush Beams\1st Floor\Flush Beams\B14(i122

Specifier:

Designer: CF

Company:

Msc:

Design meets Code minimum (L/240) Total load deflection criteria.

Design meets Code minimum (L/360) Live load deflection criteria.

Calculations assume member is fully braced.

Resistance Factor phi has been applied to all presented results per CSA O86.

BC CALC® analysis is based on Canadian Limit States Design, as per NBCC 2010 and CSA O86.


Design based on Dry Service Condition.

Importance Factor: Normal Part code: Part 9

CONFORMS TO OBC 2012**Disclosure**

Completeness and accuracy of input must be verified by anyone who would rely on output as evidence of suitability for particular application. Output here based on building code-accepted design properties and analysis methods. Installation of Boise Cascade engineered wood products must be in accordance with current Installation Guide and applicable building codes. To obtain Installation Guide or ask questions, please call 1-800-964-6999 before installation.

BC CALC®, BC FRAMER®, AJS™, ALLJOIST®, BC RIM BOARD™, BCI®, BOISE GLULAM™, SIMPLE FRAMING SYSTEM®, VERSA-LAM®, VERSA-RIM PLUS®, VERSA-RIM®, VERSA-STRAND®, VERSA-STUD® are trademarks of Boise Cascade Wood Products L.L.C.

Connection Diagram

a minimum = 0" c = 1-1/2"
b minimum = 3" d = 6"

Calculated Side Load = 335.4 lb/ft

Connection design assumes point load is top-loaded. For connection design of side-loaded point loads, please consult a technical representative or professional of Record.

Connectors are: 16d Nails

3 1/2" ARDOX SPIRAL

DWG NO. TAM 60312-17
STRUCTURAL
COMPONENT ONLY



Double 1-3/4" x 9-1/2" VERSA-LAM® 2.0 3100 SP 1st Floor\...\B9DR(i2775)

Dry | 1 span | No cantilevers | 0/12 slope (deg)

October 26, 2017 16:55:47

BC CALC® Design Report



Build 5033

Job Name:

Address:

City, Province, Postal Code: EAST GWILLIMBURY,

Customer:

Code reports: CCMC 12472-R

File Name: NEWBERRY 6A.mmdl


Description: Designs\Dropped Beams\1st Floor\Dropped Beams\B9D

Specifier:

Designer: CF

Company:

Misc:



Total Horizontal Product Length = 07-09-08

Reaction Summary (Down / Uplift) (lbs)

Bearing	Live	Dead	Snow	Wind
B0, 3-1/2"	1,247 / 0	708 / 0		
B1, 4-3/4"	190 / 0	140 / 0		

Load Summary

Tag	Description	Load Type	Ref.	Start	End	Live 1.00	Dead 0.65	Snow 1.00	Wind 1.15	Trib.
0	B10(i2839)	Conc. Pt. (lbs)	L	01-02-04	01-02-04	1,437	773			n/a

Controls Summary	Factored Demand	Factored Resistance	Demand / Resistance	Load Case	Location
Pos. Moment	2,631 ft-lbs	22,213 ft-lbs	11.8%	1	01-02-04
End Shear	2,741 lbs	11,571 lbs	23.7%	1	01-01-00
Total Load Defl.	L/999 (0.025")	n/a	n/a	4	03-04-11
Live Load Defl.	L/999 (0.016")	n/a	n/a	5	03-03-10
Max Defl.	0.025"	n/a	n/a	4	03-04-11
Span / Depth	9.1	n/a	n/a		00-00-00

Bearing Supports	Dim. (L x W)	Demand	Demand / Resistance Support	Demand / Resistance Member	Material
B0 Wall/Plate	3-1/2" x 3-1/2"	2,754 lbs	27.7%	18.4%	Unspecified
B1 Wall/Plate	4-3/4" x 3-1/2"	461 lbs	3.4%	2.3%	Unspecified

Notes

Design meets Code minimum (L/240) Total load deflection criteria.

Design meets Code minimum (L/360) Live load deflection criteria.

Calculations assume unbraced length of Top: 06-00-12, Bottom: 06-00-12.

Resistance Factor phi has been applied to all presented results per CSA O86.

BC CALC® analysis is based on Canadian Limit States Design, as per NBCC 2010 and CSA

O86.

Design based on Dry Service Condition.

Importance Factor : Normal Part code : Part 9

CONFORMS TO OBC 2012



DWG NO. TAM 60313-17
STRUCTURAL
COMPONENT ONLY



BC CALC® Design Report



Build 5033

Job Name:

Address:

City, Province, Postal Code: EAST GWILLIMBURY,

Customer:

Code reports: CCMC 12472-R

File Name: NEWBERRY6A.mmdl

Description: Designs\Dropped Beams\1st Floor\Dropped Beams\B


Specifier:

Designer: CF

Company:

Misc:

Connection Diagram



a minimum = 2" c = 2-1/2"
b minimum = 3" d = 4"

Connection design assumes point load is top-loaded. For connection design of side-loaded point loads, please consult a technical representative or professional of Record.

Member has no side loads.

Connectors are: 16d ~~EX~~ Nails

3 1/2" ARDOX SPIRAL

Disclosure

Completeness and accuracy of input must be verified by anyone who would rely on output as evidence of suitability for particular application. Output here based on building code-accepted design properties and analysis methods. Installation of Boise Cascade engineered wood products must be in accordance with current Installation Guide and applicable building codes. To obtain Installation Guide or ask questions, please call 1-800-964-6999 before installation.

BC CALC®, BC FRAMER®, AJS™, ALLJOIST®, BC RIM BOARD™, BC®, BOISE GLULAM™, SIMPLE FRAMING SYSTEM®, VERSA-LAM®, VERSA-RIM PLUS®, VERSA-RIM®, VERSA-STRAND®, VERSA-STUD® are trademarks of Boise Cascade Wood Products L.L.C.



DWG NO. TAM 60313-17
STRUCTURAL
COMPONENT ONLY



Double 1-3/4" x 9-1/2" VERSA-LAM® 2.0 3100 SP 1st Floor...\B13DR(i2890)

Dry | 1 span | No cantilevers | 0/12 slope (deg)

October 26, 2017 16:55:47

BC CALC® Design Report



Build 5033

Job Name:

Address:

City, Province, Postal Code: EAST GWILLIMBURY,

Customer:

Code reports:

CCMC 12472-R

File Name: NEWBERRY 6A.mmdl


Description: Designs\Dropped Beams\1st Floor\Dropped Beams\B131

Specifier:

Designer: CF

Company:

Misc:



Total Horizontal Product Length = 05-02-00

Reaction Summary (Down / Uplift) (lbs)

Bearing	Live	Dead	Snow	Wind
B0, 3-1/2"	1,377 / 0	713 / 0		
B1, 3-1/2"	1,119 / 0	584 / 0		

Load Summary

Tag	Description	Load Type	Ref.	Start	End	Live 1.00	Dead 0.65	Snow 1.00	Wind 1.15	Trib.
0	Smoothed Load	Unf. Lin. (lb/ft)	L	01-02-00	04-08-00	555	277			n/a
1	-	Conc. Pt. (lbs)	L	00-04-01	00-04-01	554	277			n/a

Controls Summary

	Factored Demand	Factored Resistance	Demand / Resistance	Load Case	Location
Pos. Moment	2,833 ft-lbs	25,408 ft-lbs	11.1%	1	03-01-04
End Shear	1,997 lbs	11,571 lbs	17.3%	1	04-01-00
Total Load Defl.	L/999 (0.016")	n/a	n/a	4	02-07-04
Live Load Defl.	L/999 (0.011")	n/a	n/a	5	02-07-04
Max Defl.	0.016"	n/a	n/a	4	02-07-04
Span / Depth	5.9	n/a	n/a		00-00-00

Bearing Supports

B0	Wall/Plate	3-1/2" x 3-1/2"	2,957 lbs	29.8%	19.8%	Unspecified
B1	Wall/Plate	3-1/2" x 3-1/2"	2,409 lbs	24.2%	16.1%	Unspecified

Notes

Design meets Code minimum (L/240) Total load deflection criteria.

Design meets Code minimum (L/360) Live load deflection criteria.

Calculations assume unbraced length of Top: 00-02-12, Bottom: 00-02-12.

Resistance Factor phi has been applied to all presented results per CSA O86.

BC CALC® analysis is based on Canadian Limit States Design, as per NBCC 2010 and CSA O86.

CONFORMS TO OBC 2012

Design based on Dry Service Condition.

Importance Factor: Normal Part code: Part 9



DWG NO. TAM 60314-17
STRUCTURAL
COMPONENT ONLY

BC CALC® Design Report



Build 5033

Job Name:

Address:

City, Province, Postal Code: EAST GWILLIMBURY,

Customer:

Code reports: CCMC 12472-R

File Name: NEWBERRY6A.mmdl

Description: Designs\Dropped Beams\1st Floor\Dropped Beams\B1


Specifier:

Designer: CF

Company:

Misc:

Connection Diagram



a minimum = 1" c = 3-1/2"
b minimum = 3" d = 4"

Connection design assumes point load is top-loaded. For connection design of side-loaded point loads, please consult a technical representative or professional of Record.

Member has no side loads.

Connectors are: 16d Nails

3 1/2" ARDOX SPIRAL

Disclosure

Completeness and accuracy of input must be verified by anyone who would rely on output as evidence of suitability for particular application. Output here based on building code-accepted design properties and analysis methods. Installation of Boise Cascade engineered wood products must be in accordance with current Installation Guide and applicable building codes. To obtain Installation Guide or ask questions, please call 1-800-964-6999 before installation.

BC CALCO®, BC FRAMER®, AJS™, ALLJOIST®, BC RIM BOARD™, BCI®, BOISE GLULAM™, SIMPLE FRAMING SYSTEM®, VERSA-LAM®, VERSA-RIM PLUS®, VERSA-RIM®, VERSA-STRAND®, VERSA-STUD® are trademarks of Boise Cascade Wood Products L.L.C.



DWG NO. TAM 60314-17
STRUCTURAL
COMPONENT ONLY



Triple 1-3/4" x 11-7/8" VERSA-LAM® 2.0 3100 SP 1st Floor\...\B12DR(i2879)

Dry | 1 span | No cantilevers | 0/12 slope (deg)

October 26, 2017 16:55:47

BC CALC® Design Report



Build 5033

Job Name:

Address:

City, Province, Postal Code: EAST GWILLIMBURY,

Customer:

Code reports: CCMC 12472-R

File Name: NEWBERRY 6A.mmdl


Description: Designs\Dropped Beams\1st Floor\Dropped Beams\B12I

Specifier:

Designer: CF

Company:

Misc:



Total Horizontal Product Length = 14-09-00

Reaction Summary (Down / Uplift) (lbs)

Bearing	Live	Dead	Snow	Wind
B0, 4-1/2"	3,472 / 0	1,871 / 0		
B1, 4-1/2"	3,513 / 0	1,890 / 0		


Load Summary

Tag	Description	Load Type	Ref.	Start	End	Live 1.00	Dead 0.65	Snow 1.00	Wind 1.15	Trib.
0	Smoothed Load	Unf. Lin. (lb/ft)	L	00-00-00	03-08-00	252	126			n/a
1	Smoothed Load	Unf. Lin. (lb/ft)	L	07-10-00	14-04-00	477	238			n/a
2	J2(i2877)	Conc. Pt. (lbs)	L	01-00-00	01-00-00	258	129			n/a
3	J2(i2908)	Conc. Pt. (lbs)	L	02-00-00	02-00-00	257	129			n/a
4	J2(i2898)	Conc. Pt. (lbs)	L	03-00-00	03-00-00	300	150			n/a
5	-	Conc. Pt. (lbs)	L	04-05-14	04-05-14	651	326			n/a
6	-	Conc. Pt. (lbs)	L	05-09-14	05-09-14	651	326			n/a
7	-	Conc. Pt. (lbs)	L	07-01-12	07-01-12	612	307			n/a
8	J3(i2889)	Conc. Pt. (lbs)	L	14-04-00	14-04-00	231	115			n/a

Controls Summary	Factored Demand	Factored Resistance	Demand / Resistance	Load Case	Location
Pos. Moment	26,490 ft-lbs	60,415 ft-lbs	43.8%	1	07-04-00
End Shear	6,923 lbs	21,696 lbs	31.9%	1	13-04-10
Total Load Defl.	L/369 (0.459")	0.706"	65%	4	07-04-00
Live Load Defl.	L/568 (0.299")	0.471"	63.4%	5	07-04-00
Max Defl.	0.459"	n/a	n/a	4	07-04-00
Span / Depth	14.3	n/a	n/a		00-00-00

Bearing Supports	Dim. (L x W)	Demand	Demand / Resistance Support	Demand / Resistance Member	Material
B0 Wall/Plate	4-1/2" x 5-1/4"	7,547 lbs	39.3%	26.2%	Unspecified
B1 Wall/Plate	4-1/2" x 5-1/4"	7,631 lbs	39.8%	26.5%	Unspecified

Notes



DWG NO. TAM60315-17
STRUCTURAL
COMPONENT ONLY



Triple 1-3/4" x 11-7/8" VERSA-LAM® 2.0 3100 SP 1st Floor\...\B12DR(i2879)

Dry | 1 span | No cantilevers | 0/12 slope (deg)

October 26, 2017 16:55:47

BC CALC® Design Report



Build 5033

Job Name:

Address:

City, Province, Postal Code: EAST GWILLIMBURY,

Customer:

Code reports: CCMC 12472-R

File Name: NEWBERRY 6A.mmdl

Description: Designs\Dropped Beams\1st Floor\Dropped Beams\B1

Specifier:

Designer: CF

Company:

Misc:

Design meets Code minimum (L/240) Total load deflection criteria.

Design meets Code minimum (L/360) Live load deflection criteria.

Calculations assume unbraced length of Top: 00-03-02, Bottom: 00-03-02.

Resistance Factor phi has been applied to all presented results per CSA O86.

BC CALC® analysis is based on Canadian Limit States Design, as per NBCC 2010 and CSA

O86.

Design based on Dry Service Condition.

Importance Factor: Normal Part code: Part 9


CONFORMS TO OBC 2012

Disclosure

Completeness and accuracy of input must be verified by anyone who would rely on output as evidence of suitability for particular application. Output here based on building code-accepted design properties and analysis methods. Installation of Boise Cascade engineered wood products must be in accordance with current Installation Guide and applicable building codes. To obtain Installation Guide or ask questions, please call 1-800-964-6999 before installation.

BC CALC®, BC FRAMER®, AJS™, ALLJOIST®, BC RIM BOARD™, BCI®, BOISE GLULAM™, SIMPLE FRAMING SYSTEM®, VERSA-LAM®, VERSA-RIM PLUS®, VERSA-RIM®, VERSA-STRAND®, VERSA-STUD® are trademarks of Boise Cascade Wood Products L.L.C.

Connection Diagram



a minimum = 1" c = 6-7/8"
b minimum = 3" d = 4"
e minimum = 2"

Connection design assumes point load is top-loaded. For connection design of side-loaded point loads, please consult a technical representative or professional of Record.

Nailing schedule applies to both sides of the member.

Member has no side loads.

Connectors are: 16d x 7" Nails

3 1/2" ARDOX SPIRAL



DWG NO. TAM 60315-17
STRUCTURAL
COMPONENT ONLY



Single 1-3/4" x 9-1/2" VERSA-LAM® 2.0 3100 SP Basement\Flush Beams\B4(i2880)

Dry | 1 span | No cantilevers | 0/12 slope (deg)

October 26, 2017 16:55:47

BC CALC® Design Report



Build 5033

Job Name:

Address:

City, Province, Postal Code: EAST GWILLIMBURY,

Customer:

Code reports: CCMC 12472-R

File Name: NEWBERRY 6A.mmdl


Description: Designs\Flush Beams\Basement\Flush Beams\B4(i2880)

Specifier:

Designer: CF

Company:

Misc:



Total Horizontal Product Length = 09-06-00

Reaction Summary (Down / Uplift) (lbs)

Bearing	Live	Dead	Snow	Wind
B0, 3-1/2"	753 / 0	404 / 0		
B1	608 / 0	333 / 0		

Load Summary

Tag	Description	Load Type	Ref.	Start	End	Live 1.00	Dead 0.65	Snow 1.00	Wind 1.15	Trib.
0	J3(i2767)	Conc. Pt. (lbs)	L	01-05-00	01-05-00	306	153			n/a
1	J3(i2686)	Conc. Pt. (lbs)	L	02-09-00	02-09-00	254	127			n/a
2	J3(i2686)	Conc. Pt. (lbs)	L	04-01-00	04-01-00	254	127			n/a
3	J3(i2800)	Conc. Pt. (lbs)	L	05-05-00	05-05-00	236	128			n/a
4	J5(i2848)	Conc. Pt. (lbs)	L	06-09-00	06-09-00	122	61			n/a
5	J5(i2771)	Conc. Pt. (lbs)	L	08-01-00	08-01-00	121	61			n/a
6	J5(i2813)	Conc. Pt. (lbs)	L	09-04-12	09-04-12	68	34			n/a

Controls Summary	Factored Demand	Factored Resistance	Demand / Resistance	Load Case	Location
Pos. Moment	3,794 ft-lbs	12,704 ft-lbs	29.9%	1	04-01-00
End Shear	1,627 lbs	5,785 lbs	28.1%	1	01-01-00
Total Load Defl.	L/696 (0.158")	0.458"	34.5%	4	04-09-00
Live Load Defl.	L/999 (0.103")	n/a	n/a	5	04-09-00
Max Defl.	0.158"	n/a	n/a	4	04-09-00
Span / Depth	11.6	n/a	n/a		00-00-00

Bearing Supports	Dim. (L x W)	Demand	Demand / Resistance Support	Demand / Resistance Member	Material
B0 Wall/Plate	3-1/2" x 1-3/4"	1,634 lbs	50%	21.9%	Unspecified
B1 Hanger	2" x 1-3/4"	1,329 lbs	n/a	31.1%	HUS1.81/10

Notes

Design meets Code minimum (L/240) Total load deflection criteria.

Design meets Code minimum (L/360) Live load deflection criteria.

Calculations assume member is fully braced.

Hanger Manufacturer: Unassigned

Resistance Factor phi has been applied to all presented results per CSA O86.

BC CALC® analysis is based on Canadian Limit States Design, as per NBCC 2010 and CSA O86.

Design based on Dry Service Condition.

Importance Factor: Normal Part code: Part 9

CONFORMS TO CBC 2012



DWGNO. TAM 6031617
STRUCTURAL
COMPONENT ONLY



Boise Cascade

Single 1-3/4" x 9-1/2" VERSA-LAM® 2.0 3100 SP Basement\Flush Beams\B4(i2880)

BC CALC® Design Report



Dry | 1 span | No cantilevers | 0/12 slope (deg)

October 26, 2017 16:55:47

Build 5033

Job Name:

Address:

City, Province, Postal Code: EAST GWILLIMBURY,

Customer:

Code reports: CCMC 12472-R

File Name: NEWBERRY 6Ammdl

Description: Designs\Flush Beams\Basement\Flush Beams\B4(i2880

Specifier:

Designer: CF

Company:

Misc:

Disclosure

Completeness and accuracy of input must be verified by anyone who would rely on output as evidence of suitability for particular application. Output here based on building code-accepted design properties and analysis methods. Installation of Boise Cascade engineered wood products must be in accordance with current Installation Guide and applicable building codes. To obtain Installation Guide or ask questions, please call 1-800-964-6999 before installation.

BC CALO®, BC FRAMER®, AJS™, ALLJOIST®, BC RIM BOARD™, BC®, BOISE GLULAM™, SIMPLE FRAMING SYSTEM®, VERSA-LAM®, VERSA-RIM PLUS®, VERSA-RIM®, VERSA-STRAND®, VERSA-STUD® are trademarks of Boise Cascade Wood Products L.L.C.



DWG NO. TAM 60316.17
STRUCTURAL
COMPONENT ONLY



Single 1-3/4" x 9-1/2" VERSA-LAM® 2.0 3100 SP Basement\Flush Beams\B3(i2886)

Dry | 1 span | No cantilevers | 0/12 slope (deg)

October 26, 2017 16:55:47

BC CALC® Design Report



Build 5033

Job Name:

Address:

City, Province, Postal Code: EAST GWILLIMBURY,

Customer:

Code reports: CCMC 12472-R

File Name: NEWBERRY 6A.mmdl


Description: Designs\Flush Beams\Basement\Flush Beams\B3(i2886)

Specifier:

Designer: CF

Company:

Misc:



Total Horizontal Product Length = 08-06-08

Reaction Summary (Down / Uplift) (lbs)

Bearing	Live	Dead	Snow	Wind
B0, 3-1/2"	1,077 / 0	589 / 0		
B1, 5-1/2"	642 / 0	369 / 0		

Load Summary

Tag	Description	Load Type	Ref.	Start	End	Live 1.00	Dead 0.65	Snow 1.00	Wind 1.15	Trib.
0	FC1 Floor Material	Unf. Lin. (lb/ft)	L	00-00-00	03-08-08	25	13			n/a
1	STAIR	Unf. Lin. (lb/ft)	L	00-03-08	03-08-08	240	120			n/a
2	FC1 Floor Material	Unf. Lin. (lb/ft)	L	03-08-08	08-06-08	27	14			n/a
3	E1(i380)	Conc. Pt. (lbs)	L	00-02-12	00-02-12		15			n/a
4	B4(i2880)	Conc. Pt. (lbs)	L	03-09-06	03-09-06	604	330			n/a
5	5(i345)	Conc. Pt. (lbs)	L	08-03-12	08-03-12	71	50			n/a

Controls Summary	Factored Demand	Factored Resistance	Demand / Resistance	Load Case	Location
Pos. Moment	4,759 ft-lbs	12,704 ft-lbs	37.5%	1	03-09-06
End Shear	1,864 lbs	5,785 lbs	32.2%	1	01-01-00
Total Load Defl.	L/714 (0.133")	0.396"	33.6%	4	04-00-00
Live Load Defl.	L/999 (0.086")	n/a	n/a	5	04-00-00
Max Defl.	0.133"	n/a	n/a	4	04-00-00
Span / Depth	10	n/a	n/a		00-00-00

Bearing Supports	Dim. (L x W)	Demand	Demand / Resistance Support	Demand / Resistance Member	Material
B0 Wall/Plate	3-1/2" x 1-3/4"	2,351 lbs	71.9%	31.5%	Unspecified
B1 Wall/Plate	5-1/2" x 1-3/4"	1,424 lbs	27.7%	12.1%	Unspecified

Notes

Design meets Code minimum (L/240) Total load deflection criteria.

Design meets Code minimum (L/360) Live load deflection criteria.

Calculations assume member is fully braced.

Resistance Factor phi has been applied to all presented results per CSA O86.

BC CALC® analysis is based on Canadian Limit States Design, as per NBCC 2010 and CSA O86.

Design based on Dry Service Condition.

Importance Factor : Normal Part code : Part 9

CONFORMS TO OBC 2012



DWG NO. TAN 60317-17
STRUCTURAL
COMPONENT ONLY



Boise Cascade

Single 1-3/4" x 9-1/2" VERSA-LAM® 2.0 3100 SP Basement\Flush Beams\B3(i2886)

Dry | 1 span | No cantilevers | 0/12 slope (deg)

October 26, 2017 16:55:47

BC CALC® Design Report



Build 5033

Job Name:

Address:

City, Province, Postal Code: EAST GWILLIMBURY,

Customer:

Code reports: CCMC 12472-R

File Name: NEWBERRY 6A.mmdl

Description: Designs\Flush Beams\Basement\Flush Beams\B3(i2886)

Specifier:

Designer: CF

Company:

Misc:

Disclosure

Completeness and accuracy of input must be verified by anyone who would rely on output as evidence of suitability for particular application. Output here based on building code-accepted design properties and analysis methods.

Installation of Boise Cascade engineered wood products must be in accordance with current Installation Guide and applicable building codes. To obtain Installation Guide or ask questions, please call 1-800-964-6999 before installation.

BC CALO®, BC FRAMER®, AJS™, ALLJOIST®, BC RIM BOARD™, BC®, BOISE GLULAM™, SIMPLE FRAMING SYSTEM®, VERSA-LAM®, VERSA-RIM PLUS®, VERSA-RIM®, VERSA-STRAND®, VERSA-STUD® are trademarks of Boise Cascade Wood Products L.L.C.



DWG NO. TAM 60317-17
STRUCTURAL
COMPONENT ONLY



Double 1-3/4" x 9-1/2" VERSA-LAM® 2.0 3100 SP Basement\Flush Beams\B7(i2911)

Dry | 1 span | No cantilevers | 0/12 slope (deg)

October 26, 2017 16:55:47

BC CALC® Design Report



Build 5033

Job Name:

Address:

City, Province, Postal Code: EAST GWILLIMBURY,

Customer:

Code reports:

CCMC 12472-R

File Name: NEWBERRY 6A.mmdl


Description: Designs\Flush Beams\Basement\Flush Beams\B7(i2911)

Specifier:

Designer: CF

Company:

Misc:



Total Horizontal Product Length = 04-09-02

Reaction Summary (Down / Uplift) (lbs)

Bearing	Live	Dead	Snow	Wind
B0, 3-1/2"	1,255 / 0	732 / 0		
B1, 8-1/4"	4,988 / 48	2,786 / 0		

Load Summary

Tag	Description	Load Type	Ref.	Start	End	Live 1.00	Dead 0.65	Snow 1.00	Wind 1.15	Trib.
0	FC 1 Floor Material	Unf. Lin. (lb/ft)	L	00-00-00	04-03-08	19	9			n/a
1	9(i145)	Unf. Lin. (lb/ft)	L	03-05-08	04-05-08		101			n/a
2	-	Conc. Pt. (lbs)	L	00-03-11	00-03-11	813	479			n/a
3	J1(i286)	Conc. Pt. (lbs)	L	01-09-00	01-09-00	370	185			n/a
4	-	Conc. Pt. (lbs)	L	03-04-03	03-04-03	952	508			n/a
5	-	Conc. Pt. (lbs)	L	04-03-15	04-03-15	4,026	2,159			n/a
6	-	Conc. Pt. (lbs)	L	04-03-15	04-03-15	-48				n/a

Controls Summary	Factored Demand	Factored Resistance	Demand / Resistance	Load Case	Location
Pos. Moment	1,646 ft-lbs	25,408 ft-lbs	6.5%	1	03-01-00
End Shear	1,727 lbs	11,571 lbs	14.9%	1	03-03-06
Total Load Defl.	L/999 (0.007")	n/a	n/a	6	02-03-00
Live Load Defl.	L/999 (0.004")	n/a	n/a	8	02-03-00
Max Defl.	0.007"	n/a	n/a	6	02-03-00
Span / Depth	4.9	n/a	n/a		00-00-00

Bearing Supports	Dim. (L x W)	Demand	Demand / Resistance Support	Demand / Resistance Member	Material
B0 Beam	3-1/2" x 3-1/2"	2,798 lbs	42.8%	18.7%	Unspecified
B1 Beam	8-1/4" x 3-1/2"	10,964 lbs	71.1%	31.1%	Unspecified

Notes



DWG NO. TAM 60318-17
STRUCTURAL
COMPONENT ONLY



Boise Cascade

Double 1-3/4" x 9-1/2" VERSA-LAM® 2.0 3100 SP Basement\Flush Beams\B7(i2911)

Dry | 1 span | No cantilevers | 0/12 slope (deg)

October 26, 2017 16:55:47

BC CALC® Design Report



Build 5033

Job Name:

Address:

City, Province, Postal Code: EAST GWILLIMBURY,

Customer:

Code reports: CCMC 12472-R

File Name: NEWBERRY6A.mmdl

Description: Designs\Flush Beams\Basement\Flush Beams\B7(i291

Specifier:

Designer: CF

Company:

Misc:

Design meets Code minimum (L/240) Total load deflection criteria.

Design meets Code minimum (L/360) Live load deflection criteria.

Calculations assume unbraced length of Top: 00-00-00, Bottom: 00-00-00.

Resistance Factor phi has been applied to all presented results per CSA O86.

BC CALC® analysis is based on Canadian Limit States Design, as per NBCC 2010 and CSA O86.


CONFORMS TO OBC 2012

Design based on Dry Service Condition.

Importance Factor: Normal Part code: Part 9

Connection Diagram

Concentrated side-load exceeds allowable magnitude for connection design. Please consult a technical representative or Professional Engineer for the design of the connection.

*OK WITH
MULTI-PLY
+
BOLTING.**+
BOLTS***Disclosure**

Completeness and accuracy of input must be verified by anyone who would rely on output as evidence of suitability for particular application. Output here based on building code-accepted design properties and analysis methods. Installation of Boise Cascade engineered wood products must be in accordance with current Installation Guide and applicable building codes. To obtain Installation Guide or ask questions, please call 1-800-964-6999 before installation.

BC CALC®, BC FRAMER®, AJS™, ALLJOIST®, BC RIM BOARD™, BCI®, BOISE GLULAM™, SIMPLE FRAMING SYSTEM®, VERSA-LAM®, VERSA-RIM PLUS®, VERSA-RIM®, VERSA-STRAND®, VERSA-STUD® are trademarks of Boise Cascade Wood Products L.L.C.



DWG NO. TAM 60318-17
STRUCTURAL
COMPONENT ONLY



Single 1-3/4" x 9-1/2" VERSA-LAM® 2.0 3100 SP Basement\Flush Beams\B5(i2917)

Dry | 1 span | No cantilevers | 0/12 slope (deg)

October 26, 2017 16:55:48

BC CALC® Design Report



Build 5033

Job Name:

Address:

City, Province, Postal Code: EAST GWILLIMBURY,

Customer:

Code reports: CCMC 12472-R

File Name: NEWBERRY 6A.mmdl


Description: Designs\Flush Beams\Basement\Flush Beams\B5(i2917)

Specifier:

Designer: CF

Company:

Misc:



Total Horizontal Product Length = 03-11-00

Reaction Summary (Down / Uplift) (lbs)

Bearing	Live	Dead	Snow	Wind
B0, 5-1/2"	1,245 / 0	682 / 0		
B1, 3-1/2"	741 / 0	379 / 0		

Load Summary

Tag Description	Load Type	Ref.	Start	End	Live 1.00	Dead 0.65	Snow 1.00	Wind 1.15	Trib.
0 STAIR	Unf. Lin. (lb/ft)	L	00-05-08	03-07-08	240	120			n/a
1 12(i278)	Conc. Pt. (lbs)	L	00-02-12	00-02-12	622	361			n/a
2 J4(i2833)	Conc. Pt. (lbs)	L	01-00-08	01-00-08	198	99			n/a
3 J4(i2869)	Conc. Pt. (lbs)	L	02-04-08	02-04-08	198	99			n/a
4 J4(i2825)	Conc. Pt. (lbs)	L	03-08-08	03-08-08	198	99			n/a

Controls Summary

	Factored Demand	Factored Resistance	Demand / Resistance	Load Case	Location
Pos. Moment	1,121 ft-lbs	12,704 ft-lbs	8.8%	1	02-02-06
End Shear	809 lbs	5,785 lbs	14%	1	01-03-00
Total Load Defl.	L/999 (0.006")	n/a	n/a	4	02-00-04
Live Load Defl.	L/999 (0.004")	n/a	n/a	5	02-00-04
Max Defl.	0.006"	n/a	n/a	4	02-00-04
Span / Depth	4.2	n/a	n/a		00-00-00

Disclosure

Completeness and accuracy of input must be verified by anyone who would rely on output as evidence of suitability for particular application. Output here based on building code-accepted design properties and analysis methods. Installation of Boise Cascade engineered wood products must be in accordance with current Installation Guide and applicable building codes. To obtain Installation Guide or ask questions, please call 1-800-964-6999 before installation.

Bearing Supports

	Dim. (L x W)	Demand	Demand / Resistance Support	Demand / Resistance Member	Material
B0 Wall/Plate	5-1/2" x 1-3/4"	2,720 lbs	52.9%	23.2%	Unspecified
B1 Wall/Plate	3-1/2" x 1-3/4"	1,585 lbs	48.5%	21.2%	Unspecified

Notes

Design meets Code minimum (L/240) Total load deflection criteria.

Design meets Code minimum (L/360) Live load deflection criteria.

Calculations assume member is fully braced.

Resistance Factor phi has been applied to all presented results per CSA O86.

BC CALC® analysis is based on Canadian Limit States Design, as per NBCC 2010 and CSA O86.

Design based on Dry Service Condition.

Importance Factor: Normal Part code: Part 9

CONFORMS TO QBC 2012

BC CALC®, BC FRAMER®, AJS™, ALLJOIST®, BC RIM BOARD™, BCI®, BOISE GLULAM™, SIMPLE FRAMING SYSTEM®, VERSA-LAM®, VERSA-RIM PLUS®, VERSA-RIM®, VERSA-STRAND®, VERSA-STUD® are trademarks of Boise Cascade Wood Products L.L.C.



DWG NO. TAM 60319-17
STRUCTURAL
COMPONENT ONLY



Single 1-3/4" x 9-1/2" VERSA-LAM® 2.0 3100 SP Basement\Flush Beams\B2(i2882)

Dry | 1 span | No cantilevers | 0/12 slope (deg)

October 26, 2017 16:55:48

BC CALC® Design Report



Build 5033

Job Name:

Address:

City, Province, Postal Code: EAST GWILLIMBURY,

Customer:

Code reports: CCMC 12472-R

File Name: NEWBERRY 6A.mmdl


Description: Designs\Flush Beams\Basement\Flush Beams\B2(i2882)

Specifier:

Designer: CF

Company:

Misc:



Total Horizontal Product Length = 04-08-04

Reaction Summary (Down / Uplift) (lbs)

Bearing	Live	Dead	Snow	Wind
B0, 5-1/4"	178 / 0	100 / 0		
B1, 5-1/2"	135 / 0	93 / 0		

Load Summary

Tag	Description	Load Type	Ref.	Start	End	Live 1.00	Dead 0.65	Snow 1.00	Wind 1.15	Trib.
0	Smoothed Load	Unf. Lin. (lb/ft)	L	00-00-00	03-06-04	71	36			n/a
1	FC1 Floor Material	Unf. Lin. (lb/ft)	L	00-05-04	01-06-04	3				n/a
2	-	Conc. Pt. (lbs)	L	04-02-12	04-02-12	58	44			n/a

Controls Summary

	Factored Demand	Factored Resistance	Demand / Resistance	Load Case	Location
Pos. Moment	258 ft-lbs	12,704 ft-lbs	2%	1	02-10-04
End Shear	201 lbs	5,785 lbs	3.5%	1	01-02-12
Total Load Defl.	L/999 (0.002")	n/a	n/a	4	02-03-12
Live Load Defl.	L/999 (0.001")	n/a	n/a	5	02-03-12
Max Defl.	0.002"	n/a	n/a	4	02-03-12
Span / Depth	4.9	n/a	n/a		00-00-00

Disclosure

Completeness and accuracy of input must be verified by anyone who would rely on output as evidence of suitability for particular application. Output here based on building code-accepted design properties and analysis methods. Installation of Boise Cascade engineered wood products must be in accordance with current Installation Guide and applicable building codes. To obtain Installation Guide or ask questions, please call 1-800-964-6999 before installation.

Bearing Supports

	Dim. (L x W)	Demand	Demand / Resistance Support	Demand / Resistance Member	Material
B0 Post	5-1/4" x 1-3/4"	391 lbs	5.2%	3.5%	Unspecified
B1 Wall/Plate	5-1/2" x 1-3/4"	319 lbs	6.2%	2.7%	Unspecified

Notes

Design meets Code minimum (L/240) Total load deflection criteria.

Design meets Code minimum (L/360) Live load deflection criteria.

Calculations assume member is fully braced.

Resistance Factor phi has been applied to all presented results per CSA O86.

BC CALC® analysis is based on Canadian Limit States Design, as per NBCC 2010 and CSA O86.

Design based on Dry Service Condition.

Importance Factor : Normal Part code : Part 9

CONFORMS TO OBC 2012

BC CALC®, BC FRAMER®, AJS™, ALLJOIST®, BC RIM BOARD™, BCI®, BOISE GLULAM™, SIMPLE FRAMING SYSTEM®, VERSA-LAM®, VERSA-RIM PLUS®, VERSA-RIM®, VERSA-STRAND®, VERSA-STUD® are trademarks of Boise Cascade Wood Products L.L.C.



DWG NO. TAM 60320-17
STRUCTURAL
COMPONENT ONLY



Double 1-3/4" x 9-1/2" VERSA-LAM® 2.0 3100 SP 1st Floor\...\B16(i3146)

Dry | 1 span | No cantilevers | 0/12 slope (deg)

November 30, 2017 11:46:14

BC CALC® Design Report



Build 5033

Job Name:

Address:

City, Province, Postal Code: EAST GWILLIMBURY,

Customer:

Code reports:

CCMC 12472-R

File Name: NEWBERRY 6A EL 2.mmdl


Description: Designs\Flush Beams\1st Floor\Flush Beams\B16(i3146)

Specifier:

Designer: CF

Company:

Misc:



Total Horizontal Product Length = 01-06-04

Reaction Summary (Down / Uplift) (lbs)

Bearing	Live	Dead	Snow	Wind
B0, 3-1/4"		69 / 0		
B1, 6-1/2"		98 / 0		

Load Summary

Tag	Description	Load Type	Ref.	Start	End	Live	Dead	Snow	Wind	Trib.
0	User Load	Unf. Lin. (lb/ft)	L	00-00-00	01-06-04	1.00	0.65	1.00	1.15	n/a

Controls Summary

	Factored Demand	Factored Resistance	Demand / Resistance	Load Case	Location
Pos. Moment	13 ft-lbs	n/a	n/a	0	00-07-08
End Shear	54 lbs	7,521 lbs	0.7%	0	00-03-04
Span / Depth	1.1	n/a	n/a		00-00-00

Bearing Supports

	Dim. (L x W)	Demand	Demand / Resistance Support	Demand / Resistance Member	Material
B0 Beam	3-1/4" x 3-1/2"	96 lbs	2.4%	1.1%	Unspecified
B1 Beam	6-1/2" x 3-1/2"	137 lbs	1.7%	0.8%	Unspecified

Notes

Calculations assume member is fully braced.

Resistance Factor phi has been applied to all presented results per CSA O86.

BC CALC® analysis is based on Canadian Limit States Design, as per NBCC 2010 and CSA O86.

CONFORMS TO OBC 2012

Design based on Dry Service Condition.

Importance Factor : Normal Part code : Part 9



DWG NO. TAM 60324-17
STRUCTURAL
COMPONENT ONLY

BC CALC® Design Report



Build 5033

Job Name:

Address:

City, Province, Postal Code: EAST GWILLIMBURY,

Customer:

Code reports:

CCMC 12472-R

File Name: NEWBERRY 6AEL 2.mmd

Description: Designs\Flush Beams\1st Floor\Flush Beams\B16(i314


Specifier:

Designer: CF

Company:

Msc:

Connection Diagram



a minimum = 1" c = 1 1/2"
b minimum = 3" d = 4"

Member has no side loads.

Connectors are: 16d Nails

3 1/2" ARDOX SPIRAL

Disclosure

Completeness and accuracy of input must be verified by anyone who would rely on output as evidence of suitability for particular application. Output here based on building code-accepted design properties and analysis methods. Installation of Boise Cascade engineered wood products must be in accordance with current Installation Guide and applicable building codes. To obtain Installation Guide or ask questions, please call 1-800-964-6999 before installation.

BC CALC®, BC FRAMER®, AJST™, ALLJOIST®, BC RIM BOARD™, BCI®, BOISE GLULAM™, SIMPLE FRAMING SYSTEM®, VERSA-LAM®, VERSA-RIM PLUS®, VERSA-RIM®, VERSA-STRAND®, VERSA-STUD® are trademarks of Boise Cascade Wood Products L.L.C.



DWG NO. TAM 6034-17
STRUCTURAL
COMPONENT ONLY



Double 1-3/4" x 9-1/2" VERSA-LAM® 2.0 3100 SP 1st Floor\...\B15(i3140)

Dry | 1 span | No cantilevers | 0/12 slope (deg)

November 30, 2017 11:46:00

BC CALC® Design Report



Build 5033

Job Name:

Address:

City, Province, Postal Code: EAST GWILLIMBURY,

Customer:

Code reports:

CCMC 12472-R

File Name: NEWBERRY6A EL 1.mmdl


Description: Designs\Flush Beams\1st Floor\Flush Beams\B15(i3140)

Specifier:

Designer: CF

Company:

Misc:



Total Horizontal Product Length = 01-03-04

Reaction Summary (Down / Uplift) (lbs)

Bearing	Live	Dead	Snow	Wind
B0, 3-1/4"		55 / 0		
B1, 6-1/2"		85 / 0		

Load Summary

Tag	Description	Load Type	Ref.	Start	End	Live	Dead	Snow	Wind	Trib.
0	User Load	Unf. Lin. (lb/ft)	L	00-00-00	01-03-04	1.00	0.65	1.00	1.15	n/a

Controls Summary	Factored Demand	Factored Resistance	Demand / Resistance	Load Case	Location
Pos. Moment	7 ft-lbs	n/a	n/a	0	00-06-00
End Shear	35 lbs	7,521 lbs	0.5%	0	00-03-04
Span / Depth	0.7	n/a	n/a		00-00-00

Bearing Supports	Dim. (L x W)	Demand	Demand / Resistance Support	Demand / Resistance Member	Material
B0 Beam	3-1/4" x 3-1/2"	77 lbs	1.9%	0.9%	Unspecified
B1 Beam	6-1/2" x 3-1/2"	118 lbs	1.5%	0.7%	Unspecified

Notes

Calculations assume member is fully braced.

Resistance Factor phi has been applied to all presented results per CSA O86.

BC CALC® analysis is based on Canadian Limit States Design, as per NBCC 2010 and CSA O86.

CONFORMS TO CBC 2012

Design based on Dry Service Condition.

Importance Factor : Normal Part code : Part 9



DWG NO. TAM 6032217
STRUCTURAL
COMPONENT ONLY



Double 1-3/4" x 9-1/2" VERSA-LAM® 2.0 3100 SP 1st Floor\...\B15(i3140)

Dry | 1 span | No cantilevers | 0/12 slope (deg)

November 30, 2017 11:46:00

BC CALC® Design Report



Build 5033

Job Name:

Address:

City, Province, Postal Code: EAST GWILLIMBURY,

Customer:

Code reports:

CCMC 12472-R

File Name: NEWBERRY 6A EL 1.mmdl

Description: Designs\Flush Beams\1st Floor\Flush Beams\B15(i314


Specifier:

Designer: CF

Company:

Misc:

Connection Diagram



$\$1^4$
 $\$4$ rows
 $\$2"$ min
 $\$1"$

a minimum = 1" c = 1-1/2"
 b minimum = 3" d = 4"

Member has no side loads.


Connectors are: 16d Nails

3 1/2" ARDOX SPIRAL



Disclosure

Completeness and accuracy of input must be verified by anyone who would rely on output as evidence of suitability for particular application. Output here based on building code-accepted design properties and analysis methods. Installation of Boise Cascade engineered wood products must be in accordance with current Installation Guide and applicable building codes. To obtain Installation Guide or ask questions, please call 1-800-964-6999 before installation.

BC CALC®, BC FRAMER®, AJST™, ALLJOIST®, BC RIM BOARD™, BCI®, BOISE GLULAM™, SIMPLE FRAMING SYSTEM®, VERSA-LAM®, VERSA-RIM PLUS®, VERSA-RIM®, VERSA-STRAND®, VERSA-STUD® are trademarks of Boise Cascade Wood Products L.L.C.



DWG NO. TAM 60322-17
 STRUCTURAL
 COMPONENT ONLY





Maximum Floor Spans

Live Load = 40 psf, Dead Load = 15 psf
Simple Spans, L/480 Deflection Limit
5/8" OSB G&N Sheathing

Depth	Series	Bare				1/2" Gypsum Ceiling			
		On Centre Spacing				On Centre Spacing			
		12"	16"	19.2"	24"	12"	16"	19.2"	24"
9-1/2"	NI-20	15'-1"	14'-2"	13'-9"	N/A	15'-7"	14'-8"	14'-2"	N/A
	NI-40x	16'-1"	15'-2"	14'-8"	N/A	16'-7"	15'-7"	15'-1"	N/A
	NI-60	16'-3"	15'-4"	14'-10"	N/A	16'-8"	15'-9"	15'-3"	N/A
	NI-70	17'-1"	16'-1"	15'-6"	N/A	17'-5"	16'-5"	15'-10"	N/A
	NI-80	17'-3"	16'-3"	15'-8"	N/A	17'-8"	16'-7"	16'-0"	N/A
11-7/8"	NI-20	16'-11"	16'-0"	15'-5"	N/A	17'-6"	16'-6"	16'-0"	N/A
	NI-40x	18'-1"	17'-0"	16'-5"	N/A	18'-9"	17'-6"	16'-11"	N/A
	NI-60	18'-4"	17'-3"	16'-7"	N/A	19'-0"	17'-8"	17'-1"	N/A
	NI-70	19'-6"	18'-0"	17'-4"	N/A	20'-1"	18'-7"	17'-9"	N/A
	NI-80	19'-9"	18'-3"	17'-6"	N/A	20'-4"	18'-10"	17'-11"	N/A
	NI-90x	20'-4"	18'-9"	17'-11"	N/A	20'-10"	19'-3"	18'-5"	N/A
14"	NI-40x	20'-1"	18'-7"	17'-10"	N/A	20'-10"	19'-4"	18'-6"	N/A
	NI-60	20'-5"	18'-11"	18'-1"	N/A	21'-2"	19'-7"	18'-9"	N/A
	NI-70	21'-7"	20'-0"	19'-1"	N/A	22'-3"	20'-7"	19'-8"	N/A
	NI-80	21'-11"	20'-3"	19'-4"	N/A	22'-7"	20'-11"	20'-0"	N/A
	NI-90x	22'-7"	20'-11"	19'-11"	N/A	23'-3"	21'-6"	20'-6"	N/A
16"	NI-60	22'-3"	20'-8"	19'-9"	N/A	23'-1"	21'-5"	20'-6"	N/A
	NI-70	23'-6"	21'-9"	20'-9"	N/A	24'-3"	22'-5"	21'-5"	N/A
	NI-80	23'-11"	22'-1"	21'-1"	N/A	24'-8"	22'-10"	21'-9"	N/A
	NI-90x	24'-8"	22'-9"	21'-9"	N/A	25'-4"	23'-5"	22'-4"	N/A

Depth	Series	Mid-Span Blocking				Mid-Span Blocking and 1/2" Gypsum Ceiling			
		On Centre Spacing				On Centre Spacing			
		12"	16"	19.2"	24"	12"	16"	19.2"	24"
9-1/2"	NI-20	16'-8"	15'-3"	14'-5"	N/A	16'-8"	15'-3"	14'-5"	N/A
	NI-40x	17'-11"	16'-11"	16'-1"	N/A	18'-5"	17'-1"	16'-1"	N/A
	NI-60	18'-2"	17'-1"	16'-4"	N/A	18'-7"	17'-4"	16'-4"	N/A
	NI-70	19'-2"	17'-10"	17'-2"	N/A	19'-7"	18'-3"	17'-7"	N/A
	NI-80	19'-5"	18'-0"	17'-4"	N/A	19'-10"	18'-5"	17'-8"	N/A
11-7/8"	NI-20	19'-6"	18'-1"	17'-3"	N/A	19'-11"	18'-3"	17'-3"	N/A
	NI-40x	21'-0"	19'-6"	18'-8"	N/A	21'-7"	20'-2"	19'-2"	N/A
	NI-60	21'-4"	19'-9"	18'-11"	N/A	21'-11"	20'-4"	19'-6"	N/A
	NI-70	22'-6"	20'-10"	19'-11"	N/A	23'-0"	21'-5"	20'-5"	N/A
	NI-80	22'-9"	21'-1"	20'-1"	N/A	23'-3"	21'-7"	20'-8"	N/A
	NI-90x	23'-4"	21'-8"	20'-8"	N/A	23'-10"	22'-2"	21'-2"	N/A
14"	NI-40x	23'-7"	21'-11"	20'-11"	N/A	24'-3"	22'-7"	21'-7"	N/A
	NI-60	24'-0"	22'-3"	21'-3"	N/A	24'-8"	22'-11"	21'-11"	N/A
	NI-70	25'-3"	23'-4"	22'-3"	N/A	25'-10"	24'-0"	22'-11"	N/A
	NI-80	25'-7"	23'-8"	22'-7"	N/A	26'-2"	24'-4"	23'-2"	N/A
	NI-90x	26'-4"	24'-4"	23'-3"	N/A	26'-10"	24'-11"	23'-9"	N/A
16"	NI-60	26'-5"	24'-6"	23'-4"	N/A	27'-2"	25'-3"	24'-2"	N/A
	NI-70	27'-9"	25'-8"	24'-6"	N/A	28'-5"	26'-5"	25'-2"	N/A
	NI-80	28'-2"	26'-1"	24'-10"	N/A	28'-10"	26'-9"	25'-6"	N/A
	NI-90x	29'-0"	26'-10"	25'-7"	N/A	29'-7"	27'-5"	26'-2"	N/A

- Maximum clear span applicable to simple-span residential floor construction with a design live load of 40 psf and dead load of 15 psf. The ultimate limit states are based on the factored loads of 1.50L + 1.25D. The serviceability limit states include the consideration for floor vibration, a live load deflection limit of L/480 and a total load deflection limit of L/240.
- Spans are based on a composite floor with glued-nailed oriented strand board (OSB) sheathing with a minimum thickness of 5/8 inch for a joist spacing of 19.2 inches or less. The composite floor may include 1/2 inch gypsum ceiling and/or one row of blocking at mid-span with strapping. Strapping shall be minimum 1x4 inch strap applied to underside of joists at blocking line or 1/2 inch gypsum ceiling attached to joists.
- Minimum bearing length shall be 1-3/4 inches for the end bearings.
- Bearing stiffeners are not required when I-joists are used with the spans and spacings given in this table, except as required for hangers.
- This span chart is based on uniform loads. For applications with other than uniformly distributed loads, an engineering analysis may be required based on the use of the design properties. Tables are based on Limit States Design per CSA O86-09, NBC 2010, and OBC 2012.
- Joists shall be laterally supported at supports and continuously along the compression edge. Refer to technical documentation for installation guidelines and construction details. Nordic I-joists are listed in CCMC evaluation report 13032-R and APA Product Report PR-L274C.





Maximum Floor Spans

Live Load = 40 psf, Dead Load = 15 psf
Simple Spans, L/480 Deflection Limit
3/4" OSB G&N Sheathing

Depth	Series	Bare				1/2" Gypsum Ceiling			
		On Centre Spacing				On Centre Spacing			
		12"	16"	19.2"	24"	12"	16"	19.2"	24"
9-1/2"	NI-20	15'-10"	15'-0"	14'-5"	13'-5"	16'-4"	15'-5"	14'-6"	13'-5"
	NI-40x	17'-0"	16'-0"	15'-5"	14'-9"	17'-5"	16'-5"	15'-10"	15'-2"
	NI-60	17'-2"	16'-2"	15'-7"	14'-11"	17'-6"	16'-7"	15'-11"	15'-3"
	NI-70	18'-0"	16'-11"	16'-3"	15'-7"	18'-5"	17'-3"	16'-7"	15'-11"
	NI-80	18'-3"	17'-1"	16'-5"	15'-9"	18'-8"	17'-5"	16'-9"	16'-1"
11-7/8"	NI-20	17'-10"	16'-10"	16'-2"	15'-6"	18'-6"	17'-4"	16'-9"	16'-1"
	NI-40x	19'-4"	17'-11"	17'-3"	16'-6"	19'-11"	18'-6"	17'-9"	17'-0"
	NI-60	19'-7"	18'-2"	17'-5"	16'-9"	20'-2"	18'-9"	17'-11"	17'-2"
	NI-70	20'-9"	19'-2"	18'-3"	17'-5"	21'-4"	19'-9"	18'-10"	17'-10"
	NI-80	21'-1"	19'-5"	18'-6"	17'-7"	21'-7"	20'-0"	19'-0"	18'-0"
14"	NI-90x	21'-8"	20'-0"	19'-1"	18'-0"	22'-2"	20'-6"	19'-6"	18'-6"
	NI-40x	21'-5"	19'-10"	18'-11"	17'-11"	22'-1"	20'-6"	19'-7"	18'-7"
	NI-60	21'-10"	20'-2"	19'-3"	18'-2"	22'-5"	20'-10"	19'-11"	18'-10"
	NI-70	23'-0"	21'-3"	20'-3"	19'-2"	23'-8"	21'-11"	20'-10"	19'-9"
	NI-80	23'-5"	21'-7"	20'-7"	19'-5"	24'-0"	22'-3"	21'-2"	20'-0"
16"	NI-90x	24'-1"	22'-3"	21'-2"	20'-0"	24'-8"	22'-10"	21'-9"	20'-7"
	NI-60	23'-9"	22'-0"	20'-11"	19'-10"	24'-6"	22'-9"	21'-8"	20'-6"
	NI-70	25'-1"	23'-2"	22'-0"	20'-10"	25'-9"	23'-10"	22'-9"	21'-6"
	NI-80	25'-6"	23'-6"	22'-4"	21'-2"	26'-1"	24'-2"	23'-1"	21'-10"
	NI-90x	26'-4"	24'-3"	23'-1"	21'-10"	26'-11"	24'-11"	23'-8"	22'-5"

Depth	Series	Mid-Span Blocking				Mid-Span Blocking and 1/2" Gypsum Ceiling			
		On Centre Spacing				On Centre Spacing			
		12"	16"	19.2"	24"	12"	16"	19.2"	24"
9-1/2"	NI-20	16'-10"	15'-5"	14'-6"	13'-5"	16'-10"	15'-5"	14'-6"	13'-5"
	NI-40x	18'-8"	17'-2"	16'-3"	15'-2"	18'-10"	17'-2"	16'-3"	15'-2"
	NI-60	18'-11"	17'-6"	16'-6"	15'-5"	19'-2"	17'-6"	16'-6"	15'-5"
	NI-70	20'-0"	18'-7"	17'-9"	16'-7"	20'-5"	18'-11"	17'-10"	16'-7"
	NI-80	20'-3"	18'-10"	17'-11"	16'-10"	20'-8"	19'-3"	18'-2"	16'-10"
11-7/8"	NI-20	20'-1"	18'-5"	17'-5"	16'-2"	20'-1"	18'-5"	17'-5"	16'-2"
	NI-40x	21'-10"	20'-4"	19'-4"	17'-8"	22'-5"	20'-6"	19'-4"	17'-8"
	NI-60	22'-1"	20'-7"	19'-7"	18'-4"	22'-8"	20'-10"	19'-8"	18'-4"
	NI-70	23'-4"	21'-8"	20'-8"	19'-7"	23'-10"	22'-3"	21'-2"	19'-9"
	NI-80	23'-7"	21'-11"	20'-11"	19'-9"	24'-1"	22'-6"	21'-5"	20'-0"
14"	NI-90x	24'-3"	22'-6"	21'-6"	20'-4"	24'-8"	23'-0"	22'-0"	20'-9"
	NI-40x	24'-5"	22'-9"	21'-8"	19'-5"	25'-1"	23'-2"	21'-9"	19'-5"
	NI-60	24'-10"	23'-1"	22'-0"	20'-10"	25'-6"	23'-8"	22'-4"	20'-10"
	NI-70	26'-1"	24'-3"	23'-2"	21'-10"	26'-8"	24'-11"	23'-9"	22'-4"
	NI-80	26'-6"	24'-7"	23'-5"	22'-2"	27'-1"	25'-3"	24'-1"	22'-9"
16"	NI-90x	27'-3"	25'-4"	24'-1"	22'-9"	27'-9"	25'-11"	24'-8"	23'-4"
	NI-60	27'-3"	25'-5"	24'-2"	22'-10"	28'-0"	26'-2"	24'-9"	23'-1"
	NI-70	28'-8"	26'-8"	25'-4"	23'-11"	29'-3"	27'-4"	26'-1"	24'-8"
	NI-80	29'-1"	27'-0"	25'-9"	24'-4"	29'-8"	27'-9"	26'-5"	25'-0"
	NI-90x	29'-11"	27'-10"	26'-6"	25'-0"	30'-6"	28'-5"	27'-2"	25'-8"

- Maximum clear span applicable to simple-span residential floor construction with a design live load of 40 psf and dead load of 15 psf. The ultimate limit states are based on the factored loads of 1.50L + 1.25D. The serviceability limit states include the consideration for floor vibration, a live load deflection limit of L/480 and a total load deflection limit of L/240.
- Spans are based on a composite floor with glued-nailed oriented strand board (OSB) sheathing with a minimum thickness of 3/4 inch for a joist spacing of 24 inches or less. The composite floor may include 1/2 inch gypsum ceiling and/or one row of blocking at mid-span with strapping. Strapping shall be minimum 1x4 inch strap applied to underside of joists at blocking line or 1/2 inch gypsum ceiling attached to joists.
- Minimum bearing length shall be 1-3/4 inches for the end bearings.
- Bearing stiffeners are not required when I-joists are used with the spans and spacings given in this table, except as required for hangers.
- This span chart is based on uniform loads. For applications with other than uniformly distributed loads, an engineering analysis may be required based on the use of the design properties. Tables are based on Limit States Design per CSA O86-09, NBC 2010, and OBC 2012.
- Joists shall be laterally supported at supports and continuously along the compression edge. Refer to technical documentation for installation guidelines and construction details. Nordic I-joists are listed in CCMC evaluation report 13032-R and APA Product Report PR-L274C.





Maximum Floor Spans

Live Load = 40 psf, Dead Load = 30 psf
Simple Spans, L/480 Deflection Limit
5/8" OSB G&N Sheathing

Depth	Series	Bare				1/2" Gypsum Ceiling			
		On Centre Spacing				On Centre Spacing			
		12"	16"	19.2"	24"	12"	16"	19.2"	24"
9-1/2"	NI-20	15'-1"	14'-1"	13'-3"	N/A	15'-7"	14'-1"	13'-3"	N/A
	NI-40x	16'-1"	15'-2"	14'-8"	N/A	16'-7"	15'-7"	15'-1"	N/A
	NI-60	16'-3"	15'-4"	14'-10"	N/A	16'-8"	15'-9"	15'-3"	N/A
	NI-70	17'-1"	16'-1"	15'-6"	N/A	17'-5"	16'-5"	15'-10"	N/A
	NI-80	17'-3"	16'-3"	15'-8"	N/A	17'-8"	16'-7"	16'-0"	N/A
11-7/8"	NI-20	16'-11"	16'-0"	15'-5"	N/A	17'-6"	16'-6"	16'-0"	N/A
	NI-40x	18'-1"	17'-0"	16'-5"	N/A	18'-9"	17'-6"	16'-11"	N/A
	NI-60	18'-4"	17'-3"	16'-7"	N/A	19'-0"	17'-8"	17'-1"	N/A
	NI-70	19'-6"	18'-0"	17'-4"	N/A	20'-1"	18'-7"	17'-9"	N/A
	NI-80	19'-9"	18'-3"	17'-6"	N/A	20'-4"	18'-10"	17'-11"	N/A
	NI-90x	20'-4"	18'-9"	17'-11"	N/A	20'-10"	19'-3"	18'-5"	N/A
14"	NI-40x	20'-1"	18'-7"	17'-10"	N/A	20'-10"	19'-4"	18'-6"	N/A
	NI-60	20'-5"	18'-11"	18'-1"	N/A	21'-2"	19'-7"	18'-9"	N/A
	NI-70	21'-7"	20'-0"	19'-1"	N/A	22'-3"	20'-7"	19'-8"	N/A
	NI-80	21'-11"	20'-3"	19'-4"	N/A	22'-7"	20'-11"	20'-0"	N/A
	NI-90x	22'-7"	20'-11"	19'-11"	N/A	23'-3"	21'-6"	20'-6"	N/A
16"	NI-60	22'-3"	20'-8"	19'-9"	N/A	23'-1"	21'-5"	20'-6"	N/A
	NI-70	23'-6"	21'-9"	20'-9"	N/A	24'-3"	22'-5"	21'-5"	N/A
	NI-80	23'-11"	22'-1"	21'-1"	N/A	24'-8"	22'-10"	21'-9"	N/A
	NI-90x	24'-8"	22'-9"	21'-9"	N/A	25'-4"	23'-5"	22'-4"	N/A

Depth	Series	Mid-Span Blocking				Mid-Span Blocking and 1/2" Gypsum Ceiling			
		On Centre Spacing				On Centre Spacing			
		12"	16"	19.2"	24"	12"	16"	19.2"	24"
9-1/2"	NI-20	15'-7"	14'-1"	13'-3"	N/A	15'-7"	14'-1"	13'-3"	N/A
	NI-40x	17'-9"	16'-1"	15'-1"	N/A	17'-9"	16'-1"	15'-1"	N/A
	NI-60	18'-1"	16'-4"	15'-4"	N/A	18'-1"	16'-4"	15'-4"	N/A
	NI-70	19'-2"	17'-10"	16'-9"	N/A	19'-7"	17'-10"	16'-9"	N/A
	NI-80	19'-5"	18'-0"	17'-1"	N/A	19'-10"	18'-3"	17'-1"	N/A
11-7/8"	NI-20	18'-9"	17'-0"	16'-0"	N/A	18'-9"	17'-0"	16'-0"	N/A
	NI-40x	21'-0"	19'-3"	17'-9"	N/A	21'-3"	19'-3"	17'-9"	N/A
	NI-60	21'-4"	19'-8"	18'-5"	N/A	21'-8"	19'-8"	18'-5"	N/A
	NI-70	22'-6"	20'-10"	19'-11"	N/A	23'-0"	21'-4"	20'-0"	N/A
	NI-80	22'-9"	21'-1"	20'-1"	N/A	23'-3"	21'-7"	20'-5"	N/A
	NI-90x	23'-4"	21'-8"	20'-8"	N/A	23'-10"	22'-2"	21'-2"	N/A
14"	NI-40x	23'-7"	21'-5"	19'-6"	N/A	24'-1"	21'-5"	19'-6"	N/A
	NI-60	24'-0"	22'-3"	21'-0"	N/A	24'-8"	22'-5"	21'-0"	N/A
	NI-70	25'-3"	23'-4"	22'-3"	N/A	25'-10"	24'-0"	22'-9"	N/A
	NI-80	25'-7"	23'-8"	22'-7"	N/A	26'-2"	24'-4"	23'-2"	N/A
	NI-90x	26'-4"	24'-4"	23'-3"	N/A	26'-10"	24'-11"	23'-9"	N/A
16"	NI-60	26'-5"	24'-6"	23'-4"	N/A	27'-2"	24'-10"	23'-4"	N/A
	NI-70	27'-9"	25'-8"	24'-6"	N/A	28'-5"	26'-5"	25'-2"	N/A
	NI-80	28'-2"	26'-1"	24'-10"	N/A	28'-10"	26'-9"	25'-6"	N/A
	NI-90x	29'-0"	26'-10"	25'-7"	N/A	29'-7"	27'-5"	26'-2"	N/A

- Maximum clear span applicable to simple-span residential floor construction with a design live load of 40 psf and dead load of 30 psf. The ultimate limit states are based on the factored loads of 1.50L + 1.25D. The serviceability limit states include the consideration for floor vibration, a live load deflection limit of L/480 and a total load deflection limit of L/240.
- Spans are based on a composite floor with glued-nailed oriented strand board (OSB) sheathing with a minimum thickness of 5/8 inch for a joist spacing of 19.2 inches or less. The composite floor may include 1/2 inch gypsum ceiling and/or one row of blocking at mid-span with strapping. Strapping shall be minimum 1x4 inch strap applied to underside of joists at blocking line or 1/2 inch gypsum ceiling attached to joists.
- Minimum bearing length shall be 1-3/4 inches for the end bearings.
- Bearing stiffeners are not required when I-joists are used with the spans and spacings given in this table, except as required for hangers.
- This span chart is based on uniform loads. For applications with other than uniformly distributed loads, an engineering analysis may be required based on the use of the design properties. Tables are based on Limit States Design per CSA O86-09, NBC 2010, and OBC 2012.
- Joists shall be laterally supported at supports and continuously along the compression edge. Refer to technical documentation for installation guidelines and construction details. Nordic I-joists are listed in CCMC evaluation report 13032-R and APA Product Report PR-L274C.



Maximum Floor Spans

Live Load = 40 psf, Dead Load = 30 psf
 Simple Spans, L/480 Deflection Limit
 3/4" OSB G&N Sheathing

Depth	Series	Bare				1/2" Gypsum Ceiling			
		On Centre Spacing				On Centre Spacing			
		12"	16"	19.2"	24"	12"	16"	19.2"	24"
9-1/2"	NI-20	15'-7"	14'-2"	13'-4"	12'-4"	15'-7"	14'-2"	13'-4"	12'-4"
	NI-40x	17'-0"	16'-0"	15'-1"	13'-11"	17'-5"	16'-1"	15'-1"	13'-11"
	NI-60	17'-2"	16'-2"	15'-5"	14'-3"	17'-6"	16'-5"	15'-5"	14'-3"
	NI-70	18'-0"	16'-11"	16'-3"	15'-6"	18'-5"	17'-3"	16'-7"	15'-6"
	NI-80	18'-3"	17'-1"	16'-5"	15'-9"	18'-8"	17'-5"	16'-9"	15'-10"
11-7/8"	NI-20	17'-10"	16'-10"	16'-0"	14'-10"	18'-6"	17'-1"	16'-0"	14'-10"
	NI-40x	19'-4"	17'-11"	17'-3"	15'-10"	19'-11"	18'-6"	17'-9"	15'-10"
	NI-60	19'-7"	18'-2"	17'-5"	16'-9"	20'-2"	18'-9"	17'-11"	17'-1"
	NI-70	20'-9"	19'-2"	18'-3"	17'-5"	21'-4"	19'-9"	18'-10"	17'-10"
	NI-80	21'-1"	19'-5"	18'-6"	17'-7"	21'-7"	20'-0"	19'-0"	18'-0"
14"	NI-90x	21'-8"	20'-0"	19'-1"	18'-0"	22'-2"	20'-6"	19'-6"	18'-6"
	NI-40x	21'-5"	19'-10"	18'-11"	17'-5"	22'-1"	20'-6"	19'-6"	17'-5"
	NI-60	21'-10"	20'-2"	19'-3"	18'-2"	22'-5"	20'-10"	19'-11"	18'-10"
	NI-70	23'-0"	21'-3"	20'-3"	19'-2"	23'-8"	21'-11"	20'-10"	19'-9"
	NI-80	23'-5"	21'-7"	20'-7"	19'-5"	24'-0"	22'-3"	21'-2"	20'-0"
16"	NI-90x	24'-1"	22'-3"	21'-2"	20'-0"	24'-8"	22'-10"	21'-9"	20'-7"
	NI-60	23'-9"	22'-0"	20'-11"	19'-10"	24'-6"	22'-9"	21'-8"	20'-6"
	NI-70	25'-1"	23'-2"	22'-0"	20'-10"	25'-9"	23'-10"	22'-9"	21'-6"
	NI-80	25'-6"	23'-6"	22'-4"	21'-2"	26'-1"	24'-2"	23'-1"	21'-10"
	NI-90x	26'-4"	24'-3"	23'-1"	21'-10"	26'-11"	24'-11"	23'-8"	22'-5"




Depth	Series	Mid-Span Blocking				Mid-Span Blocking and 1/2" Gypsum Ceiling			
		On Centre Spacing				On Centre Spacing			
		12"	16"	19.2"	24"	12"	16"	19.2"	24"
9-1/2"	NI-20	15'-7"	14'-2"	13'-4"	12'-4"	15'-7"	14'-2"	13'-4"	12'-4"
	NI-40x	17'-9"	16'-1"	15'-1"	13'-11"	17'-9"	16'-1"	15'-1"	13'-11"
	NI-60	18'-1"	16'-5"	15'-5"	14'-3"	18'-1"	16'-5"	15'-5"	14'-3"
	NI-70	19'-10"	17'-11"	16'-9"	15'-6"	19'-10"	17'-11"	16'-9"	15'-6"
	NI-80	20'-2"	18'-3"	17'-1"	15'-10"	20'-2"	18'-3"	17'-1"	15'-10"
11-7/8"	NI-20	18'-10"	17'-1"	16'-0"	14'-10"	18'-10"	17'-1"	16'-0"	14'-10"
	NI-40x	21'-3"	19'-3"	17'-9"	15'-10"	21'-3"	19'-3"	17'-9"	15'-10"
	NI-60	21'-9"	19'-8"	18'-5"	17'-1"	21'-9"	19'-8"	18'-5"	17'-1"
	NI-70	23'-4"	21'-5"	20'-1"	18'-6"	23'-8"	21'-5"	20'-1"	18'-6"
	NI-80	23'-7"	21'-10"	20'-5"	18'-11"	24'-1"	21'-10"	20'-5"	18'-11"
14"	NI-90x	24'-3"	22'-6"	21'-3"	19'-7"	24'-8"	22'-7"	21'-3"	19'-7"
	NI-40x	24'-2"	21'-5"	19'-6"	17'-5"	24'-2"	21'-5"	19'-6"	17'-5"
	NI-60	24'-9"	22'-5"	21'-0"	19'-6"	24'-9"	22'-5"	21'-0"	19'-6"
	NI-70	26'-1"	24'-3"	22'-9"	21'-0"	26'-8"	24'-3"	22'-9"	21'-0"
	NI-80	26'-6"	24'-7"	23'-3"	21'-6"	27'-1"	24'-10"	23'-3"	21'-6"
16"	NI-90x	27'-3"	25'-4"	24'-1"	22'-4"	27'-9"	25'-10"	24'-3"	22'-4"
	NI-60	27'-3"	24'-11"	23'-5"	21'-7"	27'-6"	24'-11"	23'-5"	21'-7"
	NI-70	28'-8"	26'-8"	25'-3"	23'-4"	29'-3"	26'-11"	25'-3"	23'-4"
	NI-80	29'-1"	27'-0"	25'-9"	23'-10"	29'-8"	27'-6"	25'-10"	23'-10"
	NI-90x	29'-11"	27'-10"	26'-6"	24'-10"	30'-6"	28'-5"	26'-11"	24'-10"

- Maximum clear span applicable to simple-span residential floor construction with a design live load of 40 psf and dead load of 30 psf. The ultimate limit states are based on the factored loads of 1.50L + 1.25D. The serviceability limit states include the consideration for floor vibration, a live load deflection limit of L/480 and a total load deflection limit of L/240.
- Spans are based on a composite floor with glued-nailed oriented strand board (OSB) sheathing with a minimum thickness of 3/4 inch for a joist spacing of 24 inches or less. The composite floor may include 1/2 inch gypsum ceiling and/or one row of blocking at mid-span with strapping. Strapping shall be minimum 1x4 inch strap applied to underside of joists at blocking line or 1/2 inch gypsum ceiling attached to joists.
- Minimum bearing length shall be 1-3/4 inches for the end bearings.
- Bearing stiffeners are not required when I-joists are used with the spans and spacings given in this table, except as required for hangers.
- This span chart is based on uniform loads. For applications with other than uniformly distributed loads, an engineering analysis may be required based on the use of the design properties. Tables are based on Limit States Design per CSA O86-09, NBC 2010, and OBC 2012.
- Joists shall be laterally supported at supports and continuously along the compression edge. Refer to technical documentation for installation guidelines and construction details. Nordic I-joists are listed in CCMC evaluation report 13032-R and APA Product Report PR-L274C.



INSTALLATION GUIDE

FOR RESIDENTIAL FLOORS



Distributed by:



N-C301 / November 2014

SAFETY AND CONSTRUCTION PRECAUTIONS



Do not walk on I-joists until fully fastened and braced, or serious injuries can result.

WARNING

I-joists are not stable until completely installed, and will not carry any load until fully braced and sheathed.

Avoid Accidents by Following these Important Guidelines:

1. Brace and nail each I-joist as it is installed, using hangers, blocking panels, rim board, and/or cross-bridging at joist ends. When I-joists are applied continuous over interior supports and a load-bearing wall is planned at that location, blocking will be required at the interior support.
2. When the building is completed, the floor sheathing will provide lateral support for the top flanges of the I-joists. Until this sheathing is applied, temporary bracing, often called struts, or temporary sheathing must be applied to prevent I-joist rollover or buckling.
 - Temporary bracing or struts must be 1x4 inch minimum, at least 8 feet long and spaced no more than 8 feet on centre, and must be secured with a minimum of two 2-1/2" nails fastened to the top surface of each I-joist. Nail the bracing to a lateral restraint at the end of each bay. Lap ends of adjoining bracing over at least two I-joists.
 - Or, sheathing (temporary or permanent) can be nailed to the top flange of the first 4 feet of I-joists at the end of the bay.
3. For cantilevered I-joists, brace top and bottom flanges, and brace ends with closure panels, rim board, or cross-bridging.
4. Install and fully nail permanent sheathing to each I-joist before placing loads on the floor system. Then, stack building materials over beams or walls only.
5. Never install a damaged I-joist.




Never stack building materials over unsheathed I-joists. Once sheathed, do not over-stress I-joist with concentrated loads from building materials.

Improper storage or installation, failure to follow applicable building codes, failure to follow span ratings for Nordic I-joists, failure to follow allowable hole sizes and locations, or failure to use web stiffeners when required can result in serious accidents. Follow these installation guidelines carefully.

STORAGE AND HANDLING GUIDELINES

1. Bundle wrap can be slippery when wet. Avoid walking on wrapped bundles.
2. Store, stack, and handle I-joists vertically and level only.
3. Always stack and handle I-joists in the upright position only.
4. Do not store I-joists in direct contact with the ground and/or flatwise.
5. Protect I-joists from weather, and use spacers to separate bundles.
6. Bundled units should be kept intact until time of installation.
7. When handling I-joists with a crane on the job site, take a few simple precautions to prevent damage to the I-joists and injury to your work crew.
 - Pick I-joists in bundles as shipped by the supplier.
 - Orient the bundles so that the webs of the I-joists are vertical.
 - Pick the bundles at the 5th points, using a spreader bar if necessary.
8. Do not handle I-joists in a horizontal orientation.
9. NEVER USE OR TRY TO REPAIR A DAMAGED I-JOIST.



MAXIMUM FLOOR SPANS

1. Maximum clear spans applicable to simple-span or multiple-span residential floor construction with a design live load of 40 psf and dead load of 15 psf. The ultimate limit states are based on the factored loads of 1.50L + 1.25D. The serviceability limit states include the consideration for floor vibration and a live load deflection limit of L/480. For multiple-span applications, the end spans shall be 40% or more of the adjacent span.
2. Spans are based on a composite floor with glued-nailed oriented strand board (OSB) sheathing with a minimum thickness of 5/8 inch for a joist spacing of 19.2 inches or less, or 3/4 inch for joist spacing of 24 inches. Adhesive shall meet the requirements given in CGS-71.26 Standard. No concrete topping or bridging element was assumed. Increased spans may be achieved with the use of gypsum and/or a row of blocking at mid-span.
3. Minimum bearing length shall be 1-3/4 inches for the end bearings, and 3-1/2 inches for the intermediate bearings.
4. Bearing stiffeners are not required when I-joists are used with the spans and spacings given in this table, except as required for hangers.
5. This span chart is based on uniform loads. For applications with other than uniform loads, an engineering analysis may be required based on the use of the design properties.
6. Tables are based on Limit States Design per CAN/CSA O86-09 Standard, and NBC 2010.
7. SI units conversion: 1 inch = 25.4 mm
1 foot = 0.305 m


MAXIMUM FLOOR SPANS FOR NORDIC I-JOISTS SIMPLE AND MULTIPLE SPANS

Joist Depth	Joist Series	Simple spans				Multiple spans			
		On centre spacing	On centre spacing	On centre spacing	On centre spacing	On centre spacing	On centre spacing	On centre spacing	On centre spacing
		12"	16"	19.2"	24"	12"	16"	19.2"	24"
12"	NL-20	13.2	14.8	16.4	18.0	13.2	14.8	16.4	18.0
16"	NL-40	13.2	14.8	16.4	18.0	13.2	14.8	16.4	18.0
19.2"	NL-60	13.2	14.8	16.4	18.0	13.2	14.8	16.4	18.0
24"	NL-80	13.2	14.8	16.4	18.0	13.2	14.8	16.4	18.0
24"	NL-90x	13.2	14.8	16.4	18.0	13.2	14.8	16.4	18.0

CCMC EVALUATION REPORT 13032-R

I-JOIST HANGERS

1. Hangers shown illustrate the three most commonly used metal hangers to support I-joists.
2. All nailing must meet the hanger manufacturer's recommendations.
3. Hangers should be selected based on the joist depth, flange width and load capacity based on the maximum spans.
4. Web stiffeners are required when the sides of the hangers do not laterally brace the top flange of the I-joist.




WEB STIFFENERS

RECOMMENDATIONS:

- A bearing stiffener is required in all engineered applications with factored reactions greater than shown in the I-joist properties table found of the I-joist Construction Guide (C101). The gap between the stiffener and the flange is at the top.
- A bearing stiffener is required when the I-joist is supported in a hanger and the sides of the hanger do not extend up to, and support, the top flange. The gap between the stiffener and flange is at the top.
- A load stiffener is required at locations where a factored concentrated load greater than 2,370 lbs is applied to the top flange between supports, or in the case of a cantilever, anywhere between the cantilever tip and the support. These values are for standard term load duration, and may be adjusted for other load durations as permitted by the code. The gap between the stiffener and the flange is at the bottom.

SI units conversion: 1 inch = 25.4 mm

FIGURE 2
WEB STIFFENER INSTALLATION DETAILS



See table below for web stiffener size requirements

STIFFENER SIZE REQUIREMENTS

Flange Width	Web Stiffener Size Each Side of Web
2-1/2"	1" x 2-5/16" minimum width
3-1/2"	1-1/2" x 2-5/16" minimum width

NORDIC I-JOIST SERIES

S-PF No.2	1950F MSR	2100F MSR	1950F MSR	2100F MSR	2400F MSR	NFG Lumber
33 pieces per unit	33 pieces per unit	33 pieces per unit	23 pieces per unit	23 pieces per unit	23 pieces per unit	23 pieces per unit
NL-20	NL-40	NL-60	NL-70	NL-80	NL-90	NL-90x
1-1/2"	1-1/2"	1-1/2"	1-1/2"	1-1/2"	1-1/2"	1-1/2"
OSB 3/8"	OSB 3/8"	OSB 3/8"	OSB 3/8"	OSB 3/8"	OSB 3/8"	OSB 3/8"
9-1/2"	9-1/2"	9-1/2"	9-1/2"	9-1/2"	9-1/2"	9-1/2"
11-7/8"	11-7/8"	11-7/8"	11-7/8"	11-7/8"	11-7/8"	11-7/8"
14"	14"	14"	14"	14"	14"	14"
16"	16"	16"	16"	16"	16"	16"

Chantiers Chibougamau Ltd. harvests its own trees, which enables Nordic products to adhere to strict quality control procedures throughout the manufacturing process. Every phase of the operation, from the forest to the finished product, reflects our commitment to quality.

Nordic Engineered Wood I-joists use only finger-jointed back splice lumber in their flanges, ensuring consistent quality, superior strength, and longer span carrying capacity.

2015-04-16

INSTALLING NORDIC I-JOISTS

1. Before laying out floor system components, verify that I-joist flange widths match hanger widths. If not, consult your supplier.
2. Except for cutting to length, I-joist flanges should **never** be cut, drilled, or notched.
3. Install I-joists so that top and bottom flanges are within 1/2 inch of true vertical alignment.
4. I-joists must be anchored securely to supports before floor sheathing is attached, and supports for multiple spans must be level.
5. Minimum bearing lengths: 1-3/4 inches for end bearings and 3-1/2 inches for intermediate bearings.
6. When using hangers, seat I-joists firmly in hanger bottoms to minimize settlement.
7. Leave a 1/16-inch gap between the I-joist end and a header.
8. Concentrated loads greater than those that can normally be expected in residential construction should only be applied to the top surface of the top flange. Normal concentrated loads include track lighting fixtures, audio equipment and security cameras. Never suspend unusual or heavy loads from the I-joist's bottom flange. Whenever possible, suspend all concentrated loads from the top of the I-joist. Or, attach the load to blocking that has been securely fastened to the I-joist webs.
9. Never install I-joists where they will be permanently exposed to weather, or where they will remain in direct contact with concrete or masonry.
10. Restrain ends of floor joists to prevent rollover. Use rim board, rim joists or I-joist blocking panels.
11. For I-joists installed over and beneath bearing walls, use full depth blocking panels, rim board, or squash blocks (cripple members) to transfer gravity loads through the floor system to the wall or foundation below.
12. Due to shrinkage, common framing lumber set on edge **may never** be used as blocking or rim boards. I-joist blocking panels or other engineered wood products – such as rim board – must be cut to fit between the I-joists, and an I-joist-compatible depth selected.
13. Provide permanent lateral support of the bottom flange of all I-joists at interior supports of multiple-span joists. Similarly, support the bottom flange of all cantilevered I-joists at the end support next to the cantilever extension. In the completed structure, the gypsum wallboard ceiling provides this lateral support. Until the final finished ceiling is applied, temporary bracing or struts must be used.
14. If square-edge panels are used, edges must be supported between I-joists with 2x4 blocking. Glue panels to blocking to minimize squeaks. Blocking is not required under structural finish flooring, such as wood strip flooring, or if a separate underlayment layer is installed.
15. Nail spacing: Space nails installed to the flange's top face in accordance with the applicable building code requirements or approved building plans.






FIGURE 1
TYPICAL NORDIC I-JOIST FLOOR FRAMING AND CONSTRUCTION DETAILS

Some framing requirements such as erection bracing and blocking panels have been omitted for clarity.




All nails shown in the above details are assumed to be common wire nails unless otherwise noted. 3" (0.122" dia.) common spiral nails may be substituted for 2-1/2" (0.128" dia.) common wire nails. Framing lumber assumed to be Spruce-Pine-Fir No. 2 or better. Individual components not shown to scale for clarity.





Blocking Panel or Rim Joist	Maximum Factored Uniform Vertical Load* (plf)
N1 Joists	3,300

*The uniform vertical load is limited to a joist depth of 16 inches or less and is based on standard term load duration. It shall not be used in the design of a bending member, such as joist, header, or rafter. For concentrated vertical load transfer, see detail 1d.




Blocking Panel or Rim Joist	Maximum Factored Uniform Vertical Load* (plf)
1-1/8" Rim Board Plus	8,090

*The uniform vertical load is limited to a rim board depth of 16 inches or less and is based on standard term load duration. It shall not be used in the design of a bending member, such as joist, header, or rafter. For concentrated vertical load transfer, see detail 1d.




Pair of Squash Blocks	Maximum Factored Vertical per Pair of Squash Blocks (lbs)
2x Lumber	3-1/2" wide: 5,500 5-1/2" wide: 8,500
1-1/8" Rim Board Plus	4,300


Provide lateral bracing per detail 1a, 1b, or 1c




Transfer load from above to bearing below. Install squish blocks per detail 1d. Match bearing area of blocks below to post above.




Use single I-joist for loads up to 3,300 pif, double I-joists for loads up to 6,600 pif (filler block not required). Attach I-joist to top plate using 2-1/2" nails at 6" o.c.



Load bearing wall above shall align vertically with the bearing below. Other conditions, such as offset bearing walls, are not covered by this detail.




Backer block (use if hanger load exceeds 360 lbs) Before installing a backer block to a double I-joist, drive three additional 3" nails through the webs and filler block where the backer block will fit. Clinch. Install backer tight to top flange. Use twelve 3" nails, clinched when possible. Maximum factored resistance for hanger for this detail = 1,620 lbs.




Top- or face-mount hanger installed per manufacturer's recommendations


For nailing schedules for multiple beams, see the manufacturer's recommendations.



2x plate flush with inside face of wall or beam. 1/8" overhang allowed past inside face of wall or beam. Top-mount hanger installed per manufacturer's recommendations




Multiple I-joist header with full depth filler block shown. Nordic Lam or SCL headers may also be used. Verify double I-joist capacity to support concentrated loads.



Do not bevel-cut joist beyond inside face of wall. Attach I-joist per detail 1b

Flange Width	Material Thickness Required*	Minimum Depth**
2-1/2"	1"	5-1/2"
3-1/2"	1-1/2"	7-1/4"

* Minimum grade for backer block material shall be S-P-F No. 2 or better for solid sawn lumber and wood structural panels conforming to CAN/CSA-O325 or CAN/CSA-Q437 Standard.
** For face-mount hangers use net joist depth minus 3-1/4" for joists with 1-1/2" thick flanges. For 2" thick flanges use net depth minus 4-1/4".




1/8" to 1/4" gap between top flange and filler block


- Notes:
1. Support back of I-joist web during nailing to prevent damage to web/flange connection.
 2. Leave a 1/8 to 1/4-inch gap between top of filler block and bottom of top I-joist flange.
 3. Filler block is required between joists for full length of span.
 4. Nail joists together with two rows of 3" nails at 12 inches o.c. (clinched when possible) on each side of the double I-joist. Total of four nails per foot required. If nails can be clinched, only two nails per foot are required.
 5. The maximum factored load that may be applied to one side of the double joist using this detail is 860 lb/ft. Verify double I-joist capacity.

FILLER BLOCK REQUIREMENTS FOR DOUBLE I-JOIST CONSTRUCTION

Flange Size	Joist Depth	Filler Block Size
2-1/2" x 1-1/2"	9-1/2" x 11-7/8" x 14"	2-1/8" x 6" x 2-1/8" x 10"
3-1/2" x 1-1/2"	9-1/2" x 11-7/8" x 14"	3" x 6" x 3" x 8" x 3" x 10" x 3" x 12"
3-1/2" x 1-1/2"	11-7/8" x 14" x 16"	3" x 7" x 3" x 9" x 3" x 11"



Optional: Minimum 1x4 inch strip applied to underside of joist at blocking line or 1/2 inch minimum gypsum ceiling attached to underside of joists.




Notes:


- In some local codes, blocking is prescriptively required in the first joist space (or first and second joist space) next to the starter joist. Where required, see local code requirements for spacing of the blocking.
- All nails are common spiral in this detail.

CANTILEVER DETAILS FOR BALCONIES (NO WALL LOAD)

3a I-JOIST CANTILEVER DETAIL FOR BALCONIES (No Wall Load)




3b LUMBER CANTILEVER DETAIL FOR BALCONIES (No Wall Load)




CANTILEVER DETAILS FOR VERTICAL BUILDING OFFSET (CONCENTRATED WALL LOAD)

4a Method 1 — SHEATHING REINFORCEMENT ONE SIDE



Method 2 — SHEATHING REINFORCEMENT TWO SIDES

- Use same installation as Method 1 but reinforce both sides of I-joist with sheathing.
- Use nailing pattern shown for Method 1 with opposite face nailing offset by 3".



Note: Condition softwood plywood sheathing or equivalent (minimum thickness 3/4") required on sides of joist. Depth shall match the full height of the joist. Nail with 2-1/2" nails at 6" o.c., top and bottom flange. Install with face grain horizontal. Attach I-joist to plate at all supports per detail 1b. Verify reinforced I-joist capacity.

4b Alternate Method 2 — DOUBLE I-JOIST





FIGURE 4 (continued)




CANTILEVER REINFORCEMENT METHODS ALLOWED

JOIST DEPTH (in.)	ROOF TRUSS SPAN (ft)				ROOF LOADING (UNFACTORED)			
	LL = 30 psf, DL = 15 psf	LL = 40 psf, DL = 15 psf	LL = 50 psf, DL = 15 psf	LL = 60 psf, DL = 15 psf	LL = 30 psf, DL = 15 psf	LL = 40 psf, DL = 15 psf	LL = 50 psf, DL = 15 psf	LL = 60 psf, DL = 15 psf
12	24	24	24	24	24	24	24	24
16	24	24	24	24	24	24	24	24
19.2	24	24	24	24	24	24	24	24
24	24	24	24	24	24	24	24	24
28	24	24	24	24	24	24	24	24
30	24	24	24	24	24	24	24	24
32	24	24	24	24	24	24	24	24
34	24	24	24	24	24	24	24	24
36	24	24	24	24	24	24	24	24
38	24	24	24	24	24	24	24	24
40	24	24	24	24	24	24	24	24
42	24	24	24	24	24	24	24	24

1. N = No reinforcement required.
2. N1 = N1 reinforced with 3/4" wood structural panel on one side only.
3. N2 = N2 reinforced with 3/4" wood structural panel on both sides, or double I-joist.
4. For larger openings, or multiple 3'-0" width openings spaced less than 6'-0" o.c., additional joists beneath the opening's cripple studs may be required.
5. Table applies to joists 12" to 24" o.c. that meet the floor span requirements for a design live load of 40 psf and dead load of 15 psf, and a live load deflection limit of L/480. Use 12" o.c. requirements for lesser spacing.
6. For conventional roof construction using a ridge beam, the Roof Truss Span column above is equivalent to the distance between the supporting wall and the ridge beam. When the roof is formed using a ridge board, the Roof Truss Span is equivalent to the distance between the supporting walls as if a truss is used.
7. Cantilevered joists supporting girder trusses or roof beams may require additional reinforcing.

RULES FOR CUTTING HOLES AND DUCT CHASE OPENINGS.

- FIGURE 7**
FIELD-CUT HOLE LOCATOR

[illegible]

reduced = $\frac{\text{actual } x D}{\text{actual } x D + \text{actual } x D}$

D	reduced	Distance from the inside face of any support to centre of hole, reduced for less-than-maximum distance shall not be less than 6 inches from the face of the support to edge of the hole.
L	lateral	The actual measured span distance between the inside faces of supports (ft).
SF	Span Adjustment Factor	given in this table.
D		The minimum distance from the inside face of any support to centre of hole from this table

SAF SAF

SAF SAF

Maximum Price: \$0.00

Quantity: 1

Total: \$0.00

Date: 2015-04-16

Joist Depth	Joist Series	Minimum distance from inside face of any support to centre of opening (R _{min})									
		8	10	12	14	16	18	20	22	24	
10	100	100	100	100	100	100	100	100	100		
10	101	100	100	100	100	100	100	100	100		
10	102	100	100	100	100	100	100	100	100		
10	103	100	100	100	100	100	100	100	100		
10	104	100	100	100	100	100	100	100	100		
10	105	100	100	100	100	100	100	100	100		
10	106	100	100	100	100	100	100	100	100		
10	107	100	100	100	100	100	100	100	100		
10	108	100	100	100	100	100	100	100	100		
10	109	100	100	100	100	100	100	100	100		
10	110	100	100	100	100	100	100	100	100		
10	111	100	100	100	100	100	100	100	100		
10	112	100	100	100	100	100	100	100	100		
10	113	100	100	100	100	100	100	100	100		
10	114	100	100	100	100	100	100	100	100		
10	115	100	100	100	100	100	100	100	100		
10	116	100	100	100	100	100	100	100	100		
10	117	100	100	100	100	100	100	100	100		
10	118	100	100	100	100	100	100	100	100		
10	119	100	100	100	100	100	100	100	100		
10	120	100	100	100	100	100	100	100	100		
10	121	100	100	100	100	100	100	100	100		
10	122	100	100	100	100	100	100	100	100		
10	123	100	100	100	100	100	100	100	100		
10	124	100	100	100	100	100	100	100	100		
10	125	100	100	100	100	100	100	100	100		
10	126	100	100	100	100	100	100	100	100		
10	127	100	100	100	100	100	100	100	100		
10	128	100	100	100	100	100	100	100	100		
10	129	100	100	100	100	100	100	100	100		
10	130	100	100	100	100	100	100	100	100		
10	131	100	100	100	100	100	100	100	100		
10	132	100	100	100	100	100	100	100	100		
10	133	100	100	100	100	100	100	100	100		
10	134	100	100	100	100	100	100	100	100		
10	135	100	100	100	100	100	100	100	100		
10	136	100	100	100	100	100	100	100	100		
10	137	100	100	100	100	100	100	100	100		
10	138	100	100	100	100	100	100	100	100		
10	139	100	100	100	100	100	100	100	100		
10	140	100	100	100	100	100	100	100	100		
10	141	100	100	100	100	100	100	100	100		
10	142	100	100	100	100	100	100	100	100		
10	143	100	100	100	100	100	100	100	100		
10	144	100	100	100	100	100	100	100	100		
10	145	100	100	100	100	100	100	100	100		
10	146	100	100	100							

Knockouts are pressured holes provided for the contractor's convenience to install electrical or small plumbing lines. They are 1-1/2 inches in diameter, and are spaced 1/2 inches on center along the length of the I-joist. Where possible, it is preferable to use knockouts instead of field-cut holes.

Never drill, cut or notch the flange, or over-cut the web.

Holes in webs should be cut with a sharp saw.

For rectangular holes, avoid over-culping the corners, as this can cause unnecessary stress concentrations. Slightly rounding the corners is recommended. Startling the rectangular hole by drilling a 1-inch diameter hole in each of the four corners and then making the cuts between the holes is another good method to minimize damage to the I-joist.

Never drill, cut or notch the flange, or over-cut the web.


Holes in webs should be cut with a sharp saw.

BRICK CANTILEVER DETAILS FOR VERTICAL BUILDING OFFSET (CONCENTRATED WALL LOAD)

5a SHEATHING REINFORCEMENT

Provide full depth blocking between joists over support (not shown)

Note: Canadian softwood plywood sheathing or equivalent (minimum thickness 3/4") required on sides of joist. Depth shall match the full height of the joist. Nail with 2-1/2" nails at 6" o.c., top and bottom flange. Install with face grain horizontal. Attach I-joist to plate at all supports per detail 1b. Verify reinforced I-joist capacity.




5b SET-BACK DETAIL

Rim board or wood structural panel closure (3/4" minimum thickness), attach per detail 1b.

Notes:

- Provide full depth blocking between joists over support (not shown for clarity)
- Attach I-joist to plate at all supports per detail 1b.
- 3-1/2" minimum I-joist bearing required.



5c SET-BACK CONNECTION

Vertical solid sawn blocks (2x6 S-P-F No. 2 or better) nailed through joist web and web of girder using 2-1/2" nails.

Alternate for opposite side.

- Notes:**
- Verify girder joist capacity if the back span exceeds the joist spacing.
 - Attach double I-joist per detail 1p, if required.





FIGURE 5 (continued)



For hip roofs with the jack trusses running parallel to the cantilevered floor joists, the I-joist reinforcement requirements for a span of 26 ft. shall be permitted to be used.

BRICK CANTILEVER REINFORCEMENT METHODS ALLOWED

JOIST DEPTH (in.)	ROOF TRUSS SPAN (ft)	ROOF LOADING (UNFACTORED)				ROOF LOADING (UNFACTORED)			
		LL = 30 psf, DL = 15 psf		LL = 40 psf, DL = 15 psf		LL = 50 psf, DL = 15 psf			
		JOIST SPACING (in.)				JOIST SPACING (in.)			
		12	16	19.2	24	12	16	19.2	24
9-1/2"	26	1	X	X	X	2	X	X	X
	28	1	X	X	X	2	X	X	X
	30	1	X	X	X	2	X	X	X
	32	1	X	X	X	2	X	X	X
	34	1	X	X	X	2	X	X	X
11-1/2"	26	1	X	X	X	1	X	X	X
	28	1	X	X	X	1	X	X	X
	30	1	X	X	X	1	X	X	X
	32	1	X	X	X	1	X	X	X
	34	1	X	X	X	1	X	X	X
14"	26	1	X	X	X	1	X	X	X
	28	1	X	X	X	1	X	X	X
	30	1	X	X	X	1	X	X	X
	32	1	X	X	X	1	X	X	X
	34	1	X	X	X	1	X	X	X
16"	26	1	X	X	X	1	X	X	X
	28	1	X	X	X	1	X	X	X
	30	1	X	X	X	1	X	X	X
	32	1	X	X	X	1	X	X	X
	34	1	X	X	X	1	X	X	X

1. N = No reinforcement required.
2. N = NI reinforced with 3/4" wood structural studs on one side only.
3. N = NI reinforced with 3/4" wood structural studs on both sides, or double I-joist.
4. N = Try a deeper joist or closer spacing.
5. Maximum design load shall be: 15 psf roof dead load, 55 psf floor total load, and 80 psf wall load. Wall load is based on 3'-0" maximum width window or door openings.
6. For larger openings, or multiple 3'-0" width openings spaced less than 6'-0" o.c., additional joists beneath the opening's cripple studs may be required.
7. Table applies to joists 12" to 24" o.c. that meet the floor span requirements for a design live load of 40 psf and dead load of 15 psf, and a live load deflection limit of L/480. Use 12" o.c. requirements for lesser spacing.
8. For conventional roof construction using a ridge beam, the Roof Truss Span column above is equivalent to the distance between the supporting wall and the ridge beam.
9. When the roof is framed using a ridge board, the Roof Truss Span is equivalent to the distance between the supporting walls as if a truss is used.
10. Cantilevered joists supporting girder trusses or roof beams may require additional reinforcing.

INSTALLING THE GLUED FLOOR SYSTEM

1. Wipe any mud, dirt, water, or ice from I-joist flanges before gluing.
2. Snap a chalk line across the I-joists four feet in from the wall for panel edge alignment and as a boundary for spreading glue.
3. Spread only enough glue to lay one or two panels at a time, or follow specific recommendations from the glue manufacturer.
4. Lay the first panel with tongue side to the wall, and nail in place. This protects the tongue of the next panel from damage when topped into the wall with a block and sledgehammer.
5. Apply a continuous line of glue (about 1/4-inch diameter) to the top flange of a single I-joist. Apply glue in a winding pattern on wide areas, such as with double I-joists.
6. Apply two lines of glue on I-joists where panel ends butt to assure proper gluing of each end.
7. After the first row of panels is in place, spread glue in the groove of one or two panels at a time before laying the next row. Glue line may be continuous or spaced, but avoid squeeze-out by applying a thinner line (1/8 inch) than used on I-joist flanges.
8. Top the second row of panels into place, using a block to protect groove edges.
9. Stagger end joints in each succeeding row of panels. A 1/8-inch space between all end joints and 1/8-inch at all edges, including T&G edges, is recommended. (Use a spacer tool or an 2-1/2" common nail to assure accurate and consistent spacing.)
10. **Complete all nailing of each panel before glue sets.** Check the manufacturer's recommendations for cure time. (Warm weather accelerates glue setting.) Use 2" ring- or screw-shank nails for panels 3/4-inch thick or less, and 2-1/2" ring- or screw-shank nails for thicker panels. Space nails per the table below. Closer nail spacing may be required by some codes, or for diaphragm construction. The finished deck can be walked on right away and will carry construction loads without damage to the glue bond.

FASTENERS FOR SHEATHING AND SUBFLOORING(1)

Maximum Joist Spacing (in.)	Minimum Panel Thickness (in.)	Nail Size and Type			Maximum Spacing of Fasteners	
		Common Wire or Spiral Nails	Ring Thread Nails or Screws	Staples	Edges	Interm. Supports
16	7/8	2"	1-3/4"	2"	6"	12"
20	5/8	2"	1-3/4"	2"	6"	12"
24	3/4	2"	1-3/4"	2"	6"	12"

1. Fasteners of sheathing and subflooring shall conform to the above table.
2. Staples shall not be less than 1/16-inch in diameter or thickness, with not less than a 3/8-inch crown driven with the crown parallel to framing.
3. Flooring screws shall not be less than 1/8-inch in diameter.
4. Special conditions may impose heavy traffic and concentrated loads that require construction in excess of the minimums shown.
5. Use only adhesives conforming to CAN/CGSB-71.26 Standard. Adhesives for Field-Gluing Plywood to Lumber Framing for Floor System, applied in accordance with the manufacturer's recommendations. If OSB panels with sealed surfaces and edges are to be used, use only solvent-based glues; check with panel manufacturer.

Ref.: NRC-CNRC, National Building Code of Canada 2010, Table 9.23.3.5.

IMPORTANT NOTE:

Floor sheathing must be field glued to the I-joist flanges in order to achieve the maximum spans shown in this document. If sheathing is nailed only, I-joist spans must be verified with your local distributor.


RIM BOARD INSTALLATION DETAILS

8a ATTACHMENT DETAILS WHERE RIM BOARDS ABOUT

Rim board Joint Between Floor Joists


2-1/2" nails at 6" o.c. (typical)

(1) 2-1/2" nail top and bottom (typical)




Rim board Joint at Corner


1-1/2" h



8b TOE-NAIL CONNECTION AT RIM BOARD




8c 2X LEDGER TO RIM BOARD ATTACHMENT DETAIL



PRODUCT WARRANTY

Customer Obligations guarantee that, in accordance with our specifications, Nords products are free from manufacturing defects in material and construction.

Furthermore, Customer Obligations guarantee that our products when utilized in accordance with our handling and installation instructions will meet or exceed our specifications for the lifetime of the structure.




MICRO CITY ENGINEERING SERVICES INC.

TEL: (519) 287 - 2242

R.R. #1, P.O. BOX 61, GLENCOE, ONTARIO, N0L 1M0

LVL HEADER AND CONVENTIONAL LUMBER NAILING DETAILS		
DETAIL NUMBER	NUMBER OF ROWS	SPACING (INCHES o/c) "d"
A	2	12
B	2	8
C	2	6
D	2	4
1A	3	12
1B	3	8
1C	3	6
1D	3	4
2A	4	12
2B	4	8
2C	4	6
2D	4	4
3A	5	12
3B	5	8
3C	5	6
3D	5	4
4A	6	12
4B	6	8
4C	6	6
4D	6	4



NOTES:

- (1) MINIMUM LUMBER EDGE DISTANCE "a" = 1"
- (2) MINIMUM LUMBER END DISTANCE "b" = 2"
- (3) MINIMUM NAIL ROW SPACING "c" = 2"
- (4) STAGGER NAILS "d/2" BETWEEN PLYS FOR MULTI-PLY MEMBERS (3 PLY OR MORE)
- (5) ALL NAILS ARE 3-1/2" ARDOX SPIRAL NAILS
- (6) DO NOT USE AIR-DRIVEN NAILS



DWG NO TAMN1001.14

STRUCTURAL

COMPONENT ONLY

TO BE USED ONLY
WITH BEAM CALCS
BEARING THE
STAMP BELOW

PROVIDE NAILING
DETAIL # X SEE
DWG #TAMN1001-14