


10/12 roof pitch unless noted



ASPHALT SHINGLES
FINISHED OVERHANG: 12"
2x6 EXTERIOR WALLS
2x6 FASCIA BOARD
HEEL: R.T.M.C.

All conventional framing to conform with Part 9 of O.B.C. 2012 (2019 amendment).
Roof rafters that cross over or meet trusses to be min. 2x4 SPF #2 @ 24" o/c with a vertical post to the truss at each cross point. Vertical posts longer than 6' to have lateral bracing so that the distance between the post end points and lateral bracing does not exceed 6'.

DESIGN CONFORMS WITH OBC 2012 (2019 amendment) OCCUPANCY:
RESIDENTIAL | PART: 9
Ss = 31.35 psf | Sr = 8.4 psf

DESIGN LOADS:

TCSL = 25.6 psf
TCDL = 6.0 psf
BCLL = 0.0 psf
BCDL = 7.4 psf

CITY OF HAWAII
BUREAU OF PERMITS
Permit No. 20-187707

HARDWARE:

LUS24 - (O)
LJS26DS - (V)
LUS26-2-(VV)

Dec 16, 2020

BEAMS:

B1= B2 = B3 =
2 - 2x10 SPF #2

DENOTES:
CONVENTIONAL
FRAMING

M13125



Job Track: 51225
Plan Log: 202401
Layout ID: 408150

Builder / Location:
GREEN PARK HOMES / WATERDOWN


Project: RUSSELL GARDENS PH.3

Date: 2020-04-27 Sales: Mario DiCaro Designer: JG


Model / Elevation:
MOUNTAINASH 4/1-std or opt.

THESE DRAWINGS CONSTITUTE THE PROPERTY OF TAMARACK ROOF TRUSSES INC., SHALL NOT BE REPRODUCED, PUBLISHED, OR REDISTRIBUTED IN ANY MANNER OR UTILIZED FOR ANY PURPOSE OTHER THAN THE MANUFACTURE OF TRUSSES BY TAMARACK ROOF TRUSSES INC AND WILL BE RETRACTED BY TAMARACK ROOF TRUSSES INC IF UTILIZED FOR ANY OTHER PURPOSE.

Mike ver B.3.1.215



10/12 roof pitch unless noted



ASPHALT SHINGLES
FINISHED OVERHANG: 12"
2x6 EXTERIOR WALLS
2x6 FASCIA BOARD
HEEL: R.T.M.C.

All conventional framing to conform with Part 9 of O.B.C. 2012 (2019 amendment). Roof rafters that cross over or meet trusses to be min. 2x4 SPF #2 @ 24" o/c with a vertical post to the truss at each cross point. Vertical posts longer than 6' to have lateral bracing so that the distance between the post end points and lateral bracing does not exceed 6'.

DESIGN CONFORMS WITH OBC 2012 (2019 amendment) OCCUPANCY: RESIDENTIAL | PART: 9
Ss = 31.35 psf | Sr = 8.4 psf

DESIGN LOADS:


TCSL = 25.6 psf
TCDL = 6.0 psf
BCLL = 0.0 psf
BCDL = 7.4 psf

HARDWARE:

LUS24 - (O)
LJS26DS - (V)
LUS28-2(VV)

BEAMS:

B20 = 2 - 2x10 SPF #2

 DENOTES:
CONVENTIONAL
FRAMING

M13125




Job Track: 51225
Plan Log: 202401
Layout ID: 408151

Builder / Location: GREEN PARK HOMES / WATERDOWN
Project: RUSSELL GARDENS PH.3
Date: 2020-04-27 Sales: Mario DiCano Designer: JG

Model / Elevation: MOUNTAINASH 4/2-std or opt.

THESE DRAWINGS CONSTITUTE THE PROPERTY OF TAMARACK ROOF TRUSSES INC., SHALL NOT BE REPRODUCED, PUBLISHED, OR REDISTRIBUTED IN ANY MANNER OR UTILIZED FOR ANY PURPOSE OTHER THAN THE MANUFACTURE OF TRUSSES BY TAMARACK ROOF TRUSSES INC AND WILL BE RETRACTED BY TAMARACK ROOF TRUSSES INC IF UTILIZED FOR ANY OTHER PURPOSE.

6/12 roof pitch unless noted



ASPHALT SHINGLES
FINISHED OVERHANG: 12"
2x6 EXTERIOR WALLS
2x6 FASCIA BOARD
HEEL: R.T.M.C.


All conventional framing to conform with Part 9 of O.B.C. 2012 (2019 amendment).
Roof rafters that cross over or meet trusses to be min. 2x4 SPF #2 @ 24" o/c with a vertical post to the truss at each cross point. Vertical posts longer than 6' to have lateral bracing so that the distance between the post end points and lateral bracing does not exceed 6'.

DESIGN CONFORMS WITH OBC 2012 (2019 amendment) OCCUPANCY: RESIDENTIAL | PART: 9
Ss = 31.35 psf | Sr = 8.4 psf

DESIGN LOADS:
TCSL = 25.6 psf
TCDL = 6.0 psf
BCLL = 0.0 psf
BCDL = 7.4 psf

HARDWARE:
LUS24 - (O)
LJS26DS - (V)
HGUS26-2 - (XX)
LUS26-2-(VV)

BEAMS:
B40= B41 = B42= *Lead Smith* Dec 16, 2020
2 - 2x10 SPF #2

 DENOTES:
CONVENTIONAL
FRAMING

M13125



Job Track: 51225
Plan Log: 202401
Layout ID: 408152

Builder / Location:
GREEN PARK HOMES / WATERDOWN

Project: RUSSELL GARDENS PH.3

Date: 2020-04-27 Sales: Mario DiCano Designer: JG

Model / Elevation:
MOUNTAINASH 4/3- std. or opt.

THESE DRAWINGS CONSTITUTE THE PROPERTY OF TAMARACK ROOF TRUSSES INC., SHALL NOT BE REPRODUCED, PUBLISHED, OR REDISTRIBUTED IN ANY MANNER OR UTILIZED FOR ANY PURPOSE OTHER THAN THE MANUFACTURE OF TRUSSES BY TAMARACK ROOF TRUSSES INC AND WILL BE RETRACTED BY TAMARACK ROOF TRUSSES INC IF UTILIZED FOR ANY OTHER PURPOSE.

Mitek ver 8.3.1.215

NOV 15 2020


 TAMARACK ROOF TRUSSES INC. ALFA LUMBER GROUP	DELIVERY SHIPLIST				Lumber Yard: TAMARACK LUMBER Builder: GREEN PARK HOMES Project: RUSSELL GARDENS PH.3 Location: WATERDOWN Model: MOUNTAINASH 4 Lot #: Elevation: 1-std or opt.		Job Track: 51225 PlanLog: 202401 Layout ID: 408150 Ref # Page: 1 of 2 Date: 04-27-2020 Designer: Sales Rep: Mario DiCano	
---	-------------------	--	--	--	---	--	---	--

Roof Trusses

PROFILE	QTY PLY	MARK TYPE	PITCH	SPAN	HEIGHT	LUMBER	OVERHANG LEFT RIGHT	HEEL HEIGHT LEFT RIGHT	LBS. BFT.	BUNDLE # STACK #	LOAD BY REMARKS
	1 2-ply	T1 Flat Girder	0 /12	34-10-00	4-01-04	2 x 6		4-01-04 4-01-04	352.6 214.67		
	1 2-ply	T1Z Flat Girder	0 /12	34-10-00	4-01-04	2 x 6		4-01-04 4-01-04	352.6 214.67		
	2	T2 Flat	0 /12	34-10-00	5-01-04	2 x 4		5-01-04 5-01-04	286.17 179.67		
	2	T3 Flat	0 /12	34-10-00	6-01-04	2 x 4		6-01-04 6-01-04	305.44 187.33		
	2	T4 Flat	0 /12	34-10-00	7-01-04	2 x 4		7-01-04 7-01-04	313.23 193.33		
	10	T5 Flat	0 /12	34-10-00	8-01-04	2 x 4		8-01-04 8-01-04	1784.6 1100.00		
	1	T6 Hip Girder	10 /12	16-07-00	4-10-07	2 x 4 2 x 6	1-03-08 1-03-08	1-07-11 1-07-11	83.68 52.50		
	1	T7 Hip	10 /12	16-05-00	6-06-07	2 x 4		1-09-06 1-07-11	69.84 44.00		
	1	T8 Hip	10 /12	16-05-00	8-02-07	2 x 4		1-09-06 1-07-11	77.45 49.33		
	1	T9 Common	10 /12	16-05-00	8-06-10	2 x 4		1-09-06 1-07-11	76.71 48.83		
	2	T10S Roof Special	10 /12	10-11-00	6-02-04	2 x 4	1-03-08 1-03-08	1-07-11 1-07-11	111.52 78.33		
	1	T11 Common	10 /12	10-11-00	6-02-04	2 x 4	1-03-08 1-03-08	1-07-11 1-07-11	48.78 32.33		
	1	T12 Common	10 /12	7-08-00	5-05-08	2 x 4		2-03-03 2-03-03	35.11 22.50		
	2	T12S Roof Special	10 /12	7-08-00	5-05-08	2 x 4		2-03-03 2-03-03	85.22 60.67		

 TAMARACK ROOF TRUSSES INC. ALPA LUMBER GROUP	DELIVERY SHIPLIST				Lumber Yard: TAMARACK LUMBER Builder: GREEN PARK HOMES Project: RUSSELL GARDENS PH.3 Location: WATERDOWN Model: MOUNTAINASH 4 Lot #: Elevation: 1-std or opt.		Job Track: 51225 Plan Log: 202401 Layout ID: 408150 Ref # Page: 2 of 2 Date: 04-27-2020 Designer: Sales Rep: Mario DiCano	
---	--------------------------	--	--	--	---	--	--	--

Roof Trusses


PROFILE	QTY PLY	MARK TYPE	PITCH	SPAN	HEIGHT	LUMBER	OVERHANG LEFT RIGHT	HEEL HEIGHT LEFT RIGHT	LBS. BFT.	BUNDLE # STACK #	LOAD BY REMARKS
	1	T15 Hip Girder	0 /12	10-11-00	1-09-07	2 x 4		1-08-15 1-08-15	37.09 24.33		
	4	G60 GABLE	6 /12	22-11-00	8-01-04	2 x 4	1-03-08	1-02-00 8-01-04	463.73 294.00		
	17	P1 Common	6 /12	18-01-00	4-06-04	2 x 4			943.11 612.00		
	2	GP1 Common Supported Gable	6 /12	18-01-00	4-06-04	2 x 4			107.34 68.00		
	21	J1 Jack-Open	6 /12	5-10-08	4-01-04	2 x 4	1-03-08	1-02-00 4-01-04	352.68 224.00		
	1	J2 Jack-Open	10 /12	3-10-08	4-10-07	2 x 4	1-03-08	1-07-11 4-10-07	15.23 9.67		
	6	J3 Jack-Open	4 /12	4-04-08	2-02-06	2 x 4	1-03-08	3-15 1-09-07	71.47 48.00		
	1	C1 Jack-Open	10 /12	1-10-15	3-02-13	2 x 4	1-03-08 1-11-09	1-07-11 3-02-13	12.28 8.33		
	1	C2 Jack-Open	10 /12	1-10-15	3-02-13	2 x 4	1-03-08 1-01	1-07-11 3-02-13	10.4 7.50		


TOTAL # TRUSS= 84 TOTAL BFT OF ALL TRUSSES= 3773.99 BFT. TOTAL WEIGHT OF ALL TRSSES 5996.28 LBS

HARDWARE

QTY	TYPE	MODEL	LENGTH
2	Hardware	LJS26DS	
6	Hardware	LUS24	
4	Hardware	LUS26-2	

TOTAL NUMBER OF
ITEMS= 12





DELIVERY SHIPLIST

Lumber Yard: TAMARACK LUMBER
 Builder: GREEN PARK HOMES
 Project: RUSSELL GARDENS PH.3
 Location: WATERDOWN
 Model: MOUNTAINASH 4
 Lot #:
 Elevation: 2-std or opt.

Job Track: 51225
 Plan Log: 202401
 Layout ID: 408151
 Ref #
 Page: 1 of 2
 Date: 04-27-2020
 Designer:
 Sales Rep: Mario DiCano

Roof Trusses

PROFILE	QTY PLY	MARK TYPE	PITCH	SPAN	HEIGHT	LUMBER	OVERHANG LEFT RIGHT	HEEL HEIGHT LEFT RIGHT	LBS. BFT.	BUNDLE # STACK #	LOAD BY REMARKS
	1 2-ply	T20 Hip Girder	10 / 12	35-02-00	4-01-11	2 x 6	1-03-08 1-03-08	1-07-11 1-07-11	365.28 218.00		
	1 2-ply	T20Z Hip Girder	10 / 12	35-02-00	4-01-11	2 x 6	1-03-08 1-03-08	1-07-11 1-07-11	366.28 218.00		
	2	T21 Hip	10 / 12	35-02-00	5-01-04	2 x 4	1-03-08 1-03-08	1-07-11 1-07-11	293.44 185.87		
	2	T22 Hip	10 / 12	35-02-00	6-01-04	2 x 4	1-03-08 1-03-08	1-07-11 1-07-11	296.43 188.67		
	2	T23 Hip	10 / 12	35-02-00	7-01-04	2 x 4	1-03-08 1-03-08	1-07-11 1-07-11	323.09 204.33		
	2	T24 Hip	10 / 12	35-02-00	8-01-04	2 x 4	1-03-08 1-03-08	1-07-11 1-07-11	326.19 204.67		
	2	T25 Hip	10 / 12	35-02-00	9-01-04	2 x 4	1-03-08 1-03-08	1-07-11 1-07-11	363.03 228.67		
	4	T26 Hip	10 / 12	35-02-00	10-01-04	2 x 4	1-03-08 1-03-08	1-07-11 1-07-11	693.28 432.00		
	2	T27 Hip	10 / 12	35-02-00	11-01-04	2 x 4	1-03-08 1-03-08	1-07-11 1-07-11	380.36 236.67		
	2	T28 Common	10 / 12	16-07-00	8-06-10	2 x 4	1-03-08 1-03-08	1-07-11 1-07-11	163.16 102.67		
	1	T29 Common	10 / 12	16-07-00	9-10-10	2 x 4	1-03-08 1-03-08	2-11-11 2-11-11	90.52 56.67		
	1	T30 Hip	10 / 12	16-07-00	9-05-12	2 x 4	1-03-08 1-03-08	2-11-11 2-11-11	97.28 61.17		
	1	T31 Hip	10 / 12	16-07-00	8-05-12	2 x 4	1-03-08 1-03-08	2-11-11 2-11-11	91.81 58.17		
	1	T32 Hip	10 / 12	16-07-00	7-05-12	2 x 4	1-03-08 1-03-08	2-11-11 2-11-11	79.39 48.83		



DELIVERY SHIPLIST

Lumber Yard: TAMARACK LUMBER
 Builder: GREEN PARK HOMES
 Project: RUSSELL GARDENS PH.3
 Location: WATERDOWN
 Model: MOUNTAINASH 4
 Lot #:
 Elevation: 2-std or opt.

Job Track: 51225
 PlanLog: 202401
 Layout ID: 408151
 Ref #
 Page: 2 of 2
 Date: 04-27-2020
 Designer:
 Sales Rep: Mario DiCano

Roof Trusses

PROFILE	QTY PLY	MARK TYPE	PITCH	SPAN	HEIGHT	LUMBER	OVERHANG LEFT RIGHT	HEEL HEIGHT LEFT RIGHT	LBS. BFT.	BUNDLE # STACK #	LOAD BY REMARKS
	1	T33X Common	10 /12	9-00-00	5-02-03	2 x 4		1-05-03 1-05-03	37.02 25.50		
	1	G33 GABLE	10 /12	8-06-00	5-02-03	2 x 4	1-03-08 1-03-08	1-07-11 1-07-11	41.52 27.83		
	2	T34 Common	10 /12	8-06-00	6-06-03	2 x 4		2-11-11 2-11-11	81.91 52.00		
	2 2-ply	T35 Flat Girder	0 /12	5-10-08	1-04-00	2 x 4		1-04-00 1-04-00	80.16 51.33		
	1	G36 GABLE	10 /12	10-11-00	6-02-04	2 x 4	1-03-08 1-03-08	1-07-11 1-07-11	53.04 35.33		
	2	PB20 Piggyback	10 /12	14-10-03	2-00-00	2 x 4			90.38 60.00		
	21	J1 Jack-Open	6 /12	5-10-08	4-01-04	2 x 4	1-03-08	1-02-00 4-01-04	352.68 224.00		

TOTAL # TRUSS= 58

TOTAL BFT OF ALL TRUSSES= 2920.18


BFT.

TOTAL WEIGHT OF ALL TRSSES 4665.24 LBS

HARDWARE

QTY	TYPE	MODEL	LENGTH
3	Hardware	LJS26DS	
4	Hardware	LUS24	
3	Hardware	LUS26-2	

TOTAL NUMBER OF
ITEMS= 10





DELIVERY SHIPLIST

Lumber Yard: TAMARACK LUMBER
 Builder: GREEN PARK HOMES
 Project: RUSSELL GARDENS PH.3
 Location: WATERDOWN
 Model: MOUNTAINASH 4
 Lot #:
 Elevation: 3- std. or opt.





Job Track: 51225
 PlanLog: 202401
 Layout ID: 408152
 Ref #
 Page: 1 of 3
 Date: 04-27-2020
 Designer:
 Sales Rep: Mario DiCano

Roof Trusses

PROFILE	QTY PLY	MARK TYPE	PITCH	SPAN	HEIGHT	LUMBER	OVERHANG LEFT RIGHT	HEEL HEIGHT LEFT RIGHT	LBS. BFT.	BUNDLE # STACK #	LOAD BY REMARKS
	1 2-ply	T40 Hip Girder	6 /12	35-02-00	4-01-04	2 x 4 2 x 6	1-03-08 1-03-08	1-02-00 1-02-00	340.74 212.00		
	1 2-ply	T40Z Hip Girder	6 /12	35-02-00	4-01-04	2 x 4 2 x 6	1-03-08 1-03-08	1-02-00 1-02-00	340.74 212.00		
	2	T41 Hip	6 /12	35-02-00	5-01-04	2 x 4	1-03-08 1-03-08	1-02-00 1-02-00	277.99 174.00		
	2	T42 Hip	6 /12	35-02-00	6-01-04	2 x 4	1-03-08 1-03-08	1-02-00 1-02-00	277.12 174.67		
	2	T43 Hip	6 /12	35-02-00	7-01-04	2 x 4	1-03-08 1-03-08	1-02-00 1-02-00	289.07 179.67		
	2	T44 Hip	6 /12	35-02-00	8-01-04	2 x 4	1-03-08 1-03-08	1-02-00 1-02-00	290.73 183.33		
	2	T45 Hip	6 /12	35-02-00	9-01-04	2 x 4	1-03-08 1-03-08	1-02-00 1-02-00	301.67 191.33		
	6	T46 Common	6 /12	35-02-00	9-11-08	2 x 4	1-03-08 1-03-08	1-02-00 1-02-00	910.08 558.00		
	1 2-ply	T47 Hip Girder	6 /12	16-07-00	4-01-04	2 x 4 2 x 6	1-03-08	1-02-00 2-02-00	158.02 100.67		
	1	T48 Hip	6 /12	16-07-00	5-01-04	2 x 4	1-03-08	1-02-00 2-02-00	68.15 43.33		
	1	T49 Common	6 /12	16-07-00	5-09-12	2 x 4	1-03-08	1-02-00 2-02-00	67.14 42.33		
	1	T50 Hip Girder	6 /12	10-11-00	2-07-04	2 x 4	1-03-08 1-03-08	1-02-00 1-02-00	42.73 28.33		
	1	T51 Hip	6 /12	10-11-00	4-07-04	2 x 4	1-03-08 1-03-08	2-02-00 2-02-00	51.54 34.50		
	1	T52 Flat	0 /12	9-04-00	2-10-00	2 x 4		2-10-00 2-10-00	36.11 23.83		

 TAMARACK ROOF TRUSSES INC. ALFA LUMBER GROUP	DELIVERY SHIPLIST	
	Lumber Yard: TAMARACK LUMBER Builder: GREEN PARK HOMES Project: RUSSELL GARDENS PH.3 Location: WATERDOWN Model: MOUNTAINASH 4 Lot #: Elevation: 3- std. or opt.	Job Track: 51225 PlanLog: 202401 Layout ID: 408152 Ref # Page: 2 of 3 Date: 04-27-2020 Designer: Sales Rep: Mario DiCano

Roof Trusses

PROFILE	QTY PLY	MARK TYPE	PITCH	SPAN	HEIGHT	LUMBER	OVERHANG LEFT RIGHT	HEEL HEIGHT LEFT RIGHT	LBS. BFT.	BUNDLE # STACK #	LOAD BY REMARKS
	1	G52 GABLE	0 / 12	9-04-00	2-10-00	2 x 4		2-10-00 2-10-00	33.75 23.33		
	1	T53 Flat Girder	0 / 12	9-04-00	3-10-00	2 x 6		3-10-00 3-10-00	50.9 31.50		
	1 2-ply	T54 Jack-Closed Girder	6 / 12	6-10-08	4-01-04	2 x 4 2 x 6		8-00 4-01-04	59.61 37.33		
	15	J1 Jack-Open	6 / 12	5-10-08	4-01-04	2 x 4	1-03-08	1-02-00 4-01-04	251.92 160.00		
	4	J40 Jack-Open	6 / 12	3-09-08	4-01-04	2 x 4		2-02-08 4-01-04	52.34 35.33		
	4	J41 Jack-Open	6 / 12	2-10-08	2-07-04	2 x 4	1-03-08	1-02-00 2-07-04	38.2 24.00		
	4	C40 Jack-Open	6 / 12	3-09-07	3-00-12	2 x 4	1-03-08 2-01-01	1-02-00 3-00-12	56.53 34.67		
	4	C41 Jack-Open	6 / 12	1-09-07	2-00-12	2 x 4	1-03-08 4-01-01	1-02-00 2-00-12	46.33 29.33		
	4	C42 Jack-Open	6 / 12	1-10-08	3-00-12	2 x 4	1-03-08 1-10-15	1-02-00 2-01-04	38.28 24.00		
	4	C43 Jack-Open	6 / 12	1-09-07	2-00-12	2 x 4	1-03-08 1-01	1-02-00 2-00-12	28.08 18.67		
	2	C44 Jack-Open	6 / 12	1-10-15	2-01-08	2 x 4	1-03-08 11-09	1-02-00 2-01-08	16.64 10.67		
	2	C45 Jack-Open	6 / 12	1-10-15	2-01-08	2 x 4	1-03-08 1-01	1-02-00 2-01-08	14.65 9.33		

TOTAL # TRUSS= 74

TOTAL BFT OF ALL TRUSSES= 2596.15

BFT.

TOTAL WEIGHT OF ALL TRSSES 4137.05 LBS

HARDWARE


QTY	TYPE	MODEL	LENGTH
1	Hardware	HGUS26-2	
4	Hardware	LJS26DS	

DELIVERY SHIPLIST		
 TAMARACK ROOF TRUSSES INC. ALFA LUMBER GROUP	Lumber Yard: TAMARACK LUMBER Builder: GREEN PARK HOMES Project: RUSSELL GARDENS PH.3 Location: WATERDOWN Model: MOUNTAINASH 4 Lot #: Elevation: 3- std. or opt.	Job Track: 51225 PlanLog: 202401 Layout ID: 408152 Ref # Page: 3 of 3 Date: 04-27-2020 Designer: Sales Rep: Mario DiCano

HARDWARE


QTY	TYPE	MODEL	LENGTH
5	Hardware	LUS24	
3	Hardware	LUS26-2	

TOTAL NUMBER OF
ITEMS= 13



JOB NAME 408150	TRUSS NAME T1	QUANTITY 1	PLY 2	JOB DESC. GREEN PARK HOMES	DRWG NO.
Tamarack Roof Truss, Burlington				TRUSS DESC.	

Version 8.310 S Oct 29 2019 Mitek Industries, Inc. Sat Apr 25 11:02:47 2020 Page 1
 ID:7vF7aG0E03cRUj6X1JSkzIWYK-VShXSDRAXNen1SLAM JSZu8zCRhpKACNPVGMyzNCnc
 Scale = 1:34.4



LUMBER

N. L. G. A. RULES

CHORDS	SIZE	LUMBER	DESCR.
R - A	2x4	DRY	No.2
A - D	2x6	DRY	No.2
D - F	2x6	DRY	No.2
F - I	2x6	DRY	No.2
I - J	2x4	DRY	No.2
R - P	2x6	DRY	No.2
P - L	2x6	DRY	No.2
L - J	2x6	DRY	No.2

ALL WEBS 2x3 DRY SEASONED LUMBER.

DESIGN CONSISTS OF 2 TRUSSES BUILT SEPARATELY THEN FASTENED TOGETHER AS FOLLOWS:

CHORDS #ROWS	SURFACE SPACING (IN)	LOAD (PLF)
TOP CHORDS : (0.122"x3") SPIRAL NAILS		
R - A 1 12	TOP	
I - J 1 12	TOP	
A - D 2 12	SIDE (183.1)	
D - F 2 12	SIDE (0.0)	
F - I 2 12	SIDE (0.0)	
BOTTOM CHORDS : (0.122"x3") SPIRAL NAILS		
R - P 2 12	SIDE (183.1)	
P - L 2 12	SIDE (183.1)	
L - J 2 12	SIDE (0.0)	
WEBS : (0.122"x3") SPIRAL NAILS		
2x3 1 6		

NAILS TO BE DRIVEN FROM ONE SIDE ONLY.

GIRDER NAILING ASSUMES NAILED HANGERS ARE FASTENED WITH MIN. 3-0 INCH NAILS.

TOP - COMPONENTS ARE LOADED FROM THE TOP AND MUST BE PLACED ON TOP EDGE OF ALL PLIES FOR THE LOAD TO BE TRANSFERRED TO EACH PLY.

SIDE - PLF SHOWN IS THE EQUIVALENT UDL APPLIED TO ONE SIDE THAT THE CORRESPONDING NAILING PATTERN SHALL BE CAPABLE OF TRANSFERING. REMAINING PLF MUST BE APPLIED ON THE OPPOSITE SIDE OR ON THE TOP.

DIMENSIONS, SUPPORTS AND LOADINGS SPECIFIED BY FABRICATOR TO BE VERIFIED BY BUILDING DESIGNER

BEARINGS

JT	FACTORED GROSS REACTION		MAXIMUM FACTORED GROSS REACTION		INPUT BRG	RECORD BRG
	VERT	HORZ	DOWN	HORZ		
R	3052	0	3052	0	3-8	3-8
J	3118	0	3118	0	3-8	3-8

UNFACTORED REACTIONS

JT	1ST LCASE		MAX./MIN. COMPONENT REACTIONS		WIND	DEAD	SOIL
	COMBINED	SNOW	LIVE	PERM.LIVE			
R	2161	1401 / 0	0 / 0	0 / 0	0 / 0	761 / 0	0 / 0
J	2208	1430 / 0	0 / 0	0 / 0	0 / 0	778 / 0	0 / 0

BEARING MATERIAL TO BE SPF NO.2 OR BETTER AT JOINT(S) R, J.

BRACING
 TOP CHORD TO BE SHEATHED OR MAX. PURLIN SPACING = 4.25 FT.
 MAX. UNBRACED BOTTOM CHORD LENGTH = 10.00 FT OR RIGID CEILING DIRECTLY APPLIED.

ALL PITCH BREAKS AND PERIMETER CORNER JOINTS MUST BE LATERALLY RESTRAINED.

LOADING
 TOTAL LOAD CASES: (4)

CHORDS					WEBS				
MEMB.	MAX. FACTORED FORCE (LBS)	FACTORED VERT. LOAD (PLF)	LC1 MAX. CSI (LC)	MAX. UNBRAC LENGTH	MEMB.	MAX. FACTORED FORCE (LBS)	MAX. CSI (LC)		
FR-TO		FROM TO			FR-TO				
R-A	-2974 / 0	0.0	0.0	0.34 (1)	8.68	K-I	0 / 5093	0.63 (1)	
A-S	-4328 / 0	-91.8	-91.8	0.20 (1)	5.32	A-Q	0 / 5078	0.63 (1)	
S-T	-4328 / 0	-91.8	-91.8	0.20 (1)	5.32	K-H	-2485 / 0	0.30 (1)	
T-B	-4328 / 0	-91.8	-91.8	0.20 (1)	5.32	Q-B	-2483 / 0	0.29 (1)	
B-U	-6696 / 0	-91.8	-91.8	0.25 (1)	4.43	M-H	0 / 2804	0.35 (1)	
U-V	-6696 / 0	-91.8	-91.8	0.25 (1)	4.43	B-O	0 / 2808	0.35 (1)	
V-C	-6696 / 0	-91.8	-91.8	0.25 (1)	4.43	M-G	-1325 / 0	0.16 (1)	
C-D	-7505 / 0	-91.8	-91.8	0.23 (1)	4.25	O-C	-1326 / 0	0.18 (1)	
D-W	-7505 / 0	-91.8	-91.8	0.23 (1)	4.25	N-G	0 / 956	0.12 (1)	
W-E	-7505 / 0	-91.8	-91.8	0.23 (1)	4.25	C-N	0 / 958	0.12 (1)	
E-X	-7505 / 0	-91.8	-91.8	0.23 (1)	4.25	N-E	-651 / 0	0.10 (1)	
X-Y	-7505 / 0	-91.8	-91.8	0.23 (1)	4.25				
Y-F	-7505 / 0	-91.8	-91.8	0.23 (1)	4.25				
F-Z	-7505 / 0	-91.8	-91.8	0.23 (1)	4.25				
Z-G	-7505 / 0	-91.8	-91.8	0.23 (1)	4.25				
Q-AA	-6699 / 0	-91.8	-91.8	0.26 (1)	4.42				
AA-AB	-6699 / 0	-91.8	-91.8	0.26 (1)	4.42				
AB-AC	-6698 / 0	-91.8	-91.8	0.26 (1)	4.42				
AC-H	-6698 / 0	-91.8	-91.8	0.26 (1)	4.42				
H-AD	-4330 / 0	-91.8	-91.8	0.21 (1)	5.30				
AD-AE	-4330 / 0	-91.8	-91.8	0.21 (1)	5.30				
AE-AF	-4330 / 0	-91.8	-91.8	0.21 (1)	5.30				
AF-I	-4330 / 0	-91.8	-91.8	0.21 (1)	5.30				
J-I	-3028 / 0	0.0	0.0	0.35 (1)	6.64				

R-AG	0 / 0	-18.5	-18.5	0.06 (4)	10.00
AG-AH	0 / 0	-18.5	-18.5	0.06 (4)	10.00
AH-Q	0 / 0	-18.5	-18.5	0.06 (4)	10.00
Q-AI	0 / 4328	-18.5	-18.5	0.33 (1)	10.00
AI-P	0 / 4326	-18.5	-18.5	0.33 (1)	10.00
P-O	0 / 4326	-18.5	-18.5	0.33 (1)	10.00
O-AJ	0 / 6696	-18.5	-18.5	0.49 (1)	10.00
AJ-AK	0 / 6696	-18.5	-18.5	0.49 (1)	10.00
AK-N	0 / 6696	-18.5	-18.5	0.49 (1)	10.00
N-AL	0 / 6698	-18.5	-18.5	0.49 (1)	10.00
AL-AM	0 / 6698	-18.5	-18.5	0.49 (1)	10.00
AM-AN	0 / 6698	-18.5	-18.5	0.49 (1)	10.00
AN-M	0 / 6698	-18.5	-18.5	0.49 (1)	10.00
M-AO	0 / 4330	-18.5	-18.5	0.33 (1)	10.00
AO-L	0 / 4330	-18.5	-18.5	0.33 (1)	10.00
L-AP	0 / 4330	-18.5	-18.5	0.33 (1)	10.00
AP-AQ	0 / 4330	-18.5	-18.5	0.33 (1)	10.00
AQ-K	0 / 4330	-18.5	-18.5	0.33 (1)	10.00

DESIGN CRITERIA

SPECIFIED LOADS:
 TOP CH. LL = 25.6 PSF
 DL = 8.0 PSF
 BOT CH. LL = 0.0 PSF
 DL = 7.4 PSF
 TOTAL LOAD = 39.0 PSF

SPACING = 24.0 IN. C/C

LOADING IN PLAT SECTION BASED ON A SLOPE OF 6.00/12

THIS TRUSS IS DESIGNED FOR RESIDENTIAL OR SMALL BUILDING REQUIREMENTS OF PART 9, NBCC 2010, NBCC 2015

THIS DESIGN COMPLIES WITH:
 - PART 9 OF CBC 2018, CBC 2012, ABC 2019
 - PART 9 OF CBC 2012 (2019 AMENDMENT)
 - CSA 086-09, CSA 086-14
 - TPIC 2011, TPIC 2014

(55% OF 31.3 P.S.F. G.S.L. PLUS 8.4 P.S.F. RAIN LOAD) EQUALS 25.6 P.S.F. SPECIFIED ROOF LIVE LOAD

ALLOWABLE DEFL.(LL) = L/360 (1.16")
 CALCULATED VERT. DEFL.(LL) = L/999 (0.20")
 ALLOWABLE DEFL.(TL) = L/600 (1.16")
 CALCULATED VERT. DEFL.(TL) = L/999 (0.38")

CSI: TC=0.35/1.00 (I-J); BC=0.49/1.00 (M-N); WB=0.63/1.00 (K-I); SS=0.17/1.00 (H-I)

DOL LUMBER=1.00 NAIL=1.00 LS BEND=1.00 COMP=1.00 SHEAR=1.00 TENS=1.00

COMPANION LIVE LOAD FACTOR = 1.00

TRUSS PLATE MANUFACTURER IS NOT RESPONSIBLE FOR QUALITY CONTROL IN THE TRUSS MANUFACTURING PLANT.

NAIL VALUES

PLATE GRIP (DRY)	SHEAR (PSI)	SECTION (PLI)
MAX MIN	MAX MIN	MAX MIN
MT20	818 354 1567 788 1987 1856	

PLATE PLACEMENT TOL. = ±0.250 inches

PLATE ROTATION TOL. = 5.0 Deg.

JSI GRIP= 0.86 (K) (INPUT = 0.90)

JSI METAL= 0.42 (F) (INPUT = 1.00)



Structural component only
 DWG# T-2007063

JOB NAME	TRUSS NAME	QUANTITY	PLY	JOB DESC.	DRWG NO.
408150	T1	1	2	GREEN PARK HOMES	
Tamarack Roof Truss, Burlington					
TRUSS DESC.					

Version 8.310 S Oct 29 2019 Mitak Industries, Inc. Sat Apr 25 11:02:47 2020 Page 2
ID:7vF7aG0E03cRU16X1/SkzWYK-VShX5DRAxNEn1SLAM IsZu8zCRhpikAQNPVGMvzNCnc

PLATES (table is in inches)

JT TYPE	PLATES	W	LEN	Y	X
A TMVW-t	MT20	6.0	9.0		Edge
B TMVW-t	MT20	5.0	6.0	2.50	2.75
C TMVW-t	MT20	5.0	6.0		
D TS-t	MT20	5.0	6.0		
E TMVW-w	MT20	3.0	6.0		
F TS-t	MT20	5.0	6.0		
G TMVW-t	MT20	5.0	6.0		
H TMVW-t	MT20	5.0	6.0	2.50	2.75
I TMVW-t	MT20	6.0	9.0		Edge
J BMV1-p	MT20	3.0	6.0		
K BMVW-t	MT20	6.0	9.0	3.00	4.25
L BS-t	MT20	5.0	6.0		
M BMVW-t	MT20	5.0	6.0	2.50	2.75
N BMVW-t	MT20	5.0	6.0		
O BMVW-t	MT20	5.0	6.0	2.50	2.75
P BS-t	MT20	5.0	6.0		
Q BMVW-t	MT20	6.0	9.0	3.00	4.25
R BMV1-p	MT20	3.0	6.0		

Edge - INDICATES REFERENCE CORNER OF PLATE TOUCHES EDGE OF CHORD.

LOADING

TOTAL LOAD CASES: (4)

CHORDS				WEBS			
MEMB.	MAX. FACTORED FORCE (LBS)	FACTORED VERT. LOAD (LBS)	MAX. CS (LC)	MAX. UNBRAC LENGTH	MEMB.	MAX. FACTORED FORCE (LBS)	MAX. CS (LC)
FR-TO		FROM TO			FR-TO		
K-AR	0 / 0	-18.5	-18.5	0.06 (4)	10.00		
AR-AS	0 / 0	-18.5	-18.5	0.06 (4)	10.00		
AS-AT	0 / 0	-18.5	-18.5	0.06 (4)	10.00		
AT-J	0 / 0	-18.5	-18.5	0.06 (4)	10.00		

FACTORED CONCENTRATED LOADS (LBS)


JT	LOC.	LC1	MAX.	MAX+	FACE	DIR.	TYPE	HEEL	CONN.
B	5-10-12	-110	-110	-	FRONT	VERT	TOTAL	-	C1
C	11-10-12	-110	-110	-	FRONT	VERT	TOTAL	-	C1
D	13-10-12	-110	-110	-	FRONT	VERT	TOTAL	-	C1
O	11-10-12	-26	-26	-	FRONT	VERT	TOTAL	-	C1
P	9-10-12	-26	-26	-	FRONT	VERT	TOTAL	-	C1
Q	5-10-12	-26	-26	-	FRONT	VERT	TOTAL	-	C1
S	1-10-12	-110	-110	-	FRONT	VERT	TOTAL	-	C1
T	3-10-12	-110	-110	-	FRONT	VERT	TOTAL	-	C1
U	7-10-12	-110	-110	-	FRONT	VERT	TOTAL	-	C1
V	9-10-12	-110	-110	-	FRONT	VERT	TOTAL	-	C1
W	15-10-12	-110	-110	-	FRONT	VERT	TOTAL	-	C1
X	17-10-12	-110	-110	-	FRONT	VERT	TOTAL	-	C1
Y	19-10-12	-110	-110	-	FRONT	VERT	TOTAL	-	C1
Z	21-10-12	-110	-110	-	FRONT	VERT	TOTAL	-	C1
AA	23-10-12	-110	-110	-	FRONT	VERT	TOTAL	-	C1
AB	25-10-12	-110	-110	-	FRONT	VERT	TOTAL	-	C1
AC	27-10-12	-110	-110	-	FRONT	VERT	TOTAL	-	C1
AD	29-10-12	-110	-110	-	FRONT	VERT	TOTAL	-	C1
AE	31-10-12	-110	-110	-	FRONT	VERT	TOTAL	-	C1
AF	33-10-12	-113	-113	-	FRONT	VERT	TOTAL	-	C1
AG	1-10-12	-26	-26	-	FRONT	VERT	TOTAL	-	C1
AH	3-10-12	-26	-26	-	FRONT	VERT	TOTAL	-	C1
AI	7-10-12	-26	-26	-	FRONT	VERT	TOTAL	-	C1
AJ	13-10-12	-26	-26	-	FRONT	VERT	TOTAL	-	C1
AK	15-10-12	-26	-26	-	FRONT	VERT	TOTAL	-	C1
AL	17-10-12	-26	-26	-	FRONT	VERT	TOTAL	-	C1
AM	19-10-12	-26	-26	-	FRONT	VERT	TOTAL	-	C1
AN	21-10-12	-26	-26	-	FRONT	VERT	TOTAL	-	C1
AO	23-10-12	-26	-26	-	FRONT	VERT	TOTAL	-	C1
AP	25-10-12	-26	-26	-	FRONT	VERT	TOTAL	-	C1
AQ	27-10-12	-26	-26	-	FRONT	VERT	TOTAL	-	C1
AR	29-10-12	-26	-26	-	FRONT	VERT	TOTAL	-	C1
AS	31-10-12	-26	-26	-	FRONT	VERT	TOTAL	-	C1
AT	33-10-12	-27	-27	-	FRONT	VERT	TOTAL	-	C1

CONNECTION REQUIREMENTS

1) C1: A SUITABLE HANGER/MECHANICAL CONNECTION IS REQUIRED.



Structural component only
DWG# T-2007063 72



LUMBER
N. L. G. A. RULES
CHORDS SIZE DRY LUMBER DESCR.
R - A 2x4 DRY No.2 SPF
A - D 2x6 DRY No.2 SPF
D - F 2x6 DRY No.2 SPF
F - I 2x6 DRY No.2 SPF
J - L 2x6 DRY No.2 SPF
P - L 2x6 DRY No.2 SPF
L - J 2x6 DRY No.2 SPF
ALL WEBS 2x3 DRY No.2 SPF
DRY: SEASONED LUMBER.

DESIGN CRITERIA
SPECIFIED LOADS:
TOP CH. LL = 25.6 PSF
DL = 8.0 PSF
BOT CH. LL = 0.0 PSF
DL = 7.4 PSF
TOTAL LOAD = 39.0 PSF
SPACING = 24.0 IN. C/C
LOADING IN FLAT SECTION BASED ON A SLOPE OF 6.00/12
THIS TRUSS IS DESIGNED FOR RESIDENTIAL OR SMALL BUILDING REQUIREMENTS OF PART 9, NBC 2010, NBC 2015
THIS DESIGN COMPLIES WITH:
- PART 9 OF CBC 2018, CBC 2012, ABC 2019
- PART 9 OF CBC 2012 (2019 AMENDMENT)
- CSA 086-09, CSA 086-14
- TPIC 2011, TPIC 2014
(55% OF 31.3 P.S.F. G.S.L. PLUS 8.4 P.S.F. RAIN LOAD) EQUALS 25.6 P.S.F. SPECIFIED ROOF LIVE LOAD
ALLOWABLE DEFL.(LL) = L/360 (1.18")
CALCULATED VERT. DEFL.(LL) = L/999 (0.28")
ALLOWABLE DEFL.(TL) = L/360 (1.18")
CALCULATED VERT. DEFL.(TL) = L/828 (0.50")
CSI: TC=0.44/1.00 (A-R:1), BC=0.81/1.00 (N-C:1), WB=0.83/1.00 (A-Q:1), SS=0.41/1.00 (M-N:1)
DOL LUMBER=1.00 NAIL=1.00 LBS BEND=1.00
COMP=1.00 SHEAR=1.00 TENS=1.00
COMPANION LIVE LOAD FACTOR = 1.00
TRUSS PLATE MANUFACTURER IS NOT RESPONSIBLE FOR QUALITY CONTROL IN THE TRUSS MANUFACTURING PLANT.
NAIL VALUES
PLATE GRIP(DRY) SHEAR SECTION (PSI) (PLI) (PLI)
MAX MIN MAX MIN MAX MIN
MT20 618 354 1667 788 1987 1656
PLATE PLACEMENT TOL. = 0.250 inches
PLATE ROTATION TOL. = 5.0 Deg.
JSI GRIP= 0.88 (M) (INPUT = 0.90)
JSI METAL= 0.50 (P) (INPUT = 1.00)

BEARING
TOP CHORD TO BE SHEATHED OR MAX. PURLIN SPACING = 3.64 FT.
MAX. UNBRACED BOTTOM CHORD LENGTH = 10.00 FT OR RIGID CEILING DIRECTLY APPLIED.
ALL PITCH BREAKS AND PERIMETER CORNER JOINTS MUST BE LATERALLY RESTRAINED.

LOADING
TOTAL LOAD CASES: (4)

MEMB.	FORCE (LBS)	VERT. LOAD (LBS)	MAX. FACTORED (LBS)	MAX. FACTORED (LBS)	WEBS	MAX. FACTORED (LBS)	MAX. FACTORED (LBS)
FR-TO	0.0	0.0	0.0	0.0	FR-TO	0.0	0.0
R-A	-3851 / 0	-91.8	-91.8	0.44 (1)	K-I	0 / 5426	0.67 (1)
A-S	-5722 / 0	-91.8	-91.8	0.25 (1)	A-Q	0 / 6717	0.83 (1)
S-T	-5722 / 0	-91.8	-91.8	0.25 (1)	K-H	-2763 / 0	0.33 (1)
T-B	-5722 / 0	-91.8	-91.8	0.25 (1)	Q-B	-2710 / 0	0.32 (1)
B-C	-8648 / 0	-91.8	-91.8	0.27 (1)	M-H	0 / 4038	0.50 (1)
C-D	-10219 / 0	-91.8	-91.8	0.34 (1)	B-O	0 / 3700	0.46 (1)
D-U	-10219 / 0	-91.8	-91.8	0.34 (1)	A-G	-1901 / 0	0.23 (1)
U-E	-10219 / 0	-91.8	-91.8	0.34 (1)	C-C	-1400 / 0	0.17 (1)
E-V	-10219 / 0	-91.8	-91.8	0.31 (1)	N-G	0 / 2591	0.92 (1)
V-F	-10219 / 0	-91.8	-91.8	0.31 (1)	C-N	0 / 1626	0.20 (1)
F-G	-10219 / 0	-91.8	-91.8	0.31 (1)	N-E	-710 / 0	0.08 (1)
G-H	-8031 / 0	-91.8	-91.8	0.23 (1)			
H-I	-4622 / 0	-91.8	-91.8	0.15 (1)			
I-J	-3871 / 0	0.0	0.0	0.35 (1)			

CHORDS
MAX. FACTORED (LBS) FACTORED (LBS) WEBS MAX. FACTORED (LBS) FACTORED (LBS)

MEMB.	FORCE (LBS)	VERT. LOAD (LBS)	MAX. FACTORED (LBS)	MAX. FACTORED (LBS)	MEMB.	FORCE (LBS)	MAX. FACTORED (LBS)
R-A	-3851 / 0	0.0	0.0	0.44 (1)	K-I	0 / 5426	0.67 (1)
A-S	-5722 / 0	-91.8	-91.8	0.25 (1)	A-Q	0 / 6717	0.83 (1)
S-T	-5722 / 0	-91.8	-91.8	0.25 (1)	K-H	-2763 / 0	0.33 (1)
T-B	-5722 / 0	-91.8	-91.8	0.25 (1)	Q-B	-2710 / 0	0.32 (1)
B-C	-8648 / 0	-91.8	-91.8	0.27 (1)	M-H	0 / 4038	0.50 (1)
C-D	-10219 / 0	-91.8	-91.8	0.34 (1)	B-O	0 / 3700	0.46 (1)
D-U	-10219 / 0	-91.8	-91.8	0.34 (1)	A-G	-1901 / 0	0.23 (1)
U-E	-10219 / 0	-91.8	-91.8	0.34 (1)	C-C	-1400 / 0	0.17 (1)
E-V	-10219 / 0	-91.8	-91.8	0.31 (1)	N-G	0 / 2591	0.92 (1)
V-F	-10219 / 0	-91.8	-91.8	0.31 (1)	C-N	0 / 1626	0.20 (1)
F-G	-10219 / 0	-91.8	-91.8	0.31 (1)	N-E	-710 / 0	0.08 (1)
G-H	-8031 / 0	-91.8	-91.8	0.23 (1)			
H-I	-4622 / 0	-91.8	-91.8	0.15 (1)			
I-J	-3871 / 0	0.0	0.0	0.35 (1)			

CHORDS #ROWS SURFACE SPACING (IN) LOAD (PLF)
TOP CHORDS: (0.122"x3") SPIRAL NAILS
R-A 1 12 TOP
I-J 1 12 TOP
A-D 2 12 SIDE(0.0)
D-F 2 12 SIDE(183.1)
F-I 2 12 TOP
BOTTOM CHORDS: (0.122"x3") SPIRAL NAILS
R-P 2 12 SIDE(0.0)
P-L 2 12 SIDE(183.1)
L-J 2 12 TOP
WEBS: (0.122"x3") SPIRAL NAILS
2x3 1 6
NAILS TO BE DRIVEN FROM ONE SIDE ONLY.
GIRDER NAILING ASSUMES NAILED HANGERS ARE FASTENED WITH MIN. 3-0 INCH NAILS.
TOP - COMPONENTS ARE LOADED FROM THE TOP AND MUST BE PLACED ON TOP EDGE OF ALL PLIES FOR THE LOAD TO BE TRANSFERRED TO EACH PLY.
SIDE - PLF SHOWN IS THE EQUIVALENT UDL APPLIED TO ONE SIDE THAT THE CORRESPONDING NAILING PATTERN SHALL BE CAPABLE OF TRANSFERING. REMAINING PLF MUST BE APPLIED ON THE OPPOSITE SIDE OR ON THE TOP.

FACTORED CONCENTRATED LOADS (LBS)

LOC.	MAX.	MAX.	FACE	DIR.	TYPE	HEEL	CONN.
S 1-10-12	-110	-110	---	BACK	VERT	TOTAL	C1
T 3-10-12	-110	-110	---	BACK	VERT	TOTAL	C1
U 15-8-12	-110	-110	---	BACK	VERT	TOTAL	C1
V 17-8-12	-110	-110	---	BACK	VERT	TOTAL	C1
W 1-10-12	-26	-26	---	BACK	VERT	TOTAL	C1
X 3-10-12	-26	-26	---	BACK	VERT	TOTAL	C1
Y 5-1-8	-727	-727	---	BACK	VERT	TOTAL	C1
Z 13-0-8	-727	-727	---	BACK	VERT	TOTAL	C1
AA 15-8-12	-26	-26	---	BACK	VERT	TOTAL	C1
AB 17-8-12	-26	-26	---	BACK	VERT	TOTAL	C1

LICENSED PROFESSIONAL ENGINEER
04/23/20
H. J. G. ALVES
100009024
PROVINCE OF ONTARIO
Structural component only
DWG# T-2007064 1/2

JOB NAME	TRUSS NAME	QUANTITY	PLY	JOB DESC.	DRWG NO.
408150	T1Z	1	2	GREEN PARK HOMES	

Tamarack Roof Truss, Burlington

Version 8.310 S Oct 29 2019 MITek Industries, Inc. Sat Apr 25 11:02:49 2020 Page 2
ID:7vf7aG0E03cRU6X1SrkziWYK-SrpIVvTQ3 UVGPVZTPnKeJDIEFIF7bWic7 NRzNCna

PLATES (table is in inches)

JT	TYPE	PLATES	W	LEN	Y	X
A	TMVW-t	MT20	6.0	9.0		Edge
B	TMWW-t	MT20	5.0	6.0	2.50	2.75
C	TMWW-t	MT20	5.0	6.0		
D	TS-t	MT20	5.0	6.0		
E	TMW-w	MT20	3.0	6.0		
F	TS-t	MT20	5.0	6.0		
G	TMWW-t	MT20	5.0	6.0		
H	TMWW-t	MT20	5.0	6.0	2.50	2.75
I	TMVW-t	MT20	6.0	9.0		Edge
J	BMV1+p	MT20	3.0	6.0		
K	BMWW-t	MT20	6.0	9.0	3.00	4.25
L	BS-t	MT20	5.0	6.0		
M	BMWW-t	MT20	5.0	6.0	2.50	2.75
N	BMWW-t	MT20	5.0	6.0		
O	BMWW-t	MT20	5.0	6.0	2.50	2.75
P	BS-t	MT20	5.0	6.0		
Q	BMWW-t	MT20	6.0	9.0	3.00	4.25
R	BMV1+p	MT20	3.0	6.0		

Edge - INDICATES REFERENCE CORNER OF PLATE TOUCHES EDGE OF CHORD.

FACTORED CONCENTRATED LOADS (LBS)

JT	LOC.	LC1	MAX-	MAX+	FACE	DIR.	TYPE	HEEL	CONN.
AC	18-3-8	-1293	-1293		BACK	VERT	TOTAL		CI


CONNECTION REQUIREMENTS

- 1) C1: A SUITABLE HANGER/MECHANICAL CONNECTION IS REQUIRED.



Structural component only
DWG# T-2007064

JOB NAME 408150	TRUSS NAME T2	QUANTITY 2	PLY 1	JOB DESC. GREEN PARK HOMES	DRWG NO.
Tamarack Roof Truss, Burlington				Version 8.310 5 Oct 29 2019 Mitek Industries, Inc. Sat Apr 25 11:02:50 2020 Page 1	
				ID:7vF7aG0E03cRUj6X1iSrKzWYK-w1MqjFT2qdMuZ416IZBXmNxiPs5Wt3nJxHzNCnZ	



LUMBER

N. L. G. A. RULES

CHORDS	SIZE	LUMBER
R - A	2x4	DRY No.2
A - C	2x4	DRY No.2
C - G	2x4	DRY No.2
G - I	2x4	DRY No.2
J - I	2x4	DRY No.2
R - O	2x4	DRY No.2
O - M	2x4	DRY No.2
M - J	2x4	DRY No.2

ALL WEBS 2x3 DRY No.2
DRY: SEASONED LUMBER.

DESCR.

SPF
SPF
SPF
SPF
SPF
SPF
SPF
SPF
SPF

DIMENSIONS, SUPPORTS AND LOADINGS SPECIFIED BY FABRICATOR TO BE VERIFIED BY BUILDING DESIGNER

BEARINGS

JT	FACTORED GROSS REACTION		MAXIMUM FACTORED GROSS REACTION		INPUT BRG	RECORD BRG
	VERT	HORZ	DOWN	HORZ		
R	1920	0	1920	0	3-8	3-8
J	1920	0	1920	0	3-8	3-8

UNFACTORED REACTIONS

JT	1ST CASE		MAX. MIN. COMPONENT REACTIONS			
	COMBINED	SNOW	LIVE	PERM. LIVE	WIND	DEAD
R	1358	891 / 0	0 / 0	0 / 0	0 / 0	467 / 0
J	1358	891 / 0	0 / 0	0 / 0	0 / 0	467 / 0

BEARING MATERIAL TO BE SPF NO.2 OR BETTER AT JOINT(S) R, J

BRACING

TOP CHORD TO BE SHEATHED OR MAX. PURLIN SPACING = 3.23 FT.
MAX. UNBRACED BOTTOM CHORD LENGTH = 10.00 FT OR RIGID CEILING DIRECTLY APPLIED.

ALL PITCH BREAKS AND PERIMETER CORNER JOINTS MUST BE Laterally RESTRAINED.

LOADING

TOTAL LOAD CASES: (4)

CHORDS			W E B S		
MEMB.	MAX. FACTORED FORCE (LBS)	FACTORED VERT. LOAD (PLF)	MAX. UNBRACED LENGTH	MEMB.	MAX. FACTORED FORCE (LBS)
FR-TO		FROM TO		FR-TO	
R-A	-1875 / 0	0.0 0.0	0.83 (1)	K-I	0 / 2630
A-B	-2042 / 0	-91.8 -91.8	0.59 (1)	A-Q	0 / 2630
B-C	-3149 / 0	-91.8 -91.8	0.74 (1)	K-H	-1535 / 0
C-D	-3149 / 0	-91.8 -91.8	0.74 (1)	Q-B	-1535 / 0
D-E	-3533 / 0	-91.8 -91.8	0.68 (1)	L-H	0 / 1444
E-F	-3533 / 0	-91.8 -91.8	0.68 (1)	B-P	0 / 1444
F-G	-3149 / 0	-91.8 -91.8	0.74 (1)	L-F	-826 / 0
G-H	-3149 / 0	-91.8 -91.8	0.74 (1)	P-D	-826 / 0
H-I	-2042 / 0	-91.8 -91.8	0.59 (1)	N-F	0 / 502
I-J	-1875 / 0	0.0 0.0	0.83 (1)	D-N	0 / 502
R-Q	0 / 0	-18.5 -18.5	0.15 (4)	N-E	-537 / 0
Q-P	0 / 2042	-18.5 -18.5	0.40 (1)		
P-O	0 / 3149	-18.5 -18.5	0.58 (1)		
O-N	0 / 3149	-18.5 -18.5	0.58 (1)		
N-M	0 / 3149	-18.5 -18.5	0.58 (1)		
M-L	0 / 3149	-18.5 -18.5	0.58 (1)		
L-K	0 / 2042	-18.5 -18.5	0.40 (1)		
K-J	0 / 0	-18.5 -18.5	0.15 (4)		

TOTAL WEIGHT = 2 X 143 = 286 lb

DESIGN CRITERIA

SPECIFIED LOADS:

TOP CH. LL	= 25.6 PSF
DL	= 8.0 PSF
BOT CH. LL	= 0.0 PSF
DL	= 7.4 PSF
TOTAL LOAD	= 39.0 PSF

SPACING = 24.0 IN. C/C

LOADING IN FLAT SECTION BASED ON A SLOPE OF 8.00/12

THIS TRUSS IS DESIGNED FOR RESIDENTIAL OR SMALL BUILDING REQUIREMENTS OF PART 9, NBC 2010, NBC 2015

THIS DESIGN COMPLIES WITH:

- PART 9 OF CBC 2018, CBC 2012, ABC 2019
- PART 9 OF CBC 2012 (2019 AMENDMENT)
- CSA 086-09, CSA 086-14
- TPIC 2011, TPIC 2014

(55% OF 31.3 P.S.F. G.S.L. PLUS 8.4 P.S.F. RAIN LOAD) EQUALS 25.6 P.S.F. SPECIFIED ROOF LIVE LOAD

ALLOWABLE DEFL. (LL) = $L/360$ (1.16")
CALCULATED VERT. DEFL. (LL) = $L/999$ (0.23")
ALLOWABLE DEFL. (TL) = $L/360$ (1.16")
CALCULATED VERT. DEFL. (TL) = $L/995$ (0.42")

CSI: TC=0.83/1.00 (A-R:1), BC=0.58/1.00 (N-P:1),
WB=0.59/1.00 (K-I:1), SS=0.25/1.00 (A-B:1)

DOL LUMBER=1.00 NAIL=1.00 LS BEND=1.10
COMP=1.10 SHEAR=1.10 TENS=1.10

COMPANION LIVE LOAD FACTOR = 1.00

TRUSS PLATE MANUFACTURER IS NOT RESPONSIBLE FOR QUALITY CONTROL IN THE TRUSS MANUFACTURING PLANT.

NAIL VALUES


PLATE GRIP (DRY)	SHEAR	SECTION
(PSI)	(PLI)	(PL)
MAX MIN	MAX MIN	MAX MIN
MT20	618	354
	1657	788
	1987	1658

PLATE PLACEMENT TOL. = 0.250 inches

PLATE ROTATION TOL. = 5.0 Deg.

JSI GRIP=0.89 (A) (INPUT = 0.99)


JSI METAL=0.99 (M) (INPUT = 1.00)



Structural component only
DWG# T-2007065

JOB NAME 408150	TRUSS NAME T3	QUANTITY 2	PLY 1	JOB DESC. GREEN PARK HOMES	DRWG NO.
Tamarack Roof Truss, Burlington				TRUSS DESC.	

Version 8.310 S Oct 29 2019 Mitek Industries, Inc. Sat Apr 25 11:02:51 2020 Page 1
 ID:7vF7aG0E03cRUj6X1SrkziWYK-OEw2wbUhbclDWfxbqpokJk233bSy0IRTUVjzNCnY
 Scale = 1:54.4



LUMBER			
N. L. G. A. RULES	CHORDS	SIZE	LUMBER
R - A	2x4	DRY	No.2
A - C	2x4	DRY	No.2
C - G	2x4	DRY	No.2
G - I	2x4	DRY	No.2
J - I	2x4	DRY	No.2
R - O	2x4	DRY	No.2
O - M	2x4	DRY	No.2
M - J	2x4	DRY	No.2
ALL WEBS 2x3 DRY, SEASONED LUMBER.			

PLATES (table in inches)				
JT	TYPE	PLATES	W	LEN Y X
A	TMWW-I	MT20	5.0	6.0 2.00 2.50
B	TMWW-I	MT20	5.0	6.0
C	TS-I	MT20	3.0	6.0
D	TMWW-I	MT20	4.0	4.0
E	TMWW-I	MT20	2.0	4.0
F	TMWW-I	MT20	4.0	4.0
G	TS-I	MT20	3.0	6.0
H	TMWW-I	MT20	5.0	6.0
I	TMWW-I	MT20	5.0	6.0 2.00 2.50
J	BMV-I-p	MT20	3.0	4.0
K	BMWW-I	MT20	5.0	6.0 2.00 2.50
L	BMWW-I	MT20	5.0	6.0
M	BS-I	MT20	3.0	6.0
N	BMWW-I	MT20	4.0	9.0
O	BS-I	MT20	3.0	6.0
P	BMWW-I	MT20	5.0	6.0
Q	BMWW-I	MT20	5.0	6.0 2.00 2.50
R	BMV-I-p	MT20	3.0	4.0

DIMENSIONS, SUPPORTS AND LOADINGS SPECIFIED BY FABRICATOR TO BE VERIFIED BY BUILDING DESIGNER

BEARINGS		FACTORED GROSS REACTION		MAXIMUM FACTORED GROSS REACTION		INPUT BRG		REQD BRG	
JT	VERT	HORZ	DOWN	HORZ	UPLIFT	IN-SX	IN-SX	BRG	IN-SX
R	1920	0	1920	0	0	3-8	3-8	3-8	3-8
J	1920	0	1920	0	0	3-8	3-8	3-8	3-8

UNFACTORED REACTIONS		1ST CASE		MAX MIN COMPONENT REACTIONS		PERMANENT WIND		DEAD		SOIL	
JT	COMBINED	SNOW	LIVE	PERMANENT	WIND	DEAD	SOIL	COMBINED	SNOW	LIVE	PERMANENT
R	1358	891 / 0	0 / 0	0 / 0	0 / 0	467 / 0	0 / 0	1358	891 / 0	0 / 0	0 / 0
J	1358	891 / 0	0 / 0	0 / 0	0 / 0	467 / 0	0 / 0	1358	891 / 0	0 / 0	0 / 0

BEARING MATERIAL TO BE SPF NO.2 OR BETTER AT JOINT(S) R, J

BRACING
 TOP CHORD TO BE SHEATHED OR MAX. PURLIN SPACING = 3.58 FT.
 MAX. UNBRACED BOTTOM CHORD LENGTH = 10.00 FT OR RIGID CEILING DIRECTLY APPLIED.

ALL PITCH BREAKS AND PERIMETER CORNER JOINTS MUST BE Laterally RESTRAINED.

1 LATERAL BRACE(S) AT 1/2 LENGTH OF A-R, I-J.

END VERTICAL(S) MUST BE SHEATHED OR HAVE BRACES AS INDICATED IN THE MAX. UNBRACED LENGTH COLUMN OF THE TABLE BELOW

LOADING
 TOTAL LOAD CASES: (4)

CHORDS		MAX. FACTORED		WEBS		MAX. FACTORED	
MEMB.	FORCE (LBS)	VERT. LOAD (PLF)	MAX. CSI (LC)	MEMB.	FORCE (LBS)	MAX. CSI (LC)	MAX. CSI (LC)
FR-TO		FROM TO		FR-TO			
R-A	-1875 / 0	0.0	0.0 0.33 (1)	K-I	0 / 2368	0.53 (1)	
A-B	-1691 / 0	-91.8	-91.8 0.55 (1)	A-Q	0 / 2368	0.53 (1)	
B-C	-2608 / 0	-91.8	-91.8 0.66 (1)	K-H	-1536 / 0	0.80 (1)	
C-D	-2608 / 0	-91.8	-91.8 0.66 (1)	Q-B	-1536 / 0	0.80 (1)	
D-E	-2627 / 0	-91.8	-91.8 0.66 (1)	L-H	0 / 1304	0.29 (1)	
E-F	-2627 / 0	-91.8	-91.8 0.66 (1)	B-P	0 / 1304	0.29 (1)	
F-G	-2608 / 0	-91.8	-91.8 0.66 (1)	L-F	-826 / 0	0.48 (1)	
G-H	-2608 / 0	-91.8	-91.8 0.66 (1)	P-D	-826 / 0	0.48 (1)	
H-I	-1691 / 0	-91.8	-91.8 0.55 (1)	N-F	0 / 453	0.10 (1)	
I-J	-1875 / 0	0.0	0.0 0.33 (1)	D-N	0 / 453	0.10 (1)	
				N-E	-537 / 0	0.31 (1)	
R-Q	0 / 0	-18.5	-18.5 0.15 (4)				
Q-P	0 / 1891	-18.5	-18.5 0.35 (1)				
P-O	0 / 2608	-18.5	-18.5 0.47 (1)				
O-N	0 / 2608	-18.5	-18.5 0.47 (1)				
N-M	0 / 2608	-18.5	-18.5 0.47 (1)				
M-L	0 / 2608	-18.5	-18.5 0.47 (1)				
L-K	0 / 1691	-18.5	-18.5 0.35 (1)				
K-J	0 / 0	-18.5	-18.5 0.15 (4)				

TOTAL WEIGHT = 2 X 153 = 305 lb

DESIGN CRITERIA

SPECIFIED LOADS:
 TOP CH. LL = 25.6 PSF
 DL = 6.0 PSF
 BOT CH. LL = 0.0 PSF
 DL = 7.4 PSF
 TOTAL LOAD = 39.0 PSF

SPACING = 24.0 IN. C/C

LOADING IN FLAT SECTION BASED ON A SLOPE OF 6.00/12

THIS TRUSS IS DESIGNED FOR RESIDENTIAL OR SMALL BUILDING REQUIREMENTS OF PART 9, NBC 2010, NBC 2015

THIS DESIGN COMPLIES WITH:
 - PART 9 OF NBC 2010, NBC 2012, ABC 2019
 - PART 9 OF NBC 2012 (2019 AMENDMENT)
 - CSA 086-09, CSA 086-14
 - TPIC 2011, TPIC 2014

(55% OF 31.3 P.S.F. G.S.L. PLUS 8.4 P.S.F. RAIN LOAD) EQUALS 25.6 P.S.F. SPECIFIED ROOF LIVE LOAD

ALLOWABLE DEFL.(LL) = L/360 (1.16")
 CALCULATED VERT. DEFL.(LL) = L/999 (0.18")
 ALLOWABLE DEFL.(TL) = L/360 (1.16")
 CALCULATED VERT. DEFL.(TL) = L/999 (0.33")

CSI: TC=0.66/1.00 (F-H:1), BC=0.47/1.00 (N-P:1), WB=0.90/1.00 (H-K:1), SSI=0.25/1.00 (A-B:1)

DOL LUMBER=1.00 NAIL=1.00 LS BEND=1.10
 COMP=1.10 SHEAR=1.10 TENS=1.10

COMPANION LIVE LOAD FACTOR = 1.00


TRUSS PLATE MANUFACTURER IS NOT RESPONSIBLE FOR QUALITY CONTROL IN THE TRUSS MANUFACTURING PLANT

NAIL VALUES
 PLATE GRIP(DRY) SHEAR SECTION (PL) (PL)
 MAX MIN MAX MIN MAX MIN
 MT20 618 354 1687 788 1987 1658

PLATE PLACEMENT TOL. = 0.250 inches

PLATE ROTATION TOL. = 5.0 Deg.


JSI GRIP= 0.88 (I) (INPUT = 0.90)
 JSI METAL= 0.83 (M) (INPUT = 1.00)



Structural component only
 DWG# T-2007066

JOB NAME 408150	TRUSS NAME T4	QUANTITY 2	PLY 1	JOB DESC. GREEN PARK HOMES	DRWG NO.
Tamarack Roof Truss, Burlington				TRUSS DESC.	

Version 8.310 S Oct 29 2019 MITek Industries, Inc. Sat Apr 25 11:02:52 2020 Page 1
ID:7vF7aG0E03cRUj6X1j8kziWYK-sQUQ8wVJmV47IE88XL1GyrhNSQJK?9W4C12AzNCnX



LUMBER			
N. L. G. A. RULES	SIZE	LUMBER	DESCR.
CHORDS			
P - A	2x4	DRY	No.2
A - C	2x4	DRY	No.2
C - F	2x4	DRY	No.2
F - H	2x4	DRY	No.2
H - I	2x4	DRY	No.2
I - N	2x4	DRY	No.2
N - K	2x4	DRY	No.2
K - L	2x4	DRY	No.2
ALL WEBS	2x3	DRY	No.2
EXCEPT			
J - H	2x4	DRY	No.2

DRY: SEASONED LUMBER.

PLATES (table is in inches)					
JT	TYPE	PLATES	W	LEN	Y X
A	TMVW-I	MT20	5.0	6.0	2.25 2.00
B	TMVW-I	MT20	4.0	6.0	
C	TS-I	MT20	3.0	6.0	
D	TMVW-I	MT20	4.0	4.0	
E	TMVW-I	MT20	2.0	4.0	
F	TS-I	MT20	3.0	6.0	
G	TMVW-I	MT20	4.0	6.0	
H	TMVW-I	MT20	5.0	6.0	2.50 2.50
I	BMV1+p	MT20	3.0	4.0	
J	BMVW-I	MT20	5.0	6.0	2.50 2.50
K	BS-I	MT20	3.0	6.0	
L	BMVW-I	MT20	4.0	9.0	
M	BMVW-I	MT20	4.0	6.0	
N	BS-I	MT20	3.0	6.0	
O	BMVW-I	MT20	5.0	6.0	2.00 2.50
P	BMV1+p	MT20	3.0	4.0	

DIMENSIONS, SUPPORTS AND LOADINGS SPECIFIED BY FABRICATOR TO BE VERIFIED BY BUILDING DESIGNER

FACTORED		MAXIMUM FACTORED		INPUT		REQRD	
JT	VERT	GROSS REACTION	GROSS REACTION	BRG	BRG	IN-SX	IN-SX
P	1920	0	1920	0	0	3-8	3-8
I	1920	0	1920	0	0	3-8	3-8

UNFACTORED REACTIONS

1ST LCASE		MAX/MIN. COMPONENT REACTIONS		WIND		DEAD		SOIL	
JT	COMBINED	SNOW	LIVE	PERM. LIVE	WIND	DEAD	SOIL	PERM. LIVE	WIND
P	1358	891/0	0/0	0/0	0/0	467/0	0/0	0/0	0/0
I	1358	891/0	0/0	0/0	0/0	467/0	0/0	0/0	0/0

BEARING MATERIAL TO BE SPF NO.2 OR BETTER AT JOINT(S) P, I

BRACING

TOP CHORD TO BE SHEATHED OR MAX. FURLIN SPACING = 3.31 FT.
MAX. UNBRACED BOTTOM CHORD LENGTH = 10.00 FT. OR RIGID CEILING DIRECTLY APPLIED.

ALL PITCH BREAKS AND PERIMETER CORNER JOINTS MUST BE Laterally RESTRAINED.

1 LATERAL BRACE(S) AT 1/2 LENGTH OF A-P, H-I, B-O, D-L, G-J.

END VERTICAL(S) MUST BE SHEATHED OR HAVE BRACES AS INDICATED IN THE MAX. UNBRACED LENGTH COLUMN OF THE TABLE BELOW

LOADING

TOTAL LOAD CASES: (4)

CHORDS		FACTORED		W E B S		FACTORED	
MEMB.	FORCE (LBS)	VERT. LOAD	LC1 MAX	MEMB.	FORCE (LBS)	VERT. LOAD	LC1 MAX
FR-TO		FROM	TO	FR-TO		FROM	TO
P-A	-1888/0	0.0	0.0 0.43 (1)	A-O	0/2315	0.52 (1)	0.52 (1)
A-B	-1882/0	-91.8	-91.8 0.82 (1)	O-B	-1465/0	0.47 (1)	0.47 (1)
B-C	-2416/0	-91.8	-91.8 0.95 (1)	B-M	0/1058	0.24 (1)	0.24 (1)
C-D	-2416/0	-91.8	-91.8 0.96 (1)	M-D	-917/0	0.54 (1)	0.54 (1)
D-E	-2415/0	-91.8	-91.8 0.74 (1)	D-L	-2/0	0.00 (1)	0.00 (1)
E-F	-2415/0	-91.8	-91.8 0.96 (1)	L-E	-616/0	0.54 (1)	0.54 (1)
F-G	-2415/0	-91.8	-91.8 0.96 (1)	L-G	0/1054	0.24 (1)	0.24 (1)
G-H	-1883/0	-91.8	-91.8 0.82 (1)	J-G	-1465/0	0.47 (1)	0.47 (1)
H-I	-1888/0	0.0	0.0 0.43 (1)	J-H	0/2316	0.37 (1)	0.37 (1)
P-O	0/0	-18.5	-18.5 0.22 (4)				
O-N	0/1862	-18.5	-18.5 0.39 (1)				
N-M	0/1862	-18.5	-18.5 0.39 (1)				
M-L	0/2416	-18.5	-18.5 0.47 (1)				
L-K	0/1863	-18.5	-18.5 0.39 (1)				
K-J	0/1863	-18.5	-18.5 0.39 (1)				
J-I	0/0	-18.5	-18.5 0.22 (4)				

TOTAL WEIGHT = 2 X 157 = 313 lb

DESIGN CRITERIA

SPECIFIED LOADS:

TOP CH. LL = 25.8 PSF
DL = 8.0 PSF
BOT CH. LL = 0.0 PSF
DL = 7.4 PSF
TOTAL LOAD = 39.0 PSF

SPACING = 24.0 IN./C

LOADING IN FLAT SECTION BASED ON A SLOPE OF 6.00/12

THIS TRUSS IS DESIGNED FOR RESIDENTIAL OR SMALL BUILDING REQUIREMENTS OF PART 9, NBCC 2010, NBCC 2015

THIS DESIGN COMPLIES WITH:

- PART 9 OF BCBC 2018, OBC 2012, ABC 2019
- PART 9 OF OBC 2012 (2019 AMENDMENT)
- CSA 088-09, CSA 088-14
- TPIC 2011, TPIC 2014

(55% OF 31.3 P.S.F. G.S.L. PLUS 8.4 P.S.F. RAIN LOAD) EQUALS 25.8 P.S.F. SPECIFIED ROOF LIVE LOAD

ALLOWABLE DEFL.(LL) = L/380 (1.16")
CALCULATED VERT. DEFL.(LL) = L/899 (0.15")
ALLOWABLE DEFL.(TL) = L/360 (1.16")
CALCULATED VERT. DEFL.(TL) = L/899 (0.29")

CSI: TC=0.96/1.00 (E-G:1), BC=0.47/1.00 (L-M:1),
WB=0.54/1.00 (D-M:1), SS=0.30/1.00 (G-H:1)

DOL LUMBER=1.00 NAIL=1.00 LS BEND=1.10
COMP=1.10 SHEAR=1.10 TENS=1.10

COMPANION LIVE LOAD FACTOR = 1.00.

TRUSS PLATE MANUFACTURER IS NOT RESPONSIBLE FOR QUALITY CONTROL IN THE TRUSS MANUFACTURING PLANT.

NAIL VALUES
PLATE GRIP(DRY) SHEAR SECTION
(PSI) (PLI) (PLI)
MAX MIN MAX MIN MAX MIN
MT20 618 354 1667 788 1987 1856

PLATE PLACEMENT TOL. = 0.250 inches

PLATE ROTATION TOL. = 5.0 Deg.


JSI GRIP = 0.90 (A) (INPUT = 0.90)
JSI METAL = 0.53 (K) (INPUT = 1.00)



Structural component only
DWG# T-2007067

JOB NAME 408150	TRUSS NAME T5	QUANTITY 10	PLY 1	JOB DESC. GREEN PARK HOMES	DRWG NO.
Tamarack Roof Truss, Burlington					

Version 8.310 S Oct 29 2019 Mitek Industries, Inc. Sat Apr 25 11:02:53 2020 Page 1
 ID:7vF7aG0E03cRUj6X1SskziWYK-Kc2pLGVx7D?x10pKiFsGp9Os5sl13ONJkybac2NcW
 34-9-5 34-10-0
 Scale = 1/4" = 1'-0"



LUMBER			
N. L. G. A. RULES	SIZE	LUMBER	DESCR.
CHORDS			
P - A	2x4	DRY	No.2
A - C	2x4	DRY	No.2
C - F	2x4	DRY	No.2
F - H	2x4	DRY	No.2
I - N	2x4	DRY	No.2
N - K	2x4	DRY	No.2
K - I	2x4	DRY	No.2
ALL WEBS	2x4	DRY	No.2
EXCEPT			
J - G	2x3	DRY	No.2
O - B	2x3	DRY	No.2
L - E	2x3	DRY	No.2
M - D	2x3	DRY	No.2

DRY: SEASONED LUMBER.

DIMENSIONS, SUPPORTS AND LOADINGS SPECIFIED BY FABRICATOR TO BE VERIFIED BY BUILDING DESIGNER

BEARINGS		FACTORED	MAXIMUM FACTORED	INPUT	RECORD
		GROSS REACTION	GROSS REACTION	BRG	BRG
JT	VERT	VERT	DOWN	UP	UP
P	1920	0	1920	0	0
I	1920	0	1920	0	0

UNFACTORED REACTIONS

1ST LCASE	MAX. MIN. COMPONENT REACTIONS						
JT	COMBINED	SNOW	LIVE	PERM. LIVE	WIND	DEAD	SOIL
P	1358	891 / 0	0 / 0	0 / 0	0 / 0	467 / 0	0 / 0
I	1358	891 / 0	0 / 0	0 / 0	0 / 0	467 / 0	0 / 0

BEARING MATERIAL TO BE SPF NO.2 OR BETTER AT JOINT(S) P, I

BRACING

TOP CHORD TO BE SHEATHED OR MAX. PURLIN SPACING = 3.56 FT.
 MAX. UNBRACED BOTTOM CHORD LENGTH = 10.00 FT. OR RIGID CEILING DIRECTLY APPLIED.

ALL PITCH BREAKS AND PERIMETER CORNER JOINTS MUST BE Laterally RESTRAINED.

1 LATERAL BRACE(S) AT 1/2 LENGTH OF A-P, H-I, G-J, B-O, E-M.

END VERTICAL(S) MUST BE SHEATHED OR HAVE BRACES AS INDICATED IN THE MAX. UNBRACED LENGTH COLUMN OF THE TABLE BELOW

LOADING

TOTAL LOAD CASES: (4)

CHORDS		FACTORED		WEBS	
MEMB.	FORCE (LBS)	VERT. LOAD (PLF)	MAX. CS (LC)	MEMB.	FORCE (LBS)
FR-TO				FR-TO	
P-A	-1868 / 0	0.0	0.0 0.55 (1)	J-H	0 / 2171
A-B	-1458 / 0	-91.8	-91.8 0.80 (1)	A-O	0 / 2171
B-C	-2108 / 0	-91.8	-91.8 0.90 (1)	J-G	-1463 / 0
C-D	-2108 / 0	-91.8	-91.8 0.90 (1)	O-B	-1462 / 0
D-E	-2108 / 0	-91.8	-91.8 0.88 (1)	L-G	0 / 982
E-F	-2108 / 0	-91.8	-91.8 0.90 (1)	B-M	0 / 980
F-G	-2108 / 0	-91.8	-91.8 0.90 (1)	L-E	-613 / 0
G-H	-1458 / 0	-91.8	-91.8 0.79 (1)	M-D	-612 / 0
H-I	-1868 / 0	0.0	0.0 0.55 (1)	M-E	-2 / 0
P-O	0 / 0	-18.5	-18.5 0.22 (4)		
O-N	0 / 1458	-18.5	-18.5 0.36 (1)		
N-M	0 / 1458	-18.5	-18.5 0.36 (1)		
M-L	0 / 2108	-18.5	-18.5 0.42 (1)		
L-K	0 / 1458	-18.5	-18.5 0.36 (1)		
K-J	0 / 1458	-18.5	-18.5 0.36 (1)		
J-I	0 / 0	-18.5	-18.5 0.22 (4)		

TOTAL WEIGHT = 10 X 178 = 1785 lb

DESIGN CRITERIA

SPECIFIED LOADS:

TOP CH. LL = 25.6 PSF
 DL = 6.0 PSF
 BOT CH. LL = 0.0 PSF
 DL = 7.4 PSF
 TOTAL LOAD = 39.0 PSF

SPACING = 24.0 IN. C/C

LOADING IN FLAT SECTION BASED ON A SLOPE OF 6.00/12

THIS TRUSS IS DESIGNED FOR RESIDENTIAL OR SMALL BUILDING REQUIREMENTS OF PART 9, NBCC 2010, NBCC 2015

THIS DESIGN COMPLIES WITH:

- PART 9 OF BCBC 2018, OBC 2012, ABC 2019
- PART 9 OF OBC 2012 (2019 AMENDMENT)
- CSA 086-08, CSA 086-14
- TPIC 2011, TPIC 2014

(65% OF 31.3 P.S.F. G.S.L. PLUS 8.4 P.S.F. RAIN LOAD) EQUALS 25.6 P.S.F. SPECIFIED ROOF LIVE LOAD

ALLOWABLE DEFL.(LL) = L/360 (1.16")
 CALCULATED VERT. DEFL.(LL) = L/999 (0.12")
 ALLOWABLE DEFL.(TL) = L/360 (1.16")
 CALCULATED VERT. DEFL.(TL) = L/999 (0.24")

CSI: TC=0.90/1.00 (B-D:1), BC=0.42/1.00 (L-M:1), WB=0.78/1.00 (E-L:1), SS=0.31/1.00 (A-B:1)

DOL LUMBER=1.00 NAIL=1.00 LS BEND=1.10 COMP=1.10 SHEAR=1.10 TENS=1.10

COMPANION LIVE LOAD FACTOR = 1.00

TRUSS PLATE MANUFACTURER IS NOT RESPONSIBLE FOR QUALITY CONTROL IN THE TRUSS MANUFACTURING PLANT.


NAIL VALUES

PLATE GRIP(DRY) SHEAR SECTION (PSI) (PLI) (PLI)
 MAX MIN MAX MIN
 MT20 618 354 1667 788 1967 1656

PLATE PLACEMENT TOL. = 0.250 inches


PLATE ROTATION TOL. = 5.0 Deg.

JSI GRIP= 0.87 (A) (INPUT = 0.90)
 JSI METAL= 0.47 (N) (INPUT = 1.00)



Structural component only
 DWG# T-2007068

JOB NAME	TRUSS NAME	QUANTITY	PLY	JOB DESC.	DRWG NO.
408150	T6	1	1	GREEN PARK HOMES	
Tamarack Roof Truss, Burlington					



Version 8.310 S Oct 29 2019 Mitek Industries, Inc. Sat Apr 25 11:02:54 2020 Page 1
ID:17vF?aG0E03cRUj6X1SrkzIWK-oppBZcXZuX7oNAOWGyNVLNxAAG1Foy0S_Oh862ZNCrV

LUMBER				DIMENSIONS, SUPPORTS AND LOADINGS SPECIFIED BY FABRICATOR TO BE VERIFIED BY BUILDING DESIGNER										TOTAL WEIGHT = 84 lb				
N. L. G. A. RULES				BEARINGS										DESIGN CRITERIA				
CHORDS	SIZE	DRY	LUMBER	DESCR.	FACTORED		MAXIMUM FACTORED		INPUT	REORD	SPECIFIED LOADS:							
A - C	2x4	DRY	No.2	SPF	GROSS REACTION		GROSS REACTION		BRG	BRG	TOP CH. LL =	25.6 PSF						
C - E	2x4	DRY	No.2	SPF	JT	VERT	HORZ	UPLIFT	IN-SX	IN-SX	DL =	6.0 PSF						
E - G	2x4	DRY	No.2	SPF	M	1888	0	1888	0	5-8	BOT CH. LL =	0.0 PSF						
M - B	2x4	DRY	No.2	SPF	H	1422	0	1422	0	5-8	DL =	7.4 PSF						
H - F	2x4	DRY	No.2	SPF	UNFACTORED REACTIONS								TOTAL LOAD = 39.0 PSF					
M - J	2x6	DRY	No.2	SPF									1ST LOASE		MAX. MIN. COMPONENT REACTIONS		SPACING = 24.0 IN. C/C	
J - H	2x8	DRY	No.2	SPF														
ALL WEBS	2x3	DRY	No.2	SPF														

PLATES (table is in inches)

JT TYPE	PLATES	W	LEN	Y	X
B TMVW+p	MT20	5.0	6.0	Edge	2.75
C TTWW+m	MT20	5.0	8.0	2.00	1.50
D TMVW+w	MT20	2.0	4.0		
E TTWW+m	MT20	5.0	8.0	2.00	1.50
F TMVW+p	MT20	5.0	8.0	Edge	2.75
H BMV1+p	MT20	3.0	5.0		
I BMVW+p	MT20	5.0	8.0	2.50	2.75
J BS+1	MT20	5.0	8.0		
K BMVWW+1	MT20	5.0	8.0		
L BMVW+1	MT20	5.0	8.0	2.50	2.75
M BMV1+p	MT20	3.0	5.0		

Edge - INDICATES REFERENCE CORNER OF PLATE TOUCHES EDGE OF CHORD.

UNFACTORED REACTIONS

JT	COMBINED	SNOW	LIVE	PERM.LIVE	WIND	DEAD	SOIL
M	1329	909 / 0	0 / 0	0 / 0	0 / 0	420 / 0	0 / 0
H	1001	683 / 0	0 / 0	0 / 0	0 / 0	318 / 0	0 / 0

BEARING MATERIAL TO BE SPF NO.2 OR BETTER AT JOINT(S) M, H

BRACING

TOP CHORD TO BE SHEATHED OR MAX. PURLIN SPACING = 4.55 FT.
MAX. UNBRACED BOTTOM CHORD LENGTH = 10.00 FT OR RIGID CEILING DIRECTLY APPLIED.

ALL PITCH BREAKS AND PERIMETER CORNER JOINTS MUST BE Laterally RESTRAINED.

LOADING

TOTAL LOAD CASES: (4)

CHORDS				WEBS			
MEMB.	MAX. FACTORED FORCE (LBS)	FACTORED VERT. LOAD (PLF)	MAX. LC1 (LC)	MEMB.	MAX. FACTORED FORCE (LBS)	MAX. UNBRACED LENGTH (FT)	MAX. LC1 (LC)
FR-TO		FROM TO		FR-TO			
A-B	0 / 41	-91.8	-91.8 0.14 (1)	10.00	L-C	0 / 383	0.08 (1)
B-C	-1847 / 0	-91.8	-91.8 0.34 (1)	4.55	C-K	0 / 310	0.08 (1)
C-D	-1841 / 0	-91.8	-91.8 0.36 (1)	4.72	K-D	-481 / 0	0.16 (1)
D-E	-1841 / 0	-91.8	-91.8 0.36 (1)	4.72	K-E	0 / 1010	0.25 (1)
E-F	-1225 / 0	-91.8	-91.8 0.30 (1)	5.40	I-E	-274 / 0	0.08 (1)
F-G	0 / 41	-91.8	-91.8 0.14 (1)	10.00	B-L	0 / 1480	0.37 (1)
M-B	-1928 / 0	0.0	0.0 0.22 (1)	8.01	I-F	0 / 981	0.24 (1)
H-F	-1380 / 0	0.0	0.0 0.16 (1)	8.88			
M-N	0 / 0	-18.5	-18.5 0.24 (1)	10.00			
N-L	0 / 0	-18.5	-18.5 0.24 (1)	10.00			
L-O	0 / 1424	-18.5	-18.5 0.70 (1)	10.00			
O-K	0 / 1424	-18.5	-18.5 0.70 (1)	10.00			
K-J	0 / 932	-18.5	-18.5 0.29 (1)	10.00			
J-I	0 / 932	-18.5	-18.5 0.29 (1)	10.00			
I-H	0 / 0	-18.5	-18.5 0.04 (4)	10.00			

FACTORED CONCENTRATED LOADS (LBS)

JT	LOC.	LC1	MAX-	MAX+	FACE	DIR.	TYPE	HEEL	CONN.
C	3-10-8	-241	-241		FRONT	VERT	TOTAL		C1
L	3-11-4	-17	-17		FRONT	VERT	TOTAL		C1
N	2-0-12	-17	-17		FRONT	VERT	TOTAL		C1
O	5-6-8	-953	-953		FRONT	VERT	TOTAL		C1

CONNECTION REQUIREMENTS

1) C1: A SUITABLE HANGER/MECHANICAL CONNECTION IS REQUIRED.

DESIGN CRITERIA

SPECIFIED LOADS:
TOP CH. LL = 25.6 PSF
DL = 6.0 PSF
BOT CH. LL = 0.0 PSF
DL = 7.4 PSF
TOTAL LOAD = 39.0 PSF

SPACING = 24.0 IN. C/C

LOADING IN FLAT SECTION BASED ON A SLOPE OF 6.00/12

THIS TRUSS IS DESIGNED FOR RESIDENTIAL OR SMALL BUILDING REQUIREMENTS OF PART 9, NBCC 2010, NBCC 2015

THIS DESIGN COMPLIES WITH:

- PART 9 OF BCBC 2018, CBC 2012, ABC 2019
- PART 9 OF CBC 2012 (2019 AMENDMENT)
- CSA 089-08, CSA 089-14
- TPC 2011, TPC 2014

(55% OF 31.3 P.S.F. G.S.L. PLUS 8.4 P.S.F. RAIN LOAD) EQUALS 25.6 P.S.F. SPECIFIED ROOF LIVE LOAD

ALLOWABLE DEFL.(LL) = 1/360 (0.55")
CALCULATED VERT. DEFL.(LL) = 1/999 (0.06")
ALLOWABLE DEFL.(TL) = 1/360 (0.55")
CALCULATED VERT. DEFL.(TL) = 1/999 (0.10")

CSI: TC=0.36/1.00 (C-D:1), BC=0.70/1.00 (K-L:1), WB=0.37/1.00 (B-L:1), SS=0.45/1.00 (K-L:1)

DOL LUMBER=1.00 NAIL=1.00 LB BEND=1.00
COMP=1.00 SHEAR=1.00 TENS=1.00

COMPANION LIVE LOAD FACTOR = 1.00

TRUSS PLATE MANUFACTURER IS NOT RESPONSIBLE FOR QUALITY CONTROL IN THE TRUSS MANUFACTURING PLANT.

NAIL VALUES

PLATE	GRIP(DRY)	SHEAR	SECTION
	(PSI)	(PLI)	(PLI)
	MAX MIN	MAX MIN	MAX MIN
MT20	618 354	1897 789	1987 1656

PLATE PLACEMENT TOL. = 0.250 inches

PLATE ROTATION TOL. = 5.0 Deg.

JSI GRIP= 0.89 (C) (INPUT = 0.90)
JSI METAL= 0.57 (J) (INPUT = 1.00)




Structural component only
DWG# T-2007069

JOB NAME	TRUSS NAME	QUANTITY	PLY	JOB DESC.	GREEN PARK HOMES	DRWG NO.
408150	17	1	1	TRUSS DESC.		

Tamarack Roof Truss, Burlington

Version 8.310 S Oct 29 2019 MTEK Industries, Inc. Sat Apr 25 11:02:55 2020 Page 1
ID:j7vF?aG0E03cRUj6X1iSkzjWYK-G?AZmyXBtqFi_KyiqfukuaTK3fVZXS_cD2RiVzNCnU



Scale = 1/25

LUMBER						
N. L. G. A. RULES						
CHORDS		SIZE	LUMBER		DESCR.	
A - B	2x4	DRY	No.2		SPF	
B - C	2x4	DRY	No.2		SPF	
C - D	2x4	DRY	No.2		SPF	
D - E	2x4	DRY	No.2		SPF	
E - F	2x4	DRY	No.2		SPF	
F - G	2x4	DRY	No.2		SPF	
G - H	2x4	DRY	No.2		SPF	
ALL WEBS		2x3	DRY	No.2		SPF
EXCEPT						
DRY: SEASONED LUMBER.						

PLATES (table in inches)

JT	TYPE	PLATES	W	LEN	Y	X
A	TMVW+p	MT20	4.0	4.0	1.00	2.00
B	TTWW+m	MT20	5.0	6.0	2.25	1.50
C	TTW-m	MT20	4.0	4.0		
D	TMVW+p	MT20	4.0	4.0	1.00	2.00
E	BMV1+p	MT20	3.0	4.0		
F	BMVWW-t	MT20	4.0	9.0		
G	BS-t	MT20	3.0	6.0		
H	BMVW-t	MT20	4.0	4.0		
I	BMV1+p	MT20	3.0	4.0		

DIMENSIONS, SUPPORTS AND LOADINGS SPECIFIED BY FABRICATOR TO BE VERIFIED BY BUILDING DESIGNER

BEARINGS	FACTORED	MAXIMUM FACTORED	INPUT	REORD
	GROSS REACTION	GROSS REACTION	BRG	BRG
JT	VERT	DOWN	HORIZ	UPLIFT
I	905	0	905	0
E	905	0	905	0

UNFACTORED REACTIONS

1ST LCASE	MAX/MIN COMPONENT REACTIONS						
JT	COMBINED	SNOW	LIVE	PERM.LIVE	WIND	DEAD	SOIL
I	840	420/0	0/0	0/0	0/0	220/0	0/0
E	840	420/0	0/0	0/0	0/0	220/0	0/0

BEARING MATERIAL TO BE SPF NO.2 OR BETTER AT JOINT(S) I, E

BRACING

TOP CHORD TO BE SHEATHED OR MAX. PURLIN SPACING = 6.25 FT.
MAX. UNBRACED BOTTOM CHORD LENGTH = 10.00 FT OR RIGID CEILING DIRECTLY APPLIED.

ALL PITCH BREAKS AND PERIMETER CORNER JOINTS MUST BE Laterally RESTRAINED.

LOADING

TOTAL LOAD CASES: (4)

CHORDS	MEMB.	MAX. FACTORED FORCE (LBS)	FACTORED VERT. LOAD (PLF)	MAX. LC1 (1)	MAX. LC2 (1)	UNBRACED LENGTH (FT)	FR-TO	WEBS	MEMB.	MAX. FACTORED FORCE (LBS)	MAX. LC1 (1)	MAX. LC2 (1)
A-B		-718/0	-91.8	-91.8	0.39 (1)	6.25	H-B			-34/68	0.02 (4)	
B-C		-558/0	-91.8	-91.8	0.28 (1)	6.25	B-F			0/14	0.00 (1)	
C-D		-728/0	-91.8	-91.8	0.42 (1)	6.25	F-C			-23/74	0.03 (4)	
D-E		-860/0	0.0	0.0	0.09 (1)	7.31	A-H			0/567	0.13 (1)	
E-F		-868/0	0.0	0.0	0.09 (1)	7.81	F-D			0/572	0.13 (1)	
H-A		0/0	-18.5	-18.5	0.13 (4)	10.00						
H-G		0/550	-18.5	-18.5	0.18 (4)	10.00						
G-F		0/550	-18.5	-18.5	0.18 (4)	10.00						
F-E		0/0	-18.5	-18.5	0.14 (4)	10.00						

TOTAL WEIGHT = 70 lb [M/F]

DESIGN CRITERIA

SPECIFIED LOADS:

TOP CH.	LL = 25.6	PSF
	DL = 8.0	PSF
BOT CH.	LL = 0.0	PSF
	DL = 7.4	PSF
TOTAL LOAD	= 39.0	PSF

SPACING = 24.0 IN. C/C

LOADING IN FLAT SECTION BASED ON A SLOPE OF 6.00/12

THIS TRUSS IS DESIGNED FOR RESIDENTIAL OR SMALL BUILDING REQUIREMENTS OF PART 9, NBCC 2010, NBCC 2015

THIS DESIGN COMPLIES WITH:

- PART 9 OF CBC 2018, CBC 2012, ABC 2019
- PART 9 OF CBC 2012 (2019 AMENDMENT)
- CSA 088-09, CSA 088-14
- TPIC 2011, TPIC 2014

(55% OF 31.3 P.S.F. G.S.L. PLUS 8.4 P.S.F. RAIN LOAD) EQUALS 25.6 P.S.F. SPECIFIED ROOF LIVE LOAD

ALLOWABLE DEFL.(LL) = $L/360$ (0.55")
CALCULATED VERT. DEFL.(LL) = $L/999$ (0.01")
ALLOWABLE DEFL.(TL) = $L/360$ (0.55")
CALCULATED VERT. DEFL.(TL) = $L/999$ (0.05")

CSI: TC=0.42/1.00 (C-D:1), BC=0.18/1.00 (F-H:4), WB=0.13/1.00 (D-F:1), SS=0.17/1.00 (B-C:1)

DCL LUMBER=1.00 NAIL=1.00 LS BEND=1.10
COMP=1.10 SHEAR=1.10 TENS=1.10

COMPANION LIVE LOAD FACTOR = 1.00

TRUSS PLATE MANUFACTURER IS NOT RESPONSIBLE FOR QUALITY CONTROL IN THE TRUSS MANUFACTURING PLANT.

NAIL VALUES

PLATE GRIP(DRY)	SHEAR	SECTION
(PSI)	(PL)	(PL)
MAX MIN	MAX MIN	MAX MIN
MT20	618	354
	1667	788
	1987	1659

PLATE PLACEMENT TOL. = 0.250 inches

PLATE ROTATION TOL. = 5.0 Deg.


JSI GRIP= 0.85 (D) (INPUT = 0.90)
JSI METAL= 0.24 (D) (INPUT = 1.00)



Structural component only
DWG# T-2007070

JOB NAME	TRUSS NAME	QUANTITY	PLY	JOB DESC.	DRWG NO.
408150	T8	1	1	GREEN PARK HOMES	
Tamarack Roof Truss, Burlington					

Version 8.310 S Oct 29 2019 MTek Industries, Inc. Sat Apr 25 11:02:56 2020 Page 1
ID:7vF?ag0E03cRUJ6X1jSrkzWYK-IBkxziYpQ8NWcUXvNNPzRo0Y13nGGpIRiAFBxzNcNt



Scale = 1:40.9

TOTAL WEIGHT = 77 lb

LUMBER

N. L. G. A. RULES

CHORDS	SIZE	DRY	LUMBER
A - C	2x4	DRY	No.2
C - D	2x4	DRY	No.2
D - F	2x4	DRY	No.2
J - A	2x4	DRY	No.2
G - F	2x4	DRY	No.2
J - H	2x4	DRY	No.2
H - G	2x4	DRY	No.2

ALL WEBS 2x3 DRY No.2
EXCEPT

DRY: SEASONED LUMBER.

PLATES (table is in inches)

JT	TYPE	PLATES	W	LEN	Y	X
A	TMV+p	MT20	3.0	4.0		
B	TMVW-t	MT20	4.0	6.0		
C	TTW-m	MT20	4.0	4.0		
D	TTW-m	MT20	4.0	4.0		
E	TMVW-t	MT20	4.0	6.0		
F	TMV+p	MT20	3.0	4.0		
G	BMVW1-t	MT20	4.0	4.0		
H	BS-t	MT20	3.0	6.0		
I	BMVWVW*4	MT20	5.0	12.0	3.00	6.00
J	BMVW1-t	MT20	4.0	4.0		

DIMENSIONS, SUPPORTS AND LOADINGS SPECIFIED BY FABRICATOR TO BE VERIFIED BY BUILDING DESIGNER

BEARINGS

	FACTORED GROSS REACTION	MAXIMUM FACTORED GROSS REACTION	INPUT BRG	RECORD BRG
JT	VERT	HORZ	UPLIFT	IN-SX
J	905	0	905	0
G	905	0	905	0

A SUITABLE HANGER/MECHANICAL CONNECTION IS REQUIRED AT JOINT G. MINIMUM BEARING LENGTH AT JOINT G = 3-8.

UNFACTORED REACTIONS

JT	1ST CASE	MAX/MIN. COMPONENT REACTIONS	DEAD	SOIL
JT	COMBINED	SNOW	LIVE	PERM/LIVE
J	640	420 / 0	0 / 0	0 / 0
G	640	420 / 0	0 / 0	0 / 0

BEARING MATERIAL TO BE SPF NO.2 OR BETTER AT JOINT(S) J

BRACING

TOP CHORD TO BE SHEATHED OR MAX. PURLIN SPACING = 6.25 FT.
MAX. UNBRACED BOTTOM CHORD LENGTH = 10.00 FT OR RIGID CEILING DIRECTLY APPLIED.

ALL PITCH BREAKS AND PERIMETER CORNER JOINTS MUST BE Laterally RESTRAINED.

LOADING

TOTAL LOAD CASES: (4)

MEMB.	CHORDS	MAX. FACTORED FORCE (LBS)	FACTORED VERT. LOAD (PLF)	MAX. FACTORED VERT. LOAD (LBS)	MAX. FACTORED HORIZ. LOAD (LBS)	WEBS	MEMB.	MAX. FACTORED FORCE (LBS)	MAX. FACTORED HORIZ. LOAD (LBS)
FR-TO						FR-TO			
A-B	0 / 27	-91.8	-91.8	0.22 (1)	10.00	B-I	-163 / 0	0.11 (1)	
B-C	-649 / 0	-91.8	-91.8	0.17 (1)	6.25	I-E	-190 / 0	0.13 (1)	
C-D	-489 / 0	-91.8	-91.8	0.01 (1)	6.25	J-B	-930 / 0	0.54 (1)	
D-E	-650 / 0	-91.8	-91.8	0.18 (1)	6.25	E-G	-935 / 0	0.57 (1)	
E-F	0 / 27	-91.8	-91.8	0.23 (1)	10.00	C-I	0 / 221	0.05 (1)	
J-A	-129 / 0	0.0	0.0	0.01 (1)	7.81	I-D	0 / 222	0.05 (1)	
G-F	-137 / 0	0.0	0.0	0.01 (1)	7.81				
J-I	0 / 590	-18.5	-18.5	0.41 (4)	10.00				
I-H	0 / 608	-18.5	-18.5	0.41 (4)	10.00				
H-G	0 / 608	-18.5	-18.5	0.41 (4)	10.00				

DESIGN CRITERIA

SPECIFIED LOADS:

TOP CH. LL	= 25.6 PSF
DL	= 6.0 PSF
BOT CH. LL	= 0.0 PSF
DL	= 7.4 PSF
TOTAL LOAD	= 39.0 PSF

SPACING = 24.0 IN/C

LOADING IN FLAT SECTION BASED ON A SLOPE OF 6.00/12

THIS TRUSS IS DESIGNED FOR RESIDENTIAL OR SMALL BUILDING REQUIREMENTS OF PART 9, NBCC 2010, NBCC 2015

THIS DESIGN COMPLIES WITH:

- PART 9 OF BCBC 2018, CBC 2012, ABC 2019
- PART 9 OF OSC 2012 (2019 AMENDMENT)
- CSA 086-09, CSA 086-14
- TPIC 2011, TPIC 2014

(55% OF 31.3 P.S.F. G.S.L. PLUS 8.4 P.S.F. RAIN LOAD) EQUALS 25.8 P.S.F. SPECIFIED ROOF LIVE LOAD

ALLOWABLE DEFL.(LL) = L/360 (0.55")
CALCULATED VERT. DEFL.(LL) = L/999 (0.02")
ALLOWABLE DEFL.(TL) = L/360 (0.55")
CALCULATED VERT. DEFL.(TL) = L/999 (0.11")

CS: TC=0.23/1.00 (E-F:1), BC=0.41/1.00 (G-I:4), WB=0.57/1.00 (E-G:1), SI=0.13/1.00 (D-E:1)

DCL LUMBER=1.00 NAIL=1.00 LS BEND=1.10
COMP=1.10 SHEAR=1.10 TENS=1.10

COMPANION LIVE LOAD FACTOR = 1.00

TRUSS PLATE MANUFACTURER IS NOT RESPONSIBLE FOR QUALITY CONTROL IN THE TRUSS MANUFACTURING PLANT.

NAIL VALUES


PLATE GRIP(DRY) SHEAR SECTION (PSI)	(PL)	(PL)
MAX MIN MAX MIN MAX MIN		
MT20	618 354 1657 788 1987 1658	

PLATE PLACEMENT TOL. = 0.250 inches

PLATE ROTATION TOL. = 5.0 Deg.

JSI GRIP= 0.75 (G) (INPUT = 0.90)

JSI METAL= 0.23 (G) (INPUT = 1.00)




Structural component only
DWG# T-2007071

JOB NAME 408150 Tamarack Roof Truss, Burlington	TRUSS NAME T9	QUANTITY 1	PLY 1	JOB DESC. GREEN PARK HOMES	DRWG NO.
				TRUSS DESC.	

Version 8.310 5 Oct 29 2019 MITek Industries, Inc. Sat Apr 25 11:02:57 2020 Page 1
ID:7vF7aG0E03cRUj6X1/SkziWYK-DOHJBeZRBVSUNE65x4wCz7ZjstBi7LOvgMwojNzNCnS

Scale = 1:48.5



LUMBER

N. L. G. A. RULES	CHORDS	SIZE	LUMBER
A - C	2x4	DRY	No.2
C - E	2x4	DRY	No.2
K - A	2x4	DRY	No.2
F - E	2x4	DRY	No.2
K - H	2x4	DRY	No.2
H - F	2x4	DRY	No.2

ALL WEBS 2x3 DRY No.2
EXCEPT

DRY: SEASONED LUMBER.

PLATES (table in inches)

JT	TYPE	PLATES	W	LEN	Y	X
A	TMVW+p	MT20	4.0	4.0	1.00	2.00
B	TMVW-t	MT20	4.0	4.0	2.00	1.25
C	TTW+p	MT20	4.0	8.0	Edge	
D	TMVW-t	MT20	4.0	4.0	2.00	1.25
E	TMVW+p	MT20	4.0	4.0	1.00	2.00
F	BMVW-t	MT20	3.0	4.0		
G	BMVW-t	MT20	4.0	6.0		
H	BS-1	MT20	3.0	6.0		
I	BMVW-t	MT20	4.0	9.0		
J	BMVW-t	MT20	4.0	4.0		
K	BMVW-t	MT20	3.0	4.0		

Edge - INDICATES REFERENCE CORNER OF PLATE TOUCHES EDGE OF CHORD.

DIMENSIONS, SUPPORTS AND LOADINGS SPECIFIED BY FABRICATOR TO BE VERIFIED BY BUILDING DESIGNER

BEARINGS

	FACTORED	MAXIMUM FACTORED	INPUT	REQD
	GROSS REACTION	GROSS REACTION	BRG	BRG
JT	VERT	DOWN	IN-SX	IN-SX
K	905	0	3-8	3-8
F	905	0	0	MECHANICAL

A SUITABLE HANGER/MECHANICAL CONNECTION IS REQUIRED AT JOINT F. MINIMUM BEARING LENGTH AT JOINT F = 3-8.

UNFACTORED REACTIONS

JT	1ST CASE	SNOW	LIVE	PERM.LIVE	WIND	DEAD	SOIL
K	640	420/0	0/0	0/0	0/0	220/0	0/0
F	640	420/0	0/0	0/0	0/0	220/0	0/0

BEARING MATERIAL TO BE SPF NO.2 OR BETTER AT JOINT(S) K

BRACING

TOP CHORD TO BE SHEATHED OR MAX. PURLIN SPACING = 6.25 FT.
MAX. UNBRACED BOTTOM CHORD LENGTH = 10.00 FT OR RIGID CEILING DIRECTLY APPLIED.

ALL PITCH BREAKS AND PERIMETER CORNER JOINTS MUST BE LATERALLY RESTRAINED.

LOADING

TOTAL LOAD CASES: (4)

CHORDS				WEBS			
MEMB.	MAX. FACTORED FORCE (LBS)	FACTORED VERT. LOAD (PL)	MAX. CSI (LC)	MEMB.	MAX. FACTORED FORCE (LBS)	MAX. CSI (LC)	
FR-TO		FROM TO		FR-TO			
A-B	-772/0	-91.8 -91.8 0.20 (1)	6.25	J-B	-135/21	0.05 (1)	
B-C	-620/0	-91.8 -91.8 0.19 (1)	6.25	B-I	-251/0	0.18 (1)	
C-D	-622/0	-91.8 -91.8 0.20 (1)	6.25	I-C	0/478	0.11 (1)	
D-E	-795/0	-91.8 -91.8 0.21 (1)	6.25	I-D	-278/0	0.20 (1)	
K-A	-873/0	0.0 0.0 0.10 (1)	7.81	G-D	-110/31	0.04 (1)	
F-E	-872/0	0.0 0.0 0.09 (1)	7.81	A-J	0/653	0.15 (1)	
				G-E	0/662	0.15 (1)	
K-J	0/0	-18.5 -18.5 0.07 (4)	10.00				
J-I	0/815	-18.5 -18.5 0.13 (1)	10.00				
I-H	0/633	-18.5 -18.5 0.14 (1)	10.00				
H-G	0/833	-18.5 -18.5 0.14 (1)	10.00				
G-F	0/0	-18.5 -18.5 0.07 (4)	10.00				

TOTAL WEIGHT = 77 lb (MTF)

DESIGN CRITERIA

SPECIFIED LOADS:
TOP CH. LL = 25.6 PSF
DL = 5.0 PSF
BOT CH. LL = 0.0 PSF
DL = 7.4 PSF
TOTAL LOAD = 39.0 PSF

SPACING = 24.0 IN. C/C

THIS TRUSS IS DESIGNED FOR RESIDENTIAL OR SMALL BUILDING REQUIREMENTS OF PART 9, NBCC 2010, NBCC 2015

THIS DESIGN COMPLIES WITH:
- PART 9 OF NBC 2018, OBC 2012, ABC 2019
- PART 9 OF OBC 2012 (2019 AMENDMENT)
- CSA 088-09, CSA 088-14
- TPIC 2011, TPIC 2014

(55 % OF 31.3 P.S.F. G.S.L. PLUS 8.4 P.S.F. RAIN LOAD) EQUALS 25.6 P.S.F. SPECIFIED ROOF LIVE LOAD

ALLOWABLE DEFL. (LL) = $L/360$ (0.55")
CALCULATED VERT. DEFL. (LL) = $L/999$ (0.02")
ALLOWABLE DEFL. (TL) = $L/360$ (0.55")
CALCULATED VERT. DEFL. (TL) = $L/999$ (0.03")

CSI: TC=0.21/1.00 (D-E:1), BC=0.14/1.00 (G-I:1), WB=0.20/1.00 (D-I:1), SSI=0.14/1.00 (D-E:1)

DOL LUMBER=1.00 NAIL=1.00 LS BEND=1.10 COMP=1.10 SHEAR=1.10 TENS=1.10

COMPANION LIVE LOAD FACTOR = 1.00

TRUSS PLATE MANUFACTURER IS NOT RESPONSIBLE FOR QUALITY CONTROL IN THE TRUSS MANUFACTURING PLANT.


NAIL VALUES

PLATE	GRIP(DRY)	SHEAR	SECTION
	(PSI)	(PLI)	(PLI)
MT20	618	354	1887 728 1987 1658

PLATE PLACEMENT TOL = 0.250 inches

PLATE ROTATION TOL = 5.0 Deg.

JSI GRIP = 0.87 (E) (INPUT = 0.90)
JSI METAL = 0.24 (E) (INPUT = 1.00)




Structural component only
DWG# T-2007072

JOB NAME	TRUSS NAME	QUANTITY	PLY	JOB DESC.	TRUSS DESC.	DRWG NO.
408150	T10S	2	1	GREEN PARK HOMES		

Tamarack Roof Truss, Burlington

Version 8.310 S Oct 29 2019 Mitek Industries, Inc. Sat Apr 25 11:02:56 2020 Page 1
ID:7vF?ag0E03cRUj6X1jSkzIWK-hariO_a4yldDrohlVoRRWDSvylX_kqu2v0IMFpzNCnR



LUMBER

N. L. G. A. RULES

CHORDS	SIZE	DRY	LUMBER
A - D	2x4	DRY	No.2
D - G	2x4	DRY	No.2
N - B	2x4	DRY	No.2
H - F	2x4	DRY	No.2
N - M	2x4	DRY	No.2
M - C	2x4	DRY	No.2
L - J	2x4	DRY	No.2
I - E	2x4	DRY	No.2
I - H	2x4	DRY	No.2

ALL WEBS	2x3	DRY	No.2
EXCEPT			
N - L	2x4	DRY	No.2
J - H	2x4	DRY	No.2

DRY: SEASONED LUMBER.

PLATES (table in inches)

JT TYPE	PLATES	W	LEN	Y	X
B, C, E, F					
B	TMVW+p	MT20	4.0	4.0	1.00 2.00
D	TTW+p	MT20	4.0	8.0	Edge
H	BMVW1-t	MT20	4.0	4.0	
I	BMV+p	MT20	3.0	4.0	
J	BVMWV-I	MT20	5.0	12.0	5.00 7.75
K	BMVWV-I	MT20	4.0	9.0	
L	BVMWV-I	MT20	5.0	12.0	5.00 7.75
M	BMV+p	MT20	3.0	4.0	
N	BMVW1-t	MT20	4.0	4.0	

Edge - INDICATES REFERENCE CORNER OF PLATE TOUCHES EDGE OF CHORD.

DIMENSIONS, SUPPORTS AND LOADINGS SPECIFIED BY FABRICATOR TO BE VERIFIED BY BUILDING DESIGNER

BEARINGS

	FACTORED GROSS REACTION	MAXIMUM FACTORED GROSS REACTION	INPUT BRG	REQD BRG
JT	VERT	HORZ	DOWN	HORZ
N	729	0	729	0
H	729	0	729	0

A SUITABLE HANGER/MECHANICAL CONNECTION IS REQUIRED AT JOINT H. MINIMUM BEARING LENGTH AT JOINT H = 1-8.

UNFACTORED REACTIONS

JT	COMBINED	SNOW	LIVE	PERM.LIVE	WIND	DEAD	SOIL
N	513	350/0	0/0	0/0	0/0	183/0	0/0
H	513	350/0	0/0	0/0	0/0	183/0	0/0

BEARING MATERIAL TO BE SPF NO.2 OR BETTER AT JOINT(S) N

BRACING

TOP CHORD TO BE SHEATHED OR MAX. PURLIN SPACING = 8.25 FT.
MAX. UNBRACED BOTTOM CHORD LENGTH = 7.81 FT. OR RIGID CEILING DIRECTLY APPLIED.

ALL PITCH BREAKS AND PERIMETER CORNER JOINTS MUST BE Laterally RESTRAINED.

LOADING

TOTAL LOAD CASES: (4)

CHORDS	MEMB.	MAX. FACTORED FORCE (LBS)	FACTORED VERT. LOAD (PLF)	MAX. UNBRACED LENGTH (LC)	W E B S	MEMB.	MAX. FACTORED FORCE (LBS)	MAX. UNBRACED LENGTH (LC)
FR-TO					FR-TO			
A-B	0/41	-91.8	-91.8	0.13 (1)	10.00	C-K	-211/0	0.07 (1)
B-C	-647/0	-91.8	-91.8	0.14 (1)	8.25	K-D	0/229	0.05 (1)
C-D	-447/0	-91.8	-91.8	0.19 (1)	8.25	K-E	-210/0	0.07 (1)
D-E	-447/0	-91.8	-91.8	0.18 (1)	8.25	N-L	-26/0	0.00 (1)
E-F	-646/0	-91.8	-91.8	0.14 (1)	8.25	B-L	0/527	0.12 (1)
F-G	0/41	-91.8	-91.8	0.13 (1)	10.00	J-F	0/526	0.12 (1)
N-B	-701/0	0.0	0.0	0.07 (1)	7.81	J-H	-26/0	0.00 (1)
H-F	-701/0	0.0	0.0	0.07 (1)	7.81			
N-M	0/20	-18.5	-18.5	0.01 (4)	10.00			
M-L	0/14	0.0	0.0	0.03 (1)	10.00			
L-C	-82/2	0.0	0.0	0.02 (1)	7.81			
L-K	0/528	-18.5	-18.5	0.13 (1)	10.00			
K-J	0/527	-18.5	-18.5	0.13 (1)	10.00			
I-J	0/14	0.0	0.0	0.03 (1)	10.00			
J-E	-93/2	0.0	0.0	0.02 (1)	7.81			
I-H	0/20	-18.5	-18.5	0.01 (4)	10.00			

TOTAL WEIGHT = 2 X 56 = 112 lb

DESIGN CRITERIA

SPECIFIED LOADS:

TOP CH.	LL	= 25.6	PSF
	DL	= 8.0	PSF
BOT CH.	LL	= 0.0	PSF
	DL	= 7.4	PSF
TOTAL LOAD	= 39.0	PSF	

SPACING = 24.0 IN.C.C.

THIS TRUSS IS DESIGNED FOR RESIDENTIAL OR SMALL BUILDING REQUIREMENTS OF PART 9, NBCC 2010, NBCC 2015

THIS DESIGN COMPLIES WITH:

- PART 9 OF BCBC 2018, OBC 2012, ABC 2019
- PART 9 OF OBC 2012 (2019 AMENDMENT)
- CSA 086-09, CSA 086-14
- TPIC 2011, TPIC 2014

DESIGN ASSUMPTIONS

OVERHANG NOT TO BE ALTERED OR CUT OFF.

(55% OF 31.3 P.S.F. G.S.L. PLUS 8.4 P.S.F. RAIN LOAD) EQUALS 25.6 P.S.F. SPECIFIED ROOF LIVE LOAD

ALLOWABLE DEFL.(LL) = $L/360$ (0.36")
CALCULATED VERT. DEFL.(LL) = $L/999$ (0.01")
ALLOWABLE DEFL.(TL) = $L/360$ (0.36")
CALCULATED VERT. DEFL.(TL) = $L/999$ (0.02")

CSI: TC=0.19/1.00 (C-D-1), BC=0.13/1.00 (K-L-1),
WB=0.12/1.00 (B-L-1), SS=0.13/1.00 (C-D-1)

DOL LUMBER=1.00 NAIL=1.00 LS BEND=1.10
COMP=1.10 SHEAR=1.10 TENS=1.10

COMPANION LIVE LOAD FACTOR = 1.00

AUTOSOLVE HEELS OFF

TRUSS PLATE MANUFACTURER IS NOT RESPONSIBLE FOR QUALITY CONTROL IN THE TRUSS MANUFACTURING PLANT.


NAIL VALUES

PLATE GRIP(DRY)	(PS)	(PL)	(PL)
MAX MIN	MAX MIN	MAX MIN	MAX MIN
MT20	618	354	1667

PLATE PLACEMENT TOL = 0.250 inches


PLATE ROTATION TOL = 5.0 Deg.

JSI GRIP = 0.74 (F) (INPUT = 0.90)
JSI METAL = 0.20 (F) (INPUT = 1.00)



Structural component only
DWG# T-2007073

JOB NAME 408150	TRUSS NAME T11	QUANTITY 1	PLY 1	JOB DESC. GREEN PARK HOMES	DRWG NO.
Tamarack Roof Truss, Burlington					



LUMBER

N. L. G. A. RULES

CHORDS	SIZE	LUMBER
A - C	2x4	DRY No.2
C - E	2x4	DRY No.2
H - B	2x4	DRY No.2
F - D	2x4	DRY No.2
H - F	2x4	DRY No.2

ALL WEBS 2x3 DRY No.2 EXCEPT

DRY: SEASONED LUMBER.

PLATES (table is in inches)

JT TYPE	PLATES	W	LEN	Y	X
B TMVW+p	MT20	4.0	4.0	1.00	2.00
C TTW+p	MT20	4.0	8.0	Edge	
D TMVW+p	MT20	4.0	4.0	1.00	2.00
F BMV+p	MT20	3.0	4.0		
G BMVWV+p	MT20	4.0	9.0		
H BMV+p	MT20	3.0	4.0		

Edge - INDICATES REFERENCE CORNER OF PLATE TOUCHES EDGE OF CHORD.

DIMENSIONS, SUPPORTS AND LOADINGS SPECIFIED BY FABRICATOR TO BE VERIFIED BY BUILDING DESIGNER

BEARINGS

	FACTORED GROSS REACTION	MAXIMUM FACTORED GROSS REACTION	INPUT BRG	REQD BRG
	VERT	HORZ	DOWN	HORZ
JT	729	0	729	0
H	729	0	729	0
F	729	0	729	0

A SUITABLE HANGER/MECHANICAL CONNECTION IS REQUIRED AT JOINT F. MINIMUM BEARING LENGTH AT JOINT F = 1-8.

UNFACTORED REACTIONS

JT	1ST CASE	MAX. MIN. COMPONENT REACTIONS	SNOW	LIVE	PERM. LIVE	WIND	DEAD	SOIL
JT	COMBINED							
H	513	350/0	0/0	0/0	0/0	0/0	163/0	0/0
F	513	350/0	0/0	0/0	0/0	0/0	163/0	0/0

BEARING MATERIAL TO BE SPF NO.2 OR BETTER AT JOINT(S) H

BRACING

TOP CHORD TO BE SHEATHED OR MAX. PURLIN SPACING = 6.25 FT.
MAX. UNBRACED BOTTOM CHORD LENGTH = 10.00 FT OR RIGID CEILING DIRECTLY APPLIED.

ALL PITCH BREAKS AND PERIMETER CORNER JOINTS MUST BE LATERALLY RESTRAINED.

LOADING

TOTAL LOAD CASES: (4)

CHORDS				WEBS			
MEMB.	MAX. FACTORED FORCE (LBS)	VERT. LOAD (PLF)	FACTORED MAX. (LC)	MEMB.	MAX. FACTORED FORCE (LBS)	VERT. LOAD (PLF)	FACTORED MAX. (LC)
FR-TO				FR-TO			
A-B	0/41	-91.8	-91.8 0.13 (1)	G-C	-15/89	0.03 (4)	
B-C	-380/0	-91.8	-91.8 0.35 (1)	B-G	0/300	0.07 (1)	
C-D	-380/0	-91.8	-91.8 0.35 (1)	G-D	0/300	0.07 (1)	
D-E	0/41	-91.8	-91.8 0.13 (1)				
H-B	-690/0	0.0	0.0 0.07 (1)				
F-D	-690/0	0.0	0.0 0.07 (1)				
H-G	0/0	-18.5	-18.5 0.16 (4)				
G-F	0/0	-18.5	-18.5 0.16 (4)				

TOTAL WEIGHT = 49 lb

(MIP)

DESIGN CRITERIA

SPECIFIED LOADS:

TOP CH.	LL = 25.6	PSF
DL =	6.0	PSF
BOT CH.	LL = 0.0	PSF
DL =	7.4	PSF
TOTAL LOAD =	39.0	PSF

SPACING = 24.0 IN./C

THIS TRUSS IS DESIGNED FOR RESIDENTIAL OR SMALL BUILDING REQUIREMENTS OF PART 9, NBCC 2010, NBCC 2015

THIS DESIGN COMPLIES WITH:

- PART 9 OF BCBC 2018, OBC 2012, ABC 2019
- PART 9 OF OBC 2012 (2019 AMENDMENT)
- CSA 088-09, CSA 088-14
- TPC 2011, TPC 2014

(55% OF 31.3 P.S.F. G.S.L. PLUS 8.4 P.S.F. RAIN LOAD) EQUALS 25.6 P.S.F. SPECIFIED ROOF LIVE LOAD

ALLOWABLE DEFL.(LL) = L/360 (0.36")
CALCULATED VERT. DEFL.(LL) = L/899 (0.00")
ALLOWABLE DEFL.(TL) = L/360 (0.36")
CALCULATED VERT. DEFL.(TL) = L/999 (0.02")

CSI: TC=0.35/1.00 (B-C:1), BC=0.16/1.00 (G-H:4), WB=0.07/1.00 (D-G:1), SS=0.15/1.00 (B-C:1)

DDL LUMBER=1.00 NAIL=1.00 LS BEND=1.10
COMP=1.10 SHEAR=1.10 TENS=1.10

COMPANION LIVE LOAD FACTOR = 1.00

TRUSS PLATE MANUFACTURER IS NOT RESPONSIBLE FOR QUALITY CONTROL IN THE TRUSS MANUFACTURING PLANT.


NAIL VALUES

PLATE GRIP(DRY)	SHEAR SECTION (PSI)	(PLI)	(PLI)
MAX MIN	MAX MIN	MAX MIN	MAX MIN
MT20	618	354	1667 788 1987 1856

PLATE PLACEMENT TOL. = 0.250 inches


PLATE ROTATION TOL. = 5.0 Deg.

JSI GRIP= 0.62 (D) (INPUT = 0.90)
JSI METAL= 0.17 (D) (INPUT = 1.00)



Structural component only
DWG# T-2007074

JOB NAME	TRUSS NAME	QUANTITY	PLY	JOB DESC.	DRWG NO.
408150	T12	1	1	GREEN PARK HOMES	
Tamarack Roof Truss, Burlington					



LUMBER			
N. L. G. A. RULES	SIZE	LUMBER	DESCR.
CHORDS			
A - B	2x4	DRY	No.2
B - C	2x4	DRY	No.2
F - A	2x4	DRY	No.2
D - C	2x4	DRY	No.2
F - D	2x4	DRY	No.2
ALL WEBS	2x3	DRY	No.2
EXCEPT			

DRY: SEASONED LUMBER.

PLATES (table in inches)

JT	TYPE	PLATES	W	LEN	Y	X
A	TMVW+p	MT20	4.0	4.0	1.00	2.00
B	TTW+p	MT20	4.0	6.0	Edge	
C	TMVW+p	MT20	4.0	4.0	1.00	2.00
D	BMV1+p	MT20	3.0	4.0		
E	BMVWW+1	MT20	4.0	9.0		
F	BMV1+p	MT20	3.0	4.0		

Edge - INDICATES REFERENCE CORNER OF PLATE TOUCHES EDGE OF CHORD.

DIMENSIONS, SUPPORTS AND LOADINGS SPECIFIED BY FABRICATOR TO BE VERIFIED BY BUILDING DESIGNER

BEARINGS

JT	FACTORED	GROSS REACTION	MAXIMUM FACTORED	INPUT	REQD
				BRG	BRG
				IN-SX	IN-SX
				MECHANICAL	MECHANICAL
F	423	0	423	0	0
D	423	0	423	0	0

A SUITABLE HANGER/MECHANICAL CONNECTION IS REQUIRED AT JOINT F, D. MINIMUM BEARING LENGTH AT JOINT F = 1-8, JOINT D = 1-8.

UNFACTORED REACTIONS

JT	1ST CASE	MAX/MIN COMPONENT REACTIONS	PERM. LIVE	WIND	DEAD	SOIL
F	299	196 / 0	0 / 0	0 / 0	103 / 0	0 / 0
D	299	196 / 0	0 / 0	0 / 0	103 / 0	0 / 0

BRACING

TOP CHORD TO BE SHEATHED OR MAX. PURLIN SPACING = 8.25 FT.
MAX. UNBRACED BOTTOM CHORD LENGTH = 10.00 FT. OR RIGID CEILING DIRECTLY APPLIED.

ALL PITCH BREAKS AND PERIMETER CORNER JOINTS MUST BE LATERALLY RESTRAINED.

LOADING

TOTAL LOAD CASES: (4)

CHORDS				WEBS			
MEMB.	MAX. FACTORED FORCE (LBS)	FACTORED VERT. LOAD (PLF)	MAX. UNBRACED LENGTH (LC)	MEMB.	MAX. FACTORED FORCE (LBS)	MAX. UNBRACED LENGTH (LC)	
FR-TO		FROM TO		FR-TO			
A-B	-214 / 0	-91.8 -91.8	0.17 (1)	6.25	E-B	-78 / 37	0.03 (1)
B-C	-214 / 0	-91.8 -91.8	0.17 (1)	6.25	A-E	0 / 184	0.04 (1)
F-A	-395 / 0	0.0 0.0	0.05 (1)	7.81	E-C	0 / 184	0.04 (1)
D-C	-395 / 0	0.0 0.0	0.05 (1)	7.81			
F-E	0 / 0	-18.5 -18.5	0.08 (4)	10.00			
E-D	0 / 0	-18.5 -18.5	0.08 (4)	10.00			

TOTAL WEIGHT = 35 lb [MIF]

DESIGN CRITERIA

SPECIFIED LOADS:

TOP CH. LL	= 25.6 PSF
DL	= 6.0 PSF
BOT CH. LL	= 0.0 PSF
DL	= 7.4 PSF
TOTAL LOAD	= 39.0 PSF

SPACING = 24.0 IN. C/C

THIS TRUSS IS DESIGNED FOR RESIDENTIAL OR SMALL BUILDING REQUIREMENTS OF PART 9, NBCC 2010, NBCC 2015

THIS DESIGN COMPLIES WITH:

- PART 9 OF BCBC 2010, OBC 2012, ABC 2010
- PART 9 OF OBC 2012 (2019 AMENDMENT)
- CSA 086-09, CSA 086-14
- TPIC 2011, TPIC 2014

(55 % OF 31.3 P.S.F. G.S.L. PLUS 8.4 P.S.F. RAIN LOAD) EQUALS 25.6 P.S.F. SPECIFIED ROOF LIVE LOAD

ALLOWABLE DEFL.(LL) = L/360 (0.28")
CALCULATED VERT. DEFL.(LL) = L/999 (0.00")
ALLOWABLE DEFL.(TL) = L/360 (0.28")
CALCULATED VERT. DEFL.(TL) = L/999 (0.01")

CSH: TC=0.17/1.00 (B-C:1), BC=0.08/1.00 (D-E:4), WB=0.04/1.00 (A-E:1), SSI=0.11/1.00 (B-C:1)

DOL LUMBER=1.00 NAIL=1.00 LS BEND=1.10
COMP=1.10 SHEAR=1.10 TENS=1.10

COMPANION LIVE LOAD FACTOR = 1.00

TRUSS PLATE MANUFACTURER IS NOT RESPONSIBLE FOR QUALITY CONTROL IN THE TRUSS MANUFACTURING PLANT.

NAIL VALUES

PLATE GRIP(DRY)	SHEAR	SECTION
(PSI)	(PL)	(PL)
MAX MIN	MAX MIN	MAX MIN
MT20	615 354	1667 788

PLATE PLACEMENT TOL = 0.250 inches

PLATE ROTATION TOL = 5.0 Deg.

JSI GRIP = 0.31 (C) (INPUT = 0.90)
JSI METAL = 0.09 (C) (INPUT = 1.00)




Structural component only
DWG# T-2007075

JOB NAME	TRUSS NAME	QUANTITY	PLY	JOB DESC.	GREEN PARK HOMES	DRWG NO.
408150	T12S	2	1	TRUSS DESC.		

Tamarack Roof Truss, Burlington

Version 3.310 S Oct 29 2019 Mtek Industries, Inc. Sat Apr 25 11:03:02 2020 Page 1
ID:4NxFt_xHSHnsgnSWZu6izNuP6-ZL5CELda? 7IKP?3keWNg3GbiUw7geceqedZOzbNCmN



LUMBER	N. L. G. A. RULES	CHORDS	SIZE	LUMBER	DESCR.
A - C	2x4	DRY	No.2	SPF	
C - E	2x4	DRY	No.2	SPF	
L - A	2x4	DRY	No.2	SPF	
F - E	2x4	DRY	No.2	SPF	
L - K	2x4	DRY	No.2	SPF	
K - B	2x4	DRY	No.2	SPF	
J - H	2x4	DRY	No.2	SPF	
G - D	2x4	DRY	No.2	SPF	
G - F	2x4	DRY	No.2	SPF	

ALL WEBS 2x3 DRY No.2 SPF

EXCEPT

DRY: SEASONED LUMBER.

PLATES (table is in inches)

JT	TYPE	PLATES	W	LEN	Y	X
A, B, D, E						
A	TMVW+p	MT20	4.0	4.0	1.00	2.00
C	TMVW+p	MT20	4.0	6.0	Edge	
F	BMVW1-t	MT20	4.0	4.0		
G	BMVW+p	MT20	3.0	4.0		
H	BMVW1-t	MT20	5.0	8.0	3.50	5.50
I	BMVW1-t	MT20	4.0	3.0		
J	BMVW1-t	MT20	5.0	8.0	3.50	5.50
K	BMVW+p	MT20	3.0	4.0		
L	BMVW1-t	MT20	4.0	4.0		

Edge - INDICATES REFERENCE CORNER OF PLATE TOUCHES EDGE OF CHORD.

DIMENSIONS, SUPPORTS AND LOADINGS SPECIFIED BY FABRICATOR TO BE VERIFIED BY BUILDING DESIGNER

BEARINGS

	FACTORED GROSS REACTION	MAXIMUM FACTORED GROSS REACTION	INPUT BRG	REQD BRG
JT	VERT	DOWN	IN-SX	IN-SX
L	423	0	0	MECHANICAL
F	423	0	0	MECHANICAL

A SUITABLE HANGER/MECHANICAL CONNECTION IS REQUIRED AT JOINT L, F. MINIMUM BEARING LENGTH AT JOINT L = 1-8, JOINT F = 1-8.

UNFACTORED REACTIONS

JT	1ST LCASE COMBINED	SNOW	LIVE	PERM.LIVE	WIND	DEAD	SOIL
L	299	196 / 0	0 / 0	0 / 0	0 / 0	103 / 0	0 / 0
F	299	196 / 0	0 / 0	0 / 0	0 / 0	103 / 0	0 / 0

BRACING

TOP CHORD TO BE SHEATHED OR MAX. PURLIN SPACING = 6.25 FT.
MAX. UNBRACED BOTTOM CHORD LENGTH = 7.81 FT. OR RIGID CEILING DIRECTLY APPLIED.

ALL PITCH BREAKS AND PERIMETER CORNER JOINTS MUST BE Laterally RESTRAINED.

LOADING

TOTAL LOAD CASES: (4)

CHORDS	MEMB.	MAX. FACTORED FORCE (LBS)	FACTORED VERT. LOAD (PLF)	LC1 MAX (PLF)	MAX (PLF)	MAX. UNBRACED LENGTH	FR-TO	MEMB.	MAX. FACTORED FORCE (LBS)	MAX (LC)
A-B	-282 / 0	-91.8	-91.8	0.06 (1)	6.25	1-C	0 / 125	0.03 (1)		
B-C	-274 / 0	-91.8	-91.8	0.07 (1)	6.25	1-D	-57 / 0	0.01 (1)		
C-D	-274 / 0	-91.8	-91.8	0.07 (1)	6.25	B-I	-57 / 0	0.01 (1)		
D-E	-282 / 0	-91.8	-91.8	0.06 (1)	6.25	L-J	-13 / 0	0.00 (1)		
L-A	-404 / 0	0.0	0.0	0.05 (1)	7.81	A-J	0 / 317	0.07 (1)		
F-E	-404 / 0	0.0	0.0	0.05 (1)	7.81	H-F	-13 / 0	0.00 (1)		
L-K	0 / 9	-18.5	-18.5	0.01 (4)	10.00	H-E	0 / 317	0.07 (1)		
K-J	0 / 11	0.0	0.0	0.01 (1)	10.00					
J-B	-182 / 0	0.0	0.0	0.01 (1)	7.81					
J-I	0 / 247	-18.5	-18.5	0.06 (1)	10.00					
I-H	0 / 247	-18.5	-18.5	0.06 (1)	10.00					
G-H	0 / 11	0.0	0.0	0.01 (1)	10.00					
H-D	-182 / 0	0.0	0.0	0.01 (1)	7.81					
G-F	0 / 9	-18.5	-18.5	0.01 (4)	10.00					

TOTAL WEIGHT = 2 X 43 = 85 lb [M/F]

DESIGN CRITERIA

SPECIFIED LOADS:
TOP CH. LL = 25.6 PSF
DL = 8.0 PSF
BOT CH. LL = 0.0 PSF
DL = 7.4 PSF
TOTAL LOAD = 39.0 PSF

SPACING = 24.0 IN. C/C

THIS TRUSS IS DESIGNED FOR RESIDENTIAL OR SMALL BUILDING REQUIREMENTS OF PART 9, NBCC 2010, NBCC 2015

THIS DESIGN COMPLIES WITH:
- PART 9 OF CBC 2018, CBC 2012, ABC 2019
- PART 9 OF CBC 2012 (2019 AMENDMENT)
- CSA 086-09, CSA 086-14
- TPIC 2011, TPIC 2014

(55% OF 81.3 P.S.F. G.S.L. PLUS 8.4 P.S.F. RAIN LOAD) EQUALS 25.6 P.S.F. SPECIFIED ROOF LIVE LOAD

ALLOWABLE DEFL.(LL) = L/360 (0.26")
CALCULATED VERT. DEFL.(LL) = L/999 (0.00")
ALLOWABLE DEFL.(TL) = L/360 (0.26")
CALCULATED VERT. DEFL.(TL) = L/999 (0.01")

CSI: TC=0.07/1.00 (C-D:1), BC=0.08/1.00 (H-I:1), WB=0.07/1.00 (A-J:1), SS=0.09/1.00 (C-D:1)

DCL LUMBER=1.00 NAIL=1.00 LS BEND=1.10
COMP=1.10 SHEAR=1.10 TENS=1.10

COMPANION LIVE LOAD FACTOR = 1.00

AUTOSOLVE HEELS OFF

TRUSS PLATE MANUFACTURER IS NOT RESPONSIBLE FOR QUALITY CONTROL IN THE TRUSS MANUFACTURING PLANT.


NAIL VALUES

PLATE GRIP(DRY)	SHEAR	SECTION
(PSI)	(PLI)	(PLI)
MAX MIN	MAX MIN	MAX MIN
MT20	618 354	1667 788

PLATE PLACEMENT TOL. = 0.250 inches

PLATE ROTATION TOL. = 5.0 Deg.


JSI GRIP= 0.30 (E) (INPUT = 0.90)
JSI METAL= 0.08 (E) (INPUT = 1.00)



Structural component only
DWG# T-2007076


DRWG NO.

0.10	10	10-11	0
------	----	-------	---



JOB NAME 408151	TRUSS NAME T20	QUANTITY 1	PLY 2	JOB DESC. GREEN PARK HOMES	DRWG NO.
Tamarack Roof Truss, Burlington				TRUSS DESC.	

Version 8.310 S Oct 29 2019 Mitek Industries, Inc. Sat Apr 25 11:19:44 2020 Page 1
ID:h2dfgC44wS_E2tznPs_atzllRw-E6e?Xz5trNUYObeR4VLHMmIFQOSI27EXMbZWzNCX
Scale = 1:57.3



LUMBER N. L. G. A. RULES CHORDS SIZE LUMBER DESCR. A - C 2x8 DRY No.2 SPF C - F 2x6 DRY No.2 SPF F - H 2x6 DRY No.2 SPF H - J 2x6 DRY No.2 SPF S - B 2x6 DRY No.2 SPF K - I 2x6 DRY No.2 SPF S - P 2x6 DRY 1650F 1.5E SPF P - N 2x6 DRY 1650F 1.5E SPF N - K 2x6 DRY 1650F 1.5E SPF ALL WEBS 2x3 DRY No.2 SPF EXCEPT				DESIGN CRITERIA *** SPECIAL LOADS ANALYSIS *** GEOMETRY AND/OR BASIC LOADS CHANGED BY USER. LOADS WERE DERIVED FROM USER INPUT NO FURTHER MODIFICATIONS WERE MADE SPECIFIED LOADS: TOP CH. LL = 25.6 PSF OL = 8.0 PSF BOT CH. LL = 0.0 PSF OL = 7.4 PSF TOTAL LOAD = 39.0 PSF SPACING = 24.0 IN. C/C LOADING IN FLAT SECTION BASED ON A SLOPE OF 6.00/12 *** NON STANDARD GIRDER *** ADDTL USER-DEFINED LOADS APPLIED TO ALL LOAD CASES. THIS TRUSS IS DESIGNED FOR RESIDENTIAL OR SMALL BUILDING REQUIREMENTS OF PART 9, NBC 2010, NBC 2015 THIS DESIGN COMPLIES WITH: - PART 8 OF CBC 2010, OBC 2012, ABC 2019 - PART 8 OF CBC 2012 (2019 AMENDMENT) - CSA 088-09, CSA 086-14 - TPIC 2011, TPIC 2014 (5% OF 31.3 P.S.F. G.S.L. PLUS 8.4 P.S.F. RAIN LOAD) EQUALS 25.6 P.S.F. SPECIFIED ROOF LIVE LOAD ALLOWABLE DEFL.(LL) = L/360 (1.17") CALCULATED VERT. DEFL.(LL) = L/999 (0.20") ALLOWABLE DEFL.(TL) = L/360 (1.17") CALCULATED VERT. DEFL.(TL) = L/999 (0.38") CSI: TC=0.42/1.00 (D-E-1), BC=0.32/1.00 (O-C-1), WB=0.56/1.00 (C-Q-1), SS=0.22/1.00 (C-D-1) DOL LUMBER=1.00 NAIL=1.00 LS BEND=1.00 COMP=1.00 SHEAR=1.00 TENS=1.00 COMPANION LIVE LOAD FACTOR = 1.00 AUTOSOLVE HEELS OFF TRUSS PLATE MANUFACTURER IS NOT RESPONSIBLE FOR QUALITY CONTROL IN THE TRUSS MANUFACTURING PLANT. NAIL VALUES PLATE GRIP(DRY) SHEAR SECTION (PSI) (PL) (PL) MAX MIN MAX MIN MAX MIN MT20 818 354 1687 789 1987 1656 PLATE PLACEMENT TOL. = 0.250 inches PLATE ROTATION TOL. = 5.0 Deg. JSI GRIP= 0.62 (M) (INPUT = 0.90) JSI METAL= 0.52 (P) (INPUT = 1.00)			
DRY: SEASONED LUMBER. DESIGN CONSISTS OF 2 TRUSSES BUILT SEPARATELY THEN FASTENED TOGETHER AS FOLLOWS: CHORDS #ROWS SURFACE SPACING (IN) LOAD(PLF) TOP CHORDS : (0.122"x3") SPIRAL NAILS A - C 2 12 SIDE(122.0) C - F 2 12 SIDE(61.0) F - H 2 12 SIDE(61.0) H - J 2 12 SIDE(122.0) S - B 2 12 TOP K - I 2 12 TOP BOTTOM CHORDS : (0.122"x3") SPIRAL NAILS S - P 2 12 SIDE(0.0) P - N 2 12 SIDE(0.0) N - K 2 12 SIDE(183.1) WEBS : (0.122"x3") SPIRAL NAILS 2x3 1 6 NAILS TO BE DRIVEN FROM ONE SIDE ONLY. GIRDER NAILING ASSUMES NAILED HANGERS ARE FASTENED WITH MIN. 3-0 INCH NAILS. TOP - COMPONENTS ARE LOADED FROM THE TOP AND MUST BE PLACED ON TOP EDGE OF ALL PLIES FOR THE LOAD TO BE TRANSFERRED TO EACH PLY.				BEARINGS FACTORED MAXIMUM FACTORED INPUT REQD GROSS REACTION GROSS REACTION BRG BRG DOWN HORZ UPLIFT IN-SX IN-SX JT 3330 0 3330 0 5-8 5-8 S 3379 0 3379 0 5-8 5-8 K 3379 0 3379 0 5-8 5-8 UNFACTORED REACTIONS 1ST LCASE MAX/MIN. COMPONENT REACTIONS JT COMBINED SNOW LIVE PERM.LIVE WIND DEAD SOIL S 2354 1553 / 0 0 / 0 0 / 0 801 / 0 0 / 0 K 2388 1572 / 0 0 / 0 0 / 0 818 / 0 0 / 0 BEARING MATERIAL TO BE SPF NO.2 OR BETTER AT JOINT(S) S, K BRACING TOP CHORD TO BE SHEATHED OR MAX. PURLIN SPACING = 3.98 FT. MAX. UNBRACED BOTTOM CHORD LENGTH = 10.00 FT OR RIGID CEILING DIRECTLY APPLIED. ALL PITCH BREAKS AND PERIMETER CORNER JOINTS MUST BE LATERALLY RESTRAINED. LOADING TOTAL LOAD CASES: (4) CHORDS MAX. FACTORED FACTORED W E B S MEMB. FORCE VERT. LOAD LC1 MAX UNBRACED MEMB. MAX. FACTORED (LBS) (PLF) CSI (LC) LENGTH (LBS) MAX FR-TO FROM TO A-B -91.8 -91.8 0.04 (1) 10.00 R-C -682 / 0 0.08 (1) B-C -3359 / 0 -91.8 -91.8 0.05 (1) 6.03 C-Q 0 / 4522 0.56 (1) C-T -6608 / 0 -91.8 -91.8 0.38 (1) 4.32 C-D -1799 / 0 0.22 (1) T-U -6608 / 0 -91.8 -91.8 0.38 (1) 4.32 D-O 0 / 1375 0.17 (1) U-V -6608 / 0 -91.8 -91.8 0.38 (1) 4.32 O-E -390 / 0 0.12 (1) V-W -6608 / 0 -91.8 -91.8 0.38 (1) 4.32 O-G 0 / 1388 0.17 (1) W-D -6608 / 0 -91.8 -91.8 0.38 (1) 4.32 M-G -1785 / 0 0.21 (1) D-X -7835 / 0 -91.8 -91.8 0.42 (1) 3.98 M-H 0 / 4493 0.58 (1) X-Y -7835 / 0 -91.8 -91.8 0.42 (1) 3.98 L-H -873 / 0 0.08 (1) Y-Z -7835 / 0 -91.8 -91.8 0.42 (1) 3.98 B-R 0 / 2729 0.34 (1) Z-E -7835 / 0 -91.8 -91.8 0.42 (1) 3.98 L-I 0 / 2764 0.34 (1) E-AA -7835 / 0 -91.8 -91.8 0.42 (1) 3.98 AA-F -7835 / 0 -91.8 -91.8 0.42 (1) 3.98 F-AB -7835 / 0 -91.8 -91.8 0.42 (1) 3.98 AB-AC -7835 / 0 -91.8 -91.8 0.42 (1) 3.98 AC-AD -7835 / 0 -91.8 -91.8 0.42 (1) 3.98 AD-G -7835 / 0 -91.8 -91.8 0.42 (1) 3.98 G-AE -6612 / 0 -91.8 -91.8 0.38 (1) 4.32 AE-AF -6612 / 0 -91.8 -91.8 0.38 (1) 4.32 AF-AG -6612 / 0 -91.8 -91.8 0.38 (1) 4.32 AG-H -6612 / 0 -91.8 -91.8 0.38 (1) 4.32 H-I -3401 / 0 -91.8 -91.8 0.05 (1) 6.00 I-J 0 / 42 -91.8 -91.8 0.04 (1) 10.00 S-B -3359 / 0 0.0 0.0 0.12 (1) 7.58 K-I -3408 / 0 0.0 0.0 0.12 (1) 7.55 S-AH 0.0 -18.5 -18.5 0.06 (4) 10.00 AH-R 0.0 -18.5 -18.5 0.06 (4) 10.00 R-AI 0.2546 -18.5 -18.5 0.16 (1) 10.00 AI-AJ 0.2546 -18.5 -18.5 0.16 (1) 10.00 AJ-AK 0.2546 -18.5 -18.5 0.16 (1) 10.00 AK-AL 0.2546 -18.5 -18.5 0.16 (1) 10.00 AL-O 0.2546 -18.5 -18.5 0.16 (1) 10.00 O-P 0.6806 -18.5 -18.5 0.32 (1) 10.00 P-AM 0.6806 -18.5 -18.5 0.32 (1) 10.00 AM-AN 0.6806 -18.5 -18.5 0.32 (1) 10.00 AN-O 0.6806 -18.5 -18.5 0.32 (1) 10.00 O-AO 0.6813 -18.5 -18.5 0.32 (1) 10.00 AO-AP 0.6813 -18.5 -18.5 0.32 (1) 10.00 AP-AQ 0.6813 -18.5 -18.5 0.32 (1) 10.00 AQ-N 0.6813 -18.5 -18.5 0.32 (1) 10.00 N-AR 0.6813 -18.5 -18.5 0.32 (1) 10.00 AR-M 0.6813 -18.5 -18.5 0.32 (1) 10.00			



Structural component only
DWG# T-2007081 1/2

JOB NAME	TRUSS NAME	QUANTITY	PLY	JOB DESC.	DRWG NO.
408151	T20	1	2	GREEN PARK HOMES	
Tamarack Roof Truss, Burlington				TRUSS DESC.	

Version 9.310 5 Oct 2019 MITek Industries, Inc. Sat Apr 25 11:19:44 2020 Page 2
ID:n2dfiqC44wS E2tqPs atzllRw-E6a?Xz51rNUYObeR4VLHMmIPOgOSI27EXMbZWzNCX

PLATES (table is in inches)

JT	TYPE	PLATES	W	LEN	Y	X
B	TMVW+p	MT20	7.0	8.0		
C	TTWW+m	MT20	8.0	9.0	3.50	1.75
D	TMWW-t	MT20	5.0	6.0	2.50	2.50
E	TMW+w	MT20	3.0	6.0		
F	TS-t	MT20	5.0	6.0		
G	TMWW-t	MT20	5.0	8.0	2.50	2.50
H	TTWW+m	MT20	8.0	9.0	3.50	1.75
I	TMVW+p	MT20	7.0	8.0		
K	BMV1+p	MT20	3.0	6.0		
L	BMWW-t	MT20	5.0	6.0	2.50	2.25
M	BMWW-t	MT20	5.0	8.0	2.50	3.00
N	BS-t	MT20	6.0	9.0		
O	BMWWW-t	MT20	5.0	12.0		
P	BS-t	MT20	6.0	9.0		
Q	BMWW-t	MT20	5.0	8.0	2.50	3.00
R	BMWW-t	MT20	5.0	6.0	2.50	2.25
S	BMV1+p	MT20	3.0	6.0		

LOADING

TOTAL LOAD CASES: 141


CHORDS				WEBS			
MEMB.	FORCE (LBS)	VERT. LOAD (LBS)	MAX. FACTORED (LBS)	MEMB.	FORCE (LBS)	MAX. FACTORED (LBS)	MAX. CS1 (LBS)
FR-TO		FROM TO		CS1 (LBS)	UNBRAC	LENGTH	FR-TO
M-AS	0 / 2579	-18.5	-18.5 0.18 (1)	10.00			
AS-AT	0 / 2579	-18.5	-18.5 0.18 (1)	10.00			
AT-AU	0 / 2579	-18.5	-18.5 0.18 (1)	10.00			
AU-L	0 / 2579	-18.5	-18.5 0.18 (1)	10.00			
L-AV	0 / 0	-18.5	-18.5 0.08 (4)	10.00			
AV-K	0 / 0	-18.5	-18.5 0.08 (4)	10.00			

FACTORED CONCENTRATED LOADS (LBS)

JT	LOC.	LC1	MAX.	MAX+	FACE	DIR.	TYPE	HEEL	CONN.
C	2-11-8	-38	-42		FRONT	VERT	DEAD		C1
C	2-11-8	-191	-191		FRONT	VERT	SNOW		C1
H	32-2-8	-38	-42		FRONT	VERT	DEAD		C1
H	32-2-8	-116	-116		FRONT	VERT	TOTAL		C1
H	32-2-8	-191	-191		FRONT	VERT	SNOW		C1
L	31-11-4	-26	-26		FRONT	VERT	TOTAL		C1
P	11-11-4	-26	-26		FRONT	VERT	TOTAL		C1
T	3-11-4	-111	-111		FRONT	VERT	TOTAL		C1
U	5-11-4	-110	-110		FRONT	VERT	TOTAL		C1
V	7-11-4	-110	-110		FRONT	VERT	TOTAL		C1
W	9-11-4	-110	-110		FRONT	VERT	TOTAL		C1
X	11-11-4	-110	-110		FRONT	VERT	TOTAL		C1
Y	13-11-4	-110	-110		FRONT	VERT	TOTAL		C1
Z	15-11-4	-110	-110		FRONT	VERT	TOTAL		C1
AA	17-11-4	-110	-110		FRONT	VERT	TOTAL		C1
AB	19-11-4	-110	-110		FRONT	VERT	TOTAL		C1
AC	21-11-4	-110	-110		FRONT	VERT	TOTAL		C1
AD	23-11-4	-110	-110		FRONT	VERT	TOTAL		C1
AE	25-11-4	-110	-110		FRONT	VERT	TOTAL		C1
AF	27-11-4	-110	-110		FRONT	VERT	TOTAL		C1
AG	29-11-4	-110	-110		FRONT	VERT	TOTAL		C1
AH	1-11-4	-26	-26		FRONT	VERT	TOTAL		C1
AI	3-11-4	-26	-26		FRONT	VERT	TOTAL		C1
AJ	5-11-4	-26	-26		FRONT	VERT	TOTAL		C1
AK	7-11-4	-26	-26		FRONT	VERT	TOTAL		C1
AL	9-11-4	-26	-26		FRONT	VERT	TOTAL		C1
AM	13-11-4	-26	-26		FRONT	VERT	TOTAL		C1
AN	15-11-4	-26	-26		FRONT	VERT	TOTAL		C1
AO	17-11-4	-26	-26		FRONT	VERT	TOTAL		C1
AP	19-11-4	-26	-26		FRONT	VERT	TOTAL		C1
AQ	21-11-4	-26	-26		FRONT	VERT	TOTAL		C1
AR	23-11-4	-26	-26		FRONT	VERT	TOTAL		C1
AS	25-11-4	-26	-26		FRONT	VERT	TOTAL		C1
AT	27-11-4	-26	-26		FRONT	VERT	TOTAL		C1
AU	29-11-4	-26	-26		FRONT	VERT	TOTAL		C1
AV	33-11-4	-26	-26		FRONT	VERT	TOTAL		C1

CONNECTION REQUIREMENTS


- 1) C1: A SUITABLE HANGER/MECHANICAL CONNECTION IS REQUIRED.



Structural component only
DWG# T-2007081 3/2

JOB NAME	TRUSS NAME	QUANTITY	PLY	JOB DESC.	DRWG NO.
408151	T20Z	1	2	GREEN PARK HOMES	
Tamarack Roof Truss, Burlington				TRUSS DESC.	

Version 8.310 S Oct 29 2019 MTEK Industries, Inc. Sat Apr 25 11:19:45 2020 Page 1
ID:h2dfgC44ws E2tzoPs atzllRw-iCQUmko9VL9YAq n0aqaJuZo4EB5KGTB585yzNCX



LUMBER	N. L. G. A. RULES	CHORDS	SIZE	DRY	LUMBER	DESCR.
A - C	2x6	DRY	No.2	SPF		
C - F	2x6	DRY	No.2	SPF		
F - H	2x6	DRY	No.2	SPF		
H - J	2x6	DRY	No.2	SPF		
S - B	2x6	DRY	No.2	SPF		
K - I	2x6	DRY	No.2	SPF		
S - P	2x6	DRY	1650F 1.5E	SPF		
P - N	2x6	DRY	1650F 1.5E	SPF		
N - K	2x6	DRY	1650F 1.5E	SPF		

ALL WEBS 2x3 DRY No.2 SPF
EXCEPT
DRY: SEASONED LUMBER.
DESIGN CONSISTS OF 2 TRUSSES BUILT SEPARATELY THEN FASTENED TOGETHER AS FOLLOWS:

CHORDS #ROWS	SURFACE SPACING (IN)	LOAD(PLF)
TOP CHORDS : (0.122"x3") SPIRAL NAILS		
A-C 2 12	SIDE(122.0)	
C-F 2 12	SIDE(183.1)	
F-H 2 12	TOP	
H-J 2 12	TOP	
S-B 2 12	TOP	
K-I 2 12	TOP	
BOTTOM CHORDS : (0.122"x3") SPIRAL NAILS		
S-P 2 12	SIDE(183.1)	
P-N 2 12	SIDE(183.1)	
N-K 2 12	TOP	
WEBS : (0.122"x3") SPIRAL NAILS		
2x3 1 6		

NAILS TO BE DRIVEN FROM ONE SIDE ONLY.
GIRDER NAILING ASSUMES NAILED HANGERS ARE FASTENED WITH MIN. 3-0 INCH NAILS.
TOP - COMPONENTS ARE LOADED FROM THE TOP AND MUST BE PLACED ON TOP EDGE OF ALL PLIES FOR THE LOAD TO BE TRANSFERRED TO EACH PLY.

DIMENSIONS, SUPPORTS AND LOADINGS SPECIFIED BY FABRICATOR TO BE VERIFIED BY BUILDING DESIGNER

BEARINGS	FACTORED GROSS REACTION	MAXIMUM FACTORED GROSS REACTION	INPUT BRG	RECORD BRG
JT	VERT	DOWN	IN-SX	IN-SX
S	4991	0	5-8	5-8
K	3694	0	5-8	5-8

UNFACTORED REACTIONS	1ST LCASE	MAX. MIN. COMPONENT REACTIONS
JT	COMBINED SNOW	LIVE PERMA LIVE WIND DEAD SOIL
S	3528	2323 / 0 0 / 0 0 / 0 1208 / 0 0 / 0
K	2808	1737 / 0 0 / 0 0 / 0 871 / 0 0 / 0

BEARING MATERIAL TO BE SPF NO.2 OR BETTER AT JOINT(S) S, K
BRACING
TOP CHORD TO BE SHEATHED OR MAX. PURLIN SPACING = 3.20 FT.
MAX. UNBRACED BOTTOM CHORD LENGTH = 10.00 FT OR RIGID CEILING DIRECTLY APPLIED.
ALL PITCH BREAKS AND PERIMETER CORNER JOINTS MUST BE Laterally RESTRAINED.

LOADING	TOTAL LOAD CASES: (4)
CHORDS	WEBS
MEMB.	MEMB.
MAX. FACTORED FORCE (LBS)	MAX. FACTORED FORCE (LBS)
VERT. LOAD LC1 MAX (PLF)	MAX. UNBRACED LENGTH FR-TO
CSI (LC)	CSI (LC)
FR-TO	FR-TO
A-B 0 / 42	-91.8 -91.8 0.04 (1) 10.00 R-C -253 / 44 0.03 (1)
B-C -5342 / 0	-91.8 -91.8 0.07 (1) 5.02 C-Q 0 / 6569 0.81 (1)
C-D -9971 / 0	-91.8 -91.8 0.39 (1) 3.64 C-Q -1958 / 0 0.23 (1)
D-T -12379 / 0	-91.8 -91.8 0.52 (1) 3.20 D-O 0 / 2694 0.33 (1)
T-E -12379 / 0	-91.8 -91.8 0.52 (1) 3.20 E-G -782 / 0 0.09 (1)
E-F -12379 / 0	-91.8 -91.8 0.49 (1) 3.23 O-G 0 / 4229 0.52 (1)
F-G -12379 / 0	-91.8 -91.8 0.49 (1) 3.23 M-H -2619 / 0 0.31 (1)
G-H -8598 / 0	-91.8 -91.8 0.33 (1) 3.93 M-H 0 / 6416 0.79 (1)
H-I -3750 / 0	-91.8 -91.8 0.06 (1) 5.79 L-H -864 / 0 0.10 (1)
I-J 0 / 42	-91.8 -91.8 0.04 (1) 10.00 B-R 0 / 4341 0.54 (1)
S-B -5197 / 0	0.0 0.0 0.19 (1) 6.41 L-I 0 / 3047 0.38 (1)
K-I -3727 / 0	0.0 0.0 0.13 (1) 7.30

FACTORED CONCENTRATED LOADS (LBS)	LOC.	MAX.	MAX.	FACE	DIR.	TYPE	HEEL	CONN.
JT								
C	2-11-8	-28	-42	---	FRONT	VERT	DEAD	C1
C	2-11-8	-117	-117	---	BACK	VERT	TOTAL	C1
C	2-11-8	-191	-191	---	FRONT	VERT	SNOW	C1
E	17-4-12	-110	-110	---	BACK	VERT	TOTAL	C1
O	17-4-12	-26	-26	---	BACK	VERT	TOTAL	C1
R	2-9-4	-26	-26	---	BACK	VERT	TOTAL	C1
T	15-4-12	-110	-110	---	BACK	VERT	TOTAL	C1
U	9-4	-29	-29	---	BACK	VERT	TOTAL	C1
V	4-8-8	-1068	-1068	---	BACK	VERT	TOTAL	C1
W	13-5-8	-1086	-1086	---	BACK	VERT	TOTAL	C1
X	15-4-12	-26	-26	---	BACK	VERT	TOTAL	C1
Y	18-5-8	-1738	-1738	---	BACK	VERT	TOTAL	C1

DESIGN CRITERIA

*** SPECIAL LOADS ANALYSIS ***
GEOMETRY AND/OR BASIC LOADS CHANGED BY USER.
LOADS WERE DERIVED FROM USER INPUT
NO FURTHER MODIFICATIONS WERE MADE

SPECIFIED LOADS:
TOP CH. LL = 25.5 PSF
DL = 6.0 PSF
BOT CH. LL = 0.0 PSF
DL = 7.4 PSF
TOTAL LOAD = 39.0 PSF

SPACING = 24.0 IN. C/C

LOADING IN FLAT SECTION BASED ON A SLOPE OF 6.00/12

*** NON STANDARD GIRDER ***
ADDTL. USER-DEFINED LOADS APPLIED TO ALL LOAD CASES.

THIS TRUSS IS DESIGNED FOR RESIDENTIAL OR SMALL BUILDING REQUIREMENTS OF PART 9, NBCC 2010, NBCC 2015

THIS DESIGN COMPLIES WITH:
- PART 9 OF NBCC 2018, OBC 2012, A8C 2019
- PART 9 OF OBC 2012 (2019 AMENDMENT)
- CSA 088-09, CSA 088-14
- TPIC 2011, TPIC 2014

(55% OF 31.3 P.S.F. G.S.L. PLUS 8.4 P.S.F. RAIN LOAD) EQUALS 25.8 P.S.F. SPECIFIED ROOF LIVE LOAD

ALLOWABLE DEFL.(LL) = L/360 (1.17")
CALCULATED VERT. DEFL.(LL) = L/999 (0.33")
ALLOWABLE DEFL.(TL) = L/360 (1.17")
CALCULATED VERT. DEFL.(TL) = L/685 (0.62")

CSI: TC=0.52/1.00 (D-E:1), BC=0.73/1.00 (C-Q:1), WB=0.81/1.00 (C-Q:1), SS=0.57/1.00 (M-O:1)

DOL LUMBER=1.00 NAIL=1.00 LS BEND=1.00
COMP=1.00 SHEAR=1.00 TENS=1.00

COMPANION LIVE LOAD FACTOR = 1.00

AUTOSOLVE HEELS OFF


TRUSS PLATE MANUFACTURER IS NOT RESPONSIBLE FOR QUALITY CONTROL IN THE TRUSS MANUFACTURING PLANT.

NAIL VALUES
PLATE GRIP(DRY) SHEAR SECTION (PSI) (PLI) (PLI)
MAX MIN MAX MIN MAX MIN
MT20 818 354 1857 788 1957 1656

PLATE PLACEMENT TOL = 0.250 inches

PLATE ROTATION TOL = 5.0 Deg.

JSI GRIP = 0.88 (D) (INPUT = 0.90)
JSI METAL = 0.84 (P) (INPUT = 1.00)



Structural component only
DWG# T-2007082 1/2

JOB NAME 408151	TRUSS NAME T20Z	QUANTITY 1	PLY 2	JOB DESC. GREEN PARK HOMES	DRWG NO.
Tamarack Roof Truss, Burlington		TRUSS DESC.			


Version 8.310 S Oct 29 2019 MITek Industries, Inc. Sat Apr 28 11:19:45 2020 Page 2
ID:h2dfiqC44wS E2tzoPs atzIRw-UCOUmk09VL9YAq n0agaJvZo4EB5KGT8585vzNCX

PLATES (table is in inches)

JT	TYPE	PLATES	W	LEN	Y	X
B	TMVW+p	MT20	7.0	8.0		
C	TTWW+m	MT20	8.0	9.0	3.50	1.75
D	TMVW-i	MT20	5.0	6.0	2.50	2.50
E	TMVW+w	MT20	3.0	6.0		
F	TS-i	MT20	5.0	6.0		
G	TMVW-i	MT20	5.0	6.0	2.50	2.50
H	TTWW+m	MT20	8.0	9.0	3.50	1.75
I	TMVW+p	MT20	7.0	8.0		
K	BMV1+p	MT20	3.0	6.0		
L	BMVW-i	MT20	5.0	6.0	2.50	2.25
M	BMVW-i	MT20	5.0	8.0	2.50	2.75
N	BS-i	MT20	6.0	9.0		
O	BMVW-i	MT20	5.0	12.0	2.75	8.00
P	BS-i	MT20	6.0	9.0		
Q	BMVW-i	MT20	5.0	8.0	2.50	2.75
R	BMVW-i	MT20	5.0	6.0	2.50	2.25
S	BMV1+p	MT20	3.0	6.0		

CONNECTION REQUIREMENTS


- 1) C1: A SUITABLE HANGER/MECHANICAL CONNECTION IS REQUIRED.



Structural component only
DWG# T-2007082 7/2

JOB NAME 408151	TRUSS NAME T21	QUANTITY 2	PLY 1	JOB DESC. GREEN PARK HOMES	DRWG NO.
Tamarack Roof Truss, Burlington				TRUSS DESC.	

Version 8.310 S Oct 29 2019 MITek Industries, Inc. Sat Apr 25 11:19:46 2020 Page 1
 ID:h2dfqC44wS_E2zqPs_atzllRw-AVmyfmMZTdCnllOYUXpMnnr1ECRIweZQhrridOzNCXh
 20 J 0 5-3-15 25-9-15 5-3-3 31-0-2 4-1-14 35-2-0 1-3-8
 Scale = 1:57.2



LUMBER
 N. L. G. A. RULES
 CHORDS SIZE LUMBER
 A - C 2x4 DRY No.2
 C - F 2x4 DRY No.2
 F - I 2x4 DRY No.2
 I - J 2x4 DRY No.2
 U - B 2x4 DRY No.2
 L - J 2x4 DRY No.2
 U - R 2x4 DRY No.2
 R - O 2x4 DRY No.2
 O - L 2x4 DRY No.2
 ALL WEBS 2x3 DRY No.2
 EXCEPT
 DRY: SEASONED LUMBER.

DIMENSIONS, SUPPORTS AND LOADINGS SPECIFIED BY FABRICATOR TO BE VERIFIED BY BUILDING DESIGNER		BEARINGS		UNFACTORED REACTIONS	
FACTORED	MAXIMUM FACTORED	INPUT	REQD	1ST CASE	MAX/MIN COMPONENT REACTIONS
GROSS REACTION	GROSS REACTION	BRG	BRG	COMBINED	SNOW LIVE PERM.LIVE WIND DEAD SOIL
VERT HORZ	DOWN HORZ UPLIFT	IN-SX	IN-SX	U	1458 971/0 0/0 0/0 488/0 0/0
L	2066 0 2066 0 0 5-8 5-8			L	1458 971/0 0/0 0/0 488/0 0/0

BEARING MATERIAL TO BE SPF NO.2 OR BETTER AT JOINT(S) U, L
BRACING
 TOP CHORD TO BE SHEATHED OR MAX. PURLIN SPACING = 3.20 FT.
 MAX. UNBRACED BOTTOM CHORD LENGTH = 10.00 FT OR RIGID CEILING DIRECTLY APPLIED.

ALL PITCH BREAKS AND PERIMETER CORNER JOINTS MUST BE Laterally RESTRAINED.
LOADING
 TOTAL LOAD CASES: (4)

CHORDS		WEBS	
MEMB.	MAX. FACTORED FORCE (LBS)	MEMB.	MAX. FACTORED FORCE (LBS)
FR-TO	FROM TO	FR-TO	FROM TO
A-B	0/41	T-C	-358/0
B-C	-1960/0	C-S	0/1837
C-D	-2871/0	S-D	-1118/0
D-E	-3508/0	D-Q	0/856
E-F	-3505/0	Q-E	-475/0
F-G	-3505/0	E-P	-2/0
G-H	-3505/0	P-G	-474/0
H-I	-2871/0	P-H	0/853
I-J	-1960/0	N-H	-1117/0
J-K	0/41	N-I	0/1837
U-B	-2037/0	M-I	-358/0
L-J	-2037/0	B-T	0/1571
		M-J	0/1571
U-T	0/0		
T-S	0/1494		
S-R	0/2871		
R-Q	0/2871		
Q-P	0/3508		
P-O	0/2872		
O-N	0/2872		
N-M	0/1494		
M-L	0/0		

Edge - INDICATES REFERENCE CORNER OF PLATE TOUCHES EDGE OF CHORD.



Structural component only
 DWG# T-2007083

DESIGN CRITERIA
 SPECIFIED LOADS:
 TOP CH. LL = 25.6 PSF
 DL = 8.0 PSF
 BOT CH. LL = 0.0 PSF
 DL = 7.4 PSF
 TOTAL LOAD = 39.0 PSF
SPACING = 24.0 IN. C/C

LOADING IN FLAT SECTION BASED ON A SLOPE OF 6.00/12

THIS TRUSS IS DESIGNED FOR RESIDENTIAL OR SMALL BUILDING REQUIREMENTS OF PART 9, NBC 2010, NBC 2015

THIS DESIGN COMPLIES WITH:
 - PART 9 OF CBC 2010, CBC 2012, ABC 2019
 - PART 9 OF CBC 2012 (2019 AMENDMENT)
 - CSA 086-09, CSA 086-14
 - TPIC 2011, TPIC 2014

(55% OF 31.3 P.S.F. G.S.L. PLUS 8.4 P.S.F. RAIN LOAD) EQUALS 25.6 P.S.F. SPECIFIED ROOF LIVE LOAD

ALLOWABLE DEFL.(LL) = L/360 (1.17')
 CALCULATED VERT. DEFL.(LL) = L/999 (0.20')
 ALLOWABLE DEFL.(TL) = L/360 (1.17')
 CALCULATED VERT. DEFL.(TL) = L/999 (0.39')

CSI: TC=0.66/1.00 (G-H-T), BC=0.62/1.00 (P-Q-T),
 WB=0.43/1.00 (D-S-T), SS=0.23/1.00 (H-T)

DOL LUMBER=1.00 NAIL=1.00 LS BEND=1.10
 COMP=1.10 SHEAR=1.10 TENS=1.10

COMPANION LIVE LOAD FACTOR = 1.00

TRUSS PLATE MANUFACTURER IS NOT RESPONSIBLE FOR QUALITY CONTROL IN THE TRUSS MANUFACTURING PLANT.

NAIL VALUES
 PLATE GRIP(DRY) SHEAR SECTION (PSI) (PLI) (PLI)
 MAX MIN MAX MIN MAX MIN
 MT20 818 354 1667 788 1987 1656


PLATE PLACEMENT TOL = 0.250 inches

PLATE ROTATION TOL = 5.0 Deg.

JSI GRIP = 0.90 (S) (INPUT = 0.90)
 JSI METAL = 0.90 (O) (INPUT = 1.00)

JOB NAME	TRUSS NAME	QUANTITY	PLY	JOB DESC.	DRWG NO.
408151	T22	2	1	GREEN PARK HOMES	
Tamarack Roof Truss, Burlington					

Version 8.310 S Oct 29 2019 Mitek Industries, Inc. Sat Apr 25 11:19:47 2020 Page 1
ID:h2dlqC44wS_E2zzqPs_atzllRw-ehJ89?n_Kml3PrKD6C22v7OAzcPwI3vZwVaFAr2NCXqg



LUMBER

N. L. G. A. RULES

CHORDS	SIZE	DRY	LUMBER
A - C	2x4	DRY	No.2
C - F	2x4	DRY	No.2
F - H	2x4	DRY	No.2
H - J	2x4	DRY	No.2
S - B	2x4	DRY	No.2
K - I	2x4	DRY	No.2
S - P	2x4	DRY	No.2
P - N	2x4	DRY	No.2
N - K	2x4	DRY	No.2

ALL WEBS 2x3 DRY No.2
EXCEPT

DRY: SEASONED LUMBER.

PLATES (table is in inches)

JT	TYPE	PLATES	W	LEN	Y	X
B	TMVW-p	MT20	5.0	6.0	1.50	3.00
C	TTWW-m	MT20	6.0	9.0	Edge	1.75
D	TMVW-l	MT20	4.0	4.0		
E	TMVW-w	MT20	2.0	4.0		
F	TS-t	MT20	3.0	6.0		
G	TMVW-t	MT20	4.0	4.0		
H	TTWW-m	MT20	6.0	9.0	Edge	1.75
I	TMVW-p	MT20	5.0	6.0	1.50	3.00
K	BMV1-p	MT20	3.0	4.0		
L, M, Q, R						
L	BMVW-t	MT20	5.0	6.0		
N	BS-1	MT20	3.0	6.0		
O	BMVWW-t	MT20	4.0	9.0		
P	BS-1	MT20	3.0	6.0		
S	BMV1-p	MT20	3.0	4.0		

Edge - INDICATES REFERENCE CORNER OF PLATE TOUCHES EDGE OF CHORD.

DIMENSIONS, SUPPORTS AND LOADINGS SPECIFIED BY FABRICATOR TO BE VERIFIED BY BUILDING DESIGNER

BEARINGS

	FACTORED	MAXIMUM FACTORED	INPUT	REQD
	GROSS REACTION	GROSS REACTION	BRG	BRG
	VERT	HORZ	DOWN	HORZ
JT	2066	0	2066	0
S	2066	0	2066	0
K	2066	0	2066	0

UNFACTORED REACTIONS

	1ST LGASE	MAX MIN. COMPONENT REACTIONS						
JT	COMBINED	SNOW	LIVE	PERM.LIVE	WIND	DEAD	SOIL	
S	1458	971/0	0/0	0/0	0/0	488/0	0/0	
K	1458	971/0	0/0	0/0	0/0	488/0	0/0	

BEARING MATERIAL TO BE SPF NO.2 OR BETTER AT JOINT(S) S, K

BRACING

TOP CHORD TO BE SHEATHED OR MAX. PURLIN SPACING = 3.28 FT.
MAX. UNBRACED BOTTOM CHORD LENGTH = 10.00 FT. OR RIGID CEILING DIRECTLY APPLIED.

ALL PITCH BREAKS AND PERIMETER CORNER JOINTS MUST BE Laterally RESTRAINED.

LOADING

TOTAL LOAD CASES: (4)

CHORDS				WEBS			
MEMB.	MAX. FACTORED	FACTORED		MEMB.	MAX. FACTORED	FACTORED	
	FORCE	VERT. LOAD	MAX		FORCE	MAX	
	(LBS)	(PLF)	CSI (LC)		(LBS)	CSI (LC)	
FR-TO		FROM TO		FR-TO			
A-B	0/41	-91.8 -91.8	0.13 (1)	10.00	R-C	-246/7	0.14 (1)
B-C	-2004/0	-91.8 -91.8	0.64 (1)	4.11	C-Q	0/1538	0.35 (1)
C-D	-2653/0	-91.8 -91.8	0.74 (1)	3.50	Q-D	-943/0	0.55 (1)
D-E	-2978/0	-91.8 -91.8	0.78 (1)	3.28	D-O	0/450	0.10 (1)
E-F	-2978/0	-91.8 -91.8	0.78 (1)	3.28	O-E	-513/0	0.30 (1)
F-G	-2978/0	-91.8 -91.8	0.78 (1)	3.28	O-G	0/450	0.10 (1)
G-H	-2653/0	-91.8 -91.8	0.74 (1)	3.50	M-G	-943/0	0.55 (1)
H-I	-2004/0	-91.8 -91.8	0.64 (1)	4.11	M-H	0/1538	0.35 (1)
I-J	0/41	-91.8 -91.8	0.13 (1)	10.00	L-H	-246/7	0.14 (1)
S-B	-2028/0	0.0 0.0	0.22 (1)	5.94	B-R	0/1580	0.36 (1)
K-I	-2028/0	0.0 0.0	0.22 (1)	5.94	L-I	0/1580	0.36 (1)
S-R	0/0	-18.5 -18.5	0.14 (4)	10.00			
R-Q	0/1532	-18.5 -18.5	0.33 (1)	10.00			
Q-P	0/2653	-18.5 -18.5	0.49 (1)	10.00			
P-O	0/2653	-18.5 -18.5	0.49 (1)	10.00			
O-N	0/2653	-18.5 -18.5	0.49 (1)	10.00			
N-M	0/2653	-18.5 -18.5	0.49 (1)	10.00			
M-L	0/1532	-18.5 -18.5	0.33 (1)	10.00			
L-K	0/0	-18.5 -18.5	0.14 (4)	10.00			

TOTAL WEIGHT = 2 X 148 = 296 lb

DESIGN CRITERIA

SPECIFIED LOADS:

TOP CH. LL	= 25.8 PSF
DL	= 6.0 PSF
BOT CH. LL	= 0.0 PSF
DL	= 7.4 PSF
TOTAL LOAD	= 39.0 PSF

SPACING = 24.0 IN. C/C

LOADING IN FLAT SECTION BASED ON A SLOPE OF 6.00/12

THIS TRUSS IS DESIGNED FOR RESIDENTIAL OR SMALL BUILDING REQUIREMENTS OF PART 9, NBCC 2010, NBCC 2015

THIS DESIGN COMPLIES WITH:

- PART 9 OF BCBC 2018, OBC 2012, ABC 2019
- PART 9 OF OBC 2012 (2019 AMENDMENT)
- CSA 086-09, CSA 086-14
- TPIC 2011, TPIC 2014

(55% OF 31.3 P.S.F. G.S.L. PLUS 8.4 P.S.F. RAIN LOAD) EQUALS 25.6 P.S.F. SPECIFIED ROOF LIVE LOAD

ALLOWABLE DEFL.(LL) = $L/380$ (1.17")
CALCULATED VERT. DEFL.(LL) = $L/899$ (0.16")
ALLOWABLE DEFL.(TL) = $L/360$ (1.17")
CALCULATED VERT. DEFL.(TL) = $L/999$ (0.29")

CSI: TC=0.78/1.00 (D-E:1), BC=0.49/1.00 (O-Q:1),
WB=0.55/1.00 (G-M:1), SS=0.27/1.00 (C-D:1)

DOL LUMBER=1.00 NAIL=1.00 LS BEND=1.10
COMP=1.10 SHEAR=1.10 TENS=1.10

COMPANION LIVE LOAD FACTOR = 1.00

TRUSS PLATE MANUFACTURER IS NOT RESPONSIBLE FOR QUALITY CONTROL IN THE TRUSS MANUFACTURING PLANT.

NAIL VALUES

PLATE GRIP(DRY)	SHEAR	SECTION
(PSI)	(PL)	(PL)
MAX MIN	MAX MIN	MAX MIN
MT20	618 354 1687 788	1987 1658

PLATE PLACEMENT TOL. = 0.250 inches

PLATE ROTATION TOL. = 5.0 Deg.

JSI GRIP=0.90 (B) (INPUT = 0.90)
JSI METAL=0.85 (N) (INPUT = 1.00)




Structural component only
DWG# T-2007084

JOB NAME: 408151 TRUSS NAME: T23 QUANTITY: 2 PLY: 1 JOB DESC: GREEN PARK HOMES TRUSS DESC: DRAWG NO. 1

Version 8.310 S Oct 29 2019 Mtek Industries, Inc. Sat Apr 25 11:19:48 2020 Page 1

ID:h2dfgC44wS_E2tqPs_atzWfW-6uWVKoc54hw0?vPgVZHSCwP40AOPUI99K0it-h2NCX1

Scale = 1:37.5



LUMBER

N. L. G. A. RULES

CHORDS SIZE

A - D 2x4 DRY No.2

D - G 2x4 DRY No.2

G - I 2x4 DRY No.2

I - L 2x4 DRY No.2

L - M 2x4 DRY No.2

M - K 2x4 DRY No.2

K - P 2x4 DRY No.2

P - M 2x4 DRY No.2

ALL WEBS 2x3 DRY No.2

EXCEPT

SPF

SPF

SPF

SPF

SPF

SPF

SPF

SPF

SPF

SPF

SPF

SPF

SPF

SPF

SPF

SPF

SPF

SPF

SPF

SPF

SPF

SPF

SPF

SPF

SPF

SPF

SPF

SPF

SPF

SPF

SPF

SPF

SPF

SPF

SPF

SPF

SPF

SPF

SPF

SPF

SPF

SPF

SPF

SPF

SPF

SPF

SPF

SPF

DIMENSIONS, SUPPORTS AND LOADINGS SPECIFIED BY FABRICATOR TO BE VERIFIED BY BUILDING DESIGNER

BEARINGS

FACTORED GROSS REACTION MAXIMUM FACTORED GROSS REACTION INPUT RECD

JT VERT 2066 0 2066 0 0 5-8 5-8

U 2066 0 2066 0 0 5-8 5-8

M 2066 0 2066 0 0 5-8 5-8

UNFACTORED REACTIONS

1ST LCASE MAX/MIN COMPONENT REACTIONS

JT COMBINED SNOW LIVE PERM.LIVE WIND DEAD SOIL

U 1458 971/0 0/0 0/0 0/0 488/0 0/0

M 1458 971/0 0/0 0/0 0/0 488/0 0/0

BEARING MATERIAL TO BE SPF NO.2 OR BETTER AT JOINTS (U), (M)

BRACING

TOP CHORD TO BE SHEATHED OR MAX. PURLIN SPACING = 3.77 FT.

MAX. UNBRACED BOTTOM CHORD LENGTH = 10.00 FT OR RIGID CEILING DIRECTLY APPLIED.

ALL PITCH BREAKS AND PERIMETER CORNER JOINTS MUST BE LATERALLY RESTRAINED.

LOADING

TOTAL LOAD CASES: (4)

CHORDS

MAX. FACTORED FACTORED

MEMB. FORCE VERT. LOAD LC1 MAX UNBRAC LENGTH FR-TO

A-B 0/141 -91.8 -91.8 0.13 (1) 10.00 C-T 0/156 0.04 (1)

B-C 0/119 -91.8 -91.8 0.14 (1) 10.00 T-D 0/76 0.03 (4)

C-D 2023/0 -91.8 -91.8 0.20 (1) 4.59 D-S 0/1220 0.27 (1)

D-E 2308/0 -91.8 -91.8 0.56 (1) 3.94 E-S -850/0 0.74 (1)

E-F 2534/0 -91.8 -91.8 0.57 (1) 3.77 F-Q 0/361 0.08 (1)

F-G 2534/0 -91.8 -91.8 0.57 (1) 3.77 G-H -461/0 0.40 (1)

G-H 2534/0 -91.8 -91.8 0.57 (1) 3.77 H-I 0/261 0.08 (1)

H-I 2308/0 -91.8 -91.8 0.55 (1) 3.94 I-J -850/0 0.74 (1)

I-J 2023/0 -91.8 -91.8 0.20 (1) 4.59 J-K 0/1220 0.27 (1)

J-K 0/119 -91.8 -91.8 0.14 (1) 10.00 K-L 0/76 0.03 (4)

K-L 0/41 -91.8 -91.8 0.13 (1) 10.00 N-J 0/156 0.04 (1)

L-M -246/0 0.0 0.0 0.03 (1) 7.81 U-C -2277/0 0.98 (1)

M-K -246/0 0.0 0.0 0.03 (1) 7.81 J-M -2277/0 0.98 (1)

U-T 0/1433 -18.5 -18.5 0.33 (1) 10.00

T-S 0/1535 -18.5 -18.5 0.35 (1) 10.00

S-R 0/2308 -18.5 -18.5 0.42 (1) 10.00

R-Q 0/2308 -18.5 -18.5 0.42 (1) 10.00

Q-P 0/2308 -18.5 -18.5 0.42 (1) 10.00

P-O 0/2308 -18.5 -18.5 0.42 (1) 10.00

O-N 0/1535 -18.5 -18.5 0.35 (1) 10.00

N-M 0/1433 -18.5 -18.5 0.33 (1) 10.00

TOTAL WEIGHT = 2 X 162 = 323 lb

DESIGN CRITERIA

SPECIFIED LOADS:

TOP CH. LL = 25.6 PSF

DL = 6.0 PSF

BOT CH. LL = 0.0 PSF

DL = 7.4 PSF

TOTAL LOAD = 38.0 PSF

SPACING = 24.0 IN. OC

LOADING IN FLAT SECTION BASED ON A SLOPE OF 6.00/12

THIS TRUSS IS DESIGNED FOR RESIDENTIAL OR SMALL BUILDING REQUIREMENTS OF PART 9, NBCC 2010, NBCC 2015

THIS DESIGN COMPLIES WITH:

- PART 9 OF CBC 2018, CBC 2012, ABC 2019

- PART 9 OF CBC 2012 (2019 AMENDMENT)

- CSA 086-09, CSA 086-14

- TPIC 2011, TPIC 2014

(55% OF 31.3 P.S.F. G.S.L. PLUS 8.4 P.S.F. RAIN LOAD) EQUALS 25.6 P.S.F. SPECIFIED ROOF LIVE LOAD

ALLOWABLE DEFL.(LL) = L/360 (1.17")

CALCULATED VERT. DEFL.(LL) = L/999 (0.13")

ALLOWABLE DEFL.(TL) = L/360 (1.17")

CALCULATED VERT. DEFL.(TL) = L/999 (0.23")

CS1: TC=0.57/1.00 (E-F:1), BC=0.42/1.00 (Q-C:1), WB=0.98/1.00 (J-M:1), SS=0.24/1.00 (D-E:1)

DOL LUMBER=1.00 NAIL=1.00 L5 BEND=1.10

COMP=1.10 SHEAR=1.10 TENS=1.10

COMPANION LIVE LOAD FACTOR = 1.00

TRUSS PLATE MANUFACTURER IS NOT RESPONSIBLE FOR QUALITY CONTROL IN THE TRUSS MANUFACTURING PLANT.

NAIL VALUES

PLATE GRIP(DRY) SHEAR SECTION

(PSI) (PL) (PL)

MAX MIN MAX MIN MAX MIN


MT20 818 354 1667 788 1937 1656

PLATE PLACEMENT TOL. = 0.250 inches

PLATE ROTATION TOL. = 5.0 Deg.

JSI GRIP = 0.89 (I) (INPUT = 0.90)

JSI METAL = 0.72 (P) (INPUT = 1.00)



Structural component only
DWG# T-2007085


JOB NAME	TRUSS NAME	QUANTITY	PLY	JOB DESC.	TRUSS DESC.	DRWG NO.
408151	T24	2	1	GREEN PARK HOMES		

Tamercat Roof Truss, Burlington

Version 8.310 5 Oct 2019 Mitak Industries, Inc. Sat Apr 25 11:18:49 2020 Page 1

ID:h2dfgC44wS E2tzqPs_atzllRw-a4RuagpEsO?ne9UbDd4W_QTXEPW57ssslNp3MEjzNCKe

Scale = 1:57.5



LUMBER N. L. G. A. RULES **CHORDS** SIZE **LUMBER** **DESCR.** **SPF** **FACTORED** **MAXIMUM FACTORED** **INPUT** **REQD** **DESIGN CRITERIA** **SPACING** **IN CC** **LOADING IN FLAT SECTION BASED ON A SLOPE** **OF 6.00/12** **THIS TRUSS IS DESIGNED FOR RESIDENTIAL OR** **SMALL BUILDING REQUIREMENTS OF PART 9,** **NBCC 2010, NBCC 2015** **THIS DESIGN COMPLIES WITH:** **- PART 9 OF BCBC 2018, OBC 2012, ABC 2019** **- PART 8 OF OBC 2012 (2019 AMENDMENT)** **- CSA 086-09, CSA 086-14** **- TPIC 2011, TPIC 2014** **(55% OF 31.3 P.S.F. G.S.L. PLUS 8.4 P.S.F. RAIN** **LOAD) EQUALS 25.6 P.S.F. SPECIFIED ROOF** **LIVE LOAD** **ALLOWABLE DEFL.(LL)= L/360 (1.17')** **CALCULATED VERT. DEFL.(LL)= L/999 (0.10')** **ALLOWABLE DEFL.(TL)= L/360 (1.17')** **CALCULATED VERT. DEFL.(TL)= L/999 (0.21')** **CSI: TC=0.73/1.00 (D-E-1), BC=0.42/1.00 (O-P-1),** **WB=0.97/1.00 (L-1), SS=0.28/1.00 (D-E-1)** **DOL LUMBER=1.00 NAIL=1.00 LS BEND=1.10** **COMP=1.10 SHEAR=1.10 TENS= 1.10** **COMPANION LIVE LOAD FACTOR = 1.00** **AUTOSOLVE HEELS OFF** **TRUSS PLATE MANUFACTURER IS NOT** **RESPONSIBLE FOR QUALITY CONTROL IN THE** **TRUSS MANUFACTURING PLANT.** **NAIL VALUES** **PLATE GRIP(DRY) SHEAR SECTION** **(PSI) (PLI) (PLI)** **MAX MIN MAX MIN MAX MIN** **MT20 618 354 1667 798 1987 1656** **PLATE PLACEMENT TOL. = 0.250 inches** **PLATE ROTATION TOL. = 5.0 Deg.** **JSI GRIP= 0.87 (I) (INPUT = 0.90)** **JSI METAL= 0.56 (I) (INPUT = 1.00)**

CHORDS	SIZE	LUMBER	DESCR.	SPF	FACTORED	MAXIMUM FACTORED	INPUT	REQD
A - D	2x4	DRY	No.2	SPF	2088	0	0	0
D - F	2x4	DRY	No.2	SPF	2088	0	0	0
F - H	2x4	DRY	No.2	SPF	2088	0	0	0
H - I	2x4	DRY	No.2	SPF	2088	0	0	0
S - B	2x4	DRY	No.2	SPF	2088	0	0	0
L - J	2x4	DRY	No.2	SPF	2088	0	0	0
S - Q	2x4	DRY	No.2	SPF	2088	0	0	0
Q - N	2x4	DRY	No.2	SPF	2088	0	0	0
N - L	2x4	DRY	No.2	SPF	2088	0	0	0
ALL WEBS	2x3	DRY	No.2	SPF	1458	971/0	0/0	0/0
EXCEPT	2x4	DRY	No.2	SPF	1458	971/0	0/0	0/0
S - C	2x4	DRY	No.2	SPF	1458	971/0	0/0	0/0
I - L	2x4	DRY	No.2	SPF	1458	971/0	0/0	0/0

DRY: SEASONED LUMBER.

PLATES (table is in inches)

JT	TYPE	PLATES	W	LEN	Y	X
B	TMV+P	MT20	3.0	4.0		
C	TMWW+I	MT20	5.0	8.0	2.50	2.50
D	TTWW+M	MT20	5.0	8.0	2.00	1.75
E	TMWW+I	MT20	4.0	4.0		
F	TS-I	MT20	3.0	6.0		
G	TMV+W	MT20	2.0	4.0		
H	TTWW+M	MT20	5.0	8.0	2.00	1.75
I	TMWW+I	MT20	5.0	8.0	2.50	2.50
J	TMV+P	MT20	3.0	4.0		
L	BMVW+I	MT20	5.0	8.0		
M	BMVW+I	MT20	4.0	4.0		
N	GS-I	MT20	3.0	6.0		
O	BMVW+I	MT20	4.0	4.0		
P	BMVW+I	MT20	4.0	6.0		
Q	GS-I	MT20	3.0	6.0		
R	BMVW+I	MT20	4.0	4.0		
S	BMVW+I	MT20	5.0	6.0		

DIMENSIONS, SUPPORTS AND LOADINGS SPECIFIED BY FABRICATOR TO BE VERIFIED BY

BUILDING DESIGNER	BEARINGS	FACTORED	MAXIMUM FACTORED	INPUT	REQD
JT	VERT	GROSS REACTION	GROSS REACTION	BRG	BRG
S	2088	0	2088	0	0
L	2088	0	2088	0	0

UNFACTORED REACTIONS

JT	1ST CASE	SNOW	LIVE	PERM. LIVE	WIND	DEAD	SOIL
S	1458	971/0	0/0	0/0	0/0	488/0	0/0
L	1458	971/0	0/0	0/0	0/0	488/0	0/0

BEARING MATERIAL TO BE SPF NO.2 OR BETTER AT JOINT(S) S, L

BRACING

TOP CHORD TO BE SHEATHED OR MAX. PURLIN SPACING = 3.81 FT.
MAX. UNBRACED BOTTOM CHORD LENGTH = 10.00 FT OR RIGID CEILING DIRECTLY APPLIED.

ALL PITCH BREAKS AND PERIMETER CORNER JOINTS MUST BE Laterally RESTRAINED.

1 LATERAL BRACE(S) AT 1/2 LENGTH OF E-O.

END VERTICAL(S) MUST BE SHEATHED OR HAVE BRACES AS INDICATED IN THE MAX. UNBRACED LENGTH COLUMN OF THE TABLE BELOW


LOADING

TOTAL LOAD CASES: (4)

CHORDS	MEMB.	MAX. FACTORED	FACTORED	VERT. LOAD	LC1	MAX	UNBRAC	MEMB.	MAX. FACTORED	FACTORED	VERT. LOAD	LC1	MAX
FR-TO		(LBS)						FR-TO		(LBS)			
A-B	0/41	-91.8	-91.8	0.13	(1)	10.00	C-R	0/64	0.02	(4)			
B-C	0/26	-91.8	-91.8	0.21	(1)	10.00	R-D	0/126	0.04	(4)			
C-D	-2006/0	-91.8	-91.8	0.29	(1)	4.50	D-P	0/898	0.22	(1)			
D-E	-2162/0	-91.8	-91.8	0.73	(1)	3.81	P-E	-650/0	0.82	(1)			
E-F	-2162/0	-91.8	-91.8	0.73	(1)	3.81	E-O	-2/0	0.00	(1)			
F-G	-2162/0	-91.8	-91.8	0.73	(1)	3.81	O-G	-649/0	0.82	(1)			
G-H	-2162/0	-91.8	-91.8	0.73	(1)	3.82	H-O	0/995	0.22	(1)			
H-I	-2006/0	-91.8	-91.8	0.29	(1)	4.50	M-H	0/126	0.04	(4)			
I-J	0/26	-91.8	-91.8	0.21	(1)	10.00	M-I	0/64	0.02	(4)			
J-K	0/41	-91.8	-91.8	0.13	(1)	10.00	S-C	-2291/0	0.97	(1)			
S-B	-284/0	0.0	0.0	0.03	(1)	7.81	I-L	-2291/0	0.97	(1)			
L-J	-284/0	0.0	0.0	0.03	(1)	7.81							
S-R	0/1487	-18.5	-18.5	0.38	(1)	10.00							
R-Q	0/1519	-18.5	-18.5	0.39	(1)	10.00							
Q-P	0/1519	-18.5	-18.5	0.39	(1)	10.00							
P-O	0/2163	-18.5	-18.5	0.42	(1)	10.00							
O-N	0/1519	-18.5	-18.5	0.39	(1)	10.00							
N-M	0/1519	-18.5	-18.5	0.39	(1)	10.00							
M-L	0/1487	-18.5	-18.5	0.38	(1)	10.00							




Structural component only
DWG# T-2007086



LUMBER				DIMENSIONS, SUPPORTS AND LOADINGS SPECIFIED BY FABRICATOR TO BE VERIFIED BY BUILDING DESIGNER								TOTAL WEIGHT = 2 X 162 = 363 lb			
N. L. G. A. RULES				BEARINGS								DESIGN CRITERIA			
SIZE				FACTORED				MAXIMUM FACTORED				INPUT			
LUMBER				GROSS REACTION				GROSS REACTION				RECORD			
DESCR.				JT				VERT				BRG			
				U				DOWN				BRG			
				L				UP				IN-SX			
				2066				0				5-8			
				0				0				5-8			
				2066				0				5-8			
				0				0				5-8			
				0				0				5-8			
				0				0				5-8			
				0				0				5-8			
				0				0				5-8			
				0				0				5-8			
				0				0				5-8			
				0				0				5-8			
				0				0				5-8			
				0				0				5-8			
				0				0				5-8			
				0				0				5-8			
				0				0				5-8			
				0				0				5-8			
				0				0				5-8			
				0				0				5-8			
				0				0				5-8			
				0				0				5-8			
				0				0				5-8			
				0				0				5-8			
				0				0				5-8			
				0				0				5-8			
				0				0				5-8			
				0				0				5-8			
				0				0				5-8			
				0				0				5-8			
				0				0				5-8			
				0				0				5-8			
				0				0				5-8			
				0				0				5-8			
				0				0				5-8			
				0				0				5-8			
				0				0				5-8			
				0				0				5-8			
				0				0				5-8			
				0				0				5-8			
				0				0				5-8			
				0				0				5-8			
				0				0				5-8			
				0				0				5-8			
				0				0				5-8			
				0				0				5-8			
				0				0				5-8			
				0				0				5-8			
				0				0				5-8			
				0				0				5-8			
				0				0				5-8			
				0				0				5-8			
				0				0				5-8			
				0				0				5-8			
				0				0				5-8			
				0				0				5-8			
				0				0				5-8			
				0				0				5-8			
				0				0				5-8			
				0				0				5-8			
				0				0				5-8			
				0				0				5-8			
				0				0				5-8			
				0				0				5-8			
				0				0				5-8			
				0				0				5-8			
				0				0				5-8			
				0				0				5-8			
				0				0				5-8			
				0				0				5-8			
				0				0				5-8			
				0				0				5-8			
				0				0				5-8			
				0				0				5-8			
				0				0				5-8			
				0				0				5-8			
				0				0				5-8			
				0				0				5-8			
				0				0				5-8			
				0				0				5-8			
				0				0				5-8			
				0				0				5-8			
				0				0				5-8			
				0				0				5-8			
				0				0				5-8			
				0				0				5-8			
				0				0				5-8			
				0				0				5-8			
				0				0				5-8			
				0				0				5-8			
				0				0				5-8			
				0				0				5-8			
				0				0				5-8			
				0				0				5-8			
				0				0				5-8			
				0				0				5-8			
				0				0				5-8			
				0				0				5-8			
				0				0				5-8			
				0				0				5-8			
				0				0				5-8			
				0				0				5-8			
				0				0				5-8			
				0				0				5-8			
				0				0				5-8			
				0				0				5-8			
				0				0				5-8			
				0				0				5-8			
				0				0				5-8			
				0				0				5-8			
				0				0				5-8			
				0				0				5-8			
				0				0				5-8			
				0				0				5-8			
				0				0				5-8			
				0				0				5-8			
				0				0				5-8			
				0											

PLATES (table is in inches)				LOADING				TOTAL LOAD CASES: (4)			
JT	TYPE	PLATES	W LEN Y X	CHORDS	MAX. FACTORED	FACTORED	WEBS	MAX. FACTORED	FORCE	MAX	CSF (LC)
B	TMVW+p	MT20	5.0 8.0 2.00 2.00	MEMB.	FORCE	VERT. LOAD LC1	MEMB.	FORCE	MAX	CSF (LC)	
C	TMVW-i	MT20	4.0 4.0 2.00 1.25	FR-TO	(LBS)	(PLF)	FR-TO	(LBS)	CSF (LC)		
D	TTWW-m	MT20	5.0 6.0 2.00 1.75	A-B	0/41	-91.8	-91.8	-357/0	0.16 (1)		
E	TMVW-i	MT20	4.0 4.0	B-C	-1994/0	-91.8	-91.8	-121/0	0.10 (1)		
F	TS-i	MT20	3.0 6.0	C-D	-1857/0	-91.8	-91.8	0/188	0.05 (4)		
G	TMVW-w	MT20	2.0 4.0	D-E	-1923/0	-91.8	-91.8	0/810	0.13 (1)		
H	TTWW-m	MT20	5.0 6.0 2.00 1.75	E-F	-1921/0	-91.8	-91.8	-569/0	0.31 (1)		
I	TMVW-i	MT20	4.0 4.0 2.00 1.25	F-G	-1921/0	-91.8	-91.8	-3/0	0.00 (1)		
J	TMVW+p	MT20	5.0 8.0 2.00 2.00	G-H	-1921/0	-91.8	-91.8	-568/0	0.31 (1)		
L	BMV1+p	MT20	3.0 4.0	H-I	-1957/0	-91.8	-91.8	0/189	0.13 (1)		
M	BMVW-i	MT20	5.0 6.0	I-J	-1994/0	-91.8	-91.8	0/187	0.05 (4)		
N, Q, S				J-K	0/41	-91.8	-91.8	-121/0	0.10 (1)		
N	BMVW-i	MT20	4.0 4.0	U-B	-2028/0	0.0	0.0	-358/0	0.18 (1)		
O	BS-i	MT20	3.0 6.0	L-J	-2028/0	0.0	0.0	0/1617	0.38 (1)		
P	BMVW-i	MT20	4.0 9.0	U-T	0/0	-18.5	-18.5	0/1617	0.38 (1)		
R	BS-i	MT20	3.0 6.0	T-S	0/1555	-18.5	-18.5				
T	BMVW-i	MT20	5.0 6.0	S-R	0/1477	-18.5	-18.5				
U	BMV1+p	MT20	3.0 4.0	R-Q	0/1477	-18.5	-18.5				
				Q-P	0/1923	-18.5	-18.5				
				P-O	0/1478	-18.5	-18.5				
				O-N	0/1478	-18.5	-18.5				
				N-M	0/1555	-18.5	-18.5				
				M-L	0/0	-18.5	-18.5				



Structural component only
DWG# T-2007087


ALLOWABLE DEF. (LL) = L/360 (1.17)
CALCULATED VERT. DEF. (LL) = L/999 (0.09)
ALLOWABLE DEF. (TL) = L/360 (1.17)
CALCULATED VERT. DEF. (TL) = L/999 (0.16)
CSI: TC=0.40/1.00 (D-E:1), BC=0.38/1.00 (P-Q:1),
WB=0.38/1.00 (B-T:1), SSI=0.25/1.00 (D-E:1)
DOL LUMBER=1.00 NAIL=1.00 LS BEND=1.10
COMP=1.10 SHEAR=1.10 TENS=1.10
COMPANION LIVE LOAD FACTOR = 1.00
TRUSS PLATE MANUFACTURER IS NOT
RESPONSIBLE FOR QUALITY CONTROL IN THE
TRUSS MANUFACTURING PLANT.
NAIL VALUES
PLATE GRIP (DRY) SHEAR SECTION
(PSI) (PLI) (PLI)
MAX MIN MAX MIN MAX MIN
MT20 818 354 1667 798 1987 1666
PLATE PLACEMENT TOL = 0.250 inches
PLATE ROTATION TOL = 5.0 Deg.
JSI GRIP= 0.89 (B) (INPUT = 0.90)
JSI METAL= 0.50 (C) (INPUT = 1.00)

Structural component only
DWG# T-2007088

JOB NAME	TRUSS NAME	QUANTITY	PLY	JOB DESC.	DRWG NO.
408151	T27	2	1	GREEN PARK HOMES	
Tamarack Roof Truss, Burlington					

Version 8.310 S Oct 29 2019 Mitek Industries, Inc. Sat Apr 25 11:19:53 2020 Page 1

ID:h2df1gC44wS_E2t2qPs_atz1lRw-TrgPQ2sivCVC7mnMST9S9GhS1uT3o2SIR1ZNUzNCXa



LUMBER	N. L. G. A. RULES	CHORDS	SIZE	LUMBER	DESCR.
A - D	2x4	DRY	No.2	SPF	
D - E	2x4	DRY	No.2	SPF	
E - G	2x4	DRY	No.2	SPF	
G - H	2x4	DRY	No.2	SPF	
H - K	2x4	DRY	No.2	SPF	
T - B	2x4	DRY	No.2	SPF	
L - J	2x4	DRY	No.2	SPF	
T - Q	2x4	DRY	No.2	SPF	
O - O	2x4	DRY	No.2	SPF	
O - L	2x4	DRY	No.2	SPF	
ALL WEBS EXCEPT	2x4	DRY	No.2	SPF	
S - C	2x3	DRY	No.2	SPF	
C - R	2x3	DRY	No.2	SPF	
N - I	2x3	DRY	No.2	SPF	
M - I	2x3	DRY	No.2	SPF	
B - S	2x3	DRY	No.2	SPF	
M - J	2x3	DRY	No.2	SPF	

DRY: SEASONED LUMBER.

PLATES (table is in inches)

JT TYPE	PLATES	W	LEN	Y	X
B	TMVW-p	MT20	5.0	8.0	1.50 3.00
C	TMVW-t	MT20	4.0	4.0	2.00 1.25
D	TS-t	MT20	3.0	6.0	
E	TMVW-in	MT20	5.0	8.0	Edge 3.00
F	TMVW-w	MT20	5.0	8.0	Edge 3.00
G	TMVW-m	MT20	5.0	8.0	Edge 3.00
H	TS-t	MT20	3.0	6.0	
I	TMVW-t	MT20	4.0	4.0	2.00 1.25
J	TMVW-p	MT20	5.0	8.0	1.50 3.00
L	BMV1-p	MT20	3.0	4.0	
M	BMVW-t	MT20	5.0	8.0	
N	BMVW-t	MT20	4.0	4.0	
O	BS-t	MT20	3.0	6.0	
P	BMVW-t	MT20	4.0	8.0	
Q	BS-t	MT20	3.0	8.0	
R	BMVW-t	MT20	4.0	4.0	
S	BMVW-t	MT20	5.0	8.0	
T	BMV1-p	MT20	3.0	4.0	

DIMENSIONS, SUPPORTS AND LOADINGS SPECIFIED BY FABRICATOR TO BE VERIFIED BY BUILDING DESIGNER

BEARINGS							
	FACTORED		MAXIMUM FACTORED			INPUT	REQD
	GROSS REACTION		GROSS REACTION			BRG	BRG
JT	VERT	HORZ	DOWN	HORZ	UPLIFT	IN-SX	IN-SX
T	2088	0	2088	0	0	5-8	5-8
L	2088	0	2088	0	0	5-8	5-8

UNFACTORED REACTIONS

1ST LCASE		MAX/MIN COMPONENT REACTIONS					
JT	COMBINED	SNOW	LIVE	PERM.LIVE	WIND	DEAD	SOIL
T	1458	971/0	0/0	0/0	0/0	488/0	0/0
L	1458	971/0	0/0	0/0	0/0	488/0	0/0

BEARING MATERIAL TO BE SPF NO.2 OR BETTER AT JOINT(S) T, L

BRACING

TOP CHORD TO BE SHEATHED OR MAX. PURLIN SPACING = 4.27 FT.
MAX. UNBRACED BOTTOM CHORD LENGTH = 10.00 FT OR RIGID CEILING DIRECTLY APPLIED.

ALL PITCH BREAKS AND PERIMETER CORNER JOINTS MUST BE LATERALLY RESTRAINED.

1 LATERAL BRACE(S) AT 1/2 LENGTH OF C-R, F-P, IN.

END VERTICAL(S) MUST BE SHEATHED OR HAVE BRACES AS INDICATED IN THE MAX. UNBRACED LENGTH COLUMN OF THE TABLE BELOW

LOADING

TOTAL LOAD CASES: (4)

CHORDS	MEMB.	MAX. FACTORED FORCE (LBS)	FACTORED VERT. LOAD (PLF)	MAX. FACTORED HORZ. LOAD (CSI (LC))	MAX. FACTORED UNBRACED LENGTH (FR-TO)	WEBS	MEMB.	MAX. FACTORED FORCE (LBS)	MAX. FACTORED HORZ. LOAD (CSI (LC))
FR-TO						FR-TO			
A-B	0/41	-91.8	-91.8	0.13 (1)	10.00	S-C	-245/10	0.17 (1)	
B-C	-2038/0	-91.8	-91.8	0.50 (1)	4.27	C-R	-314/0	0.15 (1)	
C-D	-1844/0	-91.8	-91.8	0.46 (1)	4.47	R-E	0/338	0.06 (1)	
D-E	-1844/0	-91.8	-91.8	0.46 (1)	4.47	E-P	0/469	0.08 (1)	
E-F	-1621/0	-91.8	-91.8	0.50 (1)	4.60	P-F	-699/0	0.45 (1)	
F-G	-1621/0	-91.8	-91.8	0.50 (1)	4.60	P-G	0/469	0.08 (1)	
G-H	-1844/0	-91.8	-91.8	0.46 (1)	4.47	N-G	0/338	0.05 (1)	
H-I	-1844/0	-91.8	-91.8	0.46 (1)	4.47	N-I	-314/0	0.15 (1)	
I-J	-2038/0	-91.8	-91.8	0.50 (1)	4.27	M-I	-245/10	0.17 (1)	
J-K	0/41	-91.8	-91.8	0.13 (1)	10.00	B-S	0/1637	0.37 (1)	
K-L	-2021/0	0.0	0.0	0.21 (1)	5.94	M-J	0/1637	0.37 (1)	
L-J	-2021/0	0.0	0.0	0.21 (1)	5.94				
T-S	0/0	-18.5	-18.5	0.14 (4)	10.00				
S-R	0/1597	-18.5	-18.5	0.33 (1)	10.00				
R-Q	0/1387	-18.5	-18.5	0.30 (1)	10.00				
Q-P	0/1387	-18.5	-18.5	0.30 (1)	10.00				
P-O	0/1387	-18.5	-18.5	0.30 (1)	10.00				
O-N	0/1387	-18.5	-18.5	0.30 (1)	10.00				
N-M	0/1597	-18.5	-18.5	0.33 (1)	10.00				
M-L	0/0	-18.5	-18.5	0.14 (4)	10.00				

TOTAL WEIGHT = 2 X 190 = 380 lb

DESIGN CRITERIA

SPECIFIED LOADS:
TOP CH. LL = 25.6 PSF
DL = 6.0 PSF
BOT CH. LL = 0.0 PSF
DL = 7.4 PSF
TOTAL LOAD = 39.0 PSF

SPACING = 24.0 IN. C/C

LOADING IN FLAT SECTION BASED ON A SLOPE OF 8.00/12

THIS TRUSS IS DESIGNED FOR RESIDENTIAL OR SMALL BUILDING REQUIREMENTS OF PART 9, NBCC 2010, NBCC 2015

THIS DESIGN COMPLIES WITH:

- PART 9 OF NBCC 2018, NBC 2012, ABC 2019
- PART 9 OF NBC 2012 (2019 AMENDMENT)
- CSA 086-09, CSA 066-14
- TPIC 2011, TPIC 2014

(55 % OF 31.3 P.S.F. G.S.L. PLUS 8.4 P.S.F. RAIN LOAD) EQUALS 25.8 P.S.F. SPECIFIED ROOF LIVE LOAD

ALLOWABLE DEFL.(LL) = L/360 (1.17")
CALCULATED VERT. DEFL.(LL) = L/999 (0.07")
ALLOWABLE DEFL.(TL) = L/360 (1.17")
CALCULATED VERT. DEFL.(TL) = L/999 (0.14")

CSI: TC=0.50/1.00 (E-F:1), BC=0.33/1.00 (M-N:1), WB=0.45/1.00 (F-P:1), SS=0.28/1.00 (E-F:1)

DOL LUMBER=1.00 NAIL=1.00 LS BEND=1.10
COMP=1.10 SHEAR=1.10 TENS=1.10

COMPANION LIVE LOAD FACTOR = 1.00

TRUSS PLATE MANUFACTURER IS NOT RESPONSIBLE FOR QUALITY CONTROL IN THE TRUSS MANUFACTURING PLANT.


NAIL VALUES

PLATE GRIP(DRY) SHEAR SECTION
(PSI) (PL) (PL)
MAX MIN MAX MIN MAX MIN
MT20 618 354 1667 788 1987 1658

PLATE PLACEMENT TOL = 0.250 inches

PLATE ROTATION TOL = 5.0 Deg.

JSI GRIP= 0.89 (J) (INPUT = 0.90)
JSI METAL= 0.47 (O) (INPUT = 1.00)



Structural component only
DWG# T-2007089


CONTINUED ON PAGE 2

JOB NAME	TRUSS NAME	QUANTITY	PLY	JOB DESC.	TRUSS DESC.	DRWG NO.
408151	T28	2	1	GREEN PARK HOMES		

Tamarack Roof Truss, Burlington

Version 8.310 S Oct 29 2019 Mitak Industries, Inc. Sat Apr 25 11:19:54 2020 Page 1

ID:h2dfgC44wS_E2tqPs_atzllRw-x1EndOtNgwd3kwMZ0AghhTAWTQH0oB7bX5n7vxzNCXZ



Scale: 1/4\"/>

LUMBER

N. L. G. A. RULES	
CHORDS	SIZE
A - D	2x4
D - G	2x4
L - B	2x4
H - F	2x4
L - J	2x4
J - H	2x4

ALL WEBS 2x3 DRY No.2 EXCEPT

DRY: SEASONED LUMBER.

PLATES (table is in inches)

JT TYPE	PLATES	W	LEN	Y	X
B TMV+p	MT20	3.0	4.0		
C TMWW-t	MT20	4.0	6.0		
D TTWW+p	MT20	4.0	6.0	Edge	
E TMWW-t	MT20	4.0	5.0		
F TMV+p	MT20	3.0	4.0		
H BMVW-t	MT20	4.0	4.0		
I BMWW-t	MT20	4.0	6.0		
J BS-t	MT20	3.0	6.0		
K BMWW-t	MT20	4.0	6.0		
L BMVW-t	MT20	4.0	4.0		

Edge - INDICATES REFERENCE CORNER OF PLATE TOUCHES EDGE OF CHORD.

DIMENSIONS, SUPPORTS AND LOADINGS SPECIFIED BY FABRICATOR TO BE VERIFIED BY BUILDING DESIGNER

BEARINGS

	FACTORED GROSS REACTION	MAXIMUM FACTORED GROSS REACTION	INPUT BRG	REQD BRG
JT	VERT	HORZ	DOWN	HORZ
L	1041	0	1041	0
H	1041	0	1041	0

UNFACTORED REACTIONS

1ST LCASE MAX/MIN. COMPONENT REACTIONS

JT	COMBINED	SNOW	LIVE	PERMLIVE	WIND	DEAD	SOIL
L	734	495 / 0	0 / 0	0 / 0	0 / 0	239 / 0	0 / 0
H	734	495 / 0	0 / 0	0 / 0	0 / 0	239 / 0	0 / 0

BEARING MATERIAL TO BE SPF NO.2 OR BETTER AT JOINT(S) L, H

BRACING

TOP CHORD TO BE SHEATHED OR MAX. PURLIN SPACING = 6.25 FT.
MAX. UNBRACED BOTTOM CHORD LENGTH = 10.00 FT OR RIGID CEILING DIRECTLY APPLIED.

ALL PITCH BREAKS AND PERIMETER CORNER JOINTS MUST BE Laterally RESTRAINED.

LOADING

TOTAL LOAD CASES: (4)

MEMB.	MAX. FACTORED FORCE (LBS)	FACTORED VERT. LOAD (LBS)	FACTORED HORIZ. LOAD (LBS)	MAX. UNBRACED LENGTH (FT)	MEMB.	MAX. FACTORED FORCE (LBS)	FACTORED HORIZ. LOAD (LBS)
FR-TO							
A-B	0 / 41	-91.8	-91.8	0.13 (1)	D-I	0 / 339	0.08 (1)
B-C	0 / 29	-91.8	-91.8	0.26 (1)	E-H	-222 / 0	0.09 (1)
C-D	-764 / 0	-91.8	-91.8	0.20 (1)	K-D	0 / 339	0.08 (1)
D-E	-764 / 0	-91.8	-91.8	0.20 (1)	C-K	-222 / 0	0.09 (1)
E-F	0 / 29	-91.8	-91.8	0.26 (1)	L-C	-964 / 0	0.08 (1)
F-G	0 / 41	-91.8	-91.8	0.13 (1)	E-H	-964 / 0	0.08 (1)
L-B	-270 / 0	0.0	0.0	0.03 (1)			
H-F	-270 / 0	0.0	0.0	0.03 (1)			
L-K	0 / 832	-18.5	-18.5	0.18 (4)			
K-J	0 / 459	-18.5	-18.5	0.17 (4)			
J-I	0 / 459	-18.5	-18.5	0.17 (4)			
I-H	0 / 832	-18.5	-18.5	0.18 (4)			

TOTAL WEIGHT = 2 X 82 = 163 LBS

DESIGN CRITERIA

SPECIFIED LOADS:

TOP CH.	LL = 25.6 PSF
	DL = 6.0 PSF
BOT CH.	LL = 0.0 PSF
	DL = 7.4 PSF
TOTAL LOAD	= 39.0 PSF

SPACING = 24.0 IN. C/C

THIS TRUSS IS DESIGNED FOR RESIDENTIAL OR SMALL BUILDING REQUIREMENTS OF PART 9, NBCC 2010, NBCC 2015

THIS DESIGN COMPLIES WITH:

- PART 9 OF NBCC 2018, CBC 2012, ABC 2019
- PART 9 OF CBC 2012 (2019 AMENDMENT)
- CSA 086-09, CSA 086-14
- TPIC 2011, TPIC 2014

(55% OF 31.3 P.S.F. G.S.L. PLUS 8.4 P.S.F. RAIN LOAD) EQUALS 25.6 P.S.F. SPECIFIED ROOF LIVE LOAD

ALLOWABLE DEFL.(LL) = $L/360$ (0.55")
CALCULATED VERT. DEFL.(LL) = $L/899$ (0.02")
ALLOWABLE DEFL.(TL) = $L/360$ (0.55")
CALCULATED VERT. DEFL.(TL) = $L/999$ (0.04")

CSI: TC=0.26/1.00 (B-C:1), BC=0.18/1.00 (H-I:4), WB=0.86/1.00 (E-H:1), SSI=0.14/1.00 (C-D:1)

DOL LUMBER=1.00 NAIL=1.00 LS BEND=1.10
COMP=1.10 SHEAR=1.10 TENS=1.10

COMPANION LIVE LOAD FACTOR = 1.00

TRUSS PLATE MANUFACTURER IS NOT RESPONSIBLE FOR QUALITY CONTROL IN THE TRUSS MANUFACTURING PLANT.

NAIL VALUES


PLATE GRIP(DRY) SHEAR SECTION	(PSI)	(PL)	(PL)
	MAX	MIN	MAX
MT20	618	354	1667

PLATE PLACEMENT TOL. = 0.250 inches


PLATE ROTATION TOL. = 5.0 Deg.

JSI GRIP=0.78 (C) (INPUT = 0.90)

JSI METAL=0.26 (C) (INPUT = 1.00)



Structural component only
DWG# T-2007090



LUMBER	N. L. G. A. RULES	CHORDS	SIZE	LUMBER
A - D	2x4	DRY	No.2	
D - G	2x4	DRY	No.2	
L - B	2x4	DRY	No.2	
H - F	2x4	DRY	No.2	
L - J	2x4	DRY	No.2	
J - H	2x4	DRY	No.2	
ALL WEBS	2x3	DRY	No.2	
EXCEPT				

DRY: SEASONED LUMBER.

PLATES (table is in inches)

JT	TYPE	PLATES	W	LEN	Y	X
B	TMV+p	MT20	3.0	4.0		
C	TMWW-t	MT20	4.0	4.0	2.00	1.50
D	TTWW+p	MT20	5.0	6.0	Edge	
E	TMWW-t	MT20	4.0	4.0	2.00	1.50
F	TMV+p	MT20	3.0	4.0		
H	BMVW-t	MT20	4.0	4.0		
I	BMVW-t	MT20	4.0	4.0		
J	BS-t	MT20	3.0	6.0		
K	BMVW-t	MT20	4.0	4.0		
L	BMVW-t	MT20	4.0	4.0		

Edge - INDICATES REFERENCE CORNER OF PLATE TOUCHES EDGE OF CHORD.

DIMENSIONS, SUPPORTS AND LOADINGS SPECIFIED BY FABRICATOR TO BE VERIFIED BY BUILDING DESIGNER

BEARINGS	FACTORED GROSS REACTION	MAXIMUM FACTORED GROSS REACTION	INPUT BRG	REQD BRG
JT	VERT	DOWN	IN-SX	IN-SX
L	1041	0	5-8	5-8
H	1041	0	5-8	5-8

UNFACTORED REACTIONS

1ST CASE	MAX/MIN COMPONENT REACTIONS	DEAD	SOIL
JT	COMBINED		
L	734	495/0	0/0
H	734	495/0	0/0

BEARING MATERIAL TO BE SPF NO.2 OR BETTER AT JOINT(S) L, H

BRACING

TOP CHORD TO BE SHEATHED OR MAX. PURLIN SPACING = 6.25 FT.
MAX. UNBRACED BOTTOM CHORD LENGTH = 10.00 FT OR RIGID CEILING DIRECTLY APPLIED.

ALL PITCH BREAKS AND PERIMETER CORNER JOINTS MUST BE Laterally RESTRAINED.

LOADING

TOTAL LOAD CASES: (4)

CHORDS	MAX. FACTORED FORCE (LBS)	FACTORED VERT. LOAD (PLF)	MAX. UNBRACED LENGTH (LC)	WEBS	MAX. FACTORED FORCE (LBS)	MAX. UNBRACED LENGTH (LC)
MEMB.				MEMB.		
FR-TO		FROM TO		FR-TO		
A-B	0/41	-91.8 -91.8	0.13 (1)	10.00	D-I	0/254
B-C	0/28	-91.8 -91.8	0.26 (1)	10.00	J-E	-138/14
C-D	-633/0	-91.8 -91.8	0.20 (1)	6.25	K-D	0/254
D-E	-633/0	-91.8 -91.8	0.20 (1)	8.25	C-K	-138/14
E-F	0/28	-91.8 -91.8	0.26 (1)	10.00	L-C	-875/0
F-G	0/41	-91.8 -91.8	0.13 (1)	10.00	E-H	-875/0
L-B	-278/0	0.0 0.0	0.04 (1)	7.81		
H-F	-278/0	0.0 0.0	0.04 (1)	7.81		
L-K	0/495	-18.5 -18.5	0.17 (4)	10.00		
K-J	0/395	-18.5 -18.5	0.16 (4)	10.00		
J-I	0/395	-18.5 -18.5	0.16 (4)	10.00		
I-H	0/495	-18.5 -18.5	0.17 (4)	10.00		

TOTAL WEIGHT = 91 lb

DESIGN CRITERIA

SPECIFIED LOADS:

TOP CH.	LL = 25.6 PSF
DL = 8.0 PSF	
BOT CH.	LL = 0.0 PSF
DL = 7.4 PSF	
TOTAL LOAD	= 39.0 PSF

SPACING = 24.0 IN./C

THIS TRUSS IS DESIGNED FOR RESIDENTIAL OR SMALL BUILDING REQUIREMENTS OF PART 9, NBCC 2010, NBCC 2015

THIS DESIGN COMPLIES WITH:

- PART 9 OF BCBC 2018, CBC 2012, ABC 2019
- PART 9 OF OBC 2012 (2019 AMENDMENT)
- CSA 086-09, CSA 086-14
- TPIC 2011, TPIC 2014

(55% OF 31.3 P.S.F. G.S.L. PLUS 8.4 P.S.F. RAIN LOAD) EQUALS 25.6 P.S.F. SPECIFIED ROOF LIVE LOAD

ALLOWABLE DEFL.(LL) = L/360 (0.55")
CALCULATED VERT. DEFL.(LL) = L/999 (0.02")
ALLOWABLE DEFL.(TL) = L/360 (0.55")
CALCULATED VERT. DEFL.(TL) = L/999 (0.04")

CSI: TC=0.28/1.00 (E-F:1), BC=0.17/1.00 (K-L:4),
WB=0.90/1.00 (E-H:1), SS=0.14/1.00 (E-F:1)

DOL LUMBER=1.00 NAIL=1.00 LS BEND=1.10
COMP=1.10 SHEAR=1.10 TENS=1.10

COMPANION LIVE LOAD FACTOR = 1.00

TRUSS PLATE MANUFACTURER IS NOT RESPONSIBLE FOR QUALITY CONTROL IN THE TRUSS MANUFACTURING PLANT.

NAIL VALUES

PLATE GRIP(DRY)	SHEAR (PSI)	SECTION (PLI)
MT20	618	354
	1667	788
	1987	1655


PLATE PLACEMENT TOL = 0.250 inches

PLATE ROTATION TOL = 5.0 Deg.

JSI GRIP= 0.88 (E) (INPUT = 0.90)
JSI METAL= 0.34 (C) (INPUT = 1.00)



JOB NAME 408151	TRUSS NAME T30	QUANTITY 1	PLY 1	JOB DESC. GREEN PARK HOMES	DRWG NO.
Tamarack Roof Truss, Burlington				TRUSS DESC.	



LUMBER

N. L. G. A. RULES

CHORDS	SIZE	DRY	LUMBER
A - D	2x4	DRY	No.2
D - E	2x6	DRY	No.2
E - H	2x4	DRY	No.2
L - B	2x4	DRY	No.2
I - G	2x4	DRY	No.2
L - K	2x4	DRY	No.2
K - I	2x4	DRY	No.2

ALL WEBS 2x3 DRY No.2 EXCEPT

DRY: SEASONED LUMBER.

PLATES (table is in inches)

JT TYPE	PLATES	W	LEN	Y	X
B	TMV-p	MT20	3.0	4.0	
C	TMVW-t	MT20	4.0	4.0	2.00 1.75
D	TTW-h	MT20	4.0	8.0	
E	TTW-w	MT20	5.0	8.0	Edge
F	TMVW-t	MT20	4.0	8.0	
G	TMV-p	MT20	3.0	4.0	
I	BMVW-t	MT20	4.0	4.0	
J	BMVW-t	MT20	4.0	4.0	
K	BSVW-t	MT20	6.0	9.0	Edge 3.75
L	BMVW-t	MT20	4.0	4.0	

Edge - INDICATES REFERENCE CORNER OF PLATE TOUCHES EDGE OF CHORD.

DIMENSIONS, SUPPORTS AND LOADINGS SPECIFIED BY FABRICATOR TO BE VERIFIED BY BUILDING DESIGNER

BEARINGS

FACTORED GROSS REACTION	MAXIMUM FACTORED GROSS REACTION	INPUT BRG	REQD BRG
JT VERT	DOWN	UPLIFT	IN-SX
L 1041 0	1041 0	0	5-8
I 1041 0	1041 0	0	MECHANICAL

A SUITABLE HANGER/MECHANICAL CONNECTION IS REQUIRED AT JOINT I. MINIMUM BEARING LENGTH AT JOINT I = 3-8.

UNFACTORED REACTIONS

1ST LCASE	MAX/MIN. COMPONENT REACTIONS
JT COMBINED	SNOW LIVE PERM. LIVE WIND DEAD SOIL
L 734	495 / 0 0 / 0 0 / 0 0 / 0 239 / 0 0 / 0
I 734	495 / 0 0 / 0 0 / 0 0 / 0 239 / 0 0 / 0

BEARING MATERIAL TO BE SPF NO.2 OR BETTER AT JOINT(S) L

BRACING
TOP CHORD TO BE SHEATHED OR MAX. PURLIN SPACING = 8.25 FT.
MAX. UNBRACED BOTTOM CHORD LENGTH = 10.00 FT OR RIGID CEILING DIRECTLY APPLIED.

ALL PITCH BREAKS AND PERIMETER CORNER JOINTS MUST BE Laterally RESTRAINED.

1 LATERAL BRACE(S) AT 1/2 LENGTH OF E-K.

END VERTICAL(S) MUST BE SHEATHED OR HAVE BRACES AS INDICATED IN THE MAX. UNBRACED LENGTH COLUMN OF THE TABLE BELOW

LOADING

TOTAL LOAD CASES: (4)

CHORDS				WEBS			
MEMB.	MAX. FACTORED FORCE (LBS)	FACTORED VERT. LOAD (PLF)	LC1 MAX (LC)	MAX. UNBRACED LENGTH	MEMB.	MAX. FACTORED FORCE (LBS)	MAX. CS1 (LC)
FR-TO		FROM TO			FR-TO		
A-B	0 / 41	-91.8	-91.8 0.13 (1)	10.00	C-K	-98 / 9	0.09 (1)
B-C	0 / 27	-91.8	-91.8 0.23 (1)	10.00	K-D	0 / 164	0.04 (1)
C-D	-596 / 0	-91.8	-91.8 0.18 (1)	8.25	K-E	-109 / 0	0.07 (4)
D-E	-414 / 0	-91.8	-91.8 0.01 (1)	8.25	J-E	0 / 268	0.07 (4)
E-F	-582 / 0	-91.8	-91.8 0.18 (1)	8.25	J-F	-93 / 15	0.09 (1)
F-G	0 / 27	-91.8	-91.8 0.23 (1)	10.00	L-C	-846 / 0	0.78 (1)
G-H	0 / 41	-91.8	-91.8 0.13 (1)	10.00	F-I	-852 / 0	0.79 (1)
L-B	-265 / 0	0.0	0.0 0.04 (1)	7.81			
I-G	-265 / 0	0.0	0.0 0.04 (1)	7.81			
L-K	0 / 468	-18.5	-18.5 0.36 (4)	10.00			
K-J	0 / 424	-18.5	-18.5 0.30 (4)	10.00			
J-I	0 / 477	-18.5	-18.5 0.30 (4)	10.00			

TOTAL WEIGHT = 97 lb

DESIGN CRITERIA

SPECIFIED LOADS:
TOP CH. LL = 25.8 PSF
DL = 8.0 PSF
BOT CH. LL = 0.0 PSF
DL = 7.4 PSF
TOTAL LOAD = 39.0 PSF

SPACING = 24.0 IN. C/C

LOADING IN FLAT SECTION BASED ON A SLOPE OF 6.00/12

THIS TRUSS IS DESIGNED FOR RESIDENTIAL OR SMALL BUILDING REQUIREMENTS OF PART 9, NBC 2010, NBC 2015

THIS DESIGN COMPLIES WITH:
- PART 9 OF BCBC 2018, OBC 2012, ABC 2019
- PART 9 OF OBC 2012 (2019 AMENDMENT)
- CSA 086-09, CSA 086-14
- TPIC 2011, TPIC 2014

(55% OF 31.3 P.S.F. G.S.L. PLUS 8.4 P.S.F. RAIN LOAD) EQUALS 25.8 P.S.F. SPECIFIED ROOF LIVE LOAD

ALLOWABLE DEFL.(LL) = U360 (0.55")
CALCULATED VERT. DEFL.(LL) = L / 999 (0.01")
ALLOWABLE DEFL.(TL) = U360 (0.55")
CALCULATED VERT. DEFL.(TL) = L / 999 (0.17")

CSI: TC=0.23/1.00 (B-C:1), BC=0.38/1.00 (K-L:4), WB=0.79/1.00 (F-I:1), SS=0.14/1.00 (J-K:4)

DOL LUMBER=1.00 NAIL=1.00 LS BEND=1.10 COMP=1.10 SHEAR=1.10 TENS=1.10

COMPANION LIVE LOAD FACTOR = 1.00

TRUSS PLATE MANUFACTURER IS NOT RESPONSIBLE FOR QUALITY CONTROL IN THE TRUSS MANUFACTURING PLANT.


NAIL VALUES

PLATE GRIP(DRY)	SHEAR (PSI)	SECTION (PLI)
MAX MIN	MAX MIN	MAX MIN
MT20	618 354	1867 788 1967 1856


PLATE PLACEMENT TOL = 0.250 inches

PLATE ROTATION TOL = 3.0 Deg.

JSI GRIP = 0.89 (C) (INPUT = 0.90)
JSI METAL = 0.31 (C) (INPUT = 1.00)



Structural component only
DWG# T-2007092



LUMBER		
N. L. G. A. RULES	SIZE	LUMBER
CHORDS		
A - D	2x4	DRY No.2
D - E	2x4	DRY No.2
E - H	2x4	DRY No.2
M - B	2x4	DRY No.2
I - G	2x4	DRY No.2
M - K	2x4	DRY No.2
K - I	2x4	DRY No.2
ALL WEBS	2x3	DRY No.2
EXCEPT		

DRY: SEASONED LUMBER.

PLATES (table is in inches)

JT	TYPE	PLATES	W	LEN	Y	X
B	TMV+p	MT20	3.0	4.0		
C	TMWW-i	MT20	4.0	4.0	2.00	1.75
D	TTW-m	MT20	4.0	4.0		
E	TTWW+m	MT20	5.0	6.0	2.25	1.50
F	TMWW-i	MT20	4.0	4.0	2.00	1.75
G	TMV+p	MT20	3.0	4.0		
I	BMVW1-i	MT20	4.0	4.0		
J	BMVW1-i	MT20	4.0	4.0		
K	BS-i	MT20	3.0	6.0		
L	BMVW1-i	MT20	4.0	9.0		
M	BMVW1-i	MT20	4.0	4.0		

DIMENSIONS, SUPPORTS AND LOADINGS SPECIFIED BY FABRICATOR TO BE VERIFIED BY BUILDING DESIGNER

FACTORED GROSS REACTION		MAXIMUM FACTORED GROSS REACTION		INPUT		REQD	
JT	VERT	HORZ	DOWN	HORZ	UPLIFT	BRG	IN-SX
M	1041	0	1041	0	0	5-8	5-8
I	1041	0	1041	0	0	MECHANICAL	

A SUITABLE HANGER/MECHANICAL CONNECTION IS REQUIRED AT JOINT I. MINIMUM BEARING LENGTH AT JOINT I = 3-8.

UNFACTORED REACTIONS

JT	COMBINED	SNOW	LIVE	PERM. LIVE	WIND	DEAD	SOIL
M	734	495/0	0/0	0/0	0/0	239/0	0/0
I	734	495/0	0/0	0/0	0/0	239/0	0/0

BEARING MATERIAL TO BE SPF NO.2 OR BETTER AT JOINT(S) M

BRACING

TOP CHORD TO BE SHEATHED OR MAX. PURLIN SPACING = 6.25 FT.
MAX. UNBRACED BOTTOM CHORD LENGTH = 10.00 FT OR RIGID CEILING DIRECTLY APPLIED.

ALL PITCH BREAKS AND PERIMETER CORNER JOINTS MUST BE Laterally RESTRAINED.

LOADING

TOTAL LOAD CASES: (4)

CHORDS				WEBS			
MEMB.	MAX. FACTORED FORCE (LBS)	FACTORED VERT. LOAD (PLF)	MAX. UNBRACED LENGTH (FT)	MEMB.	MAX. FACTORED FORCE (LBS)	MAX. UNBRACED LENGTH (FT)	
FR-TO		FROM TO		FR-TO			
A-B	0/41	-91.8 -91.8	0.13 (1)	C-L	-10/34	0.01 (4)	
B-C	0/22	-91.8 -91.8	0.16 (1)	L-D	8/110	0.03 (4)	
C-D	-613/0	-91.8 -91.8	0.13 (1)	E-E	0/0	0.00 (7)	
D-E	-453/0	-91.8 -91.8	0.14 (1)	F-F	0/109	0.03 (4)	
E-F	-612/0	-91.8 -91.8	0.13 (1)	G-G	-11/34	0.01 (4)	
F-G	0/22	-91.8 -91.8	0.16 (1)	H-H	-873/0	0.80 (1)	
G-H	0/41	-91.8 -91.8	0.13 (1)	I-I	-873/0	0.80 (1)	
H-I	-245/0	0.0 0.0	0.04 (1)				
I-J	-245/0	0.0 0.0	0.04 (1)				
J-K	0/457	-18.5 -18.5	0.21 (4)				
K-L	0/453	-18.5 -18.5	0.20 (4)				
L-M	0/453	-18.5 -18.5	0.20 (4)				
M-N	0/457	-18.5 -18.5	0.21 (4)				

TOTAL WEIGHT = 92 lb

DESIGN CRITERIA

SPECIFIED LOADS:
TOP CH. LL = 25.6 PSF
DL = 6.0 PSF
BOT CH. LL = 0.0 PSF
DL = 7.4 PSF
TOTAL LOAD = 39.0 PSF

SPACING = 24.0 IN. OC

LOADING IN FLAT SECTION BASED ON A SLOPE OF 6.00/12

THIS TRUSS IS DESIGNED FOR RESIDENTIAL OR SMALL BUILDING REQUIREMENTS OF PART 9, NBC 2010, NBC 2015

THIS DESIGN COMPLIES WITH:

- PART 9 OF CBC 2010, CBC 2012, ABC 2019
- PART 9 OF CBC 2012 (2019 AMENDMENT)
- CSA 086-09, CSA 088-14
- TPIC 2011, TPIC 2014

(55 % OF 31.3 P.S.F. G.S.L. PLUS 8.4 P.S.F. RAIN LOAD) EQUALS 25.6 P.S.F. SPECIFIED ROOF LIVE LOAD

ALLOWABLE DEFL.(LL) = L/360 (0.55")
CALCULATED VERT. DEFL.(LL) = L/989 (0.01")
ALLOWABLE DEFL.(TL) = L/360 (0.55")
CALCULATED VERT. DEFL.(TL) = L/989 (0.07")

CSF: TC=0.16/1.00 (F-G-1), BC=0.21/1.00 (L-J-4),
WB=0.60/1.00 (C-M-1), SS=0.12/1.00 (D-E-1)

DOL LUMBER=1.00 NAIL=1.00 LS BEND=1.10
COMP=1.10 SHEAR=1.10 TENS=1.10

COMPANION LIVE LOAD FACTOR = 1.00


TRUSS PLATE MANUFACTURER IS NOT RESPONSIBLE FOR QUALITY CONTROL IN THE TRUSS MANUFACTURING PLANT.

NAIL VALUES		PLATE GRIP (DRY)		SHEAR		SECTION	
(PS)	(PL)	(PS)	(PL)	(PS)	(PL)	(PS)	(PL)
MAX	MIN	MAX	MIN	MAX	MIN	MAX	MIN
MT20	618	354	1667	788	1987	1668	

PLATE PLACEMENT TOL. = 0.250 inches

PLATE ROTATION TOL. = 5.0 Deg.


JSI GRIP = 0.87 (C) (INPUT = 0.90)
JSI METAL = 0.31 (C) (INPUT = 1.00)



JOB NAME	TRUSS NAME	QUANTITY	PLY	JOB DESC.	TRUSS DESC.	DRWG NO.
408151	T32	1	1	GREEN PARK HOMES		

Tamarack Roof Truss, Burlington

Version 8.310 S Oct 29 2019 MITek Industries, Inc. Sat Apr 25 11:19:58 2020 Page 1
ID:n2dflgC44wS_E2tqPs_atzIfRw-ppJITWk98VDYgKFoldrJL812f0k80BSjK2zNCXV



Scale = 1/4" = 1'-0"

LUMBER	CHORDS	SIZE	DRY	LUMBER	DESCR.
A - C	2x4	DRY	No.2	SPF	
C - D	2x4	DRY	No.2	SPF	
D - F	2x4	DRY	No.2	SPF	
K - B	2x4	DRY	No.2	SPF	
G - E	2x4	DRY	No.2	SPF	
K - I	2x4	DRY	No.2	SPF	
I - G	2x4	DRY	No.2	SPF	
ALL WEBS	2x3	DRY	No.2	SPF	
EXCEPT					

DRY: SEASONED LUMBER.

PLATES (tablets in inches)

JT TYPE	PLATES	W	LEN	Y	X
B	TMVW-p	MT20	4.0	4.0	1.00 2.00
C	TTWW-m	MT20	5.0	6.0	2.25 1.50
D	TTW-m	MT20	4.0	4.0	
E	TMVW-p	MT20	4.0	4.0	1.00 2.00
G	BMV1-p	MT20	3.0	4.0	
H	BMVWW-t	MT20	4.0	9.0	
I	BS-I	MT20	3.0	6.0	
J	BMVW-t	MT20	4.0	4.0	
K	BMV1-p	MT20	3.0	4.0	

DIMENSIONS, SUPPORTS AND LOADINGS SPECIFIED BY FABRICATOR TO BE VERIFIED BY BUILDING DESIGNER

BEARINGS	FACTORED GROSS REACTION	MAXIMUM FACTORED GROSS REACTION	INPUT BRG	RECORD BRG
JT	VERT	DOWN	IN-SX	IN-SX
K	1041 0	1041 0	5-8	5-8
G	1041 0	1041 0	MECHANICAL	

A SUITABLE HANGER/MECHANICAL CONNECTION IS REQUIRED AT JOINT G. MINIMUM BEARING LENGTH AT JOINT G = 3-8.

UNFACTORED REACTIONS

1ST CASE	MAX/MIN COMPONENT REACTIONS
JT COMBINED	SNOW LIVE PERM.LIVE WIND DEAD SOIL
K	734 495/0 0/0 0/0 0/0 239/0 0/0
G	734 495/0 0/0 0/0 0/0 239/0 0/0

BEARING MATERIAL TO BE SPF NO.2 OR BETTER AT JOINT(S) K

BRACING

TOP CHORD TO BE SHEATHED OR MAX. PURLIN SPACING = 6.25 FT.
MAX. UNBRACED BOTTOM CHORD LENGTH = 10.00 FT OR RIGID CEILING DIRECTLY APPLIED.

ALL PITCH BREAKS AND PERIMETER CORNER JOINTS MUST BE Laterally RESTRAINED.

1 LATERAL BRACE(S) AT 1/2 LENGTH OF C-H.

END VERTICAL(S) MUST BE SHEATHED OR HAVE BRACES AS INDICATED IN THE MAX. UNBRACED LENGTH COLUMN OF THE TABLE BELOW

LOADING

TOTAL LOAD CASES: (4)

CHORDS	MEMB.	MAX. FACTORED FORCE (LBS)	FACTORED VERT. LOAD (PLF)	FACTORED LCI MAX	MAX. UNBRACED LENGTH FR-TO	WEBS	MEMB.	MAX. FACTORED FORCE (LBS)	MAX. CSI (LC)
A-B	0/41	-91.8	-91.8	0.13 (1)	10.00	J-C	-115/46	0.12 (1)	
B-C	-619/0	-91.8	-91.8	0.35 (1)	8.25	C-H	0/0	0.00 (1)	
C-D	-473/0	-91.8	-91.8	0.39 (1)	8.25	H-D	-115/46	0.12 (1)	
D-E	-619/0	-91.8	-91.8	0.35 (1)	8.25	B-J	0/525	0.12 (1)	
E-F	0/41	-91.8	-91.8	0.13 (1)	10.00	H-E	0/525	0.12 (1)	
K-B	-1000/0	0.0	0.0	0.16 (1)	7.81				
G-E	-1000/0	0.0	0.0	0.16 (1)	7.81				
K-J	0/0	-18.5	-18.5	0.13 (4)	10.00				
J-I	0/473	-18.5	-18.5	0.17 (4)	10.00				
I-H	0/473	-18.5	-18.5	0.17 (4)	10.00				
H-G	0/0	-18.5	-18.5	0.13 (4)	10.00				

TOTAL WEIGHT = 79 lb

(M/F)

DESIGN CRITERIA

SPECIFIED LOADS:
TOP CH. LL = 25.6 PSF
DL = 8.0 PSF
BOT CH. LL = 0.0 PSF
DL = 7.4 PSF
TOTAL LOAD = 39.0 PSF

SPACING = 24.0 IN. OC

LOADING IN FLAT SECTION BASED ON A SLOPE OF 6.00/12

THIS TRUSS IS DESIGNED FOR RESIDENTIAL OR SMALL BUILDING REQUIREMENTS OF PART 9, NBC 2010, NBCC 2015

THIS DESIGN COMPLIES WITH:
- PART 9 OF CBC 2010, CBC 2012, ABC 2019
- PART 9 OF NBC 2012 (2019 AMENDMENT)
- CSA 086-09, CSA 086-14
- TPIC 2011, TPIC 2014

(55% OF 31.3 P.S.F. G.S.L. PLUS 8.4 P.S.F. RAIN LOAD) EQUALS 25.6 P.S.F. SPECIFIED ROOF LIVE LOAD

ALLOWABLE DEFL.(LL) = L/360 (0.55")
CALCULATED VERT. DEFL.(LL) = L/999 (0.01")
ALLOWABLE DEFL.(TL) = L/360 (0.55")
CALCULATED VERT. DEFL.(TL) = L/999 (0.03")

CSI: TC=0.39/1.00 (C-D:1), BC=0.17/1.00 (H-J:4), WB=0.12/1.00 (B-J:1), SS=0.21/1.00 (C-D:1)

DOL LUMBER=1.00 NAIL=1.00 LS BEND=1.10 COMP=1.10 SHEAR=1.10 TENS=1.10

COMPANION LIVE LOAD FACTOR = 1.00

TRUSS PLATE MANUFACTURER IS NOT RESPONSIBLE FOR QUALITY CONTROL IN THE TRUSS MANUFACTURING PLANT.

NAIL VALUES

PLATE GRIP (DRY)	SHEAR (PSI)	SECTION (PLI)
MAX MIN	MAX MIN	MAX MIN
MT20	618 354	1687 788

PLATE PLACEMENT TOL. = 0.250 inches

PLATE ROTATION TOL. = 5.0 Deg.

JSI GRIP = 0.82 (B) (INPUT = 0.90)
JSI METAL = 0.23 (B) (INPUT = 1.00)




Structural component only
DWG# T-2007094

JOB NAME 408151	TRUSS NAME G33	QUANTITY 1	PLY 1	JOB DESC. GREEN PARK HOMES	DRWG NO.
--------------------	-------------------	---------------	----------	-------------------------------	----------

Tamarack Roof Truss, Burlington

Version 8.310 S Oct 29 2019 Mitek Industries, Inc. Sat Apr 25 11:19:40 2020 Page 1
ID:h2dfgC44wS_E2tZqPs_atzllRw-LLOVhjbzdt23nlsCEQP7Wb90nX9W01XJvONQkzNCXn



Scale = 1/32"

LUMBER

N. L. G. A. RULES	CHORDS	SIZE	LUMBER	DESCR.
L - B	2x4	DRY	No.2	SPF
A - D	2x4	DRY	No.2	SPF
D - G	2x4	DRY	No.2	SPF
H - F	2x4	DRY	No.2	SPF
L - H	2x4	DRY	No.2	SPF

ALL WEBS	2x3	DRY	No.2	SPF
ALL GABLE WEBS	2x3	DRY	No.2	SPF
DRY: SEASONED LUMBER.				

GABLE STUDS SPACED AT 2'-0" OC.

PLATES (table is in inches)

JT TYPE	PLATES	W	LEN	Y	X
B TMVW+p	MT20	4.0	4.0	1.00	2.00
C TMVW+w	MT20	2.0	4.0		
D TTW+p	MT20	4.0	6.0	Edge	
E TMVW+w	MT20	2.0	4.0		
F TMVW+p	MT20	4.0	4.0	1.00	2.00
H BMV1+p	MT20	3.0	4.0		
I BMVW1-t	MT20	4.0	4.0		
J BMVW1+w	MT20	2.0	4.0		
K BMVW1-t	MT20	4.0	4.0		
L BMV1+p	MT20	3.0	4.0		

Edge - INDICATES REFERENCE CORNER OF PLATE TOUCHES EDGE OF CHORD.

DIMENSIONS, SUPPORTS AND LOADINGS SPECIFIED BY FABRICATOR TO BE VERIFIED BY BUILDING DESIGNER

BEARINGS

THIS TRUSS DESIGNED FOR CONTINUOUS BEARINGS.

THIS TRUSS REQUIRES RIGID SHEATHING ON EXPOSED FACE.

BEARING MATERIAL TO BE SPF NO.2 OR BETTER AT JOINT(S).

BRACING

TOP CHORD TO BE SHEATHED OR MAX. PURLIN SPACING = 6.25 FT.

MAX. UNBRACED BOTTOM CHORD LENGTH = 10.00 FT. OR RIGID CEILING DIRECTLY APPLIED.

ALL PITCH BREAKS AND PERIMETER CORNER JOINTS MUST BE Laterally RESTRAINED.

LOADING

TOTAL LOAD CASES: (4)

CHORDS				WEBS			
MEMB.	MAX. FACTORED FORCE (LBS)	VERT. LOAD (PLF)	MAX. UNBRACED LENGTH (FT)	MEMB.	MAX. FACTORED FORCE (LBS)	MAX. UNBRACED LENGTH (FT)	
L-B	-231 / 0	0.0	0.02 (1)	J-D	-123 / 0	0.05 (1)	
A-B	0 / 41	-91.8	-91.8 0.13 (1)	K-C	-236 / 0	0.05 (1)	
B-C	-11 / 0	-91.8	-91.8 0.07 (1)	I-E	-236 / 0	0.05 (1)	
C-D	-32 / 0	-91.8	-91.8 0.07 (1)	B-K	0 / 23	0.01 (1)	
D-E	-32 / 0	-91.8	-91.8 0.07 (1)	I-F	0 / 23	0.01 (1)	
E-F	-11 / 0	-91.8	-91.8 0.07 (1)				
F-G	0 / 41	-91.8	-91.8 0.13 (1)				
H-F	-231 / 0	0.0	0.02 (1)				
L-K	0 / 0	-18.5	-18.5 0.02 (4)				
K-J	0 / 13	-18.5	-18.5 0.02 (4)				
J-I	0 / 13	-18.5	-18.5 0.02 (4)				
I-H	0 / 0	-18.5	-18.5 0.02 (4)				

TOTAL WEIGHT = 42 lb

DESIGN CRITERIA

SPECIFIED LOADS:

TOP CH.	LL = 25.6 PSF
	DL = 8.0 PSF
BOT CH.	LL = 0.0 PSF
	DL = 7.4 PSF
TOTAL LOAD =	39.0 PSF

SPACING = 2.0 IN. C/C

THIS TRUSS IS DESIGNED FOR RESIDENTIAL OR SMALL BUILDING REQUIREMENTS OF PART 9, NBCC 2010, NBCC 2015

THIS DESIGN COMPLIES WITH:
- PART 9 OF BCBC 2018, CBC 2012, ABC 2019
- PART 9 OF CBC 2012 (2019 AMENDMENT)
- CSA 086-09, CSA 085-14
- TPIC 2011, TPIC 2014

(55% OF 31.3 P.S.F. G.S.L. PLUS 8.4 P.S.F. RAIN LOAD) EQUALS 25.6 P.S.F. SPECIFIED ROOF LIVE LOAD

CSI: TO=0.13/1.00 (F-G:1), BC=0.02/1.00 (J-K:4), WB=0.05/1.00 (C-K:1), SSI=0.08/1.00 (F-G:1)

DOL LUMBER=1.00 NAIL=1.00 LS BEND=1.10 COMP=1.10 SHEAR=1.10 TENS=1.10

COMPANION LIVE LOAD FACTOR = 1.00

TRUSS PLATE MANUFACTURER IS NOT RESPONSIBLE FOR QUALITY CONTROL IN THE TRUSS MANUFACTURING PLANT.


NAIL VALUES

PLATE GRIP (DRY)	SHEAR	SECTION
(PSI)	(PLI)	(PLI)
MAX MIN	MAX MIN	MAX MIN
MT20 618 354	1667 788	1987 1658

PLATE PLACEMENT TOL = 0.250 inches


PLATE ROTATION TOL = 5.0 Deg.

JSI GRIP = 0.18 (C) (INPUT = 0.90)
JSI METAL = 0.13 (C) (INPUT = 1.00)



Structural component only
DWG# T-2007078

JOB NAME 408151	TRUSS NAME T33X	QUANTITY 1	PLY 1	JOB DESC. GREEN PARK HOMES	DRWG NO.
Tamarack Roof Truss, Burlington		TRUSS DESC.		Version 8.310 S Oct 29 2019 MITek Industries, Inc. Sat Apr 25 11:19:59 2020 Page 1	



LUMBER	N. L. G. A. RULES	CHORDS	SIZE	LUMBER	DESCR.
A - B	2x4	DRY	No.2	SPF	
B - C	2x4	DRY	No.2	SPF	
F - A	2x4	DRY	No.2	SPF	
D - C	2x4	DRY	No.2	SPF	
F - D	2x4	DRY	No.2	SPF	
ALL WEBS	2x3	DRY	No.2	SPF	

EXCEPT
DRY: SEASONED LUMBER.

PLATES (table is in inches)	JT	TYPE	PLATES	W	LEN	Y	X
A	TMW+p	MT20	4.0	4.0	1.00	2.00	
B	TTW+p	MT20	4.0	8.0	Edge		
C	TMW+p	MT20	4.0	4.0	1.00	2.00	
D	BMV1+p	MT20	3.0	4.0			
E	BMWVW-t	MT20	4.0	9.0			
F	BMV1+p	MT20	3.0	4.0			

Edge - INDICATES REFERENCE CORNER OF PLATE TOUCHES EDGE OF CHORD.

DIMENSIONS, SUPPORTS AND LOADINGS SPECIFIED BY FABRICATOR TO BE VERIFIED BY BUILDING DESIGNER

BEARINGS	FACTORED GROSS REACTION	MAXIMUM FACTORED GROSS REACTION	INPUT BRG	REORD BRG
JT	VERT	HORZ	DOWN	HORZ
F	486	0	486	0
D	486	0	486	0

UNFACTORED REACTIONS

1ST LCASE	MAX. MIN. COMPONENT REACTIONS	DEAD	SOIL
JT	COMBINED	SNOW	LIVE
F	351	230 / 0	0 / 0
D	351	230 / 0	0 / 0

BEARING MATERIAL TO BE SPF NO.2 OR BETTER AT JOINT(S) F, D

BRACING

TOP CHORD TO BE SHEATHED OR MAX. PURLIN SPACING = 6.25 FT.
MAX. UNBRACED BOTTOM CHORD LENGTH = 10.00 FT OR RIGID CEILING DIRECTLY APPLIED.

ALL PITCH BREAKS AND PERIMETER CORNER JOINTS MUST BE LATERALLY RESTRAINED.

LOADING

TOTAL LOAD CASES: (4)

CHORDS	MAX. FACTORED FORCE (LBS)	VERT. LOAD (PLF)	LC1 MAX (CSI (LC))	MAX. UNBRACED LENGTH	WEBS	MAX. FACTORED FORCE (LBS)	MAX. CSI (LC)
FR-TO					FR-TO		
A-B	-311 / 0	-91.8	-91.8 0.24 (1)	6.25	E-B	-14 / 72	0.03 (4)
B-C	-311 / 0	-91.8	-91.8 0.24 (1)	6.25	A-E	0 / 248	0.06 (1)
F-A	-454 / 0	0.0	0.0 0.05 (1)	7.81	E-C	0 / 248	0.06 (1)
D-C	-454 / 0	0.0	0.0 0.05 (1)	7.81			
F-E	0 / 0	-18.5	-18.5 0.11 (4)	10.00			
E-D	0 / 0	-18.5	-18.5 0.11 (4)	10.00			

TOTAL WEIGHT = 37 lb

DESIGN CRITERIA

SPECIFIED LOADS:
TOP CH. LL = 25.6 PSF
DL = 6.0 PSF
BOT CH. LL = 0.0 PSF
DL = 7.4 PSF
TOTAL LOAD = 39.0 PSF

SPACING = 24.0 IN./C/C

THIS TRUSS IS DESIGNED FOR RESIDENTIAL OR SMALL BUILDING REQUIREMENTS OF PART 9, NBCC 2010, NBCC 2015

THIS DESIGN COMPLIES WITH:

- PART 9 OF NBCC 2018, OBC 2012, ABC 2019
- PART 9 OF OBC 2012 (2019 AMENDMENT)
- CSA 086-09, CSA 086-14
- TPIC 2011, TPIC 2014

(55 % OF 31.3 P.S.F. G.S.L. PLUS 8.4 P.S.F. RAIN LOAD) EQUALS 25.6 P.S.F. SPECIFIED ROOF LIVE LOAD

ALLOWABLE DEFL.(LL) = L/360 (0.30")
CALCULATED VERT. DEFL.(LL) = L/999 (0.00")
ALLOWABLE DEFL.(TL) = L/360 (0.30")
CALCULATED VERT. DEFL.(TL) = L/999 (0.01")

CSI: TC=0.24/1.00 (A-B:1), BC=0.11/1.00 (E-F:4), WB=0.06/1.00 (C-E:1), SS=0.12/1.00 (A-B:1)

DOL LUMBER=1.00 NAIL=1.00 LS BEND=1.10
COMP=1.10 SHEAR=1.10 TENS=1.10

COMPANION LIVE LOAD FACTOR = 1.00

TRUSS PLATE MANUFACTURER IS NOT RESPONSIBLE FOR QUALITY CONTROL IN THE TRUSS MANUFACTURING PLANT.


NAIL VALUES

PLATE GRIP(DRY)	SHEAR (PSI)	SECTION (PLI)
MAX MIN	MAX MIN	MAX MIN
618 354	1667 788	1987 1656

PLATE PLACEMENT TOL = 0.250 inches


PLATE ROTATION TOL = 5.0 Deg.

JSI GRIP = 0.42 (A) (INPUT = 0.90)
JSI METAL = 0.12 (A) (INPUT = 1.00)



Structural component only
DWG# T-2007095

JOB NAME	TRUSS NAME	QUANTITY	PLY	JOB DESC.	DRWG NO.
408151	T34	2	1	GREEN PARK HOMES	
Tamarack Roof Truss, Burlington					



LUMBER	N. L. G. A. RULES	CHORDS	SIZE	DRY	LUMBER	DESCR.
A - B	2x4	DRY	No.2	SPF		
B - C	2x4	DRY	No.2	SPF		
F - A	2x4	DRY	No.2	SPF		
D - C	2x4	DRY	No.2	SPF		
F - D	2x4	DRY	No.2	SPF		
ALL WEBS	2x3	DRY	No.2	SPF		
EXCEPT						

DRY: SEASONED LUMBER.

PLATES (table is in inches)	JT TYPE	PLATES	W	LEN	Y	X
A - B	TMVW+p	MT20	4.0	4.0	1.00	2.00
B - C	TTW+p	MT20	4.0	6.0	Edge	
C - D	TMVW+p	MT20	4.0	4.0	1.00	2.00
D - E	BMV1+p	MT20	3.0	4.0		
E - F	BMVWW-t	MT20	4.0	9.0		
F - A	BMV1+p	MT20	3.0	4.0		

Edge - INDICATES REFERENCE CORNER OF PLATE TOUCHES EDGE OF CHORD.

DIMENSIONS, SUPPORTS AND LOADINGS SPECIFIED BY FABRICATOR TO BE VERIFIED BY BUILDING DESIGNER

BEARINGS	FACTORED	MAXIMUM FACTORED	INPUT	REQD
GROSS REACTION	GROSS REACTION	BRG	BRG	
JT VERT	DOWN	HORIZ	UPLIFT	IN-SX
F	489	0	0	0
D	489	0	0	0

A SUITABLE HANGER/MECHANICAL CONNECTION IS REQUIRED AT JOINT F, D. MINIMUM BEARING LENGTH AT JOINT F = 1-8, JOINT D = 1-8.

UNFACTORED REACTIONS

1ST LOASE		MAX. MIN. COMPONENT REACTIONS					
JT	COMBINED	SNOW	LIVE	PERM. LIVE	WIND	DEAD	SOIL
F	331	217 / 0	0 / 0	0 / 0	0 / 0	114 / 0	0 / 0
D	331	217 / 0	0 / 0	0 / 0	0 / 0	114 / 0	0 / 0

BRACING

TOP CHORD TO BE SHEATHED OR MAX. PURLIN SPACING = 6.25 FT.
MAX. UNBRACED BOTTOM CHORD LENGTH = 10.00 FT. OR RIGID CEILING DIRECTLY APPLIED.
ALL PITCH BREAKS AND PERIMETER CORNER JOINTS MUST BE Laterally RESTRAINED.

LOADING

TOTAL LOAD CASES: (4)

CHORDS	MAX. FACTORED	FACTORED	MEMB.	MAX. FACTORED
MEMB.	FORCE (LBS)	VERT. LOAD (LBS)	LENGTH	FORCE (LBS)
FR-TO				
A-B	-218 / 0	-91.8	0.21 (1)	6.25
B-C	-218 / 0	-91.8	0.21 (1)	6.25
F-A	-438 / 0	0.0	0.07 (1)	7.81
D-C	-438 / 0	0.0	0.07 (1)	7.81
F-E	0 / 0	-18.5	0.09 (4)	10.00
E-D	0 / 0	-18.5	0.09 (4)	10.00

DESIGN CRITERIA

SPECIFIED LOADS:
TOP CH. LL = 25.6 PSF
DL = 8.0 PSF
BOT CH. LL = 0.0 PSF
DL = 7.4 PSF
TOTAL LOAD = 39.0 PSF

SPACING = 24.0 IN. OC

THIS TRUSS IS DESIGNED FOR RESIDENTIAL OR SMALL BUILDING REQUIREMENTS OF PART 9, NBC 2010, NBC 2015

THIS DESIGN COMPLIES WITH:
- PART 9 OF CBC 2010, CBC 2012, ABC 2019
- PART 9 OF CBC 2012 (2019 AMENDMENT)
- CSA 088-09, CSA 088-14
- TPIC 2011, TPIC 2014

(55 % OF 31.3 P.S.F. G.S.L. PLUS 8.4 P.S.F. RAIN LOAD) EQUALS 25.6 P.S.F. SPECIFIED ROOF LIVE LOAD

ALLOWABLE DEFL. (LL) = L/360 (0.28")
CALCULATED VERT. DEFL. (LL) = L/989 (0.00")
ALLOWABLE DEFL. (TL) = L/360 (0.28")
CALCULATED VERT. DEFL. (TL) = L/989 (0.01")

CSI: TC=0.21/1.00 (A-B:1), BC=0.09/1.00 (E-F:4), WB=0.07/1.00 (B-E:1), SS=0.12/1.00 (A-B:1)

DOL LUMBER=1.00 NAIL=1.00 LS BEND=1.10
COMP=1.10 SHEAR=1.10 TENS=1.10

COMPANION LIVE LOAD FACTOR = 1.00


TRUSS PLATE MANUFACTURER IS NOT RESPONSIBLE FOR QUALITY CONTROL IN THE TRUSS MANUFACTURING PLANT.

NAIL VALUES
PLATE GRIP (DRY) SHEAR SECTION
(PSI) (PLI) (PLI)
MAX MIN MAX MIN MAX MIN
MT20 618 354 1667 788 1987 1656

PLATE PLACEMENT TOL = 0.250 inches


PLATE ROTATION TOL = 5.0 Deg.

JSI GRIP= 0.33 (A) (INPUT = 0.90)
JSI METAL= 0.09 (A) (INPUT = 1.00)



Structural component only
DWG# T-2007096

JOB NAME	TRUSS NAME	QUANTITY	PLY	JOB DESC.	DRWG NO.
408151	T35	2	2	GREEN PARK HOMES	
Tamarack Roof Truss, Burlington					
Version 8.310 S Oct 29 2019 Mitek Industries, Inc. Sat Apr 25 11:20:01 2020 Page 1					
ID:h2dflgC44wS_E2tqPs_atzllRw-EO9R5nym13W44?Ovw8lKTxhdFf_xTud8qz_ftzNCKS					
5-10-8					
Scale = 1:10					



LUMBER	CHORDS	SIZE	LUMBER	DESCR.
N. L. G. A. RULES				
F - A	2x4	DRY	No.2	SPF
A - C	2x4	DRY	No.2	SPF
D - C	2x4	DRY	No.2	SPF
F - D	2x4	DRY	No.2	SPF
ALL WEBS	2x3	DRY	No.2	SPF
DRY: SEASONED LUMBER.				

DESIGN CONSISTS OF 2 TRUSSES BUILT SEPARATELY THEN FASTENED TOGETHER AS FOLLOWS:

CHORDS #ROWS	SURFACE SPACING (IN)	LOAD (PLF)
TOP CHORDS : (0.122"x3") SPIRAL NAILS		
F-A 1	12	TOP
A-C 1	12	TOP
C-D 1	12	TOP
BOTTOM CHORDS : (0.122"x3") SPIRAL NAILS		
F-D 1	12	SIDE (97.1)
WEBS : (0.122"x3") SPIRAL NAILS		
B-E 1	6	SIDE (20.3)
2x3 1	6	

NAILS TO BE DRIVEN FROM ONE SIDE ONLY.
GIRDER NAILING ASSUMES NAILED HANGERS ARE FASTENED WITH MIN. 3-0 INCH NAILS.

TOP - COMPONENTS ARE LOADED FROM THE TOP AND MUST BE PLACED ON TOP EDGE OF ALL PLIES FOR THE LOAD TO BE TRANSFERRED TO EACH PLY.

SIDE - PLF SHOWN IS THE EQUIVALENT UDL APPLIED TO ONE SIDE THAT THE CORRESPONDING NAILING PATTERN SHALL BE CAPABLE OF TRANSFERRING. REMAINING PLF MUST BE APPLIED ON THE OPPOSITE SIDE OR ON THE TOP.

PLATES (table is in inches)	JT TYPE	PLATES	W	LEN	Y	X
A	TMVW-1	MT20	4.0	6.0		
B	TMVW-w	MT20	2.0	4.0		
C	TMVW-w	MT20	4.0	6.0		
D	BMV1-p	MT20	3.0	4.0		
E	BMVWW-1	MT20	4.0	6.0		

DIMENSIONS, SUPPORTS AND LOADINGS SPECIFIED BY FABRICATOR TO BE VERIFIED BY BUILDING DESIGNER.

BEARINGS	FACTORED	MAXIMUM FACTORED	INPUT	RECORD
GROSS REACTION	GROSS REACTION	BRG	BRG	
JT VERT	HORZ	DOWN	HORZ	UPLIFT
F 1016	0	1016	0	0
D 1085	0	1085	0	0

A SUITABLE HANGER/MECHANICAL CONNECTION IS REQUIRED AT JOINT D. MINIMUM BEARING LENGTH AT JOINT D = 1-8.

UNFACTORED REACTIONS							
	1ST LCASE	MAX./MIN. COMPONENT REACTIONS					
JT	COMBINED	SNOW	LIVE	PERM.LIVE	WIND	DEAD	SOIL
F	728	436 / 0	0 / 0	0 / 0	0 / 0	290 / 0	0 / 0
D	772	479 / 0	0 / 0	0 / 0	0 / 0	293 / 0	0 / 0

BEARING MATERIAL TO BE SPF NO.2 OR BETTER AT JOINT(S) F

BRACING
TOP CHORD TO BE SHEATHED OR MAX. PURLIN SPACING = 6.23 FT.
MAX. UNBRACED BOTTOM CHORD LENGTH = 10.00 FT OR RIGID CEILING DIRECTLY APPLIED.

ALL PITCH BREAKS AND PERIMETER CORNER JOINTS MUST BE LATERALLY RESTRAINED.

LOADING

TOTAL LOAD CASES: (4)

CHORDS	MAX. FACTORED	FACTORED	W E B S	MAX. FACTORED
MEMB.	FORCE (LBS)	VERT. LOAD (PLF)	LC1 MAX	MEMB. FORCE (LBS)
FR-TO	FROM TO	FROM TO	LENGTH	FR-TO
F-A	-885 / 0	0.0	0.0 0.05 (1)	7.81
A-G	-1706 / 0	-91.8	-91.8 0.28 (1)	6.23
G-B	-1706 / 0	-91.8	-91.8 0.28 (1)	6.23
B-C	-1706 / 0	-91.8	-91.8 0.08 (1)	6.25
D-C	-707 / 0	0.0	0.0 0.04 (1)	7.81
F-E	0 / 0	-43.5	-43.5 0.05 (4)	10.00
E-H	0 / 0	-43.5	-43.5 0.22 (1)	10.00
H-D	0 / 0	-43.5	-43.5 0.22 (1)	10.00

FACTORED CONCENTRATED LOADS (LBS)	JT	LOC.	LC1	MAX-	MAX+	FACE	DIR.	TYPE	HEEL	CONN.
E	3-0-12	-450	-450	---	---	FRONT	VERT	TOTAL	---	C1
G	1-0-12	-404	-404	---	---	TOP	VERT	TOTAL	---	C1
H	5-0-12	-452	-452	---	---	FRONT	VERT	TOTAL	---	C1

CONNECTION REQUIREMENTS

1) C1: A SUITABLE HANGER/MECHANICAL CONNECTION IS REQUIRED.

DESIGN CRITERIA

*** SPECIAL LOADS ANALYSIS ***
GEOMETRY AND/OR BASIC LOADS CHANGED BY USER.
LOADS WERE DERIVED FROM USER INPUT
NO FURTHER MODIFICATIONS WERE MADE

SPECIFIED LOADS:
TOP CH. LL = 25.6 PSF
DL = 6.0 PSF
BOT CH. LL = 0.0 PSF
DL = 7.4 PSF
TOTAL LOAD = 39.0 PSF

SPACING = 24.0 IN. OC

LOADING IN FLAT SECTION BASED ON A SLOPE OF 8.00/12

*** NON STANDARD GIRDER ***
ADDTL USER-DEFINED LOADS APPLIED TO ALL LOAD CASES.

THIS TRUSS IS DESIGNED FOR RESIDENTIAL OR SMALL BUILDING REQUIREMENTS OF PART 9, NBCC 2010, NBCC 2015

THIS DESIGN COMPLIES WITH:
- PART 9 OF CBC 2018, CBC 2012, ABC 2019
- PART 9 OF CBC 2012 (2019 AMENDMENT)
- CSA 086-09, CSA 086-14
- TPIC 2011, TPIC 2014

(55% OF 31.3 P.S.F. G.S.L. PLUS 8.4 P.S.F. RAIN LOAD) EQUALS 25.6 P.S.F. SPECIFIED ROOF LIVE LOAD

ALLOWABLE DEFL.(LL) = L/360 (0.20")
CALCULATED VERT. DEFL.(LL) = L/999 (0.02")
ALLOWABLE DEFL.(TL) = L/360 (0.20")
CALCULATED VERT. DEFL.(TL) = L/999 (0.03")

CSI: TC=0.28/1.00 (A-B:1), BC=0.22/1.00 (D-E:1), WB=0.22/1.00 (A-E:1), SS=0.16/1.00 (D-E:1)

DOL LUMBER=1.00 NAIL=1.00 LS BEND=1.00
COMP=1.00 SHEAR=1.00 TENS=1.00

COMPANION LIVE LOAD FACTOR = 1.00


TRUSS PLATE MANUFACTURER IS NOT RESPONSIBLE FOR QUALITY CONTROL IN THE TRUSS MANUFACTURING PLANT

NAIL VALUES	PLATE GRIP (DRY)	SHEAR (PSI)	SECTION (PLI)
	MAX MIN	MAX MIN	MAX MIN
MT20	818 354	1667 788	1987 1656

PLATE PLACEMENT TOL = 0.250 inches

PLATE ROTATION TOL = 5.0 Deg.

JSI GRIP = 0.59 (C) (INPUT = 0.50)
JSI METAL = 0.21 (C) (INPUT = 1.00)



Structural component only
DWG# T-2007097 1/2

JOB NAME	TRUSS NAME	QUANTITY	PLY	JOB DESC.	DRWG NO.
408151	T35	2	2	GREEN PARK HOMES	
Tamarack Roof Truss, Burlington				TRUSS DESC.	


Version 8.310 S Oct 29 2019 Mittek Industries, Inc. Sat Apr 25 11:20:01 2020 Page 2
ID:h2dflgC44wS E2tzoPs atzIRw-EO9R5nvm13W44?Ovw8IKTxzhdFf xTUd8gz 11zNCXS

PLATES (table is in inches)
JT TYPE PLATES W LEN Y X
F BMV1+p MT20 3.0 4.0



Structural component only
DWG# T-2007097 3/2

JOB NAME 408151	TRUSS NAME G36	QUANTITY 1	PLY 1	JOB DESC. GREEN PARK HOMES	DRWG NO.
Tamarack Roof Truss, Burlington		TRUSS DESC.			



LUMBER			
N. L. G. A. RULES	CHORDS	SIZE	LUMBER
P - B	2x4	DRY	No.2
A - E	2x4	DRY	No.2
E - I	2x4	DRY	No.2
J - H	2x4	DRY	No.2
P - J	2x4	DRY	No.2

ALL WEBS 2x3 DRY No.2
ALL GABLE WEBS 2x3 DRY No.2
DRY: SEASONED LUMBER.

GABLE STUDS SPACED AT 2'-0" OC.

PLATES (table is in inches)

JT TYPE	PLATES	W	LEN	Y	X
B TAWW+p	MT20	4.0	4.0	1.00	2.00
C, D, F, G					
C TAWW+w	MT20	2.0	4.0		
E TAWW+p	MT20	4.0	8.0	Edge	
H TAWW+p	MT20	4.0	4.0	1.00	2.00
J BMV1+p	MT20	3.0	4.0		
K BMVW1+L	MT20	4.0	4.0		
L, M, N					
L BMV1+w	MT20	2.0	4.0		
O BMVW1+L	MT20	4.0	4.0		
P BMV1+p	MT20	3.0	4.0		

Edge - INDICATES REFERENCE CORNER OF PLATE TOUCHES EDGE OF CHORD.

DIMENSIONS, SUPPORTS AND LOADINGS SPECIFIED BY FABRICATOR TO BE VERIFIED BY BUILDING DESIGNER

BEARINGS

THIS TRUSS DESIGNED FOR CONTINUOUS BEARINGS.

THIS TRUSS REQUIRES RIGID SHEATHING ON EXPOSED FACE.

BEARING MATERIAL TO BE SPF NO.2 OR BETTER AT JOINT(S)

BRACING

TOP CHORD TO BE SHEATHED OR MAX. PURLIN SPACING = 6.25 FT.

MAX. UNBRACED BOTTOM CHORD LENGTH = 10.00 FT OR RIGID CEILING DIRECTLY APPLIED.

ALL PITCH BREAKS AND PERIMETER CORNER JOINTS MUST BE Laterally RESTRAINED.

LOADING

TOTAL LOAD CASES: (4)

CHORDS				WEBS			
MEMB.	MAX. FACTORED FORCE (LBS)	VERT. LOAD (PLF)	MAX. UNBRACED LENGTH (LC)	MEMB.	MAX. FACTORED FORCE (LBS)	MAX. UNBRACED LENGTH (LC)	
FR-TO		FROM TO		FR-TO			
P-B	-274 / 0	0.0 0.0 0.03 (1)	7.81	M-E	-139 / 0	0.09 (1)	
A-B	0 / 41	-91.8 -91.8 0.13 (1)	10.00	N-D	-223 / 0	0.07 (1)	
B-C	-57 / 0	-91.8 -91.8 0.12 (1)	6.25	O-C	-75 / 0	0.01 (1)	
C-D	-4 / 0	-91.8 -91.8 0.08 (1)	10.00	L-F	-223 / 0	0.07 (1)	
D-E	-22 / 0	-91.8 -91.8 0.08 (1)	6.25	K-G	-75 / 0	0.01 (1)	
E-F	-22 / 0	-91.8 -91.8 0.08 (1)	6.25	S-O	0 / 20	0.00 (1)	
F-G	-4 / 0	-91.8 -91.8 0.12 (1)	10.00	K-H	0 / 20	0.00 (1)	
G-H	-57 / 0	-91.8 -91.8 0.12 (1)	6.25				
H-I	0 / 41	-91.8 -91.8 0.13 (1)	10.00				
J-H	-274 / 0	0.0 0.0 0.03 (1)	7.81				
P-O	0 / 0	-18.5 -18.5 0.01 (4)	10.00				
O-N	0 / 12	-18.5 -18.5 0.02 (4)	10.00				
N-M	0 / 7	-18.5 -18.5 0.02 (4)	10.00				
M-L	0 / 7	-18.5 -18.5 0.02 (4)	10.00				
L-K	0 / 12	-18.5 -18.5 0.02 (4)	10.00				
K-J	0 / 0	-18.5 -18.5 0.01 (4)	10.00				

TOTAL WEIGHT = 53 lb

DESIGN CRITERIA

SPECIFIED LOADS:

TOP CH.	LL	=	25.6	PSF
	DL	=	6.0	PSF
BOT CH.	LL	=	0.0	PSF
	DL	=	7.4	PSF
TOTAL LOAD	=	39.0	PSF	

SPACING = 24.0 IN. CC

THIS TRUSS IS DESIGNED FOR RESIDENTIAL OR SMALL BUILDING REQUIREMENTS OF PART 9, NBCC 2010, NBCC 2015

THIS DESIGN COMPLIES WITH:

- PART 9 OF BCBC 2018, OBC 2012, ABC 2019
- PART 9 OF OBC 2012 (2019 AMENDMENT)
- CSA 086-09, CSA 086-14
- TPIC 2011, TPIC 2014

DESIGN ASSUMPTIONS

- OVERHANG NOT TO BE ALTERED OR CUT OFF.

(55 % OF 31.3 P.S.F. G.S.L. PLUS 8.4 P.S.F. RAIN LOAD) EQUALS 25.6 P.S.F. SPECIFIED ROOF LIVE LOAD

CSI: TC=0.13/1.00 (H-t1), BC=0.02/1.00 (K-L-4), WB=0.08/1.00 (E-M-1), SSI=0.08/1.00 (A-B-1)

DOL LUMBER=1.00 NAIL=1.00 LS BEND=1.10 COMP=1.10 SHEAR=1.10 TENS=1.10

COMPANION LIVE LOAD FACTOR = 1.00

TRUSS PLATE MANUFACTURER IS NOT RESPONSIBLE FOR QUALITY CONTROL IN THE TRUSS MANUFACTURING PLANT.


NAIL VALUES

PLATE	GRIP(DRY)	SHEAR	SECTION
(PSI)	(PL)	(PL)	
MAX MIN	MAX MIN	MAX MIN	
MT20	618 354	1667 788	1987 1658

PLATE PLACEMENT TOL. = 0.250 inches

PLATE ROTATION TOL. = 5.0 Deg.

JSI GRIP= 0.21 (B) (INPUT = 0.90)
JSI METAL= 0.12 (F) (INPUT = 1.00)



Structural component only
DWG# T-2007079

Tamarack Roof Truss, Burlington


Version 8.310 S Oct 29 2019 Mitek Industries, Inc. Sat Apr 25 11:29:32 2020 Page 1

ID:7vF7aG0E03cRuj6X1lSkzWYK-QEA1x1skZWS34lYatZ2E6M6CTQSHDeTgR0n1CQzNCOX

13-8 0-0 5-10 8 5 10 8 10 7 7 15-3 2 17 7 0 19-2 12 19 10-14 34-5 9 39-3 8 48 15 5-10 8 35-2 0 38-5 8

13-8 13-8 5-10 8 5 10 8 10 7 7 15-3 2 17 7 0 19-2 12 19 10-14 34-5 9 39-3 8 48 15 5-10 8 35-2 0 38-5 8

Scale = 1/8" = 1'-0"



DESIGN CONSISTS OF 2 TRUSSES BUILT SEPARATELY THEN FASTENED TOGETHER AS FOLLOWS:

RAILS TO BE DRIVEN FROM ONE SIDE ONLY.

WIDER NAILING ASSUMES NAILED HANGERS ARE FASTENED WITH MIN. 3-0 INCH NAILS.

OP - COMPONENTS ARE LOADED FROM THE TOP AND MUST BE PLACED ON TOP EDGE OF ALL PLIES FOR THE LOAD TO BE TRANSFERRED TO EACH PLY.

DIMENSIONS, SUPPORTS AND LOADINGS SPECIFIED BY FABRICATOR TO BE VERIFIED BY BUILDING DESIGNER

BEARINGS		FACTORED		MAXIMUM FACTORED		INPUT	REQD
GROSS REACTION		GROSS REACTION				BRG	BRG
JT	VERT	HORZ	DOWN	HORZ	UPLIFT	IN-SX	IN-SX
T	3331	0	3331	0	0	5-8	5-8
K	3331	0	3331	0	0	5-8	5-8

UNFACTORED REACTIONS

1ST LCASE		MAX. MIN. COMPONENT REACTIONS					
JT	COMBINED	SNOW	LIVE	PERM. LIVE	WIND	DEAD	SOIL
	2356	1544 / 0	0 / 0	0 / 0	0 / 0	812 / 0	0 / 0
K	2356	1544 / 0	0 / 0	0 / 0	0 / 0	812 / 0	0 / 0

BEARING MATERIAL TO BE SPF NO.2 OR BETTER AT JOINT(S) T. K

BRACING

TOP CHORD TO BE SHEATHED OR MAX. FURLIN SPACING = 3.87 FT.
MAX. UNBRACED BOTTOM CHORD LENGTH = 10.00 FT OR RIGID CEILING DIRECTLY APPLIED.

ALL PITCH BREAKS AND PERIMETER CORNER JOINTS MUST BE Laterally RESTRAINED.

LOADING

TOTAL LOAD CASES: (4)

CHORDS				FACTORED				WEB S			
MAX. FACTORED		FORCE		VERT. LOAD		LC1 MAX		MAX. UNBRAC		MEMB. MAX. FACTORED	
MEMB.	FORCE (LBS)	VERT.	(PLF)	LC1	MAX CSI (LC)	MAX.	UNBRAC	MEMB.	FORCE (LBS)	MAX	FACTORED CSI (LC)
FR-TO		FROM	TO				LENGTH	FR-TO			
A-B	0 / 28	-91.8	-91.8	0.07 (1)	10.00	S-C	-427 / 8	0.05 (1)			
B-C	-5077 / 0	-91.8	-91.8	0.52 (1)	1	3.87	C-R	0 / 3083	0.38 (1)		
C-U	-7106 / 0	-91.8	-91.8	0.23 (1)	4.33	R-D	-1565 / 0	0.19 (1)			
U-V	-7106 / 0	-91.8	-91.8	0.23 (1)	4.33	O-G	0 / 1071	0.13 (1)			
V-D	-7106 / 0	-91.8	-91.8	0.23 (1)	4.33	M-G	-1565 / 0	0.19 (1)			
D-W	-7984 / 0	-91.8	-91.8	0.27 (1)	4.10	L-H	-427 / 8	0.05 (1)			
W-X	-7984 / 0	-91.8	-91.8	0.27 (1)	4.10	B-S	0 / 4592	0.57 (1)			
X-Y	-7984 / 0	-91.8	-91.8	0.27 (1)	4.10	L-I	0 / 4592	0.57 (1)			
Y-E	-7984 / 0	-91.8	-91.8	0.27 (1)	4.10	D-P	0 / 1071	0.13 (1)			
Z-F	-7984 / 0	-91.8	-91.8	0.27 (1)	4.10	M-H	0 / 3083	0.38 (1)			
E-Z	-7984 / 0	-91.8	-91.8	0.27 (1)	4.10	P-E	-505 / 0	0.06 (1)			
F-AA	-7984 / 0	-91.8	-91.8	0.27 (1)	4.10	E-O	-505 / 0	0.06 (1)			
AA-AB	-7984 / 0	-91.8	-91.8	0.27 (1)	4.10						
AB-G	-7984 / 0	-91.8	-91.8	0.27 (1)	4.10						
G-AC	-7106 / 0	-91.8	-91.8	0.23 (1)	4.33						
AC-AD	-7106 / 0	-91.8	-91.8	0.23 (1)	4.33						
AD-H	-7106 / 0	-91.8	-91.8	0.23 (1)	4.33						
H-I	-5077 / 0	-91.8	-91.8	0.52 (1)	3.87						
I-J	0 / 28	-91.8	-91.8	0.07 (1)	10.00						
T-B	-3255 / 0	0.0	0.0	0.11 (1)	7.69						
K-I	-3255 / 0	0.0	0.0	0.11 (1)	7.69						
T-AE	0 / 0	-18.5	-18.5	0.06 (4)	10.00						
AE-AF	0 / 0	-18.5	-18.5	0.06 (4)	10.00						
AF-S	0 / 0	-18.5	-18.5	0.05 (4)	10.00						
S-AG	0 / 4563	-18.5	-18.5	0.34 (1)	10.00						
AG-AH	0 / 4563	-18.5	-18.5	0.34 (1)	10.00						
AH-R	0 / 4563	-18.5	-18.5	0.34 (1)	10.00						
R-Q	0 / 7105	-18.5	-18.5	0.52 (1)	10.00						
Q-AI	0 / 7105	-18.5	-18.5	0.52 (1)	10.00						
AI-AJ	0 / 7105	-18.5	-18.5	0.52 (1)	10.00						
AJ-P	0 / 7105	-18.5	-18.5	0.52 (1)	10.00						
P-AK	0 / 8119	-18.5	-18.5	0.56 (1)	10.00						
AK-Q	0 / 8119	-18.5	-18.5	0.56 (1)	10.00						
Q-AL	0 / 7105	-18.5	-18.5	0.52 (1)	10.00						
AL-AM	0 / 7105	-18.5	-18.5	0.52 (1)	10.00						
AM-N	0 / 7105	-18.5	-18.5	0.52 (1)	10.00						
N-M	0 / 7105	-18.5	-18.5	0.52 (1)	10.00						
M-AN	0 / 4563	-18.5	-18.5	0.34 (1)	10.00						
AN-AO	0 / 4563	-18.5	-18.5	0.34 (1)	10.00						
AO-L	0 / 4563	-18.5	-18.5	0.34 (1)	10.00						
L-AP	0 / 0	-18.5	-18.5	0.06 (4)	10.00						
AP-AQ	0 / 0	-18.5	-18.5	0.06 (4)	10.00						

DESIGN CRITERIA

SPECIFIED LOADS:

TOP CH.	LL =	25.6	PSF
	DL =	6.0	PSF
BOT CH.	LL =	0.0	PSF
	DL =	7.4	PSF
TOTAL LOAD	=	39.0	PSF

SPACING = 24.0 IN. C/C

LOADING IN FLAT SECTION BASED ON A SLOPE
OF 6.00/12

THIS TRUSS IS DESIGNED FOR RESIDENTIAL OR
SMALL BUILDING REQUIREMENTS OF PART 9,
NBC 2010, NBC 2015

THIS DESIGN COMPLIES WITH:

- PART 9 OF ECBC 2018 , OBC 2012 , ABC 2019
- PART 9 OF OBC 2012 (2019 AMENDMENT)
- CBA 086-09, CSA 086-14
- TPIC 2011, TPIC 2014

(55 % OF 31.3 P.S.F. G.S.L. PLUS 8.4 P.S.F. RAIN LOAD) EQUALS 25.6 P.S.F. SPECIFIED ROOF LIVE LOAD

ALLOWABLE DEFL.(LL)= L/360 (1.17")
CALCULATED VERT. DEFL.(LL) = L/999 (0.21")
ALLOWABLE DEFL.(TL)= L/360 (1.17")
CALCULATED VERT. DEFL.(TL) = L/999 (0.39")

CSI: TC=0.52/1.00 (H-I:1), BC=0.58/1.00 (O-P:1),
WB=0.57/1.00 (B-S:1), SSI=0.18/1.00 (D-E:1)

DOL LUMBER=1.00 NAIL=1.00 LS BEND=1.00
COMP=1.00 SHEAR=1.00 TENS= 1.00

COMPANION LIVE LOAD FACTOR = 1.00

AUTOSOLVE HEELS OFF

TRUSS PLATE MANUFACTURER IS NOT RESPONSIBLE FOR QUALITY CONTROL IN THE TRUSS MANUFACTURING PLANT.

NAIL VALUES

PLATE	GRIP(DRY)		SHEAR		SECTION	
	(PSI)		(PLI)		(PLI)	
	MAX	MIN	MAX	MIN	MAX	MIN
MT20	618	354	1637	788	1987	1658

PLATE PLACEMENT TOL. = 0.250 inches

PLATE ROTATION TOL = 5.0 Deg.

JSI GRIP= 0.84 (S) (INPUT = 0.90)
JSI METAL= 0.64 (N) (INPUT = 1.00)



Structural component only
DWG# T-2007107 1/2

JOB NAME	TRUSS NAME	QUANTITY	PLY	JOB DESC.	DRWG NO.
408152	T40	1	2	GREEN PARK HOMES	
Tamarack Roof Truss, Burlington		TRUSS DESC.			

Version 8.310 S Oct 29 2019 MITek Industries, Inc. Sat Apr 25 11:29:32 2020 Page 2
ID:j7vF7aG0E03cRU6X1iSkzWYK-0EAix1sxZWS34IYeiZ2E6M6CTQSHDeTgR0niCOzNCOX

PLATES (tablets in inches)

JT	TYPE	PLATES	W	LEN	Y	X
B	TMVW-t	MT20	5.0	8.0		
C	TTWW+m	MT20	5.0	8.0	Edge	
D, E, G						
D	TMVW-t	MT20	5.0	8.0		
F	TS-t	MT20	5.0	6.0		
H	TTWW+m	MT20	5.0	8.0	Edge	
I	TMVW-t	MT20	5.0	8.0		
K	BMV1+p	MT20	3.0	6.0		
L	BMVW-t	MT20	5.0	6.0	2.50	2.50
M, O, P, R						
M	BMVW-t	MT20	5.0	8.0		
N	BS-t	MT20	5.0	6.0		
O	BS-t	MT20	5.0	8.0		
S	BMVW-t	MT20	5.0	6.0	2.50	2.50
T	BMV1+p	MT20	3.0	6.0		

Edge - INDICATES REFERENCE CORNER OF PLATE TOUCHES EDGE OF CHORD.

LOADING

TOTAL LOAD CASES: (4)


CHORDS				WEBS			
MEMB.	MAX. FACTORED FORCE (LBS)	FACTORED VERT. LOAD (LBS)	LC1 MAX (LBS)	MEMB.	MAX. FACTORED FORCE (LBS)	FACTORED UNBRAC LENGTH (LBS)	FR-TO
FR-TO		FROM	TO				
AQ-K	0.0	-18.5	-18.5	0.08 (4)	10.00		

FACTORED CONCENTRATED LOADS (LBS)

JT	LOC.	LC1	MAX.	MAX.	FACE	DIR.	TYPE	HEEL	CONN.
C	5-10-8	-438	-110	---	FRONT	VERT	TOTAL	---	C1
E	17-7-0	-110	-438	---	FRONT	VERT	TOTAL	---	C1
H	29-3-8	-438	-438	---	FRONT	VERT	TOTAL	---	C1
L	29-2-12	-28	-26	---	FRONT	VERT	TOTAL	---	C1
N	23-2-12	-28	-26	---	FRONT	VERT	TOTAL	---	C1
Q	11-11-4	-28	-26	---	FRONT	VERT	TOTAL	---	C1
S	5-11-4	-28	-26	---	FRONT	VERT	TOTAL	---	C1
U	7-11-4	-110	-110	---	FRONT	VERT	TOTAL	---	C1
V	9-11-4	-110	-110	---	FRONT	VERT	TOTAL	---	C1
W	11-11-4	-110	-110	---	FRONT	VERT	TOTAL	---	C1
X	13-11-4	-110	-110	---	FRONT	VERT	TOTAL	---	C1
Y	15-11-4	-110	-110	---	FRONT	VERT	TOTAL	---	C1
Z	19-2-12	-110	-110	---	FRONT	VERT	TOTAL	---	C1
AA	21-2-12	-110	-110	---	FRONT	VERT	TOTAL	---	C1
AB	23-2-12	-110	-110	---	FRONT	VERT	TOTAL	---	C1
AC	25-2-12	-110	-110	---	FRONT	VERT	TOTAL	---	C1
AD	27-2-12	-110	-110	---	FRONT	VERT	TOTAL	---	C1
AE	1-11-4	-28	-26	---	FRONT	VERT	TOTAL	---	C1
AF	3-11-4	-28	-26	---	FRONT	VERT	TOTAL	---	C1
AG	7-11-4	-28	-26	---	FRONT	VERT	TOTAL	---	C1
AH	9-11-4	-28	-26	---	FRONT	VERT	TOTAL	---	C1
AI	13-11-4	-28	-26	---	FRONT	VERT	TOTAL	---	C1
AJ	15-11-4	-28	-26	---	FRONT	VERT	TOTAL	---	C1
AK	17-7-0	-28	-26	---	FRONT	VERT	TOTAL	---	C1
AL	19-2-12	-28	-26	---	FRONT	VERT	TOTAL	---	C1
AM	21-2-12	-28	-26	---	FRONT	VERT	TOTAL	---	C1
AN	25-2-12	-28	-26	---	FRONT	VERT	TOTAL	---	C1
AO	27-2-12	-28	-26	---	FRONT	VERT	TOTAL	---	C1
AP	31-2-12	-28	-26	---	FRONT	VERT	TOTAL	---	C1
AQ	33-2-12	-28	-26	---	FRONT	VERT	TOTAL	---	C1

CONNECTION REQUIREMENTS


1) C1: A SUITABLE HANGER/MECHANICAL CONNECTION IS REQUIRED.



Structural component only
DWG# T-2007107 3/2

JOB NAME 408152	TRUSS NAME T40Z	QUANTITY 1	PLY 2	JOB DESC. GREEN PARK HOMES	DRWG NO.
Tamarack Roof Truss, Burlington		TRUSS DESC.			

Version 8.310 S Oct 29 2019 Mitek Industries, Inc. Sat Apr 25 11:29:34 2020 Page 1
 ID:7vF7aG0E03cRUj6X1jSkziWYK-ydH2MiuB57mK3h1? 4iCnCV?E2GhUJzKGpGJzNGOV
 13.8 0.0 5.10.8 7.11.4 10.7.7 4.7.11 15.3.2 2.3.14 17.7.0 19.10.14 4.7.11 24.2.9 4.8.15 39.3.8 35.2.0 38.5.8 1.3.8
 Scale = 1:57.3



LUMBER	N. L. G. A. RULES	CHORDS	SIZE	LUMBER	DESCR.
A - C	2x4	DRY	No.2	SPF	
C - F	2x6	DRY	No.2	SPF	
F - H	2x6	DRY	No.2	SPF	
H - J	2x4	DRY	No.2	SPF	
T - B	2x6	DRY	No.2	SPF	
K - I	2x6	DRY	No.2	SPF	
T - Q	2x6	DRY	No.2	SPF	
Q - N	2x6	DRY	No.2	SPF	
N - K	2x6	DRY	No.2	SPF	
ALL WEBS EXCEPT	2x3	DRY	No.2	SPF	

DRY: SEASONED LUMBER.

DESIGN CONSISTS OF 2 TRUSSES BUILT SEPARATELY THEN FASTENED TOGETHER AS FOLLOWS:

CHORDS #ROWS	SURFACE SPACING (IN)	LOAD(PLF)
TOP CHORDS : (0.122"x3") SPIRAL NAILS		
A - C	12	SIDE(81.0)
H - J	12	TOP
C - F	12	SIDE(81.0)
F - H	12	TOP
T - B	12	TOP
K - I	12	TOP
BOTTOM CHORDS : (0.122"x3") SPIRAL NAILS		
T - Q	12	SIDE(183.1)
Q - N	12	SIDE(0.0)
N - K	12	TOP
WEBS : (0.122"x3") SPIRAL NAILS		
2x3	6	

NAILS TO BE DRIVEN FROM ONE SIDE ONLY.

GIRDER NAILING ASSUMES NAILED HANGERS ARE FASTENED WITH MIN. 3-0 INCH NAILS.

TOP - COMPONENTS ARE LOADED FROM THE TOP AND MUST BE PLACED ON TOP EDGE OF ALL PLIES FOR THE LOAD TO BE TRANSFERRED TO EACH PLY.

DIMENSIONS, SUPPORTS AND LOADINGS SPECIFIED BY FABRICATOR TO BE VERIFIED BY BUILDING DESIGNER

BEARINGS	FACTORED GROSS REACTION	MAXIMUM FACTORED GROSS REACTION	INPUT BRG	REQD BRG
JT	VERT 4474	DOWN 4474	0	5-8
T	HORZ 0	HORZ 0	0	5-8
K	VERT 3775	DOWN 3775	0	5-8

UNFACTORED REACTIONS	1ST LCASE	MAX/MIN COMPONENT REACTIONS	LIVE	PERALIVE	WIND	DEAD	SOIL
JT	COMBINED	SNOW	0.0	0.0	0.0	1073.0	0.0
T	3162	2088.0	0.0	0.0	0.0	0.0	0.0
K	2965	1772.0	0.0	0.0	0.0	893.0	0.0

BEARING MATERIAL TO BE SPF NO.2 OR BETTER AT JOINT(S) T, K

BRACING
 TOP CHORD TO BE SHEATHED OR MAX. PURLIN SPACING = 3.19 FT.
 MAX. UNBRACED BOTTOM CHORD LENGTH = 10.00 FT. OR RIGID CEILING DIRECTLY APPLIED.

ALL PITCH BREAKS AND PERIMETER CORNER JOINTS MUST BE Laterally RESTRAINED.

LOADING	CHORDS	FACTORED	MAX. FACTORED	WEBS	FACTORED
TOTAL LOAD CASES: (4)	MEMB.	FORCE (LBS)	VERT. LOAD LC1 MAX (PLF)	MEMB.	FORCE (LBS)
	FR-TO		FROM TO	FR-TO	
	A-B	0 / 28	-91.8 -91.8 0.07 (1)	S-C	-384 / 25
	B-C	-7183 / 0	-91.8 -91.8 0.71 (1)	C-R	0 / 4687
	C-U	-10299 / 0	-91.8 -91.8 0.32 (1)	R-D	-2057 / 0
	U-V	-10299 / 0	-91.8 -91.8 0.32 (1)	O-G	0 / 3611
	V-D	-10299 / 0	-91.8 -91.8 0.45 (1)	M-G	-2637 / 0
	D-W	-12012 / 0	-91.8 -91.8 0.45 (1)	L-H	-816 / 0
	W-X	-12012 / 0	-91.8 -91.8 0.45 (1)	B-S	0 / 6479
	X-Y	-12012 / 0	-91.8 -91.8 0.45 (1)	L-I	0 / 5333
	Y-E	-12012 / 0	-91.8 -91.8 0.45 (1)	D-P	0 / 2086
	E-F	-12381 / 0	-91.8 -91.8 0.40 (1)	M-H	0 / 4950
	F-G	-12381 / 0	-91.8 -91.8 0.40 (1)	P-E	-1110 / 0
	G-H	-9388 / 0	-91.8 -91.8 0.25 (1)	E-O	0 / 383
	H-I	-5899 / 0	-91.8 -91.8 0.59 (1)		
	I-J	0 / 28	-91.8 -91.8 0.07 (1)		
	T-B	-4430 / 0	0.0 0.0 0.16 (1)		
	K-I	-3718 / 0	0.0 0.0 0.13 (1)		
	T-Z	0 / 0	-18.5 -18.5 0.08 (4)		
	Z-AA	0 / 0	-18.5 -18.5 0.08 (4)		
	AA-S	0 / 0	-18.5 -18.5 0.08 (4)		
	S-AB	0 / 6432	-18.5 -18.5 0.89 (1)		
	AB-AC	0 / 6432	-18.5 -18.5 0.89 (1)		
	AC-AD	0 / 6432	-18.5 -18.5 0.89 (1)		
	AD-R	0 / 6432	-18.5 -18.5 0.89 (1)		
	R-Q	0 / 10299	-18.5 -18.5 0.76 (1)		
	Q-AE	0 / 10299	-18.5 -18.5 0.76 (1)		
	AE-AF	0 / 10299	-18.5 -18.5 0.76 (1)		
	AF-P	0 / 10299	-18.5 -18.5 0.76 (1)		
	P-O	0 / 12288	-18.5 -18.5 0.91 (1)		
	O-N	0 / 9385	-18.5 -18.5 0.72 (1)		
	N-M	0 / 9385	-18.5 -18.5 0.72 (1)		
	M-L	0 / 5303	-18.5 -18.5 0.37 (1)		
	L-K	0 / 0	-18.5 -18.5 0.04 (4)		

FACTORED CONCENTRATED LOADS (LBS)	LOC.	LC1	MAX	FACE	DIR.	TYPE	HEEL	CONN.
JT	5-10-8	-438	-438	---	BACK	VERT	---	C1
C	18-5-8	-2436	-2436	---	BACK	VERT	---	C1
P	16-9-12	-17	-17	---	BACK	VERT	---	C1
S	5-11-4	-26	-26	---	BACK	VERT	---	C1
U	7-11-4	-110	-110	---	BACK	VERT	---	C1
V	10-9-12	-82	-82	---	BACK	VERT	---	C1
W	12-9-12	-82	-82	---	BACK	VERT	---	C1

TOTAL WEIGHT = 2 X 170 = 341 lb

DESIGN CRITERIA

SPECIFIED LOADS:
 TOP CH. LL = 25.6 PSF
 DL = 6.0 PSF
 BOT CH. LL = 0.0 PSF
 DL = 7.4 PSF
 TOTAL LOAD = 39.0 PSF

SPACING = 24.0 IN/C

LOADING IN FLAT SECTION BASED ON A SLOPE OF 6.00/12

THIS TRUSS IS DESIGNED FOR RESIDENTIAL OR SMALL BUILDING REQUIREMENTS OF PART 9, NBCC 2010, NBCC 2015

THIS DESIGN COMPLIES WITH:
 - PART 9 OF NBCC 2010, CBC 2012, ABC 2019
 - PART 9 OF CBC 2012 (2019 AMENDMENT)
 - CSA 086-05, CSA 086-14
 - TPIC 2011, TPIC 2014

(55% OF 31.3 P.S.F. G.S.L. PLUS 8.4 P.S.F. RAIN LOAD) EQUALS 25.6 P.S.F. SPECIFIED ROOF LIVE LOAD

ALLOWABLE DEFL.(LL) = L/360 (1.17')
 CALCULATED VERT. DEFL.(LL) = L/999 (0.31')
 ALLOWABLE DEFL.(TL) = L/360 (1.17')
 CALCULATED VERT. DEFL.(TL) = L/740 (0.57')

CSI: TC=0.71/1.00 (B-C:1), BC=0.91/1.00 (O-P:1), WB=0.80/1.00 (B-S:1), SS=0.15/1.00 (R-S:1)

DOL LUMBER=1.00 NAIL=1.00 LS BEND=1.00 COMP=1.00 SHEAR=1.00 TENS=1.00

COMPANION LIVE LOAD FACTOR = 1.00

AUTOSOLVE HEELS OFF


TRUSS PLATE MANUFACTURER IS NOT RESPONSIBLE FOR QUALITY CONTROL IN THE TRUSS MANUFACTURING PLANT.

NAIL VALUES
 PLATE GRIP(DRY) SHEAR SECTION (PSI) (PLI) (PLI)
 MAX MIN MAX MIN MAX MIN
 MT20 818 354 1567 788 1987 1636

PLATE PLACEMENT TOL = 0.250 inches

PLATE ROTATION TOL = 5.0 Deg.

JSI GRIP = 0.89 (S) (INPUT = 0.80)
 JSI METAL = 0.93 (N) (INPUT = 1.00)



Structural component only
 DWG# T-2007108

JOB NAME	TRUSS NAME	QUANTITY	PLY	JOB DESC.	DRWG NO.
408152	T40Z	1	2	GREEN PARK HOMES	
Tamarack Roof Truss, Burlington		TRUSS DESC.			

Version 8.310 S Oct 29 2019 MITek Industries, Inc. Sat Apr 25 11:29:34 2020 Page 2

ID:7vF?aG0E03cRU6X1SrkzWYK-ydH2MiuB57imK3i1? 4:CNcV?E2GhUJzvKGnGJzNCOV

PLATES (table is in inches)

JT	TYPE	PLATES	W	LEN	Y	X
B	TMVW-p	MT20	5.0	8.0	2.00	3.50
C	TTWW+m	MT20	8.0	9.0	Edge	
D, E, G						
D	TMWW-l	MT20	5.0	6.0		
F	TS-l	MT20	5.0	6.0		
H	TTWW+m	MT20	6.0	9.0	Edge	
I	TMVW-p	MT20	5.0	8.0	2.00	3.50
K	BMV1+p	MT20	3.0	6.0		
L	BMWW-t	MT20	5.0	8.0	2.50	3.50
M	BMWW-t	MT20	5.0	6.0	2.50	2.00
N	BS-l	MT20	5.0	8.0		
O	BMWW-t	MT20	5.0	8.0	2.75	2.75
P	BMWW-t	MT20	5.0	6.0	2.75	2.75
Q	BS-l	MT20	5.0	8.0		
R	BMWW-t	MT20	5.0	8.0	2.90	2.00
S	BMWW-t	MT20	5.0	8.0	2.50	3.50
T	BMV1+p	MT20	3.0	6.0		


Edge - INDICATES REFERENCE CORNER OF PLATE TOUCHES EDGE OF CHORD.

FACTORED CONCENTRATED LOADS (LBS)


JT	LOC.	LC1	MAX-	MAX+	FACE	DIR.	TYPE	HEEL	CONN.
X	14-9-12	-82	-82	---	BACK	VERT	TOTAL	---	C1
Y	16-9-12	-82	-82	---	BACK	VERT	TOTAL	---	C1
Z	1-11-4	-25	-25	---	BACK	VERT	TOTAL	---	C1
AA	3-11-4	-26	-26	---	BACK	VERT	TOTAL	---	C1
AB	7-11-4	-26	-26	---	BACK	VERT	TOTAL	---	C1
AC	8-10-8	-639	-639	---	BACK	VERT	TOTAL	---	C1
AD	10-9-12	-17	-17	---	BACK	VERT	TOTAL	---	C1
AE	12-9-12	-17	-17	---	BACK	VERT	TOTAL	---	C1
AF	14-9-12	-17	-17	---	BACK	VERT	TOTAL	---	C1

CONNECTION REQUIREMENTS

- 1) C1: A SUITABLE HANGER/MECHANICAL CONNECTION IS REQUIRED.



Structural component only
DWG# T-2007108



LUMBER
N. L. G. A. RULES

CHORDS	SIZE	LUMBER	DESCR.
A - D	2x4	DRY No.2	SPF
D - F	2x4	DRY No.2	SPF
F - H	2x4	DRY No.2	SPF
H - K	2x4	DRY No.2	SPF
S - B	2x4	DRY No.2	SPF
L - J	2x4	DRY No.2	SPF
S - Q	2x4	DRY No.2	SPF
Q - N	2x4	DRY No.2	SPF
N - L	2x4	DRY No.2	SPF
ALL WEBS	2x3	DRY No.2	SPF
EXCEPT			
S - C	2x4	DRY No.2	SPF
I - L	2x4	DRY No.2	SPF

DRY: SEASONED LUMBER.

PLATES (table in inches)

JT	TYPE	PLATES	W	LEN	Y	X
B	TMV-v	MT20	3.0	4.0		
C	TMW-w	MT20	5.0	8.0	2.50	2.75
D	TTW-w	MT20	5.0	8.0	2.25	2.75
E	TMW-w	MT20	4.0	4.0		
F	TS-t	MT20	3.0	8.0		
G	TMW-w	MT20	2.0	4.0		
H	TTW-w	MT20	5.0	8.0	2.25	2.75
I	TMW-w	MT20	5.0	8.0	2.50	2.75
J	TMV-v	MT20	3.0	4.0		
L	BMVW-t	MT20	4.0	9.0		Edge
M	BMW-w	MT20	4.0	4.0		
N	BS-t	MT20	3.0	8.0		
O	BMW-w	MT20	4.0	9.0		
P	BMW-w	MT20	4.0	8.0		
Q	BS-t	MT20	3.0	8.0		
R	BMW-w	MT20	4.0	4.0		
S	BMVW-t	MT20	4.0	9.0		Edge

Edge - INDICATES REFERENCE CORNER OF PLATE TOUCHES EDGE OF CHORD.

DIMENSIONS, SUPPORTS AND LOADINGS SPECIFIED BY FABRICATOR TO BE VERIFIED BY BUILDING DESIGNER

BEARINGS

JT	FACTORED GROSS REACTION		MAXIMUM FACTORED GROSS REACTION		INPUT BRG IN-SX	RECORD BRG IN-SX
	VERT	HORZ	DOWN	HORZ		
S	2063	0	2063	0	5-8	5-8
L	2063	0	2063	0	5-8	5-8

UNFACTORED REACTIONS

JT	1ST CASE		MAX MIN. COMPONENT REACTIONS		DEAD	SOIL
	COMBINED	SNOW	LIVE	PERM. LIVE		
S	1457	989 / 0	0 / 0	0 / 0	488 / 0	0 / 0
L	1457	989 / 0	0 / 0	0 / 0	488 / 0	0 / 0

BEARING MATERIAL TO BE SPF NO.2 OR BETTER AT JOINT(S) S, L

BRACING
TOP CHORD TO BE SHEATHED OR MAX. PURLIN SPACING = 2.94 FT.
MAX. UNBRACED BOTTOM CHORD LENGTH = 10.00 FT OR RIGID CEILING DIRECTLY APPLIED.

ALL PITCH BREAKS AND PERIMETER CORNER JOINTS MUST BE LATERALLY RESTRAINED.

LOADING
TOTAL LOAD CASES: (4)

MEMB.	MAX. FACTORED FORCE (LBS)	CHORDS		MAX. UNBRACED LENGTH	MEMB.	MAX. FACTORED FORCE (LBS)	MAX. FACTORED CSI (LC)
		VERT. LOAD (PLF)	CS1 (LC)				
FR-TO							
A-B	0 / 28	-91.8	-91.8 0.12 (1)	10.00	C-R	0 / 93	0.03 (4)
B-C	0 / 16	-91.8	-91.8 0.20 (1)	10.00	R-D	0 / 121	0.04 (4)
C-D	-2799 / 0	-91.8	-91.8 0.32 (1)	3.88	O-P	0 / 1267	0.29 (1)
D-E	-3508 / 0	-91.8	-91.8 0.95 (1)	2.94	P-E	-643 / 0	0.25 (1)
E-F	-3507 / 0	-91.8	-91.8 0.93 (1)	2.94	E-D	-2 / 0	0.00 (1)
F-G	-3507 / 0	-91.8	-91.8 0.93 (1)	2.94	O-G	-643 / 0	0.25 (1)
G-H	-3507 / 0	-91.8	-91.8 0.94 (1)	2.95	C-H	0 / 1265	0.28 (1)
H-I	-2799 / 0	-91.8	-91.8 0.32 (1)	3.88	M-H	0 / 121	0.04 (4)
I-J	0 / 16	-91.8	-91.8 0.20 (1)	10.00	M-I	0 / 93	0.03 (4)
J-K	0 / 28	-91.8	-91.8 0.12 (1)	10.00	S-C	-2974 / 0	0.83 (1)
S-B	-270 / 0	0.0	0.0 0.03 (1)	7.81	I-L	-2974 / 0	0.83 (1)
L-J	-270 / 0	0.0	0.0 0.03 (1)	7.81			
S-R	0 / 2417	-18.5	-18.5 0.53 (1)	10.00			
R-O	0 / 2489	-18.5	-18.5 0.54 (1)	10.00			
Q-P	0 / 2489	-18.5	-18.5 0.54 (1)	10.00			
P-O	0 / 3509	-18.5	-18.5 0.54 (1)	10.00			
O-N	0 / 2489	-18.5	-18.5 0.54 (1)	10.00			
N-M	0 / 2489	-18.5	-18.5 0.54 (1)	10.00			
M-L	0 / 2417	-18.5	-18.5 0.53 (1)	10.00			

TOTAL WEIGHT = 2 X 139 = 278 LB

DESIGN CRITERIA

SPECIFIED LOADS:

TOP CH.	LL = 25.6 PSF
DL	6.0 PSF
BDT CH.	LL = 0.0 PSF
DL	7.4 PSF
TOTAL LOAD	= 39.0 PSF

SPACING = 24.0 IN/C

LOADING IN FLAT SECTION BASED ON A SLOPE OF 8.00/12

THIS TRUSS IS DESIGNED FOR RESIDENTIAL OR SMALL BUILDING REQUIREMENTS OF PART 9, NBCC 2010, NBCC 2015

THIS DESIGN COMPLIES WITH:
- PART 9 OF BCBC 2018, OBC 2012, ABC 2019
- PART 9 OF OBC 2012 (2019 AMENDMENT)
- CSA 088-09, CSA 088-14
- TPIC 2011, TPIC 2014

(55 % OF 31.3 P.S.F. G.S.L. PLUS 8.4 P.S.F. RAIN LOAD) EQUALS 25.8 P.S.F. SPECIFIED ROOF LIVE LOAD

ALLOWABLE DEFL. (LL) = $L/360$ (1.17')
CALCULATED VERT. DEFL. (LL) = $L/999$ (0.21')
ALLOWABLE DEFL. (TL) = $L/360$ (1.17')
CALCULATED VERT. DEFL. (TL) = $L/999$ (0.41')

CSI: TC=0.95/1.00 (D-E-1), BC=0.64/1.00 (O-P-1), WB=0.83/1.00 (I-L-1), SS=0.28/1.00 (D-E-1)

DOL LUMBER=1.00 NAIL=1.00 LS BEND=1.10
COMP=1.10 SHEAR=1.10 TENS=1.10

COMPANION LIVE LOAD FACTOR = 1.00

AUTOSOLVE HEELS OFF

TRUSS PLATE MANUFACTURER IS NOT RESPONSIBLE FOR QUALITY CONTROL IN THE TRUSS MANUFACTURING PLANT.

NAIL VALUES

PLATE GRIP (DRY)	SHEAR (PSI)	SECTION (PLI)
MAX MIN	MAX MIN	MAX MIN
MT20	618 354 1667 788 1987 1658	

PLATE PLACEMENT TOL = 0.250 inches

PLATE ROTATION TOL = 5.0 Deg.

JSI GRIP = 0.89 (L) (INPUT = 0.90)
JSI METAL = 0.77 (N) (INPUT = 1.00)





Structural component only
DWG# T-2007109

JOB NAME	TRUSS NAME	QUANTITY	PLY	JOB DESC.	DRWG NO.
408152	T42	2	1	GREEN PARK HOMES	
Tamarack Roof Truss, Burlington					

Version 8.310 S Oct 29 2019 Mitek Industries, Inc. Sat Apr 25 11:29:38 2020 Page 1

ID:7vF?ag0E03cRuj6X1jSkzWYK-u?PpnOvRckyUZNSP6P6AHCHnN1r19RDGMelwLCzNCOT



LUMBER			
N. L. G. A. RULES	SIZE	LUMBER	DESCR.
CHORDS			
A - D	2x4	DRY	No.2
D - F	2x4	DRY	No.2
F - I	2x4	DRY	No.2
I - H	2x4	DRY	No.2
H - J	2x4	DRY	No.2
J - K	2x4	DRY	No.2
K - L	2x4	DRY	No.2
L - M	2x4	DRY	No.2
M - N	2x4	DRY	No.2
N - O	2x4	DRY	No.2
O - P	2x4	DRY	No.2
P - Q	2x4	DRY	No.2
Q - R	2x4	DRY	No.2
R - S	2x4	DRY	No.2
S - T	2x4	DRY	No.2
T - U	2x4	DRY	No.2
U - V	2x4	DRY	No.2
V - W	2x4	DRY	No.2
W - X	2x4	DRY	No.2
X - Y	2x4	DRY	No.2
Y - Z	2x4	DRY	No.2
Z - A	2x4	DRY	No.2
ALL WEBS EXCEPT	2x3	DRY	No.2

DRY: SEASONED LUMBER.

PLATES (table in inches)

JT	TYPE	PLATES	W	LEN	Y	X
B	TMVW-p	MT20	5.0	8.0	Edge	3.50
D	TMVW-t	MT20	4.0	4.0	2.00	1.75
O	TTWW-m	MT20	5.0	8.0	2.25	3.75
E	TMVW-w	MT20	2.0	4.0		
F	TTWW-m	MT20	5.0	8.0	2.25	3.75
G	TMVW-t	MT20	4.0	4.0	2.00	1.75
H	TMVW-p	MT20	5.0	8.0	Edge	3.50
J	BMV1-p	MT20	3.0	4.0		
K	BMVW-t	MT20	5.0	8.0	2.50	2.00
L	BMVW-t	MT20	4.0	4.0		
M	BS-t	MT20	3.0	6.0		
N	BMVW-t	MT20	4.0	9.0		
O	BS-t	MT20	3.0	6.0		
P	BMVW-t	MT20	4.0	4.0		
Q	BMVW-t	MT20	5.0	8.0	2.50	2.00
R	BMV1-p	MT20	3.0	4.0		

Edge - INDICATES REFERENCE CORNER OF PLATE TOUCHES EDGE OF CHORD.

DIMENSIONS, SUPPORTS AND LOADINGS SPECIFIED BY FABRICATOR TO BE VERIFIED BY BUILDING DESIGNER

BEARINGS		FACTORED GROSS REACTION	MAXIMUM FACTORED GROSS REACTION	INPUT BRG	RECRD BRG
JT	VERT	DOWN	DOWN	IN-SX	IN-SX
R	2063	0	2063	0	5-8
J	2063	0	2063	0	5-8

UNFACTORED REACTIONS

JT	1ST LCASE	MAX. MIN. COMPONENT REACTIONS	PERM. LIVE	WIND	DEAD	SOIL
R	1457	969 / 0	0 / 0	0 / 0	488 / 0	0 / 0
J	1457	969 / 0	0 / 0	0 / 0	488 / 0	0 / 0

BEARING MATERIAL TO BE SPF NO.2 OR BETTER AT JOINT(S) R, J

BRACING

TOP CHORD TO BE SHEATHED OR MAX. PURLIN SPACING = 2.78 FT.
MAX. UNBRACED BOTTOM CHORD LENGTH = 10.00 FT OR RIGID CEILING DIRECTLY APPLIED.

ALL PITCH BREAKS AND PERIMETER CORNER JOINTS MUST BE Laterally RESTRAINED.

LOADING

TOTAL LOAD CASES: (4)

CHORDS		WEBS	
MEMB.	MAX. FACTORED FORCE (LBS)	MEMB.	MAX. FACTORED FORCE (LBS)
FR-TO		FR-TO	
A-B	0 / 28	C-C	-353 / 0
B-C	-2834 / 0	C-P	-210 / 0
C-D	-2687 / 0	P-D	0 / 246
D-E	-3060 / 0	D-N	0 / 844
E-F	-3060 / 0	N-E	-872 / 0
F-G	-2687 / 0	N-F	0 / 844
G-H	-2834 / 0	L-F	0 / 246
H-I	0 / 28	L-G	-210 / 0
R-B	-2018 / 0	K-G	-353 / 0
J-H	-2018 / 0	B-Q	0 / 2591
		K-H	0 / 2591
R-Q	0 / 0		
Q-P	0 / 2555		
P-O	0 / 2386		
O-N	0 / 2386		
N-M	0 / 2386		
M-L	0 / 2386		
L-K	0 / 2555		
K-J	0 / 0		

TOTAL WEIGHT = 2 X 139 = 277 lb

DESIGN CRITERIA

SPECIFIED LOADS:

TOP CH. LL = 25.6 PSF
DL = 6.0 PSF
BOT CH. LL = 0.0 PSF
DL = 7.4 PSF
TOTAL LOAD = 39.0 PSF

SPACING = 24.0 IN. C/C

LOADING IN FLAT SECTION BASED ON A SLOPE OF 8.00/12

THIS TRUSS IS DESIGNED FOR RESIDENTIAL OR SMALL BUILDING REQUIREMENTS OF PART 9, NBCC 2010, NBCC 2015

THIS DESIGN COMPLIES WITH:

- PART 9 OF BCBC 2018, OBC 2012, ABC 2019
- PART 9 OF OBC 2012 (2019 AMENDMENT)
- CSA 086-09, CSA 086-14
- TPIC 2011, TPIC 2014

(65 % OF 31.3 P.S.F. G.S.L. PLUS 8.4 P.S.F. RAIN LOAD) EQUALS 25.6 P.S.F. SPECIFIED ROOF LIVE LOAD

ALLOWABLE DEFL.(LL) = L/360 (1.17")
CALCULATED VERT. DEFL.(LL) = L/999 (0.17")
ALLOWABLE DEFL.(TL) = L/360 (1.17")
CALCULATED VERT. DEFL.(TL) = L/999 (0.34")

CSI: TC=0.97/1.00 (D-E-1), BC=0.51/1.00 (K-L-1),
WB=0.59/1.00 (H-K-1), SSI=0.34/1.00 (D-E-1)

DOL LUMBER=1.00 NAIL=1.00 LBS BEND=1.10
COMP=1.10 SHEAR=1.10 TENS=1.10

COMPANION LIVE LOAD FACTOR = 1.00

TRUSS PLATE MANUFACTURER IS NOT RESPONSIBLE FOR QUALITY CONTROL IN THE TRUSS MANUFACTURING PLANT.


NAIL VALUES

PLATE GRIP(DRY) SHEAR SECTION (PSI) (PLI) (PLI)
MAX MIN MAX MIN MAX MIN
MT20 618 354 1687 788 1987 1656


PLATE PLACEMENT TOL. = 0.250 inches

PLATE ROTATION TOL. = 5.0 Deg.

JSI GRIP=0.87 (D) (INPUT = 0.90)
JSI METAL=0.75 (O) (INPUT = 1.00)



Structural component only
DWG# T-2007110



LUMBER
N. L. G. A. RULES

CHORDS	SIZE	LUMBER	DESCR.
A - D	2x4	DRY No.2	SPF
D - F	2x4	DRY No.2	SPF
F - I	2x4	DRY No.2	SPF
R - B	2x4	DRY No.2	SPF
J - H	2x4	DRY No.2	SPF
R - O	2x4	DRY No.2	SPF
O - M	2x4	DRY No.2	SPF
M - J	2x4	DRY No.2	SPF
ALL WEBS EXCEPT	2x3	DRY No.2	SPF

DRY: SEASONED LUMBER.

PLATES (table is in inches)

JT	TYPE	PLATES	W	LEN	Y	X
B	TMVW-p	MT20	5.0	8.0	Edge	3.50
C	TMWW-I	MT20	4.0	4.0	2.00	1.75
D	TTWW-m	MT20	5.0	8.0	2.25	2.00
E	TMW-w	MT20	2.0	4.0		
F	TTWW-m	MT20	5.0	8.0	2.25	2.00
G	TMWW-I	MT20	4.0	4.0	2.00	1.75
H	TMVW-p	MT20	5.0	8.0	Edge	3.50
J	BMV1-p	MT20	3.0	4.0		
K	BMWW-I	MT20	5.0	8.0	2.50	2.25
L	BMWW-I	MT20	4.0	4.0		
M	BS-I	MT20	3.0	8.0		
N	BMWW-I	MT20	4.0	9.0		
O	BS-I	MT20	3.0	8.0		
P	BMWW-I	MT20	4.0	4.0		
Q	BMWW-I	MT20	5.0	8.0	2.50	2.25
R	BMV1-p	MT20	3.0	4.0		

Edge - INDICATES REFERENCE CORNER OF PLATE TOUCHES EDGE OF CHORD.

DIMENSIONS, SUPPORTS AND LOADINGS SPECIFIED BY FABRICATOR TO BE VERIFIED BY BUILDING DESIGNER

BEARINGS

	FACTORED GROSS REACTION	MAXIMUM FACTORED GROSS REACTION	INPUT BRG IN-SX	REQRD BRG IN-SX
JT VERT	2063	0	0	5-8
R	2063	0	0	5-8
J	2063	0	0	5-8

UNFACTORED REACTIONS

1ST LCASE	MAX MIN. COMPONENT REACTIONS	SNOW	LIVE	PERM. LIVE	WIND	DEAD	SOIL
JT COMBINED	1457	968 / 0	0 / 0	0 / 0	0 / 0	488 / 0	0 / 0
J	1457	968 / 0	0 / 0	0 / 0	0 / 0	488 / 0	0 / 0

BEARING MATERIAL TO BE SPF NO.2 OR BETTER AT JOINT(S) R, J

BRACING
TOP CHORD TO BE SHEATHED OR MAX. PURLIN SPACING = 3.58 FT.
MAX. UNBRACED BOTTOM CHORD LENGTH = 10.00 FT OR RIGID CEILING DIRECTLY APPLIED.

ALL PITCH BREAKS AND PERIMETER CORNER JOINTS MUST BE Laterally RESTRAINED.

LOADING
TOTAL LOAD CASES: (4)

CHORDS				WEBS			
MEMB.	MAX. FACTORED FORCE (LBS)	VERT. LOAD (PLF)	MAX. FACTORED CS1 (LC)	MEMB.	MAX. FACTORED FORCE (LBS)	MAX. FACTORED CS1 (LC)	UNBRACED LENGTH FR-TO
FR-TO				FR-TO			
A-B	0 / 28	-91.8	-91.8 0.12 (1)	Q-C	-255 / 12	0.07 (1)	10.00
B-C	-2889 / 0	-91.8	-91.8 0.58 (1)	C-P	-435 / 0	0.42 (1)	3.58
C-D	-2539 / 0	-91.8	-91.8 0.52 (1)	P-D	0 / 350	0.08 (1)	3.83
D-E	-2559 / 0	-91.8	-91.8 0.48 (1)	D-N	0 / 482	0.11 (1)	3.85
E-F	-2559 / 0	-91.8	-91.8 0.48 (1)	N-E	-641 / 0	0.56 (1)	3.85
F-G	-2539 / 0	-91.8	-91.8 0.52 (1)	N-F	0 / 482	0.11 (1)	3.83
G-H	-2889 / 0	-91.8	-91.8 0.58 (1)	L-F	0 / 350	0.08 (1)	3.58
H-I	0 / 28	-91.8	-91.8 0.12 (1)	L-G	-435 / 0	0.42 (1)	10.00
R-B	-2014 / 0	0.0	0.0 0.20 (1)	K-G	-255 / 12	0.07 (1)	5.95
J-H	-2014 / 0	0.0	0.0 0.20 (1)	B-Q	0 / 2635	0.59 (1)	5.95
R-Q	0 / 0	-18.5	-18.5 0.15 (4)	K-H	0 / 2635	0.59 (1)	10.00
O-P	0 / 2809	-18.5	-18.5 0.49 (1)				10.00
P-O	0 / 2249	-18.5	-18.5 0.43 (1)				10.00
O-N	0 / 2249	-18.5	-18.5 0.43 (1)				10.00
N-M	0 / 2249	-18.5	-18.5 0.43 (1)				10.00
M-L	0 / 2249	-18.5	-18.5 0.43 (1)				10.00
L-K	0 / 2609	-18.5	-18.5 0.49 (1)				10.00
K-J	0 / 0	-18.5	-18.5 0.15 (4)				10.00

TOTAL WEIGHT = 2 X 145 = 289 lb

DESIGN CRITERIA

SPECIFIED LOADS:

TOP CH.	LL	DL	PSF
LL	25.6	6.0	PSF
DL	0.0	7.4	PSF
TOTAL LOAD	39.0		PSF

SPACING = 24.0 IN. C/C

LOADING IN FLAT SECTION BASED ON A SLOPE OF 6.00/12

THIS TRUSS IS DESIGNED FOR RESIDENTIAL OR SMALL BUILDING REQUIREMENTS OF PART 9, NBCC 2010, NBCC 2015

THIS DESIGN COMPLIES WITH:
 - PART 9 OF BCBC 2018, OBC 2012, ABC 2019
 - PART 9 OF OBC 2012 (2019 AMENDMENT)
 - CSA 086-09, CSA 088-14
 - TPIC 2011, TPIC 2014

(55% OF 31.3 P.S.F. G.S.L. PLUS 8.4 P.S.F. RAIN LOAD) EQUALS 25.6 P.S.F. SPECIFIED ROOF LIVE LOAD

ALLOWABLE DEFL. (LL) = L/360 (1.17)
 CALCULATED VERT. DEFL. (LL) = L/999 (0.15)
 ALLOWABLE DEFL. (TL) = L/360 (1.17)
 CALCULATED VERT. DEFL. (TL) = L/999 (0.28)

CS1: TC=0.58/1.00 (G-H-I), BC=0.49/1.00 (K-L-I), WB=0.58/1.00 (B-Q-I), SS1=0.25/1.00 (D-E-I)

DOL LUMBER=1.00 NAIL=1.00 LS BEND=1.10
 COMP=1.10 SHEAR=1.10 TENS=1.10

COMPANION LIVE LOAD FACTOR = 1.00

TRUSS PLATE MANUFACTURER IS NOT RESPONSIBLE FOR QUALITY CONTROL IN THE TRUSS MANUFACTURING PLANT.


NAIL VALUES

PLATE GRIP (DRY)	SHEAR (PSI)	SECTION (PLI)	MAX MIN	MAX MIN	MAX MIN
MT20	618	354	1667	788	1987


PLATE PLACEMENT TOL. = 0.250 inches

PLATE ROTATION TOL. = 5.0 Deg.

JSI GRIP = 0.89 (Q) (INPUT = 0.90)
 JSI METAL = 0.69 (M) (INPUT = 1.00)



Structural component only
 DWG# T-2007111



N. L. G. A. RULES	CHORDS	SIZE	LUMBER	DESCR.
A - D	2x4	DRY	No.2	SPF
D - E	2x4	DRY	No.2	SPF
E - F	2x4	DRY	No.2	SPF
F - G	2x4	DRY	No.2	SPF
G - H	2x4	DRY	No.2	SPF
H - I	2x4	DRY	No.2	SPF
I - J	2x4	DRY	No.2	SPF
J - K	2x4	DRY	No.2	SPF
K - L	2x4	DRY	No.2	SPF
L - M	2x4	DRY	No.2	SPF
M - N	2x4	DRY	No.2	SPF
N - O	2x4	DRY	No.2	SPF
O - P	2x4	DRY	No.2	SPF
P - Q	2x4	DRY	No.2	SPF
Q - R	2x4	DRY	No.2	SPF
R - S	2x4	DRY	No.2	SPF
S - T	2x4	DRY	No.2	SPF
T - U	2x4	DRY	No.2	SPF
U - V	2x4	DRY	No.2	SPF
V - W	2x4	DRY	No.2	SPF
W - X	2x4	DRY	No.2	SPF
X - Y	2x4	DRY	No.2	SPF
Y - Z	2x4	DRY	No.2	SPF
Z - A	2x4	DRY	No.2	SPF

DRY: SEASONED LUMBER.

PLATE TYPE	PLATES	W	LEN	Y	X
B	MT20	5.0	8.0	Edge	3.50
C	MT20	4.0	4.0	2.00	1.75
D	MT20	3.0	6.0		
E	MT20	4.0	8.0		
F	MT20	4.0	4.0		
G	MT20	4.0	8.0		
H	MT20	3.0	6.0		
I	MT20	4.0	4.0	2.00	1.75
J	MT20	5.0	8.0	Edge	3.50
K	MT20	3.0	4.0		
L	MT20	5.0	8.0	2.50	2.25
M	MT20	3.0	6.0		
N	MT20	4.0	9.0		
O	MT20	4.0	9.0		
P	MT20	4.0	9.0		
Q	MT20	3.0	6.0		
R	MT20	5.0	8.0	2.50	2.25
S	MT20	3.0	4.0		

Edge - INDICATES REFERENCE CORNER OF PLATE TOUCHES EDGE OF CHORD.

DIMENSIONS, SUPPORTS AND LOADINGS SPECIFIED BY FABRICATOR TO BE VERIFIED BY BUILDING DESIGNER

BEARINGS	FACTORED GROSS REACTION	MAXIMUM FACTORED GROSS REACTION	INPUT BRG	RECORD BRG
JT	VERT	HORIZ	DOWN	HORIZ
S	2083	0	2083	0
L	2083	0	2083	0

UNFACTORED REACTIONS	1ST CASE	MAX. MIN. COMPONENT REACTIONS	SNOW	LIVE	PERM. LIVE	WIND	DEAD	SOIL
JT	COMBINED							
S	1457	988 / 0	0 / 0	0 / 0	0 / 0	0 / 0	488 / 0	0 / 0
L	1457	988 / 0	0 / 0	0 / 0	0 / 0	0 / 0	488 / 0	0 / 0

BEARING MATERIAL TO BE SPF NO.2 OR BETTER AT JOINT(S) S, L

BRACING
TOP CHORD TO BE SHEATHED OR MAX. PURLIN SPACING = 3.25 FT.
MAX. UNBRACED BOTTOM CHORD LENGTH = 10.00 FT OR RIGID CEILING DIRECTLY APPLIED.

ALL PITCH BREAKS AND PERIMETER CORNER JOINTS MUST BE Laterally RESTRAINED.

1 LATERAL BRACE(S) AT 1/2 LENGTH OF C-P, F-P, F-O, I-O.

END VERTICAL(S) MUST BE SHEATHED OR HAVE BRACES AS INDICATED IN THE MAX. UNBRACED LENGTH COLUMN OF THE TABLE BELOW

CHORDS				WEBS			
MEMB.	MAX. FACTORED FORCE (LBS)	FACTORED VERT. LOAD (PL)	MAX. UNBRACED LENGTH (FT)	MEMB.	MAX. FACTORED FORCE (LBS)	MAX. UNBRACED LENGTH (FT)	MAX. UNBRACED LENGTH (FT)
FR-TO				FR-TO			
A-B	0 / 29	-91.8	-91.8 0.12 (1)	10.00	R-C	-182 / 52	0.06 (1)
B-C	-2906 / 0	-91.8	-91.8 0.83 (1)	3.25	C-P	-637 / 0	0.29 (1)
C-D	-2373 / 0	-91.8	-91.8 0.72 (1)	3.66	P-F	0 / 674	0.15 (1)
D-E	-2373 / 0	-91.8	-91.8 0.72 (1)	3.66	F-O	-222 / 0	0.11 (1)
E-F	-2100 / 0	-91.8	-91.8 0.19 (1)	4.53	O-G	0 / 674	0.15 (1)
F-G	-2100 / 0	-91.8	-91.8 0.19 (1)	4.53	G-I	-637 / 0	0.29 (1)
G-H	-2373 / 0	-91.8	-91.8 0.72 (1)	3.66	I-J	-182 / 52	0.06 (1)
H-I	-2373 / 0	-91.8	-91.8 0.72 (1)	3.66	J-K	0 / 2649	0.60 (1)
I-J	-2906 / 0	-91.8	-91.8 0.83 (1)	3.25	K-L	0 / 2649	0.60 (1)
J-K	0 / 29	-91.8	-91.8 0.12 (1)	10.00	L-M	0 / 0	0.00 (1)
K-L	-2008 / 0	0.0	0.0 0.20 (1)	5.98			
L-M	-2008 / 0	0.0	0.0 0.20 (1)	5.98			
M-N	0 / 0	-18.5	-18.5 0.20 (4)	10.00			
N-O	0 / 2630	-18.5	-18.5 0.52 (1)	10.00			
O-P	0 / 2630	-18.5	-18.5 0.52 (1)	10.00			
P-Q	0 / 2193	-18.5	-18.5 0.45 (1)	10.00			
Q-R	0 / 2630	-18.5	-18.5 0.52 (1)	10.00			
R-S	0 / 2630	-18.5	-18.5 0.52 (1)	10.00			
S-T	0 / 0	-18.5	-18.5 0.20 (4)	10.00			

TOTAL WEIGHT = 2 X 145 = 291 LB

DESIGN CRITERIA

SPECIFIED LOADS:
TOP CH. LL = 25.8 PSF
DL = 6.0 PSF
BOT CH. LL = 0.0 PSF
DL = 7.4 PSF
TOTAL LOAD = 39.0 PSF

SPACING = 24.0 IN. OC

LOADING IN FLAT SECTION BASED ON A SLOPE OF 5.00/12

THIS TRUSS IS DESIGNED FOR RESIDENTIAL OR SMALL BUILDING REQUIREMENTS OF PART 9, NBCC 2010, NBCC 2015

THIS DESIGN COMPLIES WITH:
- PART 9 OF NBCC 2010, OBC 2012, ABC 2019
- PART 9 OF OBC 2012 (2019 AMENDMENT)
- CSA 088-09, CSA 086-14
- TPIC 2011, TPIC 2014

(5% OF 31.3 P.S.F. G.S.L. PLUS 8.4 P.S.F. RAIN LOAD) EQUALS 25.6 P.S.F. SPECIFIED ROOF LIVE LOAD

ALLOWABLE DEFL.(LL) = L/360 (1.17")
CALCULATED VERT. DEFL.(LL) = L/999 (0.14")
ALLOWABLE DEFL.(TL) = L/360 (1.17")
CALCULATED VERT. DEFL.(TL) = L/999 (0.30")

CSI: TC=0.83/1.00 (I-J:1), BC=0.52/1.00 (M-O:1), WB=0.80/1.00 (B-R:1), SI=0.28/1.00 (I-J:1)

DOL LUMBER=1.00 NAIL=1.00 LS BEND=1.10
COMP=1.10 SHEAR=1.10 TENS=1.10

COMPANION LIVE LOAD FACTOR = 1.00

TRUSS PLATE MANUFACTURER IS NOT RESPONSIBLE FOR QUALITY CONTROL IN THE TRUSS MANUFACTURING PLANT.

NAIL VALUES
PLATE GRIP(DRY) SHEAR SECTION
(PSI) (PLI) (PLI)
MAX MIN MAX MIN MAX MIN
MT20 618 354 1657 788 1987 1856

PLATE PLACEMENT TOL. = 0.250 inches

PLATE ROTATION TOL. = 5.0 Deg.

JSI GRIP= 0.86 (M) (INPUT = 0.90)
JSI METAL= 0.79 (N) (INPUT = 1.00)




Structural component only
DWG# T-2007112

JOB NAME	TRUSS NAME	QUANTITY	PLY	JOB DESC.	DRWG NO.
408152	T45	2	1	GREEN PARK HOMES	
Tamarack Roof Truss, Burlington					

Version 8.310 S Oct 29 2019 MITek Industries, Inc. Sat Apr 25 11:29:39 2020 Page 1

ID:7vF?ag0E03cRUj6X1SrkzWYK-Ja5xPQyKvK3Qda_nXgtvQvRdFnmJni2c_ayWzNCOQ

Scale = 1/58.0



LUMBER

N. L. G. A. RULES

CHORDS	SIZE	LUMBER
A - D	2x4	DRY No.2
D - F	2x4	DRY No.2
F - G	2x4	DRY No.2
G - I	2x4	DRY No.2
I - L	2x4	DRY No.2
T - B	2x4	DRY No.2
M - K	2x4	DRY No.2
T - R	2x4	DRY No.2
R - O	2x4	DRY No.2
O - M	2x4	DRY No.2

ALL WEBS 2x3 DRY No.2
EXCEPT

DRY: SEASONED LUMBER.

PLATES (table is in inches)

JT	TYPE	PLATES	W	LEN	Y	X
B	TMV+p	MT20	3.0	4.0		
C	TMWW-1	MT20	5.0	6.0	2.50	2.25
D	TS-1	MT20	3.0	6.0		
E	TMWW-1	MT20	4.0	4.0	2.00	1.50
F	TTW-n	MT20	4.0	4.0	2.00	1.75
G	TTWW-m	MT20	5.0	6.0	2.00	2.00
H	TMWW-1	MT20	4.0	4.0	2.00	1.50
I	TS-1	MT20	3.0	6.0		
J	TMWW-1	MT20	5.0	6.0	2.50	2.25
K	TMV+p	MT20	3.0	4.0		
M	BMWW-1	MT20	5.0	6.0	2.25	2.00
N, P, S						
N	BMWW-1	MT20	4.0	4.0		
O	BS-1	MT20	3.0	6.0		
Q	BMWW-1	MT20	4.0	4.0		
R	BS-1	MT20	3.0	6.0		
T	BMWW-1	MT20	5.0	6.0	2.25	2.00

DIMENSIONS, SUPPORTS AND LOADINGS SPECIFIED BY FABRICATOR TO BE VERIFIED BY BUILDING DESIGNER

BEARINGS

	FACTORED GROSS REACTION	MAXIMUM FACTORED GROSS REACTION	INPUT BRG	REQD BRG
JT	VERT	DOWN	BRG	BRG
T	2063	0	5-8	5-8
M	2063	0	5-8	5-8

UNFACTORED REACTIONS

JT	1ST CASE	MAX. MIN. COMPONENT REACTIONS	DEAD	SOIL
T	COMBINED	SNOW	0/0	0/0
M	1457	968/0	0/0	0/0
	1457	968/0	0/0	0/0

BEARING MATERIAL TO BE SPF NO.2 OR BETTER AT JOINT(S) T, M

BRACING

TOP CHORD TO BE SHEATHED OR MAX. PURLIN SPACING = 3.86 FT.
MAX. UNBRACED BOTTOM CHORD LENGTH = 10.00 FT. OR RIGID CEILING DIRECTLY APPLIED.

ALL PITCH BREAKS AND PERIMETER CORNER JOINTS MUST BE Laterally RESTRAINED.

1 LATERAL BRACE(S) AT 1/2 LENGTH OF E-Q, H-P, C-T, J-M

END VERTICAL(S) MUST BE SHEATHED OR HAVE BRACES AS INDICATED IN THE MAX. UNBRACED LENGTH COLUMN OF THE TABLE BELOW

LOADING

TOTAL LOAD CASES: (4)

CHORDS	MEMB.	MAX. FACTORED FORCE (LBS)	FACTORED VERT. LOAD (PLF)	FACTORED LC1 MAX CS1 (LC)	UNBRACED LENGTH	WEBS	MEMB.	MAX. FACTORED FORCE (LBS)	MAX CS1 (LC)
FR-TO						FR-TO			
A-B	0/28	-91.8	-91.8	0.12 (1)	10.00	C-S	-110/37	0.04 (1)	
B-C	0/19	-91.8	-91.8	0.32 (1)	10.00	S-E	0/276	0.06 (1)	
C-D	-2759/0	-91.8	-91.8	0.40 (1)	3.86	E-Q	-651/0	0.31 (1)	
D-E	-2759/0	-91.8	-91.8	0.40 (1)	3.86	Q-F	0/613	0.14 (1)	
E-F	-2167/0	-91.8	-91.8	0.36 (1)	4.30	F-G	0/4	0.00 (1)	
F-G	-1925/0	-91.8	-91.8	0.18 (1)	4.71	P-G	0/609	0.14 (1)	
G-H	-2166/0	-91.8	-91.8	0.36 (1)	4.30	H-N	-682/0	0.31 (1)	
H-I	-2780/0	-91.8	-91.8	0.40 (1)	3.86	N-J	0/278	0.06 (1)	
I-J	-2780/0	-91.8	-91.8	0.40 (1)	3.86	J-M	-110/37	0.04 (1)	
J-K	0/19	-91.8	-91.8	0.32 (1)	10.00	T-C	-3040/0	0.85 (1)	
K-L	0/28	-91.8	-91.8	0.12 (1)	10.00				
T-B	-326/0	0.0	0.0	0.03 (1)	7.81				
M-K	-326/0	0.0	0.0	0.03 (1)	7.81				
T-S	0/2536	-18.5	-18.5	0.55 (1)	10.00				
S-R	0/2362	-18.5	-18.5	0.53 (1)	10.00				
R-Q	0/2362	-18.5	-18.5	0.53 (1)	10.00				
Q-P	0/1924	-18.5	-18.5	0.40 (1)	10.00				
P-O	0/2362	-18.5	-18.5	0.53 (1)	10.00				
O-N	0/2362	-18.5	-18.5	0.53 (1)	10.00				
N-M	0/2537	-18.5	-18.5	0.55 (1)	10.00				

TOTAL WEIGHT = 2 X 151 = 302 lb

DESIGN CRITERIA

SPECIFIED LOADS:

TOP CH. LL = 25.6 PSF
DL = 6.0 PSF
BOT CH. LL = 0.0 PSF
DL = 7.4 PSF
TOTAL LOAD = 39.0 PSF

SPACING = 24.0 IN. C/C

LOADING IN FLAT SECTION BASED ON A SLOPE OF 6.00/12

THIS TRUSS IS DESIGNED FOR RESIDENTIAL OR SMALL BUILDING REQUIREMENTS OF PART 9, NBC 2010, NBC 2015

THIS DESIGN COMPLIES WITH:

- PART 9 OF BCBC 2018, OBC 2012, ABC 2019
- PART 9 OF OBC 2012 (2019 AMENDMENT)
- CSA 086-09, CSA 086-14
- TPIC 2011, TPIC 2014

(55% OF 31.3 P.S.F. G.S.L. PLUS 8.4 P.S.F. RAIN LOAD) EQUALS 25.6 P.S.F. SPECIFIED ROOF LIVE LOAD

ALLOWABLE DEFL.(LL) = L/360 (1.17")
CALCULATED VERT. DEFL.(LL) = L/999 (0.15")
ALLOWABLE DEFL.(TL) = L/360 (1.17")
CALCULATED VERT. DEFL.(TL) = L/999 (0.32")

CS1: TC=0.40/1.00 (H-J), BC=0.58/1.00 (M-N), WS=0.85/1.00 (J-M), SS1=0.20/1.00 (B-C-1)

DOL LUMBER=1.00 NAIL=1.00 LS BEND=1.10
COMP=1.10 SHEAR=1.10 TENS=1.10

COMPANION LIVE LOAD FACTOR = 1.00

AUTOSOLVE HEELS OFF

TRUSS PLATE MANUFACTURER IS NOT RESPONSIBLE FOR QUALITY CONTROL IN THE TRUSS MANUFACTURING PLANT.

NAIL VALUES

PLATE GRIP(DRY) SHEAR SECTION
(PSI) (PLI) (PLI)
MAX MIN MAX MIN MAX MIN
MT20 618 354 1657 788 1987 1856

PLATE PLACEMENT TOL. = 0.250 inches

PLATE ROTATION TOL. = 5.0 Deg.


JSI GRIP = 0.89 (M) (INPUT = 0.90)

JSI METAL = 0.83 (O) (INPUT = 1.00)



Structural component only
DWG# T-2007113

JOB NAME 408152	TRUSS NAME T46	QUANTITY 6	PLY 1	JOB DESC. GREEN PARK HOMES	DRWG NO.
Tamarack Roof Truss, Burlington					



LUMBER			
N. L. G. A. RULES	SIZE	LUMBER	DESCR.
CHORDS			
A - D	2x4	DRY	No.2
D - F	2x4	DRY	No.2
F - H	2x4	DRY	No.2
H - K	2x4	DRY	No.2
S - B	2x4	DRY	No.2
L - J	2x4	DRY	No.2
S - Q	2x4	DRY	No.2
Q - N	2x4	DRY	No.2
N - L	2x4	DRY	No.2
ALL WEBS EXCEPT	2x3	DRY	No.2
S - C	2x4	DRY	No.2
I - L	2x4	DRY	No.2

DRY: SEASONED LUMBER.

PLATES (table is in inches)					
JT	TYPE	PLATES	W	LEN	X
B	TMV+p	MT20	3.0	4.0	
C	TMWW-i	MT20	5.0	6.0	2.25 2.00
D	TS-i	MT20	3.0	6.0	
E	TMWW-i	MT20	5.0	6.0	
F	TTWW+p	MT20	4.0	6.0	Edge
G	TMWW-i	MT20	5.0	6.0	
H	TS-i	MT20	3.0	6.0	
I	TMWW-i	MT20	5.0	6.0	2.25 2.00
J	TMV+p	MT20	3.0	4.0	
L	BMVW-i	MT20	4.0	9.0	Edge
M, O, P, R					
M	BMWW-i	MT20	4.0	6.0	
N	BS-i	MT20	3.0	6.0	
Q	BS-i	MT20	3.0	6.0	
S	BMVW-i	MT20	4.0	9.0	Edge

Edge - INDICATES REFERENCE CORNER OF PLATE TOUCHES EDGE OF CHORD.

DIMENSIONS, SUPPORTS AND LOADINGS SPECIFIED BY FABRICATOR TO BE VERIFIED BY BUILDING DESIGNER

FACTORED		MAXIMUM FACTORED		INPUT		REQD	
GROSS REACTION	DOWN	GROSS REACTION	DOWN	BRG	IN-SX	BRG	IN-SX
JT	VERT	JT	VERT	JT	IN-SX	JT	IN-SX
S	2083	0	2083	0	5-8	5-8	5-8
L	2083	0	2083	0	5-8	5-8	5-8

UNFACTORED REACTIONS		MAX. MIN. COMPONENT REACTIONS	
1ST CASE	2ND CASE	1ST CASE	2ND CASE
JT	COMBINED	JT	COMBINED
S	1457	999/0	0/0
L	1457	999/0	0/0

BEARING MATERIAL TO BE SPF NO.2 OR BETTER AT JOINT(S) S, L

BRACING
TOP CHORD TO BE SHEATHED OR MAX. PURLIN SPACING = 3.75 FT.
MAX. UNBRACED BOTTOM CHORD LENGTH = 10.00 FT OR RIGID CEILING DIRECTLY APPLIED.

ALL PITCH BREAKS AND PERIMETER CORNER JOINTS MUST BE LATERALLY RESTRAINED.

1 LATERAL BRACE(S) AT 1/2 LENGTH OF C-S, L.

END VERTICAL(S) MUST BE SHEATHED OR HAVE BRACES AS INDICATED IN THE MAX. UNBRACED LENGTH COLUMN OF THE TABLE BELOW

LOADING

TOTAL LOAD CASES: (4)

CHORDS		WEBS	
MEMB.	FACTORED	MEMB.	FACTORED
MAX. FORCE (LBS)	VERT. LOAD (PLF)	MAX. FORCE (LBS)	VERT. LOAD (PLF)
FR-TO	FROM TO	FR-TO	FROM TO
A-B	0/28	F-O	0/866
B-C	0/22	G-G	-728/0
C-D	-2808/0	H-H	0/391
D-E	-2808/0	I-I	-192/18
E-F	-2322/0	J-J	0/866
F-G	-2322/0	K-K	-728/0
G-H	-2808/0	L-L	0/391
H-I	-2808/0	M-M	-192/18
I-J	0/22	N-N	0/866
J-K	0/28	O-O	-728/0
K-L	-344/0	P-P	0/391
L-M	-344/0	Q-Q	-192/18
		R-R	0/866
		S-S	-728/0
		T-T	0/391
		U-U	-192/18
		V-V	0/866
		W-W	-728/0
		X-X	0/391
		Y-Y	-192/18
		Z-Z	0/866

TOTAL WEIGHT = 8 X 152 = 910 LBS

DESIGN CRITERIA

SPECIFIED LOADS:
TOP CH. LL = 25.6 PSF
DL = 8.0 PSF
BOT CH. LL = 0.0 PSF
DL = 7.4 PSF
TOTAL LOAD = 39.0 PSF

SPACING = 24.0 IN. C/C

THIS TRUSS IS DESIGNED FOR RESIDENTIAL OR SMALL BUILDING REQUIREMENTS OF PART 9, NBCC 2010, NBCC 2015

THIS DESIGN COMPLIES WITH:
- PART 9 OF BCBC 2018, OBC 2012, ABC 2019
- PART 9 OF OBC 2012 (2019 AMENDMENT)
- CSA 086-08, CSA 086-14
- TPIC 2011, TPIC 2014

(55% OF 31.3 P.S.F. G.S.L. PLUS 8.4 P.S.F. RAIN LOAD) EQUALS 25.6 P.S.F. SPECIFIED ROOF LIVE LOAD

ALLOWABLE DEFL.(LL) = L/360 (1.17")
CALCULATED VERT. DEFL.(LL) = L/999 (0.14")
ALLOWABLE DEFL.(TL) = L/360 (1.17")
CALCULATED VERT. DEFL.(TL) = L/999 (0.28")

CS: TC=0.48/1.00 (C-E:1), BC=0.53/1.00 (L-M:1), WB=0.72/1.00 (E-P:1), SS=0.22/1.00 (J-K:1)

DOL LUMBER=1.00 NAIL=1.00 LS BEND=1.10 COMP=1.10 SHEAR=1.10 TENS= 1.10

COMPANION LIVE LOAD FACTOR = 1.00

AUTOSOLVE HEELS OFF

TRUSS PLATE MANUFACTURER IS NOT RESPONSIBLE FOR QUALITY CONTROL IN THE TRUSS MANUFACTURING PLANT.

NAIL VALUES
PLATE GRIP(DRY) SHEAR SECTION (PSI) (PLI) (PLI)
MAX MIN MAX MIN MAX MIN
MT20 618 354 1667 788 1987 1858

PLATE PLACEMENT TOL = 0.250 inches

PLATE ROTATION TOL = 5.0 Deg.

JSI GRIP= 0.87 (C) (INPUT = 0.90)
JSI METAL= 0.77 (I) (INPUT = 1.00)




Structural component only
DWG# T-2007114

JOB NAME	TRUSS NAME	QUANTITY	PLY	JOB DESC.	DRWG NO.
408152	T47	1	2	GREEN PARK HOMES	
Tamarack Roof Truss, Burlington				TRUSS DESC.	

Version 8.310 S Oct 29 2019 MITek Industries, Inc. Sat Apr 25 11:28:42 2020 Page 2
ID:37vF?aG0EQ3cRUi6X1jSrkzIWK-i9m42R CCaieHlJZTfDaWTXzGSyYZDD8kZDEYrzNCON

PLATES (table is in inches)


JT	TYPE	PLATES	W	LEN	Y	X
B	TMVW-p	MT20	4.0	6.0	1.00	3.00
C	TTWW-m	MT20	5.0	6.0	2.25	2.00
D	TMW-w	MT20	2.0	4.0		
E	TTWW-m	MT20	5.0	6.0	2.25	2.00
F	TMVW-p	MT20	4.0	4.0	1.50	2.00
G	BMV1-p	MT20	3.0	6.0		
H	BMWW-t	MT20	5.0	6.0		
I	BS-t	MT20	5.0	6.0		
J	BMWWWW-t	MT20	5.0	6.0		
K	BMWW-t	MT20	5.0	6.0		
L	BMV1-p	MT20	3.0	6.0		



Structural component only
DWG# T-2007115 *3/2*

JOB NAME	TRUSS NAME	QUANTITY	PLY	JOB DESC.	DRWG NO.
408152	T48	1	1	GREEN PARK HOMES	
Tamarack Roof Truss, Burlington					

Version 8.310 5 Oct 20 2019 Mitek Industries, Inc. Sat Apr 26 11:28:43 2020 Page 1
ID:7vF?aG0E03cRUj6X1|SrkziWYK-BMKSFN?qzurVvRui0Nkp3g47HsGXldlzDyo5IzNCOM



TOTAL WEIGHT = 68 lb

LUMBER	N. L. G. A. RULES	CHORDS	SIZE	DRY	LUMBER	DESCR.
A - D	2x4	DRY	No.2	SPF		
E - F	2x4	DRY	No.2	SPF		
G - H	2x4	DRY	No.2	SPF		
I - J	2x4	DRY	No.2	SPF		
K - L	2x4	DRY	No.2	SPF		
M - N	2x4	DRY	No.2	SPF		
ALL WEBS	2x3	DRY	No.2	SPF		
EXCEPT						

DRY: SEASONED LUMBER.

PLATES (table is in inches)

JT	TYPE	PLATES	W	LEN	Y	X
B	TMV+p	MT20	3.0	4.0		
C	TMWW-t	MT20	4.0	4.0	2.00	1.75
D	TTW-m	MT20	4.0	4.0		
E	TTWW-m	MT20	5.0	6.0	2.25	2.00
F	TMVW+p	MT20	4.0	4.0	1.50	2.00
G	BMV1+p	MT20	3.0	4.0		
H	BMWW-t	MT20	4.0	6.0		
I	BS-t	MT20	3.0	6.0		
J	BMWW-t	MT20	4.0	9.0		
K	BMVW1-t	MT20	4.0	6.0		

DIMENSIONS, SUPPORTS AND LOADINGS SPECIFIED BY FABRICATOR TO BE VERIFIED BY BUILDING DESIGNER

BEARINGS	FACTORED GROSS REACTION	MAXIMUM FACTORED GROSS REACTION	INPUT BRG	REQD BRG
JT	VERT	HORIZ	DOWN	HORIZ
K	1039	0	1039	0
G	914	0	914	0

A SUITABLE HANGER/MECHANICAL CONNECTION IS REQUIRED AT JOINT G. MINIMUM BEARING LENGTH AT JOINT G = 3-8.

UNFACTORED REACTIONS

1ST CASE	SNOW	LIVE	PERM LIVE	WIND	DEAD	SOIL
JT	732	494 / 0	0 / 0	0 / 0	238 / 0	0 / 0
K	732	494 / 0	0 / 0	0 / 0	238 / 0	0 / 0
G	646	424 / 0	0 / 0	0 / 0	222 / 0	0 / 0

BEARING MATERIAL TO BE SPF NO.2 OR BETTER AT JOINT(S) K

BRACING

TOP CHORD TO BE SHEATHED OR MAX. PURLIN SPACING = 8.12 FT.
MAX. UNBRACED BOTTOM CHORD LENGTH = 10.00 FT OR RIGID CEILING DIRECTLY APPLIED.

ALL PITCH BREAKS AND PERIMETER CORNER JOINTS MUST BE Laterally RESTRAINED.

LOADING

TOTAL LOAD CASES: (4)

CHORDS	MEMB.	FORCE (LBS)	FACTORED VERT. LOAD (PLF)	MAX. CSI (LC)	MAX. UNBRACED LENGTH	FR-TO	WEBS	MEMB.	FORCE (LBS)	MAX. CSI (LC)
A-B	0 / 28	-91.8	-91.8	0.12 (1)	10.00	C-J	-232 / 0	0.10 (1)		
B-C	0 / 18	-91.8	-91.8	0.22 (1)	10.00	J-D	0 / 134	0.03 (4)		
C-D	-916 / 0	-91.8	-91.8	0.18 (1)	8.24	E-E	0 / 152	0.03 (1)		
D-E	-806 / 0	-91.8	-91.8	0.10 (1)	8.25	H-E	-163 / 0	0.06 (1)		
E-F	-821 / 0	-91.8	-91.8	0.42 (1)	6.12	K-C	-1221 / 0	0.47 (1)		
K-B	-265 / 0	0.0	0.0	0.03 (1)	7.81	H-F	0 / 769	0.17 (1)		
G-F	-868 / 0	0.0	0.0	0.10 (1)	7.81					
K-J	0 / 993	-18.5	-18.5	0.32 (4)	10.00					
J-I	0 / 731	-18.5	-18.5	0.31 (4)	10.00					
I-H	0 / 731	-18.5	-18.5	0.31 (4)	10.00					
H-G	0 / 0	-18.5	-18.5	0.15 (4)	10.00					

DESIGN CRITERIA

SPECIFIED LOADS:
TOP CH. LL = 25.8 PSF
DL = 8.0 PSF
BOT CH. LL = 0.0 PSF
DL = 7.4 PSF
TOTAL LOAD = 39.0 PSF

SPACING = 24.0 IN. CC

LOADING IN FLAT SECTION BASED ON A SLOPE OF 8.00/12

THIS TRUSS IS DESIGNED FOR RESIDENTIAL OR SMALL BUILDING REQUIREMENTS OF PART 9, NBC 2010, NBC 2015

THIS DESIGN COMPLIES WITH:
- PART 9 OF CBC 2018, CBC 2012, ABC 2019
- PART 9 OF CBC 2012 (2019 AMENDMENT)
- CSA 086-09, CSA 086-14
- TPIC 2011, TPIC 2014

(55% OF 31.3 P.S.F. G.S.L. PLUS 8.4 P.S.F. RAIN LOAD) EQUALS 25.8 P.S.F. SPECIFIED ROOF LIVE LOAD

ALLOWABLE DEFL. (LL) = L/360 (0.55")
CALCULATED VERT. DEFL. (LL) = L/999 (0.02")
ALLOWABLE DEFL. (TL) = L/360 (0.55")
CALCULATED VERT. DEFL. (TL) = L/999 (0.13")

CSI: TC=0.42/1.00 (E-F:1), BC=0.32/1.00 (J-K:4), WB=0.47/1.00 (C-K:1), SI=0.19/1.00 (E-F:1)

DOL LUMBER=1.00 NAIL=1.00 LS BEND=1.10
COMP=1.10 SHEAR=1.10 TENS=1.10

COMPANION LIVE LOAD FACTOR = 1.00

TRUSS PLATE MANUFACTURER IS NOT RESPONSIBLE FOR QUALITY CONTROL IN THE TRUSS MANUFACTURING PLANT.

NAIL VALUES
PLATE GRIP(DRY) SHEAR SECTION (PSI) (PL) (PL)
MAX MIN MAX MIN MAX MIN
MT20 618 354 1567 788 1987 1656

PLATE PLACEMENT TOL. = 0.250 inches

PLATE ROTATION TOL. = 5.0 Deg.


JSI GRIP = 0.87 (C) (INPUT = 0.80)
JSI METAL = 0.41 (C) (INPUT = 1.00)



Structural component only
DWG# T-2007116

JOB NAME 408152	TRUSS NAME T49	QUANTITY 1	PLY 1	JOB DESC. GREEN PARK HOMES	DRWG NO.
Tamarack Roof Truss, Burlington					

Version 8.310 S Oct 29 2019 MTak Industries, Inc. Sat Apr 25 11:29:44 2020 Page 1
ID:7vF?aG0E03cRUj6X1jSkzIWK-PYUqS70SkCzMXbTYa4F2buckSGdH15VRChLdkzNCOL



Scale: 3/8"=1'

LUMBER

N. L. G. A. RULES

CHORDS	SIZE	DRY	LUMBER
A - D	2x4	DRY	No.2
D - F	2x4	DRY	No.2
K - B	2x4	DRY	No.2
G - F	2x4	DRY	No.2
K - I	2x4	DRY	No.2
I - G	2x4	DRY	No.2

ALL WEBS 2x3 DRY No.2
EXCEPT

DRY: SEASONED LUMBER.

PLATES (tablets in inches)

JT	TYPE	PLATES	W	LEN	Y	X
B	TMVW-1	MT20	4.0	5.0	2.00	3.00
C	TMVW-1	MT20	4.0	4.0	2.00	1.75
D	TTW-P	MT20	4.0	4.0		
E	TMVW-1	MT20	4.0	6.0		
F	TMV-P	MT20	3.0	4.0		
G	BMVW1-1	MT20	4.0	4.0		
H	BMVW-1	MT20	4.0	2.0		
I	BS-1	MT20	3.0	6.0		
J	BMVW-1	MT20	4.0	6.0		
K	BMV1-P	MT20	3.0	4.0		

DIMENSIONS, SUPPORTS AND LOADINGS SPECIFIED BY FABRICATOR TO BE VERIFIED BY BUILDING DESIGNER

BEARINGS

	FACTORED GROSS REACTION	MAXIMUM FACTORED GROSS REACTION	INPUT BRG	REQD BRG
JT	VERT	HORZ	DOWN	HORZ
K	1039	0	1039	0
G	914	0	914	0

A SUITABLE HANGER/MECHANICAL CONNECTION IS REQUIRED AT JOINT G. MINIMUM BEARING LENGTH AT JOINT G = 3'-8".

UNFACTORED REACTIONS

JT	1ST CASE	SNOW	LIVE	PERM. LIVE	WIND	DEAD	SOIL
K	732	494 / 0	0 / 0	0 / 0	0 / 0	238 / 0	0 / 0
G	646	424 / 0	0 / 0	0 / 0	0 / 0	222 / 0	0 / 0

BEARING MATERIAL TO BE SPF NO.2 OR BETTER AT JOINT(S) K

BRACING

TOP CHORD TO BE SHEATHED OR MAX. PURLIN SPACING = 5.66 FT.
MAX. UNBRACED BOTTOM CHORD LENGTH = 10.00 FT OR RIGID CEILING DIRECTLY APPLIED.

ALL PITCH BREAKS AND PERIMETER CORNER JOINTS MUST BE Laterally RESTRAINED.

LOADING

TOTAL LOAD CASES: (4)

CHORDS				WEBS			
MEMB.	MAX. FACTORED FORCE (LBS)	FACTORED VERT. LOAD (PLF)	MAX. FACTORED LCI (LC)	MEMB.	MAX. FACTORED FORCE (LBS)	MAX. FACTORED LCI (LC)	MAX. FACTORED LCI (LC)
FR-TO		FROM TO		FR-TO			
A-B	0 / 28	-91.8	-91.8 0.12 (1)	10.00	J-C	-114 / 23	0.02 (1)
B-C	-1135 / 0	-91.8	-91.8 0.26 (1)	5.66	C-H	-418 / 0	0.22 (1)
C-D	-798 / 0	-91.8	-91.8 0.25 (1)	6.25	H-D	0 / 407	0.09 (1)
D-E	-793 / 0	-91.8	-91.8 0.15 (1)	6.25	H-E	-39 / 37	0.02 (1)
E-F	0 / 17	-91.8	-91.8 0.19 (1)	10.00	B-J	0 / 1051	0.24 (1)
K-B	-998 / 0	0.0	0.0 0.10 (1)	7.81	E-G	-1026 / 0	0.44 (1)
G-F	-129 / 0	0.0	0.0 0.02 (1)	7.81			
K-J	0 / 0	-18.5	-18.5 0.10 (4)	10.00			
J-I	0 / 1034	-18.5	-18.5 0.29 (4)	10.00			
I-H	0 / 1034	-18.5	-18.5 0.29 (4)	10.00			
H-G	0 / 722	-18.5	-18.5 0.26 (4)	10.00			

TOTAL WEIGHT = 67 lb

(M/F)

DESIGN CRITERIA

SPECIFIED LOADS:

TOP CH.	LL	=	25.6	PSF
DL	=	6.0	PSF	
BOT CH.	LL	=	0.0	PSF
DL	=	7.4	PSF	
TOTAL LOAD	=	39.0	PSF	

SPACING = 24.0 IN. C/C

THIS TRUSS IS DESIGNED FOR RESIDENTIAL OR SMALL BUILDING REQUIREMENTS OF PART 9, NBCC 2010, NBCC 2015

THIS DESIGN COMPLIES WITH:

- PART 9 OF NBCC 2010, OBC 2012, ABC 2019
- PART 9 OF OBC 2012 (2019 AMENDMENT)
- CSA 085-09, CSA 085-14
- TPIC 2011, TPIC 2014

(55 % OF 31.3 P.S.F. G.S.L. PLUS 8.4 P.S.F. RAIN LOAD) EQUALS 25.6 P.S.F. SPECIFIED ROOF LIVE LOAD

ALLOWABLE DEFL. (LL) = $L/360$ (0.55")
CALCULATED VERT. DEFL. (LL) = $L/999$ (0.03")
ALLOWABLE DEFL. (TL) = $L/360$ (0.55")
CALCULATED VERT. DEFL. (TL) = $L/999$ (0.10")

CSI: $TC=0.28/1.00$ (B-C:1), $BC=0.29/1.00$ (H-J:4),
WB=0.44/1.00 (E-G:1), $SSI=0.19/1.00$ (B-C:1)

DOL LUMBER=1.00 NAIL=1.00 LS BEND=1.10
COMP=1.10 SHEAR=1.10 TENS=1.10

COMPANION LIVE LOAD FACTOR = 1.00

TRUSS PLATE MANUFACTURER IS NOT RESPONSIBLE FOR QUALITY CONTROL IN THE TRUSS MANUFACTURING PLANT.


NAIL VALUES

PLATE GRIP (DRY)	SHEAR	SECTION
(PSI)	(PLI)	(PLI)
MAX MIN	MAX MIN	MAX MIN
MT20	818 354	1667 788 1987 1656

PLATE PLACEMENT TOL. = 0.250 inches

PLATE ROTATION TOL. = 5.0 Deg.

JSI GRIP = 0.84 (G) (INPUT = 0.90)
JSI METAL = 0.36 (I) (INPUT = 1.00)




Structural component only
DWG# T-2007117

JOB NAME	TRUSS NAME	QUANTITY	PLY	JOB DESC.	DRWG NO.
408152	T50	1	1	GREEN PARK HOMES	

Tamarack Roof Truss, Burlington

Version 8.310 S Oct 29 2019 MTEK Industries, Inc. Sat Apr 25 11:29:45 2020 Page 1

ID:7vF7aG0E03cRUj6X1SrkziWYK-7kSCgT05VV5D8I288ontH859SRg_CmbYaRXRu9AZNCOk



LUMBER N. L. G. A. RULES CHORDS SIZE LUMBER DESCR. TOTAL WEIGHT = 43 lb

N. L. G. A. RULES	CHORDS	SIZE	LUMBER	DESCR.
A - C	2x4	DRY	No.2	SPF
C - D	2x4	DRY	No.2	SPF
D - F	2x4	DRY	No.2	SPF
J - B	2x4	DRY	No.2	SPF
G - E	2x4	DRY	No.2	SPF
J - G	2x4	DRY	No.2	SPF
ALL WEBS EXCEPT	2x3	DRY	No.2	SPF

DRY: SEASONED LUMBER.

PLATES (table is in inches)

JT TYPE	PLATES	W	LEN	Y	X
B	TMVW-p	MT20	4.0	4.0	1.50 2.00
C	TTWW-m	MT20	5.0	6.0	2.00 2.00
D	TTW-m	MT20	4.0	4.0	
E	TMVW-p	MT20	4.0	4.0	1.50 2.00
G	BMV1+p	MT20	3.0	4.0	
H	BMWWW-t	MT20	4.0	9.0	
I	BMWW-t	MT20	4.0	6.0	
J	BMV1+p	MT20	3.0	4.0	

DIMENSIONS, SUPPORTS AND LOADINGS SPECIFIED BY FABRICATOR TO BE VERIFIED BY BUILDING DESIGNER

FACTORED GROSS REACTION	MAXIMUM FACTORED GROSS REACTION	INPUT BRG	REQD BRG
VERT	HORZ	DOWN	HORZ
JT 888	0	888	0
J 888	0	888	0
G 888	0	888	0

UNFACTORED REACTIONS

1ST LCASE	MAX/MIN. COMPONENT REACTIONS	PERM. LIVE	WIND	DEAD	SOIL
JT COMBINED	SNOW	LIVE	WIND	DEAD	SOIL
J 811	416 / 0	0 / 0	0 / 0	195 / 0	0 / 0
G 810	415 / 0	0 / 0	0 / 0	194 / 0	0 / 0

BEARING MATERIAL TO BE SPF NO.2 OR BETTER AT JOINT(S) J, G

BRACING

TOP CHORD TO BE SHEATHED OR MAX. PURLIN SPACING = 6.09 FT. MAX. UNBRACED BOTTOM CHORD LENGTH = 10.00 FT. OR RIGID CEILING DIRECTLY APPLIED.

ALL PITCH BREAKS AND PERIMETER CORNER JOINTS MUST BE Laterally RESTRAINED.

LOADING

TOTAL LOAD CASES: (4)

CHORDS	MAX. FACTORED FORCE (LBS)	FACTORED VERT. LOAD (LBS)	FACTORED HORZ. LOAD (LBS)	MAX. UNBRACED LENGTH (FT)	WEBS	MAX. FACTORED FORCE (LBS)	FACTORED VERT. LOAD (LBS)	FACTORED HORZ. LOAD (LBS)
MEMB.	FR-TO	FROM TO	CSI (LC)	UNBRACED LENGTH (FT)	MEMB.	FR-TO	FROM TO	CSI (LC)
A-B	0 / 28	-91.8	-91.8 0.13 (1)	10.00	I-C	-121 / 32	0.02 (1)	
B-C	-837 / 0	-91.8	-91.8 0.15 (1)	6.25	C-H	0 / 2	0.00 (4)	
C-K	-743 / 0	-91.8	-91.8 0.50 (1)	6.09	H-D	-118 / 34	0.02 (1)	
K-L	-743 / 0	-91.8	-91.8 0.50 (1)	6.09	B-I	0 / 778	0.19 (1)	
L-D	-743 / 0	-91.8	-91.8 0.50 (1)	6.09	H-E	0 / 783	0.19 (1)	
D-E	-844 / 0	-91.8	-91.8 0.15 (1)	6.25				
E-F	0 / 28	-91.8	-91.8 0.13 (1)	10.00				
J-B	-848 / 0	0.0	0.0 0.09 (1)	7.81				
G-E	-844 / 0	0.0	0.0 0.09 (1)	7.81				
J-M	0 / 0	-18.5	-18.5 0.08 (4)	10.00				
M-I	0 / 0	-18.5	-18.5 0.08 (4)	10.00				
I-N	0 / 742	-18.5	-18.5 0.18 (1)	10.00				
N-O	0 / 742	-18.5	-18.5 0.18 (1)	10.00				
O-H	0 / 742	-18.5	-18.5 0.18 (1)	10.00				
H-P	0 / 0	-18.5	-18.5 0.08 (4)	10.00				
P-G	0 / 0	-18.5	-18.5 0.08 (4)	10.00				

FACTORED CONCENTRATED LOADS (LBS)

JT	LOC.	LC1	MAX.	MAX+	FACE	DIR.	TYPE	HEEL	CONN.
C	2-10-8	-119	-119	---	FRONT	VERT	TOTAL	---	C1
D	8-0-8	-119	-119	---	FRONT	VERT	TOTAL	---	C1
H	7-11-12	-5	-5	---	FRONT	VERT	TOTAL	---	C1
I	2-11-4	-5	-5	---	FRONT	VERT	TOTAL	---	C1
K	3-11-12	-7	-7	---	FRONT	VERT	TOTAL	---	C1
L	5-11-12	-7	-7	---	FRONT	VERT	TOTAL	---	C1
M	2-0-12	-5	-5	---	FRONT	VERT	TOTAL	---	C1
N	3-11-12	-5	-5	---	FRONT	VERT	TOTAL	---	C1
O	5-11-12	-5	-5	---	FRONT	VERT	TOTAL	---	C1
P	8-10-4	-5	-5	---	FRONT	VERT	TOTAL	---	C1

CONNECTION REQUIREMENTS

1) C1: A SUITABLE HANGER/MECHANICAL CONNECTION IS REQUIRED.

DESIGN CRITERIA

SPECIFIED LOADS:
TOP CH. LL = 25.8 PSF
DL = 6.0 PSF
BOT CH. LL = 0.0 PSF
DL = 7.4 PSF
TOTAL LOAD = 39.0 PSF

SPACING = 24.0 IN/C

LOADING IN FLAT SECTION BASED ON A SLOPE OF 6.00/12

THIS TRUSS IS DESIGNED FOR RESIDENTIAL OR SMALL BUILDING REQUIREMENTS OF PART 9, NBCC 2010, NBCC 2015

THIS DESIGN COMPLIES WITH:

- PART 9 OF BCBC 2018, OBC 2012, ABC 2019
- PART 9 OF OBC 2012 (2019 AMENDMENT)
- CSA 086-09, CSA 086-14
- TPIC 2011, TPIC 2014

(55% OF 31.3 P.S.F. G.S.L. PLUS 8.4 P.S.F. RAIN LOAD) EQUALS 25.8 P.S.F. SPECIFIED ROOF LIVE LOAD

ALLOWABLE DEFL.(LL) = L/360 (0.36")
CALCULATED VERT. DEFL.(LL) = L/999 (0.01")
ALLOWABLE DEFL.(TL) = L/360 (0.36")
CALCULATED VERT. DEFL.(TL) = L/999 (0.03")

CSI: TC=0.50/1.00 (C-D:1), BC=0.18/1.00 (H-I:1),
WB=0.19/1.00 (E-H:1), SSI=0.21/1.00 (C-D:1)

DOL LUMBER=1.00 NAIL=1.00 LS BEND=1.00
COMP=1.00 SHEAR=1.00 TENS=1.00

COMPANION LIVE LOAD FACTOR = 1.00

TRUSS PLATE MANUFACTURER IS NOT RESPONSIBLE FOR QUALITY CONTROL IN THE TRUSS MANUFACTURING PLANT.

NAIL VALUES


PLATE GRIP(DRY)	SHEAR	SECTION
(PSI)	(PL)	(PL)
MAX MIN	MAX MIN	MAX MIN
MT20	618 354	1657 788

PLATE PLACEMENT TOL. = 0.250 inches


PLATE ROTATION TOL. = 5.0 Deg.

JSI GRIP = 0.77 (S) (INPUT = 0.90)

JSI METAL = 0.28 (E) (INPUT = 1.00)



Structural component only
DWG# T-2007118



LUMBER					
N. L. G. A. RULES					
CHORDS		SIZE	LUMBER		DESC
A - C	2x4	DRY	No.2		SPF
C - D	2x4	DRY	No.2		SPF
D - F	2x4	DRY	No.2		SPF
J - B	2x4	DRY	No.2		SPF
G - E	2x4	DRY	No.2		SPF
J - G	2x4	DRY	No.2		SPF
ALL WEBS EXCEPT		2x3	DRY	No.2	SPF

PLATES (table is in inches)

JT TYPE	PLATES	W	LEN	Y	X
B	TMVW-1	MT20	4.0	4.0	2.00 1.25
C	TTWW-m	MT20	5.0	6.0	2.25 2.25
D	TTW-m	MT20	4.0	4.0	
E	TMVW-1	MT20	4.0	4.0	2.00 1.25
G	BMV1+p	MT20	3.0	4.0	
H	BMVWW-1	MT20	4.0	6.0	2.00 1.50
I	BMVWW-1	MT20	4.0	4.0	
J	BMV1+p	MT20	3.0	4.0	

DIMENSIONS, SUPPORTS AND LOADINGS SPECIFIED BY FABRICATOR TO BE VERIFIED BY BUILDING DESIGNER

BEARINGS

	FACTORED GROSS REACTION	MAXIMUM FACTORED GROSS REACTION	INPUT BRG	REQD BRG
JT	VERT 726	DOWN 726	0	0
G	HORZ 0	HORZ 0	0	0
	MECHANICAL 5-8	MECHANICAL 5-8		

A SUITABLE HANGER/MECHANICAL CONNECTION IS REQUIRED AT JOINT J. MINIMUM BEARING LENGTH AT JOINT J = 1-8.

UNFACTORED REACTIONS

JT	1ST LOASE	SNOW	LIVE	PERM.LIVE	WIND	DEAD	SOIL
J	511	349 / 0	0 / 0	0 / 0	0 / 0	163 / 0	0 / 0
G	511	349 / 0	0 / 0	0 / 0	0 / 0	163 / 0	0 / 0

BEARING MATERIAL TO BE SPF NO.2 OR BETTER AT JOINT(S) G

BRACING

TOP CHORD TO BE SHEATHED OR MAX. PURLIN SPACING = 6.25 FT.

MAX. UNBRACED BOTTOM CHORD LENGTH = 10.00 FT OR RIGID CEILING DIRECTLY APPLIED.

ALL PITCH BREAKS AND PERIMETER CORNER JOINTS MUST BE Laterally RESTRAINED.

LOADING

TOTAL LOAD CASES: (4)

MEMB.	CHORDS			WEBS		
	MAX. FACTORED FORCE (LBS)	FACTORED VERT. LOAD (PLF)	MAX. FACTORED CSI (LC)	MAX. FACTORED FORCE (LBS)	MAX. FACTORED CSI (LC)	MAX. FACTORED CSI (LC)
FR-TO		FROM TO				
A-B	0 / 28	-91.8	-91.8 0.12 (1)	10.00	I-C	-78 / 18
B-C	-435 / 0	-91.8	-91.8 0.28 (1)	6.25	C-H	-4 / 0
C-D	-386 / 0	-91.8	-91.8 0.02 (1)	6.25	H-D	-82 / 19
D-E	-434 / 0	-91.8	-91.8 0.28 (1)	6.25	B-I	0 / 415
E-F	0 / 28	-91.8	-91.8 0.12 (1)	10.00	H-E	0 / 414
J-B	-688 / 0	0.0	0.0 0.08 (1)	7.81		
G-E	-688 / 0	0.0	0.0 0.08 (1)	7.81		
J-I	0 / 0	-18.5	-18.5 0.10 (4)	10.00		
I-H	0 / 387	-18.5	-18.5 0.14 (4)	10.00		
H-G	0 / 0	-18.5	-18.5 0.10 (4)	10.00		

DESIGN CRITERIA

SPECIFIED LOADS:

TOP CH. LL = 25.8 PSF

DL = 6.0 PSF

BOT CH. LL = 0.0 PSF

DL = 7.4 PSF

TOTAL LOAD = 39.0 PSF

SPACING = 24.0 IN. C/C

LOADING IN FLAT SECTION BASED ON A SLOPE OF 6.00/12

THIS TRUSS IS DESIGNED FOR RESIDENTIAL OR SMALL BUILDING REQUIREMENTS OF PART 9, NBCC 2010, NBCC 2015

THIS DESIGN COMPLIES WITH:

- PART 9 OF BCBC 2018, OBC 2012, ABC 2019
- PART 9 OF OBC 2012 (2019 AMENDMENT)
- CSA 088-09, CSA 088-14
- TPIC 2011, TPIC 2014

(55% OF 31.3 P.S.F. G.S.L. PLUS 8.4 P.S.F. RAIN LOAD) EQUALS 25.8 P.S.F. SPECIFIED ROOF LIVE LOAD

ALLOWABLE DEFL.(LL)= L/360 (0.36")

CALCULATED VERT. DEFL.(LL) = L/999 (0.01")

ALLOWABLE DEFL.(TL)= L/360 (0.36")

CALCULATED VERT. DEFL.(TL) = L/999 (0.02")

CSI: TC=0.28/1.00 (B-C:1), BC=0.14/1.00 (H-I:4), WB=0.09/1.00 (B-I:1), SSI=0.18/1.00 (B-C:1)

DOL LUMBER=1.00 NAIL=1.00 LS BEND=1.10

COMP=1.10 SHEAR=1.10 TENS=1.10

COMPANION LIVE LOAD FACTOR = 1.00

TRUSS PLATE MANUFACTURER IS NOT RESPONSIBLE FOR QUALITY CONTROL IN THE TRUSS MANUFACTURING PLANT.

NAIL VALUES

PLATE GRIP(DRY) SHEAR SECTION (PSI) (PLI) (PLI)

MAX MIN MAX MIN MAX MIN


MT20 618 354 1667 788 1987 1656

PLATE PLACEMENT TOL. = 0.250 inches

PLATE ROTATION TOL. = 5.0 Deg.

JSI GRIP = 0.66 (B) (INPUT = 0.90)

JSI METAL = 0.22 (B) (INPUT = 1.00)




Structural component only
DWG# T-2007119

JOB NAME	TRUSS NAME	QUANTITY	PLY	JOB DESC.	DRWG NO.
408152	T52	1	1	GREEN PARK HOMES	

Tamarack Roof Truss, Burlington

Version 8.310 S Oct 29 2019 Mitek Industries, Inc. Sat Apr 25 11:29:47 2020 Page 1
ID:7vF?ag0E03cRUj6X1jSrkzWYK-47az592L17LwO3BxFDpIDWem8TgSEVLtrw7E3zNCO



Scale = 1/16" = 1'-0"

LUMBER

N. L. G. A. RULES

CHORDS	SIZE	DRY	LUMBER
F - A	2x4	DRY	No.2
A - C	2x4	DRY	No.2
D - C	2x4	DRY	No.2
F - D	2x4	DRY	No.2

ALL WEBS 2x3 DRY No.2
DRY: SEASONED LUMBER.

DESCR.

SPF
SPF
SPF
SPF

PLATES (table is in inches)

JT TYPE	PLATES	W	LEN	Y	X
A TMWV-I	MT20	4.0	6.0		
B TMWV-w	MT20	2.0	4.0		
C TMWV-I	MT20	4.0	6.0		
D BMV1-p	MT20	3.0	4.0		
E BMWVW-I	MT20	4.0	9.0		
F BMV1-p	MT20	3.0	4.0		

DIMENSIONS, SUPPORTS AND LOADINGS SPECIFIED BY FABRICATOR TO BE VERIFIED BY

BUILDING DESIGNER

PROVIDE ADEQUATE DRAINAGE TO PREVENT PONDING

BEARINGS

	FACTORED GROSS REACTION	MAXIMUM FACTORED GROSS REACTION	INPUT BRG	REQD BRG
JT	VERT	HORZ	DOWN	HORZ
F	620	0	620	0
D	620	0	620	0

UNFACTORED REACTIONS

JT	1ST LCASE	MAX/MIN COMPONENT REACTIONS	PERM LIVE	WIND	DEAD	SOIL
F	COMBINED	SNOW	LIVE			
F	448	239 / 0	0 / 0	0 / 0	209 / 0	0 / 0
D	448	239 / 0	0 / 0	0 / 0	209 / 0	0 / 0

BEARING MATERIAL TO BE SPF NO.2 OR BETTER AT JOINT(S) F, D

BRACING

TOP CHORD TO BE SHEATHED OR MAX. PURLINE SPACING = 5.52 FT.
MAX. UNBRACED BOTTOM CHORD LENGTH = 10.00 FT OR RIGID CEILING DIRECTLY APPLIED.

ALL PITCH BREAKS AND PERIMETER CORNER JOINTS MUST BE Laterally RESTRAINED.

LOADING

TOTAL LOAD CASES: (4)

CHORDS	MEMB.	MAX. FACTORED FORCE (LBS)	FACTORED VERT. LOAD (PLF)	MAX. UNBRACED LENGTH	WEBS	MEMB.	MAX. FACTORED FORCE (LBS)	MAX. UNBRACED LENGTH
FR-TO					FR-TO			
F-A	-583 / 0	0.0	0.0	0.11 (1)	A-E	0 / 792	0.24 (1)	7.81
A-B	-695 / 0	-114.3	-114.3	0.55 (1)	E-B	-695 / 0	0.15 (1)	5.52
B-C	-895 / 0	-114.3	-114.3	0.55 (1)	E-C	0 / 792	0.24 (1)	5.52
D-C	-583 / 0	0.0	0.0	0.11 (1)				7.81
F-E	0 / 0	-18.5	-18.5	0.13 (4)				10.00
E-D	0 / 0	-18.5	-18.5	0.13 (4)				10.00

TOTAL WEIGHT = 36 lb

(MFR)

DESIGN CRITERIA

SPECIFIED LOADS:

TOP CH.	LL	= 25.6	PSF
	DL	= 15.0	PSF
BOT CH.	LL	= 0.0	PSF
	DL	= 7.4	PSF
TOTAL LOAD		= 48.0	PSF

SPACING = 24.0 IN/C

LOADING IN FLAT SECTION BASED ON A SLOPE OF 0.00/12

THIS TRUSS IS DESIGNED FOR RESIDENTIAL OR SMALL BUILDING REQUIREMENTS OF PART 9, NBC 2010, NBC 2015

THIS DESIGN COMPLIES WITH:

- PART 9 OF CBC 2018, CBC 2012, ABC 2019
- PART 9 OF CBC 2012 (2019 AMENDMENT)
- CSA 086-09, CSA 088-14
- TPIC 2011, TPIC 2014

(55 % OF 31.3 P.S.F. G.S.L. PLUS 8.4 P.S.F. RAIN LOAD) EQUALS 25.6 P.S.F. SPECIFIED ROOF LIVE LOAD

ALLOWABLE DEFL.(LL) = L/360 (0.31")
CALCULATED VERT. DEFL.(LL) = L/999 (0.01")
ALLOWABLE DEFL.(TL) = L/360 (0.31")
CALCULATED VERT. DEFL.(TL) = L/999 (0.03")

CSI: TC=0.55/1.00 (B-C:1), BC=0.13/1.00 (E-F:4), WB=0.24/1.00 (A-E:1), SS=0.34/1.00 (A-B:1)

DOL LUMBER=1.00 NAIL=1.00 LS BEND=1.10
COMP=1.10 SHEAR=1.10 TENS= 1.10

COMPANION LIVE LOAD FACTOR = 1.00
FLAT ROOF FACTOR = 0.75

TRUSS PLATE MANUFACTURER IS NOT RESPONSIBLE FOR QUALITY CONTROL IN THE TRUSS MANUFACTURING PLANT.

NAIL VALUES

PLATE GRIP(DRY)	SHEAR (PSI)	SECTION (PLI)
	MAX MIN	MAX MIN
MT20	618 354	1667 788


PLATE PLACEMENT TOL. = 0.250 inches

PLATE ROTATION TOL. = 5.0 Deg.

JSI GRIP= 0.61 (A) (INPUT = 0.90)
JSI METAL= 0.24 (A) (INPUT = 1.00)



Structural component only
DWG# T-2007120



Scale = 1:16.8

LUMBER					
N. L. G. A. RULES					
CHORDS	SIZE		LUMBER		DESCR.
L - A	2x4	DRY	No.2		SPF
A - F	2x4	DRY	No.2		SPF
G - I	2x4	DRY	No.2		SPF
L - G	2x4	DRY	No.2		SPF
ALL WEBS		2x3	DRY	No.2	SPF
ALL GABLE WEBS		2x3	DRY	No.2	SPF
DRY: SEASONED LUMBER.					
GABLE STUDS SPACED AT 2'-0" OC.					

PLATES (table is in inches)

JT	TYPE	PLATES	W	LEN	Y	X
A	TMV+p	MT20	3.0	4.0		
B, C, D, E						
F	TMV+w	MT20	2.0	4.0		
G	BMV1+p	MT20	3.0	4.0		
H, I, J, K						
L	BMV1+w	MT20	2.0	4.0		
M	BMV1+p	MT20	3.0	4.0		

DIMENSIONS, SUPPORTS AND LOADINGS SPECIFIED BY FABRICATOR TO BE VERIFIED BY BUILDING DESIGNER

PROVIDE ADEQUATE DRAINAGE TO PREVENT PONDING

BEARINGS

THIS TRUSS DESIGNED FOR CONTINUOUS BEARINGS.

THIS TRUSS REQUIRES RIGID SHEATHING ON EXPOSED FACE.

BEARING MATERIAL TO BE SPF NO.2 OR BETTER AT JOINT(S)

BRACING

TOP CHORD TO BE SHEATHED OR MAX. PURLIN SPACING = 10.00 FT.
MAX. UNBRACED BOTTOM CHORD LENGTH = 10.00 FT. OR RIGID CEILING DIRECTLY APPLIED.

ALL PITCH BREAKS AND PERIMETER CORNER JOINTS MUST BE Laterally RESTRAINED.

LOADING

TOTAL LOAD CASES: (4)

CHORDS				WEBS				
MEMB.	MAX. FACTORED FORCE (LBS)	FACTORED VERT. LOAD (PLF)	MAX. UNBRACED LENGTH FR-TO	MEMB.	MAX. FACTORED FORCE (LBS)	MAX. UNBRACED LENGTH FR-TO		
L-A	-101 / 0	0.0	0.03 (1)	7.81	K-B	-245 / 0	0.06 (1)	
A-B	-8 / 0	-114.3	-114.3	0.08 (1)	10.00	J-C	-224 / 0	0.05 (1)
B-C	-8 / 0	-114.3	-114.3	0.08 (1)	10.00	I-D	-237 / 0	0.05 (1)
C-D	-8 / 0	-114.3	-114.3	0.07 (1)	10.00	H-E	-198 / 0	0.04 (1)
D-E	-8 / 0	-114.3	-114.3	0.07 (1)	10.00			
E-F	-8 / 0	-114.3	-114.3	0.05 (1)	10.00			
F-G	-84 / 0	0.0	0.0	0.02 (1)	7.81			
L-K	0 / 8	-18.5	-18.5	0.02 (4)	10.00			
K-J	0 / 8	-18.5	-18.5	0.02 (4)	10.00			
J-I	0 / 8	-18.5	-18.5	0.02 (4)	10.00			
I-H	0 / 8	-18.5	-18.5	0.02 (4)	10.00			
H-G	0 / 8	-18.5	-18.5	0.02 (1)	10.00			

DESIGN CRITERIA

SPECIFIED LOADS:

TOP CH. LL = 25.6 PSF
DL = 15.0 PSF
BOT CH. LL = 0.0 PSF
DL = 7.4 PSF
TOTAL LOAD = 48.0 PSF

SPACING = 24.0 IN. C/C

LOADING IN FLAT SECTION BASED ON A SLOPE OF 0.00/12

THIS TRUSS IS DESIGNED FOR RESIDENTIAL OR SMALL BUILDING REQUIREMENTS OF PART 9, NBCC 2010, NBCC 2015

THIS DESIGN COMPLIES WITH:

- PART 9 OF BCBC 2018, CBC 2012, ABC 2019
- PART 9 OF OBC 2012 (2019 AMENDMENT)
- CSA 086-09, CSA 088-14
- TPIC 2011, TPIC 2014

(55 % OF 31.3 P.S.F. G.S.L. PLUS 8.4 P.S.F. RAIN LOAD) EQUALS 25.6 P.S.F. SPECIFIED ROOF LIVE LOAD

CSI: TC=0.08/1.00 (A-B:1), BC=0.02/1.00 (K-L:4), WS=0.06/1.00 (B-K:1), SS=0.13/1.00 (A-B:1)

DOL LUMBER=1.00 NAIL=1.00 LS BEND=1.10
COMP=1.10 SHEAR=1.10 TENS=1.70

COMPANION LIVE LOAD FACTOR = 1.00
FLAT ROOF FACTOR = 0.75

TRUSS PLATE MANUFACTURER IS NOT RESPONSIBLE FOR QUALITY CONTROL IN THE TRUSS MANUFACTURING PLANT.

NAIL VALUES

PLATE	GRIP(DRY)	SHEAR	SECTION
(PSI)	(PLI)	(PLI)	
MT20	618	354	1867 788 1987 1656

PLATE PLACEMENT TOL. = 0.250 inches

PLATE ROTATION TOL. = 5.0 Deg.

JSI GRIP= 0.17 (K) (INPUT = 0.90)
JSI METAL= 0.07 (K) (INPUT = 1.00)



Structural component only
DWG# T-2007104


JOB NAME 408152	TRUSS NAME T53	QUANTITY 1	PLY 1	JOB DESC. GREEN PARK HOMES	DRWG NO.
--------------------	-------------------	---------------	----------	-------------------------------	----------

Tamarack Roof Truss, Burlington

Version 8.310 S Oct 29 2019 MITek Industries, Inc. Sat Apr 25 11:29:48 2020 Page 1

ID:7VF?aG0E03cRU6X1ISrkzIWK-YJ7LIV3zoQTn?DmjpWk_mkn0tt?2zwn17VgZmVzNCOH

Scale = 1:22.0



LUMBER

N. L. G. A. RULES

CHORDS	SIZE	LUMBER	DESCR
F - A	2x4	DRY	No.2
A - C	2x6	DRY	No.2
D - C	2x4	DRY	No.2
F - D	2x6	DRY	No.2
ALL WEBS	2x3	DRY	No.2
DRY: SEASONED LUMBER.			

PLATES (table is in inches)

JT	TYPE	PLATES	W	LEN	Y	X
A	TMVW-t	MT20	5.0	6.0		
B	TMVW-w	MT20	3.0	6.0		
C	TMVW-t	MT20	5.0	6.0		
D	BMV1-p	MT20	3.0	6.0		
E	BMVWW-t	MT20	5.0	6.0		
F	BMV1-p	MT20	3.0	6.0		

DIMENSIONS, SUPPORTS AND LOADINGS SPECIFIED BY FABRICATOR TO BE VERIFIED BY BUILDING DESIGNER

PROVIDE ADEQUATE DRAINAGE TO PREVENT PONDING.

BEARINGS

JT	VERT	HORZ	DOWN	HORZ	UPLIFT	IN-SX	BRG	REC'D
F	988	0	988	0	0	MECHANICAL		
D	1012	0	1012	0	0	MECHANICAL		

A SUITABLE HANGER/MECHANICAL CONNECTION IS REQUIRED AT JOINT F, D. MINIMUM BEARING LENGTH AT JOINT F = 3-8, JOINT D = 3-8.

UNFACTORED REACTIONS

JT	1ST CASE	MAX. MIN.	SNOW	LIVE	PERM. LIVE	WIND	DEAD	SOIL
F	705	427 / 0	0 / 0	0 / 0	0 / 0	0 / 0	279 / 0	0 / 0
D	722	439 / 0	0 / 0	0 / 0	0 / 0	0 / 0	283 / 0	0 / 0

BRACING

TOP CHORD TO BE SHEATHED OR MAX. PURLIN SPACING = 6.25 FT.
MAX. UNBRACED BOTTOM CHORD LENGTH = 10.00 FT. OR RIGID CEILING DIRECTLY APPLIED.

ALL PITCH BREAKS AND PERIMETER CORNER JOINTS MUST BE LATERALLY RESTRAINED.

LOADING

TOTAL LOAD CASES: (4)

CHORDS	MAX. FACTORED	FACTORED	VERT. LOAD	LC1	MAX	MAX.	MEMB.	MAX. FACTORED
MEMB.	FORCE (LBS)	VERT. (PLF)	CS1 (LC)	UNBRAC	LENGTH	FR-TO	FORCE (LBS)	MAX
F-A	-846 / 0	0.0	0.0	0.23 (1)	7.45	A-E	0 / 1072	0.35 (1)
A-B	-889 / 0	-114.3	-114.3	0.24 (1)	6.25	E-B	-632 / 0	0.18 (1)
B-C	-889 / 0	-114.3	-114.3	0.24 (1)	6.25	E-C	0 / 1072	0.35 (1)
D-C	-846 / 0	0.0	0.0	0.23 (1)	7.45			
F-G	0 / 0	-18.5	-18.5	0.24 (1)	10.00			
G-H	0 / 0	-18.5	-18.5	0.24 (1)	10.00			
H-E	0 / 0	-18.5	-18.5	0.24 (1)	10.00			
E-I	0 / 0	-18.5	-18.5	0.24 (1)	10.00			
I-J	0 / 0	-18.5	-18.5	0.24 (1)	10.00			
J-D	0 / 0	-18.5	-18.5	0.24 (1)	10.00			

FACTORED CONCENTRATED LOADS (LBS)

JT	LOC.	LC1	MAX-	MAX+	FACE	DIR.	TYPE	HEEL	CONN.
G	1-8-12	-180	-180	---	FRONT	VERT	TOTAL	---	C1
H	3-8-12	-180	-180	---	FRONT	VERT	TOTAL	---	C1
I	5-8-12	-180	-180	---	FRONT	VERT	TOTAL	---	C1
J	7-8-12	-180	-180	---	FRONT	VERT	TOTAL	---	C1

CONNECTION REQUIREMENTS

1) C1: A SUITABLE HANGER/MECHANICAL CONNECTION IS REQUIRED.

TOTAL WEIGHT = 51 lb

(M/R)

DESIGN CRITERIA

SPECIFIED LOADS:

TOP CH.	LL	= 25.6	PSF
	DL	= 15.0	PSF
BOT CH.	LL	= 0.0	PSF
	DL	= 7.4	PSF
TOTAL LOAD	= 48.0	PSF	

SPACING = 24.0 IN/C

LOADING IN FLAT SECTION BASED ON A SLOPE OF 0.00/12

THIS TRUSS IS DESIGNED FOR RESIDENTIAL OR SMALL BUILDING REQUIREMENTS OF PART 9, NBC 2010, NBC 2015

THIS DESIGN COMPLIES WITH:

- PART 9 OF CBC 2018, CBC 2012, ABC 2019
- PART 9 OF CBC 2012 (2019 AMENDMENT)
- CSA 088-09, CSA 088-14
- TPIQ 2011, TPIQ 2014

(55 % OF 31.3 P.S.F. G.S.L. PLUS 8.4 P.S.F. RAIN LOAD) EQUALS 25.6 P.S.F. SPECIFIED ROOF LIVE LOAD

ALLOWABLE DEFL. (LL) = 1/360 (0.31")
CALCULATED VERT. DEFL. (LL) = 1/999 (0.02")
ALLOWABLE DEFL. (TL) = 1/360 (0.31")
CALCULATED VERT. DEFL. (TL) = 1/999 (0.04")

CSI: TC=0.24/1.00 (B-C:1), BC=0.24/1.00 (D-E:1), WB=0.35/1.00 (A-E:1), SS=0.29/1.00 (E-F:1)

DOL LUMBER=1.00 NAIL=1.00 LS BEND=1.00
COMP=1.00 SHEAR=1.00 TENS=1.00

COMPANION LIVE LOAD FACTOR = 1.00
FLAT ROOF FACTOR = 0.75

TRUSS PLATE MANUFACTURER IS NOT RESPONSIBLE FOR QUALITY CONTROL IN THE TRUSS MANUFACTURING PLANT.

NAIL VALUES

PLATE GRIP (DRY)	SHEAR	SECTION
(PSI)	(PLI)	(PLI)
MAX MIN	MAX MIN	MAX MIN
MT20	618 354	1667 788 1987 1658


PLATE PLACEMENT TOL. = 0.250 inches

PLATE ROTATION TOL. = 5.0 Deg.

JSI GRIP = 0.76 (E) (INPUT = 0.90)
JSI METAL = 0.32 (E) (INPUT = 1.00)



Structural component only
DWG# T-2007121



LUMBER					
N. L. G. A. RULES					
CHORDS		SIZE	LUMBER		DESCR.
A - C		2x4	DRY	No.2	SPF
D - C		2x4	DRY	No.2	SPF
A - D		2x6	DRY	No.2	SPF
ALL WEBS 2x3			DRY	No.2	SPF
DRY: SEASONED LUMBER.					

DESIGN CONSISTS OF 2 TRUSSES BUILT SEPARATELY THEN FASTENED TOGETHER AS FOLLOWS:

CHORDS #ROWS	SURFACE SPACING (IN)	LOAD(PLF)
TOP CHORDS : (0.122"x3") SPIRAL NAILS		
A - C 1	12	TOP
C - D 1	12	TOP
BOTTOM CHORDS : (0.122"x3") SPIRAL NAILS		
A - D 2	12	SIDE(0.0)
WEBS : (0.122"x3") SPIRAL NAILS		
2x3 1	6	

NAILS TO BE DRIVEN FROM ONE SIDE ONLY.

GIRDER NAILING ASSUMES NAILED HANGERS ARE FASTENED WITH MIN. 3-0 INCH NAILS.

TOP - COMPONENTS ARE LOADED FROM THE TOP AND MUST BE PLACED ON TOP EDGE OF ALL PLIES FOR THE LOAD TO BE TRANSFERRED TO EACH PLY.

SIDE - PLF SHOWN IS THE EQUIVALENT UDL APPLIED TO ONE SIDE THAT THE CORRESPONDING NAILING PATTERN SHALL BE CAPABLE OF TRANSFERRING. REMAINING PLF MUST BE APPLIED ON THE OPPOSITE SIDE OR ON THE TOP.

PLATES (table in inches)

JT TYPE	PLATES	W	LEN	Y	X
A	TBMH1+m	MT20	5.0	8.0	3.50
B	TMWVW-t	MT20	5.0	8.0	2.50 2.25
C	TMV-p	MT20	3.0	4.0	
D	BMVWV-1	MT20	5.0	8.0	2.50 2.75
E	BMV-w	MT20	3.0	10.0	

DIMENSIONS, SUPPORTS AND LOADINGS SPECIFIED BY FABRICATOR TO BE VERIFIED BY BUILDING DESIGNER

BEARINGS

JT	GROSS REACTION	FACTORED	MAXIMUM FACTORED	INPUT	RECORD	HEEL
	VERT	HORZ	DOWN	UP	BRG	WEDGE
A	3467	0	3467	0	5-8	2x4 L
D	2454	0	2454	0	5-8	

A SUITABLE HANGER/MECHANICAL CONNECTION IS REQUIRED AT JOINT D. MINIMUM BEARING LENGTH AT JOINT D = 4-0.

UNFACTORED REACTIONS

JT	COMBINED	SNOW	LIVE	PERM.LIVE	WIND	DEAD	SOIL
A	2449	1822/0	0/0	0/0	0/0	828/0	0/0
D	1735	1144/0	0/0	0/0	0/0	591/0	0/0

BEARING MATERIAL TO BE SPF NO.2 OR BETTER AT JOINT(S) A

BRACING
TOP CHORD TO BE SHEATHED OR MAX. PURLIN SPACING = 4.16 FT.
MAX. UNBRACED BOTTOM CHORD LENGTH = 10.00 FT OR RIGID CEILING DIRECTLY APPLIED.

ALL PITCH BREAKS AND PERIMETER CORNER JOINTS MUST BE Laterally RESTRAINED.

LOADING
TOTAL LOAD CASES: (4)

MEMB.	CHORDS			WEBS		
	MAX. FACTORED FORCE (LBS)	FACTORED VERT. LOAD (PLF)	MAX. CSI (LC)	MAX. FACTORED FORCE (LBS)	FACTORED VERT. LOAD (PLF)	MAX. CSI (LC)
FR-TO		FROM TO		FR-TO		
A-G	-4978/0	-91.8 -91.8 0.19 (1)	4.16	E-B	0/3365	0.42 (1)
G-B	-3863/0	-91.8 -91.8 0.17 (1)	4.66	B-D	-4035/0	0.53 (1)
B-C	-13/0	-91.8 -91.8 0.07 (1)	6.25	F-G	0/1740	0.00 (1)
D-C	-129/0	0.0 0.0 0.02 (1)	7.81			
A-F	0/3490	-18.5 -18.5 0.25 (1)	10.00			
F-H	0/3490	-18.5 -18.5 0.88 (1)	10.00			
H-I	0/3490	-18.5 -18.5 0.68 (1)	10.00			
I-J	0/3490	-18.5 -18.5 0.68 (1)	10.00			
J-E	0/3490	-18.5 -18.5 0.88 (1)	10.00			
E-K	0/3490	-18.5 -18.5 0.49 (1)	10.00			
K-D	0/3490	-18.5 -18.5 0.49 (1)	10.00			

FACTORED CONCENTRATED LOADS (LBS)

JT	LOC.	LC1	MAX.	MAX.	FACE	DIR.	TYPE	HEEL	CONN.
H	1-4-0	-1378	-1378	---	BACK	VERT	TOTAL	---	C1
I	2-0-0	-1000	-1000	---	FRONT	VERT	TOTAL	---	C1
J	3-0-4	-994	-994	---	FRONT	VERT	TOTAL	---	C1
J	3-3-4	-896	-896	---	BACK	VERT	TOTAL	---	C1
K	5-3-4	-896	-896	---	BACK	VERT	TOTAL	---	C1

CONNECTION REQUIREMENTS

- 1) C1: A SUITABLE HANGER/MECHANICAL CONNECTION IS REQUIRED.

TOTAL WEIGHT = 2 X 30 = 60 lb

DESIGN CRITERIA
*** SPECIAL LOADS ANALYSIS ***
GEOMETRY AND/OR BASIC LOADS CHANGED BY USER.
LOADS WERE DERIVED FROM USER INPUT
NO FURTHER MODIFICATIONS WERE MADE

SPECIFIED LOADS:
TOP CH. LL = 25.8 PSF
DL = 6.0 PSF
BOT CH. LL = 0.0 PSF
DL = 7.4 PSF
TOTAL LOAD = 39.0 PSF

SPACING = 24.0 IN/C

*** NON STANDARD GIRDER ***
ADDTL. USER-DEFINED LOADS APPLIED TO ALL LOAD CASES.

THIS TRUSS IS DESIGNED FOR RESIDENTIAL OR SMALL BUILDING REQUIREMENTS OF PART 9, NBCC 2010, NBCC 2015

THIS DESIGN COMPLIES WITH:
- PART 9 OF CBC 2018, OBC 2012, ABC 2019
- PART 9 OF OBC 2012 (2019 AMENDMENT)
- CSA 088-09, CSA 088-14
- TPIC 2011, THIC 2014

(55 % OF 31.3 P.S.F. G.S.L. PLUS 8.4 P.S.F. RAIN LOAD) EQUALS 25.6 P.S.F. SPECIFIED ROOF LIVE LOAD

ALLOWABLE DEFL.(LL) = L/360 (0.23")
CALCULATED VERT. DEFL.(LL) = L/999 (0.03")
ALLOWABLE DEFL.(TL) = L/360 (0.23")
CALCULATED VERT. DEFL.(TL) = L/999 (0.05")

CSI: TC=0.19/1.00 (A-G:1), BC=0.88/1.00 (E-F:1), WB=0.53/1.00 (B-D:1), SG=0.90/1.00 (E-F:1)

DCL LUMBER=1.00 NAIL=1.00 LS BEND=1.00
COMP=1.00 SHEAR=1.00 TENS= 1.00

COMPANION LIVE LOAD FACTOR = 1.00

TRUSS PLATE MANUFACTURER IS NOT RESPONSIBLE FOR QUALITY CONTROL IN THE TRUSS MANUFACTURING PLANT.


NAIL VALUES

PLATE	GRIP(DRY)	SHEAR (PSI)	SECTION (PLI)	MAX MIN	MAX MIN	MAX MIN
MT20	618	354	1667	788	1987	1658


PLATE PLACEMENT TOL. = 0.250 inches

PLATE ROTATION TOL. = 5.0 Deg.

JSI GRIP= 0.88 (B) (INPUT = 0.90)
JSI METAL= 0.70 (A) (INPUT = 1.00)



JOB NAME	TRUSS NAME	QUANTITY	PLY	JOB DESC.	DRWG NO.
408150	G60	4	1	GREEN PARK HOMES	
Tamarack Roof Truss, Burlington					



Version 8.310 S Oct 29 2019 MITek Industries, Inc. Sat Apr 25 11:02:39 2020 Page 1
ID:7vF7aG0E03cRUj6X1SklWYK-kwCWPUL9QwEw4keulc_ECognD4MnCBFXZZr4QzNCrk

LUMBER			
N. L. G. A. RULES	CHORDS	SIZE	LUMBER
AC - B	2x4	DRY	No.2
A - H	2x4	DRY	No.2
H - J	2x4	DRY	No.2
J - O	2x4	DRY	No.2
P - O	2x4	DRY	No.2
AC - T	2x4	DRY	No.2
T - P	2x4	DRY	No.2

ALL WEBS 2x3 DRY No.2 SPF
ALL GABLE WEBS 2x3 DRY No.2 SPF
DRY: SEASONED LUMBER.
GABLE STUDS SPACED AT 2-0-0 OC.

PLATES (table is in inches)				
JT TYPE	PLATES	W	LEN	Y X
B TMV+p	MT20	3.0	4.0	
C, D, E, F, G, I, K, L, M, N				
C TMV+w	MT20	2.0	4.0	
H TS-I	MT20	3.0	6.0	
J TTW-m	MT20	4.0	4.0	
O TMV+p	MT20	3.0	4.0	
P BMV1+p	MT20	3.0	4.0	
Q, R, S, U, V, W, X, Y, Z, AA, AB				
Q BMV1+w	MT20	2.0	4.0	
T BS-I	MT20	3.0	6.0	
AO BMV1+p	MT20	3.0	4.0	

DIMENSIONS, SUPPORTS AND LOADINGS SPECIFIED BY FABRICATOR TO BE VERIFIED BY BUILDING DESIGNER

BEARINGS
THIS TRUSS DESIGNED FOR CONTINUOUS BEARINGS.
THIS TRUSS REQUIRES RIGID SHEATHING ON EXPOSED FACE.
BEARING MATERIAL TO BE SPF NO.2 OR BETTER AT JOINT(S)

BRACING
TOP CHORD TO BE SHEATHED OR MAX. PURLIN SPACING = 6.25 FT.
MAX. UNBRACED BOTTOM CHORD LENGTH = 10.00 FT OR RIGID CEILING DIRECTLY APPLIED.
ALL PITCH BREAKS AND PERIMETER CORNER JOINTS MUST BE Laterally RESTRAINED.

1 LATERAL BRACE(S) AT 1/2 LENGTH OF O-P.
END VERTICAL(S) MUST BE SHEATHED OR HAVE BRACES AS INDICATED IN THE MAX. UNBRACED LENGTH COLUMN OF THE TABLE BELOW

LOADING

TOTAL LOAD CASES: (4)

CHORDS				WEBS			
MEMB.	MAX. FACTORED FORCE (LBS)	FACTORED VERT. LOAD (PLF)	MAX. UNBRACED LENGTH	MEMB.	MAX. FACTORED FORCE (LBS)	MAX. UNBRACED LENGTH	
FR-TO				FR-TO			
AC-B	-224 / 0	0.0	0.0 0.02 (1)	Q-N	-195 / 0	0.25 (1)	
A-B	0 / 28	-91.8	-91.8 0.12 (1)	R-M	-183 / 0	0.23 (1)	
B-C	-28 / 0	-91.8	-91.8 0.04 (1)	S-L	-188 / 0	0.24 (1)	
C-D	-19 / 0	-91.8	-91.8 0.04 (1)	U-K	-136 / 0	0.17 (1)	
D-E	-15 / 0	-91.8	-91.8 0.04 (1)	V-J	-131 / 0	0.17 (1)	
E-F	-11 / 0	-91.8	-91.8 0.04 (1)	W-I	-185 / 0	0.17 (1)	
F-G	-8 / 0	-91.8	-91.8 0.04 (1)	X-G	-183 / 0	0.11 (1)	
G-H	-6 / 0	-91.8	-91.8 0.04 (1)	Y-F	-182 / 0	0.07 (1)	
H-I	-6 / 0	-91.8	-91.8 0.04 (1)	Z-E	-182 / 0	0.05 (1)	
I-J	-6 / 0	-91.8	-91.8 0.04 (1)	AA-D	-183 / 0	0.03 (1)	
J-K	-2 / 0	-91.8	-91.8 0.03 (1)	AB-C	-176 / 0	0.03 (1)	
K-L	-2 / 0	-91.8	-91.8 0.04 (1)				
L-M	-2 / 0	-91.8	-91.8 0.04 (1)				
M-N	-2 / 0	-91.8	-91.8 0.04 (1)				
N-O	-2 / 0	-91.8	-91.8 0.04 (1)				
P-Q	-81 / 0	0.0	0.0 0.01 (1)				
AC-AB	0 / 24	-18.5	-18.5 0.02 (4)				
AB-AA	0 / 17	-18.5	-18.5 0.02 (4)				
AA-Z	0 / 13	-18.5	-18.5 0.02 (4)				
Z-Y	0 / 10	-18.5	-18.5 0.02 (4)				
Y-X	0 / 7	-18.5	-18.5 0.01 (4)				
X-W	0 / 5	-18.5	-18.5 0.02 (4)				
W-V	0 / 4	-18.5	-18.5 0.02 (4)				
V-U	0 / 2	-18.5	-18.5 0.02 (4)				
U-T	0 / 2	-18.5	-18.5 0.01 (4)				
T-S	0 / 2	-18.5	-18.5 0.02 (4)				
S-R	0 / 2	-18.5	-18.5 0.02 (4)				
R-Q	0 / 2	-18.5	-18.5 0.02 (4)				
Q-P	0 / 2	-18.5	-18.5 0.02 (4)				

TOTAL WEIGHT = 4 X 116 = 464 lb

DESIGN CRITERIA

SPECIFIED LOADS:
TOP CH. LL = 25.6 PSF
DL = 6.0 PSF
BOT CH. LL = 0.0 PSF
DL = 7.4 PSF
TOTAL LOAD = 39.0 PSF

SPACING = 24.0 IN. C/C

LOADING IN FLAT SECTION BASED ON A SLOPE OF 6.00/12

THIS TRUSS IS DESIGNED FOR RESIDENTIAL OR SMALL BUILDING REQUIREMENTS OF PART 9, NBCC 2010, NBCC 2015

THIS DESIGN COMPLIES WITH:
- PART 9 OF BCBC 2018, CBC 2012, ABC 2019
- PART 9 OF CBC 2012 (2019 AMENDMENT)
- CSA 086-09, CSA 086-14
- TPIC 2011, TPIC 2014

DESIGN ASSUMPTIONS
- OVERHANG NOT TO BE ALTERED OR CUT OFF.

(55 % OF 31.3 P.S.F. G.S.L. PLUS 8.4 P.S.F. RAIN LOAD) EQUALS 25.6 P.S.F. SPECIFIED ROOF LIVE LOAD

CSI: TC=0.12/1.00 (A-B:1), BC=0.02/1.00 (Q-R:4), WB=0.25/1.00 (N-Q:1), SS=0.09/1.00 (A-B:1)

DOL LUMBER=1.00 NAIL=1.00 LS BEND=1.10 COMP=1.10 SHEAR=1.10 TENS=1.10

COMPANION LIVE LOAD FACTOR = 1.00


TRUSS PLATE MANUFACTURER IS NOT RESPONSIBLE FOR QUALITY CONTROL IN THE TRUSS MANUFACTURING PLANT.

NAIL VALUES
PLATE GRIP(DRY) SHEAR SECTION (PS) (PL) (PL)
MAX MIN MAX MIN MAX MIN
MT20 618 354 1667 788 1987 1666


PLATE PLACEMENT TOL. = 0.250 inches

PLATE ROTATION TOL. = 5.0 Deg.

JSI GRIP = 0.60 (J) (INPUT = 0.90)
JSI METAL = 0.08 (I) (INPUT = 1.00)



Structural component only
DWG# T-2007057



LUMBER
N. L. G. A. RULES
CHORDS SIZE LUMBER
A - C 2x4 DRY No.2
C - E 2x4 DRY No.2
A - G 2x4 DRY No.2
G - E 2x4 DRY No.2
ALL WEBS 2x3 DRY No.2
DRY: SEASONED LUMBER.

DESCR.
SPF
SPF
SPF
SPF

DIMENSIONS, SUPPORTS AND LOADINGS SPECIFIED BY FABRICATOR TO BE VERIFIED BY BUILDING DESIGNER

JT	FACTORED GROSS REACTION		MAXIMUM FACTORED GROSS REACTION		INPUT BRG IN-SX	REQD BRG IN-SX
	VERT	HORZ	DOWN	HORZ		
A	134	0	134	0	18-1-0 (9-11-12) 1-0	1-0
E	134	0	134	0	18-1-0 (9-11-12) 1-0	1-0
F	883	0	883	0	18-1-0 (9-11-12) 1-0	1-0
H	883	0	883	0	18-1-0 (9-11-12) 1-0	1-0

VALUE IN PARENTHESIS INDICATES EFFECTIVE BEARING LENGTH

UNFACTORED REACTIONS

JT	1ST CASE COMBINED	MAX/MIN. COMPONENT REACTIONS					
		SNOW	LIVE	PERM. LIVE	WIND	DEAD	SOIL
A	94	68 / 0	0 / 0	0 / 0	0 / 0	28 / 0	0 / 0
E	94	68 / 0	0 / 0	0 / 0	0 / 0	28 / 0	0 / 0
F	611	385 / 0	0 / 0	0 / 0	0 / 0	218 / 0	0 / 0
H	611	385 / 0	0 / 0	0 / 0	0 / 0	218 / 0	0 / 0

BEARING MATERIAL TO BE SPF NO.2 OR BETTER AT JOINT(S) A, E, F, H

BRACING

TOP CHORD TO BE SHEATHED OR MAX. PURLIN SPACING = 10.00 FT.
MAX. UNBRACED BOTTOM CHORD LENGTH = 6.25 FT. OR RIGID CEILING DIRECTLY APPLIED.

ALL PITCH BREAKS AND PERIMETER CORNER JOINTS MUST BE LATERALLY RESTRAINED.

LOADING

TOTAL LOAD CASES: (4)

MEMB.	CHORDS		WEBS	
	MAX. FACTORED FORCE (LBS)	FACTORED VERT. LOAD LC1 MAX (PLF)	MAX. FACTORED FORCE (LBS)	MAX. FACTORED FORCE (LBS)
FR-TO				
A-J	0 / 240	-91.8 -91.8 0.12 (1)	10.00	C-F -428 / 0
J-B	0 / 301	-91.8 -91.8 0.34 (1)	10.00	F-D -436 / 0
B-C	0 / 503	-91.8 -91.8 0.37 (1)	10.00	H-C -428 / 0
C-D	0 / 503	-91.8 -91.8 0.37 (1)	10.00	B-H -438 / 0
D-L	0 / 301	-91.8 -91.8 0.34 (1)	10.00	I-J -76 / 35
L-E	0 / 240	-91.8 -91.8 0.12 (1)	10.00	K-L -76 / 35
A-I	-255 / 0	-18.5 -18.5 0.11 (1)	6.25	
I-H	-243 / 0	-18.5 -18.5 0.13 (4)	6.25	
H-G	-246 / 0	-18.5 -18.5 0.13 (4)	6.25	
G-F	-246 / 0	-18.5 -18.5 0.13 (4)	6.25	
F-K	-243 / 0	-18.5 -18.5 0.13 (4)	6.25	
K-E	-255 / 0	-18.5 -18.5 0.11 (1)	6.25	

TOTAL WEIGHT = 2 X 54 = 107 lb

DESIGN CRITERIA

SPECIFIED LOADS:
TOP CH. LL = 25.6 PSF
DL = 6.0 PSF
BOT CH. LL = 0.0 PSF
DL = 7.4 PSF
TOTAL LOAD = 39.0 PSF

SPACING = 24.0 IN. C/C

THIS TRUSS IS DESIGNED FOR RESIDENTIAL OR SMALL BUILDING REQUIREMENTS OF PART 9, NBCC 2010, NBCC 2015

THIS DESIGN COMPLIES WITH:
- PART 9 OF BCBC 2018, CBC 2012, ABC 2019
- PART 9 OF CBC 2012 (2019 AMENDMENT)
- CSA 086-09, CSA 088-14
- TPIC 2011, TPIC 2014

(55 % OF 31.3 P.S.F. G.S.L. PLUS 8.4 P.S.F. RAIN LOAD) EQUALS 25.6 P.S.F. SPECIFIED ROOF LIVE LOAD

CSI: TC=0.37/1.00 (C-D-I), BC=0.13/1.00 (F-K-4), WB=0.18/1.00 (C-H-1), SS=0.17/1.00 (D-L-1)

DOL LUMBER=1.00 NAIL=1.00 LS BEND=1.10 COMP=1.10 SHEAR=1.10 TENS=1.10

COMPANION LIVE LOAD FACTOR = 1.00


TRUSS PLATE MANUFACTURER IS NOT RESPONSIBLE FOR QUALITY CONTROL IN THE TRUSS MANUFACTURING PLANT.

NAIL VALUES
PLATE GRIP(DRY) SHEAR SECTION (PSI) (PLI) (PLI)
MAX MIN MAX MIN MAX MIN
MT20 618 354 1667 788 1987 1656

PLATE PLACEMENT TOL. = 0.250 inches


PLATE ROTATION TOL. = 5.0 Deg.

JSI GRIP= 0.48 (H) (INPUT = 0.90)
JSI METAL= 0.15 (C) (INPUT = 1.00)



Structural component only
DWG# T-2007058

JOB NAME	TRUSS NAME	QUANTITY	PLY	JOB DESC.	DRWG NO.
408150	P1	17	1	GREEN PARK HOMES	
Tamarack Roof Truss, Burlington				TRUSS DESC.	



LUMBER				DESIGN CRITERIA			
N. L. G. A. RULES				TOTAL WEIGHT = 17 X 55 = 943 lb			
CHORDS	SIZE	LUMBER	DESCR.	SPECIFIED LOADS:			
A - C	2x4	DRY	No.2	TOP CH.	LL = 25.6	PSF	
C - E	2x4	DRY	No.2	DL = 6.0	PSF		
A - G	2x4	DRY	No.2	BOT CH.	LL = 0.0	PSF	
G - E	2x4	DRY	No.2	DL = 7.4	PSF		
ALL WEBS 2x3 DRY				TOTAL LOAD = 39.0 PSF			
DRY: SEASONED LUMBER.				SPACING = 24.0 IN. CC			

PLATES (table is in inches)

JT	TYPE	PLATES	W	LEN	Y	X
A	TBM1-h	MT20	3.0	4.0		
B	TMMW-w	MT20	4.0	4.0	2.00	1.75
C	TTW-p	MT20	4.0	4.0		
D	TMMW-w	MT20	4.0	4.0	2.00	1.75
E	TBM1-h	MT20	3.0	4.0		
F	BMW1-w	MT20	2.0	4.0		
G	BS-h	MT20	3.0	6.0		
H	BMW1-w	MT20	4.0	9.0		
I	BMW1-w	MT20	2.0	4.0		

DIMENSIONS, SUPPORTS AND LOADINGS SPECIFIED BY FABRICATOR TO BE VERIFIED BY BUILDING DESIGNER

BEARINGS

JT	FACTORED GROSS REACTION	MAXIMUM FACTORED GROSS REACTION	INPUT BRG	REQD BRG
	VERT	HORZ	DOWN	HORZ
A	124	0	124	0
E	124	0	124	0
H	415	0	415	0
F	665	0	665	0
I	665	0	665	0

VALUE IN PARENTHESIS INDICATES EFFECTIVE BEARING LENGTH

UNFACTORED REACTIONS

JT	1ST LOASE	SNOW	LIVE	PERM. LIVE	WIND	DEAD	SOIL
A	87	59/0	0/0	0/0	0/0	28/0	0/0
E	87	59/0	0/0	0/0	0/0	28/0	0/0
H	293	192/0	0/0	0/0	0/0	101/0	0/0
F	471	307/0	0/0	0/0	0/0	164/0	0/0
I	471	307/0	0/0	0/0	0/0	164/0	0/0

BEARING MATERIAL TO BE SPF NO.2 OR BETTER AT JOINT(S) A, E, H, F, I

BRACING

TOP CHORD TO BE SHEATHED OR MAX. PURLIN SPACING = 10.00 FT.
MAX. UNBRACED BOTTOM CHORD LENGTH = 6.25 FT. OR RIGID CEILING DIRECTLY APPLIED.

ALL PITCH BREAKS AND PERIMETER CORNER JOINTS MUST BE Laterally RESTRAINED.

LOADING

TOTAL LOAD CASES: (4)

CHORDS				WEBS			
MEMB.	MAX. FACTORED FORCE (LBS)	FACTORED VERT. LOAD (PLF)	MAX. UNBRACED LENGTH (FT)	MEMB.	MAX. FACTORED FORCE (LBS)	MAX. UNBRACED LENGTH (FT)	
FR-TO				FR-TO			
A-K	0/248	-91.8	0.07 (1)	H-C	-445/0	0.13 (1)	
K-B	0/292	-91.8	0.32 (1)	H-D	0/59	0.01 (1)	
B-C	0/188	-91.8	0.30 (1)	F-D	-528/0	0.08 (1)	
C-D	0/188	-91.8	0.30 (1)	S-H	0/59	0.01 (1)	
D-M	0/292	-91.8	0.32 (1)	I-B	-528/0	0.08 (1)	
M-E	0/248	-91.8	0.07 (1)	J-K	-128/6	0.00 (1)	
A-J	-256/0	-18.5	0.14 (1)	L-M	-128/6	0.00 (1)	
J-I	-240/0	-18.5	0.14 (1)				
I-H	-240/0	-18.5	0.11 (1)				
H-G	-240/0	-18.5	0.11 (1)				
G-F	-240/0	-18.5	0.11 (1)				
F-L	-240/0	-18.5	0.14 (1)				
L-E	-256/0	-18.5	0.14 (1)				

THIS TRUSS IS DESIGNED FOR RESIDENTIAL OR SMALL BUILDING REQUIREMENTS OF PART 9, NBCC 2010, NBCC 2015

THIS DESIGN COMPLIES WITH:
- PART 9 OF BCBC 2018, OBC 2012, ABC 2019
- PART 9 OF OBC 2012 (2019 AMENDMENT)
- CSA 086-09, CSA 088-14
- TPIC 2011, TPIC 2014

(55% OF 31.3 P.S.F. G.S.L. PLUS 8.4 P.S.F. RAIN LOAD) EQUALS 25.6 P.S.F. SPECIFIED ROOF LIVE LOAD

CSI: TC=0.32/1.00 (D-M:1), BC=0.14/1.00 (F-L:1), WB=0.13/1.00 (C-H:1), SS=0.17/1.00 (D-M:1)

OOL LUMBER=1.00 NAIL=1.00 LS BEND=1.10
COMP=1.10 SHEAR=1.10 TENS=1.10

COMPANION LIVE LOAD FACTOR = 1.00

TRUSS PLATE MANUFACTURER IS NOT RESPONSIBLE FOR QUALITY CONTROL IN THE TRUSS MANUFACTURING PLANT.

NAIL VALUES
PLATE GRIP(DRY) SHEAR SECTION (PSI) (PLI) (PLI)
MAX MIN MAX MIN MAX MIN
MT20 618 354 1667 788 1987 1656

PLATE PLACEMENT TOL. = 0.250 inches


PLATE ROTATION TOL. = 5.0 Deg.

JSI GRIP = 0.51 (B) (INPUT = 0.90)
JSI METAL = 0.13 (C) (INPUT = 1.00)



Structural component only
DWG# T-2007062

JOB NAME	TRUSS NAME	QUANTITY	PLY	JOB DESC.	DRWG NO.
408151	PB20	2	1	GREEN PARK HOMES	
Tamarack Roof Truss, Burlington					
Version 8.310 S Oct 29 2019 MITek Industries, Inc. Sat Apr 25 11:19:42 2020 Page 1					
ID:h2dfgC44ws_E2tzqPs_atzllRw-HkWF6HrVE7mI4RFJStCxbPKbCR_v_qmDzUdZNCXI					
Scale = 1:20.3					



LUMBER				DESIGN CRITERIA			
N. L. G. A. RULES				TOTAL WEIGHT = 2 X 45 = 90 LB			
CHORDS	SIZE	LUMBER	DESCR	SPECIFIED LOADS:			
A - C	2x4	DRY	No.2	TOP CH. LL = 25.6 PSF			
C - E	2x4	DRY	No.2	DL = 8.0 PSF			
E - G	2x4	DRY	No.2	BOT CH. LL = 0.0 PSF			
G - I	2x4	DRY	No.2	DL = 7.4 PSF			
ALL WEBS	2x3	DRY	No.2	TOTAL LOAD = 39.0 PSF			
DRY: SEASONED LUMBER.				SPACING = 24.0 IN. C/C			


PLATES (table is in inches)				UNFACTORED REACTIONS			
JT TYPE	PLATES	W	LEN Y X	1ST CASE MAX./MIN. COMPONENT REACTIONS			
B TMB1-I	MT20	3.0	4.0	1.50	2.00		
C TWW+m	MT20	5.0	6.0	2.25	1.50		
D TWW+m	MT20	2.0	4.0	1.50	2.00		
E TWW+m	MT20	5.0	6.0	2.25	1.50		
F TMB1-I	MT20	3.0	4.0	1.50	2.00		
H BMW1-w	MT20	2.0	4.0	1.50	2.00		
I BMWW1-I	MT20	4.0	9.0				
J BMW1-w	MT20	2.0	4.0	1.50	2.00		

BEARING MATERIAL TO BE SPF NO.2 OR BETTER AT JOINT(S) B, F, J, I, H

BRACING
TOP CHORD TO BE SHEATHED OR MAX. PURLIN SPACING = 6.25 FT.
MAX. UNBRACED BOTTOM CHORD LENGTH = 10.00 FT OR RIGID CEILING DIRECTLY APPLIED.

LOADING
TOTAL LOAD CASES: (4)

CHORDS				WEBS			
MEMB.	MAX. FACTORED FORCE (LBS)	FACTORED VERT. LOAD (PLF)	MAX. FACTORED CS (LC)	MEMB.	MAX. FACTORED FORCE (LBS)	MAX. FACTORED CS (LC)	
FR-TO		FROM	TO	FR-TO			
A-B	0/14	-91.8	-91.8 0.02 (1)	10.00	J-C	-194/0	0.03 (1)
B-L	-31/4	-91.8	-91.8 0.01 (1)	6.25	C-I	-22/0	0.01 (1)
L-C	-60/0	-91.8	-91.8 0.03 (1)	6.25	I-D	-576/0	0.08 (1)
C-D	-8/0	-91.8	-91.8 0.39 (1)	10.00	D-E	-22/0	0.01 (1)
D-E	-8/0	-91.8	-91.8 0.39 (1)	10.00	E-H	-194/0	0.03 (1)
E-N	-60/0	-91.8	-91.8 0.03 (1)	6.25	H-K	-121/0	0.00 (1)
N-F	-31/4	-91.8	-91.8 0.01 (1)	6.25	K-L	-121/0	0.00 (1)
F-G	0/14	-91.8	-91.8 0.02 (1)	10.00			
B-K	0/42	-18.5	-18.5 0.04 (1)	10.00			
K-J	0/42	-18.5	-18.5 0.07 (4)	10.00			
J-I	0/29	-18.5	-18.5 0.10 (4)	10.00			
I-H	0/29	-18.5	-18.5 0.10 (4)	10.00			
H-M	0/42	-18.5	-18.5 0.07 (4)	10.00			
M-F	0/42	-18.5	-18.5 0.04 (1)	10.00			



Structural component only
DWG# T-2007080

CS: TC=0.39/1.00 (C-D-1), BC=0.10/1.00 (B-J-4), WB=0.08/1.00 (D-E-1), SS=0.22/1.00 (D-E-1)

DOL LUMBER=1.00 NAIL=1.00 LS BEND=1.10 COMP=1.10 SHEAR=1.10 TENS=1.10

COMPANION LIVE LOAD FACTOR = 1.00

TRUSS PLATE MANUFACTURER IS NOT RESPONSIBLE FOR QUALITY CONTROL IN THE TRUSS MANUFACTURING PLANT.


NAIL VALUES
PLATE GRIP(DRY) SHEAR SECTION (PSI) (PLI) (PLI)
MAX MIN MAX MIN MAX MIN
MT20 618 354 1667 788 1987 1658

PLATE PLACEMENT TOL. = 0.250 inches

PLATE ROTATION TOL. = 5.0 Deg.

JSI GRIP= 0.30 (D) (INPUT = 0.30)
JSI METAL= 0.12 (D) (INPUT = 1.00)

JOB NAME 408150	TRUSS NAME U1	QUANTITY 21	PLY 1	JOB DESC. GREEN PARK HOMES	DRWG NO.
Tamarack Roof Truss, Burlington					



LUMBER

N. L. G. A. RULES

CHORDS	SIZE	LUMBER
E - B	2x4	DRY No.2
A - C	2x4	DRY No.2
E - D	2x4	DRY No.2

DRY: SEASONED LUMBER.

PLATES (table is in inches)

JT	TYPE	PLATES	W	LEN	Y	X
B	TMV+p	MT20	3.0	4.0		
E	BMV1+p	MT20	3.0	4.0		

DIMENSIONS, SUPPORTS AND LOADINGS SPECIFIED BY FABRICATOR TO BE VERIFIED BY BUILDING DESIGNER

BEARINGS

JT	FACTORED GROSS REACTION	MAXIMUM FACTORED GROSS REACTION	INPUT BRG IN-SX	REQD BRG IN-SX
E	525	0	5-8	5-8
C	202	0	1-8	1-8
D	45	0	1-8	1-8

SEE MITEK STANDARD DETAIL B97791H FOR CONNECTION TO JOINT(S) C, D

UNFACTORED REACTIONS

JT	1ST CASE	MAX. MIN. COMPONENT REACTIONS	PERM. LIVE	WIND	DEAD	SOIL
E	389	257 / 0	0 / 0	0 / 0	111 / 0	0 / 0
C	139	113 / 0	0 / 0	0 / 0	26 / 0	0 / 0
D	36	0 / 0	0 / 0	0 / 0	36 / 0	0 / 0

BEARING MATERIAL TO BE SPF NO.2 OR BETTER AT JOINT(S) E

BRACING

TOP CHORD TO BE SHEATHED OR MAX. PURLIN SPACING = 8.25 FT.
MAX. UNBRACED BOTTOM CHORD LENGTH = 10.00 FT OR RIGID CEILING DIRECTLY APPLIED.

ALL FITCH BREAKS AND PERIMETER CORNER JOINTS MUST BE Laterally RESTRAINED.

LOADING

TOTAL LOAD CASES: (4)

CHORDS	MEMB.	MAX. FACTORED FORCE (LBS)	FACTORED VERT. LOAD (LBS)	FACTORED HORIZ. LOAD (LBS)	MAX. FACTORED FORCE (LBS)	MAX. FACTORED FORCE (LBS)
FR-TO						
E-B		-461 / 0	0.0	0.0	0.13 (4)	7.81
A-B		0 / 28	-91.8	-91.8	0.12 (1)	10.00
B-C		-30 / 0	-91.8	-91.8	0.54 (1)	6.25
E-D		0 / 0	-18.5	-18.5	0.13 (4)	10.00

TOTAL WEIGHT = 21 X 17 = 353 lb

DESIGN CRITERIA

SPECIFIED LOADS:

TOP CH.	LL = 25.8	PSF
DL = 6.0	PSF	
BOT CH.	LL = 0.0	PSF
DL = 7.4	PSF	
TOTAL LOAD	= 39.0	PSF

SPACING = 24.0 IN. C/C

THIS TRUSS IS DESIGNED FOR RESIDENTIAL OR SMALL BUILDING REQUIREMENTS OF PART 9, NBC 2010, NBCC 2015

THIS DESIGN COMPLIES WITH:

- PART 9 OF BCBC 2018, OBC 2012, ABC 2019
- PART 9 OF OBC 2012 (2019 AMENDMENT)
- CSA 086-09, CSA 086-14
- TPIC 2011, TPIC 2014

DESIGN ASSUMPTIONS

- OVERHANG NOT TO BE ALTERED OR CUT OFF.

(55 % OF 31.3 P.S.F. G.S.L. PLUS 8.4 P.S.F. RAIN LOAD) EQUALS 25.8 P.S.F. SPECIFIED ROOF LIVE LOAD

ALLOWABLE DEFL.(LL) = $L/360$ (0.20")
CALCULATED VERT. DEFL.(LL) = $L/999$ (0.00")
ALLOWABLE DEFL.(TL) = $L/360$ (0.20")
CALCULATED VERT. DEFL.(TL) = $L/999$ (0.03")

CSI: TC=0.54/1.00 (B-C:1), BC=0.13/1.00 (D-E:4), WB=0.03/1.00 (m/a:0), SSI=0.24/1.00 (B-C:1)

DOL LUMBER=1.00 NAIL=1.00 LS BEND=1.10
COMP=1.10 SHEAR=1.10 TENS=1.10

COMPANION LIVE LOAD FACTOR = 1.00

AUTOSOLVE RIGHT HEEL ONLY

TRUSS PLATE MANUFACTURER IS NOT RESPONSIBLE FOR QUALITY CONTROL IN THE TRUSS MANUFACTURING PLANT.

NAIL VALUES

PLATE GRIP(DRY)	SHEAR (PSI)	SECTION (PLI)
MAX MIN	MAX MIN	MAX MIN
MT20	618 354	1667 788

PLATE PLACEMENT TOL. = 0.250 inches

PLATE ROTATION TOL. = 5.0 Deg.

JSI GRIP = 0.19 (E) (INPUT = 0.50)
JSI METAL = 0.13 (B) (INPUT = 1.00)




Structural component only
DWG# T-2007059

JOB NAME	TRUSS NAME	QUANTITY	PLY	JOB DESC.	DRWG NO.
408150	J2	1	1	GREEN PARK HOMES	
TRUSS DESC.					

Tamarack Roof Truss, Burlington

Version 8.310 S Oct 29 2019 Mitek Industries, Inc. Sat Apr 25 11:32:43 2020 Page 1
ID:J7vF?aG0E03cRUj8X1;SkziWYK-dhR1F0iU8kMYU2P78gwP2_KzqQl;30rSBX3DBzNCng

Scale = 1:27.0



LUMBER

N. L. G. A. RULES

CHORDS	SIZE	LUMBER
F - B	2x4 DRY	No.2
A - C	2x4 DRY	No.2
F - D	2x4 DRY	No.2

ALL WEBS 2x3 DRY No.2
DRY: SEASONED LUMBER.

DESCR.
SPF
SPF
SPF

DIMENSIONS, SUPPORTS AND LOADINGS SPECIFIED BY FABRICATOR TO BE VERIFIED BY BUILDING DESIGNER

BEARINGS

	FACTORED GROSS REACTION	MAXIMUM FACTORED GROSS REACTION	INPUT BRG	REQD BRG
	VERT	HORZ	DOWN	HORZ
JT	341	0	341	0
F	178	0	178	0
C	36	0	40	0

SEE MITEK STANDARD DETAIL B97791H FOR CONNECTION TO JOINT(S) C, D

UNFACTORED REACTIONS

JT	1ST LCASE	SNOW	LIVE	PERM. LIVE	WIND	DEAD	SOIL
F	239	170/0	0/0	0/0	0/0	89/0	0/0
C	122	99/0	0/0	0/0	0/0	23/0	0/0
D	29	0/0	0/0	0/0	0/0	29/0	0/0

BEARING MATERIAL TO BE SPF NO 2 OR BETTER AT JOINT(S) F

BRACING

TOP CHORD TO BE SHEATHED OR MAX. PURLIN SPACING = 10.00 FT.
MAX. UNBRACED BOTTOM CHORD LENGTH = 10.00 FT. OR RIGID CEILING DIRECTLY APPLIED.
ALL PITCH BREAKS AND PERIMETER CORNER JOINTS MUST BE Laterally RESTRAINED.

LOADING

TOTAL LOAD CASES: (5)

CHORDS				WEBS			
MEMB.	MAX. FACTORED FORCE (LBS)	FACTORED VERT. LOAD (PLF)	MAX. LC1 MAX. CSI (LC)	MEMB.	MAX. FACTORED FORCE (LBS)	MAX. LC1 MAX. CSI (LC)	
FR-TO		FROM TO		FR-TO			
F-B	-305/0	0.0	0.0 0.03 (1)	7.81	B-E	0/0	0.00 (1)
A-B	0/41	-91.8	-91.8 0.14 (5)	10.00			
B-C	0/0	-91.8	-91.8 0.23 (1)	10.00			
F-E	0/0	-18.5	-18.5 0.08 (4)	10.00			
E-D	0/0	-18.5	-18.5 0.08 (4)	10.00			

CANTILEVER ANALYSIS HAS BEEN CONSIDERED IN THIS DESIGN

TOTAL WEIGHT = 15 lb

DESIGN CRITERIA

SPECIFIED LOADS:
TOP CH. LL = 25.6 PSF
DL = 8.0 PSF
BOT CH. LL = 0.0 PSF
DL = 7.4 PSF
TOTAL LOAD = 39.0 PSF

SPACING = 24.0 IN. C/C

THIS TRUSS IS DESIGNED FOR RESIDENTIAL OR SMALL BUILDING REQUIREMENTS OF PART 9, NBCC 2010, NBCC 2015

THIS DESIGN COMPLIES WITH:
- PART 9 OF NBCC 2015, OBC 2012, ABC 2019
- PART 9 OF OBC 2012 (2019 AMENDMENT)
- CSA 086-09, CSA 086-14
- TPIC 2011, TPIC 2014

(55% OF 31.3 P.S.F. G.S.L. PLUS 8.4 P.S.F. RAIN LOAD) EQUALS 25.6 P.S.F. SPECIFIED ROOF LIVE LOAD

ALLOWABLE DEFL.(LL) = $L/360$ (0.19")
CALCULATED VERT. DEFL.(LL) = $L/999$ (0.00")
ALLOWABLE DEFL.(TL) = $L/360$ (0.19")
CALCULATED VERT. DEFL.(TL) = $L/999$ (0.01")

CSI: TC=0.23/1.00 (B-C:1), BC=0.08/1.00 (D-E:4), WB=0.09/1.00 (B-E:1), SS=0.11/1.00 (B-C:1)

DOL LUMBER=1.00 NAIL=1.00 LS BEND=1.10
COMP=1.10 SHEAR=1.10 TENS=1.10

COMPANION LIVE LOAD FACTOR = 1.00

AUTOSOLVE RIGHT HEEL ONLY

TRUSS PLATE MANUFACTURER IS NOT RESPONSIBLE FOR QUALITY CONTROL IN THE TRUSS MANUFACTURING PLANT.

NAIL VALUES
PLATE GRIP(DRY) SHEAR SECTION (PSI) (PL) (PL)
MAX MIN MAX MIN MAX MIN
MT20 616 354 1667 788 1997 1656

PLATE PLACEMENT TOL. = 0.250 inches

PLATE ROTATION TOL. = 5.0 Deg.


JSI GRIP= 0.24 (B) (INPUT = 0.93)
JSI METAL= 0.06 (B) (INPUT = 1.00)



Structural component only
DWG# T-2007060

JOB NAME	TRUSS NAME	QUANTITY	PLY	JOB DESC.	DRWG NO.
408150	J3	6	1	GREEN PARK HOMES	
Tamarack Roof Truss, Burlington					

Version 8.310 S Oct 29 2019 Mitek Industries, Inc. Sat Apr 25 11:02:44 2020 Page 1
ID:7vF7aG0E03cRU6X1jSkzlWYK-5u7PSBPiFSsDAedbsB9xGWUuEIBSWG_hrGcmdzNCnf



Scale = 1:11.5

LUMBER

N.L.G.A. RULES

CHORDS SIZE

A - C 2x4 DRY No.2

B - D 2x4 DRY No.2

DRY: SEASONED LUMBER.

PLATES (table is in inches)

JT TYPE PLATES W LEN Y X
B TMB1-MT20 3.0 4.0

DIMENSIONS, SUPPORTS AND LOADINGS SPECIFIED BY FABRICATOR TO BE VERIFIED BY BUILDING DESIGNER

BEARINGS

JT	FACTORED GROSS REACTION	MAXIMUM FACTORED GROSS REACTION	INPUT BRG	REQD BRG
	VERT	DOWN	UP	
C	174	0	0	1-8
B	364	0	0	5-8
D	68	0	0	1-8

SEE MITEK STANDARD DETAIL B97791H FOR CONNECTION TO JOINT(S) C, D

UNFACTORED REACTIONS

JT	1ST LOASE	SNOW	LIVE	PERM LIVE	WIND	DEAD	SOIL
C	120	83/0	0/0	0/0	0/0	27/0	0/0
B	255	180/0	0/0	0/0	0/0	75/0	0/0
D	50	19/0	0/0	0/0	0/0	32/0	0/0

BEARING MATERIAL TO BE SPF NO.2 OR BETTER AT JOINT(S) B, D

BRACING

TOP CHORD TO BE SHEATHED OR MAX. PURLIN SPACING = 6.25 FT.
MAX. UNBRACED BOTTOM CHORD LENGTH = 10.00 FT OR RIGID CEILING DIRECTLY APPLIED.

ALL PITCH BREAKS AND PERIMETER CORNER JOINTS MUST BE Laterally RESTRAINED.

LOADING

TOTAL LOAD CASES: (4)

CHORDS				WEBS			
MEMB.	MAX. FACTORED FORCE (LBS)	FACTORED VERT. LOAD (PLF)	MAX. FACTORED LC1 MAX. UNBRACED LENGTH	MEMB.	MAX. FACTORED FORCE (LBS)	MAX. FACTORED LC1 MAX. UNBRACED LENGTH	
FR-TO				FR-TO			
A-B	0/18	-91.8	-91.8 0.11 (1)	E-F	-194/7	0.00 (1)	
B-F	-14/0	-91.8	-91.8 0.05 (4)				
F-C	0/2	-91.8	-91.8 0.22 (1)				
B-E	0/0	-18.5	-18.5 0.17 (1)				
E-D	0/0	-18.5	-18.5 0.17 (1)				

DESIGN CRITERIA

SPECIFIED LOADS:

TOP CH. LL = 25.8 PSF
DL = 6.0 PSF
BOT CH. LL = 0.0 PSF
DL = 7.4 PSF
TOTAL LOAD = 39.0 PSF

SPACING = 24.0 IN. C/C

THIS TRUSS IS DESIGNED FOR RESIDENTIAL OR SMALL BUILDING REQUIREMENTS OF PART 9, NBCC 2010, NBCC 2015

THIS DESIGN COMPLIES WITH:

- PART 9 OF NBCC 2018, CBC 2012, ABC 2019
- PART 9 OF CBC 2012 (2019 AMENDMENT)
- CSA 086-09, CSA 086-14
- TPIC 2011, TPIC 2014

(5% OF 31.3 P.S.F. G.S.L. PLUS 5.4 P.S.F. RAIN LOAD) EQUALS 25.6 P.S.F. SPECIFIED ROOF LIVE LOAD

ALLOWABLE DEFL.(LL) = $L/360$ (0.19")
CALCULATED VERT. DEFL.(LL) = $L/999$ (0.02")
ALLOWABLE DEFL.(TL) = $L/360$ (0.19")
CALCULATED VERT. DEFL.(TL) = $L/999$ (0.05")

CSI: TC=0.22/1.00 (C-F:1), BC=0.17/1.00 (D-E:1), WB=0.00/1.00 (E-F:1), SS=0.18/1.00 (B-E:1)

DOL LUMBER=1.00 NAIL=1.00 LS BEND=1.10 COMP=1.10 SHEAR=1.10 TENS=1.10

COMPANION LIVE LOAD FACTOR = 1.00

TRUSS PLATE MANUFACTURER IS NOT RESPONSIBLE FOR QUALITY CONTROL IN THE TRUSS MANUFACTURING PLANT.


NAIL VALUES

PLATE GRIP(DRY) SHEAR SECTION (PSD) (PLJ) (PLJ)
MAX MIN MAX MIN MAX MIN
MT20 618 354 1657 788 1987 1656

PLATE PLACEMENT TOL. = 0.250 inches

PLATE ROTATION TOL. = 5.0 Deg.


JSI GRIP= 0.24 (B) (INPUT = 0.90)
JSI METAL= 0.07 (B) (INPUT = 1.00)



Structural component only
DWG# T-2007061

JOB NAME	TRUSS NAME	QUANTITY	PLY	JOB DESC.	DRWG NO.
408152	J40	4	1	GREEN PARK HOMES	
Tamarack Roof Truss, Burlington				TRUSS DESC.	

Version 8.310 S Oct 29 2019 Mitek Industries, Inc. Sat Apr 25 11:29:29 2020 Page 1
ID:7vF?aG0E03cRUj6X1jSkzIWK-bfU9J?g2Gb4UDlp3CRUXVjVnrDY50PbEI2Z2b6zNCOa



LUMBER

N. L. G. A. RULES

CHORDS	SIZE	LUMBER	DESCR.
E - A	2x4	DRY No.2	SPF
A - B	2x4	DRY No.2	SPF
E - C	2x4	DRY No.2	SPF

ALL WEBS 2x3 DRY No.2 SPF
DRY: SEASONED LUMBER.

PLATES (table is in inches)

JT	TYPE	PLATES	W	LEN	Y	X
A	TMVW-1	MT20	4.0	4.0	2.00	1.25
D	BMVW-w	MT20	2.0	4.0		
E	BMV1-p	MT20	3.0	4.0		

DIMENSIONS, SUPPORTS AND LOADINGS SPECIFIED BY FABRICATOR TO BE VERIFIED BY BUILDING DESIGNER

BEARINGS

JT	VERT	HORZ	DOWN	HORZ	UPLIFT	IN-SX	REQD
E	209	0	209	0	0	MECHANICAL	1-8
B	174	0	174	0	0	1-8	1-8
C	35	0	35	0	0	1-8	1-8

A SUITABLE HANGER/MECHANICAL CONNECTION IS REQUIRED AT JOINT E. MINIMUM BEARING LENGTH AT JOINT E = 1-8.

SEE MITEK STANDARD DETAIL B97791H FOR CONNECTION TO JOINT(S) B, C

UNFACTORED REACTIONS

JT	1ST LCASE	MAX/MIN	COMPONENT REACTIONS
JT	COMBINED	SNOW	LIVE PERM.LIVE WIND DEAD SOIL
E	148	97/0	0/0 0/0 0/0 51/0 0/0
B	120	97/0	0/0 0/0 0/0 23/0 0/0
C	28	0/0	0/0 0/0 0/0 28/0 0/0

BRACING
TOP CHORD TO BE SHEATHED OR MAX. PURLIN SPACING = 10.00 FT.
MAX. UNBRACED BOTTOM CHORD LENGTH = 10.00 FT. OR RIGID CEILING DIRECTLY APPLIED.

ALL PITCH BREAKS AND PERIMETER CORNER JOINTS MUST BE Laterally RESTRAINED.

LOADING
TOTAL LOAD CASES: (4)

CHORDS				WEBS			
MEMB.	MAX. FACTORED FORCE (LBS)	FACTORED VERT. LOAD (PLF)	LC1 MAX CSI (LC)	MEMB.	MAX. FACTORED FORCE (LBS)	FACTORED VERT. LOAD (PLF)	LC1 MAX CSI (LC)
FR-TO				FR-TO			
E-A	-174/0	0.0	0.0 0.02 (1)	A-D	0/0	0.00 (1)	
A-B	0/0	-91.8	-91.8 0.22 (1)				
E-D	0/0	-18.5	-18.5 0.07 (4)				
D-C	0/0	-18.5	-18.5 0.08 (4)				

TOTAL WEIGHT = 4 X 13 = 52 lb

DESIGN CRITERIA

SPECIFIED LOADS:

TOP CH.	LL	= 25.6	PSF
	DL	= 8.0	PSF
BOT CH.	LL	= 0.0	PSF
	DL	= 7.4	PSF
TOTAL LOAD		= 39.0	PSF

SPACING = 24.0 IN/C

THIS TRUSS IS DESIGNED FOR RESIDENTIAL OR SMALL BUILDING REQUIREMENTS OF PART 9, NBC 2010, NBC 2015

THIS DESIGN COMPLIES WITH:
- PART 9 OF CBC 2018, OBC 2012, ABC 2019
- PART 9 OF OBC 2012 (2019 AMENDMENT)
- CSA 086-09, CSA 088-14
- TPIC 2011, TPIC 2014

(55 % OF 31.3 P.S.F. G.S.L. PLUS 8.4 P.S.F. RAIN LOAD) EQUALS 25.6 P.S.F. SPECIFIED ROOF LIVE LOAD

ALLOWABLE DEFL.(LL) = L/360 (0.19")
CALCULATED VERT. DEFL.(LL) = L/999 (0.00")
ALLOWABLE DEFL.(TL) = L/360 (0.18")
CALCULATED VERT. DEFL.(TL) = L/999 (0.01")

CSI: TC=0.22/1.00 (A-B:1), BC=0.08/1.00 (C-D:4), WB=0.00/1.00 (A-D:1), SS=0.12/1.00 (A-B:1)

DOL LUMBER=1.00 NAIL=1.00 LS BEND=1.10
COMP=1.10 SHEAR=1.10 TENS=1.10

COMPANION LIVE LOAD FACTOR = 1.00

TRUSS PLATE MANUFACTURER IS NOT RESPONSIBLE FOR QUALITY CONTROL IN THE TRUSS MANUFACTURING PLANT.


NAIL VALUES

PLATE	GRIP(DRY)	SHEAR	SECTION
(PSI)	(PL)	(PL)	(PL)
MAX	MIN	MAX	MIN
MT20	618	354	1657 788 1987 1658

PLATE PLACEMENT TOL. = 0.250 inches

PLATE ROTATION TOL. = 5.0 Deg.


JSI GRIP = 0.11 (A) (INPUT = 0.90)
JSI METAL = 0.03 (A) (INPUT = 1.00)



Structural component only
DWG# T-2007105

JOB NAME 408152	TRUSS NAME J41	QUANTITY 4	PLY 1	JOB DESC. GREEN PARK HOMES	DRWG NO.
Tamarack Roof Truss, Burlington				TRUSS DESC.	

Version 8.310 S Oct 29 2019 Mitek Industries, Inc. Sat Apr 25 11:29:31 2020 Page 1
ID:7vF7aG0E03cRUj6X1jSkzjWYK-Y2cwkhrJoCKCTbzSJsX7a8a7q0FFUJ5WDM29q_zNCOY



LUMBER

N. L. G. A. RULES	CHORDS	SIZE	LUMBER
E - B	2x4	DRY	No. 2
A - C	2x4	DRY	No. 2
E - D	2x4	DRY	No. 2

DRY: SEASONED LUMBER.

PLATES (table is in inches)

JT	TYPE	PLATES	W	LEN	Y	X
B	TMV+p	MT20	3.0	4.0		
E	BMV1+p	MT20	3.0	4.0		

DIMENSIONS, SUPPORTS AND LOADINGS SPECIFIED BY FABRICATOR TO BE VERIFIED BY BUILDING DESIGNER

BEARINGS

JT	FACTORED GROSS REACTION	MAXIMUM FACTORED GROSS REACTION	INPUT BRG	REQD BRG
E	319	319	5-8	5-8
C	99	99	1-8	1-8
D	23	23	1-8	1-8

SEE MITEK STANDARD DETAIL B97791H FOR CONNECTION TO JOINT(S) C, D

UNFACTORED REACTIONS

JT	COMBINED	SNOW	LIVE	PERM. LIVE	WIND	DEAD	SOIL
E	223	181/0	0/0	0/0	0/0	62/0	0/0
C	68	55/0	0/0	0/0	0/0	13/0	0/0
D	18	0/0	0/0	0/0	0/0	18/0	0/0

BEARING MATERIAL TO BE SPF NO.2 OR BETTER AT JOINT(S) E

BRACING

TOP CHORD TO BE SHEATHED OR MAX. PURLIN SPACING = 6.25 FT.
MAX. UNBRACED BOTTOM CHORD LENGTH = 10.00 FT. OR RIGID CEILING DIRECTLY APPLIED.

ALL PITCH BREAKS AND PERIMETER CORNER JOINTS MUST BE Laterally RESTRAINED.

LOADING

TOTAL LOAD CASES: (5)

MEMB.	CHORDS	MAX. FACTORED FORCE (LBS)	FACTORED VERT. LOAD (PLF)	MAX. FACTORED VERT. LOAD (LBS)	MAX. FACTORED HORIZ. LOAD (LBS)	MAX. FACTORED MOMENT (LBS-FT)
E-B	2x4	-289/0	0.0	0.0	0.02 (4)	7.81
A-B	2x4	0/28	-91.8	-91.8	0.13 (5)	10.00
B-C	2x4	-15/0	-91.8	-91.8	0.13 (1)	6.25
E-D	2x4	0/0	-18.5	-18.5	0.03 (4)	10.00

CANTILEVER ANALYSIS HAS BEEN CONSIDERED IN THIS DESIGN

TOTAL WEIGHT = 4 X 10 = 38 lb

DESIGN CRITERIA

SPECIFIED LOADS:

TOP CH.	LL	= 25.6	PSF
	DL	= 8.0	PSF
BOT CH.	LL	= 0.0	PSF
	DL	= 7.4	PSF
TOTAL LOAD		= 39.0	PSF

SPACING = 24.0 IN/C

THIS TRUSS IS DESIGNED FOR RESIDENTIAL OR SMALL BUILDING REQUIREMENTS OF PART 9, NBC 2010, NBC 2015

THIS DESIGN COMPLIES WITH:

- PART 9 OF CBC 2018, CBC 2012, ABC 2019
- PART 9 OF CBC 2012 (2019 AMENDMENT)
- CSA 088-09, CSA 088-14
- TPC 2011, TPC 2014

DESIGN ASSUMPTIONS

- OVERHANG NOT TO BE ALTERED OR CUT OFF.

(55 % OF 31.3 P.S.F. G.S.L. PLUS 8.4 P.S.F. RAIN LOAD) EQUALS 25.6 P.S.F. SPECIFIED ROOF LIVE LOAD

ALLOWABLE DEFL.(LL) = $L/360$ (0.18")
CALCULATED VERT. DEFL.(LL) = $L/999$ (0.00")
ALLOWABLE DEFL.(TL) = $L/360$ (0.18")
CALCULATED VERT. DEFL.(TL) = $L/999$ (0.00")

CSI: TC=0.13/1.00 (B-C:1), BC=0.03/1.00 (D-E:4),
WB=0.00/1.00 (W-B:0), SSI=0.11/1.00 (B-C:1)

DOL LUMBER=1.00 NAIL=1.00 LB BEND=1.10
COMP=1.10 SHEAR=1.10 TENS=1.10

COMPANION LIVE LOAD FACTOR = 1.00

AUTOSOLVE RIGHT HEEL ONLY

TRUSS PLATE MANUFACTURER IS NOT RESPONSIBLE FOR QUALITY CONTROL IN THE TRUSS MANUFACTURING PLANT.


NAIL VALUES

PLATE GRIP (DRY)	SHEAR	SECTION
(PSI)	(PL)	(PL)
MAX	MIN	MAX
MT20	618	354
	1687	788
	1987	1656

PLATE PLACEMENT TOL. = 0.250 inches

PLATE ROTATION TOL. = 5.0 Deg.

JSI GRIP=0.12 (E) (INPUT = 0.90)
JSI METAL=0.08 (B) (INPUT = 1.00)




Structural component only
DWG# T-2007106

JOB NAME	TRUSS NAME	QUANTITY	PLY	JOB DESC.	DRWG NO.
408150	C1	1	1	GREEN PARK HOMES	
Tamarack Roof Truss, Burlington				TRUSS DESC.	

Version 8.310 S Oct 29 2019 MITek Industries, Inc. Sat Apr 25 11:02:37 2020 Page 1

ID:7vF7aG0E03cRUj6X1jSrkzWYK-oX4m_oJvul_CqZaFmuZV9nkjvPNuJLXy4F4I0XzNCnm



Scale = 1:19.0

LUMBER

N. L. G. A. RULES

CHORDS	SIZE	LUMBER
F - B	2x4	DRY No.2
A - C	2x4	DRY No.2
F - D	2x4	DRY No.2
ALL WEBS	2x3	DRY No.2
DRY: SEASONED LUMBER.		

DESCR.

SPF

SPF

SPF

SPF

DIMENSIONS, SUPPORTS AND LOADINGS SPECIFIED BY FABRICATOR TO BE VERIFIED BY BUILDING DESIGNER

BEARINGS

JT	FACTORED GROSS REACTION	MAXIMUM FACTORED GROSS REACTION	INPUT BRG	REQD BRG
JT	VERT	HORZ	DOWN	HORZ
F	297	0	297	0
C	42	0	42	0
D	36	0	40	0

SEE MITEK STANDARD DETAIL B97791H FOR CONNECTION TO JOINT(S) C, D

PROVIDE ANCHORAGE AT BEARING JOINT C FOR 150 LBS. FACTORED UPLIFT

UNFACTORED REACTIONS

JT	1ST CASE	SNOW	LIVE	PERM. LIVE	WIND	DEAD	SOIL
F	208	145/0	0/0	0/0	0/0	63/0	0/0
C	29	23/-26	0/0	0/0	0/0	5/0	0/0
D	29	0/0	0/0	0/0	0/0	29/0	0/0

BEARING MATERIAL TO BE SPF NO.2 OR BETTER AT JOINT(S) F, C

BRACING

TOP CHORD TO BE SHEATHED OR MAX. PURLIN SPACING = 6.25 FT.
MAX. UNBRACED BOTTOM CHORD LENGTH = 10.00 FT. OR RIGID CEILING DIRECTLY APPLIED.

ALL PITCH BREAKS AND PERIMETER CORNER JOINTS MUST BE LATERALLY RESTRAINED.

LOADING

TOTAL LOAD CASES: (5)

CHORDS	MAX. FACTORED FORCE (LBS)	FACTORED VERT. LOAD (PLF)	FACTORED LGT. MAX. CS (LC)	MAX. UNBRACED LENGTH	WEBS	MAX. FACTORED FORCE (LBS)	MAX. CS (LC)
FR-TO		FROM TO			FR-TO		
F-B	-297/0	0.0	0.0	0.03 (1)	B-E	0/0	0.00 (1)
A-B	0/41	-91.8	-91.8	0.14 (5)			
B-C	-297/0	-91.8	-91.8	0.14 (5)			
F-E	0/0	-18.5	-18.5	0.08 (4)			
E-G	0/0	-18.5	-18.5	0.08 (4)			
G-D	0/0	-18.5	-18.5	0.08 (4)			

FACTORED CONCENTRATED LOADS (LBS)

JT	LOC.	LC1	MAX-	MAX+	FACE	DIR.	TYPE	HEEL	CONN.
G	2-0-12	I	I	---	BACK	VERT	TOTAL	---	C1

CONNECTION REQUIREMENTS

1) C1: A SUITABLE HANGER/MECHANICAL CONNECTION IS REQUIRED.

CANTILEVER ANALYSIS HAS BEEN CONSIDERED IN THIS DESIGN

TOTAL WEIGHT = 12 lb

(M)

DESIGN CRITERIA

SPECIFIED LOADS:

TOP CH.	LL = 25.6	PSF
DL = 6.0	PSF	
BOT CH.	LL = 0.0	PSF
DL = 7.4	PSF	
TOTAL LOAD	= 39.0	PSF

SPACING = 24.0 IN. C/C

THIS TRUSS IS DESIGNED FOR RESIDENTIAL OR SMALL BUILDING REQUIREMENTS OF PART 9, NBC 2010, NBC 2015

THIS DESIGN COMPLIES WITH:

- PART 9 OF CBC 2018, OBC 2012, ABC 2018
- PART 9 OF OBC 2012 (2019 AMENDMENT)
- CSA 086-09, CSA 086-14
- TPIC 2011, TPIC 2014

DESIGN ASSUMPTIONS

- OVERHANG NOT TO BE ALTERED OR CUT OFF.

(55 % OF 31.3 P.S.F. G.S.L. PLUS 8.4 P.S.F. RAIN LOAD) EQUALS 25.6 P.S.F. SPECIFIED ROOF LIVE LOAD

ALLOWABLE DEFL. (LL) = $L/360$ (0.19")
CALCULATED VERT. DEFL. (LL) = $L/999$ (0.00")
ALLOWABLE DEFL. (TL) = $L/360$ (0.19")
CALCULATED VERT. DEFL. (TL) = $L/999$ (0.01")

CSI: TC=0.14/1.00 (A-B-5), BC=0.08/1.00 (D-E-4), WB=0.00/1.00 (B-E-1), SS=0.09/1.00 (A-B-5)

DOL LUMBER=1.00 NAIL=1.00 LS BEND=1.10
COMP=1.10 SHEAR=1.10 TENS=1.10

COMPANION LIVE LOAD FACTOR = 1.00

AUTOSOLVE RIGHT HEEL ONLY

TRUSS PLATE MANUFACTURER IS NOT RESPONSIBLE FOR QUALITY CONTROL IN THE TRUSS MANUFACTURING PLANT.

NAIL VALUES

PLATE GRIP (DRY)	SHEAR	SECTION
(PSI)	(PLI)	(PLI)
MAX MIN	MAX MIN	MAX MIN
MT20	618 354	1667 788
	1987	1656

PLATE PLACEMENT TOL. = 0.250 inches

PLATE ROTATION TOL. = 5.0 Deg.

JSI GRIP = 0.20 (B) (INPUT = 0.90)
JSI METAL = 0.05 (B) (INPUT = 1.00)




Structural component only
DWG# T-2007055

JOB NAME	TRUSS NAME	QUANTITY	PLY	JOB DESC.	DRWG NO.
408150	C2	1	1	GREEN PARK HOMES	
Tamarack Roof Truss, Burlington					

Version 8.310 S Oct 29 2019 Mitek Industries, Inc. Sat Apr 25 11:02:38 2020 Page 1
ID: j7vF7aG0E03cRUj5X1jS/kzIwYK-Gke8C8KXfc63Sj9SKb4I?GVwpk52on6IvpjY_zNCn

Scale = 1:19.0



LUMBER

N. L. G. A. RULES

CHORDS	SIZE	LUMBER
E - B	2x4 DRY	No.2
A - C	2x4 DRY	No.2
E - D	2x4 DRY	No.2

ALL WEBS 2x3 DRY No.2
DRY: SEASONED LUMBER.

DESCR.
SPF
SPF
SPF

DIMENSIONS, SUPPORTS AND LOADINGS SPECIFIED BY FABRICATOR TO BE VERIFIED BY BUILDING DESIGNER

BEARINGS

JT	VERT	HORZ	DOWN	HORZ	UPLIFT	IN-SX	IN-SX
E	278	0	278	0	0	5-8	5-8
C	42	0	42	0	-36	1-8	1-8
D	18	0	20	0	0	1-8	1-8

SEE MITEK STANDARD DETAIL B97791H FOR CONNECTION TO JOINT(S) C, D

PROVIDE ANCHORAGE AT BEARING JOINT C FOR 150 LBS. FACTORED UPLIFT

UNFACTORED REACTIONS

JT	1ST CASE	MAX. MIN. COMPONENT REACTIONS
E	194	145/0 0/0 0/0 0/0 48/0 0/0
C	29	23/-26 0/0 0/0 0/0 5/0 0/0
D	14	0/0 0/0 0/0 0/0 14/0 0/0

BEARING MATERIAL TO BE SPF NO.2 OR BETTER AT JOINT(S) E, C

BRACING

TOP CHORD TO BE SHEATHED OR MAX. PURLIN SPACING = 6.25 FT.
MAX. UNBRACED BOTTOM CHORD LENGTH = 10.00 FT OR RIGID CEILING DIRECTLY APPLIED.

ALL PITCH BREAKS AND PERIMETER CORNER JOINTS MUST BE Laterally RESTRAINED.

LOADING

TOTAL LOAD CASES: (5)

CHORDS	MAX. FACTORED	FACTORED	W E B S	MAX. FACTORED
MEMB.	FORCE (LBS)	VERT. LOAD LC1 (PLF)	CS1 (LC) UNBRAC LENGTH FR-TO	MEMB. FORCE (LBS) CS1 (LC)
FR-TO				
E-B	-261/0	0.0 0.0 0.03 (1)	7.81	B-D 0/0 0.00 (1)
A-B	0/41	-91.8 -91.8 0.13 (1)	10.00	
B-C	-29/0	-91.8 -91.8 0.12 (1)	6.25	
E-D	0/0	-18.5 -18.5 0.02 (4)	10.00	

CANTILEVER ANALYSIS HAS BEEN CONSIDERED IN THIS DESIGN

TOTAL WEIGHT = 10 lb

DESIGN CRITERIA

SPECIFIED LOADS:

TOP CH.	LL = 25.6 PSF
	DL = 6.0 PSF
BOT CH.	LL = 0.0 PSF
	DL = 7.4 PSF
TOTAL LOAD	= 39.0 PSF

SPACING = 24.0 IN. C/C

THIS TRUSS IS DESIGNED FOR RESIDENTIAL OR SMALL BUILDING REQUIREMENTS OF PART 9, NBCC 2010, NBCC 2015

THIS DESIGN COMPLIES WITH:

- PART 9 OF CBC 2018, OBC 2012, ABC 2019
- PART 9 OF OBC 2012 (2019 AMENDMENT)
- CSA 086-09, CSA 086-14
- TPIC 2011, TPIC 2014

DESIGN ASSUMPTIONS

- OVERHANG NOT TO BE ALTERED OR CUT OFF.

(55 % OF 31.3 P.S.F. G.S.L. PLUS 8.4 P.S.F. RAIN LOAD) EQUALS 25.6 P.S.F. SPECIFIED ROOF LIVE LOAD

ALLOWABLE DEFL. (TL) = L/360 (0.19")
CALCULATED VERT. DEFL. (TL) = L/999 (0.00")

CS1: TC=0.13/1.00 (A-B:1), SC=0.02/1.00 (D-E:4),
WB=0.00/1.00 (B-D:1), SS1=0.08/1.00 (B-C:1)

DOL LUMBER=1.00 NAIL=1.00 LS BEND=1.10
COMP=1.10 SHEAR=1.10 TENS=1.10

COMPANION LIVE LOAD FACTOR = 1.00

TRUSS PLATE MANUFACTURER IS NOT RESPONSIBLE FOR QUALITY CONTROL IN THE TRUSS MANUFACTURING PLANT.


NAIL VALUES

PLATE GRIP (DRY)	SHEAR	SECTION
(PSI)	(PL)	(PL)
MAX MIN	MAX MIN	MAX MIN
MT20	618 354 1687 788 1987 1655	

PLATE PLACEMENT TOL. = 0.250 inches

PLATE ROTATION TOL. = 5.0 Deg.

JSI GRIP= 0.20 (B) (INPUT = 0.90)
JSI METAL= 0.05 (B) (INPUT = 1.00)




Structural component only
DWG# T-2007056

JOB NAME	TRUSS NAME	QUANTITY	PLY	JOB DESC.	DRWG NO.
408152	C40	4	1	GREEN PARK HOMES	
Tamarack Roof Truss, Burlington					

Version 8.310 S Oct 29 2019 Mitek Industries, Inc. Sat Apr 25 11:29:21 2020 Page 1
ID:7vF7aG0E03cRUj6X1jSkziWYK-q778eGk1873dG3CXkLFA19Pt_o08nd2voddJZzNCOI

Scale = 1:17.5



LUMBER

N. L. G. A. RULES	CHORDS	SIZE	LUMBER
E - B	2x4	DRY	No.2
A - C	2x4	DRY	No.2
E - D	2x4	DRY	No.2

DRY: SEASONED LUMBER.

PLATES (table is in inches)

JT TYPE	PLATES	W	LEN	Y	X
B	TMV+p	MT20	3.0	4.0	
E	BMV1+p	MT20	3.0	4.0	

DIMENSIONS, SUPPORTS AND LOADINGS SPECIFIED BY FABRICATOR TO BE VERIFIED BY BUILDING DESIGNER

JT	FACTORED GROSS REACTION		MAXIMUM FACTORED GROSS REACTION		INPUT BRG IN-SX	REQD BRG IN-SX
	VERT	HORZ	DOWN	HORZ		
E	405	0	405	0	5-8	5-8
C	130	0	130	0	1-8	1-8
D	45	0	50	0	1-8	1-8

SEE MITEK STANDARD DETAIL 897791H FOR CONNECTION TO JOINT(S) C, D

UNFACTORED REACTIONS

1ST CASE		MAX./MIN. COMPONENT REACTIONS					
JT	COMBINED	SNOW	LIVE	PERM. LIVE	WIND	DEAD	SOIL
E	288	190 / 0	0 / 0	0 / 0	0 / 0	96 / 0	0 / 0
C	90	73 / 0	0 / 0	0 / 0	0 / 0	17 / 0	0 / 0
D	38	0 / 0	0 / 0	0 / 0	0 / 0	38 / 0	0 / 0

BEARING MATERIAL TO BE SPF NO.2 OR BETTER AT JOINT(S) E, C

BRACING

TOP CHORD TO BE SHEATHED OR MAX. PURLIN SPACING = 6.25 FT.
MAX. UNBRACED BOTTOM CHORD LENGTH = 10.00 FT OR RIGID CEILING DIRECTLY APPLIED.

ALL PITCH BREAKS AND PERIMETER CORNER JOINTS MUST BE Laterally RESTRAINED.

LOADING

TOTAL LOAD CASES: (4)

MEMB.	CHORDS		FACTORED		MAX. MEMB. FORCE (LBS)	MAX. FACTORED FORCE (LBS)	MAX. FACTORED CSI (LC)
	MAX. FORCE (LBS)	VERT. LOAD (LBS)	VERT. LOAD (LBS)	MAX. MEMB. FORCE (LBS)			
FR-TO							
E-B	-342 / 0	0.0	0.0	0.13 (4)	7.81		
A-B	0 / 28	-91.8	-91.8	0.12 (1)	10.00		
B-C	-19 / 0	-91.8	-91.8	0.22 (1)	6.25		
E-D	0 / 0	-18.5	-18.5	0.13 (4)	10.00		

DESIGN CRITERIA

SPECIFIED LOADS:
TOP CH. LL = 25.6 PSF
DL = 6.0 PSF
BOT CH. LL = 0.0 PSF
DL = 7.4 PSF
TOTAL LOAD = 39.0 PSF

SPACING = 24.0 IN. C/C

THIS TRUSS IS DESIGNED FOR RESIDENTIAL OR SMALL BUILDING REQUIREMENTS OF PART 9, NBC 2010, NBC 2015

THIS DESIGN COMPLIES WITH:
- PART 9 OF BCBC 2018, OBC 2012, ABC 2019
- PART 9 OF OBC 2012 (2019 AMENDMENT)
- CSA 088-06, CSA 086-14
- TPIC 2011, TPIC 2014

DESIGN ASSUMPTIONS

- OVERHANG NOT TO BE ALTERED OR CUT OFF.

(55 % OF 31.3 P.S.F. G.S.L. PLUS 8.4 P.S.F. RAIN LOAD) EQUALS 25.6 P.S.F. SPECIFIED ROOF LIVE LOAD

ALLOWABLE DEFL. (LL) = $L/360$ (0.20")
CALCULATED VERT. DEFL. (LL) = $L/999$ (0.00")
ALLOWABLE DEFL. (TL) = $L/360$ (0.20")
CALCULATED VERT. DEFL. (TL) = $L/999$ (0.03")

CSI: TC=0.22/1.00 (B-C:1), BC=0.13/1.00 (D-E:4),
WB=0.00/1.00 (n/a:0), SSI=0.15/1.00 (B-C:1)

DCL LUMBER=1.00 NAIL=1.00 LS BEND=1.10
COMP=1.10 SHEAR=1.10 TENS=1.10

COMPANION LIVE LOAD FACTOR = 1.00

AUTOSOLVE RIGHT HEEL ONLY

TRUSS PLATE MANUFACTURER IS NOT RESPONSIBLE FOR QUALITY CONTROL IN THE TRUSS MANUFACTURING PLANT.

NAIL VALUES

PLATE GRIP (DRY)	SHEAR	SECTION
(PSI)	(PL)	(PL)
MAX	MIN	MAX
MT20	618	354
	1667	788
	1987	1668


PLATE PLACEMENT TOL = 0.250 inches

PLATE ROTATION TOL = 5.0 Deg.

JSI GRIP = 0.14 (2) (INPUT = 0.90)
JSI METAL = 0.09 (5) (INPUT = 1.00)



Structural component only
DWG# T-2007098



LUMBER			
N. L. G. A. RULES	SIZE	DRY	LUMBER
E - B	2x4	DRY	No.2
A - C	2x4	DRY	No.2
E - D	2x4	DRY	No.2

DRY: SEASONED LUMBER.

PLATES (table is in inches)				
JT TYPE	PLATES	W	LEN	Y X
B TMV+p	MT20	3.0	4.0	
E BMV1+p	MT20	3.0	4.0	

DIMENSIONS, SUPPORTS AND LOADINGS SPECIFIED BY FABRICATOR TO BE VERIFIED BY BUILDING DESIGNER

FACTORED GROSS REACTION		MAXIMUM FACTORED GROSS REACTION		INPUT BRG		REQD BRG	
JT	VERT	HORZ	DOWN	HORZ	UPLIFT	IN-SX	IN-SX
E	284	0	284	0	0	5-8	5-8
C	63	0	63	0	0	1-8	1-8
D	44	0	52	0	0	1-8	1-8

SEE MITEK STANDARD DETAIL B97791H FOR CONNECTION TO JOINT(S) C, D

UNFACTORED REACTIONS		MAX./MIN. COMPONENT REACTIONS	
JT	COMBINED	SNOW	LIVE
E	200	137/0	0/0
C	46	21/0	0/0
D	36	0/-3	0/0

BEARING MATERIAL TO BE SPF NO.2 OR BETTER AT JOINT(S) E, C

BRACING
TOP CHORD TO BE SHEATHED OR MAX. PURLIN SPACING = 10.00 FT.
MAX. UNBRACED BOTTOM CHORD LENGTH = 10.00 FT. OR RIGID CEILING DIRECTLY APPLIED.

ALL PITCH BREAKS AND PERIMETER CORNER JOINTS MUST BE Laterally RESTRAINED.

LOADING
TOTAL LOAD CASES: (7)

CHORDS		WEBS	
MEMB.	MAX. FACTORED FORCE (LBS)	MAX. FACTORED VERT. LOAD (LBS)	MAX. FACTORED HORZ. LOAD (LBS)
FR-TO			
E-B	-227/0	0.0	0.0 0.11 (4)
A-B	0/28	-91.8	-91.8 0.12 (1)
B-C	-9/9	-91.8	-91.8 0.08 (4)
E-F	0/0	-18.5	-18.5 0.14 (4)
F-G	0/0	-18.5	-18.5 0.14 (4)
G-D	0/0	-18.5	-18.5 0.14 (4)

FACTORED CONCENTRATED LOADS (LBS)		FACE		DIR.		TYPE		HEEL		CONN.	
JT	LOC.	LC1	MAX.	MAX.	BACK	VERT	TOTAL	---	---	C1	C1
F	1-11-4	7	1	12	BACK	VERT	TOTAL	---	---	C1	C1
G	3-11-4	1	1	---	BACK	VERT	TOTAL	---	---	C1	C1

CONNECTION REQUIREMENTS

- 1) C1: A SUITABLE HANGER/MECHANICAL CONNECTION IS REQUIRED.

TOTAL WEIGHT = 4 X 12 = 48 lb

DESIGN CRITERIA

SPECIFIED LOADS:
TOP CH. LL = 25.6 PSF
DL = 6.0 PSF
BOT CH. LL = 0.0 PSF
DL = 7.4 PSF
TOTAL LOAD = 39.0 PSF

SPACING = 24.0 IN. OC

THIS TRUSS IS DESIGNED FOR RESIDENTIAL OR SMALL BUILDING REQUIREMENTS OF PART 9, NBC 2010, NBC 2015

THIS DESIGN COMPLIES WITH:
- PART 9 OF CBC 2010, CBC 2012, ABC 2019
- PART 9 OF OBC 2012 (2019 AMENDMENT)
- CSA 088-09, CSA 088-14
- TPIC 2011, TPIC 2014

DESIGN ASSUMPTIONS
- OVERHANG NOT TO BE ALTERED OR CUT OFF.

(55% OF 31.3 P.S.F. G.S.L. PLUS 8.4 P.S.F. RAIN LOAD) EQUALS 25.6 P.S.F. SPECIFIED ROOF LIVE LOAD

ALLOWABLE DEFL.(LL) = L/360 (0.20")
CALCULATED VERT. DEFL.(LL) = L/999 (0.01")
ALLOWABLE DEFL.(TL) = L/360 (0.20")
CALCULATED VERT. DEFL.(TL) = L/999 (0.04")

CSI: TC=0.12/1.00 (A-B:1), BC=0.14/1.00 (D-E:4),
WB=0.00/1.00 (n/a:0), SS=0.09/1.00 (A-B:1)

DOL LUMBER=0.98 NAIL=0.98 LS BEND=1.10
COMP=1.10 SHEAR=1.10 TENS=1.10

COMPANION LIVE LOAD FACTOR = 1.00

AUTOSOLVE RIGHT HEEL ONLY

TRUSS PLATE MANUFACTURER IS NOT RESPONSIBLE FOR QUALITY CONTROL IN THE TRUSS MANUFACTURING PLANT.

NAIL VALUES
PLATE GRIP(DRY) SHEAR SECTION
(PSI) (PLI) (PLI)
MAX MIN MAX MIN MAX MIN
MT20 618 354 1667 788 1987 1656

PLATE PLACEMENT TOL. = 0.250 inches

PLATE ROTATION TOL. = 5.0 Deg.


JSI GRIP=0.10 (E) (INPUT = 0.80)
JSI METAL=0.06 (B) (INPUT = 1.00)



Structural component only.
DWG# T-2007099

JOB NAME	TRUSS NAME	QUANTITY	PLY	JOB DESC.	DRWG NO.
408152	C42	4	1	GREEN PARK HOMES	
Tamarack Roof Truss, Burlington				TRUSS DESC.	

Version 8.310 S Oct 29 2019 Mitek Industries, Inc. Set Apr 25 11:29:24 2020 Page 1
ID:7vF7aG0E03cRUj6X1jSkzIWK-FihGGHmvR2R87Xx6PtvMognw6CsuL8MVcmrHwuzNCO



LUMBER

N. L. G. A. RULES			
CHORDS	SIZE		LUMBER
E - B	2x4	DRY	No.2
A - C	2x4	DRY	No.2
E - D	2x4	DRY	No.2

DRY: SEASONED LUMBER.

PLATES (table is in inches)

JT TYPE	PLATES	W	LEN	Y	X
B TMV+p	MT20	3.0	4.0		
E BMV1+p	MT20	3.0	4.0		

DIMENSIONS, SUPPORTS AND LOADINGS SPECIFIED BY FABRICATOR TO BE VERIFIED BY BUILDING DESIGNER

BEARINGS

JT	FACTORED GROSS REACTION	MAXIMUM FACTORED GROSS REACTION	INPUT BRG IN-SX	REQD BRG IN-SX
E	351	351	5-8	5-8
C	130	130	1-8	1-8
D	16	17	1-8	1-8

SEE MITEK STANDARD DETAIL B97791H FOR CONNECTION TO JOINT(S) C, D

UNFACTORED REACTIONS

JT	1ST LCASE	MAX/MIN. COMPONENT REACTIONS	PERM. LIVE	WIND	DEAD	SOIL
E	COMBINED	190/0	0/0	0/0	60/0	0/0
C		73/0	0/0	0/0	17/0	0/0
D		0/0	0/0	0/0	12/0	0/0

BEARING MATERIAL TO BE SPF NO.2 OR BETTER AT JOINT(S) E

BRACING

TOP CHORD TO BE SHEATHED OR MAX. PURLIN SPACING = 6.25 FT.
MAX. UNBRACED BOTTOM CHORD LENGTH = 10.00 FT OR RIGID CEILING DIRECTLY APPLIED.

ALL PITCH BREAKS AND PERIMETER CORNER JOINTS MUST BE Laterally RESTRAINED.

LOADING

TOTAL LOAD CASES: (5)

MEMB.	CHORDS	MAX. FACTORED FORCE (LBS)	FACTORED VERT. LOAD (PLF)	LC1 MAX	LC2 MAX	UNBRACED LENGTH FR-TO	MEMB.	WEBS	MAX. FACTORED FORCE (LBS)	LC1 MAX	LC2 MAX
E-B		-342/0	0.0	0.0	0.01 (4)	7.81					
A-B		0/28	-91.8	-91.8	0.13 (5)	10.00					
B-C		-19/0	-91.8	-91.8	0.22 (1)	6.25					
E-D		0/0	-18.5	-18.5	0.02 (4)	10.00					

CANTILEVER ANALYSIS HAS BEEN CONSIDERED IN THIS DESIGN

TOTAL WEIGHT = 4 X 10 = 38 lb

DESIGN CRITERIA

SPECIFIED LOADS:

TOP CH.	LL	=	25.6	PSF
	DL	=	8.0	PSF
BOT CH.	LL	=	0.0	PSF
	DL	=	7.4	PSF
TOTAL LOAD	=	38.0	PSF	

SPACING = 24.0 IN. C/C

THIS TRUSS IS DESIGNED FOR RESIDENTIAL OR SMALL BUILDING REQUIREMENTS OF PART 9, NBC 2010, NBC 2015

THIS DESIGN COMPLIES WITH:

- PART 9 OF CBC 2018, OBC 2012, ABC 2019
- PART 9 OF OBC 2012 (2019 AMENDMENT)
- CSA 066-09, CSA 086-14
- TPIC 2011, TPIC 2014

DESIGN ASSUMPTIONS

- OVERHANG NOT TO BE ALTERED OR CUT OFF.

155 % OF 31.3 P.S.F. G.S.L. PLUS 8.4 P.S.F. RAIN LOAD) EQUALS 25.6 P.S.F. SPECIFIED ROOF LIVE LOAD

ALLOWABLE DEFL.(LL) = $L/360$ (0.19")
CALCULATED VERT. DEFL.(LL) = $L/999$ (0.00")
ALLOWABLE DEFL.(TL) = $L/360$ (0.19")
CALCULATED VERT. DEFL.(TL) = $L/999$ (0.00")

CSI: TC=0.22/1.00 (B-C:1), BC=0.02/1.00 (D-E:4), WB=0.00/1.00 (n/a:0), SSI=0.15/1.00 (B-C:1)

DOL LUMBER=1.00 NAIL=1.00 LS BEND=1.10
COMP=1.10 SHEAR=1.10 TENS=1.10

COMPANION LIVE LOAD FACTOR = 1.00

AUTOSOLVE RIGHT HEEL ONLY

TRUSS PLATE MANUFACTURER IS NOT RESPONSIBLE FOR QUALITY CONTROL IN THE TRUSS MANUFACTURING PLANT.

NAIL VALUES

PLATE GRIP(DRY)	SHEAR	SECTION
(PSI)	(PLI)	(PLI)
MAX MIN	MAX MIN	MAX MIN
MT20	518 354	1987 768 1987 1656

PLATE PLACEMENT TOL. = 0.250 inches

PLATE ROTATION TOL. = 5.0 Deg.

JSI GRIP= 0.14 (E) (INPUT = 0.90)
JSI METAL= 0.09 (B) (INPUT = 1.00)




Structural component only
DWG# T-2007100

JOB NAME	TRUSS NAME	QUANTITY	PLY	JOB DESC.	DRWG NO.
408152	C43	4	1	GREEN PARK HOMES	
Tamarack Roof Truss, Burlington				TRUSS DESC.	

Version 8.310 S Oct 29 2019 Mitek Industries, Inc. Sat Apr 25 11:29:25 2020 Page 1
ID:37vF7aG0E03cRUj6X1JSkzIWYK-juETdnYCMa2lgWibzObKik7UcCo4bcaqQbrSKzNCOe

Scale = 1/12.1



TOTAL WEIGHT = 4 X 7 = 28 lb

LUMBER			
N. L. G. A. RULES	SIZE	DRY	LUMBER
E - B	2x4	DRY	No.2
A - C	2x4	DRY	No.2
E - D	2x4	DRY	No.2

DRY: SEASONED LUMBER.

PLATES (table is in inches)

JT	TYPE	PLATES	W	LEN	Y	X
B	TMV+p	MT20	3.0	4.0		
E	BMV1+p	MT20	3.0	4.0		

DIMENSIONS, SUPPORTS AND LOADINGS SPECIFIED BY FABRICATOR TO BE VERIFIED BY BUILDING DESIGNER

JT	FACTORED GROSS REACTION		MAXIMUM FACTORED GROSS REACTION		INPUT BRG	REQD BRG
	VERT	HORZ	DOWN	HORZ		
E	271	0	271	0	5-8	5-8
C	45	0	45	0	1-8	1-8
D	8	0	17	0	1-8	1-8

SEE MITEK STANDARD DETAIL B97791H FOR CONNECTION TO JOINT(S) C, D

PROVIDE ANCHORAGE AT BEARING JOINT C FOR 150 LBS FACTORED UPLIFT
PROVIDE ANCHORAGE AT BEARING JOINT D FOR 150 LBS FACTORED UPLIFT

UNFACTORED REACTIONS

JT	1ST CASE	SNOW	LIVE	PERM. LIVE	WIND	DEAD	SOIL
E	188	141/0	0/0	0/0	0/0	47/0	0/0
C	31	24/-16	0/0	0/0	0/0	7/0	0/0
D	7	0/-8	0/0	0/0	0/0	12/0	0/0

BEARING MATERIAL TO BE SPF NO.2 OR BETTER AT JOINT(S) E, C

BRACING

TOP CHORD TO BE SHEATHED OR MAX. PURLIN SPACING = 6.25 FT.
MAX. UNBRACED BOTTOM CHORD LENGTH = 10.00 FT OR RIGID CEILING DIRECTLY APPLIED.
ALL PITCH BREAKS AND PERIMETER CORNER JOINTS MUST BE Laterally RESTRAINED.

LOADING

TOTAL LOAD CASES: (5)

MEMB.	CHORDS		FACTORED		WEBS		FACTORED	
	FORCE (LBS)	VERT. LOAD (PL)	MAX	CS1 (LC)	MAX	MEMB.	FORCE (LBS)	MAX
FR-TO						FR-TO		
E-B	-244/0	0.0	0.0	0.04 (5)	7.81			
A-B	0/28	-91.8	-91.8	0.12 (1)	10.00			
B-C	-17/0	-91.8	-91.8	0.09 (1)	6.25			
E-D	0/0	-18.5	-18.5	0.04 (5)	10.00			

CANTILEVER ANALYSIS HAS BEEN CONSIDERED IN THIS DESIGN

DESIGN CRITERIA

SPECIFIED LOADS:
TOP CH. LL = 25.8 PSF
DL = 6.0 PSF
BOT CH. LL = 0.0 PSF
DL = 7.4 PSF
TOTAL LOAD = 39.0 PSF

SPACING = 24.0 IN. OC

THIS TRUSS IS DESIGNED FOR RESIDENTIAL OR SMALL BUILDING REQUIREMENTS OF PART 9, NBC 2010, NBC 2015

THIS DESIGN COMPLIES WITH:

- PART 9 OF CBC 2018, CBC 2012, ABC 2019
- PART 9 OF CBC 2012 (2019 AMENDMENT)
- CSA 088-09, CSA 088-14
- TPIC 2011, TPIC 2014

DESIGN ASSUMPTIONS

OVERHANG NOT TO BE ALTERED OR CUT OFF.

(55% OF 31.3 P.S.F. G.S.L. PLUS 8.4 P.S.F. RAIN LOAD) EQUALS 25.8 P.S.F. SPECIFIED ROOF LIVE LOAD

ALLOWABLE DEFL.(LL) = L/360 (0.19")
CALCULATED VERT. DEFL.(LL) = L/999 (0.00")
ALLOWABLE DEFL.(TL) = L/360 (0.19")
CALCULATED VERT. DEFL.(TL) = L/999 (0.00")

CS1: TC=0.12/1.00 (A-B:1), BC=0.04/1.00 (D-E:5),
WB=0.00/1.00 (n/a:0), SS1=0.09/1.00 (A-B:1)

DCL LUMBER=1.00 NAIL=1.00 LS BEND=1.10
COMP=1.10 SHEAR=1.10 TENS=1.10

COMPANION LIVE LOAD FACTOR = 1.00

AUTOSOLVE RIGHT HEEL ONLY

TRUSS PLATE MANUFACTURER IS NOT RESPONSIBLE FOR QUALITY CONTROL IN THE TRUSS MANUFACTURING PLANT.


NAIL VALUES

PLATE	GRIP(DRY)	SHEAR	SECTION
(PSI)	(PL)	(PL)	(PL)
MAX	MIN	MAX	MIN
MT20	618	354	1667
	788		1987
			1656

PLATE PLACEMENT TOL. = 0.250 inches

PLATE ROTATION TOL. = 5.0 Deg.


JSI GRIP= 0.10 (E) (INPUT = 0.50)
JSI METAL= 0.07 (B) (INPUT = 1.00)



Structural component only
DWG# T-2007101

JOB NAME	TRUSS NAME	QUANTITY	PLY	JOB DESC.	DRWG NO.
408152	C44	2	1	GREEN PARK HOMES	
Tamarack Roof Truss, Burlington		TRUSS DESC.			

Version 8.310 5 Oct 29 2019 Mitek Industries, Inc. Sat Apr 25 11:29:26 2020 Page 1
ID:7vF?ag0E03cRUj6X1SrkzIwYK-B4o1hzoAzgIvMq5UXlxq15IH?X4p2an34KO_rzNCOd



TOTAL WEIGHT = 2 X 8 = 17 lb

LUMBER

N. L. G. A. RULES

CHORDS	SIZE	LUMBER
E - B	2x4	DRY No.2
A - C	2x4	DRY No.2
E - D	2x4	DRY No.2

DRY: SEASONED LUMBER.

PLATES (tablets in inches)

JT TYPE	PLATES	W	LEN	Y	X
B TMV+p	MT20	3.0	4.0		
E BMV1+p	MT20	3.0	4.0		

DIMENSIONS, SUPPORTS AND LOADINGS SPECIFIED BY FABRICATOR TO BE VERIFIED BY BUILDING DESIGNER

BEARINGS

JT	VERT	HORZ	DOWN	HORZ	UPLIFT	IN-SX	REQD
E	264	0	264	0	0	5-8	5-8
C	86	0	86	0	0	1-8	1-8
D	23	0	23	0	0	1-8	1-8

SEE MITEK STANDARD DETAIL B97791H FOR CONNECTION TO JOINT(S) C, D

UNFACTORED REACTIONS

JT	COMBINED	SNOW	LIVE	PERM. LIVE	WIND	DEAD	SOIL
E	185	130 / 0	0 / 0	0 / 0	0 / 0	55 / 0	0 / 0
C	46	37 / 0	0 / 0	0 / 0	0 / 0	9 / 0	0 / 0
D	18	0 / 0	0 / 0	0 / 0	0 / 0	18 / 0	0 / 0

BEARING MATERIAL TO BE SPF NO.2 OR BETTER AT JOINT(S) E, C

BRACING

TOP CHORD TO BE SHEATHED OR MAX. PURLIN SPACING = 10.00 FT.
MAX. UNBRACED BOTTOM CHORD LENGTH = 10.00 FT. OR RIGID CEILING DIRECTLY APPLIED.

ALL PITCH BREAKS AND PERIMETER CORNER JOINTS MUST BE LATERALLY RESTRAINED.

LOADING

TOTAL LOAD CASES: (5)

CHORDS		WEBS	
MEMB.	MAX. FACTORED FORCE (LBS)	MAX. FACTORED VERT. LOAD LC1 (PLF)	MAX. FACTORED UNBRAC LENGTH FR-TO
FR-TO			
E-B	-234 / 0	0.0	0.02 (4)
A-B	0 / 28	-91.8	0.13 (5)
B-C	-10 / 0	-91.8	0.08 (1)
E-F	0 / 0	-18.5	0.03 (4)
F-D	0 / 0	-18.5	0.03 (4)

FACTORED CONCENTRATED LOADS (LBS)

JT	LOC.	LC1	MAX-	MAX+	FACE	DIR.	TYPE	HEEL	CONN.
F	2-0-12	1	1	---	FRONT	VERT	TOTAL	---	C1

CONNECTION REQUIREMENTS

1) C1: A SUITABLE HANGER/MECHANICAL CONNECTION IS REQUIRED.

CANTILEVER ANALYSIS HAS BEEN CONSIDERED IN THIS DESIGN

DESIGN CRITERIA

SPECIFIED LOADS:

TOP CH.	LL = 25.6	PSF
DL = 6.0	PSF	
BOT CH.	LL = 0.0	PSF
DL = 7.4	PSF	
TOTAL LOAD = 39.0	PSF	

SPACING = 24.0 IN/C

THIS TRUSS IS DESIGNED FOR RESIDENTIAL OR SMALL BUILDING REQUIREMENTS OF PART 9, NBCC 2010, NBCC 2015

THIS DESIGN COMPLIES WITH:

- PART 9 OF BCBC 2018, OBC 2012, ABC 2019
- PART 9 OF OBC 2012 (2019 AMENDMENT)
- CSA 086-09, CSA 086-14
- TPIC 2011, TPIC 2014

DESIGN ASSUMPTIONS

- OVERHANG NOT TO BE ALTERED OR CUT OFF.

(55 % OF 31.3 P.S.F. G.S.L. PLUS 8.4 P.S.F. RAIN LOAD) EQUALS 25.6 P.S.F. SPECIFIED ROOF LIVE LOAD

ALLOWABLE DEFL. (LL) = $L/360$ (0.19")
CALCULATED VERT. DEFL. (LL) = $L/989$ (0.00")
ALLOWABLE DEFL. (TL) = $L/360$ (0.19")
CALCULATED VERT. DEFL. (TL) = $L/989$ (0.00")

CSI: TC=0.13/1.00 (A-B-5), BC=0.02/1.00 (D-E-4), WB=0.00/1.00 (v-a-0), SS=0.10/1.00 (A-B-5)

DOL LUMBER=1.00 NAIL=1.00 LS BEND=1.10
COMP=1.10 SHEAR=1.10 TENS=1.10

COMPANION LIVE LOAD FACTOR = 1.00

AUTOSOLVE RIGHT HEEL ONLY

TRUSS PLATE MANUFACTURER IS NOT RESPONSIBLE FOR QUALITY CONTROL IN THE TRUSS MANUFACTURING PLANT.


NAIL VALUES

PLATE GRIP (DRY)	SHEAR	SECTION
(PSI)	(PLI)	(PLI)
MAX	MIN	MAX
MT20	618	354
	1667	788
	1987	1556

PLATE PLACEMENT TOL. = 0.250 inches

PLATE ROTATION TOL. = 5.0 Deg.


JSI GRIP= 0.10 (E) (INPUT = 0.30)
JSI METAL= 0.06 (B) (INPUT = 1.00)



Structural component only
DWG# T-2007102

JOB NAME	TRUSS NAME	QUANTITY	PLY	JOB DESC.	DRWG NO.
408152	C45	2	1	GREEN PARK HOMES	
Tamarack Roof Truss, Burlington				TRUSS DESC.	

Version 8.310 S Oct 29 2019 Mitek Industries, Inc. Sat Apr 25 11:29:27 2020 Page 1
ID:7vF?aG0E03cRUj6X1JSkziWYK-IHMPuJookzqm_gh40S3PIPT_PIZYV6xik4xXDzNCC0



Scale = 1/4\"/>

LUMBER			
N. L. G. A. RULES	SIZE	DRY	LUMBER
E - B	2x4	DRY	No.2
A - C	2x4	DRY	No.2
E - D	2x4	DRY	No.2

DRY: SEASONED LUMBER.

PLATES (table is in inches)				
JT	TYPE	PLATES	W	LEN Y X
B	TMV+p	MT20	3.0	4.0
E	BMV1+p	MT20	3.0	4.0

DIMENSIONS, SUPPORTS AND LOADINGS SPECIFIED BY FABRICATOR TO BE VERIFIED BY BUILDING DESIGNER

JT	FACTORED GROSS REACTION		MAXIMUM FACTORED GROSS REACTION		INPUT BRG IN-SX	REQD BRG IN-SX
	VERT	HORZ	DOWN	HORZ		
E	254	0	254	0	5-8	5-8
C	66	0	66	0	1-8	1-8
D	16	0	16	0	1-8	1-8

SEE MITEK STANDARD DETAIL B97781H FOR CONNECTION TO JOINT(S) C, D

UNFACTORED REACTIONS

JT	1ST LCASE	SNOW	LIVE	PERM. LIVE	WIND	DEAD	SOIL
E	177	138 / 0	0 / 0	0 / 0	0 / 0	47 / 0	0 / 0
C	48	37 / 0	0 / 0	0 / 0	0 / 0	9 / 0	0 / 0
D	13	0 / 0	0 / 0	0 / 0	0 / 0	13 / 0	0 / 0

BEARING MATERIAL TO BE SPF NO.2 OR BETTER AT JOINT(S) E, C

BRACING

TOP CHORD TO BE SHEATHED OR MAX. PURLIN SPACING = 10.00 FT.
MAX. UNBRACED BOTTOM CHORD LENGTH = 10.00 FT. OR RIGID CEILING DIRECTLY APPLIED.

ALL PITCH BREAKS AND PERIMETER CORNER JOINTS MUST BE LATERALLY RESTRAINED.

LOADING

TOTAL LOAD CASES: (5)

MEMB.	CHORDS		WEBS	
	MAX. FACTORED FORCE (LBS)	FACTORED VERT. LOAD LC1 (PLF)	MAX. FACTORED UNBRAC LENGTH FR-TO	MAX. FACTORED FORCE (LBS)
FR-TO				
E-B	-234 / 0	0.0	0.0 0.01 (4)	7.81
A-B	0 / 28	-91.8	-91.8 0.12 (1)	10.00
B-C	-10 / 0	-91.8	-91.8 0.08 (1)	10.00
E-D	0 / 0	-18.5	-18.5 0.02 (4)	10.00

CANTILEVER ANALYSIS HAS BEEN CONSIDERED IN THIS DESIGN

TOTAL WEIGHT = 2 X 7 = 15 lb

DESIGN CRITERIA

SPECIFIED LOADS:

TOP CH.	LL = 25.6	PSF
DL = 6.0	PSF	
BOT CH.	LL = 0.0	PSF
DL = 7.4	PSF	
TOTAL LOAD = 39.0	PSF	

SPACING = 24.0 IN. OC

THIS TRUSS IS DESIGNED FOR RESIDENTIAL OR SMALL BUILDING REQUIREMENTS OF PART 9, NBC 2010, NBC 2015

THIS DESIGN COMPLIES WITH:

- PART 9 OF CBC 2018, CBC 2012, ABC 2019
- PART 9 OF CBC 2012 (2019 AMENDMENT)
- CSA 088-09, CSA 088-14
- TPIC 2011, TPIC 2014

DESIGN ASSUMPTIONS

- OVERHANG NOT TO BE ALTERED OR CUT OFF.

(55 % OF 31.3 P.S.F. G.S.L. PLUS 8.4 P.S.F. RAIN LOAD) EQUALS 25.6 P.S.F. SPECIFIED ROOF LIVE LOAD

ALLOWABLE DEFL. (LL) = $L/360$ (0.19')
CALCULATED VERT. DEFL. (LL) = $L/989$ (0.00')
ALLOWABLE DEFL. (TL) = $L/360$ (0.19')
CALCULATED VERT. DEFL. (TL) = $L/999$ (0.00')

CSI: TC=0.12/1.00 (A-B:1), BC=0.02/1.00 (D-E:4), WB=0.00/1.00 (n/a:0), SS=0.09/1.00 (A-B:1)

DOL LUMBER=1.00 NAIL=1.00 LS BEND=1.10
COMP=1.10 SHEAR=1.10 TENS=1.10

COMPANION LIVE LOAD FACTOR = 1.00

AUTOSOLVE RIGHT HEEL ONLY

TRUSS PLATE MANUFACTURER IS NOT RESPONSIBLE FOR QUALITY CONTROL IN THE TRUSS MANUFACTURING PLANT.


NAIL VALUES

PLATE	GRIP(DRY)	SHEAR	SECTION
(PSI)	(PLI)	(PLI)	(PLI)
MAX MIN	MAX MIN	MAX MIN	MAX MIN
MT20	618 354	1667 788	1987 1656

PLATE PLACEMENT TOL. = 0.250 inches

PLATE ROTATION TOL. = 5.0 Deg.

JSI GRIP= 0.10 (E) (INPUT = 0.90)
JSI METAL= 0.06 (B) (INPUT = 1.00)



Structural component only
DWG# T-2007103

LUL/LUS/LJS/HUS/HHUS/HGUS

Standard and Double-Shear Joist Hangers



This product is preferable to similar connectors because of
a) easier installation, b) higher capacities, c) lower installed
cost, or a combination of these features.

Most hangers in this series have double-shear nailing — an innovation that distributes the load through two points on each joist nail for greater strength. This allows for fewer nails, faster installation, and the use of all common nails for the same connection. (Do not bend or remove tabs)

Double-shear hangers range from the light capacity LUS hangers to the highest capacity HGUS hangers. For medium load truss applications, the HUS offers a lower cost alternative and easier installation than the HGUS hangers, while providing greater load capacity and bearing than the LUS.

Material: See table on pp. 258–259.


Finish: Galvanized. Some products available in stainless steel or ZMAX[®] coating; see Corrosion Information, pp. 20–24.

Installation:

- Use all specified fasteners; see General Notes.
- Nails must be driven at an angle through the joist or truss into the header to achieve the tabulated resistances (except LUL).
- Where 16d commons are specified, 10d commons may be used at 0.83 of the tabulated factored resistance.
- Not designed for welded or nailer applications.
- With single ply 2x carrying members, use 10d x 1½" nails into the header and 10d commons into the joist, and reduce the resistance to 0.64 of the table value where 16d nails are specified and 0.77 where 10d nails are specified.

Options:

- LUS, LJS, LUL and HUS hangers cannot be modified.
- Other sizes available; consult your Simpson Strong-Tie representative.
- See Hanger Options information on p. 126.




Double-Shear Nailing Top View




Double-Shear Nailing Side View; Do not bend tab




Dome Double-Shear Nailing Side View (available on some models)
U.S. Patent 5,603,580




LUS28




LU26L




HUS210
(HUS26, HUS28, and HHUS similar)



HGUS28-2




HHUS210-2



LJS26DS

Typical HUS26 Installation with Reduced Heel Height
(Truss Designer to provide fastener quantity for connecting multiple members together)



LUL/LUS/LJS/HUS/HHUS/HGUS**HHUS/HGUS**

See Hanger Options information on pp. 125–127.



HHUS — Sloped and/or Skewed Seat

- HHUS hangers can be skewed to a maximum of 45° and/or sloped to a maximum of 45°
- For skew only, maximum factored down resistance is 0.85 of the table value
- For sloped only or sloped and skewed hangers, the maximum factored down resistance is 0.72 of the table value
- Uplift resistances for sloped/skewed conditions are 0.62 of the table value
- The joist must be bevel-cut to allow for double-shear nailing

HGUS — Skewed Seat

- HGUS hangers can be skewed only to a maximum of 45°. Factored resistances are:

HGUS Seat Width	Joist	Down Resistance	Uplift
$W < 2"$	Bevel or square cut	0.62 of table value	0.46 of table value
$2" < W < 6"$	Bevel cut	0.67 of table value	0.41 of table value
$2" < W < 6"$	Square cut	0.46 of table value	0.41 of table value
$W > 6"$	Bevel cut	0.75 of table value	0.41 of table value



Top View HHUS Hanger Skewed Right
(joist must be bevel cut)
All joist nails installed on the outside angle (non-acute side).

Standard and Double-Shear Joist Hangers (cont.)

These products are available with additional corrosion protection. For more information, see p. 24.

These products are approved for installation with the Strong-Drive® SD Connector screw. See pp. 32–34 for more information.

Model No.	Ga.	Dimensions (in.)				Fasteners		Factored Resistance			
		W	H	B	d _e ³	Header	Joist	D.Fir-L		S-P-F	
								Uplift	Normal	Uplift	Normal
								(K _D = 1.15) lb.	(K _D = 1.00) lb.	(K _D = 1.15) lb.	(K _D = 1.00) lb.
Single 2x Sizes											
LUS24	18	1 1/8	3 1/4	1 1/4	2 1/4	(4) 10d	(2) 10d	710	1625	845	1155
								3.16	7.23	2.87	5.14
LU24L	22	1 1/8	3	1 1/4	2 1/8	(4) 10d	(2) 10d x 1 1/2"	360	1020	320	725
								1.60	4.54	1.42	3.22
LU26L	22	1 1/8	5	1 1/4	4 1/4	(6) 10d	(4) 10d x 1 1/2"	720	1805	645	1140
								3.20	7.14	2.87	5.07
SS LUS26	18	1 1/8	4 1/4	1 1/4	3 3/4	(4) 10d	(4) 10d	1420	2170	1290	1630
								6.32	9.65	5.74	7.25
HUS26	16	1 1/8	5 1/4	3	3 1/8	(14) 16d	(6) 16d	2705	4940	2065	3875
								11.90	21.97	9.20	17.24
LJS26DS	18	1 1/8	5	3 1/4	4 1/4	(16) 16d	(6) 16d	2055	4265	1460	4115
								9.14	18.97	6.49	18.31
HGUS26	12	1 1/8	5 1/4	5	4 1/4	(20) 16d	(8) 16d	2685	6625	2685	5700
								11.96	29.51	11.96	25.35
LU28L	20	1 1/8	6 1/4	1 1/4	5 1/4	(8) 10d	(6) 10d x 1 1/2"	1140	2185	1020	1550
								5.07	9.72	4.54	8.89
SS LUS28	18	1 1/8	6 1/4	1 1/4	3 3/4	(6) 10d	(4) 10d	1420	2520	1290	1790
								6.32	11.21	5.74	7.96
HUS28	16	1 1/8	7 1/8	3	6 1/8	(22) 16d	(8) 16d	3605	5385	2675	4345
								16.04	23.86	11.90	19.33
HGUS28	12	1 1/8	7 1/4	5	6 1/4	(36) 16d	(12) 16d	3310	7675	3310	6900
								14.74	34.19	14.74	30.73
LU210L	20	1 1/8	8	1 1/4	7 1/4	(10) 10d	(6) 10d x 1 1/2"	1140	2495	1020	1770
								5.07	11.10	4.54	7.87
SS LUS210	18	1 1/8	7 1/8	1 1/4	3 3/4	(8) 10d	(4) 10d	1420	2785	1290	2210
								6.32	12.39	5.74	9.83

1. Factored uplift resistances have been increased 15% for wind or earthquake loading; no further increase is allowed.
2. Designer must ensure that hanger is compatible with truss when reduced heel height is used.
3. d_e is the distance from the bearing seat to the top joist nail.
4. Resistances shown require a minimum 2-ply girder truss. For fastening to single-ply truss request technical bulletin T-C-N10TRSSCN and/or see installation notes.
5. Nails: 16d = 0.162" dia. x 3 1/2" long. See pp. 27–28 for other nail sizes and information.

Face-Mount Hangers


SIMPSON

Strong-Tie

These products are available with additional corrosion protection. For more information, see p. 24.

These products are approved for installation with the Strong-Drive® SD Connector screw. See pp. 32-34 for more information.

Model No.	Ga.	Dimensions (in.)				Fasteners		Factored Resistance							
		W	H	B	d _g ²	Header	Joist	D-Fir-L		S-P-F					
								Uplift	Normal	Uplift	Normal				
								(K _g = 1.15) lb.	(K _g = 1.00) lb.	(K _g = 1.15) lb.	(K _g = 1.00) lb.				
												kN	kN	kN	kN
Double 2x Sizes															
LUS24-2	18	3 1/8	3 1/8	2	1 1/8	(4) 16d	(2) 16d	835	2020	590	1435				
								3.71	8.99	2.62	6.38				
LUS26-2	18	3 1/8	4 1/8	2	4	(4) 16d	(4) 16d	1720	2595	1545	1920				
								7.65	11.54	6.87	8.54				
HHUS26-2	14	3 1/8	5 1/8	3	3 1/8	(14) 16d	(6) 16d	2850	7335	2065	5205				
								12.68	32.83	9.20	23.15				
HGUS26-2	12	3 1/8	5 1/8	4	4 1/8	(20) 16d	(8) 16d	4385	8950	3110	6355				
								19.51	39.81	13.83	28.27				
LUS28-2	18	3 1/8	7	2	4	(6) 16d	(4) 16d	1720	3325	1545	2575				
								7.65	14.79	6.87	11.45				
HHUS28-2	14	3 1/8	7 1/8	3	6 1/8	(22) 16d	(8) 16d	3765	8940	2675	6345				
								16.75	39.77	11.90	28.22				
HGUS28-2	12	3 1/8	7 1/8	4	8 1/8	(36) 16d	(12) 16d	6070	12980	4310	9215				
								27.00	57.74	19.17	40.99				
LUS210-2	18	3 1/8	9	2	6	(8) 16d	(6) 16d	2580	4500	2320	3195				
								11.48	20.02	10.32	14.21				
HHUS210-2	14	3 1/8	9 1/8	3	8	(30) 16d	(10) 16d	4670	9660	4235	7000				
								20.77	42.97	18.84	31.14				
HGUS210-2	12	3 1/8	9 1/8	4	8 1/8	(46) 16d	(16) 16d	6840	14015	4855	10270				
								30.43	62.34	21.60	45.69				
Triple 2x Sizes															
HGUS26-3	12	4 1/8	5 1/8	4	4 1/8	(20) 16d	(8) 16d	4385	8950	3110	6355				
								19.51	39.81	13.83	28.27				
HGUS28-3	12	4 1/8	7 1/8	4	6 1/8	(36) 16d	(12) 16d	6070	12980	4310	9215				
								27.00	57.74	19.17	40.99				
HHUS210-3	14	4 1/8	9	3	7 1/8	(30) 16d	(10) 16d	4670	9670	4235	6865				
								20.77	43.02	18.84	30.64				
HGUS210-3	12	4 1/8	9 1/8	4	8 1/8	(46) 16d	(16) 16d	6840	14645	4855	10400				
								30.43	65.14	21.60	46.26				
Quadruple 2x Sizes															
HGUS26-4	12	6 1/8	5 1/8	4	4 1/8	(20) 16d	(8) 16d	4385	8950	3110	6355				
								19.51	39.81	13.83	28.27				
HGUS28-4	12	6 1/8	7 1/8	4	6 1/8	(36) 16d	(12) 16d	6070	12980	4310	9215				
								27.00	57.74	19.17	40.99				
HHUS210-4	14	6 1/8	8 1/8	3	7 1/8	(30) 16d	(10) 16d	4670	10155	4235	7210				
								20.77	45.17	18.84	32.07				
HGUS210-4	12	6 1/8	9 1/8	4	8 1/8	(46) 16d	(16) 16d	6840	14645	4855	10400				
								30.43	65.14	21.60	46.26				
HGUS212-4	12	6 1/8	10 1/8	4	10 1/8	(56) 16d	(20) 16d	7640	14995	5425	10645				
								33.98	66.70	24.13	47.35				
HGUS214-4	12	6 1/8	12 1/8	4	11 1/8	(66) 16d	(22) 16d	10130	16400	7195	11645				
								45.06	72.95	32.00	51.80				
4x Sizes															
LUS46	18	3 1/8	4 1/8	2	3 1/8	(4) 16d	(4) 16d	1720	2595	1545	1920				
								7.65	11.54	6.87	8.54				
HHUS46	14	3 1/8	5 1/8	3	3 1/8	(14) 16d	(6) 16d	2540	7335	2065	5205				
								11.30	32.83	9.20	23.15				
HGUS46	12	3 1/8	5 1/8	4	4 1/8	(20) 16d	(8) 16d	4385	8950	3110	6355				
								19.51	39.81	13.83	28.27				
LUS48	18	3 1/8	6 1/8	2	3 1/8	(6) 16d	(4) 16d	1720	3325	1545	2575				
								7.65	14.79	6.87	11.45				
HHUS48	14	3 1/8	7 1/8	3	6 1/8	(22) 16d	(8) 16d	3765	8940	2675	6345				
								16.75	39.77	11.90	28.22				
HGUS48	12	3 1/8	7 1/8	4	6 1/8	(36) 16d	(12) 16d	6070	12980	4310	9215				
								27.00	57.74	19.17	40.99				
LUS410	18	3 1/8	8 1/8	2	5 1/8	(8) 16d	(6) 16d	2580	4500	2320	3195				
								11.48	20.02	10.32	14.21				
HGUS410	12	3 1/8	9	4	8 1/8	(46) 16d	(16) 16d	6840	14015	4855	10270				
								30.43	62.34	21.60	45.69				
HGUS412	12	3 1/8	10 1/8	4	10 1/8	(56) 16d	(20) 16d	7640	14995	5425	10645				
								33.98	66.70	24.13	47.35				
HGUS414	12	3 1/8	12 1/8	4	11 1/8	(66) 16d	(22) 16d	10130	16400	7195	11645				
								45.06	72.95	32.00	51.80				



Plated Truss Connectors

See footnotes
on p. 258.

TC - Truss Connectors

SIMPSON
Strong-Tie

The TC truss connector is an ideal connector for scissor trusses and can allow horizontal movement up to 1¼". The TC also attaches plated trusses to top plates or sill plates to resist uplift forces. Typically used on one or both ends of truss as determined by the building designer.

Material: 16 gauge

Finish: G90 galvanized


Design: Factored resistances are in accordance with CSA 086-14

Installation:


- Use all specified fasteners.
- Nails: 10d = 0.148" dia. x 3" long common wire, 10d x 1½" = 0.148" dia. x 1½" long.
- Drive 10d nails into the truss at the inside end of the slotted holes (inside end is towards the centre of the truss) and clinch on the back side. Do not seat these nails into the truss—allow room under the nail head for movement of the truss with respect to the wall.

Optional TC Installation:


- Bend one flange up 90°. Drive specified nails into the top and face of the top plates or install Titen® screws into the top and face of masonry wall. See optional load tables and installation details.




TC24
U.S. Patent 4,932,173




Typical TC24 Installation



TC26
(TC28 Similar)



Optional TC26 Installation for Grouted Concrete Block using a Wood Nailer (8", 10", 12" Wall Installation Similar)



Optional TC26 Installation for Grouted Concrete Block using Titen Screws

Model No.	Fasteners		Factored Resistance	
	Truss	Wall Plates	D.Fir-L	S-P-F
			Uplift (K _u =1.15)	Uplift (K _u =1.15)
TC24	(4) 10d	(4) 10d	605	430
TC26	(5) 10d	(6) 10d	1015	720
TC28	(5) 10d	(6) 10d	1015	720

Optional TC Installation Table


Model No.	Fasteners		Factored Resistance	
	Truss	Wall Plates	D.Fir-L	S-P-F
			Uplift (K _u =1.15)	Uplift (K _u =1.15)
TC26	(5) 10d	(6) 10d x 1½"	810	660
	(5) 10d	(6) 10d	930	660

1. Factored resistances have been increased 15% for earthquake or wind loading; no further increase allowed; reduce where other loads govern.

2. Grout strength is 15 MPa minimum.

3. Optional TC26 installation with 10d nails requires minimum 3" top plate thickness.

4. TC26 fastened to grouted concrete block with (5) - 3/16" x 2 1/4" Titen screws has a factored uplift resistance of 275 lb.



DESIGN

For more information, contact your local Simpson Strong-Tie distributor or visit us online at www.simpsonstrongtie.com.
© 2017 Simpson Strong-Tie Company. All rights reserved.

(800) 999-5099
strongtie.com

H/TSP

Seismic and Hurricane Ties (cont.)

These products are available with additional corrosion protection. For more information, see p. 24.

These products are approved for installation with the Strong-Drive® SD Connector screw. See pp. 32–34 for more information.

Model No.	Ga.	Fasteners			Factored Resistance ($K_D = 1.15$)					
		To Rafters/ Truss	To Plates	To Studs	D.Fir-L			S-P-F		
					Uplift	Lateral		Uplift	Lateral	
						F ₁	F ₂		F ₁	F ₂
					lb.	lb.	lb.	lb.	lb.	lb.
					kN	kN	kN	kN	kN	kN
H1	18	(6) 8d x 1½"	(4) 8d	—	740	685	300	680	485	215
SS H2A	18	(5) 8d x 1½"	(2) 8d x 1½"	(5) 8d x 1½"	830	220	75	590	155	55
SS H2.5A	18	(5) 8d	(5) 8d	—	805	160	160	755	160	160
H2.5T	18	(5) 8d	(5) 8d	—	835	175	210	740	160	210
SS H3	18	(4) 8d	(4) 8d	—	740	180	265	615	125	190
H6	16	—	(8) 8d	(8) 8d	1585	1085	—	1125	770	—
H7Z	16	(4) 8d	(2) 8d	(8) 8d	1390	670	—	990	475	—
SS H8 ²	18	(5) 10d x 1½"	(5) 10d x 1½"	—	1120	—	—	1025	—	—
SS H10A ²	18	(9) 10d x 1½"	(9) 10d x 1½"	—	1735	795	410	1505	565	290
H10AR	18	(9) 10d x 1½"	(9) 10d x 1½"	—	1485	690	430	1220	570	305
H10A-2	18	(9) 10d x 1½"	(9) 10d x 1½"	—	1835	1275	430	1645	880	305
H10S ^{2,3}	18	(8) 8d x 1½"	(8) 8d x 1½"	(8) 8d	1465	795	315	1040	565	225
H11Z	18	(6) 16d x 2½"	(6) 16d x 2½"	—	1095	920	545	780	855	390
H14	18	[1] (12) 8d x 1½"	(13) 8d	—	2390	855	320	1805	610	230
		[2] (12) 8d x 1½"	(15) 8d	—	10.63	3.80	1.42	8.03	2.71	1.02
		(9) 10d x 1½"	(6) 10d x 1½"	—	2390	855	320	1805	610	230
TSP	16	(9) 10d x 1½"	(6) 10d x 1½"	—	10.63	3.80	1.42	8.03	2.71	1.02
		(9) 10d x 1½"	(6) 10d x 1½"	—	1295	440	—	920	310	—
		(9) 10d x 1½"	(6) 10d	—	5.76	1.96	—	4.09	1.38	—
					1560	440	—	1105	310	—
					6.94	1.96	—	4.92	1.38	—

1. Factored resistances have been increased 15% for short term loading; no further increase is allowed.
2. Factored resistances are for one anchor. A minimum rafter thickness of 2½" must be used when framing anchors are installed on the same side of the plate (exception: H2.5A).
3. H8 factored uplift resistances for stud-to-bottom plate installations are 595 lb. (2.65 kN) for D.Fir-L and 390 lb. (1.74 kN) for S-P-F.
4. When cross-grain bending or cross-grain tension cannot be avoided, mechanical reinforcement to resist such forces should be considered.
5. Hurricane ties are shown installed on the outside of the wall for clarity. Installation on the inside of the wall is acceptable. For a continuous load path, connections at the top and bottom of the wall must be on the same side of the wall (see technical bulletin T-HTIECONPATH).
6. Factored resistances in the F₁ direction are not intended to replace diaphragm boundary members or prevent cross grain bending of the truss or rafter members. Additional shear transfer elements shall be considered where there may be effects of cross grain bending or tension.

7. H10S can have the stud offset a maximum of 1" from the rafter (centre to centre) for a reduced uplift of 1435 lb. (6.38 kN) D.Fir-L and 1015 lb. (4.51 kN) S-P-F.
8. H10S nails to plates are optional for uplift but required for lateral loads.
9. H10A may be field-bent up to a slope of 6/12. Multiply the tabulated uplift value x 0.75. Full tabulated lateral resistances apply.
10. The factored resistances of stainless-steel connectors match carbon-steel connectors when installed with Simpson Strong-Tie® stainless-steel, GCNR ring-shank nails. For more information, refer to engineering letter L-F-SSNAILS at strongtie.com.
11. D.Fir-L/S-P-F factored uplift resistances for the H2.5A fastened to a 2x4 truss bottom chord and double top plates using (5) 8d x 1½" nails into the top plates and (3) 8d x 1½" nails into the lowest three flange holes into the truss bottom chord is 495 lb. (2.20 kN).
12. Nails: 16d x 2½" = 0.162" dia. x 2½" long, 10d = 0.148" dia. x 3" long, 10d x 1½" = 0.148" dia. x 1½" long, 8d = 0.131" dia. x 2½" long, 8d x 1½" = 0.131" dia. x 1½" long. See pp. 27–28 for other nail sizes and information.



BEARING ANCHORAGE BY TOE-NAILS FOR LATERAL CAPACITY

B97791H1

NAIL TYPE	LENGTH (IN)	DIAMETER (IN)	NAIL LATERAL CAPACITY (LB)	
			S-P-F	D. FIR
COMMON WIRE	3.00	0.144	132	147
	3.25	0.144	132	147
	3.50	0.160	159	177
COMMON SPIRAL	3.00	0.122	97	108
	3.25	0.122	97	108
	3.50	0.152	145	162

NOTES:


1. Rafter and ceiling members may be anchored to top and bottom chords of girder truss by toe-nailing rafter and ceiling members to girder chords provided the reaction does not exceed the lateral capacities in the table. Hangers (specified by others) are required for reactions higher than the maximum toe-nail capacity. Reactions are based on factored loads.
2. Toe nail capacities shown in the table are for one toe-nail. For additional toe-nails multiply values in table by the number of toe-nails used. Toe-nail capacities take into account toe-nailing factor J_A in CSA O86-14, section 12.9.4.1.
3. For 9-3/4 gauge 3.25" common wire gun nails (diameter = 0.120") use 3" common spiral nail values.
4. Maximum number of toe-nails allowed depends on the lumber size & species to be toe-nailed to supporting member and nail diameter, as shown in tables below.
5. Nail values in table are based on the following relative lumber densities: G = 0.42 (SPF), G = 0.49 (D. Fir).
6. Toe-nails shall be driven at approximately 1/3 the nail length from the edge of the joist/truss chord and driven at an angle of 30° to the grain of the member (See next page for nailing on bearing plate).
7. For loads due to wind the nail lateral capacity in this table may be multiplied by 1.15 (K_D factor).
8. Lumber must be dry (< 19% moisture content) at the time of nail installation.
9. Nail values in this table comply with CSA O86-14, section 12.9.4
10. This design is not valid after March 31, 2021.



Nail type	Common wire	Common spiral	Common wire	Common spiral
Nail dia. (in)	0.160	0.152	0.144	0.122
	(3.5" nail)		(3" and 3.25" nail)	
LUMBER SIZE	MAXIMUM NUMBER OF TOE-NAILS			
2X4 SPF	2	2	3	3
2X4 D. Fir	2	2	2	2
2X6 SPF	4	4	4	5
2X6 D. Fir	3	3	3	4

MiTek® MiTek Canada Inc
100 Industrial Rd.
Bradford, Ontario L3Z 3G7

December 2, 2019.



BEARING ANCHORAGE BY TOE-NAILS FOR WIND LOADING

B97791H2



NAIL TYPE	LENGTH (IN)	DIAMETER (IN)	NAIL WITHDRAWAL CAPACITY (LB)	
			S-P-F	D. FIR
COMMON WIRE	3.00	0.144	30	42
	3.25	0.144	32	45
	3.50	0.160	38	52
COMMON SPIRAL	3.00	0.122	26	36
	3.25	0.122	28	40
	3.50	0.152	36	50

Note: If using truss with D. Fir lumber and S-P-F bearing plate, use values in table for S-P-F.



NOTES:

1. Truss chord, rafter, or ceiling members may be anchored to bearing plate by toe-nails, provided that the actual factored uplift force due to **wind** or **earthquake** load does not exceed the withdrawal capacities in the table. Hangers (specified by others) are required for uplift forces that are higher than the maximum toe-nail withdrawal capacity.
2. Toe nail capacities shown in the table are for **one** toe-nail. For additional toe-nails multiply values in table by the number of toe-nails used. Toe-nail capacities take into account toe-nailing factor J_A in CSA O86-14, section 12.9.5.2.
3. For 9- 3/4 gauge 3.25" common wire gun nails (diameter = 0.120") use 3" common spiral nail values.
4. Maximum number of toe-nails allowed depends on the lumber size & species to be toe-nailed to supporting member and nail diameter, as shown in table above.
5. Nail values in table are based on the following relative lumber densities: $G = 0.42$ (SPF), $G = 0.49$ (D. Fir).
6. Toe-nails shall be driven at approximately 1/3 the nail length from the edge of the joist/truss chord and driven at an angle of 30° to the grain of the member (See drawing on detail B37579H1).
7. Lumber must be dry (< 19% moisture content) at the time of nail installation.
8. Nail values in this table comply with CSA O86-14, section 12.9.5
9. This design is not valid after March 31, 2021.

Toe-nailing on 2x6 Bearing Plate




Toe-nailing on 2x4 Bearing Plate





MiTek® MiTek Canada Inc
100 Industrial Rd.
Bradford, Ontario L3Z 3G7

December 2, 2019



Symbols

PLATE LOCATION AND ORIENTATION



For 4 x 2 orientation, locate plates 0-1/4\"



This symbol indicates the required direction of slots in connector plates.

*Plate location details available in MiTek software or upon request.

PLATE SIZE

4 x 4

The first dimension is the plate width measured perpendicular to slots. Second dimension is the length parallel to slots.

LATERAL BRACING LOCATION



Indicated by symbol shown and/or by text in the bracing section of the output. Use T, I or Eliminator bracing if indicated.

BEARING




Indicates location where bearings (supports) occur. Icons vary but reaction section indicates joint number where bearings occur.

Industry Standards:

TPIC: Truss Design Procedures and Specifications for Light Metal Plate Connected Wood Trusses
DSB-89: Design Standard for Bracing
BCSI: Building Component Safety Information, Guide to Good Practice for Handling, Installing & Bracing of Metal Plate Connected Wood Trusses.

Numbering System



JOINTS ARE GENERALLY NUMBERED/LETTERED CLOCKWISE AROUND THE TRUSS STARTING AT THE JOINT FARTHEST TO THE LEFT.

CHORDS AND WEBS ARE IDENTIFIED BY END JOINT NUMBERS/LETTERS.

PRODUCT CODE APPROVALS

CCMC Reports:

11996-L, 10319-L, 13270-L, 12691-R

© 2007 MiTek® All Rights Reserved

MiTek
POWER TO PERFORM.™

MiTek Engineering Reference Sheet: MI-7473C rev. 10-08



General Safety Notes

Failure to Follow Could Cause Property Damage or Personal Injury


1. Additional stability bracing for truss system, e.g. diagonal or X-bracing, is always required. See BCSI.
2. Truss bracing must be designed by an engineer. For wide truss spacing, individual lateral braces themselves may require bracing, or alternative T, I, or Eliminator bracing should be considered.
3. Never exceed the design loading shown and never stack materials on inadequately braced trusses.
4. Provide copies of this truss design to the building designer, erection supervisor, property owner and all other interested parties.
5. Cut members to bear tightly against each other.
6. Place plates on each face of truss at each joint and embed fully. Knots and wane at joint locations are regulated by TPIC.
7. Design assumes trusses will be suitably protected from the environment in accord with TPIC.
8. Unless otherwise noted, moisture content of lumber shall not exceed 19% at time of fabrication.
9. Unless expressly noted, this design is not applicable for use with fire retardant, preservative treated, or green lumber.
10. Camber is a non-structural consideration and is the responsibility of truss fabricator. General practice is to camber for dead load deflection.
11. Plate type, size, orientation and location dimensions indicated are minimum plating requirements.
12. Lumber used shall be of the species and size, and in all respects, equal to or better than that specified.
13. Top chords must be sheathed or purlins provided at spacing indicated on design.
14. Bottom chords require lateral bracing at 10 ft. spacing, or less, if no ceiling is installed, unless otherwise noted.
15. Connections not shown are the responsibility of others.
16. Do not cut or alter truss member or plate without prior approval of an engineer.
17. Install and load vertically unless indicated otherwise.
18. Use of green or treated lumber may pose unacceptable environmental, health or performance risks. Consult with project engineer before use.
19. Review all portions of this design (front, back, words and pictures) before use. Reviewing pictures alone is not sufficient.
20. Design assumes manufacture in accordance with TPIC Quality Criteria.

Overview:

Where piggybacks are connected overtop of base trusses, 2x4 purlins must be first added to the flat portion of the base truss at a spacing no more than 24" o/c. These purlins not only provide support for the piggyback trusses above, but are required to laterally support the top chord of the base truss which will not have the sheathing directly connected to the flat portion of the base truss. This ensures the top chord, most often in compression, will not buckle laterally.

Further, the purlins in the plane of the flat portion require diagonal bracing to prevent lateral displacement of the purlins themselves where under certain conditions, the trusses may in fact all buckle in the same direction if this additional bracing is not added in the plane of the purlins.

Detail:




NOTE: THE SLOPED PORTION OF THE TOP CHORD OF THE BASE TRUSS AND PIGGYBACK TRUSS IN THIS SKETCH IS ASSUMED TO BE SHEATHED IN ACCORDANCE WITH THE OBC.

SKETCH FROM BCSI-CANADA 2013

Disclaimer:

OWTFA Tech Notes are intended to provide guidance to the design community both within the membership as well as to third party designers who might benefit from the information. The details have been developed by the OWTFA technical committee and although there may be professional engineers involved in development, the information contained in the tech-note are not intended to be used without having a professional engineer review the information for a specific application. The OWTFA takes no responsibility with respect to the information provided but has developed this tech-note to offer guidance where it is not currently readily available.



Alves Engineering Services Inc.

5208 Easton road
Burlington, Ontario L7L 6N6
(289) 259 5455

RESPONSABILITIES

- 1-Alves Engineering Services Inc. is responsible for the design of trusses as individual components
- 2-It is the responsibility of others to ascertain that the design loads utilized on this drawing meet or exceed the actual dead load imposed by the structure and the live load imposed by the local building code or the authorities having jurisdictions.
- 3- All dimensions are to be verified by owner, contractor, architect or other authority before manufacture.
- 4- Alves Engineering Services Inc. bears no responsibility for the erection of the trusses. Persons erecting trusses are cautioned to seek professional advice regarding temporary and permanent bracing system. Bracing shown on Alves Engineering Services Inc. drawings is specified for the truss as a single component and forms an integral part of the truss design, but is not meant to represent the only required bracing for that truss when trusses are installed in a series of trusses forming a roof truss system.
- 5- It is the manufactures responsibility to ensure that the trusses are manufactured in conformance with Alves Engineering Services Inc. specifications outlined below.

SPECIFICATIONS

- 1-Truss components sealed by Alves Engineering Services Inc. conform to the relevant sections of the current Building Code of Ontario and Canada (part 4 or part 9) or the current Canadian code for Farm Buildings in accordance with the application specified on the sealed truss component drawing. All truss component design procedures must conform to the current design standard issued by the truss plate institute of Canada (TPIC). All lumber and nailing stresses to conform to the current CSA wood design standard identified on the current Building Code and TPIC.
- 2- Lumber is to be the sizes and grade specified on the truss drawing.
- 3- Moist content of lumber is not to exceed 19% in service unless otherwise specified.
- 4- Plates shall be applied to both faces of the each truss joint and shall be positioned as shown on the truss drawings
- 5- Lumber used on manufacture of trusses is not to be treated with chemicals unless otherwise specified on the truss drawings.
- 6- The top chord is assumed to be continuously laterally braced by the roof sheathing or purlins at intervals specified on the truss drawing but not exceeding 24" c/c for (part 9) and not exceeding 48" for (part 4 or farm design)
- 7- When rigid ceiling is not attached directly to the bottom chord, lateral bracing is required and it should not exceed more than 3m or 10' intervals.
- 8-Refer to Mitek sheet M117473C REV.10-08 attached for information on symbols, numbering system and General Safety notes.

T-1800219

Feb 09, 2018