


6/12 roof pitch unless noted



ASPHALT SHINGLES
FINISHED OVERHANG: 12"
2x6 EXTERIOR WALLS
2x6 FASCIA BOARD
HEEL: R.T.M.C.

All conventional framing to conform with Part 9 of O.B.C. 2012 (2019 amendment). Roof rafters that cross over or meet trusses to be min. 2x4 SPF #2 @ 24" o/c with a vertical post to the truss at each cross point. Vertical posts longer than 6' to have lateral bracing so that the distance between the post end points and lateral bracing does not exceed 6'.

DESIGN CONFORMS WITH OBC 2012
(2019 amendment) OCCUPANCY:
RESIDENTIAL | PART: 9
Ss = 31.35 psf | Sr = 8.4 psf

DESIGN LOADS:

TCSL = 25.6 psf
TCDL = 6.0 psf
BCLL = 0.0 psf
BCDL = 7.4 psf

CITY OF HAMILTON
Building Division

HARDWARE:

LUS24 - (O)
LJS26DS - (V)
HGUS26-2 - (XX)
LUS26-2-(VV)

THESE STAMPED DRAWINGS SHALL BE AVAILABLE ON SITE

THE OWNER AND/OR CONTRACTOR SHALL COMPLY WITH
THE ONTARIO BUILDING CODE AND ALL OTHER APPLICABLE LAW

BEAMS:

B40= B41 = B42:
2 - 2x10 SPF #2

These drawings and/or specifications have been reviewed by

42=  FEB. 23/12

DATE

 **DENOTES:**
CONVENTIONAL
FRAMING

M13125

Job Track: **51225**Plan Log: **202401**

Layout ID: 408152

Builder / Location:	
---------------------	--

GREEN PARK HOMES / WATERDOWN

Project: **RUSSELL GARDENS PH.3**

Date: 2020-04-27

Sales: **Mario DiCanno**

Designer: JG

Model / Elevation:

MOUNTAINASH 4/3- std. or opt.

THESE DRAWINGS CONSTITUTE THE PROPERTY OF TAMARACK ROOF TRUSSES INC., SHALL NOT BE REPRODUCED, PUBLISHED, OR REDISTRIBUTED IN ANY MANNER OR UTILIZED FOR ANY PURPOSE OTHER THAN THE MANUFACTURE OF TRUSSES BY TAMARACK ROOF TRUSSES INC AND WILL BE RETRACTED BY TAMARACK ROOF TRUSSES INC IF UTILIZED FOR ANY OTHER PURPOSE.

Mitek ver 8.3.1.215

LOT 227




DELIVERY SHIPLIST

Lumber Yard: TAMARACK LUMBER
 Builder: GREEN PARK HOMES
 Project: RUSSELL GARDENS PH.3
 Location: WATERDOWN
 Model: MOUNTAINASH 4
 Lot #: 227
 Elevation: 3- std. or opt.

Job Track: 51225
 PlanLog: 202401
 Layout ID: 408152
 Ref #
 Page: 1 of 3
 Date: 04-27-2020
 Designer:
 Sales Rep: Mario DiCano

Roof Trusses

PROFILE	QTY PLY	MARK TYPE	PITCH	SPAN	HEIGHT	LUMBER	OVERHANG LEFT RIGHT	HEEL HEIGHT LEFT RIGHT	LBS. BFT.	BUNDLE # STACK #	LOAD BY REMARKS
	1 2-ply	T40 Hip Girder	6 /12	35-02-00	4-01-04	2 x 4 2 x 6	1-03-08 1-03-08	1-02-00 1-02-00	340.74 212.00		
	1 2-ply	T40Z Hip Girder	6 /12	35-02-00	4-01-04	2 x 4 2 x 6	1-03-08 1-03-08	1-02-00 1-02-00	340.74 212.00		
	2	T41 Hip	6 /12	35-02-00	5-01-04	2 x 4	1-03-08 1-03-08	1-02-00 1-02-00	277.99 174.00		
	2	T42 Hip	6 /12	35-02-00	6-01-04	2 x 4	1-03-08 1-03-08	1-02-00 1-02-00	277.12 174.67		
	2	T43 Hip	6 /12	35-02-00	7-01-04	2 x 4	1-03-08 1-03-08	1-02-00 1-02-00	289.07 179.67		
	2	T44 Hip	6 /12	35-02-00	8-01-04	2 x 4	1-03-08 1-03-08	1-02-00 1-02-00	280.73 183.33		
	2	T45 Hip	6 /12	35-02-00	9-01-04	2 x 4	1-03-08 1-03-08	1-02-00 1-02-00	301.67 191.33		
	6	T46 Common	6 /12	35-02-00	9-11-08	2 x 4	1-03-08 1-03-08	1-02-00 1-02-00	910.08 558.00		
	1 2-ply	T47 Hip Girder	6 /12	16-07-00	4-01-04	2 x 4 2 x 6	1-03-08	1-02-00 2-02-00	156.02 100.87		
	1	T48 Hip	6 /12	16-07-00	5-01-04	2 x 4	1-03-08	1-02-00 2-02-00	68.15 43.33		
	1	T49 Common	6 /12	16-07-00	5-09-12	2 x 4	1-03-08	1-02-00 2-02-00	67.14 42.33		
	1	T50 Hip Girder	6 /12	10-11-00	2-07-04	2 x 4	1-03-08 1-03-08	1-02-00 1-02-00	42.73 28.33		
	1	T51 Hip	6 /12	10-11-00	4-07-04	2 x 4	1-03-08 1-03-08	2-02-00 2-02-00	51.54 34.50		
	1	T52 Flat	0 /12	9-04-00	2-10-00	2 x 4		2-10-00 2-10-00	36.11 23.83		



DELIVERY SHIPLIST

Lumber Yard: TAMARACK LUMBER
 Builder: GREEN PARK HOMES
 Project: RUSSELL GARDENS PH.3
 Location: WATERDOWN
 Model: MOUNTAINASH 4
 Lot #: 227
 Elevation: 3- std. or opt.

Job Track: 51225
 Plan Log: 202401
 Layout ID: 408152
 Ref #:
 Page: 2 of 3
 Date: 04-27-2020
 Designer:
 Sales Rep: Mario DiCano

Roof Trusses

PROFILE	QTY PLY	MARK TYPE	PITCH	SPAN	HEIGHT	LUMBER	OVERHANG LEFT RIGHT	HEEL HEIGHT LEFT RIGHT	LBS. BFT.	BUNDLE # STACK #	LOAD BY REMARKS
	1	G52 GABLE	0 / 12	9-04-00	2-10-00	2 x 4		2-10-00 2-10-00	33.75 23.33		
	1	T53 Flat Girder	0 / 12	9-04-00	3-10-00	2 x 6		3-10-00 3-10-00	50.9 31.50		
	1 2-ply	T54 Jack-Closed Girder	6 / 12	6-10-08	4-01-04	2 x 4 2 x 6		8-00 4-01-04	59.61 37.33		
	15	J1 Jack-Open	6 / 12	5-10-08	4-01-04	2 x 4	1-03-08	1-02-00 4-01-04	251.92 160.00		
	4	J40 Jack-Open	6 / 12	3-09-08	4-01-04	2 x 4		2-02-08 4-01-04	52.34 35.33		
	4	J41 Jack-Open	6 / 12	2-10-08	2-07-04	2 x 4	1-03-08	1-02-00 2-07-04	38.2 24.00		
	4	C40 Jack-Open	6 / 12	3-09-07	3-00-12	2 x 4	1-03-08 2-01-01	1-02-00 3-00-12	56.53 34.67		
	4	C41 Jack-Open	6 / 12	1-09-07	2-00-12	2 x 4	1-03-08 4-01-01	1-02-00 2-00-12	46.33 29.33		
	4	C42 Jack-Open	6 / 12	1-10-08	3-00-12	2 x 4	1-03-08 1-10-15	1-02-00 2-01-04	38.28 24.00		
	4	C43 Jack-Open	6 / 12	1-09-07	2-00-12	2 x 4	1-03-08 1-01	1-02-00 2-00-12	28.08 18.67		
	2	C44 Jack-Open	6 / 12	1-10-15	2-01-08	2 x 4	1-03-08 11-09	1-02-00 2-01-08	16.64 10.67		
	2	C45 Jack-Open	6 / 12	1-10-15	2-01-08	2 x 4	1-03-08 1-01	1-02-00 2-01-08	14.65 9.33		

TOTAL # TRUSS= 74

TOTAL BFT OF ALL TRUSSES= 2596.15 BFT.

TOTAL WEIGHT OF ALL TRSSES 4137.05 LBS

HARDWARE

QTY	TYPE	MODEL	LENGTH
1	Hardware	HGUS26-2	
4	Hardware	LJS26DS	

DELIVERY SHIPLIST




Lumber Yard: TAMARACK LUMBER
 Builder: GREEN PARK HOMES
 Project: RUSSELL GARDENS PH.3
 Location: WATERDOWN
 Model: MOUNTAINASH 4
 Lot #: 227
 Elevation: 3- std. or opt.

Job Track: 51225
 PlanLog: 202401
 Layout ID: 408152
 Ref #
 Page: 3 of 3
 Date: 04-27-2020
 Designer:
 Sales Rep: Mario DiCano

HARDWARE

QTY	TYPE	MODEL	LENGTH
5	Hardware	LUS24	
3	Hardware	LUS26-2	

TOTAL NUMBER OF
 ITEMS= 13



LUMBER
 N. L. G. A. RULES
 CHORDS SIZE DRY LUMBER DESCR. SPF

R - A	2x4	DRY	No.2	SPF
A - D	2x6	DRY	No.2	SPF
D - F	2x6	DRY	No.2	SPF
F - I	2x6	DRY	No.2	SPF
I - J	2x4	DRY	No.2	SPF
J - P	2x6	DRY	No.2	SPF
P - L	2x6	DRY	No.2	SPF
L - J	2x6	DRY	No.2	SPF
ALL WEBS	2x3	DRY	No.2	SPF
DRY: SEASONED LUMBER.				


DESIGN CONSISTS OF 2 TRUSSES BUILT SEPARATELY THEN FASTENED TOGETHER AS FOLLOWS:

CHORDS #ROWS	SURFACE SPACING (IN)	LOAD (PLF)
TOP CHORDS: (0.122"x3") SPIRAL NAILS		
R - A	12	TOP
I - J	12	TOP
A - D	12	SIDE (183.1)
D - F	12	SIDE (0.0)
F - I	12	SIDE (0.0)
BOTTOM CHORDS: (0.122"x3") SPIRAL NAILS		
R - P	12	SIDE (183.1)
P - L	12	SIDE (183.1)
L - J	12	SIDE (0.0)
WEBS: (0.122"x3") SPIRAL NAILS		
2x3	8	

NAILS TO BE DRIVEN FROM ONE SIDE ONLY.
 GIRDER NAILING ASSUMES NAILED HANGERS ARE FASTENED WITH MIN. 3-0 INCH NAILS.

TOP - COMPONENTS ARE LOADED FROM THE TOP AND MUST BE PLACED ON TOP EDGE OF ALL PLIES FOR THE LOAD TO BE TRANSFERRED TO EACH PLY.

SIDE - PLF SHOWN IS THE EQUIVALENT UDL APPLIED TO ONE SIDE THAT THE CORRESPONDING NAILING PATTERN SHALL BE CAPABLE OF TRANSFERRING. REMAINING PLF MUST BE APPLIED ON THE OPPOSITE SIDE OR ON THE TOP.



Structural component only
 DWG# T-2007063 1/2

DIMENSIONS, SUPPORTS AND LOADINGS SPECIFIED BY FABRICATOR TO BE VERIFIED BY BUILDING DESIGNER

FACTORED GROSS REACTION		MAXIMUM FACTORED GROSS REACTION		INPUT BRG		REQD BRG	
JT	VERT	HORIZ	DOWN	HORIZ	UPLIFT	IN-SX	IN-SX
R	3052	0	3052	0	3-8	3-8	
J	3118	0	3118	0	3-8	3-8	

UNFACTORED REACTIONS

JT	1ST LOSE	MAX/MIN	COMPONENT REACTIONS
R	2181	1401/0	0/0
J	2208	1430/0	0/0

BEARING MATERIAL TO BE SPF NO.2 OR BETTER AT JOINT(S) R, J

BRACING
 TOP CHORD TO BE SHEATHED OR MAX. PURLIN SPACING = 4.25 FT.
 MAX. UNBRACED BOTTOM CHORD LENGTH = 10.00 FT. OR RIGID CEILING DIRECTLY APPLIED.

ALL PITCH BREAKS AND PERIMETER CORNER JOINTS MUST BE Laterally RESTRAINED.

LOADING

TOTAL LOAD CASES: (4)

CHORDS		FACTORED		WEBS	
MEMB.	MAX. FACTORED FORCE (LBS)	VERT. LOAD (PLF)	MAX. CS1 (LC)	MEMB.	MAX. FACTORED FORCE (LBS)
FR-TO		FROM	TO	FR-TO	
R-A	-2974/0	0.0	0.0 0.34 (1)	K-I	0/5083
A-S	-4328/0	-91.8	-91.8 0.20 (1)	A-Q	0/5078
S-T	-4328/0	-91.8	-91.8 0.20 (1)	K-H	-2463/0
T-B	-4328/0	-91.8	-91.8 0.20 (1)	C-B	-2463/0
B-U	-6698/0	-91.8	-91.8 0.25 (1)	M-H	0/2804
U-V	-6698/0	-91.8	-91.8 0.25 (1)	B-O	0/2808
V-C	-6698/0	-91.8	-91.8 0.25 (1)	M-G	-1325/0
C-D	-7505/0	-91.8	-91.8 0.23 (1)	O-C	-1325/0
D-W	-7505/0	-91.8	-91.8 0.23 (1)	N-G	0/958
W-E	-7505/0	-91.8	-91.8 0.23 (1)	C-N	0/958
E-X	-7505/0	-91.8	-91.8 0.23 (1)	N-E	-851/0
X-Y	-7505/0	-91.8	-91.8 0.23 (1)		
Y-F	-7505/0	-91.8	-91.8 0.23 (1)		
F-Z	-7505/0	-91.8	-91.8 0.23 (1)		
Z-G	-7505/0	-91.8	-91.8 0.23 (1)		
G-AA	-6698/0	-91.8	-91.8 0.26 (1)		
AA-AB	-6698/0	-91.8	-91.8 0.26 (1)		
AB-AC	-6698/0	-91.8	-91.8 0.26 (1)		
AC-H	-6698/0	-91.8	-91.8 0.26 (1)		
H-AD	-4330/0	-91.8	-91.8 0.21 (1)		
AD-AE	-4330/0	-91.8	-91.8 0.21 (1)		
AE-AF	-4330/0	-91.8	-91.8 0.21 (1)		
AF-I	-4330/0	-91.8	-91.8 0.21 (1)		
J-I	-3028/0	0.0	0.0 0.35 (1)		
R-AG	0/0	-18.5	-18.5 0.08 (4)		
AG-AH	0/0	-18.5	-18.5 0.08 (4)		
AH-Q	0/0	-18.5	-18.5 0.08 (4)		
Q-AI	0/4328	-18.5	-18.5 0.33 (1)		
AI-P	0/4328	-18.5	-18.5 0.33 (1)		
P-O	0/4328	-18.5	-18.5 0.33 (1)		
O-AJ	0/8998	-18.5	-18.5 0.49 (1)		
AJ-K	0/8998	-18.5	-18.5 0.49 (1)		
K-N	0/8998	-18.5	-18.5 0.49 (1)		
N-AL	0/8998	-18.5	-18.5 0.49 (1)		
AL-AM	0/8998	-18.5	-18.5 0.49 (1)		
AM-AN	0/8998	-18.5	-18.5 0.49 (1)		
AN-M	0/8998	-18.5	-18.5 0.49 (1)		
M-AO	0/4330	-18.5	-18.5 0.33 (1)		
AO-L	0/4330	-18.5	-18.5 0.33 (1)		
L-AP	0/4330	-18.5	-18.5 0.33 (1)		
AP-AD	0/4330	-18.5	-18.5 0.33 (1)		
AD-K	0/4330	-18.5	-18.5 0.33 (1)		

TOTAL WEIGHT = 2 X 176 = 353 lb

DESIGN CRITERIA

SPECIFIED LOADS:
 TOP CH. LL = 25.6 PSF
 DL = 6.0 PSF
 BOT CH. LL = 0.0 PSF
 DL = 7.4 PSF
 TOTAL LOAD = 39.0 PSF

SPACING = 24.0 IN. C/C

LOADING IN FLAT SECTION BASED ON A SLOPE OF 6.00/12

THIS TRUSS IS DESIGNED FOR RESIDENTIAL OR SMALL BUILDING REQUIREMENTS OF PART 9, NBC 2010, NBC 2015

THIS DESIGN COMPLIES WITH:
 - PART 9 OF CBC 2018, CBC 2012, ABC 2019
 - PART 9 OF CBC 2012 (2019 AMENDMENT)
 - CSA 088-09, CSA 088-14
 - TPIC 2011, TPIC 2014

(55 % OF 31.3 P.S.F. G.S.L. PLUS 8.4 P.S.F. RAIN LOAD) EQUALS 26.6 P.S.F. SPECIFIED ROOF LIVE LOAD

ALLOWABLE DEFL. (LL) = L/360 (1.16")
 CALCULATED VERT. DEFL. (LL) = U/999 (0.20")
 ALLOWABLE DEFL. (TL) = L/360 (1.16")
 CALCULATED VERT. DEFL. (TL) = U/999 (0.38")

CSI: TC=0.35/1.00 (I-K:1), BC=0.48/1.00 (M-N:1), WB=0.69/1.00 (I-K:1), SB=0.17/1.00 (H-I:1)

DOL LUMBER=1.00 NAIL=1.00 LB BEND=1.00
 COMP=1.00 SHEAR=1.00 TENS=1.00

COMPANION LIVE LOAD FACTOR = 1.00

TRUSS PLATE MANUFACTURER IS NOT RESPONSIBLE FOR QUALITY CONTROL IN THE TRUSS MANUFACTURING PLANT.

NAIL VALUES
 PLATE GRIP(DRY) SHEAR SECTION (PSI) (PLI) (PLI)
 MAX MIN MAX MIN MAX MIN
 MT20 618 354 1687 788 1687 1656

PLATE PLACEMENT TOL. = 0.260 inches

PLATE ROTATION TOL. = 5.0 Deg.

JSI GRIP= 0.68 (K) (INPUT = 0.80)
 JSI METAL= 0.42 (P) (INPUT = 1.00)

PLATES (table is in inches)

JT	TYPE	PLATES	W	LEN	Y	X
A	TMVW-I	MT20	6.0	9.0		Edge
B	TMVW-I	MT20	5.0	6.0	2.50	2.75
C	TMVW-I	MT20	5.0	6.0		
D	TS-I	MT20	5.0	6.0		
E	TMVW-I	MT20	3.0	6.0		
F	TS-I	MT20	5.0	6.0		
G	TMVW-I	MT20	5.0	6.0		
H	TMVW-I	MT20	5.0	6.0	2.50	2.75
I	TMVW-I	MT20	6.0	9.0		Edge
J	BMV1-p	MT20	3.0	6.0		
K	BMVW-I	MT20	6.0	9.0	3.00	4.25
L	BS-I	MT20	5.0	6.0		
M	BMVW-I	MT20	5.0	6.0	2.50	2.75
N	BMVW-I	MT20	5.0	6.0		
O	BMVW-I	MT20	5.0	6.0	2.50	2.75
P	BS-I	MT20	5.0	6.0		
Q	BMVW-I	MT20	6.0	9.0	3.00	4.25
R	BMV1-p	MT20	3.0	6.0		

Edge - INDICATES REFERENCE CORNER OF PLATE TOUCHES EDGE OF CHORD.

LOADING

TOTAL LOAD CASES: (4)

CHORDS				WEBS			
MEMB.	MAX. FACTORED FORCE (LBS)	VERT. LOAD (PLF)	CS (LC)	MAX. UNBRAC (LBS)	MAX. FACTORED FORCE (LBS)	CS (LC)	MAX. UNBRAC (LBS)
FR-TO		FROM	TO	LENGTH	FR-TO		
K-AR	0.0	-18.5	-18.5	0.06 (4)	10.00		
AR-AS	0.0	-18.5	-18.5	0.06 (4)	10.00		
AS-AT	0.0	-18.5	-18.5	0.06 (4)	10.00		
AT-J	0.0	-18.5	-18.5	0.06 (4)	10.00		

FACTORED CONCENTRATED LOADS (LBS)

JT	LOC.	LOC	MAX-	MAX+	FACE	DIR.	TYPE	HEEL	CONN.
B	5-10-12	-110	-110	---	FRONT	VERT	TOTAL	---	C1
C	11-10-12	-110	-110	---	FRONT	VERT	TOTAL	---	C1
D	13-10-12	-110	-110	---	FRONT	VERT	TOTAL	---	C1
O	11-10-12	-28	-28	---	FRONT	VERT	TOTAL	---	C1
P	9-10-12	-28	-28	---	FRONT	VERT	TOTAL	---	C1
Q	5-10-12	-28	-28	---	FRONT	VERT	TOTAL	---	C1
S	1-10-12	-110	-110	---	FRONT	VERT	TOTAL	---	C1
T	3-10-12	-110	-110	---	FRONT	VERT	TOTAL	---	C1
U	7-10-12	-110	-110	---	FRONT	VERT	TOTAL	---	C1
V	9-10-12	-110	-110	---	FRONT	VERT	TOTAL	---	C1
W	15-10-12	-110	-110	---	FRONT	VERT	TOTAL	---	C1
X	17-10-12	-110	-110	---	FRONT	VERT	TOTAL	---	C1
Y	19-10-12	-110	-110	---	FRONT	VERT	TOTAL	---	C1
Z	21-10-12	-110	-110	---	FRONT	VERT	TOTAL	---	C1
AA	23-10-12	-110	-110	---	FRONT	VERT	TOTAL	---	C1
AB	25-10-12	-110	-110	---	FRONT	VERT	TOTAL	---	C1
AC	27-10-12	-110	-110	---	FRONT	VERT	TOTAL	---	C1
AD	29-10-12	-110	-110	---	FRONT	VERT	TOTAL	---	C1
AE	31-10-12	-110	-110	---	FRONT	VERT	TOTAL	---	C1
AF	33-10-12	-113	-113	---	FRONT	VERT	TOTAL	---	C1
AG	1-10-12	-28	-28	---	FRONT	VERT	TOTAL	---	C1
AH	3-10-12	-28	-28	---	FRONT	VERT	TOTAL	---	C1
AI	7-10-12	-28	-28	---	FRONT	VERT	TOTAL	---	C1
AJ	13-10-12	-28	-28	---	FRONT	VERT	TOTAL	---	C1
AK	15-10-12	-28	-28	---	FRONT	VERT	TOTAL	---	C1
AL	17-10-12	-28	-28	---	FRONT	VERT	TOTAL	---	C1
AM	19-10-12	-28	-28	---	FRONT	VERT	TOTAL	---	C1
AN	21-10-12	-28	-28	---	FRONT	VERT	TOTAL	---	C1
AO	23-10-12	-28	-28	---	FRONT	VERT	TOTAL	---	C1
AP	25-10-12	-28	-28	---	FRONT	VERT	TOTAL	---	C1
AQ	27-10-12	-28	-28	---	FRONT	VERT	TOTAL	---	C1
AR	29-10-12	-28	-28	---	FRONT	VERT	TOTAL	---	C1
AS	31-10-12	-28	-28	---	FRONT	VERT	TOTAL	---	C1
AT	33-10-12	-27	-27	---	FRONT	VERT	TOTAL	---	C1

CONNECTION REQUIREMENTS

1) C1: A SUITABLE HANGER/MECHANICAL CONNECTION IS REQUIRED.



Structural component only
DWG# T-2007063 7/2


JOB NAME	TRUSS NAME	QUANTITY	PLY	JOB DESC.	DRWG NO.
408150	T1Z	1	2	GREEN PARK HOMES	

Tamarack Roof Truss, Burlington

Version 8.310 S Oct 29 2019 Mitak Industries, Inc. Sat Apr 26 11:02:48 2020 Page 1

ID:37vF?aG0E03cRUj6X1jSkziWYK-zifwZSolhMefWNwhG566h7Ury008GaeTEqvOzNCnb

Scale = 1/54.4



LUMBER			
N. L. G. A. RULES	SIZE	LUMBER	DESCR.
CHORDS			
R - A	2x4	DRY No.2	SPF
A - D	2x8	DRY No.2	SPF
D - F	2x8	DRY No.2	SPF
F - I	2x8	DRY No.2	SPF
J - L	2x4	DRY No.2	SPF
R - P	2x8	DRY No.2	SPF
P - L	2x8	DRY No.2	SPF
L - J	2x8	DRY No.2	SPF

ALL WEBS 2x3 DRY No.2 SPF

DRY: SEASONED LUMBER.

DESIGN CONSISTS OF 2 TRUSSES BUILT SEPARATELY THEN FASTENED TOGETHER AS FOLLOWS:

CHORDS	#ROWS	SURFACE SPACING (IN)	LOAD (PLF)
TOP CHORDS : (0.122"x3") SPIRAL NAILS			
R - A	1	12	TOP
A - D	1	12	TOP
D - F	1	12	SIDE(0.0)
F - I	2	12	SIDE(183.1)
I - L	2	12	TOP
BOTTOM CHORDS : (0.122"x3") SPIRAL NAILS			
R - P	2	12	SIDE(0.0)
P - L	2	12	SIDE(183.1)
L - J	2	12	TOP
WEBS : (0.122"x3") SPIRAL NAILS			
2x3	1	6	

NAILS TO BE DRIVEN FROM ONE SIDE ONLY.

GIRDER NAILING ASSUMES NAILED HANGERS ARE FASTENED WITH MIN. 3-0 INCH NAILS.

TOP - COMPONENTS ARE LOADED FROM THE TOP AND MUST BE PLACED ON TOP EDGE OF ALL PLIES FOR THE LOAD TO BE TRANSFERRED TO EACH PLY.

SIDE - PLF SHOWN IS THE EQUIVALENT UDL APPLIED TO ONE SIDE THAT THE CORRESPONDING NAILING PATTERN SHALL BE CAPABLE OF TRANSFERING. REMAINING PLF MUST BE APPLIED ON THE OPPOSITE SIDE OR ON THE TOP.

DIMENSIONS, SUPPORTS AND LOADINGS SPECIFIED BY FABRICATOR TO BE VERIFIED BY BUILDING DESIGNER

BEARINGS							
	FACTORED	GROSS REACTION		MAXIMUM FACTORED		INPUT	REQD
		VERT	HORZ	DOWN	HORZ	UPLIFT	BRG
JT							
R	4002	0	4002	0	0	3-8	3-8
J	3132	0	3132	0	0	3-8	3-8

UNFACTORED REACTIONS

1ST CASE	MAX/MIN. COMPONENT REACTIONS						
	COMBINED	SNOW	LIVE	PERM.LIVE	WIND	DEAD	SOIL
JT	2824	1886 / 0	0 / 0	0 / 0	0 / 0	938 / 0	0 / 0
R	2212	1470 / 0	0 / 0	0 / 0	0 / 0	742 / 0	0 / 0

BEARING MATERIAL TO BE SPF NO.2 OR BETTER AT JOINT(S) R, J

BRACING

TOP CHORD TO BE SHEATHED OR MAX. PURLIN SPACING = 3.84 FT.

MAX. UNBRACED BOTTOM CHORD LENGTH = 10.00 FT. OR RIGID CEILING DIRECTLY APPLIED.

ALL PITCH BREAKS AND PERIMETER CORNER JOINTS MUST BE Laterally RESTRAINED.

LOADING

TOTAL LOAD CASES: (4)

CHORDS				WEBS			
MEMB.	MAX. FACTORED FORCE (LBS)	FACTORED VERT. LOAD (PLF)	MAX. CSI (LC)	MEMB.	MAX. FACTORED FORCE (LBS)	MAX. CSI (LC)	
FR-TO		FROM TO		FR-TO			
R-A	-3851 / 0	0.0	0.0 0.44 (1)	K-I	0 / 5428	0.87 (1)	
A-S	-5722 / 0	-91.8	-91.8 0.25 (1)	A-Q	0 / 8717	0.83 (1)	
S-T	-5722 / 0	-91.8	-91.8 0.25 (1)	K-H	-2763 / 0	0.33 (1)	
T-B	-5722 / 0	-91.8	-91.8 0.25 (1)	Q-B	-2710 / 0	0.32 (1)	
B-C	-8548 / 0	-91.8	-91.8 0.27 (1)	M-H	0 / 4038	0.80 (1)	
C-D	-10219 / 0	-91.8	-91.8 0.34 (1)	B-O	0 / 3700	0.48 (1)	
D-U	-10219 / 0	-91.8	-91.8 0.34 (1)	M-G	-1901 / 0	0.23 (1)	
U-E	-10219 / 0	-91.8	-91.8 0.34 (1)	C-Q	-1400 / 0	0.17 (1)	
E-V	-10219 / 0	-91.8	-91.8 0.31 (1)	N-G	0 / 2591	0.32 (1)	
V-F	-10219 / 0	-91.8	-91.8 0.31 (1)	C-N	0 / 1826	0.20 (1)	
F-G	-10219 / 0	-91.8	-91.8 0.31 (1)	N-E	-710 / 0	0.08 (1)	
Q-H	-8031 / 0	-91.8	-91.8 0.28 (1)				
H-I	-4822 / 0	-91.8	-91.8 0.18 (1)				
I-J	-3071 / 0	0.0	0.0 0.35 (1)				

R-W	0 / 0	-18.5	-18.5 0.15 (1)	10.00
W-X	0 / 0	-18.5	-18.5 0.15 (1)	10.00
X-Y	0 / 0	-18.5	-18.5 0.15 (1)	10.00
Y-Q	0 / 0	-18.5	-18.5 0.15 (1)	10.00
Q-P	0 / 5722	-18.5	-18.5 0.44 (1)	10.00
P-O	0 / 5722	-18.5	-18.5 0.44 (1)	10.00
O-Z	0 / 8846	-18.5	-18.5 0.81 (1)	10.00
Z-AA	0 / 8846	-18.5	-18.5 0.81 (1)	10.00
AA-N	0 / 8846	-18.5	-18.5 0.81 (1)	10.00
N-AB	0 / 8031	-18.5	-18.5 0.74 (1)	10.00
AB-AC	0 / 8031	-18.5	-18.5 0.74 (1)	10.00
AC-M	0 / 8031	-18.5	-18.5 0.74 (1)	10.00
M-L	0 / 4622	-18.5	-18.5 0.33 (1)	10.00
L-K	0 / 4622	-18.5	-18.5 0.33 (1)	10.00
K-J	0 / 0	-18.5	-18.5 0.04 (1)	10.00

FACTORED CONCENTRATED LOADS (LBS)							
JT	LOC.	LC1	MAX.	MAX.	FACE	DIR.	CONN.
S	1-10-12	-110	-110	---	BACK	VERT	TOTAL
T	3-10-12	-110	-110	---	BACK	VERT	TOTAL
U	15-8-12	-110	-110	---	BACK	VERT	TOTAL
V	17-8-12	-110	-110	---	BACK	VERT	TOTAL
W	1-10-12	-28	-28	---	BACK	VERT	TOTAL
X	3-10-12	-28	-28	---	BACK	VERT	TOTAL
Y	5-1-8	-727	-727	---	BACK	VERT	TOTAL
Z	13-0-8	-727	-727	---	BACK	VERT	TOTAL
AA	15-8-12	-28	-28	---	BACK	VERT	TOTAL
AB	17-8-12	-28	-28	---	BACK	VERT	TOTAL

DESIGN CRITERIA

SPECIFIED LOADS:

TOP CH. LL = 25.6 PSF

DL = 6.0 PSF

BOT CH. LL = 0.0 PSF

DL = 7.4 PSF

TOTAL LOAD = 39.0 PSF

SPACING = 24.0 IN. C/C

LOADING IN FLAT SECTION BASED ON A SLOPE OF 8.00/12

THIS TRUSS IS DESIGNED FOR RESIDENTIAL OR SMALL BUILDING REQUIREMENTS OF PART 9, NBC 2010, NBCC 2015

THIS DESIGN COMPLIES WITH:

- PART 9 OF CBC 2018, CBC 2012, ABC 2019
- PART 9 OF CBC 2012 (2019 AMENDMENT)
- CSA 088-08, CSA 088-14
- TPIC 2011, TPIC 2014

(55% OF 31.3 P.S.F. G.S.L. PLUS 8.4 P.S.F. RAIN LOAD) EQUALS 25.6 P.S.F. SPECIFIED ROOF LIVE LOAD

ALLOWABLE DEFL.(LL) = L/360 (1.16")

CALCULATED VERT. DEFL.(LL) = L/899 (0.28")

ALLOWABLE DEFL.(TL) = L/360 (1.16")

CALCULATED VERT. DEFL.(TL) = L/828 (0.60")

CSI: TC=0.44/1.00 (A-R:1), BC=0.81/1.00 (N-O:1),

WB=0.83/1.00 (A-Q:1), SS=0.41/1.00 (M-N:1)

DOL LUMBER=1.00 NAIL=1.00 LS BEND=1.00

COMP=1.00 SHEAR=1.00 TENS=1.00

COMPANION LIVE LOAD FACTOR = 1.00

TRUSS PLATE MANUFACTURER IS NOT RESPONSIBLE FOR QUALITY CONTROL IN THE TRUSS MANUFACTURING PLANT.

NAIL VALUES

PLATE GRIP(DRY) SHEAR SECTION

(PSI) (PLI) (PLI)

MAX MIN MAX MIN MAX MIN


MT20 618 354 1887 788 1887 1858

PLATE PLACEMENT TOL. = 0.250 inches

PLATE ROTATION TOL. = 5.0 Deg.

JSI GRIP= 0.88 (M) (INPUT = 0.90)

JSI METAL= 0.50 (P) (INPUT = 1.00)



Structural component only

DWG# T-2007064 1/L

JOB NAME	TRUSS NAME	QUANTITY	PLY	JOB DESC.	DRWG NO.
408150	T1Z	1	2	GREEN PARK HOMES	
Tamarack Roof Truss, Burlington					

Version 8.310 S Oct 29 2019 MTEK Industries, Inc. Sat Apr 26 11:02:48 2020 Page 2
ID:7vF7aG0E03cRUI6X1SkziWYK-SrplVvTQ3 UVGPVZTPnKeJDIEFIF7bWig7 NRrzNCna

PLATES (table in inches)

JT	TYPE	PLATES	W	LEN	Y	X
A	TMWW-t	MT20	6.0	9.0		Edge
B	TMWW-t	MT20	5.0	6.0	2.50	2.75
C	TMWW-t	MT20	5.0	6.0		
D	TS-t	MT20	5.0	6.0		
E	TMWW-w	MT20	3.0	6.0		
F	TS-t	MT20	5.0	6.0		
G	TMWW-t	MT20	5.0	6.0		
H	TMWW-t	MT20	5.0	6.0	2.50	2.75
I	TMWW-t	MT20	6.0	9.0		Edge
J	BMV1+p	MT20	3.0	6.0		
K	BMWW-t	MT20	6.0	9.0	3.00	4.25
L	BS-t	MT20	6.0	6.0		
M	BMWW-t	MT20	5.0	6.0	2.50	2.75
N	BMWW-t	MT20	6.0	6.0		
O	BMWW-t	MT20	5.0	6.0	2.50	2.75
P	BS-t	MT20	5.0	6.0		
Q	BMWW-t	MT20	6.0	9.0	3.00	4.25
R	BMV1+p	MT20	3.0	6.0		

Edge - INDICATES REFERENCE CORNER OF PLATE TOUCHES EDGE OF CHORD.

FACTORED CONCENTRATED LOADS (LBS)

JT	LOC.	LC1	MAX-	MAX+	FACE	DIR.	TYPE	HEEL	CONN.
AC	18-3-8	-1293	-1293	---	BACK	VERT	TOTAL	---	CI

CONNECTION REQUIREMENTS

- 1) C1: A SUITABLE HANGER/MECHANICAL CONNECTION IS REQUIRED.




Structural component only
DWG# T-2007064 72

JOB NAME	TRUSS NAME	QUANTITY	PLY	JOB DESC.	DRWG NO.
408150	T2	2	1	GREEN PARK HOMES	

Tamarack Roof Truss, Burlington

Version 8.310 S Oct 29 2019 Mitek Industries, Inc. Sat Apr 25 11:02:50 2020 Page 1
ID:7vF7aG0E03cRUj8X1jSkzWYK-wtMqjFT2qdMuZ4H16ZBXmNxiPs5W3njxZHnCNZ



LUMBER	CHORDS	SIZE	LUMBER	DESCR.
N. L. G. A. RULES				
R - A	2x4	DRY	No.2	SPF
A - C	2x4	DRY	No.2	SPF
C - G	2x4	DRY	No.2	SPF
G - I	2x4	DRY	No.2	SPF
I - J	2x4	DRY	No.2	SPF
J - O	2x4	DRY	No.2	SPF
O - M	2x4	DRY	No.2	SPF
M - J	2x4	DRY	No.2	SPF
ALL WEBS	2x3	DRY	No.2	SPF
DRY: SEASONED LUMBER.				

PLATES (table in inches)	JT TYPE	PLATES	W	LEN	Y	X
A	TMVW-1	MT20	5.0	6.0	2.00	2.25
B	TMVW-1	MT20	5.0	6.0		
C	TS-1	MT20	3.0	6.0		
D	TMVW-1	MT20	4.0	4.0		
E	TMVW-1	MT20	2.0	4.0		
F	TMVW-1	MT20	4.0	4.0		
G	TS-1	MT20	3.0	6.0		
H	TMVW-1	MT20	5.0	6.0		
I	TMVW-1	MT20	5.0	6.0	2.00	2.25
J	BMV1+p	MT20	3.0	4.0		
K	BMVW-1	MT20	5.0	6.0	2.00	2.25
L	BMVW-1	MT20	5.0	6.0		
M	BS-1	MT20	3.0	6.0		
N	BMVW-1	MT20	4.0	6.0		
O	BS-1	MT20	3.0	6.0		
P	BMVW-1	MT20	5.0	6.0		
Q	BMVW-1	MT20	5.0	6.0	2.00	2.25
R	BMV1+p	MT20	3.0	4.0		

DIMENSIONS, SUPPORTS AND LOADINGS SPECIFIED BY FABRICATOR TO BE VERIFIED BY BUILDING DESIGNER

BEARINGS	FACTORED	MAXIMUM FACTORED	INPUT	REQD
	GROSS REACTION	GROSS REACTION	BRG	BRG
JT	VERT	HORZ	DOWN	UPLIFT
R	1920	0	0	3-8
J	1920	0	0	3-8

UNFACTORED REACTIONS	1ST CASE	MAX/MIN COMPONENT REACTIONS
	COMBINED	SNOW
R	1358	891 / 0
J	1358	891 / 0

BEARING MATERIAL TO BE SPF NO.2 OR BETTER AT JOINT(S) R, J

BRACING
TOP CHORD TO BE SHEATHED OR MAX. PURLIN SPACING = 3.23 FT.
MAX. UNBRACED BOTTOM CHORD LENGTH = 10.00 FT OR RIGID CEILING DIRECTLY APPLIED.

ALL PITCH BREAKS AND PERIMETER CORNER JOINTS MUST BE Laterally RESTRAINED.

LOADING	TOTAL LOAD CASES: (4)
CHORDS	WEBS
MEMB.	MEMB.
MAX. FACTORED	MAX. FACTORED
FORCE (LBS)	FORCE (LBS)
VERT. LOAD (LBS)	VERT. LOAD (LBS)
PLF (LBS)	PLF (LBS)
CSF (LBS)	CSF (LBS)
MAX. UNBRACED LENGTH (LBS)	MAX. UNBRACED LENGTH (LBS)
FR-TO	FR-TO
R-A	-1875 / 0
A-B	-2042 / 0
B-C	-3149 / 0
C-D	-3149 / 0
D-E	-3533 / 0
E-F	-3533 / 0
F-G	-3149 / 0
G-H	-3149 / 0
H-I	-2042 / 0
I-J	-1875 / 0
R-Q	0 / 0
Q-P	0 / 2042
P-O	0 / 3149
O-N	0 / 3149
N-M	0 / 3149
M-L	0 / 3149
L-K	0 / 2042
K-J	0 / 0

TOTAL WEIGHT = 2 X 143 = 286 lb

DESIGN CRITERIA
SPECIFIED LOADS:
TOP CH. LL = 25.6 PSF
DL = 8.0 PSF
BOT CH. LL = 0.0 PSF
DL = 7.4 PSF
TOTAL LOAD = 39.0 PSF
SPACING = 24.0 IN. C.C.

LOADING IN FLAT SECTION BASED ON A SLOPE OF 6.00/12

THIS TRUSS IS DESIGNED FOR RESIDENTIAL OR SMALL BUILDING REQUIREMENTS OF PART 9, NBC 2010, NBC 2015

THIS DESIGN COMPLIES WITH:
- PART 9 OF CBC 2010, CBC 2012, ABC 2019
- PART 9 OF CBC 2012 (2019 AMENDMENT)
- CSA 088-09, CSA 088-14
- TPIC 2011, TPIC 2014

(55% OF 31.3 P.S.F. G.S.L. PLUS 8.4 P.S.F. RAIN LOAD) EQUALS 25.6 P.S.F. SPECIFIED ROOF LIVE LOAD

ALLOWABLE DEFL.(LL) = L/360 (1.16")
CALCULATED VERT. DEFL.(LL) = L/998 (0.23")
ALLOWABLE DEFL.(TL) = L/360 (1.16")
CALCULATED VERT. DEFL.(TL) = L/998 (0.42")

CSI: TC=0.83/1.00 (A-R:1), BC=0.58/1.00 (N-P:1), WB=0.59/1.00 (I-K:1), SS=0.25/1.00 (A-B:1)

DOL LUMBER=1.00 NAIL=1.00 LS BEND=1.10
COMP=1.10 SHEAR=1.10 TENS=1.10

COMPANION LIVE LOAD FACTOR = 1.00

TRUSS PLATE MANUFACTURER IS NOT RESPONSIBLE FOR QUALITY CONTROL IN THE TRUSS MANUFACTURING PLANT.

NAIL VALUES
PLATE GRIP(DRY) SHEAR SECTION
(PS) (PL) (PL) (PL)
MAX MIN MAX MIN MAX MIN
MT20 618 354 1687 788 1987 1658

PLATE PLACEMENT TOL. = 0.250 inches

PLATE ROTATION TOL. = 5.0 Deg.

JSI GRIP = 0.89 (A) (INPUT = 0.90)
JSI METAL = 0.98 (A) (INPUT = 1.00)




Structural component only
DWG# T-2007065

JOB NAME 408150	TRUSS NAME T3	QUANTITY 2	PLY 1	JOB DESC. GREEN PARK HOMES	TRUSS DESC.	DRWG NO.
---------------------------	-------------------------	----------------------	-----------------	--------------------------------------	-------------	----------

Tamarack Roof Truss, Burlington

Version 8.310 S Oct 29 2019 MITek Industries, Inc. Sat Apr 25 11:02:31 2020 Page 1
ID: i7vF?aG0E03cRUj6X1JsrkzIWK-0Ew2wbUhbclDWjxbqpkJk233bSy0IRTUVizNCnY



LUMBER	SIZE	DESCR.
N. L. G. A. RULES		
CHORDS		
R - A	2x4 DRY	No.2
A - C	2x4 DRY	No.2
C - G	2x4 DRY	No.2
G - I	2x4 DRY	No.2
I - J	2x4 DRY	No.2
J - O	2x4 DRY	No.2
O - M	2x4 DRY	No.2
M - J	2x4 DRY	No.2
ALL WEBS	2x3 DRY	No.2
DRY: SEASONED LUMBER.		

PLATES (table is in inches)	W	LEN	Y	X
JT TYPE				
A - TMVW-1	MT20	5.0	8.0	2.00 2.50
B - TMVW-1	MT20	5.0	8.0	
C - TS-1	MT20	3.0	8.0	
D - TMVW-1	MT20	4.0	4.0	
E - TMVW-1	MT20	2.0	4.0	
F - TMVW-1	MT20	4.0	4.0	
G - TS-1	MT20	3.0	8.0	
H - TMVW-1	MT20	5.0	8.0	
I - TMVW-1	MT20	5.0	8.0	2.00 2.50
J - BMV1-p	MT20	3.0	4.0	
K - BMVW-1	MT20	5.0	8.0	2.00 2.50
L - BMVW-1	MT20	5.0	8.0	
M - BS-1	MT20	3.0	8.0	
N - BMVW-1	MT20	4.0	8.0	
O - BS-1	MT20	3.0	8.0	
P - BMVW-1	MT20	5.0	8.0	
Q - BMVW-1	MT20	5.0	8.0	2.00 2.50
R - BMV1-p	MT20	3.0	4.0	

DIMENSIONS, SUPPORTS AND LOADINGS SPECIFIED BY FABRICATOR TO BE VERIFIED BY BUILDING DESIGNER

BEARINGS	FACTORED GROSS REACTION	MAXIMUM FACTORED GROSS REACTION	INPUT BRG	REQD BRG
JT	VERT	HORZ	DOWN	HORZ
R	1920	0	1920	0
J	1920	0	1920	0

UNFACTORED REACTIONS

1ST CASE	MAX. MIN. COMPONENT REACTIONS
JT	COMBINED
R	1368
J	1368

BEARING MATERIAL TO BE SPF NO.2 OR BETTER AT JOINT(S) R, J

BRACING

TOP CHORD TO BE SHEATHED OR MAX. PURLIN SPACING = 3.59 FT.
MAX. UNBRACED BOTTOM CHORD LENGTH = 10.00 FT OR RIGID CEILING DIRECTLY APPLIED.

ALL PITCH BREAKS AND PERIMETER CORNER JOINTS MUST BE LATERALLY RESTRAINED.

1 LATERAL BRACE(S) AT 1/2 LENGTH OF A-R, I-J.

END VERTICAL(S) MUST BE SHEATHED OR HAVE BRACES AS INDICATED IN THE MAX. UNBRACED LENGTH COLUMN OF THE TABLE BELOW

LOADING

TOTAL LOAD CASES: (4)

CHORDS	MEMB.	MAX. FACTORED FORCE (LBS)	VERT. LOAD (PLF)	MAX. FACTORED FORCE (LBS)	MAX. FACTORED FORCE (LBS)	MAX. FACTORED FORCE (LBS)	MAX. FACTORED FORCE (LBS)
FR-TO							
R-A	-1875 / 0	0.0	0.0	0.33 (1)	4.90	K-I	0 / 2388
A-B	-1691 / 0	-91.8	-91.8	0.56 (1)	4.46	A-Q	0 / 2388
B-C	-2608 / 0	-91.8	-91.8	0.68 (1)	3.63	K-H	-1538 / 0
C-D	-2608 / 0	-91.8	-91.8	0.68 (1)	3.63	Q-B	-1538 / 0
D-E	-2627 / 0	-91.8	-91.8	0.58 (1)	3.59	L-H	0 / 1304
E-F	-2627 / 0	-91.8	-91.8	0.58 (1)	3.59	B-P	0 / 1304
F-G	-2608 / 0	-91.8	-91.8	0.68 (1)	3.63	L-F	-828 / 0
G-H	-2608 / 0	-91.8	-91.8	0.68 (1)	3.63	P-D	-828 / 0
H-I	-1691 / 0	-91.8	-91.8	0.55 (1)	4.46	N-F	0 / 453
I-J	-1875 / 0	0.0	0.0	0.33 (1)	4.90	D-N	0 / 453
R-Q	0 / 0	-18.5	-18.5	0.15 (4)	10.00	N-E	-537 / 0
Q-P	0 / 1691	-18.5	-18.5	0.35 (1)	10.00		
P-O	0 / 2608	-18.5	-18.5	0.47 (1)	10.00		
O-N	0 / 2608	-18.5	-18.5	0.47 (1)	10.00		
N-M	0 / 2608	-18.5	-18.5	0.47 (1)	10.00		
M-L	0 / 2608	-18.5	-18.5	0.47 (1)	10.00		
L-K	0 / 1691	-18.5	-18.5	0.35 (1)	10.00		
K-J	0 / 0	-18.5	-18.5	0.15 (4)	10.00		

TOTAL WEIGHT = 2 X 153 = 305 lb

DESIGN CRITERIA

SPECIFIED LOADS:

TOP CH.	LL =	25.6	PSF
	DL =	6.0	PSF
BOT CH.	LL =	0.0	PSF
	DL =	7.4	PSF
TOTAL LOAD	=	39.0	PSF

SPACING = 24.0 IN. C/C

LOADING IN FLAT SECTION BASED ON A SLOPE OF 8.00/12

THIS TRUSS IS DESIGNED FOR RESIDENTIAL OR SMALL BUILDING REQUIREMENTS OF PART 9, NBC 2010, NBC 2015

THIS DESIGN COMPLIES WITH:

- PART 9 OF NBC 2010, CBC 2012, ABC 2010
- PART 9 OF CBC 2012 (2019 AMENDMENT)
- CSA 086-09, CSA 085-14
- TPIC 2011, TPIC 2014

(55% OF 31.3 P.S.F. G.S.L. PLUS 8.4 P.S.F. RAIN LOAD) EQUALS 26.6 P.S.F. SPECIFIED ROOF LIVE LOAD

ALLOWABLE DEFL.(LL) = L/360 (1.16")
CALCULATED VERT. DEFL.(LL) = L/999 (0.18")
ALLOWABLE DEFL.(TL) = L/360 (1.16")
CALCULATED VERT. DEFL.(TL) = L/999 (0.33")

CSI: TC=0.88/1.00 (F-H:1), BC=0.47/1.00 (N-P:1), WB=0.98/1.00 (H-K:1), SSI=0.25/1.00 (A-B:1)

DOL LUMBER=1.00 NAIL=1.00 LS BEND=1.10
COMP=1.10 SHEAR=1.10 TENS=1.10

COMPANION LIVE LOAD FACTOR = 1.00

TRUSS PLATE MANUFACTURER IS NOT RESPONSIBLE FOR QUALITY CONTROL IN THE TRUSS MANUFACTURING PLANT.

NAIL VALUES

PLATE GRIP (DRY)	SHEAR	SECTION
(PSI)	(PLI)	(PLI)
MAX MIN	MAX MIN	MAX MIN
MT20	618 354 1887 788 1987 1858	

PLATE PLACEMENT TOL = 0.250 inches


PLATE ROTATION TOL = 5.0 Deg.

JSI GRIP = 0.88 (J) (INPUT = 0.90)
JSI METAL = 0.83 (M) (INPUT = 1.00)



Structural component only
DWG# T-2007066

JOB NAME	TRUSS NAME	QUANTITY	PLY	JOB DESC.	DRWG NO.
408150	T4	2	1	GREEN PARK HOMES	
Tamarack Roof Truss, Burlington					
Version 8.310 S Oct 29 2019 Mitek Industries, Inc. Sat Apr 25 11:02:52 2020 Page 1					
ID:17vF7aG0E03cRUJ6X11SkzWYK-sQUQ8wVJMv47IE88XL1GyrHNSOJK7q9W4C12AzNCnX					
Scale = 1:54.0					



LUMBER			
N. L. G. A. RULES	CHORDS	SIZE	LUMBER
P - A	2x4	DRY	No.2
A - C	2x4	DRY	No.2
C - F	2x4	DRY	No.2
F - H	2x4	DRY	No.2
I - H	2x4	DRY	No.2
P - N	2x4	DRY	No.2
N - K	2x4	DRY	No.2
K - I	2x4	DRY	No.2
ALL WEBS	2x3	DRY	No.2
EXCEPT			
J - H	2x4	DRY	No.2

DRY: SEASONED LUMBER.

PLATES (table is in inches)					
JT	TYPE	PLATES	W	LEN	Y X
A	TMVW-1	MT20	5.0	8.0	2.25 2.00
B	TMVW-1	MT20	4.0	8.0	
C	TS-1	MT20	3.0	8.0	
D	TMVW-1	MT20	4.0	4.0	
E	TMVW-1	MT20	2.0	4.0	
F	TS-1	MT20	3.0	8.0	
G	TMVW-1	MT20	4.0	8.0	
H	TMVW-1	MT20	5.0	8.0	2.50 2.50
I	BMV1+p	MT20	3.0	4.0	
J	BMVW-1	MT20	5.0	8.0	2.50 2.50
K	BS-1	MT20	3.0	8.0	
L	BMVW-1	MT20	4.0	8.0	
M	BMVW-1	MT20	4.0	8.0	
N	BS-1	MT20	3.0	8.0	
O	BMVW-1	MT20	5.0	8.0	2.00 2.50
P	BMV1+p	MT20	3.0	4.0	

DIMENSIONS, SUPPORTS AND LOADINGS SPECIFIED BY FABRICATOR TO BE VERIFIED BY BUILDING DESIGNER

BEARINGS		FACTORED		MAXIMUM FACTORED		INPUT		REQ'D	
JT	VERT	GROSS	REACTION	GROSS	REACTION	BRG	IN-SX	BRG	IN-SX
P	1920	0	1920	0	0	3-8	3-8	3-8	3-8
I	1920	0	1920	0	0	3-8	3-8	3-8	3-8

UNFACTORED REACTIONS

JT	1ST CASE	MAX/MIN	COMPONENT	REACTIONS	SNOW	LIVE	PERM	LIVE	WIND	DEAD	SOIL
P	1358	891/0	0/0	0/0	0/0	0/0	0/0	487/0	0/0	487/0	0/0
I	1358	891/0	0/0	0/0	0/0	0/0	0/0	487/0	0/0	487/0	0/0

BEARING MATERIAL TO BE SPF NO.2 OR BETTER AT JOINT(S) P, I

BRACING

TOP CHORD TO BE SHEATHED OR MAX. PURLIN SPACING = 3.31 FT.
MAX. UNBRACED BOTTOM CHORD LENGTH = 10.00 FT OR RIGID CEILING DIRECTLY APPLIED.
ALL PITCH BREAKS AND PERIMETER CORNER JOINTS MUST BE LATERALLY RESTRAINED.

1 LATERAL BRACE(S) AT 1/2 LENGTH OF A-P, H-I, B-O, D-L, G-J.

END VERTICAL(S) MUST BE SHEATHED OR HAVE BRACES AS INDICATED IN THE MAX. UNBRACED LENGTH COLUMN OF THE TABLE BELOW

LOADING

TOTAL LOAD CASES: (4)

CHORDS		FACTORED		WEBS		FACTORED	
MEMB.	FORCE (LBS)	VERT. LOAD	LC1 MAX	MEMB.	FORCE (LBS)	VERT. LOAD	LC1 MAX
FR-TO		FROM	TO	FR-TO		FROM	TO
P-A	-1888/0	0.0	0.0 0.43 (1)	A-O	0/2315	0.52 (1)	0.47 (1)
A-B	-1892/0	-91.8	-91.8 0.82 (1)	O-B	-1488/0	0.47 (1)	0.24 (1)
B-C	-2418/0	-91.8	-91.8 0.95 (1)	B-M	0/1058	0.24 (1)	0.54 (1)
C-D	-2418/0	-91.8	-91.8 0.95 (1)	M-D	-817/0	0.54 (1)	0.00 (1)
D-E	-2415/0	-91.8	-91.8 0.74 (1)	D-L	-2/0	0.00 (1)	0.54 (1)
E-F	-2415/0	-91.8	-91.8 0.98 (1)	L-E	-818/0	0.54 (1)	0.24 (1)
F-G	-2415/0	-91.8	-91.8 0.95 (1)	L-G	0/1064	0.24 (1)	0.47 (1)
G-H	-1683/0	-91.8	-91.8 0.82 (1)	J-G	-1485/0	0.47 (1)	0.37 (1)
H-I	-1688/0	0.0	0.0 0.43 (1)	J-H	0/2316	0.37 (1)	
P-O	0/0	-18.5	-18.5 0.22 (4)				
O-N	0/1882	-18.5	-18.5 0.39 (1)				
N-M	0/1862	-18.5	-18.5 0.39 (1)				
M-L	0/2418	-18.5	-18.5 0.47 (1)				
L-K	0/1863	-18.5	-18.5 0.39 (1)				
K-J	0/1883	-18.5	-18.5 0.39 (1)				
J-I	0/0	-18.5	-18.5 0.22 (4)				

TOTAL WEIGHT = 2 X 157 = 313 lb

DESIGN CRITERIA

SPECIFIED LOADS:

TOP CH.	LL	= 25.8	PSF
DL	= 8.0	PSF	
BOT CH.	LL	= 0.0	PSF
DL	= 7.4	PSF	
TOTAL LOAD	= 39.0	PSF	

SPACING = 24.0 IN/C

LOADING IN FLAT SECTION BASED ON A SLOPE OF 6.00/12

THIS TRUSS IS DESIGNED FOR RESIDENTIAL OR SMALL BUILDING REQUIREMENTS OF PART 9, NBCO 2010, NBCO 2015

THIS DESIGN COMPLIES WITH:

- PART 9 OF NBCO 2010, NBCO 2012, ABC 2019
- PART 9 OF NBCO 2012 (2019 AMENDMENT)
- CSA 086-09, CSA 088-14
- TPIC 2011, TPIC 2014

(55% OF 31.3 P.S.F. G.S.L. PLUS 8.4 P.S.F. RAIN LOAD) EQUALS 26.6 P.S.F. SPECIFIED ROOF LIVE LOAD

ALLOWABLE DEFL.(LL) = L/360 (1.16')
CALCULATED VERT. DEFL.(LL) = L/999 (0.15')
ALLOWABLE DEFL.(TL) = L/360 (1.16')
CALCULATED VERT. DEFL.(TL) = L/999 (0.29')

CSI: TC=0.98/1.00 (E-G:1), BC=0.47/1.00 (L-M:1), WB=0.54/1.00 (D-M:1), SS=0.30/1.00 (G-H:1)

DOL LUMBER=1.00 NAIL=1.00 LB BEND=1.10
COMP=1.10 SHEAR=1.10 TENS=1.10

COMPANION LIVE LOAD FACTOR = 1.00.

TRUSS PLATE MANUFACTURER IS NOT RESPONSIBLE FOR QUALITY CONTROL IN THE TRUSS MANUFACTURING PLANT.


NAIL VALUES

PLATE GRIP(DRY)	SHEAR	SECTION
(PSI)	(PLI)	(PLI)
MAX	MIN	MAX MIN
MT20	818	354 1687 788 1987 1686

PLATE PLACEMENT TOL. = 0.250 inches

PLATE ROTATION TOL. = 5.0 Deg.


JSI GRIP = 0.90 (A) (INPUT = 0.90)
JSI METAL = 0.53 (K) (INPUT = 1.00)



Structural component only
DWG# T-2007067

JOB NAME	TRUSS NAME	QUANTITY	PLY	JOB DESC.	DRWG NO.
408150	T5	10	1	GREEN PARK HOMES	
Tamarack Roof Truss, Burlington					

Version 8.310 5 Oct 29 2019 MTEK Industries, Inc. Sat Apr 25 11:02:53 2020 Page 1
 ID:7VF?aG0E03cRUj6X1jSkzWYK-Kc2pLGWx7D?xI0pKiFsGp9Os5sli3ONJkybacZNCnW
 34-9.3 J4 10-0
 9.28 = 1.543



LUMBER				
N. L. G. A. RULES				
CHORDS	SIZE	DRY	No.2	DESCR.
P - A	2x4	DRY	No.2	SPF
A - C	2x4	DRY	No.2	SPF
C - F	2x4	DRY	No.2	SPF
F - H	2x4	DRY	No.2	SPF
I - H	2x4	DRY	No.2	SPF
P - N	2x4	DRY	No.2	SPF
N - K	2x4	DRY	No.2	SPF
K - I	2x4	DRY	No.2	SPF
ALL WEBS	2x4	DRY	No.2	SPF
EXCEPT				
J - G	2x3	DRY	No.2	SPF
O - B	2x3	DRY	No.2	SPF
L - E	2x3	DRY	No.2	SPF
M - D	2x3	DRY	No.2	SPF

DRY: SEASONED LUMBER.

PLATES (tablets in inches)

JT	TYPE	PLATES	W	LEN	Y	X
A	TMVW-1	MT20	5.0	8.0	2.50	2.50
B	TMVW-1	MT20	4.0	8.0		
C	TS-1	MT20	3.0	8.0		
D	TMVW-1	MT20	2.0	4.0		
E	TMVW-1	MT20	4.0	4.0		
F	TS-1	MT20	3.0	8.0		
G	TMVW-1	MT20	4.0	8.0		
H	TMVW-1	MT20	5.0	8.0	2.50	2.50
I	BMV-1	MT20	3.0	4.0		
J	BMVW-1	MT20	5.0	8.0	2.50	2.50
K	BS-1	MT20	3.0	8.0		
L	BMVW-1	MT20	4.0	8.0		
M	BMVW-1	MT20	4.0	8.0		
N	BS-1	MT20	3.0	8.0		
O	BMVW-1	MT20	5.0	8.0	2.50	2.50
P	BMV-1	MT20	3.0	4.0		

DIMENSIONS, SUPPORTS AND LOADINGS SPECIFIED BY FABRICATOR TO BE VERIFIED BY BUILDING DESIGNER

BEARINGS

JT	VERT	HORZ	DOWN	HORZ	UPLIFT	IN-SX	REQD
P	1820	0	1920	0	0	3-8	3-8
I	1820	0	1920	0	0	3-8	3-8

UNFACTORED REACTIONS

JT	1ST CASE	MAX. MIN.	COMBINED	SNOW	LIVE	PERM. LIVE	WIND	DEAD	SOIL
P	1358	891 / 0	0 / 0	0 / 0	0 / 0	0 / 0	467 / 0	0 / 0	0 / 0
I	1358	891 / 0	0 / 0	0 / 0	0 / 0	0 / 0	467 / 0	0 / 0	0 / 0

BEARING MATERIAL TO BE SPF NO.2 OR BETTER AT JOINT(S) P, I

BRACING

TOP CHORD TO BE SHEATHED OR MAX. PURLIN SPACING = 3.58 FT.
 MAX. UNBRACED BOTTOM CHORD LENGTH = 10.00 FT OR RIGID CEILING DIRECTLY APPLIED.

ALL PITCH BREAKS AND PERIMETER CORNER JOINTS MUST BE LATERALLY RESTRAINED.

1 LATERAL BRACE(S) AT 1/2 LENGTH OF A-P, H-I, G-J, B-O, E-M.

END VERTICAL(S) MUST BE SHEATHED OR HAVE BRACES AS INDICATED IN THE MAX. UNBRACED LENGTH COLUMN OF THE TABLE BELOW

LOADING

TOTAL LOAD CASES: (4)

CHORDS				WEBS			
MEMB.	MAX. FACTORED FORCE (LBS)	FACTORED VERT. LOAD (PLF)	MAX. FACTORED CSI (LC)	MEMB.	MAX. FACTORED FORCE (LBS)	MAX. FACTORED CSI (LC)	
FR-TO		FROM TO	LENGTH	FR-TO			
P-A	-1888 / 0	0.0	0.0 0.55 (1)	4.91	J-H	0 / 2171	0.35 (1)
A-B	-1458 / 0	-91.8	-91.8 0.80 (1)	4.28	A-O	0 / 2171	0.35 (1)
B-C	-2108 / 0	-91.8	-91.8 0.90 (1)	3.58	J-G	-1463 / 0	0.81 (1)
C-D	-2108 / 0	-91.8	-91.8 0.80 (1)	3.58	O-B	-1462 / 0	0.81 (1)
D-E	-2108 / 0	-91.8	-91.8 0.68 (1)	4.00	L-G	0 / 982	0.16 (1)
E-F	-2108 / 0	-91.8	-91.8 0.90 (1)	3.58	R-M	0 / 980	0.16 (1)
F-G	-2108 / 0	-91.8	-91.8 0.90 (1)	3.58	L-E	-613 / 0	0.78 (1)
G-H	-1458 / 0	-91.8	-91.8 0.79 (1)	4.27	M-D	-612 / 0	0.77 (1)
H-I	-1888 / 0	0.0	0.0 0.55 (1)	4.91	M-E	-2 / 0	0.00 (1)
P-O	0 / 0	-18.5	-18.5 0.22 (4)	10.00			
O-N	0 / 1458	-18.5	-18.5 0.36 (1)	10.00			
N-M	0 / 1458	-18.5	-18.5 0.36 (1)	10.00			
M-L	0 / 2108	-18.5	-18.5 0.42 (1)	10.00			
L-K	0 / 1458	-18.5	-18.5 0.36 (1)	10.00			
K-J	0 / 1458	-18.5	-18.5 0.36 (1)	10.00			
J-I	0 / 0	-18.5	-18.5 0.22 (4)	10.00			

TOTAL WEIGHT = 10 X 178 = 1785 lb

DESIGN CRITERIA

SPECIFIED LOADS:
 TOP CH. LL = 25.8 PSF
 DL = 8.0 PSF
 BOT CH. LL = 0.0 PSF
 DL = 7.4 PSF
 TOTAL LOAD = 39.0 PSF

SPACING = 24.0 IN. C/C

LOADING IN FLAT SECTION BASED ON A SLOPE OF 8.00/12

THIS TRUSS IS DESIGNED FOR RESIDENTIAL OR SMALL BUILDING REQUIREMENTS OF PART 9, NBC 2010, NBC 2015

THIS DESIGN COMPLIES WITH:
 - PART 9 OF CBC 2018, OBC 2012, ABC 2019
 - PART 9 OF OBC 2012 (2019 AMENDMENT)
 - CSA 086-09, CSA 088-14
 - TPIC 2011, TPIC 2014

(55 % OF 31.3 P.S.F. G.S.L. PLUS 8.4 P.S.F. RAIN LOAD) EQUALS 25.8 P.S.F. SPECIFIED ROOF LIVE LOAD

ALLOWABLE DEFL.(LL) = L/360 (1.16")
 CALCULATED VERT. DEFL.(LL) = L/999 (0.12")
 ALLOWABLE DEFL.(TL) = L/360 (1.16")
 CALCULATED VERT. DEFL.(TL) = L/999 (0.24")

CSK TC=0.90/1.00 (B-O:1), BC=0.42/1.00 (L-M:1), WB=0.78/1.00 (E-L:1), SS=0.31/1.00 (A-B:1)

DOL LUMBER=1.00 NAIL=1.00 LS BEND=1.10
 COMP=1.10 SHEAR=1.10 TENS=1.10

COMPANION LIVE LOAD FACTOR = 1.00

TRUSS PLATE MANUFACTURER IS NOT RESPONSIBLE FOR QUALITY CONTROL IN THE TRUSS MANUFACTURING PLANT.


NAIL VALUES

PLATE GRIP(DRY) SHEAR SECTION
 (PSI) (PLI) (PLI)
 MAX MIN MAX MIN MAX MIN
 MT20 618 354 1887 788 1987 1636


PLATE PLACEMENT TOL. = 0.250 inches

PLATE ROTATION TOL. = 5.0 Deg.

JSI GRIP = 0.87 (A) (INPUT = 0.90)
 JSI METAL = 0.47 (N) (INPUT = 1.00)



Structural component only
 DWG# T-2007068



LUMBER

N. L. G. A. RULES

CHORDS	SIZE	LUMBER	DESCR.
A - C	2x4	DRY No.2	SPF
C - E	2x4	DRY No.2	SPF
E - G	2x4	DRY No.2	SPF
G - I	2x4	DRY No.2	SPF
I - J	2x4	DRY No.2	SPF
J - H	2x4	DRY No.2	SPF
ALL WEBS EXCEPT	2x3	DRY No.2	SPF

DRY: SEASONED LUMBER.

PLATES (table is in inches)

JT TYPE	PLATES	W	LEN	Y	X
B TMVW+p	MT20	5.0	6.0	Edge	2.75
C TTWW+m	MT20	5.0	6.0	2.00	1.50
D TMW+w	MT20	2.0	4.0		
E TTWW+m	MT20	5.0	6.0	2.00	1.50
F TMVW+p	MT20	5.0	6.0	Edge	2.75
H BMV+p	MT20	3.0	6.0		
I BMWV+1	MT20	5.0	6.0	2.50	2.75
J BS+1	MT20	5.0	6.0		
K BMWVW+1	MT20	5.0	6.0		
L BMWVW+1	MT20	5.0	6.0	2.50	2.75
M BMV+1+p	MT20	3.0	6.0		

Edge - INDICATES REFERENCE CORNER OF PLATE TOUCHES EDGE OF CHORD.

DIMENSIONS, SUPPORTS AND LOADINGS SPECIFIED BY FABRICATOR TO BE VERIFIED BY BUILDING DESIGNER

FACTORED		MAXIMUM FACTORED		INPUT	REQRD
	GROSS REACTION	GROSS REACTION		BRG	BRG
JT	VERT	DOWN	HORZ	UPLIFT	IN-SX
M	1888 0	1888 0	0	5-8	5-8
H	1422 0	1422 0	0	5-8	5-8

UNFACTORED REACTIONS

	1ST LOASE	MAX/MIN	COMPONENT REACTIONS
JT COMBINED	SNOW	LIVE	PERM.LIVE
M	1328	809 / 0	0 / 0
H	1001	683 / 0	0 / 0

BEARING MATERIAL TO BE SPF NO.2 OR BETTER AT JOINT(S) M, H

BRACING

TOP CHORD TO BE SHEATHED OR MAX. PURLIN SPACING = 4.55 FT.

MAX. UNBRACED BOTTOM CHORD LENGTH = 10.00 FT OR RIGID CEILING DIRECTLY APPLIED.

ALL PITCH BREAKS AND PERIMETER CORNER JOINTS MUST BE Laterally RESTRAINED.

LOADING

TOTAL LOAD CASES: (4)

CHORDS				WEBS			
MEMB.	FORCE (LBS)	VERT. LOAD	LC1 MAX	MEMB.	FORCE (LBS)	VERT. LOAD	LC1 MAX
FR-TO				FR-TO			
A-B	0 / 41	-91.8	-91.8	10.00	L-C	0 / 383	0.09 (1)
B-C	-1847 / 0	-91.8	-91.8	0.34 (1)	4.55	C-K	0 / 310
C-D	-1641 / 0	-91.8	-91.8	0.36 (1)	4.72	K-D	-481 / 0
D-E	-1641 / 0	-91.8	-91.8	0.36 (1)	4.72	K-E	0 / 1010
E-F	-1225 / 0	-91.8	-91.8	0.30 (1)	5.40	L-E	-274 / 0
F-G	0 / 41	-91.8	-91.8	0.14 (1)	10.00	B-L	0 / 1480
G-H	-1828 / 0	0.0	0.0	0.22 (1)	8.01	L-F	0 / 981
H-F	-1380 / 0	0.0	0.0	0.16 (1)	8.68		
M-N	0 / 0	-18.5	-18.5	0.24 (1)	10.00		
N-L	0 / 0	-18.5	-18.5	0.24 (1)	10.00		
L-O	0 / 1424	-18.5	-18.5	0.70 (1)	10.00		
O-K	0 / 1424	-18.5	-18.5	0.70 (1)	10.00		
K-J	0 / 932	-18.5	-18.5	0.28 (1)	10.00		
J-I	0 / 932	-18.5	-18.5	0.29 (1)	10.00		
I-H	0 / 0	-18.5	-18.5	0.04 (4)	10.00		

FACTORED CONCENTRATED LOADS (LBS)

JT	LOC.	LC1	MAX-	MAX+	FACE	DIR.	TYPE	HEEL	CONN.
C	3-10-8	-241	-241	---	FRONT	VERT	TOTAL	---	C1
L	3-11-4	-17	-17	---	FRONT	VERT	TOTAL	---	C1
N	2-0-12	-17	-17	---	FRONT	VERT	TOTAL	---	C1
O	-8-6-8	-953	-953	---	FRONT	VERT	TOTAL	---	C1

CONNECTION REQUIREMENTS

1) C1: A SUITABLE HANGER/MECHANICAL CONNECTION IS REQUIRED.

DESIGN CRITERIA

SPECIFIED LOADS:

TOP CH. LL = 25.6 PSF

DL = 8.0 PSF

BOT CH. LL = 0.0 PSF

DL = 7.4 PSF

TOTAL LOAD = 39.0 PSF

SPACING = 24.0 IN. C/C

LOADING IN FLAT SECTION BASED ON A SLOPE OF 6.00/12

THIS TRUSS IS DESIGNED FOR RESIDENTIAL OR SMALL BUILDING REQUIREMENTS OF PART 9, NBCC 2010, NBCC 2015

THIS DESIGN COMPLIES WITH:

- PART 9 OF BCBC 2018, OBC 2012, ABO 2019
- PART 9 OF OBC 2012 (2019 AMENDMENT)
- CSA 088-09, CSA 088-14
- TPIC 2011, TPIC 2014

(55% OF 31.3 P.S.F. G.S.L. PLUS 8.4 P.S.F. RAIN LOAD) EQUALS 25.6 P.S.F. SPECIFIED ROOF LIVE LOAD

ALLOWABLE DEFL.(LL) = L/360 (0.65")

CALCULATED VERT. DEFL.(LL) = L/999 (0.08")

ALLOWABLE DEFL.(TL) = L/360 (0.65")

CALCULATED VERT. DEFL.(TL) = L/999 (0.10")

CSI: TC=0.38/1.00 (C-D:1), BC=0.70/1.00 (K-L:1), WB=0.37/1.00 (B-L:1), SS=0.45/1.00 (K-L:1)

DOL LUMBER=1.00 NAIL=1.00 LB BEND=1.00

COMP=1.00 SHEAR=1.00 TENS=1.00

COMPANION LIVE LOAD FACTOR = 1.00

TRUSS PLATE MANUFACTURER IS NOT RESPONSIBLE FOR QUALITY CONTROL IN THE TRUSS MANUFACTURING PLANT.

NAIL VALUES

PLATE GRIP(DRY) SHEAR SECTION (PSI) (PLI) (PLI)

MAX MIN MAX MIN MAX MIN

MT20 618 354 1887 788 1907 1888

PLATE PLACEMENT TOL. = 0.250 inches

PLATE ROTATION TOL. = 5.0 Deg.

JSI GRIP= 0.89 (C) (INPUT = 0.90)

JSI METAL= 0.57 (J) (INPUT = 1.00)




Structural component only
DWG# T-2007069

JOB NAME	TRUSS NAME	QUANTITY	PLY	JOB DESC.	GREEN PARK HOMES	DRWG NO.
408150	T7	1	1	TRUSS DESC.		

Tamarack Roof Truss, Burlington

Version 8.310 S Oct 29 2019 Mtek Industries, Inc. Sat Apr 25 11:02:55 2020 Page 1
ID:7vF7aG0E03cRUj6X1jSikziWYK-G?AZmyXBtqFi_KyjqhukaTK3IVZXS_cD2RiIVzNCnU



Scale = 1/32

LUMBER TOTAL WEIGHT = 70 lb (M/F)

N. L. G. A. RULES	CHORDS	SIZE	LUMBER	DESCR.
A - B	2x4	DRY	No.2	SPF
B - C	2x4	DRY	No.2	SPF
C - D	2x4	DRY	No.2	SPF
I - A	2x4	DRY	No.2	SPF
E - D	2x4	DRY	No.2	SPF
I - G	2x4	DRY	No.2	SPF
G - E	2x4	DRY	No.2	SPF

ALL WEBS 2x3 DRY No.2 SPF

EXCEPT

DRY: SEASONED LUMBER.

PLATES (table in inches)	JT	TYPE	PLATES	W	LEN	Y	X
A	TMVW+p	MT20	4.0	4.0	1.00	2.00	
B	TTWW+m	MT20	6.0	6.0	2.25	1.50	
C	TTW-m	MT20	4.0	4.0			
D	TMVW+p	MT20	4.0	4.0	1.00	2.00	
E	BMV1+p	MT20	3.0	4.0			
F	BMVW-w	MT20	4.0	6.0			
G	BS-1	MT20	3.0	6.0			
H	BMVW-l	MT20	4.0	4.0			
I	BMV1+p	MT20	3.0	4.0			

DIMENSIONS, SUPPORTS AND LOADINGS SPECIFIED BY FABRICATOR TO BE VERIFIED BY BUILDING DESIGNER

BEARINGS	FACTORED	MAXIMUM FACTORED	INPUT	REQD
JT	GROSS REACTION	GROSS REACTION	BRG	BRG
	VERT	HORZ	DOWN	HORZ
I	905	0	905	0
E	905	0	905	0

UNFACTORED REACTIONS	1ST CASE	MAX/MIN COMPONENT REACTIONS	SNOW	LIVE	PERM.LIVE	WIND	DEAD	SOIL
JT	COMBINED							
I	840	420 / 0	0 / 0	0 / 0	0 / 0	0 / 0	220 / 0	0 / 0
E	840	420 / 0	0 / 0	0 / 0	0 / 0	0 / 0	220 / 0	0 / 0

BEARING MATERIAL TO BE SPF NO.2 OR BETTER AT JOINT(S) I, E

BRACING
TOP CHORD TO BE SHEATHED OR MAX. PURLIN SPACING = 8.25 FT.
MAX. UNBRACED BOTTOM CHORD LENGTH = 10.00 FT OR RIGID CEILING DIRECTLY APPLIED.

ALL PITCH BREAKS AND PERIMETER CORNER JOINTS MUST BE Laterally RESTRAINED.

LOADING
TOTAL LOAD CASES: (4)

CHORDS	MEMB.	MAX. FACTORED FORCE (LBS)	VERT. LOAD LGT (PLF)	MAX. CSI (LC)	MAX. UNBRACED LENGTH FR-TO	MEMB.	MAX. FACTORED FORCE (LBS)	MAX. CSI (LC)
A-B	-718 / 0	-91.8	-91.8	0.39 (1)	8.25	H-B	-34 / 68	0.02 (4)
B-C	-558 / 0	-91.8	-91.8	0.28 (1)	6.25	B-F	0 / 14	0.00 (1)
C-D	-729 / 0	-91.8	-91.8	0.42 (1)	8.25	F-C	-23 / 74	0.03 (4)
I-A	-880 / 0	0.0	0.0	0.08 (1)	7.81	A-H	0 / 587	0.13 (1)
E-D	-858 / 0	0.0	0.0	0.09 (1)	7.81	F-D	0 / 572	0.13 (1)
I-H	0 / 0	-18.5	-18.5	0.13 (4)	10.00			
H-G	0 / 650	-18.5	-18.5	0.18 (4)	10.00			
G-F	0 / 650	-18.5	-18.5	0.18 (4)	10.00			
F-E	0 / 0	-18.5	-18.5	0.14 (4)	10.00			

DESIGN CRITERIA

SPECIFIED LOADS:
TOP CH. LL = 25.8 PSF
DL = 8.0 PSF
BOT CH. LL = 0.0 PSF
DL = 7.4 PSF
TOTAL LOAD = 39.0 PSF

SPACING = 24.0 IN. C/C

LOADING IN FLAT SECTION BASED ON A SLOPE OF 6.00/12

THIS TRUSS IS DESIGNED FOR RESIDENTIAL OR SMALL BUILDING REQUIREMENTS OF PART 9, NBC 2010, NBC 2015

THIS DESIGN COMPLIES WITH:
- PART 9 OF CBC 2018, CBC 2012, ABC 2019
- PART 9 OF CBC 2012 (2019 AMENDMENT)
- CSA 086-09, CSA 086-14
- TPIC 2011, TPIC 2014

(55% OF 31.3 P.S.F. G.S.L. PLUS 8.4 P.S.F. RAIN LOAD) EQUALS 28.6 P.S.F. SPECIFIED ROOF LIVE LOAD

ALLOWABLE DEFL.(LL) = L/360 (0.55")
CALCULATED VERT. DEFL.(LL) = L/989 (0.01")
ALLOWABLE DEFL.(TL) = L/360 (0.55")
CALCULATED VERT. DEFL.(TL) = L/999 (0.05")
CSI: TC=0.42/1.00 (C-D:1), BC=0.18/1.00 (F-H:4),
WB=0.13/1.00 (D-F:1), SS=0.17/1.00 (B-C:1)

DOL LUMBER=1.00 NAIL=1.00 LS BEND=1.10
COMP=1.10 SHEAR=1.10 TENS=1.10

COMPANION LIVE LOAD FACTOR = 1.00

TRUSS PLATE MANUFACTURER IS NOT RESPONSIBLE FOR QUALITY CONTROL IN THE TRUSS MANUFACTURING PLANT

NAIL VALUES
PLATE GRIP(DRY) SHEAR SECTION
(PSI) (PLI) (PLI)
MAX MIN MAX MIN MAX MIN
MT20 618 354 1687 788 1987 1658

PLATE PLACEMENT TOL. = 0.250 inches

PLATE ROTATION TOL. = 5.0 Deg.

JSI GRIP=0.85 (D) (INPUT = 0.89)
JSI METAL=0.24 (D) (INPUT = 1.00)




Structural component only
DWG# T-2007070

JOB NAME	TRUSS NAME	QUANTITY	PLY	JOB DESC.	GREEN PARK HOMES	DRWG NO.
408150	T8	1	1	TRUSS DESC.		

Tamarack Roof Truss, Burlington

Version 8.310 S Oct 29 2019 MITek Industries, Inc. Sat Apr 25 11:02:56 2020 Page 1
ID:17vF7aG0E03cRUI6X1SrkdWYK4BkxziYpQ8NWcUXvNNPzRo0Y13nGGpHRIAFBxzNCnT



TOTAL WEIGHT = 77 lb (M/F)

LUMBER			
N. L. G. A. RULES	CHORDS	SIZE	LUMBER
A - C	2x4	DRY	No.2
C - D	2x4	DRY	No.2
D - F	2x4	DRY	No.2
J - A	2x4	DRY	No.2
G - F	2x4	DRY	No.2
J - H	2x4	DRY	No.2
H - G	2x4	DRY	No.2
ALL WEBS	2x3	DRY	No.2
EXCEPT			

DRY: SEASONED LUMBER.

PLATES (table is in inches)

JT	TYPE	PLATES	W	LEN	Y	X
A	TMV+p	MT20	3.0	4.0		
B	TMVW-t	MT20	4.0	8.0		
C	TTW-m	MT20	4.0	4.0		
D	TTW-m	MT20	4.0	4.0		
E	TMVW-t	MT20	4.0	8.0		
F	TMV+p	MT20	3.0	4.0		
G	BMVW1-t	MT20	4.0	4.0		
H	BS4	MT20	3.0	8.0		
I	BMVWVW1-t	MT20	5.0	12.0	3.00	6.00
J	BMVW1-t	MT20	4.0	4.0		

DIMENSIONS, SUPPORTS AND LOADINGS SPECIFIED BY FABRICATOR TO BE VERIFIED BY BUILDING DESIGNER									
BEARINGS									
	FACTORED	MAXIMUM FACTORED	INPUT	REQD					
	GROSS REACTION	GROSS REACTION	BRG	BRG					
JT	VERT	HORZ	DOWN	HORZ	UPLIFT	IN-SX	IN-SX		
J	905	0	905	0	0	3-8	3-8		
G	905	0	905	0	0	MECHANICAL			

A SUITABLE HANGER/MECHANICAL CONNECTION IS REQUIRED AT JOINT G. MINIMUM BEARING LENGTH AT JOINT G = 3-8.

UNFACTORED REACTIONS							
JT	1ST LCASE	SNOW	LIVE	PERM.LIVE	WIND	DEAD	SOIL
J	COMBINED	640	420 / 0	0 / 0	0 / 0	220 / 0	0 / 0
G		640	420 / 0	0 / 0	0 / 0	220 / 0	0 / 0

BEARING MATERIAL TO BE SPF NO.2 OR BETTER AT JOINT(S) J

BRACING
TOP CHORD TO BE SHEATHED OR MAX. PURLIN SPACING = 8.25 FT.
MAX. UNBRACED BOTTOM CHORD LENGTH = 10.00 FT OR RIGID CEILING DIRECTLY APPLIED.

ALL PITCH BREAKS AND PERIMETER CORNER JOINTS MUST BE Laterally RESTRAINED.

LOADING							
TOTAL LOAD CASES: (4)							

CHORDS				WEBS			
MEMB.	MAX. FACTORED FORCE (LBS)	FACTORED VERT. LOAD (PL)	MAX. CSI (LC)	MEMB.	MAX. FACTORED FORCE (LBS)	MAX. CSI (LC)	
FR-TO		FROM	TO	FR-TO			
A-B	0 / 27	-91.8	-91.8 0.22 (1)	10.00	B-I	-183 / 0	0.11 (1)
B-C	-648 / 0	-91.8	-91.8 0.17 (1)	8.25	I-E	-190 / 0	0.13 (1)
C-D	-488 / 0	-91.8	-91.8 0.01 (1)	8.25	J-B	-935 / 0	0.54 (1)
D-E	-650 / 0	-91.8	-91.8 0.16 (1)	8.25	E-G	-935 / 0	0.57 (1)
E-F	0 / 27	-91.8	-91.8 0.23 (1)	10.00	C-I	0 / 221	0.05 (1)
J-A	-129 / 0	0.0	0.0 0.01 (1)	7.81	I-D	0 / 222	0.05 (1)
G-F	-137 / 0	0.0	0.0 0.01 (1)	7.81			
J-I	0 / 590	-18.5	-18.5 0.41 (4)	10.00			
I-H	0 / 608	-18.5	-18.5 0.41 (4)	10.00			
H-G	0 / 809	-18.5	-18.5 0.41 (4)	10.00			

DESIGN CRITERIA

SPECIFIED LOADS:	
TOP CH.	LL = 25.6 PSF
	OL = 8.0 PSF
BOT CH.	LL = 0.0 PSF
	OL = 7.4 PSF
TOTAL LOAD	= 39.0 PSF

SPACING = 24.0 IN. CG

LOADING IN FLAT SECTION BASED ON A SLOPE OF 6.00/12

THIS TRUSS IS DESIGNED FOR RESIDENTIAL OR SMALL BUILDING REQUIREMENTS OF PART 9, NBC 2010, NBC 2015

THIS DESIGN COMPLIES WITH:
- PART 9 OF CBC 2015, OBC 2012, ABC 2018
- PART 9 OF OBC 2012 (2018 AMENDMENT)
- CSA 088-09, CSA 088-14
- TPIC 2011, TPIC 2014

(55 % OF 31.3 P.S.F. G.S.L. PLUS 8.4 P.S.F. RAIN LOAD) EQUALS 25.6 P.S.F. SPECIFIED ROOF LIVE LOAD

ALLOWABLE DEFL. (LL) = L/360 (0.65")
CALCULATED VERT. DEFL. (LL) = L/989 (0.02")
ALLOWABLE DEFL. (TL) = L/360 (0.65")
CALCULATED VERT. DEFL. (TL) = L/989 (0.11")

CSI: TC=0.23/1.00 (E-F:1), BC=0.41/1.00 (G-I:4), WB=0.57/1.00 (E-G:1), SS=0.13/1.00 (D-E:1)

DOL LUMBER=1.00 NAIL=1.00 LB BEND=1.10 COMP=1.10 SHEAR=1.10 TENS=1.10

COMPANION LIVE LOAD FACTOR = 1.00

TRUSS PLATE MANUFACTURER IS NOT RESPONSIBLE FOR QUALITY CONTROL IN THE TRUSS MANUFACTURING PLANT.


NAIL VALUES
PLATE GRIP(DRY) SHEAR SECTION (PSI) (PLI) (PLI)
MAX MIN MAX MIN MAX MIN
MT20 618 354 1937 785 1937 1859

PLATE PLACEMENT TOL = 0.250 inches

PLATE ROTATION TOL = 5.0 Deg.

JSI GRIP= 0.75 (G) (INPUT = 0.80)

JSI METAL= 0.23 (G) (INPUT = 1.00)



Structural component only
DWG# T-2007071


JOB NAME	TRUSS NAME	QUANTITY	PLY	JOB DESC.	GREEN PARK HOMES	DRWG NO.
408150	T9	1	1	TRUSS DESC.		

Tamarack Roof Truss, Burlington

Version 8.310 5 Oct 29 2019 MITK Industries, Inc. Sat Apr 25 11:02:57 2020 Page 1

ID:7vF?aG0E03cRUj6X1jSkzIWYK-DOHJBeZBBSVNEe65x4wCz?ZjsTBI?LQvgMwojNzNCnS

Scale = 1:18.5



LUMBER	N. L. G. A. RULES	CHORDS	SIZE	LUMBER
A - C	2x4	DRY	No.2	
C - E	2x4	DRY	No.2	
K - A	2x4	DRY	No.2	
F - E	2x4	DRY	No.2	
K - H	2x4	DRY	No.2	
H - F	2x4	DRY	No.2	
ALL WEBS	2x3	DRY	No.2	
EXCEPT				

DRY: SEASONED LUMBER.

PLATES (tab/ets in inches)	PLATES	W	LEN	Y	X
A - TMVW+p	MT20	4.0	4.0	1.00	2.00
B - TMVW-i	MT20	4.0	4.0	2.00	1.25
C - TTW+p	MT20	4.0	4.0	Edge	
D - TMVW-i	MT20	4.0	4.0	2.00	1.25
E - TMVW+p	MT20	4.0	4.0	1.00	2.00
F - BMV1+p	MT20	3.0	4.0		
G - BMVW-i	MT20	4.0	4.0		
H - BS-i	MT20	3.0	6.0		
I - BMVW-i	MT20	4.0	9.0		
J - BMVW-i	MT20	4.0	4.0		
K - BMV1+p	MT20	3.0	4.0		

Edge - INDICATES REFERENCE CORNER OF PLATE TOUCHES EDGE OF CHORD.

DIMENSIONS, SUPPORTS AND LOADINGS SPECIFIED BY FABRICATOR TO BE VERIFIED BY BUILDING DESIGNER

FACTORED	MAXIMUM FACTORED	INPUT	RECORD
GROSS REACTION	GROSS REACTION	BRG	BRG
VERT	HORIZ	DOWN	HORIZ
UPLIFT	IN-SX	IN-SX	
JT	905	0	905
K	905	0	905
F	905	0	905

A SUITABLE HANGER/MECHANICAL CONNECTION IS REQUIRED AT JOINT F. MINIMUM BEARING LENGTH AT JOINT F = 3-8.

UNFACTORED REACTIONS

1ST CASE		MAX. MIN. COMPONENT REACTIONS					
	COMBINED	SNOW	LIVE	PERM. LIVE	WIND	DEAD	SO
JT	840	420 / 0	0 / 0	0 / 0	0 / 0	220 / 0	0 /
K	840	420 / 0	0 / 0	0 / 0	0 / 0	220 / 0	0 /
F	840	420 / 0	0 / 0	0 / 0	0 / 0	220 / 0	0 /

BEARING MATERIAL TO BE SPF NO.2 OR BETTER AT JOINT(S) K

BRACING

TOP CHORD TO BE SHEATHED OR MAX. PURLIN SPACING = 8.25 FT.
MAX. UNBRACED BOTTOM CHORD LENGTH = 10.00 FT. OR RIGID CEILING DIRECTLY APPLIED.

ALL PITCH BREAKS AND PERIMETER CORNER JOINTS MUST BE Laterally RESTRAINED.

LOADING

TOTAL LOAD CASES: (4)

CHORDS				WEBS				
MEMB.	FORCE	FACTORED		MAX.	MEMB.	MAX.	FACTORED	
	(LBS)	VERT. LOAD LC1	(PLF)	CS1 (LC)	UNBRAC	FORCE	MAX	
FR-TO		FROM	TO		LENGTH	FR-TO	CS1 (LC)	
A-B	-772 / 0	-91.8	-91.8	0.20 (1)	6.25	J-B	-135 / 21	0.05 (1)
B-C	-620 / 0	-91.8	-91.8	0.19 (1)	6.25	B-I	-251 / 0	0.18 (1)
C-D	-622 / 0	-91.8	-91.8	0.20 (1)	6.25	I-C	0 / 478	0.11 (1)
D-E	-795 / 0	-91.8	-91.8	0.21 (1)	6.25	I-D	-278 / 0	0.20 (1)
K-A	-873 / 0	0.0	0.0	0.10 (1)	7.81	G-D	-110 / 31	0.04 (1)
F-E	-872 / 0	0.0	0.0	0.09 (1)	7.81	A-J	0 / 653	0.15 (1)
						G-E	0 / 662	0.15 (1)
K-J	0 / 0	-18.5	-18.5	0.07 (4)	10.00			
J-I	0 / 815	-18.5	-18.5	0.13 (1)	10.00			
I-H	0 / 833	-18.5	-18.5	0.14 (1)	10.00			
H-G	0 / 833	-18.5	-18.5	0.14 (1)	10.00			
G-F	0 / 0	-18.5	-18.5	0.07 (4)	10.00			

TOTAL WEIGHT = 77 lb

DESIGN CRITERIA

SPECIFIED LOADS:

TOP CH.	LL = 25.8	PSF
DL = 8.0	PSF	
BOT CH.	LL = 0.0	PSF
DL = 7.4	PSF	
TOTAL LOAD = 39.0	PSF	

SPACING = 24.0 IN. C/C

THIS TRUSS IS DESIGNED FOR RESIDENTIAL OR SMALL BUILDING REQUIREMENTS OF PART 9, NBC 2010, NBC 2015

THIS DESIGN COMPLIES WITH:
- PART 9 OF CBC 2018, OBC 2012, ABC 2019
- PART 9 OF OBC 2012 (2018 AMENDMENT)
- CSA 086-09, CSA 086-14
- TPIC 2011, TPIC 2014

(55% OF 31.3 P.S.F. G.S.L. PLUS 8.4 P.S.F. RAIN LOAD) EQUALS 25.8 P.S.F. SPECIFIED ROOF LIVE LOAD

ALLOWABLE DEFL.(LL) = 1/360 (0.55")
CALCULATED VERT. DEFL.(LL) = 1/999 (0.02")
ALLOWABLE DEFL.(TL) = 1/360 (0.55")
CALCULATED VERT. DEFL.(TL) = 1/999 (0.03")

CSI: TC=0.21/1.00 (D-E:1), BC=0.14/1.00 (G-I:1), WB=0.20/1.00 (D-I:1), SS=0.14/1.00 (D-E:1)

DOL LUMBER=1.00 NAIL=1.00 LS BEND=1.10
COMP=1.10 SHEAR=1.10 TENS=1.10

COMPANION LIVE LOAD FACTOR = 1.00

TRUSS PLATE MANUFACTURER IS NOT RESPONSIBLE FOR QUALITY CONTROL IN THE TRUSS MANUFACTURING PLANT.

NAIL VALUES

PLATE	GRIP(DRY)	SHEAR	SECTION
(PSI)	(PLI)	(PLI)	
MAX	MIN	MAX	MIN
MT20	618	354	1667
	768	1987	1658


PLATE PLACEMENT TOL = 0.250 inches

PLATE ROTATION TOL = 5.0 Deg.

JSI GRIP = 0.87 (E) (INPUT = 0.90)
JSI METAL = 0.24 (E) (INPUT = 1.00)



Structural component only
DWG# T-2007072



LUMBER					
N. L. G. A. RULES					
CHORDS		SIZE	LUMBER		QESCR.
A - D	2x4	DRY	No.2		SPF
D - G	2x4	DRY	No.2		SPF
N - B	2x4	DRY	No.2		SPF
H - F	2x4	DRY	No.2		SPF
N - M	2x4	DRY	No.2		SPF
M - C	2x4	DRY	No.2		SPF
L - J	2x4	DRY	No.2		SPF
I - E	2x4	DRY	No.2		SPF
I - H	2x4	DRY	No.2		SPF
ALL WEBS		2x3	DRY	No.2	SPF
EXCEPT					
N - L	2x4	DRY	No.2		SPF
J - H	2x4	DRY	No.2		SPF
DRY; SEASONED LUMBER.					

PLATES (table in inches)

JT TYPE	PLATES	W	LEN	Y	X
B, C, E, F					
D	TMVW-p	MT20	4.0	4.0	1.00 2.00
B	TTW-p	MT20	4.0	8.0	Edge
H	BMVW1-t	MT20	4.0	4.0	
I	BMV-p	MT20	3.0	4.0	
J	BMVWW1-t	MT20	6.0	12.0	5.00 7.75
K	BMVWW1-t	MT20	4.0	9.0	
L	BMVWW1-t	MT20	6.0	12.0	5.00 7.75
M	BMV-p	MT20	3.0	4.0	
N	BMVW1-t	MT20	4.0	4.0	

Edge - INDICATES REFERENCE CORNER OF PLATE TOUCHES EDGE OF CHORD.

DIMENSIONS, SUPPORTS AND LOADINGS SPECIFIED BY FABRICATOR TO BE VERIFIED BY BUILDING DESIGNER

BEARINGS

FACTORED	MAXIMUM FACTORED	INPUT	RECORD
GROSS REACTION	GROSS REACTION	BRG	BRG
JT VERT	HORZ	DOWN	HORZ
N 729	0	729	0
H 729	0	729	0

A SUITABLE HANGER/MECHANICAL CONNECTION IS REQUIRED AT JOINT H. MINIMUM BEARING LENGTH AT JOINT H = 1-8.

UNFACTORED REACTIONS

1ST CASE	MAX/MIN	COMPONENT REACTIONS
JT	COMBINED	SNOW
		LIVE
N	513	350 / 0
H	513	350 / 0

PERM. LIVE WIND DEAD SOIL

BEARING MATERIAL TO BE SPF NO.2 OR BETTER AT JOINT(S) N

BRACING

TOP CHORD TO BE SHEATHED OR MAX. PURLIN SPACING = 6.25 FT.

MAX. UNBRACED BOTTOM CHORD LENGTH = 7.81 FT OR RIGID CEILING DIRECTLY APPLIED.

ALL PITCH BREAKS AND PERIMETER CORNER JOINTS MUST BE LATERALLY RESTRAINED.

LOADING

TOTAL LOAD CASES: (4)

CHORDS	MAX. FACTORED	FACTORED	VERT. LOAD	LC1	MAX	MEMB.	MAX. FACTORED	WEBS	MAX. FACTORED
MEMB.	FORCE	FORCE	VERT.	LC1	MAX	MEMB.	FORCE	MAX	MEMB.
	(LBS)	(LBS)	(LBS)	(LBS)	(LBS)		(LBS)	(LBS)	
FR-TO						FR-TO			
A-B	0 / 41	-91.8	-91.8	0.13 (1)	10.00	C-K	-211 / 0	0.07 (1)	
B-C	-847 / 0	-91.8	-91.8	0.14 (1)	6.25	K-D	0 / 229	0.05 (1)	
C-D	-447 / 0	-91.8	-91.8	0.19 (1)	6.25	K-E	-210 / 0	0.07 (1)	
D-E	-447 / 0	-91.8	-91.8	0.18 (1)	6.25	N-L	-26 / 0	0.00 (1)	
E-F	-846 / 0	-91.8	-91.8	0.14 (1)	6.25	B-L	0 / 527	0.12 (1)	
F-G	0 / 41	-91.8	-91.8	0.13 (1)	10.00	J-F	0 / 526	0.12 (1)	
N-B	-701 / 0	0.0	0.0	0.07 (1)	7.81	J-H	-26 / 0	0.00 (1)	
H-F	-701 / 0	0.0	0.0	0.07 (1)	7.81				
N-M	0 / 20	-18.5	-18.5	0.01 (4)	10.00				
M-L	0 / 14	0.0	0.0	0.03 (1)	10.00				
L-C	-92 / 2	0.0	0.0	0.02 (1)	7.81				
L-K	0 / 528	-18.5	-18.5	0.13 (1)	10.00				
K-J	0 / 527	-18.5	-18.5	0.13 (1)	10.00				
I-J	0 / 14	0.0	0.0	0.03 (1)	10.00				
J-E	-93 / 2	0.0	0.0	0.02 (1)	7.81				
I-H	0 / 20	-18.5	-18.5	0.01 (4)	10.00				

TOTAL WEIGHT = 2 X 56 = 112 b

DESIGN CRITERIA

SPECIFIED LOADS:

TOP CH.	LL	= 26.6	PSF
	DL	= 6.0	PSF
BOT CH.	LL	= 0.0	PSF
	DL	= 7.4	PSF
TOTAL LOAD		= 39.0	PSF

SPACING = 24.0 IN. G/C

THIS TRUSS IS DESIGNED FOR RESIDENTIAL OR SMALL BUILDING REQUIREMENTS OF PART 9, NBC 2010, NBC 2015

DESIGN ASSUMPTIONS

OVERHANG NOT TO BE ALTERED OR CUT OFF.

(55 % OF 31.3 P.S.F. G.S.L. PLUS 8.4 P.S.F. RAIN LOAD) EQUALS 25.8 P.S.F. SPECIFIED ROOF LIVE LOAD

ALLOWABLE DEFL. (LL) = $L/360$ (0.36")

CALCULATED VERT. DEFL. (LL) = $L/999$ (0.01")

ALLOWABLE DEFL. (TL) = $L/360$ (0.36")

CALCULATED VERT. DEFL. (TL) = $L/999$ (0.02")

CS: TC=0.19/1.00 (C-D:1), BC=0.13/1.00 (K-L:1), WB=0.12/1.00 (B-L:1), SS=0.13/1.00 (C-D:1)

DOL LUMBER=1.00 NAIL=1.00 LS BEND=1.10

COMP=1.10 SHEAR=1.10 TENS=1.10

COMPANION LIVE LOAD FACTOR = 1.00

AUTOSOLVE HEELS OFF

TRUSS PLATE MANUFACTURER IS NOT RESPONSIBLE FOR QUALITY CONTROL IN THE TRUSS MANUFACTURING PLANT.

NAIL VALUES

PLATE GRIP (DRY)	SHEAR	SECTION
(PS)	(PL)	(PL)
MAX	MIN	MAX MIN
MT20	818	364 1887 788 1887 1856

PLATE PLACEMENT TOL. = 0.250 inches

PLATE ROTATION TOL. = 5.0 Deg.

JSI GRIP = 0.74 (F) (INPUT = 0.90)


JSI METAL = 0.20 (F) (INPUT = 1.00)



JOB NAME	TRUSS NAME	QUANTITY	PLY	JOB DESC.	GREEN PARK HOMES	DRWG NO.
408150	T11	1	1	TRUSS DESC.		

Tamarack Roof Truss, Burlington

Version 6.310 S Oct 29 2019 Milltek Industries, Inc. Sat Apr 25 11:02:59 2020 Page 1
ID:17vF7aG0E03cRUj8X1jSrkziWYK-9mP4cKajl3l4TxGU3Vzq2Qa15HssTHxB7gPvoGzNCnO



Scale = 1/32"

LUMBER					DIMENSIONS, SUPPORTS AND LOADINGS SPECIFIED BY FABRICATOR TO BE VERIFIED BY BUILDING DESIGNER										TOTAL WEIGHT = 49 lb						
N. L. G. A. RULES					BEARINGS										(MIP)						
CHORDS SIZE					LUMBER					DESCR.					DESIGN CRITERIA						
A - C	2x4	DRY	No.2	SPF	FACTORED					MAXIMUM FACTORED					INPUT		RECORD				
C - E	2x4	DRY	No.2	SPF	GROSS REACTION					GROSS REACTION					BRG					BRG	
H - B	2x4	DRY	No.2	SPF	JT	VERT	HORZ	DOWN	HORZ	UPLIFT	IN-SX	IN-SX						SPECIFIED LOADS:			
F - D	2x4	DRY	No.2	SPF	H	729	0	729	0	0	5-8	5-8						TOP CH. LL = 25.8 PSF			
H - F	2x4	DRY	No.2	SPF	F	729	0	729	0	0	MECHANICAL							DL = 6.0 PSF			
ALL WEBS 2x3 DRY No.2 SPF					A SUITABLE HANGER/MECHANICAL CONNECTION IS REQUIRED AT JOINT F. MINIMUM BEARING LENGTH AT JOINT F = 1-8.															BOT CH. LL = 0.0 PSF	
EXCEPT																				DL = 7.4 PSF	
DRY: SEASONED LUMBER.																				TOTAL LOAD = 39.0 PSF	
																				SPACING = 24.0 IN. GC	

PLATES (table is in inches)

JT	TYPE	PLATES	W	LEN	Y	X
B	TMVW+p	MT20	4.0	4.0	1.00	2.00
C	TTW+p	MT20	4.0	6.0	Edge	
D	TMVW+p	MT20	4.0	4.0	1.00	2.00
F	BMV1+p	MT20	3.0	4.0		
G	BMVWW-1	MT20	4.0	9.0		
H	BMV1+p	MT20	3.0	4.0		

Edge - INDICATES REFERENCE CORNER OF PLATE TOUCHES EDGE OF CHORD.

UNFACTORED REACTIONS

JT	COMBINED	SNOW	LIVE	PERM. LIVE	WIND	DEAD	SOIL
H	513	380/0	0/0	0/0	0/0	183/0	0/0
F	513	350/0	0/0	0/0	0/0	183/0	0/0

BEARING MATERIAL TO BE SPF NO.2 OR BETTER AT JOINT(S) H

BRACING

TOP CHORD TO BE SHEATHED OR MAX. PURLIN SPACING = 6.25 FT.
MAX. UNBRACED BOTTOM CHORD LENGTH = 10.00 FT OR RIGID CEILING DIRECTLY APPLIED.

ALL PITCH BREAKS AND PERIMETER CORNER JOINTS MUST BE Laterally RESTRAINED.

LOADING

TOTAL LOAD CASES: (4)

CHORDS				WEBS			
MEMB.	MAX. FACTORED FORCE (LBS)	FACTORED VERT. LOAD LC1 (PLF)	MAX. CS1 (LC)	MEMB.	MAX. FACTORED FORCE (LBS)	MAX. CS1 (LC)	
FR-TO		FROM TO		FR-TO			
A-B	0/41	-91.8	-91.8 0.13 (1)	10.00	G-C	-15/89	0.03 (4)
B-C	-380/0	-91.8	-91.8 0.36 (1)	8.25	B-G	0/300	0.07 (1)
C-D	-380/0	-91.8	-91.8 0.35 (1)	8.25	G-D	0/300	0.07 (1)
D-E	0/41	-91.8	-91.8 0.13 (1)	10.00			
H-B	-890/0	0.0	0.0 0.07 (1)	7.81			
F-D	-890/0	0.0	0.0 0.07 (1)	7.81			
H-G	0/0	-18.5	-18.5 0.18 (4)	10.00			
G-F	0/0	-18.5	-18.5 0.18 (4)	10.00			

THIS DESIGN COMPLIES WITH:

- PART 8 OF CBC 2018, CBC 2012, ABC 2019
- PART 8 OF CBC 2012 (2019 AMENDMENT)
- CSA 088-09, CSA 088-14
- TPIC 2011, TPIC 2014

(55% OF 31.3 P.S.F. G.S.L. PLUS 8.4 P.S.F. RAIN LOAD) EQUALS 25.6 P.S.F. SPECIFIED ROOF LIVE LOAD

ALLOWABLE DEFL. (LL) = L/360 (0.36")
CALCULATED VERT. DEFL. (LL) = L/999 (0.00")
ALLOWABLE DEFL. (TL) = L/360 (0.36")
CALCULATED VERT. DEFL. (TL) = L/999 (0.02")

CSI: TC=0.35/1.00 (B-C:1), SC=0.18/1.00 (G-H:1),
WB=0.07/1.00 (D-G:1), SS=0.15/1.00 (B-C:1)

DOL LUMBER=1.00 NAIL=1.00 LS BEND=1.10
COMP=1.10 SHEAR=1.10 TENS=1.10

COMPANION LIVE LOAD FACTOR = 1.00

TRUSS PLATE MANUFACTURER IS NOT RESPONSIBLE FOR QUALITY CONTROL IN THE TRUSS MANUFACTURING PLANT.


NAIL VALUES

PLATE	GRIP (DRY)	SHEAR	SECTION
(PSI)	(PLI)	(PLI)	(PLI)
MAX MIN	MAX MIN	MAX MIN	MAX MIN
MT20	818	354	1667

PLATE PLACEMENT TOL. = 0.250 inches

PLATE ROTATION TOL. = 5.0 Deg.

JSI GRIP= 0.82 (D) (INPUT = 0.80)
JSI METAL= 0.17 (D) (INPUT = 1.00)




Structural component only
DWG# T-2007074

JOB NAME	TRUSS NAME	QUANTITY	PLY	JOB DESC.	GREEN PARK HOMES	DRWG NO.
408150	T12	1	1	TRUSS DESC.		

Tamareck Pool Truss, Burlington

Version 8.310 S Oct 29 2019 Mtek Industries, Inc. Sat Apr 25 11:03:01 2020 Page 1
ID:4NxGf1_xHSHnsgnSWZu6izNuP6-59Xq1?cyEg?oIFQsAw?88qPP4ZoxCqUb_u0s8zNCnO

Scale = 1/12.5



LUMBER	N. L. G. A. RULES	CHORDS	SIZE	DRY	LUMBER
A - B	2x4	DRY	No.2		
B - C	2x4	DRY	No.2		
F - A	2x4	DRY	No.2		
D - C	2x4	DRY	No.2		
F - D	2x4	DRY	No.2		

ALL WEBS 2x3 DRY No.2
EXCEPT

DRY: SEASONED LUMBER.

PLATES (table in inches)

JT	TYPE	PLATES	W	LEN	Y	X
A	TMVW+p	MT20	4.0	4.0	1.00	2.00
B	TTW+p	MT20	4.0	6.0	Edge	
C	TMVW+p	MT20	4.0	4.0	1.00	2.00
D	BMV1+p	MT20	3.0	4.0		
E	BMVWW-t	MT20	4.0	9.0		
F	BMV1+p	MT20	3.0	4.0		

Edge - INDICATES REFERENCE CORNER OF PLATE TOUCHES EDGE OF CHORD.

DIMENSIONS, SUPPORTS AND LOADINGS SPECIFIED BY FABRICATOR TO BE VERIFIED BY BUILDING DESIGNER

BEARINGS	FACTORED	MAXIMUM FACTORED	INPUT	REQD
	GROSS REACTION	GROSS REACTION	BRG	BRG
JT	VERT	HORZ	DOWN	HORZ
F	423	0	423	0
D	423	0	423	0

A SUITABLE HANGER/MECHANICAL CONNECTION IS REQUIRED AT JOINT F, D. MINIMUM BEARING LENGTH AT JOINT F = 1-8, JOINT D = 1-8.

UNFACTORED REACTIONS

JT	1ST CASE	MAX/MIN	COMPONENT REACTIONS
	COMBINED	SNOW	LIVE
F	289	196 / 0	0 / 0
D	289	196 / 0	0 / 0

BRACING

TOP CHORD TO BE SHEATHED OR MAX. PURLIN SPACING = 6.25 FT.
MAX. UNBRACED BOTTOM CHORD LENGTH = 10.00 FT. OR RIGID CEILING DIRECTLY APPLIED.

ALL PITCH BREAKS AND PERIMETER CORNER JOINTS MUST BE Laterally RESTRAINED.

LOADING

TOTAL LOAD CASES: (4)

CHORDS				WEBS				
MEMB.	MAX. FACTORED FORCE (LBS)	FACTORED VERT. LOAD (PLF)	MAX. CSI (LC)	MAX. UNBRAC LENGTH	MEMB.	MAX. FACTORED FORCE (LBS)	MAX. CSI (LC)	
FR-TO		FROM	TO	FR-TO				
A-B	-214 / 0	-91.8	-91.8	0.17 (1)	8.25	E-B	-78 / 37	0.09 (1)
B-C	-214 / 0	-91.8	-91.8	0.17 (1)	8.25	A-E	0 / 184	0.04 (1)
F-A	-395 / 0	0.0	0.0	0.05 (1)	7.81	E-C	0 / 184	0.04 (1)
D-C	-395 / 0	0.0	0.0	0.05 (1)	7.81			
F-E	0 / 0	-18.5	-18.5	0.08 (4)	10.00			
E-D	0 / 0	-18.5	-18.5	0.08 (4)	10.00			

TOTAL WEIGHT = 35 lb (MIF)

DESIGN CRITERIA

SPECIFIED LOADS:
TOP CH. LL = 25.8 PSF
DL = 8.0 PSF
BOT CH. LL = 0.0 PSF
DL = 7.4 PSF
TOTAL LOAD = 39.0 PSF

SPACING = 24.0 IN. C/C

THIS TRUSS IS DESIGNED FOR RESIDENTIAL OR SMALL BUILDING REQUIREMENTS OF PART 9, NBCC 2010, NBCC 2015

THIS DESIGN COMPLIES WITH:

- PART 9 OF BCBC 2018, CBC 2012, ABC 2019
- PART 9 OF CBC 2012 (2019 AMENDMENT)
- CSA 088-09, CSA 088-14
- TPIC 2011, TPIC 2014

(55 % OF 31.3 P.S.F. G.S.L. PLUS 8.4 P.S.F. RAIN LOAD) EQUALS 25.8 P.S.F. SPECIFIED ROOF LIVE LOAD

ALLOWABLE DEFL.(LL) = L/360 (0.26")
CALCULATED VERT. DEFL.(LL) = L/999 (0.00")
ALLOWABLE DEFL.(TL) = L/360 (0.26")
CALCULATED VERT. DEFL.(TL) = L/999 (0.01")

CSI: TC=0.17/1.00 (B-C:1), BC=0.08/1.00 (D-E:1), WB=0.04/1.00 (A-E:1), SSI=0.11/1.00 (B-C:1)

DOL LUMBER=1.00 NAIL=1.00 LB BEND=1.10
COMP=1.10 SHEAR=1.10 TENS=1.10

COMPANION LIVE LOAD FACTOR = 1.00

TRUSS PLATE MANUFACTURER IS NOT RESPONSIBLE FOR QUALITY CONTROL IN THE TRUSS MANUFACTURING PLANT.

NAIL VALUES

PLATE	GRIP(DRY)	SHEAR	SECTION
(PSI)	(PLI)	(PLI)	
	MAX	MIN	MAX
MT20	618	354	1687

PLATE PLACEMENT TOL. = 0.260 inches

PLATE ROTATION TOL. = 5.0 Deg.

JSI GRIP= 0.31 (C) (INPUT = 0.90)
JSI METAL= 0.09 (C) (INPUT = 1.00)




Structural component only
DWG# T-2007075

JOB NAME	TRUSS NAME	QUANTITY	PLY	JOB DESC.	GREEN PARK HOMES	DRWG NO.
408150	T12S	2	1	TRUSS DESC.		

Tamarack Roof Truss, Burlington

Version 8.310 S Oct 29 2019 Mittek Industries, Inc. Sat Apr 25 11:03:02 2020 Page 1
ID:4NxGft_xHSHnsgnSWZu6izNuP6-ZL5CEld.a? 7IKP?3keWNg3GbiUw7geceqcdZObzNCnN



Scale = 1/31.8

LUMBER

N. L. G. A. RULES	CHORDS	SIZE	LUMBER	DESCR.
A - C	2x4	DRY	No.2	SPF
C - E	2x4	DRY	No.2	SPF
L - A	2x4	DRY	No.2	SPF
F - E	2x4	DRY	No.2	SPF
L - K	2x4	DRY	No.2	SPF
K - B	2x4	DRY	No.2	SPF
J - H	2x4	DRY	No.2	SPF
G - D	2x4	DRY	No.2	SPF
G - F	2x4	DRY	No.2	SPF
ALL WEBS	2x3	DRY	No.2	SPF
EXCEPT				

DRY: SEASONED LUMBER.

PLATES (table in inches)

JT TYPE	PLATES	W	LEN	Y	X
A, B, D, E					
A	TMVW+p	MT20	4.0	4.0	1.00 2.00
C	TTW+p	MT20	4.0	8.0	Edge
F	BMVW1-i	MT20	4.0	4.0	
G	BMV+p	MT20	3.0	4.0	
H	BMVWW-i	MT20	5.0	8.0	3.50 5.50
I	BMVWW-i	MT20	4.0	9.0	
J	BMVWW-i	MT20	5.0	8.0	3.50 5.50
K	BMV+p	MT20	3.0	4.0	
L	BMVW1-i	MT20	4.0	4.0	

Edge - INDICATES REFERENCE CORNER OF PLATE TOUCHES EDGE OF CHORD.

DIMENSIONS, SUPPORTS AND LOADINGS SPECIFIED BY FABRICATOR TO BE VERIFIED BY BUILDING DESIGNER

BEARINGS

	FACTORED GROSS REACTION	MAXIMUM FACTORED GROSS REACTION	INPUT BRG	RECORD BRG
JT	VERT	DOWN	HORIZ	UPLIFT
L	423	0	423	0
F	423	0	423	0

A SUITABLE HANGER/MECHANICAL CONNECTION IS REQUIRED AT JOINT L, F. MINIMUM BEARING LENGTH AT JOINT L = 1-8, JOINT F = 1-8.

UNFACTORED REACTIONS

JT	1ST LOASE	MAX/MIN COMPONENT REACTIONS	SNOW	LIVE	PERM.LIVE	WIND	DEAD	SOIL
L	293	198 / 0	0 / 0	0 / 0	0 / 0	103 / 0	0 / 0	0 / 0
F	293	198 / 0	0 / 0	0 / 0	0 / 0	103 / 0	0 / 0	0 / 0

BRACING

TOP CHORD TO BE SHEATHED OR MAX. PURLIN SPACING = 6.25 FT.
MAX. UNBRACED BOTTOM CHORD LENGTH = 7.81 FT. OR RIGID CEILING DIRECTLY APPLIED.

ALL PITCH BREAKS AND PERIMETER CORNER JOINTS MUST BE Laterally RESTRAINED.

LOADING

TOTAL LOAD CASES: (4)

CHORDS	MEMB.	MAX. FACTORED FORCE (LBS)	FACTORED VERT. LOAD (PLF)	MAX. FACTORED VERT. LOAD (LC1)	MAX. FACTORED VERT. LOAD (LC)	MAX. FACTORED VERT. LOAD (LC)	MAX. FACTORED VERT. LOAD (LC)	MAX. FACTORED VERT. LOAD (LC)
FR-TO								
A-B	-282 / 0	-91.8	-91.8	0.08 (1)	6.25	1-C	0 / 125	0.03 (1)
B-C	-274 / 0	-91.8	-91.8	0.07 (1)	6.25	1-D	-57 / 0	0.01 (1)
C-D	-274 / 0	-91.8	-91.8	0.07 (1)	6.25	B-I	-57 / 0	0.01 (1)
D-E	-282 / 0	-91.8	-91.8	0.08 (1)	6.25	L-J	-13 / 0	0.00 (1)
L-A	-404 / 0	0.0	0.0	0.05 (1)	7.81	A-J	0 / 317	0.07 (1)
F-E	-404 / 0	0.0	0.0	0.05 (1)	7.81	H-F	-13 / 0	0.00 (1)
L-K	0 / 9	-18.5	-18.5	0.01 (4)	10.00	H-E	0 / 317	0.07 (1)
K-J	0 / 11	0.0	0.0	0.01 (1)	10.00			
J-B	-182 / 0	0.0	0.0	0.01 (1)	10.00			
J-I	0 / 247	-18.5	-18.5	0.08 (1)	10.00			
I-H	0 / 247	-18.5	-18.5	0.03 (1)	10.00			
G-H	0 / 11	0.0	0.0	0.01 (1)	10.00			
H-D	-182 / 0	0.0	0.0	0.01 (1)	7.81			
G-F	0 / 9	-18.5	-18.5	0.01 (4)	10.00			

TOTAL WEIGHT = 2 X 43 = 85 lb

DESIGN CRITERIA

SPECIFIED LOADS:

TOP CH.	LL	=	25.6	PSF
	DL	=	8.0	PSF
BOT CH.	LL	=	0.0	PSF
	DL	=	7.4	PSF
TOTAL LOAD		=	39.0	PSF

SPACING = 24.0 IN. G.C.

THIS TRUSS IS DESIGNED FOR RESIDENTIAL OR SMALL BUILDING REQUIREMENTS OF PART 9, NBCC 2010, NBCC 2015

THIS DESIGN COMPLIES WITH:
- PART 9 OF CBC 2018, CBC 2012, ABC 2010
- PART 9 OF CBC 2012 (2018 AMENDMENT)
- CSA 086-09, CSA 086-14
- TPIC 2011, TPIC 2014

(55% OF 31.3 P.S.F. G.S.L. PLUS 8.4 P.S.F. RAIN LOAD) EQUALS 25.6 P.S.F. SPECIFIED ROOF LIVE LOAD

ALLOWABLE DEFL.(LL) = $L/360$ (0.26")
CALCULATED VERT. DEFL.(LL) = $L/989$ (0.00")
ALLOWABLE DEFL.(TL) = $L/360$ (0.26")
CALCULATED VERT. DEFL.(TL) = $L/989$ (0.01")

CSI: TC=0.07/1.00 (C-D:1), BC=0.06/1.00 (H-I:1), WB=0.07/1.00 (A-J:1), SI=0.08/1.00 (C-D:1)

DOL LUMBER=1.00 NAIL=1.00 LS BEND=1.10
COMP=1.10 SHEAR=1.10 TENS=1.10

COMPANION LIVE LOAD FACTOR = 1.00

AUTOSOLVE HEELS OFF

TRUSS PLATE MANUFACTURER IS NOT RESPONSIBLE FOR QUALITY CONTROL IN THE TRUSS MANUFACTURING PLANT.


NAIL VALUES

PLATE	GRIP(DRY)	SHEAR	SECTION
(PS)	(PL)	(PL)	(PL)
MAX	MIN	MAX	MIN
MT20	618	354	1887
	788	1987	1856

PLATE PLACEMENT TOL. = 0.250 inches

PLATE ROTATION TOL. = 5.0 Deg.

JSI GRIP= 0.30 (E) (INPUT = 0.80)
JSI METAL= 0.05 (E) (INPUT = 1.00)




Structural component only
DWG# T-2007076

JOB NAME	TRUSS NAME	QUANTITY	PLY	JOB DESC.	GREEN PARK HOMES	ORWG NO.
408150	T15	1	1	TRUSS DESC.		

Tamarack Roof Truss, Burlington

Version 8.310 9 Oct 20 2019 MTK Industries, Inc. Sat Apr 25 11:03:03 2020 Page 1
ID:7vF7aG0E03cRUj6X1jSkziWYK-1Xf6ShsCmIFWYzAFIL1cDGpbHuDP_en2IN7x1zNCnM



LUMBER	CHORDS	SIZE	LUMBER	DESCR.
N. L. G. A. RULES				
A - C	2x4	DRY	No.2	SPF
F - A	2x4	DRY	No.2	SPF
D - C	2x4	DRY	No.2	SPF
F - D	2x4	DRY	No.2	SPF
ALL WEBS	2x3	DRY	No.2	SPF
EXCEPT				

DRY: SEASONED LUMBER.

PLATES (tablets in inches)

JT	TYPE	PLATES	W	LEN	Y	X
A	TMW-I	MT20	4.0	9.0		Edge
B	TMW-w	MT20	2.0	4.0		
C	TMW-I	MT20	4.0	9.0		Edge
D	BMV1-p	MT20	3.0	4.0		
E	BMWVW-I	MT20	6.0	9.0		
F	BMV1-p	MT20	3.0	4.0		

Edge - INDICATES REFERENCE CORNER OF PLATE TOUCHES EDGE OF CHORD.

DIMENSIONS, SUPPORTS AND LOADINGS SPECIFIED BY FABRICATOR TO BE VERIFIED BY BUILDING DESIGNER

BEARINGS

	FACTORED	GROSS REACTION	MAXIMUM FACTORED	INPUT	RECORD
	VERT	HORZ	DOWN	HORZ	UPLIFT
JT	976	0	976	0	0
F	1015	0	1015	0	0
D					

UNFACTORED REACTIONS

JT	1ST CASE	MAX	MIN	COMPONENT REACTIONS
	COMBINED	SNOW	LIVE	PERM LIVE
F	690	453 / 0	0 / 0	0 / 0
D	716	478 / 0	0 / 0	0 / 0

BEARING MATERIAL TO BE SPF NO.2 OR BETTER AT JOINT(S) F, D

BRACING

TOP CHORD TO BE SHEATHED OR MAX. PURLIN SPACING = 3.55 FT.
MAX. UNBRACED BOTTOM CHORD LENGTH = 10.00 FT OR RIGID CEILING DIRECTLY APPLIED.

ALL PITCH BREAKS AND PERIMETER CORNER JOINTS MUST BE Laterally RESTRAINED.

LOADING

TOTAL LOAD CASES: (4)

MEMB.	CHORDS	MAX. FACTORED	FORCE	VERT. LOAD	FACTORED	VERT. LOAD	MAX	CS1 (LC)	UNBRAC	MEMB.	WEBS	MAX. FACTORED	FORCE	MAX	CS1 (LC)
FR-TO															
A-G	-2081 / 0	-91.8	-91.8	0.79 (1)	3.55	A-E	0 / 2157	0.53 (1)							
G-H	-2081 / 0	-91.8	-91.8	0.79 (1)	3.55	E-B	-878 / 0	0.14 (1)							
H-I	-2081 / 0	-91.8	-91.8	0.79 (1)	3.55	E-C	0 / 2157	0.53 (1)							
I-B	-2081 / 0	-91.8	-91.8	0.79 (1)	3.55										
B-J	-2081 / 0	-91.8	-91.8	0.79 (1)	3.55										
J-K	-2081 / 0	-91.8	-91.8	0.79 (1)	3.55										
K-C	-2081 / 0	-91.8	-91.8	0.79 (1)	3.55										
F-A	-889 / 0	0.0	0.0	0.10 (1)	7.81										
D-C	-938 / 0	0.0	0.0	0.11 (1)	7.81										
F-L	0 / 0	-18.5	-18.5	0.22 (4)	10.00										
L-M	0 / 0	-18.5	-18.5	0.22 (4)	10.00										
M-N	0 / 0	-18.5	-18.5	0.22 (4)	10.00										
N-E	0 / 0	-18.5	-18.5	0.22 (4)	10.00										
E-O	0 / 0	-18.5	-18.5	0.22 (4)	10.00										
O-P	0 / 0	-18.5	-18.5	0.22 (4)	10.00										
P-D	0 / 0	-18.5	-18.5	0.22 (4)	10.00										

FACTORED CONCENTRATED LOADS (LBS)

JT	LOC.	LC1	MAX.	MAX+	FACE	DIR.	TYPE	HEEL	CONN.
C	10-11-0	-123	-123	---	BACK	VERT	TOTAL	---	C1
G	9-14	-90	-90	---	BACK	VERT	TOTAL	---	C1
H	2-9-14	-82	-82	---	BACK	VERT	TOTAL	---	C1
I	4-9-14	-82	-82	---	BACK	VERT	TOTAL	---	C1
J	6-9-14	-82	-82	---	BACK	VERT	TOTAL	---	C1
K	8-9-14	-82	-82	---	BACK	VERT	TOTAL	---	C1
L	9-14	-51	-51	---	BACK	VERT	TOTAL	---	C1
M	2-9-14	-49	-49	---	BACK	VERT	TOTAL	---	C1
N	4-9-14	-49	-49	---	BACK	VERT	TOTAL	---	C1
O	6-9-14	-49	-49	---	BACK	VERT	TOTAL	---	C1
P	8-9-14	-49	-49	---	BACK	VERT	TOTAL	---	C1

CONNECTION REQUIREMENTS

1) C1: A SUITABLE HANGER/MECHANICAL CONNECTION IS REQUIRED.

DESIGN CRITERIA

SPECIFIED LOADS:

TOP CH.	LL	=	25.6	PSF
	DL	=	8.0	PSF
BOT CH.	LL	=	0.0	PSF
	DL	=	7.4	PSF
TOTAL LOAD		=	39.0	PSF

SPACING = 24.0 IN. CG

LOADING IN FLAT SECTION BASED ON A SLOPE OF 6.00/12

THIS TRUSS IS DESIGNED FOR RESIDENTIAL OR SMALL BUILDING REQUIREMENTS OF PART 9, NBCC 2010, NBCC 2015

THIS DESIGN COMPLIES WITH:

- PART 9 OF NBCC 2010, CBC 2012, ABC 2010
- PART 9 OF CBC 2012 (2019 AMENDMENT)
- CSA 086-09, CSA 086-14
- TPIC 2011, TPIC 2014

(55 % OF 31.3 P.S.F. G.S.L. PLUS 8.4 P.S.F. RAIN LOAD) EQUALS 26.6 P.S.F. SPECIFIED ROOF LIVE LOAD

ALLOWABLE DEFL.(LL) = L/360 (0.36")
CALCULATED VERT. DEFL.(LL) = L/999 (0.08")
ALLOWABLE DEFL.(TL) = L/360 (0.36")
CALCULATED VERT. DEFL.(TL) = L/817 (0.16")

CS1: TC=0.79/1.00 (A-B:1), BC=0.22/1.00 (E-F:4), WB=0.53/1.00 (A-E:1), SS1=0.39/1.00 (A-B:1)

DOL LUMBER=1.00 NAIL=1.00 LS BEND=1.00
COMP=1.00 SHEAR=1.00 TENS=1.00

COMPANION LIVE LOAD FACTOR = 1.00

AUTOSOLVE HEELS OFF

TRUSS PLATE MANUFACTURER IS NOT RESPONSIBLE FOR QUALITY CONTROL IN THE TRUSS MANUFACTURING PLANT.


NAIL VALUES

PLATE	GRIP(DRY)	SHEAR	SECTION
(PSI)	(PLI)	(PLI)	
MT20	618	354	1867
			788
			1987
			1856

PLATE PLACEMENT TOL. = 0.250 inches


PLATE ROTATION TOL. = 5.0 Deg.

JSI GRIP = 0.89 (A) (INPUT = 0.90)
JSI METAL = 0.40 (E) (INPUT = 1.00)



Structural component only
DWG# T-2007077

JOB NAME 408151	TRUSS NAME T20	QUANTITY 1	PLY 2	JOB DESC. GREEN PARK HOMES	DRWG NO.
Tamarack Roof Truss, Burlington				Version 9.310 S Oct 29 2019 Mitek Industries, Inc. Sat Apr 26 11:19:44 2020 Page 1	
ID: h2dlfgC44wS_E2tqPs_atzIRw-E6e7Kz51rNUYObeR4VLHmIPQqOSi27EXMbZWzNCX				Scale: 1/8" = 1'-0"	



CHORDS	SIZE	LUMBER	DESCR.
A - C	2x8	DRY No.2	SPF
C - F	2x8	DRY No.2	SPF
F - H	2x8	DRY No.2	SPF
H - J	2x8	DRY No.2	SPF
S - B	2x8	DRY No.2	SPF
K - I	2x8	DRY No.2	SPF
S - P	2x8	DRY 1650F 1.5E	SPF
P - N	2x8	DRY 1650F 1.5E	SPF
N - K	2x8	DRY 1650F 1.5E	SPF

ALL WEBS 2x3 DRY No.2 SPF
EXCEPT

DRY: SEASONED LUMBER.

DESIGN CONSISTS OF 2 TRUSSES BUILT SEPARATELY THEN FASTENED TOGETHER AS FOLLOWS:

CHORDS #ROWS	SURFACE SPACING (IN)	LOAD (PLF)
TOP CHORDS : (0.122"x3") SPIRAL NAILS		
A - C	2 12	SIDE (122.0)
C - F	2 12	SIDE (61.0)
F - H	2 12	SIDE (61.0)
H - J	2 12	SIDE (122.0)
S - B	2 12	TOP
K - I	2 12	TOP
BOTTOM CHORDS : (0.122"x3") SPIRAL NAILS		
S - P	2 12	SIDE (0.0)
P - N	2 12	SIDE (0.0)
N - K	2 12	SIDE (183.1)

WEBS : (0.122"x3") SPIRAL NAILS
2x3 1 6

NAILS TO BE DRIVEN FROM ONE SIDE ONLY.

GIRDER NAILING ASSUMES NAILED HANGERS ARE FASTENED WITH MIN. 3-0 INCH NAILS.

TOP - COMPONENTS ARE LOADED FROM THE TOP AND MUST BE PLACED ON TOP EDGE OF ALL PLIES FOR THE LOAD TO BE TRANSFERRED TO EACH PLY.

DIMENSIONS, SUPPORTS AND LOADINGS SPECIFIED BY FABRICATOR TO BE VERIFIED BY BUILDING DESIGNER

FACTORED GROSS REACTION		MAXIMUM FACTORED GROSS REACTION		INPUT BRG		RECORD BRG	
JT	VERT	DOWN	HORIZ	UPLIFT	IN-SX	IN-SX	IN-SX
S	3350	0	3330	0	5-8	5-8	5-8
K	3379	0	3379	0	5-8	5-8	5-8

UNFACTORED REACTIONS

JT	COMBINED	SNOW	LIVE	PERM. LIVE	WIND	DEAD	SOIL
S	2354	1553 / 0	0 / 0	0 / 0	0 / 0	801 / 0	0 / 0
K	2388	1572 / 0	0 / 0	0 / 0	0 / 0	816 / 0	0 / 0

BEARING MATERIAL TO BE SPF NO.2 OR BETTER AT JOINT(S) S, K

BRACING
TOP CHORD TO BE SHEATHED OR MAX. PURLIN SPACING = 3.98 FT.
MAX. UNBRACED BOTTOM CHORD LENGTH = 10.00 FT. OR RIGID CEILING DIRECTLY APPLIED.

ALL PITCH BREAKS AND PERIMETER CORNER JOINTS MUST BE Laterally RESTRAINED.

LOADING
TOTAL LOAD CASES: (4)

CHORDS				WEBS			
MEMB.	MAX. FACTORED FORCE (LBS)	FACTORED VERT. LOAD (PLF)	LC1 MAX CSI (LC)	MAX. UNBRAC LENGTH	MEMB.	MAX. FACTORED FORCE (LBS)	MAX FACTORED CSI (LC)
FR-TO		FROM	TO		FR-TO		
A-B	0 / 42	-91.8	-91.8 0.04 (1)	10.00	R-C	-662 / 0	0.08 (1)
B-C	-3359 / 0	-91.8	-91.8 0.05 (1)	8.03	C-Q	0 / 4522	0.56 (1)
C-T	-8808 / 0	-91.8	-91.8 0.38 (1)	4.32	C-D	-1799 / 0	0.22 (1)
T-U	-8808 / 0	-91.8	-91.8 0.38 (1)	4.32	D-O	0 / 1375	0.17 (1)
U-V	-8808 / 0	-91.8	-91.8 0.38 (1)	4.32	O-E	-990 / 0	-0.12 (1)
V-W	-8808 / 0	-91.8	-91.8 0.38 (1)	4.32	O-G	0 / 1368	0.17 (1)
W-D	-8808 / 0	-91.8	-91.8 0.38 (1)	4.32	M-G	-1786 / 0	0.21 (1)
D-X	-7835 / 0	-91.8	-91.8 0.42 (1)	3.98	M-H	0 / 4493	0.58 (1)
X-Y	-7835 / 0	-91.8	-91.8 0.42 (1)	3.98	L-H	-873 / 0	0.08 (1)
Y-Z	-7835 / 0	-91.8	-91.8 0.42 (1)	3.98	B-R	0 / 2729	0.34 (1)
Z-E	-7835 / 0	-91.8	-91.8 0.42 (1)	3.98	L-I	0 / 2764	0.34 (1)
E-AA	-7835 / 0	-91.8	-91.8 0.42 (1)	3.98			
AA-F	-7835 / 0	-91.8	-91.8 0.42 (1)	3.98			
F-AB	-7835 / 0	-91.8	-91.8 0.42 (1)	3.98			
AB-AC	-7835 / 0	-91.8	-91.8 0.42 (1)	3.98			
AC-AD	-7835 / 0	-91.8	-91.8 0.42 (1)	3.98			
AD-G	-7835 / 0	-91.8	-91.8 0.42 (1)	3.98			
G-AE	-8612 / 0	-91.8	-91.8 0.38 (1)	4.32			
AE-AF	-8612 / 0	-91.8	-91.8 0.38 (1)	4.32			
AF-AG	-8612 / 0	-91.8	-91.8 0.38 (1)	4.32			
AG-H	-8612 / 0	-91.8	-91.8 0.38 (1)	4.32			
H-I	-3401 / 0	-91.8	-91.8 0.05 (1)	6.00			
I-J	0 / 42	-91.8	-91.8 0.04 (1)	10.00			
S-B	-3368 / 0	0.0	0.0 0.12 (1)	7.58			
K-I	-3406 / 0	0.0	0.0 0.12 (1)	7.55			

SAH	0.0	-18.5	-18.5 0.08 (4)	10.00
RAH	0.0	-18.5	-18.5 0.08 (4)	10.00
RAI	0.2546	-18.5	-18.5 0.16 (1)	10.00
ALAJ	0.2546	-18.5	-18.5 0.16 (1)	10.00
AKAL	0.2546	-18.5	-18.5 0.16 (1)	10.00
ALQ	0.2546	-18.5	-18.5 0.16 (1)	10.00
Q-P	0.6808	-18.5	-18.5 0.32 (1)	10.00
P-AM	0.6808	-18.5	-18.5 0.32 (1)	10.00
AM-AN	0.6808	-18.5	-18.5 0.32 (1)	10.00
AN-O	0.6808	-18.5	-18.5 0.32 (1)	10.00
O-AO	0.6813	-18.5	-18.5 0.32 (1)	10.00
AO-AP	0.6813	-18.5	-18.5 0.32 (1)	10.00
AP-AQ	0.6813	-18.5	-18.5 0.32 (1)	10.00
AQ-N	0.6813	-18.5	-18.5 0.32 (1)	10.00
N-AR	0.6813	-18.5	-18.5 0.32 (1)	10.00
AR-M	0.6813	-18.5	-18.5 0.32 (1)	10.00

DESIGN CRITERIA

*** SPECIAL LOADS ANALYSIS ***
GEOMETRY AND/OR BASIC LOADS CHANGED BY USER.
LOADS WERE DERIVED FROM USER INPUT
NO FURTHER MODIFICATIONS WERE MADE

SPECIFIED LOADS:
TOP CH. LL = 25.8 PSF
DL = 6.0 PSF
BOT CH. LL = 0.0 PSF
DL = 7.4 PSF
TOTAL LOAD = 39.0 PSF

SPACING = 24.0 IN./C/C

LOADING IN FLAT SECTION BASED ON A SLOPE OF 6.00/12

*** NON STANDARD GIRDER ***
ADDTL. USER-DEFINED LOADS APPLIED TO ALL LOAD CASES.

THIS TRUSS IS DESIGNED FOR RESIDENTIAL OR SMALL BUILDING REQUIREMENTS OF PART 9, NBC 2010, NBC 2015

THIS DESIGN COMPLIES WITH:
- PART 9 OF CBC 2018, CBC 2012, ABC 2019
- PART 9 OF CBC 2012 (2019 AMENDMENT)
- CSA 088-09, CSA 088-14
- TPIG 2011, TPIG 2014

(65 % OF 31.3 P.S.F. G.S.L. PLUS 8.4 P.S.F. RAIN LOAD) EQUALS 25.8 P.S.F. SPECIFIED ROOF LIVE LOAD

ALLOWABLE DEFL. (LL) = L/360 (1.17")
CALCULATED VERT. DEFL. (LL) = L/999 (0.20")
ALLOWABLE DEFL. (TL) = L/360 (1.17")
CALCULATED VERT. DEFL. (TL) = L/999 (0.36")

CSK: TC=0.42/1.00 (D-E:1), SC=0.32/1.00 (O-Q:1),
WB=0.58/1.00 (C-Q:1), SS=0.22/1.00 (O-D:1)

DOL LUMBER=1.00 NAIL=1.00 LS BEND=1.00
COMP=1.00 SHEAR=1.00 TENS=1.00

COMPANION LIVE LOAD FACTOR = 1.00

AUTOSOLVE HEELS OFF


TRUSS PLATE MANUFACTURER IS NOT RESPONSIBLE FOR QUALITY CONTROL IN THE TRUSS MANUFACTURING PLANT.

NAIL VALUES
PLATE GRIP(DRY) SHEAR SECTION
(PSI) (PLI)
MAX MIN MAX MIN MAX MIN
MT20 818 354 1897 788 1987 1656

PLATE PLACEMENT TOL. = 0.250 inches

PLATE ROTATION TOL. = 5.0 Deg.

JSI GRIP = 0.82 (M) (INPUT = 0.90)
JSI METAL = 0.52 (P) (INPUT = 1.00)



Structural component only
DWG# T-2007081 1/2

JOB NAME	TRUSS NAME	QUANTITY	PLY	JOB DESC.	DRWG NO.
408151	T20	1	2	GREEN PARK HOMES	

Tamarack Roof Truss, Burlington

Version 8.310 S Oct 29 2019 Mitek Industries, Inc. Sat Apr 25 11:19:44 2020 Page 2
ID:12d11qC44wS E21zqPs atzIRw-E6e?Xz151rNUYObsR4VLHMmIPQqOS27EXMbZWzNCX

PLATES (Hebels in inches)

JT	TYPE	PLATES	W	LEN	Y	X
B	TMVW+p	MT20	7.0	8.0		
C	TTWW+m	MT20	8.0	9.0	3.50	1.75
D	TMWW-i	MT20	5.0	6.0	2.50	2.50
E	TMVW-w	MT20	3.0	6.0		
F	TS-i	MT20	5.0	6.0		
G	TMWW-i	MT20	5.0	6.0	2.50	2.50
H	TTWW+m	MT20	8.0	9.0	3.50	1.75
I	TMVW+p	MT20	7.0	8.0		
K	BMV1+p	MT20	3.0	6.0		
L	BMWW-i	MT20	5.0	6.0	2.50	2.25
M	BMWW-i	MT20	5.0	6.0	2.50	3.00
N	BS-i	MT20	8.0	9.0		
O	BMWWW-i	MT20	6.0	12.0		
P	BS-i	MT20	6.0	9.0		
Q	BMWW-i	MT20	5.0	6.0	2.50	3.00
R	BMWW-i	MT20	5.0	6.0	2.50	2.25
S	BMV1+p	MT20	3.0	6.0		

LOADING

TOTAL LOAD CASES: 141

CHORDS


MEMB.	MAX. FACTORED FORCE (LBS)	VERT. LOAD (PLF)	LC1 (LBS)	MAX. UNBRAC. LENGTH FR-TO	MEMB.	MAX. FACTORED FORCE (LBS)	MAX. UNBRAC. LENGTH FR-TO
FR-TO							
M-AS	0 / 2578	-18.5	-18.5	0.18 (1)			10.00
AS-AT	0 / 2578	-18.5	-18.5	0.18 (1)			10.00
AT-AU	0 / 2578	-18.5	-18.5	0.18 (1)			10.00
AU-L	0 / 2578	-18.5	-18.5	0.18 (1)			10.00
L-AV	0 / 0	-18.5	-18.5	0.08 (4)			10.00
AV-K	0 / 0	-18.5	-18.5	0.08 (4)			10.00

FACTORED CONCENTRATED LOADS (LBS)

JT	LOC.	LC1	MAX.	MAX+	FACE	DIR.	TYPE	HEEL	CONN.
C	2-11-8	-38	-42	---	FRONT	VERT	DEAD	---	C1
C	2-11-8	-191	-191	---	FRONT	VERT	SNOW	---	C1
H	32-2-8	-38	-42	---	FRONT	VERT	DEAD	---	C1
H	32-2-8	-116	-116	---	FRONT	VERT	TOTAL	---	C1
H	32-2-8	-191	-191	---	FRONT	VERT	SNOW	---	C1
L	31-11-4	-28	-28	---	FRONT	VERT	TOTAL	---	C1
P	11-11-4	-28	-28	---	FRONT	VERT	TOTAL	---	C1
T	3-11-4	-111	-111	---	FRONT	VERT	TOTAL	---	C1
U	5-11-4	-110	-110	---	FRONT	VERT	TOTAL	---	C1
V	7-11-4	-110	-110	---	FRONT	VERT	TOTAL	---	C1
W	9-11-4	-110	-110	---	FRONT	VERT	TOTAL	---	C1
X	11-11-4	-110	-110	---	FRONT	VERT	TOTAL	---	C1
Y	13-11-4	-110	-110	---	FRONT	VERT	TOTAL	---	C1
Z	15-11-4	-110	-110	---	FRONT	VERT	TOTAL	---	C1
AA	17-11-4	-110	-110	---	FRONT	VERT	TOTAL	---	C1
AB	19-11-4	-110	-110	---	FRONT	VERT	TOTAL	---	C1
AC	21-11-4	-110	-110	---	FRONT	VERT	TOTAL	---	C1
AD	23-11-4	-110	-110	---	FRONT	VERT	TOTAL	---	C1
AE	25-11-4	-110	-110	---	FRONT	VERT	TOTAL	---	C1
AF	27-11-4	-110	-110	---	FRONT	VERT	TOTAL	---	C1
AG	29-11-4	-110	-110	---	FRONT	VERT	TOTAL	---	C1
AH	1-11-4	-28	-28	---	FRONT	VERT	TOTAL	---	C1
AI	3-11-4	-28	-28	---	FRONT	VERT	TOTAL	---	C1
AJ	5-11-4	-28	-28	---	FRONT	VERT	TOTAL	---	C1
AK	7-11-4	-28	-28	---	FRONT	VERT	TOTAL	---	C1
AL	9-11-4	-28	-28	---	FRONT	VERT	TOTAL	---	C1
AM	13-11-4	-28	-28	---	FRONT	VERT	TOTAL	---	C1
AN	15-11-4	-28	-28	---	FRONT	VERT	TOTAL	---	C1
AO	17-11-4	-28	-28	---	FRONT	VERT	TOTAL	---	C1
AP	19-11-4	-28	-28	---	FRONT	VERT	TOTAL	---	C1
AQ	21-11-4	-28	-28	---	FRONT	VERT	TOTAL	---	C1
AR	23-11-4	-28	-28	---	FRONT	VERT	TOTAL	---	C1
AS	25-11-4	-28	-28	---	FRONT	VERT	TOTAL	---	C1
AT	27-11-4	-28	-28	---	FRONT	VERT	TOTAL	---	C1
AU	29-11-4	-28	-28	---	FRONT	VERT	TOTAL	---	C1
AV	33-11-4	-28	-28	---	FRONT	VERT	TOTAL	---	C1

CONNECTION REQUIREMENTS


1) C1: A SUITABLE HANGER/MECHANICAL CONNECTION IS REQUIRED.



Structural component only
DWG# T-2007081 3/2

JOB NAME	TRUSS NAME	QUANTITY	PLY	JOB DESC.	DRWG NO.
408151	T20Z	1	2	GREEN PARK HOMES	
Tamarack Pool Truss, Burlington				TRUSS DESC.	

Version 8.310 S Oct 29 2019 MTEK Industries, Inc. Sat Apr 26 11:19:45 2020 Page 1
ID:n2dlgC44ws E2tzqPs_atzllRw-JGOJmko9VL9YAq nDagaJuZo4EB5KGTB585yzNCX
Scale = 1:57.3



CHORDS	SIZE	LUMBER	DESCR.
A - C	2x8	DRY No.2	SPF
C - F	2x8	DRY No.2	SPF
F - H	2x8	DRY No.2	SPF
H - J	2x8	DRY No.2	SPF
S - B	2x8	DRY No.2	SPF
K - I	2x8	DRY No.2	SPF
S - P	2x8	DRY 1850F 1.5E	SPF
P - N	2x8	DRY 1850F 1.5E	SPF
N - K	2x8	DRY 1850F 1.5E	SPF

ALL WEBS 2x3 DRY No.2 SPF

DRY: SEASONED LUMBER.

DESIGN CONSISTS OF 2 TRUSSES BUILT SEPARATELY THEN FASTENED TOGETHER AS FOLLOWS:

CHORDS #ROWS	SURFACE SPACING (IN)	LOAD (PLF)
TOP CHORDS: (0.122"x3") SPIRAL NAILS		
A-C 2	12	SIDE(122.0)
C-F 2	12	SIDE(183.1)
F-H 2	12	TOP
H-J 2	12	TOP
S-B 2	12	TOP
K-I 2	12	TOP
BOTTOM CHORDS: (0.122"x3") SPIRAL NAILS		
S-P 2	12	SIDE(183.1)
P-N 2	12	SIDE(183.1)
N-K 2	12	TOP
WEBS: (0.122"x3") SPIRAL NAILS		
2x3 1	6	

NAILS TO BE DRIVEN FROM ONE SIDE ONLY.

GIRDER NAILING ASSUMES NAILED HANGERS ARE FASTENED WITH MIN. 3-0 INCH NAILS.

TOP - COMPONENTS ARE LOADED FROM THE TOP AND MUST BE PLACED ON TOP EDGE OF ALL PLIES FOR THE LOAD TO BE TRANSFERRED TO EACH PLY.

DIMENSIONS, SUPPORTS AND LOADINGS SPECIFIED BY FABRICATOR TO BE VERIFIED BY BUILDING DESIGNER

BEARINGS	FACTORED GROSS REACTION	MAXIMUM FACTORED GROSS REACTION	INPUT BRG IN-SX	RECORD BRG IN-SX
JT	VERT	HORIZ	DOWN	HORIZ
S	4991	0	4991	0
K	3694	0	3694	0

UNFACTORED REACTIONS	1ST CASE	MAX/MIN	COMPONENT REACTIONS
JT	COMBINED	SNOW	LIVE
S	3528	2323 / 0	0 / 0
K	2808	1737 / 0	0 / 0

BEARING MATERIAL TO BE SPF NO.2 OR BETTER AT JOINT(S) S, K

BRACING

TOP CHORD TO BE SHEATHED OR MAX. PURLIN SPACING = 3.20 FT. MAX. UNBRACED BOTTOM CHORD LENGTH = 10.00 FT. OR RIGID CEILING DIRECTLY APPLIED.

ALL PITCH BREAKS AND PERIMETER CORNER JOINTS MUST BE Laterally RESTRAINED.

LOADING

TOTAL LOAD CASES: (4)

CHORDS	MAX. FACTORED MEMB. FORCE (LBS)	FACTORED VERT. LOAD (PLF)	MAX. UNBRACED LENGTH (FT)	WEBS	MAX. FACTORED MEMB. FORCE (LBS)	MAX. UNBRACED LENGTH (FT)
FR-TO				FR-TO		
A-B	0 / 42	-91.8	-91.8 0.04 (1)	10.00	R-C	-263 / 44
B-C	-5342 / 0	-91.8	-91.8 0.07 (1)	5.02	C-Q	0 / 6569
C-D	-9971 / 0	-91.8	-91.8 0.39 (1)	3.64	Q-D	-1958 / 0
D-E	-12379 / 0	-91.8	-91.8 0.52 (1)	3.20	D-O	0 / 2694
E-F	-12379 / 0	-91.8	-91.8 0.52 (1)	3.20	O-E	-782 / 0
F-G	-12379 / 0	-91.8	-91.8 0.49 (1)	3.23	G-O	0 / 4229
G-H	-5599 / 0	-91.8	-91.8 0.49 (1)	3.23	M-G	-2819 / 0
H-I	-3750 / 0	-91.8	-91.8 0.33 (1)	3.93	M-H	0 / 6416
I-J	0 / 42	-91.8	-91.8 0.08 (1)	5.79	L-H	-864 / 0
S-B	-5197 / 0	0.0	-91.8 0.04 (1)	10.00	B-R	0 / 4341
K-I	-3727 / 0	0.0	0.0 0.19 (1)	6.41	L-I	0 / 3047
			0.0 0.13 (1)	7.30		
S-U	0 / 0	-18.5	-18.5 0.20 (1)	10.00		
U-R	0 / 0	-18.5	-18.5 0.20 (1)	10.00		
R-V	0 / 4073	-18.5	-18.5 0.36 (1)	10.00		
V-Q	0 / 4073	-18.5	-18.5 0.36 (1)	10.00		
Q-P	0 / 9971	-18.5	-18.5 0.73 (1)	10.00		
P-W	0 / 9971	-18.5	-18.5 0.73 (1)	10.00		
W-X	0 / 9971	-18.5	-18.5 0.73 (1)	10.00		
X-O	0 / 9971	-18.5	-18.5 0.73 (1)	10.00		
O-Y	0 / 8800	-18.5	-18.5 0.58 (1)	10.00		
Y-N	0 / 8800	-18.5	-18.5 0.58 (1)	10.00		
N-M	0 / 8600	-18.5	-18.5 0.58 (1)	10.00		
M-L	0 / 2039	-18.5	-18.5 0.16 (1)	10.00		
L-K	0 / 0	-18.5	-18.5 0.05 (1)	10.00		

FACTORED CONCENTRATED LOADS (LBS)	JT	LOC.	LC1	MAX.	MAX+	FACE	DIR.	TYPE	HEEL	CONN.
C	2-11-8	-38	-42	---	---	FRONT	VERT	DEAD	---	C1
C	2-11-8	-117	-117	---	---	BACK	VERT	TOTAL	---	C1
C	2-11-8	-191	-191	---	---	FRONT	VERT	SNOW	---	C1
E	17-4-12	-110	-110	---	---	BACK	VERT	TOTAL	---	C1
O	17-4-12	-28	-28	---	---	BACK	VERT	TOTAL	---	C1
R	2-9-4	-28	-28	---	---	BACK	VERT	TOTAL	---	C1
T	15-4-12	-110	-110	---	---	BACK	VERT	TOTAL	---	C1
U	9-4	-29	-29	---	---	BACK	VERT	TOTAL	---	C1
V	4-8-8	-1068	-1068	---	---	BACK	VERT	TOTAL	---	C1
W	13-5-8	-1068	-1068	---	---	BACK	VERT	TOTAL	---	C1
X	15-4-12	-28	-28	---	---	BACK	VERT	TOTAL	---	C1
Y	18-5-8	-1738	-1738	---	---	BACK	VERT	TOTAL	---	C1

DESIGN CRITERIA

*** SPECIAL LOADS ANALYSIS ***
GEOMETRY AND/OR BASIC LOADS CHANGED BY USER.
LOADS WERE DERIVED FROM USER INPUT
NO FURTHER MODIFICATIONS WERE MADE

SPECIFIED LOADS:

TOP CH. LL = 25.6 PSF
DL = 8.0 PSF
BOT CH. LL = 0.0 PSF
DL = 7.4 PSF
TOTAL LOAD = 39.0 PSF

SPACING = 24.0 IN. C/C

LOADING IN FLAT SECTION BASED ON A SLOPE OF 6.00/12

*** NON STANDARD GIRDER ***
ADDTL USER-DEFINED LOADS APPLIED TO ALL LOAD CASES.

THIS TRUSS IS DESIGNED FOR RESIDENTIAL OR SMALL BUILDING REQUIREMENTS OF PART 9, NBCC 2010, NBCC 2015

THIS DESIGN COMPLIES WITH:
- PART 9 OF NBC 2010, NBC 2012, ABC 2019
- PART 9 OF NBC 2012 (2019 AMENDMENT)
- CSA 088-08, CSA 088-14
- TPIC 2011, TPIC 2014

(55% OF 31.3 P.S.F. G.S.L. PLUS 8.4 P.S.F. RAIN LOAD) EQUALS 26.6 P.S.F. SPECIFIED ROOF LIVE LOAD

ALLOWABLE DEFL.(LL) = L/360 (1.17")
CALCULATED VERT. DEFL.(LL) = U/989 (0.33")
ALLOWABLE DEFL.(TL) = L/360 (1.17")
CALCULATED VERT. DEFL.(TL) = U/685 (0.62")

CSI: TC=0.52/1.00 (D-E:1), BC=0.73/1.00 (O-Q:1),

WB=0.81/1.00 (C-Q:1), SS=0.57/1.00 (M-O:1)

DOL LUMBER=1.00 NAIL=1.00 LS BEND=1.00
COMP=1.00 SHEAR=1.00 TENS=1.00

COMPANION LIVE LOAD FACTOR = 1.00

AUTOSOLVE HEELS OFF

TRUSS PLATE MANUFACTURER IS NOT RESPONSIBLE FOR QUALITY CONTROL IN THE TRUSS MANUFACTURING PLANT.

NAIL VALUES

PLATE GRIP(DRY) SHEAR SECTION
(P.S.I) (P.L.I) (P.L.I)
MAX MIN MAX MIN MAX MIN
MT20 619 354 1867 788 1987 1856

PLATE PLACEMENT TOL. = 0.250 inches

PLATE ROTATION TOL. = 5.0 Deg.

JSI GRIP=0.88 (D) (INPUT = 0.90)
JSI METAL=0.84 (P) (INPUT = 1.00)



Structural component only
DWG# T-2007082. 1/2

CONTINUED ON PAGE 2

JOB NAME	TRUSS NAME	QUANTITY	PLY	UOB DESC.	GREEN PARK HOMES	DRWG NO.
408151	T20Z	1	2	TRUSS DESC.		

Tamarack Roof Truss, Burlington


Version 8.310 S Oct 29 2019 MiTek Industries, Inc. Sat Apr 25 11:19:45 2020 Page 2
ID:h2dflqC44wS E2lzaPs atzllRw-JCOJmko9VL9YAq n0agaJuZo4EB5KGTB585yzNCX

PLATES (table is in inches)

JT	TYPE	PLATES	W	LEN	Y	X
B	TMVW+p	MT20	7.0	8.0		
C	TTWW+m	MT20	8.0	9.0	3.50	1.75
O	TMWW-i	MT20	5.0	8.0	2.50	2.50
E	TMVW+w	MT20	3.0	6.0		
F	TS-i	MT20	5.0	6.0		
G	TMWW-i	MT20	5.0	6.0	2.50	2.50
H	TTWW+m	MT20	8.0	9.0	3.50	1.75
I	TMVW+p	MT20	7.0	8.0		
K	BMV1+p	MT20	3.0	6.0		
L	BMWW-i	MT20	5.0	8.0	2.50	2.25
M	BMWW-i	MT20	5.0	8.0	2.50	2.75
N	BS-i	MT20	8.0	9.0		
O	BMWWW-i	MT20	5.0	12.0	2.75	6.00
P	BS-i	MT20	8.0	9.0		
Q	BMWW-i	MT20	5.0	8.0	2.50	2.75
R	BMWW-i	MT20	5.0	8.0	2.50	2.25
S	BMV1+p	MT20	3.0	6.0		

CONNECTION REQUIREMENTS

- 1) C1: A SUITABLE HANGER/MECHANICAL CONNECTION IS REQUIRED.




Structural component only
DWG# T-2007082 7/2

JOB NAME	TRUSS NAME	QUANTITY	PLY	JOB DESC.	TRUSS DESC.	DRWG NO.
408151	T21	2	1	GREEN PARK HOMES		

Tamarack Roof Truss, Burlington

Version 8.310 S Oct 29 2019 Mitak Industries, Inc. Sat Apr 25 11:19:46 2020 Page 1
ID:h2dlqC44wS_E2tqPs_atzllRw-AVlmymMZTDnllOYUXpMnrlECRIweZChridOzNCXh
20 3 0 5 3 15 25 8 15 35 2 0 38 5 8
Scale = 1:57.3



LUMBER			
N. L. G. A. RULES	SIZE	DRY	LUMBER
CHORDS			
A - C	2x4	DRY	No.2
C - F	2x4	DRY	No.2
F - I	2x4	DRY	No.2
I - K	2x4	DRY	No.2
U - 8	2x4	DRY	No.2
L - J	2x4	DRY	No.2
U - R	2x4	DRY	No.2
R - O	2x4	DRY	No.2
O - L	2x4	DRY	No.2
ALL WEBS EXCEPT	2x3	DRY	No.2

DRY: SEASONED LUMBER.

PLATES (tablets in inches)			
JT TYPE	PLATES	W	LEN Y X
B TMVW+p	MT20	5.0	8.0 Edge 2.75
C TTWW+m	MT20	5.0	9.0 Edge 1.75
D, E, H			
D TMVW-t	MT20	4.0	4.0
F TS-t	MT20	3.0	8.0
G TMW+w	MT20	2.0	4.0
I TTWW+m	MT20	6.0	8.0 Edge 1.75
J TMVW+p	MT20	5.0	8.0 Edge 2.75
L BMV1+p	MT20	3.0	4.0
M BMVW-t	MT20	4.0	8.0 2.00 2.75
N BMVW-t	MT20	5.0	8.0 2.50 2.75
O BS-t	MT20	3.0	8.0
P BMVWV-t	MT20	4.0	9.0
Q BMVW-t	MT20	4.0	4.0
R BS-t	MT20	3.0	8.0
S BMVW-t	MT20	5.0	8.0
T BMVW-t	MT20	4.0	8.0 2.00 2.75
U BMV1+p	MT20	3.0	4.0

Edge - INDICATES REFERENCE CORNER OF PLATE TOUCHES EDGE OF CHORD.

DIMENSIONS, SUPPORTS AND LOADINGS SPECIFIED BY FABRICATOR TO BE VERIFIED BY BUILDING DESIGNER

FACTORED		MAXIMUM FACTORED		INPUT	REQD
JT	GROSS REACTION	GROSS REACTION	GROSS REACTION	BRG	BRG
	VERT	HORZ	DOWN	HORZ	UPLIFT
U	2068	0	2068	0	0
L	2068	0	2068	0	0
				5-8	5-8
				5-8	5-8

UNFACTORED REACTIONS		1ST LOOSE		MAX/MIN. COMPONENT REACTIONS	
JT	COMBINED	SNOW	LIVE	PERM. LIVE	WIND
U	1458	971/0	0/0	0/0	488/0
L	1458	971/0	0/0	0/0	488/0

BEARING MATERIAL TO BE SPF NO.2 OR BETTER AT JOINT(S) U, L

BRACING
TOP CHORD TO BE SHEATHED OR MAX. PURLIN SPACING = 3.20 FT.
MAX. UNBRACED BOTTOM CHORD LENGTH = 10.00 FT OR RIGID CEILING DIRECTLY APPLIED.

ALL PITCH BREAKS AND PERIMETER CORNER JOINTS MUST BE LATERALLY RESTRAINED.

LOADING

TOTAL LOAD CASES: (4)

CHORDS		FACTORED		WEBS	
MEMB.	MAX. FORCE (LBS)	VERT. LOAD (LBS)	MAX. CSI (LC)	MEMB.	MAX. FORCE (LBS)
FR-TO		FROM TO		FR-TO	
A-B	0/41	-91.8 -81.8 0.13 (1)	10.00	T-C	-358/0
B-C	-1980/0	-91.8 -81.8 0.38 (1)	4.46	C-S	0/1836
C-D	-2871/0	-91.8 -81.8 0.57 (1)	3.59	S-D	-1118/0
D-E	-3508/0	-91.8 -81.8 0.65 (1)	3.21	D-Q	0/886
E-F	-3508/0	-91.8 -81.8 0.53 (1)	3.36	Q-E	-475/0
F-G	-3508/0	-91.8 -81.8 0.63 (1)	3.36	E-P	-2/0
G-H	-3508/0	-91.8 -81.8 0.86 (1)	3.20	P-G	-474/0
H-I	-2871/0	-91.8 -81.8 0.57 (1)	3.59	P-H	0/853
I-J	-1980/0	-91.8 -81.8 0.38 (1)	4.46	H-N	-1117/0
J-K	0/41	-91.8 -81.8 0.13 (1)	10.00	N-I	0/1837
U-B	-2037/0	0.0 0.0 0.22 (1)	5.92	M-I	-358/0
L-J	-2037/0	0.0 0.0 0.22 (1)	5.92	B-T	0/1571
				M-J	0/1571
U-T	0/0	-18.5 -18.5 0.10 (4)	10.00		
T-S	0/1494	-18.5 -18.5 0.30 (1)	10.00		
S-R	0/2871	-18.5 -18.5 0.51 (1)	10.00		
R-Q	0/2871	-18.5 -18.5 0.51 (1)	10.00		
Q-P	0/3508	-18.5 -18.5 0.62 (1)	10.00		
P-O	0/2872	-18.5 -18.5 0.51 (1)	10.00		
O-N	0/2872	-18.5 -18.5 0.51 (1)	10.00		
N-M	0/1494	-18.5 -18.5 0.30 (1)	10.00		
M-L	0/0	-18.5 -18.5 0.10 (4)	10.00		

TOTAL WEIGHT = 2 X 147 = 293 lb

DESIGN CRITERIA

SPECIFIED LOADS:
TOP CH. LL = 25.8 PSF
DL = 8.0 PSF
BOT CH. LL = 0.0 PSF
DL = 7.4 PSF
TOTAL LOAD = 39.0 PSF

SPACING = 24.0 IN. C/C

LOADING IN FLAT SECTION BASED ON A SLOPE OF 8.00/12

THIS TRUSS IS DESIGNED FOR RESIDENTIAL OR SMALL BUILDING REQUIREMENTS OF PART 9, NBC 2010, NBC 2015

THIS DESIGN COMPLIES WITH:
- PART 9 OF CBC 2018, CBC 2012, ABC 2019
- PART 9 OF CBC 2012 (2019 AMENDMENT)
- CSA 088-09, CSA 088-14
- TPIC 2011, TPIC 2014

(65% OF 31.3 P.S.F. G.S.L. PLUS 8.4 P.S.F. RAIN LOAD) EQUALS 25.8 P.S.F. SPECIFIED ROOF LIVE LOAD

ALLOWABLE DEFL. (LL) = L/360 (1.17")
CALCULATED VERT. DEFL. (LL) = L/999 (0.20")
ALLOWABLE DEFL. (TL) = L/360 (1.17")
CALCULATED VERT. DEFL. (TL) = L/999 (0.39")

CSI: TC=0.86/1.00 (G-H:1), BC=0.62/1.00 (P-Q:1),
WB=0.43/1.00 (D-S:1), SS=0.23/1.00 (H-I:1)

DOL LUMBER=1.00 NAIL=1.00 LB BEND=1.10
COMP=1.10 SHEAR=1.10 TENS=1.10

COMPANION LIVE LOAD FACTOR = 1.00


TRUSS PLATE MANUFACTURER IS NOT RESPONSIBLE FOR QUALITY CONTROL IN THE TRUSS MANUFACTURING PLANT.

NAIL VALUES
PLATE GRIP (DRY) SHEAR SECTION (PSI) (PL) (PL)
MAX MIN MAX MIN MAX MIN
MT20 618 354 1687 788 1987 1656

PLATE PLACEMENT TOL. = 0.250 inches


PLATE ROTATION TOL. = 5.0 Deg.

JSI GRIP = 0.90 (S) (INPUT = 0.90)
JSI METAL = 0.90 (O) (INPUT = 1.00)



Structural component only
DWG# T-2007083

JOB NAME	TRUSS NAME	QUANTITY	PLY	JOB DESC.	ORWG NO.
408151	T22	2	1	GREEN PARK HOMES	
Tamarack Roof Truss, Burlington					
Version 8.310 S Oct 29 2019 Mtek Industries, Inc. Sat Apr 25 11:19:47 2020 Page 1					
ID:h2dflgC44wS_E2tqPs_atzIRw-ehJ89?n_Kml3PrKD8C22v7OAZcpWk3vZwVafArzNCKp					



LUMBER			
N. L. G. A. RULES	CHORDS	SIZE	LUMBER
A - C	2x4	DRY	No.2
C - F	2x4	DRY	No.2
F - H	2x4	DRY	No.2
H - J	2x4	DRY	No.2
S - B	2x4	DRY	No.2
K - I	2x4	DRY	No.2
S - P	2x4	DRY	No.2
P - N	2x4	DRY	No.2
N - K	2x4	DRY	No.2

ALL WEBS 2x3 DRY No.2
EXCEPT

DRY: SEASONED LUMBER.

PLATES (table is in inches)					
JT	TYPE	PLATES	W	LEN	Y X
B	TMVW-p	MT20	5.0	8.0	1.50 3.00
C	TTWW-hm	MT20	8.0	9.0	Edge 1.75
D	TMVW-l	MT20	4.0	4.0	
F	TMVW-w	MT20	2.0	4.0	
G	TS-l	MT20	3.0	8.0	
H	TMVW-t	MT20	4.0	4.0	
I	TTWW-hm	MT20	8.0	9.0	Edge 1.75
J	TMVW-p	MT20	5.0	8.0	1.50 3.00
K	BMV1-p	MT20	3.0	4.0	
L, M, Q, R					
L	BMVW-t	MT20	5.0	8.0	
N	BS-1	MT20	3.0	8.0	
O	BMVW-w	MT20	4.0	9.0	
P	BS-1	MT20	3.0	8.0	
S	BMV1-p	MT20	3.0	4.0	

Edge - INDICATES REFERENCE CORNER OF PLATE TOUCHES EDGE OF CHORD.

DIMENSIONS, SUPPORTS AND LOADINGS SPECIFIED BY FABRICATOR TO BE VERIFIED BY BUILDING DESIGNER

BEARINGS		FACTORED	MAXIMUM FACTORED	INPUT	REQD
JT	VERT	GROSS REACTION	GROSS REACTION	BRG	BRG
S	2088	0	2088	0	5-8
K	2088	0	2088	0	5-8

UNFACTORED REACTIONS		1ST LOUSE	MAX./MIN. COMPONENT REACTIONS	WIND	DEAD	SOIL
JT	COMBINED	SNOW	LIVE	PERM.LIVE	WIND	DEAD
S	1458	971 / 0	0 / 0	0 / 0	0 / 0	488 / 0
K	1458	971 / 0	0 / 0	0 / 0	0 / 0	488 / 0

BEARING MATERIAL TO BE SPF NO.2 OR BETTER AT JOINT(S) S, K

BRACING
TOP CHORD TO BE SHEATHED OR MAX. PURLIN SPACING = 3.28 FT.
MAX. UNBRACED BOTTOM CHORD LENGTH = 10.00 FT OR RIGID CEILING DIRECTLY APPLIED.

ALL PITCH BREAKS AND PERIMETER CORNER JOINTS MUST BE Laterally RESTRAINED.

LOADING
TOTAL LOAD CASES: (4)

CHORDS		WEBS	
MEMB.	MAX. FACTORED FORCE (LBS)	MEMB.	MAX. FACTORED FORCE (LBS)
FR-TO		FR-TO	
A-B	0 / 41	R-C	-246 / 7
B-C	-2004 / 0	C-Q	0 / 1538
C-D	-2653 / 0	Q-D	-943 / 0
D-E	-2978 / 0	D-O	0 / 450
E-F	-2978 / 0	O-E	-513 / 0
F-G	-2978 / 0	G-O	0 / 450
G-H	-2653 / 0	M-G	-943 / 0
H-I	-2004 / 0	M-H	0 / 1538
I-J	0 / 41	L-H	-246 / 7
S-B	-2028 / 0	B-R	0 / 1580
K-I	-2028 / 0	L-I	0 / 1580
S-R	0 / 0		
R-Q	0 / 1532		
Q-P	0 / 2853		
P-O	0 / 2853		
O-N	0 / 2853		
N-M	0 / 2853		
M-L	0 / 1532		
L-K	0 / 0		

TOTAL WEIGHT = 2 X 148 = 288 lb

DESIGN CRITERIA

SPECIFIED LOADS:
TOP CH. LL = 25.8 PSF
DL = 8.0 PSF
BOT CH. LL = 0.0 PSF
DL = 7.4 PSF
TOTAL LOAD = 39.0 PSF

SPACING = 24.0 IN. C.C.

LOADING IN FLAT SECTION BASED ON A SLOPE OF 5.00/12

THIS TRUSS IS DESIGNED FOR RESIDENTIAL OR SMALL BUILDING REQUIREMENTS OF PART 9, NBC 2010, NBCC 2015

THIS DESIGN COMPLIES WITH:
- PART 9 OF NBC 2010, CBC 2012, ABC 2019
- PART 9 OF CBC 2012 (2019 AMENDMENT)
- CSA 088-09, CSA 088-14
- TPIC 2011, TPIC 2014

(55% OF 31.3 P.S.F. G.S.L. PLUS 8.4 P.S.F. RAIN LOAD) EQUALS 25.8 P.S.F. SPECIFIED ROOF LIVE LOAD

ALLOWABLE DEFL.(LL) = L/380 (1.17")
CALCULATED VERT. DEFL.(LL) = L/999 (0.16")
ALLOWABLE DEFL.(TL) = L/360 (1.17")
CALCULATED VERT. DEFL.(TL) = L/999 (0.29")

CSK: TC=0.78/1.00 (D-E:1), BC=0.49/1.00 (O-Q:1),
WB=0.58/1.00 (G-M:1), SL=0.27/1.00 (G-D:1)

DOL LUMBER=1.00 NAIL=1.00 LS BEND=1.10
COMP=1.10 SHEAR=1.10 TENS=1.10

COMPANION LIVE LOAD FACTOR = 1.00

TRUSS PLATE MANUFACTURER IS NOT RESPONSIBLE FOR QUALITY CONTROL IN THE TRUSS MANUFACTURING PLANT.

NAIL VALUES
PLATE GRIP (DRY) SHEAR SECTION
(PSI) (PLI) (PLI)
MAX MIN MAX MIN MAX MIN
MT20 .618 .354 .687 .788 .1987 .1856


PLATE PLACEMENT TOL. = 0.250 inches

PLATE ROTATION TOL. = 5.0 Deg.

JSI GRIP = 0.90 (B) (INPUT = 0.80)
JSI METAL = 0.95 (N) (INPUT = 1.00)



Structural component only
DWG# T-2007084



LUMBER

N. L. G. A. RULES

CHORDS	SIZE	DRY	LUMBER
A - D	2x4	DRY	No.2
D - G	2x4	DRY	No.2
G - I	2x4	DRY	No.2
I - L	2x4	DRY	No.2
U - B	2x4	DRY	No.2
M - K	2x4	DRY	No.2
U - R	2x4	DRY	No.2
R - P	2x4	DRY	No.2
P - M	2x4	DRY	No.2

ALL WEBS 2x3 DRY No.2
EXCEPT

DRY: SEASONED LUMBER.

PLATES (tab/e/a/n/inches)

JT	TYPE	PLATES	W	LEN	Y	X
B	TMV+p	MT20	3.0	4.0		
C	TMVW+l	MT20	5.0	8.0	2.50	2.25
D	TTWW+m	MT20	5.0	8.0	2.00	1.75
E	TMVW+l	MT20	4.0	4.0		
F	TMVW+l	MT20	2.0	4.0		
G	TS-l	MT20	3.0	6.0		
H	TMVW+l	MT20	4.0	4.0		
I	TTWW+m	MT20	5.0	8.0	2.00	1.75
J	TMVW+l	MT20	5.0	8.0	2.50	2.25
K	TMV+p	MT20	3.0	4.0		
M	BMVW+l	MT20	5.0	8.0	2.25	3.00
N	BMVW+l	MT20	4.0	4.0		
O	BMVW+l	MT20	4.0	8.0		
P	BS-l	MT20	3.0	6.0		
Q	BMVW+l	MT20	4.0	9.0		
R	BS-l	MT20	3.0	6.0		
S	BMVW+l	MT20	4.0	8.0		
T	BMVW+l	MT20	4.0	4.0		
U	BMVW+l	MT20	5.0	8.0	2.25	3.00

DIMENSIONS, SUPPORTS AND LOADINGS SPECIFIED BY FABRICATOR TO BE VERIFIED BY BUILDING DESIGNER

BEARINGS

	FACTORED GROSS REACTION	MAXIMUM FACTORED GROSS REACTION	INPUT BRG IN-SX	REQD BRG IN-SX
JT	VERT	DOWN	UPLIFT	
U	2086	0	0	5-8
M	2086	0	0	5-8

UNFACTORED REACTIONS

1ST CASE	MAX/MIN COMPONENT REACTIONS
JT	COMBINED
U	1458
M	1458

BRACING

TOP CHORD TO BE SHEATHED OR MAX. PURLIN SPACING = 3.77 FT.
MAX. UNBRACED BOTTOM CHORD LENGTH = 10.00 FT OR RIGID CEILING DIRECTLY APPLIED.

ALL PITCH BREAKS AND PERIMETER CORNER JOINTS MUST BE LATERALLY RESTRAINED.

LOADING

TOTAL LOAD CASES: (4)

CHORDS				WEBS			
MEMB.	MAX. FACTORED FORCE (LBS)	FACTORED VERT. LOAD (PLF)	MAX. FACTORED CSI (LC)	MEMB.	MAX. FACTORED FORCE (LBS)	MAX. FACTORED CSI (LC)	
FR-TO		FROM TO		FR-TO			
A-B	0/141	-91.8	-91.8 0.13 (1)	C-T	0/166	0.04 (1)	
B-C	0/118	-91.8	-91.8 0.14 (1)	T-D	0/76	0.03 (4)	
C-D	-2023/0	-91.8	-91.8 0.20 (1)	D-S	0/1220	0.27 (1)	
D-E	-2308/0	-91.8	-91.8 0.55 (1)	S-E	-850/0	0.74 (1)	
E-F	-2534/0	-91.8	-91.8 0.57 (1)	F-Q	0/361	0.08 (1)	
F-G	-2534/0	-91.8	-91.8 0.57 (1)	Q-F	-481/0	0.40 (1)	
G-H	-2534/0	-91.8	-91.8 0.55 (1)	H-Q	0/361	0.08 (1)	
H-I	-2308/0	-91.8	-91.8 0.14 (1)	I-O	-850/0	0.74 (1)	
I-J	-2023/0	-91.8	-91.8 0.20 (1)	O-I	0/1220	0.27 (1)	
J-K	0/118	-91.8	-91.8 0.14 (1)	K-I	0/76	0.03 (4)	
K-L	0/141	-91.8	-91.8 0.13 (1)	L-N	0/166	0.04 (1)	
L-M	-246/0	0.0	0.0 0.03 (1)	M-N	-2277/0	0.98 (1)	
M-K	-246/0	0.0	0.0 0.03 (1)	N-M	-2277/0	0.98 (1)	

J-T	0/1433	-18.5	-18.5 0.33 (1)	10.00
T-S	0/1635	-18.5	-18.5 0.35 (1)	10.00
S-R	0/2308	-18.5	-18.5 0.42 (1)	10.00
R-Q	0/2308	-18.5	-18.5 0.42 (1)	10.00
Q-P	0/2308	-18.5	-18.5 0.42 (1)	10.00
P-O	0/2308	-18.5	-18.5 0.42 (1)	10.00
O-N	0/1535	-18.5	-18.5 0.35 (1)	10.00
N-M	0/1433	-18.5	-18.5 0.33 (1)	10.00

DESIGN CRITERIA

SPECIFIED LOADS:

TOP CH. LL = 25.6 PSF
DL = 6.0 PSF

BOT CH. LL = 0.0 PSF
DL = 7.4 PSF

TOTAL LOAD = 38.0 PSF

SPACING = 24.0 IN. CG

LOADING IN FLAT SECTION BASED ON A SLOPE OF 6.00/12

THIS TRUSS IS DESIGNED FOR RESIDENTIAL OR SMALL BUILDING REQUIREMENTS OF PART 9, NBC 2010, NBC 2015

THIS DESIGN COMPLIES WITH:

- PART 9 OF CBC 2010, CBC 2012, ABC 2019
- PART 9 OF CBC 2012 (2019 AMENDMENT)
- CSA 088-09, CSA 088-14
- TPIC 2011, TPIC 2014

(55% OF 31.3 P.S.F. G.S.L PLUS 8.4 P.S.F. RAIN LOAD) EQUALS 25.6 P.S.F. SPECIFIED ROOF LIVE LOAD

ALLOWABLE DEFL. (LL) = L/360 (1.17")
CALCULATED VERT. DEFL. (LL) = L/999 (0.13")
ALLOWABLE DEFL. (TL) = L/360 (1.17")
CALCULATED VERT. DEFL. (TL) = L/999 (0.23")

CSK TC=0.57/1.00 (E-F:1), SC=0.42/1.00 (O-Q:1), WB=0.98/1.00 (J-M:1), SS=0.24/1.00 (D-E:1)

DOL LUMBER=1.00 NAIL=1.00 LS BEND=1.10
COMP=1.10 SHEAR=1.10 TENS=1.10

COMPANION LIVE LOAD FACTOR = 1.00

TRUSS PLATE MANUFACTURER IS NOT RESPONSIBLE FOR QUALITY CONTROL IN THE TRUSS MANUFACTURING PLANT.


NAIL VALUES

PLATE	GRIP(DRY)	SHEAR	SECTION
	(PSI)	(PLI)	(PLI)
MT20	618	354	1667

PLATE PLACEMENT TOL. = 0.250 inches

PLATE ROTATION TOL = 5.0 Deg.


JSI GRP = 0.89 (I) (INPUT = 0.90)
JSI METAL = 0.72 (P) (INPUT = 1.00)



JOB NAME	TRUSS NAME	QUANTITY	PLY	JOB DESC.	DRWG NO.
408151	T24	2	1	GREEN PARK HOMES	
TRUSS DESC.					

Tamrack Roof Truss, Burlington

Version 8.310 S Oct 29 2019 Mitek Industries, Inc. Sat Apr 25 11:13:48 2020 Page 1
ID:h2dlgC44ws E2tqPs_atzllRw-a4RuagpEsO?ne8U6Dd4W_QTXEPW57sssNp3MEjzNCXg



TOTAL WEIGHT = 2 X 163 = 326 lb

LUMBER	SIZE	DRY	LUMBER	DESCR
N. L. G. A. RULES				
CHORDS				
A - D	2x4	DRY	No.2	SPF
D - F	2x4	DRY	No.2	SPF
F - H	2x4	DRY	No.2	SPF
H - K	2x4	DRY	No.2	SPF
S - B	2x4	DRY	No.2	SPF
L - J	2x4	DRY	No.2	SPF
S - Q	2x4	DRY	No.2	SPF
Q - N	2x4	DRY	No.2	SPF
N - L	2x4	DRY	No.2	SPF
ALL WEBS	2x3	DRY	No.2	SPF
EXCEPT				
S - C	2x4	DRY	No.2	SPF
I - L	2x4	DRY	No.2	SPF

DRY: SEASONED LUMBER.

PLATES (tablets in inches)	W	LEN	Y	X
JT TYPE				
B TMV+p	MT20	3.0	4.0	
C TMWW-t	MT20	5.0	8.0	2.50 2.50
D TTWW+m	MT20	5.0	8.0	2.00 1.75
E TMWW-t	MT20	4.0	4.0	
F TS-t	MT20	3.0	8.0	
G TMW-w	MT20	2.0	4.0	
H TTWW+m	MT20	5.0	8.0	2.00 1.75
I TMWW-t	MT20	5.0	8.0	2.50 2.50
J TMV+p	MT20	3.0	4.0	
L BMVW-t	MT20	5.0	8.0	
M BMWW-t	MT20	4.0	4.0	
N BS-t	MT20	3.0	8.0	
O BMWW-t	MT20	4.0	8.0	
P BMWW-t	MT20	4.0	8.0	
Q BS-t	MT20	3.0	8.0	
R BMWW-t	MT20	4.0	4.0	
S BMVW-t	MT20	5.0	8.0	

DIMENSIONS, SUPPORTS AND LOADINGS SPECIFIED BY FABRICATOR TO BE VERIFIED BY BUILDING DESIGNER

BEARINGS	FACTORED	MAXIMUM FACTORED	INPUT	REQD
	GROSS REACTION	GROSS REACTION	BRG	BRG
JT	VERT	DOWN	UPLIFT	IN-SX
S	2088 0	2088 0	0 0	5-8 5-8
L	2088 0	2088 0	0 0	5-8 5-8

UNFACTORED REACTIONS	1ST CASE	MAX/MIN COMPONENT REACTIONS
JT	COMBINED	SNOW LIVE PERM LIVE WIND DEAD SOIL
S	1458 971/0	0/0 0/0 0/0 488/0 0/0
L	1458 971/0	0/0 0/0 0/0 488/0 0/0

BEARING MATERIAL TO BE SPF NO.2 OR BETTER AT JOINT(S) S, L

BRACING
TOP CHORD TO BE SHEATHED OR MAX. PURLIN SPACING = 3.81 FT.
MAX. UNBRACED BOTTOM CHORD LENGTH = 10.00 FT OR RIGID CEILING DIRECTLY APPLIED.
ALL PITCH BREAKS AND PERIMETER CORNER JOINTS MUST BE Laterally RESTRAINED.

1 LATERAL BRACE(S) AT 1/2 LENGTH OF E-O.

END VERTICAL(S) MUST BE SHEATHED OR HAVE BRACES AS INDICATED IN THE MAX. UNBRACED LENGTH COLUMN OF THE TABLE BELOW

LOADING	CHORDS	WEBS
TOTAL LOAD CASES: (4)		
	MAX. FACTORED FORCE (LBS)	MAX. FACTORED FORCE (LBS)
	VERT. LOAD (LBS)	MAX. FACTORED FORCE (LBS)
	FROM TO	FROM TO
	FR-TO	FR-TO
	A-B 0/41	C-R 0/64
	B-C 0/28	R-D 0/126
	C-D -2008/0	D-P 0/998
	D-E -2183/0	P-E -650/0
	E-F -2182/0	F-E 0/0
	F-G -2182/0	G-G -649/0
	G-H -2182/0	H-H 0/998
	H-I -2008/0	I-H 0/126
	I-J 0/28	J-I 0/84
	J-K 0/41	K-S -2291/0
	S-B -284/0	B-L -2291/0
	L-J -284/0	
	S-R 0/1487	
	R-Q 0/1519	
	Q-P 0/1519	
	P-O 0/2183	
	O-N 0/1519	
	N-M 0/1519	
	M-L 0/1487	

DESIGN CRITERIA

SPECIFIED LOADS:
TOP CH. LL = 25.6 PSF
OL = 8.0 PSF
BOT CH. LL = 0.0 PSF
OL = 7.4 PSF
TOTAL LOAD = 39.0 PSF

SPACING = 24.0 IN/C

LOADING IN FLAT SECTION BASED ON A SLOPE OF 6.00/12

THIS TRUSS IS DESIGNED FOR RESIDENTIAL OR SMALL BUILDING REQUIREMENTS OF PART 9, NBC 2010, NBC 2015

THIS DESIGN COMPLIES WITH:
- PART 9 OF CBC 2018, CBC 2012, ABC 2019
- PART 9 OF CBC 2012 (2019 AMENDMENT)
- CSA 086-09, CSA 086-14
- TPIC 2011, TPIC 2014

(55 % OF 31.3 P.S.F. G.S.L. PLUS 8.4 P.S.F. RAIN LOAD) EQUALS 25.8 P.S.F. SPECIFIED ROOF LIVE LOAD

ALLOWABLE DEFL (LL) = L/360 (1.17')
CALCULATED VERT. DEFL (LL) = L/999 (0.10')
ALLOWABLE DEFL (TL) = L/360 (1.17')
CALCULATED VERT. DEFL (TL) = L/999 (0.21')

CSI: TC=0.73/1.00 (D-E-1), BC=0.42/1.00 (O-P-1), WB=0.97/1.00 (I-L-1), SS=0.28/1.00 (D-E-1)

DOL LUMBER=1.00 NAIL=1.00 LS BEND=1.10
COMP=1.10 SHEAR=1.10 TENS=1.10

COMPANION LIVE LOAD FACTOR = 1.00

AUTOSOLVE HEELS OFF

TRUSS PLATE MANUFACTURER IS NOT RESPONSIBLE FOR QUALITY CONTROL IN THE TRUSS MANUFACTURING PLANT.

NAIL VALUES
PLATE GRIP(DRY) SHEAR SECTION
(PSI) (PLI) (PLI)
MAX MIN MAX MIN MAX MIN
MT20 618 354 1687 788 1987 1658

PLATE PLACEMENT TOL. = 0.250 inches

PLATE ROTATION TOL. = 5.0 Deg.

JSI GRIP= 0.87 (I) (INPUT = 0.90)
JSI METAL= 0.58 (I) (INPUT = 1.00)



Structural component only
DWG# T-2007086



DESCR.	<u>BEARINGS</u>							
SPF	FACTORED		MAXIMUM FACTORED		INPUT	RECORD		
SPF	GROSS REACTION		GROSS REACTION		BRG	BRG		
SPF	JT	VERT	HORZ	DOWN	HORZ	UPLIFT	IN-SX	
SPF	U	2066	0	2066	0	0	5-8	
SPF	L	2066	0	2066	0	0	5-8	
SPF								
SPF								
SPF								
SPF	<u>UNFACTORED REACTIONS</u>							
SPF	1ST CASE		MAX/MIN. COMPONENT REACTIONS					
SPF	JT	COMBINED	SNOW	LIVE	PERM. LIVE	WIND	DEAD	SOIL
SPF	U	1458	971 / 0	0 / 0	0 / 0	0 / 0	488 / 0	0 / 0
SPF	L	1458	971 / 0	0 / 0	0 / 0	0 / 0	488 / 0	0 / 0
SPF								
SPF	BEARING MATERIAL TO BE SPF NO.2 OR BETTER AT JOINT(S) U, L							
SPF								
SPF	<u>BRACING</u>							
SPF	TOP CHORD TO BE SHEATHED OR MAX. PURLIN SPACING = 4.44 FT.							

MAX. UNBRACED BOTTOM CHORD LENGTH = 10.00 FT OR RIGID CEILING DIRECTLY APPLIED.

ALL PITCH BREAKS AND PERIMETER CORNER JOINTS MUST BE Laterally RESTRAINED.

1 LATERAL BRACE(S) AT 1/2 LENGTH OF E-Q, E-P, G-P.

END VERTICAL(S) MUST BE SHEATHED OR HAVE BRACES AS INDICATED IN THE MAX. UNBRACED LENGTH COLUMN OF THE TABLE BELOW

LOADING
TOTAL LOAD CASES: (4)

CHORDS				WEBS			
MEMB.	MAX. FACTORED FORCE (LBS)	FACTORED VERT. LOAD L ₁ (PLF)	MAX CSI (L ₁)	MAX. UNBRACED LENGTH	MEMB.	MAX. FACTORED FORCE (LBS)	MAX CSI (L ₁)
FR-TO		FROM TO		FR-TO			
A-B	0 / 41	-91.8	-91.8 0.13 (1)	10.00	T-C	-357 / 0	0.18 (1)
B-C	-1994 / 0	-91.8	-91.8 0.30 (2)	4.53	C-S	-121 / 0	0.10 (1)
C-D	-1857 / 0	-91.8	-91.8 0.29 (1)	4.57	S-D	0 / 188	0.05 (4)
D-E	-1923 / 0	-91.8	-91.8 0.40 (1)	4.44	D-Q	0 / 810	0.13 (1)
E-F	-1921 / 0	-91.8	-91.8 0.37 (1)	4.49	Q-E	-569 / 0	0.31 (1)
F-G	-1921 / 0	-91.8	-91.8 0.37 (1)	4.49	E-P	-3 / 0	0.00 (1)
G-H	-1821 / 0	-91.8	-91.8 0.40 (1)	4.45	P-H	-568 / 0	0.31 (1)
H-I	-1857 / 0	-91.8	-91.8 0.29 (1)	4.57	H-I	0 / 807	0.13 (1)
I-J	-1904 / 0	-91.8	-91.8 0.30 (1)	4.53	N-H	0 / 189	0.05 (4)
J-K	0 / 41	-91.8	-91.8 0.13 (1)	10.00	N-I	-121 / 0	0.10 (1)
U-B	-2028 / 0	0.0	0.0 0.22 (1)	5.84	M-I	-358 / 0	0.18 (1)
L-J	-2028 / 0	0.0	0.0 0.22 (1)	5.84	R-T	0 / 1917	

U-T	0' 0	-18.5	-18.5	0.08 (4)	10.00	M-J	0' 1617	0.38 (1)
T-S	0' 1555	-18.5	-18.5	0.30 (1)	10.00			0.38 (1)
S-R	0' 1477	-18.5	-18.5	0.30 (1)	10.00			
R-Q	0' 1477	-18.5	-18.5	0.30 (1)	10.00			
Q-P	0' 1923	-18.5	-18.5	0.38 (1)	10.00			
P-O	0' 1478	-18.5	-18.5	0.30 (1)	10.00			
O-N	0' 1478	-18.5	-18.5	0.30 (1)	10.00			
N-M	0 1555	-18.5	-18.5	0.31 (1)	10.00			
M-L	0' 0	-18.5	-18.5	0.08 (4)	10.00			

DESIGN CRITERIA

SPECIFIED LOADS:
TOP CH. LL = 25.6 PSF
DL = 8.0 PSF
BOT CH. LL = 0.0 PSF
DL = 7.4 PSF
TOTAL LOAD = 39.0 PSF

SPACING = 24.0 IN./C

LOADING IN FLAT SECTION BASED ON A SLOPE OF 8.00/12

THIS TRUSS IS DESIGNED FOR RESIDENTIAL OF SMALL BUILDING REQUIREMENTS OF PART 9, NBC 2010, NBC 2015

THIS DESIGN COMPLIES WITH:
- PART 9 OF NBC 2018, NBC 2012, ABC 2019
- PART 9 OF NBC 2012 (2019 AMENDMENT)
- CSA 088-09, CSA 088-14
- TPIC 2011, TPIC 2014

(55 % OF 31.3 P.S.F. G.S.L PLUS 8.4 P.S.F. RAIN LOAD) EQUALS 25.6 P.S.F. SPECIFIED ROOF LIVE LOAD

ALLOWABLE DEFL.(LL)= L/360 (1.17")
CALCULATED VERT. DEFL.(LL) = L/999 (0.08")
ALLOWABLE DEFL.(TL)= L/360 (1.17")
CALCULATED VERT. DEFL.(TL) = L/999 (0.16")

CSI: YC=0.40/1.00 (D-E:1), BC=0.38/1.00 (P-Q:1),
WB=0.38/1.00 (B-T:1), SSI=0.25/1.00 (D-E:1)

DOL LUMBER=1.00 NAIL=1.00 LS BEND=1.10
COMP=1.10 SHEAR=1.10 TENS= 1.10

COMPANION LIVE LOAD FACTOR = 1.00

TRUSS PLATE MANUFACTURER IS NOT RESPONSIBLE FOR QUALITY CONTROL IN THE TRUSS MANUFACTURING PLANT .

NAIL VALUES
PLATE GRP(DRY) SHEAR SECTION
(PSI) (PLI) (PLI)
MAX MIN MAX MIN MAX MIN
MT20 818 354 1887 788 1987 1888

PLATE PLACEMENT TOL = 0.250 inches

PLATE ROTATION TOL = 5.0 Deg.

JSI GRIP= 0.89 (B) (INPUT = 0.90)
JSI METAL= 0.50 (O) (INPUT = 1.00)




JOB NAME	TRUSS NAME	QUANTITY	PLY	JOB DESC.	DRWG NO.
408151	T27	2	1	GREEN PARK HOMES	
Tamarack Roof Truss, Burlington				TRUSS DESC.	

Version 8.310 S Oct 28 2019 Mitek Industries, Inc. Sat Apr 25 11:10:53 2020 Page 1

ID:h2dlqC44wS_E2tqPs_atzllRw-TrgPQ2svvcVG7mnMST9S9GeH81uT3o2SIR1ZNUzNCXa

Scale = 1:99.9



TOTAL WEIGHT = 2 X 190 = 380 lb

LUMBER	N. L. G. A. RULES	CHORDS	SIZE	DRY	LUMBER	DESCR.
A - D	2x4	DRY	No.2	SPF		
E - G	2x4	DRY	No.2	SPF		
H - K	2x4	DRY	No.2	SPF		
L - J	2x4	DRY	No.2	SPF		
M - I	2x4	DRY	No.2	SPF		
N - O	2x4	DRY	No.2	SPF		
P - L	2x4	DRY	No.2	SPF		
ALL WEBS EXCEPT	2x4	DRY	No.2	SPF		
S - C	2x3	DRY	No.2	SPF		
N - I	2x3	DRY	No.2	SPF		
M - J	2x3	DRY	No.2	SPF		
B - S	2x3	DRY	No.2	SPF		
M - J	2x3	DRY	No.2	SPF		

DRY: SEASONED LUMBER.

PLATES (table is in inches)

JT	TYPE	PLATES	W	LEN	Y	X
B	TMW-p	MT20	5.0	6.0	1.50	3.00
C	TMW-l	MT20	4.0	4.0	2.00	1.25
D	TS-l	MT20	3.0	6.0		
E	TTW-m	MT20	5.0	8.0	Edge	3.00
F	TMW-w	MT20	2.0	4.0		
G	TTW-m	MT20	6.0	8.0	Edge	3.00
H	TS-l	MT20	3.0	6.0		
I	TMW-l	MT20	4.0	4.0	2.00	1.25
J	TMW-p	MT20	5.0	6.0	1.50	3.00
L	BMV-l	MT20	3.0	4.0		
M	BMW-w	MT20	5.0	6.0		
N	BMW-l	MT20	4.0	4.0		
O	SS-l	MT20	3.0	6.0		
P	BMW-w	MT20	4.0	9.0		
Q	SS-l	MT20	3.0	6.0		
R	BMW-l	MT20	4.0	4.0		
S	BMW-l	MT20	5.0	6.0		
T	BMV-l	MT20	3.0	4.0		

DIMENSIONS, SUPPORTS AND LOADINGS SPECIFIED BY FABRICATOR TO BE VERIFIED BY BUILDING DESIGNER

BEARINGS	FACTORED	MAXIMUM FACTORED	INPUT	REQD
	GROSS REACTION	GROSS REACTION	BRG	BRG
JT	VERT	HORZ	DOWN	HORZ
T	2088	0	2088	0
L	2088	0	2088	0

UNFACTORED REACTIONS

1ST CASE	MAX/MIN. COMPONENT REACTIONS					
JT	COMBINED	SNOW	LIVE	PERM. LIVE	WIND	DEAD
T	1458	971/0	0/0	0/0	0/0	488/0
L	1458	971/0	0/0	0/0	0/0	488/0

BEARING MATERIAL TO BE SPF NO.2 OR BETTER AT JOINT(S) T, L

BRACING

TOP CHORD TO BE SHEATHED OR MAX. PURLIN SPACING = 4.27 FT.
MAX. UNBRACED BOTTOM CHORD LENGTH = 10.00 FT. OR RIGID CEILING DIRECTLY APPLIED.

ALL PITCH BREAKS AND PERIMETER CORNER JOINTS MUST BE Laterally RESTRAINED.

1 LATERAL BRACE(S) AT 1/2 LENGTH OF C-R, F-P, I-N.

END VERTICAL(S) MUST BE SHEATHED OR HAVE BRACES AS INDICATED IN THE MAX. UNBRACED LENGTH COLUMN OF THE TABLE BELOW

LOADING

TOTAL LOAD CASES: (4)

CHORDS	MAX. FACTORED	FACTORED	WEBS	MAX. FACTORED
MEMB.	FORCE (LBS)	VERT. LOAD L ₀₁ (PLF)	MAX. UNBRACED LENGTH (LC)	MEMB. FORCE (LBS)
FR-TO				
A-B	0/141	-91.8	-91.8	0.13 (1)
B-C	-2039/0	-91.8	-91.8	0.50 (1)
C-D	-1844/0	-91.8	-91.8	0.48 (1)
D-E	-1844/0	-91.8	-91.8	0.48 (1)
E-F	-1821/0	-91.8	-91.8	0.50 (1)
F-G	-1821/0	-91.8	-91.8	0.50 (1)
G-H	-1844/0	-91.8	-91.8	0.48 (1)
H-I	-1844/0	-91.8	-91.8	0.48 (1)
I-J	-2039/0	-91.8	-91.8	0.50 (1)
J-K	0/141	-91.8	-91.8	0.13 (1)
T-B	-2021/0	0.0	0.0	0.21 (1)
L-J	-2021/0	0.0	0.0	0.21 (1)
T-S	0/0	-18.5	-18.5	0.14 (4)
S-R	0/1597	-18.5	-18.5	0.33 (1)
R-Q	0/1387	-18.5	-18.5	0.30 (1)
Q-P	0/1387	-18.5	-18.5	0.30 (1)
P-O	0/1387	-18.5	-18.5	0.30 (1)
O-N	0/1387	-18.5	-18.5	0.30 (1)
N-M	0/1597	-18.5	-18.5	0.33 (1)
M-L	0/0	-18.5	-18.5	0.14 (4)

DESIGN CRITERIA

SPECIFIED LOADS:
TOP CH. LL = 26.8 PSF
DL = 6.0 PSF
BOT CH. LL = 0.0 PSF
DL = 7.4 PSF
TOTAL LOAD = 39.0 PSF

SPACING = 24.0 IN. C/C

LOADING IN FLAT SECTION BASED ON A SLOPE OF 6.00/12

THIS TRUSS IS DESIGNED FOR RESIDENTIAL OR SMALL BUILDING REQUIREMENTS OF PART 9, NBC 2010, NBC 2015

THIS DESIGN COMPLIES WITH:
- PART 9 OF BCBC 2018, OBC 2012, ABC 2019
- PART 9 OF OBC 2012 (2019 AMENDMENT)
- CSA 086-08, CSA 086-14
- TPIC 2011, TPIC 2014

(56 % OF 31.3 P.S.F. G.S.L. PLUS 8.4 P.S.F. RAIN LOAD) EQUALS 25.8 P.S.F. SPECIFIED ROOF LIVE LOAD

ALLOWABLE DEFL.(LL) = L/360 (1.17")
CALCULATED VERT. DEFL.(LL) = L/999 (0.07")
ALLOWABLE DEFL.(TL) = L/360 (1.17")
CALCULATED VERT. DEFL.(TL) = L/999 (0.14")

CS: TC=0.60/1.00 (E-F:1), BC=0.33/1.00 (M-N:1), WB=0.45/1.00 (F-P:1), SS=0.28/1.00 (E-F:1)

DOL LUMBER=1.00 NAIL=1.00 LS BEND=1.10
COMP=1.10 SHEAR=1.10 TENS=1.10

COMPANION LIVE LOAD FACTOR = 1.00

TRUSS PLATE MANUFACTURER IS NOT RESPONSIBLE FOR QUALITY CONTROL IN THE TRUSS MANUFACTURING PLANT.

NAIL VALUES
PLATE GRIP(DRY) SHEAR SECTION (PSI) (PL) (PL)
MAX MIN MAX MIN MAX MIN
MT20 818 354 1687 788 1997 1658

PLATE PLACEMENT TOL. = 0.250 inches

PLATE ROTATION TOL. = 5.0 Deg.

JSI GRIP= 0.89 (J) (INPUT = 0.90)
JSI METAL= 0.47 (O) (INPUT = 1.00)




Structural component only
DWG# T-2007089

CONTINUED ON PAGE 2

JOB NAME	TRUSS NAME	QUANTITY	PLY	JOB DESC.	DRWG NO.
408151	T28	2	1	GREEN PARK HOMES	

Tamarack Roof Truss, Burlington

Version 8.310 S Oct 29 2019 Mittek Industries, Inc. Sat Apr 25 11:19:54 2020 Page 1



LUMBER			
N. L. G. A. RULES	CHORDS	SIZE	LUMBER
A - D	2x4	DRY	No.2
D - G	2x4	DRY	No.2
L - B	2x4	DRY	No.2
H - F	2x4	DRY	No.2
L - J	2x4	DRY	No.2
J - H	2x4	DRY	No.2
ALL WEBS	2x3	DRY	No.2
EXCEPT			

DRY: SEASONED LUMBER.

PLATES (tablets in inches)

JT	TYPE	PLATES	W	LEN	Y	X
B	TMV+p	MT20	3.0	4.0		
C	TMWW-t	MT20	4.0	8.0		
D	TTWW+p	MT20	4.0	8.0		Edge
E	TMWW-t	MT20	4.0	8.0		
F	TMV+p	MT20	3.0	4.0		
H	BMVW1-t	MT20	4.0	4.0		
I	BMVW1-t	MT20	4.0	8.0		
J	BS-t	MT20	3.0	8.0		
K	BMVW1-t	MT20	4.0	8.0		
L	BMVW1-t	MT20	4.0	4.0		

Edge - INDICATES REFERENCE CORNER OF PLATE TOUCHES EDGE OF CHORD.

DIMENSIONS, SUPPORTS AND LOADINGS SPECIFIED BY FABRICATOR TO BE VERIFIED BY BUILDING DESIGNER

BEARINGS		FACTORED GROSS REACTION		MAXIMUM FACTORED GROSS REACTION		INPUT		REQD	
JT	VERT	HORIZ	DOWN	HORIZ	UPLIFT	IN-SX	IN-SX	BRG	BRG
L	1041	0	1041	0	0	5-8	5-8		
H	1041	0	1041	0	0	5-8	5-8		

UNFACTORED REACTIONS

JT	1ST CASE	MAX/MIN	COMPONENT REACTIONS	SNOW	LIVE	PERM	LIVE	WIND	DEAD	SOIL
L	734	485 / 0	0 / 0	0 / 0	0 / 0	0 / 0	239 / 0	0 / 0	0 / 0	0 / 0
H	734	485 / 0	0 / 0	0 / 0	0 / 0	0 / 0	239 / 0	0 / 0	0 / 0	0 / 0

BEARING MATERIAL TO BE SPF NO.2 OR BETTER AT JOINT(S) L, H

BRACING

TOP CHORD TO BE SHEATHED OR MAX. PURLIN SPACING = 8.25 FT.
MAX. UNBRACED BOTTOM CHORD LENGTH = 10.00 FT OR RIGID CEILING DIRECTLY APPLIED.

ALL PITCH BREAKS AND PERIMETER CORNER JOINTS MUST BE Laterally RESTRAINED.

LOADING

TOTAL LOAD CASES: (4)

CHORDS		FACTORED		WEBS	
MEMB.	FORCE (LBS)	VERT. LOAD (LBS)	LC1 MAX (PLF)	MEMB.	FORCE (LBS)
FR-TO				FR-TO	
A-B	0 / 41	-91.8	-91.8 0.13 (1)	D-I	0 / 339
B-C	0 / 29	-91.8	-91.8 0.28 (1)	I-E	-222 / 0
C-D	-784 / 0	-91.8	-91.8 0.20 (1)	K-D	0 / 339
D-E	-784 / 0	-91.8	-91.8 0.20 (1)	C-K	-222 / 0
E-F	0 / 29	-91.8	-91.8 0.26 (1)	L-C	-984 / 0
F-G	0 / 41	-91.8	-91.8 0.13 (1)	E-H	-984 / 0
L-B	-270 / 0	0.0	0.0 0.03 (1)		
H-F	-270 / 0	0.0	0.0 0.03 (1)		
L-K	0 / 632	-18.5	-18.5 0.18 (4)		
K-J	0 / 459	-18.5	-18.5 0.17 (4)		
J-I	0 / 459	-18.5	-18.5 0.17 (4)		
I-H	0 / 632	-18.5	-18.5 0.18 (4)		

TOTAL WEIGHT = 2 X 82 = 164 lb

DESIGN CRITERIA

SPECIFIED LOADS:

TOP CH. LL	= 25.6	PSF
DL	= 8.0	PSF
BOY CH. LL	= 0.0	PSF
DL	= 7.4	PSF
TOTAL LOAD	= 39.0	PSF

SPACING = 24.0 IN/C

THIS TRUSS IS DESIGNED FOR RESIDENTIAL OR SMALL BUILDING REQUIREMENTS OF PART 9, NBC 2010, NBC 2015

THIS DESIGN COMPLIES WITH:

- PART 9 OF CBC 2018, CBC 2012, ABC 2019
- PART 9 OF CBC 2012 (2019 AMENDMENT)
- CSA 086-08, CSA 086-14
- TPIC 2011, TPIC 2014

(55 % OF 31.3 P.S.F. G.S.L. PLUS 8.4 P.S.F. RAIN LOAD) EQUALS 25.6 P.S.F. SPECIFIED ROOF LIVE LOAD

ALLOWABLE DEFL.(LL) = $L/360$ (0.55")
CALCULATED VERT. DEFL.(LL) = $L/989$ (0.02")
ALLOWABLE DEFL.(TL) = $L/360$ (0.55")
CALCULATED VERT. DEFL.(TL) = $L/989$ (0.04")

CSI: TC=0.26/1.00 (B-C:1), BC=0.18/1.00 (H-I:4), WB=0.88/1.00 (E-H:1), SS=0.14/1.00 (C-D:1)

DOL LUMBER=1.00 NAIL=1.00 LS BEND=1.10
COMP=1.10 SHEAR=1.10 TENS=1.10

COMPANION LIVE LOAD FACTOR = 1.00

TRUSS PLATE MANUFACTURER IS NOT RESPONSIBLE FOR QUALITY CONTROL IN THE TRUSS MANUFACTURING PLANT

NAIL VALUES

PLATE GRIP (DRY)	SHEAR (PSI)	SECTION (PLI)
MAX MIN	MAX MIN	MAX MIN
MT20	618 384	1687 788

PLATE PLACEMENT TOL. = 0.250 inches

PLATE ROTATION TOL. = 5.0 Deg.

JSI GRIP = 0.78 (C) (INPUT = 0.80)
JSI METAL = 0.28 (C) (INPUT = 1.00)




Structural component only
DWG# T-2007090

JOB NAME	TRUSS NAME	QUANTITY	PLY	JOB DESC.	DRWG NO.
408151	T29	1	1	GREEN PARK HOMES	

Tamarack Roof Truss, Burlington

Version 8.310 S Oct 29 2019 AMtek Industries, Inc. Sat Apr 25 11:19:55 2020 Page 1
ID:h2d1gC44wS_E2tqPs_atzllRw-PEoArkt7RElW4xlatBwEhig9qdOXaSkmlWpSNzNCXY



Scale = 1:54.7

CHORDS	SIZE	LUMBER
A - D	2x4	DRY No.2
D - G	2x4	DRY No.2
L - B	2x4	DRY No.2
H - F	2x4	DRY No.2
L - J	2x4	DRY No.2
J - H	2x4	DRY No.2

ALL WEBS 2x3 DRY No.2 EXCEPT

DRY: SEASONED LUMBER.

PLATES (table is in inches)

JT TYPE	PLATES	W	LEN	Y	X
B TMV+p	MT20	3.0	4.0		
C TMWW-1	MT20	4.0	4.0	2.00	1.50
D TTWW+p	MT20	5.0	8.0	Edge	
E TMWW-1	MT20	4.0	4.0	2.00	1.50
F TMV+p	MT20	3.0	4.0		
H BMWW-1	MT20	4.0	4.0		
I BMWW-1	MT20	4.0	4.0		
J BS-1	MT20	3.0	8.0		
K BMWW-1	MT20	4.0	4.0		
L BMWW-1	MT20	4.0	4.0		

Edge - INDICATES REFERENCE CORNER OF PLATE TOUCHES EDGE OF CHORD.

DIMENSIONS, SUPPORTS AND LOADINGS SPECIFIED BY FABRICATOR TO BE VERIFIED BY BUILDING DESIGNER

BEARINGS

DESCR.	SPF	FACTORED GROSS REACTION	MAXIMUM FACTORED GROSS REACTION	INPUT BRG	RECORD BRG
JT	SPF	VERT	HORZ	DOWN	HORZ
L	SPF	1041	0	1041	0
H	SPF	1041	0	1041	0

UNFACTORED REACTIONS

JT	COMBINED	1ST CASE SNOW	MAX/MIN. COMPONENT REACTIONS	LIVE	PERM.LIVE	WIND	DEAD	SOIL
L	734	485/0	0/0	0/0	0/0	0/0	239/0	0/0
H	734	485/0	0/0	0/0	0/0	0/0	239/0	0/0

BEARING MATERIAL TO BE SPF NO.2 OR BETTER AT JOINT(S) L, H

BRACING

TOP CHORD TO BE SHEATHED OR MAX. PURLIN SPACING = 6.25 FT.
MAX. UNBRACED BOTTOM CHORD LENGTH = 10.00 FT OR RIGID CEILING DIRECTLY APPLIED.

ALL PITCH BREAKS AND PERIMETER CORNER JOINTS MUST BE Laterally RESTRAINED.

LOADING

TOTAL LOAD CASES: (4)

CHORDS				WEBS			
MEMB.	MAX. FACTORED FORCE (LBS)	FACTORED VERT. LOAD (PLF)	MAX. CSI (LC)	MEMB.	MAX. FACTORED FORCE (LBS)	MAX. CSI (LC)	UNBRACED LENGTH FR-TO
FR-TO		FROM TO		FR-TO			
A-B	0/41	-91.8	-91.8 0.13 (1)	D-I	0/254	0.08 (1)	10.00
B-C	0/28	-91.8	-91.8 0.28 (1)	E-H	-138/14	0.10 (1)	10.00
C-D	-633/0	-91.8	-91.8 0.20 (1)	K-L	0/254	0.08 (1)	10.00
D-E	-633/0	-91.8	-91.8 0.20 (1)	M-N	-138/14	0.10 (1)	10.00
E-F	0/28	-91.8	-91.8 0.28 (1)	O-P	-138/14	0.10 (1)	10.00
F-G	0/41	-91.8	-91.8 0.13 (1)	Q-R	-138/14	0.10 (1)	10.00
G-H	-278/0	0.0	0.0 0.04 (1)	S-T	-138/14	0.10 (1)	10.00
H-I	-278/0	0.0	0.0 0.04 (1)	U-V	-138/14	0.10 (1)	10.00
I-J	0/495	-18.5	-18.5 0.17 (4)				
J-K	0/395	-18.5	-18.5 0.16 (4)				
K-L	0/395	-18.5	-18.5 0.16 (4)				
L-M	0/495	-18.5	-18.5 0.17 (4)				

TOTAL WEIGHT = 91 lb

DESIGN CRITERIA

SPECIFIED LOADS:

TOP CH.	LL = 25.8 PSF
	DL = 8.0 PSF
BOT CH.	LL = 0.0 PSF
	DL = 7.4 PSF
TOTAL LOAD	= 39.0 PSF

SPACING = 24.0 IN. C/C

THIS TRUSS IS DESIGNED FOR RESIDENTIAL OR SMALL BUILDING REQUIREMENTS OF PART 9, NBCC 2010, NBCC 2015

THIS DESIGN COMPLIES WITH:

- PART 9 OF NBCC 2010, NBCC 2015, ABC 2019
- PART 9 OF NBCC 2012 (2019 AMENDMENT)
- CSA 088-09, CSA 088-14
- TPIC 2011, TPIC 2014

(55% OF 31.3 P.S.F. G.S.L. PLUS 8.4 P.S.F. RAIN LOAD) EQUALS 25.8 P.S.F. SPECIFIED ROOF LIVE LOAD

ALLOWABLE DEFL. (LL) = $L/360$ (0.65")
CALCULATED VERT. DEFL. (LL) = $L/999$ (0.02")
ALLOWABLE DEFL. (TL) = $L/360$ (0.65")
CALCULATED VERT. DEFL. (TL) = $L/999$ (0.04")

CSI: TC=0.28/1.00 (E-F:1), BC=0.17/1.00 (K-L:4), WB=0.90/1.00 (E-H:1), SB=0.14/1.00 (E-F:1)

DOL LUMBER=1.00 NAIL=1.00 LS BEND=1.10
COMP=1.10 SHEAR=1.10 TENS=1.10

COMPANION LIVE LOAD FACTOR = 1.00

TRUSS PLATE MANUFACTURER IS NOT RESPONSIBLE FOR QUALITY CONTROL IN THE TRUSS MANUFACTURING PLANT.


NAIL VALUES

PLATE	GRP(DRY)	SHEAR	SECTION
	(PSI)	(PLI)	(PLI)
MT20	618	354	1697

PLATE PLACEMENT TOL = 0.250 inches

PLATE ROTATION TOL = 5.0 Deg.


JSI GRIP = 0.88 (E) (INPUT = 0.80)
JSI METAL = 0.34 (C) (INPUT = 1.00)



Structural component only
DWG# T-2007091

JOB NAME 408151	TRUSS NAME T30	QUANTITY 1	PLY 1	JOB DESC. GREEN PARK HOMES	DRWG NO.
--------------------	-------------------	---------------	----------	-------------------------------	----------

Tamarack Roof Truss, Burlington



LUMBER	N. L. G. A. RULES	CHORDS	SIZE	LUMBER	DESCR.
A - D	2x4	DRY	No.2	SPF	
D - E	2x6	DRY	No.2	SPF	
E - H	2x4	DRY	No.2	SPF	
L - B	2x4	DRY	No.2	SPF	
I - G	2x4	DRY	No.2	SPF	
L - K	2x4	DRY	No.2	SPF	
K - I	2x4	DRY	No.2	SPF	
ALL WEBS EXCEPT	2x3	DRY	No.2	SPF	

DRY: SEASONED LUMBER.

PLATES (table in inches)	PLATES	W	LEN	Y	X
B	TMV-p	MT20	3.0	4.0	
C	TMVW-1	MT20	4.0	4.0	2.00 1.75
D	TMV-h	MT20	4.0	8.0	
E	TMVW-m	MT20	5.0	8.0	Edge
F	TMVW-1	MT20	4.0	8.0	
G	TMV-p	MT20	3.0	4.0	
I	BMVW-1	MT20	4.0	4.0	
J	BMVW-1	MT20	4.0	4.0	
K	BSVW-1	MT20	8.0	9.0	Edge 3.75
L	BMVW-1	MT20	4.0	4.0	

Edge - INDICATES REFERENCE CORNER OF PLATE TOUCHES EDGE OF CHORD.

DIMENSIONS, SUPPORTS AND LOADINGS SPECIFIED BY FABRICATOR TO BE VERIFIED BY BUILDING DESIGNER					
BEARINGS					
JT	FACTORED GROSS REACTION	MAXIMUM FACTORED GROSS REACTION	INPUT BRG	REQD BRG	
L	1041 0	1041 0	5-8	5-8	
I	1041 0	1041 0	MECHANICAL		

A SUITABLE HANGER/MECHANICAL CONNECTION IS REQUIRED AT JOINT I. MINIMUM BEARING LENGTH AT JOINT I = 3-8.

UNFACTORED REACTIONS							
1ST LOASE	COMBINED	SNOW	LIVE	PERM LIVE	WIND	DEAD	SOIL
JT	734	495 / 0	0 / 0	0 / 0	0 / 0	239 / 0	0 / 0
L	734	495 / 0	0 / 0	0 / 0	0 / 0	239 / 0	0 / 0

BEARING MATERIAL TO BE SPF NO.2 OR BETTER AT JOINT(S) L

BRACING
TOP CHORD TO BE SHEATHED OR MAX. PURLIN SPACING = 8.25 FT.
MAX. UNBRACED BOTTOM CHORD LENGTH = 10.00 FT OR RIGID CEILING DIRECTLY APPLIED.

ALL PITCH BREAKS AND PERIMETER CORNER JOINTS MUST BE Laterally RESTRAINED.

1 LATERAL BRACE(S) AT 1/2 LENGTH OF E-K.

END VERTICAL(S) MUST BE SHEATHED OR HAVE BRACES AS INDICATED IN THE MAX. UNBRACED LENGTH COLUMN OF THE TABLE BELOW

CHORDS				WEBS			
MEMB.	MAX. FACTORED FORCE (LBS)	FACTORED VERT. LOAD (PLF)	MAX. FACTORED CS (LC)	MEMB.	MAX. FACTORED FORCE (LBS)	MAX. FACTORED CS (LC)	
FR-TO		FROM TO		FR-TO			
A-B	0 / 41	-91.8	-91.8 0.13 (1)	C-K	-88 / 9	0.09 (1)	
B-C	0 / 27	-91.8	-91.8 0.23 (1)	K-D	0 / 184	0.04 (1)	
C-D	-588 / 0	-91.8	-91.8 0.18 (1)	E-F	-109 / 0	0.07 (4)	
D-E	-414 / 0	-91.8	-91.8 0.01 (1)	F-G	0 / 288	0.07 (4)	
E-F	-582 / 0	-91.8	-91.8 0.18 (1)	G-H	-93 / 15	0.09 (1)	
F-G	0 / 27	-91.8	-91.8 0.23 (1)	H-I	-848 / 0	0.78 (1)	
G-H	0 / 41	-91.8	-91.8 0.13 (1)	I-J	-882 / 0	0.79 (1)	
H-I	-265 / 0	0.0	0.0 0.04 (1)				
I-J	-265 / 0	0.0	0.0 0.04 (1)				
J-K	0 / 488	-18.5	-18.5 0.38 (4)				
K-L	0 / 424	-18.5	-18.5 0.30 (4)				
L-K	0 / 477	-18.5	-18.5 0.30 (4)				

TOTAL WEIGHT = 97 lb

DESIGN CRITERIA

SPECIFIED LOADS:
TOP CH. LL = 25.8 PSF
DL = 6.0 PSF
BOT CH. LL = 0.0 PSF
DL = 7.4 PSF
TOTAL LOAD = 39.0 PSF

SPACING = 24.0 IN. C/C

LOADING IN FLAT SECTION BASED ON A SLOPE OF 8.00/12

THIS TRUSS IS DESIGNED FOR RESIDENTIAL OR SMALL BUILDING REQUIREMENTS OF PART 9, NBC 2010, NBC 2015

THIS DESIGN COMPLIES WITH:
- PART 9 OF CBC 2018, OBC 2012, ABC 2019
- PART 9 OF OBC 2012 (2019 AMENDMENT)
- CSA 088-09, CSA 088-14
- TPIC 2011, TPIC 2014

(55% OF 31.3 P.S.F. G.S.L. PLUS 8.4 P.S.F. RAIN LOAD) EQUALS 25.8 P.S.F. SPECIFIED ROOF LIVE LOAD

ALLOWABLE DEFL. (LL) = L/360 (0.55")
CALCULATED VERT. DEFL. (LL) = L/999 (0.01")
ALLOWABLE DEFL. (TL) = L/360 (0.55")
CALCULATED VERT. DEFL. (TL) = L/999 (0.17")

CSI: TC=0.23/1.00 (B-C:1), BC=0.38/1.00 (K-L:4), WB=0.79/1.00 (F-I:1), SS=0.14/1.00 (J-K:4)

DOL LUMBER=1.00 NAIL=1.00 LS BEND=1.10 COMP=1.10 SHEAR=1.10 TENS=1.10

COMPANION LIVE LOAD FACTOR = 1.00

TRUSS PLATE MANUFACTURER IS NOT RESPONSIBLE FOR QUALITY CONTROL IN THE TRUSS MANUFACTURING PLANT.

NAIL VALUES
PLATE GRIP (DRY) SHEAR SECTION (PSI) (PLI) (PLI)
MAX MIN MAX MIN MAX MIN
MT20 618 354 1687 788 1987 1658

PLATE PLACEMENT TOL. = 0.250 inches

PLATE ROTATION TOL. = 5.0 Deg.

JSI GRIP=0.89 (C) (INPUT = 0.90)
JSI METAL=0.31 (C) (INPUT = 1.00)




Structural component only
DWG# T-2007092

JOB NAME	TRUSS NAME	QUANTITY	PLY	JOB DESC.	GREEN PARK HOMES	DRWG NO.
408151	T31	1	1	TRUSS DESC.		

Tamarack Roof Truss, Burlington

Version 8.310 3 Oct 29 2019 Mike Industries, Inc. Sat Apr 25 11:19:57 2020 Page 1
ID:h2dlfgC44ws_E2kqPs_atzllRw-LowwGPvFz0ebO58hIDCJ5o2BeID?ZetID3?nWfzNCKW



Scale = 1/4" = 1'-0"

N. L. G. A. RULES	CHORDS	SIZE	DRY	LUMBER
A - D	2x4	DRY	No.2	
D - E	2x4	DRY	No.2	
E - H	2x4	DRY	No.2	
M - B	2x4	DRY	No.2	
I - G	2x4	DRY	No.2	
M - K	2x4	DRY	No.2	
K - I	2x4	DRY	No.2	

ALL WEBS 2x3 DRY No.2
EXCEPT

DRY; SEASONED LUMBER.

PLATES (table in inches)

JT	TYPE	PLATES	W	LEN	Y	X
B	TMV+p	MT20	3.0	4.0		
C	TMWW-i	MT20	4.0	4.0	2.00	1.75
D	TTW-m	MT20	4.0	4.0		
E	TTWW+m	MT20	5.0	6.0	2.25	1.50
F	TMWW-i	MT20	4.0	4.0	2.00	1.75
G	TMV+p	MT20	3.0	4.0		
I	BMVW1-i	MT20	4.0	4.0		
J	BMWW-i	MT20	4.0	4.0		
K	BS-i	MT20	3.0	6.0		
L	BMVW1-i	MT20	4.0	9.0		
M	BMVW1-i	MT20	4.0	4.0		

DIMENSIONS, SUPPORTS AND LOADINGS SPECIFIED BY FABRICATOR TO BE VERIFIED BY BUILDING DESIGNER

FACTORED	MAXIMUM FACTORED	INPUT	REQD
GROSS REACTION	GROSS REACTION	BRG	BRG
JT VERT	DOWN	HORIZ	UPLIFT
M 1041	0	1041	0
I 1041	0	1041	0
		5-8	5-8
		MECHANICAL	

A SUITABLE HANGER/MECHANICAL CONNECTION IS REQUIRED AT JOINT I. MINIMUM BEARING LENGTH AT JOINT I = 3-8.

UNFACTORED REACTIONS

JT	COMBINED	SNOW	LIVE	PERM.LIVE	WIND	DEAD	SOIL
M	734	495/0	0/0	0/0	0/0	239/0	0/0
I	734	495/0	0/0	0/0	0/0	239/0	0/0

BEARING MATERIAL TO BE SPF NO.2 OR BETTER AT JOINT(S) M

BRACING

TOP CHORD TO BE SHEATHED OR MAX. PURLIN SPACING = 8.25 FT.
MAX. UNBRACED BOTTOM CHORD LENGTH = 10.00 FT OR RIGID CEILING DIRECTLY APPLIED.

ALL PITCH BREAKS AND PERIMETER CORNER JOINTS MUST BE Laterally RESTRAINED.

LOADING

TOTAL LOAD CASES: (4)

CHORDS	MAX. FACTORED	FACTORED	MAX.	MEMB.	MAX. FACTORED	WEBS	MAX. FACTORED
MEMB.	FORCE	VERT. LOAD	LC1	MAX	FORCE	MEMB.	FORCE
(LBS)	(PLF)	CS1(LC)	UNBRAC	LENGTH	(LBS)	CS1(LC)	
FR-TO							
A-B	0/41	-91.8	-91.8	0.13 (1)	10.00	C-L	-10/34
B-C	0/22	-91.8	-91.8	0.16 (1)	10.00	L-D	0/110
C-D	-813/0	-91.8	-91.8	0.13 (1)	8.25	L-E	0/0
D-E	-453/0	-91.8	-91.8	0.14 (1)	6.25	J-E	0/109
E-F	-612/0	-91.8	-91.8	0.13 (1)	6.25	J-F	-11/34
F-G	0/22	-91.8	-91.8	0.18 (1)	10.00	M-C	-873/0
G-H	0/41	-91.8	-91.8	0.13 (1)	10.00	F-I	-873/0
M-B	-245/0	0.0	0.0	0.04 (1)	7.81		
I-G	-245/0	0.0	0.0	0.04 (1)	7.81		
M-L	0/457	-18.5	-18.5	0.21 (4)	10.00		
L-K	0/453	-18.5	-18.5	0.20 (4)	10.00		
K-J	0/453	-18.5	-18.5	0.20 (4)	10.00		
J-I	0/457	-18.5	-18.5	0.21 (4)	10.00		

TOTAL WEIGHT = 92 lb

DESIGN CRITERIA

SPECIFIED LOADS:
TOP CH. LL = 25.8 PSF
DL = 8.0 PSF
BOT CH. LL = 0.0 PSF
DL = 7.4 PSF
TOTAL LOAD = 39.0 PSF

SPACING = 24.0 IN. C/C

LOADING IN FLAT SECTION BASED ON A SLOPE OF 6.00/12

THIS TRUSS IS DESIGNED FOR RESIDENTIAL OR SMALL BUILDING REQUIREMENTS OF PART 9, NBCC 2010, NBCC 2015

THIS DESIGN COMPLIES WITH:
- PART 9 OF BCBC 2018, OBC 2012, ABC 2018
- PART 9 OF OBC 2012 (2019 AMENDMENT)
- CSA 086-09, CSA 086-14
- TPIC 2011, TPIC 2014

(55% OF 31.3 P.S.F. G.S.L. PLUS 8.4 P.S.F. RAIN LOAD) EQUALS 25.8 P.S.F. SPECIFIED ROOF LIVE LOAD

ALLOWABLE DEFL.(LL) = L/360 (0.55")
CALCULATED VERT. DEFL(LL) = L/988 (0.01")
ALLOWABLE DEFL.(TL) = L/360 (0.55")
CALCULATED VERT. DEFL.(TL) = L/988 (0.07")

CSI: TC=0.18/1.00 (F-B:1), BC=0.21/1.00 (I-J:4),
WB=0.50/1.00 (C-M:1), SS=0.12/1.00 (D-E:1)

DOL LUMBER=1.00 NAIL=1.00 L3 BEND=1.10
COMP=1.10 SHEAR=1.10 TENS=1.10

COMPANION LIVE LOAD FACTOR = 1.00

TRUSS PLATE MANUFACTURER IS NOT RESPONSIBLE FOR QUALITY CONTROL IN THE TRUSS MANUFACTURING PLANT.

NAIL VALUES
PLATE GRIP(DRY) SHEAR SECTION
(PSI) (PL) (PL)
MAX MIN MAX MIN MAX MIN
MT20 818 354 1667 788 1987 1668

PLATE PLACEMENT TOL. = 0.250 inches

PLATE ROTATION TOL. = 5.0 Deg.

JSI GRIP = 0.87 (C) (INPUT = 0.90)
JSI METAL = 0.31 (C) (INPUT = 1.00)




Structural component only
DWG# T-2007093

JOB NAME	TRUSS NAME	QUANTITY	PLY	JOB DESC.	GREEN PARK HOMES	DRWG NO.
408151	T32	1	1	TRUSS DESC.		

Tamarack Roof Truss, Burlington

Version 8.310 S Oct 29 2019 Mtek Industries, Inc. Sat Apr 26 11:19:28 2020 Page 1
ID:h2dlfgC44wS_E2tzqPs_atzllRw-ppUJTtwk98VDYgKF0ldrJL8I2f0k8OBSJK2zNCXV



TOTAL WEIGHT = 79 lb
[M/F]

LUMBER	N. L. & A. RULES	CHORDS	SIZE	LUMBER	DESCR.
A - C	2x4	DRY	No.2	SPF	
D - D	2x4	DRY	No.2	SPF	
E - F	2x4	DRY	No.2	SPF	
G - B	2x4	DRY	No.2	SPF	
H - E	2x4	DRY	No.2	SPF	
I - G	2x4	DRY	No.2	SPF	
J - G	2x4	DRY	No.2	SPF	
ALL WEBS EXCEPT	2x3	DRY	No.2	SPF	

DRY: SEASONED LUMBER.

PLATES (table in inches)

JT TYPE	PLATES	W	LEN	Y	X
B	TMVW+p	MT20	4.0	4.0	1.00 2.00
C	TTWW+m	MT20	5.0	6.0	2.25 1.50
D	TTW-m	MT20	4.0	4.0	
E	TMVW+p	MT20	4.0	4.0	1.00 2.00
G	BMV1+p	MT20	3.0	4.0	
H	BMVWW-1	MT20	4.0	9.0	
I	BS-1	MT20	3.0	6.0	
J	BMVWW-1	MT20	4.0	4.0	
K	BMV1+p	MT20	3.0	4.0	

DIMENSIONS, SUPPORTS AND LOADINGS SPECIFIED BY FABRICATOR TO BE VERIFIED BY BUILDING DESIGNER

BEARINGS

	FACTORED GROSS REACTION	MAXIMUM FACTORED GROSS REACTION	INPUT BRG	REQD BRG
JT	VERT	HORZ	DOWN	HORZ
K	1041	0	1041	0
G	1041	0	1041	0

A SUITABLE HANGER/MECHANICAL CONNECTION IS REQUIRED AT JOINT G. MINIMUM BEARING LENGTH AT JOINT G = 3-8.

UNFACTORED REACTIONS

JT	1ST LCASE	MAX/MIN COMPONENT REACTIONS	SNOW	LIVE	PERM. LIVE	WIND	DEAD	SOIL
K	734	495 / 0	0 / 0	0 / 0	0 / 0	0 / 0	239 / 0	0 / 0
G	734	495 / 0	0 / 0	0 / 0	0 / 0	0 / 0	239 / 0	0 / 0

BEARING MATERIAL TO BE SPF NO.2 OR BETTER AT JOINT(S) K

BRACING

TOP CHORD TO BE SHEATHED OR MAX. PURLIN SPACING = 6.25 FT.
MAX. UNBRACED BOTTOM CHORD LENGTH = 10.00 FT OR RIGID CEILING DIRECTLY APPLIED.

ALL PITCH BREAKS AND PERIMETER CORNER JOINTS MUST BE Laterally RESTRAINED.

1 LATERAL BRACE(S) AT 1/2 LENGTH OF C-H.

END VERTICAL(S) MUST BE SHEATHED OR HAVE BRACES AS INDICATED IN THE MAX. UNBRACED LENGTH COLUMN OF THE TABLE BELOW

LOADING

TOTAL LOAD CASES: (4)

MEMB.	CHORDS	MAX. FACTORED FORCE (LBS)	FACTORED VERT. LOAD (PLF)	LC1 MAX	CS1 (LC)	UNBRAC LENGTH FR-TO	MEMB.	WEBS	MAX. FACTORED FORCE (LBS)	MAX CS1 (LC)
FR-TO			FROM	TO			FR-TO			
A-B	0 / 41	-91.8	-91.8	0.13 (1)	10.00	J-C	-115 / 46	0.12 (1)		
B-C	-618 / 0	-91.8	-91.8	0.35 (1)	8.25	C-H	0 / 0	0.00 (1)		
C-D	-473 / 0	-91.8	-91.8	0.39 (1)	8.25	H-D	-115 / 46	0.12 (1)		
D-E	-618 / 0	-91.8	-91.8	0.35 (1)	8.25	B-J	0 / 528	0.12 (1)		
E-F	0 / 41	-91.8	-91.8	0.13 (1)	10.00	H-E	0 / 528	0.12 (1)		
K-B	-1000 / 0	0.0	0.0	0.16 (1)	7.81					
G-E	-1000 / 0	0.0	0.0	0.16 (1)	7.81					
K-J	0 / 0	-18.5	-18.5	0.13 (4)	10.00					
J-I	0 / 473	-18.5	-18.5	0.17 (4)	10.00					
I-H	0 / 473	-18.5	-18.5	0.17 (4)	10.00					
H-G	0 / 0	-18.5	-18.5	0.13 (4)	10.00					

DESIGN CRITERIA

SPECIFIED LOADS:
TOP CH. LL = 25.6 PSF
DL = 6.0 PSF
BOT CH. LL = 0.0 PSF
DL = 7.4 PSF
TOTAL LOAD = 39.0 PSF

SPACING = 24.0 IN. C/C

LOADING IN FLAT SECTION BASED ON A SLOPE OF 6.00/12

THIS TRUSS IS DESIGNED FOR RESIDENTIAL OR SMALL BUILDING REQUIREMENTS OF PART 9, NBC 2010, NBC 2015

THIS DESIGN COMPLIES WITH:
- PART 9 OF NBC 2018, OBC 2012, ABC 2019
- PART 9 OF OBC 2012 (2018 AMENDMENT)
- CSA 088-09, CSA 088-14
- TPIC 2011, TPIC 2014

(55 % OF 31.3 P.S.F. G.S.L. PLUS 8.4 P.S.F. RAIN LOAD) EQUALS 25.6 P.S.F. SPECIFIED ROOF LIVE LOAD

ALLOWABLE DEFL. (LL) = L/360 (0.55")
CALCULATED VERT. DEFL. (LL) = L/999 (0.01")
ALLOWABLE DEFL. (TL) = L/360 (0.55")
CALCULATED VERT. DEFL. (TL) = L/999 (0.03")

CSI: TC=0.39/1.00 (C-D:1), BC=0.17/1.00 (H-J:4), WB=0.12/1.00 (B-J:1), BS=0.21/1.00 (G-D:1)

DOL LUMBER=1.00 NAIL=1.00 LS BEND=1.10 COMP=1.10 SHEAR=1.10 TENS=1.10

COMPANION LIVE LOAD FACTOR = 1.00

TRUSS PLATE MANUFACTURER IS NOT RESPONSIBLE FOR QUALITY CONTROL IN THE TRUSS MANUFACTURING PLANT.

NAIL VALUES
PLATE GRIP (DRY) SHEAR SECTION (PSI) (PLI) (PLI)
MAX MIN MAX MIN MAX MIN
MT20 618 354 1667 788 1987 1667

PLATE PLACEMENT TOL. = 0.250 inches

PLATE ROTATION TOL. = 5.0 Deg.


JSI GRIP = 0.82 (B) (INPUT = 0.90)
JSI METAL = 0.23 (B) (INPUT = 1.00)



Structural component only
DWG# T-2007094

JOB NAME	TRUSS NAME	QUANTITY	PLY	JOB DESC.	DRWG NO.
408151	G33	1	1	GREEN PARK HOMES	
Tamarack Roof Truss, Burlington		TRUSS DESC.		Version 6.310 S Oct 29 2019 Mitek Industries, Inc. Sat Apr 25 11:19:30 2020 Page 1	

ID:h2dfiqC44wS_E2tzqPs_atzlfRw-LLOVhobzdl23nlsCEQP7Wb90nX9W01XJvONQKzNCXn



Scale = 1/32" = 1'-0"

LUMBER			
N. L. G. A. RULES	SIZE	DRY	LUMBER
CHORDS	2x4	DRY	No.2
L - B	2x4	DRY	No.2
A - D	2x4	DRY	No.2
D - G	2x4	DRY	No.2
H - F	2x4	DRY	No.2
L - H	2x4	DRY	No.2

ALL WEBS	2x3	DRY	No.2
ALL GABLE WEBS	2x3	DRY	No.2
DRY: SEASONED LUMBER.			

GABLE STUDS SPACED AT 2'-0" OC.

PLATES (table in inches)				
JT TYPE	PLATES	W	LEN	Y X
B TMVW+p	MT20	4.0	4.0	1.00 2.00
C TMVW+w	MT20	2.0	4.0	
D TTW+p	MT20	4.0	8.0	Edge
E TMVW+w	MT20	2.0	4.0	
F TMVW+p	MT20	4.0	4.0	1.00 2.00
H BMV1+p	MT20	3.0	4.0	
I BMVW1-t	MT20	4.0	4.0	
J BMVW1+w	MT20	2.0	4.0	
K BMVW1-t	MT20	4.0	4.0	
L BMV1+p	MT20	3.0	4.0	

Edge - INDICATES REFERENCE CORNER OF PLATE TOUCHES EDGE OF CHORD.

DIMENSIONS, SUPPORTS AND LOADINGS SPECIFIED BY FABRICATOR TO BE VERIFIED BY BUILDING DESIGNER

BEARINGS

THIS TRUSS DESIGNED FOR CONTINUOUS BEARINGS.

THIS TRUSS REQUIRES RIGID SHEATHING ON EXPOSED FACE.

BEARING MATERIAL TO BE SPF NO.2 OR BETTER AT JOINT(S)

BRACING

TOP CHORD TO BE SHEATHED OR MAX. PURLIN SPACING = 8.25 FT.

MAX. UNBRACED BOTTOM CHORD LENGTH = 10.00 FT OR RIGID CEILING DIRECTLY APPLIED.

ALL PITCH BREAKS AND PERIMETER CORNER JOINTS MUST BE Laterally RESTRAINED.

LOADING

TOTAL LOAD CASES: (4)

CHORDS				WEBS			
MEMB.	MAX. FACTORED FORCE (LBS)	FACTORED VERT. LOAD (PLF)	MAX. UNBRACED LENGTH (FT)	MEMB.	MAX. FACTORED FORCE (LBS)	FACTORED VERT. LOAD (PLF)	MAX. UNBRACED LENGTH (FT)
FR-TO				FR-TO			
L-B	-231 / 0	0.0	0.02 (1)	J-D	-123 / 0	0.05 (1)	7.81
A-B	0 / 41	-91.8	-91.8 0.13 (1)	K-C	-236 / 0	0.05 (1)	10.00
B-C	-11 / 0	-91.8	-91.8 0.07 (1)	I-E	-236 / 0	0.05 (1)	6.25
C-D	-32 / 0	-91.8	-91.8 0.07 (1)	B-K	0 / 23	0.01 (1)	6.25
D-E	-32 / 0	-91.8	-91.8 0.07 (1)	I-F	0 / 23	0.01 (1)	6.25
E-F	-11 / 0	-91.8	-91.8 0.07 (1)				
F-G	0 / 41	-91.8	-91.8 0.13 (1)				
H-F	-231 / 0	0.0	0.02 (1)				
L-K	0 / 0	-18.5	-18.5 0.02 (4)				
K-J	0 / 13	-18.5	-18.5 0.02 (4)				
J-I	0 / 13	-18.5	-18.5 0.02 (4)				
I-H	0 / 0	-18.5	-18.5 0.02 (4)				

TOTAL WEIGHT = 42 lb

DESIGN CRITERIA

SPECIFIED LOADS:

TOP CH.	LL =	25.6	PSF
	DL =	8.0	PSF
BOT CH.	LL =	0.0	PSF
	DL =	7.4	PSF
TOTAL LOAD	=	39.0	PSF

SPACING = 24.0 IN. C/C

THIS TRUSS IS DESIGNED FOR RESIDENTIAL OR SMALL BUILDING REQUIREMENTS OF PART 9, NBCC 2010, NBCC 2015

THIS DESIGN COMPLIES WITH:

- PART 9 OF BCBC 2018, OBC 2012, ABC 2010
- PART 9 OF OBC 2012 (2018 AMENDMENT)
- CSA 086-09, CSA 086-14
- TPIC 2011, TPIC 2014

(55% OF 31.3 P.S.F. G.S.L. PLUS 8.4 P.S.F. RAIN LOAD) EQUALS 25.6 P.S.F. SPECIFIED ROOF LIVE LOAD

CSI: TC=0.13/1.00 (F-G:1), BC=0.02/1.00 (J-K:4), WB=0.05/1.00 (C-K:1), SS=0.08/1.00 (F-G:1)

DOL LUMBER=1.00 NAIL=1.00 LS BEND=1.10 COMP=1.10 SHEAR=1.10 TENS=1.10

COMPANION LIVE LOAD FACTOR = 1.00

TRUSS PLATE MANUFACTURER IS NOT RESPONSIBLE FOR QUALITY CONTROL IN THE TRUSS MANUFACTURING PLANT.

NAIL VALUES


PLATE GRIP (DRY)	SHEAR	SECTION
(PSI)	(PLI)	(PLI)
MAX MIN	MAX MIN	MAX MIN
MT20	518	354
	1667	788
	1987	1658

PLATE PLACEMENT TOL. = 0.250 inches

PLATE ROTATION TOL. = 5.0 Deg.


JSI GRIP = 0.18 (C) (INPUT = 0.80)

JSI METAL = 0.13 (C) (INPUT = 1.00)



Structural component only
DWG# T-2007078

JOB NAME	TRUSS NAME	QUANTITY	PLY	JOB DESC.	DRWG NO.
408151	T33X	1	1	GREEN PARK HOMES	
Tamarack Roof Truss, Burlington		TRUSS DESC.		Version 8.310 S Oct 29 2019 Mitek Industries, Inc. Sat Apr 25 11:19:59 2020 Page 1	



LUMBER			
N. L. G. A. RULES	CHORDS	SIZE	LUMBER
A - B	2x4	DRY	No.2
B - C	2x4	DRY	No.2
F - A	2x4	DRY	No.2
D - C	2x4	DRY	No.2
F - D	2x4	DRY	No.2
ALL WEBS	2x3	DRY	No.2
EXCEPT			

DRY: SEASONED LUMBER.

PLATES (table is in inches)

JT TYPE	PLATES	W	LEN	Y	X
A - B	TMVV+p	MT20	4.0	4.0	1.00 2.00
B - C	TTW+p	MT20	4.0	8.0	Edge
C - D	TMVV+p	MT20	4.0	4.0	1.00 2.00
D - E	BMV1+p	MT20	3.0	4.0	
E - F	BMV1+p	MT20	4.0	9.0	
F - D	BMV1+p	MT20	3.0	4.0	

Edge - INDICATES REFERENCE CORNER OF PLATE TOUCHES EDGE OF CHORD.

DIMENSIONS, SUPPORTS AND LOADINGS SPECIFIED BY FABRICATOR TO BE VERIFIED BY BUILDING DESIGNER

BEARINGS

	FACTORED	MAXIMUM FACTORED	INPUT	REQD
	GROSS REACTION	GROSS REACTION	BRG	BRG
JT	VERT	HORZ	DOWN	HORZ
F	498	0	498	0
D	498	0	498	0

UNFACTORED REACTIONS

JT	1ST CASE	MAX/MIN	COMPONENT REACTIONS	DEAD	SOIL
F	351	230 / 0	0 / 0	0 / 0	121 / 0
D	351	230 / 0	0 / 0	0 / 0	121 / 0

BEARING MATERIAL TO BE SPF NO.2 OR BETTER AT JOINT(S) F, D

BRACING

TOP CHORD TO BE SHEATHED OR MAX. PURLIN SPACING = 6.25 FT.
MAX. UNBRACED BOTTOM CHORD LENGTH = 10.00 FT. OR RIGID CEILING DIRECTLY APPLIED.

ALL PITCH BREAKS AND PERIMETER CORNER JOINTS MUST BE LATERALLY RESTRAINED.

LOADING

TOTAL LOAD CASES: (4)

CHORDS				WEBS			
MEMB.	MAX. FACTORED FORCE (LBS)	VERT. LOAD (PLF)	MAX. FACTORED UNBRACED LENGTH (FT)	MEMB.	MAX. FACTORED FORCE (LBS)	MAX. FACTORED UNBRACED LENGTH (FT)	
FR-TO				FR-TO			
A-B	-311 / 0	-91.8	-91.8 0.24 (1)	E-B	-14 / 72	0.03 (4)	
B-C	-311 / 0	-91.8	-91.8 0.24 (1)	A-E	0 / 246	0.06 (1)	
F-A	-464 / 0	0.0	0.0 0.05 (1)	E-C	0 / 246	0.06 (1)	
D-C	-464 / 0	0.0	0.0 0.05 (1)				
F-E	0 / 0	-18.5	-18.5 0.11 (4)				
E-D	0 / 0	-18.5	-18.5 0.11 (4)				

TOTAL WEIGHT = 37 lb

DESIGN CRITERIA

SPECIFIED LOADS:

TOP CH.	LL = 25.6	PSF
DL =	6.0	PSF
BOT CH.	LL = 0.0	PSF
DL =	7.4	PSF
TOTAL LOAD =	39.0	PSF

SPACING = 24.0 IN. O/C

THIS TRUSS IS DESIGNED FOR RESIDENTIAL OR SMALL BUILDING REQUIREMENTS OF PART 9, NBC 2010, NSCC 2015

THIS DESIGN COMPLIES WITH:

- PART 9 OF BCBC 2018, CBC 2012, ABC 2019
- PART 9 OF CBC 2012 (2019 AMENDMENT)
- CSA 088-09, CSA 088-14
- TPIC 2011, TPIC 2014

(55 % OF 31.3 P.S.F. G.S.L. PLUS 8.4 P.S.F. RAIN LOAD) EQUALS 25.6 P.S.F. SPECIFIED ROOF LIVE LOAD

ALLOWABLE DEFL. (LL) = $L/360$ (0.30")
CALCULATED VERT. DEFL. (LL) = $L/999$ (0.00")
ALLOWABLE DEFL. (TL) = $L/360$ (0.30")
CALCULATED VERT. DEFL. (TL) = $L/999$ (0.01")

CSI: $T_C=0.24/1.00$ (A-B:1), $B_C=0.11/1.00$ (E-F:4),
WB=0.06/1.00 (C-E:1), $S_S=0.12/1.00$ (A-B:1)

COL LUMBER=1.00 NAIL=1.00 LS BEND=1.10
COMP=1.10 SHEAR=1.10 TENS=1.10

COMPANION LIVE LOAD FACTOR = 1.00

TRUSS PLATE MANUFACTURER IS NOT RESPONSIBLE FOR QUALITY CONTROL IN THE TRUSS MANUFACTURING PLANT.

NAIL VALUES

PLATE	GRP(DRY)	SHEAR	SECTION
(PSI)	(PLI)	(PLI)	(PLI)
MAX	MIN	MAX	MIN
MT20	618	354	1687

PLATE PLACEMENT TOL. = 0.250 inches

PLATE ROTATION TOL. = 5.0 Deg.


JSI GRIP = 0.42 (A) (INPUT = 0.90)
JSI METAL = 0.12 (A) (INPUT = 1.00)



Structural component only
DWG# T-2007095

JOB NAME	TRUSS NAME	QUANTITY	PLY	JOB DESC.	DRWG NO.
408151	T34	2	1	GREEN PARK HOMES	
Tamarack Roof Truss, Burlington		TRUSS DESC.			

Version 8.310 S Oct 29 2019 MITek Industries, Inc. Sat Apr 26 11:20:00 2020 Page 1
ID:h2dlfgC44wS_E2tqzPa_atzllRw-mBc3uRx8GmODTrpNfRn5kkQXdrLiC2aUv0ER7azNCXT



Scale = 1/8" = 1'-0"

LUMBER	CHORDS	SIZE	DRY	LUMBER	DESCR.
N. L. G. A. RULES					
A - B	2x4	DRY	No.2	SPF	
B - C	2x4	DRY	No.2	SPF	
D - C	2x4	DRY	No.2	SPF	
F - D	2x4	DRY	No.2	SPF	
F - E	2x4	DRY	No.2	SPF	

ALL WEBS 2x3 DRY No.2 SPF

DRY: SEASONED LUMBER.

PLATES (tablets in inches)	JT TYPE	PLATES	W	LEN	Y	X
A - B	TMVW+p	MT20	4.0	4.0	1.00	2.00
B - C	TTW+p	MT20	4.0	6.0	Edge	
C - D	TMVW+p	MT20	4.0	4.0	1.00	2.00
D - E	BMV1+p	MT20	3.0	4.0		
E - F	BMV1+p	MT20	4.0	9.0		
F - D	BMV1+p	MT20	3.0	4.0		

Edge - INDICATES REFERENCE CORNER OF PLATE TOUCHES EDGE OF CHORD.

DIMENSIONS, SUPPORTS AND LOADINGS SPECIFIED BY FABRICATOR TO BE VERIFIED BY BUILDING DESIGNER

BEARINGS	FACTORED	MAXIMUM FACTORED	INPUT	REQD
	GROSS REACTION	GROSS REACTION	BRG	BRG
JT	VERT	HORZ	DOWN	HORZ
F	469	0	489	0
D	469	0	489	0

A SUITABLE HANGER/MECHANICAL CONNECTION IS REQUIRED AT JOINT F, D. MINIMUM BEARING LENGTH AT JOINT F = 1-8, JOINT D = 1-8.

UNFACTORED REACTIONS

JT	1ST CASE	SNOW	LIVE	PERM.LIVE	WIND	DEAD	SOIL
F	331	217/0	0/0	0/0	0/0	114/0	0/0
D	331	217/0	0/0	0/0	0/0	114/0	0/0

BRACING

TOP CHORD TO BE SHEATHED OR MAX. PURLIN SPACING = 6.25 FT.
MAX. UNBRACED BOTTOM CHORD LENGTH = 10.00 FT. OR RIGID CEILING DIRECTLY APPLIED.
ALL PITCH BREAKS AND PERIMETER CORNER JOINTS MUST BE Laterally RESTRAINED.

LOADING

TOTAL LOAD CASES: (4)

CHORDS	MEMB.	MAX. FACTORED FORCE (LBS)	FACTORED VERT. LOAD (PLF)	MAX. FACTORED VERT. LOAD (LC)	MAX. FACTORED VERT. LOAD (LC)	MAX. FACTORED VERT. LOAD (LC)	MAX. FACTORED VERT. LOAD (LC)	MAX. FACTORED VERT. LOAD (LC)	MAX. FACTORED VERT. LOAD (LC)
FR-TO									
A-B	-218/0	-91.8	-91.8	0.21 (1)	6.25	E-B	-111/32	0.07 (1)	
B-C	-218/0	-91.8	-91.8	0.21 (1)	6.25	A-E	0/197	0.04 (1)	
F-A	-438/0	0.0	0.0	0.07 (1)	7.81	E-C	0/197	0.04 (1)	
D-C	-438/0	0.0	0.0	0.07 (1)	7.81				
F-E	0/0	-18.5	-18.5	0.09 (4)	10.00				
E-D	0/0	-18.5	-18.5	0.09 (4)	10.00				

TOTAL WEIGHT = 2 X 41 = 82 K (M/F)

DESIGN CRITERIA

SPECIFIED LOADS:
TOP CH. LL = 25.8 PSF
DL = 6.0 PSF
BOT CH. LL = 0.0 PSF
DL = 7.4 PSF
TOTAL LOAD = 39.0 PSF

SPACING = 24.0 IN. C/G

THIS TRUSS IS DESIGNED FOR RESIDENTIAL OR SMALL BUILDING REQUIREMENTS OF PART 9, NBC 2010, NSCC 2018

THIS DESIGN COMPLIES WITH:
- PART 9 OF NBC 2010, OBC 2012, ABC 2019
- PART 9 OF OBC 2012 (2019 AMENDMENT)
- CSA 086-09, CSA 086-14
- TPIC 2011, TPIC 2014

(55% OF 31.3 P.S.F. G.S.L. PLUS 8.4 P.S.F. RAIN LOAD) EQUALS 25.8 P.S.F. SPECIFIED ROOF LIVE LOAD

ALLOWABLE DEFL. (LL) = L/360 (0.28")
CALCULATED VERT. DEFL. (LL) = L/889 (0.00")
ALLOWABLE DEFL. (TL) = L/360 (0.28")
CALCULATED VERT. DEFL. (TL) = L/889 (0.01")

CS: TC=0.21/1.00 (A-B:1), BC=0.09/1.00 (E-F:4), WB=0.07/1.00 (B-E:1), SS=0.12/1.00 (A-B:1)

DOL LUMBER=1.00 NAIL=1.00 LS BEND=1.10
COMP=1.10 SHEAR=1.10 TENS=1.10

COMPANION LIVE LOAD FACTOR = 1.00

TRUSS PLATE MANUFACTURER IS NOT RESPONSIBLE FOR QUALITY CONTROL IN THE TRUSS MANUFACTURING PLANT.

NAIL VALUES
PLATE GRIP(DRY) SHEAR SECTION (PS) (PL) (PL)
MAX MIN MAX MIN MAX MIN
MT20 618 354 1687 789 1987 1656

PLATE PLACEMENT TOL. = 0.250 inches


PLATE ROTATION TOL. = 5.0 Deg.

JSI GRIP= 0.33 (A) (INPUT = 0.90)
JSI METAL= 0.09 (A) (INPUT = 1.00)



Structural component only
DWG# T-2007096

JOB NAME	TRUSS NAME	QUANTITY	PLY	JOB DESC.	DRWG NO.
408151	T35	2	2	GREEN PARK HOMES	
Tamarack Roof Truss, Burlington					
Version 8.310 S Oct 29 2019 MITek Industries, Inc. Sat Apr 25 11:20:01 2020 Page 1					
ID: h2d1lgC44wS_E2tzqPs_atzllRw-EO8R5nvm13W44?Ovw8IKTxzdFF_xTud8gz_f1zNCXS					



LUMBER			
N. L. G. A. RULES	CHORDS	SIZE	LUMBER
F - A	2x4	DRY	No.2
A - C	2x4	DRY	No.2
D - C	2x4	DRY	No.2
F - D	2x4	DRY	No.2
ALL WEBS 2x3 DRY No.2 SPF			
DRY: SEASONED LUMBER.			

DESIGN CONSISTS OF 2 TRUSSES BUILT SEPARATELY THEN FASTENED TOGETHER AS FOLLOWS:

CHORDS #ROWS	SURFACE SPACING (IN.)	LOAD (PLF)
TOP CHORDS : (0.122"x3") SPIRAL NAILS		
F - A	12	TOP
A - C	12	TOP
C - D	12	TOP
BOTTOM CHORDS : (0.122"x3") SPIRAL NAILS		
F - D	11	SIDE (97.1)
WEBS : (0.122"x3") SPIRAL NAILS		
B - E	6	SIDE (20.3)
2x3	6	

NAILS TO BE DRIVEN FROM ONE SIDE ONLY.

GIRDER NAILING ASSUMES NAILED HANGERS ARE FASTENED WITH MIN. 3-0 INCH NAILS.

TOP - COMPONENTS ARE LOADED FROM THE TOP AND MUST BE PLACED ON TOP EDGE OF ALL PLIES FOR THE LOAD TO BE TRANSFERRED TO EACH PLY.

SIDE - PLF SHOWN IS THE EQUIVALENT UDL APPLIED TO ONE SIDE THAT THE CORRESPONDING NAILING PATTERN SHALL BE CAPABLE OF TRANSFERING. REMAINING PLF MUST BE APPLIED ON THE OPPOSITE SIDE OR ON THE TOP.

PLATES (table is in inches)

JT TYPE	PLATES	W	LEN	Y	X
A TMVW-1	MT20	4.0	8.0		
B TMVW-1	MT20	2.0	4.0		
C TMVW-1	MT20	4.0	8.0		
D BMV1+p	MT20	3.0	4.0		
E BMVWW-1	MT20	4.0	9.0		

DIMENSIONS, SUPPORTS AND LOADINGS SPECIFIED BY FABRICATOR TO BE VERIFIED BY BUILDING DESIGNER.

BEARINGS

	FACTORED GROSS REACTION	MAXIMUM FACTORED GROSS REACTION	INPUT BRG	REQD BRG
JT VERT				
F	1018	0	1018	0
D	1085	0	1085	0

A SUITABLE HANGER/MECHANICAL CONNECTION IS REQUIRED AT JOINT D. MINIMUM BEARING LENGTH AT JOINT D = 1-8.

UNFACTORED REACTIONS

JT	1ST CASE	MAX/MIN. COMPONENT REACTIONS	SNOW	LIVE	PERM. LIVE	WIND	DEAD	SOIL
F	726	436/0	0/0	0/0	0/0	0/0	290/0	0/0
D	772	479/0	0/0	0/0	0/0	0/0	293/0	0/0

BEARING MATERIAL TO BE SPF NO.2 OR BETTER AT JOINT(S) F

BRACING

TOP CHORD TO BE SHEATHED OR MAX. PURLIN SPACING = 6.23 FT. MAX. UNBRACED BOTTOM CHORD LENGTH = 10.00 FT OR RIGID CEILING DIRECTLY APPLIED.

ALL PITCH BREAKS AND PERIMETER CORNER JOINTS MUST BE Laterally RESTRAINED.

LOADING

TOTAL LOAD CASES: (4)

CHORDS				WEBS			
MEMB.	MAX. FACTORED FORCE (LBS)	FACTORED VERT. LOAD (PLF)	MAX. FACTORED CSI (LC)	MEMB.	MAX. FACTORED FORCE (LBS)	MAX. FACTORED CSI (LC)	
FR-TO		FROM TO		FR-TO			
F - A	-865/0	0.0	0.0	0.05 (1)	7.81	A - E	0/1810
A - G	-1706/0	-91.8	-91.8	0.26 (1)	6.23	E - B	-482/0
G - B	-1706/0	-91.8	-91.8	0.26 (1)	6.23	E - C	0/1810
B - C	-1706/0	-91.8	-91.8	0.08 (1)	6.25		
D - C	-707/0	0.0	0.0	0.04 (1)	7.81		
F - E	0/0	-43.5	-43.5	0.05 (1)	10.00		
E - H	0/0	-43.5	-43.5	0.22 (1)	10.00		
H - D	0/0	-43.5	-43.5	0.22 (1)	10.00		

FACTORED CONCENTRATED LOADS (LBS)

JT	LOC.	LC1	MAX-	MAX+	FACE	DIR.	TYPE	HEEL	CONN.
E	3-0-12	-450	-450	---	FRONT	VERT	TOTAL	---	C1
G	1-0-12	-404	-404	---	TOP	VERT	TOTAL	---	C1
H	5-0-12	-452	-452	---	FRONT	VERT	TOTAL	---	C1

CONNECTION REQUIREMENTS

1) C1: A SUITABLE HANGER/MECHANICAL CONNECTION IS REQUIRED.

TOTAL WEIGHT = 4 X 20 = 80 LB

DESIGN CRITERIA

*** SPECIAL LOADS ANALYSIS ***
GEOMETRY AND/OR BASIC LOADS CHANGED BY USER.
LOADS WERE DERIVED FROM USER INPUT
NO FURTHER MODIFICATIONS WERE MADE

SPECIFIED LOADS:

TOP CH.	LL	=	25.8	PSF
DL	=	8.0	PSF	
BOT CH.	LL	=	0.0	PSF
DL	=	7.4	PSF	
TOTAL LOAD	=	39.0	PSF	

SPACING = 24.0 IN. C/C

LOADING IN FLAT SECTION BASED ON A SLOPE OF 8.00/12

*** NON STANDARD GIRDER ***
ADDTL USER-DEFINED LOADS APPLIED TO ALL LOAD CASES.

THIS TRUSS IS DESIGNED FOR RESIDENTIAL OR SMALL BUILDING REQUIREMENTS OF PART 9, NBCC 2010, NBCC 2015

THIS DESIGN COMPLIES WITH:
- PART 9 OF NBCC 2010, NBC 2012, ABC 2019
- PART 9 OF NBC 2012 (2019 AMENDMENT)
- CSA 089-09, CSA 088-14
- TPIC 2011, TPIC 2014

(55 % OF 31.3 P.S.F. G.S.L. PLUS 8.4 P.S.F. RAIN LOAD) EQUALS 25.8 P.S.F. SPECIFIED ROOF LIVE LOAD

ALLOWABLE DEFL. (LL) = $\frac{1}{980}$ (0.20")
CALCULATED VERT. DEFL. (LL) = $\frac{1}{989}$ (0.02")
ALLOWABLE DEFL. (TL) = $\frac{1}{380}$ (0.26")
CALCULATED VERT. DEFL. (TL) = $\frac{1}{989}$ (0.03")

CSI: TC=0.28/1.00 (A-B:1), BC=0.22/1.00 (D-E:1), WB=0.22/1.00 (A-E:1), GS=0.18/1.00 (D-E:1)

DOL LUMBER=1.00 NAIL=1.00 LS BEND=1.00
COMP=1.00 SHEAR=1.00 TENS=1.00

COMPANION LIVE LOAD FACTOR = 1.00


TRUSS PLATE MANUFACTURER IS NOT RESPONSIBLE FOR QUALITY CONTROL IN THE TRUSS MANUFACTURING PLANT

NAIL VALUES	PLATE GRIP (DRY)	SHEAR (PSI)	SECTION (PLI)
	MAX	MIN	MAX
MT20	818	354	1867

PLATE PLACEMENT TOL. = 0.250 inches

PLATE ROTATION TOL. = 5.0 Deg.

JSI GRIP = 0.59 (C) INPUT = 0.90
JSI METAL = 0.21 (C) INPUT = 1.00



Structural component only
DWG# T-2007097 1/2


CONTINUED ON PAGE 2

JOB NAME	TRUSS NAME	QUANTITY	PLY	JOB DESC.	DRWG NO.
408151	T35	2	2	GREEN PARK HOMES	
Tamarack Roof Truss, Burlington		TRUSS DESC.			

PLATES (table is in inches)

JT	TYPE	PLATES	W	LEN	Y	X
F	BMV1+p	MT20	3.0	4.0		

Version 8.310 S Oct 29 2019 Mittek Industries, Inc. Sat Apr 25 11:20:01 2020 Page 2
ID:h2dflqC44wS E2IzqPs atzIIIRw-EQ9R5nym13W44?Ovw8jKTzhdFf xTUd8gz fIzNCKS




Structural component only
DWG# T-2007097 342

JOB NAME	TRUSS NAME	QUANTITY	PLY	JOB DESC.	DRWG NO.
408151	G36	1	1	GREEN PARK HOMES	

Tamarack Roof Truss, Burlington

Version 8.310 S Oct 29 2019 Mtek Industries, Inc. Sat Apr 26 11:19:41 2020 Page 1
ID:h2dlgC44wS_E2bzqPs_alzllRw-pXyivxjDkw7vhwa3lxxelk8KIBIVFSmhYZ7xyBzNCXm



Scale = 1/32

N. L. G. A. RULES	CHORDS	SIZE	LUMBER
P - B	2x4	DRY	No.2
A - E	2x4	DRY	No.2
E - I	2x4	DRY	No.2
J - H	2x4	DRY	No.2
P - J	2x4	DRY	No.2

ALL WEBS 2x3 DRY No.2
ALL GABLE WEBS 2x3 DRY No.2
DRY: SEASONED LUMBER.

GABLE STUDS SPACED AT 2-0-0 OC.

PLATES (table in inches)

JT TYPE	PLATES	W	LEN	Y	X
B TMVW+p	MT20	4.0	4.0	1.00	2.00
C, D, F, G					
C TMVW+w	MT20	2.0	4.0		
E TTW+p	MT20	4.0	8.0	Edge	
H TMVW+p	MT20	4.0	4.0	1.00	2.00
J BMV1+p	MT20	3.0	4.0		
K BMVW1-i	MT20	4.0	4.0		
L, M, N					
L BMV1+w	MT20	2.0	4.0		
O BMVW1-i	MT20	4.0	4.0		
P BMV1+p	MT20	3.0	4.0		

Edge - INDICATES REFERENCE CORNER OF PLATE TOUCHES EDGE OF CHORD.

DIMENSIONS, SUPPORTS AND LOADINGS SPECIFIED BY FABRICATOR TO BE VERIFIED BY BUILDING DESIGNER

BEARINGS

THIS TRUSS DESIGNED FOR CONTINUOUS BEARINGS.

THIS TRUSS REQUIRES RIGID SHEATHING ON EXPOSED FACE.

BEARING MATERIAL TO BE SPF NO.2 OR BETTER AT JOINT(S)

BRACING

TOP CHORD TO BE SHEATHED OR MAX. PURLIN SPACING = 8.25 FT.

MAX. UNBRACED BOTTOM CHORD LENGTH = 10.00 FT. OR RIGID CEILING DIRECTLY APPLIED.

ALL PITCH BREAKS AND PERIMETER CORNER JOINTS MUST BE Laterally RESTRAINED.

LOADING

TOTAL LOAD CASES: (4)

CHORDS	MEMB.	MAX. FACTORED FORCE (LBS)	VERT. LOAD (PLF)	LC1 MAX	LC2 MAX	UNBRAC LENGTH	FR-TO	WEBS	MEMB.	MAX. FACTORED FORCE (LBS)	MAX. CSI (LC)
P-B	-274/0	0.0	0.0	0.03 (1)	7.81	M-E	-139/0	0.08 (1)			
A-B	0/41	-91.8	-91.8	0.12 (1)	10.00	N-D	-223/0	0.07 (1)			
B-C	-57/0	-91.8	-91.8	0.12 (1)	8.25	O-C	-75/0	0.01 (1)			
C-D	-4/0	-91.8	-91.8	0.08 (1)	10.00	L-F	-223/0	0.07 (1)			
D-E	-22/0	-91.8	-91.8	0.08 (1)	8.25	K-G	-75/0	0.01 (1)			
E-F	-22/0	-91.8	-91.8	0.08 (1)	8.25	B-O	0/20	0.00 (1)			
F-G	-4/0	-91.8	-91.8	0.08 (1)	10.00	K-H	0/20	0.00 (1)			
G-H	-57/0	-91.8	-91.8	0.12 (1)	10.00						
H-I	0/41	-91.8	-91.8	0.12 (1)	10.00						
J-H	-274/0	0.0	0.0	0.03 (1)	7.81						
P-O	0/0	-18.5	-18.5	0.01 (4)	10.00						
O-N	0/12	-18.5	-18.5	0.02 (4)	10.00						
N-M	0/7	-18.5	-18.5	0.02 (4)	10.00						
M-L	0/7	-18.5	-18.5	0.02 (4)	10.00						
L-K	0/12	-18.5	-18.5	0.02 (4)	10.00						
K-J	0/0	-18.5	-18.5	0.01 (4)	10.00						

TOTAL WEIGHT = 53.6 kN

DESIGN CRITERIA

SPECIFIED LOADS:

TOP CH.	LL	=	25.8	PSF
	DL	=	6.0	PSF
BOT CH.	LL	=	0.0	PSF
	DL	=	7.4	PSF
TOTAL LOAD		=	39.0	PSF

SPACING = 24.0 IN. O.C.

THIS TRUSS IS DESIGNED FOR RESIDENTIAL OR SMALL BUILDING REQUIREMENTS OF PART 9, NBCC 2010, NBCC 2016

THIS DESIGN COMPLIES WITH:

- PART 9 OF BCBC 2018, CBC 2012, ABC 2019
- PART 9 OF CBC 2012 (2018 AMENDMENT)
- CSA 086-09, CSA 086-14
- TPIC 2011, TPIC 2014

DESIGN ASSUMPTIONS

- OVERHANG NOT TO BE ALTERED OR CUT OFF.

(55 % OF 31.3 P.S.F. G.S.L. PLUS 8.4 P.S.F. RAIN LOAD) EQUALS 25.8 P.S.F. SPECIFIED ROOF LIVE LOAD

CSI: TC=0.13/1.00 (H-K), BC=0.02/1.00 (K-L), WB=0.08/1.00 (E-M), SSI=0.08/1.00 (A-B)

DOL LUMBER=1.00 NAIL=1.00 LB BEND=1.10 COMP=1.10 SHEAR=1.10 TENS=1.10

COMPANION LIVE LOAD FACTOR = 1.00

TRUSS PLATE MANUFACTURER IS NOT RESPONSIBLE FOR QUALITY CONTROL IN THE TRUSS MANUFACTURING PLANT.

NAIL VALUES

PLATE GRIP (DRY)	SHEAR	SECTION
(PSI)	(PLI)	(PLI)
MAX MIN	MAX MIN	MAX MIN
MT20	618 354 1887 788 1987 1888	

PLATE PLACEMENT TOL. = 0.250 inches


PLATE ROTATION TOL. = 5.0 Deg.

JSI GRIP= 0.21 (B) (INPUT = 0.90)

JSI METAL= 0.12 (F) (INPUT = 1.00)



Structural component only
DWG# T-2007079



LUMBER

N. L. G. A. RULES

CHORDS	SIZE	DRY	LUMBER	DESCR.
A - C	2x4	DRY	No.2	SPF
C - F	2x6	DRY	No.2	SPF
F - H	2x6	DRY	No.2	SPF
H - J	2x4	DRY	No.2	SPF
T - B	2x6	DRY	No.2	SPF
K - I	2x6	DRY	No.2	SPF
T - Q	2x6	DRY	No.2	SPF
Q - N	2x6	DRY	No.2	SPF
N - K	2x6	DRY	No.2	SPF

ALL WEBS 2x3 DRY No.2 EXCEPT

DRY: SEASONED LUMBER.

DESIGN CONSISTS OF 2 TRUSSES BUILT SEPARATELY THEN FASTENED TOGETHER AS FOLLOWS:

CHORDS #ROWS	SURFACE SPACING (IN)	LOAD (PLF)
TOP CHORDS : (0.122"x3") SPIRAL NAILS		
A-C 1 12	SIDE(81.0)	
H-J 1 12	SIDE(81.0)	
C-F 2 12	SIDE(81.0)	
F-H 2 12	SIDE(81.0)	
T-B 2 12	TOP	
K-I 2 12	TOP	
BOTTOM CHORDS : (0.122"x3") SPIRAL NAILS		
T-Q 2 12	SIDE(183.1)	
Q-N 2 12	SIDE(0.0)	
N-K 2 12	SIDE(183.1)	
WEBS : (0.122"x3") SPIRAL NAILS		
2x3 1 6		

NAILS TO BE DRIVEN FROM ONE SIDE ONLY.

GIRDER NAILING ASSUMES NAILED HANGERS ARE FASTENED WITH MIN. 3-0 INCH NAILS.

TOP - COMPONENTS ARE LOADED FROM THE TOP AND MUST BE PLACED ON TOP EDGE OF ALL PLIES FOR THE LOAD TO BE TRANSFERRED TO EACH PLY.

DIMENSIONS, SUPPORTS AND LOADINGS SPECIFIED BY FABRICATOR TO BE VERIFIED BY BUILDING DESIGNER

BEARINGS

	FACTORED GROSS REACTION	MAXIMUM FACTORED GROSS REACTION	INPUT BRG	REQD BRG
JT	VERY	DOWN	IN-SX	IN-SX
T	3331 0	3331 0	5-8	5-8
K	3331 0	3331 0	5-8	5-8

UNFACTORED REACTIONS

1ST CASE	MAX/MIN COMPONENT REACTIONS	WIND	DEAD	SOIL
JT COMBINED	SNOW	LIVE	PERM.LIVE	
T	2358 1844 / 0	0 / 0	0 / 0	812 / 0
K	2358 1844 / 0	0 / 0	0 / 0	812 / 0

BEARING MATERIAL TO BE SPF NO.2 OR BETTER AT JOINT(S) T, K

BRACING
TOP CHORD TO BE SHEATHED OR MAX. PURLIN SPACING = 3.87 FT.
MAX. UNBRACED BOTTOM CHORD LENGTH = 10.00 FT OR RIGID CEILING DIRECTLY APPLIED.

ALL PITCH BREAKS AND PERIMETER CORNER JOINTS MUST BE Laterally RESTRAINED.

LOADING
TOTAL LOAD CASES: (4)

CHORDS				WEBS			
MEMB.	MAX. FACTORED FORCE (LBS)	FACTORED VERT. LOAD (LBS)	MAX. FACTORED CSI (LC)	MEMB.	MAX. FACTORED FORCE (LBS)	MAX. FACTORED CSI (LC)	
FR-TO				FR-TO			
A-B	0 / 28	-91.8	-91.8 0.07 (1)	S-C	-427 / 8	0.05 (1)	
B-C	-5077 / 0	-91.8	-91.8 0.52 (1)	C-R	0 / 3083	0.38 (1)	
C-U	-7108 / 0	-91.8	-91.8 0.23 (1)	R-D	-1565 / 0	0.19 (1)	
U-V	-7108 / 0	-91.8	-91.8 0.23 (1)	Q-G	0 / 1071	0.13 (1)	
V-D	-7108 / 0	-91.8	-91.8 0.23 (1)	M-G	-1565 / 0	0.19 (1)	
D-W	-7894 / 0	-91.8	-91.8 0.27 (1)	L-H	-427 / 8	0.05 (1)	
W-X	-7894 / 0	-91.8	-91.8 0.27 (1)	B-S	0 / 4592	0.57 (1)	
X-Y	-7894 / 0	-91.8	-91.8 0.27 (1)	L-I	0 / 4592	0.57 (1)	
Y-E	-7894 / 0	-91.8	-91.8 0.27 (1)	D-P	0 / 1071	0.13 (1)	
E-Z	-7894 / 0	-91.8	-91.8 0.27 (1)	M-H	0 / 3083	0.38 (1)	
Z-F	-7894 / 0	-91.8	-91.8 0.27 (1)	P-E	-505 / 0	0.06 (1)	
F-AA	-7894 / 0	-91.8	-91.8 0.27 (1)	E-O	-505 / 0	0.06 (1)	
AA-AB	-7894 / 0	-91.8	-91.8 0.27 (1)				
AB-G	-7894 / 0	-91.8	-91.8 0.27 (1)				
G-AC	-7108 / 0	-91.8	-91.8 0.23 (1)				
AC-AD	-7108 / 0	-91.8	-91.8 0.23 (1)				
AD-H	-7108 / 0	-91.8	-91.8 0.23 (1)				
H-I	-5077 / 0	-91.8	-91.8 0.52 (1)				
I-J	0 / 28	-91.8	-91.8 0.07 (1)				
T-B	-3255 / 0	0.0	0.0 0.11 (1)				
K-I	-3255 / 0	0.0	0.0 0.11 (1)				

DESIGN CRITERIA

SPECIFIED LOADS:
TOP CH. LL = 25.6 PSF
DL = 8.0 PSF
BOT CH. LL = 0.0 PSF
DL = 7.4 PSF
TOTAL LOAD = 39.0 PSF

SPACING = 24.0 IN. C/C

LOADING IN FLAT SECTION BASED ON A SLOPE OF 6.00/12

THIS TRUSS IS DESIGNED FOR RESIDENTIAL OR SMALL BUILDING REQUIREMENTS OF PART 9, NBC 2010, NBC 2015

THIS DESIGN COMPLIES WITH:
PART 9 OF NBC 2010, OBC 2012, ABC 2019
PART 9 OF OBC 2012 (2019 AMENDMENT)
CSA 088-09, CSA 088-14
TPIC 2011, TPIC 2014

(55% OF 31.3 P.S.F. G.S.L. PLUS 8.4 P.S.F. RAIN LOAD) EQUALS 25.6 P.S.F. SPECIFIED ROOF LIVE LOAD

ALLOWABLE DEFL.(LL) = L/380 (1.17")
CALCULATED VERT. DEFL.(LL) = L/989 (0.21")
ALLOWABLE DEFL.(TL) = L/380 (1.17")
CALCULATED VERT. DEFL.(TL) = L/989 (0.39")

CSI: TC=0.82/1.00 (H-I), BC=0.68/1.00 (O-P), WB=0.57/1.00 (B-S), SSI=0.16/1.00 (D-E)

DOL LUMBER=1.00 NAIL=1.00 LS BEND=1.00 COMP=1.00 SHEAR=1.00 TENS=1.00

COMPANION LIVE LOAD FACTOR = 1.00

AUTOSOLVE HEELS OFF


TRUSS PLATE MANUFACTURER IS NOT RESPONSIBLE FOR QUALITY CONTROL IN THE TRUSS MANUFACTURING PLANT.

NAIL VALUES
PLATE GRIP(DRY) SHEAR SECTION (PSI) (PLI) (PLI)
MAX MIN MAX MIN MAX MIN
MT20 618 354 1667 788 1987 1668

PLATE PLACEMENT TOL. = 0.250 inches

PLATE ROTATION TOL. = 5.0 Deg.

JSI GRIP = 0.84 (3) (INPUT = 0.90)
JSI METAL = 0.84 (N) (INPUT = 1.00)



Structural component only
DWG# T-2007107 1/2

JOB NAME	TRUSS NAME	QUANTITY	PLY	JOB DESC.	DRWG NO.
408152	T40	1	2	GREEN PARK HOMES	
Tamarack Roof Truss, Burlington		TRUSS DESC.			

Version 8.310 S Oct 29 2019 MITek Industries, Inc. Sat Apr 28 11:28:32 2020 Page 2
ID:7vF7aG0E03cRU6X1ISrkzWYK-0EAix1sXZWS34YeiZ2E6M6CTQSHDeTgR0niCOzNCOX

PLATES (table is in inches)

JT	TYPE	PLATES	W	LEN	Y	X
B	TMVW-t	MT20	5.0	8.0		
C	TTWW-m	MT20	5.0	8.0	Edge	
D, E, G						
D	TMVW-t	MT20	5.0	8.0		
F	TS-t	MT20	5.0	8.0		
H	TTWW-m	MT20	5.0	8.0	Edge	
I	TMVW-t	MT20	5.0	8.0		
K	BMV1-p	MT20	3.0	6.0		
L	BMVW-t	MT20	5.0	8.0	2.50	2.50
M, O, P, R						
M	BMVW-t	MT20	5.0	8.0		
N	BS-t	MT20	5.0	8.0		
Q	BS-t	MT20	5.0	8.0		
S	BMVW-t	MT20	5.0	8.0	2.50	2.50
T	BMV1-p	MT20	3.0	6.0		

Edge - INDICATES REFERENCE CORNER OF PLATE TOUCHES EDGE OF CHORD.

LOADING

TOTAL LOAD CASES: (4)


CHORDS				WEBS			
MEMB.	FORCE (LBS)	VERT. LOAD (LBS)	LC1 (PL)	MAX CS1 (LC)	MAX UNBRAC LENGTH	MEMB. FORCE (LBS)	MAX CS1 (LC)
FR-TO						FR-TO	
AQ-K	0:0			-18.5	-18.5 0.08 (4) 10.00		

FACTORED CONCENTRATED LOADS (LBS)

JT	LOC.	LC1	MAX-	MAX+	FACE	DIR.	TYPE	HEGL	CONN.
C	5-10-8	-438	-438	---	FRONT	VERT	TOTAL	---	C1
E	17-7-0	-110	-110	---	FRONT	VERT	TOTAL	---	C1
H	29-3-8	-438	-438	---	FRONT	VERT	TOTAL	---	C1
L	29-2-12	-28	-28	---	FRONT	VERT	TOTAL	---	C1
N	23-2-12	-28	-28	---	FRONT	VERT	TOTAL	---	C1
Q	11-11-4	-28	-28	---	FRONT	VERT	TOTAL	---	C1
S	5-11-4	-28	-28	---	FRONT	VERT	TOTAL	---	C1
U	7-11-4	-110	-110	---	FRONT	VERT	TOTAL	---	C1
V	9-11-4	-110	-110	---	FRONT	VERT	TOTAL	---	C1
W	11-11-4	-110	-110	---	FRONT	VERT	TOTAL	---	C1
X	13-11-4	-110	-110	---	FRONT	VERT	TOTAL	---	C1
Y	15-11-4	-110	-110	---	FRONT	VERT	TOTAL	---	C1
Z	19-2-12	-110	-110	---	FRONT	VERT	TOTAL	---	C1
AA	21-2-12	-110	-110	---	FRONT	VERT	TOTAL	---	C1
AB	23-2-12	-110	-110	---	FRONT	VERT	TOTAL	---	C1
AC	25-2-12	-110	-110	---	FRONT	VERT	TOTAL	---	C1
AD	27-2-12	-110	-110	---	FRONT	VERT	TOTAL	---	C1
AE	1-11-4	-28	-28	---	FRONT	VERT	TOTAL	---	C1
AF	3-11-4	-28	-28	---	FRONT	VERT	TOTAL	---	C1
AG	7-11-4	-28	-28	---	FRONT	VERT	TOTAL	---	C1
AH	9-11-4	-28	-28	---	FRONT	VERT	TOTAL	---	C1
AI	13-11-4	-28	-28	---	FRONT	VERT	TOTAL	---	C1
AJ	15-11-4	-28	-28	---	FRONT	VERT	TOTAL	---	C1
AK	17-7-0	-28	-28	---	FRONT	VERT	TOTAL	---	C1
AL	19-2-12	-28	-28	---	FRONT	VERT	TOTAL	---	C1
AM	21-2-12	-28	-28	---	FRONT	VERT	TOTAL	---	C1
AN	23-2-12	-28	-28	---	FRONT	VERT	TOTAL	---	C1
AO	25-2-12	-28	-28	---	FRONT	VERT	TOTAL	---	C1
AP	27-2-12	-28	-28	---	FRONT	VERT	TOTAL	---	C1
AQ	31-2-12	-28	-28	---	FRONT	VERT	TOTAL	---	C1
AQ	33-2-12	-28	-28	---	FRONT	VERT	TOTAL	---	C1

CONNECTION REQUIREMENTS

- 1) C1: A SUITABLE HANGER/MECHANICAL CONNECTION IS REQUIRED.




Structural component only
DWG# T-2007107 3/2

JOB NAME	TRUSS NAME	QUANTITY	PLY	JOB DESC.	TRUSS DESC.	DRWG NO.
408152	T40Z	1	2	GREEN PARK HOMES		

Tamarack Roof Truss, Burlington

Version 8.310 S Oct 29 2019 Mitek Industries, Inc. Sat Apr 25 11:29:34 2020 Page 1
ID:7vF7aG0E03cRUj6X1jSrksWYK-ydH2MluB57imK31?_4CnCV7E2GhUJzKGPjGJzNCOV



CHORDS	SIZE	DRY	LUMBER	DESCR.
A - C	2x4	DRY	No.2	SPF
C - F	2x6	DRY	No.2	SPF
F - H	2x6	DRY	No.2	SPF
H - J	2x4	DRY	No.2	SPF
J - B	2x4	DRY	No.2	SPF
K - I	2x6	DRY	No.2	SPF
T - Q	2x6	DRY	No.2	SPF
Q - N	2x6	DRY	No.2	SPF
N - K	2x6	DRY	No.2	SPF

ALL WEBS 2x3 DRY No.2 SPF
EXCEPT

DRY: SEASONED LUMBER.

DESIGN CONSISTS OF 2 TRUSSES BUILT SEPARATELY THEN FASTENED TOGETHER AS FOLLOWS:

CHORDS #ROWS	SURFACE SPACING (IN)	LOAD (PLF)
TOP CHORDS: (0.122"x3") SPIRAL NAILS		
A-C 1 12		SIDE(81.0)
H-J 1 12		TOP
C-F 2 12		SIDE(81.0)
F-H 2 12		TOP
T-B 2 12		TOP
K-I 2 12		TOP
BOTTOM CHORDS: (0.122"x3") SPIRAL NAILS		
T-Q 2 12		SIDE(183.1)
Q-N 2 12		SIDE(0.0)
N-K 2 12		TOP
WEBS: (0.122"x3") SPIRAL NAILS		
2x3 1 6		

NAILS TO BE DRIVEN FROM ONE SIDE ONLY.

GIRDER NAILING ASSUMES NAILED HANGERS ARE FASTENED WITH MIN. 3-0 INCH NAILS.

TOP - COMPONENTS ARE LOADED FROM THE TOP AND MUST BE PLACED ON TOP EDGE OF ALL PLIES FOR THE LOAD TO BE TRANSFERRED TO EACH PLY.

DIMENSIONS, SUPPORTS AND LOADINGS SPECIFIED BY FABRICATOR TO BE VERIFIED BY BUILDING DESIGNER

BEARINGS	FACTORED GROSS REACTION	MAXIMUM FACTORED GROSS REACTION	INPUT BRG	REQD BRG
JT	VERT 4474	DOWN 4474	0	5-8
T	HORZ 0	HORZ 0	0	5-8
K	VERT 3775	DOWN 3775	0	5-8

UNFACTORED REACTIONS

1ST LOAGE	MAX MIN COMPONENT REACTIONS
JT	COMBINED SNOW LIVE PERM.LIVE WIND DEAD SOIL
T	3182 2088 / 0 0 / 0 0 / 0 1073 / 0 0 / 0
K	2885 1772 / 0 0 / 0 0 / 0 893 / 0 0 / 0

BEARING MATERIAL TO BE SPF NO.2 OR BETTER AT JOINT(S) T, K

BRACING

TOP CHORD TO BE SHEATHED OR MAX. PURLIN SPACING = 3.19 FT.
MAX. UNBRACED BOTTOM CHORD LENGTH = 10.00 FT OR RIGID CEILING DIRECTLY APPLIED.

ALL PITCH BREAKS AND PERIMETER CORNER JOINTS MUST BE LATERALLY RESTRAINED.

LOADING

TOTAL LOAD CASES: (4)

CHORDS	MAX. FACTORED MEMB. FORCE (LBS)	FACTORED VERT. LOAD (PLF)	MAX. FACTORED CSI (LC)	WEBS	MAX. FACTORED MEMB. FORCE (LBS)	MAX. FACTORED CSI (LC)
FR-TO		FROM TO		FR-TO		
A-B	0 / 28	-91.8 -91.8 0.07 (1)	10.00	S-C	-384 / 25	0.05 (1)
B-C	-7163 / 0	-91.8 -91.8 0.71 (1)	3.19	C-R	0 / 4887	0.59 (1)
C-U	-10289 / 0	-91.8 -91.8 0.32 (1)	3.62	R-D	-2057 / 0	0.25 (1)
U-V	-10289 / 0	-91.8 -91.8 0.32 (1)	3.62	O-G	0 / 3611	0.45 (1)
V-D	-10289 / 0	-91.8 -91.8 0.32 (1)	3.62	M-G	-2637 / 0	0.32 (1)
D-W	-12012 / 0	-91.8 -91.8 0.45 (1)	3.27	L-H	-916 / 0	0.08 (1)
W-X	-12012 / 0	-91.8 -91.8 0.45 (1)	3.27	B-S	0 / 8479	0.80 (1)
X-Y	-12012 / 0	-91.8 -91.8 0.45 (1)	3.27	L-I	0 / 5333	0.88 (1)
Y-E	-12012 / 0	-91.8 -91.8 0.45 (1)	3.27	D-P	0 / 2088	0.28 (1)
E-F	-12381 / 0	-91.8 -91.8 0.40 (1)	3.28	M-H	0 / 4950	0.61 (1)
F-G	-12381 / 0	-91.8 -91.8 0.40 (1)	3.28	P-E	-1110 / 0	0.14 (1)
G-H	-9388 / 0	-91.8 -91.8 0.25 (1)	3.84	E-O	0 / 383	0.05 (1)
H-I	-5888 / 0	-91.8 -91.8 0.59 (1)	3.58			
I-J	0 / 28	-91.8 -91.8 0.07 (1)	10.00			
T-B	-4430 / 0	0.0 0.0 0.16 (1)	6.82			
K-I	-3718 / 0	0.0 0.0 0.13 (1)	7.31			

CHORDS	MAX. FACTORED MEMB. FORCE (LBS)	FACTORED VERT. LOAD (PLF)	MAX. FACTORED CSI (LC)	WEBS	MAX. FACTORED MEMB. FORCE (LBS)	MAX. FACTORED CSI (LC)
FR-TO		FROM TO		FR-TO		
T-Z	0 / 0	-18.5 -18.5 0.08 (4)	10.00			
Z-AA	0 / 0	-18.5 -18.5 0.08 (4)	10.00			
AA-S	0 / 0	-18.5 -18.5 0.08 (4)	10.00			
S-AB	0 / 8432	-18.5 -18.5 0.69 (1)	10.00			
AB-AC	0 / 8432	-18.5 -18.5 0.69 (1)	10.00			
AC-AD	0 / 8432	-18.5 -18.5 0.69 (1)	10.00			
AD-R	0 / 8432	-18.5 -18.5 0.69 (1)	10.00			
R-Q	0 / 10288	-18.5 -18.5 0.78 (1)	10.00			
Q-AE	0 / 10288	-18.5 -18.5 0.78 (1)	10.00			
AE-AF	0 / 10288	-18.5 -18.5 0.78 (1)	10.00			
AF-P	0 / 10288	-18.5 -18.5 0.78 (1)	10.00			
P-O	0 / 12286	-18.5 -18.5 0.91 (1)	10.00			
O-N	0 / 9385	-18.5 -18.5 0.72 (1)	10.00			
N-M	0 / 9385	-18.5 -18.5 0.72 (1)	10.00			
M-L	0 / 5303	-18.5 -18.5 0.37 (1)	10.00			
L-K	0 / 0	-18.5 -18.5 0.04 (4)	10.00			

FACTORED CONCENTRATED LOADS (LBS)

JT	LOC.	LC1	MAX.	FACE	DIR.	TYPE	HEEL	CONN.
C	5-10-8	-438	-438	---	BACK	VERT	TOTAL	C1
O	18-5-8	-2436	-2436	---	BACK	VERT	TOTAL	C1
P	18-9-12	-17	-17	---	BACK	VERT	TOTAL	C1
S	5-11-4	-26	-26	---	BACK	VERT	TOTAL	C1
U	7-11-4	-110	-110	---	BACK	VERT	TOTAL	C1
V	10-9-12	-82	-82	---	BACK	VERT	TOTAL	C1
W	12-9-12	-82	-82	---	BACK	VERT	TOTAL	C1

TOTAL WEIGHT = 2 X 170 = 341 LBS

DESIGN CRITERIA

SPECIFIED LOADS:

TOP CH. LL = 26.8 PSF
DL = 8.0 PSF
BOT CH. LL = 0.0 PSF
DL = 7.4 PSF
TOTAL LOAD = 38.0 PSF

SPACING = 24.0 IN. C/C

LOADING IN FLAT SECTION BASED ON A SLOPE OF 8.00/12

THIS TRUSS IS DESIGNED FOR RESIDENTIAL OR SMALL BUILDING REQUIREMENTS OF PART 9, NBCC 2010, NBCC 2015

THIS DESIGN COMPLIES WITH:

- PART 8 OF CBC 2018, OBC 2012, ABC 2019
- PART 8 OF OBC 2012 (2019 AMENDMENT)
- CSA 088-09, CSA 088-14
- TPIC 2011, TPIC 2014

(55 % OF 31.3 P.S.F. G.S.L. PLUS 8.4 P.S.F. RAIN LOAD) EQUALS 25.8 P.S.F. SPECIFIED ROOF LIVE LOAD

ALLOWABLE DEFL.(LL) = L/360 (1.17")
CALCULATED VERT. DEFL.(LL) = L/898 (0.31")
ALLOWABLE DEFL.(TL) = L/360 (1.17")
CALCULATED VERT. DEFL.(TL) = L/740 (0.57")

CS: TC=0.71/1.00 (B-C:1), BC=0.91/1.00 (O-P:1), WB=0.80/1.00 (B-S:1), SSI=0.18/1.00 (R-S:1)

DOL LUMBER=1.00 NAIL=1.00 LS BEND=1.00
COMP=1.00 SHEAR=1.00 TENS=1.00

COMPANION LIVE LOAD FACTOR = 1.00

AUTOSOLVE HEELS OFF

TRUSS PLATE MANUFACTURER IS NOT RESPONSIBLE FOR QUALITY CONTROL IN THE TRUSS MANUFACTURING PLANT.

NAIL VALUES

PLATE GRIP(DRY) SHEAR SECTION (PSI) (PLI) (PLI)
MAX MIN MAX MIN MAX MIN
MT20 616 354 1887 768 1887 1656

PLATE PLACEMENT TOL. = 0.250 inches

PLATE ROTATION TOL. = 5.0 Deg.

JSI GRIP = 0.89 (S) (INPUT = 0.90)
JSI METAL = 0.93 (N) (INPUT = 1.00)

CONTINUED ON PAGE 2



Structural component only
DWG# T-2007108

JOB NAME	TRUSS NAME	QUANTITY	PLY	JOB DESC.	DRWG NO.
408152	T40Z	1	2	GREEN PARK HOMES	
Tamarack Roof Truss, Burlington		TRUSS DESC.			

Version 8.310 S Oct 29 2019 Mittek Industries, Inc. Sat Apr 26 11:29:34 2020 Page 2
ID:37vF?aG0E03cRUI6X1/S/kziWYK-ydH2MluB57imK3i1? 4iCnCV?E2GhUJzvKGpGJzNGOV

PLATES (table is in inches)

JT	TYPE	PLATES	W	LEN	Y	X
B	TMWV-p	MT20	5.0	8.0	2.00	3.50
C	TTWW+m	MT20	6.0	9.0	Edge	
D, E, G						
D	TMWV-i	MT20	5.0	8.0		
F	TS-i	MT20	5.0	8.0		
H	TTWW+m	MT20	6.0	9.0	Edge	
I	TMWV-p	MT20	5.0	8.0	2.00	3.50
K	BMV1+p	MT20	3.0	6.0		
L	BMWV-i	MT20	5.0	8.0	2.50	3.50
M	BMWV-i	MT20	5.0	8.0	2.50	2.00
N	BS-i	MT20	5.0	8.0		
O	BMWV-i	MT20	5.0	8.0	2.75	2.75
P	BMWV-i	MT20	5.0	8.0	2.75	2.75
Q	BS-i	MT20	5.0	8.0		
R	BMWV-i	MT20	5.0	8.0	2.50	2.00
S	BMWV-i	MT20	5.0	8.0	2.50	3.50
T	BMV1+p	MT20	3.0	6.0		


Edge - INDICATES REFERENCE CORNER OF PLATE TOUCHES EDGE OF CHORD.

FACTORED CONCENTRATED LOADS (LBS)

JT	LOC.	LC1	MAX-	MAX+	FACE	DIR.	TYPE	HEEL	CONN.
X	14-9-12	-82	-82	---	BACK	VERT	TOTAL	---	C1
Y	18-9-12	-82	-82	---	BACK	VERT	TOTAL	---	C1
Z	1-11-4	-25	-26	---	BACK	VERT	TOTAL	---	C1
AA	3-11-4	-26	-26	---	BACK	VERT	TOTAL	---	C1
AB	7-11-4	-26	-26	---	BACK	VERT	TOTAL	---	C1
AC	8-10-8	-639	-639	---	BACK	VERT	TOTAL	---	C1
AD	10-9-12	-17	-17	---	BACK	VERT	TOTAL	---	C1
AE	12-9-12	-17	-17	---	BACK	VERT	TOTAL	---	C1
AF	14-9-12	-17	-17	---	BACK	VERT	TOTAL	---	C1

CONNECTION REQUIREMENTS

- 1) C1: A SUITABLE HANGER/MECHANICAL CONNECTION IS REQUIRED.




Structural component only
DWG# T-2007108

JOB NAME	TRUSS NAME	QUANTITY	PLY	JOB DESC.	GREEN PARK HOMES	DRWG NO.
408152	T41	2	1	TRUSS DESC.		

Tamarack Roof Truss, Burlington

Version 8.310 S Oct 29 2019 Mitek Industries, Inc. Sat Apr 26 11:29:35 2020 Page 1

ID:7vF7aG0E03cRUj6X1jSkzWYK-QprQa2vpRqdxDHDYhbk_kd2eSiQx867_0NplzNGOU



TOTAL WEIGHT = 2 X 139 = 278 lb

LUMBER	N. L. G. A. RULES	CHORDS	SIZE	DRY	LUMBER	DESCR.
A - D	2x4	DRY	No.2	SPF		
D - F	2x4	DRY	No.2	SPF		
F - H	2x4	DRY	No.2	SPF		
H - K	2x4	DRY	No.2	SPF		
S - B	2x4	DRY	No.2	SPF		
L - J	2x4	DRY	No.2	SPF		
S - Q	2x4	DRY	No.2	SPF		
Q - N	2x4	DRY	No.2	SPF		
N - L	2x4	DRY	No.2	SPF		
ALL WEBS	2x3	DRY	No.2	SPF		
EXCEPT						
S - C	2x4	DRY	No.2	SPF		
I - L	2x4	DRY	No.2	SPF		

DRY: SEASONED LUMBER.

PLATES (table in inches)	JT TYPE	PLATES	W	LEN	Y	X
B TMV+p	MT20	3.0	4.0			
C TMWW-i	MT20	5.0	8.0	2.50	2.75	
D TTWW-m	MT20	5.0	8.0	2.25	2.75	
E TMWW-i	MT20	4.0	4.0			
F TS-i	MT20	3.0	8.0			
G TMW+w	MT20	2.0	4.0			
H TTWW-m	MT20	5.0	8.0	2.25	2.75	
I TMWW-i	MT20	5.0	8.0	2.50	2.75	
J TMV+p	MT20	3.0	4.0			
L BMWW-i	MT20	4.0	9.0			Edge
M BMWW-i	MT20	4.0	4.0			
N BS-i	MT20	3.0	8.0			
O BMWW-i	MT20	4.0	9.0			
P BMWW-i	MT20	4.0	6.0			
Q BS-i	MT20	3.0	8.0			
R BMWW-i	MT20	4.0	4.0			
S BMWW-i	MT20	4.0	9.0			Edge

Edge - INDICATES REFERENCE CORNER OF PLATE TOUCHES EDGE OF CHORD.

DIMENSIONS, SUPPORTS AND LOADINGS SPECIFIED BY FABRICATOR TO BE VERIFIED BY BUILDING DESIGNER

BEARINGS

JT	FACTORED GROSS REACTION	MAXIMUM FACTORED GROSS REACTION	INPUT BRG	REQD BRG
S	2083	0	0	5-8
L	2083	0	0	5-8

UNFACTORED REACTIONS

JT	1ST CASE	MAX/MIN	COMPONENT REACTIONS	WIND	DEAD	SOIL
S	1487	989 / 0	0 / 0	0 / 0	488 / 0	0 / 0
L	1487	989 / 0	0 / 0	0 / 0	488 / 0	0 / 0

BEARING MATERIAL TO BE SPF NO.2 OR BETTER AT JOINT(S) S, L

BRACING

TOP CHORD TO BE SHEATHED OR MAX. PURLIN SPACING = 2.94 FT.
MAX. UNBRACED BOTTOM CHORD LENGTH = 10.00 FT OR RIGID CEILING DIRECTLY APPLIED.

ALL PITCH BREAKS AND PERIMETER CORNER JOINTS MUST BE Laterally RESTRAINED.

LOADING

TOTAL LOAD CASES: (4)

MEMB.	CHORDS	MAX. FACTORED FORCE (LBS)	VERT. LOAD (PLF)	FACTORED VERT. LOAD (LC1)	MAX. FACTORED VERT. LOAD (LC1)	MAX. FACTORED VERT. LOAD (LC1)	MAX. FACTORED VERT. LOAD (LC1)	MAX. FACTORED VERT. LOAD (LC1)	MAX. FACTORED VERT. LOAD (LC1)
FR-TO									
A-B	0 / 28	-91.8	-91.8	0.12 (1)	10.00	C-R	0 / 93	0.03 (4)	
B-C	0 / 18	-91.8	-91.8	0.20 (1)	10.00	R-D	0 / 121	0.04 (4)	
C-D	-2799 / 0	-91.8	-91.8	0.32 (1)	3.88	D-P	0 / 1287	0.29 (1)	
D-E	-3507 / 0	-91.8	-91.8	0.95 (1)	2.94	P-E	-843 / 0	0.25 (1)	
E-F	-3507 / 0	-91.8	-91.8	0.93 (1)	2.94	E-O	-2 / 0	0.00 (1)	
F-G	-3507 / 0	-91.8	-91.8	0.93 (1)	2.94	O-G	-843 / 0	0.25 (1)	
G-H	-3507 / 0	-91.8	-91.8	0.94 (1)	2.95	H-H	0 / 1288	0.28 (1)	
H-I	-2799 / 0	-91.8	-91.8	0.32 (1)	3.88	M-H	0 / 121	0.04 (4)	
I-J	0 / 18	-91.8	-91.8	0.20 (1)	10.00	M-I	0 / 93	0.03 (4)	
J-K	0 / 28	-91.8	-91.8	0.12 (1)	10.00	S-C	-2974 / 0	0.83 (1)	
S-B	-270 / 0	0.0	0.0	0.03 (1)	7.81	I-L	-2974 / 0	0.83 (1)	
L-J	-270 / 0	0.0	0.0	0.03 (1)	7.81				
S-R	0 / 2417	-18.5	-18.5	0.83 (1)	10.00				
R-Q	0 / 2489	-18.5	-18.5	0.54 (1)	10.00				
Q-P	0 / 2489	-18.5	-18.5	0.54 (1)	10.00				
P-O	0 / 3509	-18.5	-18.5	0.64 (1)	10.00				
O-N	0 / 2489	-18.5	-18.5	0.54 (1)	10.00				
N-M	0 / 2489	-18.5	-18.5	0.54 (1)	10.00				
M-L	0 / 2417	-18.5	-18.5	0.53 (1)	10.00				

DESIGN CRITERIA

SPECIFIED LOADS:

TOP CH.	LL	=	25.8	PSF
	DL	=	8.0	PSF
BOT CH.	LL	=	0.0	PSF
	DL	=	7.4	PSF
TOTAL LOAD		=	39.0	PSF

SPACING = 24.0 IN/C

LOADING IN FLAT SECTION BASED ON A SLOPE OF 8.00/12

THIS TRUSS IS DESIGNED FOR RESIDENTIAL OR SMALL BUILDING REQUIREMENTS OF PART 9, NBC 2010, NBC 2015

THIS DESIGN COMPLIES WITH:

- PART 9 OF CBC 2010, CBC 2012, A8C 2019
- PART 9 OF CBC 2012 (2019 AMENDMENT)
- CSA 088-09, CSA 088-14
- TPIC 2011, TPIC 2014

(55 % OF 31.3 P.S.F. G.S.L. PLUS 8.4 P.S.F. RAIN LOAD) EQUALS 25.8 P.S.F. SPECIFIED ROOF LIVE LOAD

ALLOWABLE DEFL.(LL) = L/360 (1.17")
CALCULATED VERT. DEFL.(LL) = L/899 (0.21")
ALLOWABLE DEFL.(TL) = L/360 (1.17")
CALCULATED VERT. DEFL.(TL) = L/899 (0.41")

CSI: TC=0.85/1.00 (D-E:1), BC=0.84/1.00 (O-P:1),
WB=0.83/1.00 (H-L:1), SS=0.29/1.00 (D-E:1)

DOL LUMBER=1.00 NAIL=1.00 LS BEND=1.10
COMP=1.10 SHEAR=1.10 TENS=1.10

COMPANION LIVE LOAD FACTOR = 1.00

AUTOSOLVE HEELS OFF

TRUSS PLATE MANUFACTURER IS NOT RESPONSIBLE FOR QUALITY CONTROL IN THE TRUSS MANUFACTURING PLANT.

NAIL VALUES


PLATE GRIP (DRY)	SHEAR	SECTION
(PSI)	(PLI)	(PLI)
MAX	MIN	MAX
MT20	618	354
	1887	788
	1887	1656

PLATE PLACEMENT TOL. = 0.250 inches

PLATE ROTATION TOL. = 5.0 Deg.

JSI GRIP = 0.89 (L) (INPUT = 0.80)


JSI METAL = 0.77 (N) (INPUT = 1.00)



Structural component only
DWG# T-2007109

JOB NAME	TRUSS NAME	QUANTITY	PLY	JOB DESC.	DRWG NO.
408152	T42	2	1	GREEN PARK HOMES	
Tamarack Roof Truss, Burlington					

Version 8.310 S Oct 29 2019 MiTek Industries, Inc. Sat Apr 25 11:29:36 2020 Page 1
ID: i7vF?aG0E03cRUj6X1jSrkzWYK-u?PpnOvRckyUZNSp6PAHCHnN1r18RDGM6wL0zNCOT



LUMBER				TOTAL WEIGHT = 2 X 139 = 277 lb			
N. L. G. A. RULES							
CHORDS	SIZE	LUMBER	DESCR.				
A - D	2x4	DRY	No.2				
D - F	2x4	DRY	No.2				
F - I	2x4	DRY	No.2				
R - B	2x4	DRY	No.2				
J - H	2x4	DRY	No.2				
R - O	2x4	DRY	No.2				
O - M	2x4	DRY	No.2				
M - J	2x4	DRY	No.2				
ALL WEBS	2x3	DRY	No.2				
EXCEPT							
DRY: SEASONED LUMBER.							

PLATES (tablets in inches)			
JT	TYPE	PLATES	W LEN Y X
B	TMWW-p	MT20	5.0 8.0 Edge 3.50
C	TMWW-l	MT20	4.0 4.0 2.00 1.75
D	TTWW-m	MT20	5.0 8.0 2.25 3.75
E	TMWW-w	MT20	2.0 4.0
F	TTWW-m	MT20	5.0 8.0 2.25 3.75
G	TMWW-l	MT20	4.0 4.0 2.00 1.75
H	TMWW-p	MT20	5.0 8.0 Edge 3.50
J	BMV1-p	MT20	3.0 4.0
K	BMVW-l	MT20	5.0 8.0 2.50 2.00
L	BMVW-l	MT20	4.0 4.0
M	BS-l	MT20	3.0 6.0
N	BMVW-w	MT20	4.0 9.0
O	BS-l	MT20	3.0 6.0
P	BMVW-l	MT20	4.0 4.0
Q	BMVW-l	MT20	5.0 8.0 2.50 2.00
R	BMV1-p	MT20	3.0 4.0

Edge - INDICATES REFERENCE CORNER OF PLATE TOUCHES EDGE OF CHORD.

DIMENSIONS, SUPPORTS AND LOADINGS SPECIFIED BY FABRICATOR TO BE VERIFIED BY BUILDING DESIGNER							
<u>BEARINGS</u>							
	FACTORED		MAXIMUM FACTORED		INPUT		REQRD
	GROSS REACTION		GROSS REACTION		BRG		BRG
JT	VERT	HORZ	DOWN	HORZ	UPLIFT	IN-SX	IN-SX
R	2083	0	2083	0	0	5-8	5-8
J	2083	0	2083	0	0	5-8	5-8
<u>UNFACTORED REACTIONS</u>							
	1ST CASE	MAX/MIN COMPONENT REACTIONS					
JT	COMBINED	SNOW	LIVE	PERM. LIVE	WIND	DEAD	SOIL
R	1457	889 / 0	0 / 0	0 / 0	0 / 0	488 / 0	0 / 0
J	1457	889 / 0	0 / 0	0 / 0	0 / 0	488 / 0	0 / 0

BEARING MATERIAL TO BE SPF NO.2 OR BETTER AT JOINT(S) R, J
BRACING
TOP CHORD TO BE SHEATHED OR MAX. PURLIN SPACING = 2.78 FT.
MAX. UNBRACED BOTTOM CHORD LENGTH = 10.00 FT OR RIGID CEILING DIRECTLY APPLIED.
ALL PITCH BREAKS AND PERIMETER CORNER JOINTS MUST BE Laterally RESTRAINED.


LOADING									
TOTAL LOAD CASES: (4)									
CHORDS					WEBS				
MEMB.	MAX. FACTORED FORCE (LBS)	VERT. LOAD LOI (PLF)	MAX. UNBRACED LENGTH (FT)	MAX. FACTORED FORCE (LBS)	MEMB.	MAX. FACTORED FORCE (LBS)	MAX. UNBRACED LENGTH (FT)	MAX. FACTORED FORCE (LBS)	MAX. UNBRACED LENGTH (FT)
FR-TO	FROM	TO	FROM	TO	FR-TO	FROM	TO	FROM	TO
A-B	0 / 28	-18.5	-18.5	0.10 (4)	10.00	Q-C	-353 / 0	0.08 (1)	0.08 (1)
B-C	-2834 / 0	-18.5	-18.5	0.39 (1)	3.81	C-P	-210 / 0	0.13 (1)	0.13 (1)
C-D	-2887 / 0	-18.5	-18.5	0.37 (1)	3.81	P-O	0 / 246	0.08 (4)	0.08 (4)
D-E	-3080 / 0	-18.5	-18.5	0.97 (1)	2.78	D-N	0 / 844	0.19 (1)	0.19 (1)
E-F	-3080 / 0	-18.5	-18.5	0.97 (1)	2.78	N-E	-872 / 0	0.51 (1)	0.51 (1)
F-G	-2887 / 0	-18.5	-18.5	0.37 (1)	3.81	E-F	0 / 844	0.19 (1)	0.19 (1)
G-H	-2834 / 0	-18.5	-18.5	0.39 (1)	3.81	F-F	0 / 248	0.08 (4)	0.08 (4)
H-I	0 / 28	-18.5	-18.5	0.12 (1)	10.00	L-G	-210 / 0	0.13 (1)	0.13 (1)
R-B	-2018 / 0	0.0	0.0	0.20 (1)	5.94	K-Q	-353 / 0	0.08 (1)	0.08 (1)
J-H	-2018 / 0	0.0	0.0	0.20 (1)	5.94	B-Q	0 / 2591	0.58 (1)	0.58 (1)
R-Q	0 / 0	-18.5	-18.5	0.10 (4)	10.00	K-H	0 / 2591	0.58 (1)	0.58 (1)
Q-P	0 / 2555	-18.5	-18.5	0.51 (1)	10.00				
P-O	0 / 2388	-18.5	-18.5	0.49 (1)	10.00				
O-N	0 / 2388	-18.5	-18.5	0.49 (1)	10.00				
N-M	0 / 2388	-18.5	-18.5	0.49 (1)	10.00				
M-L	0 / 2388	-18.5	-18.5	0.49 (1)	10.00				
L-K	0 / 2555	-18.5	-18.5	0.51 (1)	10.00				
K-J	0 / 0	-18.5	-18.5	0.10 (4)	10.00				


DESIGN CRITERIA
SPECIFIED LOADS:
TOP CH. LL = 25.8 PSF
OL = 6.0 PSF
BOT CH. LL = 0.0 PSF
DL = 7.4 PSF
TOTAL LOAD = 39.0 PSF
SPACING = 24.0 IN. C/C
LOADING IN FLAT SECTION BASED ON A SLOPE OF 8.00/12
THIS TRUSS IS DESIGNED FOR RESIDENTIAL OR SMALL BUILDING REQUIREMENTS OF PART 9, NBC 2010, NBC 2015
THIS DESIGN COMPLIES WITH:
- PART 9 OF CBC 2018, CBC 2012, ABC 2019
- PART 9 OF CBC 2012 (2019 AMENDMENT)
- CSA 080-09, CSA 088-14
- TPIC 2011, TPIC 2014
(55 % OF 31.3 P.S.F. G.S.L. PLUS 8.4 P.S.F. RAIN LOAD) EQUALS 25.8 P.S.F. SPECIFIED ROOF LIVE LOAD
ALLOWABLE DEFL.(LL) = L/360 (1.17")
CALCULATED VERT. DEFL.(LL) = L/899 (0.17")
ALLOWABLE DEFL.(TL) = L/360 (1.17")
CALCULATED VERT. DEFL.(TL) = L/899 (0.34")
CSI: TC=0.97/1.00 (D-E:1), BC=0.51/1.00 (K-L:1), WB=0.58/1.00 (H-K:1), SS=0.34/1.00 (D-E:1)
DOL LUMBER=1.00 NAIL=1.00 LS BEND=1.10
COMP=1.10 SHEAR=1.10 TENS=1.10
COMPANION LIVE LOAD FACTOR = 1.00

TRUSS PLATE MANUFACTURER IS NOT RESPONSIBLE FOR QUALITY CONTROL IN THE TRUSS MANUFACTURING PLANT.
NAIL VALUES
PLATE GRIP(DRY) SHEAR SECTION
(PSI) (PLI) (PLI)
MAX MIN MAX MIN MAX MIN
MT20 818 354 1887 768 1987 1658
PLATE PLACEMENT TOL. = 0.250 inches
PLATE ROTATION TOL. = 5.0 Deg.
JSI GRIP= 0.87 (D) (INPUT = 0.80)
JSI METAL= 0.75 (D) (INPUT = 1.00)



Structural component only
DWG# T-2007110





LUMBER

N. L. G. A. RULES


CHORDS	SIZE	DRY	LUMBER	DESCR.
A - D	2x4	DRY	No.2	SPF
D - F	2x4	DRY	No.2	SPF
F - G	2x4	DRY	No.2	SPF
G - I	2x4	DRY	No.2	SPF
I - L	2x4	DRY	No.2	SPF
L - B	2x4	DRY	No.2	SPF
M - K	2x4	DRY	No.2	SPF
T - R	2x4	DRY	No.2	SPF
R - O	2x4	DRY	No.2	SPF
O - M	2x4	DRY	No.2	SPF
ALL WEBS	2x3	DRY	No.2	SPF

EXCEPT

DRY: SEASONED LUMBER.

PLATES (table in inches)

JT TYPE	PLATES	W	LEN	Y	X
B TMV-p	MT20	3.0	4.0		
C TMWW-t	MT20	5.0	6.0	2.50	2.25
D TS-t	MT20	3.0	6.0		
E TMWW-t	MT20	4.0	4.0	2.00	1.50
F TTW-h	MT20	4.0	4.0	2.00	1.75
G TTWW-m	MT20	5.0	6.0	2.00	2.00
H TMWW-t	MT20	4.0	4.0	2.00	1.50
I TS-t	MT20	3.0	6.0		
J TMWW-t	MT20	5.0	6.0	2.50	2.25
K TMV-p	MT20	3.0	4.0		
M BMVW-t	MT20	5.0	6.0	2.25	2.00
N, P, S					
N BMWW-t	MT20	4.0	4.0		
O BS-t	MT20	3.0	6.0		
Q BMWW-t	MT20	4.0	9.0		
R BS-t	MT20	3.0	6.0		
T BMVW-t	MT20	5.0	6.0	2.25	2.00



Structural component only
DWG# T-2007113

DIMENSIONS, SUPPORTS AND LOADINGS SPECIFIED BY FABRICATOR TO BE VERIFIED BY BUILDING DESIGNER

BEARINGS

JT	FACTORED GROSS REACTION		MAXIMUM FACTORED GROSS REACTION		INPUT BRG	REQD BRG
	VERT	HORZ	DOWN	HORZ		
T	2083	0	2083	0	5-8	5-8
M	2083	0	2083	0	5-8	5-8

UNFACTORED REACTIONS

JT	1ST LOASE		MAX/MIN. COMPONENT REACTIONS		WIND	DEAD	SOIL
	COMBINED	SNOW	LIVE	PERM. LIVE			
T	1457	869 / 0	0 / 0	0 / 0	0 / 0	488 / 0	0 / 0
M	1457	869 / 0	0 / 0	0 / 0	0 / 0	488 / 0	0 / 0

BEARING MATERIAL TO BE SPF NO.2 OR BETTER AT JOINT(S) T, M

BRACING
TOP CHORD TO BE SHEATHED OR MAX. PURLIN SPACING = 3.66 FT.
MAX. UNBRACED BOTTOM CHORD LENGTH = 10.00 FT OR RIGID CEILING DIRECTLY APPLIED.

ALL PITCH BREAKS AND PERIMETER CORNER JOINTS MUST BE Laterally RESTRAINED.

1 LATERAL BRACE(S) AT 1/2 LENGTH OF E-Q, H-P, C-T, J-M

END VERTICAL(S) MUST BE SHEATHED OR HAVE BRACES AS INDICATED IN THE MAX. UNBRACED LENGTH COLUMN OF THE TABLE BELOW

LOADING
TOTAL LOAD CASES: (4)

CHORDS				WEBS			
MEMB.	MAX. FACTORED FORCE (LBS)	FACTORED VERT. LOAD (PLF)	MAX. UNBRACED LENGTH (LC)	MEMB.	MAX. FACTORED FORCE (LBS)	FACTORED VERT. LOAD (PLF)	MAX. UNBRACED LENGTH (LC)
FR-TO				FR-TO			
A-B	0 / 28	-91.8	-91.8 0.12 (1)	C-S	-110 / 37	0.04 (1)	10.00
B-C	0 / 19	-91.8	-91.8 0.32 (1)	S-E	0 / 278	0.08 (1)	10.00
C-D	-2759 / 0	-91.8	-91.8 0.40 (1)	E-Q	-681 / 0	0.31 (1)	3.86
D-E	-2759 / 0	-91.8	-91.8 0.40 (1)	Q-F	0 / 813	0.14 (1)	3.86
E-F	-2167 / 0	-91.8	-91.8 0.38 (1)	F-G	0 / 4	0.00 (1)	4.30
F-G	-1925 / 0	-91.8	-91.8 0.18 (1)	G-H	0 / 609	0.14 (1)	4.71
G-H	-2168 / 0	-91.8	-91.8 0.36 (1)	H-I	-682 / 0	0.31 (1)	4.30
H-I	-2780 / 0	-91.8	-91.8 0.40 (1)	I-J	0 / 278	0.08 (1)	3.86
I-J	-2780 / 0	-91.8	-91.8 0.40 (1)	J-K	-110 / 37	0.04 (1)	3.86
J-K	0 / 19	-91.8	-91.8 0.32 (1)	K-L	-3040 / 0	0.85 (1)	10.00
K-L	0 / 28	-91.8	-91.8 0.12 (1)	L-M	-3041 / 0	0.85 (1)	10.00
T-B	-325 / 0	0.0	0.0 0.03 (1)				7.81
M-K	-326 / 0	0.0	0.0 0.03 (1)				7.81
T-S	0 / 2638	-18.5	-18.5 0.55 (1)				10.00
S-R	0 / 2362	-18.5	-18.5 0.53 (1)				10.00
R-Q	0 / 2362	-18.5	-18.5 0.53 (1)				10.00
Q-P	0 / 1924	-18.5	-18.5 0.40 (1)				10.00
P-O	0 / 2362	-18.5	-18.5 0.53 (1)				10.00
O-N	0 / 2362	-18.5	-18.5 0.53 (1)				10.00
N-M	0 / 2537	-18.5	-18.5 0.58 (1)				10.00

TOTAL WEIGHT = 2 X 151 = 302 b

DESIGN CRITERIA

SPECIFIED LOADS:
TOP CH. LL = 25.8 PSF
DL = 6.0 PSF
BOT CH. LL = 0.0 PSF
DL = 7.4 PSF
TOTAL LOAD = 39.0 PSF

SPACING = 24.0 IN. C/C

LOADING IN FLAT SECTION BASED ON A SLOPE OF 8.00/12

THIS TRUSS IS DESIGNED FOR RESIDENTIAL OR SMALL BUILDING REQUIREMENTS OF PART 9, NBC 2010, NBC 2015

THIS DESIGN COMPLIES WITH:
- PART 9 OF CBC 2018, OBC 2012, ABC 2019
- PART 9 OF OBC 2012 (2019 AMENDMENT)
- CSA 086-09, CSA 086-14
- TPC 2011, TPC 2014

(55 % OF 31.3 P.S.F. G.S.L. PLUS 8.4 P.S.F. RAIN LOAD) EQUALS 25.8 P.S.F. SPECIFIED ROOF LIVE LOAD

ALLOWABLE DEFL.(LL) = L/360 (1.17")
CALCULATED VERT. DEFL.(LL) = L/999 (0.15")
ALLOWABLE DEFL.(TL) = L/360 (1.17")
CALCULATED VERT. DEFL.(TL) = L/999 (0.32")

CSK: TC=0.40/1.00 (H-J:1), BC=0.58/1.00 (M-N:1), WB=0.85/1.00 (J-M:1), SS=0.20/1.00 (B-C:1)

DOL LUMBER=1.00 NAIL=1.00 LS BEND=1.10
COMP=1.10 SHEAR=1.10 TENS=1.10

COMPANION LIVE LOAD FACTOR = 1.00

AUTOSOLVE HEELS OFF


TRUSS PLATE MANUFACTURER IS NOT RESPONSIBLE FOR QUALITY CONTROL IN THE TRUSS MANUFACTURING PLANT.

NAIL VALUES
PLATE GRIP(DRY) SHEAR SECTION (PS) (PLI) (PLI)
MAX MIN MAX MIN MAX MIN
MT20 618 354 1667 798 1997 1658

PLATE PLACEMENT TOL. = 0.250 inches

PLATE ROTATION TOL. = 5.0 Deg.

JSI GRIP = 0.89 (M) (INPUT = 0.90)
JSI METAL = 0.83 (O) (INPUT = 1.00)



LUMBER

N. L. G. A. RULES

CHORDS	SIZE	DRY	LUMBER	DESCR.
A - D	2x4	DRY	No.2	SPF
D - F	2x4	DRY	No.2	SPF
F - H	2x4	DRY	No.2	SPF
H - K	2x4	DRY	No.2	SPF
K - L	2x4	DRY	No.2	SPF
L - J	2x4	DRY	No.2	SPF
J - Q	2x4	DRY	No.2	SPF
Q - N	2x4	DRY	No.2	SPF
N - L	2x4	DRY	No.2	SPF
ALL WEBS	2x3	DRY	No.2	SPF
EXCEPT				
S - C	2x4	DRY	No.2	SPF
I - L	2x4	DRY	No.2	SPF

DRY: SEASONED LUMBER.

PLATES (table is in inches)

JT TYPE	PLATES	W	LEN Y	X
B TMV+p	MT20	3.0	4.0	
C TMWW-i	MT20	5.0	8.0	2.25 2.00
D TS-i	MT20	3.0	8.0	
E TMWW+i	MT20	5.0	8.0	
F TTWW+p	MT20	4.0	8.0	Edge
G TMWW-i	MT20	5.0	8.0	
H TS-i	MT20	3.0	8.0	
I TMWW-i	MT20	5.0	8.0	2.25 2.00
J TMV+p	MT20	3.0	4.0	
L BMWW-i	MT20	4.0	9.0	Edge
M, O, P, R				
N BMWW+i	MT20	4.0	8.0	
M BS-i	MT20	3.0	8.0	
Q BS-i	MT20	3.0	8.0	
S BMWW-i	MT20	4.0	9.0	Edge

Edge - INDICATES REFERENCE CORNER OF PLATE TOUCHES EDGE OF CHORD.

DIMENSIONS, SUPPORTS AND LOADINGS SPECIFIED BY FABRICATOR TO BE VERIFIED BY BUILDING DESIGNER

BEARINGS

JT	FACTORED GROSS REACTION		MAXIMUM FACTORED GROSS REACTION		INPUT BRG	REQD BRG
	VERT	HORZ	DOWN	HORZ		
S	2083	0	2083	0	5-8	5-8
L	2083	0	2083	0	5-8	5-8

UNFACTORED REACTIONS

JT	1ST LCASE		MAX/MIN. COMPONENT REACTIONS		WIND	DEAD	SOIL
	COMBINED	SNOW	LIVE	PERM. LIVE			
S	1457	969 / 0	0 / 0	0 / 0	0 / 0	488 / 0	0 / 0
L	1457	969 / 0	0 / 0	0 / 0	0 / 0	488 / 0	0 / 0

BEARING MATERIAL TO BE SPF NO.2 OR BETTER AT JOINT(S) S, L

BRACING

TOP CHORD TO BE SHEATHED OR MAX. PURLIN SPACING = 3.75 FT.
MAX. UNBRACED BOTTOM CHORD LENGTH = 10.00 FT. OR RIGID CEILING DIRECTLY APPLIED.

ALL PITCH BREAKS AND PERIMETER CORNER JOINTS MUST BE Laterally RESTRAINED.

1 LATERAL BRACE(S) AT 1/2 LENGTH OF G-S, L.

END VERTICAL(S) MUST BE SHEATHED OR HAVE BRACES AS INDICATED IN THE MAX. UNBRACED LENGTH COLUMN OF THE TABLE BELOW

LOADING

TOTAL LOAD CASES: (4)

MEMB.	CHORDS		WEBS	
	MAX. FACTORED FORCE (LBS)	VERT. LOAD LC1 (PLF)	MAX. FACTORED FORCE (LBS)	MAX. FACTORED FORCE (LBS)
FR-TO				
A-B	0 / 28	-91.8 -91.8 0.12 (1)	10.00	F-O 0 / 868
B-C	0 / 22	-91.8 -91.8 0.40 (1)	10.00	O-G -728 / 0
C-D	-2808 / 0	-91.8 -91.8 0.49 (1)	3.75	G-M 0 / 391
D-E	-2808 / 0	-91.8 -91.8 0.49 (1)	3.75	M-I -182 / 18
E-F	-2322 / 0	-91.8 -91.8 0.46 (1)	4.07	I-P 0 / 886
F-G	-2322 / 0	-91.8 -91.8 0.46 (1)	4.07	P-F -728 / 0
G-H	-2808 / 0	-91.8 -91.8 0.49 (1)	3.75	F-E 0 / 391
H-I	-2808 / 0	-91.8 -91.8 0.49 (1)	3.75	E-P -192 / 18
I-J	0 / 22	-91.8 -91.8 0.40 (1)	10.00	P-R -3084 / 0
J-K	0 / 28	-91.8 -91.8 0.12 (1)	10.00	R-E -3084 / 0
K-L	-344 / 0	0.0 0.0 0.03 (1)	7.81	
L-J	-344 / 0	0.0 0.0 0.03 (1)	7.81	
S-R	0 / 2574	-18.5 -18.5 0.53 (1)	10.00	
R-Q	0 / 2291	-18.5 -18.5 0.47 (1)	10.00	
Q-P	0 / 2291	-18.5 -18.5 0.47 (1)	10.00	
P-O	0 / 1782	-18.5 -18.5 0.38 (1)	10.00	
O-N	0 / 2291	-18.5 -18.5 0.47 (1)	10.00	
N-M	0 / 2291	-18.5 -18.5 0.47 (1)	10.00	
M-L	0 / 2574	-18.5 -18.5 0.53 (1)	10.00	

TOTAL WEIGHT = 6 X 152 = 910 LBS

DESIGN CRITERIA

SPECIFIED LOADS:
TOP CH. LL = 25.8 PSF
OL = 8.0 PSF
BOT CH. LL = 0.0 PSF
OL = 7.4 PSF
TOTAL LOAD = 39.0 PSF

SPACING = 24.0 IN. C/C

THIS TRUSS IS DESIGNED FOR RESIDENTIAL OR SMALL BUILDING REQUIREMENTS OF PART 9, NBCC 2010, NBCC 2015

THIS DESIGN COMPLIES WITH:
- PART 9 OF BCBC 2018, OBC 2012, ABC 2019
- PART 9 OF OBC 2012 (2018 AMENDMENT)
- CSA 088-09, CSA 088-14
- TPIC 2011, TPIC 2014

(55 % OF 31.3 P.S.F. G.S.L. PLUS 8.4 P.S.F. RAIN LOAD) EQUALS 25.8 P.S.F. SPECIFIED ROOF LIVE LOAD

ALLOWABLE DEFL.(LL) = L/380 (1.17")
CALCULATED VERT. DEFL.(LL) = L/999 (0.14")
ALLOWABLE DEFL.(TL) = L/380 (1.17")
CALCULATED VERT. DEFL.(TL) = L/999 (0.28")

CSI: TC=0.49/1.00 (C-E:1), BC=0.53/1.00 (L-M:1), WB=0.72/1.00 (E-P:1), SS=0.22/1.00 (I-J:1)

DOL LUMBER=1.00 NAIL=1.00 LS BEND=1.10
COMP=1.10 SHEAR=1.10 TENS=1.10

COMPANION LIVE LOAD FACTOR = 1.00

AUTOSOLVE HEELS OFF


TRUSS PLATE MANUFACTURER IS NOT RESPONSIBLE FOR QUALITY CONTROL IN THE TRUSS MANUFACTURING PLANT.

NAIL VALUES
PLATE GRIP(DRY) SHEAR SECTION (PSI) (PLI) (PLI)
MAX MIN MAX MIN MAX MIN
MT20 618 354 1667 788 1987 1656

PLATE PLACEMENT TOL = 0.250 inches


PLATE ROTATION TOL = 5.0 Deg.

JSI GRIP = 0.87 (C) (INPUT = 0.90)
JSI METAL = 0.77 (I) (INPUT = 1.00)



Structural component only
DWG# T-2007114

JOB NAME 408152	TRUSS NAME T47	QUANTITY 1	PLY 2	JOB DESC. GREEN PARK HOMES	DRWG NO.
Tamarack Roof Truss, Burlington				Version 3.310 S Oct 29 2019 Mitek Industries, Inc. Sat Apr 25 11:29:42 2020 Page 1	



LUMBER				
N. L. G. A. RULES				
CHORDS	SIZE		LUMBER	DESCR
A - C	2x4	DRY	No.2	SPF
C - E	2x4	DRY	No.2	SPF
E - F	2x4	DRY	No.2	SPF
L - B	2x6	DRY	No.2	SPF
G - F	2x4	DRY	No.2	SPF
L - I	2x6	DRY	No.2	SPF
I - G	2x6	DRY	No.2	SPF
ALL WEBS	2x3	DRY	No.2	SPF
EXCEPT				

EXCEPT
DRY: SEASONED LUMBER.
DESIGN CONSISTS OF 2 TRUSSES BUILT SEPARATELY THEN FASTENED TOGETHER AS FOLLOWS:

CHORDS #ROWS	SURFACE SPACING (IN)	LOAD (PLF)
TOP CHORDS: (0.122"x3") SPIRAL NAILS		
A-C	12	SIDE (61.0)
C-E	12	SIDE (61.0)
E-F	12	TOP
G-F	12	TOP
L-B	12	TOP
BOTTOM CHORDS: (0.122"x3") SPIRAL NAILS		
L-I	12	SIDE (0.0)
I-G	12	TOP
WEBS: (0.122"x3") SPIRAL NAILS		
2x3	6	

NAILS TO BE DRIVEN FROM ONE SIDE ONLY.
GIRDER NAILING ASSUMES NAILED HANGERS ARE FASTENED WITH MIN. 3-0 INCH NAILS.

TOP - COMPONENTS ARE LOADED FROM THE TOP AND MUST BE PLACED ON TOP EDGE OF ALL PLIES FOR THE LOAD TO BE TRANSFERRED TO EACH PLY.

SIDE - PLF SHOWN IS THE EQUIVALENT UDL APPLIED TO ONE SIDE THAT THE CORRESPONDING NAILING PATTERN SHALL BE CAPABLE OF TRANSFERRING. REMAINING PLF MUST BE APPLIED ON THE OPPOSITE SIDE OR ON THE TOP.

DIMENSIONS, SUPPORTS AND LOADINGS SPECIFIED BY FABRICATOR TO BE VERIFIED BY BUILDING DESIGNER

JT	FACTORED GROSS REACTION		MAXIMUM FACTORED GROSS REACTION		INPUT BRG	RECORD BRG
	VERT	HORZ	DOWN	HORZ		
L	2005	0	2005	0	5-8	5-8
G	1397	0	1397	0	MECHANICAL	

A SUITABLE HANGER/MECHANICAL CONNECTION IS REQUIRED AT JOINT G. MINIMUM BEARING LENGTH AT JOINT G = 2-0.

UNFACTORED REACTIONS

JT	1ST CASE	2ND CASE	3RD CASE	4TH CASE	5TH CASE	6TH CASE	7TH CASE	8TH CASE
L	1412	956 / 0	0 / 0	0 / 0	0 / 0	457 / 0	0 / 0	0 / 0
G	985	682 / 0	0 / 0	0 / 0	0 / 0	323 / 0	0 / 0	0 / 0

BEARING MATERIAL TO BE SPF NO.2 OR BETTER AT JOINT(S) L

BRACING
TOP CHORD TO BE SHEATHED OR MAX. PURLIN SPACING = 5.18 FT.
MAX. UNBRACED BOTTOM CHORD LENGTH = 10.00 FT OR RIGID CEILING DIRECTLY APPLIED.

ALL PITCH BREAKS AND PERIMETER CORNER JOINTS MUST BE Laterally RESTRAINED.

LOADING
TOTAL LOAD CASES: (4)

CHORDS				WEBS			
MEMB.	MAX. FACTORED FORCE (LBS)	FACTORED VERT. LOAD (PLF)	MAX. FACTORED CSI (LC)	MEMB.	MAX. FACTORED FORCE (LBS)	MAX. FACTORED CSI (LC)	
FR-TO		FROM TO		FR-TO			
A-B	0 / 28	-91.8 -91.8	0.07 (1)	10.00	K-C	0 / 943	0.12 (1)
B-C	-2643 / 0	-91.8 -91.8	0.37 (1)	5.18	C-J	-846 / 0	0.13 (1)
C-D	-1951 / 0	-91.8 -91.8	0.10 (1)	6.17	J-D	-371 / 0	0.08 (1)
D-E	-1951 / 0	-91.8 -91.8	0.10 (1)	6.17	E-E	0 / 1047	0.13 (1)
E-F	-1405 / 0	-91.8 -91.8	0.14 (1)	6.25	H-E	-445 / 0	0.08 (1)
L-B	-1885 / 0	0.0 0.0	0.07 (1)	7.81	B-K	0 / 2382	0.29 (1)
G-F	-1389 / 0	0.0 0.0	0.08 (1)	7.81	H-F	0 / 1375	0.17 (1)
L-M	0 / 0	-18.5 -18.5	0.10 (1)	10.00			
M-N	0 / 0	-18.5 -18.5	0.10 (1)	10.00			
N-O	0 / 0	-18.5 -18.5	0.10 (1)	10.00			
O-K	0 / 0	-18.5 -18.5	0.10 (1)	10.00			
K-J	0 / 2389	-18.5 -18.5	0.24 (1)	10.00			
J-I	0 / 1243	-18.5 -18.5	0.11 (1)	10.00			
I-H	0 / 1243	-18.5 -18.5	0.11 (1)	10.00			
H-G	0 / 0	-18.5 -18.5	0.02 (4)	10.00			

FACTORED CONCENTRATED LOADS (LBS)

JT	LOC.	LC1	MAX-	MAX+	FACE	DIR.	TYPE	HEEL	CONN.
C	5-10-8	-320	-320	---	FRONT	VERT	TOTAL	---	C1
M	1-11-4	-26	-26	---	FRONT	VERT	TOTAL	---	C1
N	3-11-4	-26	-26	---	FRONT	VERT	TOTAL	---	C1
O	5-8-8	-1076	-1076	---	FRONT	VERT	TOTAL	---	C1

CONNECTION REQUIREMENTS

1) C1: A SUITABLE HANGER/MECHANICAL CONNECTION IS REQUIRED.

TOTAL WEIGHT = 2 X 78 = 156 LB

DESIGN CRITERIA

SPECIFIED LOADS:
TOP CH. LL = 25.8 PSF
DL = 8.0 PSF
BOT CH. LL = 0.0 PSF
DL = 7.4 PSF
TOTAL LOAD = 39.0 PSF

SPACING = 24.0 IN. C/C

LOADING IN FLAT SECTION BASED ON A SLOPE OF 6.00/12

THIS TRUSS IS DESIGNED FOR RESIDENTIAL OR SMALL BUILDING REQUIREMENTS OF PART 9, NBC 2010, NBC 2015

THIS DESIGN COMPLIES WITH:
- PART 9 OF CBC 2018, OBC 2012, ABC 2019
- PART 9 OF OBC 2012 (2019 AMENDMENT)
- CSA 088-09, CSA 088-14
- TPIC 2011, TPIC 2014

(55% OF 31.3 P.S.F. G.S.L. PLUS 8.4 P.S.F. RAIN LOAD) EQUALS 25.6 P.S.F. SPECIFIED ROOF LIVE LOAD

ALLOWABLE DEFL. (LL) = L/360 (0.55")
CALCULATED VERT. DEFL. (LL) = L/999 (0.03")
ALLOWABLE DEFL. (TL) = L/360 (0.55")
CALCULATED VERT. DEFL. (TL) = L/999 (0.08")

CSI: TC=0.37/1.00 (B-C:1), BC=0.24/1.00 (J-K:1), WB=0.29/1.00 (B-K:1), SSI=0.37/1.00 (K-L:1)

DOL LUMBER=1.00 NAIL=1.00 LS BEND=1.00
COMP=1.00 SHEAR=1.00 TENS=1.00

COMPANION LIVE LOAD FACTOR = 1.00

AUTOSOLVE RIGHT HEEL ONLY

TRUSS PLATE MANUFACTURER IS NOT RESPONSIBLE FOR QUALITY CONTROL IN THE TRUSS MANUFACTURING PLANT


NAIL VALUES

PLATE GRIP (DRY)	SHEAR (PSI)	SECTION (PLI)	MAX MIN	MAX MIN	MAX MIN
MT20	616	354	1687	788	1987

PLATE PLACEMENT TOL. = 0.250 inches

PLATE ROTATION TOL. = 5.0 Deg.

JSI GRIP = 0.80 (B) (INPUT = 0.90)
JSI METAL = 0.32 (B) (INPUT = 1.00)



Structural component only
DWG# T-2007115 1/1

JOB NAME	TRUSS NAME	QUANTITY	PLY	JOB DESC.	DRWG NO.
408152	T47	1	2	GREEN PARK HOMES	
Tamarack Roof Truss, Burlington		TRUSS DESC.			

Version 8.310 S Oct 29 2019 Mittek Industries, Inc. Sat Apr 25 11:28:42 2020 Page 2
ID:17vF7aG0E03cRU6X1ISrkzWYK-i9m42R CCaleHljZTfDaWTXzGSvYZ008kZDEYrzNCON

PLATES (table in inches)

JT TYPE	PLATES	W	LEN	Y	X
B TMVW-p	MT20	4.0	6.0	1.00	3.00
C TTWW-m	MT20	5.0	6.0	2.25	2.00
D TMW-w	MT20	2.0	4.0		
E TTWW-m	MT20	5.0	6.0	2.25	2.00
F TMVW-p	MT20	4.0	4.0	1.50	2.00
G BMV1-p	MT20	3.0	6.0		
H BMWW-t	MT20	5.0	6.0		
I BS-t	MT20	5.0	6.0		
J BMWWW-t	MT20	5.0	6.0		
K BMWW-t	MT20	5.0	6.0		
L BMV1-p	MT20	3.0	6.0		




Structural component only
DWG# T-2007115 *ML*

JOB NAME	TRUSS NAME	QUANTITY	PLY	JOB DESC.	GREEN PARK HOMES	DRWG NO.
408152	T48	1	1	TRUSS DESC.		

Tamarack Roof Truss, Burlington

Version 8.310 S Oct 29 2019 Mike Industries, Inc. Sat Apr 26 11:29:43 2020 Page 1
ID:17VF?aG0E03cRUj6X1jSkzjWYK-BMKSFn?qzurVvRu10Nkp3g47HsGXldizDyo5IzNCOM



LUMBER N. L. G. A. RULES **CHORDS** SIZE LUMBER DESCR. **BEARINGS** **DESIGN CRITERIA** **SPACING** **LOADING IN FLAT SECTION BASED ON A SLOPE OF 8.00/12** **THIS TRUSS IS DESIGNED FOR RESIDENTIAL OR SMALL BUILDING REQUIREMENTS OF PART 9, NBC 2010, NBC 2015** **THIS DESIGN COMPLIES WITH:** **55% OF 31.3 P.S.F. G.S.L. PLUS 8.4 P.S.F. RAIN LOAD EQUALS 25.6 P.S.F. SPECIFIED ROOF LIVE LOAD** **ALLOWABLE DEFL.(LL)= L/360 (0.66')** **CALCULATED VERT. DEFL.(LL)= L/999 (0.02')** **ALLOWABLE DEFL.(TL)= L/360 (0.66')** **CALCULATED VERT. DEFL.(TL)= L/999 (0.13')** **CSI: TC=0.42/1.00 (E-F:1), BC=0.32/1.00 (J-K:4), WB=0.47/1.00 (C-K:1), SS=0.19/1.00 (E-F:1)** **DOL LUMBER=1.00 NAIL=1.00 LS BEND=1.10 COMP=1.10 SHEAR=1.10 TENS=1.10** **COMPANION LIVE LOAD FACTOR = 1.00** **TRUSS PLATE MANUFACTURER IS NOT RESPONSIBLE FOR QUALITY CONTROL IN THE TRUSS MANUFACTURING PLANT.** **NAIL VALUES** **PLATE GRIP(DRY) SHEAR SECTION (PSI) (PLI) (PLI)** **MAX MIN MAX MIN MAX MIN** **MT20 618 354 1687 758 1987 1688** **PLATE PLACEMENT TOL. = 0.250 inches** **PLATE ROTATION TOL. = 5.0 Deg.** **JSI GRIP= 0.87 (C) (INPUT = 0.90)** **JSI METAL= 0.41 (C) (INPUT = 1.00)**

CHORDS	SIZE	LUMBER	DESCR.
A - D	2x4	DRY No.2	SPF
D - E	2x4	DRY No.2	SPF
E - F	2x4	DRY No.2	SPF
K - B	2x4	DRY No.2	SPF
G - F	2x4	DRY No.2	SPF
K - I	2x4	DRY No.2	SPF
I - G	2x4	DRY No.2	SPF
ALL WEBS EXCEPT	2x3	DRY No.2	SPF

DRY: SEASONED LUMBER.

PLATES (tablets in inches)

JT	TYPE	PLATES	W	LEN	Y	X
B	TMV+p	MT20	3.0	4.0		
C	TMVW-l	MT20	4.0	4.0	2.00	1.75
D	TTW-m	MT20	4.0	4.0		
E	TTW-m	MT20	5.0	8.0	2.25	2.00
F	TMVW+p	MT20	4.0	4.0	1.50	2.00
G	BMV1+p	MT20	3.0	4.0		
H	BMVW-l	MT20	4.0	8.0		
I	BS-l	MT20	3.0	6.0		
J	BMVW+l	MT20	4.0	9.0		
K	BMVW1-l	MT20	4.0	8.0		

DIMENSIONS, SUPPORTS AND LOADINGS SPECIFIED BY FABRICATOR TO BE VERIFIED BY BUILDING DESIGNER

BEARINGS	FACTORED GROSS REACTION	MAXIMUM FACTORED GROSS REACTION	INPUT BRG	REQD BRG
JT	VERT	HORZ	DOWN	HORZ
K	1039	0	1039	0
G	914	0	914	0

A SUITABLE HANGER/MECHANICAL CONNECTION IS REQUIRED AT JOINT G. MINIMUM BEARING LENGTH AT JOINT G = 3-8.

UNFACTORED REACTIONS

JT	COMBINED	SNOW	LIVE	PERM LIVE	WIND	DEAD	SOIL
K	732	494 / 0	0 / 0	0 / 0	0 / 0	238 / 0	0 / 0
G	646	424 / 0	0 / 0	0 / 0	0 / 0	222 / 0	0 / 0

BEARING MATERIAL TO BE SPF NO.2 OR BETTER AT JOINT(S) K

BRACING

TOP CHORD TO BE SHEATHED OR MAX. PURLIN SPACING = 8.12 FT.
MAX. UNBRACED BOTTOM CHORD LENGTH = 10.00 FT OR RIGID CEILING DIRECTLY APPLIED.

ALL PITCH BREAKS AND PERIMETER CORNER JOINTS MUST BE Laterally RESTRAINED.

LOADING

TOTAL LOAD CASES: (4)

CHORDS	MAX. FACTORED	FACTORED	WEBS	MAX. FACTORED
MEMB.	FORCE (LBS)	VERT. LOAD (PLF)	CS1 (LC)	MEMB. FORCE (LBS)
FR-TO		FROM TO	LENGTH	FR-TO
A-B	0 / 28	-91.8 -91.8	0.12 (1)	10.00
B-C	0 / 18	-91.8 -91.8	0.22 (1)	10.00
C-D	-916 / 0	-91.8 -91.8	0.18 (1)	6.24
D-E	-806 / 0	-91.8 -91.8	0.10 (1)	6.25
E-F	-821 / 0	-91.8 -91.8	0.42 (1)	6.12
K-B	-265 / 0	0.0 0.0	0.03 (1)	7.81
G-F	-868 / 0	0.0 0.0	0.10 (1)	7.81
K-J	0 / 983	-18.5 -18.5	0.32 (4)	10.00
J-I	0 / 731	-18.5 -18.5	0.31 (4)	10.00
I-H	0 / 731	-18.5 -18.5	0.31 (4)	10.00
H-G	0 / 0	-18.5 -18.5	0.15 (4)	10.00




Structural component only
DWG# T-2007116

JOB NAME	TRUSS NAME	QUANTITY	PLY	JOB DESC.	GREEN PARK HOMES	DRWG NO.
408152	T49	1	1	TRUSS DESC.		

Tamarack Roof Truss, Burlington

Version 8.310 S Oct 29 2019 Mitek Industries, Inc. Sat Apr 25 11:29:44 2020 Page 1
ID:7VF?aG0E03cRUj8X1iSkzWYK-IYUqS70SkCzMXbTYa4F2bucKSGdH15VRCilLdkzNCO



Scale: 3/8"=1'

LUMBER	N. L. G. A. RULES	CHORDS	SIZE	LUMBER	DESCR.
A - D	2x4	DRY	No.2	SPF	
D - F	2x4	DRY	No.2	SPF	
K - B	2x4	DRY	No.2	SPF	
G - F	2x4	DRY	No.2	SPF	
K - I	2x4	DRY	No.2	SPF	
I - G	2x4	DRY	No.2	SPF	

ALL WEBS 2x3 DRY No.2
EXCEPT

DRY: SEASONED LUMBER.

PLATES (table in inches)

JT TYPE	PLATES	W	LEN	Y	X
B TMVW-1	MT20	4.0	6.0	2.00	3.00
C TMVW-1	MT20	4.0	4.0	2.00	1.75
D TTW-p	MT20	4.0	4.0		
E TMVW-1	MT20	4.0	6.0		
F TMV-p	MT20	3.0	4.0		
G BMVW-1	MT20	4.0	4.0		
H BMVW-1	MT20	4.0	9.0		
I BS-1	MT20	3.0	8.0		
J BMVW-1	MT20	4.0	8.0		
K BMV-1-p	MT20	3.0	4.0		

DIMENSIONS, SUPPORTS AND LOADINGS SPECIFIED BY FABRICATOR TO BE VERIFIED BY BUILDING DESIGNER

BEARINGS	FACTORED GROSS REACTION	MAXIMUM FACTORED GROSS REACTION	INPUT BRG	REQD BRG
JT	VERT	DOWN	UP	IN-SX
K	1039	0	0	5-8
G	914	0	0	MECHANICAL

A SUITABLE HANGER/MECHANICAL CONNECTION IS REQUIRED AT JOINT G. MINIMUM BEARING LENGTH AT JOINT G = 3-8.

UNFACTORED REACTIONS
1ST LC CASE MAX/MIN COMPONENT REACTIONS

JT	COMBINED	SNOW	LIVE	PERM LIVE	WIND	DEAD	SOIL
K	732	494 / 0	0 / 0	0 / 0	0 / 0	238 / 0	0 / 0
G	848	424 / 0	0 / 0	0 / 0	0 / 0	222 / 0	0 / 0

BEARING MATERIAL TO BE SPF NO.2 OR BETTER AT JOINT(S) K

BRACING
TOP CHORD TO BE SHEATHED OR MAX. PURLIN SPACING = 5.66 FT.
MAX. UNBRACED BOTTOM CHORD LENGTH = 10.00 FT OR RIGID CEILING DIRECTLY APPLIED.

ALL PITCH BREAKS AND PERIMETER CORNER JOINTS MUST BE Laterally RESTRAINED.

LOADING

TOTAL LOAD CASES: (4)

CHORDS	MEMB.	MAX. FACTORED FORCE (LBS)	FACTORED VERT. LOAD (PLF)	MAX. FACTORED VERT. LOAD (LC1)	MAX. FACTORED VERT. LOAD (LC)	UNBRACED LENGTH	WEBS	MEMB.	MAX. FACTORED FORCE (LBS)	MAX. FACTORED VERT. LOAD (LC)
FR-TO							FR-TO			
A-B	0 / 28	-91.8	-91.8	0.12 (1)	10.00	J-C	-114 / 23	0.02 (1)		
B-C	-1135 / 0	-91.8	-91.8	0.26 (1)	5.66	C-H	-418 / 0	0.22 (1)		
C-D	-799 / 0	-91.8	-91.8	0.25 (1)	8.25	H-D	0 / 407	0.09 (1)		
D-E	-799 / 0	-91.8	-91.8	0.15 (1)	6.25	E-H	-39 / 37	0.02 (1)		
E-F	0 / 17	-91.8	-91.8	0.19 (1)	10.00	B-J	0 / 1051	0.24 (1)		
K-B	-998 / 0	0.0	0.0	0.10 (1)	7.81	E-G	-1028 / 0	0.44 (1)		
G-F	-129 / 0	0.0	0.0	0.02 (1)	7.81					
K-J	0 / 0	-18.5	-18.5	0.10 (4)	10.00					
J-I	0 / 1034	-18.5	-18.5	0.29 (4)	10.00					
I-H	0 / 1034	-18.5	-18.5	0.29 (4)	10.00					
H-G	0 / 722	-18.5	-18.5	0.26 (4)	10.00					

TOTAL WEIGHT = 67 lb

DESIGN CRITERIA

SPECIFIED LOADS:
TOP CH. LL = 25.6 PSF
DL = 8.0 PSF
BOT CH. LL = 0.0 PSF
DL = 7.4 PSF
TOTAL LOAD = 39.0 PSF

SPACING = 24" I.N.C/G

THIS TRUSS IS DESIGNED FOR RESIDENTIAL OR SMALL BUILDING REQUIREMENTS OF PART 9, NBCC 2010, NBCC 2015

THIS DESIGN COMPLIES WITH:
- PART 9 OF BCBC 2018, CBC 2012, ABC 2019
- PART 9 OF CBC 2012 (2019 AMENDMENT)
- CSA 088-09, CSA 088-14
- TPIC 2011, TPIC 2014

(65% OF 31.3 P.S.F. G.S.L. PLUS 8.4 P.S.F. RAIN LOAD) EQUALS 25.8 P.S.F., SPECIFIED ROOF LIVE LOAD

ALLOWABLE DEFL.(LL) = L/360 (0.55")
CALCULATED VERT. DEFL.(LL) = L/999 (0.03")
ALLOWABLE DEFL.(TL) = L/360 (0.55")
CALCULATED VERT. DEFL.(TL) = L/999 (0.10")

CSI: TC=0.28/1.00 (B-C:1), BC=0.29/1.00 (H-J:4),
WB=0.44/1.00 (E-G:1), SS=0.19/1.00 (B-C:1)

DOL LUMBER=1.00 NAIL=1.00 LB BEND=1.10
COMP=1.10 SHEAR=1.10 TENS=1.10

COMPANION LIVE LOAD FACTOR = 1.00


TRUSS PLATE MANUFACTURER IS NOT RESPONSIBLE FOR QUALITY CONTROL IN THE TRUSS MANUFACTURING PLANT.

NAIL VALUES
PLATE GRIP(DRY) SHEAR SECTION
(PSI) (PL) (PL)
MAX MIN MAX MIN MAX MIN
MT20 618 354 1687 788 1687 1658

PLATE PLACEMENT TOL. = 0.250 inches

PLATE ROTATION TOL. = 5.0 Deg.


JSI GRIP = 0.84 (G) (INPUT = 0.90)
JSI METAL = 0.36 (I) (INPUT = 1.00)



Structural component only
DWG# T-2007117

Tamareck Roof Truss, Burlington

Version 8.310 S Oct 29 2019 Mitek Industries, Inc. Sat Apr 25 11:29:48 2020 Page 1
ID:7vF7aG0E03cRUj8X1jSrkzWYK-cw0b1p1j3pD3mvcKIViWhjg3K9V4MkIBBSheczNCOJ



TOTAL WEIGHT = 52 lb (M/F)

LUMBER

N. L. G. A. RULES	CHORDS	SIZE	LUMBER
A - C	2x4	DRY	No.2
C - D	2x4	DRY	No.2
D - F	2x4	DRY	No.2
J - B	2x4	DRY	No.2
G - E	2x4	DRY	No.2
J - G	2x4	DRY	No.2
ALL WEBS	2x3	DRY	No.2

EXCEPT
DRY: SEASONED LUMBER.

PLATES (table in inches)						
JT	TYPE	PLATES	W	LEN	Y	X
B	TMVW-1	MT20	4.0	4.0	2.00	1.25
C	TTWW-m	MT20	5.0	6.0	2.25	2.25
D	TTW-m	MT20	4.0	4.0		
E	TMVW-1	MT20	4.0	4.0	2.00	1.25
G	BMV1-p	MT20	3.0	4.0		
H	BMVWW-1	MT20	4.0	6.0	2.00	1.50
I	BMVWW-1	MT20	4.0	4.0		
J	BMV1-p	MT20	3.0	4.0		

DIMENSIONS, SUPPORTS AND LOADINGS SPECIFIED BY FABRICATOR TO BE VERIFIED BY BUILDING DESIGNER

BEARINGS

	FACTORED GROSS REACTION	MAXIMUM FACTORED GROSS REACTION	INPUT BRG	REQD BRG
JT	VERT 728	DOWN 728	0	0
J	HORIZ 0	HORIZ 0	0	0
G	UPLIFT 0	UPLIFT 0	5-8	5-8

A SUITABLE HANGER/MECHANICAL CONNECTION IS REQUIRED AT JOINT J. MINIMUM BEARING LENGTH AT JOINT J = 1-8.

UNFACTORED REACTIONS

1ST CASE	MAX/MIN. COMPONENT REACTIONS
JT	SNOW 3487.0
J	LIVE 0.0
G	PERM. LIVE 0.0
	WIND 0.0
	DEAD 163.7
	SOIL 0.0

BEARING MATERIAL TO BE SPF NO.2 OR BETTER AT JOINT(S) G

BRACING
TOP CHORD TO BE SHEATHED OR MAX. PURLIN SPACING = 0.25 FT.
MAX. UNBRACED BOTTOM CHORD LENGTH = 10.00 FT OR RIGID CEILING DIRECTLY APPLIED.

ALL PITCH BREAKS AND PERIMETER CORNER JOINTS MUST BE Laterally RESTRAINED.

LOADING							
TOTAL LOAD CASES: (4)							
CHORDS				WEBS			
MEMB.	MAX. FACTORED FORCE (LBS)	FACTORED VERT. LOAD (PLF)	MAX. CSI (LC)	MEMB.	MAX. FACTORED FORCE (LBS)	MAX. CSI (LC)	
FR-TO		FROM TO		FR-TO			
A-B	0.728	-91.8	-91.8 0.12 (1)	10.00	I-C	-78.18	0.02 (1)
B-C	-435.7	-91.8	-91.8 0.28 (1)	8.25	C-H	-4.7	0.00 (1)
C-D	-386.7	-91.8	-91.8 0.02 (1)	6.26	H-D	-52.19	0.03 (1)
D-E	-434.7	-91.8	-91.8 0.28 (1)	8.25	E-I	0.415	0.09 (1)
E-F	0.728	-91.8	-91.8 0.12 (1)	10.00	H-E	0.414	0.09 (1)
J-B	-888.7	0.0	0.0 0.08 (1)	7.81			
G-E	-888.7	0.0	0.0 0.08 (1)	7.81			
J-I	0.0	-18.5	-18.5 0.10 (4)	10.00			
I-H	0.387	-18.5	-18.5 0.14 (4)	10.00			
H-G	0.0	-18.5	-18.5 0.10 (4)	10.00			

DESIGN CRITERIA

SPECIFIED LOADS:
TOP CH. LL = 25.8 PSF
DL = 6.0 PSF
BOT CH. LL = 0.0 PSF
DL = 7.4 PSF
TOTAL LOAD = 39.0 PSF

SPACING = 24.0 IN. C/C

LOADING IN FLAT SECTION BASED ON A SLOPE OF 8.00/12

THIS TRUSS IS DESIGNED FOR RESIDENTIAL OR SMALL BUILDING REQUIREMENTS OF PART 9, NBCC 2010, NBCC 2015

THIS DESIGN COMPLIES WITH:
- PART 9 OF NBCC 2010, OBC 2012, ABC 2019
- PART 9 OF OBC 2012 (2019 AMENDMENT)
- CSA 088-09, CSA 088-14
- TPIC 2011, TPIC 2014

(65 % OF 31.3 P.S.F. G.S.L. PLUS 8.4 P.S.F. RAIN LOAD) EQUALS 25.8 P.S.F. SPECIFIED ROOF LIVE LOAD

ALLOWABLE DEFL.(LL) = L/360 (0.36")
CALCULATED VERT. DEFL.(LL) = L/889 (0.01")
ALLOWABLE DEFL.(TL) = L/360 (0.36")
CALCULATED VERT. DEFL.(TL) = L/889 (0.02")

CSI: TO=0.28/1.00 (B-C:1), BC=0.14/1.00 (H-I:4), WS=0.09/1.00 (B-I:1), SS=0.18/1.00 (B-C:1)

COL LUMBER=1.00 NAIL=1.00 LB BEND=1.10 COMP=1.10 SHEAR=1.10 TENS=1.10

COMPANION LIVE LOAD FACTOR = 1.00


TRUSS PLATE MANUFACTURER IS NOT RESPONSIBLE FOR QUALITY CONTROL IN THE TRUSS MANUFACTURING PLANT.

NAIL VALUES
PLATE GRIP(DRY) SHEAR SECTION (PSI) (PLI) (PLI)
MAX MIN MAX MIN MAX MIN
MT20 618 354 1667 788 1987 1658


PLATE PLACEMENT TOL. = 0.250 inches

PLATE ROTATION TOL. = 5.0 Deg.

JSI GRIP = 0.88 (B) (INPUT = 0.90)
JSI METAL = 0.22 (B) (INPUT = 1.00)



Structural component only
DWG# T-2007119



LUMBER

N. L. G. A. RULES	SIZE	LUMBER	DESCR.
CHORDS	2x4	DRY	SPF
F - A	2x4	DRY	SPF
A - C	2x4	DRY	SPF
D - C	2x4	DRY	SPF
F - D	2x4	DRY	SPF
ALL WEBS	2x3	DRY	SPF
DRY: SEASONED LUMBER.			

PLATES (table in inches)

JT TYPE	PLATES	W	LEN	Y	X
A	TMVW-1	MT20	4.0	6.0	
B	TMVW-w	MT20	2.0	4.0	
C	TMVW-1	MT20	4.0	6.0	
D	BMV1+p	MT20	3.0	4.0	
E	BMVWW-1	MT20	4.0	9.0	
F	BMV1+p	MT20	3.0	4.0	

DIMENSIONS, SUPPORTS AND LOADINGS SPECIFIED BY FABRICATOR TO BE VERIFIED BY BUILDING DESIGNER

BEARINGS

FACTORED	MAXIMUM FACTORED	INPUT	REQD
GROSS REACTION	GROSS REACTION	BRG	BRG
DOWN	DOWN	IN-SX	IN-SX
JT F 820 0	820 0	5-8	5-8
D 820 0	820 0	5-8	5-8

UNFACTORED REACTIONS

1ST CASE	MAX./MIN. COMPONENT REACTIONS	WIND	DEAD	SOIL
JT COMBINED	SNOW	LIVE	PERM. LIVE	
F 448 239/0	0/0	0/0	209/0	0/0
D 448 239/0	0/0	0/0	209/0	0/0

BEARING MATERIAL TO BE SPF NO.2 OR BETTER AT JOINT(S) F, D
 BRACING
 TOP CHORD TO BE SHEATHED OR MAX. PURLIN SPACING = 5.52 FT.
 MAX. UNBRACED BOTTOM CHORD LENGTH = 10.00 FT OR RIGID CEILING DIRECTLY APPLIED.
 ALL PITCH BREAKS AND PERIMETER CORNER JOINTS MUST BE Laterally RESTRAINED.

LOADING

TOTAL LOAD CASES: (4)

CHORDS					WEBS				
MAX. FACTORED		FACTORED		MAX. UNBRAC LENGTH	MAX. FACTORED		MAX. UNBRAC LENGTH	MAX. FACTORED	
MEMB.	FORCE (LBS)	VERT. LOAD (PLF)	LC1 MAX CSI (LC)		MEMB.	FORCE (LBS)			MAX CSI (LC)
FR-TO		FROM	TO		FR-TO				
F-A	-583 / 0	0.0	0.0	0.11 (1)	7.81	A-E	0 / 792	0.24 (1)	
A-B	-895 / 0	-114.3	-114.3	0.55 (1)	5.52	E-B	-858 / 0	0.15 (1)	
B-C	-895 / 0	-114.3	-114.3	0.55 (1)	5.52	E-C	0 / 792	0.24 (1)	
D-C	-583 / 0	0.0	0.0	0.11 (1)	7.81				
F-E	0 / 0	-18.5	-18.5	0.13 (4)	10.00				
E-D	0 / 0	-18.5	-18.5	0.13 (4)	10.00				

DESIGN CRITERIA

SPECIFIED LOADS:

TOP CH.	LL	PSF
DL	15.0	PSF
DL	7.4	PSF
TOTAL LOAD	48.0	PSF

SPACING = 24.0 IN. C/C

LOADING IN FLAT SECTION BASED ON A SLOPE OF 0.00/12

THIS TRUSS IS DESIGNED FOR RESIDENTIAL OR SMALL BUILDING REQUIREMENTS OF PART 9, NBC 2010, NBC 2015

THIS DESIGN COMPLIES WITH:
 - PART 9 OF NBC 2010, NBC 2012, ABC 2019
 - PART 9 OF NBC 2012 (2019 AMENDMENT)
 - CSA 086-09, CSA 088-14
 - TPIC 2011, TPIC 2014

(65% OF 31.3 P.S.F. G.S.L. PLUS 8.4 P.S.F. RAIN LOAD) EQUALS 25.8 P.S.F. SPECIFIED ROOF LIVE LOAD

ALLOWABLE DEFL.(LL) = L/360 (0.31')
 CALCULATED VERT. DEFL.(LL) = L/999 (0.01')
 ALLOWABLE DEFL.(TL) = L/360 (0.31')
 CALCULATED VERT. DEFL.(TL) = L/999 (0.03')

CSI: TC=0.55/1.00 (B-C:1), BC=0.13/1.00 (E-F:4), WB=0.24/1.00 (A-E:1), CSI=0.34/1.00 (A-B:1)

DOL LUMBER=1.00 NAIL=1.00 LS BEND=1.10 COMP=1.10 SHEAR=1.10 TENS=1.10

COMPANION LIVE LOAD FACTOR = 1.00
 FLAT ROOF FACTOR = 0.75

TRUSS PLATE MANUFACTURER IS NOT RESPONSIBLE FOR QUALITY CONTROL IN THE TRUSS MANUFACTURING PLANT


NAIL VALUES

PLATE GRIP(DRY)	SHEAR	SECTION
(PSI)	(PLI)	(PU)
MAX	MIN	MAX
MT20	818	354
	1887	788
	1887	1886

PLATE PLACEMENT TOL = 0.250 inches

PLATE ROTATION TOL = 5.0 Deg.


JSI GRIP= 0.81 (A) (INPUT = 0.90)
 JSI METAL= 0.24 (A) (INPUT = 1.00)



Structural component only
 DWG# T-2007120

JOB NAME	TRUSS NAME	QUANTITY	PLY	JOB DESC.	DRWG NO.
408152	G52	1	1	GREEN PARK HOMES	
Tamarack Roof Truss, Burlington				TRUSS DESC.	

Version 8.310 9 Oct 2019 Mytek Industries, Inc. Sat Apr 25 11:28:28 2020 Page 1
ID:7vF7aG0E03cRUj6X1tSrkzIWK-7Twn6ipQVHydc8EieizlyWyePpDiHyU4WOpV3IzNCOB



LUMBER

N. L. G. A. RULES

CHORDS	SIZE	DRY	LUMBER
L - A	2x4	DRY	No.2
A - F	2x4	DRY	No.2
G - F	2x4	DRY	No.2
L - G	2x4	DRY	No.2

ALL WEBS 2x3 DRY No.2
ALL GABLE WEBS 2x3 DRY No.2
SPF

DRY: SEASONED LUMBER.

GABLE STUDS SPACED AT 2-0-0 OC.

PLATES (table is in inches)

JT TYPE	PLATES	W	LEN	Y	X
A TMV+p	MT20	3.0	4.0		
B, C, D, E					
B TMV+w	MT20	2.0	4.0		
F TMV+p	MT20	3.0	4.0		
G BMV1+p	MT20	3.0	4.0		
H, I, J, K					
H BMV1+w	MT20	2.0	4.0		
L BMV1+p	MT20	3.0	4.0		

DIMENSIONS, SUPPORTS AND LOADINGS SPECIFIED BY FABRICATOR TO BE VERIFIED BY BUILDING DESIGNER

PROVIDE ADEQUATE DRAINAGE TO PREVENT PONDING

BEARINGS

THIS TRUSS DESIGNED FOR CONTINUOUS BEARINGS.

THIS TRUSS REQUIRES RIGID SHEATHING ON EXPOSED FACE.

BEARING MATERIAL TO BE SPF NO.2 OR BETTER AT JOINT(S)

BRACING

TOP CHORD TO BE SHEATHED OR MAX. PURLIN SPACING = 10.00 FT.

MAX. UNBRACED BOTTOM CHORD LENGTH = 10.00 FT OR RIGID CEILING DIRECTLY APPLIED.

ALL PITCH BREAKS AND PERIMETER CORNER JOINTS MUST BE Laterally RESTRAINED.

LOADING

TOTAL LOAD CASES: (4)

CHORDS				WEBS			
MEMB.	MAX. FACTORED FORCE (LBS)	VERT. LOAD LC1 (PLF)	MAX. CSI (LC)	MEMB.	MAX. FACTORED FORCE (LBS)	MAX. CSI (LC)	
FR-TO	FROM	TO	LENGTH	FR-TO	FROM	TO	
L-A	-101 / 0	0.0	0.0 0.03 (1)	7.81	K-B	-245 / 0	0.05 (1)
A-B	-8 / 0	-114.3 -114.3	0.08 (1)	10.00	J-C	-224 / 0	0.05 (1)
B-C	-8 / 0	-114.3 -114.3	0.08 (1)	10.00	I-D	-237 / 0	0.05 (1)
C-D	-8 / 0	-114.3 -114.3	0.07 (1)	10.00	H-E	-186 / 0	0.04 (1)
D-E	-8 / 0	-114.3 -114.3	0.07 (1)	10.00			
E-F	-8 / 0	-114.3 -114.3	0.05 (1)	10.00			
G-F	-84 / 0	0.0	0.0 0.02 (1)	7.81			
L-K	0 / 8	-18.5 -18.5	0.02 (4)	10.00			
K-J	0 / 8	-18.5 -18.5	0.02 (4)	10.00			
J-I	0 / 8	-18.5 -18.5	0.02 (4)	10.00			
I-H	0 / 8	-18.5 -18.5	0.02 (4)	10.00			
H-G	0 / 8	-18.5 -18.5	0.02 (1)	10.00			

DESIGN CRITERIA

SPECIFIED LOADS:

TOP CH. LL = 25.8 PSF
DL = 15.0 PSF

BOT CH. LL = 0.0 PSF
DL = 7.4 PSF

TOTAL LOAD = 48.0 PSF

SPACING = 24.0 IN. C/D

LOADING IN FLAT SECTION BASED ON A SLOPE OF 0.00/12

THIS TRUSS IS DESIGNED FOR RESIDENTIAL OR SMALL BUILDING REQUIREMENTS OF PART 9, NBC 2010, NBC 2015

THIS DESIGN COMPLIES WITH:

- PART 9 OF CBC 2019, CBC 2012, ABC 2019
- PART 9 OF CBC 2012 (2019 AMENDMENT)
- CSA 088-09, CSA 088-14
- TPIC 2011, TPIC 2014

(55 % OF 31.3 P.S.F. G.S.L. PLUS 8.4 P.S.F. RAIN LOAD) EQUALS 25.8 P.S.F. SPECIFIED ROOF LIVE LOAD

CSI: TC=0.08/1.00 (A-B:1), BC=0.02/1.00 (K-L:4), WB=0.08/1.00 (B-K:1), GS=0.13/1.00 (A-B:1)

DOL LUMBER=1.00 NAIL=1.00 LS BEND=1.10 COMP=1.10 SHEAR=1.10 TENS=1.10

COMPANION LIVE LOAD FACTOR = 1.00
FLAT ROOF FACTOR = 0.75

TRUSS PLATE MANUFACTURER IS NOT RESPONSIBLE FOR QUALITY CONTROL IN THE TRUSS MANUFACTURING PLANT.

NAIL VALUES

PLATE	GRIP (DRY)	SHEAR	SECTION
	(PSI)	(PLI)	(PLI)
MT20	618	334	1887
	618	334	1887

PLATE PLACEMENT TOL. = 0.250 inches

PLATE ROTATION TOL. = 5.0 Deg.


JSI GRIP = 0.17 (K) (INPUT = 0.90)
JSI METAL = 0.07 (K) (INPUT = 1.00)



Structural component only
DWG# T-2007104

Tamarack Pool Truss, Burlington

Version 8.310 S Oct 29 2019 Mittek Industries, Inc. Sat Apr 25 11:28:48 2020 Page 1
ID:17vF?aG0E03cRUj6X1jSrKzIWYK-YJ7LIV3zoQTn?DmjpWk_mkn0t?2zwn17VgZmVzNCOH



LUMBER				
N. L. G. A. RULES				
CHORDS		SIZE	LUMBER	DESCR.
F - A	2x4	DRY	No.2	SPF
A - C	2x6	DRY	No.2	SPF
D - C	2x4	DRY	No.2	SPF
F - D	2x6	DRY	No.2	SPF
ALL WEBS		2x3	DRY	No.2
DRY: SEASONED LUMBER.				

PLATES (table is in inches)						
JT	TYPE	PLATES	W	LEN	Y	X
A	TMVW-I	MT20	5.0	6.0		
B	TMVW+V	MT20	3.0	6.0		
C	TMVW-I	MT20	5.0	6.0		
D	BMV1+p	MT20	3.0	6.0		
E	BMVWW-I	MT20	5.0	8.0		
F	BMV1+p	MT20	3.0	8.0		

DIMENSIONS, SUPPORTS AND LOADINGS SPECIFIED BY FABRICATOR TO BE VERIFIED BY BUILDING DESIGNER

PROVIDE ADEQUATE DRAINAGE TO PREVENT PONDING

BEARINGS		FACTORED GROSS REACTION		MAXIMUM FACTORED GROSS REACTION		INPUT BRG	REQD BRG
	VERT	HORZ	DOWN	HORZ	UPLIFT	IN-SX	IN-SX
JT	988	0	988	0	0	MECHANICAL	
F							
D	1012	0	1012	0	0	MECHANICAL	

A SUITABLE HANGER/MECHANICAL CONNECTION IS REQUIRED AT JOINT F, D. MINIMUM BEARING LENGTH AT JOINT F = 3-8, JOINT D = 3-8.

TOTAL WEIGHT = 51 lb
(MIR)

DESIGN CRITERIA

SPECIFIED LOADS:

TOP CH.	LL =	25.8	PSF
	DL =	15.0	PSF
BOT CH.	LL =	0.0	PSF
	DL =	7.4	PSF
TOTAL LOAD	=	48.0	PSF

SPACING = 24.0 IN. C/C

LOADING IN FLAT SECTION BASED ON A SLOPE
OF 0.00/12

THIS TRUSS IS DESIGNED FOR RESIDENTIAL OR
SMALL BUILDING REQUIREMENTS OF PART 9,
NBCC 2010, NBCC 2015

THIS DESIGN COMPLIES WITH:
 - PART 9 OF BCBC 2018, OBC 2012, ABC 2019
 - PART 9 OF OBC 2012 (2019 AMENDMENT)
 - CSA 088-08, CSA 088-14
 - TPIG 2011, TPIG 2014

(55 % OF 31.3 P.S.F. G.S.L. PLUS 8.4 P.S.F. RAIN LOAD) EQUALS 25.6 P.S.F. SPECIFIED ROOF LIVE LOAD

ALLOWABLE DEFL.(LL) = $L/360$ (0.31")
CALCULATED VERT. DEFL.(LL) = $L/999$ (0.02")
ALLOWABLE DEFL.(TL) = $L/360$ (0.31")
CALCULATED VERT. DEFL.(TL) = $L/999$ (0.04")

CSI: TC=0.24/1.00 (B-C:1), BC=0.24/1.00 (D-E:1),
WB=0.35/1.00 (A-E:1), SSI=0.29/1.00 (E-F:1)

DOL LUMBER=1.00 NAIL=1.00 LS BEND=1.00
COMP=1.00 SHEAR=1.00 TENS= 1.00

COMPANION LIVE LOAD FACTOR = 1.00
FLAT ROOF FACTOR = 0.76

TRUSS PLATE MANUFACTURER IS NOT RESPONSIBLE FOR QUALITY CONTROL IN THE TRUSS MANUFACTURING PLANT.

NAIL VALUES

PLATE	GRIP(DRY)		SHEAR		SECTION	
	{PSI}		{PLI}		{PLI}	
	MAX	MIN	MAX	MIN	MAX	MIN
MT20	618	354	1867	788	1987	1658

PLATE PLACEMENT TOL. = 0.250 inches

PLATE ROTATION TOL. = 5.0 Deg.

JSI GRIP= 0.76 (E) (INPUT = 0.80)
JSI METAL= 0.32 (E) (INPUT = 1.00)



Structural component only
DWG# T-2007121

UNFACTORED REACTIONS

1ST LCASE		MAX. MIN. COMPONENT REACTIONS					
JT	COMBINED	SNOW	LIVE	PERM. LIVE	WIND	DEAD	SOIL
F	705	427/0	0/0	0/0	0/0	279/0	0/0
D	722	439/0	0/0	0/0	0/0	283/0	0/0

BRACING

TOP CHORD TO BE SHEATHED OR MAX. PURLIN SPACING = 8.25 FT.
MAX. UNBRACED BOTTOM CHORD LENGTH = 10.00 FT OR RIGID CEILING DIRECTLY APPLIED

ALL PITCH BREAKS AND PERIMETER CORNER JOINTS MUST BE Laterally RESTRAINED

LOADING

TOTAL LOAD CASES: (4)

CHORDS				WEBS			
MAX. FACTORED		FACTORED		MAX. FACTORED		MAX. FACTORED	
MEMB.	FORCE (LBS)	VERT. LOAD	LC1 MAX (PLI)	MAX. UNBRAC	MEMB.	FORCE (LBS)	MAX. CSI (LC)
FR-TO		FROM	TO	LENGTH	FR-TO		
F-A	-848 / 0	0.0	0.0	0.23 (1)	7.45	A-E	0
A-B	-869 / 0	-114.3	-114.3	0.24 (1)	6.26	E-B	-832 / 0
B-C	-869 / 0	-114.3	-114.3	0.24 (1)	6.25	E-C	0 / 1072
D-C	-848 / 0	0.0	0.0	0.23 (1)	7.45		0.36 (1)
F-G	0 / 0	-18.5	-18.5	0.24 (1)	10.00		
G-H	0 / 0	-18.5	-18.5	0.24 (1)	10.00		
H-E	0 / 0	-18.5	-18.5	0.24 (1)	10.00		
E-I	0 / 0	-18.5	-18.5	0.24 (1)	10.00		
I-J	0 / 0	-18.5	-18.5	0.24 (1)	10.00		
J-D	0 / 0	-18.5	-18.5	0.24 (1)	10.00		

FACTORED CONCENTRATED LOADS (LBS)


JT	LOC.	LG1	MAX-	MAX+	FACE	DIR.	TYPE	HEEL	CONN
G	1-9-12	-180	-190	---	FRONT	VERT	TOTAL	---	C1
H	3-9-12	-190	-190	---	FRONT	VERT	TOTAL	---	C1
I	5-9-12	-180	-190	---	FRONT	VERT	TOTAL	---	C1
J	7-9-12	-180	-190	---	FRONT	VERT	TOTAL	---	C1

CONNECTION REQUIREMENTS

1) C1: A SUITABLE HANGER/MECHANICAL CONNECTION IS REQUIRED

JOB NAME	TRUSS NAME	QUANTITY	PLY	JOB DESC.	TRUSS DESC.	DRWG NO.
408152	T54	1	2	GREEN PARK HOMES		
Tamarack Roof Truss, Burlington						

Version 8.310 S Oct 29 2019 MitEK Industries, Inc. Sat Apr 25 11:29:50 2020 Page 1
ID:7vF?aG0E03cRUj6X1jSrkzWYK-UIF5jA4DJ2jVFWw6xLMSr9sN4hadRnVJap9lrOzNCOF



LUMBER	N. L. G. A. RULES	CHORDS	SIZE	LUMBER	DESCR.
A - C	2x4	DRY	No.2	SPF	
D - C	2x4	DRY	No.2	SPF	
A - D	2x8	DRY	No.2	SPF	
ALL WEBS	2x3	DRY	No.2	SPF	
DRY: SEASONED LUMBER.					

DESIGN CONSISTS OF 2 TRUSSES BUILT SEPARATELY THEN FASTENED TOGETHER AS FOLLOWS:

CHORDS #ROWS	SURFACE SPACING (IN)	LOAD(PLF)
TOP CHORDS: (0.122"x3") SPIRAL NAILS		
A - C	12	TOP
C - D	12	TOP
BOTTOM CHORDS: (0.122"x3") SPIRAL NAILS		
A - D	12	SIDE(0.0)
WEBS: (0.122"x3") SPIRAL NAILS		
2x3	8	

NAILS TO BE DRIVEN FROM ONE SIDE ONLY.

GIRDER NAILING ASSUMES NAILED HANGERS ARE FASTENED WITH MIN. 3-0 INCH NAILS.

TOP - COMPONENTS ARE LOADED FROM THE TOP AND MUST BE PLACED ON TOP EDGE OF ALL PLIES FOR THE LOAD TO BE TRANSFERRED TO EACH PLY.

SIDE - PLF SHOWN IS THE EQUIVALENT UDL APPLIED TO ONE SIDE THAT THE CORRESPONDING NAILING PATTERN SHALL BE CAPABLE OF TRANSFERRING. REMAINING PLF MUST BE APPLIED ON THE OPPOSITE SIDE OR ON THE TOP.

PLATES (table is in inches)

JT	TYPE	PLATES	W	LEN	Y	X
A	TBMH1+m	MT20	5.0	8.0	3.50	
B	TMWW-1	MT20	5.0	8.0	2.50	2.25
C	TMV+p	MT20	3.0	4.0		
D	BMVW1-t	MT20	5.0	8.0	2.50	2.75
E	BMVW+w	MT20	3.0	10.0		

DIMENSIONS, SUPPORTS AND LOADINGS SPECIFIED BY FABRICATOR TO BE VERIFIED BY BUILDING DESIGNER

BEARINGS	FACTORED GROSS REACTION	MAXIMUM FACTORED GROSS REACTION	INPUT 8RG	REQD 8RG	HEEL WEDGE
JT	VERT	HORZ	UP/LT	IN-SX	IN-SX
A	3467	0	3467	0	5-8
D	2454	0	2454	0	5-8

A SUITABLE HANGER/MECHANICAL CONNECTION IS REQUIRED AT JOINT D. MINIMUM BEARING LENGTH AT JOINT D = 4-0.

UNFACTORED REACTIONS

JT	COMBINED	SNOW	LIVE	PERM.LIVE	WIND	DEAD	SOIL
A	2449	1822 / 0	0 / 0	0 / 0	0 / 0	828 / 0	0 / 0
D	1735	1144 / 0	0 / 0	0 / 0	0 / 0	581 / 0	0 / 0

BEARING MATERIAL TO BE SPF NO.2 OR BETTER AT JOINT(S) A

BRACING

TOP CHORD TO BE SHEATHED OR MAX. PURLIN SPACING = 4.16 FT. MAX. UNBRACED BOTTOM CHORD LENGTH = 10.00 FT OR RIGID CEILING DIRECTLY APPLIED.

ALL PITCH BREAKS AND PERIMETER CORNER JOINTS MUST BE Laterally RESTRAINED.

LOADING

TOTAL LOAD CASES: (4)

CHORDS	MAX. FACTORED FORCE (LBS)	FACTORED VERT. LOAD (PLF)	MAX. FACTORED VERT. LOAD (LBS)	MAX. FACTORED HORIZ. LOAD (LBS)	WEBS	MAX. FACTORED FORCE (LBS)	MAX. FACTORED HORIZ. LOAD (LBS)
FR-TO		FROM TO			FR-TO		
A-G	-4978 / 0	-91.8	-91.8	0.19 (1)	E-H	0 / 3365	0.42 (1)
G-B	-3683 / 0	-91.8	-91.8	0.17 (1)	B-D	-4035 / 0	0.53 (1)
B-C	-13 / 0	-91.8	-91.8	0.07 (1)	F-G	0 / 1740	0.00 (1)
D-C	-129 / 0	0.0	0.0	0.02 (1)			
A-F	0 / 3490	-18.5	-18.5	0.25 (1)			
F-H	0 / 3490	-18.5	-18.5	0.88 (1)			
H-I	0 / 3490	-18.5	-18.5	0.88 (1)			
I-J	0 / 3490	-18.5	-18.5	0.88 (1)			
J-E	0 / 3490	-18.5	-18.5	0.88 (1)			
E-K	0 / 3490	-18.5	-18.5	0.49 (1)			
K-D	0 / 3490	-18.5	-18.5	0.49 (1)			

FACTORED CONCENTRATED LOADS (LBS)

JT	LOC.	LC1	MAX.	MAX.	FACE	DIR.	TYPE	HEEL	CONN.
H	1-4-0	-1378	-1378	---	BACK	VERT	TOTAL	---	C1
I	2-0-0	-1000	-1000	---	FRONT	VERT	TOTAL	---	C1
J	3-0-4	-994	-994	---	FRONT	VERT	TOTAL	---	C1
J	3-3-4	-898	-898	---	BACK	VERT	TOTAL	---	C1
K	5-3-4	-898	-898	---	BACK	VERT	TOTAL	---	C1

CONNECTION REQUIREMENTS

1) C1: A SUITABLE HANGER/MECHANICAL CONNECTION IS REQUIRED.

TOTAL WEIGHT = 2 X 30 = 60 lb

DESIGN CRITERIA

*** SPECIAL LOADS ANALYSIS ***
GEOMETRY AND/OR BASIC LOADS CHANGED BY USER.
LOADS WERE DERIVED FROM USER INPUT
NO FURTHER MODIFICATIONS WERE MADE

SPECIFIED LOADS:

TOP CH. LL	= 25.8 PSF
DL	= 6.0 PSF
BOT CH. LL	= 0.0 PSF
DL	= 7.4 PSF
TOTAL LOAD	= 39.0 PSF

SPACING = 24.0 IN. GID

*** NON STANDARD GIRDER ***

ADDTL USER-DEFINED LOADS APPLIED TO ALL LOAD CASES.

THIS TRUSS IS DESIGNED FOR RESIDENTIAL OR SMALL BUILDING REQUIREMENTS OF PART 9, NBC 2010, NBC 2015

THIS DESIGN COMPLIES WITH:
- PART 9 OF BCBC 2018, CBC 2012, ABC 2019
- PART 9 OF CBC 2012 (2019 AMENDMENT)
- CSA 086-09, CSA 086-14
- TPIC 2011, TPIC 2014

(55 % OF 31.3 P.S.F. G.S.L. PLUS 8.4 P.S.F. RAIN LOAD) EQUALS 25.8 P.S.F. SPECIFIED ROOF LIVE LOAD

ALLOWABLE DEFL. (LL) = L/360 (0.23")
CALCULATED VERT. DEFL. (LL) = L/999 (0.03")
ALLOWABLE DEFL. (TL) = L/360 (0.23")
CALCULATED VERT. DEFL. (TL) = L/998 (0.05")

CSI: TC=0.19/1.00 (A-G:1), BC=0.68/1.00 (E-F:1), WB=0.53/1.00 (B-D:1), SS=0.90/1.00 (E-F:1)

DOL LUMBER=1.00 NAIL=1.00 LS BEND=1.00 COMP=1.00 SHEAR=1.00 TENS=1.00

COMPANION LIVE LOAD FACTOR = 1.00

TRUSS PLATE MANUFACTURER IS NOT RESPONSIBLE FOR QUALITY CONTROL IN THE TRUSS MANUFACTURING PLANT.


NAIL VALUES

PLATE GRIP(DRY)	SHEAR (PSI)	SECTION (PLI)
MT20	618 354 1667 788 1987 1656	

PLATE PLACEMENT TOL. = 0.250 inches

PLATE ROTATION TOL. = 5.0 Deg.

JSI GRIP= 0.88 (B) (INPUT = 0.90)
JSI METAL= 0.70 (A) (INPUT = 1.00)




Structural component only
DWG# T-2007122

JOB NAME 408150	TRUSS NAME G60	QUANTITY 4	PLY 1	JOB DESC. GREEN PARK HOMES	DRWG NO.
--------------------	-------------------	---------------	----------	-------------------------------	----------

Tamareck Roof Truss, Burlington

Version 8.310 S Oct 29 2019 Mitek Industries, Inc. Sat Apr 25 11:02:39 2020 Page 1

ID:7vF7aG0E03cRUj6XfjSkziWYK-kvCWPUL9QwEw4kscic_ECpgnD4MnCBFXZZ4QzNCnk



Scale = 1/4" = 1'-0"

LUMBER				
N.L.G.A. RULES	CHORDS	SIZE	LUMBER	DESCR.
AC - B	2x4	DRY	No.2	SPF
A - H	2x4	DRY	No.2	SPF
H - J	2x4	DRY	No.2	SPF
J - O	2x4	DRY	No.2	SPF
P - O	2x4	DRY	No.2	SPF
AC - T	2x4	DRY	No.2	SPF
T - P	2x4	DRY	No.2	SPF
ALL WEBS	2x3	DRY	No.2	SPF
ALL GABLE WEBS	2x3	DRY	No.2	SPF
DRY: SEASONED LUMBER.				
GABLE STUDS SPACED AT 2'-0" OC.				

PLATES (table in inches)				
PLATE TYPE	PLATES	W	LEN	Y
B TMV+p	MT20	3.0	4.0	
C, D, E, F, G, I, K, L, M, N	MT20	2.0	4.0	
H TS-I	MT20	3.0	8.0	
J TTW-m	MT20	4.0	4.0	
K TMV+p	MT20	3.0	4.0	
L BMV1+p	MT20	3.0	4.0	
O, R, S, U, V, W, X, Y, Z, AA, AB	MT20	2.0	4.0	
T BS-I	MT20	3.0	8.0	
AC BMV1+p	MT20	3.0	4.0	

DIMENSIONS, SUPPORTS AND LOADINGS SPECIFIED BY FABRICATOR TO BE VERIFIED BY BUILDING DESIGNER

BEARINGS
THIS TRUSS DESIGNED FOR CONTINUOUS BEARINGS.
THIS TRUSS REQUIRES RIGID SHEATHING ON EXPOSED FACE.
BEARING MATERIAL TO BE SPF NO.2 OR BETTER AT JOINT(S)

BRACING
TOP CHORD TO BE SHEATHED OR MAX. PURLINE SPACING = 8.25 FT.
MAX. UNBRACED BOTTOM CHORD LENGTH = 10.00 FT OR RIGID CEILING DIRECTLY APPLIED.
ALL PITCH BREAKS AND PERIMETER CORNER JOINTS MUST BE Laterally RESTRAINED.

1 LATERAL BRACE(S) AT 1/2 LENGTH OF O-P.

END VERTICAL(S) MUST BE SHEATHED OR HAVE BRACES AS INDICATED IN THE MAX. UNBRACED LENGTH COLUMN OF THE TABLE BELOW

LOADING
TOTAL LOAD CASES: (4)

CHORDS				WEBS			
MEMB.	MAX. FACTORED FORCE (LBS)	FACTORED VERT. LOAD (PLF)	MAX. CSI (LC)	MEMB.	MAX. FACTORED FORCE (LBS)	MAX. CSI (LC)	
FR-TO		FROM TO		FR-TO			
AC-B	-224/0	0.0 0.0	0.02 (1)	Q-N	-195/0	0.25 (1)	
A-B	0/28	-91.8 -91.8	0.12 (1)	R-M	-183/0	0.23 (1)	
B-C	-28/0	-91.8 -91.8	0.04 (1)	S-L	-189/0	0.24 (1)	
C-D	-19/0	-91.8 -91.8	0.04 (1)	U-K	-136/0	0.17 (1)	
D-E	-15/0	-91.8 -91.8	0.04 (1)	V-J	-131/0	0.17 (1)	
E-F	-11/0	-91.8 -91.8	0.04 (1)	W-I	-185/0	0.17 (1)	
F-G	-8/0	-91.8 -91.8	0.04 (1)	X-G	-183/0	0.11 (1)	
G-H	-8/0	-91.8 -91.8	0.04 (1)	Y-F	-182/0	0.07 (1)	
H-I	-8/0	-91.8 -91.8	0.04 (1)	Z-E	-182/0	0.05 (1)	
I-J	-8/0	-91.8 -91.8	0.04 (1)	AA-D	-183/0	0.03 (1)	
J-K	-2/0	-91.8 -91.8	0.03 (1)	AB-C	-178/0	0.03 (1)	
K-L	-2/0	-91.8 -91.8	0.04 (1)				
L-M	-2/0	-91.8 -91.8	0.04 (1)				
M-N	-2/0	-91.8 -91.8	0.04 (1)				
N-O	-2/0	-91.8 -91.8	0.04 (1)				
P-O	-81/0	0.0 0.0	0.01 (1)				
AC-AB	0/24	-18.5 -18.5	0.02 (4)				
AB-AA	0/17	-18.5 -18.5	0.02 (4)				
AA-Z	0/19	-18.5 -18.5	0.02 (4)				
Z-Y	0/10	-18.5 -18.5	0.02 (4)				
Y-X	0/7	-18.5 -18.5	0.01 (4)				
X-W	0/5	-18.5 -18.5	0.02 (4)				
W-V	0/4	-18.5 -18.5	0.02 (4)				
V-U	0/2	-18.5 -18.5	0.01 (4)				
U-T	0/2	-18.5 -18.5	0.02 (4)				
T-S	0/2	-18.5 -18.5	0.02 (4)				
S-R	0/2	-18.5 -18.5	0.02 (4)				
R-Q	0/2	-18.5 -18.5	0.02 (4)				
Q-P	0/2	-18.5 -18.5	0.02 (4)				

TOTAL WEIGHT = 4 X 116 = 464 lb (M)

DESIGN CRITERIA

SPECIFIED LOADS:
TOP CH. LL = 25.8 PSF
OL = 8.0 PSF
BOT CH. LL = 0.0 PSF
OL = 7.4 PSF
TOTAL LOAD = 39.0 PSF

SPACING = 24.0 IN. OC

LOADING IN FLAT SECTION BASED ON A SLOPE OF 8.00/12

THIS TRUSS IS DESIGNED FOR RESIDENTIAL OR SMALL BUILDING REQUIREMENTS OF PART 9, NBC 2010, NBC 2015

THIS DESIGN COMPLIES WITH:
- PART 9 OF CBC 2018, CBC 2012, ABC 2019
- PART 9 OF CBC 2012 (2018 AMENDMENT)
- CSA 086-08, CSA 088-14
- TPIC 2011, TPIC 2014

DESIGN ASSUMPTIONS
- OVERHANG NOT TO BE ALTERED OR CUT OFF.

(55% OF 31.3 P.S.F. G.S.L. PLUS 8.4 P.S.F. RAIN LOAD) EQUALS 25.8 P.S.F. SPECIFIED ROOF LIVE LOAD

CSI: TC=0.12/1.00 (A-B:1), BC=0.02/1.00 (Q-R:4), WB=0.25/1.00 (N-Q:1), SS=0.09/1.00 (A-B:1)

DOL LUMBER=1.00 NAIL=1.00 LS BEND=1.10
COMP=1.10 SHEAR=1.10 TENS=1.10

COMPANION LIVE LOAD FACTOR = 1.00


TRUSS PLATE MANUFACTURER IS NOT RESPONSIBLE FOR QUALITY CONTROL IN THE TRUSS MANUFACTURING PLANT.

NAIL VALUES
PLATE GRIP(DRY) SHEAR SECTION
(PSI) (PLI) (PLI)
MAX MIN MAX MIN MAX MIN
MT20 818 354 1887 788 1887 1856

PLATE PLACEMENT TOL. = 0.250 inches

PLATE ROTATION TOL. = 5.0 Deg.

JSI GRIP = 0.80 (J) (INPUT = 0.80)
JSI METAL = 0.08 (I) (INPUT = 1.00)




Structural component only
DWG# T-2007057

JOB NAME	TRUSS NAME	QUANTITY	PLY	JOB DESC.	GREEN PARK HOMES	DRWG NO.
408150	GP1	2	1	TRUSS DESC.		

Tamarack Roof Truss, Burlington

Version 8.310 S Oct 29 2019 Mitek Industries, Inc. Sat Apr 25 11:02:40 2020 Page 1

ID:7vF?aG0E03cRUj6X1jSrkzWYK-C6mudqMnBDMnh0JqS07DnQMnfcNpWgWomDIPdszNCn



LUMBER				DESIGN CRITERIA			
N. L. G. A. RULES				TOTAL WEIGHT = 2 X 54 = 107 lb			
CHORDS	SIZE	LUMBER	DESCR.	SPECIFIED LOADS:			
A - C	2x4	DRY	No.2	TOP CH. LL =	25.8	PSF	
C - E	2x4	DRY	No.2	DL =	6.0	PSF	
A - G	2x4	DRY	No.2	BOT CH. LL =	0.0	PSF	
G - E	2x4	DRY	No.2	DL =	7.4	PSF	
ALL WEBS	2x3	DRY	No.2	TOTAL LOAD =	39.0	PSF	
DRY: SEASONED LUMBER.				SPACING =	24.0	IN. O.C.	

PLATES (table in inches)					
JT	TYPE	PLATES	W	LEN	Y X
A	TBM1-h	MT20	3.0	4.0	
B	TMW+w	MT20	4.0	4.0	
C	TTWW+p	MT20	4.0	6.0	Edge
D	TMW+w	MT20	2.0	4.0	
E	TBM1-h	MT20	3.0	4.0	
F	BMWW1-t	MT20	4.0	4.0	
G	BS-t	MT20	3.0	6.0	
H	BMWW1-t	MT20	4.0	4.0	

Edge - INDICATES REFERENCE CORNER OF PLATE TOUCHES EDGE OF CHORD.

DIMENSIONS, SUPPORTS AND LOADINGS SPECIFIED BY FABRICATOR TO BE VERIFIED BY BUILDING DESIGNER

BEARINGS		FACTORED		MAXIMUM FACTORED		INPUT		REQD	
JT	GROSS REACTION	VERT	HORZ	GROSS REACTION	DOWN	HORZ	UPLIFT	BRG	BRG
A	134	0	0	134	0	0	18-1-0 (9-11-10)1-0		
E	134	0	0	134	0	0	18-1-0 (9-11-10)1-0		
F	883	0	0	883	0	0	18-1-0 (9-11-10)1-0		
H	883	0	0	883	0	0	18-1-0 (9-11-10)1-0		

VALUE IN PARENTHESIS INDICATES EFFECTIVE BEARING LENGTH

UNFACTORED REACTIONS

JT	1ST CASE	SNOW	LIVE	PERM. LIVE	WIND	DEAD	SOIL
A	94	687/0	0/0	0/0	0/0	287/0	0/0
E	94	687/0	0/0	0/0	0/0	287/0	0/0
F	811	3957/0	0/0	0/0	0/0	2187/0	0/0
H	811	3957/0	0/0	0/0	0/0	2187/0	0/0

BEARING MATERIAL TO BE SPF NO.2 OR BETTER AT JOINT(S) A, E, F, H

BRACING

TOP CHORD TO BE SHEATHED OR MAX. PURLIN SPACING = 10.00 FT.
MAX. UNBRACED BOTTOM CHORD LENGTH = 6.25 FT. OR RIGID CEILING DIRECTLY APPLIED.

ALL PITCH BREAKS AND PERIMETER CORNER JOINTS MUST BE LATERALLY RESTRAINED.

LOADING

TOTAL LOAD CASES: (4)

CHORDS				WEBS			
MEMB.	MAX. FACTORED FORCE (LBS)	FACTORED VERT. LOAD (PLF)	MAX. CS1 (LC)	MEMB.	MAX. FACTORED FORCE (LBS)	MAX. CS1 (LC)	
FR-TO		FROM	TO	FR-TO			
A-J	0/240	-91.8	-91.8 0.12 (1)	10.00	C-F	-428/0	0.18 (1)
J-B	0/301	-91.8	-91.8 0.34 (1)	10.00	F-D	-436/0	0.08 (1)
B-C	0/503	-91.8	-91.8 0.37 (1)	10.00	H-C	-428/0	0.18 (1)
C-D	0/503	-91.8	-91.8 0.37 (1)	10.00	B-H	-438/0	0.08 (1)
D-L	0/301	-91.8	-91.8 0.34 (1)	10.00	I-J	-76/35	0.00 (1)
L-E	0/240	-91.8	-91.8 0.12 (1)	10.00	K-L	-76/35	0.00 (1)
A-I	-255/0	-18.5	-18.5 0.11 (1)	6.25			
I-H	-243/0	-18.5	-18.5 0.13 (4)	6.25			
H-G	-246/0	-18.5	-18.5 0.13 (4)	6.25			
G-F	-246/0	-18.5	-18.5 0.13 (4)	6.25			
F-K	-243/0	-18.5	-18.5 0.13 (4)	6.25			
K-E	-255/0	-18.5	-18.5 0.11 (1)	6.25			

THIS TRUSS IS DESIGNED FOR RESIDENTIAL OR SMALL BUILDING REQUIREMENTS OF PART 9, NBCG 2010, NBCG 2015

THIS DESIGN COMPLIES WITH:
- PART 9 OF NBCG 2018, NBC 2012, ABC 2019
- PART 9 OF OBC 2012 (2019 AMENDMENT)
- CSA 088-09, CSA 088-14
- TPIC 2011, TPIC 2014

(55% OF 31.3 P.S.F. G.S.L. PLUS 8.4 P.S.F. RAIN LOAD) EQUALS 25.8 P.S.F. SPECIFIED ROOF LIVE LOAD

CSI: TC=0.37/1.00 (C-D:1), BC=0.13/1.00 (F-K:4), WB=0.18/1.00 (C-H:1), SSI=0.17/1.00 (D-L:1)

DOL LUMBER=1.00 NAIL=1.00 LB BEND=1.10 COMP=1.10 SHEAR=1.10 TENS=1.10

COMPANION LIVE LOAD FACTOR = 1.00

TRUSS PLATE MANUFACTURER IS NOT RESPONSIBLE FOR QUALITY CONTROL IN THE TRUSS MANUFACTURING PLANT.

NAIL VALUES
PLATE GRIP(DRY) SHEAR SECTION
(PSI) (PLI) (PLI)
MAX MIN MAX MIN MAX MIN
MT20 618 354 1667 788 1987 1858

PLATE PLACEMENT TOL. = 0.250 inches

PLATE ROTATION TOL. = 5.0 Deg.


JSI GRIP= 0.46 (H) (INPUT = 0.90)
JSI METAL= 0.15 (C) (INPUT = 1.00)



Structural component only
DWG# T-2007058

JOB NAME	TRUSS NAME	QUANTITY	PLY	JOB DESC.	DRWG NO.
408150	P1	17	1	GREEN PARK HOMES	
Tamarack Roof Truss, Burlington					

Version 8.310 S Oct 29 2019 MITek Industries, Inc. Sat Apr 25 11:02:45 2020 Page 1
ID:7vF7aG0E03cRUj8X1(SkzIWK-Z4ZngXQw0m_4ooBoEZ)OUT3e9d5nBxS8vV0A14zNCne



LUMBER				DESIGN CRITERIA			
N.L.G.A. RULES				TOTAL WEIGHT = 17 X 55 = 943 lb			
CHORDS	SIZE	LUMBER	DESCR.	SPECIFIED LOADS:			
A - C	2x4	DRY	No.2	TOP CH. LL	=	25.6	PSF
C - E	2x4	DRY	No.2	DL	=	6.0	PSF
A - G	2x4	DRY	No.2	BOT CH. LL	=	0.0	PSF
G - E	2x4	DRY	No.2	DL	=	7.4	PSF
ALL WEBS	2x3	DRY	No.2	TOTAL LOAD	=	39.0	PSF
DRY: SEASONED LUMBER.				SPACING	=	24.0	IN. O.C.

PLATES (tablets in inches)			
JT TYPE	PLATES	W	LEN Y X
A TBM1-h	MT20	3.0	4.0
B TMWW-I	MT20	4.0	4.0
C TTW-p	MT20	4.0	4.0
D TMWW-I	MT20	4.0	4.0
E TBM1-h	MT20	3.0	4.0
F BMW1-w	MT20	2.0	4.0
G BS-I	MT20	3.0	6.0
H BMWW1-I	MT20	4.0	9.0
I BMW1-w	MT20	2.0	4.0

DIMENSIONS, SUPPORTS AND LOADINGS SPECIFIED BY FABRICATOR TO BE VERIFIED BY BUILDING DESIGNER

BEARINGS			
JT	FACTORED GROSS REACTION	MAXIMUM FACTORED GROSS REACTION	INPUT REQD BRG IN-SX
A	124 0	124 0	18'-0" (11'-11 1/2")
E	124 0	124 0	18'-0" (11'-11 1/2")
H	415 0	415 0	18'-0" (11'-11 1/2")
F	666 0	666 0	18'-0" (11'-11 1/2")
I	666 0	666 0	18'-0" (11'-11 1/2")

VALUE IN PARENTHESIS INDICATES EFFECTIVE BEARING LENGTH

UNFACTORED REACTIONS			
JT	IST CASE	SNOW	LIVE
A	87	59/0	0/0
E	87	59/0	0/0
H	283	192/0	0/0
F	471	307/0	0/0
I	471	307/0	0/0

BEARING MATERIAL TO BE SPF NO.2 OR BETTER AT JOINT(S) A, E, H, F, I

BRACING
TOP CHORD TO BE SHEATHED OR MAX. PURLIN SPACING = 10.00 FT.
MAX. UNBRACED BOTTOM CHORD LENGTH = 6.25 FT. OR RIGID CEILING DIRECTLY APPLIED.

ALL PITCH BREAKS AND PERIMETER CORNER JOINTS MUST BE LATERALLY RESTRAINED.

LOADING
TOTAL LOAD CASES: (4)

CHORDS				WEBS			
MEMB.	MAX. FACTORED FORCE (LBS)	FACTORED VERT. LOAD (LBS)	MAX. FACTORED CS (LC)	MEMB.	MAX. FACTORED FORCE (LBS)	MAX. FACTORED CS (LC)	
FR-TO		FROM TO	LENGTH	FR-TO			
A-K	0/248	-91.8 -91.8	0.07 (1)	H-C	-445/0	0.13 (1)	
K-B	0/292	-91.8 -91.8	0.32 (1)	H-D	0/59	0.01 (1)	
B-C	0/188	-91.8 -91.8	0.30 (1)	F-D	-528/0	0.08 (1)	
C-D	0/188	-91.8 -91.8	0.30 (1)	B-H	0/59	0.01 (1)	
D-M	0/292	-91.8 -91.8	0.32 (1)	I-B	-528/0	0.08 (1)	
M-E	0/248	-91.8 -91.8	0.07 (1)	J-K	-128/8	0.00 (1)	
A-J	-256/0	-18.5 -18.5	0.14 (1)	L-M	-128/8	0.00 (1)	
J-I	-240/0	-18.5 -18.5	0.14 (1)				
I-H	-240/0	-18.5 -18.5	0.11 (1)				
H-G	-240/0	-18.5 -18.5	0.11 (1)				
G-F	-240/0	-18.5 -18.5	0.11 (1)				
F-L	-240/0	-18.5 -18.5	0.14 (1)				
L-E	-256/0	-18.5 -18.5	0.14 (1)				

THIS TRUSS IS DESIGNED FOR RESIDENTIAL OR SMALL BUILDING REQUIREMENTS OF PART 9, NBCC 2010, NBCC 2015

THIS DESIGN COMPLIES WITH:
- PART 9 OF NBCC 2010, CBC 2012, ABC 2019
- PART 9 OF CBC 2012 (2019 AMENDMENT)
- CSA 088-09, CSA 088-14
- TPIC 2011, TPIC 2014

(65% OF 31.3 P.S.F. G.S.L. PLUS 8.4 P.S.F. RAIN LOAD) EQUALS 25.6 P.S.F. SPECIFIED ROOF LIVE LOAD

CSI: TC=0.32/1.00 (D-M:1), BC=0.14/1.00 (F-L:1), WB=0.13/1.00 (C-H:1), SS=0.17/1.00 (D-M:1)

DOL LUMBER=1.00 NAIL=1.00 LS BEND=1.10 COMP=1.10 SHEAR=1.10 TENS=1.10

COMPANION LIVE LOAD FACTOR = 1.00


TRUSS PLATE MANUFACTURER IS NOT RESPONSIBLE FOR QUALITY CONTROL IN THE TRUSS MANUFACTURING PLANT.

NAIL VALUES
PLATE GRP(DRY) SHEAR SECTION (PSI) (PLI) (PLI)
MAX MIN MAX MIN MAX MIN
MT20 618 354 1687 788 1987 1856


PLATE PLACEMENT TOL. = 0.250 inches

PLATE ROTATION TOL. = 5.0 Deg.

JSI GRIP = 0.51 (B) (INPUT = 0.90)
JSI METAL = 0.13 (C) (INPUT = 1.00)



Structural component only
DWG# T-2007062



BEARINGS		FACTORED GROSS REACTION		MAXIMUM FACTORED GROSS REACTION			INPUT BRG	REQRD BRG
JT	VERT	HORZ	DOWN	HORZ	UPLIFT	IN-SX	IN-SX	
B	189	0	189	0	0	13-7-1	13-7-1	
F	189	0	189	0	0	13-7-1	13-7-1	
T	288	0	288	0	0	13-7-1	13-7-1	
I	683	0	683	0	0	13-7-1	13-7-1	
H	288	0	288	0	0	13-7-1	13-7-1	

SPECIFIED LOADS:
 TOP CH. LL = 25.6 PSF
 DL = 6.0 PSF
 BOT CH. LL = 0.0 PSF
 DL = 7.4 PSF
TOTAL LOAD = 39.0 PSF

SPACING = 24.0 IN. C/D

THIS DESIGN COMPLIES WITH:

- PART 9 OF BCBC 2018, OBC 2012, ABC 2019
- PART 9 OF OBC 2012 (2019 AMENDMENT)
- CSA 086-09, CSA 086-14
- TPIC 2011, TPIC 2014

DOL LUMBER=1.00 NAIL=1.00 LS BEND=1.10
COMP=1.10 SHEAR=1.10 TENS=1.10


TRUSS PLATE MANUFACTURER IS NOT RESPONSIBLE FOR QUALITY CONTROL IN THE TRUSS MANUFACTURING PLANT.

NAIL VALUES					
PLATE	GRIP(DRY)		SHEAR		SECTION
	(PSI)		(PLI)		(PLI)
	MAX	MIN	MAX	MIN	MAX MIN
MT20	618	354	1887	788	1987 1658

PLATE PLACEMENT TOL = 0.250 inches

PLATE ROTATION TOL. = 5.0 Deg.


JSI GRIP= 0.30 {D} (INPUT = 0.90)
JSI METAL= 0.12 {D} (INPUT = 1.00)



Tamarack Roof Truss, Burlington

Version 8.310 S Oct 29 2019 Mtek Industries, Inc. Sat Apr 25 11:02:42 2020 Page 1
ID:7vF?aG0E03cRUj8X1jSrkzjWYK-9Vt1WN1jrcVxKT0ZR9hsrR4TQ3l_cmhDXnWhizNCnh

Scale = 1/29.9



TOTAL WEIGHT = 21 X 17 = 353 lb

SPF

DRY: SEASONED LUMBER.

JT VE

JT	FACTORED GROSS REACTION		MAXIMUM FACTORED GROSS REACTION			INPUT BRG	REQRD BRG
	VERT	HORZ	DOWN	HORZ	UPLIFT	IN-SX	IN-SX
E	525	0	525	0	0	5-8	5-8
C	202	0	202	0	0	1-8	1-8
D	45	0	50	0	0	1-8	1-8

SEE MITEK STANDARD DETAIL B97791H FOR CONNECTION TO JOINT(S) C, D

369	257 / 0
-----	---------

NOT CORRE		WHA MIN. COMPONENT REACTIONS					
JT	COMBINED	SNOW	LIVE	PERM.LIVE	WIND	DEAD	SOIL
E	369	257 / 0	0 / 0	0 / 0	0 / 0	111 / 0	0 / 0
C	139	113 / 0	0 / 0	0 / 0	0 / 0	26 / 0	0 / 0
D	36	0 / 0	0 / 0	0 / 0	0 / 0	36 / 0	0 / 0

BEARING MATERIAL TO BE SPF NO.2 OR BETTER AT JOINT(S) E

100% 90% 80% 70% 60% 50% 40% 30% 20% 10% 0%

MAX. UNBRACED BOTTOM CHORD LENGTH = 10.00 FT OR RIGID CEILING DIRECTLY APPLIED

ALL PITCH BREAKS AND PERIMETER CORNER JOINTS MUST BE WATER-TIGHT.

ALL FITCH BREAKS AND PERIMETER CORNER JOINTS MUST BE Laterally RESTRAINED.

CHO

CHORDS			FACTORED				WEBB		
MEMB.	MAX. FORCE (LBS)		VERT. LOAD (P.LF)	LCI	MAX. CSI (LC)	MAX. UNBRAC LENGTH	MEMB. FR-TO	MAX. FORCE (LBS)	MAX. CSI (LC)
FR-TO			FROM	TO					
E-B	-481 0		0.0	0.0	0.13 (4)	7.81			
A-B	0 / 28		-91.8	-91.8	0.12 (1)	10.00			
B-C	-30 0		-91.8	-91.8	0.54 (1)	6.25			
E-D	0 / 0		-18.5	-18.5	0.13 (4)	10.00			

TOTAL LOAD =

SPACING = 24.0 IN. C/C

THIS TRUSS IS DESIGNED FOR RESIDENTIAL OR
SMALL BUILDING REQUIREMENTS OF PART 9,
NBC 2010, NBC 2015

THIS DESIGN COMPLIES WITH:
- PART 9 OF 8CBC 2018, OBC 2012, ABC 2019
- PART 9 OF OBC 2012 (2018 AMENDMENT)
- CSA 888-09, CSA 888-14
- TPIC 2011, TPIC 2014

07/20/2015 10:01:10 AM

(55 % OF 31.3 P.S.F. G.S.L. PLUS 8.4 P.S.F. RAIN LOAD) EQUALS 25.6 P.S.F. SPECIFIED ROOF LIVE LOAD

ALLOWABLE DEFL.(LL)= L/360 (0.20")
CALCULATED VERT. DEFL.(LL) = 1/999 (0.00")
ALLOWABLE DEFL.(TL)= L/360 (0.20")
CALCULATED VERT. DEFL.(TL) = 1/999 (0.03")

CSI: TC=0.64/1.00 (B-C:1), BC=0.13/1.00 (D-E:4),
WB=0.00/1.00 (n/a:0), SSI=0.24/1.00 (B-C:1)

DOL LUMBER=1.00 NAIL=1.00 LS BEND=1.10
COMP=1.10 SHEAR=1.10 TENS= 1.10

COMPANION LIVE LOAD FACTOR = 1.00

AUTOSOLVE RIGHT. HEEL ONLY

TRUSS PLATE MANUFACTURER IS NOT RESPONSIBLE FOR QUALITY CONTROL IN THE TRUSS MANUFACTURING PLANT.

MAX

MT20	618	354	1687	788	1987	1658
------	-----	-----	------	-----	------	------

PLATE PLACEMENT TOL. = 0.250 inches


PLATE ROTATION TOL. = 5.0 Deg

JSI GRIP= 0.10 (E) (INPUT = 0.90)
JSI METAL= 0.13 (B) (INPUT = 1.00)



Structural component only
DWG# T-2007059

JOB NAME	TRUSS NAME	QUANTITY	PLY	JOB DESC.	DRWG NO.
408150	J2	1	1	GREEN PARK HOMES	
Tamarack Roof Truss, Burlington					
Version 8.310 S Oct 29 2019 Mitek Industries, Inc. Sat Apr 25 11:02:43 2020 Page 1					
ID:7vF7aG0E03cRUJ8X1tS/kziWYK-dhR1FrOUBKMYU2P78gwP2_KzqQl30rSBX3DBzNCng					
Scale = 1/27.0					



LUMBER			
N.L.G.A. RULES	CHORDS	SIZE	LUMBER
F - B	2x4	DRY	No.2
A - C	2x4	DRY	No.2
F - D	2x4	DRY	No.2
ALL WEBS 2x3 DRY, SEASONED LUMBER.			

PLATES (table in inches)				
JT TYPE	PLATES	W	LEN	Y X
B TMVW+p	MT20	4.0	4.0	1.00 2.00
E BMVW+p	MT20	2.0	4.0	
F BMV1+p	MT20	3.0	4.0	

DIMENSIONS, SUPPORTS AND LOADINGS SPECIFIED BY FABRICATOR TO BE VERIFIED BY BUILDING DESIGNER

FACTORED		MAXIMUM FACTORED		INPUT		REQD	
GROSS REACTION		GROSS REACTION		BRG		BRG	
JT		DOWN	HORIZ	UPLIFT	IN-SX	IN-SX	
F	341	0	341	0	5-8	5-8	
C	178	0	178	0	1-8	1-8	
D	38	0	40	0	1-8	1-8	

SEE MITEK STANDARD DETAIL B97791H FOR CONNECTION TO JOINT(S) C, D

UNFACTORED REACTIONS		MAX/MIN COMPONENT REACTIONS					
JT	1ST CASE	SNOW	LIVE	PERM.LIVE	WIND	DEAD	SOIL
F	239	170/0	0/0	0/0	0/0	89/0	0/0
C	122	99/0	0/0	0/0	0/0	23/0	0/0
D	29	0/0	0/0	0/0	0/0	29/0	0/0

BEARING MATERIAL TO BE SPF NO.2 OR BETTER AT JOINT(S) F

BRACING
TOP CHORD TO BE SHEATHED OR MAX. PURLIN SPACING = 10.00 FT.
MAX. UNBRACED BOTTOM CHORD LENGTH = 10.00 FT OR RIGID CEILING DIRECTLY APPLIED.
ALL PITCH BREAKS AND PERIMETER CORNER JOINTS MUST BE Laterally RESTRAINED.

LOADING
TOTAL LOAD CASES: (5)

CHORDS		FACTORED		WEBS		FACTORED	
MEMB.	FORCE (LBS)	VERT.	LOAD LC1	MAX	MAX.	MEMB.	FORCE (LBS)
FR-TO		FROM	TO	LENGTH	FR-TO		
F-B	-305/0	0.0	0.0	0.03 (1)	7.81	B-E	0/0
A-B	0/41	-91.8	-91.8	0.14 (5)	10.00		
B-C	0/0	-91.8	-91.8	0.23 (1)	10.00		
F-E	0/0	-18.5	-18.5	0.08 (4)	10.00		
E-D	0/0	-18.5	-18.5	0.08 (4)	10.00		

CANTILEVER ANALYSIS HAS BEEN CONSIDERED IN THIS DESIGN

TOTAL WEIGHT = 15 lb (M)

DESIGN CRITERIA

SPECIFIED LOADS:
TOP CH. LL = 25.6 PSF
OL = 8.0 PSF
BOT CH. LL = 0.0 PSF
OL = 7.4 PSF
TOTAL LOAD = 39.0 PSF

SPACING = 24.0 IN./C/C

THIS TRUSS IS DESIGNED FOR RESIDENTIAL OR SMALL BUILDING REQUIREMENTS OF PART 9, NBC 2010, NBC 2015

THIS DESIGN COMPLIES WITH:
- PART 9 OF CBC 2018, CBC 2012, ABC 2019
- PART 9 OF CBC 2012 (2019 AMENDMENT)
- CSA 088-09, CSA 088-14
- TPIC 2011, TPIC 2014

(55% OF 31.3 P.S.F. G.S.L. PLUS 8.4 P.S.F. RAIN LOAD) EQUALS 25.6 P.S.F. SPECIFIED ROOF LIVE LOAD

ALLOWABLE DEFL.(LL) = L/380 (0.18")
CALCULATED VERT. DEFL.(LL) = L/899 (0.00")
ALLOWABLE DEFL.(TL) = L/380 (0.18")
CALCULATED VERT. DEFL.(TL) = L/999 (0.01")

CSI: TC=0.23/1.00 (B-C:1), BC=0.09/1.00 (D-E:4), WB=0.00/1.00 (B-E:1), SS=0.11/1.00 (B-C:1)

DOL LUMBER=1.00 NAIL=1.00 LS BEND=1.10 COMP=1.10 SHEAR=1.10 TENS=1.10

COMPANION LIVE LOAD FACTOR = 1.00

AUTOSOLVE RIGHT HEEL ONLY

TRUSS PLATE MANUFACTURER IS NOT RESPONSIBLE FOR QUALITY CONTROL IN THE TRUSS MANUFACTURING PLANT.

NAIL VALUES
PLATE GRIP(DRY) SHEAR SECTION (PSI) (PL) (PL)
MAX MIN MAX MIN MAX MIN
MT20 618 354 1667 788 1987 1656

PLATE PLACEMENT TOL. = 0.250 inches

PLATE ROTATION TOL. = 5.0 Deg.


JSI GRIP = 0.24 (B) (INPUT = 0.90)
JSI METAL = 0.06 (B) (INPUT = 1.00)



Structural component only
DWG# T-2007060

JOB NAME 408150	TRUSS NAME J3	QUANTITY 6	PLY 1	JOB DESC. GREEN PARK HOMES	DRWG NO.
Tamarack Roof Truss, Burlington				TRUSS DESC.	


Version 8.310 S Oct 29 2019 Mitek Industries, Inc. Sat Apr 25 11:02:44 2020 Page 1
ID:1vF?aG0E03cRU0X1jSkzjWYK-5u7PSBPfSsDAedbsB9xGWUuEIBSWG_hrGcmdzNCnf



JOB NAME	TRUSS NAME	QUANTITY	PLY	JOB DESC.	DRWG NO.
408152	J40	4	1	GREEN PARK HOMES	

Tamarack Roof Truss, Burlington

Version 8.310 S Oct 29 2019 Mitek Industries, Inc. Sat Apr 25 11:28:29 2020 Page 1
ID: j7vF7aG0E03cRU6X1jS4zIWYK-bU9J7q2Gb4UDlp3CRUXVjVnDY50PbE2Z2b8zNCOa



Scale = 1:23.2

LUMBER	CHORDS	SIZE	LUMBER	DESCR.
N. L. G. A. RULES	E - A	2x4	DRY	No.2
	A - B	2x4	DRY	No.2
	E - C	2x4	DRY	No.2
ALL WEBS	2x3	DRY	No.2	SPF
DRY: SEASONED LUMBER.				

PLATES (table is in inches)	JT TYPE	PLATES	W	LEN	Y	X
A	TMVW-1	MT20	4.0	4.0	2.00	1.25
D	BMVW-w	MT20	2.0	4.0		
E	BMV1+p	MT20	3.0	4.0		

DIMENSIONS, SUPPORTS AND LOADINGS SPECIFIED BY FABRICATOR TO BE VERIFIED BY BUILDING DESIGNER

BEARINGS	FACTORED	MAXIMUM FACTORED	INPUT	RECORD
JT	VERT	GROSS REACTION	GROSS REACTION	BRG
E	209	0	209	0
B	174	0	174	0
C	35	0	35	0

A SUITABLE HANGER/MECHANICAL CONNECTION IS REQUIRED AT JOINT E. MINIMUM BEARING LENGTH AT JOINT E = 1-8.

SEE MITEK STANDARD DETAIL B97791H FOR CONNECTION TO JOINT(S) B, C

UNFACTORED REACTIONS							
	1ST CASE	MAX/MIN COMPONENT REACTIONS					
JT	COMBINED	SNOW	LIVE	PERM. LIVE	WIND	DEAD	SOIL
E	148	87/0	0/0	0/0	0/0	51/0	0/0
B	120	87/0	0/0	0/0	0/0	23/0	0/0
C	28	0/0	0/0	0/0	0/0	28/0	0/0

BRACING
TOP CHORD TO BE SHEATHED OR MAX. PURLIN SPACING = 10.00 FT.
MAX. UNBRACED BOTTOM CHORD LENGTH = 10.00 FT OR RIGID CEILING DIRECTLY APPLIED.

ALL PITCH BREAKS AND PERIMETER CORNER JOINTS MUST BE Laterally RESTRAINED.

LOADING
TOTAL LOAD CASES: (4)

CHORDS	MAX. FACTORED	FACTORED	WEBS	MAX. FACTORED
MEMB.	FORCE (LBS)	VERT. LOAD	CS1 (LC)	MEMB. FORCE (LBS)
FR-TO		FROM TO	UNBRAC LENGTH	FR-TO
E-A	-174/0	0.0	0.0	0.02 (1)
A-B	0/0	-91.8	-91.8	0.22 (1)
E-D	0/0	-18.5	-18.5	0.07 (4)
D-C	0/0	-18.5	-18.5	0.08 (4)

DESIGN CRITERIA

SPECIFIED LOADS:
TOP CH. LL = 25.8 PSF
DL = 6.0 PSF
BOT CH. LL = 0.0 PSF
DL = 7.4 PSF
TOTAL LOAD = 39.0 PSF

SPACING = 24.0 IN. CG

THIS TRUSS IS DESIGNED FOR RESIDENTIAL OR SMALL BUILDING REQUIREMENTS OF PART 9, NBCC 2010, NBCC 2015

THIS DESIGN COMPLIES WITH:
- PART 9 OF BCBC 2018, OBC 2012, ABC 2019
- PART 9 OF OBC 2012 (2019 AMENDMENT)
- CSA 086-09, CSA 086-14
- TPIC 2011, TPIC 2014

(55 % OF 31.3 P.S.F. G.S.L. PLUS 8.4 P.S.F. RAIN LOAD) EQUALS 25.8 P.S.F. SPECIFIED ROOF LIVE LOAD

ALLOWABLE DEFL. (LL) = L/360 (0.18")
CALCULATED VERT. DEFL. (LL) = 1/999 (0.00")
ALLOWABLE DEFL. (TL) = L/360 (0.18")
CALCULATED VERT. DEFL. (TL) = 1/999 (0.01")

CSI: TC=0.22/1.00 (A-B:1), BC=0.08/1.00 (C-D:4), WB=0.00/1.00 (A-D:1), SS=0.12/1.00 (A-B:1)

DOL LUMBER=1.00 NAIL=1.00 LS BEND=1.10 COMP=1.10 SHEAR=1.10 TENG=1.10

COMPANION LIVE LOAD FACTOR = 1.00


TRUSS PLATE MANUFACTURER IS NOT RESPONSIBLE FOR QUALITY CONTROL IN THE TRUSS MANUFACTURING PLANT.

NAIL VALUES
PLATE GRIP(DRY) SHEAR SECTION
(PSI) (PLI) (PLI)
MAX MIN MAX MIN MAX MIN
MT20 618 354 1687 788 1887 1858

PLATE PLACEMENT TOL. = 0.250 inches

PLATE ROTATION TOL. = 5.0 Deg.

JSI GRIP= 0.11 (A) (INPUT = 0.90)
JSI METAL= 0.03 (A) (INPUT = 1.00)




Structural component only
DWG# T-2007105

JOB NAME 408152	TRUSS NAME J41	QUANTITY 4	PLY 1	JOB DESC. GREEN PARK HOMES	DRWG NO.
Tamarack Roof Truss, Burlington					

Version 8.310 S Oct 29 2019 Mitek Industries, Inc. Sat Apr 25 11:29:31 2020 Page 1
ID:17vF7aG0E03cRUJ6X1SrkzIWK-Y2cwkhJbCKCTbzSJsX7a8a7q0FFUJ5WDM29q_zNCOY

Scale = 1:15.7



LUMBER			
N. L. G. A. RULES	SIZE	LUMBER	DESCR.
CHORDS	2x4	DRY	No.2
E - B	2x4	DRY	No.2
A - C	2x4	DRY	No.2
E - D	2x4	DRY	No.2

DRY: SEASONED LUMBER.

PLATES (table in inches)

JT	TYPE	PLATES	W	LEN	Y	X
B	TMV+p	MT20	3.0	4.0		
E	BMV1+p	MT20	3.0	4.0		

DIMENSIONS, SUPPORTS AND LOADINGS SPECIFIED BY FABRICATOR TO BE VERIFIED BY BUILDING DESIGNER

BEARINGS		FACTORED		MAXIMUM FACTORED		INPUT		RECORD	
JT	VERT	GROSS REACTION	HORZ	DOWN	HORZ	BRG	IN-SX	BRG	IN-SX
E	319	0	319	0	0	5-8	5-8	5-8	5-8
C	99	0	99	0	0	1-8	1-8	1-8	1-8
D	23	0	23	0	0	1-8	1-8	1-8	1-8

SEE MITEK STANDARD DETAIL B97791H FOR CONNECTION TO JOINT(S) C, D

UNFACTORED REACTIONS

1ST CASE		MAX. MIN. COMPONENT REACTIONS		WIND		DEAD		SOIL	
JT	COMBINED	SNOW	LIVE	PERM. LIVE	WIND	DEAD	SOIL	DEAD	SOIL
E	223	161 / 0	0 / 0	0 / 0	0 / 0	62 / 0	0 / 0	0 / 0	0 / 0
C	68	55 / 0	0 / 0	0 / 0	0 / 0	13 / 0	0 / 0	0 / 0	0 / 0
D	18	0 / 0	0 / 0	0 / 0	0 / 0	18 / 0	0 / 0	0 / 0	0 / 0

BEARING MATERIAL TO BE SPF NO.2 OR BETTER AT JOINT(S) E

BRACING

TOP CHORD TO BE SHEATHED OR MAX. PURLIN SPACING = 6.25 FT.
MAX. UNBRACED BOTTOM CHORD LENGTH = 10.00 FT OR RIGID CEILING DIRECTLY APPLIED.

ALL PITCH BREAKS AND PERIMETER CORNER JOINTS MUST BE Laterally RESTRAINED.

LOADING

TOTAL LOAD CASES: (5)

CHORDS		FACTORED		WEBS		FACTORED	
MEMB.	FORCE (LBS)	VERT. LOAD (PLF)	MAX. CSI (LC)	MEMB.	FORCE (LBS)	MAX. CSI (LC)	MAX. FACTORED
FR-TO		FROM TO		FR-TO			
E-B	-289 / 0	0.0	0.0 0.02 (4)	7.81			
A-B	0 / 28	-91.8	-91.8 0.13 (5)	10.00			
B-C	-15 / 0	-91.8	-91.8 0.13 (1)	6.25			
E-D	0 / 0	-18.5	-18.5 0.03 (4)	10.00			

CANTILEVER ANALYSIS HAS BEEN CONSIDERED IN THIS DESIGN

TOTAL WEIGHT = 4 X 10 = 38 lb

DESIGN CRITERIA

SPECIFIED LOADS:

TOP CH.	LL = 28.8	PSF
DL = 6.0	PSF	
BOT CH.	LL = 0.0	PSF
DL = 7.4	PSF	
TOTAL LOAD	= 39.0	PSF

SPACING = 24.0 IN. O.C.

THIS TRUSS IS DESIGNED FOR RESIDENTIAL OR SMALL BUILDING REQUIREMENTS OF PART 9, NBCG 2010, NBCG 2015

THIS DESIGN COMPLIES WITH:

- PART 9 OF NBCG 2010, CBC 2012, ABC 2019
- PART 9 OF CBC 2012 (2019 AMENDMENT)
- CSA 088-09, CSA 088-14
- TPIC 2011, TPIC 2014

DESIGN ASSUMPTIONS

- OVERHANG NOT TO BE ALTERED OR CUT OFF.

(55 % OF 31.3 P.S.F. G.S.L. PLUS 8.4 P.S.F. RAIN LOAD) EQUALS 25.6 P.S.F. SPECIFIED ROOF LIVE LOAD

ALLOWABLE DEFL. (LL) = L/380 (0.19")
CALCULATED VERT. DEFL. (LL) = L/989 (0.00")
ALLOWABLE DEFL. (TL) = L/380 (0.19")
CALCULATED VERT. DEFL. (TL) = L/989 (0.00")

CSI: TC=0.13/1.00 (B-C:1), BC=0.03/1.00 (D-E:4), WB=0.00/1.00 (A-B:0), SI=0.11/1.00 (B-C:1)

DOL LUMBER=1.00 NAIL=1.00 LS BEND=1.10
COMP=1.10 SHEAR=1.10 TENS=1.10

COMPANION LIVE LOAD FACTOR = 1.00

AUTOSOLVE RIGHT HEEL ONLY

TRUSS PLATE MANUFACTURER IS NOT RESPONSIBLE FOR QUALITY CONTROL IN THE TRUSS MANUFACTURING PLANT.


NAIL VALUES

PLATE	GRIP (DRY)	SHEAR	SECTION
(PSI)	(PLI)	(PLI)	(PLI)
MAX	MIN	MAX	MIN
MT20	618	364	1867 788 1867 1656

PLATE PLACEMENT TOL. = 0.250 inches

PLATE ROTATION TOL. = 5.0 Deg.

JSI GRIP = 0.12 (E) (INPUT = 0.90)
JSI METAL = 0.08 (B) (INPUT = 1.00)




Structural component only
DWG# T-2007106

JOB NAME 408150	TRUSS NAME C1	QUANTITY 1	PLY 1	JOB DESC. GREEN PARK HOMES	ORWG NO.
Tamarack Roof Truss, Burlington					

Version 8.310 S Oct 29 2019 Mitek Industries, Inc. Sat Apr 25 11:02:37 2020 Page 1
ID:7vF?aG0E03cRUj8X1j5RkziWYK-oX4m_oJvuf_CqZaFmuZV9nkjvPNuJLXy4F4l0XzNCnm

Scale = 1:19.6



LUMBER			
N. L. G. A. RULES	CHORDS	SIZE	LUMBER
F - B	2x4	DRY	No.2
A - C	2x4	DRY	No.2
F - D	2x4	DRY	No.2
ALL WEBS	2x3	DRY	No.2
DRY: SEASONED LUMBER.			

PLATES (table is in inches)					
JT TYPE	PLATES	W	LEN	Y	X
B TMVW+p	MT20	4.0	4.0	1.00	2.00
E BMVW+w	MT20	2.0	4.0		
F BMV1+p	MT20	3.0	4.0		

DIMENSIONS, SUPPORTS AND LOADINGS SPECIFIED BY FABRICATOR TO BE VERIFIED BY BUILDING DESIGNER

FACTORED		MAXIMUM FACTORED		INPUT		REQD	
GROSS REACTION		GROSS REACTION		BRG		BRG	
JT	VERT	HORZ	DOWN	HORZ	UPLIFT	IN-SX	IN-SX
F	297	0	297	0	5.8	5.8	
C	42	0	42	0	1.8	1.8	
D	38	0	40	0	1.8	1.8	

SEE MTEK STANDARD DETAIL 897791H FOR CONNECTION TO JOINT(S) C, D

PROVIDE ANCHORAGE AT BEARING JOINT C FOR 150 LBS FACTORED UPLIFT

UNFACTORED REACTIONS

1ST CASE		MAX/MIN		COMPONENT REACTIONS			
JT	COMBINED	SNOW	LIVE	PERM.LIVE	WIND	DEAD	SOIL
F	208	145/0	0/0	0/0	0/0	63/0	0/0
C	29	23/-28	0/0	0/0	0/0	5/0	0/0
D	29	0/0	0/0	0/0	0/0	29/0	0/0

BEARING MATERIAL TO BE SPF NO.2 OR BETTER AT JOINT(S) F, C

BRACING

TOP CHORD TO BE SHEATHED OR MAX. PURLIN SPACING = 6.25 FT.
MAX. UNBRACED BOTTOM CHORD LENGTH = 10.00 FT OR RIGID CEILING DIRECTLY APPLIED.

ALL PITCH BREAKS AND PERIMETER CORNER JOINTS MUST BE Laterally RESTRAINED.

LOADING

TOTAL LOAD CASES: (5)

CHORDS		FACTORED		WEBS		FACTORED	
MEMB.	FORCE (LBS)	VERT. LOAD	LC1 MAX (PLF)	MAX. CS1 (LC)	MEMB.	FORCE (LBS)	MAX CS1 (LC)
FR-TO					FR-TO		
F-B	-281/0	0.0	0.0	0.03 (1)	B-E	0/0	0.00 (1)
A-B	0/41	-91.8	-91.8	0.14 (5)			
B-C	-29/0	-91.8	-91.8	0.14 (5)			
F-E	0/0	-18.5	-18.5	0.08 (4)			
E-G	0/0	-18.5	-18.5	0.08 (4)			
G-D	0/0	-18.5	-18.5	0.08 (4)			

FACTORED CONCENTRATED LOADS (LBS)

JT	LOC	LC1	MAX-	MAX+	FACE	DIR.	TYPE	HEEL	CONN.
G	2-0-12	1	1	---	BACK	VERT	TOTAL	---	C1

CONNECTION REQUIREMENTS

1) C1: A SUITABLE HANGER/MECHANICAL CONNECTION IS REQUIRED.

CANTILEVER ANALYSIS HAS BEEN CONSIDERED IN THIS DESIGN

TOTAL WEIGHT = 12 lb

DESIGN CRITERIA

SPECIFIED LOADS:

TOP CH.	LL	=	25.8	PSF
	DL	=	8.0	PSF
BOT CH.	LL	=	0.0	PSF
	DL	=	7.4	PSF
TOTAL LOAD		=	39.0	PSF

SPACING = 24.0 IN. C/C

THIS TRUSS IS DESIGNED FOR RESIDENTIAL OR SMALL BUILDING REQUIREMENTS OF PART 9, NBC 2010, NBC 2015

THIS DESIGN COMPLIES WITH:

- PART 9 OF CBC 2010, CBC 2012, ABC 2019
- PART 9 OF CBC 2012 (2019 AMENDMENT)
- CSA 088-09, CSA 088-14
- TPIC 2011, TPIC 2014

DESIGN ASSUMPTIONS

OVERHANG NOT TO BE ALTERED OR CUT OFF.

(85 % OF 31.3 P.S.F. G.S.L. PLUS 8.4 P.S.F. RAIN LOAD) EQUALS 25.8 P.S.F. SPECIFIED ROOF LIVE LOAD

ALLOWABLE DEFL.(LL) = $L/380$ (0.19")

CALCULATED VERT. DEFL.(LL) = $L/999$ (0.00")

ALLOWABLE DEFL.(TL) = $L/380$ (0.19")

CALCULATED VERT. DEFL.(TL) = $L/999$ (0.01")

CS1: TC=0.14/1.00 (A-B:5), BC=0.08/1.00 (D-E:4), WB=0.00/1.00 (B-E:1), SS1=0.09/1.00 (A-B:5)

DOL LUMBER=1.00 NAIL=1.00 LS BEND=1.10 COMP=1.10 SHEAR=1.10 TENS=1.10

COMPANION LIVE LOAD FACTOR = 1.00

AUTOSOLVE RIGHT HEEL ONLY

TRUSS PLATE MANUFACTURER IS NOT RESPONSIBLE FOR QUALITY CONTROL IN THE TRUSS MANUFACTURING PLANT.


NAIL VALUES

PLATE	GRIP(DRY)		SHEAR		SECTION	
	(PSI)		(PL)		(PL)	
	MAX	MIN	MAX	MIN	MAX	MIN
MT20	818	354	1687	788	1987	1858


PLATE PLACEMENT TOL. = 0.250 inches

PLATE ROTATION TOL. = 5.0 Deg.

JSI GRIP = 0.20 (B) (INPUT = 0.80)
JSI METAL = 0.05 (B) (INPUT = 1.00)



Structural component only
DWG# T-2007055



LUMBER				
N. L. G. A. RULES				
CHORDS	SIZE			LUMBER
E - B	2x4	DRY		No.2
A - C	2x4	DRY		No.2
E - D	2x4	DRY		No.2
ALL WEBS 2x3		DRY		No.2
DRY: SEASONED LUMBER.				

PLATES (table is in inches)

JT TYPE	PLATES	W	LEN	Y	X
B	TMVW-p	MT20	4.0	4.0	1.00 2.00
D	BMV1-l	MT20	4.0	4.0	2.00 1.25
E	BMV1-p	MT20	3.0	4.0	

DIMENSIONS, SUPPORTS AND LOADINGS SPECIFIED BY FABRICATOR TO BE VERIFIED BY BUILDING DESIGNER

BEARINGS

FACTORED	MAXIMUM FACTORED	INPUT	RECORD
GROSS REACTION	GROSS REACTION	BRG	BRG
JT VERT	DOWN	UP	IN-SX
E	278	0	5-8
C	42	0	1-8
D	18	0	1-8

SEE MITEK STANDARD DETAIL B97791H FOR CONNECTION TO JOINT(S) C, D

PROVIDE ANCHORAGE AT BEARING JOINT C FOR 150 LBS FACTORED UPLIFT

UNFACTORED REACTIONS

1ST CASE	MAX MIN. COMPONENT REACTIONS
COMBINED	SNOW LIVE PERM. LIVE WIND DEAD SOIL
E	184 145/0 0/0 0/0 0/0 48/0 0/0
C	29 23/-28 0/0 0/0 0/0 5/0 0/0
D	14 0/0 0/0 0/0 0/0 14/0 0/0

BEARING MATERIAL TO BE SPF NO.2 OR BETTER AT JOINT(S) E, C

BRACING

TOP CHORD TO BE SHEATHED OR MAX. PURLIN SPACING = 8.25 FT.
MAX. UNBRACED BOTTOM CHORD LENGTH = 10.00 FT OR RIGID CEILING DIRECTLY APPLIED.

ALL PITCH BREAKS AND PERIMETER CORNER JOINTS MUST BE Laterally RESTRAINED.

LOADING

TOTAL LOAD CASES: (5)

CHORDS	MAX. FACTORED	FACTORED	WEBS	MAX. FACTORED
MEMB.	FORCE (LBS)	VERT. LOAD LOI (PLF)	MEMB.	FORCE (LBS)
FR-TO		FROM TO	FR-TO	
E-B	-281/0	0.0 0.0 0.03 (1)	B-D	0/0
A-B	0/41	-91.8 -91.8 0.13 (1)		
B-C	-28/0	-91.8 -91.8 0.12 (1)		
E-D	0/0	-18.5 -18.5 0.02 (4)		

CANTILEVER ANALYSIS HAS BEEN CONSIDERED IN THIS DESIGN

DESIGN CRITERIA

SPECIFIED LOADS:

TOP CH.	LL	PSF
	25.6	PSF
BOT CH.	LL	PSF
	7.4	PSF
TOTAL LOAD	39.0	PSF

SPACING = 24.0 IN./C

THIS TRUSS IS DESIGNED FOR RESIDENTIAL OR SMALL BUILDING REQUIREMENTS OF PART 9, NBCC 2010, NBCC 2015

THIS DESIGN COMPLIES WITH:

- PART 9 OF NBCC 2010, CBC 2012, ABC 2019
- PART 9 OF CBC 2012 (2019 AMENDMENT)
- CSA 088-09, CSA 088-14
- TPIC 2011, TPIC 2014

DESIGN ASSUMPTIONS

OVERHANG NOT TO BE ALTERED OR CUT OFF.

(55 % OF 31.3 P.S.F. G.S.L. PLUS 8.4 P.S.F. RAIN LOAD) EQUALS 25.6 P.S.F. SPECIFIED ROOF LIVE LOAD

ALLOWABLE DEFL.(TL) = L/360 (0.19")
CALCULATED VERT. DEFL.(TL) = L/999 (0.60")

CSI: TC=0.13/1.00 (A-B:1), BC=0.02/1.00 (D-E:4),
WB=0.00/1.00 (B-D:1), SSI=0.08/1.00 (B-C:1)

DOL LUMBER=1.00 NAIL=1.00 LS BEND=1.10
COMP=1.10 SHEAR=1.10 TENS=1.10

COMPANION LIVE LOAD FACTOR = 1.00

TRUSS PLATE MANUFACTURER IS NOT RESPONSIBLE FOR QUALITY CONTROL IN THE TRUSS MANUFACTURING PLANT.


NAIL VALUES

PLATE	GRP(DRY)	SHEAR	SECTION
(PSI)	(PLI)	(PLI)	(PLI)
MAX MIN	MAX MIN	MAX MIN	MAX MIN
MT20	618 354	1687 788	1987 1656

PLATE PLACEMENT TOL. = 0.250 inches


PLATE ROTATION TOL. = 5.0 Deg.

JSI GRIP = 0.20 (B) (INPUT = 0.80)
JSI METAL = 0.05 (B) (INPUT = 1.00)



JOB NAME 408152	TRUSS NAME C40	QUANTITY 4	PLY 1	JOB DESC. GREEN PARK HOMES	DRWG NO.
Tamarack Roof Truss, Burlington					

Version 8.310 S Oct 29 2019 Mitek Industries, Inc. Sat Apr 25 11:29:21 2020 Page 1
ID:7vF7aG0E03cRUj6X1jSkzWYK-q778aGk1873dG3CXKlA19Pt_o08nd2voddJZzNCOI



LUMBER

N. L. G. A. RULES	CHORDS	SIZE	DRY	LUMBER	DESCR.
E - B	2x4	DRY	No.2	SPF	
A - C	2x4	DRY	No.2	SPF	
E - D	2x4	DRY	No.2	SPF	

DRY: SEASONED LUMBER.

PLATES (table in inches)

JT	TYPE	PLATES	W	LEN	Y	X
B	TMV+p	MT20	3.0	4.0		
E	BMV1+p	MT20	3.0	4.0		

DIMENSIONS, SUPPORTS AND LOADINGS SPECIFIED BY FABRICATOR TO BE VERIFIED BY BUILDING DESIGNER

BEARINGS

JT	VERT	HORZ	DOWN	HORZ	UPLIFT	IN-SX	REGRD
E	405	0	405	0	0	5-8	5-8
C	130	0	130	0	0	1-8	1-8
D	45	0	50	0	0	1-8	1-8

SEE MITEK STANDARD DETAIL 897791H FOR CONNECTION TO JOINT(S) C, D

UNFACTORED REACTIONS

JT	1ST CASE	SNOW	LIVE	PERM. LIVE	WIND	DEAD	SOIL
E	288	180 / 0	0 / 0	0 / 0	0 / 0	98 / 0	0 / 0
C	80	73 / 0	0 / 0	0 / 0	0 / 0	17 / 0	0 / 0
D	36	0 / 0	0 / 0	0 / 0	0 / 0	38 / 0	0 / 0

BEARING MATERIAL TO BE SPF NO.2 OR BETTER AT JOINT(S) E, C

BRACING

TOP CHORD TO BE SHEATHED OR MAX. PURLIN SPACING = 8.25 FT.
MAX. UNBRACED BOTTOM CHORD LENGTH = 10.00 FT OR RIGID CEILING DIRECTLY APPLIED.

ALL PITCH BREAKS AND PERIMETER CORNER JOINTS MUST BE LATERALLY RESTRAINED.

LOADING

TOTAL LOAD CASES: (4)

CHORDS				WEBS			
MEMB.	MAX. FACTORED FORCE (LBS)	FACTORED VERT. LOAD (PLF)	MAX. FACTORED CSI (LC)	MEMB.	MAX. FACTORED FORCE (LBS)	MAX. FACTORED CSI (LC)	
FR-TO		FROM	TO	FR-TO			
E-B	-342 / 0	0.0	0.0 0.13 (4)	7.81			
A-B	0 / 28	-91.8	-91.8 0.12 (1)	10.00			
B-C	-19 / 0	-91.8	-91.8 0.22 (1)	6.25			
E-D	0 / 0	-18.5	-18.5 0.13 (4)	10.00			

TOTAL WEIGHT = 4 X 14 = 57 lb

DESIGN CRITERIA

SPECIFIED LOADS:

TOP CH.	LL = 25.8	PSF
DL = 8.0	PSF	
BOT CH.	LL = 0.0	PSF
DL = 7.4	PSF	
TOTAL LOAD	= 39.0	PSF

SPACING = 24.0 IN. C/C

THIS TRUSS IS DESIGNED FOR RESIDENTIAL OR SMALL BUILDING REQUIREMENTS OF PART 8, NBCG 2010, NBCG 2015

THIS DESIGN COMPLIES WITH:

- PART 9 OF CBCG 2010, CBC 2012, ABC 2019
- PART 9 OF CBCG 2012 (2019 AMENDMENT)
- CSA 088-09, CSA 088-14
- TPIC 2011, TPIC 2014

DESIGN ASSUMPTIONS

OVERHANG NOT TO BE ALTERED OR CUT OFF.

(65% OF 31.3 P.S.F. G.S.L. PLUS 8.4 P.S.F. RAIN LOAD) EQUALS 25.6 P.S.F. SPECIFIED ROOF LIVE LOAD

ALLOWABLE DEFL.(LL) = L/360 (0.20")
CALCULATED VERT. DEFL.(LL) = L/999 (0.00")
ALLOWABLE DEFL.(TL) = L/360 (0.20")
CALCULATED VERT. DEFL.(TL) = L/999 (0.03")

CSI: TC=0.22/1.00 (B-C:1), SC=0.13/1.00 (D-E:4),
WB=0.00/1.00 (n/a:0), SSI=0.15/1.00 (B-C:1)

DOL LUMBER=1.00 NAIL=1.00 LS BEND=1.10
COMP=1.10 SHEAR=1.10 TENS=1.10

COMPANION LIVE LOAD FACTOR = 1.00

AUTOSOLVE RIGHT HEEL ONLY

TRUSS PLATE MANUFACTURER IS NOT RESPONSIBLE FOR QUALITY CONTROL IN THE TRUSS MANUFACTURING PLANT.

NAIL VALUES

PLATE	GRIP(DRY)	SHEAR	SECTION
(PSI)	(PLI)	(PLI)	(PLI)
MAX	MIN	MAX	MIN
MT20	616	354	1667 788 1987 1658

PLATE PLACEMENT TOL = 0.250 inches

PLATE ROTATION TOL = 5.0 Deg.

JSI GRIP = 0.14 (E) (INPUT = 0.90)
JSI METAL = 0.09 (B) (INPUT = 1.00)




Structural component only
DWG# T-2007098

JOB NAME	TRUSS NAME	QUANTITY	PLY	JOB DESC.	GREEN PARK HOMES	DRWG NO.
408152	C41	4	1	TRUSS DESC.		

Tamarack Roof Truss, Burlington

Version 8.310 S Oct 29 2019 Mitek Industries, Inc. Sat Apr 25 11:29:23 2020 Page 1
ID:7vF7aG0E03cRU(6X1)SrkzWYK-nV7u2yHglUKVNMvAN7FSFnyoUmch6LN66kNSzNCOg



Scale = 1:12.1

LUMBER

N. L. G. A. RULES	SIZE	LUMBER
CHORDS	2x4	DRY
E - B	2x4	DRY
A - C	2x4	DRY
E - D	2x4	DRY

DRY: SEASONED LUMBER.

PLATES (table is in inches)

JT TYPE	PLATES	W	LEN	Y	X
B	TMV+p	MT20	3.0	4.0	
E	BMV1+p	MT20	3.0	4.0	

DIMENSIONS, SUPPORTS AND LOADINGS SPECIFIED BY FABRICATOR TO BE VERIFIED BY BUILDING DESIGNER

DESCR.	SPF	SPF	FACTORED GROSS REACTION	MAXIMUM FACTORED GROSS REACTION	INPUT BRG	REQD BRG
JT			VERT	HORZ	DOWN	HORZ
E			284	0	284	0
C			63	0	63	0
D			44	0	52	0

SEE MITEK STANDARD DETAIL B97791H FOR CONNECTION TO JOINT(S) C, D

UNFACTORED REACTIONS

JT	1ST CASE	SNOW	LIVE	PERM. LIVE	WIND	DEAD	SOIL
E	200	137 / 0	0 / 0	0 / 0	0 / 0	82 / 0	0 / 0
C	46	21 / 0	0 / 0	0 / 0	0 / 0	25 / 0	0 / 0
D	35	0 / -3	0 / 0	0 / 0	0 / 0	37 / 0	0 / 0

BEARING MATERIAL TO BE SPF NO.2 OR BETTER AT JOINT(S) E, C

BRACING

TOP CHORD TO BE SHEATHED OR MAX. PURLIN SPACING = 10.00 FT.
MAX. UNBRACED BOTTOM CHORD LENGTH = 10.00 FT OR RIGID CEILING DIRECTLY APPLIED.

ALL PITCH BREAKS AND PERIMETER CORNER JOINTS MUST BE Laterally RESTRAINED.

LOADING

TOTAL LOAD CASES: (7)

CHORDS	MEMB.	MAX. FACTORED FORCE (LBS)	FACTORED VERT. LOAD (PLF)	FACTORED MAX. LOAD (LC1)	MAX. UNBRACED LENGTH (FR-TO)	WEBS	MEMB.	MAX. FACTORED FORCE (LBS)	MAX. LOAD (LC1)
E-B		-227 / 0	0.0	0.0	0.11 (4)	7.81			
A-B		0 / 28	-91.8	-91.8	0.12 (1)	10.00			
B-C		-9 / 9	-91.8	-91.8	0.08 (4)	10.00			
E-F		0 / 0	-18.5	-18.5	0.14 (4)	10.00			
F-G		0 / 0	-18.5	-18.5	0.14 (4)	10.00			
G-D		0 / 0	-18.5	-18.5	0.14 (4)	10.00			

FACTORED CONCENTRATED LOADS (LBS)

JT	LOC.	LC1	MAX.	MAX+	FACE	DIR.	TYPE	HEEL	CONN.
F	1-11.4	7	1	12	BACK	VERT	TOTAL	---	C1
G	3-11.4	1	1	---	BACK	VERT	TOTAL	---	C1

CONNECTION REQUIREMENTS

1) C1: A SUITABLE HANGER/MECHANICAL CONNECTION IS REQUIRED.

TOTAL WEIGHT = 4 X 12 = 48 lb

DESIGN CRITERIA

SPECIFIED LOADS:
TOP CH. LL = 25.6 PSF
DL = 6.0 PSF
BOT CH. LL = 0.0 PSF
DL = 7.4 PSF
TOTAL LOAD = 39.0 PSF

SPACING = 24.0 IN. C/C

THIS TRUSS IS DESIGNED FOR RESIDENTIAL OR SMALL BUILDING REQUIREMENTS OF PART 9, NBC 2010, NBC 2015

THIS DESIGN COMPLIES WITH:
- PART 9 OF BCBC 2018, OBC 2012, ABC 2019
- PART 9 OF OBC 2012 (2019 AMENDMENT)
- CSA 086-09, CSA 086-14
- TPIC 2011, TPIC 2014

DESIGN ASSUMPTIONS

- OVERHANG NOT TO BE ALTERED OR CUT OFF.
(55 % OF 31.3 P.S.F. G.S.L. PLUS 8.4 P.S.F. RAIN LOAD) EQUALS 25.6 P.S.F. SPECIFIED ROOF LIVE LOAD

ALLOWABLE DEFL.(LL) = $L/360$ (0.20")
CALCULATED VERT. DEFL.(LL) = $L/999$ (0.01")
ALLOWABLE DEFL.(TL) = $L/360$ (0.20")
CALCULATED VERT. DEFL.(TL) = $L/999$ (0.04")

CSI: TC=0.12/1.00 (A-B:1), BC=0.14/1.00 (D-E:4),
WB=0.00/1.00 (n/a:0), SS=0.09/1.00 (A-B:1)

DOL LUMBER=0.99 NAIL=0.98 LS BEND=1.10
COMP=1.10 SHEAR=1.10 TENS=1.10

COMPANION LIVE LOAD FACTOR = 1.00

AUTOSOLVE RIGHT HEEL ONLY

TRUSS PLATE MANUFACTURER IS NOT RESPONSIBLE FOR QUALITY CONTROL IN THE TRUSS MANUFACTURING PLANT.

NAIL VALUES

PLATE	GRIP(DRY)	SHEAR	SECTION
(PSI)	(PL)	(PL)	(PL)
MAX MIN	MAX MIN	MAX MIN	MAX MIN
MT20	618	354	1687

PLATE PLACEMENT TOL. = 0.250 inches

PLATE ROTATION TOL. = 5.0 Deg.


JSI GRIP= 0.10 (E) (INPUT = 0.80)
JSI METAL= 0.08 (B) (INPUT = 1.00)



Structural component only
DWG# T-2007099

JOB NAME	TRUSS NAME	QUANTITY	PLY	JOB DESC.	DRWG NO.
408152	C42	4	1	GREEN PARK HOMES	
Tamarack Roof Truss, Burlington				TRUSS DESC.	

Version 8.310 S Oct 29 2019 Mitek Industries, Inc. Sat Apr 25 11:29:24 2020 Page 1
ID1vF7aG0E03cRUj6X1jS/kzWYK-FinGGHmvR2RB7Xx8PtvMognw8CsuL8MVcmfHwuzNCO



TOTAL WEIGHT = 4 X 10 = 38 lb

LUMBER			
N. L. G. A. RULES	CHORDS	SIZE	LUMBER
E - B	2x4	DRY	No.2
A - C	2x4	DRY	No.2
E - D	2x4	DRY	No.2

DRY: SEASONED LUMBER.

PLATES (tablets in inches)					
JT	TYPE	PLATES	W	LEN	X
B	TMV+p	MT20	3.0	4.0	
E	BMV1+p	MT20	3.0	4.0	

DIMENSIONS, SUPPORTS AND LOADINGS SPECIFIED BY FABRICATOR TO BE VERIFIED BY BUILDING DESIGNER

READINGS		FACTORED	MAXIMUM FACTORED	INPUT	REQD
JT	VERT	GROSS REACTION	GROSS REACTION	BRG	BRG
E	381	0	381	0	5-8
C	130	0	130	0	1-8
D	16	0	17	0	1-8

SEE MITEK STANDARD DETAIL 897791H FOR CONNECTION TO JOINT(S) C, D

UNFACTORED REACTIONS		1ST CASE	MAX/MIN COMPONENT REACTIONS
JT	COMBINED	SNOW	LIVE
E	250	190/0	0/0
C	90	73/0	0/0
D	12	0/0	0/0

BEARING MATERIAL TO BE SPF NO.2 OR BETTER AT JOINT(S) E

BRACING
TOP CHORD TO BE SHEATHED OR MAX. PURLIN SPACING = 6.25 FT.
MAX. UNBRACED BOTTOM CHORD LENGTH = 10.00 FT OR RIGID CEILING DIRECTLY APPLIED.

ALL PITCH BREAKS AND PERIMETER CORNER JOINTS MUST BE Laterally RESTRAINED.

LOADING
TOTAL LOAD CASES: (5)

CHORDS		WEBS	
MEMB.	MAX. FACTORED FORCE (LBS)	MAX. FACTORED VERT. LOAD (LBS)	MAX. FACTORED CS1 (LC)
FR-TO			
E-B	-342/0	0.0	0.01 (4)
A-B	0/28	-91.8	0.13 (5)
B-C	-19/0	-91.8	0.22 (1)
E-D	0/0	-18.5	0.02 (4)

CANTILEVER ANALYSIS HAS BEEN CONSIDERED IN THIS DESIGN

DESIGN CRITERIA

SPECIFIED LOADS:
TOP CH. LL = 25.8 PSF
DL = 8.0 PSF
BOT CH. LL = 0.0 PSF
DL = 7.4 PSF
TOTAL LOAD = 39.0 PSF

SPACING = 24.0 IN. C/C

THIS TRUSS IS DESIGNED FOR RESIDENTIAL OR SMALL BUILDING REQUIREMENTS OF PART 9, NBC 2010, NBC 2015

THIS DESIGN COMPLIES WITH:
- PART 9 OF CBC 2018, CBC 2012, ABC 2019
- PART 9 OF CBC 2012 (2019 AMENDMENT)
- CSA 088-09, CSA 088-14
- TPIC 2011, TPIC 2014

DESIGN ASSUMPTIONS
- OVERHANG NOT TO BE ALTERED OR CUT OFF.

(55% OF 31.3 P.S.F. G.S.L. PLUS 8.4 P.S.F. RAIN LOAD) EQUALS 25.8 P.S.F. SPECIFIED ROOF LIVE LOAD

ALLOWABLE DEFL.(LL) = $L/360$ (0.19")
CALCULATED VERT. DEFL.(LL) = $L/999$ (0.00")
ALLOWABLE DEFL.(TL) = $L/360$ (0.19")
CALCULATED VERT. DEFL.(TL) = $L/999$ (0.00")

CS1: TC=0.22/1.00 (B-C:1), BC=0.02/1.00 (D-E:4), WB=0.00/1.00 (n/a:0), SS1=0.15/1.00 (B-C:1)

DOL LUMBER=1.00 NAIL=1.00 LS BEND=1.10
COMP=1.10 SHEAR=1.10 TENS=1.10

COMPANION LIVE LOAD FACTOR = 1.00

AUTOSOLVE RIGHT HEEL ONLY


TRUSS PLATE MANUFACTURER IS NOT RESPONSIBLE FOR QUALITY CONTROL IN THE TRUSS MANUFACTURING PLANT.

NAIL VALUES
PLATE GRIP(DRY) SHEAR SECTION
(PSI) (PLI) (PLI)
MAX MIN MAX MIN MAX MIN
MT20 '618 '354 '1667 '788 '1987 '1658

PLATE PLACEMENT TOL = 0.250 inches


PLATE ROTATION TOL = 5.0 Deg.

JSI GRIP = 0.14 (E) (INPUT = 0.90)
JSI METAL = 0.09 (B) (INPUT = 1.00)



Structural component only
DWG# T-2007100

JOB NAME	TRUSS NAME	QUANTITY	PLY	JOB DESC.	DRWG NO.
408152	C44	2	1	GREEN PARK HOMES	
Tamarack Roof Truss, Burlington					
Version 8.310 S Oct 29 2019 Mitek Industries, Inc. Sat Apr 25 11:29:28 2020 Page 1					
ID:17vF?aG0E03cRUj8X1jSikzIWK-B4o1hzoAtgVmq5UXlxq15H1?X4p2sn34KO_nzNCOd					
Scale = 1:10.4					



LUMBER	N. L. G. A. RULES	CHORDS	SIZE	LUMBER	DESCR.
E - B	2x4	DRY	No.2	SPF	
A - G	2x4	DRY	No.2	SPF	
E - D	2x4	DRY	No.2	SPF	

DRY: SEASONED LUMBER.

PLATES (tablets in inches)	JT	TYPE	PLATES	W	LEN	Y	X
B	TMV+p	MT20	3.0	4.0			
E	BMV1+p	MT20	3.0	4.0			

DIMENSIONS, SUPPORTS AND LOADINGS SPECIFIED BY FABRICATOR TO BE VERIFIED BY BUILDING DESIGNER

BEARINGS		FACTORED	MAXIMUM FACTORED	INPUT	REQD
		GROSS REACTION	GROSS REACTION	BRG	BRG
JT	VERT	HORZ	DOWN	UPLIFT	IN-SX
E	284	0	284	0	5-8
C	66	0	66	0	1-8
D	23	0	26	0	1-8

SEE MITEK STANDARD DETAIL 897791H FOR CONNECTION TO JOINT(S) C, D

UNFACTORED REACTIONS	1ST CASE	SNOW	LIVE	PERM. LIVE	WIND	DEAD	SOIL
JT	COMBINED						
E	188	130/0	0/0	0/0	0/0	55/0	0/0
C	48	37/0	0/0	0/0	0/0	9/0	0/0
D	18	0/0	0/0	0/0	0/0	18/0	0/0

BEARING MATERIAL TO BE SPF NO.2 OR BETTER AT JOINT(S) E, C

BRACING
TOP CHORD TO BE SHEATHED OR MAX. PURLIN SPACING = 10.00 FT.
MAX. UNBRACED BOTTOM CHORD LENGTH = 10.00 FT OR RIGID CEILING DIRECTLY APPLIED.

ALL PITCH BREAKS AND PERIMETER CORNER JOINTS MUST BE Laterally RESTRAINED.

LOADING
TOTAL LOAD CASES: (5)

CHORDS	MAX. FACTORED FORCE (LBS)	FACTORED VERT. LOAD (LBS)	FACTORED HORZ. LOAD (LBS)	MAX. FACTORED FORCE (LBS)	FACTORED VERT. LOAD (LBS)	FACTORED HORZ. LOAD (LBS)
MEMB.	FR-TO	FR-TO	FR-TO	MEMB.	FR-TO	FR-TO
E-B	-234/0	0.0	0.0	0.02 (4)	7.81	
A-B	0/28	-91.8	-91.8	0.13 (5)	10.00	
B-C	-10/0	-91.8	-91.8	0.06 (1)	10.00	
E-F	0/0	-18.5	-18.5	0.03 (4)	10.00	
F-D	0/0	-18.5	-18.5	0.03 (4)	10.00	

FACTORED CONCENTRATED LOADS (LBS)	JT	LOC.	LC1	MAX-	MAX+	FACE	DIR.	TYPE	HEEL	CONN.
F	2-0-12	1	1	...	...	FRONT	VERT	TOTAL	...	C1

CONNECTION REQUIREMENTS

1) C1: A SUITABLE HANGER/MECHANICAL CONNECTION IS REQUIRED.

CANTILEVER ANALYSIS HAS BEEN CONSIDERED IN THIS DESIGN

TOTAL WEIGHT = 2 X 8 = 17 lb

DESIGN CRITERIA

SPECIFIED LOADS:
TOP CH. LL = 25.6 PSF
DL = 6.0 PSF
BOT CH. LL = 0.0 PSF
DL = 7.4 PSF
TOTAL LOAD = 39.0 PSF

SPACING = 24.0 IN/C

THIS TRUSS IS DESIGNED FOR RESIDENTIAL OR SMALL BUILDING REQUIREMENTS OF PART 9, NBC 2010, NBC 2015

THIS DESIGN COMPLIES WITH:
- PART 9 OF CBC 2018, CBC 2012, ABC 2019
- PART 9 OF CBC 2012 (2019 AMENDMENT)
- CSA 088-09, CSA 088-14
- TPIC 2011, TPIC 2014

DESIGN ASSUMPTIONS
OVERHANG NOT TO BE ALTERED OR CUT OFF.

(65 % OF 31.3 P.S.F. G.S.L. PLUS 8.4 P.S.F. RAIN LOAD) EQUALS 25.6 P.S.F. SPECIFIED ROOF LIVE LOAD

ALLOWABLE DEFL.(LL) = $L/360$ (0.18")
CALCULATED VERT. DEFL.(LL) = $L/999$ (0.00")
ALLOWABLE DEFL.(TL) = $L/360$ (0.18")
CALCULATED VERT. DEFL.(TL) = $L/999$ (0.00")

CSI: TC=0.13/1.00 (A-B:5), BC=0.03/1.00 (D-E:4), WB=0.00/1.00 (v-a:0), SS=0.10/1.00 (A-B:5)

DOL LUMBER=1.00 NAIL=1.00 LS BEND=1.10 COMP=1.10 SHEAR=1.10 TENS=1.10

COMPANION LIVE LOAD FACTOR = 1.00

AUTOSOLVE RIGHT HEEL ONLY


TRUSS PLATE MANUFACTURER IS NOT RESPONSIBLE FOR QUALITY CONTROL IN THE TRUSS MANUFACTURING PLANT.

NAIL VALUES
PLATE GRP(DRY) SHEAR SECTION
(PSI) (PLJ) (PLJ)
MAX MIN MAX MIN MAX MIN
MT20 818 354 1687 788 1987 1656

PLATE PLACEMENT TOL = 0.250 inches

PLATE ROTATION TOL = 5.0 Deg.

JSI GRIP = 0.10 (E) (INPUT = 0.90)
JSI METAL = 0.08 (B) (INPUT = 1.00)




Structural component only
DWG# T-2007102

JOB NAME 408152	TRUSS NAME C45	QUANTITY 2	PLY 1	JOB DESC. GREEN PARK HOMES	DRWG NO.
--------------------	-------------------	---------------	----------	-------------------------------	----------

Tamarack Roof Truss, Burlington

Version 8.310 S Oct 29 2019 Mitek Industries, Inc. Sat Apr 25 11:28:27 2020 Page 1
ID:7vF7aG0E03cRUJ8X1fSrkzWYK-IHMPuJookzqm_gh4DS3PIPT_PiZYV8xIk4xXDzNCOC



Scale = 1/16"

LUMBER N. L. G. A. RULES CHORDS SIZE LUMBER DESCR. SPF
E - B 2x4 DRY No.2 SPF
A - C 2x4 DRY No.2 SPF
E - D 2x4 DRY No.2 SPF
DRY: SEASONED LUMBER.

CHORDS	SIZE	LUMBER	DESCR.	SPF
E - B	2x4	DRY	No.2	SPF
A - C	2x4	DRY	No.2	SPF
E - D	2x4	DRY	No.2	SPF

DRY: SEASONED LUMBER.

PLATES (table in inches)

JT TYPE	PLATES	W	LEN	V	X
B TMV+p	MT20	3.0	4.0		
E BMV1+p	MT20	3.0	4.0		

DIMENSIONS, SUPPORTS AND LOADINGS SPECIFIED BY FABRICATOR TO BE VERIFIED BY BUILDING DESIGNER

JT	FACTORED GROSS REACTION		MAXIMUM FACTORED GROSS REACTION		INPUT BRG IN-SX	RECORD BRG IN-SX
	VERT	HORZ	DOWN	HORZ		
E	254	0	254	0	5-8	5-8
C	68	0	68	0	1-8	1-8
D	16	0	16	0	1-8	1-8

SEE MITEK STANDARD DETAIL 897791H FOR CONNECTION TO JOINT(S) C, D

UNFACTORED REACTIONS

JT	1ST CASE	MAX. MIN. COMPONENT REACTIONS					
		SNOW	LIVE	PERM. LIVE	WIND	DEAD	SOIL
E	177	130 / 0	0 / 0	0 / 0	0 / 0	47 / 0	0 / 0
C	46	37 / 0	0 / 0	0 / 0	0 / 0	9 / 0	0 / 0
D	13	0 / 0	0 / 0	0 / 0	0 / 0	13 / 0	0 / 0

BEARING MATERIAL TO BE SPF NO.2 OR BETTER AT JOINT(S) E, C

BRACING

TOP CHORD TO BE SHEATHED OR MAX. PURLIN SPACING = 10.00 FT.
MAX. UNBRACED BOTTOM CHORD LENGTH = 10.00 FT OR RIGID CEILING DIRECTLY APPLIED.

ALL PITCH BREAKS AND PERIMETER CORNER JOINTS MUST BE LATERALLY RESTRAINED.

LOADING

TOTAL LOAD CASES: (5)

CHORDS				WEBS			
MEMB.	MAX. FACTORED FORCE (LBS)	FACTORED VERT. LOAD (PLF)	LC1 MAX CS1 (LC)	MAX. UNBRACED LENGTH	MEMB.	MAX. FACTORED FORCE (LBS)	MAX CS1 (LC)
FR-TO		FROM TO		FR-TO			
E-B	234 / 0	0.0	0.0	0.01 (4)	7.81		
A-B	0 / 28	-81.8	-91.8	0.12 (1)	10.00		
B-C	-10 / 0	-91.8	-91.8	0.06 (1)	10.00		
E-D	0 / 0	-18.5	-18.5	0.02 (4)	10.00		

CANTILEVER ANALYSIS HAS BEEN CONSIDERED IN THIS DESIGN

DESIGN CRITERIA

SPECIFIED LOADS:

TOP CH. LL = 25.8 PSF

DL = 6.0 PSF

BOT CH. LL = 0.0 PSF

DL = 7.4 PSF

TOTAL LOAD = 39.0 PSF

SPACING = 24.0 IN. O.C.

THIS TRUSS IS DESIGNED FOR RESIDENTIAL OR SMALL BUILDING REQUIREMENTS OF PART 9, NBCC 2010, NBCC 2015

THIS DESIGN COMPLIES WITH:

- PART 9 OF CBC 2010, CBC 2012, ABC 2018

- PART 9 OF CBC 2012 (2019 AMENDMENT)

- CSA 086-09, CSA 086-14

- TPIC 2011, TPIC 2014

DESIGN ASSUMPTIONS

OVERHANG NOT TO BE ALTERED OR CUT OFF.

(55 % OF 31.3 P.S.F. G.S.L. PLUS 8.4 P.S.F. RAIN

LOAD) EQUALS 28.6 P.S.F. SPECIFIED ROOF

LIVE LOAD

ALLOWABLE DEFL. (LL) = $L/360$ (0.19")

CALCULATED VERT. DEFL. (LL) = $L/999$ (0.00")

ALLOWABLE DEFL. (TL) = $L/360$ (0.19")

CALCULATED VERT. DEFL. (TL) = $L/999$ (0.00")

CS1: TC=0.12/1.00 (A-B:1), BC=0.02/1.00 (D-E:4),

WB=0.00/1.00 (n/a:0), SS=0.08/1.00 (A-B:1)

DOL LUMBER=1.00 NAIL=1.00 LS BEND=1.10

COMP=1.10 SHEAR=1.10 TENS=1.10

COMPANION LIVE LOAD FACTOR = 1.00

AUTOSOLVE RIGHT HEEL ONLY

TRUSS PLATE MANUFACTURER IS NOT RESPONSIBLE FOR QUALITY CONTROL IN THE TRUSS MANUFACTURING PLANT.

NAIL VALUES

PLATE GRIP(DRY) SHEAR SECTION

(PSI) (PLI) (PLI)

MAX MIN MAX MIN MAX MIN

MT20 618 354 1887 788 1987 1658

PLATE PLACEMENT TOL = 0.250 inches

PLATE ROTATION TOL = 5.0 Deg.

JSI GRIP = 0.10 (E) (INPUT = 0.90)

JSI METAL = 0.08 (B) (INPUT = 1.00)



Structural component only
DWG# T-2007103

LUL/LUS/LJS/HUS/HHUS/HGUS

Standard and Double-Shear Joist Hangers



This product is preferable to similar connectors because of
 a) easier installation, b) higher capacities, c) lower installed
 cost, or a combination of these features.

Most hangers in this series have double-shear nailing — an innovation that distributes the load through two points on each joist nail for greater strength. This allows for fewer nails, faster installation, and the use of all common nails for the same connection. (Do not bend or remove tabs)

Double-shear hangers range from the light capacity LUS hangers to the highest capacity HGUS hangers. For medium load truss applications, the HUS offers a lower cost alternative and easier installation than the HGUS hangers, while providing greater load capacity and bearing than the LUS.

Material: See table on pp. 258–259.

Finish: Galvanized. Some products available in stainless steel or ZMAX® coating; see Corrosion Information, pp. 20–24.

Installation:


- Use all specified fasteners; see General Notes.
- Nails must be driven at an angle through the joist or truss into the header to achieve the tabulated resistances (except LUL).
- Where 16d commons are specified, 10d commons may be used at 0.83 of the tabulated factored resistance.
- Not designed for welded or nailer applications.
- With single ply 2x carrying members, use 10d x 1½" nails into the header and 10d commons into the joist, and reduce the resistance to 0.64 of the table value where 16d nails are specified and 0.77 where 10d nails are specified.

Options:


- LUS, LJS, LUL and HUS hangers cannot be modified.
- Other sizes available; consult your Simpson Strong-Tie representative.
- See Hanger Options Information on p. 126.




Double-Shear
Nailing
Top View




Double-Shear
Nailing
Side View;
Do not
bend tab




Double-Shear
Nailing Side View
(available on
some models)
U.S. Patent 5,803,680




✓ LUS28




LUS28L




✓ HUS210
(HUS26, HUS28,
and HHUS similar)



✓ HGUS28-2




✓ HHUS210-2



LJS26DS

Typical HUS26
Installation
with Reduced
Heel Height
(Truss Designer
to provide
fastener quantity
for connecting
multiple members
together)



LUL/LUS/LJS/HUS/HHUS/HGUS**HHUS/HGUS**

See Hanger Options Information on pp. 125–127.



HHUS — Sloped and/or Skewed Seat

- HHUS hangers can be skewed to a maximum of 45° and/or sloped to a maximum of 45°
- For skew only, maximum factored down resistance is 0.85 of the table value
- For sloped only or sloped and skewed hangers, the maximum factored down resistance is 0.72 of the table value
- Uplift resistances for sloped/skewed conditions are 0.62 of the table value
- The joist must be bevel-cut to allow for double-shear nailing

HGUS — Skewed Seat

- HGUS hangers can be skewed only to a maximum of 45°. Factored resistances are:

HGUS Seat Width	Joist	Down Resistance	Uplift
$W < 2"$	Bevel or square cut	0.62 of table value	0.46 of table value
$2" < W < 6"$	Bevel cut	0.67 of table value	0.41 of table value
$2" < W < 6"$	Square cut	0.48 of table value	0.41 of table value
$W > 6"$	Bevel cut	0.75 of table value	0.41 of table value



Top View HHUS Hanger Skewed Right
(joist must be bevel cut)
All joist nails installed on the outside angle (non-acute side).

Standard and Double-Shear Joist Hangers (cont.)

These products are available with additional corrosion protection. For more information, see p. 24.

These products are approved for installation with the Strong-Drive® SD Connector screw. See pp. 32–34 for more information.

Model No.	Ga.	Dimensions (in.)					Fasteners		Factored Resistance			
		W	H	B	d _g ³	Header	Joist		D.Fir-L		S-P-F	
									Uplift	Normal	Uplift	Normal
									(K _D = 1.15)	(K _D = 1.00)	(K _D = 1.15)	(K _D = 1.00)
									lb.	lb.	lb.	lb.
									kN	kN	kN	kN
Single 2x Sizes												
LUS24	18	1 1/8	3 1/4	1 3/4	2 1/4	(4) 10d	(2) 10d		710	1625	645	1155
									3.16	7.23	2.87	5.14
LU24L	22	1 1/8	3	1 1/2	2 1/8	(4) 10d	(2) 10d x 1 1/2"		360	1020	320	725
									1.60	4.54	1.42	3.22
LU20L	22	1 1/8	5	1 1/2	4 1/4	(6) 10d	(4) 10d x 1 1/2"		720	1605	645	1140
									3.20	7.14	2.87	5.07
SS LUS26	18	1 1/8	4 1/4	1 3/4	3 3/4	(4) 10d	(4) 10d		1420	2170	1290	1830
									6.32	9.65	5.74	7.25
HUS28	16	1 1/2	5 1/2	3	3 3/8	(14) 16d	(6) 16d		2705	4940	2065	3675
									11.90	21.97	9.20	17.24
LJS26DS	18	1 1/8	5	3 1/2	4 1/4	(16) 16d	(6) 16d		2055	4265	1460	4115
									9.14	18.97	6.49	18.31
HGUS26	12	1 1/8	5 1/2	5	4 1/4	(20) 16d	(8) 16d		2685	6625	2685	6700
									11.98	29.51	11.98	25.35
LU28L	20	1 1/8	6 1/4	1 1/2	5 1/4	(8) 10d	(6) 10d x 1 1/2"		1140	2185	1020	1550
									5.07	9.72	4.54	6.89
SS LUS28	18	1 1/8	6 1/4	1 3/4	3 3/4	(8) 10d	(4) 10d		1420	2620	1290	1790
									6.32	11.21	5.74	7.98
HUS26	16	1 1/2	7 1/8	3	6 1/8	(22) 16d	(8) 16d		3605	5365	2675	4345
									16.04	23.88	11.90	19.33
HGUS28	12	1 1/2	7 1/2	5	6 1/4	(36) 16d	(12) 16d		3310	7675	3310	6900
									14.74	34.19	14.74	30.73
LU210L	20	1 1/8	8	1 1/2	7 1/4	(10) 10d	(8) 10d x 1 1/2"		1140	2495	1020	1770
									5.07	11.10	4.54	7.87
SS LUS210	18	1 1/8	7 1/8	1 1/2	3 3/4	(8) 10d	(4) 10d		1420	2785	1290	2210
									6.32	12.39	5.74	9.83

1. Factored uplift resistances have been increased 15% for wind or earthquake loading; no further increase is allowed.
2. Designer must ensure that hanger is compatible with truss when reduced heel height is used.
3. d_g is the distance from the bearing seat to the top joist nail.
4. Resistances shown require a minimum 2-ply glider truss. For fastening to single-ply truss request technical bulletin T-C-N10TRSSON and/or see installation notes.
5. Nails: 16d = 0.162" dia. x 3 1/2" long. See pp. 27–28 for other nail sizes and information.

Face-Mount Hangers

These products are available with additional corrosion protection. For more information, see p. 24.

These products are approved for installation with the Strong-Drive® SD Connector screw. See pp. 32-34 for more information.

Model No.	Ga.	Dimensions (in.)				Fasteners		Factored Resistance			
		W	H	B	d _g ³	Header	Joist	D-Fir-L		S-P-F	
								Uplift	Normal	Uplift	Normal
								(K _D = 1.15) lb. kN	(K _D = 1.00) lb. kN	(K _D = 1.15) lb. kN	(K _D = 1.00) lb. kN
Double 2x Sizes											
LUS24-2	18	3 1/8	3 1/8	2	1 1/8	(4) 16d	(2) 16d	835 3.71	2020 8.99	590 2.62	1435 6.38
LUS26-2	18	3 1/8	4 1/8	2	4	(4) 16d	(4) 16d	1720 7.65	2595 11.54	1545 6.87	1920 8.64
HHUS26-2	14	3 1/8	5 1/8	3	3 1/8	(14) 16d	(8) 16d	2850 12.68	7335 32.83	2065 9.20	5205 23.15
HGUS26-2	12	3 1/8	5 1/8	4	4 1/8	(20) 16d	(8) 16d	4385 19.51	8950 39.81	3110 13.83	8355 28.27
LUS28-2	18	3 1/8	7	2	4	(8) 16d	(4) 16d	1720 7.65	3325 14.79	1545 6.87	2675 11.45
HHUS28-2	14	3 1/8	7 1/8	3	6 1/8	(22) 16d	(8) 16d	3765 16.75	8940 39.77	2675 11.90	8345 28.22
HGUS28-2	12	3 1/8	7 1/8	4	8 1/8	(36) 16d	(12) 16d	6070 27.00	12980 57.74	4310 19.17	9215 40.99
LUS210-2	18	3 1/8	9	2	6	(8) 16d	(8) 16d	2580 11.48	4500 20.02	2320 10.32	3195 14.21
HHUS210-2	14	3 1/8	9 1/8	3	8	(30) 16d	(10) 16d	4670 26.77	9660 42.97	4235 18.84	7000 31.14
HGUS210-2	12	3 1/8	9 1/8	4	8 1/8	(48) 16d	(16) 16d	6840 30.43	14015 62.34	4855 21.60	10270 45.89
Triple 2x Sizes											
HGUS26-3	12	4 1/8	5 1/8	4	4 1/8	(20) 16d	(8) 16d	4385 19.51	8950 39.81	3110 13.83	8355 28.27
HGUS28-3	12	4 1/8	7 1/8	4	6 1/8	(36) 16d	(12) 16d	6070 27.00	12980 57.74	4310 19.17	9215 40.99
HHUS210-3	14	4 1/8	9	3	7 1/8	(30) 16d	(10) 16d	4670 20.77	9670 43.02	4235 18.84	8865 30.54
HGUS210-3	12	4 1/8	9 1/8	4	8 1/8	(48) 16d	(16) 16d	6840 30.43	14645 65.14	4855 21.60	10400 46.28
Quadruple 2x Sizes											
HGUS28-4	12	6 1/8	5 1/8	4	4 1/8	(20) 16d	(8) 16d	4385 19.51	8950 39.81	3110 13.83	8355 28.27
HGUS28-4	12	6 1/8	7 1/8	4	6 1/8	(36) 16d	(12) 16d	6070 27.00	12980 57.74	4310 19.17	9215 40.99
HHUS210-4	14	6 1/8	8 1/8	3	7 1/8	(30) 16d	(10) 16d	4670 20.77	10150 45.17	4235 18.84	7210 32.07
HGUS210-4	12	6 1/8	8 1/8	4	8 1/8	(48) 16d	(16) 16d	6840 30.43	14645 65.14	4855 21.60	10400 46.28
HGUS212-4	12	6 1/8	10 1/8	4	10 1/8	(56) 16d	(20) 16d	7640 33.98	14895 66.70	5425 24.13	10645 47.35
HGUS214-4	12	6 1/8	12 1/8	4	11 1/8	(66) 16d	(22) 16d	10130 45.06	16400 72.95	7195 32.00	11645 51.80
4x Sizes											
LUS46	18	3 1/8	4 1/8	2	3 3/8	(4) 16d	(4) 16d	1720 7.65	2595 11.54	1545 6.87	1920 8.64
HHUS46	14	3 1/8	5 1/8	3	3 1/8	(14) 16d	(8) 16d	2840 11.30	7335 32.83	2065 9.20	5205 23.15
HGUS46	12	3 1/8	5 1/8	4	4 3/8	(20) 16d	(8) 16d	4385 19.51	8950 39.81	3110 13.83	8355 28.27
LUS48	18	3 1/8	6 3/8	2	3 1/8	(8) 16d	(4) 16d	1720 7.65	3325 14.79	1545 6.87	2675 11.45
HHUS48	14	3 1/8	7 1/8	3	6 1/8	(22) 16d	(8) 16d	3765 16.75	8940 39.77	2675 11.90	8345 28.22
HGUS48	12	3 1/8	7 1/8	4	6 3/8	(36) 16d	(12) 16d	6070 27.00	12980 57.74	4310 19.17	9215 40.99
LUS410	18	3 1/8	8 3/8	2	5 3/8	(8) 16d	(8) 16d	2580 11.48	4500 20.02	2320 10.32	3195 14.21
HGUS410	12	3 1/8	9	4	8 1/8	(48) 16d	(16) 16d	6840 30.43	14015 62.34	4855 21.60	10270 45.89
HGUS412	12	3 1/8	10 3/8	4	10 3/8	(56) 16d	(20) 16d	7640 33.98	14895 66.70	5425 24.13	10645 47.35
HGUS414	12	3 1/8	12 3/8	4	11 3/8	(66) 16d	(22) 16d	10130 45.06	16400 72.95	7195 32.00	11645 51.80

TC - Truss Connectors

SIMPSON
Strong-Tie

The TC truss connector is an ideal connector for scissor trusses and can allow horizontal movement up to 1/4". The TC also attaches plated trusses to top plates or sill plates to resist uplift forces. Typically used on one or both ends of truss as determined by the building designer.

Material: 16 gauge

Finish: G90 galvanized


Design: Factored resistances are in accordance with CSA 086-14

Installation:


- Use all specified fasteners.
- Nails: 10d = 0.148" dia. x 3" long common wire, 10d x 1 1/2" = 0.148" dia. x 1 1/2" long.
- Drive 10d nails into the truss at the inside end of the slotted holes (inside end is towards the centre of the truss) and clinch on the back side. Do not seat these nails into the truss—allow room under the nail head for movement of the truss with respect to the wall.

Optional TC Installation:


- Bend one flange up 90°. Drive specified nails into the top and face of the top plates or install Titen® screws into the top and face of masonry wall. See optional load tables and installation details.




TC24
U.S. Patent 4,932,173




Typical TC24 Installation



TC26
(TC28 Similar)



Optional TC26 Installation for Grouted Concrete Block using a Wood Nailer (8", 10", 12" Wall Installation Similar)



Optional TC26 Installation for Grouted Concrete Block using Titen Screws

Model No.	Fasteners		Factored Resistance	
	Truss	Wall Plates	D.Fir-L	S-P-F
			Uplift ($K_c=1.18$)	Uplift ($K_c=1.15$)
TC24	(4) 10d	(4) 10d	605	430
TC26	(5) 10d	(6) 10d	1015	720
TC28	(5) 10d	(8) 10d	1015	720

Optional TC Installation Table

Model No.	Fasteners		Factored Resistance	
	Truss	Wall Plates	D.Fir-L	S-P-F
			Uplift ($K_c=1.18$)	Uplift ($K_c=1.15$)
TC26	(5) 10d	(8) 10d x 1 1/2"	810	660
	(5) 10d	(6) 10d	930	660

1. Factored resistances have been increased 15% for earthquake or wind loading; no further increase allowed; reduce where other loads govern.

2. Grout strength is 15 MPa minimum.

3. Optional TC28 installation with 10d nails requires minimum 3" top plate thickness.

4. TC26 fastened to grouted concrete block with (8) - 3/8" x 2 1/4" Titen screws has a factored uplift resistance of 275 lb.



(800) 999-5099
strongtie.com

H/TSP

SIMPSON
Strong-Tie

Seismic and Hurricane Ties (cont.)

These products are available with additional corrosion protection. For more information, see p. 24.

These products are approved for installation with the Strong-Drive® SD Connector screw. See pp. 32-34 for more information.

Model No.	Ga.	Fasteners			Factored Resistance (K _f = 1.15)					
					D.Fir-L			S-P-F		
		To Rafter/Truss	To Plates	To Studs	Uplift	Lateral		Uplift	Lateral	
						F ₁	F ₂		F ₁	F ₂
					lb.	lb.	lb.	lb.	lb.	lb.
					kN	kN	kN	kN	kN	kN
H1	18	(6) 8d x 1½"	(4) 8d	—	740	685	300	680	485	215
					3.29	3.06	1.33	3.02	2.10	0.96
SS H2A	18	(5) 8d x 1½"	(2) 8d x 1½"	(5) 8d x 1½"	830	220	75	590	155	55
					3.69	0.98	0.33	2.62	0.69	0.24
SS H2.5A	18	(5) 8d	(5) 8d	—	805	180	180	765	180	180
					3.58	0.71	0.71	3.36	0.71	0.71
H2.5T	18	(5) 8d	(5) 8d	—	835	175	210	740	160	210
					3.71	0.78	0.93	3.29	0.71	0.93
SS H3	18	(4) 8d	(4) 8d	—	740	180	265	615	125	180
					3.29	0.80	1.18	2.74	0.56	0.85
H6	16	—	(8) 8d	(8) 8d	1585	1085	—	1125	770	—
					7.05	4.83	—	5.00	3.43	—
H7Z	18	(4) 8d	(2) 8d	(8) 8d	1390	870	—	990	475	—
					6.18	2.88	—	4.40	2.11	—
SS H8 ^a	18	(5) 10d x 1½"	(5) 10d x 1½"	—	1120	—	—	1025	—	—
					4.98	—	—	4.60	—	—
SS H10A ^b	18	(9) 10d x 1½"	(9) 10d x 1½"	—	1735	795	410	1505	565	290
					7.72	3.54	1.82	6.69	2.51	1.29
H10AR	18	(9) 10d x 1½"	(9) 10d x 1½"	—	1485	690	430	1220	570	305
					6.61	3.07	1.91	5.43	2.54	1.36
H10A-2	18	(9) 10d x 1½"	(9) 10d x 1½"	—	1835	1275	430	1645	880	305
					8.16	5.67	1.91	7.32	3.91	1.36
H10S ^{c,d}	18	(8) 8d x 1½"	(8) 8d x 1½"	(8) 8d	1465	795	315	1040	565	225
					6.52	3.54	1.40	4.63	2.51	1.00
H11Z	18	(6) 16d x 2½"	(6) 16d x 2½"	—	1095	920	545	780	655	390
					4.87	4.09	2.42	3.47	2.91	1.73
H14	18	[1] (12) 8d x 1½"	(13) 8d	—	2390	855	320	1805	610	230
					10.63	3.80	1.42	8.03	2.71	1.02
		[2] (12) 8d x 1½"	(15) 8d	—	2390	865	320	1805	610	230
					10.63	3.80	1.42	8.03	2.71	1.02
TSP	18	(9) 10d x 1½"	(6) 10d x 1½"	—	1295	440	—	920	310	—
					5.76	1.96	—	4.09	1.38	—
		(9) 10d x 1½"	(6) 10d	—	1560	440	—	1105	310	—
					6.94	1.96	—	4.92	1.38	—

- Factored resistances have been increased 15% for short term loading; no further increase is allowed.
- Factored resistances are for one anchor. A minimum rafter thickness of 2½" must be used when framing anchors are installed on the same side of the plate (exception: H2.5A).
- H8 factored uplift resistances for stud-to-bottom plate installations are 595 lb. (2.65 kN) for D.Fir-L and 390 lb. (1.74 kN) for S-P-F.
- When cross-grain bending or cross-grain tension cannot be avoided, mechanical reinforcement to resist such forces should be considered.
- Hurricane ties are shown installed on the outside of the wall for clarity. Installation on the inside of the wall is acceptable. For a continuous load path, connections at the top and bottom of the wall must be on the same side of the wall (see technical bulletin T-HTIECONPATH).
- Factored resistances in the F₁ direction are not intended to replace diaphragm boundary members or prevent cross grain bending of the truss or rafter members. Additional shear transfer elements shall be considered where there may be effects of cross grain bending or tension.

- H10S can have the stud offset a maximum of 1" from the rafter (centre to centre) for a reduced uplift of 1435 lb. (6.38 kN) D.Fir-L and 1015 lb. (4.51 kN) S-P-F.
- H10S nails to plates are optional for uplift but required for lateral loads.
- H10A may be field-bent up to a slope of 8/12. Multiply the tabulated uplift value x 0.75. Full tabulated lateral resistances apply.
- The factored resistances of stainless-steel connectors match carbon-steel connectors when installed with Simpson Strong-Tie® stainless-steel, SCNR ring-shank nails. For more information, refer to engineering letter L-F-SSNAILS at strongtie.com.
- D.Fir-L/S-P-F factored uplift resistances for the H2.5A fastened to a 2x4 truss bottom chord and double top plates using (5) 8d x 1½" nails into the top plates and (3) 8d x 1½" nails into the lowest three flange holes into the truss bottom chord is 495 lb. (2.20 kN).
- Nails: 16d x 2½" = 0.162" dia. x 2½" long, 10d = 0.148" dia. x 3" long, 10d x 1½" = 0.148" dia. x 1½" long, 8d = 0.131" dia. x 2½" long, 8d x 1½" = 0.131" dia. x 1½" long. See pp. 27-28 for other nail sizes and information.



BEARING ANCHORAGE BY TOE-NAILS FOR LATERAL CAPACITY

B97791H1

NAIL TYPE	LENGTH (IN)	DIAMETER (IN)	NAIL LATERAL CAPACITY (LB)	
			S-P-F	D. FIR
COMMON WIRE	3.00	0.144	132	147
	3.25	0.144	132	147
	3.50	0.160	159	177
COMMON SPIRAL	3.00	0.122	97	108
	3.25	0.122	97	108
	3.50	0.152	145	162

NOTES:

1. Rafter and ceiling members may be anchored to top and bottom chords of girder truss by toe-nailing rafter and ceiling members to girder chords provided the reaction does not exceed the lateral capacities in the table. Hangers (specified by others) are required for reactions higher than the maximum toe-nail capacity. Reactions are based on factored loads.
2. Toe nail capacities shown in the table are for one toe-nail. For additional toe-nails multiply values in table by the number of toe-nails used. Toe-nail capacities take into account toe-nailing factor J_A in CSA O86-14, section 12.9.4.1.
3. For 9-3/4 gauge 3.25" common wire gun nails (diameter = 0.120") use 3" common spiral nail values.
4. Maximum number of toe-nails allowed depends on the lumber size & species to be toe-nailed to supporting member and nail diameter, as shown in tables below.
5. Nail values in table are based on the following relative lumber densities: $G = 0.42$ (SPF), $G = 0.49$ (D. Fir).
6. Toe-nails shall be driven at approximately 1/3 the nail length from the edge of the joist/truss chord and driven at an angle of 30° to the grain of the member (See next page for nailing on bearing plate).
7. For loads due to wind the nail lateral capacity in this table may be multiplied by 1.15 (K_D factor).
8. Lumber must be dry (< 19% moisture content) at the time of nail installation.
9. Nail values in this table comply with CSA O86-14, section 12.9.4.
10. This design is not valid after March 31, 2021.




TOE-NAIL INSTALLATION

Nail type	Common wire	Common spiral	Common wire	Common spiral
Nail dia. (in)	0.160	0.152	0.144	0.122
	(3.5" nail)		(3" and 3.25" nail)	
LUMBER SIZE	MAXIMUM NUMBER OF TOE-NAILS			
2X4 SPF	2	2	3	3
2X4 D. Fir	2	2	2	2
2X6 SPF	4	4	4	5
2X6 D. Fir	3	3	3	4

MiTek® MiTek Canada Inc
100 Industrial Rd.
Bradford, Ontario L3Z 3G7

December 2, 2019.

PEO
Certificate No. 10889486



BEARING ANCHORAGE BY TOE-NAILS FOR WIND LOADING

B97791H2



NAIL TYPE	LENGTH (IN)	DIAMETER (IN)	NAIL WITHDRAWAL CAPACITY (LB)	
			S-P-F	D. FIR
COMMON WIRE	3.00	0.144	30	42
	3.25	0.144	32	45
	3.50	0.160	38	52
COMMON SPIRAL	3.00	0.122	26	36
	3.25	0.122	28	40
	3.50	0.152	36	50

Note: If using truss with D. Fir lumber and S-P-F bearing plate, use values in table for S-P-F.



NOTES:

1. Truss chord, rafter, or ceiling members may be anchored to bearing plate by toe-nails, provided that the actual factored uplift force due to wind or earthquake load does not exceed the withdrawal capacities in the table. Hangers (specified by others) are required for uplift forces that are higher than the maximum toe-nail withdrawal capacity.
2. Toe nail capacities shown in the table are for one toe-nail. For additional toe-nails multiply values in table by the number of toe-nails used. Toe-nail capacities take into account toe-nailing factor J_A in CSA O86-14, section 12.9.5.2.
3. For 9-3/4 gauge 3.25" common wire gun nails (diameter = 0.120") use 3" common spiral nail values.
4. Maximum number of toe-nails allowed depends on the lumber size & species to be toe-nailed to supporting member and nail diameter, as shown in table above.
5. Nail values in table are based on the following relative lumber densities: $G = 0.42$ (SPF), $G = 0.49$ (D. Fir).
6. Toe-nails shall be driven at approximately 1/3 the nail length from the edge of the joist/truss chord and driven at an angle of 30° to the grain of the member (See drawing on detail B37579H1).
7. Lumber must be dry (< 19% moisture content) at the time of nail installation.
8. Nail values in this table comply with CSA O86-14, section 12.9.5
9. This design is not valid after March 31, 2021.

Toe-nailing on 2x6 Bearing Plate



Toe-nailing on 2x4 Bearing Plate



MiTek

MiTek Canada Inc
100 Industrial Rd.
Bradford, Ontario L3Z 3G7



PEO
Certificate No. 10889485



December 2, 2019

Symbols

PLATE LOCATION AND ORIENTATION



This symbol indicates the required direction of slots in connector plates.

*Plate location details available in MiTek software or upon request.

PLATE SIZE

4 x 4

The first dimension is the plate width measured perpendicular to slots. Second dimension is the length parallel to slots.

LATERAL BRACING LOCATION



Indicated by symbol shown and/or by text in the bracing section of the output. Use T, I or Eliminator bracing if indicated.

BEARING




Indicates location where bearings (supports) occur. Icons vary but reaction section indicates joint number where bearings occur.

Industry Standards:

TPIC: Truss Design Procedures and Specifications for Light Metal Plate Connected Wood Trusses
DSB-89: Design Standard for Bracing
BCSI: Building Component Safety Information, Guide to Good Practice for Handling, Installing & Bracing of Metal Plate Connected Wood Trusses.

Numbering System



JOINTS ARE GENERALLY NUMBERED/LETTERED CLOCKWISE AROUND THE TRUSS STARTING AT THE JOINT FARTHEST TO THE LEFT.

CHORDS AND WEBS ARE IDENTIFIED BY END JOINT NUMBERS/LETTERS.

PRODUCT CODE APPROVALS

CCMC Reports:

11996-L, 10319-L, 13270-L, 12691-R

© 2007 MiTek® All Rights Reserved

MiTek
POWER TO PERFORM.™

MiTek Engineering Reference Sheet: MM-7473C rev. 10-08



General Safety Notes

Failure to Follow Could Cause Property Damage or Personal Injury


1. Additional stability bracing for truss system, e.g. diagonal or X-bracing, is always required. See BCSI.
2. Truss bracing must be designed by an engineer. For wide truss spacing, individual lateral braces themselves may require bracing, or alternative T, I, or Eliminator bracing should be considered.
3. Never exceed the design loading shown and never stock materials on inadequately braced trusses.
4. Provide copies of this truss design to the building designer, erection supervisor, property owner and all other interested parties.
5. Cut members to bear tightly against each other.
6. Place plates on each face of truss at each joint and embed fully. Knots and wane at joint locations are regulated by TPIC.
7. Design assumes trusses will be suitably protected from the environment in accord with TPIC.
8. Unless otherwise noted, moisture content of lumber shall not exceed 19% at time of fabrication.
9. Unless expressly noted, this design is not applicable for use with fire retardant, preservative treated, or green lumber.
10. Camber is a non-structural consideration and is the responsibility of truss fabricator. General practice is to camber for dead load deflection.
11. Plate type, size, orientation and location dimensions indicated are minimum plating requirements.
12. Lumber used shall be of the species and size, and in all respects, equal to or better than that specified.
13. Top chords must be sheathed or purlins provided at spacing indicated on design.
14. Bottom chords require lateral bracing at 10 ft. spacing, or less, if no ceiling is installed, unless otherwise noted.
15. Connections not shown are the responsibility of others.
16. Do not cut or alter truss member or plate without prior approval of an engineer.
17. Install and load vertically unless indicated otherwise.
18. Use of green or treated lumber may pose unacceptable environmental, health or performance risks. Consult with project engineer before use.
19. Review all portions of this design (front, back, words and pictures) before use. Reviewing pictures alone is not sufficient.
20. Design assumes manufacture in accordance with TPIC Quality Criteria.

Overview:

Where piggybacks are connected overtop of base trusses, 2x4 purlins must be first added to the flat portion of the base truss at a spacing no more than 24" o/c. These purlins not only provide support for the piggyback trusses above, but are required to laterally support the top chord of the base truss which will not have the sheathing directly connected to the flat portion of the base truss. This ensures the top chord, most often in compression, will not buckle laterally.

Further, the purlins in the plane of the flat portion require diagonal bracing to prevent lateral displacement of the purlins themselves where under certain conditions, the trusses may in fact all buckle in the same direction. If this additional bracing is not added in the plane of the purlins.

Detail:



NOTE: THE SLOPED PORTION OF THE TOP CHORD OF THE BASE TRUSS AND PIGGYBACK TRUSS IN THIS SKETCH IS ASSUMED TO BE SHEATHED IN ACCORDANCE WITH THE OBC.

SKETCH FROM BCSI-CANADA 2013

Disclaimer:

OWTFA Tech Notes are intended to provide guidance to the design community both within the membership as well as to third party designers who might benefit from the information. The details have been developed by the OWTFA technical committee and although there may be professional engineers involved in development, the information contained in the tech-note are not intended to be used without having a professional engineer review the information for a specific application. The OWTFA takes no responsibility with respect to the information provided but has developed this tech-note to offer guidance where it is not currently readily available.



Alves Engineering Services Inc.

5208 Easton road
Burlington, Ontario L7L 6N6
(289) 259 5455

RESPONSABILITIES

- 1-Alves Engineering Services Inc. is responsible for the design of trusses as individual components
- 2-It is the responsibility of others to ascertain that the design loads utilized on this drawing meet or exceed the actual dead load imposed by the structure and the live load imposed by the local building code or the authorities having jurisdictions.
- 3- All dimensions are to be verified by owner, contractor, architect or other authority before manufacture.
- 4- Alves Engineering Services Inc. bears no responsibility for the erection of the trusses. Persons erecting trusses are cautioned to seek professional advice regarding temporary and permanent bracing system. Bracing shown on Alves Engineering Services Inc. drawings is specified for the truss as a single component and forms an integral part of the truss design, but is not meant to represent the only required bracing for that truss when trusses are installed in a series of trusses forming a roof truss system.
- 5- It is the manufactures responsibility to ensure that the trusses are manufactured in conformance with Alves Engineering Services Inc. specifications outlined below.

SPECIFICATIONS

- 1-Truss components sealed by Alves Engineering Services Inc. conform to the relevant sections of the current Building Code of Ontario and Canada (part 4 or part 9) or the current Canadian code for Farm Buildings in accordance with the application specified on the sealed truss component drawing. All truss component design procedures must conform to the current design standard issued by the truss plate institute of Canada (TPIC). All lumber and nailing stresses to conform to the current CSA wood design standard identified on the current Building Code and TPIC.
- 2- Lumber is to be the sizes and grade specified on the truss drawing.
- 3- Moist content of lumber is not to exceed 19% in service unless otherwise specified.
- 4- Plates shall be applied to both faces of the each truss joint and shall be positioned as shown on the truss drawings
- 5- Lumber used on manufacture of trusses is not to be treated with chemicals unless otherwise specified on the truss drawings.
- 6- The top chord is assumed to be continuously laterally braced by the roof sheathing or purlins at intervals specified on the truss drawing but not exceeding 24" c/c for (part 9) and not exceeding 48" for (part 4 or farm design)
- 7- When rigid ceiling is not attached directly to the bottom chord, lateral bracing is required and it should not exceed more than 3m or 10' intervals.
- 8-Refer to Mitek sheet M117473C REV.10-08 attached for information on symbols, numbering system and General Safety notes.

T-1900213

Feb 09, 2018