


6/12 roof pitch unless noted



ASPHALT SHINGLES
FINISHED OVERHANG: 12"
2x6 EXTERIOR WALLS
2x6 FASCIA BOARD
HEEL: R.T.M.C.


All conventional framing to conform with Part 9 of O.B.C. 2012 (2019 amendment). Roof rafters that cross over or meet trusses to be min. 2x4 SPF #2 @ 24" o/c with a vertical post to the truss at each cross point. Vertical posts longer than 6' to have lateral bracing so that the distance between the post end points and lateral bracing does not exceed 6'.

DESIGN CONFORMS WITH OBC 2012 (2019 amendment) OCCUPANCY: RESIDENTIAL | PART: 9
Ss = 31.35 psf | Sr = 8.4 psf

DESIGN LOADS:
TCSL = 25.6 psf
TCDL = 6.0 psf
BCLL = 0.0 psf
BCDL = 7.4 psf

HARDWARE:
LUS24 - (O)
LJS26DS - (V)
HGUS26-2 - (XX)
LUS26-2-(VV)
CITY OF HAMILTON Building Division
Permit No. 21-107135
THESE STAMPED DRAWINGS SHALL BE AVAILABLE ON SITE

BEAMS:
B40= B41 = B42=
2 - 2x10 SPF #2
THESE DRAWINGS AND/OR SPECIFICATIONS HAVE BEEN REVIEWED BY
MAR 09 2021
DATE

 DENOTES:
CONVENTIONAL
FRAMING

M13125



Job Track: 51225
Plan Log: 202401
Layout ID: 408152

Builder / Location: GREEN PARK HOMES / WATERDOWN
Project: RUSSELL GARDENS PH.3
Date: 2020-04-27 Sales: Mario DiCano Designer: JG

Model / Elevation: MOUNTAINASH 4/3- std. or opt. LOT 274
Milek ver 8.3.1.215

THESE DRAWINGS CONSTITUTE THE PROPERTY OF TAMARACK ROOF TRUSSES INC., SHALL NOT BE REPRODUCED, PUBLISHED, OR REDISTRIBUTED IN ANY MANNER OR UTILIZED FOR ANY PURPOSE OTHER THAN THE MANUFACTURE OF TRUSSES BY TAMARACK ROOF TRUSSES INC AND WILL BE RETRACTED BY TAMARACK ROOF TRUSSES INC IF UTILIZED FOR ANY OTHER PURPOSE.

DELIVERY SHIPLIST



Lumber Yard: TAMARACK LUMBER
 Builder: GREEN PARK HOMES
 Project: RUSSELL GARDENS PH.3
 Location: WATERDOWN
 Model: MOUNTAINASH 4
 Lot #: 274
 Elevation: 3- std. or opt.

Job Track: 51225
 PlanLog: 202401
 Layout ID: 408152
 Ref #
 Page: 1 of 3
 Date: 04-27-2020
 Designer:
 Sales Rep: Mario DiCano

Roof Trusses

PROFILE	QTY PLY	MARK TYPE	PITCH	SPAN	HEIGHT	LUMBER	OVERHANG LEFT RIGHT	HEEL HEIGHT LEFT RIGHT	LBS. BFT.	BUNDLE # STACK #	LOAD BY REMARKS
	1 2-ply	T40 Hip Girder	6/12	35-02-00	4-01-04	2 x 4 2 x 6	1-03-08 1-03-08	1-02-00 1-02-00	340.74 212.00		
	1 2-ply	T40Z Hip Girder	6/12	35-02-00	4-01-04	2 x 4 2 x 6	1-03-08 1-03-08	1-02-00 1-02-00	340.74 212.00		
	2	T41 Hip	6/12	35-02-00	5-01-04	2 x 4	1-03-08 1-03-08	1-02-00 1-02-00	277.99 174.00		
	2	T42 Hip	6/12	35-02-00	6-01-04	2 x 4	1-03-08 1-03-08	1-02-00 1-02-00	277.12 174.67		
	2	T43 Hip	6/12	35-02-00	7-01-04	2 x 4	1-03-08 1-03-08	1-02-00 1-02-00	289.07 179.67		
	2	T44 Hip	6/12	35-02-00	8-01-04	2 x 4	1-03-08 1-03-08	1-02-00 1-02-00	280.73 183.33		
	2	T45 Hip	6/12	35-02-00	9-01-04	2 x 4	1-03-08 1-03-08	1-02-00 1-02-00	301.67 191.33		
	6	T46 Common	6/12	35-02-00	9-11-08	2 x 4	1-03-08 1-03-08	1-02-00 1-02-00	910.08 558.00		
	1 2-ply	T47 Hip Girder	6/12	16-07-00	4-01-04	2 x 4 2 x 6	1-03-08	1-02-00 2-02-00	158.02 100.67		
	1	T48 Hip	6/12	16-07-00	5-01-04	2 x 4	1-03-08	1-02-00 2-02-00	68.15 43.33		
	1	T49 Common	6/12	16-07-00	5-09-12	2 x 4	1-03-08	1-02-00 2-02-00	67.14 42.33		
	1	T50 Hip Girder	6/12	10-11-00	2-07-04	2 x 4	1-03-08 1-03-08	1-02-00 1-02-00	42.73 28.33		
	1	T51 Hip	6/12	10-11-00	4-07-04	2 x 4	1-03-08 1-03-08	2-02-00 2-02-00	51.54 34.50		
	1	T52 Flat	0/12	9-04-00	2-10-00	2 x 4		2-10-00 2-10-00	36.11 23.83		

DELIVERY SHIPLIST



Lumber Yard: TAMARACK LUMBER
 Builder: GREEN PARK HOMES
 Project: RUSSELL GARDENS PH.3
 Location: WATERDOWN
 Model: MOUNTAINASH 4
 Lot #: 274
 Elevation: 3- std. or opt.

Job Track: 51225
 PlanLog: 202401
 Layout ID: 408152
 Ref #
 Page: 2 of 3
 Date: 04-27-2020
 Designer:
 Sales Rep: Mario DiCano

Roof Trusses

PROFILE	QTY PLY	MARK TYPE	PITCH	SPAN	HEIGHT	LUMBER	OVERHANG LEFT RIGHT	HEEL HEIGHT LEFT RIGHT	LBS. BFT.	BUNDLE # STACK #	LOAD BY REMARKS
	1	G52 GABLE	0/12	9-04-00	2-10-00	2 x 4		2-10-00 2-10-00	33.75 23.33		
	1	T53 Flat Girder	0/12	9-04-00	3-10-00	2 x 6		3-10-00 3-10-00	50.9 31.50		
	1 2-ply	T54 Jack-Closed Girder	6/12	6-10-08	4-01-04	2 x 4 2 x 6		8-00 4-01-04	59.81 37.33		
	15	J1 Jack-Open	6/12	5-10-08	4-01-04	2 x 4	1-03-08	1-02-00 4-01-04	251.92 160.00		
	4	J40 Jack-Open	6/12	3-09-08	4-01-04	2 x 4		2-02-08 4-01-04	52.34 35.33		
	4	J41 Jack-Open	6/12	2-10-08	2-07-04	2 x 4	1-03-08	1-02-00 2-07-04	38.2 24.00		
	4	C40 Jack-Open	6/12	3-09-07	3-00-12	2 x 4	1-03-08 2-01-01	1-02-00 3-00-12	56.53 34.67		
	4	C41 Jack-Open	6/12	1-09-07	2-00-12	2 x 4	1-03-08 4-01-01	1-02-00 2-00-12	46.33 29.33		
	4	C42 Jack-Open	6/12	1-10-08	3-00-12	2 x 4	1-03-08 1-10-15	1-02-00 2-01-04	38.28 24.00		
	4	C43 Jack-Open	6/12	1-09-07	2-00-12	2 x 4	1-03-08 1-01	1-02-00 2-00-12	28.08 18.87		
	2	C44 Jack-Open	6/12	1-10-15	2-01-08	2 x 4	1-03-08 11-09	1-02-00 2-01-08	16.64 10.67		
	2	C45 Jack-Open	6/12	1-10-15	2-01-08	2 x 4	1-03-08 1-01	1-02-00 2-01-08	14.85 9.33		

TOTAL # TRUSS= 74

TOTAL BFT OF ALL TRUSSES= 2596.15

BFT.

TOTAL WEIGHT OF ALL TRSSES 4137.05 LBS

HARDWARE

QTY	TYPE	MODEL	LENGTH
1	Hardware	HGUS26-2	
4	Hardware	LJS26DS	

DELIVERY SHIPLIST



Lumber Yard: TAMARACK LUMBER
Builder: GREEN PARK HOMES
Project: RUSSELL GARDENS PH.3
Location: WATERDOWN
Model: MOUNTAINASH 4
Lot #: 274
Elevation: 3- std. or opt.

Job Track: 51225
PlanLog: 202401
Layout ID: 408152
Ref #
Page: 3 of 3
Date: 04-27-2020
Designer:
Sales Rep: Mario DiCano

HARDWARE

QTY	TYPE	MODEL	LENGTH
5	Hardware	LUS24	
3	Hardware	LUS28-2	



TOTAL NUMBER OF
ITEMS=

13

JOB NAME	TRUSS NAME	QUANTITY	PLY	JOB DESC.	GREEN PARK HOMES	DRWG NO.
408150	T1	1	2	TRUSS DESC.		

Tamarack Roof Truss, Burlington

Version 8.310 S Oct 29 2019 MTek Industries, Inc. Sat Apr 25 11:02:47 2020 Page 1
ID:7vF7aG0E03cRUj8X1jSkziWYK-VShX5DRAXNEn15LAM_IsZu8zCRhpfkAONpVGMzNCnc



LUMBER			
N. L. G. A. RULES	SIZE	LUMBER	DESCR.
CHORDS			
R - A	2x4	DRY	No.2
A - D	2x6	DRY	No.2
D - F	2x6	DRY	No.2
F - I	2x6	DRY	No.2
J - L	2x4	DRY	No.2
R - P	2x6	DRY	No.2
P - L	2x6	DRY	No.2
L - J	2x6	DRY	No.2
ALL WEBS	2x3	DRY	No.2
DRY: SEASONED LUMBER.			SPF

DESIGN CONSISTS OF 2 TRUSSES BUILT SEPARATELY THEN FASTENED TOGETHER AS FOLLOWS:

CHORDS #ROWS	SURFACE SPACING (IN)	LOAD(PLF)
TOP CHORDS : (0.122"x3") SPIRAL NAILS		
R - A	12	TOP
I - J	12	TOP
A - D	12	SIDE(183.1)
D - F	12	SIDE(0.0)
F - I	12	SIDE(0.0)
BOTTOM CHORDS : (0.122"x3") SPIRAL NAILS		
R - P	12	SIDE(183.1)
P - L	12	SIDE(183.1)
L - J	12	SIDE(0.0)
WEBS : (0.122"x3") SPIRAL NAILS		
2x3	6	

NAILS TO BE DRIVEN FROM ONE SIDE ONLY.

GIRDER NAILING ASSUMES NAILED HANGERS ARE FASTENED WITH MIN. 3-0 INCH NAILS.

TOP - COMPONENTS ARE LOADED FROM THE TOP AND MUST BE PLACED ON TOP EDGE OF ALL PUES FOR THE LOAD TO BE TRANSFERRED TO EACH PLY.

SIDE - PLF SHOWN IS THE EQUIVALENT UDL APPLIED TO ONE SIDE THAT THE CORRESPONDING NAILING PATTERN SHALL BE CAPABLE OF TRANSFERING. REMAINING PLF MUST BE APPLIED ON THE OPPOSITE SIDE OR ON THE TOP.

DIMENSIONS, SUPPORTS AND LOADINGS SPECIFIED BY FABRICATOR TO BE VERIFIED BY BUILDING DESIGNER

BEARINGS		FACTORED		GROSS REACTION		MAXIMUM FACTORED		INPUT		REQD	
JT	VERT	HORZ	DOWN	HORZ	UPLIFT	BRG	IN-SX	BRG	IN-SX		
R	3052	0	3052	0	0	3-8		3-8			
J	3118	0	3118	0	0	3-8		3-8			

UNFACTORED REACTIONS							
	1ST LCASE	MAX./MIN. COMPONENT REACTIONS					
JT	COMBINED	SNOW	LIVE	PERM.LIVE	WIND	DEAD	SOIL
R	2161	1401 / 0	0 / 0	0 / 0	0 / 0	781 / 0	0 / 0
J	2209	1430 / 0	0 / 0	0 / 0	0 / 0	778 / 0	0 / 0

BEARING MATERIAL TO BE SPF NO.2 OR BETTER AT JOINT(S) R, J

BRACING
TOP CHORD TO BE SHEATHED OR MAX. PURLIN SPACING = 4.25 FT.
MAX. UNBRACED BOTTOM CHORD LENGTH = 10.00 FT OR RIGID CEILING DIRECTLY APPLIED.

ALL PITCH BREAKS AND PERIMETER CORNER JOINTS MUST BE LATERALLY RESTRAINED.

LOADING

TOTAL LOAD CASES: (4)

CHORDS				WEBS			
MEMB.	MAX. FACTORED FORCE (LBS)	FACTORED VERT. LOAD (PLF)	MAX. CSI (LC)	MAX. UNBRAC	MEMB.	MAX. FACTORED FORCE (LBS)	MAX. CSI (LC)
FR-TO		FROM TO		LENGTH	FR-TO		
R-A	-2874 / 0	0.0	0.0 0.34 (1)	6.68	K-I	0 / 5083	0.63 (1)
A-S	-4326 / 0	-91.8	-91.8 0.20 (1)	5.32	A-Q	0 / 5078	0.63 (1)
S-T	-4326 / 0	-91.8	-91.8 0.20 (1)	5.32	K-H	-2485 / 0	0.30 (1)
T-B	-4326 / 0	-91.8	-91.8 0.20 (1)	5.32	Q-B	-2483 / 0	0.29 (1)
B-U	-6898 / 0	-91.8	-91.8 0.25 (1)	4.43	M-H	0 / 2804	0.35 (1)
U-V	-6898 / 0	-91.8	-91.8 0.25 (1)	4.43	B-O	0 / 2808	0.35 (1)
V-C	-6898 / 0	-91.8	-91.8 0.25 (1)	4.43	M-G	-1325 / 0	0.16 (1)
C-D	-7505 / 0	-91.8	-91.8 0.23 (1)	4.25	O-C	-1326 / 0	0.16 (1)
D-W	-7505 / 0	-91.8	-91.8 0.23 (1)	4.25	N-G	0 / 958	0.12 (1)
W-E	-7505 / 0	-91.8	-91.8 0.23 (1)	4.25	C-N	0 / 958	0.12 (1)
E-X	-7505 / 0	-91.8	-91.8 0.23 (1)	4.25	N-E	-851 / 0	0.10 (1)
X-Y	-7505 / 0	-91.8	-91.8 0.23 (1)	4.25			
Y-F	-7505 / 0	-91.8	-91.8 0.23 (1)	4.25			
F-Z	-7505 / 0	-91.8	-91.8 0.23 (1)	4.25			
Z-G	-7505 / 0	-91.8	-91.8 0.23 (1)	4.25			
G-AA	-6898 / 0	-91.8	-91.8 0.26 (1)	4.42			
AA-AB	-6898 / 0	-91.8	-91.8 0.26 (1)	4.42			
AB-AC	-6898 / 0	-91.8	-91.8 0.26 (1)	4.42			
AC-H	-6898 / 0	-91.8	-91.8 0.26 (1)	4.42			
H-AD	-4330 / 0	-91.8	-91.8 0.21 (1)	5.30			
AD-AE	-4330 / 0	-91.8	-91.8 0.21 (1)	5.30			
AE-AF	-4330 / 0	-91.8	-91.8 0.21 (1)	5.30			
AF-I	-4330 / 0	-91.8	-91.8 0.21 (1)	5.30			
I-J	-3028 / 0	0.0	0.0 0.35 (1)	6.64			

R-AG	0 / 0	-18.5	-18.5 0.08 (4)	10.00
AG-AH	0 / 0	-18.5	-18.5 0.08 (4)	10.00
AH-Q	0 / 0	-18.5	-18.5 0.08 (4)	10.00
Q-AI	0 / 4328	-18.5	-18.5 0.33 (1)	10.00
AI-P	0 / 4328	-18.5	-18.5 0.33 (1)	10.00
P-O	0 / 4326	-18.5	-18.5 0.33 (1)	10.00
O-AJ	0 / 6898	-18.5	-18.5 0.49 (1)	10.00
AJ-AK	0 / 6898	-18.5	-18.5 0.49 (1)	10.00
AK-N	0 / 6898	-18.5	-18.5 0.49 (1)	10.00
N-AL	0 / 6898	-18.5	-18.5 0.49 (1)	10.00
AL-AM	0 / 6898	-18.5	-18.5 0.49 (1)	10.00
AM-AN	0 / 6898	-18.5	-18.5 0.49 (1)	10.00
AN-M	0 / 6898	-18.5	-18.5 0.49 (1)	10.00
MAO	0 / 4330	-18.5	-18.5 0.33 (1)	10.00
AO-L	0 / 4330	-18.5	-18.5 0.33 (1)	10.00
L-AP	0 / 4330	-18.5	-18.5 0.33 (1)	10.00
AP-AQ	0 / 4330	-18.5	-18.5 0.33 (1)	10.00
AQ-K	0 / 4330	-18.5	-18.5 0.33 (1)	10.00

TOTAL WEIGHT = 2 X 176 = 353 lb

DESIGN CRITERIA

SPECIFIED LOADS:

TOP CH. LL	= 25.6 PSF
DL	= 6.0 PSF
BOT CH. LL	= 0.0 PSF
DL	= 7.4 PSF
TOTAL LOAD	= 38.0 PSF

SPACING = 24.0 IN./C/C

LOADING IN FLAT SECTION BASED ON A SLOPE OF 6.00/12

THIS TRUSS IS DESIGNED FOR RESIDENTIAL OR SMALL BUILDING REQUIREMENTS OF PART 9, NBC0 2010, NBC0 2015

THIS DESIGN COMPLIES WITH:

- PART 9 OF CBC0 2010, OSC 2012, ABC 2019
- PART 9 OF OSC 2012 (2019 AMENDMENT)
- CSA 086-09, CSA 086-14
- TPIC 2011, TPIC 2014

(55% OF 31.3 P.S.F. G.S.L. PLUS 8.4 P.S.F. RAIN LOAD) EQUALS 26.6 P.S.F. SPECIFIED ROOF LIVE LOAD

ALLOWABLE DEFL.(LL) = L/360 (1.16")
CALCULATED VERT. DEFL.(LL) = L/999 (0.20")
ALLOWABLE DEFL.(TL) = L/360 (1.16")
CALCULATED VERT. DEFL.(TL) = L/999 (0.38")

CSK: TC=0.35/1.00 (I-J:1), BC=0.49/1.00 (M-N:1), WB=0.63/1.00 (K:1), SS=0.17/1.00 (H:1)

DOL LUMBER=1.00 NAIL=1.00 LS BEND=1.00
COMP=1.00 SHEAR=1.00 TENS=1.00

COMPANION LIVE LOAD FACTOR = 1.00

TRUSS PLATE MANUFACTURER IS NOT RESPONSIBLE FOR QUALITY CONTROL IN THE TRUSS MANUFACTURING PLANT.


NAIL VALUES

PLATE GRIP (ORV)	SHEAR (PSI)	SECTION (PLI)
MAX MIN	MAX MIN	MAX MIN
MT20	618 354 1667 788 1887 1856	

PLATE PLACEMENT TOL. = 0.250 inches

PLATE ROTATION TOL. = 5.0 Deg.

JSI GRIP = 0.66 (K) (INPUT = 0.90)
JSI METAL = 0.42 (P) (INPUT = 1.00)



Structural component only
DWG# T-2007063 1/2

JOB NAME 408150	TRUSS NAME T1	QUANTITY 1	PLY 2	JOB DESC. GREEN PARK HOMES	DRWG NO.
Tamarack Roof Truss, Burlington				TRUSS DESC.	

Version 8.310 S Oct 29 2019 Mitek Industries, Inc. Sat Apr 25 11:02:47 2020 Page 2
 ID:37vF7aG0E03cRU6X1jSrtzWYK-VShX5DRAXNEn15LAM JsZu8zCRhp/kAQNpVGMvzNCnc

PLATES (table in inches)

JT	TYPE	PLATES	W	LEN	Y	X
A	TMWW-I	MT20	6.0	9.0		Edge
B	TMWW-I	MT20	5.0	6.0	2.50	2.75
C	TMWW-I	MT20	5.0	6.0		
D	TS-I	MT20	5.0	6.0		
E	TMW+W	MT20	3.0	6.0		
F	TS-I	MT20	5.0	6.0		
G	TMWW-I	MT20	5.0	6.0		
H	TMWW-I	MT20	5.0	6.0	2.50	2.75
I	TMWW-I	MT20	6.0	9.0		Edge
J	BMV1+p	MT20	3.0	6.0		
K	BMWW-I	MT20	6.0	9.0	3.00	4.25
L	BS-I	MT20	5.0	6.0		
M	BMWW-I	MT20	5.0	6.0	2.50	2.75
N	BMWW-I	MT20	5.0	6.0		
O	BMWW-I	MT20	5.0	6.0	2.50	2.75
P	BS-I	MT20	5.0	6.0		
Q	BMWW-I	MT20	6.0	9.0	3.00	4.25
R	BMV1+p	MT20	3.0	6.0		

Edge - INDICATES REFERENCE CORNER OF PLATE TOUCHES EDGE OF CHORD.

LOADING

TOTAL LOAD CASES: (4)


CHORDS		WEBS	
MEMB.	MAX. FACTORED FORCE (LBS)	FACTORED VERT. LOAD (PLF)	MAX. FACTORED MEMB. FORCE (LBS)
FR-TO		FROM TO	LENGTH FR-TO
K-AR	0/0	-18.5	-18.5 0.08 (4) 10.00
AR-AS	0/0	-18.5	-18.5 0.08 (4) 10.00
AS-AT	0/0	-18.5	-18.5 0.08 (4) 10.00
AT-J	0/0	-18.5	-18.5 0.08 (4) 10.00

FACTORED CONCENTRATED LOADS (LBS)

JT	LOC.	LC1	MAX-	MAX+	FACE	DIR.	TYPE	HEEL	CONN.
B	5-10-12	-110	-110	---	FRONT	VERT	TOTAL	---	C1
C	11-10-12	-110	-110	---	FRONT	VERT	TOTAL	---	C1
D	13-10-12	-110	-110	---	FRONT	VERT	TOTAL	---	C1
O	11-10-12	-26	-26	---	FRONT	VERT	TOTAL	---	C1
P	9-10-12	-26	-26	---	FRONT	VERT	TOTAL	---	C1
Q	5-10-12	-26	-26	---	FRONT	VERT	TOTAL	---	C1
S	1-10-12	-110	-110	---	FRONT	VERT	TOTAL	---	C1
T	3-10-12	-110	-110	---	FRONT	VERT	TOTAL	---	C1
U	7-10-12	-110	-110	---	FRONT	VERT	TOTAL	---	C1
V	9-10-12	-110	-110	---	FRONT	VERT	TOTAL	---	C1
W	15-10-12	-110	-110	---	FRONT	VERT	TOTAL	---	C1
X	17-10-12	-110	-110	---	FRONT	VERT	TOTAL	---	C1
Y	19-10-12	-110	-110	---	FRONT	VERT	TOTAL	---	C1
Z	21-10-12	-110	-110	---	FRONT	VERT	TOTAL	---	C1
AA	23-10-12	-110	-110	---	FRONT	VERT	TOTAL	---	C1
AB	25-10-12	-110	-110	---	FRONT	VERT	TOTAL	---	C1
AC	27-10-12	-110	-110	---	FRONT	VERT	TOTAL	---	C1
AD	29-10-12	-110	-110	---	FRONT	VERT	TOTAL	---	C1
AE	31-10-12	-110	-110	---	FRONT	VERT	TOTAL	---	C1
AF	33-10-12	-113	-113	---	FRONT	VERT	TOTAL	---	C1
AG	1-10-12	-28	-28	---	FRONT	VERT	TOTAL	---	C1
AH	3-10-12	-28	-28	---	FRONT	VERT	TOTAL	---	C1
AI	7-10-12	-28	-28	---	FRONT	VERT	TOTAL	---	C1
AJ	13-10-12	-28	-28	---	FRONT	VERT	TOTAL	---	C1
AK	15-10-12	-28	-28	---	FRONT	VERT	TOTAL	---	C1
AL	17-10-12	-28	-28	---	FRONT	VERT	TOTAL	---	C1
AM	19-10-12	-28	-28	---	FRONT	VERT	TOTAL	---	C1
AN	21-10-12	-28	-28	---	FRONT	VERT	TOTAL	---	C1
AO	23-10-12	-26	-26	---	FRONT	VERT	TOTAL	---	C1
AP	25-10-12	-26	-26	---	FRONT	VERT	TOTAL	---	C1
AQ	27-10-12	-26	-26	---	FRONT	VERT	TOTAL	---	C1
AR	29-10-12	-26	-26	---	FRONT	VERT	TOTAL	---	C1
AS	31-10-12	-26	-26	---	FRONT	VERT	TOTAL	---	C1
AT	33-10-12	-27	-27	---	FRONT	VERT	TOTAL	---	C1


CONNECTION REQUIREMENTS

- 1) C1: A SUITABLE HANGER MECHANICAL CONNECTION IS REQUIRED.



Structural component only
 DWG# T-2007063 7/2

JOB NAME 408150	TRUSS NAME T1Z	QUANTITY 1	PLY 2	JOB DESC. GREEN PARK HOMES	DRWG NO.
Tamarack Roof Truss, Burlington				TRUSS DESC.	
Version 8.310 S Oct 29 2019 Mitek Industries, Inc. Sat Apr 25 11:02:49 2020 Page 1					
ID:7V7?aG0E03cRUj6X1jSkzWYK-zFwIZSohMelfWnwhG566h7Ury0O8GacTEqyOzNcb					
Scale = 1:54.4					



LUMBER			
N. L. G. A. RULES			
CHORDS	SIZE	LUMBER	DESCR.
R - A	2x4	DRY	No.2
A - D	2x6	DRY	No.2
D - F	2x6	DRY	No.2
F - I	2x6	DRY	No.2
J - I	2x4	DRY	No.2
R - P	2x6	DRY	No.2
P - L	2x6	DRY	No.2
L - J	2x6	DRY	No.2
ALL WEBS	2x3	DRY	No.2
DRY: SEASONED LUMBER.			SPF

DESIGN CONSISTS OF 2 TRUSSES BUILT SEPARATELY THEN FASTENED TOGETHER AS FOLLOWS:

CHORDS #ROWS	SURFACE SPACING (IN)	LOAD (PLF)
TOP CHORDS: (0.122"x3") SPIRAL NAILS		
R - A	12	TOP
I - J	12	TOP
A - D	12	SIDE(0.0)
D - F	12	SIDE(183.1)
F - I	12	TOP
BOTTOM CHORDS: (0.122"x3") SPIRAL NAILS		
R - P	12	SIDE(0.0)
P - L	12	SIDE(183.1)
L - J	12	TOP
WEBS: (0.122"x3") SPIRAL NAILS		
2x3	8	

NAILS TO BE DRIVEN FROM ONE SIDE ONLY.

GIRDER NAILING ASSUMES NAILED HANGERS ARE FASTENED WITH MIN. 3-0 INCH NAILS.

TOP - COMPONENTS ARE LOADED FROM THE TOP AND MUST BE PLACED ON TOP EDGE OF ALL PLIES FOR THE LOAD TO BE TRANSFERRED TO EACH PLY.

SIDE - PLF SHOWN IS THE EQUIVALENT UDL APPLIED TO ONE SIDE THAT THE CORRESPONDING NAILING PATTERN SHALL BE CAPABLE OF TRANSFERRING. REMAINING PLF MUST BE APPLIED ON THE OPPOSITE SIDE OR ON THE TOP.

DIMENSIONS, SUPPORTS AND LOADINGS SPECIFIED BY FABRICATOR TO BE VERIFIED BY BUILDING DESIGNER

BEARINGS		FACTORED GROSS REACTION		MAXIMUM FACTORED GROSS REACTION		INPUT BRG		REQD BRG	
JT	VERT	HORZ	DOWN	HORZ	UPLIFT	IN-SX	IN-SX	IN-SX	IN-SX
R	4002	0	4002	0	0	3-8	3-8	3-8	3-8
J	3132	0	3132	0	0	3-8	3-8	3-8	3-8

UNFACTORED REACTIONS		1ST LCASE		MAX MIN COMPONENT REACTIONS	
JT	COMBINED	SNOW	LIVE	PERM.LIVE	WIND
R	2824	1886 / 0	0 / 0	0 / 0	938 / 0
J	2212	1470 / 0	0 / 0	0 / 0	742 / 0

BEARING MATERIAL TO BE SPF NO.2 OR BETTER AT JOINT(S) R, J

BRACING
TOP CHORD TO BE SHEATHED OR MAX. PURLIN SPACING = 3.84 FT.
MAX. UNBRACED BOTTOM CHORD LENGTH = 10.00 FT OR RIGID CEILING DIRECTLY APPLIED.

ALL PITCH BREAKS AND PERIMETER CORNER JOINTS MUST BE Laterally RESTRAINED.

LOADING
TOTAL LOAD CASES: (4)

CHORDS		MAX. FACTORED		FACTORED		WEBS		MAX. FACTORED	
MEMB.	FORCE (LBS)	VERT.	LC1	MAX	UNBRAC	MEMB.	FORCE (LBS)	MAX	CSI (LC)
FR-TO		FROM	TO	CS1 (LC)	LENGTH	FR-TO			
R-A	-3851 / 0	0.0	0.0	0.44 (1)	6.01	K-I	0 / 5428	0.67 (1)	
A-S	-5722 / 0	-91.8	-91.8	0.26 (1)	4.72	A-Q	0 / 6717	0.83 (1)	
S-T	-5722 / 0	-91.8	-91.8	0.26 (1)	4.72	K-H	-2763 / 0	0.33 (1)	
T-B	-5722 / 0	-91.8	-91.8	0.25 (1)	4.72	Q-B	-2710 / 0	0.32 (1)	
B-C	-8848 / 0	-91.8	-91.8	0.27 (1)	3.93	M-H	0 / 4038	0.50 (1)	
C-D	-10219 / 0	-91.8	-91.8	0.34 (1)	3.64	B-O	0 / 3700	0.46 (1)	
D-U	-10219 / 0	-91.8	-91.8	0.34 (1)	3.64	M-G	-1801 / 0	0.23 (1)	
U-E	-10219 / 0	-91.8	-91.8	0.34 (1)	3.64	O-C	-1400 / 0	0.17 (1)	
E-V	-10219 / 0	-91.8	-91.8	0.31 (1)	3.67	N-G	0 / 2591	0.32 (1)	
V-F	-10219 / 0	-91.8	-91.8	0.31 (1)	3.67	C-N	0 / 1628	0.20 (1)	
F-G	-10219 / 0	-91.8	-91.8	0.31 (1)	3.67	N-E	-710 / 0	0.08 (1)	
G-H	-8031 / 0	-91.8	-91.8	0.23 (1)	4.14				
H-I	-4822 / 0	-91.8	-91.8	0.15 (1)	5.25				
I-J	-3071 / 0	0.0	0.0	0.35 (1)	6.80				
R-W	0 / 0	-18.5	-18.5	0.15 (1)	10.00				
W-X	0 / 0	-18.5	-18.5	0.15 (1)	10.00				
X-Y	0 / 0	-18.5	-18.5	0.15 (1)	10.00				
Y-Q	0 / 0	-18.5	-18.5	0.15 (1)	10.00				
Q-P	0 / 5722	-18.5	-18.5	0.44 (1)	10.00				
P-O	0 / 5722	-18.5	-18.5	0.44 (1)	10.00				
O-Z	0 / 6846	-18.5	-18.5	0.81 (1)	10.00				
Z-AA	0 / 6846	-18.5	-18.5	0.81 (1)	10.00				
AA-N	0 / 6846	-18.5	-18.5	0.81 (1)	10.00				
N-AB	0 / 8031	-18.5	-18.5	0.74 (1)	10.00				
AB-AC	0 / 8031	-18.5	-18.5	0.74 (1)	10.00				
AC-M	0 / 8031	-18.5	-18.5	0.74 (1)	10.00				
M-L	0 / 4822	-18.5	-18.5	0.33 (1)	10.00				
L-K	0 / 4822	-18.5	-18.5	0.33 (1)	10.00				
K-J	0 / 0	-18.5	-18.5	0.04 (4)	10.00				

FACTORED CONCENTRATED LOADS (LBS)		LOC.		MAX.		FACE		DIR.		TYPE		HEEL		CONN.	
JT	LOC.	LC1	MAX.	FACE	DIR.	TYPE	HEEL	CONN.							
S	1-10-12	-110	-110	---	BACK	VERT	TOTAL	---	C1						
T	3-10-12	-110	-110	---	BACK	VERT	TOTAL	---	C1						
U	15-8-12	-110	-110	---	BACK	VERT	TOTAL	---	C1						
V	17-8-12	-110	-110	---	BACK	VERT	TOTAL	---	C1						
W	1-10-12	-26	-26	---	BACK	VERT	TOTAL	---	C1						
X	3-10-12	-26	-26	---	BACK	VERT	TOTAL	---	C1						
Y	5-1-8	-727	-727	---	BACK	VERT	TOTAL	---	C1						
Z	13-0-8	-727	-727	---	BACK	VERT	TOTAL	---	C1						
AA	15-8-12	-26	-26	---	BACK	VERT	TOTAL	---	C1						
AB	17-8-12	-26	-26	---	BACK	VERT	TOTAL	---	C1						

TOTAL WEIGHT = 2 X 176 = 353 lb

DESIGN CRITERIA

SPECIFIED LOADS:
TOP CH. LL = 25.6 PSF
DL = 6.0 PSF
BOY CH. LL = 0.0 PSF
DL = 7.4 PSF
TOTAL LOAD = 39.0 PSF

SPACING = 24.0 IN. C/C

LOADING IN FLAT SECTION BASED ON A SLOPE OF 6.00/12

THIS TRUSS IS DESIGNED FOR RESIDENTIAL OR SMALL BUILDING REQUIREMENTS OF PART 9, NBCO 2010, NBCO 2015

THIS DESIGN COMPLIES WITH:
- PART 9 OF CBCO 2018, CBCO 2012, ABC 2019
- PART 9 OF CBCO 2012 (2019 AMENDMENT)
- CSA 086-09, CSA 086-14
- TPIC 2011, TPIC 2014

55% OF 31.3 P.S.F. G.S.L. PLUS 8.4 P.S.F. RAIN LOAD) EQUALS 25.6 P.S.F. SPECIFIED ROOF LIVE LOAD

ALLOWABLE DEFL.(LL) = L/360 (1.16")
CALCULATED VERT. DEFL.(LL) = L/999 (0.28")
ALLOWABLE DEFL.(TL) = L/360 (1.16")
CALCULATED VERT. DEFL.(TL) = L/628 (0.50")

CSI: TC=0.44/1.00 (A-R:1), BC=0.81/1.00 (V-O:1), WB=0.83/1.00 (A-Q:1), SS=0.41/1.00 (M-N:1)

DOL LUMBER=1.00 NAIL=1.00 LS BEND=1.00
COMP=1.00 SHEAR=1.00 TENS=1.00

COMPANION LIVE LOAD FACTOR = 1.00

TRUSS PLATE MANUFACTURER IS NOT RESPONSIBLE FOR QUALITY CONTROL IN THE TRUSS MANUFACTURING PLANT.

NAIL VALUES
PLATE GRIP(DRY) SHEAR SECTION
(PSI) (PLI) (PLI)
MAX MIN MAX MIN MAX MIN
MT20 618 354 1687 769 1987 1658

PLATE PLACEMENT TOL = 0.250 inches

PLATE ROTATION TOL = 5.0 Deg.

JSI GRIP = 0.88 (M) (INPUT = 0.90)

JSI METAL = 0.50 (P) (INPUT = 1.00)



Structural component only
DWG# T-2007064 1/2

JOB NAME 408150	TRUSS NAME T1Z	QUANTITY 1	PLY 2	JOB DESC. GREEN PARK HOMES	TRUSS DESC.	DWG NO.
Tamarack Roof Truss, Burlington						

Version 8.310 S Oct 29 2019 Mitek Industries, Inc. Sat Apr 25 11:02:49 2020 Page 2
 ID: i7vF?aG0E03cRUI6X1iSkziWYK-SrpIvVTQ3 UVQPVZTPnKeJDIEFIF7bWq7 NRizNCna

PLATES (table is in inches)

JT	TYPE	PLATES	W	LEN	Y	X
A	TMVW-t	MT20	6.0	9.0		Edge
B	TMWW-t	MT20	5.0	8.0	2.50	2.75
C	TMWW-t	MT20	5.0	8.0		
D	TS-t	MT20	5.0	8.0		
E	TMW-w	MT20	3.0	6.0		
F	TS-t	MT20	5.0	8.0		
G	TMWW-t	MT20	5.0	8.0		
H	TMWW-t	MT20	5.0	6.0	2.50	2.75
I	TMVW-t	MT20	6.0	9.0		Edge
J	BMV1-p	MT20	3.0	6.0		
K	BMWW-t	MT20	6.0	9.0	3.00	4.25
L	BS-t	MT20	5.0	8.0		
M	BMWW-t	MT20	5.0	8.0	2.50	2.75
N	BMWW-t	MT20	5.0	8.0		
O	BMWW-t	MT20	5.0	8.0	2.50	2.75
P	BS-t	MT20	5.0	8.0		
Q	BMWW-t	MT20	8.0	9.0	3.00	4.25
R	BMV1-p	MT20	3.0	6.0		

Edge - INDICATES REFERENCE CORNER OF PLATE TOUCHES EDGE OF CHORD.

FACTORED CONCENTRATED LOADS (LBS)

JT	LOC.	LC1	MAX-	MAX+	FACE	DIR.	TYPE	HEEL	CONN.
AC	18-3-8	-1293	-1293		BACK	VERT	TOTAL		C1

CONNECTION REQUIREMENTS

- 1) C1: A SUITABLE HANGER/MECHANICAL CONNECTION IS REQUIRED.




Structural component only
 DWG# T-2007064 72

JOB NAME: 408150 TRUSS NAME: T3 QUANTITY: 2 PLY: 1 JOB DESC: GREEN PARK HOMES TRUSS DESC: DRWG NO. Tamarack Roof Truss, Burlington

Version 8.310 S Oct 29 2019 MITEX Industries, Inc. Sat Apr 25 11:02:51 2020 Page 1
ID: j7vF?aG0E03cRUj8X1jSkziWYK-OEw2wbUhbcdDWjxbqpkokJaK233bSy0iRTUVizNCnY

Scale = 1/4" = 1'-0"



LUMBER			
N. L. G. A. RULES	CHORDS	SIZE	LUMBER
R - A	2x4	DRY	No.2
A - C	2x4	DRY	No.2
C - G	2x4	DRY	No.2
G - I	2x4	DRY	No.2
J - L	2x4	DRY	No.2
R - O	2x4	DRY	No.2
O - M	2x4	DRY	No.2
M - J	2x4	DRY	No.2
ALL WEBS 2x3 DRY SEASONED LUMBER.			

PLATES (Table in inches)					
JT	TYPE	PLATES	W	LEN	Y X
A	TMVW-1	MT20	5.0	6.0	2.00 2.50
B	TMVW-1	MT20	5.0	6.0	
C	TS-1	MT20	3.0	6.0	
D	TMVW-1	MT20	4.0	4.0	
E	TMVW-1	MT20	2.0	4.0	
F	TMVW-1	MT20	4.0	4.0	
G	TS-1	MT20	3.0	6.0	
H	TMVW-1	MT20	5.0	6.0	
I	TMVW-1	MT20	5.0	6.0	2.00 2.50
J	BMV1-p	MT20	3.0	4.0	
K	BMVW-1	MT20	5.0	6.0	2.00 2.50
L	BMVW-1	MT20	5.0	6.0	
M	BS-1	MT20	3.0	6.0	
N	BMVW-1	MT20	4.0	6.0	
O	BS-1	MT20	3.0	6.0	
P	BMVW-1	MT20	5.0	6.0	
Q	BMVW-1	MT20	5.0	6.0	2.00 2.50
R	BMV1-p	MT20	3.0	4.0	

DIMENSIONS, SUPPORTS AND LOADINGS SPECIFIED BY FABRICATOR TO BE VERIFIED BY BUILDING DESIGNER

BEARINGS							
FACTORED				MAXIMUM FACTORED			
GROSS REACTION				GROSS REACTION			
JT	VERT	HORZ	DOWN	JT	VERT	HORZ	DOWN
R	1920	0	1920	0	0	0	0
J	1920	0	1920	0	0	0	0

UNFACTORED REACTIONS							
1ST CASE MAX. MIN. COMPONENT REACTIONS							
JT	COMBINED	SNOW	LIVE	PERM. LIVE	WIND	DEAD	SOIL
R	1358	891 / 0	0 / 0	0 / 0	0 / 0	487 / 0	0 / 0
J	1358	891 / 0	0 / 0	0 / 0	0 / 0	487 / 0	0 / 0

BEARING MATERIAL TO BE SPF NO.2 OR BETTER AT JOINT(S) R, J

BRACING
TOP CHORD TO BE SHEATHED OR MAX. PURLIN SPACING = 3.59 FT.
MAX. UNBRACED BOTTOM CHORD LENGTH = 10.00 FT OR RIGID CEILING DIRECTLY APPLIED.

ALL PITCH BREAKS AND PERIMETER CORNER JOINTS MUST BE LATERALLY RESTRAINED.

1 LATERAL BRACE(S) AT 1/2 LENGTH OF A-R, I-J.

END VERTICAL(S) MUST BE SHEATHED OR HAVE BRACES AS INDICATED IN THE MAX. UNBRACED LENGTH COLUMN OF THE TABLE BELOW

LOADING
TOTAL LOAD CASES: (4)

CHORDS				WEBS			
MAX. FACTORED				MAX. FACTORED			
MEMB.	FORCE (LBS)	VERT. LOAD (PLF)	MAX. CSI (LC)	MEMB.	FORCE (LBS)	MAX. CSI (LC)	
FR-TO		FROM TO		FR-TO			
A-B	-1875 / 0	0.0	0.0 0.33 (1)	4.90	K-I	0 / 2388	0.53 (1)
A-B	-1891 / 0	-91.8	-91.8 0.55 (1)	4.46	A-Q	0 / 2388	0.53 (1)
B-C	-2808 / 0	-91.8	-91.8 0.68 (1)	3.63	K-H	-1536 / 0	0.90 (1)
C-D	-2808 / 0	-91.8	-91.8 0.68 (1)	3.63	C-B	-1536 / 0	0.90 (1)
D-E	-2827 / 0	-91.8	-91.8 0.58 (1)	3.59	L-H	0 / 1304	0.29 (1)
E-F	-2827 / 0	-91.8	-91.8 0.58 (1)	3.59	B-P	0 / 1304	0.29 (1)
F-G	-2808 / 0	-91.8	-91.8 0.68 (1)	3.63	L-F	-828 / 0	0.48 (1)
G-H	-2808 / 0	-91.8	-91.8 0.68 (1)	3.63	P-D	-828 / 0	0.48 (1)
H-I	-1891 / 0	-91.8	-91.8 0.55 (1)	4.46	N-F	0 / 453	0.10 (1)
J-I	-1875 / 0	0.0	0.0 0.33 (1)	4.90	D-N	0 / 453	0.10 (1)
R-Q	0 / 0	-18.5	-18.5 0.15 (4)	10.00	N-E	-537 / 0	0.31 (1)
Q-P	0 / 1891	-18.5	-18.5 0.35 (1)	10.00			
P-O	0 / 2808	-18.5	-18.5 0.47 (1)	10.00			
O-N	0 / 2808	-18.5	-18.5 0.47 (1)	10.00			
N-M	0 / 2808	-18.5	-18.5 0.47 (1)	10.00			
M-L	0 / 2808	-18.5	-18.5 0.47 (1)	10.00			
L-K	0 / 1891	-18.5	-18.5 0.35 (1)	10.00			
K-J	0 / 0	-18.5	-18.5 0.15 (4)	10.00			

TOTAL WEIGHT = 2 X 153 = 305 lb

DESIGN CRITERIA			
SPECIFIED LOADS:			
TOP CH.	LL	=	25.6 PSF
	DL	=	6.0 PSF
BOT CH.	LL	=	0.0 PSF
	DL	=	7.4 PSF
TOTAL LOAD	=	39.0 PSF	
SPACING = 24.0 IN. C/C			

LOADING IN FLAT SECTION BASED ON A SLOPE OF 6.00/12

THIS TRUSS IS DESIGNED FOR RESIDENTIAL OR SMALL BUILDING REQUIREMENTS OF PART 9, NBC 2010, NBC 2015

THIS DESIGN COMPLIES WITH:
- PART 9 OF CBC 2018, CBC 2012, ABC 2010
- PART 9 OF CBC 2012 (2019 AMENDMENT)
- CSA 086-09, CSA 088-14
- TPIC 2011, TPIC 2014

(55% OF 31.3 P.S.F. G.S.L. PLUS 8.4 P.S.F. RAIN LOAD) EQUALS 25.6 P.S.F. SPECIFIED ROOF LIVE LOAD

ALLOWABLE DEFL. (LL) = L/380 (1.16")
CALCULATED VERT. DEFL. (LL) = L/999 (0.18")
ALLOWABLE DEFL. (TL) = L/380 (1.16")
CALCULATED VERT. DEFL. (TL) = L/999 (0.33")

CSI: TC=0.68/1.00 (F-H:1), BC=0.47/1.00 (N-P:1), WB=0.90/1.00 (H-K:1), SS=0.25/1.00 (A-B:1)

DOL LUMBER=1.00 NAIL=1.00 LS BEND=1.10 COMP=1.10 SHEAR=1.10 TENS=1.10

COMPANION LIVE LOAD FACTOR = 1.00

TRUSS PLATE MANUFACTURER IS NOT RESPONSIBLE FOR QUALITY CONTROL IN THE TRUSS MANUFACTURING PLANT.

NAIL VALUES			
PLATE GRIP (DRY)	SHEAR	SECTION	
(PSI)	(PLI)	(PLI)	
MAX MIN	MAX MIN	MAX MIN	
MT20	818	354	1887 788 1887 1858

PLATE PLACEMENT TOL. = 0.250 inches


PLATE ROTATION TOL. = 5.0 Deg.

JSI GRIP=0.88 (I) (INPUT = 0.90)
JSI METAL=0.83 (M) (INPUT = 1.00)



Structural component only
DWG# T-2007066

JOB NAME 408150	TRUSS NAME T4	QUANTITY 2	PLY 1	JOB DESC. GREEN PARK HOMES	DRWG NO.
Tamarack Roof Truss, Burlington				Version 8.310 S Oct 29 2019 MTek Industries, Inc. Sat Apr 25 11:02:52 2020 Page 1	
ID:7v7aG0E03cRUj6X1jSrkzIWKYK-sQUQ8wVJmV47IE88XL1GyrhNSQJK7q9W4C12AzNCnX					



LUMBER			
N. L. G. A. RULES	CHORDS	SIZE	LUMBER
P - A	2x4	DRY	No.2
A - C	2x4	DRY	No.2
C - F	2x4	DRY	No.2
F - H	2x4	DRY	No.2
I - H	2x4	DRY	No.2
P - N	2x4	DRY	No.2
N - K	2x4	DRY	No.2
K - I	2x4	DRY	No.2
ALL WEBS	2x3	DRY	No.2
EXCEPT	J - H	2x4	DRY
DRY: SEASONED LUMBER.			

PLATES (table is in inches)					
JT	TYPE	PLATES	W	LEN	Y X
A	TMVW-1	MT20	5.0	8.0	2.25 2.00
B	TMVW-1	MT20	4.0	8.0	
C	TS-1	MT20	3.0	6.0	
D	TMVW-1	MT20	4.0	4.0	
E	TMVW-1	MT20	2.0	4.0	
F	TS-1	MT20	3.0	6.0	
G	TMVW-1	MT20	4.0	8.0	
H	TMVW-1	MT20	5.0	6.0	2.50 2.50
I	BMV1+p	MT20	3.0	4.0	
J	BMVW-1	MT20	5.0	6.0	2.50 2.50
K	BS-1	MT20	3.0	6.0	
L	BMVW-1	MT20	4.0	9.0	
M	BMVW-1	MT20	4.0	6.0	
N	BS-1	MT20	3.0	6.0	
O	BMVW-1	MT20	5.0	6.0	2.00 2.50
P	BMV1+p	MT20	3.0	4.0	

DIMENSIONS, SUPPORTS AND LOADINGS SPECIFIED BY FABRICATOR TO BE VERIFIED BY BUILDING DESIGNER

BEARINGS		FACTORED	MAXIMUM FACTORED	INPUT	RECORD
JT	VERT	GROSS REACTION	GROSS REACTION	BRG	BRG
P	1920	0	1920	0	3-8
I	1920	0	1920	0	3-8

UNFACTORED REACTIONS

JT	1ST CASE	MAX/MIN. COMPONENT REACTIONS	MAX	MIN	COMPONENT REACTIONS
P	1358	891 / 0	0 / 0	0 / 0	0 / 0
I	1358	891 / 0	0 / 0	0 / 0	0 / 0

BEARING MATERIAL TO BE SPF NO.2 OR BETTER AT JOINT(S) P, I

BRACING

TOP CHORD TO BE SHEATHED OR MAX. PURLIN SPACING = 3.31 FT.
MAX. UNBRACED BOTTOM CHORD LENGTH = 10.00 FT. OR RIGID CEILING DIRECTLY APPLIED.

ALL PITCH BREAKS AND PERIMETER CORNER JOINTS MUST BE Laterally RESTRAINED.

1 LATERAL BRACE(S) AT 1/2 LENGTH OF A-P, H-I, B-O, D-L, G-J.

END VERTICAL(S) MUST BE SHEATHED OR HAVE BRACES AS INDICATED IN THE MAX. UNBRACED LENGTH COLUMN OF THE TABLE BELOW

LOADING

TOTAL LOAD CASES: (4)

CHORDS		WEBS	
MEMB.	MAX. FACTORED FORCE (LBS)	MEMB.	MAX. FACTORED FORCE (LBS)
FR-TO		FR-TO	
P-A	-1888 / 0	A-O	0 / 2315
A-B	-1882 / 0	O-B	-1468 / 0
B-C	-2416 / 0	C-B	0 / 1058
C-D	-2416 / 0	D-C	-917 / 0
D-E	-2415 / 0	E-D	-2 / 0
E-F	-2415 / 0	F-E	-616 / 0
F-G	-2415 / 0	G-F	0 / 1054
G-H	-1863 / 0	H-G	-1465 / 0
H-I	-1868 / 0	I-H	0 / 2316
P-O	0 / 0	O-P	0 / 2316
O-N	0 / 1882	N-O	0 / 1882
N-M	0 / 1662	M-N	0 / 1662
M-L	0 / 2418	L-M	0 / 2418
L-K	0 / 1883	K-L	0 / 1883
K-J	0 / 1883	J-K	0 / 1883
J-I	0 / 0	I-J	0 / 0

TOTAL WEIGHT = 2 X 157 = 313 lb

DESIGN CRITERIA

SPECIFIED LOADS:
TOP CH. LL = 25.8 PSF
DL = 8.0 PSF
BOT CH. LL = 0.0 PSF
DL = 7.4 PSF
TOTAL LOAD = 39.0 PSF

SPACING = 24.0 IN. C/C

LOADING IN FLAT SECTION BASED ON A SLOPE OF 6.0/12

THIS TRUSS IS DESIGNED FOR RESIDENTIAL OR SMALL BUILDING REQUIREMENTS OF PART 9, NBCC 2010, NBCC 2015

THIS DESIGN COMPLIES WITH:
- PART 9 OF BCBC 2018, OBC 2012, ABC 2019
- PART 9 OF OBC 2012 (2019 AMENDMENT)
- CSA 088-09, CSA 088-14
- TPIC 2011, TPIC 2014

(55% OF 31.3 P.S.F. G.S.L. PLUS 8.4 P.S.F. RAIN LOAD) EQUALS 25.8 P.S.F. SPECIFIED ROOF LIVE LOAD

ALLOWABLE DEFL.(LL) = L/360 (1.16")
CALCULATED VERT. DEFL.(LL) = L/899 (0.15")
ALLOWABLE DEFL.(TL) = L/360 (1.16")
CALCULATED VERT. DEFL.(TL) = L/899 (0.29")

CSI: TC=0.98/1.00 (E-G:1), BC=0.47/1.00 (L-M:1),
WB=0.54/1.00 (D-M:1), SS=0.30/1.00 (G-H:1)

DOL LUMBER=1.00 NAIL=1.00 LS BEND=1.10
COMP=1.10 SHEAR=1.10 TENS=1.10

COMPANION LIVE LOAD FACTOR = 1.00.

TRUSS PLATE MANUFACTURER IS NOT RESPONSIBLE FOR QUALITY CONTROL IN THE TRUSS MANUFACTURING PLANT.

NAIL VALUES
PLATE GRIP(DRY) SHEAR SECTION
(PSI) (PLI) (PLI)
MAX MIN MAX MIN MAX MIN
MT20 618 354 1667 788 1987 1668


PLATE PLACEMENT TOL. = 0.250 inches

PLATE ROTATION TOL. = 5.0 Deg.

JSI GRIP= 0.90 (A) (INPUT = 0.90)
JSI METAL= 0.53 (K) (INPUT = 1.00)



Structural component only
DWG# T-2007067



LUMBER			
N. L. G. A. RULES	SIZE	LUMBER	DESCR.
CHORDS			
P - A	2x4 DRY	No.2	SPF
A - C	2x4 DRY	No.2	SPF
C - F	2x4 DRY	No.2	SPF
F - H	2x4 DRY	No.2	SPF
I - H	2x4 DRY	No.2	SPF
P - N	2x4 DRY	No.2	SPF
N - K	2x4 DRY	No.2	SPF
K - J	2x4 DRY	No.2	SPF
ALL WEBS EXCEPT	2x4 DRY	No.2	SPF
J - G	2x3 DRY	No.2	SPF
O - B	2x3 DRY	No.2	SPF
L - E	2x3 DRY	No.2	SPF
M - D	2x3 DRY	No.2	SPF

DRY: SEASONED LUMBER.

PLATES (table is in inches)

JT	TYPE	PLATES	W	LEN	Y	X
A	TMVW-t	MT20	5.0	8.0	2.50	2.50
B	TMVW-t	MT20	4.0	8.0		
C	TS-t	MT20	3.0	8.0		
D	TMVW-t	MT20	2.0	4.0		
E	TMVW-t	MT20	4.0	4.0		
F	TS-t	MT20	3.0	8.0		
G	TMVW-t	MT20	4.0	8.0		
H	TMVW-t	MT20	5.0	8.0	2.50	2.50
I	BMVt-p	MT20	3.0	4.0		
J	BMVW-t	MT20	5.0	8.0	2.50	2.50
K	BS-t	MT20	3.0	6.0		
L	BMVW-t	MT20	4.0	8.0		
M	BMVW-t	MT20	3.0	6.0		
N	BS-t	MT20	3.0	6.0		
O	BMVW-t	MT20	5.0	8.0	2.50	2.50
P	BMVt-p	MT20	3.0	4.0		

DIMENSIONS, SUPPORTS AND LOADINGS SPECIFIED BY FABRICATOR TO BE VERIFIED BY BUILDING DESIGNER

FACTORED		MAXIMUM FACTORED		INPUT		REQD	
JT	VERT	GROSS REACTION	DOWN	BRG	IN-SX	BRG	IN-SX
P	1920	0	0	0	3-8	3-8	3-8
I	1920	0	1920	0	0	3-8	3-8

UNFACTORED REACTIONS

JT	1ST LCASE	2ND LCASE	3RD LCASE	4TH LCASE	5TH LCASE	6TH LCASE	7TH LCASE	8TH LCASE
P	1358	891 / 0	0 / 0	0 / 0	0 / 0	487 / 0	0 / 0	0 / 0
I	1358	891 / 0	0 / 0	0 / 0	0 / 0	487 / 0	0 / 0	0 / 0

BEARING MATERIAL TO BE SPF NO.2 OR BETTER AT JOINT(S) P, I

BRACING

TOP CHORD TO BE SHEATHED OR MAX. PURLIN SPACING = 3.58 FT.
MAX. UNBRACED BOTTOM CHORD LENGTH = 10.00 FT OR RIGID CEILING DIRECTLY APPLIED.

ALL PITCH BREAKS AND PERIMETER CORNER JOINTS MUST BE Laterally RESTRAINED.

1 LATERAL BRACE(S) AT 1/2 LENGTH OF A-P, H-I, G-J, B-O, E-M.

END VERTICAL(S) MUST BE SHEATHED OR HAVE BRACES AS INDICATED IN THE MAX. UNBRACED LENGTH COLUMN OF THE TABLE BELOW

LOADING

TOTAL LOAD CASES: (4)

CHORDS		FACTORED		MAX. FACTORED		WEBS		MAX. FACTORED	
MEMB.	FORCE (LBS)	VERT. LOAD (PLF)	LC1 MAX (LC)	UNBRACED LENGTH	FR-TO	MEMB.	FORCE (LBS)	MAX (LC)	UNBRACED LENGTH
P-A	-1868 / 0	0.0	0.0	0.55 (1)	4.91	J-H	0 / 2171	0.35 (1)	
A-B	-1458 / 0	-91.8	-91.8	0.80 (1)	4.26	A-O	0 / 2171	0.35 (1)	
B-C	-2108 / 0	-91.8	-91.8	0.90 (1)	3.58	J-G	-1483 / 0	0.61 (1)	
C-D	-2108 / 0	-91.8	-91.8	0.90 (1)	3.58	O-B	-1483 / 0	0.61 (1)	
D-E	-2108 / 0	-91.8	-91.8	0.68 (1)	4.00	L-G	0 / 982	0.16 (1)	
E-F	-2108 / 0	-91.8	-91.8	0.90 (1)	3.58	B-M	0 / 982	0.16 (1)	
F-G	-2108 / 0	-91.8	-91.8	0.90 (1)	3.58	L-E	-613 / 0	0.78 (1)	
G-H	-1458 / 0	-91.8	-91.8	0.79 (1)	4.27	M-D	-612 / 0	0.77 (1)	
H-I	-1868 / 0	0.0	0.0	0.55 (1)	4.91	M-E	-2 / 0	0.00 (1)	
P-O	0 / 0	-18.5	-18.5	0.22 (4)	10.00				
O-N	0 / 1458	-18.5	-18.5	0.38 (1)	10.00				
N-M	0 / 1458	-18.5	-18.5	0.38 (1)	10.00				
M-L	0 / 2108	-18.5	-18.5	0.42 (1)	10.00				
L-K	0 / 1458	-18.5	-18.5	0.38 (1)	10.00				
K-J	0 / 1458	-18.5	-18.5	0.38 (1)	10.00				
J-I	0 / 0	-18.5	-18.5	0.22 (4)	10.00				

TOTAL WEIGHT = 10 X 178 = 1785 lb

DESIGN CRITERIA

SPECIFIED LOADS:
TOP CH. LL = 25.8 PSF
DL = 6.0 PSF
BOT CH. LL = 0.0 PSF
DL = 7.4 PSF
TOTAL LOAD = 38.0 PSF

SPACING = 24.0 IN. C/C

LOADING IN FLAT SECTION BASED ON A SLOPE OF 6.00/12

THIS TRUSS IS DESIGNED FOR RESIDENTIAL OR SMALL BUILDING REQUIREMENTS OF PART 9, NBC 2010, NBC 2015

THIS DESIGN COMPLIES WITH:
- PART 9 OF CBC 2018, CBC 2012, ABC 2019
- PART 9 OF CBC 2012 (2019 AMENDMENT)
- CSA 086-09, CSA 088-14
- TPIC 2011, TPIC 2014

(55 % OF 31.3 P.S.F. G.S.L. PLUS 8.4 P.S.F. RAIN LOAD) EQUALS 25.8 P.S.F. SPECIFIED ROOF LIVE LOAD

ALLOWABLE DEFL.(LL) = L/360 (1.16")
CALCULATED VERT. DEFL.(LL) = L/999 (0.12")
ALLOWABLE DEFL.(TL) = L/360 (1.16")
CALCULATED VERT. DEFL.(TL) = L/999 (0.24")

CSI: TC=0.80/1.00 (B-D:1), BC=0.42/1.00 (L-M:1), WB=0.79/1.00 (E-L:1), SS=0.31/1.00 (A-B:1)

DOL LUMBER=1.00 NAIL=1.00 LS BEND=1.10 COMP=1.10 SHEAR=1.10 TENS=1.10

COMPANION LIVE LOAD FACTOR = 1.00


TRUSS PLATE MANUFACTURER IS NOT RESPONSIBLE FOR QUALITY CONTROL IN THE TRUSS MANUFACTURING PLANT.

NAIL VALUES
PLATE GRIP(DRY) SHEAR SECTION (PS) (PL) (PL)
MAX MIN MAX MIN MAX MIN
MT20 618 354 1667 788 1937 1656


PLATE PLACEMENT TOL. = 0.250 inches

PLATE ROTATION TOL. = 5.0 Deg.


JSI GRIP = 0.87 (A) (INPUT = 0.90)
JSI METAL = 0.47 (N) (INPUT = 1.00)



Structural component only
DWG# T-2007068

DAWG NO.


JSI GRIP= 0.89 (C) (INPUT = 0.90)
JSI METAL= 0.57 (J) (INPUT = 1.00)



JOB NAME	TRUSS NAME	QUANTITY	PLY	JOB DESC.	GREEN PARK HOMES	DRWG NO.
408150	T7	1	1	TRUSS DESC.		

Tamarack Roof Truss, Burlington

Version 8.310 S Oct 29 2019 Mtek Industries, Inc. Sat Apr 25 11:02:55 2020 Page 1
ID:7vF7aG0E03cRUj8X1iSrkzWYK-G?AZmyXBtqFI_Ky|qhuquaTK3IVZXS_cD2RiIVzNCnU



Scale = 1/32" = 1'-0"

LUMBER	N. L. G. A. RULES	CHORDS	SIZE	DRY	LUMBER	DESCR.
A - B	2x4	DRY	No.2	SPF		
B - C	2x4	DRY	No.2	SPF		
C - D	2x4	DRY	No.2	SPF		
I - A	2x4	DRY	No.2	SPF		
E - D	2x4	DRY	No.2	SPF		
I - G	2x4	DRY	No.2	SPF		
G - E	2x4	DRY	No.2	SPF		

ALL WEBS	2x3	DRY	No.2	SPF
EXCEPT				

DRY: SEASONED LUMBER.

PLATES (tablets in inches)

JT	TYPE	PLATES	W	LEN	Y	X
A	TMVW+p	MT20	4.0	4.0	1.00	2.00
B	TTWV+m	MT20	5.0	6.0	2.25	1.50
C	TTW-m	MT20	4.0	4.0		
D	TMVW+p	MT20	4.0	4.0	1.00	2.00
E	BMV1+p	MT20	3.0	4.0		
F	BMWWV-l	MT20	4.0	9.0		
G	BS-l	MT20	3.0	6.0		
H	BMWW-l	MT20	4.0	4.0		
I	BMV1+p	MT20	3.0	4.0		

DIMENSIONS, SUPPORTS AND LOADINGS SPECIFIED BY FABRICATOR TO BE VERIFIED BY BUILDING DESIGNER

JT	FACTORED GROSS REACTION		MAXIMUM FACTORED GROSS REACTION		INPUT BRG	REQD BRG
	VERT	HORZ	DOWN	UPLIFT		
I	905	0	905	0	3-8	3-8
E	905	0	905	0	5-8	5-8

UNFACTORED REACTIONS

JT	1ST LOSE	MAX/MIN. COMPONENT REACTIONS	SNOW	LIVE	PERM. LIVE	WIND	DEAD	SOIL
I	COMBINED	840	420 / 0	0 / 0	0 / 0	0 / 0	220 / 0	0 / 0
E	COMBINED	840	420 / 0	0 / 0	0 / 0	0 / 0	220 / 0	0 / 0

BEARING MATERIAL TO BE SPF NO.2 OR BETTER AT JOINT(S) I, E

BRACING

TOP CHORD TO BE SHEATHED OR MAX. PURLIN SPACING = 6.25 FT.
MAX. UNBRACED BOTTOM CHORD LENGTH = 10.00 FT. OR RIGID CEILING DIRECTLY APPLIED.

ALL PITCH BREAKS AND PERIMETER CORNER JOINTS MUST BE LATERALLY RESTRAINED.

LOADING

TOTAL LOAD CASES: (4)

CHORDS			WEBS						
MEMB.	MAX. FACTORED FORCE (LBS)	FACTORED VERT. LOAD (PLF)	LC1 MAX CSI (LC)	MAX. UNBRACED LENGTH	MEMB.	MAX. FACTORED FORCE (LBS)	MAX CSI (LC)		
FR-TO		FROM	TO	FR-TO					
A-B	-718 / 0	-91.8	-91.8	0.39 (1)	6.25	H-B	-34 / 68 0.02 (4)		
B-C	-558 / 0	-91.8	-91.8	0.28 (1)	6.25	B-F	0 / 14 0.00 (1)		
C-D	-729 / 0	-91.8	-91.8	0.42 (1)	6.25	F-C	-23 / 74 0.03 (4)		
I-A	-880 / 0	0.0	0.0	0.09 (1)	7.81	A-H	0 / 567 0.13 (1)		
E-D	-858 / 0	0.0	0.0	0.09 (1)	7.81	F-D	0 / 572 0.13 (1)		
I-H	0 / 0	-18.5	-18.5	0.13 (4)	10.00				
H-G	0 / 550	-18.5	-18.5	0.18 (4)	10.00				
G-F	0 / 550	-18.5	-18.5	0.18 (4)	10.00				
F-E	0 / 0	-18.5	-18.5	0.14 (4)	10.00				

TOTAL WEIGHT = 70 lb

DESIGN CRITERIA

SPECIFIED LOADS:

TOP CH. LL	= 25.6 PSF
DL	= 8.0 PSF
BOT CH. LL	= 0.0 PSF
DL	= 7.4 PSF
TOTAL LOAD	= 39.0 PSF

SPACING = 24.0 IN. C/C

LOADING IN FLAT SECTION BASED ON A SLOPE OF 6.00/12

THIS TRUSS IS DESIGNED FOR RESIDENTIAL OR SMALL BUILDING REQUIREMENTS OF PART 9, NBCC 2010, NBCC 2015

THIS DESIGN COMPLIES WITH:

- PART 9 OF NBC 2010, CBC 2012, ABC 2019
- PART 9 OF NBC 2012 (2019 AMENDMENT)
- CSA 088-09, CSA 086-14
- TPIC 2011, TPIC 2014

(55% OF 31.3 P.S.F. G.S.L. PLUS 8.4 P.S.F. RAIN LOAD) EQUALS 25.8 P.S.F. SPECIFIED ROOF LIVE LOAD

ALLOWABLE DEFL. (LL) = $L/360$ (0.55")
CALCULATED VERT. DEFL. (LL) = $L/989$ (0.01")
ALLOWABLE DEFL. (TL) = $L/360$ (0.55")
CALCULATED VERT. DEFL. (TL) = $L/989$ (0.05")

CSI: TC=0.42/1.00 (C-D:1), BC=0.18/1.00 (F-H:4), WB=0.13/1.00 (D-F:1), SS=0.17/1.00 (B-C:1)

DOL LUMBER=1.00 NAIL=1.00 LS BEND=1.10
COMP=1.10 SHEAR=1.10 TENS=1.10

COMPANION LIVE LOAD FACTOR = 1.00

TRUSS PLATE MANUFACTURER IS NOT RESPONSIBLE FOR QUALITY CONTROL IN THE TRUSS MANUFACTURING PLANT.

NAIL VALUES

PLATE	GRIP (DRY) (PS)	SHEAR (PLI)	SECTION (PLI)
MT20	618	354	1867
	788	1987	1856

PLATE PLACEMENT TOL. = 0.250 inches

PLATE ROTATION TOL. = 5.0 Deg.


JSI GRIP = 0.85 (D) (INPUT = 0.90)
JSI METAL = 0.24 (D) (INPUT = 1.00)



Structural component only
DWG# T-2007070

JOB NAME 408150	TRUSS NAME T8	QUANTITY 1	PLY 1	JOB DESC. GREEN PARK HOMES	DRWG NO.
Tamarack Roof Truss, Burlington				TRUSS DESC.	

Version 8.310 S Oct 29 2019 MITK Industries, Inc. Sat Apr 25 11:02:58 2020 Page 1
ID:17VF7aG0E03cRUj6X1SrKzIYpQ8NwUxvNNPzRo0Y3nGGpIIRiAFBzNCnT



LUMBER			
N. L. G. A. RULES	SIZE	DRY	LUMBER
A - C	2x4	DRY	No.2
C - D	2x4	DRY	No.2
D - F	2x4	DRY	No.2
J - A	2x4	DRY	No.2
G - F	2x4	DRY	No.2
H - H	2x4	DRY	No.2
J - H	2x4	DRY	No.2

ALL WEBS 2x3 DRY No.2
EXCEPT

DRY: SEASONED LUMBER.

PLATES (table is in inches)

JT	TYPE	PLATES	W	LEN	Y	X
A	TMV-p	MT20	3.0	4.0		
B	TMWW-t	MT20	4.0	6.0		
C	TTW-m	MT20	4.0	4.0		
D	TTW-m	MT20	4.0	4.0		
E	TMWW-t	MT20	4.0	6.0		
F	TMV-p	MT20	3.0	4.0		
G	BMVW-t	MT20	4.0	4.0		
H	BS-t	MT20	3.0	6.0		
I	BMVWW-t	MT20	5.0	12.0	3.00	6.00
J	BMVW-t	MT20	4.0	4.0		

DIMENSIONS, SUPPORTS AND LOADINGS SPECIFIED BY FABRICATOR TO BE VERIFIED BY BUILDING DESIGNER

FACTORED		MAXIMUM FACTORED		INPUT		REQD	
JT	VERT	GROSS REACTION	GROSS REACTION	BRG	BRG	BRG	BRG
J	905	0	905	0	0	3-8	3-8
G	905	0	905	0	0	MECHANICAL	

A SUITABLE HANGER/MECHANICAL CONNECTION IS REQUIRED AT JOINT G. MINIMUM BEARING LENGTH AT JOINT G = 3-8.

UNFACTORED REACTIONS

JT	COMBINED	SNOW	LIVE	PERM.LIVE	WIND	DEAD	SOIL
J	640	420 / 0	0 / 0	0 / 0	0 / 0	220 / 0	0 / 0
G	640	420 / 0	0 / 0	0 / 0	0 / 0	220 / 0	0 / 0

BEARING MATERIAL TO BE SPF NO.2 OR BETTER AT JOINT(S) J

BRACING

TOP CHORD TO BE SHEATHED OR MAX. PURLIN SPACING = 8.25 FT.
MAX. UNBRACED BOTTOM CHORD LENGTH = 10.00 FT OR RIGID CEILING DIRECTLY APPLIED.

ALL PITCH BREAKS AND PERIMETER CORNER JOINTS MUST BE Laterally RESTRAINED.

LOADING

TOTAL LOAD CASES: (4)

CHORDS				WEBS			
MEMB.	MAX. FACTORED FORCE (LBS)	FACTORED VERT. LOAD (LBS)	MAX. CSI (LC)	MEMB.	MAX. FACTORED FORCE (LBS)	MAX. CSI (LC)	
FR-TO		FROM TO		FR-TO			
A-B	0 / 27	-91.8 -91.8	0.22 (1)	10.00	B-I	-163 / 0	0.11 (1)
B-C	-649 / 0	-91.8 -91.8	0.17 (1)	8.25	I-E	-190 / 0	0.13 (1)
C-D	-489 / 0	-91.8 -91.8	0.01 (1)	8.25	J-B	-830 / 0	0.54 (1)
D-E	-650 / 0	-91.8 -91.8	0.18 (1)	8.25	E-G	-935 / 0	0.57 (1)
E-F	0 / 27	-91.8 -91.8	0.23 (1)	10.00	C-I	0 / 221	0.05 (1)
J-A	-129 / 0	0.0 0.0	0.01 (1)	7.81	I-D	0 / 222	0.05 (1)
G-F	-137 / 0	0.0 0.0	0.01 (1)	7.81			
J-I	0 / 590	-18.5 -18.5	0.41 (4)	10.00			
I-H	0 / 608	-18.5 -18.5	0.41 (4)	10.00			
H-G	0 / 608	-18.5 -18.5	0.41 (4)	10.00			

TOTAL WEIGHT = 77 b

DESIGN CRITERIA

SPECIFIED LOADS:

TOP CH. LL	= 25.6 PSF
DL	= 6.0 PSF
BOT CH. LL	= 0.0 PSF
DL	= 7.4 PSF
TOTAL LOAD	= 39.0 PSF

SPACING = 24.0 IN./C/C

LOADING IN FLAT SECTION BASED ON A SLOPE OF 6.00/12

THIS TRUSS IS DESIGNED FOR RESIDENTIAL OR SMALL BUILDING REQUIREMENTS OF PART 9, NBCC 2010, NBCC 2015

THIS DESIGN COMPLIES WITH:
- PART 9 OF BCBC 2018, OBC 2012, ABC 2019
- PART 9 OF OBC 2012 (2019 AMENDMENT)
- CSA 088-09, CSA 088-14
- TPIC 2011, TPIC 2014

(55 % OF 31.3 P.S.F. G.S.I. PLUS 8.4 P.S.F. RAIN LOAD) EQUALS 25.6 P.S.F. SPECIFIED ROOF LIVE LOAD

ALLOWABLE DEFL.(LL) = L/360 (0.55")
CALCULATED VERT. DEFL.(LL) = L/999 (0.02")
ALLOWABLE DEFL.(TL) = L/360 (0.55")
CALCULATED VERT. DEFL.(TL) = L/999 (0.11")

CSI: TC=0.23/1.00 (E-F:1), BC=0.41/1.00 (G-I:4), WB=0.57/1.00 (E-G:1), SSI=0.13/1.00 (D-E:1)

DOL LUMBER=1.00 NAIL=1.00 LBS BEND=1.10
COMP=1.10 SHEAR=1.10 TENS=1.10

COMPANION LIVE LOAD FACTOR = 1.00

TRUSS PLATE MANUFACTURER IS NOT RESPONSIBLE FOR QUALITY CONTROL IN THE TRUSS MANUFACTURING PLANT


NAIL VALUES

PLATE GRIP(DRY)	SHEAR (PSI)	SECTION (PLI)
MAX MIN	MAX MIN	MAX MIN
MT20	618 354	1667 789

PLATE PLACEMENT TOL. = 0.250 inches


PLATE ROTATION TOL. = 5.0 Deg.

JSI GRIP= 0.75 (G) (INPUT = 0.80)
JSI METAL= 0.23 (G) (INPUT = 1.00)



Structural component only
DWG# T-2007071

JOB NAME	TRUSS NAME	QUANTITY	PLY	JOB DESC.	DRWG NO.
408150	T9	1	1	GREEN PARK HOMES	
Tamarack Roof Truss, Burlington				TRUSS DESC.	



LUMBER	N. L. G. A. RULES	CHORDS	SIZE	LUMBER	DESCR.
A - C	2x4	DRY	No.2	SPF	
C - E	2x4	DRY	No.2	SPF	
K - A	2x4	DRY	No.2	SPF	
F - E	2x4	DRY	No.2	SPF	
K - H	2x4	DRY	No.2	SPF	
H - F	2x4	DRY	No.2	SPF	

ALL WEBS 2x3 DRY No.2
EXCEPT

DRY: SEASONED LUMBER.

PLATES (tablets in inches)

JT	TYPE	PLATES	W	LEN	Y	X
A	TMVW+p	MT20	4.0	4.0	1.00	2.00
B	TMVW-i	MT20	4.0	4.0	2.00	1.25
C	TTW+p	MT20	4.0	6.0	Edge	
D	TMVW-i	MT20	4.0	4.0	2.00	1.25
E	TMVW+p	MT20	4.0	4.0	1.00	2.00
F	BMV1+p	MT20	3.0	4.0		
G	BMVW-i	MT20	4.0	6.0		
H	BS-i	MT20	3.0	6.0		
I	BMVW-i	MT20	4.0	9.0		
J	BMVW-i	MT20	4.0	4.0		
K	BMV1+p	MT20	3.0	4.0		

Edge - INDICATES REFERENCE CORNER OF PLATE TOUCHES EDGE OF CHORD.

DIMENSIONS, SUPPORTS AND LOADINGS SPECIFIED BY FABRICATOR TO BE VERIFIED BY BUILDING DESIGNER

BEARINGS	FACTORED	MAXIMUM FACTORED	INPUT	REQD
	GROSS REACTION	GROSS REACTION	BRG	BRG
JT	VERT	DOWN	UP	IN-SX
K	905	0	0	3-8
F	905	0	0	MECHANICAL

A SUITABLE HANGER/MECHANICAL CONNECTION IS REQUIRED AT JOINT F. MINIMUM BEARING LENGTH AT JOINT F = 3'-8".

UNFACTORED REACTIONS

JT	1ST CASE	MAX/MIN. COMPONENT REACTIONS	PERM. LIVE	WIND	DEAD	SOIL
K	640	420 / 0	0 / 0	0 / 0	220 / 0	0 / 0
F	640	420 / 0	0 / 0	0 / 0	220 / 0	0 / 0

BEARING MATERIAL TO BE SPF NO.2 OR BETTER AT JOINT(S) K

BRACING

TOP CHORD TO BE SHEATHED OR MAX. PURLIN SPACING = 6.25 FT.
MAX. UNBRACED BOTTOM CHORD LENGTH = 10.00 FT. OR RIGID CEILING DIRECTLY APPLIED.

ALL PITCH BREAKS AND PERIMETER CORNER JOINTS MUST BE Laterally RESTRAINED.

LOADING

TOTAL LOAD CASES: (4)

CHORDS	MAX. FACTORED	FACTORED	WEBS	MAX. FACTORED
MEMB.	FORCE (LBS)	VERT. LOAD (LBS)	MEMB.	FORCE (LBS)
FR-TO		FROM TO	FR-TO	
A-B	-772 / 0	-91.8 -91.8 0.20 (1)	J-B	-135 / 21
B-C	-620 / 0	-91.8 -91.8 0.19 (1)	B-I	-251 / 0
C-D	-822 / 0	-91.8 -91.8 0.20 (1)	I-C	0 / 478
D-E	-795 / 0	-91.8 -91.8 0.21 (1)	I-D	-278 / 0
K-A	-873 / 0	0.0 0.0 0.10 (1)	G-D	-110 / 31
F-E	-872 / 0	0.0 0.0 0.09 (1)	A-J	0 / 653
			G-E	0 / 662
K-J	0 / 0	-18.5 -18.5 0.07 (4)		
J-I	0 / 615	-18.5 -18.5 0.13 (1)		
I-H	0 / 633	-18.5 -18.5 0.14 (1)		
H-G	0 / 633	-18.5 -18.5 0.14 (1)		
G-F	0 / 0	-18.5 -18.5 0.07 (4)		

DESIGN CRITERIA

SPECIFIED LOADS:
TOP CH. LL = 25.6 PSF
DL = 6.0 PSF
BOT CH. LL = 0.0 PSF
DL = 7.4 PSF
TOTAL LOAD = 39.0 PSF

SPACING = 24.0 IN. C/C

THIS TRUSS IS DESIGNED FOR RESIDENTIAL OR SMALL BUILDING REQUIREMENTS OF PART 9, NBCC 2010, NBCC 2015

THIS DESIGN COMPLIES WITH:
- PART 9 OF BCBC 2018, OBC 2012, ABC 2019
- PART 9 OF OBC 2012 (2019 AMENDMENT)
- CSA 088-09, CSA 088-14
- TPIC 2011, TPIC 2014

(55% OF 31.3 P.S.F. G.S.L. PLUS 6.4 P.S.F. RAIN LOAD) EQUALS 25.6 P.S.F. SPECIFIED ROOF LIVE LOAD

ALLOWABLE DEFL.(LL) = L/360 (0.55")
CALCULATED VERT. DEFL.(LL) = L/999 (0.02")
ALLOWABLE DEFL.(TL) = L/360 (0.55")
CALCULATED VERT. DEFL.(TL) = L/999 (0.03")

CSI: TC=0.21/1.00 (D-E:1), BC=0.14/1.00 (G-I:1),
WB=0.20/1.00 (D-E:1), SSI=0.14/1.00 (D-E:1)

DOL LUMBER=1.00 NAIL=1.00 LS BEND=1.10
COMP=1.10 SHEAR=1.10 TENS=1.10

COMPANION LIVE LOAD FACTOR = 1.00

TRUSS PLATE MANUFACTURER IS NOT RESPONSIBLE FOR QUALITY CONTROL IN THE TRUSS MANUFACTURING PLANT.

NAIL VALUES
PLATE GRIP(DRY) SHEAR SECTION
(PS) (PL) (PL)
MAX MIN MAX MIN MAX MIN
MT20 618 354 1687 786 1907 1666

PLATE PLACEMENT TOL. = 0.250 inches

PLATE ROTATION TOL. = 5.0 Deg.

JSI GRIP= 0.87 (E) (INPUT = 0.90)
JSI METAL= 0.24 (E) (INPUT = 1.00)




Structural component only
DWG# T-2007072

JOB NAME	TRUSS NAME	QUANTITY	PLY	JOB DESC.	DRWG NO.
408150	T10S	2	1	GREEN PARK HOMES	
Tamarack Roof Truss, Burlington					

Version 8.310 S Oct 28 2019 Mitek Industries, Inc. Sat Apr 25 11:02:58 2020 Page 1
ID:17vF7aG0E03cRU(8X1)SkziWYK-hanO_a4yldDrohiVoRRW05vytX_kqu2v0IMFp2NCnR

Scale = 1/32



LUMBER	N. L. G. A. RULES	CHORDS	SIZE	DRY	LUMBER
A - D	2x4	DRY	No.2		
D - G	2x4	DRY	No.2		
N - B	2x4	DRY	No.2		
H - F	2x4	DRY	No.2		
N - M	2x4	DRY	No.2		
M - C	2x4	DRY	No.2		
L - J	2x4	DRY	No.2		
I - E	2x4	DRY	No.2		
I - H	2x4	DRY	No.2		
ALL WEBS	2x3	DRY	No.2		
EXCEPT					
N - L	2x4	DRY	No.2		
J - H	2x4	DRY	No.2		

DRY: SEASONED LUMBER.

PLATES (table in inches)

JT TYPE	PLATES	W	LEN	Y	X
B, C, E, F					
B	TMVW+p	MT20	4.0	4.0	1.00 2.00
D	TTW+p	MT20	4.0	8.0	Edge
H	BMVW1-i	MT20	4.0	4.0	
I	BMV+p	MT20	3.0	4.0	
J	BVMWW-i	MT20	5.0	12.0	5.00 7.75
K	BMVWW-i	MT20	4.0	9.0	
L	BVMWW-i	MT20	5.0	12.0	5.00 7.75
M	BMV+p	MT20	3.0	4.0	
N	BMVW1-i	MT20	4.0	4.0	

Edge - INDICATES REFERENCE CORNER OF PLATE TOUCHES EDGE OF CHORD.

DIMENSIONS, SUPPORTS AND LOADINGS SPECIFIED BY FABRICATOR TO BE VERIFIED BY BUILDING DESIGNER

FACTORED	MAXIMUM FACTORED	INPUT	RECORD
GROSS REACTION	GROSS REACTION	BRG	BRG
JT VERT	HORZ	DOWN	HORZ
N	729	0	0
H	729	0	0

A SUITABLE HANGER/MECHANICAL CONNECTION IS REQUIRED AT JOINT H. MINIMUM BEARING LENGTH AT JOINT H = 1-8.

UNFACTORED REACTIONS

1ST LOOSE	MAX/MIN. COMPONENT REACTIONS	WIND	DEAD	SOIL
JT COMBINED	SNOW	LIVE	PERM. LIVE	
N	513	350 / 0	0 / 0	0 / 0
H	513	350 / 0	0 / 0	0 / 0

BEARING MATERIAL TO BE SPF NO.2 OR BETTER AT JOINT(S) N

BRACING

TOP CHORD TO BE SHEATHED OR MAX. PURLIN SPACING = 6.25 FT.
MAX. UNBRACED BOTTOM CHORD LENGTH = 7.81 FT OR RIGID CEILING DIRECTLY APPLIED.

ALL PITCH BREAKS AND PERIMETER CORNER JOINTS MUST BE Laterally RESTRAINED.

LOADING

TOTAL LOAD CASES: (4)

CHORDS	MAX. FACTORED	FACTORED	VERT. LOAD	LC1	MAX	MAX	UNBRAC	FR-TO	WEBS	MAX. FACTORED	MAX
MEMB.	FORCE	VERT. LOAD	LC1	MAX	MAX	UNBRAC	FR-TO	MEMB.	FORCE	MAX	
(LBS)	(LBS)	(PLF)	(LBS)	(LBS)	(LBS)	(LBS)	(LBS)	(LBS)	(LBS)	(LBS)	(LBS)
FR-TO											
A-B	0 / 41	-91.8	-91.8	0.13 (1)	10.00	C-K	-211 / 0	0.07 (1)			
B-C	-847 / 0	-91.8	-91.8	0.14 (1)	8.25	K-D	0 / 229	0.05 (1)			
C-D	-447 / 0	-91.8	-91.8	0.18 (1)	6.25	K-E	-210 / 0	0.07 (1)			
D-E	-447 / 0	-91.8	-91.8	0.18 (1)	6.25	N-L	-26 / 0	0.00 (1)			
E-F	-848 / 0	-91.8	-91.8	0.14 (1)	6.25	B-L	0 / 527	0.12 (1)			
F-G	0 / 41	-91.8	-91.8	0.13 (1)	10.00	J-F	0 / 528	0.12 (1)			
N-B	-701 / 0	0.0	0.0	0.07 (1)	7.81	J-H	-26 / 0	0.00 (1)			
H-F	-701 / 0	0.0	0.0	0.07 (1)	7.81						
N-M	0 / 20	-18.5	-18.5	0.01 (4)	10.00						
M-L	0 / 14	0.0	0.0	0.03 (1)	10.00						
L-C	-92 / 2	0.0	0.0	0.02 (1)	7.81						
L-K	0 / 528	-18.5	-18.5	0.13 (1)	10.00						
K-J	0 / 627	-18.5	-18.5	0.13 (1)	10.00						
I-J	0 / 14	0.0	0.0	0.03 (1)	10.00						
J-E	-93 / 2	0.0	0.0	0.02 (1)	7.81						
I-H	0 / 20	-18.5	-18.5	0.01 (4)	10.00						

TOTAL WEIGHT = 2 X 56 = 112 lb

DESIGN CRITERIA

SPECIFIED LOADS:
TOP CH. LL = 25.0 PSF
DL = 6.0 PSF
BOT CH. LL = 0.0 PSF
DL = 7.4 PSF
TOTAL LOAD = 39.0 PSF

SPACING = 24.0 IN/CG

THIS TRUSS IS DESIGNED FOR RESIDENTIAL OR SMALL BUILDING REQUIREMENTS OF PART 9, NBC 2010, NBC 2015

THIS DESIGN COMPLIES WITH:
- PART 9 OF NBC 2010, NBC 2012, ABC 2018
- PART 9 OF NBC 2012 (2019 AMENDMENT)
- CSA 086-09, CSA 086-14
- TPIC 2011, TPIC 2014

DESIGN ASSUMPTIONS
- OVERHANG NOT TO BE ALTERED OR CUT OFF.

(55 % OF 31.3 P.S.F. G.S.L. PLUS 8.4 P.S.F. RAIN LOAD) EQUALS 25.8 P.S.F. SPECIFIED ROOF LIVE LOAD

ALLOWABLE DEFL.(LL) = L/360 (0.38")
CALCULATED VERT. DEFL.(LL) = L/999 (0.01")
ALLOWABLE DEFL.(TL) = L/360 (0.38")
CALCULATED VERT. DEFL.(TL) = L/999 (0.02")
CSI: TC=0.19/1.00 (C-D:1), BC=0.13/1.00 (K-L:1),
WB=0.12/1.00 (B-L:1), SS=0.13/1.00 (C-D:1)

DOL LUMBER=1.00 NAIL=1.00 LS BEND=1.10
COMP=1.10 SHEAR=1.10 TENS=1.10

COMPANION LIVE LOAD FACTOR = 1.00

AUTOSOLVE HEELS OFF

TRUSS PLATE MANUFACTURER IS NOT RESPONSIBLE FOR QUALITY CONTROL IN THE TRUSS MANUFACTURING PLANT.

NAIL VALUES
PLATE GRIP(DRY) SHEAR SECTION
(PS) (PL) (PL)
MAX MIN MAX MIN MAX MIN
MT20 618 354 1887 788 1987 1656

PLATE PLACEMENT TOL. = 0.250 inches


PLATE ROTATION TOL. = 5.0 Deg.

JSI GRIP= 0.74 (F) (INPUT = 0.90)
JSI METAL= 0.20 (F) (INPUT = 1.00)



Structural component only
DWG# T-2007073

JOB NAME	TRUSS NAME	QUANTITY	PLY	JOB DESC.	DRWG NO.
408150	T11	1	1	GREEN PARK HOMES	
Tamarack Roof Truss, Burlington		TRUSS DESC.		Version 8.310.5 Oct 29 2019 Mitek Industries, Inc. Sat Apr 25 11:02:59 2020 Page 1	
				ID:17vF7a30E03cRuj8X1jSkzIWYK-9mP4cKajl3i4TxGU3Vzg2Qe15H8aTHx87gPvoGzNCnQ	



Scale = 1/32"

LUMBER			
N. L. G. A. RULES	CHORDS	SIZE	LUMBER
A - C	2x4	DRY	No.2
C - E	2x4	DRY	No.2
H - B	2x4	DRY	No.2
F - D	2x4	DRY	No.2
H - F	2x4	DRY	No.2

ALL WEBS 2x3 DRY No.2 EXCEPT

DRY: SEASONED LUMBER.

PLATES (table in inches)

JT TYPE	PLATES	W	LEN	Y	X
B	TMVW+P	MT20	4.0	4.0	1.00 2.00
C	TTW+P	MT20	4.0	6.0	Edge
D	TMVW+P	MT20	4.0	4.0	1.00 2.00
F	BMV1+P	MT20	3.0	4.0	
G	BMVW+P	MT20	4.0	4.0	
H	BMV1+P	MT20	3.0	4.0	

Edge - INDICATES REFERENCE CORNER OF PLATE TOUCHES EDGE OF CHORD.

DIMENSIONS, SUPPORTS AND LOADINGS SPECIFIED BY FABRICATOR TO BE VERIFIED BY BUILDING DESIGNER

BEARINGS		FACTORED	MAXIMUM FACTORED	INPUT	REQ'D
		GROSS REACTION	GROSS REACTION	BRG	BRG
JT	VERT	HORZ	DOWN	UPLIFT	IN-SX
H	729	0	729	0	5-8
F	729	0	729	0	5-8

A SUITABLE HANGER/MECHANICAL CONNECTION IS REQUIRED AT JOINT F. MINIMUM BEARING LENGTH AT JOINT F = 1-8.

UNFACTORED REACTIONS

JT	1ST LOASE	MAX/MIN. COMPONENT REACTIONS	SNOW	LIVE	PERM.LIVE	WIND	DEAD	SOIL
H	COMBINED	513	350 / 0	0 / 0	0 / 0	0 / 0	163 / 0	0 / 0
F	COMBINED	513	350 / 0	0 / 0	0 / 0	0 / 0	163 / 0	0 / 0

BEARING MATERIAL TO BE SPF NO.2 OR BETTER AT JOINT(S) H

BRACING

TOP CHORD TO BE SHEATHED OR MAX. PURLIN SPACING = 6.25 FT.
MAX. UNBRACED BOTTOM CHORD LENGTH = 10.00 FT. OR RIGID CEILING DIRECTLY APPLIED.

ALL PITCH BREAKS AND PERIMETER CORNER JOINTS MUST BE Laterally RESTRAINED.

LOADING

TOTAL LOAD CASES: (4)

CHORDS		FACTORED		WEBS	
MEMB.	MAX. FORCE (LBS)	VERT. LOAD (PLF)	MAX. UNBRACED LENGTH (FT)	MEMB.	MAX. FORCE (LBS)
A-B	0 / 41	-91.8	-91.8 0.13 (1)	G-C	-15 / 89
B-C	-380 / 0	-91.8	-91.8 0.35 (1)	G-D	0 / 300
C-D	-380 / 0	-91.8	-91.8 0.35 (1)	G-E	0 / 300
D-E	0 / 41	-91.8	-91.8 0.13 (1)	G-F	0 / 300
H-B	-690 / 0	0.0	0.0 0.07 (1)		
F-D	-690 / 0	0.0	0.0 0.07 (1)		
H-G	0 / 0	-18.5	-18.5 0.16 (4)		
G-F	0 / 0	-18.5	-18.5 0.16 (4)		

TOTAL WEIGHT = 49 lb (M/F)

DESIGN CRITERIA

SPECIFIED LOADS:
TOP CH. LL = 25.6 PSF
DL = 6.0 PSF
BOT CH. LL = 0.0 PSF
DL = 0.0 PSF
TOTAL LOAD = 39.0 PSF

SPACING = 24.0 IN. C/C

THIS TRUSS IS DESIGNED FOR RESIDENTIAL OR SMALL BUILDING REQUIREMENTS OF PART 9, NBC 2010, NBCC 2015

THIS DESIGN COMPLIES WITH:
- PART 9 OF NBC 2010, NBC 2012, ABC 2019
- PART 9 OF NBC 2012 (2019 AMENDMENT)
- CSA 088-09, CSA 086-14
- TPIC 2011, TPIC 2014

(55% OF 31.3 P.S.F. G.S.I. PLUS 8.4 P.S.F. RAIN LOAD) EQUALS 25.6 P.S.F. SPECIFIED ROOF LIVE LOAD

ALLOWABLE DEFL.(LL) = L/360 (0.36")
CALCULATED VERT. DEFL.(LL) = L/999 (0.00")
ALLOWABLE DEFL.(TL) = L/360 (0.36")
CALCULATED VERT. DEFL.(TL) = L/999 (0.02")

CSI: TC=0.35/1.00 (B-C:1), BC=0.16/1.00 (G-H:4), WB=0.07/1.00 (D-G:1), SS=0.15/1.00 (B-C:1)

DOL LUMBER=1.00 NAIL=1.00 LS 8END=1.10
COMP=1.10 SHEAR=1.10 TENS=1.10

COMPANION LIVE LOAD FACTOR = 1.00

TRUSS PLATE MANUFACTURER IS NOT RESPONSIBLE FOR QUALITY CONTROL IN THE TRUSS MANUFACTURING PLANT.


NAIL VALUES

PLATE	GRIP(DRY)	SHEAR	SECTION
(PSI)	(PL)	(PL)	(PL)
MT20	618	354	1887

PLATE PLACEMENT TOL. = 0.250 inches

PLATE ROTATION TOL. = 5.0 Deg.


JSI GRIP= 0.62 (D) (INPUT = 0.90)
JSI METAL= 0.17 (D) (INPUT = 1.00)



Structural component only
DWG# T-2007074

JOB NAME	TRUSS NAME	QUANTITY	PLY	JOB DESC.	TRUSS DESC.	DRWG NO.
408150	T12	1	1	GREEN PARK HOMES		
Tamarack Roof Truss, Burlington						

Version 8.310 S Oct 29 2019 MITek Industries, Inc. Sat Apr 25 11:03:01 2020 Page 1
ID:4NxGlt_xHSHnstgnSWZu6izNuP8-59Xq1?oyEg?oiFQsAw?B8BrjPP4ZbxCqUb_u0s8zNCnO



Scale = 1:32.5

LUMBER			
N. L. G. A. RULES			
CHORDS	SIZE		LUMBER
A - B	2x4	DRY	No.2
B - C	2x4	DRY	No.2
F - A	2x4	DRY	No.2
D - C	2x4	DRY	No.2
F - D	2x4	DRY	No.2

ALL WEBS 2x3 DRY No.2
EXCEPT
DRY: SEASONED LUMBER.

PLATES (Table in inches)	JT TYPE	PLATES	W	LEN	Y	X
A	TMVW+p	MT20	4.0	4.0	1.00	2.00
B	TTW+p	MT20	4.0	8.0	Edge	
C	TMVW+p	MT20	4.0	4.0	1.00	2.00
D	BMV1+p	MT20	3.0	4.0		
E	BMVWW-I	MT20	4.0	9.0		
F	BMV1+p	MT20	3.0	4.0		

Edge - INDICATES REFERENCE CORNER OF PLATE TOUCHES EDGE OF CHORD.

DIMENSIONS, SUPPORTS AND LOADINGS SPECIFIED BY FABRICATOR TO BE VERIFIED BY BUILDING DESIGNER

JT	FACTORED GROSS REACTION		MAXIMUM FACTORED GROSS REACTION		INPUT BRG	REQRD BRG
	VERT	HORZ	DOWN	HORZ		
F	423	0	423	0	0	0
D	423	0	423	0	0	0

A SUITABLE HANGER/MECHANICAL CONNECTION IS REQUIRED AT JOINT F, D. MINIMUM BEARING LENGTH AT JOINT F = 1-8, JOINT D = 1-8.

UNFACTORED REACTIONS

JT	1ST CASE COMBINED	MAX/MIN. COMPONENT REACTIONS					
		SNOW	LIVE	PERM. LIVE	WIND	DEAD	SOIL
F	299	196 / 0	0 / 0	0 / 0	0 / 0	103 / 0	0 / 0
D	299	196 / 0	0 / 0	0 / 0	0 / 0	103 / 0	0 / 0

BRACING

TOP CHORD TO BE SHEATHED OR MAX. PURLIN SPACING = 6.25 FT.
MAX. UNBRACED BOTTOM CHORD LENGTH = 10.00 FT OR RIGID CEILING DIRECTLY APPLIED.

ALL PITCH BREAKS AND PERIMETER CORNER JOINTS MUST BE LATERALLY RESTRAINED.

LOADING

TOTAL LOAD CASES: (4)

CHORDS					WEBB				
MEMB.	MAX. FACTORED FORCE (LBS)	FACTORED VERT. LOAD (PLF)	MAX. FACTORED VERT. LOAD (LBS)	MAX. UNBRACED LENGTH (FT)	MEMB.	MAX. FACTORED FORCE (LBS)	MAX. FACTORED VERT. LOAD (LBS)	MAX. FACTORED VERT. LOAD (LBS)	
FR-TO		FROM	TO		FR-TO				
A-B	-214 / 0	-91.8	-91.8	0.17 (1)	E-B	-78 / 37	0.03 (1)		
B-C	-214 / 0	-91.8	-91.8	0.17 (1)	A-E	0 / 184	0.04 (1)		
F-A	-395 / 0	0.0	0.0	0.05 (1)	E-C	0 / 184	0.04 (1)		
D-C	-395 / 0	0.0	0.0	0.05 (1)					
F-E	0 / 0	-18.5	-18.5	0.08 (4)	10.00				
E-D	0 / 0	-18.5	-18.5	0.08 (4)	10.00				

TOTAL WEIGHT = 35 lb [M][F]

DESIGN CRITERIA

SPECIFIED LOADS:
TOP CH. LL = 25.6 PSF
DL = 8.0 PSF
BOT CH. LL = 8.0 PSF
DL = 7.4 PSF
TOTAL LOAD = 39.0 PSF

SPACING = 24.0 IN. O.C.

THIS TRUSS IS DESIGNED FOR RESIDENTIAL OR SMALL BUILDING REQUIREMENTS OF PART 9, NBCC 2010, NBCC 2015

THIS DESIGN COMPLIES WITH:
- PART 9 OF BCBC 2018, CBC 2012, ABC 2019
- PART 9 OF CBC 2012 (2019 AMENDMENT)
- CSA 088-09, CSA 088-14
- TPIC 2011, TPIC 2014

(55 % OF 31.3 P.S.F. G.S.L. PLUS 8.4 P.S.F. RAIN LOAD) EQUALS 25.6 P.S.F. SPECIFIED ROOF LIVE LOAD

ALLOWABLE DEFL.(LL) = $L/360$ (0.26")
CALCULATED VERT. DEFL.(LL) = $1/999$ (0.00")
ALLOWABLE DEFL.(TL) = $L/360$ (0.26")
CALCULATED VERT. DEFL.(TL) = $1/999$ (0.01")

CSI: TC=0.17/1.00 (B-C:1), BC=0.08/1.00 (D-E:4), WB=0.04/1.00 (A-E:1), SS=0.11/1.00 (B-C:1)

DOL LUMBER=1.00 NAIL=1.00 LS BEND=1.10
COMP=1.10 SHEAR=1.10 TENS=1.10

COMPANION LIVE LOAD FACTOR = 1.00


TRUSS PLATE MANUFACTURER IS NOT RESPONSIBLE FOR QUALITY CONTROL IN THE TRUSS MANUFACTURING PLANT.

NAIL VALUES
PLATE GRIP(DRY) SHEAR SECTION
(PS) (PL) (PL)
MAX MIN MAX MIN MAX MIN
MT20 618 354 1667 788 1987 1656

PLATE PLACEMENT TOL. = 0.250 inches


PLATE ROTATION TOL. = 5.0 Deg.

JSI GRIP= 0.31 (C) (INPUT = 0.90)
JSI METAL= 0.08 (C) (INPUT = 1.00)



Structural component only
DWG# T-2007075

JOB NAME	TRUSS NAME	QUANTITY	PLY	JOB DESC.	DRWG NO.
408150	T12S	2	1	GREEN PARK HOMES	
Tamarack Roof Truss, Burlington					
Version 8.310 S Oq 29 2019 Mitek Industries, Inc. Sat Apr 25 11:03:02 2020 Page 1					
ID:4NxGft_xHSHnsgnSWZu6izNuP6-ZL5CEldA? 7IKP?3keWNg3GbiUw7geceqedZOzbNCnN					
Scale = 1/31.6					



LUMBER			
N. L. G. A. RULES	SIZE	LUMBER	DESCR.
CHORDS			
A - C	2x4	DRY	No.2
C - E	2x4	DRY	No.2
L - A	2x4	DRY	No.2
F - E	2x4	DRY	No.2
L - K	2x4	DRY	No.2
K - B	2x4	DRY	No.2
J - H	2x4	DRY	No.2
G - D	2x4	DRY	No.2
G - F	2x4	DRY	No.2
ALL WEBS	2x3	DRY	No.2
EXCEPT			

DRY: SEASONED LUMBER.

PLATES (table is in inches)

JT TYPE	PLATES	W	LEN	Y	X
A, B, D, E					
A	TMVW+p	MT20	4.0	4.0	1.00 2.00
C	TTW+p	MT20	4.0	8.0	Edge
F	BMVW1-i	MT20	4.0	4.0	
G	BMV+p	MT20	3.0	4.0	
H	BMVWW-j	MT20	5.0	8.0	3.50 5.50
I	BMVWW-i	MT20	4.0	9.0	
J	BMVWW-i	MT20	5.0	8.0	3.50 5.50
K	BMV+p	MT20	3.0	4.0	
L	BMVW1-i	MT20	4.0	4.0	

Edge - INDICATES REFERENCE CORNER OF PLATE TOUCHES EDGE OF CHORD.

DIMENSIONS, SUPPORTS AND LOADINGS SPECIFIED BY FABRICATOR TO BE VERIFIED BY BUILDING DESIGNER

BEARINGS

	FACTORED	MAXIMUM FACTORED	INPUT	REQD
	GROSS REACTION	GROSS REACTION	BRG	BRG
JT	VERT	DOWN	IN-SX	IN-SX
L	423	0	0	MECHANICAL
F	423	0	0	MECHANICAL

A SUITABLE HANGER/MECHANICAL CONNECTION IS REQUIRED AT JOINT L, F. MINIMUM BEARING LENGTH AT JOINT L = 1-8, JOINT F = 1-8.

UNFACTORED REACTIONS

JT	1ST CASE	MAX/MIN. COMPONENT REACTIONS					
	COMBINED	SNOW	LIVE	PERM.LIVE	WIND	DEAD	SOIL
L	299	196 / 0	0 / 0	0 / 0	0 / 0	103 / 0	0 / 0
F	299	196 / 0	0 / 0	0 / 0	0 / 0	103 / 0	0 / 0

BRACING

TOP CHORD TO BE SHEATHED OR MAX. PURLIN SPACING = 6.25 FT.
MAX. UNBRACED BOTTOM CHORD LENGTH = 7.81 FT OR RIGID CEILING DIRECTLY APPLIED.

ALL PITCH BREAKS AND PERIMETER CORNER JOINTS MUST BE Laterally RESTRAINED.

LOADING

TOTAL LOAD CASES: (4)

CHORDS				WEBS			
MEMB.	MAX. FACTORED FORCE (LBS)	VERT. LOAD (PLF)	MAX. CSI (LC)	MEMB.	MAX. FACTORED FORCE (LBS)	MAX. CSI (LC)	
FR-TO				FR-TO			
A-B	-282 / 0	-91.8	-91.8 0.06 (1)	I-C	0 / 125	0.03 (1)	
B-C	-274 / 0	-91.8	-91.8 0.07 (1)	I-D	-57 / 0	0.01 (1)	
C-D	-274 / 0	-91.8	-91.8 0.07 (1)	B-I	-57 / 0	0.01 (1)	
D-E	-282 / 0	-91.8	-91.8 0.06 (1)	L-J	-13 / 0	0.00 (1)	
L-A	-404 / 0	0.0	0.0 0.05 (1)	A-J	0 / 317	0.07 (1)	
F-E	-404 / 0	0.0	0.0 0.05 (1)	H-F	-13 / 0	0.00 (1)	
				H-E	0 / 317	0.07 (1)	
L-K	0 / 9	-18.5	-18.5 0.01 (4)				
K-J	0 / 11	0.0	0.0 0.01 (1)				
J-B	-182 / 0	0.0	0.0 0.01 (1)				
J-I	0 / 247	-18.5	-18.5 0.08 (1)				
I-H	0 / 247	-18.5	-18.5 0.08 (1)				
G-H	0 / 11	0.0	0.0 0.01 (1)				
H-D	-182 / 0	0.0	0.0 0.01 (1)				
G-F	0 / 9	-18.5	-18.5 0.01 (4)				

TOTAL WEIGHT = 2 X 43 = 85 lb

DESIGN CRITERIA

SPECIFIED LOADS:

TOP CH. LL	=	25.6	PSF
DL	=	6.0	PSF
BOT CH. LL	=	0.0	PSF
DL	=	7.4	PSF
TOTAL LOAD	=	39.0	PSF

SPACING = 24.0 IN. OC

THIS TRUSS IS DESIGNED FOR RESIDENTIAL OR SMALL BUILDING REQUIREMENTS OF PART 9, NBC 2010, NBC 2015

THIS DESIGN COMPLIES WITH:
- PART 9 OF BCBC 2018, CBC 2012, ABC 2019
- PART 9 OF CBC 2012 (2019 AMENDMENT)
- CSA 088-09, CSA 088-14
- TPIC 2011, TPIC 2014

(55 % OF 31.3 P.S.F. G.S.L. PLUS 8.4 P.S.F. RAIN LOAD) EQUALS 25.6 P.S.F. SPECIFIED ROOF LIVE LOAD

ALLOWABLE DEFL. (LL) = $L/360$ (0.28")
CALCULATED VERT. DEFL. (LL) = $L/889$ (0.00")
ALLOWABLE DEFL. (TL) = $L/360$ (0.28")
CALCULATED VERT. DEFL. (TL) = $L/889$ (0.01")

CSI: TC=0.07/1.00 (C-D:1), BC=0.06/1.00 (H-I:1), WB=0.07/1.00 (A-J:1), SS=0.09/1.00 (C-D:1)

DOL LUMBER=1.00 NAIL=1.00 LS BEND=1.10 COMP=1.10 SHEAR=1.10 TENS=1.10

COMPANION LIVE LOAD FACTOR = 1.00

AUTOSOLVEHEELS OFF

TRUSS PLATE MANUFACTURER IS NOT RESPONSIBLE FOR QUALITY CONTROL IN THE TRUSS MANUFACTURING PLANT.


NAIL VALUES

PLATE	GRIP(DRY)	SHEAR	SECTION
(PSI)	(PLI)	(PLI)	(PLI)
MAX MIN	MAX MIN	MAX MIN	MAX MIN
MT20	618 354	1667 768	1987 1656

PLATE PLACEMENT TOL. = 0.250 inches


PLATE ROTATION TOL. = 5.0 Deg.

JSI GRIP = 0.30 (E) (INPUT = 0.90)
JSI METAL = 0.08 (E) (INPUT = 1.00)



Structural component only
DWG# T-2007076

JOB NAME 408150	TRUSS NAME T15	QUANTITY 1	PLY 1	JOB DESC. GREEN PARK HOMES	DRWG NO.
Tamarack Roof Truss, Burlington				Version 8.310 S Oct 29 2019 Mitek Industries, Inc. Sat Apr 25 11:03:03 2020 Page 1	
ID:17vF?aG0E03cRUJ6X1SrkziWYK-1XibSheCmIFWYZaFILtcD0pbHuOpP_en2IN7x1zNCnM				10/10/10 10:11:00	
Scale = 1:16.8					



LUMBER			
N. L. G. A. RULES	SIZE	LUMBER	DESCR.
A - C	2x4	DRY	No.2
F - A	2x4	DRY	No.2
D - C	2x4	DRY	No.2
F - D	2x4	DRY	No.2
ALL WEBS EXCEPT	2x3	DRY	No.2

DRY: SEASONED LUMBER.

PLATES (table in inches)				
JT	TYPE	PLATES	W	LEN Y X
A	TMVW-1	MT20	4.0	9.0 Edge
B	TMVW-1	MT20	2.0	4.0
C	TMVW-1	MT20	4.0	9.0 Edge
D	BMVW-1	MT20	3.0	4.0
E	BMVW-1	MT20	8.0	9.0
F	BMVW-1	MT20	3.0	4.0

Edge - INDICATES REFERENCE CORNER OF PLATE TOUCHES EDGE OF CHORD.

DIMENSIONS, SUPPORTS AND LOADINGS SPECIFIED BY FABRICATOR TO BE VERIFIED BY BUILDING DESIGNER

FACTORED		MAXIMUM FACTORED		INPUT		REQD	
JT	VERT	GROSS REACTION	DOWN	BRG	IN-SX	BRG	IN-SX
F	978	0	978	0	5-8	5-8	5-8
D	1015	0	1015	0	5-8	5-8	5-8

UNFACTORED REACTIONS

JT	1ST CASE	MAX. MIN. COMPONENT REACTIONS	SNOW	LIVE	PERM. LIVE	WIND	DEAD	SOIL
F	690	453 / 0	0 / 0	0 / 0	0 / 0	0 / 0	237 / 0	0 / 0
D	716	478 / 0	0 / 0	0 / 0	0 / 0	0 / 0	237 / 0	0 / 0

BEARING MATERIAL TO BE SPF NO.2 OR BETTER AT JOINT(S) F, D

BRACING

TOP CHORD TO BE SHEATHED OR MAX. PURLIN SPACING = 3.55 FT.
MAX. UNBRACED BOTTOM CHORD LENGTH = 10.00 FT. OR RIGID CEILING DIRECTLY APPLIED.

ALL PITCH BREAKS AND PERIMETER CORNER JOINTS MUST BE Laterally RESTRAINED.

LOADING

TOTAL LOAD CASES: (4)

CHORDS		FACTORED		WEBS		FACTORED	
MEMB.	FORCE (LBS)	VERT. LOAD (LBS)	MAX. (LBS)	MEMB.	FORCE (LBS)	MAX. (LBS)	MAX. (LBS)
FR-TO		FROM	TO	FR-TO			
A-G	-2081 / 0	-91.8	-91.8	0.78 (1)	3.55	A-E	0 / 2157
G-H	-2081 / 0	-91.8	-91.8	0.78 (1)	3.55	E-B	-878 / 0
H-I	-2081 / 0	-91.8	-91.8	0.78 (1)	3.55	E-C	0 / 2157
I-B	-2081 / 0	-91.8	-91.8	0.78 (1)	3.55		
B-J	-2081 / 0	-91.8	-91.8	0.78 (1)	3.55		
J-K	-2081 / 0	-91.8	-91.8	0.78 (1)	3.55		
K-C	-2081 / 0	-91.8	-91.8	0.78 (1)	3.55		
F-A	-869 / 0	0.0	0.0	0.10 (1)	7.81		
D-C	-938 / 0	0.0	0.0	0.11 (1)	7.81		
F-L	0 / 0	-18.5	-18.5	0.22 (4)	10.00		
L-M	0 / 0	-18.5	-18.5	0.22 (4)	10.00		
M-N	0 / 0	-18.5	-18.5	0.22 (4)	10.00		
N-E	0 / 0	-18.5	-18.5	0.22 (4)	10.00		
E-O	0 / 0	-18.5	-18.5	0.22 (4)	10.00		
O-P	0 / 0	-18.5	-18.5	0.22 (4)	10.00		
P-D	0 / 0	-18.5	-18.5	0.22 (4)	10.00		

FACTORED CONCENTRATED LOADS (LBS)

JT	LOC.	LC1	MAX.	FACE	DIR.	TYPE	HEEL	CONN.
C	10-11-0	-123	-123	---	BACK	VERT	TOTAL	C1
G	9-14	-80	-80	---	BACK	VERT	TOTAL	C1
H	2-9-14	-82	-82	---	BACK	VERT	TOTAL	C1
I	4-9-14	-82	-82	---	BACK	VERT	TOTAL	C1
J	6-9-14	-82	-82	---	BACK	VERT	TOTAL	C1
K	8-9-14	-82	-82	---	BACK	VERT	TOTAL	C1
L	9-14	-51	-51	---	BACK	VERT	TOTAL	C1
M	2-9-14	-49	-49	---	BACK	VERT	TOTAL	C1
N	4-9-14	-49	-49	---	BACK	VERT	TOTAL	C1
O	6-9-14	-49	-49	---	BACK	VERT	TOTAL	C1
P	8-9-14	-49	-49	---	BACK	VERT	TOTAL	C1

CONNECTION REQUIREMENTS

1) C1: A SUITABLE HANGER/MECHANICAL CONNECTION IS REQUIRED.

DESIGN CRITERIA

SPECIFIED LOADS:
TOP CH. LL = 25.6 PSF
DL = 8.0 PSF
BOT CH. LL = 0.0 PSF
DL = 7.4 PSF
TOTAL LOAD = 39.0 PSF

SPACING = 24.0 IN. C/C

LOADING IN FLAT SECTION BASED ON A SLOPE OF 8.00/12

THIS TRUSS IS DESIGNED FOR RESIDENTIAL OR SMALL BUILDING REQUIREMENTS OF PART 9, NBC 2010, NBC 2015

THIS DESIGN COMPLIES WITH:
- PART 9 OF CBC 2018, CBC 2012, ABC 2019
- PART 9 OF CBC 2012 (2019 AMENDMENT)
- CSA 086-09, CSA 086-14
- TPIC 2011, TPIC 2014

(55% OF 31.3 P.S.F. G.S.L. PLUS 8.4 P.S.F. RAIN LOAD) EQUALS 25.6 P.S.F. SPECIFIED ROOF LIVE LOAD

ALLOWABLE DEFL. (LL) = L/360 (0.36")
CALCULATED VERT. DEFL. (LL) = L/999 (0.03")
ALLOWABLE DEFL. (TL) = L/360 (0.36")
CALCULATED VERT. DEFL. (TL) = L/817 (0.16")

CSI: TC=0.79/1.00 (A-B:1), BC=0.22/1.00 (E-F:4), WB=0.53/1.00 (A-E:1), SS=0.39/1.00 (A-B:1)

DOL LUMBER=1.00 NAIL=1.00 LS BEND=1.00 COMP=1.00 SHEAR=1.00 TENS=1.00

COMPANION LIVE LOAD FACTOR = 1.00

AUTOSOLVE HEELS OFF

TRUSS PLATE MANUFACTURER IS NOT RESPONSIBLE FOR QUALITY CONTROL IN THE TRUSS MANUFACTURING PLANT.

NAIL VALUES

PLATE	GRIP (DRY)	SHEAR (PSI)	SECTION (PLI)
MT20	618	354	1687
	788	1987	1858


PLATE PLACEMENT TOL. = 0.250 inches

PLATE ROTATION TOL. = 5.0 Deg.

JSI GRIP = 0.89 (A) (INPUT = 0.90)
JSI METAL = 0.40 (E) (INPUT = 1.00)



Structural component only
DWG# T-2007077



LUMBER	N. L. G. A. RULES	CHORDS	SIZE	DRY	LUMBER	DESCR.
A - C	2x8	DRY	No.2	SPF		
C - F	2x8	DRY	No.2	SPF		
F - H	2x8	DRY	No.2	SPF		
H - J	2x8	DRY	No.2	SPF		
S - B	2x8	DRY	No.2	SPF		
K - I	2x8	DRY	No.2	SPF		
S - P	2x8	DRY	1650F 1.5E	SPF		
P - N	2x8	DRY	1650F 1.5E	SPF		
N - K	2x8	DRY	1650F 1.5E	SPF		

ALL WEBS EXCEPT 2x3 DRY No.2 SPF

DRY: SEASONED LUMBER.

DESIGN CONSISTS OF 2 TRUSSES BUILT SEPARATELY THEN FASTENED TOGETHER AS FOLLOWS:

CHORDS #ROWS	SURFACE SPACING (IN)	LOAD (PLF)
TOP CHORDS: (0.122"x3") SPIRAL NAILS		
A - G 2	12	SIDE(122.0)
C - F 2	12	SIDE(81.0)
F - H 2	12	SIDE(81.0)
H - J 2	12	SIDE(122.0)
S - B 2	12	TOP
K - I 2	12	TOP
BOTTOM CHORDS: (0.122"x3") SPIRAL NAILS		
S - P 2	12	SIDE(0.0)
P - N 2	12	SIDE(0.0)
N - K 2	12	SIDE(183.1)
WEBS: (0.122"x3") SPIRAL NAILS		
2x3 1	6	

NAILS TO BE DRIVEN FROM ONE SIDE ONLY.

GIRDER NAILING ASSUMES NAILED HANGERS ARE FASTENED WITH MIN. 3-0 INCH NAILS.

TOP - COMPONENTS ARE LOADED FROM THE TOP AND MUST BE PLACED ON TOP EDGE OF ALL FLIES FOR THE LOAD TO BE TRANSFERRED TO EACH PLY.

DIMENSIONS, SUPPORTS AND LOADINGS SPECIFIED BY FABRICATOR TO BE VERIFIED BY BUILDING DESIGNER

BEARINGS	FACTORED GROSS REACTION	MAXIMUM FACTORED GROSS REACTION	INPUT BRG	REQD BRG
JT	VERT	DOWN	UPLIFT	IN-SX
S	3330	0	0	5-8
K	3379	0	0	5-8

UNFACTORED REACTIONS	1ST CASE	MAX./MIN. COMPONENT REACTIONS
JT	COMBINED	SNOW LIVE PERM LIVE WIND DEAD SOIL
S	2354	1553 / 0 0 / 0 0 / 0 801 / 0 0 / 0
K	2388	1572 / 0 0 / 0 0 / 0 816 / 0 0 / 0

BEARING MATERIAL TO BE SPF NO.2 OR BETTER AT JOINT(S) S, K

BRACING

TOP CHORD TO BE SHEATHED OR MAX. PURLIN SPACING = 3.98 FT. MAX. UNBRACED BOTTOM CHORD LENGTH = 10.00 FT OR RIGID CEILING DIRECTLY APPLIED.

ALL PITCH BREAKS AND PERIMETER CORNER JOINTS MUST BE Laterally RESTRAINED.

LOADING

TOTAL LOAD CASES: (4)

CHORDS	MAX. FACTORED MEMB. FORCE (LBS)	FACTORED VERT. LOAD LC1 (PLF)	MAX. CSI (LC)	MAX. UNBRAC LENGTH	WEBS	MAX. FACTORED MEMB. FORCE (LBS)	MAX. CSI (LC)
FR-TO		FROM TO			FR-TO		
A-B	0 / 42	-91.8	-91.8	0.04 (1)	10.00	R-C	-662 / 0
B-C	-3359 / 0	-91.8	-91.8	0.05 (1)	8.03	C-Q	0 / 4522
C-T	-8806 / 0	-91.8	-91.8	0.38 (1)	4.32	Q-D	-1799 / 0
T-U	-8806 / 0	-91.8	-91.8	0.38 (1)	4.32	D-O	0 / 1375
U-V	-8806 / 0	-91.8	-91.8	0.38 (1)	4.32	O-E	-990 / 0
V-W	-6608 / 0	-91.8	-91.8	0.38 (1)	4.32	O-G	0 / 1388
W-D	-8806 / 0	-91.8	-91.8	0.38 (1)	4.32	M-G	-1786 / 0
D-X	-7835 / 0	-91.8	-91.8	0.42 (1)	3.98	M-H	0 / 4493
X-Y	-7835 / 0	-91.8	-91.8	0.42 (1)	3.98	L-H	-673 / 0
Y-Z	-7835 / 0	-91.8	-91.8	0.42 (1)	3.98	B-R	0 / 2729
Z-E	-7835 / 0	-91.8	-91.8	0.42 (1)	3.98	L-I	0 / 2764
E-AA	-7835 / 0	-91.8	-91.8	0.42 (1)	3.98		
AA-F	-7835 / 0	-91.8	-91.8	0.42 (1)	3.98		
F-AB	-7835 / 0	-91.8	-91.8	0.42 (1)	3.98		
AB-AC	-7835 / 0	-91.8	-91.8	0.42 (1)	3.98		
AC-AD	-7835 / 0	-91.8	-91.8	0.42 (1)	3.98		
AD-G	-7835 / 0	-91.8	-91.8	0.42 (1)	3.98		
G-AE	-6612 / 0	-91.8	-91.8	0.38 (1)	4.32		
AE-AF	-6612 / 0	-91.8	-91.8	0.38 (1)	4.32		
AF-AG	-6612 / 0	-91.8	-91.8	0.38 (1)	4.32		
AG-H	-6612 / 0	-91.8	-91.8	0.38 (1)	4.32		
H-I	-3401 / 0	-91.8	-91.8	0.05 (1)	6.00		
I-J	0 / 42	-91.8	-91.8	0.04 (1)	10.00		
S-B	-3366 / 0	0.0	0.0	0.12 (1)	7.58		
K-I	-3406 / 0	0.0	0.0	0.12 (1)	7.58		

S-AH	0 / 0	-18.5	-18.5	0.06 (4)	10.00
AH-R	0 / 0	-18.5	-18.5	0.06 (4)	10.00
R-AI	0 / 2546	-18.5	-18.5	0.16 (1)	10.00
AI-AJ	0 / 2546	-18.5	-18.5	0.16 (1)	10.00
AJ-AK	0 / 2546	-18.5	-18.5	0.16 (1)	10.00
AK-AL	0 / 2546	-18.5	-18.5	0.16 (1)	10.00
AL-O	0 / 2546	-18.5	-18.5	0.16 (1)	10.00
O-P	0 / 8806	-18.5	-18.5	0.32 (1)	10.00
P-AM	0 / 8806	-18.5	-18.5	0.32 (1)	10.00
AM-AN	0 / 8806	-18.5	-18.5	0.32 (1)	10.00
AN-O	0 / 8806	-18.5	-18.5	0.32 (1)	10.00

TOTAL WEIGHT = 2 X 183 = 366 lb

DESIGN CRITERIA

*** SPECIAL LOADS ANALYSIS ***
GEOMETRY AND/OR BASIC LOADS CHANGED BY USER.
LOADS WERE DERIVED FROM USER INPUT
NO FURTHER MODIFICATIONS WERE MADE

SPECIFIED LOADS:

TOP CH. LL = 25.6 PSF
DL = 8.0 PSF
BOT CH. LL = 0.0 PSF
DL = 7.4 PSF
TOTAL LOAD = 39.0 PSF

SPACING = 24.0 IN. C/C

LOADING IN FLAT SECTION BASED ON A SLOPE OF 6.0/12

*** NON STANDARD GIRDER ***
ADDTL USER-DEFINED LOADS APPLIED TO ALL LOAD CASES.

THIS TRUSS IS DESIGNED FOR RESIDENTIAL OR SMALL BUILDING REQUIREMENTS OF PART 9, NBC 2010, NBC 2015

THIS DESIGN COMPLIES WITH:

- PART 9 OF BCBC 2018, CBC 2019
- PART 9 OF CBC 2012 (2019 AMENDMENT)
- CSA 088-09, CSA 088-14
- TPIC 2011, TPIC 2014

(5% OF 31.3 P.S.F. G.S.L. PLUS 8.4 P.S.F. RAIN LOAD) EQUALS 26.8 P.S.F. SPECIFIED ROOF LIVE LOAD

ALLOWABLE DEFL. (LL) = L/360 (1.17')
CALCULATED VERT. DEFL. (LL) = U/999 (0.20')
ALLOWABLE DEFL. (TL) = L/360 (1.17')
CALCULATED VERT. DEFL. (TL) = U/999 (0.38')

CSI: TC=0.42/1.00 (D-E:1), BC=0.32/1.00 (O-Q:1), WB=0.58/1.00 (C-Q:1), SS=0.22/1.00 (C-D:1)

DOL LUMBER=1.00 NAIL=1.00 LS BEND=1.00 COMP=1.00 SHEAR=1.00 TENS=1.00

COMPANION LIVE LOAD FACTOR = 1.00

AUTOSOLVE HEELS OFF


TRUSS PLATE MANUFACTURER IS NOT RESPONSIBLE FOR QUALITY CONTROL IN THE TRUSS MANUFACTURING PLANT.

NAIL VALUES

PLATE GRIP (DRY)	SHEAR	SECTION
(PSI)	(PLI)	(PLI)
MAX MIN	MAX MIN	MAX MIN
MT20	618 354	1687 788 1987 1656

PLATE PLACEMENT TOL. = 0.250 inches

PLATE ROTATION TOL. = 5.0 Deg.




C	TTWW+m	MT20	8.0	9.0	3.50	1.75
D	TTWW-t	MT20	5.0	6.0	2.50	2.50
E	TTWW+w	MT20	3.0	6.0		
F	TS-t	MT20	5.0	6.0		
G	TTWW-t	MT20	5.0	6.0	2.50	2.50
H	TTWW+m	MT20	8.0	9.0	3.50	1.75
I	TTWW+p	MT20	7.0	8.0		
K	BMV1+p	MT20	3.0	6.0		
L	BMWW-t	MT20	5.0	6.0	2.50	2.25
M	BMWW-l	MT20	5.0	8.0	2.50	3.00
N	BS-t	MT20	8.0	9.0		
O	BMWWW-t	MT20	5.0	12.0		
P	BS-t	MT20	8.0	9.0		
Q	BMWW-t	MT20	5.0	8.0	2.50	3.00
R	BMWW-t	MT20	5.0	6.0	2.50	2.25
S	BMV1+p	MT20	3.0	6.0		


CHORDS				WEBS			
MEMB.	MAX. FACTORED FORCE (LBS)	FACTORED VERT. LOAD (PLF)	LC1 MAX. CSI (LC)	MAX. UNBRAC LENGTH	MEMB.	MAX. FACTORED FORCE (LBS)	MAX. CSI (LC)
FR-TO		FROM TO			FR-TO		
M-AS	0/2579	-18.5	-18.5 0.18 (1)	10.00			
AS-AT	0/2579	-18.5	-18.5 0.18 (1)	10.00			
AT-AU	0/2579	-18.5	-18.5 0.18 (1)	10.00			
AU-L	0/2579	-18.5	-18.5 0.18 (1)	10.00			
L-AV	0/0	-18.5	-18.5 0.08 (4)	10.00			
AV-K	0/0	-18.5	-18.5 0.08 (4)	10.00			

FACTORED CONCENTRATED LOADS (LBS)									
JT	LOC.	LC1	MAX.	MAX+	FACE	DIR.	TYPE	HEEL	CONN.
C	2-11-8	-38	-42	---	FRONT	VERT	DEAD	---	C1
C	2-11-8	-191	-191	---	FRONT	VERT	SNOW	---	C1
H	32-2-8	-38	-42	---	FRONT	VERT	DEAD	---	C1
H	32-2-8	-116	-116	---	FRONT	VERT	TOTAL	---	C1
H	32-2-8	-191	-191	---	FRONT	VERT	SNOW	---	C1
L	31-11-4	-28	-28	---	FRONT	VERT	TOTAL	---	C1
P	11-11-4	-26	-28	---	FRONT	VERT	TOTAL	---	C1
T	3-11-4	-111	-111	---	FRONT	VERT	TOTAL	---	C1
U	5-11-4	-110	-110	---	FRONT	VERT	TOTAL	---	C1
V	7-11-4	-110	-110	---	FRONT	VERT	TOTAL	---	C1
W	9-11-4	-110	-110	---	FRONT	VERT	TOTAL	---	C1
X	11-11-4	-110	-110	---	FRONT	VERT	TOTAL	---	C1
Y	13-11-4	-110	-110	---	FRONT	VERT	TOTAL	---	C1
Z	15-11-4	-110	-110	---	FRONT	VERT	TOTAL	---	C1
AA	17-11-4	-110	-110	---	FRONT	VERT	TOTAL	---	C1
AB	19-11-4	-110	-110	---	FRONT	VERT	TOTAL	---	C1
AC	21-11-4	-110	-110	---	FRONT	VERT	TOTAL	---	C1
AD	23-11-4	-110	-110	---	FRONT	VERT	TOTAL	---	C1
AE	25-11-4	-110	-110	---	FRONT	VERT	TOTAL	---	C1
AF	27-11-4	-110	-110	---	FRONT	VERT	TOTAL	---	C1
AG	29-11-4	-110	-110	---	FRONT	VERT	TOTAL	---	C1
AH	1-11-4	-26	-26	---	FRONT	VERT	TOTAL	---	C1
AI	3-11-4	-28	-28	---	FRONT	VERT	TOTAL	---	C1
AJ	5-11-4	-28	-28	---	FRONT	VERT	TOTAL	---	C1
AK	7-11-4	-26	-26	---	FRONT	VERT	TOTAL	---	C1
AL	9-11-4	-26	-26	---	FRONT	VERT	TOTAL	---	C1
AM	13-11-4	-26	-26	---	FRONT	VERT	TOTAL	---	C1
AN	15-11-4	-26	-26	---	FRONT	VERT	TOTAL	---	C1
AO	17-11-4	-26	-26	---	FRONT	VERT	TOTAL	---	C1
AP	19-11-4	-26	-26	---	FRONT	VERT	TOTAL	---	C1
AQ	21-11-4	-26	-26	---	FRONT	VERT	TOTAL	---	C1
AR	23-11-4	-26	-26	---	FRONT	VERT	TOTAL	---	C1
AS	25-11-4	-28	-26	---	FRONT	VERT	TOTAL	---	C1
AT	27-11-4	-28	-26	---	FRONT	VERT	TOTAL	---	C1
AU	29-11-4	-26	-26	---	FRONT	VERT	TOTAL	---	C1
AV	33-11-4	-26	-26	---	FRONT	VERT	TOTAL	---	C1

CONNECTION REQUIREMENTS

1) C1: A SUITABLE HANGER/MECHANICAL CONNECTION IS REQUIRED.





TOTAL WEIGHT = 2 X 183 = 365 lb

LUMBER				
N. L. G. A. RULES				
CHORDS	SIZE	LUMBER	DESCR.	
A - C	2x6	DRY	No.2	SPF
C - F	2x6	DRY	No.2	SPF
F - H	2x6	DRY	No.2	SPF
H - J	2x6	DRY	No.2	SPF
S - B	2x6	DRY	No.2	SPF
K - I	2x6	DRY	No.2	SPF
S - P	2x6	DRY	1650F 1.5E	SPF
P - N	2x6	DRY	1650F 1.5E	SPF
N - K	2x6	DRY	1650F 1.5E	SPF
ALL WEBS EXCEPT	2x3	DRY	No.2	SPF

DRY: SEASONED LUMBER.

DESIGN CONSISTS OF 2 TRUSSES BUILT SEPARATELY THEN FASTENED TOGETHER AS FOLLOWS:

CHORDS #ROWS	SURFACE SPACING (IN)	LOAD (PLF)
TOP CHORDS: (0.122"x3") SPIRAL NAILS		
A-C	2	12
C-F	2	12
F-H	2	12
H-J	2	12
S-B	2	12
K-I	2	12
BOTTOM CHORDS: (0.122"x3") SPIRAL NAILS		
S-P	2	12
P-N	2	12
N-K	2	12
WEBS: (0.122"x3") SPIRAL NAILS		
2x3	1	6

NAILS TO BE DRIVEN FROM ONE SIDE ONLY.

GIRDER NAILING ASSUMES NAILED HANGERS ARE FASTENED WITH MIN. 3-0 INCH NAILS.

TOP - COMPONENTS ARE LOADED FROM THE TOP AND MUST BE PLACED ON TOP EDGE OF ALL PLIES FOR THE LOAD TO BE TRANSFERRED TO EACH PLY.

DIMENSIONS, SUPPORTS AND LOADINGS SPECIFIED BY FABRICATOR TO BE VERIFIED BY BUILDING DESIGNER

FACTORED		MAXIMUM FACTORED		INPUT		RECORD	
GROSS REACTION	GROSS REACTION	DOWN	UP	BRG	BRG	IN-SX	IN-SX
JT	VERT	HORZ	HORZ	UPLIFT	IN-SX	IN-SX	IN-SX
S	4991	0	4991	0	5-8	5-8	5-8
K	3694	0	3694	0	5-8	5-8	5-8
UNFACTORED REACTIONS							
1ST LCASE	MAX / MIN COMPONENT REACTIONS						
JT	COMBINED	SNOW	LIVE	PERM. LIVE	WIND	DEAD	SOIL
S	3528	2323 / 0	0 / 0	0 / 0	0 / 0	1208 / 0	0 / 0
K	2608	1737 / 0	0 / 0	0 / 0	0 / 0	871 / 0	0 / 0

BEARING MATERIAL TO BE SPF NO.2 OR BETTER AT JOINT(S) S, K

BRACING

TOP CHORD TO BE SHEATHED OR MAX. PURLIN SPACING = 3.20 FT. MAX. UNBRACED BOTTOM CHORD LENGTH = 10.00 FT. OR RIGID CEILING DIRECTLY APPLIED.

ALL PITCH BREAKS AND PERIMETER CORNER JOINTS MUST BE Laterally RESTRAINED.

LOADING

TOTAL LOAD CASES: (4)

CHORDS		WEBS	
MEMB.	MAX. FACTORED FORCE (LBS)	MEMB.	MAX. FACTORED FORCE (LBS)
FR-TO		FR-TO	
A-B	0 / 42	R-C	-253 / 44
B-C	-5342 / 0	C-Q	0 / 8589
C-D	-9871 / 0	D-O	-1958 / 0
O-T	-12379 / 0	O-D	0 / 2694
T-E	-12379 / 0	O-E	-782 / 0
E-F	-12379 / 0	O-G	0 / 4229
F-G	-12379 / 0	M-G	-2619 / 0
G-H	-5599 / 0	M-H	0 / 8416
H-I	-3750 / 0	L-H	-864 / 0
I-J	0 / 42	B-R	0 / 4341
S-B	-5197 / 0	L-I	0 / 3047
K-I	-3727 / 0		
S-U	0 / 0		
U-R	0 / 0		
R-V	0 / 4073		
V-Q	0 / 4073		
Q-P	0 / 9971		
P-W	0 / 9971		
W-X	0 / 9971		
X-O	0 / 9971		
O-Y	0 / 8600		
Y-N	0 / 8600		
N-M	0 / 8600		
M-L	0 / 2039		
L-K	0 / 0		

FACTORED CONCENTRATED LOADS (LBS)		FACE		DIR.		TYPE		HEEL		CONN.	
LOC.	LC1	MAX.	MAX.	FRONT	VERT	DEAD	DEAD	---	---	C1	C1
C	2-11-8	-38	-42	---	---	TOTAL	TOTAL	---	---	C1	C1
C	2-11-8	-117	-117	---	---	TOTAL	TOTAL	---	---	C1	C1
C	2-11-8	-191	-191	---	---	TOTAL	TOTAL	---	---	C1	C1
E	17-4-12	-110	-110	---	---	TOTAL	TOTAL	---	---	C1	C1
O	17-4-12	-28	-28	---	---	TOTAL	TOTAL	---	---	C1	C1
O	2-11-8	-28	-28	---	---	TOTAL	TOTAL	---	---	C1	C1

DESIGN CRITERIA

*** SPECIAL LOADS ANALYSIS ***
GEOMETRY AND/OR BASIC LOADS CHANGED BY USER.
LOADS WERE DERIVED FROM USER INPUT
NO FURTHER MODIFICATIONS WERE MADE

SPECIFIED LOADS:

TOP CH. LL = 25.6 PSF

DL = 6.0 PSF

BOT CH. LL = 0.0 PSF

DL = 7.4 PSF

TOTAL LOAD = 39.0 PSF

SPACING = 24.0 IN. C/C

LOADING IN FLAT SECTION BASED ON A SLOPE OF 6.00/12

*** NON STANDARD GIRDER ***
ADDTL USER-DEFINED LOADS APPLIED TO ALL LOAD CASES.

THIS TRUSS IS DESIGNED FOR RESIDENTIAL OR SMALL BUILDING REQUIREMENTS OF PART 9, NBCC 2010, NBCC 2015

THIS DESIGN COMPLIES WITH:
- PART 9 OF NBCC 2018, OBC 2012, ABC 2019
- PART 9 OF OBC 2012 (2019 AMENDMENT)
- CSA 088-09, CSA 088-14
- TPIC 2011, TPIC 2014

(65 % OF 31.3 P.S.F. G.S.L. PLUS 8.4 P.S.F. RAIN LOAD) EQUALS 25.8 P.S.F. SPECIFIED ROOF LIVE LOAD

ALLOWABLE DEFL.(LL) = L/360 (1.17")

CALCULATED VERT. DEFL.(LL) = L/999 (0.33")

ALLOWABLE DEFL.(TL) = L/360 (1.17")

CALCULATED VERT. DEFL.(TL) = L/685 (0.62")

CSI: TC=0.52/1.00 (D-E-1), BC=0.73/1.00 (O-Q-1), WB=0.81/1.00 (C-Q-1), SS=0.57/1.00 (M-O-1)

DOL LUMBER-1.00 NAIL-1.00 LS BEND-1.00 COMP-1.00 SHEAR-1.00 TENS-1.00


COMPANION LIVE LOAD FACTOR = 1.00

AUTOSOLVE HEELS OFF

TRUSS PLATE MANUFACTURER IS NOT RESPONSIBLE FOR QUALITY CONTROL IN THE TRUSS MANUFACTURING PLANT.

NAIL VALUES
PLATE GRIP(DRY) SHEAR SECTION
(PSI) (PLI) (PLI)
MAX MIN MAX MIN MAX MIN
MT20 818 354 1887 788 1987 1658

PLATE PLACEMENT TOL = 0.250 inches



JOB NAME 408151	TRUSS NAME T20Z	QUANTITY 1	PLY 2	JOB DESC. GREEN PARK HOMES	DRWG NO.
Tamarack Roof Truss, Burlington					


Version 8.310 S Oct 29 2019 MTEK Industries, Inc. Sat Apr 25 11:19:45 2020 Page 2
ID:12dflqC44wS E2tzoPs atzIRw-JCOUmko9VL9YAq n0aqaJuZo4EB5KGT8585vzNCX

PLATES (table is in inches)

JT	TYPE	PLATES	W	LEN	Y	X
B	TMVW+p	MT20	7.0	8.0		
C	TTWW+m	MT20	8.0	9.0	3.50	1.75
D	TMVW-t	MT20	5.0	8.0	2.50	2.50
E	TMVW+w	MT20	3.0	6.0		
F	TS-t	MT20	5.0	6.0		
G	TMVW-l	MT20	5.0	8.0	2.50	2.50
H	TTWW+m	MT20	8.0	9.0	3.50	1.75
I	TMVW+p	MT20	7.0	8.0		
K	BMV1+p	MT20	3.0	6.0		
L	BMVW-t	MT20	5.0	8.0	2.50	2.25
M	BMVW-l	MT20	5.0	8.0	2.50	2.75
N	BS-t	MT20	6.0	9.0		
O	BMVWW-t	MT20	5.0	12.0	2.75	6.00
P	BS-l	MT20	8.0	9.0		
Q	BMVW-t	MT20	5.0	8.0	2.50	2.75
R	BMVW-l	MT20	5.0	8.0	2.50	2.25
S	BMV1+p	MT20	3.0	6.0		

CONNECTION REQUIREMENTS


- 1) C1: A SUITABLE HANGER/MECHANICAL CONNECTION IS REQUIRED.



Structural component only
DWG# T-2007082 7/2

JOB NAME	TRUSS NAME	QUANTITY	PLY	JOB DESC.	DRWG NO.
408151	T21	2	1	GREEN PARK HOMES	
Tamarack Roof Truss, Burlington				TRUSS DESC.	

Version 8.310 S Oct 29 2019 Mitek Industries, Inc. Sat Apr 25 11:19:46 2020 Page 1
 ID:h2dlqC44ws_E2tqPs_atzlfRw-AVlmymMZTdnI0YUXpMnr1ECRIweZChrridOzNCXh
 1.3.3 0.0 4.1.14 4.1.14 5.5.3 9.7.1 5.5.3 14.11.0 5.5.3 20.3.0 5.5.3 25.6.15 5.5.3 31.0.2 4.1.14 35.2.0 1.3.3
 Scale = 1:57.3



LUMBER
 N. L. G. A. RULES
 CHORDS SIZE LUMBER DESCR.
 A - C 2x4 DRY No.2 SPF
 C - F 2x4 DRY No.2 SPF
 F - I 2x4 DRY No.2 SPF
 I - K 2x4 DRY No.2 SPF
 U - B 2x4 DRY No.2 SPF
 L - J 2x4 DRY No.2 SPF
 U - R 2x4 DRY No.2 SPF
 R - O 2x4 DRY No.2 SPF
 O - L 2x4 DRY No.2 SPF
 ALL WEBS 2x3 DRY No.2 SPF
 EXCEPT
 DRY: SEASONED LUMBER.

CHORDS	SIZE	LUMBER	DESCR.
A - C	2x4	DRY No.2	SPF
C - F	2x4	DRY No.2	SPF
F - I	2x4	DRY No.2	SPF
I - K	2x4	DRY No.2	SPF
U - B	2x4	DRY No.2	SPF
L - J	2x4	DRY No.2	SPF
U - R	2x4	DRY No.2	SPF
R - O	2x4	DRY No.2	SPF
O - L	2x4	DRY No.2	SPF
ALL WEBS	2x3	DRY No.2	SPF
EXCEPT			

DESIGN CRITERIA
 SPECIFIED LOADS:
 TOP CH. LL = 25.8 PSF
 DL = 6.0 PSF
 BOT CH. LL = 0.0 PSF
 DL = 7.4 PSF
 TOTAL LOAD = 39.0 PSF
 SPACING = 24.0 IN. OC
 LOADING IN FLAT SECTION BASED ON A SLOPE OF 6.00/12
 THIS TRUSS IS DESIGNED FOR RESIDENTIAL OR SMALL BUILDING REQUIREMENTS OF PART 9, NBC 2010, NBC 2015
 THIS DESIGN COMPLIES WITH:
 - PART 9 OF CBC 2018, CBC 2012, ABC 2019
 - PART 9 OF CBC 2012 (2019 AMENDMENT)
 - CSA 086-09, CSA 086-14
 - TPIC 2011, TPIC 2014
 (55% OF 31.3 P.S.F. G.S.L. PLUS 8.4 P.S.F. RAIN LOAD) EQUALS 25.6 P.S.F. SPECIFIED ROOF LIVE LOAD

BRACING
 TOP CHORD TO BE SHEATHED OR MAX. PURLIN SPACING = 3.20 FT.
 MAX. UNBRACED BOTTOM CHORD LENGTH = 10.00 FT OR RIGID CEILING DIRECTLY APPLIED.
 ALL PITCH BREAKS AND PERIMETER CORNER JOINTS MUST BE LATERALLY RESTRAINED.

LOADING
 TOTAL LOAD CASES: (4)
 CHORDS
 MAX. FACTORED FORCE (LBS) VERT. LOAD LC1 MAX. MAX. MEMB. MAX. FACTORED FORCE (LBS) WEBS
 FR-TO (PLF) FROM TO CSI (LC) UNBRACED LENGTH FR-TO (LBS) CSI (LC)

MEMB.	FORCE (LBS)	VERT. LOAD LC1	MAX.	MAX.	MEMB.	FORCE (LBS)	MAX.
FR-TO	(PLF)	FROM	TO	CSI (LC)	UNBRACED	LENGTH	FR-TO
A-B	0/41	-91.8	-91.8	0.13 (1)	10.00	T-C	-358/0
B-C	-1980/0	-91.8	-91.8	0.38 (1)	4.48	C-S	0/1838
C-D	-2871/0	-91.8	-91.8	0.57 (1)	3.59	S-D	-1118/0
D-E	-3506/0	-91.8	-91.8	0.85 (1)	3.21	D-Q	0/856
E-F	-3506/0	-91.8	-91.8	0.83 (1)	3.36	Q-E	-475/0
F-G	-3506/0	-91.8	-91.8	0.83 (1)	3.36	E-P	-2/0
G-H	-3506/0	-91.8	-91.8	0.66 (1)	3.20	P-G	-474/0
H-I	-2871/0	-91.8	-91.8	0.57 (1)	3.59	I-H	0/853
I-J	-1980/0	-91.8	-91.8	0.38 (1)	4.48	N-H	-1117/0
J-K	0/41	-91.8	-91.8	0.13 (1)	10.00	N-I	0/1837
U-B	-2037/0	0.0	0.0	0.22 (1)	5.92	M-I	-358/0
L-J	-2037/0	0.0	0.0	0.22 (1)	5.92	B-T	0/1571
U-T	0/0	-18.5	-18.5	0.10 (4)	10.00	M-J	0/1571
T-S	0/1494	-18.5	-18.5	0.30 (1)	10.00		
S-R	0/2871	-18.5	-18.5	0.51 (1)	10.00		
R-Q	0/2871	-18.5	-18.5	0.51 (1)	10.00		
Q-P	0/3506	-18.5	-18.5	0.62 (1)	10.00		
P-O	0/2872	-18.5	-18.5	0.51 (1)	10.00		
O-N	0/2872	-18.5	-18.5	0.51 (1)	10.00		
N-M	0/1494	-18.5	-18.5	0.30 (1)	10.00		
M-L	0/0	-18.5	-18.5	0.10 (4)	10.00		

Edge - INDICATES REFERENCE CORNER OF PLATE TOUCHES EDGE OF CHORD.
 ALLOWABLE DEFL. (LL) = L/360 (1.17")
 CALCULATED VERT. DEFL. (LL) = L/999 (0.20")
 ALLOWABLE DEFL. (TL) = L/360 (1.17")
 CALCULATED VERT. DEFL. (TL) = L/999 (0.39")
 CSI: TC=0.66/1.00 (G-H:1), BC=0.62/1.00 (P-Q:1), WB=0.43/1.00 (D-S:1), SS=0.22/1.00 (H-I:1)
 DOL LUMBER=1.00 NAIL=1.00 LS BEND=1.10
 COMP=1.10 SHEAR=1.10 TENS=1.10
 COMPANION LIVE LOAD FACTOR = 1.00
 TRUSS PLATE MANUFACTURER IS NOT RESPONSIBLE FOR QUALITY CONTROL IN THE TRUSS MANUFACTURING PLANT.

PLATE PLACEMENT TOL. = 0.250 inches
PLATE ROTATION TOL. = 5.0 Deg.
 JSI GRIP = 0.90 (S) (INPUT = 0.90)
 JSI METAL = 0.90 (O) (INPUT = 1.00)


STRUCTURAL COMPONENT ONLY
DWG# T-2007083

LICENSED PROFESSIONAL ENGINEER
H. J. G. ALVES
100009024
PROVINCE OF ONTARIO

JOB NAME	TRUSS NAME	QUANTITY	PLY	JOB DESC.	TRUSS DESC.	DRWG NO.
408151	T22	2	1	GREEN PARK HOMES		

Tamarack Roof Truss, Burlington

Version 8.310 S Oct 29 2019 MTek Industries, Inc. Sat Apr 25 11:19:47 2020 Page 1
ID:h2dlfgC44wS_E2tqPs_atzllRw-ehJ897n_Kml3PrKD6C22y7OAzopWl3vZwVaFArZNCXq



LUMBER			
N. L. G. A. RULES	SIZE	LUMBER	DESCR.
CHORDS			
A - C	2x4	DRY	No.2
C - F	2x4	DRY	No.2
F - H	2x4	DRY	No.2
H - J	2x4	DRY	No.2
S - B	2x4	DRY	No.2
K - I	2x4	DRY	No.2
S - P	2x4	DRY	No.2
P - N	2x4	DRY	No.2
N - K	2x4	DRY	No.2
ALL WEBS	2x3	DRY	No.2
EXCEPT			SPF
DRY: SEASONED LUMBER.			

PLATES (Tables in inches)					
JT	TYPE	PLATES	W	LEN	Y X
B	TMVW-p	MT20	5.0	6.0	1.50 3.00
C	TTWW+m	MT20	6.0	9.0	Edge 1.75
D	TMVW-t	MT20	4.0	4.0	
E	TMVW-w	MT20	2.0	4.0	
F	TS-t	MT20	3.0	6.0	
G	TMVW-t	MT20	4.0	4.0	
H	TTWW+m	MT20	6.0	9.0	Edge 1.75
I	TMVW-p	MT20	5.0	6.0	1.50 3.00
K	BMV1-p	MT20	3.0	4.0	
L, M, Q, R					
L	BMVW-t	MT20	5.0	6.0	
N	BS-t	MT20	3.0	6.0	
O	BMVWW-t	MT20	4.0	9.0	
P	BS-t	MT20	3.0	6.0	
S	BMV1-p	MT20	3.0	4.0	

Edge - INDICATES REFERENCE CORNER OF PLATE TOUCHES EDGE OF CHORD.

DIMENSIONS, SUPPORTS AND LOADINGS SPECIFIED BY FABRICATOR TO BE VERIFIED BY BUILDING DESIGNER

BEARINGS							
	FACTORED	GROSS REACTION		MAXIMUM FACTORED	INPUT	REQD	
		DOWN	UP	BRG	IN-SX	BRG	
JT	VERT	HORZ					
S	2066	0	2066	0	5-8	5-8	
K	2066	0	2066	0	5-8	5-8	
UNFACTORED REACTIONS							
	1ST CASE	MAX/MIN COMPONENT REACTIONS					
	COMBINED	SNOW	LIVE	PERM.LIVE	WIND	DEAD	SOIL
S	1458	971/0	0/0	0/0	0/0	488/0	0/0
K	1458	971/0	0/0	0/0	0/0	488/0	0/0

BEARING MATERIAL TO BE SPF NO.2 OR BETTER AT JOINT(S) S, K

BRACING

TOP CHORD TO BE SHEATHED OR MAX. PURLIN SPACING = 3.28 FT.
MAX. UNBRACED BOTTOM CHORD LENGTH = 10.00 FT. OR RIGID CEILING DIRECTLY APPLIED.

ALL PITCH BREAKS AND PERIMETER CORNER JOINTS MUST BE Laterally RESTRAINED.

LOADING

TOTAL LOAD CASES: (4)

CHORDS				WEBS			
MEMB.	FORCE (LBS)	FACTORED VERT. LOAD (PLF)	MAX. UNBRACED LENGTH (FT)	MEMB.	FORCE (LBS)	FACTORED VERT. LOAD (PLF)	MAX. UNBRACED LENGTH (FT)
FR-TO		FROM TO		FR-TO		FROM TO	
A-B	0/41	-91.8 -91.8 0.13 (1)	10.00	R-C	-246/7	0.14 (1)	
B-C	-2004/0	-91.8 -91.8 0.64 (1)	4.11	C-O	0/1538	0.35 (1)	
C-D	-2853/0	-91.8 -91.8 0.74 (1)	3.50	Q-D	-943/0	0.55 (1)	
D-E	-2978/0	-91.8 -91.8 0.78 (1)	3.28	D-O	0/450	0.10 (1)	
E-F	-2978/0	-91.8 -91.8 0.78 (1)	3.28	O-E	-513/0	0.30 (1)	
F-G	-2978/0	-91.8 -91.8 0.78 (1)	3.28	O-G	0/450	0.10 (1)	
G-H	-2853/0	-91.8 -91.8 0.74 (1)	3.50	M-G	-943/0	0.55 (1)	
H-I	-2004/0	-91.8 -91.8 0.64 (1)	4.11	M-H	0/1538	0.35 (1)	
I-J	0/41	-91.8 -91.8 0.13 (1)	10.00	L-H	-246/7	0.14 (1)	
S-B	-2026/0	0.0 0.0 0.22 (1)	5.94	B-R	0/1580	0.38 (1)	
K-I	-2026/0	0.0 0.0 0.22 (1)	5.94	L-I	0/1580	0.38 (1)	
S-R	0/0	-18.5 -18.5 0.14 (4)	10.00				
R-Q	0/1532	-18.5 -18.5 0.33 (1)	10.00				
Q-P	0/2853	-18.5 -18.5 0.49 (1)	10.00				
P-O	0/2853	-18.5 -18.5 0.49 (1)	10.00				
O-N	0/2853	-18.5 -18.5 0.49 (1)	10.00				
N-M	0/2853	-18.5 -18.5 0.49 (1)	10.00				
M-L	0/1532	-18.5 -18.5 0.33 (1)	10.00				
L-K	0/0	-18.5 -18.5 0.14 (4)	10.00				

TOTAL WEIGHT = 2 X 148 = 296 lb

DESIGN CRITERIA

SPECIFIED LOADS:

TOP CH. LL = 25.6 PSF
DL = 6.0 PSF
BOT CH. LL = 0.0 PSF
DL = 7.4 PSF
TOTAL LOAD = 39.0 PSF

SPACING = 24.0 IN. C/C

LOADING IN FLAT SECTION BASED ON A SLOPE OF 8.00/12

THIS TRUSS IS DESIGNED FOR RESIDENTIAL OR SMALL BUILDING REQUIREMENTS OF PART 9, NBC 2010, NBC 2015

THIS DESIGN COMPLIES WITH:

- PART 9 OF NBC 2018, OBC 2012, ABC 2019
- PART 9 OF OBC 2012 (2019 AMENDMENT)
- CSA 088-09, CSA 088-14
- TPIC 2011, TPIC 2014

(55 % OF 31.3 P.S.F. G.S.L. PLUS 8.4 P.S.F. RAIN LOAD) EQUALS 25.6 P.S.F. SPECIFIED ROOF LIVE LOAD

ALLOWABLE DEFL.(LL) = L/360 (1.17")
CALCULATED VERT. DEFL.(LL) = L/999 (0.16")
ALLOWABLE DEFL.(TL) = L/360 (1.17")
CALCULATED VERT. DEFL.(TL) = L/999 (0.29")

CSI: TC=0.78/1.00 (D-E:1), BC=0.49/1.00 (O-Q:1)
WB=0.55/1.00 (G-M:1), SS=0.27/1.00 (C-D:1)

DDL LUMBER=1.00 NAIL=1.00 LS BEND=1.10
COMP=1.10 SHEAR=1.10 TENS=1.10

COMPANION LIVE LOAD FACTOR = 1.00

TRUSS PLATE MANUFACTURER IS NOT RESPONSIBLE FOR QUALITY CONTROL IN THE TRUSS MANUFACTURING PLANT.

NAIL VALUES

PLATE GRIP(DRY) SHEAR SECTION (PSI) (PLI) (PLI)
MAX MIN MAX MIN MAX MIN
MT20 -818 354 1887 788 1987 1856

PLATE PLACEMENT TOL. = 0.250 inches

PLATE ROTATION TOL. = 5.0 Deg.

JSI GRIP = 0.90 (B) (INPUT = 0.90)
JSI METAL = 0.85 (N) (INPUT = 1.00)




Structural component only
DWG# T-2007084

JOB NAME: 408151 TRUSS NAME: T23 QUANTITY: 2 PLY: 1 JOB DESC: GREEN PARK HOMES TRUSS DESC: T23 DRWG NO. 1

Version 8.310 S Oct 29 2019 Mtek Industries, Inc. Sat Apr 25 11:19:48 2020 Page 1

ID:h2dflgC44wS E2tzqPs_atzIRw-6uWKNKoc54w07vPgVZHSCwP40ArOPU99KoiH2NCXf

Scale = 1:57.5



CHORDS	SIZE	DRY	NO.2	DESCR.
A - D	2x4	DRY	No.2	SPF
D - G	2x4	DRY	No.2	SPF
G - I	2x4	DRY	No.2	SPF
I - L	2x4	DRY	No.2	SPF
L - B	2x4	DRY	No.2	SPF
M - K	2x4	DRY	No.2	SPF
U - R	2x4	DRY	No.2	SPF
R - P	2x4	DRY	No.2	SPF
P - M	2x4	DRY	No.2	SPF
ALL WEBS	2x3	DRY	No.2	SPF
EXCEPT				

DRY: SEASONED LUMBER.

PLATES (table is in inches)	W	LEN	Y	X
JT TMV+p	MT20	3.0	4.0	
C TMW+W	MT20	5.0	8.0	2.50 2.25
D TMW+W	MT20	5.0	8.0	2.00 1.75
E TMW+W	MT20	4.0	4.0	
F TMW+W	MT20	4.0	4.0	
G TS-1	MT20	3.0	8.0	
H TMW+W	MT20	4.0	4.0	
I TMW+W	MT20	5.0	8.0	2.00 1.75
J TMW+W	MT20	5.0	8.0	2.50 2.25
K TMV+p	MT20	3.0	4.0	
M BMVW-1	MT20	5.0	8.0	2.25 3.00
N BMW+W	MT20	4.0	4.0	
O BMW+W	MT20	4.0	4.0	
P BS-1	MT20	3.0	8.0	
Q BMW+W	MT20	4.0	4.0	
R BS-1	MT20	3.0	8.0	
S BMW+W	MT20	4.0	4.0	
T BMW+W	MT20	4.0	4.0	
U BMVW-1	MT20	5.0	8.0	2.25 3.00

DIMENSIONS, SUPPORTS AND LOADINGS SPECIFIED BY FABRICATOR TO BE VERIFIED BY BUILDING DESIGNER

BEARINGS	FACTORED GROSS REACTION	MAXIMUM FACTORED GROSS REACTION	INPUT BRG	RECORD BRG
JT	VERT	DOWN	IN-SX	IN-SX
U	2068	0	5-8	5-8
M	2068	0	5-8	5-8

UNFACTORED REACTIONS

1ST LCASE	SNOW	LIVE	PERM.LIVE	WIND	DEAD	SOIL
JT	1458	971/0	0/0	0/0	488/0	0/0
U	1458	971/0	0/0	0/0	488/0	0/0
M	1458	971/0	0/0	0/0	488/0	0/0

BEARING MATERIAL TO BE SPF NO.2 OR BETTER AT JOINT(S) U, M

BRACING

TOP CHORD TO BE SHEATHED OR MAX. PURLIN SPACING = 3.77 FT.
MAX. UNBRACED BOTTOM CHORD LENGTH = 10.00 FT. OR RIGID CEILING DIRECTLY APPLIED.

ALL PITCH BREAKS AND PERIMETER CORNER JOINTS MUST BE LATERALLY RESTRAINED.

LOADING

TOTAL LOAD CASES: (4)

CHORDS	MEMB.	MAX. FACTORED FORCE (LBS)	FACTORED VERT. LOAD (PLF)	MAX. FACTORED HORIZ. LOAD (PLF)	MAX. FACTORED UNBRACED LENGTH (FT)	WEBS	MEMB.	MAX. FACTORED FORCE (LBS)	MAX. FACTORED HORIZ. LOAD (PLF)
FR-TO						FR-TO			
A-B	0/141	-91.8	-91.8	0.13 (1)	10.00	C-T	0/156	0.04 (1)	
B-C	0/119	-91.8	-91.8	0.14 (1)	10.00	T-D	0/78	0.03 (4)	
C-D	-2023/0	-91.8	-91.8	0.20 (1)	4.59	D-S	0/1220	0.27 (1)	
D-E	-2308/0	-91.8	-91.8	0.55 (1)	3.94	S-E	-850/0	0.74 (1)	
E-F	-2534/0	-91.8	-91.8	0.57 (1)	3.77	E-Q	0/361	0.08 (1)	
F-G	-2534/0	-91.8	-91.8	0.57 (1)	3.77	Q-F	-461/0	0.40 (1)	
G-H	-2534/0	-91.8	-91.8	0.57 (1)	3.77	H-Q	0/361	0.08 (1)	
H-I	-2308/0	-91.8	-91.8	0.55 (1)	3.94	O-H	-850/0	0.74 (1)	
I-J	-2023/0	-91.8	-91.8	0.20 (1)	4.59	C-I	0/1220	0.27 (1)	
J-K	0/119	-91.8	-91.8	0.14 (1)	10.00	N-I	0/78	0.03 (4)	
K-L	0/141	-91.8	-91.8	0.13 (1)	10.00	N-J	0/156	0.04 (1)	
U-B	-246/0	0.0	0.0	0.03 (1)	7.81	U-C	-2277/0	0.98 (1)	
M-K	-246/0	0.0	0.0	0.03 (1)	7.81	J-M	-2277/0	0.98 (1)	
U-T	0/1433	-18.5	-18.5	0.33 (1)	10.00				
T-S	0/1535	-18.5	-18.5	0.35 (1)	10.00				
S-R	0/2308	-18.5	-18.5	0.42 (1)	10.00				
R-Q	0/2308	-18.5	-18.5	0.42 (1)	10.00				
Q-P	0/2308	-18.5	-18.5	0.42 (1)	10.00				
P-O	0/2308	-18.5	-18.5	0.42 (1)	10.00				
O-N	0/1535	-18.5	-18.5	0.35 (1)	10.00				
N-M	0/1433	-18.5	-18.5	0.33 (1)	10.00				

TOTAL WEIGHT = 2 X 162 = 323 lb

DESIGN CRITERIA

SPECIFIED LOADS:

TOP CH.	LL	=	25.6	PSF
	DL	=	6.0	PSF
BOT CH.	LL	=	0.0	PSF
	DL	=	7.4	PSF
TOTAL LOAD		=	39.0	PSF

SPACING = 24.0 IN. OC

LOADING IN FLAT SECTION BASED ON A SLOPE OF 6.00/12

THIS TRUSS IS DESIGNED FOR RESIDENTIAL OR SMALL BUILDING REQUIREMENTS OF PART 9, NBC 2010, NBC 2015

THIS DESIGN COMPLIES WITH:

- PART 9 OF NBC 2010, CBC 2012, ABC 2019
- PART 9 OF CBC 2012 (2019 AMENDMENT)
- CSA 086-09, CSA 088-14
- TPIC 2011, TPIC 2014

(55% OF 31.3 P.S.F. G.S.L. PLUS 8.4 P.S.F. RAIN LOAD) EQUALS 25.6 P.S.F. SPECIFIED ROOF LIVE LOAD

ALLOWABLE DEFL.(LL) = L/360 (1.17")

CALCULATED VERT. DEFL.(LL) = L/999 (0.13")

ALLOWABLE DEFL.(TL) = L/360 (1.17")

CALCULATED VERT. DEFL.(TL) = L/999 (0.23")

CSI: TO=0.57/1.00 (E-F:1), BC=0.42/1.00 (O-Q:1),

WB=0.98/1.00 (J-M:1), SSI=0.24/1.00 (D-E:1)

DOL LUMBER=1.00 NAIL=1.00 LB BEND=1.10

COMP=1.10 SHEAR=1.10 TENS=1.10

COMPANION LIVE LOAD FACTOR = 1.00

TRUSS PLATE MANUFACTURER IS NOT RESPONSIBLE FOR QUALITY CONTROL IN THE TRUSS MANUFACTURING PLANT.


NAIL VALUES

PLATE GRIP(DRY)	SHEAR	SECTION
(PSI)	(PLI)	(PLI)
MAX MIN	MAX MIN	MAX MIN
MT20	618 354	1867 768 1987 1656

PLATE PLACEMENT TOL. = 0.250 inches

PLATE ROTATION TOL. = 5.0 Deg.

JSI GRIP = 0.89 (I) (INPUT = 0.90)
JSI METAL = 0.72 (P) (INPUT = 1.00)




Structural component only
DWG# T-2007085

Version 8.310 S Oct 29 2019 MITek Industries, Inc. Sat Apr 25 11:19:49 2020 Page 1

ID:h2dlfGc44wS E2zqPs_atzllRw-s4RuappEsO?ne9Ubd4W QTXEWP57ssnQ3MEjzNCXc

138 0.0 311.13 311.13 395 792 470 144.2 309.14 352.0 274.14 194 31.23 311.13 138

Scale = 1:57.5



TOTAL WEIGHT = 2 X 183 = 326 lb

LUMBER			
N. L. G. A. RULES	CHORDS	SIZE	LUMBER
A - D	2x4	DRY	No.2
D - F	2x4	DRY	No.2
F - H	2x4	DRY	No.2
H - K	2x4	DRY	No.2
S - B	2x4	DRY	No.2
L - J	2x4	DRY	No.2
S - Q	2x4	DRY	No.2
Q - N	2x4	DRY	No.2
N - L	2x4	DRY	No.2
ALL WEBS EXCEPT	2x3	DRY	No.2
S - C	2x4	DRY	No.2
I - L	2x4	DRY	No.2

DRY: SEASONED LUMBER.

PLATES (table in inches)

JT	TYPE	PLATES	W	LEN	Y	X
B	TMV-p	MT20	3.0	4.0		
C	TMW-W1	MT20	5.0	8.0	2.50	2.50
D	TTWW-m	MT20	5.0	8.0	2.00	1.75
E	TMW-W1	MT20	4.0	4.0		
F	TS-I	MT20	3.0	8.0		
G	TMW-W1	MT20	2.0	4.0		
H	TTWW-m	MT20	5.0	8.0	2.00	1.75
I	TMW-W1	MT20	5.0	8.0	2.50	2.50
J	TMV-p	MT20	3.0	4.0		
L	BMW-W1-I	MT20	5.0	8.0		
M	BMW-W1	MT20	4.0	4.0		
N	BS-I	MT20	3.0	8.0		
O	BMW-W1	MT20	4.0	4.0		
P	BMW-W1	MT20	4.0	8.0		
Q	BS-I	MT20	3.0	8.0		
R	BMW-W1	MT20	4.0	4.0		
S	BMW-W1	MT20	5.0	8.0		

SUMMATIONS, SUPPORTS AND LOADINGS SPECIFIED BY FABRICATOR TO BE VERIFIED BY BUILDING DESIGNER

JT	FACTORED GROSS REACTION		MAXIMUM FACTORED GROSS REACTION		INPUT BRG	RECORD BRG
	VERT	HORZ	DOWN	HORZ	IN-SX	IN-SX
S	2068	0	2068	0	5-8	5-8
L	2068	0	2068	0	5-8	5-8

UNFACTORED REACTIONS

JT	1ST CASE COMBINED		MAX./MIN. COMPONENT REACTIONS		WIND	DEAD	SOIL
	SNOW	LIVE	PERM. LIVE	WIND			
S	1458	971 / 0	0 / 0	0 / 0	0 / 0	488 / 0	0 / 0
L	1458	971 / 0	0 / 0	0 / 0	0 / 0	488 / 0	0 / 0

BEARING MATERIAL TO BE SPF NO.2 OR BETTER AT JOINT(S) S, L

BRACING

TOP CHORD TO BE SHEATHED OR MAX. PURLIN SPACING = 3.81 FT.
MAX. UNBRACED BOTTOM CHORD LENGTH = 10.00 FT. OR RIGID CEILING DIRECTLY APPLIED.

ALL PITCH BREAKS AND PERIMETER CORNER JOINTS MUST BE Laterally RESTRAINED.

1 LATERAL BRACE(S) AT 1/2 LENGTH OF E-O.

END VERTICAL(S) MUST BE SHEATHED OR HAVE BRACES AS INDICATED IN THE MAX. UNBRACED LENGTH COLUMN OF THE TABLE BELOW

LOADING

TOTAL LOAD CASES: (4)

MEMB.	MAX. FACTORED FORCE (LBS)	CHORDS			WEBS			
		FACTORED VERT. LOAD (PLF)	MAX. LG1 (LC)	MAX. UNBRACED LENGTH	MEMB. MAX. FACTORED FORCE (LBS)	MAX. CSI (LC)		
FR-TO		FROM	TO	FR-TO				
A-B	0 / 41	-91.8	-91.8	0.13 (1)	10.00	C-R	0 / 64	0.02 (4)
B-C	0 / 26	-91.8	-91.8	0.21 (1)	10.00	R-D	0 / 128	0.04 (4)
C-D	-2006 / 0	-91.8	-91.8	0.29 (1)	4.50	D-P	0 / 998	0.22 (1)
D-E	-2169 / 0	-91.8	-91.8	0.73 (1)	3.81	P-E	-650 / 0	0.82 (1)
E-F	-2162 / 0	-91.8	-91.8	0.73 (1)	3.81	E-O	-2 / 0	0.00 (1)
F-G	-2162 / 0	-91.8	-91.8	0.73 (1)	3.81	O-G	-649 / 0	0.82 (1)
G-H	-2162 / 0	-91.8	-91.8	0.73 (1)	3.82	H-H	0 / 996	0.22 (1)
H-I	-2006 / 0	-91.8	-91.8	0.29 (1)	4.50	M-H	0 / 126	0.04 (4)
I-J	0 / 28	-91.8	-91.8	0.21 (1)	10.00	M-I	0 / 84	0.02 (4)
J-K	0 / 41	-91.8	-91.8	0.13 (1)	10.00	S-C	-2291 / 0	0.97 (1)
K-B	-284 / 0	0.0	0.0	0.03 (1)	7.81	I-L	-2291 / 0	0.97 (1)
L-J	-284 / 0	0.0	0.0	0.03 (1)	7.81			

S-R	0 / 1487	-18.5	-18.5	0.38 (1)	10.00
R-Q	0 / 1519	-18.5	-18.5	0.39 (1)	10.00
Q-P	0 / 1510	-18.5	-18.5	0.39 (1)	10.00
P-O	0 / 2183	-18.5	-18.5	0.42 (1)	10.00
O-N	0 / 1519	-18.5	-18.5	0.39 (1)	10.00
N-M	0 / 1519	-18.5	-18.5	0.39 (1)	10.00
M-L	0 / 1487	-18.5	-18.5	0.38 (1)	10.00

DESIGN CRITERIA

SPECIFIED LOADS:

TOP CH. LL	=	25.6	PSF
DL	=	6.0	PSF
BOT CH. LL	=	0.0	PSF
DL	=	7.4	PSF
TOTAL LOAD	=	39.0	PSF

SPACING = 24.0 IN. C/C

LOADING IN FLAT SECTION BASED ON A SLOPE OF 6.00/12

THIS TRUSS IS DESIGNED FOR RESIDENTIAL OR SMALL BUILDING REQUIREMENTS OF PART 9, NBC 2010, NBC 2015

THIS DESIGN COMPLIES WITH:

- PART 9 OF CBC 2018, CBC 2012, ABC 2019
- PART 9 OF CBC 2012 (2019 AMENDMENT)
- CSA 086-03, CSA 086-14
- TPIC 2011, TPIC 2014

(55 % OF 31.3 P.S.F. G.S.L. PLUS 8.4 P.S.F. RAIN LOAD) EQUALS 25.6 P.S.F. SPECIFIED ROOF LIVE LOAD

ALLOWABLE DEFL.(LL) = L/360 (1.17")
CALCULATED VERT. DEFL.(LL) = L/989 (0.10")
ALLOWABLE DEFL.(TL) = L/360 (1.17")
CALCULATED VERT. DEFL.(TL) = L/989 (0.21")

CSK: TC=0.73/1.00 (D-E:1), BC=0.42/1.00 (O-P:1), WB=0.97/1.00 (L-I:1), SS=0.28/1.00 (D-E:1)

DOL LUMBER=1.00 NAIL=1.00 LS BEND=1.10
COMP=1.10 SHEAR=1.10 TENS= 1.10

COMPANION LIVE LOAD FACTOR = 1.00

AUTOSOLVE HEELS OFF

TRUSS PLATE MANUFACTURER IS NOT RESPONSIBLE FOR QUALITY CONTROL IN THE TRUSS MANUFACTURING PLANT .

NAIL VALUES

PLATE	GRIP(DRY)	SHEAR (PSI)	SECTION (PLI)
MAX MIN	MAX MIN	MAX MIN	MAX MIN
MT20	618 354	1887 798	1987 1656


PLATE PLACEMENT TOL. = 0.250 inches

PLATE ROTATION TOL. = 5.0 Deg.

JSI GRIP= 0.87 (I) (INPUT = 0.90)
JSI METAL= 0.56 (I) (INPUT = 1.00)

Structural component only
DWG# T-2007086

JOB NAME	TRUSS NAME	QUANTITY	PLY	JOB DESC.	DRWG NO.
408151	T25	2	1	GREEN PARK HOMES	
Tamarack Roof Truss, Burlington					
Version 8.310 S Oct 29 2019 Mitek Industries, Inc. Sat Apr 25 11:19:50 2020 Page 1					
ID:h2dlgC44wS_E2tqPs_atzlfRw-2G7Ho0pedh7eGJ2nnKblXd0n8pl_sTb?cTpm9zNCXo					
35-20 38 5-8 1-3-8					
Scale = 1:57.3					




LUMBER				DESIGN CRITERIA			
N. L. G. A. RULES				TOTAL WEIGHT = 2 X 182 = 363 lb			
CHORDS				SPECIFIED LOADS:			
A - D	2x4	DRY	No.2	TOP CH. LL	=	25.6	PSF
D - F	2x4	DRY	No.2	DL	=	8.0	PSF
F - H	2x4	DRY	No.2	BOY CH. LL	=	0.0	PSF
H - K	2x4	DRY	No.2	DL	=	7.4	PSF
U - B	2x4	DRY	No.2	TOTAL LOAD	=	39.0	PSF
L - J	2x4	DRY	No.2	SPACING = 24.0 IN. OC			
U - R	2x4	DRY	No.2	LOADING IN FLAT SECTION BASED ON A SLOPE			
O - L	2x4	DRY	No.2	OF 8.00/12			
ALL WEBS	2x3	DRY	No.2	THIS TRUSS IS DESIGNED FOR RESIDENTIAL OR			
EXCEPT				SMALL BUILDING REQUIREMENTS OF PART 9,			
D - Q	2x4	DRY	No.2	NBC 2010, NBCC 2015			
E - P	2x4	DRY	No.2	THIS DESIGN COMPLIES WITH:			
P - H	2x4	DRY	No.2	- PART 9 OF NBC 2010, CBC 2012, ABC 2019			
DRY: SEASONED LUMBER.				- PART 9 OF CBC 2012 (2019 AMENDMENT)			
				- CSA 086-09, CSA 086-14			
				- TPIC 2011, TPIC 2014			
				(55% OF 31.3 P.S.F. G.S.L. PLUS 8.4 P.S.F. RAIN			
				LOAD) EQUALS 25.6 P.S.F. SPECIFIED ROOF			
				LIVE LOAD			
				ALLOWABLE DEFL.(LL) = L/360 (1.17)			
				CALCULATED VERT. DEFL.(LL) = L/999 (0.06")			
				ALLOWABLE DEFL.(TL) = L/360 (1.17)			
				CALCULATED VERT. DEFL.(TL) = L/999 (0.16")			
				CSI: TC=0.40/1.00 (D-E:1), BC=0.38/1.00 (P-Q:1),			
				WB=0.38/1.00 (B-T:1), SS=0.25/1.00 (D-E:1)			
				DOL LUMBER=1.00 NAIL=1.00 LS BEND=1.10			
				COMP=1.10 SHEAR=1.10 TENS=1.10			
				COMPANION LIVE LOAD FACTOR = 1.00			
				TRUSS PLATE MANUFACTURER IS NOT			
				RESPONSIBLE FOR QUALITY CONTROL IN THE			
				TRUSS MANUFACTURING PLANT.			
				NAIL VALUES			
				PLATE GRIP(DRY) SHEAR SECTION			
				(PSI) (PLI) (PLI)			
				MAX MIN MAX MIN MAX MIN			
				MT20 618 384 1667 788 1987 1656			
				PLATE PLACEMENT TOL. = 0.250 inches			
				PLATE ROTATION TOL. = 5.0 Deg.			
				JSI GRIP = 0.89 (B) (INPUT = 0.90)			
				JSI METAL = 0.50 (C) (INPUT = 1.00)			

PLATES (table in inches)				BEARINGS			
JT	TYPE	PLATES	W	LEN	Y	X	
B	TMWV-p	MT20	5.0	8.0	2.00	2.00	
C	TMWV-l	MT20	4.0	4.0	2.00	1.25	
D	TTWV-m	MT20	5.0	6.0	2.00	1.75	
E	TMWV-l	MT20	4.0	4.0			
F	TS-l	MT20	3.0	6.0			
G	TMWV-w	MT20	2.0	4.0			
H	TTWV-m	MT20	5.0	8.0	2.00	1.75	
I	TMWV-l	MT20	4.0	4.0	2.00	1.25	
J	TMWV-p	MT20	5.0	6.0	2.00	2.00	
L	BMV1-p	MT20	3.0	4.0			
M	BMWV-l	MT20	5.0	6.0			
N, Q, S							
N	BMWV-l	MT20	4.0	4.0			
O	BS-l	MT20	3.0	6.0			
P	BMWVW-l	MT20	4.0	4.0			
R	BS-l	MT20	3.0	6.0			
T	BMWV-l	MT20	5.0	6.0			
U	BMV1-p	MT20	3.0	4.0			
CHORDS				WEBS			
MAX. FACTORED FORCE (LBS)				MAX. FACTORED FORCE (LBS)			
VERT. LOAD LC1 MAX				MAX. FACTORED FORCE (LBS)			
FROM TO				FROM TO			
FR-TO				FR-TO			
A-B	0/41	-91.8	-91.8 0.13 (1)	10.00	T-C	-357/0	0.18 (1)
B-C	-1994/0	-91.8	-91.8 0.30 (1)	4.53	C-S	-121/0	0.10 (1)
C-D	-1957/0	-91.8	-91.8 0.29 (1)	4.57	S-D	0/188	0.05 (4)
D-E	-1823/0	-91.8	-91.8 0.40 (1)	4.44	D-Q	0/810	0.13 (1)
E-F	-1921/0	-91.8	-91.8 0.37 (1)	4.49	Q-E	-569/0	0.31 (1)
F-G	-1921/0	-91.8	-91.8 0.37 (1)	4.49	E-P	-3/0	0.00 (1)
G-H	-1921/0	-91.8	-91.8 0.40 (1)	4.45	P-G	-568/0	0.31 (1)
H-I	-1957/0	-91.8	-91.8 0.29 (1)	4.57	P-H	0/807	0.13 (1)
I-J	-1994/0	-91.8	-91.8 0.30 (1)	4.83	N-H	0/189	0.05 (4)
J-K	0/41	-91.8	-91.8 0.13 (1)	10.00	N-I	-121/0	0.10 (1)
U-B	-2028/0	0.0	0.0 0.22 (1)	5.94	M-I	-358/0	0.18 (1)
L-J	-2028/0	0.0	0.0 0.22 (1)	5.94	B-T	0/1617	0.38 (1)
U-T	0/0	-18.5	-18.5 0.08 (4)	10.00	M-J	0/1617	0.38 (1)
T-S	0/1555	-18.5	-18.5 0.30 (1)	10.00			
S-R	0/1477	-18.5	-18.5 0.30 (1)	10.00			
R-Q	0/1477	-18.5	-18.5 0.30 (1)	10.00			
Q-P	0/1823	-18.5	-18.5 0.38 (1)	10.00			
P-O	0/1478	-18.5	-18.5 0.30 (1)	10.00			
O-N	0/1478	-18.5	-18.5 0.30 (1)	10.00			
N-M	0/1555	-18.5	-18.5 0.31 (1)	10.00			
M-L	0/0	-18.5	-18.5 0.08 (4)	10.00			

Structural component only
DWG# T-2007087

JOB NAME 408151	TRUSS NAME T27	QUANTITY 2	PLY 1	JOB DESC. GREEN PARK HOMES	DRWG NO.
Tamarack Roof Truss, Burlington		Version 8.310 S Oct 29 2019 MITek Industries, Inc. Sat Apr 25 11:19:53 2020 Page 1			
		ID:h2dflgC44wS_E2t2qPs_atzllFw-TrgPQ2slvcVC7mmMST9S9GaHs1uT3o2SIR1ZNUzNCXa			
		Scale = 1:50.0			



CHORDS	SIZE	LUMBER	DESCR.
A - D	2x4	DRY No.2	SPF
D - E	2x4	DRY No.2	SPF
E - G	2x4	DRY No.2	SPF
G - H	2x4	DRY No.2	SPF
H - K	2x4	DRY No.2	SPF
T - B	2x4	DRY No.2	SPF
L - J	2x4	DRY No.2	SPF
T - Q	2x4	DRY No.2	SPF
Q - O	2x4	DRY No.2	SPF
O - L	2x4	DRY No.2	SPF
ALL WEBS EXCEPT	2x4	DRY No.2	SPF
S - C	2x3	DRY No.2	SPF
O - R	2x3	DRY No.2	SPF
N - I	2x3	DRY No.2	SPF
M - I	2x3	DRY No.2	SPF
B - S	2x3	DRY No.2	SPF
M - J	2x3	DRY No.2	SPF

DRY: SEASONED LUMBER.

PLATES (table is in inches)

JT TYPE	PLATES	W	LEN	Y	X
B TMVW-p	MT20	5.0	8.0	1.50	3.00
C TMVW-i	MT20	4.0	4.0	2.00	1.25
D TS-1	MT20	3.0	8.0		
E TTVW-m	MT20	5.0	8.0	Edge	3.00
F TMVW-i	MT20	2.0	4.0		
G TTVW-m	MT20	5.0	8.0	Edge	3.00
H TS-1	MT20	3.0	8.0		
I TMVW-i	MT20	4.0	4.0	2.00	1.25
J TMVW-p	MT20	5.0	8.0	1.50	3.00
L BMV1+p	MT20	3.0	4.0		
M BMVW-i	MT20	5.0	8.0		
N BMVW-i	MT20	4.0	4.0		
O BS-1	MT20	3.0	8.0		
P BMVW-i	MT20	4.0	4.0		
Q BS-1	MT20	3.0	8.0		
R BMVW-i	MT20	4.0	4.0		
S BMVW-i	MT20	5.0	8.0		
T BMV1+p	MT20	3.0	4.0		

DIMENSIONS, SUPPORTS AND LOADINGS SPECIFIED BY FABRICATOR TO BE VERIFIED BY BUILDING DESIGNER

BEARINGS	FACTORED GROSS REACTION	MAXIMUM FACTORED GROSS REACTION	INPUT BRG IN-SX	REQD BRG IN-SX
JT VERT	2068	0	0	5-8
T 2068	0	2068	0	5-8
L 2068	0	2068	0	5-8

UNFACTORED REACTIONS

1ST CASE	MAX/MIN. COMPONENT REACTIONS	PERM. LIVE WIND	DEAD	SOIL
JT COMBINED	SNOW	LIVE	PERM. LIVE	WIND
T 1458	971 / 0	0 / 0	0 / 0	488 / 0
L 1458	971 / 0	0 / 0	0 / 0	488 / 0

BEARING MATERIAL TO BE SPF NO.2 OR BETTER AT JOINT(S) T, L

BRACING

TOP CHORD TO BE SHEATHED OR MAX. PURLIN SPACING = 4.27 FT.
MAX. UNBRACED BOTTOM CHORD LENGTH = 10.00 FT OR RIGID CEILING DIRECTLY APPLIED.

ALL PITCH BREAKS AND PERIMETER CORNER JOINTS MUST BE Laterally RESTRAINED.

1 LATERAL BRACE(S) AT 1/2 LENGTH OF G-R, F-P, I-N.

END VERTICAL(S) MUST BE SHEATHED OR HAVE BRACES AS INDICATED IN THE MAX. UNBRACED LENGTH COLUMN OF THE TABLE BELOW

LOADING

TOTAL LOAD CASES: (4)

CHORDS	MAX. FACTORED FORCE (LBS)	FACTORED VERT. LOAD (PLF)	MAX. CS (LC)	MAX. UNBRACED LENGTH	WEBS	MAX. FACTORED FORCE (LBS)	MAX. CS (LC)
FR-TO					FR-TO		
A-B	0 / 41	-91.8	-91.8	0.13 (1)	10.00	S-C	-245 / 10
B-C	-2039 / 0	-91.8	-91.8	0.50 (1)	4.27	C-R	-314 / 0
C-D	-1844 / 0	-91.8	-91.8	0.46 (1)	4.47	R-E	0 / 338
D-E	-1844 / 0	-91.8	-91.8	0.46 (1)	4.47	E-P	0 / 489
E-F	-1621 / 0	-91.8	-91.8	0.50 (1)	4.60	P-F	-699 / 0
F-G	-1621 / 0	-91.8	-91.8	0.50 (1)	4.80	G-P	0 / 489
G-H	-1844 / 0	-91.8	-91.8	0.46 (1)	4.47	N-G	0 / 338
H-I	-1844 / 0	-91.8	-91.8	0.46 (1)	4.47	I-N	-314 / 0
I-J	-2039 / 0	-91.8	-91.8	0.50 (1)	4.27	M-I	-245 / 10
J-K	0 / 41	-91.8	-91.8	0.13 (1)	10.00	B-S	0 / 1637
T-B	-2021 / 0	0.0	0.0	0.21 (1)	5.94	M-J	0 / 1637
L-J	-2021 / 0	0.0	0.0	0.21 (1)	5.94		
T-S	0 / 0	-18.5	-18.5	0.14 (4)	10.00		
S-R	0 / 1597	-18.5	-18.5	0.33 (1)	10.00		
R-Q	0 / 1387	-18.5	-18.5	0.30 (1)	10.00		
Q-P	0 / 1387	-18.5	-18.5	0.30 (1)	10.00		
P-O	0 / 1387	-18.5	-18.5	0.30 (1)	10.00		
O-N	0 / 1387	-18.5	-18.5	0.30 (1)	10.00		
N-M	0 / 1597	-18.5	-18.5	0.33 (1)	10.00		
M-L	0 / 0	-18.5	-18.5	0.14 (4)	10.00		

DESIGN CRITERIA

SPECIFIED LOADS:
TOP CH. LL = 25.6 PSF
DL = 6.0 PSF
BOT CH. LL = 0.0 PSF
DL = 7.4 PSF
TOTAL LOAD = 39.0 PSF

SPACING = 24.0 IN. C/C

LOADING IN FLAT SECTION BASED ON A SLOPE OF 8.00/12

THIS TRUSS IS DESIGNED FOR RESIDENTIAL OR SMALL BUILDING REQUIREMENTS OF PART 9, NBC 2010, NBC 2015

THIS DESIGN COMPLIES WITH:

- PART 9 OF CBC 2018, CBC 2012, ABC 2019
- PART 9 OF CBC 2012 (2019 AMENDMENT)
- CSA 086-08, CSA 086-14
- TPC 2011, TPC 2014

(55 % OF 31.3 P.S.F. G.S.L. PLUS 8.4 P.S.F. RAIN LOAD) EQUALS 25.6 P.S.F. SPECIFIED ROOF LIVE LOAD

ALLOWABLE DEFL. (LL) = L/360 (1.17')
CALCULATED VERT. DEFL. (LL) = L/999 (0.07')
ALLOWABLE DEFL. (TL) = L/360 (1.17')
CALCULATED VERT. DEFL. (TL) = L/999 (0.14')

CSI: TC=0.50/1.00 (E-F:1), BC=0.33/1.00 (M-N:1),
WB=0.45/1.00 (F-P:1), SS=0.28/1.00 (E-F:1)

DOL LUMBER=1.00 NAIL=1.00 LS BEND=1.10
COMP=1.10 SHEAR=1.10 TENS=1.10

COMPANION LIVE LOAD FACTOR = 1.00


TRUSS PLATE MANUFACTURER IS NOT RESPONSIBLE FOR QUALITY CONTROL IN THE TRUSS MANUFACTURING PLANT

NAIL VALUES
PLATE GRIP (DRY) SHEAR SECTION
(PSI) (PLI) (PLI)
MAX MIN MAX MIN MAX MIN
MT20 618 354 1667 788 1987 1658

PLATE PLACEMENT TOL. = 0.250 inches

PLATE ROTATION TOL. = 5.0 Deg.


JSI GRIP= 0.89 (J) (INPUT = 0.90)
JSI METAL= 0.47 (O) (INPUT = 1.00)



Structural component only
DWG# T-2007089

JOB NAME 408151	TRUSS NAME T28	QUANTITY 2	PLY 1	JOB DESC. GREEN PARK HOMES	DRWG NO.
Tamarack Roof Truss, Burlington				TRUSS DESC.	

Version 8.310 S Oct 29 2019 Mittek Industries, Inc. Sat Apr 25 11:19:54 2020 Page 1
 ID:h2dfgC44wS_E2tzqPs_atzIRw-x1EndQINgwd3kvMZ0AghhTAWTQH00b7bX5n7vxzNCXZ



Scale: 1/4"=1'

LUMBER

N.L.G.A. RULES

CHORDS	SIZE	DRY	LUMBER	DESCR.
A - D	2x4	DRY	No.2	SPF
D - G	2x4	DRY	No.2	SPF
L - B	2x4	DRY	No.2	SPF
H - F	2x4	DRY	No.2	SPF
L - J	2x4	DRY	No.2	SPF
J - H	2x4	DRY	No.2	SPF
ALL WEBS EXCEPT	2x3	DRY	No.2	SPF

DRY: SEASONED LUMBER.

PLATES (table is in inches)

JT TYPE	PLATES	W	LEN	Y	X
B TMV+p	MT20	3.0	4.0		
C TMWW-t	MT20	4.0	8.0		
D TTWW+p	MT20	4.0	8.0	Edge	
E TMWW-t	MT20	4.0	8.0		
F TMV+p	MT20	3.0	4.0		
H BMVW-t	MT20	4.0	4.0		
I BMVW-t	MT20	4.0	8.0		
J BS-t	MT20	3.0	8.0		
K BMVW-t	MT20	4.0	8.0		
L BMVW-t	MT20	4.0	4.0		

Edge - INDICATES REFERENCE CORNER OF PLATE TOUCHES EDGE OF CHORD.

DIMENSIONS, SUPPORTS AND LOADINGS SPECIFIED BY FABRICATOR TO BE VERIFIED BY BUILDING DESIGNER

BEARINGS

JT	FACTORED GROSS REACTION		MAXIMUM FACTORED GROSS REACTION		INPUT BRG	REQD BRG
	VERT	HORZ	DOWN	HORZ		
L	1041	0	1041	0	5-8	5-8
H	1041	0	1041	0	5-8	5-8

UNFACTORED REACTIONS

JT	1ST CASE		MAX/MIN COMPONENT REACTIONS		WIND	DEAD	SOIL
	COMBINED	SNOW	LIVE	PERM LIVE			
L	734	495 / 0	0 / 0	0 / 0	0 / 0	239 / 0	0 / 0
H	734	495 / 0	0 / 0	0 / 0	0 / 0	239 / 0	0 / 0

BEARING MATERIAL TO BE SPF NO.2 OR BETTER AT JOINT(S) L, H

BRACING
 TOP CHORD TO BE SHEATHED OR MAX. PURLIN SPACING = 8.25 FT.
 MAX. UNBRACED BOTTOM CHORD LENGTH = 10.00 FT. OR RIGID CEILING DIRECTLY APPLIED.

ALL PITCH BREAKS AND PERIMETER CORNER JOINTS MUST BE LATERALLY RESTRAINED.

LOADING
 TOTAL LOAD CASES: (4)

MEMB.	CHORDS			WEBS		
	MAX. FACTORED FORCE (LBS)	FACTORED VERT. LOAD (LBS)	MAX. CSI (LC)	MEMB. FORCE (LBS)	MAX. FACTORED FORCE (LBS)	MAX. CSI (LC)
FR-TO		FROM TO		FR-TO		
A-B	0 / 41	-91.8	-91.8 0.13 (1)	0-1	0 / 339	0.08 (1)
B-C	0 / 29	-91.8	-91.8 0.28 (1)	1-E	-222 / 0	0.09 (1)
C-D	-764 / 0	-91.8	-91.8 0.20 (1)	2-K	0 / 339	0.08 (1)
D-E	-764 / 0	-91.8	-91.8 0.20 (1)	3-K	-222 / 0	0.09 (1)
E-F	0 / 29	-91.8	-91.8 0.28 (1)	4-L	-964 / 0	0.66 (1)
F-G	0 / 41	-91.8	-91.8 0.13 (1)	5-H	-884 / 0	0.66 (1)
G-H	-270 / 0	0.0	0.0 0.03 (1)			
H-F	-270 / 0	0.0	0.0 0.03 (1)			
L-K	0 / 632	-18.5	-18.5 0.18 (4)			
K-J	0 / 459	-18.5	-18.5 0.17 (4)			
J-I	0 / 459	-18.5	-18.5 0.17 (4)			
I-H	0 / 632	-18.5	-18.5 0.18 (4)			

TOTAL WEIGHT = 2 X 82 = 163 lb (M/F)

DESIGN CRITERIA

SPECIFIED LOADS:
 TOP CH. LL = 25.6 PSF
 DL = 6.0 PSF
 BOT CH. LL = 0.0 PSF
 DL = 7.4 PSF
 TOTAL LOAD = 39.0 PSF

SPACING = 24.0 IN./C

THIS TRUSS IS DESIGNED FOR RESIDENTIAL OR SMALL BUILDING REQUIREMENTS OF PART 9, NBCC 2010, NBCC 2015

THIS DESIGN COMPLIES WITH:
 - PART 9 OF BCBC 2018, OBC 2012, ABC 2018
 - PART 9 OF OBC 2012 (2018 AMENDMENT)
 - CSA 086-09, CSA 086-14
 - TPIC 2011, TPIC 2014

(55 % OF 31.3 P.S.F. G.S.L. PLUS 6.4 P.S.F. RAIN LOAD) EQUALS 25.6 P.S.F. SPECIFIED ROOF LIVE LOAD

ALLOWABLE DEFL.(LL) = L/360 (0.55")
 CALCULATED VERT. DEFL.(LL) = L/999 (0.02")
 ALLOWABLE DEFL.(TL) = L/360 (0.55")
 CALCULATED VERT. DEFL.(TL) = L/999 (0.04")

CSI: TC=0.28/1.00 (B-C:1), BC=0.18/1.00 (H-4), WB=0.68/1.00 (E-H:1), SSI=0.14/1.00 (C-D:1)

DOL LUMBER=1.00 NAIL=1.00 LS BEND=1.10
 COMP=1.10 SHEAR=1.10 TENS=1.10

COMPANION LIVE LOAD FACTOR = 1.00


TRUSS PLATE MANUFACTURER IS NOT RESPONSIBLE FOR QUALITY CONTROL IN THE TRUSS MANUFACTURING PLANT.

NAIL VALUES
 PLATE GRIP(DRY) SHEAR SECTION (PSI) (PLI) (PLI)
 MAX MIN MAX MIN MAX MIN
 MT20 618 354 1867 788 1887 1656

PLATE PLACEMENT TOL. = 0.250 inches

PLATE ROTATION TOL. = 5.0 Deg.


JSI GRIP= 0.78 (C) (INPUT = 0.90)
 JSI METAL= 0.28 (C) (INPUT = 1.00)



Structural component only
 DWG# T-2007090

Structural component only
DWG# T-2007091

JOB NAME	TRUSS NAME	QUANTITY	PLY	JOB DESC.	DRWG NO.
408151	T30	1	1	GREEN PARK HOMES	
Tamarack Roof Truss, Burlington					



Scale = 1/4" = 1'-0"

LUMBER	N. L. G. A. RULES	CHORDS	SIZE	LUMBER	DESCR.
A - D	2x4	DRY	No.2	SPF	
E - H	2x6	DRY	No.2	SPF	
I - L	2x4	DRY	No.2	SPF	
M - P	2x4	DRY	No.2	SPF	
Q - R	2x4	DRY	No.2	SPF	
S - T	2x4	DRY	No.2	SPF	
U - V	2x4	DRY	No.2	SPF	
W - X	2x4	DRY	No.2	SPF	
Y - Z	2x4	DRY	No.2	SPF	

ALL WEBS 2x3 DRY No.2 EXCEPT

DRY: SEASONED LUMBER.

PLATES (tablets in inches)

JT TYPE	PLATES	W	LEN	Y	X
B TMV+p	MT20	3.0	4.0		
C TMVW-I	MT20	4.0	4.0	2.00	1.75
D TTW-n	MT20	4.0	8.0		
E TTWW+m	MT20	5.0	8.0	Edge	
F TMVW-I	MT20	4.0	8.0		
G TMV+p	MT20	3.0	4.0		
I BMVW-I	MT20	4.0	4.0		
J BMVW-I	MT20	4.0	4.0		
K BSWW-I	MT20	6.0	9.0	Edge	3.75
L BMVW-I	MT20	4.0	4.0		

Edge - INDICATES REFERENCE CORNER OF PLATE TOUCHES EDGE OF CHORD.

DIMENSIONS, SUPPORTS AND LOADINGS SPECIFIED BY FABRICATOR TO BE VERIFIED BY BUILDING DESIGNER

BEARINGS	FACTORED	MAXIMUM FACTORED	INPUT	RECORD
JT	GROSS REACTION	GROSS REACTION	BRG	BRG
L	VERT	HORIZ	DOWN	HORIZ
I	1041	0	1041	0
I	1041	0	1041	0

A SUITABLE HANGER/MECHANICAL CONNECTION IS REQUIRED AT JOINT I. MINIMUM BEARING LENGTH AT JOINT I = 3-8.

UNFACTORED REACTIONS

JT	1ST CASE	MAX/MIN	COMPONENT REACTIONS	DEAD	SOIL
L	734	495/0	0/0	0/0	239/0
I	734	495/0	0/0	0/0	239/0

BEARING MATERIAL TO BE SPF NO.2 OR BETTER AT JOINT(S) L.

BRACING

TOP CHORD TO BE SHEATHED OR MAX. PURLIN SPACING = 6.25 FT.
MAX. UNBRACED BOTTOM CHORD LENGTH = 10.00 FT OR RIGID CEILING DIRECTLY APPLIED.

ALL PITCH BREAKS AND PERIMETER CORNER JOINTS MUST BE Laterally RESTRAINED.

1 LATERAL BRACE(S) AT 1/2 LENGTH OF E-K.

END VERTICAL(S) MUST BE SHEATHED OR HAVE BRACES AS INDICATED IN THE MAX. UNBRACED LENGTH COLUMN OF THE TABLE BELOW

LOADING

TOTAL LOAD CASES: (4)

MEMB.	CHORDS	MAX. FACTORED	FORCE	VERT. LOAD	LC1	MAX	MAX.	MEMB.	WEBS	MAX. FACTORED	FORCE	MAX
FR-TO								FR-TO				
A-B	0/41	-91.8	-91.8	0.13 (1)	10.00			C-K	-98/9	0.09 (1)		
B-C	0/27	-91.8	-91.8	0.23 (1)	10.00			K-D	0/164	0.04 (1)		
C-D	-566/0	-91.8	-91.8	0.18 (1)	6.25			K-E	-109/0	0.07 (4)		
D-E	-414/0	-91.8	-91.8	0.01 (1)	6.25			J-F	0/288	0.07 (4)		
E-F	-582/0	-91.8	-91.8	0.18 (1)	6.25			J-F	-93/15	0.09 (1)		
F-G	0/27	-91.8	-91.8	0.23 (1)	10.00			L-C	-846/0	0.78 (1)		
G-H	0/41	-91.8	-91.8	0.13 (1)	10.00			F-I	-662/0	0.79 (1)		
L-B	-265/0	0.0	0.0	0.04 (1)	7.81							
I-G	-265/0	0.0	0.0	0.04 (1)	7.81							
L-K	0/468	-18.5	-18.5	0.38 (4)	10.00							
K-J	0/424	-18.5	-18.5	0.30 (4)	10.00							
J-I	0/477	-18.5	-18.5	0.30 (4)	10.00							

TOTAL WEIGHT = 97 lb

DESIGN CRITERIA

SPECIFIED LOADS:
TOP CH. LL = 25.6 PSF
DL = 8.0 PSF
BOT CH. LL = 0.0 PSF
DL = 7.4 PSF
TOTAL LOAD = 39.0 PSF

SPACING = 24.0 IN. C/C

LOADING IN FLAT SECTION BASED ON A SLOPE OF 6.00/12

THIS TRUSS IS DESIGNED FOR RESIDENTIAL OR SMALL BUILDING REQUIREMENTS OF PART 9, NBCC 2010, NBCC 2015

THIS DESIGN COMPLIES WITH:
- PART 9 OF CBC 2010, CBC 2012, ABC 2019
- PART 9 OF CBC 2012 (2019 AMENDMENT)
- CSA 088-09, CSA 088-14
- TPIC 2011, TPIC 2014

(55% OF 31.3 P.S.F. G.S.L. PLUS 8.4 P.S.F. RAIN LOAD) EQUALS 25.6 P.S.F. SPECIFIED ROOF LIVE LOAD

ALLOWABLE DEFL. (LL) = L/360 (0.55")
CALCULATED VERT. DEFL. (LL) = L/999 (0.01")
ALLOWABLE DEFL. (TL) = L/360 (0.55")
CALCULATED VERT. DEFL. (TL) = L/999 (0.17")

CSI: TC=0.23/1.00 (B-C:1), BC=0.38/1.00 (K-L:4), WB=0.79/1.00 (F-I:1), SSI=0.14/1.00 (J-K:4)

DOL LUMBER=1.00 NAIL=1.00 LS BEND=1.10
COMP=1.10 SHEAR=1.10 TENS=1.10

COMPANION LIVE LOAD FACTOR = 1.00

TRUSS PLATE MANUFACTURER IS NOT RESPONSIBLE FOR QUALITY CONTROL IN THE TRUSS MANUFACTURING PLANT.

NAIL VALUES
PLATE GRIP(DRY) SHEAR SECTION
(PSI) (PLI) (PLI)
MAX MIN MAX MIN MAX MIN
MT20 618 354 1667 788 1987 1656

PLATE PLACEMENT TOL. = 0.250 inches

PLATE ROTATION TOL. = 5.0 Deg.

JSI GRIP=0.89 (C) (INPUT = 0.90)
JSI METAL=0.31 (C) (INPUT = 1.00)




Structural component only
DWG# T-2007092

JOB NAME	TRUSS NAME	QUANTITY	PLY	JOB DESC.	GREEN PARK HOMES	DRWG NO.
408151	T31	1	1	TRUSS DESC.		

Tamarack Roof Truss, Burlington

Version 8.310 S Oct 29 2019 Mitek Industries, Inc. Sat Apr 25 11:19:57 2020 Page 1
ID:h2dlfgC44wS_E2bzqPs_atzllRw-LcwwGPvFzr0ebO56hIDQJ5o2BeID?Ze1D3?nWFzNCXW



Scale = 1/48.0

LUMBER	N. L. G. A. RULES	CHORDS	SIZE	DRY	NO.2
A - D	2x4	DRY	No.2		
D - E	2x4	DRY	No.2		
E - H	2x4	DRY	No.2		
M - B	2x4	DRY	No.2		
I - G	2x4	DRY	No.2		
M - K	2x4	DRY	No.2		
K - I	2x4	DRY	No.2		

ALL WEBS 2x3 DRY NO.2 EXCEPT

DRY: SEASONED LUMBER.

PLATES (table is in inches)

JT	TYPE	PLATES	W	LEN	Y	X
B	TMV+P	MT20	3.0	4.0		
C	TMVW+1	MT20	4.0	4.0	2.00	1.75
D	TTW+m	MT20	4.0	4.0		
E	TTWV+m	MT20	5.0	6.0	2.25	1.50
F	TMVW+1	MT20	4.0	4.0	2.00	1.75
G	TMV+P	MT20	3.0	4.0		
I	BMVW+1	MT20	4.0	4.0		
J	BMVW+1	MT20	4.0	4.0		
K	BS+1	MT20	3.0	6.0		
L	BMVWV+1	MT20	4.0	6.0		
M	BMVW+1	MT20	4.0	4.0		

DIMENSIONS, SUPPORTS AND LOADINGS SPECIFIED BY FABRICATOR TO BE VERIFIED BY BUILDING DESIGNER

BEARINGS

	FACTORED GROSS REACTION	MAXIMUM FACTORED GROSS REACTION	INPUT BRG	REQD BRG
JT	VERT	HORZ	DOWN	HORZ
M	1041	0	1041	0
I	1041	0	1041	0

A SUITABLE HANGER/MECHANICAL CONNECTION IS REQUIRED AT JOINT I. MINIMUM BEARING LENGTH AT JOINT I = 3-0.

UNFACTORED REACTIONS

JT	1ST LOASE	MAX	MIN	COMPONENT REACTIONS
M	734	495/0	0/0	PERM.LIVE
I	734	495/0	0/0	WIND DEAD SOIL

BEARING MATERIAL TO BE SPF NO.2 OR BETTER AT JOINT(S) M

BRACING

TOP CHORD TO BE SHEATHED OR MAX. PURLIN SPACING = 8.25 FT.
MAX. UNBRACED BOTTOM CHORD LENGTH = 10.00 FT OR RIGID CEILING DIRECTLY APPLIED.

ALL PITCH BREAKS AND PERIMETER CORNER JOINTS MUST BE Laterally RESTRAINED.

LOADING

TOTAL LOAD CASES: (4)

CHORDS	MEMB.	MAX. FACTORED FORCE (LBS)	VERT. LOAD (PLF)	LC1 MAX	LC2 MAX	MAX. UNBRACED LENGTH	WEBS	MEMB.	MAX. FACTORED FORCE (LBS)	MAX. UNBRACED LENGTH
A-B	0/41	-91.8	-91.8	0.13 (1)	10.00	10.00	C-L	-10/34	0.01 (4)	10.00
B-G	0/22	-91.8	-91.8	0.16 (1)	10.00	10.00	L-D	0/110	0.03 (4)	10.00
C-D	-613/0	-91.8	-91.8	0.13 (1)	6.25	6.25	L-E	0/0	0.00 (1)	6.25
D-E	-453/0	-91.8	-91.8	0.14 (1)	6.25	6.25	J-E	0/109	0.03 (4)	6.25
E-F	-612/0	-91.8	-91.8	0.13 (1)	6.25	6.25	J-F	-11/34	0.01 (4)	6.25
F-G	0/22	-91.8	-91.8	0.16 (1)	10.00	10.00	M-C	-873/0	0.80 (1)	10.00
G-H	0/41	-91.8	-91.8	0.13 (1)	10.00	10.00	F-I	-873/0	0.80 (1)	10.00
H-I	-245/0	0.0	0.0	0.04 (1)	7.81	7.81				
I-G	-245/0	0.0	0.0	0.04 (1)	7.81	7.81				
M-L	0/457	-18.5	-18.5	0.21 (4)	10.00	10.00				
L-K	0/453	-18.5	-18.5	0.20 (4)	10.00	10.00				
K-J	0/453	-18.5	-18.5	0.20 (4)	10.00	10.00				
J-I	0/457	-18.5	-18.5	0.21 (4)	10.00	10.00				

TOTAL WEIGHT = 92 lb

DESIGN CRITERIA

SPECIFIED LOADS:
TOP CH. LL = 25.6 PSF
OL = 8.0 PSF
BOT CH. LL = 0.0 PSF
OL = 7.4 PSF
TOTAL LOAD = 39.0 PSF

SPACING = 21.0 IN. OC

LOADING IN PLAT SECTION BASED ON A SLOPE OF 6.00/12

THIS TRUSS IS DESIGNED FOR RESIDENTIAL OR SMALL BUILDING REQUIREMENTS OF PART 9, NBC 2010, NBC 2015

THIS DESIGN COMPLIES WITH:
- PART 9 OF BCBC 2010, OBC 2012, ABC 2019
- PART 9 OF OBC 2012 (2019 AMENDMENT)
- CSA 086-08, CSA 088-14
- TPIC 2011, TPIC 2014

(55% OF 31.3 P.S.F. G.S.L. PLUS 8.4 P.S.F. RAIN LOAD) EQUALS 25.6 P.S.F. SPECIFIED ROOF LIVE LOAD

ALLOWABLE DEFL.(LL) = L/360 (0.55")
CALCULATED VERT. DEFL.(LL) = L/989 (0.01")
ALLOWABLE DEFL.(TL) = L/360 (0.55")
CALCULATED VERT. DEFL.(TL) = L/989 (0.07")

CSI: TC=0.16/1.00 (F-G-1), BC=0.21/1.00 (I-J-4),
WB=0.50/1.00 (C-M-1), SS=0.12/1.00 (D-E-1)

DOL LUMBER=1.00 NAIL=1.00 LS BEND=1.10
COMP=1.10 SHEAR=1.10 TENS=1.10

COMPANION LIVE LOAD FACTOR = 1.00


TRUSS PLATE MANUFACTURER IS NOT RESPONSIBLE FOR QUALITY CONTROL IN THE TRUSS MANUFACTURING PLANT.

NAIL VALUES
PLATE GRIP(DRY) SHEAR SECTION (PSI) (PLI) (PLI)
MAX MIN MAX MIN MAX MIN
MT20 610 354 1667 788 1887 1666

PLATE PLACEMENT TOL. = 0.250 inches

PLATE ROTATION TOL. = 5.0 Deg.

JSI GRIP = 0.87 (C) (INPUT = 0.80)
JSI METAL = 0.31 (C) (INPUT = 1.00)




Structural component only
DWG# T-2007093

JOB NAME 408151	TRUSS NAME T32	QUANTITY 1	PLY 1	JOB DESC. GREEN PARK HOMES	TRUSS DESC.	DRWG NO.
--------------------	-------------------	---------------	----------	-------------------------------	-------------	----------

Tamarack Roof Truss, Burlington

Version 8.310 S Oct 29 2019 Mitek Industries, Inc. Sat Apr 25 11:19:58 2020 Page 1
ID:h2dligC44wS_E2tqPs_atzllRw-ppUllTwk98VDYgKF0ldrJL812f0k80BSJK2izNCXV



Scale: 1/4" = 1'-0"

LUMBER	N. L. G. A. RULES	SIZE	DRY	LUMBER
CHORDS				
A - C	2x4	DRY	No.2	
C - D	2x4	DRY	No.2	
D - F	2x4	DRY	No.2	
K - B	2x4	DRY	No.2	
G - E	2x4	DRY	No.2	
K - I	2x4	DRY	No.2	
I - G	2x4	DRY	No.2	

ALL WEBS 2x3 DRY No.2
EXCEPT

DRY: SEASONED LUMBER.

PLATES (table in inches)

JT	TYPE	PLATES	W	LEN	Y	X
B	TMVW+p	MT20	4.0	4.0	1.00	2.00
C	TTWW+m	MT20	5.0	8.0	2.25	1.50
D	TTW-m	MT20	4.0	4.0		
E	TMVW+p	MT20	4.0	4.0	1.00	2.00
G	BMV1+p	MT20	3.0	4.0		
H	BMVWW-l	MT20	4.0	9.0		
I	BS-l	MT20	3.0	6.0		
J	BMVWW-l	MT20	4.0	4.0		
K	BMV1+p	MT20	3.0	4.0		

DIMENSIONS, SUPPORTS AND LOADINGS SPECIFIED BY FABRICATOR TO BE VERIFIED BY BUILDING DESIGNER

BEARINGS	FACTORED	MAXIMUM FACTORED	INPUT	REQD
	GROSS REACTION	GROSS REACTION	BRG	BRG
JT	VERT	HORZ	DOWN	HORZ
K	1041	0	1041	0
G	1041	0	1041	0

A SUITABLE HANGER/MECHANICAL CONNECTION IS REQUIRED AT JOINT G. MINIMUM BEARING LENGTH AT JOINT G = 3-8.

UNFACTORED REACTIONS

JT	1ST CASE	MAX/MIN. COMPONENT REACTIONS	SNOW	LIVE	PERM. LIVE	WIND	DEAD	SOIL
K	734	495/0	0/0	0/0	0/0	0/0	239/0	0/0
G	734	495/0	0/0	0/0	0/0	0/0	239/0	0/0

BEARING MATERIAL TO BE SPF NO.2 OR BETTER AT JOINT(S) K

BRACING

TOP CHORD TO BE SHEATHED OR MAX. PURLIN SPACING = 8.25 FT.
MAX. UNBRACED BOTTOM CHORD LENGTH = 10.00 FT OR RIGID CEILING DIRECTLY APPLIED.

ALL PITCH BREAKS AND PERIMETER CORNER JOINTS MUST BE Laterally RESTRAINED.

1 LATERAL BRACE(S) AT 1/2 LENGTH OF C-H.

END VERTICAL(S) MUST BE SHEATHED OR HAVE BRACES AS INDICATED IN THE MAX. UNBRACED LENGTH COLUMN OF THE TABLE BELOW

LOADING

TOTAL LOAD CASES: (4)

CHORDS	MEMB.	MAX. FACTORED FORCE (LBS)	FACTORED VERT. LOAD (PLF)	MAX. UNBRACED LENGTH (LC)	WEBS	MEMB.	MAX. FACTORED FORCE (LBS)	MAX. UNBRACED LENGTH (LC)
FR-TO					FR-TO			
A-B	0/41	-91.8	-91.8	0.13 (1)	J-C	-115/46	0.12 (1)	10.00
B-C	-619/0	-91.8	-91.8	0.35 (1)	C-H	0/0	0.00 (1)	6.25
C-D	-473/0	-91.8	-91.8	0.39 (1)	H-D	-115/46	0.12 (1)	6.25
D-E	-619/0	-91.8	-91.8	0.35 (1)	B-J	0/528	0.12 (1)	6.25
E-F	0/41	-91.8	-91.8	0.13 (1)	H-E	0/528	0.12 (1)	10.00
K-B	-1000/0	0.0	0.0	0.16 (1)				7.81
G-E	-1000/0	0.0	0.0	0.16 (1)				7.81
K-J	0/0	-18.5	-18.5	0.13 (4)				10.00
J-I	0/473	-18.5	-18.5	0.17 (4)				10.00
I-H	0/473	-18.5	-18.5	0.17 (4)				10.00
H-G	0/0	-18.5	-18.5	0.13 (4)				10.00

TOTAL WEIGHT = 79 LB (MIF)

DESIGN CRITERIA

SPECIFIED LOADS:
TOP CH. LL = 25.6 PSF
DL = 8.0 PSF
BOT CH. LL = 0.0 PSF
DL = 7.4 PSF
TOTAL LOAD = 39.0 PSF

SPACING = 24.0 IN. C/C

LOADING IN FLAT SECTION BASED ON A SLOPE OF 6.0/12

THIS TRUSS IS DESIGNED FOR RESIDENTIAL OR SMALL BUILDING REQUIREMENTS OF PART 9, NBCC 2010, NBCC 2015

THIS DESIGN COMPLIES WITH:
- PART 9 OF NBCC 2010, OBC 2012, ABC 2019
- PART 9 OF OBC 2012 (2019 AMENDMENT)
- CSA 086-09, CSA 086-14
- TPIC 2011, TPIC 2014

(55% OF 31.3 P.S.F. G.S.L. PLUS 8.4 P.S.F. RAIN LOAD) EQUALS 25.6 P.S.F. SPECIFIED ROOF LIVE LOAD

ALLOWABLE DEFL. (LL) = L/360 (0.55")
CALCULATED VERT. DEFL. (LL) = L/999 (0.01")
ALLOWABLE DEFL. (TL) = L/360 (0.55")
CALCULATED VERT. DEFL. (TL) = L/999 (0.03")

CSI: TC=0.39/1.00 (C-D:1), BC=0.17/1.00 (H-J:4), WB=0.12/1.00 (B-J:1), SS=0.21/1.00 (C-D:1)

DOL LUMBER=1.00 NAIL=1.00 LS BEND=1.10
COMP=1.10 SHEAR=1.10 TENS=1.10

COMPANION LIVE LOAD FACTOR = 1.00

TRUSS PLATE MANUFACTURER IS NOT RESPONSIBLE FOR QUALITY CONTROL IN THE TRUSS MANUFACTURING PLANT.

NAIL VALUES
PLATE GRIP (DRY) SHEAR SECTION (PSI) (PLI) (PLI)
MAX MIN MAX MIN MAX MIN
MT20 618 354 1687 788 1987 1656

PLATE PLACEMENT TOL. = 0.250 inches


PLATE ROTATION TOL. = 5.0 Deg.

JSI GRIP = 0.82 (B) (INPUT = 0.90)
JSI METAL = 0.23 (B) (INPUT = 1.00)



Structural component only
DWG# T-2007094

JOB NAME	TRUSS NAME	QUANTITY	PLY	JOB DESC.	DRWG NO.
408151	G33	1	1	GREEN PARK HOMES	
Tamarack Roof Truss, Burlington				TRUSS DESC.	



LUMBER			
N. L. G. A. RULES	SIZE	LUMBER	DESCR.
CHORDS			
L - B	2x4	DRY	No.2
A - D	2x4	DRY	No.2
D - G	2x4	DRY	No.2
H - F	2x4	DRY	No.2
L - H	2x4	DRY	No.2
ALL WEBS	2x3	DRY	No.2
ALL GABLE WEBS	2x3	DRY	No.2
DRY: SEASONED LUMBER.			

GABLE STUDS SPACED AT 2'-0" O.C.

PLATES (tablets in inches)					
JT	TYPE	PLATES	W	LEN	Y X
B	TMVW+p	MT20	4.0	4.0	1.00 2.00
C	TMVW+w	MT20	2.0	4.0	
D	TTW+p	MT20	4.0	8.0	Edge
E	TMVW+w	MT20	2.0	4.0	
F	TMVW+p	MT20	4.0	4.0	1.00 2.00
H	BMV1+p	MT20	3.0	4.0	
I	BMVW1-t	MT20	4.0	4.0	
J	BMV1+w	MT20	2.0	4.0	
K	BMVW1-t	MT20	4.0	4.0	
L	BMV1+p	MT20	3.0	4.0	

Edge - INDICATES REFERENCE CORNER OF PLATE TOUCHES EDGE OF CHORD.

DIMENSIONS, SUPPORTS AND LOADINGS SPECIFIED BY FABRICATOR TO BE VERIFIED BY BUILDING DESIGNER

BEARINGS

THIS TRUSS DESIGNED FOR CONTINUOUS BEARINGS.
THIS TRUSS REQUIRES RIGID SHEATHING ON EXPOSED FACE.
BEARING MATERIAL TO BE SPF NO.2 OR BETTER AT JOINT(S)

BRACING

TOP CHORD TO BE SHEATHED OR MAX. PURLIN SPACING = 8.25 FT.
MAX. UNBRACED BOTTOM CHORD LENGTH = 10.00 FT OR RIGID CEILING DIRECTLY APPLIED.

ALL PITCH BREAKS AND PERIMETER CORNER JOINTS MUST BE LATERALLY RESTRAINED.

LOADING

TOTAL LOAD CASES: (4)

CHORDS				WEBS			
MEMB.	MAX. FACTORED FORCE (LBS)	VERT. LOAD (PLF)	FACTORED LC1 MAX CSI (LC)	MEMB.	MAX. FACTORED FORCE (LBS)	MAX. FACTORED UNBRAC LENGTH	FR-TO
L-B	-231 / 0	0.0	0.0 0.02 (1)	J-D	-123 / 0	7.81	
A-B	0 / 41	-91.8	-91.8 0.13 (1)	K-C	-238 / 0	10.00	
B-C	-11 / 0	-91.8	-91.8 0.07 (1)	I-E	-238 / 0	6.25	
C-D	-32 / 0	-91.8	-91.8 0.07 (1)	B-K	0 / 23	6.25	
D-E	-32 / 0	-91.8	-91.8 0.07 (1)	I-F	0 / 23	6.25	
E-F	-11 / 0	-91.8	-91.8 0.07 (1)				
F-G	0 / 41	-91.8	-91.8 0.13 (1)				
H-F	-231 / 0	0.0	0.0 0.02 (1)				
L-K	0 / 0	-18.5	-18.5 0.02 (4)				
K-J	0 / 13	-18.5	-18.5 0.02 (4)				
J-I	0 / 13	-18.5	-18.5 0.02 (4)				
I-H	0 / 0	-18.5	-18.5 0.02 (4)				

TOTAL WEIGHT = 42 lb (M)

DESIGN CRITERIA

SPECIFIED LOADS:

TOP CH. LL = 25.6 PSF
DL = 8.0 PSF
BOT CH. LL = 0.0 PSF
DL = 7.4 PSF
TOTAL LOAD = 39.0 PSF

SPACING = 24.0 IN. C/C

THIS TRUSS IS DESIGNED FOR RESIDENTIAL OR SMALL BUILDING REQUIREMENTS OF PART 9, NBCC 2010, NBCC 2015

THIS DESIGN COMPLIES WITH:

- PART 9 OF NBCC 2010, OBC 2012, ABC 2019
- PART 9 OF OBC 2012 (2019 AMENDMENT)
- CSA 088-09, CSA 088-14
- TPIC 2011, TPIC 2014

(55% OF 31.3 P.S.F. G.S.L. PLUS 8.4 P.S.F. RAIN LOAD) EQUALS 25.6 P.S.F. SPECIFIED ROOF LIVE LOAD

CSI: TC=0.13/1.00 (F-G:1), BC=0.02/1.00 (J-K:4), WB=0.05/1.00 (C-K:1), SS=0.08/1.00 (F-G:1)

DOL LUMBER=1.00 NAIL=1.00 LS BEND=1.10 COMP=1.10 SHEAR=1.10 TENS=1.10

COMPANION LIVE LOAD FACTOR = 1.00

TRUSS PLATE MANUFACTURER IS NOT RESPONSIBLE FOR QUALITY CONTROL IN THE TRUSS MANUFACTURING PLANT.

NAIL VALUES

PLATE GRIP(DRY) SHEAR SECTION
(PSI) (PLI) (PLI)
MAX MIN MAX MIN MAX MIN
MT20 618 354 1687 788 1987 1688

PLATE PLACEMENT TOL. = 0.250 inches

PLATE ROTATION TOL. = 5.0 Deg.


JSI GRIP= 0.18 (C) (INPUT = 0.80)
JSI METAL= 0.13 (C) (INPUT = 1.00)



Structural component only
DWG# T-2007078

JOB NAME	TRUSS NAME	QUANTITY	PLY	JOB DESC.	DRWG NO.
408151	T33X	1	1	GREEN PARK HOMES	
Tamarack Roof Truss, Burlington		TRUSS DESC.			

Version 8.310 S Oct 29 2019 MITek Industries, Inc. Sat Apr 25 11:19:59 2020 Page 1
ID:h2dlqC44wS_E2t2qPs_atzllRw-I?2gh5wVWVGmhfWpIGsOWuMTR?ITcdKhMUu68zNCXU



Scale = 1/2" = 1'-0"

LUMBER			
N. L. G. A. RULES	CHORDS	SIZE	LUMBER
A - B	2x4	DRY	No.2
B - C	2x4	DRY	No.2
F - A	2x4	DRY	No.2
D - C	2x4	DRY	No.2
F - D	2x4	DRY	No.2

ALL WEBS 2x3 DRY No.2
EXCEPT

DRY: SEASONED LUMBER.

PLATES (table is in inches)

JT	TYPE	PLATES	W	LEN	Y	X
A	TMVW+p	MT20	4.0	4.0	1.00	2.00
B	FTW+p	MT20	4.0	6.0	Edge	
C	TMVW+p	MT20	4.0	4.0	1.00	2.00
D	BMV1+p	MT20	3.0	4.0		
E	BMVWW+1	MT20	4.0	9.0		
F	BMV1+p	MT20	3.0	4.0		

Edge - INDICATES REFERENCE CORNER OF PLATE TOUCHES EDGE OF CHORD.

DIMENSIONS, SUPPORTS AND LOADINGS SPECIFIED BY FABRICATOR TO BE VERIFIED BY BUILDING DESIGNER

BEARINGS		FACTORED	MAXIMUM FACTORED	INPUT	REQD
JT	GROSS REACTION	GROSS REACTION	DOWN	UP	BRG
F	498	0	498	0	3-0
D	498	0	498	0	3-0

UNFACTORED REACTIONS

JT	1ST CASE	MAX/MIN. COMPONENT REACTIONS	PERM. LIVE	WIND	DEAD	SOIL
F	COMBINED	SNOW	LIVE	PERM. LIVE	WIND	DEAD
F	351	230 / 0	0 / 0	0 / 0	0 / 0	121 / 0
D	351	230 / 0	0 / 0	0 / 0	0 / 0	121 / 0

BEARING MATERIAL TO BE SPF NO.2 OR BETTER AT JOINT(S) F, D

BRACING

TOP CHORD TO BE SHEATHED OR MAX. PURLIN SPACING = 8.25 FT.
MAX. UNBRACED BOTTOM CHORD LENGTH = 10.00 FT. OR RIGID CEILING DIRECTLY APPLIED.

ALL PITCH BREAKS AND PERIMETER CORNER JOINTS MUST BE Laterally RESTRAINED.

LOADING

TOTAL LOAD CASES: (4)

CHORDS		FACTORED		WEBS	
MEMB.	FORCE (LBS)	VERT. LOAD	MAX. (LBS)	MEMB.	FORCE (LBS)
FR-TO		FROM TO	CS1 (LC)	FR-TO	
A-B	-311 / 0	-91.8 -91.8	0.24 (1)	E-B	-14 / 72
B-C	-311 / 0	-91.8 -91.8	0.24 (1)	A-E	0 / 248
F-A	-464 / 0	0.0 0.0	0.05 (1)	E-C	0 / 248
D-C	-464 / 0	0.0 0.0	0.05 (1)		
F-E	0 / 0	-18.5 -18.5	0.11 (4)		
E-D	0 / 0	-18.5 -18.5	0.11 (4)		

DESIGN CRITERIA

SPECIFIED LOADS:
TOP CH. LL = 25.6 PSF
OL = 6.0 PSF
BOT CH. LL = 0.0 PSF
DL = 7.4 PSF
TOTAL LOAD = 39.0 PSF

SPACING = 24.0 IN. CG

THIS TRUSS IS DESIGNED FOR RESIDENTIAL OR SMALL BUILDING REQUIREMENTS OF PART 9, NBCC 2010, NBCC 2015

THIS DESIGN COMPLIES WITH:
- PART 9 OF BCBC 2018, OBC 2012, ABC 2019
- PART 9 OF OBC 2012 (2019 AMENDMENT)
- CSA 086-09, CSA 088-14
- TPIC 2011, TPIC 2014

(55 % OF 31.3 P.S.F. G.S.L. PLUS 8.4 P.S.F. RAIN LOAD) EQUALS 25.6 P.S.F. SPECIFIED ROOF LIVE LOAD

ALLOWABLE DEFL. (LL) = L/360 (0.30")
CALCULATED VERT. DEFL. (LL) = L/999 (0.00")
ALLOWABLE DEFL. (TL) = L/360 (0.30")
CALCULATED VERT. DEFL. (TL) = L/999 (0.01")

CS1: TC=0.24/1.00 (A-B:1), BC=0.11/1.00 (E-F:4),
WB=0.06/1.00 (C-E:1), SS1=0.12/1.00 (A-B:1)

DOL LUMBER=1.00 NAIL=1.00 LS BEND=1.10
COMP=1.10 SHEAR=1.10 TENS=1.10

COMPANION LIVE LOAD FACTOR = 1.00

TRUSS PLATE MANUFACTURER IS NOT RESPONSIBLE FOR QUALITY CONTROL IN THE TRUSS MANUFACTURING PLANT.

NAIL VALUES
PLATE GRIP(DRY) SHEAR SECTION
(PSI) (PLI) (PLI)
MAX MIN MAX MIN MAX MIN
MT20 618 354 1667 788 1987 1656

PLATE PLACEMENT TOL. = 0.250 inches

PLATE ROTATION TOL. = 5.0 Deg.

JSI GRIP= 0.42 (A) (INPUT = 0.90)
JSI METAL= 0.12 (A) (INPUT = 1.00)




Structural component only
DWG# T-2007095

Tamarack Roof Truss, Burlington




JSI GRIP= 0.33 (A) (INPUT = 0.90)
JSI METAL= 0.09 (A) (INPUT = 1.00)



JOB NAME 408151	TRUSS NAME T35	QUANTITY 2	PLY 2	JOB DESC. GREEN PARK HOMES	DRWG NO.
Tamarack Roof Truss, Burlington				TRUSS DESC.	

Version 8.310 S Oct 29 2019 Mitek Industries, Inc. Sat Apr 25 11:20:01 2020 Page 1
ID: h2d1qC44wS_E2tzqPs_atzllRw-EO9R5nym13W44?Ovw8IKTxzhdF1_xTud8pz_11zNCXS



LUMBER				
N. L. G. A. RULES	CHORDS	SIZE	LUMBER	DESCR.
F - A	2x4	DRY	No.2	SPF
A - C	2x4	DRY	No.2	SPF
D - C	2x4	DRY	No.2	SPF
F - D	2x4	DRY	No.2	SPF

ALL WEBS 2x3 DRY No.2 SPF
DRY: SEASONED LUMBER.

DESIGN CONSISTS OF 2 TRUSSES BUILT SEPARATELY THEN FASTENED TOGETHER AS FOLLOWS:

CHORDS #ROWS	SURFACE SPACING (IN.)	LOAD (PLF)
TOP CHORDS : (0.122"x3") SPIRAL NAILS		
F - A	12	TOP
A - C	12	TOP
C - D	12	TOP
BOTTOM CHORDS : (0.122"x3") SPIRAL NAILS		
F - D	11	SIDE (97.1)
WEBS : (0.122"x3") SPIRAL NAILS		
B - E	8	SIDE (20.3)
2x3	8	

NAILS TO BE DRIVEN FROM ONE SIDE ONLY.

GIRDER NAILING ASSUMES NAILED HANGERS ARE FASTENED WITH MIN. 3-0 INCH NAILS.

TOP - COMPONENTS ARE LOADED FROM THE TOP AND MUST BE PLACED ON TOP EDGE OF ALL PLIES FOR THE LOAD TO BE TRANSFERRED TO EACH PLY.

SIDE - PLF SHOWN IS THE EQUIVALENT UDL APPLIED TO ONE SIDE THAT THE CORRESPONDING NAILING PATTERN SHALL BE CAPABLE OF TRANSFERRING. REMAINING PLF MUST BE APPLIED ON THE OPPOSITE SIDE OR ON THE TOP.

PLATES (table in inches)	JT TYPE	PLATES	W	LEN	Y	X
A	TMVW-1	MT20	4.0	8.0		
B	TMVW-1	MT20	2.0	4.0		
C	TMVW-1	MT20	4.0	8.0		
D	BMVW-1	MT20	3.0	4.0		
E	BMVW-1	MT20	4.0	8.0		

DIMENSIONS, SUPPORTS AND LOADINGS SPECIFIED BY FABRICATOR TO BE VERIFIED BY BUILDING DESIGNER.

BEARINGS

JT	FACTORED GROSS REACTION	MAXIMUM FACTORED GROSS REACTION	INPUT BRG	RECORD BRG
F	1016	0	0	5-8
D	1085	0	0	5-8

A SUITABLE HANGER/MECHANICAL CONNECTION IS REQUIRED AT JOINT D. MINIMUM BEARING LENGTH AT JOINT D = 1-8.

UNFACTORED REACTIONS

JT	1ST CASE	MAX/MIN COMPONENT REACTIONS	SNOW	LIVE	PERM LIVE	WIND	DEAD	SOIL
F	726	436 / 0	0 / 0	0 / 0	0 / 0	290 / 0	0 / 0	0 / 0
D	772	479 / 0	0 / 0	0 / 0	0 / 0	293 / 0	0 / 0	0 / 0

BEARING MATERIAL TO BE SPF NO.2 OR BETTER AT JOINT(S) F

BRACING

TOP CHORD TO BE SHEATHED OR MAX. PURLIN SPACING = 6.23 FT.
MAX. UNBRACED BOTTOM CHORD LENGTH = 10.00 FT OR RIGID CEILING DIRECTLY APPLIED.

ALL PITCH BREAKS AND PERIMETER CORNER JOINTS MUST BE LATERALLY RESTRAINED.

LOADING

TOTAL LOAD CASES: (4)

CHORDS				WEBS			
MEMB.	MAX. FACTORED FORCE (LBS)	FACTORED VERT. LOAD (PLF)	LC1 MAX	MAX. UNBRACED LENGTH	MEMB.	MAX. FACTORED FORCE (LBS)	MAX. UNBRACED LENGTH
FR-TO		FROM TO			FR-TO		
F-A	-985 / 0	0.0	0.0	0.05 (1)	A-E	0 / 1810	0.22 (1)
A-G	-1706 / 0	-91.8	-91.8	0.28 (1)	E-B	-482 / 0	0.04 (1)
G-B	-1706 / 0	-91.8	-91.8	0.28 (1)	B-C	0 / 1810	0.22 (1)
B-C	-1706 / 0	-91.8	-91.8	0.08 (1)	C-D		
D-C	-707 / 0	0.0	0.0	0.04 (1)			
F-E	0 / 0	-43.5	-43.5	0.05 (1)			
E-H	0 / 0	-43.5	-43.5	0.22 (1)			
H-D	0 / 0	-43.5	-43.5	0.22 (1)			

FACTORED CONCENTRATED LOADS (LBS)

JT	LOC.	LC1	MAX.	MAX.	FACE	DIR.	TYPE	HEEL	CONN.
E	3-0-12	-450	-450	---	FRONT	VERT	TOTAL	---	C1
G	1-0-12	-404	-404	---	FRONT	VERT	TOTAL	---	C1
H	5-0-12	-452	-452	---	FRONT	VERT	TOTAL	---	C1

CONNECTION REQUIREMENTS

1) C1: A SUITABLE HANGER/MECHANICAL CONNECTION IS REQUIRED.

TOTAL WEIGHT = 4 X 20 = 80 lb

DESIGN CRITERIA

*** SPECIAL LOADS ANALYSIS ***
GEOMETRY AND/OR BASIC LOADS CHANGED BY USER.
LOADS WERE DERIVED FROM USER INPUT
NO FURTHER MODIFICATIONS WERE MADE

SPECIFIED LOADS:

TOP CH.	LL	=	25.8	PSF
	DL	=	8.0	PSF
BOT CH.	LL	=	0.0	PSF
	DL	=	7.4	PSF
TOTAL LOAD		=	39.0	PSF

SPACING = 24.0 IN. C/C

LOADING IN FLAT SECTION BASED ON A SLOPE OF 0.00/12

*** NON STANDARD GIRDER ***

ADDTL. USER-DEFINED LOADS APPLIED TO ALL LOAD CASES.

THIS TRUSS IS DESIGNED FOR RESIDENTIAL OR SMALL BUILDING REQUIREMENTS OF PART 9, NBC 2010, NBCC 2015

THIS DESIGN COMPLIES WITH:
- PART 9 OF NBC 2010, NBC 2015, ABC 2019
- PART 9 OF NBC 2012 (2019 AMENDMENT)
- CSA 086-09, CSA 086-14
- TPIC 2011, TPIC 2014

(55 % OF 31.3 P.S.F. G.S.L. PLUS 8.4 P.S.F. RAIN LOAD) EQUALS 25.6 P.S.F. SPECIFIED ROOF LIVE LOAD

ALLOWABLE DEFL. (LL) = L/360 (0.20")
CALCULATED VERT. DEFL. (LL) = L/999 (0.02")
ALLOWABLE DEFL. (TL) = L/360 (0.20")
CALCULATED VERT. DEFL. (TL) = L/999 (0.03")

CSI: TC=0.28/1.00 (A-B:1), BC=0.22/1.00 (D-E:1), WB=0.22/1.00 (A-E:1), SS=0.18/1.00 (D-E:1)

DOL LUMBER=1.00 NAIL=1.00 LS BEND=1.00
COMP=1.00 SHEAR=1.00 TENS=1.00

COMPANION LIVE LOAD FACTOR = 1.00

TRUSS PLATE MANUFACTURER IS NOT RESPONSIBLE FOR QUALITY CONTROL IN THE TRUSS MANUFACTURING PLANT

NAIL VALUES	PLATE GRIP (DRY)	SHEAR (PSI)	SECTION (PLI)
MT20	518	354	1667
			788
			1987
			1658

PLATE PLACEMENT TOL. = 0.250 inches

PLATE ROTATION TOL. = 5.0 Deg.

JSI GRIP = 0.59 (C) (INPUT = 0.90)
JSI METAL = 0.21 (C) (INPUT = 1.00)



Structural component only
DWG# T-2007097 1/2


CONTINUED ON PAGE 2

JOB NAME	TRUSS NAME	QUANTITY	PLY	JOB DESC.	DRWG NO.
408151	T35	2	2	GREEN PARK HOMES	

Tamarack Roof Truss, Burlington


Version 8.310 S Oct 29 2019 Mitek Industries, Inc. Sat Apr 25 11:26:01 2020 Page 2
ID:h2dfiqC44wS E2tzoPs atzllRw-EO9R5nym13W44?Ovw8IKTxzhdFf xTud8gz l1zNCKXS

PLATES (table is in inches)
JT TYPE PLATES W LEN Y X
F BMV1+p MT20 3.0 4.0



Structural component only
DWG# T-2007097 32

JOB NAME	TRUSS NAME	QUANTITY	PLY	JOB DESC.	DRWG NO.
408151	G36	1	1	GREEN PARK HOMES	
Tamarack Roof Truss, Burlington					
Version 8.310 S Oct 29 2019 Mittek Industries, Inc. Sat Apr 25 11:19:41 2020 Page 1					
ID:h2dflgC44wS E2tzqPs atzllRw-pXyvtvxDkw7vhwS3lxxelk8KIBtVFSmhYZ7xyBzNCXm					
10 1 8 10 11 0 12 2 8					
Scale = 1/32					



LUMBER			
N. L. G. A. RULES	CHORDS	SIZE	LUMBER
P - B	2x4	DRY	No.2
A - E	2x4	DRY	No.2
E - I	2x4	DRY	No.2
J - H	2x4	DRY	No.2
P - J	2x4	DRY	No.2
ALL WEBS	2x3	DRY	No.2
ALL GABLE WEBS	2x3	DRY	No.2
DRY: SEASONED LUMBER.			
GABLE STUDS SPACED AT 2'-0" OC.			

PLATES (table in inches)					
JT TYPE	PLATES	W	LEN	Y	X
B TMVW+p	MT20	4.0	4.0	1.00	2.00
C, D, F, G					
C TMVW+w	MT20	2.0	4.0		
E TTW+p	MT20	4.0	6.0	Edge	
H TMVW+p	MT20	4.0	4.0	1.00	2.00
J BMV1+p	MT20	3.0	4.0		
K BMWW1-t	MT20	4.0	4.0		
L, M, N					
L BMW1+w	MT20	2.0	4.0		
O BMWW1-t	MT20	4.0	4.0		
P BMV1+p	MT20	3.0	4.0		

Edge - INDICATES REFERENCE CORNER OF PLATE TOUCHES EDGE OF CHORD.

DIMENSIONS, SUPPORTS AND LOADINGS SPECIFIED BY FABRICATOR TO BE VERIFIED BY BUILDING DESIGNER

BEARINGS
THIS TRUSS DESIGNED FOR CONTINUOUS BEARINGS.
THIS TRUSS REQUIRES RIGID SHEATHING ON EXPOSED FACE.
BEARING MATERIAL TO BE SPF NO.2 OR BETTER AT JOINT(S)

BRACING
TOP CHORD TO BE SHEATHED OR MAX. PURLIN SPACING = 6.25 FT.
MAX. UNBRACED BOTTOM CHORD LENGTH = 10.00 FT OR RIGID CEILING DIRECTLY APPLIED.
ALL PITCH BREAKS AND PERIMETER CORNER JOINTS MUST BE Laterally RESTRAINED.

LOADING
TOTAL LOAD CASES: (4)

CHORDS				WEBS			
MEMB.	MAX. FACTORED FORCE (LBS)	FACTORED VERT. LOAD (PLF)	MAX. UNBRACED LENGTH (L/C)	MEMB.	MAX. FACTORED FORCE (LBS)	MAX. UNBRACED LENGTH (L/C)	
FR-TO				FR-TO			
P-B	-274 / 0	0.0	0.0 0.03 (1)	M-E	-139 / 0	0.03 (1)	
A-B	0 / 41	-91.8	-91.8 0.13 (1)	N-D	-223 / 0	0.07 (1)	
B-C	-57 / 0	-91.8	-91.8 0.12 (1)	O-C	-75 / 0	0.01 (1)	
C-D	-4 / 0	-91.8	-91.8 0.03 (1)	L-F	-223 / 0	0.07 (1)	
D-E	-22 / 0	-91.8	-91.8 0.03 (1)	K-G	-75 / 0	0.01 (1)	
E-F	-22 / 0	-91.8	-91.8 0.03 (1)	B-O	0 / 20	0.00 (1)	
F-G	-4 / 0	-91.8	-91.8 0.03 (1)	K-H	0 / 20	0.00 (1)	
G-H	-57 / 0	-91.8	-91.8 0.12 (1)				
H-I	0 / 41	-91.8	-91.8 0.13 (1)				
J-H	-274 / 0	0.0	0.0 0.03 (1)				
P-O	0 / 0	-18.5	-18.5 0.01 (4)				
O-N	0 / 12	-18.5	-18.5 0.02 (4)				
N-M	0 / 7	-18.5	-18.5 0.02 (4)				
M-L	0 / 7	-18.5	-18.5 0.02 (4)				
L-K	0 / 12	-18.5	-18.5 0.02 (4)				
K-J	0 / 0	-18.5	-18.5 0.01 (4)				

TOTAL WEIGHT = 53 lb

DESIGN CRITERIA

SPECIFIED LOADS:
TOP CH. LL = 25.6 PSF
DL = 6.0 PSF
BOT CH. LL = 0.0 PSF
DL = 7.4 PSF
TOTAL LOAD = 39.0 PSF

SPACING = 24.0 IN. CG

THIS TRUSS IS DESIGNED FOR RESIDENTIAL OR SMALL BUILDING REQUIREMENTS OF PART 9, NBCC 2010, NBCC 2015

THIS DESIGN COMPLIES WITH:
- PART 9 OF BCBC 2018, OBC 2012, ABC 2019
- PART 9 OF OBC 2012 (2018 AMENDMENT)
- CSA 088-09, CSA 088-14
- TPIC 2011, TPIC 2014

DESIGN ASSUMPTIONS
- OVERHANG NOT TO BE ALTERED OR CUT OFF.

(55% OF 31.3 P.S.F. G.S.L. PLUS 8.4 P.S.F. RAIN LOAD) EQUALS 25.6 P.S.F. SPECIFIED ROOF LIVE LOAD

CSI: TC=0.13/1.00 (H-I), BC=0.02/1.00 (K-L), WB=0.08/1.00 (E-M), SSI=0.08/1.00 (A-B-I)
DOL LUMBER=1.00 NAIL=1.00 LS BEND=1.10
COMP=1.10 SHEAR=1.10 TENS=1.10

COMPANION LIVE LOAD FACTOR = 1.00

TRUSS PLATE MANUFACTURER IS NOT RESPONSIBLE FOR QUALITY CONTROL IN THE TRUSS MANUFACTURING PLANT.

NAIL VALUES
PLATE GRIP (DRY) SHEAR SECTION
(PSI) (PL) (PL)
MAX MIN MAX MIN MAX MIN
MT20 618 354 1867 788 1987 1856

PLATE PLACEMENT TOL. = 0.250 inches


PLATE ROTATION TOL. = 5.0 Deg.

JSI GRIP= 0.21 (B) (INPUT = 0.80)
JSI METAL= 0.12 (F) (INPUT = 1.00)



Structural component only
DWG# T-2007079

JOB NAME 408152	TRUSS NAME T40	QUANTITY 1	PLY 2	JOB DESC. GREEN PARK HOMES	DRWG NO.
Tamarack Roof Truss, Burlington				Version 8.310 S Oct 29 2019 Mtek Industries, Inc. Sat Apr 25 11:28:32 2020 Page 1	
ID: 7VF7aG0E03cRUj6X11SkzWYK-0EA1x1sxZWS34IVetZ2E6M8CTQSHDeTgr0nICQzNCOX				Scale = 1:37.0	



LUMBER			
N. L. G. A. RULES	SIZE	DRY	LUMBER
CHORDS	2x4	DRY	No. 2
A - C	2x4	DRY	No. 2
C - F	2x4	DRY	No. 2
F - H	2x4	DRY	No. 2
H - J	2x4	DRY	No. 2
T - B	2x4	DRY	No. 2
K - I	2x4	DRY	No. 2
T - Q	2x4	DRY	No. 2
Q - N	2x4	DRY	No. 2
N - K	2x4	DRY	No. 2
ALL WEBS	2x3	DRY	No. 2
EXCEPT			

DRY: SEASONED LUMBER.

DESIGN CONSISTS OF 2 TRUSSES BUILT SEPARATELY THEN FASTENED TOGETHER AS FOLLOWS:

CHORDS #ROWS	SURFACE SPACING (IN)	LOAD (PLF)
TOP CHORDS: (0.122'X3") SPIRAL NAILS		
A - C 1 12	SIDE(61.0)	
H - J 1 12	SIDE(61.0)	
C - F 2 12	SIDE(61.0)	
F - H 2 12	SIDE(61.0)	
T - B 2 12	TOP	
K - I 2 12	TOP	
BOTTOM CHORDS: (0.122'X3") SPIRAL NAILS		
T - Q 2 12	SIDE(183.1)	
Q - N 2 12	SIDE(0.0)	
N - K 2 12	SIDE(183.1)	
WEBS: (0.122'X3") SPIRAL NAILS		
2x3 1 8		

NAILS TO BE DRIVEN FROM ONE SIDE ONLY.

GIRDER NAILING ASSUMES NAILED HANGERS ARE FASTENED WITH MIN. 3-0 INCH NAILS.

TOP - COMPONENTS ARE LOADED FROM THE TOP AND MUST BE PLACED ON TOP EDGE OF ALL PLIES FOR THE LOAD TO BE TRANSFERRED TO EACH PLY.

DIMENSIONS, SUPPORTS AND LOADINGS SPECIFIED BY FABRICATOR TO BE VERIFIED BY BUILDING DESIGNER

BEARINGS			
FACTORED	MAXIMUM FACTORED	INPUT	REQD
GROSS REACTION	GROSS REACTION	BRG	BRG
JT VERT	JT VERT	IN-SX	IN-SX
T 3331 0	3331 0	5-8	5-8
K 3331 0	3331 0	5-8	5-8

UNFACTORED REACTIONS			
1ST LOASE	MAX. MIN. COMPONENT REACTIONS		
COMBINED	SNOW	LIVE	PERM. LIVE
T 2356	1544 / 0	0 / 0	0 / 0
K 2356	1544 / 0	0 / 0	0 / 0

BEARING MATERIAL TO BE SPF NO. 2 OR BETTER AT JOINT(S) T, K

BRACING

TOP CHORD TO BE SHEATHED OR MAX. PURLIN SPACING = 3.87 FT.

MAX. UNBRACED BOTTOM CHORD LENGTH = 10.00 FT OR RIGID CEILING DIRECTLY APPLIED.

ALL PITCH BREAKS AND PERIMETER CORNER JOINTS MUST BE Laterally RESTRAINED.

LOADING			
TOTAL LOAD CASES: (4)			
CHORDS	FACTORED	WEBS	FACTORED
MEMB.	FORCE (LBS)	MEMB.	FORCE (LBS)
FR-TO	FROM TO	FR-TO	FROM TO
A-B 0 / 28	-91.8 -91.8 0.07 (1)	10.00	S-C -427 / 8
B-C -5077 / 0	-91.8 -91.8 0.52 (1)	3.87	C-R 0 / 3083
C-U -7108 / 0	-91.8 -91.8 0.23 (1)	4.33	R-D -1685 / 0
U-V -7108 / 0	-91.8 -91.8 0.23 (1)	4.33	O-G 0 / 1071
V-D -7108 / 0	-91.8 -91.8 0.23 (1)	4.33	M-G -1565 / 0
D-W -7994 / 0	-91.8 -91.8 0.27 (1)	4.10	L-H -427 / 8
W-X -7994 / 0	-91.8 -91.8 0.27 (1)	4.10	B-S 0 / 4592
X-Y -7994 / 0	-91.8 -91.8 0.27 (1)	4.10	L-I 0 / 4592
Y-E -7994 / 0	-91.8 -91.8 0.27 (1)	4.10	D-P 0 / 1071
E-Z -7994 / 0	-91.8 -91.8 0.27 (1)	4.10	M-H 0 / 3083
Z-F -7994 / 0	-91.8 -91.8 0.27 (1)	4.10	P-E -505 / 0
F-AA -7994 / 0	-91.8 -91.8 0.27 (1)	4.10	E-O -505 / 0
AA-AB -7994 / 0	-91.8 -91.8 0.27 (1)	4.10	
AB-G -7994 / 0	-91.8 -91.8 0.27 (1)	4.10	
G-AC -7106 / 0	-91.8 -91.8 0.23 (1)	4.33	
AC-AD -7108 / 0	-91.8 -91.8 0.23 (1)	4.33	
AD-H -7106 / 0	-91.8 -91.8 0.23 (1)	4.33	
H-I -5077 / 0	-91.8 -91.8 0.52 (1)	3.87	
I-J 0 / 28	-91.8 -91.8 0.07 (1)	10.00	
T-B -3255 / 0	0.0 0.0 0.11 (1)	7.89	
K-I -3255 / 0	0.0 0.0 0.11 (1)	7.89	

DESIGN CRITERIA

SPECIFIED LOADS:

TOP CH. LL = 25.6 PSF

DL = 6.0 PSF

BOT CH. LL = 0.0 PSF

DL = 7.4 PSF

TOTAL LOAD = 39.0 PSF

SPACING = 24.0 IN. C/C

LOADING IN FLAT SECTION BASED ON A SLOPE OF 6.00/12

THIS TRUSS IS DESIGNED FOR RESIDENTIAL OR SMALL BUILDING REQUIREMENTS OF PART 9, NBC 2010, NBC 2015

THIS DESIGN COMPLIES WITH:

- PART 9 OF SBC 2018, OBC 2012, ABC 2019
- PART 9 OF OBC 2012 (2019 AMENDMENT)
- CSA 086-09, CSA 086-14
- TPIC 2011, TPIC 2014

(65% OF 31.3 P.S.F. G.S.L. PLUS 8.4 P.S.F. RAIN LOAD) EQUALS 26.8 P.S.F. SPECIFIED ROOF LIVE LOAD

ALLOWABLE DEFL.(LL) = L/360 (1.17")

CALCULATED VERT. DEFL.(LL) = L/999 (0.21")

ALLOWABLE DEFL.(TL) = L/360 (1.17")

CALCULATED VERT. DEFL.(TL) = L/999 (0.39")

CS: TO=0.52/1.00 (H-I), BC=0.56/1.00 (O-P), WB=0.57/1.00 (B-S), SS=0.18/1.00 (D-E)

DOL LUMBER=1.00 NAIL=1.00 LB BEND=1.00

COMP=1.00 SHEAR=1.00 TENS=1.00

COMPANION LIVE LOAD FACTOR = 1.00

AUTOSOLVE HEELS OFF

TRUSS PLATE MANUFACTURER IS NOT RESPONSIBLE FOR QUALITY CONTROL IN THE TRUSS MANUFACTURING PLANT

NAIL VALUES

PLATE GRIP(DRY) SHEAR SECTION (PSI) (PLI) (PLI)

MAX MIN MAX MIN MAX MIN


MT20 618 354 1687 788 1987 1686

PLATE PLACEMENT TOL = 0.250 inches

PLATE ROTATION TOL = 5.0 Deg.

JSI GRIP= 0.84 (S) (INPUT = 0.90)

JSI METAL= 0.84 (N) (INPUT = 1.00)



Structural component only

DWG# T-2007107 1/2

JOB NAME	TRUSS NAME	QUANTITY	PLY	JOB DESC.	DRWG NO.
408152	T40	1	2	GREEN PARK HOMES	
Tamarack Roof Truss, Burlington				TRUSS DESC.	

Version 8.310 S Oct 29 2019 MITek Industries, Inc. Sat Apr 25 11:29:32 2020 Page 2
ID:47vF7aG0E03cRU6X1iSrkzWYK-0EA1x1sxZWS34IYeiZ2E6M6CTQSHDeTgR0niCQzNCOX

PLATES (table is in inches)

JT	TYPE	PLATES	W	LEN	Y	X
B	TMVW-1	MT20	5.0	8.0		
C	TTWW+m	MT20	5.0	8.0	Edge	
D, E, G						
D	TMVW-1	MT20	5.0	8.0		
F	TS-1	MT20	5.0	8.0		
H	TTWW+m	MT20	5.0	8.0	Edge	
I	TMVW-1	MT20	5.0	8.0		
K	BMV1+p	MT20	3.0	8.0		
L	BMVW-1	MT20	5.0	8.0	2.50	2.50
M, O, P, R						
M	BMVW-1	MT20	5.0	8.0		
N	BS-1	MT20	5.0	8.0		
Q	BS-1	MT20	5.0	8.0		
S	BMVW-1	MT20	5.0	8.0	2.50	2.50
T	BMV1+p	MT20	3.0	8.0		

Edge - INDICATES REFERENCE CORNER OF PLATE TOUCHES EDGE OF CHORD.

LOADING

TOTAL LOAD CASES: (4)


CHORDS				WEBS			
MEMB.	MAX. FACTORED FORCE (LBS)	FACTORED VERT. LOAD (PLF)	LC1 MAX CS1 (LC)	MEMB.	MAX. FACTORED FORCE (LBS)	FACTORED VERT. LOAD (PLF)	LC1 MAX CS1 (LC)
FR-TO		FROM TO	LENGTH FR-TO				
AQ-K	0:0	-18.5	-18.5 0.08 (4)				10.00

FACTORED CONCENTRATED LOADS (LBS)

JT	LOC.	LC1	MAX.	FACE	DIR.	TYPE	HEEL	CONN.
C	5-10-8	-438	-438	---	FRONT	VERT	TOTAL	--- C1
E	17-7-0	-110	-110	---	FRONT	VERT	TOTAL	--- C1
H	29-3-8	-438	-438	---	FRONT	VERT	TOTAL	--- C1
L	29-2-12	-28	-28	---	FRONT	VERT	TOTAL	--- C1
N	23-2-12	-28	-28	---	FRONT	VERT	TOTAL	--- C1
Q	11-11-4	-28	-28	---	FRONT	VERT	TOTAL	--- C1
S	5-11-4	-28	-28	---	FRONT	VERT	TOTAL	--- C1
U	7-11-4	-110	-110	---	FRONT	VERT	TOTAL	--- C1
V	9-11-4	-110	-110	---	FRONT	VERT	TOTAL	--- C1
W	11-11-4	-110	-110	---	FRONT	VERT	TOTAL	--- C1
X	13-11-4	-110	-110	---	FRONT	VERT	TOTAL	--- C1
Y	15-11-4	-110	-110	---	FRONT	VERT	TOTAL	--- C1
Z	19-2-12	-110	-110	---	FRONT	VERT	TOTAL	--- C1
AA	21-2-12	-110	-110	---	FRONT	VERT	TOTAL	--- C1
AB	23-2-12	-110	-110	---	FRONT	VERT	TOTAL	--- C1
AC	25-2-12	-110	-110	---	FRONT	VERT	TOTAL	--- C1
AD	27-2-12	-110	-110	---	FRONT	VERT	TOTAL	--- C1
AE	1-11-4	-28	-28	---	FRONT	VERT	TOTAL	--- C1
AF	3-11-4	-28	-28	---	FRONT	VERT	TOTAL	--- C1
AG	7-11-4	-28	-28	---	FRONT	VERT	TOTAL	--- C1
AH	9-11-4	-28	-28	---	FRONT	VERT	TOTAL	--- C1
AI	13-11-4	-28	-28	---	FRONT	VERT	TOTAL	--- C1
AJ	15-11-4	-28	-28	---	FRONT	VERT	TOTAL	--- C1
AK	17-7-0	-28	-28	---	FRONT	VERT	TOTAL	--- C1
AL	19-2-12	-28	-28	---	FRONT	VERT	TOTAL	--- C1
AM	21-2-12	-28	-28	---	FRONT	VERT	TOTAL	--- C1
AN	25-2-12	-28	-28	---	FRONT	VERT	TOTAL	--- C1
AO	27-2-12	-28	-28	---	FRONT	VERT	TOTAL	--- C1
AP	31-2-12	-28	-28	---	FRONT	VERT	TOTAL	--- C1
AQ	33-2-12	-28	-28	---	FRONT	VERT	TOTAL	--- C1

CONNECTION REQUIREMENTS


1) C1: A SUITABLE HANGER/MECHANICAL CONNECTION IS REQUIRED.



Structural component only
DWG# T-2007107 2/2

JOB NAME	TRUSS NAME	QUANTITY	PLY	JOB DESC.	DRWG NO.
408152	T40Z	1	2	GREEN PARK HOMES	
Tamarack Roof Truss, Burlington				TRUSS DESC.	

Version 8.310 S Oct 29 2019 Mitek Industries, Inc. Sat Apr 25 11:29:34 2020 Page 1
ID:7vF7aG0E03cRUj6X1SrkzWYK-ydH2MiuB57mK31I?_4IcnCv7E2GhUJzvKGpGJzNCOV
5639 = 1:37.3



LUMBER
N. L. G. A. RULES
CHORDS SIZE LUMBER DESCR.
A - C 2x4 DRY No.2 SPF
C - F 2x6 DRY No.2 SPF
F - H 2x6 DRY No.2 SPF
H - J 2x4 DRY No.2 SPF
J - K 2x6 DRY No.2 SPF
K - L 2x6 DRY No.2 SPF
L - M 2x6 DRY No.2 SPF
M - N 2x6 DRY No.2 SPF
N - K 2x6 DRY No.2 SPF
ALL WEBS 2x3 DRY No.2 SPF
EXCEPT

DESIGN CRITERIA
SPECIFIED LOADS:
TOP CH. LL = 25.8 PSF
DL = 8.0 PSF
BOT CH. LL = 0.0 PSF
DL = 7.4 PSF
TOTAL LOAD = 39.0 PSF
SPACING = 24.0 IN./C/C

LOADING IN FLAT SECTION BASED ON A SLOPE OF 6.00/12
THIS TRUSS IS DESIGNED FOR RESIDENTIAL OR SMALL BUILDING REQUIREMENTS OF PART 9, NBCC 2010, NBCC 2015

THIS DESIGN COMPLIES WITH:
- PART 9 OF NBCC 2010, CBC 2012, ABC 2019
- PART 9 OF CBC 2012 (2019 AMENDMENT)
- CSA 086-09, CSA 086-14
- TPIC 2011, TPIC 2014

(55% OF 31.3 P.S.F. G.S.L. PLUS 8.4 P.S.F. RAIN LOAD) EQUALS 25.8 P.S.F. SPECIFIED ROOF LIVE LOAD

ALLOWABLE DEFL.(LL) = L/360 (1.17")
CALCULATED VERT. DEFL.(LL) = L/999 (0.31")
ALLOWABLE DEFL.(TL) = L/360 (1.17")
CALCULATED VERT. DEFL.(TL) = L/740 (0.57")

CSK: TC=0.71/1.00 (B-C:1), BC=0.91/1.00 (O-P:1), WB=0.80/1.00 (B-S:1), SS=0.15/1.00 (R-S:1)

DOL LUMBER=1.00 NAIL=1.00 LS BEND=1.00 COMP=1.00 SHEAR=1.00 TENS=1.00

COMPANION LIVE LOAD FACTOR = 1.00

AUTOSOLVE HEELS OFF

TRUSS PLATE MANUFACTURER IS NOT RESPONSIBLE FOR QUALITY CONTROL IN THE TRUSS MANUFACTURING PLANT.

NAIL VALUES
PLATE GRIP(DRY) SHEAR SECTION
(PSI) (PLI) (PLI)
MT20 618 354 1687 788 1987 1656

PLATE PLACEMENT TOL. = 0.250 inches

PLATE ROTATION TOL. = 5.0 Deg.

JSI GRIP= 0.89 (S) (INPUT = 0.90)
JSI METAL= 0.93 (N) (INPUT = 1.00)

FACTORED CONCENTRATED LOADS (LBS)

JT LOC. LC1 MAX- MAX+ FACE DIR. TYPE HEEL CONN.

C 5-10-8 -438 -438 --- BACK VERT TOTAL --- C1

O 18-5-8 -2436 -2436 --- BACK VERT TOTAL --- C1

P 18-9-12 -17 -17 --- BACK VERT TOTAL --- C1

S 5-11-4 -26 -26 --- BACK VERT TOTAL --- C1

U 7-11-4 -110 -110 --- BACK VERT TOTAL --- C1

V 10-9-12 -82 -82 --- BACK VERT TOTAL --- C1

W 12-9-12 -82 -82 --- BACK VERT TOTAL --- C1

T-Z 0-0 -18.5 -18.5 0.08 (4) 10.00

Z-AA 0-0 -18.5 -18.5 0.08 (4) 10.00


AA-S 0-0 -18.5 -18.5 0.08 (4) 10.00

S-AB 0/6432 -18.5 -18.5 0.69 (1) 10.00

AB-AC 0/6432 -18.5 -18.5 0.69 (1) 10.00

AC-AD 0/6432 -18.5 -18.5 0.69 (1) 10.00

AD-R 0/6432 -18.5 -18.5 0.69 (1) 10.00



Structural component only
DWG# T-2007108

JOB NAME	TRUSS NAME	QUANTITY	PLY	JOB DESC.	DRWG NO.
408152	T40Z	1	2	GREEN PARK HOMES	

Tamarack Roof Truss, Burlington

Version 8.316 S Oct 29 2019 Mitak Industries, Inc. Sat Apr 25 11:29:34 2020 Page 2
ID:17vF?ag0E03cRUj8X1ISrkzIWK-ydH2MiuB57imK31? 4iCnCV?E2GhUJzvKGpGJzNCOV

PLATES (table is in inches)

JT	TYPE	PLATES	W	LEN	Y	X
S	TMVW-p	MT20	5.0	8.0	2.00	3.50
C	TTWW+m	MT20	6.0	9.0	Edge	
D, E, G						
D	TMVW-t	MT20	5.0	6.0		
F	TS-t	MT20	5.0	8.0		
H	TTWW+m	MT20	6.0	9.0	Edge	
I	TMVW-p	MT20	5.0	8.0	2.00	3.50
K	BMV1+p	MT20	3.0	8.0		
L	BMVW-t	MT20	5.0	8.0	2.50	3.50
M	BMVW-t	MT20	5.0	8.0	2.50	2.00
N	BS-t	MT20	5.0	6.0		
O	BMVW-t	MT20	5.0	8.0	2.75	2.75
P	BMVW-t	MT20	5.0	6.0	2.75	2.75
Q	BS-t	MT20	5.0	6.0		
R	BMVW-t	MT20	5.0	8.0	2.50	2.00
S	BMVW-t	MT20	5.0	8.0	2.50	3.50
T	BMV1+p	MT20	3.0	6.0		


Edge - INDICATES REFERENCE CORNER OF PLATE TOUCHES EDGE OF CHORD.

FACTORED CONCENTRATED LOADS (LBS)

JT	LOC.	LC1	MAX-	MAX+	FACE	DIR.	TYPE	HEEL	CONN.
X	14-9-12	-82	-82	---	BACK	VERT	TOTAL	---	C1
Y	16-9-12	-82	-82	---	BACK	VERT	TOTAL	---	C1
Z	1-11-4	-25	-25	---	BACK	VERT	TOTAL	---	C1
AA	3-11-4	-25	-25	---	BACK	VERT	TOTAL	---	C1
AB	7-11-4	-25	-25	---	BACK	VERT	TOTAL	---	C1
AC	8-10-8	-839	-839	---	BACK	VERT	TOTAL	---	C1
AD	10-9-12	-17	-17	---	BACK	VERT	TOTAL	---	C1
AE	12-9-12	-17	-17	---	BACK	VERT	TOTAL	---	C1
AF	14-9-12	-17	-17	---	BACK	VERT	TOTAL	---	C1


CONNECTION REQUIREMENTS

- 1) C1: A SUITABLE HANGER/MECHANICAL CONNECTION IS REQUIRED.



Structural component only
DWG# T-2007108

JOB NAME 408152	TRUSS NAME T41	QUANTITY 2	PLY 1	JOB DESC. GREEN PARK HOMES	DRWG NO.
Tamarack Roof Truss, Burlington				Version 8.310.5 Oct 29 2019 Mitek Industries, Inc. Sat Apr 25 11:29:35 2020 Page 1	
ID:7vF7aG0E03cRUj8X1jSrkzWYK-QprQa2vprQdxDHDYhbxk_kd2aSiQx967_0NplzNCOU				Scale = 1:37.5	



LUMBER

N.L.G.A. RULES

CHORDS	SIZE	DRY	LUMBER	DESCR.
A - D	2x4	DRY	No.2	SPF
D - F	2x4	DRY	No.2	SPF
F - H	2x4	DRY	No.2	SPF
H - K	2x4	DRY	No.2	SPF
S - B	2x4	DRY	No.2	SPF
L - J	2x4	DRY	No.2	SPF
S - Q	2x4	DRY	No.2	SPF
Q - N	2x4	DRY	No.2	SPF
N - L	2x4	DRY	No.2	SPF
ALL WEBS EXCEPT	2x3	DRY	No.2	SPF
S - C	2x4	DRY	No.2	SPF
I - L	2x4	DRY	No.2	SPF

DRY: SEASONED LUMBER.

PLATES (table in inches)

JT TYPE	PLATES	W	LEN	Y	X
B TMV+p	MT20	3.0	4.0		
C TMWW-t	MT20	5.0	8.0	2.50	2.75
D TTWW-m	MT20	5.0	8.0	2.25	2.75
E TMWW-t	MT20	4.0	4.0		
F TS-t	MT20	3.0	8.0		
G TMW+w	MT20	2.0	4.0		
H TTWW-m	MT20	5.0	8.0	2.25	2.75
I TMWW-t	MT20	5.0	8.0	2.50	2.75
J TMV-p	MT20	3.0	4.0		
L BMVW-t	MT20	4.0	9.0		Edge
M BMWW-t	MT20	4.0	4.0		
N BS-t	MT20	3.0	8.0		
O BMWW-t	MT20	4.0	9.0		
P BMWW-t	MT20	4.0	8.0		
Q BS-t	MT20	3.0	8.0		
R BMWW-t	MT20	4.0	4.0		
S BMVW-t	MT20	4.0	9.0		Edge

Edge - INDICATES REFERENCE CORNER OF PLATE TOUCHES EDGE OF CHORD.

DIMENSIONS, SUPPORTS AND LOADINGS SPECIFIED BY FABRICATOR TO BE VERIFIED BY BUILDING DESIGNER

BEARINGS

	FACTORED GROSS REACTION	MAXIMUM FACTORED GROSS REACTION	INPUT BRG	REQD BRG
JT	VERT	DOWN	0	0
S	2063	0	0	5-8
L	2063	0	0	5-8

UNFACTORED REACTIONS

1ST CASE	MAX/MIN COMPONENT REACTIONS
JT COMBINED	SNOW LIVE PERM.LIVE WIND DEAD SOIL
S	1457 989 / 0 0 / 0 0 / 0 488 / 0 0 / 0
L	1457 989 / 0 0 / 0 0 / 0 488 / 0 0 / 0

BEARING MATERIAL TO BE SPF NO.2 OR BETTER AT JOINT(S) S, L

BRACING

TOP CHORD TO BE SHEATHED OR MAX. PURLIN SPACING = 2.94 FT.

MAX. UNBRACED BOTTOM CHORD LENGTH = 10.00 FT OR RIGID CEILING DIRECTLY APPLIED.

ALL PITCH BREAKS AND PERIMETER CORNER JOINTS MUST BE LATERALLY RESTRAINED.

LOADING

TOTAL LOAD CASES: (4)

CHORDS				WEBS			
MEMB.	MAX. FACTORED FORCE (LBS)	FACTORED VERT. LOAD (PLF)	MAX. UNBRACED LENGTH (FT)	MEMB.	MAX. FACTORED FORCE (LBS)	MAX. UNBRACED LENGTH (FT)	CSF (LC)
FR-TO				FR-TO			
A-B	0 / 28	-91.8	-91.8 0.12 (1)	10.00	C-R	0 / 93	0.03 (4)
B-C	0 / 16	-91.8	-91.8 0.20 (1)	10.00	R-D	0 / 121	0.04 (4)
C-D	-2799 / 0	-91.8	-91.8 0.32 (1)	3.88	D-P	0 / 1267	0.29 (1)
D-E	-3508 / 0	-91.8	-91.8 0.95 (1)	2.94	P-E	-643 / 0	0.25 (1)
E-F	-3507 / 0	-91.8	-91.8 0.93 (1)	2.94	E-O	-2 / 0	0.00 (1)
F-G	-3507 / 0	-91.8	-91.8 0.93 (1)	2.94	O-G	-643 / 0	0.25 (1)
G-H	-3507 / 0	-91.8	-91.8 0.94 (1)	2.95	O-H	0 / 1268	0.28 (1)
H-I	-2799 / 0	-91.8	-91.8 0.32 (1)	3.88	M-H	0 / 121	0.04 (4)
I-J	0 / 16	-91.8	-91.8 0.20 (1)	10.00	M-I	0 / 93	0.03 (4)
J-K	0 / 28	-91.8	-91.8 0.12 (1)	10.00	S-C	-2974 / 0	0.83 (1)
S-B	-270 / 0	0.0	0.0 0.03 (1)	7.81	I-L	-2974 / 0	0.83 (1)
L-J	-270 / 0	0.0	0.0 0.03 (1)	7.81			
S-R	0 / 2417	-18.5	-18.5 0.53 (1)	10.00			
R-Q	0 / 2489	-18.5	-18.5 0.54 (1)	10.00			
Q-P	0 / 2489	-18.5	-18.5 0.54 (1)	10.00			
P-O	0 / 3509	-18.5	-18.5 0.64 (1)	10.00			
O-N	0 / 2489	-18.5	-18.5 0.54 (1)	10.00			
N-M	0 / 2489	-18.5	-18.5 0.54 (1)	10.00			
M-L	0 / 2417	-18.5	-18.5 0.53 (1)	10.00			

DESIGN CRITERIA

SPECIFIED LOADS:

TOP CH. LL = 26.6 PSF
DL = 6.0 PSF

BOT CH. LL = 0.0 PSF
DL = 7.4 PSF

TOTAL LOAD = 39.0 PSF

SPACING = 24.0 IN/CIC

LOADING IN FLAT SECTION BASED ON A SLOPE OF 6.00/12

THIS TRUSS IS DESIGNED FOR RESIDENTIAL OR SMALL BUILDING REQUIREMENTS OF PART 9, NBCC 2010, NBCC 2015

THIS DESIGN COMPLIES WITH:

- PART 9 OF BCBC 2018, OBC 2012, ABC 2019
- PART 9 OF OBC 2012 (2019 AMENDMENT)
- CSA 088-09, CSA 088-14
- TPIC 2011, TPIC 2014

(55% OF 31.3 P.S.F. G.S.L. PLUS 8.4 P.S.F. RAIN LOAD) EQUALS 25.6 P.S.F. SPECIFIED ROOF LIVE LOAD

ALLOWABLE DEFL.(LL) = L/360 (1.17")
CALCULATED VERT. DEFL.(LL) = L/999 (0.21")
ALLOWABLE DEFL.(TL) = L/360 (1.17")
CALCULATED VERT. DEFL.(TL) = L/999 (0.41")

CSF: TC=0.85/1.00 (D-E:1), BC=0.64/1.00 (O-P:1), WB=0.83/1.00 (I-L:1), SS=0.28/1.00 (D-E:1)

DOL LUMBER=1.00 NAIL=1.00 LS 8END=1.10
COMP=1.10 SHEAR=1.10 TENS=1.10

COMPANION LIVE LOAD FACTOR = 1.00

AUTOSOLVE HEELS OFF

TRUSS PLATE MANUFACTURER IS NOT RESPONSIBLE FOR QUALITY CONTROL IN THE TRUSS MANUFACTURING PLANT.


NAIL VALUES

PLATE GRIP(DRY)	SHEAR (PSI)	SECTION (PLI)
MAX MIN	MAX MIN	MAX MIN
MT20	618 354 1667 788	1987 1656

PLATE PLACEMENT TOL. = 0.250 inches

PLATE ROTATION TOL. = 5.0 Deg.

JSI GRIP= 0.89 (L) (INPUT = 0.90)
JSI METAL= 0.77 (N) (INPUT = 1.00)




Structural component only
DWG# T-2007109

JOB NAME 408152	TRUSS NAME T42	QUANTITY 2	PLY 1	JOB DESC. GREEN PARK HOMES	TRUSS DESC.	DRWG NO.
---------------------------	--------------------------	----------------------	-----------------	--------------------------------------	-------------	----------

Tamarack Roof Truss, Burlington

Version 8.310 S Oct 29 2019 MITek Industries, Inc. Sat Apr 25 11:29:38 2020 Page 1

ID: i7vF?aG0E03cRuj6X1Srk2WYK-u?PpnOvRckyUZNSp6P6AHCHn1r19RDGMewLCzNCOT



TOTAL WEIGHT = 2 X 139 = 278

LUMBER			
N. L. G. A. RULES			
CHORDS	SIZE	LUMBER	DESCR.
A - D	2x4	DRY	No.2
D - F	2x4	DRY	No.2
F - I	2x4	DRY	No.2
R - B	2x4	DRY	No.2
J - H	2x4	DRY	No.2
R - O	2x4	DRY	No.2
O - M	2x4	DRY	No.2
M - J	2x4	DRY	No.2
ALL WEBS	2x3	DRY	No.2
EXCEPT			
DRY: SEASONED LUMBER.			

DIMENSIONS, SUPPORTS AND LOADINGS SPECIFIED BY FABRICATOR TO BE VERIFIED BY BUILDING DESIGNER									
BEARINGS									
	FACTORED	MAXIMUM FACTORED	INPUT	RECORD					
	GROSS REACTION	GROSS REACTION	BRG	BRG					
JT	VERT	HORZ	DOWN	HORZ	UPLIFT	IN-SX	IN-SX		
R	2083	0	2083	0	0	5-8	5-8		
J	2083	0	2083	0	0	5-8	5-8		
UNFACTORED REACTIONS									
	1ST LOASE	MAX/MIN. COMPONENT REACTIONS							
JT	COMBINED	SNOW	LIVE	PERM. LIVE	WIND	DEAD	SOIL		
R	1457	969 / 0	0 / 0	0 / 0	0 / 0	488 / 0	0 / 0		
J	1457	969 / 0	0 / 0	0 / 0	0 / 0	488 / 0	0 / 0		

DESIGN CRITERIA

SPECIFIED LOADS:
TOP CH. LL = 25.6 PSF
DL = 6.0 PSF
BOT CH. LL = 0.0 PSF
DL = 7.4 PSF
TOTAL LOAD = 39.0 PSF

SPACING = 24.0 IN. C/C

LOADING IN FLAT SECTION BASED ON A SLOPE OF 6.00/12

THIS TRUSS IS DESIGNED FOR RESIDENTIAL OR SMALL BUILDING REQUIREMENTS OF PART 9, NBC 2010, NBCC 2016

THIS DESIGN COMPLIES WITH:
- PART 9 OF BCBC 2018, CBC 2012, ABC 2019
- PART 9 OF CBC 2012 (2018 AMENDMENT)
- CSA 088-09, CSA 088-14
- TPIC 2011, TPIC 2014

(55% OF 31.3 P.S.F. G.S.L. PLUS 8.4 P.S.F. RAIN LOAD) EQUALS 25.6 P.S.F. SPECIFIED ROOF LIVE LOAD

ALLOWABLE DEFL.(LL) = L/360 (1.17")
CALCULATED VERT. DEFL.(LL) = L/999 (0.17")
ALLOWABLE DEFL.(TL) = L/360 (1.17")
CALCULATED VERT. DEFL.(TL) = L/999 (0.34")

CSI: TC=0.97/1.00 (D-E:1), BC=0.51/1.00 (K-L:1), WB=0.68/1.00 (H-K:1), SSI=0.34/1.00 (D-E:1)

DOL LUMBER=1.00 NAIL=1.00 LS BEND=1.10
COMP=1.10 SHEAR=1.10 TENS=1.10

COMPANION LIVE LOAD FACTOR = 1.00

TRUSS PLATE MANUFACTURER IS NOT RESPONSIBLE FOR QUALITY CONTROL IN THE TRUSS MANUFACTURING PLANT

NAIL VALUES			
PLATE GRIP(DRY)	SHEAR (PSI)	SECTION (PLI)	MAX MIN
MT20	618	354	1687 788 1987 1658

PLATE PLACEMENT TOL. = 0.250 inches

PLATE ROTATION TOL. = 5.0 Deg.

JSI GRIP = 0.87 (D) (INPUT = 0.90)
JSI METAL = 0.75 (C) (INPUT = 1.00)

PLATES (tablets in inches)				
JT	TYPE	PLATES	W	LEN Y X
B	TMWV-p	MT20	5.0	3.0 Edge 3.50
C	TMWV-l	MT20	4.0	4.0 2.00 1.75
D	TTWV-m	MT20	5.0	3.0 2.25 3.75
E	TMWV-w	MT20	2.0	4.0
F	TTWV-m	MT20	5.0	3.0 2.25 3.75
G	TMWV-l	MT20	4.0	4.0 2.00 1.75
H	TMWV-p	MT20	5.0	3.0 Edge 3.50
J	BMV-l-p	MT20	3.0	4.0
K	BMWV-l	MT20	5.0	3.0 2.50 2.00
L	BMWV-l	MT20	4.0	4.0
M	BS-l	MT20	3.0	6.0
N	BMWV-l	MT20	4.0	3.0
O	BS-l	MT20	3.0	6.0
P	BMWV-l	MT20	4.0	4.0
Q	BMWV-l	MT20	5.0	3.0 2.50 2.00
R	BMV-l-p	MT20	3.0	4.0

Edge - INDICATES REFERENCE CORNER OF PLATE TOUCHES EDGE OF CHORD.


BRACING
TOP CHORD TO BE SHEATHED OR MAX. PURLIN SPACING = 2.78 FT.
MAX. UNBRACED BOTTOM CHORD LENGTH = 10.00 FT. OR RIGID CEILING DIRECTLY APPLIED.

ALL PITCH BREAKS AND PERIMETER CORNER JOINTS MUST BE LATERALLY RESTRAINED.

LOADING


TOTAL LOAD CASES: (4)

CHORDS				WEBS			
MEMB.	MAX. FACTORED FORCE (LBS)	FACTORED VERT. LOAD (PLF)	MAX. CSI (LC)	MEMB.	MAX. FACTORED FORCE (LBS)	MAX. CSI (LC)	
FR-TO		FROM TO	LENGTH	FR-TO			
A-B	0 / 28	-91.8 -91.8	0.12 (1)	10.00	Q-C	-353 / 0	0.08 (1)
B-C	-2834 / 0	-91.8 -91.8	0.39 (1)	3.81	C-P	-210 / 0	0.13 (1)
C-D	-2887 / 0	-91.8 -91.8	0.37 (1)	3.91	P-D	0 / 246	0.08 (4)
D-E	-3060 / 0	-91.8 -91.8	0.97 (1)	2.78	D-N	0 / 844	0.19 (1)
E-F	-3060 / 0	-91.8 -91.8	0.37 (1)	3.91	N-E	-872 / 0	0.51 (1)
F-G	-2887 / 0	-91.8 -91.8	0.39 (1)	3.81	N-F	0 / 844	0.19 (1)
G-H	-2834 / 0	-91.8 -91.8	0.39 (1)	3.81	L-F	0 / 246	0.08 (4)
H-I	0 / 28	-91.8 -91.8	0.12 (1)	10.00	L-G	-210 / 0	0.13 (1)
R-B	-2018 / 0	0.0 0.0	0.20 (1)	5.94	K-G	-353 / 0	0.08 (1)
J-H	-2018 / 0	0.0 0.0	0.20 (1)	5.94	B-Q	0 / 2591	0.58 (1)
					K-H	0 / 2591	0.58 (1)
R-Q	0 / 0	-18.5 -18.5	0.10 (4)	10.00			
Q-P	0 / 2555	-18.5 -18.5	0.51 (1)	10.00			
P-O	0 / 2388	-18.5 -18.5	0.49 (1)	10.00			
O-N	0 / 2388	-18.5 -18.5	0.49 (1)	10.00			
N-M	0 / 2388	-18.5 -18.5	0.49 (1)	10.00			
M-L	0 / 2388	-18.5 -18.5	0.49 (1)	10.00			
L-K	0 / 2555	-18.5 -18.5	0.51 (1)	10.00			
K-J	0 / 0	-18.5 -18.5	0.10 (4)	10.00			



Structural component only
DWG# T-2007110

JOB NAME 408152	TRUSS NAME T43	QUANTITY 2	PLY 1	JOB DESC. GREEN PARK HOMES	TRUSS DESC.	DWG NO.
Tamarack Roof Truss, Burlington				Version 8.310 5 Oct 29 2019 Mitek Industries, Inc. Sat Apr 25 11:29:37 2020 Page 1 ID:17vF7aG0E03cRUj8X1SfKziWYK-MCzB kw3N24LBWQcg8dPpPq2FRBXuKPbiVT1ezNCOS		



LUMBER		
N. L. G. A. RULES	CHORDS	SIZE
A - D	2x4	DRY
D - F	2x4	DRY
F - I	2x4	DRY
I - B	2x4	DRY
B - H	2x4	DRY
H - O	2x4	DRY
O - M	2x4	DRY
M - J	2x4	DRY
ALL WEBS	2x3	DRY
EXCEPT		
DRY: SEASONED LUMBER.		

PLATES (tablets in inches)					
JT	TYPE	PLATES	W	LEN	Y X
B	TMVW-p	MT20	5.0	8.0	Edge 3.50
C	TMVW-t	MT20	4.0	4.0	2.00 1.75
D	TTWW-m	MT20	5.0	8.0	2.25 2.00
E	TMVW-w	MT20	2.0	4.0	
F	TTWW-m	MT20	5.0	8.0	2.25 2.00
G	TMVW-t	MT20	4.0	4.0	2.00 1.75
H	TMVW-p	MT20	5.0	8.0	Edge 3.50
J	BMV1-p	MT20	3.0	4.0	
K	BMVW-t	MT20	5.0	8.0	2.50 2.25
L	BMVW-t	MT20	4.0	4.0	
M	BS-t	MT20	3.0	8.0	
N	BMVW-w	MT20	4.0	9.0	
O	BS-t	MT20	3.0	8.0	
P	BMVW-t	MT20	4.0	4.0	
Q	BMVW-t	MT20	5.0	8.0	2.50 2.25
R	BMV1-p	MT20	3.0	4.0	

Edge - INDICATES REFERENCE CORNER OF PLATE TOUCHES EDGE OF CHORD.

DIMENSIONS, SUPPORTS AND LOADINGS SPECIFIED BY FABRICATOR TO BE VERIFIED BY BUILDING DESIGNER

BEARINGS							
JT	FACTORED GROSS REACTION	MAXIMUM FACTORED GROSS REACTION	INPUT BRG	REQD BRG			
JT	VERT	HORZ	DOWN	HORZ	UPLIFT	IN-SX	IN-SX
R	2063	0	2063	0	0	5-8	5-8
J	2063	0	2063	0	0	5-8	5-8

UNFACTORED REACTIONS							
JT	1ST LOASE COMBINED	SNOW	LIVE	PERM. LIVE	WIND	DEAD	SOIL
R	1457	969	0	0	0	488	0
J	1457	969	0	0	0	488	0

BEARING MATERIAL TO BE SPF NO.2 OR BETTER AT JOINT(S) R, J

BRACING
TOP CHORD TO BE SHEATHED OR MAX. PURLIN SPACING = 3.58 FT.
MAX. UNBRACED BOTTOM CHORD LENGTH = 10.00 FT. OR RIGID CEILING DIRECTLY APPLIED.

ALL PITCH BREAKS AND PERIMETER CORNER JOINTS MUST BE Laterally RESTRAINED.

LOADING									
TOTAL LOAD CASES: (4)									
CHORDS					WEBS				
MEMB.	MAX. FACTORED FORCE (LBS)	FACTORED VERT. LOAD (PLF)	MAX. UNBRACED LENGTH (FT)	MAX. UNBRACED LENGTH (FT)	MEMB.	MAX. FACTORED FORCE (LBS)	MAX. UNBRACED LENGTH (FT)	MAX. UNBRACED LENGTH (FT)	MAX. UNBRACED LENGTH (FT)
FR-TO					FR-TO				
A-B	0/28	-91.8	-91.8	0.12 (1)	10.00	C-C	-255/12	0.07 (1)	0.07 (1)
B-C	-2869/0	-91.8	-91.8	0.59 (1)	3.58	C-P	-435/0	0.42 (1)	0.42 (1)
C-D	-2539/0	-91.8	-91.8	0.52 (1)	3.83	P-D	0/350	0.08 (1)	0.08 (1)
D-E	-2559/0	-91.8	-91.8	0.48 (1)	3.65	D-N	0/482	0.11 (1)	0.11 (1)
E-F	-2559/0	-91.8	-91.8	0.48 (1)	3.65	N-E	-841/0	0.59 (1)	0.59 (1)
F-G	-2539/0	-91.8	-91.8	0.52 (1)	3.83	N-F	0/482	0.11 (1)	0.11 (1)
G-H	-2869/0	-91.8	-91.8	0.59 (1)	3.58	L-F	0/350	0.08 (1)	0.08 (1)
H-I	0/28	-91.8	-91.8	0.12 (1)	10.00	L-G	-435/0	0.42 (1)	0.42 (1)
R-B	-2014/0	0.0	0.0	0.20 (1)	5.95	K-G	-255/12	0.07 (1)	0.07 (1)
J-H	-2014/0	0.0	0.0	0.20 (1)	5.95	K-Q	0/2835	0.59 (1)	0.59 (1)
R-Q	0/0	-18.5	-18.5	0.15 (4)	10.00	K-H	0/2835	0.59 (1)	0.59 (1)
Q-P	0/2609	-18.5	-18.5	0.49 (1)	10.00				
P-O	0/2249	-18.5	-18.5	0.43 (1)	10.00				
O-N	0/2249	-18.5	-18.5	0.43 (1)	10.00				
N-M	0/2249	-18.5	-18.5	0.43 (1)	10.00				
M-L	0/2249	-18.5	-18.5	0.43 (1)	10.00				
L-K	0/2609	-18.5	-18.5	0.49 (1)	10.00				
K-J	0/0	-18.5	-18.5	0.15 (4)	10.00				

TOTAL WEIGHT = 2 X 145 = 289 lb

DESIGN CRITERIA		
SPECIFIED LOADS:		
TOP CH. LL	=	25.8 PSF
DL	=	6.0 PSF
BOT CH. LL	=	0.0 PSF
DL	=	7.4 PSF
TOTAL LOAD	=	39.0 PSF
SPACING	=	24.0 IN. OC

LOADING IN FLAT SECTION BASED ON A SLOPE OF 6.00/12
THIS TRUSS IS DESIGNED FOR RESIDENTIAL OR SMALL BUILDING REQUIREMENTS OF PART 9, NBC 2010, NBC 2015

THIS DESIGN COMPLIES WITH:
- PART 9 OF CBC 2015, CBC 2012, ABC 2019
- PART 9 OF OBC 2012 (2019 AMENDMENT)
- CSA 086-09, CSA 086-14
- TPIC 2011, TPIC 2014

(55% OF 31.3 P.S.F. G.S.L. PLUS 8.4 P.S.F. RAIN LOAD) EQUALS 25.8 P.S.F. SPECIFIED ROOF LIVE LOAD

ALLOWABLE DEFL. (LL) = L/360 (1.17")
CALCULATED VERT. DEFL. (LL) = L/999 (0.15")
ALLOWABLE DEFL. (TL) = L/360 (1.17")
CALCULATED VERT. DEFL. (TL) = L/999 (0.28")
CSI: TG=0.59/1.00 (G-H:1), BC=0.49/1.00 (K-L:1), WB=0.59/1.00 (B-C:1), SS=0.25/1.00 (D-E:1)
DCL LUMBER=1.00 NAIL=1.00 LBS BEND=1.10
COMP=1.10 SHEAR=1.10 TENS=1.10
COMPANION LIVE LOAD FACTOR = 1.00

TRUSS PLATE MANUFACTURER IS NOT RESPONSIBLE FOR QUALITY CONTROL IN THE TRUSS MANUFACTURING PLANT.

NAIL VALUES			
PLATE GRIP (DRY)	SHEAR (PS)	SECTION (PL)	MAX MIN
MT20	618	354	1687 788 1987 1658

PLATE PLACEMENT TOL. = 0.250 inches

PLATE ROTATION TOL. = 5.0 Deg.

JSI GRIP = 0.89 (OI (INPUT = 0.90)
JSI METAL = 0.89 (IM (INPUT = 1.00)




Structural component only
DWG# T-2007111

JOB NAME 408152	TRUSS NAME T44	QUANTITY 2	PLY 1	JOB DESC. GREEN PARK HOMES	DRWG NO.
Tamarack Roof Truss, Burlington				TRUSS DESC.	

Version 8.310 S Dec 29 2019 Mitek Industries, Inc. Sat Apr 25 11:29:38 2020 Page 1
ID:17vF7aG0E03cRUj8X1|SrkziWYK-rOXZC4xi8MCCog?oEq9eMdMA6NVEDKWyqyF1P4zNCOR

Scale = 1/8" = 1'-0"



LUMBER			
N. L. G. A. RULES	CHORDS	SIZE	LUMBER
A - D	2x4	DRY	No.2
D - E	2x4	DRY	No.2
E - G	2x4	DRY	No.2
G - H	2x4	DRY	No.2
H - K	2x4	DRY	No.2
S - B	2x4	DRY	No.2
L - J	2x4	DRY	No.2
S - Q	2x4	DRY	No.2
Q - N	2x4	DRY	No.2
N - L	2x4	DRY	No.2
ALL WEBS EXCEPT	2x3	DRY	No.2

DRY: SEASONED LUMBER.

PLATES (table in inches)

JT	TYPE	PLATES	W	LEN	Y	X
B	TMVW-p	MT20	5.0	8.0	Edge	3.50
C	TMVW-1	MT20	4.0	4.0	2.00	1.75
D	TS-1	MT20	3.0	6.0		
E	TTW-m	MT20	4.0	8.0		
F	TMVW-1	MT20	4.0	4.0		
G	TTW-m	MT20	4.0	8.0		
H	TS-1	MT20	3.0	6.0		
I	TMVW-1	MT20	4.0	4.0	2.00	1.75
J	TMVW-p	MT20	5.0	8.0	Edge	3.50
L	BMV1-p	MT20	3.0	4.0		
M	BMVW-1	MT20	5.0	8.0	2.50	2.25
N	BS-1	MT20	3.0	6.0		
O	BMVW-1	MT20	4.0	9.0		
P	BMVW-1	MT20	4.0	9.0		
Q	BS-1	MT20	3.0	6.0		
R	BMVW-1	MT20	5.0	8.0	2.50	2.25
S	BMV1-p	MT20	3.0	4.0		

Edge - INDICATES REFERENCE CORNER OF PLATE TOUCHES EDGE OF CHORD.

DIMENSIONS, SUPPORTS AND LOADINGS SPECIFIED BY FABRICATOR TO BE VERIFIED BY BUILDING DESIGNER

BEARINGS			
	FACTORED	MAXIMUM FACTORED	INPUT
	GROSS REACTION	GROSS REACTION	BRG
JT	VERT	DOWN	UP
S	2063	0	0
L	2063	0	0

UNFACTORED REACTIONS

JT	1ST LOASE	MAX/MIN. COMPONENT REACTIONS					
S	COMBINED	SNOW	LIVE	PERM. LIVE	WIND	DEAD	SOIL
L	1457	969 / 0	0 / 0	0 / 0	0 / 0	488 / 0	0 / 0

BEARING MATERIAL TO BE SPF NO.2 OR BETTER AT JOINT(S) S, L

BRACING

TOP CHORD TO BE SHEATHED OR MAX. PURLIN SPACING = 3.25 FT.
MAX. UNBRACED BOTTOM CHORD LENGTH = 10.00 FT. OR RIGID CEILING DIRECTLY APPLIED.

ALL PITCH BREAKS AND PERIMETER CORNER JOINTS MUST BE LATERALLY RESTRAINED.

1 LATERAL BRACE(S) AT 1/2 LENGTH OF C-P, F-P, F-O, I-O.

END VERTICAL(S) MUST BE SHEATHED OR HAVE BRACES AS INDICATED IN THE MAX. UNBRACED LENGTH COLUMN OF THE TABLE BELOW

LOADING

TOTAL LOAD CASES: (4)

CHORDS				WEBS			
MEMB.	MAX. FACTORED FORCE (LBS)	FACTORED VERT. LOAD (LBS)	MAX. FACTORED CSI (LC)	MEMB.	MAX. FACTORED FORCE (LBS)	MAX. FACTORED CSI (LC)	
FR-TO		FROM TO		FR-TO			
A-B	0 / 28	-91.8	-91.8 0.12 (1)	10.00	R-C	-182 / 52	0.08 (1)
B-C	-2908 / 0	-91.8	-91.8 0.83 (1)	3.25	C-P	-637 / 0	0.29 (1)
C-D	-2373 / 0	-91.8	-91.8 0.72 (1)	3.66	P-E	0 / 674	0.15 (1)
D-E	-2373 / 0	-91.8	-91.8 0.72 (1)	3.66	F-F	-222 / 0	0.11 (1)
E-F	-2100 / 0	-91.8	-91.8 0.19 (1)	4.53	F-O	-222 / 0	0.11 (1)
F-G	-2100 / 0	-91.8	-91.8 0.19 (1)	4.53	O-G	0 / 674	0.15 (1)
G-H	-2373 / 0	-91.8	-91.8 0.72 (1)	3.66	O-I	-837 / 0	0.29 (1)
H-I	-2373 / 0	-91.8	-91.8 0.72 (1)	3.66	M-I	-182 / 52	0.08 (1)
I-J	-2908 / 0	-91.8	-91.8 0.83 (1)	3.25	B-R	0 / 2849	0.60 (1)
J-K	0 / 28	-91.8	-91.8 0.12 (1)	10.00	M-J	0 / 2849	0.60 (1)
S-B	-2008 / 0	0.0	0.0 0.20 (1)	5.96			
L-J	-2008 / 0	0.0	0.0 0.20 (1)	5.96			
S-R	0 / 0	-18.5	-18.5 0.20 (4)	10.00			
R-Q	0 / 2630	-18.5	-18.5 0.52 (1)	10.00			
Q-P	0 / 2630	-18.5	-18.5 0.52 (1)	10.00			
P-O	0 / 2183	-18.5	-18.5 0.45 (1)	10.00			
O-N	0 / 2630	-18.5	-18.5 0.52 (1)	10.00			
N-M	0 / 2630	-18.5	-18.5 0.52 (1)	10.00			
M-L	0 / 0	-18.5	-18.5 0.20 (4)	10.00			

TOTAL WEIGHT = 2 X 145 = 291 lb (MRF)

DESIGN CRITERIA

SPECIFIED LOADS:
TOP CH. LL = 25.8 PSF
DL = 6.0 PSF
BOT CH. LL = 0.0 PSF
DL = 7.4 PSF
TOTAL LOAD = 39.0 PSF

SPACING = 24.0 IN. C/C

LOADING IN FLAT SECTION BASED ON A SLOPE OF 6.00/12

THIS TRUSS IS DESIGNED FOR RESIDENTIAL OR SMALL BUILDING REQUIREMENTS OF PART 9, NBC 2010, NBC 2015

THIS DESIGN COMPLIES WITH:
- PART 9 OF NBC 2010, OBC 2012, ABC 2019
- PART 9 OF OBC 2012 (2019 AMENDMENT)
- CSA 086-09, CSA 086-14
- TPIC 2011, TPIC 2014

(55 % OF 31.3 P.S.F. G.S.L. PLUS 8.4 P.S.F. RAIN LOAD) EQUALS 25.8 P.S.F. SPECIFIED ROOF LIVE LOAD

ALLOWABLE DEFL.(LL) = L/360 (1.17")
CALCULATED VERT. DEFL.(LL) = L/899 (0.14")
ALLOWABLE DEFL.(TL) = L/360 (1.17")
CALCULATED VERT. DEFL.(TL) = L/899 (0.30")

CSI: TC=0.83/1.00 (I-J-1), BC=0.52/1.00 (M-O-1),
WB=0.60/1.00 (B-R-1), SS=0.28/1.00 (I-J-1)

DOE LUMBER=1.00 NAIL=1.00 LS BEND=1.10
COMP=1.10 SHEAR=1.10 TENS=1.10

COMPANION LIVE LOAD FACTOR = 1.00

TRUSS PLATE MANUFACTURER IS NOT RESPONSIBLE FOR QUALITY CONTROL IN THE TRUSS MANUFACTURING PLANT.

NAIL VALUES
PLATE GRIP(DRY) SHEAR SECTION (PSI) (PLI)
MAX MIN MAX MIN MAX MIN
MT20 616 354 1867 788 1987 1656

PLATE PLACEMENT TOL. = 0.250 inches


PLATE ROTATION TOL. = 5.0 Deg.

JSI GRIP= 0.88 (M) (INPUT = 0.90)
JSI METAL= 0.79 (N) (INPUT = 1.00)



Structural component only
DWG# T-2007112

JOB NAME 408152	TRUSS NAME T45	QUANTITY 2	PLY 1	JOB DESC. GREEN PARK HOMES	DRWG NO.
Tamarack Roof Truss, Burlington				Version 8.310 S Oct 29 2019 Matek Industries, Inc. Sat Apr 25 11:29:39 2020 Page 1	
ID:7vF7aG0E03cRUj6X1jSkzIWYK-Ja5xPQyKvfk3Qaa_nXqtwqvHdFwMjnl2c_ayWzNCOQ				35.20 36.58 1.20	
				Scale = 1/50.0	



LUMBER			
N. L. & A. RULES	SIZE	DRY	LUMBER
CHORDS			
A - D	2x4	DRY	No.2
D - F	2x4	DRY	No.2
F - G	2x4	DRY	No.2
G - I	2x4	DRY	No.2
I - L	2x4	DRY	No.2
T - B	2x4	DRY	No.2
M - K	2x4	DRY	No.2
T - R	2x4	DRY	No.2
R - O	2x4	DRY	No.2
O - M	2x4	DRY	No.2
ALL WEBS	2x3	DRY	No.2
EXCEPT			
DRY: SEASONED LUMBER.			

BEARINGS

	FACTORED	MAXIMUM FACTORED	INPUT	REQ'D
	GROSS REACTION	GROSS REACTION	BRG	BRG
JT	VERT	HORZ	DOWN	HORZ
T	2063	0	2063	0
M	2063	0	2063	0

UNFACTORED REACTIONS

1ST LCASE	MAX/MIN	COMPONENT REACTIONS					
JT	COMBINED	SNOW	LIVE	PERM. LIVE	WIND	DEAD	SOIL
T	1457	869 / 0	0 / 0	0 / 0	0 / 0	488 / 0	0 / 0
M	1457	869 / 0	0 / 0	0 / 0	0 / 0	488 / 0	0 / 0

BEARING MATERIAL TO BE SPF NO.2 OR BETTER AT JOINT(S) T, M

BRACING

TOP CHORD TO BE SHEATHED OR MAX. PURLIN SPACING = 3.86 FT.
MAX. UNBRACED BOTTOM CHORD LENGTH = 10.00 FT. OR RIGID CEILING DIRECTLY APPLIED.

ALL PITCH BREAKS AND PERIMETER CORNER JOINTS MUST BE LATERALLY RESTRAINED.

1 LATERAL BRACE(S) AT 1/2 LENGTH OF E-Q, H-P, G-T, J-M.

END VERTICAL(S) MUST BE SHEATHED OR HAVE BRACES AS INDICATED IN THE MAX. UNBRACED LENGTH COLUMN OF THE TABLE BELOW

LOADING

TOTAL LOAD CASES: (4)

CHORDS				WEBS			
MEMB.	MAX. FACTORED FORCE (LBS)	FACTORED VERT. LOAD (PLF)	MAX. UNBRACED LENGTH (FT)	MEMB.	MAX. FACTORED FORCE (LBS)	MAX. UNBRACED LENGTH (FT)	MAX. UNBRACED LENGTH (FT)
FR-TO		FROM TO		FR-TO			
A-B	0 / 28	-91.8 -91.8	0.12 (1)	10.00	C-S	-110 / 37	0.04 (1)
B-C	0 / 19	-91.8 -91.8	0.32 (1)	10.00	S-E	0 / 276	0.06 (1)
C-D	-2759 / 0	-91.8 -91.8	0.40 (1)	3.86	E-Q	-881 / 0	0.31 (1)
D-E	-2759 / 0	-91.8 -91.8	0.40 (1)	3.86	Q-F	0 / 813	0.14 (1)
E-F	-2167 / 0	-91.8 -91.8	0.36 (1)	4.30	F-G	0 / 4	0.00 (1)
F-G	-1925 / 0	-91.8 -91.8	0.16 (1)	4.71	G-H	0 / 609	0.14 (1)
G-H	-2168 / 0	-91.8 -91.8	0.36 (1)	4.30	H-I	-682 / 0	0.31 (1)
H-I	-2760 / 0	-91.8 -91.8	0.40 (1)	3.86	I-J	0 / 278	0.06 (1)
I-J	-2760 / 0	-91.8 -91.8	0.40 (1)	3.86	J-K	-110 / 37	0.04 (1)
J-K	0 / 19	-91.8 -91.8	0.32 (1)	10.00	K-L	-3040 / 0	0.85 (1)
K-L	0 / 28	-91.8 -91.8	0.12 (1)	10.00	L-M	-3041 / 0	0.85 (1)
L-M	-326 / 0	0.0 0.0	0.03 (1)	7.81			
M-K	-326 / 0	0.0 0.0	0.03 (1)	7.81			
T-S	0 / 2536	-18.5 -18.5	0.55 (1)	10.00			
S-R	0 / 2382	-18.5 -18.5	0.53 (1)	10.00			
R-Q	0 / 2382	-18.5 -18.5	0.53 (1)	10.00			
Q-P	0 / 1924	-18.5 -18.5	0.40 (1)	10.00			
P-O	0 / 2382	-18.5 -18.5	0.53 (1)	10.00			
O-N	0 / 2382	-18.5 -18.5	0.53 (1)	10.00			
N-M	0 / 2537	-18.5 -18.5	0.56 (1)	10.00			

TOTAL WEIGHT = 2 X 151 = 302 b

DESIGN CRITERIA

SPECIFIED LOADS:
TOP CH. LL = 25.6 PSF
DL = 6.0 PSF
BOT CH. LL = 0.0 PSF
DL = 7.4 PSF
TOTAL LOAD = 39.0 PSF

SPACING = 24.0 IN. C/C

LOADING IN FLAT SECTION BASED ON A SLOPE OF 6.00/12

THIS TRUSS IS DESIGNED FOR RESIDENTIAL OR SMALL BUILDING REQUIREMENTS OF PART 9, NBC 2010, NBC 2015

THIS DESIGN COMPLIES WITH:
- PART 9 OF CBC 2018, CBC 2012, ABC 2019
- PART 9 OF CBC 2012 (2019 AMENDMENT)
- CSA 086-09, CSA 086-14
- TPIC 2011, TPIC 2014

(55% OF 31.3 P.S.F. G.S.L. PLUS 8.4 P.S.F. RAIN LOAD) EQUALS 25.6 P.S.F. SPECIFIED ROOF LIVE LOAD

ALLOWABLE DEFL. (LL) = L/360 (1.17")
CALCULATED VERT. DEFL. (LL) = L/999 (0.15")
ALLOWABLE DEFL. (TL) = L/360 (1.17")
CALCULATED VERT. DEFL. (TL) = L/999 (0.32")

CSI: TC=0.40/1.00 (H-J:1), BC=0.56/1.00 (M-N:1), WB=0.65/1.00 (J-M:1), SS=0.20/1.00 (B-C:1)

DOL LUMBER=1.00 NAIL=1.00 LS BEND=1.10 COMP=1.10 SHEAR=1.10 TENS=1.10

COMPANION LIVE LOAD FACTOR = 1.00

AUTOSOLVE HEELS OFF

TRUSS PLATE MANUFACTURER IS NOT RESPONSIBLE FOR QUALITY CONTROL IN THE TRUSS MANUFACTURING PLANT.

NAIL VALUES
PLATE GRIP(DRY) SHEAR SECTION (PS) (PL) (PL)
MAX MIN MAX MIN MAX MIN
MT20 618 354 1687 788 1987 1688


PLATE PLACEMENT TOL. = 0.250 inches

PLATE ROTATION TOL. = 5.0 Deg.

JSI GRIP = 0.89 (M) (INPUT = 0.90)
JSI METAL = 0.83 (O) (INPUT = 1.00)



Structural component only
DWG# T-2007113



LUMBER				
N. L. G. A. RULES	CHORDS	SIZE	DRY	LUMBER
A - C	2x4	DRY	No.2	SPF
C - E	2x4	DRY	No.2	SPF
E - F	2x4	DRY	No.2	SPF
L - G	2x6	DRY	No.2	SPF
G - F	2x4	DRY	No.2	SPF
L - I	2x6	DRY	No.2	SPF
I - G	2x6	DRY	No.2	SPF
ALL WEBS EXCEPT	2x3	DRY	No.2	SPF

DRY, SEASONED LUMBER.

DESIGN CONSISTS OF 2 TRUSSES BUILT SEPARATELY THEN FASTENED TOGETHER AS FOLLOWS:

CHORDS #ROWS	SURFACE SPACING (IN)	LOAD (PLF)
TOP CHORDS : (0.122'X3') SPIRAL NAILS		
A - C	12	SIDE (61.0)
C - E	12	SIDE (61.0)
E - F	12	TOP
G - F	12	TOP
L - B	12	TOP
BOTTOM CHORDS : (0.122'X3') SPIRAL NAILS		
L - I	12	SIDE (61.0)
I - G	12	TOP
WEBS : (0.122'X3') SPIRAL NAILS		
2x3	6	

NAILS TO BE DRIVEN FROM ONE SIDE ONLY.

GIRDER NAILING ASSUMES NAILED HANGERS ARE FASTENED WITH MIN. 3-0 INCH NAILS.

TOP - COMPONENTS ARE LOADED FROM THE TOP AND MUST BE PLACED ON TOP EDGE OF ALL PLIES FOR THE LOAD TO BE TRANSFERRED TO EACH PLY.

SIDE - PLF SHOWN IS THE EQUIVALENT UDL APPLIED TO ONE SIDE THAT THE CORRESPONDING NAILING PATTERN SHALL BE CAPABLE OF TRANSFERRING. REMAINING PLF MUST BE APPLIED ON THE OPPOSITE SIDE OR ON THE TOP.

DIMENSIONS, SUPPORTS AND LOADINGS SPECIFIED BY FABRICATOR TO BE VERIFIED BY BUILDING DESIGNER

BEARINGS		FACTORED	MAXIMUM FACTORED	INPUT	RECORD
JT	GROSS REACTION	GROSS REACTION	BRG	BRG	
L	2005	0	2005	0	5-8
G	1397	0	1397	0	5-8

A SUITABLE HANGER/MECHANICAL CONNECTION IS REQUIRED AT JOINT G. MINIMUM BEARING LENGTH AT JOINT G = 2-0.

UNFACTORED REACTIONS

1ST CASE	MAX/MIN. COMPONENT REACTIONS						
JT	COMBINED	SNOW	LIVE	PERM.LIVE	WIND	DEAD	SOIL
L	1412	958 / 0	0 / 0	0 / 0	0 / 0	457 / 0	0 / 0
G	985	662 / 0	0 / 0	0 / 0	0 / 0	323 / 0	0 / 0

BEARING MATERIAL TO BE SPF NO.2 OR BETTER AT JOINT(S) L.

BRACING

TOP CHORD TO BE SHEATHED OR MAX. PURLIN SPACING = 5.18 FT.
MAX. UNBRACED BOTTOM CHORD LENGTH = 10.00 FT. OR RIGID CEILING DIRECTLY APPLIED.

ALL PITCH BREAKS AND PERIMETER CORNER JOINTS MUST BE LATERALLY RESTRAINED.

LOADING

TOTAL LOAD CASES: (4)

CHORDS		WEBS	
MEMB.	MAX. FACTORED FORCE (LBS)	MEMB.	MAX. FACTORED FORCE (LBS)
FR-TO		FR-TO	
A-B	0 / 28	K-C	0 / 943
B-C	-2643 / 0	C-J	-846 / 0
C-D	-1951 / 0	J-D	-371 / 0
D-E	-1951 / 0	E-D	0 / 1047
E-F	-1405 / 0	F-E	-448 / 0
F-G	-1885 / 0	G-F	0 / 2382
G-H	-1369 / 0	H-F	0 / 1375
L-M	0 / 0		
M-N	0 / 0		
N-O	0 / 0		
O-K	0 / 0		
K-J	0 / 2389		
J-I	0 / 1243		
I-H	0 / 1243		
H-G	0 / 0		

FACTORED CONCENTRATED LOADS (LBS)

JT	LOC.	LC1	MAX.	MAX+	FACE	DIR.	TYPE	HEEL	CONN.
C	5-10-8	-320	-320	---	FRONT	VERT	TOTAL	---	C1
M	1-11-4	-25	-25	---	FRONT	VERT	TOTAL	---	C1
N	3-11-4	-25	-25	---	FRONT	VERT	TOTAL	---	C1
O	5-6-8	-1076	-1076	---	FRONT	VERT	TOTAL	---	C1

CONNECTION REQUIREMENTS

1) C1: A SUITABLE HANGER/MECHANICAL CONNECTION IS REQUIRED.

TOTAL WEIGHT = 2 X 78 = 156 LB

DESIGN CRITERIA

SPECIFIED LOADS:
TOP CH. LL = 25.8 PSF
DL = 8.0 PSF
BOT CH. LL = 0.0 PSF
DL = 7.4 PSF
TOTAL LOAD = 39.0 PSF

SPACING = 24.0 IN. C/C

LOADING IN FLAT SECTION BASED ON A SLOPE OF 6.00/12

THIS TRUSS IS DESIGNED FOR RESIDENTIAL OR SMALL BUILDING REQUIREMENTS OF PART 9, NBCC 2010, NBCC 2015

THIS DESIGN COMPLIES WITH:
- PART 9 OF CBC 2018, CBC 2012, ABC 2019
- PART 9 OF CBC 2012 (2019 AMENDMENT)
- CSA 086-09, CSA 088-14
- TPIC 2011, TPIC 2014

(5% OF 31.3 P.S.F. G.S.L. PLUS 8.4 P.S.F. RAIN LOAD) EQUALS 25.8 P.S.F. SPECIFIED ROOF LIVE LOAD

ALLOWABLE DEFL.(LL) = L/360 (0.55")
CALCULATED VERT. DEFL.(LL) = L/999 (0.03")
ALLOWABLE DEFL.(TL) = L/360 (0.55")
CALCULATED VERT. DEFL.(TL) = L/999 (0.06")

CS: TC=0.37/1.00 (B-C:1), BC=0.24/1.00 (J-K:1), WB=0.29/1.00 (B-K:1), SS=0.37/1.00 (K-L:1)

DOL LUMBER=1.00 NAIL=1.00 LS BEND=1.00
COMP=1.00 SHEAR=1.00 TENS=1.00

COMPANION LIVE LOAD FACTOR = 1.00

AUTOSOLVE RIGHT HEEL ONLY


TRUSS PLATE MANUFACTURER IS NOT RESPONSIBLE FOR QUALITY CONTROL IN THE TRUSS MANUFACTURING PLANT.

NAIL VALUES
PLATE GRIP(DRY) SHEAR SECTION (PSI) (PL) (PL)
MAX MIN MAX MIN MAX MIN
MT20 618 354 1607 788 1987 1656

PLATE PLACEMENT TOL. = 0.250 inches

PLATE ROTATION TOL. = 5.0 Deg.

JSI GRIP= 0.80 (B) (INPUT = 0.90)
JSI METAL= 0.32 (B) (INPUT = 1.00)



Structural component only
DWG# T-2007115 1/2


CONTINUED ON PAGE 2

JOB NAME 408152	TRUSS NAME T47	QUANTITY 1	PLY 2	JOB DESC. GREEN PARK HOMES	DRWG NO.
Tamarack Roof Truss, Burlington				TRUSS DESC.	

Version 8.310 S Oct 29 2019 Mittek Industries, Inc. Sat Apr 25 11:29:42 2020 Page 2
 ID:17vF?aG0E03cRUj6X1S/kziWYK-9m42R CCaleHIJZTIDaWTXzGSvYZDD8kZDEYrzNCON

PLATES (table is in inches)


JT	TYPE	PLATES	W	LEN	Y	X
B	TMVW-p	MT20	4.0	8.0	1.00	3.00
C	TTWW-m	MT20	5.0	8.0	2.25	2.00
D	TMW-w	MT20	2.0	4.0		
E	TTWW-m	MT20	5.0	8.0	2.25	2.00
F	TMVW-p	MT20	4.0	4.0	1.50	2.00
G	BMV1-p	MT20	3.0	8.0		
H	BMWW-t	MT20	5.0	8.0		
I	BS-t	MT20	5.0	8.0		
J	BMWWW-t	MT20	5.0	8.0		
K	BMWW-t	MT20	5.0	8.0		
L	BMV1-p	MT20	3.0	8.0		



Structural component only
 DWG# T-2007115 *3/2*

JOB NAME	TRUSS NAME	QUANTITY	PLY	JOB DESC.	DRWG NO.
408152	T48	1	1	GREEN PARK HOMES	
Tamarack Roof Truss, Burlington				TRUSS DESC.	

Version 8.310 S Oct 29 2019 MTek Industries, Inc. Sat Apr 25 11:29:43 2020 Page 1
ID:17VF?aG0E03cRUJ6X1jSkziWYK-BMKSF?QzuvVvRu0Nkp3g47HsGXldlzDyo5izNCOM



LUMBER			
N. L. G. A. RULES			
CHORDS	SIZE	LUMBER	DESCR.
A - D	2x4	DRY No.2	SPF
D - E	2x4	DRY No.2	SPF
E - F	2x4	DRY No.2	SPF
K - B	2x4	DRY No.2	SPF
G - F	2x4	DRY No.2	SPF
K - I	2x4	DRY No.2	SPF
I - G	2x4	DRY No.2	SPF
ALL WEBS	2x3	DRY No.2	SPF
EXCEPT			

DRY: SEASONED LUMBER.

PLATES (table in inches)

JT	TYPE	PLATES	W	LEN	Y	X
B	TMV-p	MT20	3.0	4.0		
C	TMVW-1	MT20	4.0	4.0	2.00	1.75
D	TTW-m	MT20	4.0	4.0		
E	TTW-m	MT20	5.0	6.0	2.25	2.00
F	TMVW-p	MT20	4.0	4.0	1.50	2.00
G	BMV1-p	MT20	3.0	4.0		
H	BMVW-1	MT20	4.0	6.0		
I	BS-1	MT20	3.0	6.0		
J	BMVW-1	MT20	4.0	9.0		
K	BMVW-1	MT20	4.0	6.0		

DIMENSIONS, SUPPORTS AND LOADINGS SPECIFIED BY FABRICATOR TO BE VERIFIED BY BUILDING DESIGNER

BEARINGS		FACTORED		MAXIMUM FACTORED		INPUT		REQD	
JT	VERT	GROSS REACTION	SNOW	GROSS REACTION	DOWN	BRG	IN-SX	BRG	IN-SX
K	1039	0	1039	0	0	5-8	5-8		
G	914	0	914	0	0	MECHANICAL	MECHANICAL		

A SUITABLE HANGER/MECHANICAL CONNECTION IS REQUIRED AT JOINT G. MINIMUM BEARING LENGTH AT JOINT G = 3-8.

UNFACTORED REACTIONS

JT	COMBINED	SNOW	LIVE	PERM	LIVE	WIND	DEAD	SOIL
K	732	494 / 0	0 / 0	0 / 0	0 / 0	0 / 0	238 / 0	0 / 0
G	646	424 / 0	0 / 0	0 / 0	0 / 0	0 / 0	222 / 0	0 / 0

BEARING MATERIAL TO BE SPF NO.2 OR BETTER AT JOINT(S) K

BRACING

TOP CHORD TO BE SHEATHED OR MAX. PURLIN SPACING = 6.12 FT.
MAX. UNBRACED BOTTOM CHORD LENGTH = 10.00 FT. OR RIGID CEILING DIRECTLY APPLIED.
ALL PITCH BREAKS AND PERIMETER CORNER JOINTS MUST BE LATERALLY RESTRAINED.

LOADING

TOTAL LOAD CASES: (4)

CHORDS		FACTORED			WEBS			
MEMB.	FORCE (LBS)	VERT. LOAD	LC1	MAX. CSI (LC)	MAX. UNBRAC LENGTH	MEMB.	MAX. FORCE (LBS)	MAX. FACTORED CSI (LC)
FR-TO		FROM	TO			FR-TO		
A-B	0 / 28	-91.8	-91.8	0.12 (1)	10.00	C-J	-232 / 0	0.10 (1)
B-C	0 / 18	-91.8	-91.8	0.22 (1)	10.00	J-D	0 / 134	0.03 (4)
C-D	-916 / 0	-91.8	-91.8	0.18 (1)	8.24	J-E	0 / 152	0.03 (1)
D-E	-808 / 0	-91.8	-91.8	0.10 (1)	8.25	H-E	-163 / 0	0.06 (1)
E-F	-821 / 0	-91.8	-91.8	0.42 (1)	6.12	K-C	-1221 / 0	0.47 (1)
K-B	-265 / 0	0.0	0.0	0.03 (1)	7.81	H-F	0 / 769	0.17 (1)
G-F	-866 / 0	0.0	0.0	0.10 (1)	7.81			
K-J	0 / 993	-18.5	-18.5	0.32 (4)	10.00			
J-I	0 / 731	-18.5	-18.5	0.31 (4)	10.00			
I-H	0 / 731	-18.5	-18.5	0.31 (4)	10.00			
H-G	0 / 0	-18.5	-18.5	0.15 (4)	10.00			

TOTAL WEIGHT = 68 lb [M]F

DESIGN CRITERIA

SPECIFIED LOADS:
TOP CH. LL = 25.6 PSF
DL = 6.0 PSF
BOT CH. LL = 0.0 PSF
DL = 7.4 PSF
TOTAL LOAD = 39.0 PSF

SPACING = 24.0 IN. OC

LOADING IN FLAT SECTION BASED ON A SLOPE OF 6.00/12

THIS TRUSS IS DESIGNED FOR RESIDENTIAL OR SMALL BUILDING REQUIREMENTS OF PART 9, NBCC 2010, NBCC 2015

THIS DESIGN COMPLIES WITH:
- PART 9 OF CBC 2018, CBC 2012, ABC 2019
- PART 9 OF CBC 2012 (2019 AMENDMENT)
- CSA 086-09, CSA 086-14
- TPIC 2011, TPIC 2014

(55% OF 31.3 P.S.F. G.S.L. PLUS 8.4 P.S.F. RAIN LOAD) EQUALS 25.6 P.S.F. SPECIFIED ROOF LIVE LOAD

ALLOWABLE DEFL.(LL) = L/360 (0.55")
CALCULATED VERT. DEFL.(LL) = 1/999 (0.02")
ALLOWABLE DEFL.(TL) = L/360 (0.55")
CALCULATED VERT. DEFL.(TL) = 1/999 (0.13")

CSI TC=0.42/1.00 (E-F:1), BC=0.32/1.00 (J-K:4), WS=0.47/1.00 (C-K:1), SS=0.19/1.00 (E-F:1)

DOL LUMBER=1.00 NAIL=1.00 LS BEND=1.10
COMP=1.10 SHEAR=1.10 TENS=1.10

COMPANION LIVE LOAD FACTOR = 1.00


TRUSS PLATE MANUFACTURER IS NOT RESPONSIBLE FOR QUALITY CONTROL IN THE TRUSS MANUFACTURING PLANT.

NAIL VALUES
PLATE GRIP(DRY) SHEAR SECTION
(PSI) (PLI) (PLI)
MAX MIN MAX MIN MAX MIN
MT20 618 354 1867 788 1867 1868

PLATE PLACEMENT TOL. = 0.250 inches


PLATE ROTATION TOL. = 5.0 Deg.

JSI GRIP = 0.87 (C) (INPUT = 0.90)
JSI METAL = 0.41 (C) (INPUT = 1.00)



Structural component only
DWG# T-2007116

JOB NAME	TRUSS NAME	QUANTITY	PLY	JOB DESC.	DRWG NO.
408152	T49	1	1	GREEN PARK HOMES	
Tamarack Roof Truss, Burlington		TRUSS DESC.			



LUMBER			
N. L. & A. RULES	SIZE	LUMBER	DESCR.
CHORDS			
A - D	2x4	DRY	No.2
D - F	2x4	DRY	No.2
K - B	2x4	DRY	No.2
G - F	2x4	DRY	No.2
K - I	2x4	DRY	No.2
I - G	2x4	DRY	No.2
ALL WEBS EXCEPT	2x3	DRY	No.2

DRY, SEASONED LUMBER.

PLATES (table is in inches)					
JT	TYPE	PLATES	W	LEN	Y X
B	TMW-1	MT20	4.0	8.0	2.00 3.00
C	TMW-1	MT20	4.0	4.0	2.00 1.75
D	TTW-p	MT20	4.0	4.0	
E	TMW-1	MT20	4.0	6.0	
F	TMV-p	MT20	3.0	4.0	
G	BMW-1	MT20	4.0	4.0	
H	BMW-1	MT20	4.0	9.0	
I	BS-1	MT20	3.0	6.0	
J	BMW-1	MT20	4.0	6.0	
K	BMV-1	MT20	3.0	4.0	

DIMENSIONS, SUPPORTS AND LOADINGS SPECIFIED BY FABRICATOR TO BE VERIFIED BY BUILDING DESIGNER							
<u>BEARINGS</u>							
	FACTORED GROSS REACTION		MAXIMUM FACTORED GROSS REACTION		INPUT BRG	REQD BRG	
JT	VERT	HORZ	DOWN	HORZ	UPLIFT	IN-SX	IN-SX
K	1039	0	1039	0	0	5-8	5-8
G			914	0	0	MECHANICAL	

A SUITABLE HANGER/MECHANICAL CONNECTION IS REQUIRED AT JOINT G. MINIMUM BEARING LENGTH AT JOINT G = 3-8.

UNFACTORED REACTIONS							
JT	1ST CASE COMBINED	MAX/MIN. COMPONENT REACTIONS	SNOW	LIVE	PERM. LIVE	WIND	DEAD
K	732	494 / 0	0 / 0	0 / 0	0 / 0	0 / 0	238 / 0
G	646	424 / 0	0 / 0	0 / 0	0 / 0	0 / 0	222 / 0

BEARING MATERIAL TO BE SPF NO.2 OR BETTER AT JOINT(S) K

BRACING

TOP CHORD TO BE SHEATHED OR MAX. PURLIN SPACING = 5.66 FT.

MAX. UNBRACED BOTTOM CHORD LENGTH = 10.00 FT OR RIGID CEILING DIRECTLY APPLIED.

ALL PITCH BREAKS AND PERIMETER CORNER JOINTS MUST BE Laterally RESTRAINED.

LOADING							
TOTAL LOAD CASES: (4)							
CHORDS							
MEMB.	MAX. FACTORED FORCE (LBS)	FACTORED VERT. LOAD (PLF)	MAX. UNBRACED LENGTH (LC)	MAX. FACTORED FORCE (LBS)	MEMB.	MAX. FACTORED FORCE (LBS)	MAX. UNBRACED LENGTH (LC)
FR-TO		FROM TO			FR-TO		
A-B	0 / 28	-91.8 -91.8	0.12 (1)	10.00	J-C	-114 / 23	0.02 (1)
B-C	-1135 / 0	-91.8 -91.8	0.28 (1)	5.68	C-H	-418 / 0	0.22 (1)
C-D	-799 / 0	-91.8 -91.8	0.25 (1)	8.25	H-D	0 / 407	0.09 (1)
D-E	-793 / 0	-91.8 -91.8	0.15 (1)	8.25	H-E	-39 / 37	0.02 (1)
E-F	0 / 17	-91.8 -91.8	0.19 (1)	10.00	B-J	0 - 1051	0.24 (1)
K-B	-998 / 0	0.0 0.0	0.10 (1)	7.81	E-G	-1028 / 0	0.44 (1)
G-F	-129 / 0	0.0 0.0	0.02 (1)	7.81			
K-J	0 / 0	-18.5 -18.5	0.10 (4)	10.00			
J-I	0 / 1034	-18.5 -18.5	0.29 (4)	10.00			
I-H	0 / 1034	-18.5 -18.5	0.29 (4)	10.00			
H-G	0 / 722	-18.5 -18.5	0.26 (4)	10.00			

DESIGN CRITERIA	
SPECIFIED LOADS:	
TOP CH. LL = 25.6 PSF	
DL = 6.0 PSF	
BOT CH. LL = 0.0 PSF	
DL = 7.4 PSF	
TOTAL LOAD = 39.0 PSF	

SPACING = 24.0 IN. C/C

THIS TRUSS IS DESIGNED FOR RESIDENTIAL OR SMALL BUILDING REQUIREMENTS OF PART 9, NBC 2010, NBCC 2015

THIS DESIGN COMPLIES WITH:

- PART 9 OF BCBC 2018, OBC 2012, ABC 2019
- PART 9 OF OBC 2012 (2019 AMENDMENT)
- CSA 088-09, CSA 088-14
- TPIC 2011, TPIC 2014

(55% OF 31.3 P.S.F. G.S.L. PLUS 8.4 P.S.F. RAIN LOAD) EQUALS 25.6 P.S.F. SPECIFIED ROOF LIVE LOAD

ALLOWABLE DEFL.(LL) = L/360 (0.55")

CALCULATED VERT. DEFL.(LL) = L/999 (0.03")

ALLOWABLE DEFL.(TL) = L/360 (0.55")

CALCULATED VERT. DEFL.(TL) = L/999 (0.10")

CSI: TC=0.28/1.00 (B-C:1), BC=0.29/1.00 (H-J:4), WB=0.44/1.00 (E-G:1), SS=0.19/1.00 (B-C:1)

DOL LUMBER=1.00 NAIL=1.00 LS BEND=1.10 COMP=1.10 SHEAR=1.10 TENS=1.10

COMPANION LIVE LOAD FACTOR = 1.00

TRUSS PLATE MANUFACTURER IS NOT RESPONSIBLE FOR QUALITY CONTROL IN THE TRUSS MANUFACTURING PLANT.

NAIL VALUES

PLATE GRIP(DRY) SHEAR SECTION (PSI) (PLI) (PLI)

MAX MIN MAX MIN MAX MIN


MT20 618 354 1667 788 1987 1658

PLATE PLACEMENT TOL. = 0.250 inches

PLATE ROTATION TOL. = 5.0 Deg.

JSI GRIP = 0.84 (G) (INPUT = 0.90)

JSI METAL = 0.36 (I) (INPUT = 1.00)



Structural component only.
DWG# T-2007117


PLATES (table is in inches)					
JT	TYPE	PLATES	W	LEN	Y X
B	TMVW-p	MT20	4.0	4.0	1.50 2.00
C	TTWW-m	MT20	5.0	6.0	2.00 2.00
D	TTW-m	MT20	4.0	4.0	
E	TMVW-p	MT20	4.0	4.0	1.50 2.00
G	BMV1+p	MT20	3.0	4.0	
H	BMVWW-t	MT20	4.0	9.0	
I	BMVW-t	MT20	4.0	8.0	
J	BMV1+p	MT20	3.0	4.0	

CHORDS				WEBS			
MEMB.	MAX. FACTORED FORCE (LBS)	FACTORED VERT. LOAD LC1 (PLF)	MAX CSI (LC)	MAX. UNBRAC	MEMB.	MAX. FACTORED FORCE (LBS)	MAX CSI (LC)
FR-TO		FROM TO		LENGTH FR-TO			
A-B	0 / 28	-91.8	-91.8 0.13 (1)	10.00	I-C	-121 / 32	0.02 (1)
B-C	-837 / 0	-91.8	-91.8 0.15 (1)	8.25	C-H	0 / 2	0.00 (4)
C-K	-743 / 0	-91.8	-91.8 0.50 (1)	8.09	H-D	-116 / 34	0.02 (1)
L-D	-743 / 0	-91.8	-91.8 0.50 (1)	8.09	B-I	0 / 778	0.19 (1)
D-E	-844 / 0	-91.8	-91.8 0.50 (1)	6.09	H-E	0 / 783	0.19 (1)
E-F	0 / 28	-91.8	-91.8 0.13 (1)	10.00			
J-B	-848 / 0	0.0	0.0 0.09 (1)	7.81			
G-E	-844 / 0	0.0	0.0 0.09 (1)	7.81			
J-M	0 / 0	-18.5	-18.5 0.08 (4)	10.00			
M-I	0 / 0	-18.5	-18.5 0.08 (4)	10.00			
K-N	0 / 742	-18.5	-18.5 0.18 (1)	10.00			
N-O	0 / 742	-18.5	-18.5 0.18 (1)	10.00			
O-H	0 / 742	-18.5	-18.5 0.18 (1)	10.00			
H-P	0 / 0	-18.5	-18.6 0.06 (4)	10.00			
P-G	0 / 0	-18.5	-18.5 0.08 (4)	10.00			


FACTORED CONCENTRATED LOADS (LBS)									
JT	LOC.	LC1	MAX-	MAX+	FACE	DIR.	TYPE	HEEL	CON
C	2-10-8	-119	-119	---	FRONT	VERT	TOTAL	---	CH
D	8-0-8	-119	-119	---	FRONT	VERT	TOTAL	---	CH
H	7-11-2	-5	-5	---	FRONT	VERT	TOTAL	---	CH
I	2-11-4	-5	-5	---	FRONT	VERT	TOTAL	---	CH
K	3-11-2	-7	-7	---	FRONT	VERT	TOTAL	---	CH
L	5-11-2	-7	-7	---	FRONT	VERT	TOTAL	---	CH
M	2-0-12	-5	-5	---	FRONT	VERT	TOTAL	---	CH
N	3-11-2	-5	-5	---	FRONT	VERT	TOTAL	---	CH
O	5-11-2	-5	-5	---	FRONT	VERT	TOTAL	---	CH
P	8-10-4	-5	-5	---	FRONT	VERT	TOTAL	---	CH

1) C1: A SUITABLE HANGER/MECHANICAL CONNECTION IS REQUIRED.

JSI GRIP= 0.77 (E) (INPUT = 0.90)
JSI METAL= 0.28 (E) (INPUT = 1.00)



JOB NAME	TRUSS NAME	QUANTITY	PLY	JOB DESC.	DRWG NO.
408152	T51	1	1	GREEN PARK HOMES	
Tamarack Roof Truss, Burlington		TRUSS DESC.		Version 8.310 S Oct 29 2019 MITek Industries, Inc. Sat Apr 26 11:29:46 2020 Page 1	



LUMBER	N. L. G. A. RULES	CHORDS	SIZE	LUMBER	DESCR.
A - C	2x4	DRY	No.2	SPF	
C - D	2x4	DRY	No.2	SPF	
D - F	2x4	DRY	No.2	SPF	
J - B	2x4	DRY	No.2	SPF	
G - E	2x4	DRY	No.2	SPF	
J - G	2x4	DRY	No.2	SPF	

ALL WEBS 2x3 DRY No.2 SPF

DRY: SEASONED LUMBER.

PLATES (table in inches)

JT	TYPE	PLATES	W	LEN	Y	X
B	TMW-1	MT20	4.0	4.0	2.00	1.25
C	TTW-m	MT20	5.0	6.0	2.25	2.25
D	TTW-m	MT20	4.0	4.0		
E	TMW-1	MT20	4.0	4.0	2.00	1.25
G	BMV1-p	MT20	3.0	4.0		
H	BMWW-1	MT20	4.0	6.0	2.00	1.50
I	BMWW-1	MT20	4.0	4.0		
J	BMV1-p	MT20	3.0	4.0		

DIMENSIONS, SUPPORTS AND LOADINGS SPECIFIED BY FABRICATOR TO BE VERIFIED BY BUILDING DESIGNER

BEARINGS	FACTORED	MAXIMUM FACTORED	INPUT	RECORD
JT	GROSS REACTION	GROSS REACTION	BRG	BRG
J	VERT	DOWN	0	0
J	HORZ	HORZ	0	0
G	VERT	DOWN	0	0
G	HORZ	HORZ	0	0

A SUITABLE HANGER/MECHANICAL CONNECTION IS REQUIRED AT JOINT J. MINIMUM BEARING LENGTH AT JOINT J = 1.8.

UNFACTORED REACTIONS

1ST LCASE	MAX/MIN. COMPONENT REACTIONS
JT	COMBINED
J	511 349/0
G	511 349/0

BEARING MATERIAL TO BE SPF NO.2 OR BETTER AT JOINT(S) G

BRACING

TOP CHORD TO BE SHEATHED OR MAX. PURLIN SPACING = 6.25 FT.
MAX. UNBRACED BOTTOM CHORD LENGTH = 10.00 FT OR RIGID CEILING DIRECTLY APPLIED.

ALL PITCH BREAKS AND PERIMETER CORNER JOINTS MUST BE Laterally RESTRAINED.

LOADING

TOTAL LOAD CASES: (4)

CHORDS	MAX. FACTORED	FACTORED	WEBS	MAX. FACTORED
MEMB.	FORCE (LBS)	VERT. LOAD LC1 (LBS)	MEMB.	FORCE (LBS)
FR-TO	FROM TO	FROM TO	FR-TO	FROM TO
A-B	0/28	-91.8 -91.8 0.12 (1)	I-C	-78/18 0.02 (1)
B-C	-435/0	-91.8 -91.8 0.28 (1)	C-H	-4/0 0.00 (1)
C-D	-388/0	-91.8 -91.8 0.02 (1)	H-D	-82/19 0.03 (1)
D-E	-434/0	-91.8 -91.8 0.28 (1)	B-I	0/415 0.09 (1)
E-F	0/28	-91.8 -91.8 0.12 (1)	H-E	0/414 0.09 (1)
J-B	-688/0	0.0 0.0 0.08 (1)		
G-E	-688/0	0.0 0.0 0.08 (1)		
J-I	0/0	-18.5 -18.5 0.10 (4)		
I-H	0/387	-18.5 -18.5 0.14 (4)		
H-G	0/0	-18.5 -18.5 0.10 (4)		

DESIGN CRITERIA

SPECIFIED LOADS:
TOP CH. LL = 25.8 PSF
DL = 6.0 PSF
BOT CH. LL = 0.0 PSF
DL = 7.4 PSF
TOTAL LOAD = 39.0 PSF

SPACING = 24.0 IN. C/C

LOADING IN FLAT SECTION BASED ON A SLOPE OF 5.00/12

THIS TRUSS IS DESIGNED FOR RESIDENTIAL OR SMALL BUILDING REQUIREMENTS OF PART 9, NBC 2010, NBC 2015

THIS DESIGN COMPLIES WITH:
- PART 9 OF CBC 2018, CBC 2012, ABC 2019
- PART 9 OF CBC 2012 (2019 AMENDMENT)
- CSA 088-09, CSA 088-14
- TPIC 2011, TPIC 2014

(55 % OF 31.3 P.S.F. G.S.L. PLUS 8.4 P.S.F. RAIN LOAD) EQUALS 25.8 P.S.F. SPECIFIED ROOF LIVE LOAD

ALLOWABLE DEFL.(LL) = L/360 (0.38")
CALCULATED VERT. DEFL.(LL) = L/999 (0.01")
ALLOWABLE DEFL.(TL) = L/360 (0.38")
CALCULATED VERT. DEFL.(TL) = L/999 (0.02")

CSI: TC=0.28/1.00 (B-C:1), BC=0.14/1.00 (H-I:4), WB=0.08/1.00 (B-C:1), SSI=0.18/1.00 (B-C:1)

DOL LUMBER=1.00 NAIL=1.00 LBS BEND=1.10
COMP=1.10 SHEAR=1.10 TENS=1.10

COMPANION LIVE LOAD FACTOR = 1.00


TRUSS PLATE MANUFACTURER IS NOT RESPONSIBLE FOR QUALITY CONTROL IN THE TRUSS MANUFACTURING PLANT.

NAIL VALUES
PLATE GRIP(DRY) SHEAR SECTION
(PSI) (PLI) (PLI)
MAX MIN MAX MIN MAX MIN
MT20 618 354 1867 788 1987 1656

PLATE PLACEMENT TOL. = 0.250 inches

PLATE ROTATION TOL. = 5.0 Deg.

JSI GRIP = 0.68 (B) (INPUT = 0.90)
JSI METAL = 0.22 (B) (INPUT = 1.00)




Structural component only
DWG# T-2007119

JOB NAME	TRUSS NAME	QUANTITY	PLY	JOB DESC.	GREEN PARK HOMES	DRWG NO.
408152	T52	1	1	TRUSS DESC.		

Tamarack Roof Truss, Burlington

Version 9.310 S Oct 29 2019 Mitek Industries, Inc. Sat Apr 25 11:29:47 2020 Page 1
ID: i7vF?ag0E03cRUj6X1jSrkzWYK-47az592L17LwO3BXFDpIDWEm8TgSEVliurw?E3zNCOI



Scale = 1:10.0

LUMBER			
N. L. G. A. RULES	CHORDS	SIZE	LUMBER
F - A	2x4	DRY	No.2
A - C	2x4	DRY	No.2
D - C	2x4	DRY	No.2
F - D	2x4	DRY	No.2
ALL WEBS	2x3	DRY	No.2
DRY, SEASONED LUMBER.			

PLATES (table in inches)					
JT	TYPE	PLATES	W	LEN	Y X
A	TMVW-1	MT20	4.0	6.0	
B	TMVW-1	MT20	2.0	4.0	
C	TMVW-1	MT20	4.0	6.0	
D	BMV1-p	MT20	3.0	4.0	
E	BMVW-1	MT20	4.0	6.0	
F	BMV1-p	MT20	3.0	4.0	

DIMENSIONS, SUPPORTS AND LOADINGS SPECIFIED BY FABRICATOR TO BE VERIFIED BY BUILDING DESIGNER

PROVIDE ADEQUATE DRAINAGE TO PREVENT PONDING

BEARINGS

	FACTORED	MAXIMUM FACTORED	INPUT	RECORD
	GROSS REACTION	GROSS REACTION	BRG	BRG
JT	VERT	HORZ	DOWN	HORZ
F	820	0	820	0
D	820	0	820	0

UNFACTORED REACTIONS

JT	COMBINED	SNOW	LIVE	PERM.LIVE	WIND	DEAD	SOIL
F	448	239 / 0	0 / 0	0 / 0	0 / 0	209 / 0	0 / 0
D	448	239 / 0	0 / 0	0 / 0	0 / 0	209 / 0	0 / 0

BEARING MATERIAL TO BE SPF NO.2 OR BETTER AT JOINT(S) F, D

BRACING

TOP CHORD TO BE SHEATHED OR MAX. PURLINE SPACING = 5.52 FT.
MAX. UNBRACED BOTTOM CHORD LENGTH = 10.00 FT. OR RIGID CEILING DIRECTLY APPLIED.

ALL PITCH BREAKS AND PERIMETER CORNER JOINTS MUST BE LATERALLY RESTRAINED.

LOADING

TOTAL LOAD CASES: (4)

CHORDS				WEBS			
MEMB.	MAX. FACTORED FORCE (LBS)	FACTORED VERT. LOAD (PLF)	MAX. UNBRACED LENGTH (FT)	MEMB.	MAX. FACTORED FORCE (LBS)	MAX. UNBRACED LENGTH (FT)	MEMB.
F-A	-583 / 0	0.0	0.0	0.11 (1)	7.81	A-E	0 / 792
A-B	-585 / 0	-114.3	-114.3	0.55 (1)	5.52	E-B	-858 / 0
B-C	-585 / 0	-114.3	-114.3	0.55 (1)	5.52	E-C	0 / 792
D-C	-583 / 0	0.0	0.0	0.11 (1)	7.81		
F-E	0 / 0	-18.5	-18.5	0.13 (4)	10.00		
E-D	0 / 0	-18.5	-18.5	0.13 (4)	10.00		

TOTAL WEIGHT = 36 LB (MTR)

DESIGN CRITERIA

SPECIFIED LOADS:
TOP CH. LL = 25.6 PSF
DL = 15.0 PSF
BOT CH. LL = 0.0 PSF
DL = 7.4 PSF
TOTAL LOAD = 48.0 PSF

SPACING = 24.0 IN. C/C

LOADING IN FLAT SECTION BASED ON A SLOPE OF 0.00/12

THIS TRUSS IS DESIGNED FOR RESIDENTIAL OR SMALL BUILDING REQUIREMENTS OF PART 9, NBCC 2010, NBCC 2015

THIS DESIGN COMPLIES WITH:
- PART 9 OF BCBC 2018, OBC 2012, ABC 2019
- PART 9 OF OBC 2012 (2019 AMENDMENT)
- CSA 088-09, CSA 088-14
- TPIC 2011, TPIC 2014

(55% OF 31.3 P.S.F. G.S.L. PLUS 8.4 P.S.F. RAIN LOAD) EQUALS 25.6 P.S.F. SPECIFIED ROOF LIVE LOAD

ALLOWABLE DEFL. (LL) = L/360 (0.31")
CALCULATED VERT. DEFL. (LL) = L/999 (0.01")
ALLOWABLE DEFL. (TL) = L/360 (0.31")
CALCULATED VERT. DEFL. (TL) = L/999 (0.03")

CSI: TC=0.55/1.00 (B-C:1), BC=0.13/1.00 (E-F:4), WB=0.24/1.00 (A-E:1), SS=0.34/1.00 (A-B:1)

DOL LUMBER=1.00 NAIL=1.00 LS BEND=1.10 COMP=1.10 SHEAR=1.10 TENS= 1.10

COMPANION LIVE LOAD FACTOR = 1.00
FLAT ROOF FACTOR = 0.75


TRUSS PLATE MANUFACTURER IS NOT RESPONSIBLE FOR QUALITY CONTROL IN THE TRUSS MANUFACTURING PLANT.

NAIL VALUES
PLATE GRIP (DRY) SHEAR SECTION
(PSI) (PLI) (PLI)
MAX MIN MAX MIN MAX MIN
MT20 818 354 1687 788 1987 1656

PLATE PLACEMENT TOL. = 0.25 inches

PLATE ROTATION TOL. = 5.0 Deg.

JSI GRIP= 0.61 (A) (INPUT = 0.99)
JSI METAL= 0.24 (A) (INPUT = 1.00)




Structural component only
DWG# T-2007120

JOB NAME 408152	TRUSS NAME G52	QUANTITY 1	PLY 1	JOB DESC. GREEN PARK HOMES	TRUSS DESC.	DRWG NO.
--------------------	-------------------	---------------	----------	-------------------------------	-------------	----------

Tamarack Roof Truss, Burlington

Version 8.310 3 Oct 29 2019 Mitek Industries, Inc. Sat Apr 25 11:29:28 2020 Page 1
ID:7vF?aG0E03cRU6X1jSrkzWYK-7Twn6pQVHydc8EteizlyWyePpDihyU4WOpV3izNCOB



LUMBER			
N. L. G. A. RULES	CHORDS	SIZE	LUMBER
L - A	2x4	DRY	No.2
A - F	2x4	DRY	No.2
G - F	2x4	DRY	No.2
L - G	2x4	DRY	No.2
ALL WEBS	2x3	DRY	No.2
ALL GABLE WEBS	2x3	DRY	No.2
DRY: SEASONED LUMBER.			
GABLE STUDS SPACED AT 2'-0" O.C.			

DIMENSIONS, SUPPORTS AND LOADINGS SPECIFIED BY FABRICATOR TO BE VERIFIED BY BUILDING DESIGNER
PROVIDE ADEQUATE DRAINAGE TO PREVENT PONDING
BEARINGS
 THIS TRUSS DESIGNED FOR CONTINUOUS BEARINGS.
 THIS TRUSS REQUIRES RIGID SHEATHING ON EXPOSED FACE.
 BEARING MATERIAL TO BE SPF NO.2 OR BETTER AT JOINT(S)
BRACING
 TOP CHORD TO BE SHEATHED OR MAX. PURLIN SPACING = 10.00 FT.
 MAX. UNBRACED BOTTOM CHORD LENGTH = 10.00 FT OR RIGID CEILING DIRECTLY APPLIED.
 ALL PITCH BREAKS AND PERIMETER CORNER JOINTS MUST BE Laterally RESTRAINED.

LOADING

TOTAL LOAD CASES: (4)

CHORDS				WEBS			
MEMB.	MAX. FACTORED FORCE (LBS)	VERT. LOAD (PLF)	MAX. CSI (LC)	MEMB.	MAX. FACTORED FORCE (LBS)	MAX. CSI (LC)	UNBRACED LENGTH FR-TO
FR-TO		FROM TO		FR-TO			
L-A	-101/0	0.0 0.0	0.03 (1)	7.81	K-B	-245/0	0.08 (1)
A-B	-8/0	-114.3 -114.3	0.08 (1)	10.00	J-C	-224/0	0.05 (1)
B-C	-8/0	-114.3 -114.3	0.08 (1)	10.00	I-D	-237/0	0.05 (1)
C-D	-8/0	-114.3 -114.3	0.07 (1)	10.00	H-E	-188/0	0.04 (1)
D-E	-8/0	-114.3 -114.3	0.07 (1)	10.00			
E-F	-8/0	-114.3 -114.3	0.05 (1)	10.00			
G-F	-84/0	0.0 0.0	0.02 (1)	7.81			
L-K	0/8	-18.5 -18.5	0.02 (4)	10.00			
K-J	0/8	-18.5 -18.5	0.02 (4)	10.00			
J-I	0/8	-18.5 -18.5	0.02 (4)	10.00			
I-H	0/8	-18.5 -18.5	0.02 (4)	10.00			
H-G	0/8	-18.5 -18.5	0.02 (1)	10.00			

DESIGN CRITERIA

SPECIFIED LOADS:
 TOP CH. LL = 25.6 PSF
 DL = 15.0 PSF
 BOT CH. LL = 0.0 PSF
 DL = 7.4 PSF
 TOTAL LOAD = 48.0 PSF

SPACING = 24.0 IN./C

LOADING IN FLAT SECTION BASED ON A SLOPE OF 0.00/12

THIS TRUSS IS DESIGNED FOR RESIDENTIAL OR SMALL BUILDING REQUIREMENTS OF PART 9, NBC 2010, NBC 2015

THIS DESIGN COMPLIES WITH:
 - PART 9 OF BCBC 2018, CBC 2012, ABC 2019
 - PART 9 OF CBC 2012 (2019 AMENDMENT)
 - CSA 088-09, CSA 088-14
 - TPIC 2011, TPIC 2014

(55% OF 31.3 P.S.F. G.S.L. PLUS 8.4 P.S.F. RAIN LOAD) EQUALS 25.6 P.S.F. SPECIFIED ROOF LIVE LOAD

CSI: TC=0.08/1.00 (A-B:1), BC=0.02/1.00 (K-L:4), WB=0.06/1.00 (B-K:1), SS=0.13/1.00 (A-B:1)

DOL LUMBER=1.00 NAIL=1.00 LS BEND=1.10 COMP=1.10 SHEAR=1.10 TENS=1.10

**COMPANION LIVE LOAD FACTOR = 1.00
 FLAT ROOF FACTOR = 0.75**

TRUSS PLATE MANUFACTURER IS NOT RESPONSIBLE FOR QUALITY CONTROL IN THE TRUSS MANUFACTURING PLANT.

NAIL VALUES
 PLATE GRIP(DRY) SHEAR SECTION
 (PSI) (PLI) (PLI)
 MAX MIN MAX MIN MAX MIN
 MT20 618 354 1687 788 1987 1656


PLATE PLACEMENT TOL. = 0.250 inches

PLATE ROTATION TOL. = 5.0 Deg.

**JSI GRIP = 0.17 (K) (INPUT = 0.90)
 JSI METAL = 0.07 (K) (INPUT = 1.00)**



Structural component only
 DWG# T-2007104



LUMBER
N. L. G. A. RULES

CHORDS	SIZE	DRY	LUMBER
F - A	2x4	DRY	No.2
A - C	2x6	DRY	No.2
D - C	2x4	DRY	No.2
F - D	2x6	DRY	No.2

ALL WEBS 2x3 DRY
DRY: SEASONED LUMBER.

DIMENSIONS, SUPPORTS AND LOADINGS SPECIFIED BY FABRICATOR TO BE VERIFIED BY BUILDING DESIGNER

PROVIDE ADEQUATE DRAINAGE TO PREVENT PONDING

BEARINGS

JT	FACTORED		MAXIMUM FACTORED		INPUT	RECORD
	GROSS REACTION	DOWN	GROSS REACTION	UP/LIFT		
F	988	0	988	0	MECHANICAL	BRG
D	1012	0	1012	0	MECHANICAL	BRG

A SUITABLE HANGER/MECHANICAL CONNECTION IS REQUIRED AT JOINT F, D. MINIMUM BEARING LENGTH AT JOINT F = 3-8, JOINT D = 3-8.

UNFACTORED REACTIONS

1ST LOASE		MAX./MIN. COMPONENT REACTIONS					
JT	COMBINED	SNOW	LIVE	PERM.LIVE	WIND	DEAD	SOIL
F	705	427 / 0	0 / 0	0 / 0	0 / 0	279 / 0	0 / 0
D	722	439 / 0	0 / 0	0 / 0	0 / 0	283 / 0	0 / 0

BRACING

TOP CHORD TO BE SHEATHED OR MAX. PURLIN SPACING = 8.25 FT.
MAX. UNBRACED BOTTOM CHORD LENGTH = 10.00 FT OR RIGID CEILING DIRECTLY APPLIED.

ALL PITCH BREAKS AND PERIMETER CORNER JOINTS MUST BE Laterally RESTRAINED.

LOADING

TOTAL LOAD CASES: (4)

MEMB.	CHORDS				WEBS			
	MAX. FACTORED FORCE (LBS)	FACTORED VERT. LOAD (PLF)	MAX. LC1 (LC)	MAX. MAX+ (LC)	MEMB. MAX. FACTORED FORCE (LBS)	MAX. LC1 (LC)	MAX. MAX+ (LC)	MEMB. MAX. FACTORED FORCE (LBS)
FR-TO		FROM	CS1 (LC)	UNBRAC LENGTH	FR-TO			
F-A	-846 / 0	0.0	0.0	0.23 (1)	7.45	A-E	0 / 1072	0.35 (1)
A-B	-889 / 0	-114.3	-114.3	0.24 (1)	6.25	E-B	-632 / 0	0.18 (1)
B-C	-889 / 0	-114.3	-114.3	0.24 (1)	6.25	E-C	0 / 1072	0.35 (1)
D-C	-846 / 0	0.0	0.0	0.23 (1)	7.45			
F-G	0 / 0	-18.5	-18.5	0.24 (1)	10.00			
G-H	0 / 0	-18.5	-18.5	0.24 (1)	10.00			
H-E	0 / 0	-18.5	-18.5	0.24 (1)	10.00			
E-I	0 / 0	-18.5	-18.5	0.24 (1)	10.00			
I-J	0 / 0	-18.5	-18.5	0.24 (1)	10.00			
J-D	0 / 0	-18.5	-18.5	0.24 (1)	10.00			

FACTORED CONCENTRATED LOADS (LBS)

JT	LOC.	LC1	MAX.	MAX+	FACE	DIR.	TYPE	HEEL	CONN.
G	1-9-12	-180	-190	---	FRONT	VERT	TOTAL	---	C1
H	3-9-12	-190	-190	---	FRONT	VERT	TOTAL	---	C1
I	5-9-12	-190	-190	---	FRONT	VERT	TOTAL	---	C1
J	7-9-12	-190	-190	---	FRONT	VERT	TOTAL	---	C1

CONNECTION REQUIREMENTS

1) C1: A SUITABLE HANGER/MECHANICAL CONNECTION IS REQUIRED.

TOTAL WEIGHT = 61 lb (M/R)

DESIGN CRITERIA

SPECIFIED LOADS:
TOP CH. LL = 25.5 PSF
DL = 15.0 PSF
BOT CH. LL = 0.0 PSF
DL = 7.4 PSF
TOTAL LOAD = 48.0 PSF

SPACING = 24.0 IN./C

LOADING IN FLAT SECTION BASED ON A SLOPE OF 0.0W/12

THIS TRUSS IS DESIGNED FOR RESIDENTIAL OR SMALL BUILDING REQUIREMENTS OF PART 9, NBCC 2010, NBCC 2015

THIS DESIGN COMPLIES WITH:

- PART 9 OF CBC 2018, CBC 2012, ABC 2019
- PART 9 OF CBC 2012 (2019 AMENDMENT)
- CSA 088-09, CSA 088-14
- TPIC 2011, TPIC 2014

(5% OF 31.3 P.S.F. G.S.L. PLUS 8.4 P.S.F. RAIN LOAD) EQUALS 25.6 P.S.F. SPECIFIED ROOF LIVE LOAD

ALLOWABLE DEFL.(LL) = L/360 (0.31")
CALCULATED VERT. DEFL.(LL) = L/999 (0.02")
ALLOWABLE DEFL.(TL) = L/360 (0.31")
CALCULATED VERT. DEFL.(TL) = L/999 (0.04")

CSI: TC=0.24/1.00 (B-C:1), BC=0.24/1.00 (D-E:1), WB=0.35/1.00 (A-E:1), SE=0.29/1.00 (E-F:1)

DOL LUMBER=1.00 NAIL=1.00 LS BEND=1.00
COMP=1.00 SHEAR=1.00 TENS=1.00

COMPANION LIVE LOAD FACTOR = 1.00
FLAT ROOF FACTOR = 0.75

TRUSS PLATE MANUFACTURER IS NOT RESPONSIBLE FOR QUALITY CONTROL IN THE TRUSS MANUFACTURING PLANT.

NAIL VALUES
PLATE GRIP(DRY) SHEAR SECTION
(PSI) (PLI) (PLI)
MAX MIN MAX MIN MAX MIN
MT20 618 354 1687 788 1987 1658


PLATE PLACEMENT TOL. = 0.250 inches

PLATE ROTATION TOL. = 5.0 Deg.

JSI GRIP = 0.76 (E) (INPUT = 0.90)
JSI METAL = 0.32 (E) (INPUT = 1.00)



Structural component only
DWG# T-2007121



LUMBER

N. L. G. A. RULES	CHORDS	SIZE	LUMBER	DESCR.
A - C	2x4	DRY	No.2	SPF
D - C	2x4	DRY	No.2	SPF
A - D	2x6	DRY	No.2	SPF

ALL WEBS 2x3 DRY No.2 SPF
 DRY: SEASONED LUMBER.

DESIGN CONSISTS OF 2 TRUSSES BUILT SEPARATELY THEN FASTENED TOGETHER AS FOLLOWS:

CHORDS #ROWS	SURFACE SPACING (IN)	LOAD (PLF)
TOP CHORDS : (0.122"x3") SPIRAL NAILS		
A - C 1 12	TOP	
C - D 1 12	TOP	
BOTTOM CHORDS : (0.122"x3") SPIRAL NAILS		
A - D 2 12	SIDE (0.0)	
WEBS : (0.122"x3") SPIRAL NAILS		
2x3 1 8		

NAILS TO BE DRIVEN FROM ONE SIDE ONLY.

GIRDER NAILING ASSUMES NAILED HANGERS ARE FASTENED WITH MIN. 3/4 INCH NAILS.

TOP - COMPONENTS ARE LOADED FROM THE TOP AND MUST BE PLACED ON TOP EDGE OF ALL PLIES FOR THE LOAD TO BE TRANSFERRED TO EACH PLY.

SIDE - PLF SHOWN IS THE EQUIVALENT UDL APPLIED TO ONE SIDE THAT THE CORRESPONDING NAILING PATTERN SHALL BE CAPABLE OF TRANSFERRING. REMAINING PLF MUST BE APPLIED ON THE OPPOSITE SIDE OR ON THE TOP.

PLATES (tblg in inches)

JT	TYPE	PLATES	W	LEN	Y	X
A	TBMH+m	MT20	5.0	8.0	3.50	
B	TBMW+1	MT20	5.0	6.0	2.50	2.25
C	TMY+p	MT20	3.0	4.0		
D	BMVW+1	MT20	5.0	6.0	2.50	2.75
E	BMW+w	MT20	3.0	10.0		

DIMENSIONS, SUPPORTS AND LOADINGS SPECIFIED BY FABRICATOR TO BE VERIFIED BY BUILDING DESIGNER

BEARINGS

JT	VERT	HORZ	MAXIMUM FACTORED GROSS REACTION	DOWN	UP	MECHANICAL	HEEL WEDGE
A	3487	0	3487	0	0	5-8	5-8
D	2454	0	2454	0	0	MECHANICAL	2x4 L

A SUITABLE HANGER/MECHANICAL CONNECTION IS REQUIRED AT JOINT D. MINIMUM BEARING LENGTH AT JOINT D = 4.0.

UNFACTORED REACTIONS

JT	1ST CASE	MAX. MIN. COMPONENT REACTIONS	SNOW	LIVE	PERM. LIVE	WIND	DEAD	SOIL
A	2449	1622 / 0	0 / 0	0 / 0	0 / 0	828 / 0	0 / 0	0 / 0
D	1735	1144 / 0	0 / 0	0 / 0	0 / 0	591 / 0	0 / 0	0 / 0

BEARING MATERIAL TO BE SPF NO.2 OR BETTER AT JOINT(S) A

BRACING
 TOP CHORD TO BE SHEATHED OR MAX. PURLIN SPACING = 4.16 FT.
 MAX. UNBRACED BOTTOM CHORD LENGTH = 10.00 FT. OR RIGID CEILING DIRECTLY APPLIED.

ALL PITCH BREAKS AND PERIMETER CORNER JOINTS MUST BE Laterally RESTRAINED.

LOADING
 TOTAL LOAD CASES: (4)

CHORDS				WEBS			
MEMB.	MAX. FACTORED FORCE (LBS)	FACTORED VERT. LOAD (PLF)	MAX. CSI (LC)	MEMB.	MAX. FACTORED FORCE (LBS)	MAX. CSI (LC)	
FR-TO		FROM TO	LENGTH	FR-TO			
A-G	-4978 / 0	-91.8 -91.8	0.19 (1)	4.16	E-B	0 / 3385	0.42 (1)
G-B	-3863 / 0	-91.8 -91.8	0.17 (1)	4.66	B-D	-4035 / 0	0.53 (1)
B-C	-13 / 0	-91.8 -91.8	0.07 (1)	6.25	F-G	0 / 1740	0.00 (1)
D-C	-129 / 0	0.0 0.0	0.02 (1)	7.81			
A-F	0 / 3490	-18.5 -18.5	0.25 (1)	10.00			
F-H	0 / 3490	-18.5 -18.5	0.88 (1)	10.00			
H-I	0 / 3490	-18.5 -18.5	0.88 (1)	10.00			
I-J	0 / 3490	-18.5 -18.5	0.88 (1)	10.00			
J-E	0 / 3490	-18.5 -18.5	0.88 (1)	10.00			
E-K	0 / 3490	-18.5 -18.5	0.49 (1)	10.00			
K-D	0 / 3490	-18.5 -18.5	0.49 (1)	10.00			

FACTORED CONCENTRATED LOADS (LBS)

JT	LOC.	LG1	MAX.	MAX+	FACE	DIR.	TYPE	HEEL	CONN.
H	1-4-0	-1378	-1378	---	BACK	VERT	TOTAL	---	C1
I	2-0-0	-1000	-1000	---	FRONT	VERT	TOTAL	---	C1
J	3-0-4	-894	-894	---	FRONT	VERT	TOTAL	---	C1
J	3-3-4	-896	-896	---	BACK	VERT	TOTAL	---	C1
K	5-3-4	-896	-896	---	BACK	VERT	TOTAL	---	C1

CONNECTION REQUIREMENTS

- 1) C1: A SUITABLE HANGER/MECHANICAL CONNECTION IS REQUIRED.

TOTAL WEIGHT = 2 X 30 = 60 lb

DESIGN CRITERIA

*** SPECIAL LOADS ANALYSIS ***
 GEOMETRY AND/OR BASIC LOADS CHANGED BY USER.
 LOADS WERE DERIVED FROM USER INPUT
 NO FURTHER MODIFICATIONS WERE MADE

SPECIFIED LOADS:
 TOP CH. LL = 25.8 PSF
 DL = 6.0 PSF
 BOT CH. LL = 0.0 PSF
 DL = 7.4 PSF
 TOTAL LOAD = 39.0 PSF

SPACING = 24.0 IN. OC

*** NON STANDARD GIRDER ***
 ADDTL USER-DEFINED LOADS APPLIED TO ALL LOAD CASES.

THIS TRUSS IS DESIGNED FOR RESIDENTIAL OR SMALL BUILDING REQUIREMENTS OF PART 9, NBC 2010, NBCC 2015

THIS DESIGN COMPLIES WITH:
 - PART 9 OF BCBC 2018, OBC 2012, ABC 2019
 - PART 9 OF OBC 2012 (2019 AMENDMENT)
 - CSA 088-09, CSA 088-14
 - TPIC 2011, TPIC 2014

(65 % OF 31.3 P.S.F. G.S.L. PLUS 8.4 P.S.F. RAIN LOAD) EQUALS 25.8 P.S.F. SPECIFIED ROOF LIVE LOAD

ALLOWABLE DEFL. (LL) = L/360 (0.23")
 CALCULATED VERT. DEFL. (LL) = L/999 (0.03")
 ALLOWABLE DEFL. (TL) = L/360 (0.23")
 CALCULATED VERT. DEFL. (TL) = L/999 (0.05")

CSI: TG=0.19/1.00 (A-G-I), BG=0.88/1.00 (E-F-I), WB=0.53/1.00 (B-D-I), SB=0.90/1.00 (E-F-I)

DOL LUMBER=1.00 NAIL=1.00 LS BEND=1.00
 COMP=1.00 SHEAR=1.00 TENS=1.00

COMPANION LIVE LOAD FACTOR = 1.00

TRUSS PLATE MANUFACTURER IS NOT RESPONSIBLE FOR QUALITY CONTROL IN THE TRUSS MANUFACTURING PLANT.

NAIL VALUES
 PLATE GRIP (DRY) SHEAR SECTION (PSI) (PLI) (PLI)
 MAX MIN MAX MIN MAX MIN
 MT20 818 354 1687 788 1987 1656

PLATE PLACEMENT TOL. = 5.0 inches

PLATE ROTATION TOL. = 5.0 Deg.

JSI GRIP = 0.88 (B) (INPUT = 0.90)
 JSI METAL = 0.70 (A) (INPUT = 1.00)




JOB NAME	TRUSS NAME	QUANTITY	PLY	JOB DESC.	GREEN PARK HOMES	DRWG NO.
408150	G60	4	1	TRUSS DESC.		

Tamarack Roof Truss, Burlington

Version 8.310 S Oct 29 2019 Mytek Industries, Inc. Sat Apr 25 11:02:39 2020 Page 1

ID:17VF7aG0E03cRUj6X1Sik2WYK-kwCWPUL9QwEw4kEulc_ECPgnD4MnCBFXZZr4QzNCnk



LUMBER	N. L. G. A. RULES	CHORDS	SIZE	LUMBER	DESCR.
AC - B	2x4	DRY	No.2	SPF	
A - H	2x4	DRY	No.2	SPF	
H - J	2x4	DRY	No.2	SPF	
J - O	2x4	DRY	No.2	SPF	
P - D	2x4	DRY	No.2	SPF	
AC - T	2x4	DRY	No.2	SPF	
T - P	2x4	DRY	No.2	SPF	
ALL WEBS	2x3	DRY	No.2	SPF	
ALL GABLE WEBS	2x3	DRY	No.2	SPF	
DRY: SEASONED LUMBER.					
GABLE STUDS SPACED AT 2'-0" OC.					

DIMENSIONS, SUPPORTS AND LOADINGS SPECIFIED BY FABRICATOR TO BE VERIFIED BY BUILDING DESIGNER

BEARINGS

THIS TRUSS DESIGNED FOR CONTINUOUS BEARINGS.

THIS TRUSS REQUIRES RIGID SHEATHING ON EXPOSED FACE.

BEARING MATERIAL TO BE SPF NO.2 OR BETTER AT JOINT(S)

BRACING

TOP CHORD TO BE SHEATHED OR MAX. FURLIN SPACING = 6.25 FT.

MAX. UNBRACED BOTTOM CHORD LENGTH = 10.00 FT OR RIGID CEILING DIRECTLY APPLIED.

ALL PITCH BREAKS AND PERIMETER CORNER JOINTS MUST BE Laterally RESTRAINED.

1 LATERAL BRACE(S) AT 1/2 LENGTH OF O-P.

END VERTICAL(S) MUST BE SHEATHED OR HAVE BRACES AS INDICATED IN THE MAX. UNBRACED LENGTH COLUMN OF THE TABLE BELOW

TOTAL WEIGHT = 4 X 116 = 464 lb

PLATES (table in inches)	JT TYPE	PLATES	W	LEN	Y	X
B TMV+p	MT20	3.0	4.0			
C, D, E, F, G, I, K, L, M, N						
C TMW+w	MT20	2.0	4.0			
H TS-i	MT20	3.0	6.0			
J TTW-m	MT20	4.0	4.0			
O TMV+p	MT20	3.0	4.0			
P BMV+p	MT20	3.0	4.0			
Q, R, S, U, V, W, X, Y, Z, AA, AB						
O BMW1+w	MT20	2.0	4.0			
T BS-i	MT20	3.0	6.0			
AC BMV+p	MT20	3.0	4.0			

LOADING									
TOTAL LOAD CASES: (4)									
CHORDS					WEBS				
MEMB.	MAX. FACTORED FORCE (LBS)	VERT. LOAD (PLF)	MAX. FACTORED CSI (LC)	MAX. UNBRACED LENGTH (FT)	MEMB.	MAX. FACTORED FORCE (LBS)	MAX. FACTORED CSI (LC)	MAX. UNBRACED LENGTH (FT)	
FR-TO		FROM TO			FR-TO				
AC-B	-224 / 0	0.0	0.0	0.02 (1)	7.81	C-N	-185 / 0	0.25 (1)	
A-B	0 / 28	-91.8	-91.8	0.12 (1)	10.00	R-M	-183 / 0	0.23 (1)	
B-C	-28 / 0	-91.8	-91.8	0.04 (1)	8.25	S-L	-188 / 0	0.24 (1)	
C-D	-19 / 0	-91.8	-91.8	0.04 (1)	8.25	U-K	-136 / 0	0.17 (1)	
D-E	-15 / 0	-91.8	-91.8	0.04 (1)	8.25	V-J	-131 / 0	0.17 (1)	
E-F	-11 / 0	-91.8	-91.8	0.04 (1)	8.25	W-I	-185 / 0	0.17 (1)	
F-G	-8 / 0	-91.8	-91.8	0.04 (1)	10.00	X-G	-183 / 0	0.11 (1)	
G-H	-6 / 0	-91.8	-91.8	0.04 (1)	10.00	Y-F	-182 / 0	0.07 (1)	
H-I	-6 / 0	-91.8	-91.8	0.04 (1)	10.00	Z-E	-182 / 0	0.05 (1)	
I-J	-9 / 0	-91.8	-91.8	0.04 (1)	10.00	AA-D	-183 / 0	0.03 (1)	
J-K	-2 / 0	-91.8	-91.8	0.03 (1)	10.00	AB-C	-176 / 0	0.03 (1)	
K-L	-2 / 0	-91.8	-91.8	0.04 (1)	10.00				
L-M	-2 / 0	-91.8	-91.8	0.04 (1)	10.00				
M-N	-2 / 0	-91.8	-91.8	0.04 (1)	10.00				
N-O	-2 / 0	-91.8	-91.8	0.04 (1)	10.00				
P-O	-81 / 0	0.0	0.0	0.01 (1)	6.25				
AC-AB	0 / 24	-18.5	-18.5	0.02 (4)	10.00				
AB-AA	0 / 17	-18.5	-18.5	0.02 (4)	10.00				
AA-Z	0 / 13	-18.5	-18.5	0.02 (4)	10.00				
Z-Y	0 / 10	-18.5	-18.5	0.02 (4)	10.00				
Y-X	0 / 7	-18.5	-18.5	0.01 (4)	10.00				
X-W	0 / 5	-18.5	-18.5	0.02 (4)	10.00				
W-V	0 / 4	-18.5	-18.5	0.02 (4)	10.00				
V-U	0 / 2	-18.5	-18.5	0.01 (4)	10.00				
U-T	0 / 2	-18.5	-18.5	0.02 (4)	10.00				
T-S	0 / 2	-18.5	-18.5	0.02 (4)	10.00				
S-R	0 / 2	-18.5	-18.5	0.02 (4)	10.00				
R-Q	0 / 2	-18.5	-18.5	0.02 (4)	10.00				
Q-P	0 / 2	-18.5	-18.5	0.02 (4)	10.00				

DESIGN CRITERIA

SPECIFIED LOADS:

TOP CH. LL = 25.8 PSF

DL = 8.0 PSF

BOT CH. LL = 0.0 PSF

DL = 7.4 PSF

TOTAL LOAD = 39.0 PSF

SPACING = 24.0 IN. C/C

LOADING IN FLAT SECTION BASED ON A SLOPE OF 0.00712

THIS TRUSS IS DESIGNED FOR RESIDENTIAL OR SMALL BUILDING REQUIREMENTS OF PART 9, NBC 2010, NBC 2015

THIS DESIGN COMPLIES WITH:

- PART 9 OF CBC 2018, CBC 2012, ABC 2010
- PART 9 OF CBC 2012 (2019 AMENDMENT)
- CSA 086-09, CSA 086-14
- TPIC 2011, TPIC 2014

DESIGN ASSUMPTIONS

OVERHANG NOT TO BE ALTERED OR CUT OFF.

(55 % OF 31.3 P.S.F. G.S.L. PLUS 8.4 P.S.F. RAIN LOAD) EQUALS 25.6 P.S.F. SPECIFIED ROOF LIVE LOAD

CSI: TC=0.12/1.00 (A-B:1), BC=0.02/1.00 (Q-R:4), WB=0.25/1.00 (N-Q:1), SS=0.09/1.00 (A-B:1)

DOL LUMBER=1.00 NAIL=1.00 LBS BEND=1.10 COMP=1.10 SHEAR=1.10 TENS=1.10

COMPANION LIVE LOAD FACTOR = 1.00

TRUSS PLATE MANUFACTURER IS NOT RESPONSIBLE FOR QUALITY CONTROL IN THE TRUSS MANUFACTURING PLANT.

NAIL VALUES

PLATE GRIP (DRY) SHEAR SECTION (PSI) (PLI) (PLI)

MAX MIN MAX MIN MAX MIN


MT20 616 354 1867 789 1997 1656

PLATE PLACEMENT TOL. = 0.250 inches

PLATE ROTATION TOL. = 5.0 Deg.

JSI GRIP=0.60 (J) (INPUT = 0.90)


JSI METAL=0.08 (I) (INPUT = 1.00)



Structural component only
DWG# T-2007057

JOB NAME 408150	TRUSS NAME GP1	QUANTITY 2	PLY 1	JOB DESC. GREEN PARK HOMES	DRWG NO.
Tamarack Roof Truss, Burlington				TRUSS DESC.	

Version 8.310 S Oct 29 2019 Mitek Industries, Inc. Sat Apr 25 11:02:40 2020 Page 1
ID:17vF7aG0E03cRUj6X1iSkziWYK-C6mudqMnBDMnh0JqS07DnQMncNpWgWomDIPdszNCn




LUMBER N. L. G. A. RULES CHORDS SIZE LUMBER DESCR. A - C 2x4 DRY No.2 SPF C - E 2x4 DRY No.2 SPF A - G 2x4 DRY No.2 SPF G - E 2x4 DRY No.2 SPF ALL WEBS 2x3 DRY No.2 SPF DRY: SEASONED LUMBER.				BEARINGS FACTORED GROSS REACTION MAXIMUM FACTORED GROSS REACTION INPUT REQD BRG BRG JT VERT HORZ DOWN HORZ UPLIFT IN-SX IN-SX A 134 0 134 0 0 18-1-0 (9-11-18)11-0 E 134 0 134 0 0 18-1-0 (9-11-18)11-0 F 863 0 863 0 0 18-1-0 (9-11-18)11-0 H 863 0 863 0 0 18-1-0 (9-11-18)11-0 VALUE IN PARENTHESIS INDICATES EFFECTIVE BEARING LENGTH				DESIGN CRITERIA SPECIFIED LOADS: TOP CH. LL = 25.6 PSF DL = 6.0 PSF BOT CH. LL = 0.0 PSF DL = 7.4 PSF TOTAL LOAD = 39.0 PSF SPACING = 24.0 IN. C/C THIS TRUSS IS DESIGNED FOR RESIDENTIAL OR SMALL BUILDING REQUIREMENTS OF PART 9, NBCC 2010, NBCC 2015 THIS DESIGN COMPLIES WITH: - PART 9 OF BCBC 2018, CBC 2012, ABC 2019 - PART 9 OF OBC 2012 (2019 AMENDMENT) - CSA 086-09, CSA 086-14 - TPIC 2011, TPIC 2014 (56% OF 31.3 P.S.F. G.S.L. PLUS 8.4 P.S.F. RAIN LOAD) EQUALS 25.6 P.S.F. SPECIFIED ROOF LIVE LOAD CSI: TC=0.371/0.0 (C-D:1), BC=0.13/1.00 (F-K:4), WB=0.18/1.00 (C-H:1), SS=0.17/1.00 (D-L:1) DOL LUMBER=1.00 NAIL=1.00 LS BEND=1.10 COMP=1.10 SHEAR=1.10 TENS=1.10 COMPANION LIVE LOAD FACTOR = 1.00 TRUSS PLATE MANUFACTURER IS NOT RESPONSIBLE FOR QUALITY CONTROL IN THE TRUSS MANUFACTURING PLANT. NAIL VALUES PLATE GRIP(DRY) SHEAR SECTION (PSI) (PLI) (PLI) MAX MIN MAX MIN MAX MIN MT20 618 354 1667 788 1967 1656 PLATE PLACEMENT TOL. = 0.250 inches PLATE ROTATION TOL. = 5.0 Deg. JSI GRIP= 0.48 (H) (INPUT = 0.80) JSI METAL= 0.15 (C) (INPUT = 1.00)																																																																																																											
PLATES (table is in inches) JT TYPE PLATES W LEN Y X A TBM1-h MT20 3.0 4.0 B TBM1-w MT20 2.0 4.0 C TTMW+p MT20 4.0 6.0 Edge D TBM1-w MT20 2.0 4.0 E TBM1-h MT20 3.0 4.0 F BMMW1-t MT20 4.0 4.0 G BS-1 MT20 3.0 6.0 H BMMW1-t MT20 4.0 4.0 Edge - INDICATES REFERENCE CORNER OF PLATE TOUCHES EDGE OF CHORD.				UNFACTORED REACTIONS 1ST LOASE MAX/MIN COMPONENT REACTIONS JT COMBINED SNOW LIVE PERM.LIVE WIND DEAD SOIL A 94 68/0 0/0 0/0 0/0 28/0 0/0 E 94 68/0 0/0 0/0 0/0 28/0 0/0 F 611 385/0 0/0 0/0 0/0 216/0 0/0 H 611 385/0 0/0 0/0 0/0 216/0 0/0 BEARING MATERIAL TO BE SPF NO.2 OR BETTER AT JOINT(S) A, E, F, H BRACING TOP CHORD TO BE SHEATHED OR MAX. PURLIN SPACING = 10.00 FT. MAX. UNBRACED BOTTOM CHORD LENGTH = 6.25 FT. OR RIGID CEILING DIRECTLY APPLIED. ALL PITCH BREAKS AND PERIMETER CORNER JOINTS MUST BE Laterally RESTRAINED.				LOADING TOTAL LOAD CASES: (4) <table border="1"> <thead> <tr> <th rowspan="2">MEMB.</th> <th rowspan="2">MAX. FACTORED FORCE (LBS)</th> <th colspan="3">CHORDS</th> <th colspan="3">WEBS</th> </tr> <tr> <th>MAX. FACTORED FORCE (LBS)</th> <th>VERT. LOAD (PLF)</th> <th>MAX. FACTORED FORCE (LBS)</th> <th>MAX. FACTORED FORCE (LBS)</th> <th>MAX. FACTORED FORCE (LBS)</th> </tr> </thead> <tbody> <tr> <td>FR-TO</td> <td></td> <td></td> <td></td> <td></td> <td></td> <td></td> </tr> <tr> <td>A-J</td> <td>0/240</td> <td>-91.8</td> <td>-91.8</td> <td>0.12 (1)</td> <td>10.00</td> <td>C-F -428/0 0.18 (1)</td> </tr> <tr> <td>J-B</td> <td>0/301</td> <td>-91.8</td> <td>-91.8</td> <td>0.34 (1)</td> <td>10.00</td> <td>F-D -436/0 0.08 (1)</td> </tr> <tr> <td>B-C</td> <td>0/503</td> <td>-91.8</td> <td>-91.8</td> <td>0.37 (1)</td> <td>10.00</td> <td>H-C -428/0 0.18 (1)</td> </tr> <tr> <td>C-D</td> <td>0/503</td> <td>-91.8</td> <td>-91.8</td> <td>0.37 (1)</td> <td>10.00</td> <td>B-H -436/0 0.08 (1)</td> </tr> <tr> <td>D-L</td> <td>0/301</td> <td>-91.8</td> <td>-91.8</td> <td>0.34 (1)</td> <td>10.00</td> <td>I-J -76/35 0.00 (1)</td> </tr> <tr> <td>L-E</td> <td>0/240</td> <td>-91.8</td> <td>-91.8</td> <td>0.12 (1)</td> <td>10.00</td> <td>K-L -76/35 0.00 (1)</td> </tr> <tr> <td>A-I</td> <td>-255/0</td> <td>-18.5</td> <td>-18.5</td> <td>0.11 (1)</td> <td>6.25</td> <td></td> </tr> <tr> <td>I-H</td> <td>-243/0</td> <td>-18.5</td> <td>-18.5</td> <td>0.13 (4)</td> <td>6.25</td> <td></td> </tr> <tr> <td>H-G</td> <td>-246/0</td> <td>-18.5</td> <td>-18.5</td> <td>0.13 (4)</td> <td>6.25</td> <td></td> </tr> <tr> <td>G-F</td> <td>-246/0</td> <td>-18.5</td> <td>-18.5</td> <td>0.13 (4)</td> <td>6.25</td> <td></td> </tr> <tr> <td>F-K</td> <td>-243/0</td> <td>-18.5</td> <td>-18.5</td> <td>0.13 (4)</td> <td>6.25</td> <td></td> </tr> <tr> <td>K-E</td> <td>-255/0</td> <td>-18.5</td> <td>-18.5</td> <td>0.11 (1)</td> <td>6.25</td> <td></td> </tr> </tbody> </table>				MEMB.	MAX. FACTORED FORCE (LBS)	CHORDS			WEBS			MAX. FACTORED FORCE (LBS)	VERT. LOAD (PLF)	MAX. FACTORED FORCE (LBS)	MAX. FACTORED FORCE (LBS)	MAX. FACTORED FORCE (LBS)	FR-TO							A-J	0/240	-91.8	-91.8	0.12 (1)	10.00	C-F -428/0 0.18 (1)	J-B	0/301	-91.8	-91.8	0.34 (1)	10.00	F-D -436/0 0.08 (1)	B-C	0/503	-91.8	-91.8	0.37 (1)	10.00	H-C -428/0 0.18 (1)	C-D	0/503	-91.8	-91.8	0.37 (1)	10.00	B-H -436/0 0.08 (1)	D-L	0/301	-91.8	-91.8	0.34 (1)	10.00	I-J -76/35 0.00 (1)	L-E	0/240	-91.8	-91.8	0.12 (1)	10.00	K-L -76/35 0.00 (1)	A-I	-255/0	-18.5	-18.5	0.11 (1)	6.25		I-H	-243/0	-18.5	-18.5	0.13 (4)	6.25		H-G	-246/0	-18.5	-18.5	0.13 (4)	6.25		G-F	-246/0	-18.5	-18.5	0.13 (4)	6.25		F-K	-243/0	-18.5	-18.5	0.13 (4)	6.25		K-E	-255/0	-18.5	-18.5	0.11 (1)	6.25	
MEMB.	MAX. FACTORED FORCE (LBS)	CHORDS			WEBS																																																																																																														
		MAX. FACTORED FORCE (LBS)	VERT. LOAD (PLF)	MAX. FACTORED FORCE (LBS)	MAX. FACTORED FORCE (LBS)	MAX. FACTORED FORCE (LBS)																																																																																																													
FR-TO																																																																																																																			
A-J	0/240	-91.8	-91.8	0.12 (1)	10.00	C-F -428/0 0.18 (1)																																																																																																													
J-B	0/301	-91.8	-91.8	0.34 (1)	10.00	F-D -436/0 0.08 (1)																																																																																																													
B-C	0/503	-91.8	-91.8	0.37 (1)	10.00	H-C -428/0 0.18 (1)																																																																																																													
C-D	0/503	-91.8	-91.8	0.37 (1)	10.00	B-H -436/0 0.08 (1)																																																																																																													
D-L	0/301	-91.8	-91.8	0.34 (1)	10.00	I-J -76/35 0.00 (1)																																																																																																													
L-E	0/240	-91.8	-91.8	0.12 (1)	10.00	K-L -76/35 0.00 (1)																																																																																																													
A-I	-255/0	-18.5	-18.5	0.11 (1)	6.25																																																																																																														
I-H	-243/0	-18.5	-18.5	0.13 (4)	6.25																																																																																																														
H-G	-246/0	-18.5	-18.5	0.13 (4)	6.25																																																																																																														
G-F	-246/0	-18.5	-18.5	0.13 (4)	6.25																																																																																																														
F-K	-243/0	-18.5	-18.5	0.13 (4)	6.25																																																																																																														
K-E	-255/0	-18.5	-18.5	0.11 (1)	6.25																																																																																																														



Structural component only
DWG# T-2007058

JOB NAME 408150	TRUSS NAME P1	QUANTITY 17	PLY 1	JOB DESC. GREEN PARK HOMES	DRWG NO.
Tamarack Roof Truss, Burlington				TRUSS DESC.	

Version 8.310 S Oct 29 2019 Mitek Industries, Inc. Sat Apr 25 11:32:45 2020 Page 1
ID:17vF7aG0E03cRUj8X1jSrklWYK-Z4ZngXQw0m_400BoEzJOUT3e9d5nBxS8vV0A14zNCne



TOTAL WEIGHT = 17 X 55 = 945 lb

LUMBER

N. L. G. A. RULES

CHORDS	SIZE	LUMBER	DESCR.
A - C	2x4	DRY No.2	SPF
C - E	2x4	DRY No.2	SPF
A - G	2x4	DRY No.2	SPF
G - E	2x4	DRY No.2	SPF

ALL WEBS 2x3 DRY No.2 SPF
DRY: SEASONED LUMBER.

PLATES (tablets in inches)

JT TYPE	PLATES	W	LEN	Y	X
A	TBM1-h	MT20	3.0	4.0	
B	TBMW-t	MT20	4.0	4.0	2.00 1.75
C	TTW-p	MT20	4.0	4.0	
D	TBMW-t	MT20	4.0	4.0	2.00 1.75
E	TBM1-h	MT20	3.0	4.0	
F	BMW1-w	MT20	2.0	4.0	
G	BS-t	MT20	3.0	6.0	
H	BMW1-w	MT20	4.0	9.0	
I	BMW1-w	MT20	2.0	4.0	

DIMENSIONS, SUPPORTS AND LOADINGS SPECIFIED BY FABRICATOR TO BE VERIFIED BY BUILDING DESIGNER

BEARINGS

JT	FACTORED GROSS REACTION		MAXIMUM FACTORED GROSS REACTION		INPUT BRG	REQD BRG
	VERT	HORZ	DOWN	HORZ		
A	124	0	124	0	18-1-0 (11-11)B1-0	
E	124	0	124	0	18-1-0 (11-11)B1-0	
H	415	0	415	0	18-1-0 (11-11)B1-0	
F	666	0	666	0	18-1-0 (11-11)B1-0	
I	666	0	666	0	18-1-0 (11-11)B1-0	

VALUE IN PARENTHESIS INDICATES EFFECTIVE BEARING LENGTH

UNFACTORED REACTIONS

JT	1ST CASE COMBINED	MAX./MIN. COMPONENT REACTIONS					
		SNOW	LIVE	PERM.LIVE	WIND	DEAD	SOIL
A	87	59/0	0/0	0/0	0/0	28/0	0/0
E	87	59/0	0/0	0/0	0/0	28/0	0/0
H	293	192/0	0/0	0/0	0/0	101/0	0/0
F	471	307/0	0/0	0/0	0/0	164/0	0/0
I	471	307/0	0/0	0/0	0/0	164/0	0/0

BEARING MATERIAL TO BE SPF NO.2 OR BETTER AT JOINT(S) A, E, H, F, I

BRACING
TOP CHORD TO BE SHEATHED OR MAX. PURLIN SPACING = 10.00 FT.
MAX. UNBRACED BOTTOM CHORD LENGTH = 6.25 FT OR RIGID CEILING DIRECTLY APPLIED.

ALL PITCH BREAKS AND PERIMETER CORNER JOINTS MUST BE LATERALLY RESTRAINED.

LOADING
TOTAL LOAD CASES: (4)

CHORDS				WEBS			
MEMB.	MAX. FACTORED FORCE (LBS)	FACTORED VERT. LOAD (PLF)	MAX. CS (LC)	MEMB.	MAX. FACTORED FORCE (LBS)	MAX. CS (LC)	
FR-TO		FROM TO		FR-TO			
A-K	0/246	-91.8 -91.8 0.07 (1)	10.00	H-C	-445/0	0.13 (1)	
K-B	0/292	-91.8 -91.8 0.32 (1)	10.00	H-D	0/59	0.01 (1)	
B-C	0/186	-91.8 -91.8 0.30 (1)	10.00	F-D	-528/0	0.08 (1)	
C-D	0/186	-91.8 -91.8 0.30 (1)	10.00	B-H	0/59	0.01 (1)	
D-M	0/292	-91.8 -91.8 0.32 (1)	10.00	I-B	-528/0	0.08 (1)	
M-E	0/246	-91.8 -91.8 0.07 (1)	10.00	J-K	-128/6	0.00 (1)	
				L-M	-128/6	0.00 (1)	
A-J	-256/0	-18.5 -18.5 0.14 (1)	6.25				
J-I	-240/0	-18.5 -18.5 0.14 (1)	6.25				
I-H	-240/0	-18.5 -18.5 0.11 (1)	6.25				
H-G	-240/0	-18.5 -18.5 0.11 (1)	6.25				
G-F	-240/0	-18.5 -18.5 0.11 (1)	6.25				
F-L	-240/0	-18.5 -18.5 0.14 (1)	6.25				
L-E	-256/0	-18.5 -18.5 0.14 (1)	6.25				

DESIGN CRITERIA

SPECIFIED LOADS:
TOP CH. LL = 25.6 PSF
DL = 8.0 PSF
BOT CH. LL = 0.0 PSF
DL = 7.4 PSF
TOTAL LOAD = 39.0 PSF

SPACING = 24.0 IN. G/C

THIS TRUSS IS DESIGNED FOR RESIDENTIAL OR SMALL BUILDING REQUIREMENTS OF PART 9, NBCC 2010, NBCC 2015

THIS DESIGN COMPLIES WITH:
- PART 9 OF BCBC 2016, CBC 2012, ABC 2019
- PART 9 OF CBC 2012 (2019 AMENDMENT)
- CSA 086-09, CSA 086-14
- TPIC 2011, TPIC 2014

(55% OF 31.3 P.S.F. G.S.L. PLUS 8.4 P.S.F. RAIN LOAD) EQUALS 25.6 P.S.F. SPECIFIED ROOF LIVE LOAD

CSI: TC=0.32/1.00 (D-M:1), BC=0.14/1.00 (F-L:1), WB=0.13/1.00 (C-H:1), SSI=0.17/1.00 (D-M:1)

DOL LUMBER=1.00 NAIL=1.00 LS BEND=1.10 COMP=1.10 SHEAR=1.10 TENS=1.10

COMPANION LIVE LOAD FACTOR = 1.00

TRUSS PLATE MANUFACTURER IS NOT RESPONSIBLE FOR QUALITY CONTROL IN THE TRUSS MANUFACTURING PLANT.

NAIL VALUES
PLATE GRIP(DRY) SHEAR SECTION (PSI) (PL) (PL)
MAX MIN MAX MIN MAX MIN
MT20 618 354 1697 788 1987 1656

PLATE PLACEMENT TOL. = 0.250 inches

PLATE ROTATION TOL. = 5.0 Deg.

JSI GRIP= 0.51 (B) (INPUT = 0.90)
JSI METAL= 0.13 (C) (INPUT = 1.00)




Structural component only
DWG# T-2007062

JOB NAME	TRUSS NAME	QUANTITY	PLY	JOB DESC.	GREEN PARK HOMES	DRWG NO.
408151	PB20	2	1	TRUSS DESC.		

Tamarack Roof Truss, Burlington

Version 8.310 S Oct 29 2019 MTek Industries, Inc. Sat Apr 25 11:19:42 2020 Page 1
ID:h2dlIqC44wS_E2IzqPs_aizlIRw-HkWF6HjrVE7mI4RFJISiCxbPKbCR_v_qmDtlUUDzNCXI



LUMBER	N. L. G. A. RULES	CHORDS	SIZE	DRY	LUMBER	QESCR.
A - C	2x4	DRY	No.2	SPF		
C - E	2x4	DRY	No.2	SPF		
E - G	2x4	DRY	No.2	SPF		
B - F	2x4	DRY	No.2	SPF		
ALL WEBS	2x3	DRY	No.2	SPF		
DRY: SEASONED LUMBER.						

PLATES (table is in inches)	JT TYPE	PLATES	W	LEN	Y	X
B	TMB1-I	MT20	3.0	4.0	1.50	2.00
C	TTWW+m	MT20	5.0	6.0	2.25	1.50
D	TMW+w	MT20	2.0	4.0		
E	TTWW+m	MT20	5.0	6.0	2.25	1.50
F	TMB1-I	MT20	3.0	4.0	1.50	2.00
H	BMW1+w	MT20	2.0	4.0		
I	BMWW1-I	MT20	4.0	9.0		
J	BMW1+w	MT20	2.0	4.0		

DIMENSIONS, SUPPORTS AND LOADINGS SPECIFIED BY FABRICATOR TO BE VERIFIED BY BUILDING DESIGNER

BEARINGS	FACTORED	MAXIMUM FACTORED	INPUT	REQD
GROSS REACTION	GROSS REACTION	BRG	BRG	BRG
VERT	HORZ	DOWN	HORZ	UPLIFT
IN-SX	IN-SX	IN-SX	IN-SX	IN-SX
JT	169	0	169	0
B	169	0	169	0
F	288	0	288	0
J	683	0	683	0
I	288	0	288	0
H	288	0	288	0

UNFACTORED REACTIONS

1ST CASE	MAX./MIN. COMPONENT REACTIONS	SNOW	LIVE	PERM.LIVE	WIND	DEAD	SOIL
COMBINED							
JT	116	93/0	0/0	0/0	0/0	23/0	0/0
B	116	93/0	0/0	0/0	0/0	23/0	0/0
F	207	118/0	0/0	0/0	0/0	89/0	0/0
J	481	327/0	0/0	0/0	0/0	154/0	0/0
I	207	118/0	0/0	0/0	0/0	89/0	0/0
H							

BEARING MATERIAL TO BE SPF NO.2 OR BETTER AT JOINT(S) B, F, J, I, H

BRACING

TOP CHORD TO BE SHEATHED OR MAX. PURLIN SPACING = 8.25 FT.
MAX. UNBRACED BOTTOM CHORD LENGTH = 10.00 FT OR RIGID CEILING DIRECTLY APPLIED.

ALL PITCH BREAKS AND PERIMETER CORNER JOINTS MUST BE LATERALLY RESTRAINED.

LOADING

TOTAL LOAD CASES: (4)

CHORDS			WEBS			
MEMB.	MAX. FACTORED FORCE (LBS)	FACTORED VERT. LOAD (FLP)	LC1 MAX CSI (LC)	MEMB.	MAX. FACTORED FORCE (LBS)	MAX CSI (LC)
FR-TO		FROM	TO	FR-TO		
A-B	0/14	-91.8	-91.8	0.02 (1)	10.00	J-C -194 / 0 0.03 (1)
B-L	-31/4	-91.8	-91.8	0.01 (1)	6.25	C-I -22 / 0 0.01 (1)
L-C	-80/0	-91.8	-91.8	0.03 (1)	6.25	I-D -578 / 0 0.08 (1)
C-D	-8/0	-91.8	-91.8	0.39 (1)	10.00	H-E -22 / 0 0.01 (1)
D-E	-8/0	-91.8	-91.8	0.39 (1)	10.00	E-D -194 / 0 0.03 (1)
E-N	-80/0	-91.8	-91.8	0.03 (1)	6.25	K-L -121 / 0 0.00 (1)
N-F	-31/4	-91.8	-91.8	0.01 (1)	6.25	M-N -121 / 0 0.00 (1)
F-G	0/14	-91.8	-91.8	0.02 (1)	10.00	
B-K	0/42	-18.5	-18.5	0.04 (1)	10.00	
K-J	0/42	-18.5	-18.5	0.07 (4)	10.00	
J-I	0/29	-18.5	-18.5	0.10 (4)	10.00	
I-H	0/29	-18.5	-18.5	0.10 (4)	10.00	
H-M	0/42	-18.5	-18.5	0.07 (4)	10.00	
M-F	0/42	-18.5	-18.5	0.04 (1)	10.00	

DESIGN CRITERIA

SPECIFIED LOADS:
TOP CH. LL = 25.6 PSF
DL = 6.0 PSF
BOT CH. LL = 0.0 PSF
DL = 7.4 PSF
TOTAL LOAD = 39.0 PSF

SPACING = 24.0 IN./C

LOADING IN FLAT SECTION BASED ON A SLOPE OF 6.00/12

THIS TRUSS IS DESIGNED FOR RESIDENTIAL OR SMALL BUILDING REQUIREMENTS OF PART 9, NBCC 2010, NBCC 2015

THIS DESIGN COMPLIES WITH:
- PART 9 OF CBC 2018, CBC 2012, ABC 2019
- PART 9 OF CBC 2012 (2019 AMENDMENT)
- CSA 086-09, CSA 086-14
- TPIC 2011, TPIC 2014

(65 % OF 31.3 P.S.F. G.S.L. PLUS 8.4 P.S.F. RAIN LOAD) EQUALS 25.6 P.S.F. SPECIFIED ROOF LIVE LOAD

CSI: TC=0.39/1.00 (C-D:1), BC=0.10/1.00 (I-J:4), WB=0.09/1.00 (D-E:1), SSI=0.22/1.00 (D-E:1)

DOL LUMBER=1.00 NAIL=1.00 LS BEND=1.10 COMP=1.10 SHEAR=1.10 TENS=1.10

COMPANION LIVE LOAD FACTOR = 1.00

TRUSS PLATE MANUFACTURER IS NOT RESPONSIBLE FOR QUALITY CONTROL IN THE TRUSS MANUFACTURING PLANT.

NAIL VALUES
PLATE GRIP(DRY) SHEAR SECTION
(PSI) (PL) (PL)
MAX MIN MAX MIN MAX MIN
MT20 618 354 1887 788 1987 1656

PLATE PLACEMENT TOL = 0.250 inches

PLATE ROTATION TOL = 5.0 Deg.

JSI GRIP = 0.30 (D) (INPUT = 0.90)
JSI METAL = 0.12 (D) (INPUT = 1.00)




Structural component only
DWG# T-2007080

JOB NAME	TRUSS NAME	QUANTITY	PLY	JOB DESC.	TRUSS DESC.	DRWG NO.
408150	U1	21	1	GREEN PARK HOMES		

Tamarack Roof Truss, Burlington

Version 8.310 S Oct 29 2019 Mitek Industries, Inc. Sat Apr 25 11:02:42 2020 Page 1
ID:7vF?aG0E03cRUj6X1jSkzIwYK-9Vf1WN1jroVxKTDZRHsrR4TO3I_cmhDXnWhizNCnh



Scale = 1/2" = 1'-0"

LUMBER	N. L. G. A. RULES	CHORDS	SIZE	DRY	LUMBER
E - B	2x4	DRY	No.2		
A - C	2x4	DRY	No.2		
E - D	2x4	DRY	No.2		

DRY: SEASONED LUMBER.

PLATES (table is in inches)	JT TYPE	PLATES	W	LEN	Y	X
B	TMV+p	MT20	3.0	4.0		
E	BMV1+p	MT20	3.0	4.0		

DIMENSIONS, SUPPORTS AND LOADINGS SPECIFIED BY FABRICATOR TO BE VERIFIED BY BUILDING DESIGNER

BEARINGS	FACTORED	MAXIMUM FACTORED	INPUT	RECORD
GROSS REACTION	GROSS REACTION	GROSS REACTION	BRG	BRG
JT VERT	JT VERT	JT VERT	BRG	BRG
E	525	0	5-8	5-8
C	202	0	1-8	1-8
D	45	0	1-8	1-8

SEE MITEK STANDARD DETAIL B97791H FOR CONNECTION TO JOINT(S) C, D

UNFACTORED REACTIONS	1ST CASE	MAX/MIN. COMPONENT REACTIONS	PERM. LIVE	WIND	DEAD	SOIL
JT COMBINED	JT COMBINED	JT COMBINED	JT COMBINED	JT COMBINED	JT COMBINED	JT COMBINED
E	389	257 / 0	0 / 0	0 / 0	111 / 0	0 / 0
C	139	113 / 0	0 / 0	0 / 0	26 / 0	0 / 0
D	36	0 / 0	0 / 0	0 / 0	36 / 0	0 / 0

BEARING MATERIAL TO BE SPF NO.2 OR BETTER AT JOINT(S) E

BRACING
TOP CHORD TO BE SHEATHED OR MAX. PURLIN SPACING = 8.25 FT.
MAX. UNBRACED BOTTOM CHORD LENGTH = 10.00 FT OR RIGID CEILING DIRECTLY APPLIED.

ALL PITCH BREAKS AND PERIMETER CORNER JOINTS MUST BE Laterally RESTRAINED.

LOADING
TOTAL LOAD CASES: (4)

CHORDS			WEBS		
MEMB.	MAX. FACTORED FORCE (LBS)	FACTORED VERT. LOAD (PLF)	LC1 MAX CSI (LC)	MEMB.	MAX. FACTORED FORCE (LBS)
FR-TO		FROM TO	UNBRACED LENGTH FR-TO		MAX CSI (LC)
E-B	-481 / 0	0.0 0.0	0.13 (4) 7.81		
A-B	0 / 28	-91.8 -91.8	0.12 (1) 10.00		
B-C	-30 / 0	-91.8 -91.8	0.54 (1) 6.25		
E-D	0 / 0	-18.5 -18.5	0.13 (4) 10.00		

TOTAL WEIGHT = 21 X 17 = 353 lb

DESIGN CRITERIA

SPECIFIED LOADS:
TOP CH. LL = 25.8 PSF
DL = 6.0 PSF
BOT CH. LL = 0.0 PSF
DL = 7.4 PSF
TOTAL LOAD = 39.0 PSF

SPACING = 24.0 IN. OC

THIS TRUSS IS DESIGNED FOR RESIDENTIAL OR SMALL BUILDING REQUIREMENTS OF PART 9, NBC 2010, NBC 2015

THIS DESIGN COMPLIES WITH:
- PART 9 OF NBC 2010, NBC 2012, ABC 2019
- PART 9 OF NBC 2012 (2019 AMENDMENT)
- CSA 086-09, CSA 086-14
- TPIC 2011, TPIC 2014

DESIGN ASSUMPTIONS
OVERHANG NOT TO BE ALTERED OR CUT OFF.

(55 % OF 31.3 P.S.F. G.S.L. PLUS 8.4 P.S.F. RAIN LOAD) EQUALS 26.8 P.S.F. SPECIFIED ROOF LIVE LOAD

ALLOWABLE DEFL.(LL) = L/360 (0.20")
CALCULATED VERT. DEFL.(LL) = L/999 (0.00")
ALLOWABLE DEFL.(TL) = L/360 (0.20")
CALCULATED VERT. DEFL.(TL) = L/999 (0.03")

CS1: TC=0.54/1.00 (B-C:1), BC=0.13/1.00 (D-E:4), WB=0.00/1.00 (n/a:0), SS1=0.24/1.00 (B-C:1)

DOL LUMBER=1.00 NAIL=1.00 LS BEND=1.10
COMP=1.10 SHEAR=1.10 TENS=1.10

COMPANION LIVE LOAD FACTOR = 1.00

AUTOSOLVE RIGHT HEEL ONLY


TRUSS PLATE MANUFACTURER IS NOT RESPONSIBLE FOR QUALITY CONTROL IN THE TRUSS MANUFACTURING PLANT.

NAIL VALUES					
PLATE	GRIP(DRY)		SHEAR		SECTION
	(PS)		(PL)		(PL)
	MAX	MIN	MAX	MIN	MAX MIN
MT20	818	354	1667	788	1987 1658

PLATE PLACEMENT TOL. = 0.250 inches

PLATE ROTATION TOL. = 5.0 Deg.

JSI GRIP = 0.19 (E) (INPUT = 0.90)
JSI METAL = 0.13 (B) (INPUT = 1.00)




Structural component only
DWG# T-2007059

JOB NAME	TRUSS NAME	QUANTITY	PLY	JOB DESC.	GREEN PARK HOMES	DRWG NO.
408150	J2	1	1	TRUSS DESC.		

Tamarack Roof Truss, Burlington

Version 8.310 S Oct 29 2019 Mitek Industries, Inc. Sat Apr 25 11:02:43 2020 Page 1
ID:17vF7aG0E03cRUj8X1jSkzWYK-dhR1F0IU8kMYU2P78gwP2_KzqQIj30rSBX3DBzNCng



Scale = 1/2" = 1'-0"

LUMBER	DESCR.
N. L. G. A. RULES	
CHORDS	
F - B 2x4 DRY No.2	SPF
A - C 2x4 DRY No.2	SPF
F - D 2x4 DRY No.2	SPF
ALL WEBS 2x3 DRY No.2	SPF
DRY: SEASONED LUMBER.	

PLATES (table is in inches)	W	LEN	Y	X
JT TYPE PLATES				
B TMVW+p MT20	4.0	4.0	1.00	2.00
E BMW+w MT20	2.0	4.0		
F BMV1+p MT20	3.0	4.0		

DIMENSIONS, SUPPORTS AND LOADINGS SPECIFIED BY FABRICATOR TO BE VERIFIED BY BUILDING DESIGNER

FACTORED GROSS REACTION	MAXIMUM FACTORED GROSS REACTION	INPUT BRG	REQD BRG
VERT	HORZ	DOWN	HORZ
JT 341	0	341	0
F 341	0	341	0
C 178	0	178	0
D 38	0	40	0

SEE MITEK STANDARD DETAIL B97781H FOR CONNECTION TO JOINT(S) C, D

UNFACTORED REACTIONS		MAX/MIN COMPONENT REACTIONS					
JT	1ST LCASE COMBINED	SNOW	LIVE	PERM.LIVE	WIND	DEAD	SC
F	239	170/0	0/0	0/0	0/0	69/0	0/0
C	122	99/0	0/0	0/0	0/0	23/0	0/0
D	29	0/0	0/0	0/0	0/0	29/0	0/0

BEARING MATERIAL TO BE SPF NO.2 OR BETTER AT JOINT(S) F

BRACING
TOP CHORD TO BE SHEATHED OR MAX. PURLIN SPACING = 10.00 FT.
MAX. UNBRACED BOTTOM CHORD LENGTH = 10.00 FT OR RIGID CEILING DIRECTLY APPLIED.

ALL PITCH BREAKS AND PERIMETER CORNER JOINTS MUST BE LATERALLY RESTRAINED.

LOADING
TOTAL LOAD CASES: (5)

CHORDS	MAX. FACTORED FORCE (LBS)	FACTORED VERT. LOAD (LBS)	MAX. VERT. LOAD (LBS)	MAX. HORZ. LOAD (LBS)	UNBRACED LENGTH FR-TO	WEBS	MAX. FACTORED FORCE (LBS)	MAX. HORZ. LOAD (LBS)
FR-TO								
F-B	-305/0	0.0	0.0	0.03 (1)	7.81	B-E	0/0	0.00 (1)
A-B	0/41	-91.8	-91.8	0.14 (5)	10.00			
B-C	0/0	-91.8	-91.8	0.23 (1)	10.00			
F-E	0/0	-18.5	-18.5	0.08 (4)	10.00			
E-D	0/0	-18.5	-18.5	0.08 (4)	10.00			

CANTILEVER ANALYSIS HAS BEEN CONSIDERED IN THIS DESIGN

TOTAL WEIGHT = 15 lb

DESIGN CRITERIA

SPECIFIED LOADS:
TOP CH. LL = 25.6 PSF
DL = 6.0 PSF
BOT CH. LL = 0.0 PSF
DL = 7.4 PSF
TOTAL LOAD = 39.0 PSF

SPACING = 24.0 IN. C/C

THIS TRUSS IS DESIGNED FOR RESIDENTIAL OR SMALL BUILDING REQUIREMENTS OF PART 9, NBC 2010, NBCC 2015

THIS DESIGN COMPLIES WITH:
- PART 9 OF CBC 2018, OBC 2012, ABC 2019
- PART 9 OF OBC 2012 (2019 AMENDMENT)
- CSA 088-09, CSA 088-14
- TPIC 2011, TPIC 2014

(55 % OF 31.3 P.S.F. G.S.L. PLUS 6.4 P.S.F. RAIN LOAD) EQUALS 25.6 P.S.F. SPECIFIED ROOF LIVE LOAD

ALLOWABLE DEFL.(LL) = L/360 (0.19")
CALCULATED VERT. DEFL.(LL) = L/999 (0.00")
ALLOWABLE DEFL.(TL) = L/360 (0.19")
CALCULATED VERT. DEFL.(TL) = L/999 (0.01")

CSI: TC=0.23/1.00 (B-C:1), BC=0.08/1.00 (D-E:4), WB=0.00/1.00 (B-E:1), SST=0.11/1.00 (B-C:1)

DOL LUMBER=1.00 NAIL=1.00 LS BEND=1.10
COMP=1.10 SHEAR=1.10 TENS=1.10

COMPANION LIVE LOAD FACTOR = 1.00

AUTOSOLVE RIGHT HEEL ONLY

TRUSS PLATE MANUFACTURER IS NOT RESPONSIBLE FOR QUALITY CONTROL IN THE TRUSS MANUFACTURING PLANT.

NAIL VALUES
PLATE GRIP(DRY) (PSI) SHEAR (PLI) SECTION (PLI)
MAX MIN MAX MIN MAX MIN
MT20 618 354 1667 788 1697 1658

PLATE PLACEMENT TOL. = 0.250 inches

PLATE ROTATION TOL. = 5.0 Deg.


JSI GRIP= 0.24 (B) (INPUT = 0.99)
JSI METAL= 0.06 (B) (INPUT = 1.00)



Structural component only
DWG# T-2007060

JOB NAME	TRUSS NAME	QUANTITY	PLY	JOB DESC.	DRWG NO.
408152	J40	4	1	GREEN PARK HOMES	
Tamarack Roof Truss, Burlington				TRUSS DESC.	

Version 8.310 S Oct 29 2019 Mitek Industries, Inc. Sat Apr 25 11:29:29 2020 Page 1
ID:37vF?aG0E03cRUj6X1jSrkzWYK-bfU8J?2Gb4UDlp3CRUXVjVnrDY50PbEi222b6zNCOa



Scale = 1/23.2

LUMBER			
N. L. G. A. RULES	CHORDS	SIZE	LUMBER
E - A	2x4	DRY	No.2
A - B	2x4	DRY	No.2
E - C	2x4	DRY	No.2
ALL WEBS	2x3	DRY	No.2
DRY: SEASONED LUMBER.			

PLATES (table in inches)					
JT	TYPE	PLATES	W	LEN	Y X
A	TMVW-t	MT20	4.0	4.0	2.00 1.25
D	BMW-w	MT20	2.0	4.0	
E	BMV1-p	MT20	3.0	4.0	

DIMENSIONS, SUPPORTS AND LOADINGS SPECIFIED BY FABRICATOR TO BE VERIFIED BY BUILDING DESIGNER

FACTORED GROSS REACTION		MAXIMUM FACTORED GROSS REACTION		INPUT BRG		REQ'D BRG	
JT	VERT	HORZ	DOWN	HORZ	UPLIFT	IN-SX	IN-SX
E	209	0	209	0	0	MECHANICAL	
B	174	0	174	0	0	1-8	1-8
C	35	0	39	0	0	1-8	1-8

A SUITABLE HANGER/MECHANICAL CONNECTION IS REQUIRED AT JOINT E. MINIMUM BEARING LENGTH AT JOINT E = 1-8.

SEE MITEK STANDARD DETAIL 697791H FOR CONNECTION TO JOINT(S) B, C

UNFACTORED REACTIONS

1ST LOASE		MAX./MIN. COMPONENT REACTIONS		PERM. LIVE		WIND		DEAD		SOIL	
JT	COMBINED	SNOW	LIVE	PERM. LIVE	WIND	DEAD	SOIL	COMBINED	SNOW	LIVE	PERM. LIVE
E	148	97/0	0/0	0/0	0/0	51/0	0/0				
B	120	97/0	0/0	0/0	0/0	23/0	0/0				
C	28	0/0	0/0	0/0	0/0	28/0	0/0				

BRACING

TOP CHORD TO BE SHEATHED OR MAX. PURLIN SPACING = 10.00 FT.
MAX. UNBRACED BOTTOM CHORD LENGTH = 10.00 FT OR RIGID CEILING DIRECTLY APPLIED.

ALL PITCH BREAKS AND PERIMETER CORNER JOINTS MUST BE LATERALLY RESTRAINED.

LOADING

TOTAL LOAD CASES: (4)

CHORDS		FACTORED		WEBS		FACTORED	
MEMB.	FORCE (LBS)	VERT. LOAD (PLF)	LC1 MAX	MAX. MEMB. FORCE (LBS)	UNBRACED LENGTH	FR-TO	CS1 (LC)
FR-TO		FROM	TO				
E-A	-174/0	0.0	0.0	0.02 (1)	7.81	A-D	0/0
A-B	0/0	-91.8	-91.8	0.22 (1)	10.00		0.00 (1)
E-D	0/0	-18.5	-18.5	0.07 (4)	10.00		
D-C	0/0	-18.5	-18.5	0.08 (4)	10.00		

TOTAL WEIGHT = 4 X 13 = 52 lb

DESIGN CRITERIA

SPECIFIED LOADS:
TOP CH. LL = 25.6 PSF
DL = 6.0 PSF
BOT CH. LL = 0.0 PSF
DL = 7.4 PSF
TOTAL LOAD = 39.0 PSF

SPACING = 24.0 IN. C/C

THIS TRUSS IS DESIGNED FOR RESIDENTIAL OR SMALL BUILDING REQUIREMENTS OF PART 9, NBCC 2010, NBCC 2015

THIS DESIGN COMPLIES WITH:

- PART 9 OF BCBC 2018, CBC 2012, ABC 2019
- PART 9 OF CBC 2012 (2019 AMENDMENT)
- CSA 088-09, CSA 088-14
- TPIC 2011, TPIC 2014

(55 % OF 31.3 P.S.F. G.S.L. PLUS 8.4 P.S.F. RAIN LOAD) EQUALS 25.6 P.S.F. SPECIFIED ROOF LIVE LOAD

ALLOWABLE DEFL.(LL) = L/360 (0.19")
CALCULATED VERT. DEFL.(LL) = L/999 (0.00")
ALLOWABLE DEFL.(TL) = L/360 (0.19")
CALCULATED VERT. DEFL.(TL) = L/999 (0.01")

CSI: TC=0.22/1.00 (A-B:1), BC=0.08/1.00 (C-D:4),
WB=0.00/1.00 (A-D:1), SS=0.12/1.00 (A-B:1)

DOL LUMBER=1.00 NAIL=1.00 LS BEND=1.10
COMP=1.10 SHEAR=1.10 TENS=1.10

COMPANION LIVE LOAD FACTOR = 1.00

TRUSS PLATE MANUFACTURER IS NOT RESPONSIBLE FOR QUALITY CONTROL IN THE TRUSS MANUFACTURING PLANT.

NAIL VALUES
PLATE GRIP(DRY) SHEAR SECTION
(PSI) (PLI) (PLI)
MAX MIN MAX MIN MAX MIN
MT20 618 354 1857 788 1987 1656

PLATE PLACEMENT TOL = 0.250 inches

PLATE ROTATION TOL = 5.0 Deg.


JSI GRIP = 0.11 (A) (INPUT = 0.90)
JSI METAL = 0.03 (A) (INPUT = 1.00)



Structural component only
DWG# T-2007105

JOB NAME	TRUSS NAME	QUANTITY	PLY	JOB DESC.	TRUSS DESC.	ORWG NO.
408152	J41	4	1	GREEN PARK HOMES		
Tamarack Roof Truss, Burlington						

Version 8.310 S Oct 29 2019 Mitek Industries, Inc. Sat Apr 25 11:28:31 2020 Page 1
ID:17vF?aG0E03cRUj6X1jSrkzIWYK-Y2cwkhrJoCKCTbzSJsX?a8a7q0FFUJ5WDM29g_zNCOY



TOTAL WEIGHT = 4 X 10 = 38 lb

LUMBER			
N. L. G. A. RULES	CHORDS	SIZE	LUMBER
E - B	2x4	DRY	No.2
A - C	2x4	DRY	No.2
E - D	2x4	DRY	No.2

DRY: SEASONED LUMBER.

DIMENSIONS, SUPPORTS AND LOADINGS SPECIFIED BY FABRICATOR TO BE VERIFIED BY BUILDING DESIGNER

FACTORED		MAXIMUM FACTORED		INPUT		REQ'D	
GROSS REACTION	DOWN	GROSS REACTION	DOWN	8RG	8RG	8RG	8RG
JT	319	319	0	5-8	5-8	5-8	5-8
E	99	99	0	1-8	1-8	1-8	1-8
C	23	23	0	1-8	1-8	1-8	1-8

DESIGN CRITERIA

SPECIFIED LOADS:
TOP CH. LL = 25.6 PSF
DL = 6.0 PSF
BOT CH. LL = 0.0 PSF
DL = 7.4 PSF
TOTAL LOAD = 39.0 PSF

SPACING = 24.0 IN. C/C

THIS TRUSS IS DESIGNED FOR RESIDENTIAL OR SMALL BUILDING REQUIREMENTS OF PART 9, NBCC 2010, NBCC 2015

THIS DESIGN COMPLIES WITH:
- PART 9 OF CBC 2018, CBC 2012, ABC 2019
- PART 9 OF CBC 2012 (2019 AMENDMENT)
- CSA 088-09, CSA 088-14
- TPIC 2011, TPIC 2014

DESIGN ASSUMPTIONS
- OVERHANG NOT TO BE ALTERED OR CUT OFF.

(55% OF 31.3 P.S.F. G.S.L. PLUS 8.4 P.S.F. RAIN LOAD) EQUALS 25.6 P.S.F. SPECIFIED ROOF LIVE LOAD

ALLOWABLE DEFL.(LL) = L/360 (0.19")
CALCULATED VERT. DEFL.(LL) = L/999 (0.00")
ALLOWABLE DEFL.(TL) = L/360 (0.19")
CALCULATED VERT. DEFL.(TL) = L/999 (0.00")

CSI: TC=0.13/1.00 (B-C:1), BC=0.03/1.00 (D-E:4), WB=0.00/1.00 (n/a:0), SSI=0.11/1.00 (B-C:1)

DOL LUMBER=1.00 NAIL=1.00 LB BEND=1.10 COMP=1.10 SHEAR=1.10 TENS=1.10

COMPANION LIVE LOAD FACTOR = 1.00

AUTOSOLVE RIGHT HEEL ONLY

TRUSS PLATE MANUFACTURER IS NOT RESPONSIBLE FOR QUALITY CONTROL IN THE TRUSS MANUFACTURING PLANT.

NAIL VALUES

PLATE	GRIP(DRY)	SHEAR	SECTION
(PSI)	(PL)	(PL)	(PL)
MT20	618	354	1667 788 1987 1656

PLATE PLACEMENT TOL = 0.250 Inches

PLATE ROTATION TOL = 5.0 Deg.

JSI GRIP= 0.12 (E) (INPUT = 0.90)
JSI METAL= 0.08 (B) (INPUT = 1.00)

PLATES (table is in inches)				
JT	TYPE	PLATES	W	LEN Y X
B	TMV+p	MT20	3.0	4.0
E	BMV1+p	MT20	3.0	4.0

SEE MITEK STANDARD DETAIL B97791H FOR CONNECTION TO JOINT(S) C, D

UNFACTORED REACTIONS

1ST LCASE	MAX. MIN. COMPONENT REACTIONS						
JT	COMBINED	SNOW	LIVE	PERM. LIVE	WIND	DEAD	SOIL
E	223	181/0	0/0	0/0	0/0	62/0	0/0
C	68	56/0	0/0	0/0	0/0	13/0	0/0
D	18	0/0	0/0	0/0	0/0	18/0	0/0

BEARING MATERIAL TO BE SPF NO.2 OR BETTER AT JOINT(S) E

BRACING

TOP CHORD TO BE SHEATHED OR MAX. PURLIN SPACING = 6.25 FT.
MAX. UNBRACED BOTTOM CHORD LENGTH = 10.00 FT OR RIGID CEILING DIRECTLY APPLIED.


ALL PITCH BREAKS AND PERIMETER CORNER JOINTS MUST BE Laterally RESTRAINED.

LOADING

TOTAL LOAD CASES: (5)

CHORDS		FACTORED		WEBS		FACTORED	
MEMB.	FORCE (LBS)	VERT. LOAD (PLF)	LC1 MAX	MAX. UNBRACED LENGTH	MEMB.	FORCE (LBS)	MAX. CSI (LC)
FR-TO		FROM TO			FR-TO		
E-B	-289/0	0.0	0.0	0.02 (4)	7.81		
A-B	0/28	-91.8	-91.8	0.13 (5)	10.00		
B-C	-15/0	-91.8	-91.8	0.13 (1)	6.25		
E-D	0/0	-18.5	-18.5	0.03 (4)	10.00		

CANTILEVER ANALYSIS HAS BEEN CONSIDERED IN THIS DESIGN




Structural component only
DWG# T-2007108

JOB NAME 408150	TRUSS NAME C1	QUANTITY 1	PLY 1	JOB DESC. GREEN PARK HOMES	TRUSS DESC.	DRWG NO.
---------------------------	-------------------------	----------------------	-----------------	--------------------------------------	-------------	----------

Tamarack Roof Truss, Burlington

Version 8.310 S Oct 29 2019 Mitek Industries, Inc. Sat Apr 25 11:02:37 2020 Page 1
ID17vF?aG0E03cRUj6X1jSrkziWYK-oX4m_oJvul_CqZaFmuZV9nkjvPNuJLXy4F4l0XzNcNm



Scale = 1:19.0

LUMBER			
N. L. G. A. RULES	SIZE	LUMBER	DESCR.
CHORDS			
F - B	2x4	DRY	No.2
A - C	2x4	DRY	No.2
F - D	2x4	DRY	No.2
ALL WEBS	2x3	DRY	No.2
DRY: SEASONED LUMBER.			

DESCR.
SPF
SPF
SPF

DIMENSIONS, SUPPORTS AND LOADINGS SPECIFIED BY FABRICATOR TO BE VERIFIED BY BUILDING DESIGNER

BEARINGS

	FACTORED GROSS REACTION	MAXIMUM FACTORED GROSS REACTION	INPUT BRG	REQD BRG
	VERT	HORZ	DOWN	UPLIFT
JT	297	0	0	5-8
F	42	0	42	1-8
C	42	0	0	1-8
D	36	0	0	1-8

SEE MITEK STANDARD DETAIL B97791H FOR CONNECTION TO JOINT(S) C, D

PROVIDE ANCHORAGE AT BEARING JOINT C FOR 150 LBS FACTORED UPLIFT

UNFACTORED REACTIONS

JT	1ST CASE	MAX/MIN COMPONENT REACTIONS	SNOW	LIVE	PERM LIVE	WIND	DEAD	SOIL
F	208	145/0	0/0	0/0	0/0	0/0	63/0	0/0
C	29	23/-26	0/0	0/0	0/0	0/0	5/0	0/0
D	29	0/0	0/0	0/0	0/0	0/0	29/0	0/0

BEARING MATERIAL TO BE SPF NO.2 OR BETTER AT JOINT(S) F, C

BRACING

TOP CHORD TO BE SHEATHED OR MAX. PURLIN SPACING = 6.25 FT.
MAX. UNBRACED BOTTOM CHORD LENGTH = 10.00 FT OR RIGID CEILING DIRECTLY APPLIED.

ALL PITCH BREAKS AND PERIMETER CORNER JOINTS MUST BE Laterally RESTRAINED.

LOADING

TOTAL LOAD CASES: (5)

CHORDS				WEBS			
MEMB.	MAX. FACTORED FORCE (LBS)	VERT. LOAD (PLF)	MAX. FACTORED CSI (LC)	MEMB.	MAX. FACTORED FORCE (LBS)	MAX. FACTORED CSI (LC)	
FR-TO		FROM TO		FR-TO			
F-B	-281/0	0.0	0.0 0.03 (1)	B-E	0/0	0.00 (1)	
A-B	0/41	-91.8	-91.8 0.14 (5)				
B-C	-29/0	-91.8	-91.8 0.14 (5)				
F-E	0/0	-18.5	-18.5 0.08 (4)				
E-G	0/0	-18.5	-18.5 0.08 (4)				
G-D	0/0	-18.5	-18.5 0.08 (4)				

FACTORED CONCENTRATED LOADS (LBS)

JT	LOC.	LC1	MAX-	MAX+	FACE	DIR.	TYPE	HEEL	CONN.
G	2-0-12	1	1	1	BACK	VERT	TOTAL		C1

CONNECTION REQUIREMENTS

1) C1: A SUITABLE HANGER/MECHANICAL CONNECTION IS REQUIRED.

CANTILEVER ANALYSIS HAS BEEN CONSIDERED IN THIS DESIGN

DESIGN CRITERIA

SPECIFIED LOADS:

TOP CH. LL	= 25.6 PSF
DL	= 6.0 PSF
BOT CH. LL	= 0.0 PSF
DL	= 7.4 PSF
TOTAL LOAD	= 39.0 PSF

SPACING = 24.0 IN. C/C

THIS TRUSS IS DESIGNED FOR RESIDENTIAL OR SMALL BUILDING REQUIREMENTS OF PART 9, NBCG 2010, NBCG 2015

THIS DESIGN COMPLIES WITH:

- PART 9 OF NBCG 2010, OBC 2012, ABC 2010
- PART 9 OF OBC 2012 (2019 AMENDMENT)
- CSA 088-09, CSA 088-14
- TPIC 2011, TPIC 2014

DESIGN ASSUMPTIONS

OVERHANG NOT TO BE ALTERED OR CUT OFF.

(55 % OF 31.3 P.S.F. G.S.L. PLUS 8.4 P.S.F. RAIN LOAD) EQUALS 25.6 P.S.F. SPECIFIED ROOF LIVE LOAD

ALLOWABLE DEFL.(LL) = $L/380$ (0.19')
CALCULATED VERT. DEFL.(LL) = $L/999$ (0.00')
ALLOWABLE DEFL.(TL) = $L/380$ (0.19')
CALCULATED VERT. DEFL.(TL) = $L/999$ (0.01')

CSI: TC=0.14/1.00 (A-B-5), BC=0.08/1.00 (D-E-4),
WB=0.00/1.00 (B-E-1), SS=0.08/1.00 (A-B-5)

DOL LUMBER=1.00 NAIL=1.00 LS BEND=1.10
COMP=1.10 SHEAR=1.10 TENS=1.10

COMPANION LIVE LOAD FACTOR = 1.00

AUTOSOLVE RIGHT HEEL ONLY

TRUSS PLATE MANUFACTURER IS NOT RESPONSIBLE FOR QUALITY CONTROL IN THE TRUSS MANUFACTURING PLANT.

NAIL VALUES

PLATE GRIP(DRY)	SHEAR (PSI)	SECTION (PLI)
MAX MIN	MAX MIN	MAX MIN
MT20	618 354	1887 788

PLATE PLACEMENT TOL = 0.250 inches

PLATE ROTATION TOL = 5.0 Deg.


JSI GRIP = 0.20 (B) (INPUT = 0.90)
JSI METAL = 0.05 (B) (INPUT = 1.00)



Structural component only
DWG# T-2007055

JOB NAME	TRUSS NAME	QUANTITY	PLY	JOB DESC.	DRWG NO.
408150	C2	1	1	GREEN PARK HOMES	
Tamarack Roof Truss, Burlington				TRUSS DESC.	

Version 8.310 S Oct 29 2019 Mitek Industries, Inc. Sat Apr 25 11:02:38 2020 Page 1
ID:7vF7aG0E03cRUj8X1jSkzIWK-Gke8C8KXlc83Sj9SKb4i7GVwpk52on6lvpIY_zNCn



Scale = 1:10.0

LUMBER			
N. L. G. A. RULES	SIZE	LUMBER	DESCR.
CHORDS			
E - B	2x4 DRY	No.2	SPF
A - C	2x4 DRY	No.2	SPF
E - D	2x4 DRY	No.2	SPF
ALL WEBS	2x3 DRY	No.2	SPF
DRY: SEASONED LUMBER.			

PLATES (table is in inches)					
JT TYPE	PLATES	W	LEN	Y	X
B TMVW+p	MT20	4.0	4.0	1.00	2.00
D BMV1-i	MT20	4.0	4.0	2.00	1.25
E BMV1-p	MT20	3.0	4.0		

DIMENSIONS, SUPPORTS AND LOADINGS SPECIFIED BY FABRICATOR TO BE VERIFIED BY BUILDING DESIGNER

BEARINGS		FACTORED		MAXIMUM FACTORED		INPUT		RECORD	
JT	VERT	GROSS REACTION	DOWN	GROSS REACTION	HORIZ	UPLIFT	IN-SX	BRG	IN-SX
E	278	0	278	0	0	0	5-8	5-8	5-8
C	42	0	42	0	38	1-8	1-8	1-8	1-8
D	18	0	20	0	0	1-8	1-8	1-8	1-8

SEE MITEK STANDARD DETAIL B97791H FOR CONNECTION TO JOINT(S) C, D

PROVIDE ANCHORAGE AT BEARING JOINT C FOR 150 LBS. FACTORED UPLIFT

UNFACTORED REACTIONS		1ST LCASE		MAX/MIN. COMPONENT REACTIONS	
JT	COMBINED	SNOW	LIVE	PERM.LIVE	WIND
E	184	145/0	0/0	0/0	0/0
C	29	23/-28	0/0	0/0	0/0
D	14	0/0	0/0	0/0	0/0

BEARING MATERIAL TO BE SPF NO.2 OR BETTER AT JOINT(S) E, C

BRACING

TOP CHORD TO BE SHEATHED OR MAX. PURLIN SPACING = 6.25 FT.
MAX. UNBRACED BOTTOM CHORD LENGTH = 10.00 FT. OR RIGID CEILING DIRECTLY APPLIED.

ALL PITCH BREAKS AND PERIMETER CORNER JOINTS MUST BE LATERALLY RESTRAINED.

LOADING

TOTAL LOAD CASES: (5)

CHORDS		FACTORED		WEBS	
MEMB.	MAX. FACTORED FORCE (LBS)	VERT. LOAD	LC1 MAX (PLF)	MAX. UNBRAC LENGTH FR-TO	MEMB. MAX. FACTORED FORCE (LBS)
FR-TO					
E-B	-281/0	0.0	0.0	0.03 (1)	7.81
A-B	0/41	-91.8	-91.8	0.13 (1)	10.00
B-C	-29/0	-91.8	-91.8	0.12 (1)	6.25
E-D	0/0	-18.5	-18.5	0.02 (4)	10.00

CANTILEVER ANALYSIS HAS BEEN CONSIDERED IN THIS DESIGN

TOTAL WEIGHT = 10 lb

DESIGN CRITERIA

SPECIFIED LOADS:
TOP CH. LL = 25.6 PSF
DL = 6.0 PSF
BOT CH. LL = 0.0 PSF
DL = 7.4 PSF
TOTAL LOAD = 39.0 PSF

SPACING = 24.0 IN/C

THIS TRUSS IS DESIGNED FOR RESIDENTIAL OR SMALL BUILDING REQUIREMENTS OF PART 9, NBCC 2010, NBCC 2015

THIS DESIGN COMPLIES WITH:

- PART 9 OF BCBC 2010, OBC 2012, ABC 2019
- PART 9 OF OBC 2012 (2019 AMENDMENT)
- CSA 088-09, CSA 088-14
- TPIC 2011, TPIC 2014

DESIGN ASSUMPTIONS

OVERHANG NOT TO BE ALTERED OR CUT OFF.

(55 % OF 31.3 P.S.F. G.S.L. PLUS 8.4 P.S.F. RAIN LOAD) EQUALS 25.6 P.S.F. SPECIFIED ROOF LIVE LOAD

ALLOWABLE DEFL. (TL) = L/360 (0.10")
CALCULATED VERT. DEFL. (TL) = L/999 (0.00")

CSI: TO=0.13/1.00 (A-B:1), BC=0.02/1.00 (D-E:4),
WB=0.00/1.00 (B-D:1), SI=0.08/1.00 (B-C:1)

DOL LUMBER=1.00 NAIL=1.00 LS BEND=1.10
COMP=1.10 SHEAR=1.10 TENS=1.10

COMPANION LIVE LOAD FACTOR = 1.00

TRUSS PLATE MANUFACTURER IS NOT RESPONSIBLE FOR QUALITY CONTROL IN THE TRUSS MANUFACTURING PLANT.


NAIL VALUES

PLATE GRIP (DRY)	SHEAR SECTION (PSI)	(PLI)	(PLI)
MAX MIN	MAX MIN	MAX MIN	MAX MIN
MT20	618	354	1867

PLATE PLACEMENT TOL. = 0.250 inches


PLATE ROTATION TOL. = 5.0 Deg.

JSI GRIP = 0.20 (B) (INPUT = 0.90)
JSI METAL = 0.05 (B) (INPUT = 1.00)



Structural component only
DWG# T-2007056

JOB NAME	TRUSS NAME	QUANTITY	PLY	JOB DESC.	DRWG NO.
408152	C40	4	1	GREEN PARK HOMES	
Tamarack Roof Truss, Burlington					
Version 8.310 S Oct 28 2019 MTEK Industries, Inc. Sat Apr 25 11:29:21 2020 Page 1					
ID:17vF7aG0E03cRUj6X1jSkzlWYK-q778eGk1873dG3CXkILfA19Pt_o08nd2voddJZzNCOi					



LUMBER	N. L. G. A. RULES	CHORDS	SIZE	LUMBER
E - B	2x4	DRY	No.2	
A - C	2x4	DRY	No.2	
E - D	2x4	DRY	No.2	

DRY: SEASONED LUMBER.

PLATES (tablets in inches)	W	LEN	Y	X
JT TYPE	MT20	3.0	4.0	
B TMV+p	MT20	3.0	4.0	
E BMV1+p	MT20	3.0	4.0	

DIMENSIONS, SUPPORTS AND LOADINGS SPECIFIED BY FABRICATOR TO BE VERIFIED BY BUILDING DESIGNER

BEARINGS

JT	FACTORED GROSS REACTION	MAXIMUM FACTORED GROSS REACTION	INPUT BRG	RECORD BRG
E	405	405	0	5-8
C	130	130	0	1-8
D	45	50	0	1-8

SEE MITEK STANDARD DETAIL B97791H FOR CONNECTION TO JOINT(S) C, D

UNFACTORED REACTIONS

JT	1ST CASE COMBINED	SNOW	LIVE	PERM. LIVE	WIND	DEAD	SOIL
E	288	190 / 0	0 / 0	0 / 0	0 / 0	98 / 0	0 / 0
C	90	73 / 0	0 / 0	0 / 0	0 / 0	17 / 0	0 / 0
D	36	0 / 0	0 / 0	0 / 0	0 / 0	38 / 0	0 / 0

BEARING MATERIAL TO BE SPF NO.2 OR BETTER AT JOINT(S) E, C

BRACING

TOP CHORD TO BE SHEATHED OR MAX. PURLIN SPACING = 6.25 FT.
MAX. UNBRACED BOTTOM CHORD LENGTH = 10.00 FT. OR RIGID CEILING DIRECTLY APPLIED.

ALL PITCH BREAKS AND PERIMETER CORNER JOINTS MUST BE Laterally RESTRAINED.

LOADING

TOTAL LOAD CASES: (4)

CHORDS	MAX. FACTORED FORCE (LBS)	FACTORED VERT. LOAD (PLF)	LC1 MAX. (LC)	MAX. UNBRACED LENGTH FR-TO	WEBS	MAX. FACTORED FORCE (LBS)	MAX. (LC)
FR-TO							
E-B	-342 / 0	0.0	0.0	0.13 (4)	7.81		
A-B	0 / 28	-91.8	-91.8	0.12 (1)	10.00		
B-C	-19 / 0	-91.8	-91.8	0.22 (1)	6.25		
E-D	0 / 0	-18.5	-18.5	0.13 (4)	10.00		

TOTAL WEIGHT = 4 X 14 = 57 lb

DESIGN CRITERIA

SPECIFIED LOADS:

TOP CH.	LL	=	25.8	PSF
	DL	=	6.0	PSF
BOT CH.	LL	=	0.0	PSF
	DL	=	7.4	PSF
TOTAL LOAD		=	39.0	PSF

SPACING = 24.0 IN. OC

THIS TRUSS IS DESIGNED FOR RESIDENTIAL OR SMALL BUILDING REQUIREMENTS OF PART 9, NBC 2010, NBCC 2015

THIS DESIGN COMPLIES WITH:

- PART 9 OF BCRC 2018, OBC 2012, ABC 2019
- PART 9 OF OBC 2012 (2019 AMENDMENT)
- CSA 088-09, CSA 086-14
- TPIC 2011, TPIC 2014

DESIGN ASSUMPTIONS

- OVERHANG NOT TO BE ALTERED OR CUT OFF.

(55 % OF 31.3 P.S.F. G.S.L. PLUS 8.4 P.S.F. RAIN LOAD) EQUALS 25.6 P.S.F. SPECIFIED ROOF LIVE LOAD

ALLOWABLE DEFL. (LL) = $L/360$ (0.20")
CALCULATED VERT. DEFL. (LL) = $L/999$ (0.00")
ALLOWABLE DEFL. (TL) = $L/360$ (0.20")
CALCULATED VERT. DEFL. (TL) = $L/999$ (0.03")

CSI: TC=0.22/1.00 (B-C:1), BC=0.13/1.00 (D-E:4).
WB=0.00/1.00 (n/a:0), SSI=0.15/1.00 (B-C:1)

DOL LUMBER=1.00 NAIL=1.00 LB BEND=1.10
COMP=1.10 SHEAR=1.10 TENS=1.10

COMPANION LIVE LOAD FACTOR = 1.00

AUTOSOLVE RIGHT HEEL ONLY

TRUSS PLATE MANUFACTURER IS NOT RESPONSIBLE FOR QUALITY CONTROL IN THE TRUSS MANUFACTURING PLANT.

NAIL VALUES

PLATE	GRIP (DRY)	SHEAR	SECTION
(PS)	(PL)	(PL)	(PL)
MAX	MIN	MAX	MIN
618	354	1887	788

PLATE PLACEMENT TOL = 0.250 inches


PLATE ROTATION TOL = 5.0 Deg.

JSI GRIP= 0.14 (E) (INPUT = 0.90)
JSI METAL= 0.09 (B) (INPUT = 1.00)



Structural component only
DWG# T-2007098

JOB NAME	TRUSS NAME	QUANTITY	PLY	JOB DESC.	DRWG NO.
408152	C41	4	1	GREEN PARK HOMES	
Tamarack Roof Truss, Burlington					
Version 8.310 3 Oct 29 2019 Mittek Industries, Inc. Sat Apr 25 11:29:23 2020 Page 1					
ID:7vF?aG0E03cRUj6X1jSrkzIWK-nV7u2yHglJKVNMvRAN7FSFnyoUmch6LN66kNSzNCOg					
Scale = 1:12.1					



LUMBER			
N. L. G. A. RULES			
CHORDS	SIZE	DRY	LUMBER
E - B	2x4	DRY	No.2
A - C	2x4	DRY	No.2
E - D	2x4	DRY	No.2
DRY, SEASONED LUMBER.			

PLATES (table is in inches)				
JT	TYPE	PLATES	W	LEN Y X
B	TMV+p	MT20	3.0	4.0
E	BMV1+p	MT20	3.0	4.0

DIMENSIONS, SUPPORTS AND LOADINGS SPECIFIED BY FABRICATOR TO BE VERIFIED BY BUILDING DESIGNER

JT	FACTORED GROSS REACTION		MAXIMUM FACTORED GROSS REACTION		INPUT BRG	REQD BRG
	VERT	HORZ	DOWN	HORZ	IN-SX	IN-SX
E	284	0	284	0	5-8	5-8
C	63	0	63	0	1-8	1-8
D	44	0	52	0	1-8	1-8

SEE MITTEK STANDARD DETAIL B87791H FOR CONNECTION TO JOINT(S) C, D

UNFACTORED REACTIONS

JT	1ST LOASE		MAX/MIN. COMPONENT REACTIONS		WIND	DEAD	SOIL
	COMBINED	SNOW	LIVE	PERM. LIVE	IN-SX	IN-SX	IN-SX
E	200	137/0	0/0	0/0	0/0	62/0	0/0
C	48	21/0	0/0	0/0	0/0	25/0	0/0
D	35	0/3	0/0	0/0	0/0	37/0	0/0

BEARING MATERIAL TO BE SPF NO.2 OR BETTER AT JOINT(S) E, C

BRACING

TOP CHORD TO BE SHEATHED OR MAX. PURLIN SPACING = 10.00 FT.
MAX. UNBRACED BOTTOM CHORD LENGTH = 10.00 FT OR RIGID CEILING DIRECTLY APPLIED.

ALL PITCH BREAKS AND PERIMETER CORNER JOINTS MUST BE Laterally RESTRAINED.

LOADING

TOTAL LOAD CASES: (7)

MEMB.	CHORDS		FACTORED		WEBS		FACTORED	
	MAX. FORCE (LBS)	VERT. LOAD (LBS)	MAX. (PL)	MAX. (LC)	MEMB. FORCE (LBS)	MAX. (PL)	MAX. (LC)	MEMB. FORCE (LBS)
FR-TO								
E-B	227/0	0.0	0.0	0.11 (4)	7.61			
A-B	0/28	-91.8	-91.8	0.12 (1)	10.00			
B-C	-9/9	-91.8	-91.8	0.08 (4)	10.00			
E-F	0/0	-18.5	-18.5	0.14 (4)	10.00			
F-G	0/0	-18.5	-18.5	0.14 (4)	10.00			
G-D	0/0	-18.5	-18.5	0.14 (4)	10.00			

FACTORED CONCENTRATED LOADS (LBS)

JT	LOC.	LC1	MAX.	MAX.	FACE	DIR.	TYPE	HEEL	CONN.
F	1-11-4	7	1	12	BACK	VERT	TOTAL		C1
G	3-11-4	1	1		BACK	VERT	TOTAL		C1

CONNECTION REQUIREMENTS

1) C1: A SUITABLE HANGER/MECHANICAL CONNECTION IS REQUIRED.

TOTAL WEIGHT = 4 X 12 = 48 lb (M)

DESIGN CRITERIA

SPECIFIED LOADS:
TOP CH. LL = 25.6 PSF
DL = 8.0 PSF
BOT CH. LL = 0.0 PSF
DL = 7.4 PSF
TOTAL LOAD = 39.0 PSF

SPACING = 24.0 IN. C/C

THIS TRUSS IS DESIGNED FOR RESIDENTIAL OR SMALL BUILDING REQUIREMENTS OF PART 9, NBCC 2010, NBCC 2015

THIS DESIGN COMPLIES WITH:
- PART 9 OF BCBC 2018, OBC 2012, ABC 2019
- PART 9 OF OBC 2012 (2019 AMENDMENT)
- CSA 088-09, CSA 088-14
- TPIC 2011, TPIC 2014

DESIGN ASSUMPTIONS

- OVERHANG NOT TO BE ALTERED OR CUT OFF.

(55% OF 31.3 P.S.F. G.S.L. PLUS 8.4 P.S.F. RAIN LOAD) EQUALS 25.6 P.S.F. SPECIFIED ROOF LIVE LOAD

ALLOWABLE DEFL.(LL) = L/360 (0.20")
CALCULATED VERT. DEFL.(LL) = U/999 (0.01")
ALLOWABLE DEFL.(TL) = L/360 (0.20")
CALCULATED VERT. DEFL.(TL) = U/999 (0.04")

CSI: TC=0.12/1.00 (A-B:1), BC=0.14/1.00 (D-E:4),
WB=0.00/1.00 (n/a:0), SSI=0.09/1.00 (A-B:1)

DOL LUMBER=0.88 NAIL=0.98 LS BEND=1.10
COMP=1.10 SHEAR=1.10 TENS=1.10

COMPANION LIVE LOAD FACTOR = 1.00

AUTOSOLVE RIGHT HEEL ONLY

TRUSS PLATE MANUFACTURER IS NOT RESPONSIBLE FOR QUALITY CONTROL IN THE TRUSS MANUFACTURING PLANT.


NAIL VALUES

PLATE GRIP(DRY) SHEAR SECTION
(PSI) (PLI) (PLI)
MAX MIN MAX MIN MAX MIN
MT20 618 354 1667 788 1987 1856

PLATE PLACEMENT TOL. = 0.250 inches

PLATE ROTATION TOL. = 5.0 Deg.

JSI GRIP= 0.10 (E) (INPUT = 0.90)
JSI METAL= 0.08 (B) (INPUT = 1.00)




Structural component only.
DWG# T-2007099

JOB NAME	TRUSS NAME	QUANTITY	PLY	JOB DESC.	GREEN PARK HOMES	DRWG NO.
408152	C42	4	1	TRUSS DESC.		

Tamarack Roof Truss, Burlington

Version 8.310 S Oct 29 2019 Mitek Industries, Inc. Sat Apr 25 11:29:24 2020 Page 1
ID:37vF7aG0E03cRUj6X1jSkzIWK-FihGGHmvR2RB7Xx6PivMognw6CsuL8MVcmrHwuzNCO



Scale = 1/16" = 1'-0"

LUMBER	N. L. G. A. RULES	CHORDS	SIZE	LUMBER
E - B	2x4	DRY	No.2	
A - C	2x4	DRY	No.2	
E - D	2x4	DRY	No.2	

DRY: SEASONED LUMBER.

PLATES (table is in inches)	JT TYPE	PLATES	W	LEN	Y	X
B	TMV+p	MT20	3.0	4.0		
E	BMV1+p	MT20	3.0	4.0		

DIMENSIONS, SUPPORTS AND LOADINGS SPECIFIED BY FABRICATOR TO BE VERIFIED BY BUILDING DESIGNER

BEARINGS	FACTORED	MAXIMUM FACTORED	INPUT	REQD
	GROSS REACTION	GROSS REACTION	BRG	BRG
	VERT	HORZ	DOWN	UP/LIFT
	IN-SX	IN-SX	IN-SX	IN-SX
JT	361	0	361	0
E	361	0	361	0
C	130	0	130	0
D	18	0	17	0

SEE MITEK STANDARD DETAIL B97791H FOR CONNECTION TO JOINT(S) C, D

UNFACTORED REACTIONS

1ST CASE	SNOW	LIVE	PERM. LIVE	WIND	DEAD	SOIL
JT	COMBINED	MAX/MIN	COMPONENT REACTIONS			
E	250	190/0	0/0	0/0	60/0	0/0
C	90	73/0	0/0	0/0	17/0	0/0
D	12	0/0	0/0	0/0	12/0	0/0

BEARING MATERIAL TO BE SPF NO.2 OR BETTER AT JOINT(S) E

BRACING

TOP CHORD TO BE SHEATHED OR MAX. PURLIN SPACING = 6.25 FT.
MAX. UNBRACED BOTTOM CHORD LENGTH = 10.00 FT OR RIGID CEILING DIRECTLY APPLIED.

ALL PITCH BREAKS AND PERIMETER CORNER JOINTS MUST BE LATERALLY RESTRAINED.

LOADING

TOTAL LOAD CASES: (5)

CHORDS				WEBS			
MEMB.	MAX. FACTORED FORCE (LBS)	FACTORED VERT. LOAD (PLF)	LC1 MAX CSI (LC)	MAX. UNBRAC LENGTH	MEMB.	MAX. FACTORED FORCE (LBS)	MAX CSI (LC)
FR-TO		FROM	TO		FR-TO		
E-B	-342/0	0.0	0.0	0.01 (4)	7.81		
A-B	0/28	-91.8	-91.8	0.13 (5)	10.00		
B-C	-19/0	-91.8	-91.8	0.22 (1)	6.25		
E-D	0/0	-18.5	-18.5	0.02 (4)	10.00		

CANTILEVER ANALYSIS HAS BEEN CONSIDERED IN THIS DESIGN

TOTAL WEIGHT = 4 X 10 = 38 lb

DESIGN CRITERIA

SPECIFIED LOADS:

TOP CH. LL	= 25.6	PSF
DL	= 6.0	PSF
BOT CH. LL	= 0.0	PSF
DL	= 7.4	PSF
TOTAL LOAD	= 39.0	PSF

SPACING = 24.0 IN. C/C

THIS TRUSS IS DESIGNED FOR RESIDENTIAL OR SMALL BUILDING REQUIREMENTS OF PART 9, NBCC 2010, NBCC 2015

THIS DESIGN COMPLIES WITH:

- PART 9 OF BCBC 2018, OBC 2012, ABC 2018
- PART 9 OF OBC 2012 (2018 AMENDMENT)
- CSA 086-09, CSA 086-14
- TPIC 2011, TPIC 2014

DESIGN ASSUMPTIONS

OVERHANG NOT TO BE ALTERED OR CUT OFF.

(55 % OF 31.3 P.S.F. G.S.L. PLUS 8.4 P.S.F. RAIN LOAD) EQUALS 25.6 P.S.F. SPECIFIED ROOF LIVE LOAD

ALLOWABLE DEFL.(LL) = L/360 (0.19")
CALCULATED VERT. DEFL.(LL) = L/999 (0.00")
ALLOWABLE DEFL.(TL) = L/360 (0.19")
CALCULATED VERT. DEFL.(TL) = L/999 (0.00")

CSI: TC=0.22/1.00 (B-C:1), EC=0.02/1.00 (D-E:4),
WB=0.00/1.00 (N/A:0), SSI=0.15/1.00 (B-C:1)

DOL LUMBER=1.00 NAIL=1.00 LS BEND=1.10
COMP=1.10 SHEAR=1.10 TENS=1.10

COMPANION LIVE LOAD FACTOR = 1.00

AUTOSOLVE RIGHT HEEL ONLY

TRUSS PLATE MANUFACTURER IS NOT RESPONSIBLE FOR QUALITY CONTROL IN THE TRUSS MANUFACTURING PLANT.


NAIL VALUES

PLATE GRIP (DRY)	SHEAR	SECTION
(PSI)	(PLI)	(PLI)
MAX	MIN	MAX
MIN	MAX	MIN
MT20	618	354
	1667	788
	1987	1656

PLATE PLACEMENT TOL. = 0.250 inches

PLATE ROTATION TOL. = 5.0 Deg.

JSI GRIP= 0.14 (E) (INPUT = 0.90)
JSI METAL= 0.09 (B) (INPUT = 1.00)




Structural component only
DWG# T-2007100

JOB NAME 408152	TRUSS NAME C43	QUANTITY 4	PLY 1	JOB DESC. GREEN PARK HOMES	TRUSS DESC.	DRWG NO.
---------------------------	--------------------------	----------------------	-----------------	--------------------------------------	-------------	----------

Tamarack Roof Truss, Burlington

Version 8.310 S Oct 29 2019 Mitek Industries, Inc. Sat Apr 25 11:29:25 2020 Page 1
ID: i7vF7aG0E03cRUj8X1SrkziWYK-juEFTdnYCMa2lgWibQbK1K7UcCo4bceqQbrSKzNCOe



Scale = 1/16\"/>

LUMBER				
N. L. G. A. RULES				
CHORDS	SIZE		LUMBER	DESCR.
E - B	2x4	DRY	No.2	SPF
A - C	2x4	DRY	No.2	SPF
E - D	2x4	DRY	No.2	SPF
DRY: SEASONED LUMBER				

PLATES (table is in inches)

JT	TYPE	PLATES	W	LEN	Y	X
B	TMV-p	MT20	3.0	4.0		
E	BMV1-p	MT20	3.0	4.0		

DIMENSIONS, SUPPORTS AND LOADINGS SPECIFIED BY FABRICATOR TO BE VERIFIED BY BUILDING DESIGNER

BEARINGS

JT	FACTORED GROSS REACTION		MAXIMUM FACTORED GROSS REACTION		INPUT BRG	REQD BRG
	VERT	HORZ	DOWN	HORZ		
E	271	0	271	0	5-8	5-8
C	45	0	45	0	1-8	1-8
D	8	0	17	0	1-8	1-8

SEE MITEK STANDARD DETAIL B97791H FOR CONNECTION TO JOINT(S) C, D

PROVIDE ANCHORAGE AT BEARING JOINT C FOR 150 LBS FACTORED UPLIFT
PROVIDE ANCHORAGE AT BEARING JOINT D FOR 150 LBS FACTORED UPLIFT

UNFACTORED REACTIONS

JT	COMBINED	MAX/MIN. COMPONENT REACTIONS					
		SNOW	LIVE	PERM. LIVE	WIND	DEAD	SOIL
E	188	141 / 0	0 / 0	0 / 0	0 / 0	47 / 0	0 / 0
C	31	24 / -18	0 / 0	0 / 0	0 / 0	7 / 0	0 / 0
D	7	0 / -8	0 / 0	0 / 0	0 / 0	12 / 0	0 / 0

BEARING MATERIAL TO BE SPF NO.2 OR BETTER AT JOINT(S) E, C

BRACING
TOP CHORD TO BE SHEATHED OR MAX. PURLIN SPACING = 8.25 FT.
MAX. UNBRACED BOTTOM CHORD LENGTH = 10.00 FT. OR RIGID CEILING DIRECTLY APPLIED.

ALL PITCH BREAKS AND PERIMETER CORNER JOINTS MUST BE LATERALLY RESTRAINED.

LOADING

TOTAL LOAD CASES: (5)									
CHORDS					WEBS				
MEMB.	MAX. FACTORED FORCE (LBS)	FACTORED VERT. LOAD (PLF)	LOAD C1	MAX CSI (L.C)	MAX. UNBRAC LENGTH	MEMB.	MAX. FACTORED FORCE (LBS)	MAX CSI (L.C)	
FR-TO		FROM	TO			FR-TO			
E-B	-244 / 0	0.0	0.0	0.04 (5)	7.81				
A-B	0 / 28	-91.8	-91.8	0.12 (1)	10.00				
B-C	-17 / 0	-91.8	-91.8	0.09 (1)	6.25				
E-D	0 / 0	-18.5	-18.5	0.04 (5)	10.00				

CANTILEVER ANALYSIS HAS BEEN CONSIDERED IN THIS DESIGN

TOTAL WEIGHT = 4 X 7 = 28 lb

DESIGN CRITERIA

SPECIFIED LOADS:
TOP CH. LL = 25.8 PSF
DL = 6.0 PSF
BOT CH. LL = 0.0 PSF
DL = 7.4 PSF
TOTAL LOAD = 39.0 PSF

SPACING = 24.0 IN. C/C

THIS TRUSS IS DESIGNED FOR RESIDENTIAL OR SMALL BUILDING REQUIREMENTS OF PART 9, NBC 2010, NBCC 2015

THIS DESIGN COMPLIES WITH:
- PART 9 OF CBC 2018, OBC 2012, ABC 2019
- PART 9 OF OBC 2012 (2019 AMENDMENT)
- CSA 088-09, CSA 088-14
- TPIC 2011, TPIC 2014

DESIGN ASSUMPTIONS
- OVERHANG NOT TO BE ALTERED OR CUT OFF.

(55 % OF 31.3 P.S.F. G.S.L. PLUS 8.4 P.S.F. RAIN LOAD) EQUALS 25.8 P.S.F. SPECIFIED ROOF LIVE LOAD

ALLOWABLE DEFL.(LL) = L/380 (0.19")
CALCULATED VERT. DEFL.(LL) = L/999 (0.00")
ALLOWABLE DEFL.(TL) = L/380 (0.19")
CALCULATED VERT. DEFL.(TL) = L/999 (0.00")

CSI: TC=0.12/1.00 (A-B:1), BC=0.04/1.00 (D-E:5),
WB=0.09/1.00 (W&D), SB=0.09/1.00 (A-B:1)

DOL LUMBER=1.00 NAIL=1.00 LS BEND=1.10
COMP=1.10 SHEAR=1.10 TENS=1.10

COMPANION LIVE LOAD FACTOR = 1.00

AUTOSOLVE RIGHT HEEL ONLY

TRUSS PLATE MANUFACTURER IS NOT RESPONSIBLE FOR QUALITY CONTROL IN THE TRUSS MANUFACTURING PLANT.


NAIL VALUES

PLATE GRIP (DRY)	SHEAR (PSI)	SECTION (PLI)
MAX MIN	MAX MIN	MAX MIN
MT20	618 354	1667 788

PLATE PLACEMENT TOL. = 0.250 inches


PLATE ROTATION TOL. = 5.0 Deg.

JSI GRIP = 0.10 (E) (INPUT = 0.80)
JSI METAL = 0.07 (B) (INPUT = 1.00)



Structural component only
DWG# T-2007101

JOB NAME	TRUSS NAME	QUANTITY	PLY	JOB DESC.	DRWG NO.
408152	C44	2	1	GREEN PARK HOMES	
Tamarack Roof Truss, Burlington					



LUMBER			
N. L. G. A. RULES	SIZE	LUMBER	DESCR.
CHORDS	2x4	DRY	No.2
E - B	2x4	DRY	No.2
A - C	2x4	DRY	No.2
E - D	2x4	DRY	No.2

DRY: SEASONED LUMBER.

PLATES (table is in inches)				
JT	TYPE	PLATES	W	LEN Y X
B	TMV+p	MT20	3.0	4.0
E	BMV1+p	MT20	3.0	4.0

DIMENSIONS, SUPPORTS AND LOADINGS SPECIFIED BY FABRICATOR TO BE VERIFIED BY BUILDING DESIGNER

BEARINGS		FACTORED	MAXIMUM FACTORED	INPUT	REQD
JT	VERT	GROSS REACTION	GROSS REACTION	BRG	BRG
E	264	0	0	5-8	5-8
C	68	0	0	1-8	1-8
D	23	0	0	1-8	1-8

SEE MTEK STANDARD DETAIL B97791H FOR CONNECTION TO JOINT(S) C, D

UNFACTORED REACTIONS		1ST LCASE	SNOW	LIVE	PERM LIVE	WIND	DEAD	SOIL
JT	COMBINED	MAX	MIN	COMPONENT	REACTIIONS			
E	185	130/0	0/0	0/0	0/0	0/0	55/0	0/0
C	48	37/0	0/0	0/0	0/0	0/0	9/0	0/0
D	18	0/0	0/0	0/0	0/0	0/0	18/0	0/0

BEARING MATERIAL TO BE SPF NO.2 OR BETTER AT JOINT(S) E, C

BRACING
TOP CHORD TO BE SHEATHED OR MAX. PURLIN SPACING = 10.00 FT.
MAX. UNBRACED BOTTOM CHORD LENGTH = 10.00 FT OR RIGID CEILING DIRECTLY APPLIED.

ALL PITCH BREAKS AND PERIMETER CORNER JOINTS MUST BE Laterally RESTRAINED.

LOADING
TOTAL LOAD CASES: (5)

CHORDS		MAX. FACTORED	FACTORED	WEBS	MAX. FACTORED
MEMB.	FORCE	VERT.	LOAD	MEMB.	FORCE
FR-TO	(LBS)	FROM	TO	FR-TO	(LBS)
E-B	-234/0	0.0	0.0	0.02 (4)	7.81
A-B	0/28	-91.8	-91.8	0.13 (5)	10.00
B-C	-10/0	-91.8	-91.8	0.08 (1)	10.00
E-F	0/0	-18.5	-18.5	0.03 (4)	10.00
F-D	0/0	-18.5	-18.5	0.03 (4)	10.00

FACTORED CONCENTRATED LOADS (LBS)		JT	LOC.	LC1	MAX.	MAX+	FACE	DIR.	TYPE	HEEL	CONN.
F	2-0-12	1	1	1	1	1	FRONT	VERT	TOTAL	---	C1

CONNECTION REQUIREMENTS

1) C1: A SUITABLE HANGER/MECHANICAL CONNECTION IS REQUIRED.

CANTILEVER ANALYSIS HAS BEEN CONSIDERED IN THIS DESIGN

TOTAL WEIGHT = 2 X 8 = 17 lb

DESIGN CRITERIA

SPECIFIED LOADS:
TOP CH. LL = 25.6 PSF
DL = 6.0 PSF
BOT CH. LL = 0.0 PSF
DL = 7.4 PSF
TOTAL LOAD = 38.0 PSF

SPACING = 24.0 IN. C/C

THIS TRUSS IS DESIGNED FOR RESIDENTIAL OR SMALL BUILDING REQUIREMENTS OF PART 9, NBC 2010, NBC 2015

THIS DESIGN COMPLIES WITH:
- PART 9 OF BCBC 2018, OBC 2012, ABC 2019
- PART 9 OF OBC 2012 (2019 AMENDMENT)
- CSA 088-09, CSA 088-14
- TPIC 2011, TPIC 2014

DESIGN ASSUMPTIONS
OVERHANG NOT TO BE ALTERED OR CUT OFF.

(65 % OF 31.3 P.S.F. G.S.L. PLUS 8.4 P.S.F. RAIN LOAD) EQUALS 25.6 P.S.F. SPECIFIED ROOF LIVE LOAD

ALLOWABLE DEFL.(LL) = L/360 (0.18")
CALCULATED VERT. DEFL.(LL) = L/989 (0.00")
ALLOWABLE DEFL.(TL) = L/360 (0.18")
CALCULATED VERT. DEFL.(TL) = L/989 (0.00")

CSI: TC=0.13/1.00 (A-B:5), BC=0.03/1.00 (D-E:4), WB=0.00/1.00 (n/a:0), SSI=0.10/1.00 (A-B:5)

DOL LUMBER=1.00 NAIL=1.00 LS BEND=1.10
COMP=1.10 SHEAR=1.10 TENS=1.10

COMPANION LIVE LOAD FACTOR = 1.00

AUTOSOLVE RIGHT HEEL ONLY


TRUSS PLATE MANUFACTURER IS NOT RESPONSIBLE FOR QUALITY CONTROL IN THE TRUSS MANUFACTURING PLANT.

NAIL VALUES
PLATE GRIP(DRY) SHEAR SECTION
(PSI) (PLI) (PLI)
MAX MIN MAX MIN MAX MIN
MT20 618 354 1687 788 1987 1656

PLATE PLACEMENT TOL. = 0.250 inches

PLATE ROTATION TOL. = 5.0 Deg.

JSI GRIP=0.10 (E) (INPUT = 0.90)
JSI METAL=0.08 (B) (INPUT = 1.00)



Structural component only
DWG# T-2007102



DIMENSIONS, SUPPORTS AND LOADINGS SPECIFIED BY FABRICATOR TO BE VERIFIED BY

SEE MITEK STANDARD DETAIL B97791H FOR CONNECTION TO JOINT(S) C. D.

UNFACTORED REACTIONS

BEARING MATERIAL TO BE SPF NO.2 OR BETTER AT JOINT(S) E. C

BRACING

TOP CHORD TO BE SHEATHED OR MAX. PURLIN SPACING = 10.00 FT.
MAX. UNBRACED BOTTOM CHORD LENGTH = 10.00 FT OR RIGID CEILING DIRECTLY APPLIED.

ALL PITCH BREAKS AND PERIMETER CORNER JOINTS MUST BE Laterally RESTRAINED.

LOADING

TOTAL LOAD CASES: (5)

CANTILEVER ANALYSIS HAS BEEN CONSIDERED IN THIS DESIGN

DESIGN CRITERIA

SPECIFIED LOADS:			
TOP CH.	LL	= 25.6	PSF
	DL	= 6.0	PSF
BOT CH.	LL	= 0.0	PSF
	DL	= 7.4	PSF
TOTAL LOAD		= 39.0	PSF

SPACING = 24.0 IN. C/C

THIS TRUSS IS DESIGNED FOR RESIDENTIAL OR
SMALL BUILDING REQUIREMENTS OF PART 9,
NBCC 2010, NBCC 2015

THIS DESIGN COMPLIES WITH:
 - PART 9 OF CBC 2018, OBC 2012, ABC 2019
 - PART 9 OF OBC 2012 (2019 AMENDMENT)
 - CSA 088-09, CSA 088-14
 - TPIC 2011, TPIC 2014

DESIGN ASSUMPTIONS

-OVERHANG NOT TO BE ALTERED OR CUT OFF.

(55 % OF 31.3 P.S.F. G.S.L. PLUS 8.4 P.S.F. RAIN LOAD) EQUALS 25.6 P.S.F. SPECIFIED ROOF LIVE LOAD

ALLOWABLE DEFL.(LL) = $L/360$ (0.19")
CALCULATED VERT. DEFL.(LL) = $L/999$ (0.00")
ALLOWABLE DEFL.(TL) = $L/360$ (0.19")
CALCULATED VERT. DEFL.(TL) = $L/999$ (0.00")

CSI: TC=0.12/1.00 (A-B:1) , BC=0.02/1.00 (D-E:4) ,
WB=0.00/1.00 (n/a:0) , SSI=0.09/1.00 (A-B:1)

DOL LUMBER=1.00 NAIL=1.00 LS BEND=1.10
COMP=1.10 SHEAR=1.10 TENS= 1.10

COMPANION LIVE LOAD FACTOR = 1.00

AUTOSOLVE RIGHT HEEL ONLY

TRUSS PLATE MANUFACTURER IS NOT RESPONSIBLE FOR QUALITY CONTROL IN THE TRUSS MANUFACTURING PLANT.

NAIL VALUES

PLATE	GRIP(DRY) (PSI)		SHEAR (PLI)		SECTION (PLI)	
	MAX	MIN	MAX	MIN	MAX	MIN
MT20	618	354	1987	788	1987	1656

PLATE PLACEMENT TOL. = 0.250 inches

PLATE ROTATION TOL. = 5.0 Deg.

JSI GRIP= 0.10 (E) (INPUT = 0.90)
JSI METAL= 0.06 (B) (INPUT = 1.00)



Structural component only
DWG# T-2007103

LUL/LUS/LJS/HUS/HHUS/HGUS

Standard and Double-Shear Joist Hangers



This product is preferable to similar connectors because of
a) easier installation, b) higher capacities, c) lower installed
cost, or a combination of these features.

Most hangers in this series have double-shear nailing — an innovation that distributes the load through two points on each joist nail for greater strength. This allows for fewer nails, faster installation, and the use of all common nails for the same connection. (Do not bend or remove tabs)

Double-shear hangers range from the light capacity LUS hangers to the highest capacity HGUS hangers. For medium load truss applications, the HUS offers a lower cost alternative and easier installation than the HGUS hangers, while providing greater load capacity and bearing than the LUS.

Material: See table on pp. 258–259.

Finish: Galvanized. Some products available in stainless steel or ZMAX® coating; see Corrosion Information, pp. 20–24.

Installation:


- Use all specified fasteners; see General Notes.
- Nails must be driven at an angle through the joist or truss into the header to achieve the tabulated resistances (except LUL).
- Where 16d commons are specified, 10d commons may be used at 0.83 of the tabulated factored resistance.
- Not designed for welded or nailer applications.
- With single ply 2x carrying members, use 10d x 1½" nails into the header and 10d commons into the joist, and reduce the resistance to 0.64 of the table value where 16d nails are specified and 0.77 where 10d nails are specified.

Options:


- LUS, LJS, LUL and HUS hangers cannot be modified.
- Other sizes available; consult your Simpson Strong-Tie representative.
- See Hanger Options Information on p. 126.




Double-Shear Nailing Top View




Double-Shear Nailing Side View; Do not bend tab




Dome Double-Shear Nailing Side View (available on some models)
U.S. Patent 5,603,580




LUS28




LU26L



HUS210
(HUS26, HUS28, and HHUS similar)





HGUS28-2



HHUS210-2

Typical HUS26 Installation with Reduced Heel Height
(Truss Designer to provide fastener quantity for connecting multiple members together)



LJS26DS

LUL/LUS/LJS/HUS/HHUS/HGUS**HHUS/HGUS**

See Hanger Options information on pp. 125–127.


HHUS — Sloped and/or Skewed Seat

- HHUS hangers can be skewed to a maximum of 45° and/or sloped to a maximum of 45°
- For skew only, maximum factored down resistance is 0.85 of the table value
- For sloped only or sloped and skewed hangers, the maximum factored down resistance is 0.72 of the table value
- Uplift resistances for sloped/skewed conditions are 0.62 of the table value
- The joist must be bevel-cut to allow for double-shear nailing

HGUS — Skewed Seat

- HGUS hangers can be skewed only to a maximum of 45°. Factored resistances are:

HGUS Seat Width	Joist	Down Resistance	Uplift
$W < 2"$	Bevel or square cut	0.62 of table value	0.46 of table value
$2" < W < 6"$	Bevel cut	0.67 of table value	0.41 of table value
$2" < W < 6"$	Square cut	0.46 of table value	0.41 of table value
$W > 6"$	Bevel cut	0.75 of table value	0.41 of table value



Top View HHUS Hanger
Skewed Right
(joist must be bevel cut)
All joist nails installed on the
outside angle (non-acute side).

Standard and Double-Shear Joist Hangers (cont.)

These products are available with additional corrosion protection. For more information, see p. 24.

These products are approved for installation with the Strong-Drive® SD Connector screw. See pp. 32–34 for more information.

Model No.	Ga.	Dimensions (in.)				Fasteners		Factored Resistance				
		W	H	B	d _g ³	Header	Joist	D.Fir-L		S-P-F		
								Uplift	Normal	Uplift	Normal	
								(K _D = 1.15) lb.	(K _D = 1.00) lb.	(K _D = 1.15) lb.	(K _D = 1.00) lb.	
Single 2x Sizes												
■	LUS24	18	1 1/8	3 1/4	1 1/4	2 1/4	(4) 10d	(2) 10d	710	1626	645	1155
									3.16	7.23	2.87	5.14
	LU24L	22	1 1/8	3	1 1/4	2 1/8	(4) 10d	(2) 10d x 1 1/2"	360	1020	320	725
									1.60	4.54	1.42	3.22
	LU26L	22	1 1/8	5	1 1/4	4 1/4	(6) 10d	(4) 10d x 1 1/2"	720	1605	645	1140
									3.20	7.14	2.87	5.07
SS	LUS26	18	1 1/8	4 1/4	1 1/4	3 3/4	(4) 10d	(4) 10d	1420	2170	1290	1630
									6.32	9.65	5.74	7.25
■	HUS28	16	1 1/8	5 1/4	3	3 1/8	(14) 16d	(6) 16d	2705	4940	2065	3875
									11.30	21.97	9.20	17.24
	LJS28DS	18	1 1/8	5	3 1/2	4 1/4	(16) 16d	(6) 16d	2055	4265	1460	4115
									9.14	18.97	6.49	18.31
	HGUS26	12	1 1/8	5 1/4	5	4 1/4	(20) 16d	(8) 16d	2885	6625	2685	5700
									11.96	29.51	11.96	25.35
	LU28L	20	1 1/8	6 1/4	1 1/4	5 1/4	(8) 10d	(6) 10d x 1 1/2"	1140	2185	1020	1550
									5.07	9.72	4.54	8.89
SS	LUS28	18	1 1/8	6 1/4	1 1/4	3 3/4	(6) 10d	(4) 10d	1420	2520	1290	1790
									6.32	11.21	5.74	7.96
■	HUS28	16	1 1/8	7 1/4	3	6 1/8	(22) 16d	(8) 16d	3605	5365	2675	4345
									16.04	23.86	11.90	19.33
	HGUS28	12	1 1/8	7 1/4	5	6 1/4	(36) 16d	(12) 16d	3310	7675	3310	6900
									14.74	34.19	14.74	30.73
	LU210L	20	1 1/8	8	1 1/4	7 1/4	(10) 10d	(8) 10d x 1 1/2"	1140	2495	1020	1770
									5.07	11.10	4.54	7.87
SS	LUS210	18	1 1/8	7 1/4	1 1/4	3 3/4	(8) 10d	(4) 10d	1420	2785	1290	2210
									6.32	12.39	5.74	9.83

1. Factored uplift resistances have been increased 15% for wind or earthquake loading; no further increase is allowed.
2. Designer must ensure that hanger is compatible with truss when reduced heel height is used.
3. d_g is the distance from the bearing seat to the top joist nail.
4. Resistances shown require a minimum 2-ply girder truss. For fastening to single-ply truss request technical bulletin T-C-N10TRSSCN and/or see installation notes.
5. Nails: 16d = 0.162" dia. x 3 1/2" long. See pp. 27–28 for other nail sizes and information.

Face-Mount Hangers

These products are available with additional corrosion protection. For more information, see p. 24.

These products are approved for installation with the Strong-Drive® SD Connector screw. See pp. 32-34 for more information.

Model No.	Ga.	Dimensions (in.)				Fasteners		Factored Resistance						
		W	H	B	d _g ^a	Header	Joist	D.Fir-L		S-P-F				
								Uplift	Normal	Uplift	Normal			
								(K _g = 1.15) lb.	(K _g = 1.00) lb.	(K _g = 1.15) lb.	(K _g = 1.00) lb.			
kN												kN	kN	kN
Double 2x Sizes														
LUS24-2	18	3 1/8	3 1/8	2	1 1/2	(4) 16d	(2) 16d	835	2020	590	1435			
SS LUS26-2	18	3 1/8	4 1/8	2	4	(4) 16d	(4) 16d	3.71	8.99	2.62	6.38			
								1720	2595	1545	1920			
HHUS26-2	14	3 1/8	5 1/8	3	3 1/8	(14) 16d	(6) 16d	7.65	11.54	6.87	8.64			
								2850	7335	2065	5205			
HGUS28-2	12	3 1/8	5 1/8	4	4 1/8	(20) 16d	(8) 16d	12.68	32.63	9.20	23.15			
								4385	8950	3110	6355			
SS LUS28-2	18	3 1/8	7	2	4	(6) 16d	(4) 16d	19.51	39.81	13.83	28.27			
								1720	3325	1545	2575			
HHUS28-2	14	3 1/8	7 1/8	3	6 1/8	(22) 16d	(8) 16d	7.65	14.79	6.87	11.45			
								3765	8940	2675	6345			
HGUS28-2	12	3 1/8	7 1/8	4	8 1/8	(36) 16d	(12) 16d	16.75	39.77	11.90	28.22			
								6070	12980	4310	9215			
SS LUS210-2	18	3 1/8	0	2	6	(8) 16d	(6) 16d	27.00	57.74	19.17	40.99			
								2580	4500	2320	3195			
HHUS210-2	14	3 1/8	9 1/8	3	8	(30) 16d	(10) 16d	11.48	20.02	10.32	14.21			
								4670	9600	4235	7000			
HGUS210-2	12	3 1/8	9 1/8	4	8 1/8	(46) 16d	(16) 16d	26.77	42.97	18.84	31.14			
								6840	14015	4855	10270			
								30.43	62.34	21.60	45.69			
Triple 2x Sizes														
HGUS28-3	12	4 1/8	5 1/8	4	4 1/8	(20) 16d	(8) 16d	4385	8950	3110	6355			
HGUS28-3	12	4 1/8	7 1/8	4	6 1/8	(36) 16d	(12) 16d	19.51	39.81	13.83	28.27			
								6070	12980	4310	9215			
HHUS210-3	14	4 1/8	9	3	7 1/8	(30) 16d	(10) 16d	27.00	57.74	19.17	40.99			
								4670	9670	4235	6865			
HGUS210-3	12	4 1/8	9 1/8	4	8 1/8	(46) 16d	(16) 16d	20.77	43.02	18.84	30.54			
								6840	14645	4855	10400			
								30.43	65.14	21.60	46.26			
Quadruple 2x Sizes														
HGUS28-4	12	6 1/8	5 1/8	4	4 1/8	(20) 16d	(8) 16d	4385	8950	3110	6355			
HGUS28-4	12	6 1/8	7 1/8	4	6 1/8	(36) 16d	(12) 16d	19.51	39.81	13.83	28.27			
								6070	12980	4310	9215			
HHUS210-4	14	6 1/8	9	3	7 1/8	(30) 16d	(10) 16d	27.00	57.74	19.17	40.99			
								4670	10155	4235	7210			
HGUS210-4	12	6 1/8	9 1/8	4	8 1/8	(46) 16d	(16) 16d	20.77	45.17	18.84	32.07			
								6840	14645	4855	10400			
HGUS212-4	12	6 1/8	10 1/8	4	10 1/8	(56) 16d	(20) 16d	30.43	65.14	21.60	46.26			
								7640	14995	5425	10645			
HGUS214-4	12	6 1/8	12 1/8	4	11 1/8	(66) 16d	(22) 16d	33.98	66.70	24.13	47.35			
								10130	16400	7195	11645			
								45.06	72.95	32.00	51.80			
4x Sizes														
LUS46	18	3 1/8	4 1/8	2	3 1/8	(4) 16d	(4) 16d	1720	2595	1545	1920			
HHUS46	14	3 1/8	5 1/8	3	3 1/8	(14) 16d	(6) 16d	7.65	11.54	6.87	8.64			
								2540	7335	2065	5205			
HGUS46	12	3 1/8	5 1/8	4	4 1/8	(20) 16d	(8) 16d	11.30	32.63	9.20	23.15			
								4385	8950	3110	6355			
LUS48	18	3 1/8	6 1/8	2	3 1/8	(6) 16d	(4) 16d	19.51	39.81	13.83	28.27			
								1720	3325	1545	2575			
HHUS48	14	3 1/8	7 1/8	3	6 1/8	(22) 16d	(8) 16d	7.65	14.79	6.87	11.45			
								3765	8940	2675	6345			
HGUS48	12	3 1/8	7 1/8	4	6 1/8	(36) 16d	(12) 16d	16.75	39.77	11.90	28.22			
								6070	12980	4310	9215			
LUS410	18	3 1/8	8 1/8	2	5 1/8	(8) 16d	(6) 16d	27.00	57.74	19.17	40.99			
								2580	4500	2320	3195			
HGUS410	12	3 1/8	9	4	8 1/8	(46) 16d	(16) 16d	11.48	20.02	10.32	14.21			
								6840	14015	4855	10270			
HGUS412	12	3 1/8	10 1/8	4	10 1/8	(56) 16d	(20) 16d	30.43	62.34	21.60	45.69			
								7640	14995	5425	10645			
HGUS414	12	3 1/8	12 1/8	4	11 1/8	(66) 16d	(22) 16d	33.98	66.70	24.13	47.35			
								10130	16400	7195	11645			
								46.08	72.95	32.00	51.80			

C-C-CAN2018 © 2017 SIMPSON STRONG-TIE COMPANY INC.



Plated Truss Connectors

TC - Truss Connectors

SIMPSON
Strong-Tie

The TC truss connector is an ideal connector for scissor trusses and can allow horizontal movement up to 1/4". The TC also attaches plated trusses to top plates or sill plates to resist uplift forces. Typically used on one or both ends of truss as determined by the building designer.

Material: 16 gauge

Finish: G90 galvanized


Design: Factored resistances are in accordance with CSA 086-14

Installation:

- Use all specified fasteners.
- Nails: 10d = 0.148" dia. x 3" long common wire, 10d x 1 1/2" = 0.148" dia. x 1 1/2" long.
- Drive 10d nails into the truss at the inside end of the slotted holes (inside end is towards the centre of the truss) and clinch on the back side. Do not seat these nails into the truss—allow room under the nail head for movement of the truss with respect to the wall.


Optional TC Installation:

- Bend one flange up 90°. Drive specified nails into the top and face of the top plates or install Titen® screws into the top and face of masonry wall. See optional load tables and installation details.




TC24

U.S. Patent 4,932,173




TC26


(TC28 Similar)



Typical TC24 Installation



Optional TC26 Installation for Grouted Concrete Block using a Wood Nailer (8", 10", 12" Wall Installation Similar)



Optional TC26 Installation for Grouted Concrete Block using Titen Screws

Model No.	Fasteners		Factored Resistance	
	Truss	Wall Plates	D.Fir-L	S-P-F
			Uplift (K ₀ =1.15)	Uplift (K ₀ =1.15)
TC24	(4) 10d	(4) 10d	605	430
TC26	(6) 10d	(6) 10d	1015	720
TC28	(5) 10d	(6) 10d	1015	720

Optional TC Installation Table

Model No.	Fasteners		Factored Resistance	
	Truss	Wall Plates	D.Fir-L	S-P-F
			Uplift (K ₀ =1.15)	Uplift (K ₀ =1.15)
TC28	(5) 10d	(6) 10d x 1 1/2"	810	660
	(5) 10d	(6) 10d	930	660

1. Factored resistances have been increased 16% for earthquake or wind loading; no further increase allowed; reduce where other loads govern.
2. Grout strength is 15 MPa minimum.
3. Optional TC26 installation with 10d nails requires minimum 3" top plate thickness.
4. TC28 fastened to grouted concrete block with (6) - 3/8" x 2 1/4" Titen screws has a factored uplift resistance of 275 lb.



(800) 999-5099
strongtie.com

H/TSP

Seismic and Hurricane Ties (cont.)

These products are available with additional corrosion protection. For more information, see p. 24.

These products are approved for installation with the Strong-Drive® SD Connector screw. See pp. 32-34 for more information.

Model No.	Ga.	Fasteners			Factored Resistance ($K_D = 1.15$)					
		To Rafters/ Truss	To Plates	To Studs	D.Fir-L			S-P-F		
					Uplift	Lateral		Uplift	Lateral	
						F ₁	F ₂		F ₁	F ₂
					lb.	lb.	lb.	lb.	lb.	lb.
					kN	kN	kN	kN	kN	kN
H1	18	(8) 8d x 1 1/2"	(4) 8d	—	740	685	300	680	485	215
					3.29	3.05	1.33	3.02	2.16	0.96
SS H2A	18	(5) 8d x 1 1/2"	(2) 8d x 1 1/2"	(5) 8d x 1 1/2"	830	220	75	590	155	55
					3.69	0.98	0.33	2.62	0.69	0.24
SS H2.5A	18	(5) 8d	(5) 8d	—	805	160	160	755	160	160
					3.58	0.71	0.71	3.36	0.71	0.71
H2.5T	18	(5) 8d	(5) 8d	—	835	175	210	740	160	210
					3.71	0.78	0.93	3.29	0.71	0.93
SS H3	18	(4) 8d	(4) 8d	—	740	180	265	615	125	190
					3.29	0.80	1.18	2.74	0.56	0.85
H6	16	—	(8) 8d	(8) 8d	1585	1085	—	1125	770	—
					7.05	4.83	—	5.00	3.43	—
H7Z	16	(4) 8d	(2) 8d	(8) 8d	1390	670	—	990	475	—
					6.18	2.98	—	4.40	2.11	—
SS H8 ²	18	(5) 10d x 1 1/2"	(5) 10d x 1 1/2"	—	1120	—	—	1025	—	—
					4.98	—	—	4.58	—	—
SS H10A ³	18	(9) 10d x 1 1/2"	(9) 10d x 1 1/2"	—	1735	795	410	1505	565	290
					7.72	3.54	1.82	6.69	2.51	1.29
H10AR	18	(9) 10d x 1 1/2"	(9) 10d x 1 1/2"	—	1485	690	430	1220	570	305
					6.61	3.07	1.91	5.43	2.54	1.36
H10A-2	18	(9) 10d x 1 1/2"	(9) 10d x 1 1/2"	—	1835	1275	430	1645	880	305
					8.16	5.67	1.91	7.32	3.91	1.36
H10S ^{2,3}	18	(8) 8d x 1 1/2"	(8) 8d x 1 1/2"	(8) 8d	1465	795	315	1040	565	225
					6.52	3.54	1.40	4.63	2.51	1.00
H11Z	18	(6) 16d x 2 1/2"	(6) 16d x 2 1/2"	—	1095	920	545	780	655	390
					4.87	4.09	2.42	3.47	2.91	1.73
H14	18	[1] (12) 8d x 1 1/2"	(13) 8d	—	2390	855	320	1805	610	230
		[2] (12) 8d x 1 1/2"	(15) 8d	—	10.63	3.80	1.42	8.03	2.71	1.02
TSP	16	(9) 10d x 1 1/2"	(6) 10d x 1 1/2"	—	2390	855	320	1805	610	230
					10.63	3.80	1.42	8.03	2.71	1.02
		(9) 10d x 1 1/2"	(6) 10d	—	1295	440	—	920	310	—
					5.76	1.96	—	4.09	1.38	—
		(9) 10d x 1 1/2"	(6) 10d	—	1560	440	—	1105	310	—
					6.94	1.96	—	4.92	1.38	—

- Factored resistances have been increased 15% for short term loading; no further increase is allowed.
- Factored resistances are for one anchor. A minimum rafter thickness of 2 1/2" must be used when framing anchors are installed on the same side of the plate (exception: H2.5A).
- H8 factored uplift resistances for stud-to-bottom plate installations are 595 lb. (2.65 kN) for D.Fir-L and 390 lb. (1.74 kN) for S-P-F.
- When cross-grain bending or cross-grain tension cannot be avoided, mechanical reinforcement to resist such forces should be considered.
- Hurricane ties are shown installed on the outside of the wall for clarity. Installation on the inside of the wall is acceptable. For a continuous load path, connections at the top and bottom of the wall must be on the same side of the wall (see technical bulletin T-HITECONPATH).
- Factored resistances in the F₁ direction are not intended to replace diaphragm boundary members or prevent cross grain bending of the truss or rafter members. Additional shear transfer elements shall be considered where there may be effects of cross grain bending or tension.

- H10S can have the stud offset a maximum of 1" from the rafter (centre to centre) for a reduced uplift of 1435 lb. (6.38 kN) D.Fir-L and 1015 lb. (4.51 kN) S-P-F.
- H10S nails to plates are optional for uplift but required for lateral loads.
- H10A may be field-bent up to a slope of 8/12. Multiply the tabulated uplift value x 0.75. Full tabulated lateral resistances apply.
- The factored resistances of stainless-steel connectors match carbon-steel connectors when installed with Simpson Strong-Tie® stainless-steel, SCNR ring-shank nails. For more information, refer to engineering letter L-F-SSNAILS at strongtie.com.
- D.Fir-L/S-P-F factored uplift resistances for the H2.5A fastened to a 2x4 truss bottom chord and double top plates using (5) 8d x 1 1/2" nails into the top plates and (3) 8d x 1 1/2" nails into the lowest three flange holes into the truss bottom chord is 495 lb. (2.20 kN).
- Nails: 16d x 2 1/2" = 0.162" dia. x 2 1/2" long, 10d = 0.148" dia. x 3" long, 10d x 1 1/2" = 0.148" dia. x 1 1/2" long, 8d = 0.131" dia. x 2 1/2" long, 8d x 1 1/2" = 0.131" dia. x 1 1/2" long. See pp. 27-28 for other nail sizes and information.



BEARING ANCHORAGE BY TOE-NAILS FOR LATERAL CAPACITY

B97791H1

NAIL TYPE	LENGTH (IN)	DIAMETER (IN)	NAIL LATERAL CAPACITY (LB)	
			S-P-F	D. FIR
COMMON WIRE	3.00	0.144	132	147
	3.25	0.144	132	147
	3.50	0.160	159	177
COMMON SPIRAL	3.00	0.122	97	108
	3.25	0.122	97	108
	3.50	0.152	145	162

NOTES:

1. Rafter and ceiling members may be anchored to top and bottom chords of girder truss by toe-nailing rafter and ceiling members to girder chords provided the reaction does not exceed the lateral capacities in the table. Hangers (specified by others) are required for reactions higher than the maximum toe-nail capacity. Reactions are based on factored loads.
2. Toe nail capacities shown in the table are for one toe-nail. For additional toe-nails multiply values in table by the number of toe-nails used. Toe-nail capacities take into account toe-nailing factor J_A in CSA O86-14, section 12.9.4.1.
3. For 9-3/4 gauge 3.25" common wire gun nails (diameter = 0.120") use 3" common spiral nail values.
4. Maximum number of toe-nails allowed depends on the lumber size & species to be toe-nailed to supporting member and nail diameter, as shown in tables below.
5. Nail values in table are based on the following relative lumber densities: G = 0.42 (SPF), G = 0.49 (D. Fir).
6. Toe-nails shall be driven at approximately 1/3 the nail length from the edge of the joist/truss chord and driven at an angle of 30° to the grain of the member (See next page for nailing on bearing plate).
7. For loads due to wind the nail lateral capacity in this table may be multiplied by 1.15 (K_D factor).
8. Lumber must be dry (< 19% moisture content) at the time of nail installation.
9. Nail values in this table comply with CSA O86-14, section 12.9.4
10. This design is not valid after March 31, 2021.



TOE-NAIL INSTALLATION

Nail type	Common wire	Common spiral	Common wire	Common spiral
Nail dia. (In)	0.160	0.152	0.144	0.122
	(3.5" nail)		(3" and 3.25" nail)	
LUMBER SIZE	MAXIMUM NUMBER OF TOE-NAILS			
2X4 SPF	2	2	3	3
2X4 D. Fir	2	2	2	2
2X6 SPF	4	4	4	5
2X6 D. Fir	3	3	3	4

MiTek® MiTek Canada Inc
100 Industrial Rd.
Bradford, Ontario L3Z 3G7

December 2, 2019



BEARING ANCHORAGE BY TOE-NAILS FOR WIND LOADING

B97791H2



NAIL TYPE	LENGTH (IN)	DIAMETER (IN)	NAIL WITHDRAWAL CAPACITY (LB)	
			S-P-F	D. FIR
COMMON WIRE	3.00	0.144	30	42
	3.25	0.144	32	45
	3.50	0.160	38	52
COMMON SPIRAL	3.00	0.122	26	36
	3.25	0.122	28	40
	3.50	0.152	36	50

Note: If using truss with D. Fir lumber and S-P-F bearing plate, use values in table for S-P-F.



NOTES:

1. Truss chord, rafter, or ceiling members may be anchored to bearing plate by toe-nails, provided that the actual factored uplift force due to wind or earthquake load does not exceed the withdrawal capacities in the table. Hangers (specified by others) are required for uplift forces that are higher than the maximum toe-nail withdrawal capacity.
2. Toe nail capacities shown in the table are for one toe-nail. For additional toe-nails multiply values in table by the number of toe-nails used. Toe-nail capacities take into account toe-nailing factor J_A in CSA O86-14, section 12.9.5.2.
3. For 9-3/4 gauge 3.25" common wire gun nails (diameter = 0.120") use 3" common spiral nail values.
4. Maximum number of toe-nails allowed depends on the lumber size & species to be toe-nailed to supporting member and nail diameter, as shown in table above.
5. Nail values in table are based on the following relative lumber densities: $G = 0.42$ (SPF), $G = 0.49$ (D. Fir).
6. Toe-nails shall be driven at approximately 1/3 the nail length from the edge of the joist/truss chord and driven at an angle of 30° to the grain of the member (See drawing on detail B37579H1).
7. Lumber must be dry (< 19% moisture content) at the time of nail installation.
8. Nail values in this table comply with CSA O86-14, section 12.9.5
9. This design is not valid after March 31, 2021.

Toe-nailing on 2x6 Bearing Plate



Toe-nailing on 2x4 Bearing Plate



MiTek®

MiTek Canada Inc
100 Industrial Rd.
Bradford, Ontario L3Z 3G7


PEO
Certificate No. 10889485




December 2, 2019

Symbols

PLATE LOCATION AND ORIENTATION



Center plate on joint, unless x, y offsets are indicated. Dimensions are in ft-in-sixteenths or mm. Apply plates to both sides of truss and fully embed teeth.



For 4 x 2 orientation, locate plates 0-1/16" from outside edge of truss.



This symbol indicates the required direction of slots in connector plates.

*Plate location details available in MiTek software or upon request.

PLATE SIZE

4 x 4

The first dimension is the plate width measured perpendicular to slots. Second dimension is the length parallel to slots.

LATERAL BRACING LOCATION



Indicated by symbol shown and/or by text in the bracing section of the output. Use T, I or Eliminator bracing if indicated.

BEARING




Indicates location where bearings (supports) occur. Icons vary but reaction section indicates joint number where bearings occur.


Industry Standards:

TPIC: Truss Design Procedures and Specifications for Light Metal Plate Connected Wood Trusses
DSB-89: Design Standard for Bracing.
BCSI: Building Component Safety Information, Guide to Good Practice for Handling, Installing & Bracing of Metal Plate Connected Wood Trusses.

Numbering System



dimensions shown in ft-in-sixteenths or mm (Drawings not to scale)



JOINTS ARE GENERALLY NUMBERED/LETTERED CLOCKWISE AROUND THE TRUSS STARTING AT THE JOINT FARTHEST TO THE LEFT.

CHORDS AND WEBS ARE IDENTIFIED BY END JOINT NUMBERS/LETTERS.

PRODUCT CODE APPROVALS

CCMC Reports:

11996-L 10319-L, 13270-L, 12691-R

© 2007 MiTek® All Rights Reserved

MiTek
POWER TO PERFORM.™

MiTek Engineering Reference Sheet: MII-7473C rev. 10-08

General Safety Notes

Failure to Follow Could Cause Property Damage or Personal Injury


1. Additional stability bracing for truss system, e.g. diagonal or X-bracing, is always required. See BCSI.
2. Truss bracing must be designed by an engineer. For wide truss spacing, individual lateral braces themselves may require bracing, or alternative T, I, or Eliminator bracing should be considered.
3. Never exceed the design loading shown and never stack materials on inadequately braced trusses.
4. Provide copies of this truss design to the building designer, erection supervisor, property owner and all other interested parties.
5. Cut members to bear tightly against each other.
6. Place plates on each face of truss at each joint and embed fully. Knots and wane of joint locations are regulated by TPIC.
7. Design assumes trusses will be suitably protected from the environment in accord with TPIC.
8. Unless otherwise noted, moisture content of lumber shall not exceed 19% at time of fabrication.
9. Unless expressly noted, this design is not applicable for use with fire retardant, preservative treated, or green lumber.
10. Camber is a non-structural consideration and is the responsibility of truss fabricator. General practice is to camber for dead load deflection.
11. Plate type, size, orientation and location dimensions indicated are minimum plating requirements.
12. Lumber used shall be of the species and size, and in all respects, equal to or better than that specified.
13. Top chords must be sheathed or purlins provided at spacing indicated on design.
14. Bottom chords require lateral bracing at 10 ft. spacing, or less, if no ceiling is installed, unless otherwise noted.
15. Connections not shown are the responsibility of others.
16. Do not cut or alter truss member or plate without prior approval of an engineer.
17. Install and load vertically unless indicated otherwise.
18. Use of green or treated lumber may pose unacceptable environmental, health or performance risks. Consult with project engineer before use.
19. Review all portions of this design (front, back, words and pictures) before use. Reviewing pictures alone is not sufficient.
20. Design assumes manufacture in accordance with TPIC Quality Criteria.

Overview:

Where piggybacks are connected ovetop of base trusses, 2x4 purlins must be first added to the flat portion of the base truss at a spacing no more than 24" o/c. These purlins not only provide support for the piggyback trusses above, but are required to laterally support the top chord of the base truss which will not have the sheathing directly connected to the flat portion of the base truss. This ensures the top chord, most often in compression, will not buckle laterally.

Further, the purlins in the plane of the flat portion require diagonal bracing to prevent lateral displacement of the purlins themselves where under certain conditions, the trusses may in fact all buckle in the same direction if this additional bracing is not added in the plane of the purlins.

Detail:




NOTE: THE SLOPED PORTION OF THE TOP CHORD OF THE BASE TRUSS AND PIGGYBACK TRUSS IN THIS SKETCH IS ASSUMED TO BE SHEATHED IN ACCORDANCE WITH THE OBC.

SKETCH FROM BCSI-CANADA 2013

Disclaimer:

OWTFA Tech Notes are intended to provide guidance to the design community both within the membership as well as to third party designers who might benefit from the information. The details have been developed by the OWTFA technical committee and although there may be professional engineers involved in development, the information contained in the tech-note are not intended to be used without having a professional engineer review the information for a specific application. The OWTFA takes no responsibility with respect to the information provided but has developed this tech-note to offer guidance where it is not currently readily available.



Alves Engineering Services Inc.

5208 Easton road
Burlington, Ontario L7L 6N6
(289) 259 5455

RESPONSABILITIES

- 1-Alves Engineering Services Inc. is responsible for the design of trusses as individual components
- 2-It is the responsibility of others to ascertain that the design loads utilized on this drawing meet or exceed the actual dead load imposed by the structure and the live load imposed by the local building code or the authorities having jurisdictions.
- 3- All dimensions are to be verified by owner, contractor, architect or other authority before manufacture.
- 4- Alves Engineering Services Inc. bears no responsibility for the erection of the trusses. Persons erecting trusses are cautioned to seek professional advice regarding temporary and permanent bracing system. Bracing shown on Alves Engineering Services Inc. drawings is specified for the truss as a single component and forms an integral part of the truss design, but is not meant to represent the only required bracing for that truss when trusses are installed in a series of trusses forming a roof truss system.
- 5- It is the manufactures responsibility to ensure that the trusses are manufactured in conformance with Alves Engineering Services Inc. specifications outlined below.

SPECIFICATIONS

- 1-Truss components sealed by Alves Engineering Services Inc. conform to the relevant sections of the current Building Code of Ontario and Canada (part 4 or part 9) or the current Canadian code for Farm Buildings in accordance with the application specified on the sealed truss component drawing. All truss component design procedures must conform to the current design standard issued by the truss plate institute of Canada (TPIC). All lumber and nailing stresses to conform to the current CSA wood design standard identified on the current Building Code and TPIC.
- 2- Lumber is to be the sizes and grade specified on the truss drawing.
- 3- Moist content of lumber is not to exceed 19% in service unless otherwise specified.
- 4- Plates shall be applied to both faces of the each truss joint and shall be positioned as shown on the truss drawings
- 5- Lumber used on manufacture of trusses is not to be treated with chemicals unless otherwise specified on the truss drawings.
- 6- The top chord is assumed to be continuously laterally braced by the roof sheathing or purlins at intervals specified on the truss drawing but not exceeding 24" c/c for (part 9) and not exceeding 48" for (part 4 or farm design)
- 7- When rigid ceiling is not attached directly to the bottom chord, lateral bracing is required and it should not exceed more than 3m or 10' intervals.
- 8- Refer to Mitek sheet MII7473C REV.10-08 attached for information on symbols, numbering system and General Safety notes.

F-1900213

Feb 09, 2018