




Hanger Name	Symbol	QTY
LUS24	▲	4
HGUS26-2	■	4



These plans have been reviewed for use with the corrections as noted. No other changes may be made without written approval of the Building Standards Branch. All work must comply with Zoning By-Law 2018-043, as amended, and the Ontario Building Code, as amended. These approved documents must be kept on site at all times. The building permit must be clearly posted on site at all times.

Discipline	Reviewer	BCIN	Date
Building Code	H. Authier	43236	2021-02-24
Sewage System			
Zoning			

CONVENTIONAL FRAMING BY OTHERS

ALL CONVENTIONAL FRAMING TO CONFORM WITH PART 9 OF THE OBC. ROOF RAFTERS THAT CROSS OVER TRUSSES TO BE MIN. 2x4 SIF @ 24" C/C WITH A 2x4 VERTICAL POST TO THE TRUSS BELOW. VERTICAL POSTS TO BE LATERALLY BRACED SO THAT UNBRACED LENGTH DOES NOT EXCEED 6'. DESIGN OF CONVENTIONAL FRAMING IS THE RESPONSIBILITY OF THE PROJECT ENGINEER.

JOB INFORMATION

Customer	GREENPARK HOMES
Job #	20-00422R0
Address	TRINAR HALL EAST GWILLIMBURY, ON
Model	BRENTWOOD 4 EL 2
Sales Rep	RALPH MIRIGELLO
Designer	KR
Date	12/17/2020
Path	C:\MITEK\CA\JOBS\GREENPARK HOMES\TRINAR HALL\BRENTWOOD 4\LEVEL 2\T-BRENTWOOD4-2\

DESIGN INFORMATION

Code	NBCC 2015
Bldg	Residential - HSB (NBCC Part 9)
TC LL	34.8 lb/ft ²
TC DL	8.0 lb/ft ²
BC LL	10.5 lb/ft ²
BC DL	7.3 lb/ft ²
Deflection	LL=L/360 TL=L/360
Spacing	24" O/C unless otherwise noted
Complies With	OBC 2012 (2019 Amendment) CSA O86-14 and TPIC 2014

IMPORTANT INFORMATION

Refer to truss drawings in the Truss Engineering Package for ply-to-ply attachment notes

For site-framed valleys: top chords of all roof trusses must be laterally supported using 2x4 continuous bracing @24 O/C - all bracing must be anchored at ends as per TPIC Installation Guidelines

Read all notes on this page in addition to those shown on the KOTT Truss Engineering package

Field erection, handling and bracing are not the responsibility of KOTT, or KOTT Engineering

Unless noted otherwise, hurricane ties are to be installed at the bearings of all trusses > 40 ft clear span, and any girder or beam supporting trusses with a clear span >40 ft. See hanger legend for type.

Unless noted otherwise, for Part 9 bldgs, all trusses are to be anchored to the top of supporting walls as follows: trusses with a clear span <40 ft use 3-1/4" nails @ each bearing; trusses with a clear span >40 ft use 3-1/4" nails @ each bearing in addition to the appropriate hurricane tie.

KOTT Inc.
14 Anderson Blvd.
Uxbridge, ON
905.642.4400



NE1220-147
GREENPARK - TRINAR HALL -
BRENTWOOD 4 EL 2

ENGINEERING NOTE PAGE (ENP-1)

PLEASE READ PRIOR TO INSTALLATION



These plans have been reviewed for use with the corrections as noted. No other changes may be made without written approval of the Building Standards Branch. All work must comply with Zoning By-Law 2018-043, as amended, and the Ontario Building Code, as amended. These approved documents must be kept on site at all times. The building permit must be clearly posted on site at all times.

Discipline	Reviewer	BCIN	Date
Building Code	H. Authier	43236	2021-02-24
Sewage System			
Zoning			

RESPONSIBILITIES

THIS DESIGN IS FOR AN INDIVIDUAL BUILDING COMPONENT AND HAS BEEN BASED ON INFORMATION PROVIDED BY KOTT DESIGN. THE UNDERSIGNED ENGINEER DISCLAIMS ANY RESPONSIBILITY FOR DAMAGES AS A RESULT OF FAULTY OR INCORRECT INFORMATION, SPECIFICATION AND/OR DESIGNS FURNISHED TO THE ENGINEER. THE UNDERSIGNED ENGINEER IS ONLY RESPONSIBLE FOR THE STRUCTURAL INTEGRITY OF THIS BUILDING COMPONENT FOR THE CONDITIONS AND LOADS SHOWN ON THIS DRAWING. THE STRUCTURAL INTEGRITY OF THE BUILDING AND THE VERIFICATION OF THE DIMENSIONS AND THE DESIGN LOADS USED ARE THE RESPONSIBILITY OF THE BUILDING DESIGNER.

TRUSSES ARE DESIGNED IN CONFORMANCE WITH THE RELEVANT SECTIONS OF THE NATIONAL BUILDING CODE OF CANADA OR THE CANADIAN CODE FOR FARM BUILDINGS, WHICHEVER APPLIES TO THE BUILDING TYPE INDICATED ON THE DRAWING

IT IS THE RESPONSIBILITY OF KOTT TO ENSURE THAT TRUSSES ARE MANUFACTURED IN CONFORMANCE WITH THESE DESIGNS AND WITH THE SPECIFICATIONS OUTLINED BELOW. THE UNDERSIGNED ENGINEER IS NOT RESPONSIBLE FOR QUALITY CONTROL IN THE TRUSS MANUFACTURING PLANT.

USE AND OCCUPANCY

- The building is of the type indicated on the drawing

LOADING

- The truss loading intensity and distribution as well as load transfer mechanism is that indicated on the drawing
- No buildings, trees, parapets or other projections higher than the roof for which the trusses are used are located within a distance less than ten (10) times the difference in height, or five metres (16 ft) whichever is greater, unless the drawing indicates that the snow drifting has been taken into account

HANDLING, INSTALLATION AND BRACING

- The trusses must be handled and installed by a qualified professional as per the supplied document titled *Information for Truss Installers* and the BCSI-B1 and BCSI-B3 Summary Sheets
- The compression chords are laterally braced by continuous rigid diaphragm sheathing or as specified on the drawing
- Temporary and permanent bracing must be installed as indicated on the truss drawing and according to the BCSI-B1 and BCSI-B3 Summary Sheets. Bracing for the lateral stability of the truss is to be provided by the building designer
- **It is recommended that a Professional Engineer's advice be obtained for the bracing of trusses spanning more than 12.37m (40'-7")**


SUPPORTS

- The trusses are to be supported at the bearing points indicated and anchored to the supports where considered necessary by the designer of the overall structure
- Bearing sizes shown are the minimum required to prevent crushing of the truss members and do not necessarily take into account stability of the overall building structure
- Elevation of bearings must be carefully checked and shimmed to alignment for solid bearings
- Adequate wood truss bearing is the responsibility of the building designer.

DIMENSIONS

- Geometry of the truss and dimensions indicated on the drawing are identical to those of the installed truss.

Version 8.420 S Oct 9 2020 Mitek Industries, Inc. Sun Dec 20 11:35:28 2020 Page 1
ID:mCCrvcxnlFAPc08wPalN0zHzlx-C7vnRyhToE88bl1v QmdccfSnFzuWxVif5bJuy7



LUMBER			
N. L. G. A. RULES	CHORDS	SIZE	LUMBER
A - D	2x4	DRY	No.2
D - G	2x4	DRY	No.2
G - I	2x4	DRY	No.2
I - L	2x4	DRY	No.2
V - B	2x6	DRY	No.2
M - K	2x6	DRY	No.2
V - Q	2x6	DRY	No.2
Q - M	2x6	DRY	No.2
ALL WEBS EXCEPT	2x3	DRY	No.2

DRY: SEASONED LUMBER.

DESIGN CONSISTS OF 2 TRUSSES BUILT SEPARATELY THEN FASTENED TOGETHER AS FOLLOWS:

CHORDS#ROWS	SURFACE SPACING (IN)	LOAD(PLF)
TOP CHORDS : (0.122"x3") SPIRAL NAILS		
A-D	12	SIDE(0.0)
D-G	12	SIDE(55.1)
G-I	12	SIDE(0.0)
I-L	12	SIDE(0.0)
V-B	2	TOP
M-K	2	TOP
BOTTOM CHORDS : (0.122"x3") SPIRAL NAILS		
V-Q	2	SIDE(22.0)
Q-M	2	SIDE(22.0)
WEBS : (0.122"x3") SPIRAL NAILS		
2x3	6	

NAILS TO BE DRIVEN FROM ONE SIDE ONLY.

GIRDER NAILING ASSUMES NAILED HANGERS ARE FASTENED WITH MIN. 3-0 INCH NAILS.

TOP - COMPONENTS ARE LOADED FROM THE TOP AND MUST BE PLACED ON TOP EDGE OF ALL PLIES FOR THE LOAD TO BE TRANSFERRED TO EACH PLY.

SIDE - PLF SHOWN IS THE EQUIVALENT UDL APPLIED TO ONE SIDE THAT THE CORRESPONDING NAILING PATTERN SHALL BE CAPABLE OF TRANSFERRING. REMAINING PLF MUST BE APPLIED ON THE OPPOSITE SIDE OR ON THE TOP.



READ ALL NOTES ON THIS PAGE AND ON ENGINEERING NOTE PAGE ENP-1. THIS NOTE PAGE IS AN INTEGRAL PART OF THIS DRAWING AS IT CONTAINS SPECIFICATIONS AND CRITERIA USED IN THE DESIGN OF THIS COMPONENT.

DIMENSIONS, SUPPORTS AND LOADINGS SPECIFIED BY FABRICATOR TO BE VERIFIED BY BUILDING DESIGNER

BEARINGS					
FACTORED GROSS REACTION	MAXIMUM FACTORED GROSS REACTION	INPUT BRG	REQRD BRG		
JT VERT	6335	0	6335	0	5-8
V	5506	0	5506	0	5-8

UNFACTORED REACTIONS							
1ST LCASE MAX/MIN COMPONENT REACTIONS							
JT	COMBINED	SNOW	LIVE	PERM.LIVE	WIND	DEAD	SOIL
V	4688	2704 / 0	804 / 0	0 / 0	0 / 0	1180 / 0	0 / 0
M	4074	2353 / 0	698 / 0	0 / 0	0 / 0	1025 / 0	0 / 0

BEARING MATERIAL TO BE SPF NO.2 OR BETTER AT JOINT(S) V, M

BRACING
TOP CHORD TO BE SHEATHED OR MAX. PURLIN SPACING = 3.05 FT.
MAX. UNBRACED BOTTOM CHORD LENGTH = 10.00 FT OR RIGID CEILING DIRECTLY APPLIED.

ALL PITCH BREAKS AND PERIMETER CORNER JOINTS MUST BE LATERALLY RESTRAINED.

CHORDS				WEBS			
MEMB.	MAX. FACTORED FORCE (LBS)	FACTORED VERT. LOAD (PLF)	FACTORED LC1 MAX. CSI (LC)	MEMB.	MAX. FACTORED FORCE (LBS)	MAX. FACTORED DEAD CSI (LC)	MAX. FACTORED WIND CSI (LC)
FR-TO		FROM	TO	LENGTH	FR-TO		
A-B	0 / 47	-124.4	-124.4	0.09 (1)	10.00	U-C -1353 / 0	0.14 (1)
B-C	-8630 / 0	-124.4	-124.4	0.24 (1)	3.64	C-T	0 / 786
C-D	-7326 / 0	-124.4	-124.4	0.26 (1)	3.45	T-D	0 / 425
D-E	-8060 / 0	-234.6	-234.6	0.50 (1)	3.05	D-S	0 / 3290
E-F	-7850 / 0	-124.4	-124.4	0.48 (1)	3.14	S-E	-563 / 0
F-G	-7850 / 0	-124.4	-124.4	0.43 (1)	3.19	E-R	-365 / 0
G-H	-7850 / 0	-124.4	-124.4	0.43 (1)	3.19	R-F	-487 / 0
H-I	-7098 / 0	-124.4	-124.4	0.39 (1)	3.39	F-H	0 / 1155
I-J	-6802 / 0	-124.4	-124.4	0.24 (1)	3.60	P-H	-1491 / 0
J-K	-6114 / 0	-124.4	-124.4	0.22 (1)	3.80	P-I	0 / 2159
K-L	0 / 47	-124.4	-124.4	0.09 (1)	10.00	O-I	0 / 1199
V-B	-5799 / 0	0.0	0.0	0.21 (1)	6.12	O-J	0 / 773
M-K	-5375 / 0	0.0	0.0	0.19 (1)	6.32	N-J	-1338 / 0
V-W	0 / 0	-74.0	-74.0	0.25 (1)	10.00	B-U	0 / 5806
W-U	0 / 0	-74.0	-74.0	0.25 (1)	10.00	N-K	0 / 5355
U-T	0 / 5528	-74.0	-74.0	0.49 (1)	10.00		
T-X	0 / 6066	-74.0	-74.0	0.59 (1)	10.00		
X-S	0 / 6066	-74.0	-74.0	0.59 (1)	10.00		
S-R	0 / 8060	-39.2	-39.2	0.57 (1)	10.00		
R-Q	0 / 7098	-39.2	-39.2	0.52 (1)	10.00		
Q-P	0 / 7098	-39.2	-39.2	0.52 (1)	10.00		
P-O	0 / 5683	-39.2	-39.2	0.44 (1)	10.00		
O-Y	0 / 5099	-39.2	-39.2	0.45 (1)	10.00		
Y-N	0 / 5099	-74.0	-74.0	0.45 (1)	10.00		
N-M	0 / 0	-74.0	-74.0	0.04 (2)	10.00		

FACTORED CONCENTRATED LOADS (LBS)							
JT	LOC.	LC1	MAX-	MAX+	FACE	DIR.	TYPE
D	6-0-8	-560	-560		FRONT	VERT	TOTAL
I	22-11-8	-560	-560		FRONT	VERT	TOTAL
S	9-10-8	-1596	-1596		FRONT	VERT	TOTAL
W	1-4-8	-736	-736		FRONT	VERT	TOTAL
X	7-7-8	-736	-736		FRONT	VERT	TOTAL
Y	23-1-8	-1596	-1596		FRONT	VERT	TOTAL

CONNECTION REQUIREMENTS

1) C1: A SUITABLE HANGER/MECHANICAL CONNECTION IS REQUIRED.

DESIGN CRITERIA

*** SPECIAL LOADS ANALYSIS ***
GEOMETRY AND/OR BASIC LOADS CHANGED BY USER.
LOADS WERE DERIVED FROM USER INPUT
NO FURTHER MODIFICATIONS WERE MADE

SPECIFIED LOADS:
TOP CH. LL = 34.8 PSF
DL = 8.0 PSF
BOT CH. LL = 10.5 PSF
DL = 7.3 PSF
TOTAL LOAD = 60.6 PSF

SPACING = 24.0 IN. C/C

LOADING IN FLAT SECTION BASED ON A SLOPE OF 2.00/12 MINIMUM

GIRDER TYPE: CPrimeHip
SIDE SETBACK = 6-0-0
END SETBACK = 6-0-0
END WALL WIDTH = 5-8
CORNER FRAMING TYPE: CONVENTIONAL
END JACK TYPE: CONVENTIONAL
APPLIED TO FRONT SIDE
- ADDTL LOADS BASED ON 55 % OF GSL
LOADS APPLIED TO FIRST 9-10-8 OF SPAN MEASURED FROM THE LEFT.

GIRDER TYPE: CPrimeHip
SIDE SETBACK = 6-0-0
END SETBACK = 6-0-0
END WALL WIDTH = 5-8
CORNER FRAMING TYPE: CONVENTIONAL
END JACK TYPE: CONVENTIONAL
APPLIED TO FRONT SIDE
- ADDTL LOADS BASED ON 55 % OF GSL
LOADS APPLIED TO FIRST 6-2-0 OF SPAN MEASURED FROM THE RIGHT.

*** NON STANDARD GIRDER ***
ADDTL USER-DEFINED LOADS APPLIED TO ALL LOAD CASES.

THIS TRUSS IS DESIGNED FOR RESIDENTIAL OR SMALL BUILDING REQUIREMENTS OF PART 9, NBCC 2015

THIS DESIGN COMPLIES WITH:
- PART 9 OF BCBC 2015, ABC 2019
- PART 9 OF OBC 2012 (2019 AMENDMENT)
- CSA 086-14
- TPIC 2014

(55 % OF 48.1 P.S.F. G.S.L. PLUS 8.4 P.S.F. RAIN LOAD)
EQUALS 34.8 P.S.F. SPECIFIED ROOF LIVE LOAD

ALLOWABLE DEFL.(LL) = L/360 (0.97")
CALCULATED VERT. DEFL.(LL) = L/999 (0.15")
ALLOWABLE DEFL.(TL) = L/360 (0.97")
CALCULATED VERT. DEFL.(TL) = L/999 (0.25")

CSI: TC=0.50/1.00 (D-E-1), BC=0.59/1.00 (S-T-1),
WB=0.72/1.00 (B-U-1), SS=0.53/1.00 (N-O-1)

DOL LUMBER=1.00 NAIL=1.00 LS BEND=1.00 COMP=1.00
SHEAR=1.00 TENS=1.00

COMPANION LIVE LOAD FACTOR = 1.00



These plans have been reviewed for use with the corrections as noted. No other changes may be made without written approval of the Building Standards Branch. All work must comply with Zoning By-Law 2018-043, as amended, and the Ontario Building Code, as amended. These approved documents must be kept on site at all times. The building permit must be clearly posted on site at all times.

Discipline	Reviewer	BCIN	Date
Building Code	H. Author	43236	2021-02-24
Sewage System			
Zoning			

CONTINUED ON PAGE 2



PLATES (table is in inches)					
JT	TYPE	PLATES	W	LEN	Y X
B	TMVW-t	MT20	5.0	8.0	1.50 3.75
C	TMWW-t	MT20	3.0	4.0	1.50 1.50
D	TTWW-m	MT20	6.0	8.0	2.25 3.50
E	TMWW-t	MT20	3.0	4.0	
F	TMWW-w	MT20	2.0	4.0	
G	TS-t	MT20	3.0	6.0	
H	TMWW-t	MT20	3.0	4.0	
I	TTWW-m	MT20	5.0	8.0	2.00 3.50
J	TMWW-t	MT20	3.0	4.0	1.50 1.50
K	TMVW-t	MT20	5.0	8.0	1.75 3.75
M	BMV1+p	MT20	3.0	4.0	
N	BMWW-t	MT20	5.0	6.0	2.50 1.75
O	BMWW+t	MT20	3.0	4.0	
P	BMWW-t	MT20	4.0	4.0	2.00 1.50
Q	BS-t	MT20	4.0	6.0	
R	BMWWW-t	MT20	4.0	6.0	
S	BMWW+t	MT20	4.0	5.0	2.25 1.50
T	BMWW+t	MT20	3.0	4.0	
U	BMWW-t	MT20	5.0	6.0	2.50 1.50
V	BMV1+p	MT20	3.0	4.0	2.25 1.50

TRUSS PLATE MANUFACTURER IS NOT RESPONSIBLE FOR QUALITY CONTROL IN THE TRUSS MANUFACTURING PLANT .

NAIL VALUES

PLATE	GRIP(DRY)	SHEAR	SECTION
	(PSI)	(PLI)	(PLI)
	MAX MIN	MAX MIN	MAX MIN
MT20	650 371	1747 788	1987 1873

PLATE PLACEMENT TOL. = 0.250 inches

PLATE ROTATION TOL. = 5.0 Deg.

JSI GRIP= 0.90 (I) (INPUT = 0.90)

JSI METAL= 0.88 (Q) (INPUT = 1.00)

READ ALL NOTES ON THIS PAGE AND ON ENGINEERING NOTE PAGE ENP-1. THIS NOTE PAGE IS AN INTEGRAL PART OF THIS DRAWING AS IT CONTAINS SPECIFICATIONS AND CRITERIA USED IN THE DESIGN OF THIS COMPONENT.




These plans have been reviewed for use with the corrections as noted. No other changes may be made without written approval of the Building Standards Branch. All work must comply with Zoning By-Law 2018-043, as amended, and the Ontario Building Code, as amended. These approved documents must be kept on site at all times. The building permit must be clearly posted on site at all times.

Discipline	Reviewer	BCIN	Date
Building Code	H. Authier	43236	2021-02-24
Sewage System			
Zoning			



Version 8.420 S Oct 9 2020 MiTek Industries, Inc. Sun Dec 20 11:35:29 2020 Page 1
ID:mCCrycXnlFAPc08wPalN0zHzlx-hJT9eli5ZXG?DSc6Hix?Ap8fBc4dvIrAxP7WY7



LUMBER
N. L. G. A. RULES

CHORDS	SIZE	LUMBER	DESCR.
A - D	2x4	DRY No.2	SPF
D - G	2x4	DRY 2100F 1.8E	SPF
G - I	2x4	DRY 2100F 1.8E	SPF
I - L	2x4	DRY No.2	SPF
V - B	2x8	DRY No.2	SPF
M - K	2x8	DRY No.2	SPF
V - Q	2x8	DRY 2100F 1.8E	SPF
Q - M	2x8	DRY 2100F 1.8E	SPF
ALL WEBS	2x3	DRY No.2	SPF
EXCEPT			
B - U	2x4	DRY No.2	SPF
N - K	2x4	DRY No.2	SPF

DRY: SEASONED LUMBER.

PLATES (table is in inches)

JT	TYPE	PLATES	W	LEN	Y	X
B	TMWW-t	MT20	8.0	10.0	2.25	5.00
C	TMWW-t	MT20	4.0	4.0	1.75	1.50
D	TTWW-m	MT20	8.0	10.0	Edge 4.25	
E	TMWW-t	MT20	4.0	4.0	1.75	2.00
F	TMWW-t	MT20	2.0	4.0		
G	TS-t	MT20	3.0	10.0		
H	TMWW-t	MT20	4.0	4.0	1.75	2.00
I	TTWW-m	MT20	8.0	10.0	Edge 4.25	
J	TMWW-t	MT20	4.0	4.0	1.75	1.50
K	TMWW-t	MT20	6.0	10.0	2.25	5.00
N	BMVW-t	MT20	2.0	8.0	4.25	3.50
O	BMVW-t	MT20	4.0	10.0	1.75	2.75
P	BMVW-t	MT20	4.0	4.0		
Q	BMVW-t	MT20	5.0	8.0	2.00	1.50
R	BS-t	MT18HS	6.0	12.0		
S	BMVW-t	MT20	4.0	6.0	1.50	3.00
T	BMVW-t	MT20	5.0	8.0	2.00	1.50
U	BMVW-t	MT20	4.0	4.0		
V	BMVW-t	MT20	4.0	10.0	1.75	2.75
W	BMVW-t	MT20	2.0	8.0	4.25	1.75

Edge - INDICATES REFERENCE CORNER OF PLATE TOUCHES EDGE OF CHORD.



READ ALL NOTES ON THIS PAGE AND ON ENGINEERING NOTE PAGE ENP-1. THIS NOTE PAGE IS AN INTEGRAL PART OF THIS DRAWING AS IT CONTAINS SPECIFICATIONS AND CRITERIA USED IN THE DESIGN OF THIS COMPONENT.

DIMENSIONS, SUPPORTS AND LOADINGS SPECIFIED BY FABRICATOR TO BE VERIFIED BY BUILDING DESIGNER

BEARINGS

FACTORED GROSS REACTION	MAXIMUM FACTORED GROSS REACTION	INPUT BRG	REQRD BRG
JT VERT	4542	0	4-15
V	4542	0	4-15

UNFACTORED REACTIONS

1ST LCASE	MAX/MIN COMPONENT REACTIONS
JT COMBINED	1941 / 0
V	1941 / 0
M	1941 / 0

BEARING MATERIAL TO BE SPF NO.2 OR BETTER AT JOINT(S) V, M

BRACING
TOP CHORD TO BE SHEATHED OR MAX. PURLIN SPACING = 1.94 FT.
MAX. UNBRACED BOTTOM CHORD LENGTH = 10.00 FT OR RIGID CEILING DIRECTLY APPLIED.
ALL PITCH BREAKS AND PERIMETER CORNER JOINTS MUST BE LATERALLY RESTRAINED.

LOADING
TOTAL LOAD CASES: (4)

CHORDS				WEBS			
MEMB.	MAX. FACTORED FORCE (LBS)	FACTORED VERT. LOAD (PLF)	FACTORED HORZ. LOAD (LC)	MEMB.	MAX. FACTORED FORCE (LBS)	FACTORED VERT. LOAD (PLF)	FACTORED HORZ. LOAD (LC)
FR-TO				FR-TO			
A-B	0 / 38	-124.4	-124.4 0.18 (1)	U-C	-1315 / 0	0.23 (1)	
B-C	-5974 / 0	-124.4	-124.4 0.67 (1)	C-T	0 / 864	0.21 (1)	
C-D	-8770 / 0	-124.4	-124.4 0.77 (1)	T-D	-94 / 231	0.06 (3)	
D-E	-8299 / 0	-234.6	-234.6 0.86 (1)	D-S	0 / 3016	0.75 (1)	
E-F	-8948 / 0	-234.6	-234.6 0.92 (1)	S-E	-1703 / 0	0.44 (1)	
F-G	-8948 / 0	-234.6	-234.6 0.92 (1)	E-R	0 / 874	0.22 (1)	
G-H	-8948 / 0	-234.6	-234.6 0.92 (1)	R-F	-903 / 0	0.23 (1)	
H-I	-8299 / 0	-234.6	-234.6 0.86 (1)	R-H	0 / 874	0.22 (1)	
I-J	-8770 / 0	-124.4	-124.4 0.77 (1)	P-H	-1703 / 0	0.44 (1)	
J-K	-5974 / 0	-124.4	-124.4 0.67 (1)	P-I	0 / 3016	0.75 (1)	
K-L	0 / 38	-124.4	-124.4 0.18 (1)	O-I	-94 / 231	0.06 (3)	
V-B	-4349 / 0	0.0	0.0 0.23 (1)	Q-J	0 / 864	0.21 (1)	
M-K	-4349 / 0	0.0	0.0 0.23 (1)	N-J	-1315 / 0	0.23 (1)	
V-U	0 / 0	-74.0	-74.0 0.10 (1)	B-U	0 / 5518	0.98 (1)	
U-T	0 / 5354	-74.0	-74.0 0.38 (1)	N-K	0 / 5518	0.98 (1)	
T-S	0 / 6034	-74.0	-74.0 0.37 (1)				
S-R	0 / 8269	-74.0	-74.0 0.54 (1)				
R-Q	0 / 8269	-74.0	-74.0 0.54 (1)				
Q-P	0 / 8269	-74.0	-74.0 0.54 (1)				
P-O	0 / 6034	-74.0	-74.0 0.37 (1)				
O-N	0 / 5354	-74.0	-74.0 0.38 (1)				
N-M	0 / 0	-74.0	-74.0 0.10 (1)				

FACTORED CONCENTRATED LOADS (LBS)

JT	LOC.	LC1	MAX.	MAX+	FACE	DIR.	TYPE	HEEL	CONN.
D	6-0-0	-560	-560	---	FRONT	VERT	TOTAL	---	C1
I	23-0-0	-560	-560	---	FRONT	VERT	TOTAL	---	C1

CONNECTION REQUIREMENTS

- 1) C1: A SUITABLE HANGER/MECHANICAL CONNECTION IS REQUIRED.

DESIGN CRITERIA

SPECIFIED LOADS:
TOP CH. LL = 34.8 PSF
DL = 8.0 PSF
BOT CH. LL = 10.5 PSF
DL = 7.3 PSF
TOTAL LOAD = 60.6 PSF

SPACING = 24.0 IN. C/C

LOADING IN FLAT SECTION BASED ON A SLOPE OF 2.00/12 MINIMUM

GIRDER TYPE: CPrimeHip
SIDE SETBACK = 6-0-0
END SETBACK = 6-0-0
END WALL WIDTH = 5-8
CORNER FRAMING TYPE: CONVENTIONAL
END JACK TYPE: CONVENTIONAL
APPLIED TO FRONT SIDE
- ADDTL LOADS BASED ON 55 % OF GSL.

THIS TRUSS IS DESIGNED FOR RESIDENTIAL OR SMALL BUILDING REQUIREMENTS OF PART 9, NBCC 2015

THIS DESIGN COMPLIES WITH:
- PART 9 OF BCBC 2018, ABC 2019
- PART 9 OF OBC 2012 (2019 AMENDMENT)
- CSA 086-14
- TPIC 2014

(55 % OF 48.1 P.S.F. G.S.L. PLUS 8.4 P.S.F. RAIN LOAD)
EQUALS 34.8 P.S.F. SPECIFIED ROOF LIVE LOAD

ALLOWABLE DEFL. (LL) = L/360 (0.97")
CALCULATED VERT. DEFL. (LL) = L/969 (0.34")
ALLOWABLE DEFL. (TL) = L/360 (0.97")
CALCULATED VERT. DEFL. (TL) = L/615 (0.57")

CSI: TC=0.92/1.00 (E-F:1), BC=0.54/1.00 (R-S:1), WB=0.98/1.00 (K-N:1), SSI=0.51/1.00 (D-E:1)

DOL LUMBER=1.00 NAIL=1.00 LS BEND=1.00 COMP=1.00
SHEAR=1.00 TENS=1.00

COMPANION LIVE LOAD FACTOR = 1.00

TRUSS PLATE MANUFACTURER IS NOT RESPONSIBLE FOR QUALITY CONTROL IN THE TRUSS MANUFACTURING PLANT.

NAIL VALUES
PLATE GRIP(DRY) SHEAR SECTION (PSI) (PLI) (PLI)
MAX MIN MAX MIN MAX MIN
MT20 650 371 1747 788 1987 1873
MT18HS588 403 2455 1382 3163 3004

PLATE PLACEMENT TOL. = 0.250 inches
PLATE ROTATION TOL. = 5.0 Deg.

JSI GRIP= 0.89 (P) (INPUT = 0.90)
JSI METAL = 0.98 (D) (INPUT = 1.00)




These plans have been reviewed for use with the corrections as noted. No other changes may be made without written approval of the Building Standards Branch. All work must comply with Zoning By-Law 2018-043, as amended, and the Ontario Building Code, as amended. These approved documents must be kept on site at all times. The building permit must be clearly posted on site at all times.

Discipline	Reviewer	BCIN	Date
Building Code	H. Author	43236	2021-02-24
Sewage System			
Zoning			



Version 8.420 S Oct 9 2020 Mitek Industries, Inc. Sun Dec 20 11:35:30 2020 Page 1
ID:mCCrycxlIfAPc08wPaINt0zHzx-9W1YseilKrOrrcBlrPSEi1h1Kb48MbE Pb8CmNy75



Scale = 1:19.2

TOTAL WEIGHT = 2 X 10 = 20 lb

LUMBER
N. L. G. A. RULES

CHORDS	SIZE	LUMBER	DESCR.
E - B	2x4	DRY	No.2
A - C	2x4	DRY	No.2
E - D	2x4	DRY	No.2

DRY: SEASONED LUMBER.

PLATES (table is in inches)

JT	TYPE	PLATES	W	LEN	Y	X
B	TMV+p	MT20	2.0	4.0		
E	BMV1+p	MT20	2.0	4.0		

DIMENSIONS, SUPPORTS AND LOADINGS SPECIFIED BY FABRICATOR TO BE VERIFIED BY BUILDING DESIGNER

BEARINGS

	FACTORED GROSS REACTION	MAXIMUM FACTORED GROSS REACTION	INPUT BRG	REQRD BRG
JT	VERT	HORZ	DOWN	HORZ
E	528	0	528	0
C	188	0	188	0
D	35	0	44	0

SEE MITEK STANDARD DETAIL B97791H FOR CONNECTION TO JOINT(S) C, D

UNFACTORED REACTIONS

JT	1ST LCASE	SNOW	LIVE	PERM. LIVE	WIND	DEAD	SOIL
E	372	270 / 0	23 / 0	0 / 0	0 / 0	78 / 0	0 / 0
C	130	105 / 0	0 / 0	0 / 0	0 / 0	24 / 0	0 / 0
D	32	0 / 0	19 / 0	0 / 0	0 / 0	13 / 0	0 / 0

BEARING MATERIAL TO BE SPF NO.2 OR BETTER AT JOINT(S) E

BRACING
TOP CHORD TO BE SHEATHED OR MAX. PURLIN SPACING = 8.25 FT.
MAX. UNBRACED BOTTOM CHORD LENGTH = 10.00 FT OR RIGID CEILING DIRECTLY APPLIED.

ALL PITCH BREAKS AND PERIMETER CORNER JOINTS MUST BE Laterally RESTRAINED.

LOADING
TOTAL LOAD CASES: (4)

CHORDS				WEBS			
MEMB.	MAX. FACTORED FORCE (LBS)	FACTORED VERT. LOAD (PLF)	FACTORED LC1 MAX. CSI (LC)	MEMB.	MAX. FACTORED FORCE (LBS)	MAX. FACTORED CSI (LC)	UNBRACED LENGTH
FR-TO		FROM TO		FR-TO			
E-B	-483 / 0	0.0	0.0 0.02 (3)	E-B	7.81		
A-B	0 / 38	-124.4	-124.4 0.16 (1)	A-B	10.00		
B-C	-28 / 0	-124.4	-124.4 0.34 (1)	B-C	6.25		
E-D	0 / 0	-39.2	-39.2 0.03 (3)	E-D	10.00		

DESIGN CRITERIA

SPECIFIED LOADS:
TOP CH. LL = 34.8 PSF
DL = 8.0 PSF
BOT CH. LL = 10.5 PSF
DL = 7.3 PSF
TOTAL LOAD = 60.6 PSF

SPACING = 24.0 IN. C/C

THIS TRUSS IS DESIGNED FOR RESIDENTIAL OR SMALL BUILDING REQUIREMENTS OF PART 9, NBC 2015

THIS DESIGN COMPLIES WITH:
- PART 9 OF BCBC 2018, ABC 2019
- PART 9 OF OBC 2012 (2019 AMENDMENT)
- CSA 086-14
- TPIC 2014

DESIGN ASSUMPTIONS
- OVERHANG NOT TO BE ALTERED OR CUT OFF.

(55 % OF 48.1 P.S.F. G.S.L. PLUS 8.4 P.S.F. RAIN LOAD)
EQUALS 34.8 P.S.F. SPECIFIED ROOF LIVE LOAD

ALLOWABLE DEFL.(LL)= L/360 (0.19")
CALCULATED VERT. DEFL.(LL) = L/ 999 (0.00")
ALLOWABLE DEFL.(TL)= L/360 (0.19")
CALCULATED VERT. DEFL.(TL) = L/ 999 (0.00")

CSI: TC=0.34/1.00 (B-C:1) , BC=0.03/1.00 (D-E:3) ,
WB=0.00/1.00 (n/a:0) , SSI=0.22/1.00 (B-C:1)

DOL LUMBER=1.00 NAIL=1.00 LS BEND=1.10 COMP=1.10
SHEAR=1.10 TENS= 1.10

COMPANION LIVE LOAD FACTOR = 1.00

TRUSS PLATE MANUFACTURER IS NOT RESPONSIBLE FOR QUALITY CONTROL IN THE TRUSS MANUFACTURING PLANT .

NAIL VALUES
PLATE GRIP(DRY) SHEAR SECTION (PSI) (PLI) (PLI)
MAX MIN MAX MIN MAX MIN
MT20 650 371 1747 788 1987 1873

PLATE PLACEMENT TOL. = 0.250 inches

PLATE ROTATION TOL. = 5.0 Deg.

JSI GRIP= 0.27 (B) (INPUT = 0.90)
JSI METAL= 0.20 (B) (INPUT = 1.00)



READ ALL NOTES ON THIS PAGE AND ON ENGINEERING NOTE PAGE ENP-1. THIS NOTE PAGE IS AN INTEGRAL PART OF THIS DRAWING AS IT CONTAINS SPECIFICATIONS AND CRITERIA USED IN THE DESIGN OF THIS COMPONENT.




These plans have been reviewed for use with the corrections as noted. No other changes may be made without written approval of the Building Standards Branch. All work must comply with Zoning By-Law 2018-043, as amended, and the Ontario Building Code, as amended. These approved documents must be kept on site at all times. The building permit must be clearly posted on site at all times.

Discipline	Reviewer	BCIN	Date
Building Code	H. Authier	43236	2021-02-24
Sewage System			
Zoning			



Version 8.420 S Oct 9 2020 Mitek Industries, Inc. Sun Dec 20 11:35:30 2020 Page 1
ID:mCCrycxnlfAPc08wPalNt0zHzlx-9W1YseilKrotrCBlrPSEI1h4Bb4BMbE Pb8CIny75



Scale = 1:14.0

TOTAL WEIGHT = 2 X 7 = 15 lb

LUMBER				DESCR.
N. L. G. A. RULES	CHORDS	SIZE	LUMBER	
E - B	2x4	DRY	No.2	SPF
A - C	2x4	DRY	No.2	SPF
E - D	2x4	DRY	No.2	SPF

DRY: SEASONED LUMBER.

PLATES (table is in inches)				
JT	TYPE	PLATES	W	LEN Y X
B	TMV+p	MT20	2.0	4.0
E	BMV1+p	MT20	2.0	4.0

DIMENSIONS, SUPPORTS AND LOADINGS SPECIFIED BY FABRICATOR TO BE VERIFIED BY BUILDING DESIGNER

BEARINGS		FACTORED		MAXIMUM FACTORED		INPUT		REQRD	
JT	VERT	GROSS REACTION	HORZ	GROSS REACTION	HORZ	UPLIFT	IN-SX	BRG	IN-SX
E	370	0	370	0	0	5-8	1-8	1-8	1-8
C	96	0	96	0	0	1-8	1-8	1-8	1-8
D	35	0	44	0	0	1-8	1-8	1-8	1-8

SEE MITEK STANDARD DETAIL B97791H FOR CONNECTION TO JOINT(S) C, D

UNFACTORED REACTIONS		1ST LCASE		MAX/MIN COMPONENT REACTIONS					
JT	COMBINED	SNOW	LIVE	PERM.LIVE	WIND	DEAD	SOIL		
E	264	183 / 0	23 / 0	0 / 0	0 / 0	58 / 0	0 / 0		
C	86	54 / 0	0 / 0	0 / 0	0 / 0	12 / 0	0 / 0		
D	32	0 / 0	19 / 0	0 / 0	0 / 0	13 / 0	0 / 0		

BEARING MATERIAL TO BE SPF NO.2 OR BETTER AT JOINT(S) E

BRACING
TOP CHORD TO BE SHEATHED OR MAX. PURLIN SPACING = 8.25 FT.
MAX. UNBRACED BOTTOM CHORD LENGTH = 10.00 FT OR RIGID CEILING DIRECTLY APPLIED.

ALL PITCH BREAKS AND PERIMETER CORNER JOINTS MUST BE Laterally RESTRAINED.

LOADING
TOTAL LOAD CASES: (5)

C H O R D S		W E B S	
MEMB.	MAX. FACTORED FORCE (LBS)	FACTORED VERT. LOAD (PLF)	MAX. FACTORED FORCE (LBS)
FR-TO		FROM TO	LENGTH FR-TO
E-B	-327 / 0	0.0 0.0 0.02 (3)	7.81
A-B	0 / 38	-124.4 -124.4 0.16 (1)	10.00
B-C	-14 / 0	-124.4 -124.4 0.09 (1)	6.25
E-D	0 / 0	-39.2 -39.2 0.03 (3)	10.00

CANTILEVER ANALYSIS HAS BEEN CONSIDERED IN THIS DESIGN

DESIGN CRITERIA

SPECIFIED LOADS:
TOP CH. LL = 34.8 PSF
DL = 8.0 PSF
BOT CH. LL = 10.5 PSF
DL = 7.3 PSF
TOTAL LOAD = 60.6 PSF

SPACING = 24.0 IN. C/C

THIS TRUSS IS DESIGNED FOR RESIDENTIAL OR SMALL BUILDING REQUIREMENTS OF PART 9, NBCC 2015

THIS DESIGN COMPLIES WITH:
- PART 9 OF BCBC 2018, ABC 2019
- PART 9 OF OBC 2012 (2019 AMENDMENT)
- CSA 086-14
- TPIC 2014

DESIGN ASSUMPTIONS
- OVERHANG NOT TO BE ALTERED OR CUT OFF.

(55 % OF 48.1 P.S.F. G.S.L. PLUS 8.4 P.S.F. RAIN LOAD)
EQUALS 34.8 P.S.F. SPECIFIED ROOF LIVE LOAD

ALLOWABLE DEFL.(LL)= L/360 (0.19")
CALCULATED VERT. DEFL.(LL) = L/ 999 (0.00")
ALLOWABLE DEFL.(TL)= L/360 (0.19")
CALCULATED VERT. DEFL.(TL) = L/ 999 (0.00")

CSI: TC=0.16/1.00 (A-B:1) , BC=0.03/1.00 (D-E:3) ,
WB=0.00/1.00 (n/a:0) , SSI=0.12/1.00 (A-B:1)

DOL LUMBER=1.00 NAIL=1.00 LS BEND=1.10 COMP=1.10
SHEAR=1.10 TENS= 1.10

COMPANION LIVE LOAD FACTOR = 1.00

TRUSS PLATE MANUFACTURER IS NOT RESPONSIBLE FOR QUALITY CONTROL IN THE TRUSS MANUFACTURING PLANT .

NAIL VALUES
PLATE GRIP(DRY) SHEAR SECTION
(PSI) (PLI) (PLI)
MAX MIN MAX MIN MAX MIN
MT20 650 371 1747 788 1987 1873

PLATE PLACEMENT TOL. = 0.250 inches

PLATE ROTATION TOL. = 5.0 Deg.

JSI GRIP= 0.18 (B) (INPUT = 0.90)
JSI METAL= 0.14 (B) (INPUT = 1.00)




READ ALL NOTES ON THIS PAGE AND ON ENGINEERING NOTE PAGE ENP-1. THIS NOTE PAGE IS AN INTEGRAL PART OF THIS DRAWING AS IT CONTAINS SPECIFICATIONS AND CRITERIA USED IN THE DESIGN OF THIS COMPONENT.



These plans have been reviewed for use with the corrections as noted. No other changes may be made without written approval of the Building Standards Branch. All work must comply with Zoning By-Law 2018-043, as amended, and the Ontario Building Code, as amended. These approved documents must be kept on site at all times. The building permit must be clearly posted on site at all times.

Discipline	Reviewer	BCIN	Date
Building Code	H. Authier	43236	2021-02-24
Sewage System			
Zoning			





TOTAL WEIGHT = 2 X 12 = 24 lb

LUMBER			
N. L. G. A. RULES	CHORDS	SIZE	LUMBER
E - B	2x4	DRY	No.2
A - C	2x4	DRY	No.2
E - D	2x4	DRY	No.2

DESCR. SPF
SPF
SPF

DRY: SEASONED LUMBER.

PLATES (table is in inches)				
JT	TYPE	PLATES	W	LEN Y X
B	TMV+p	MT20	2.0	4.0
E	BMV1+p	MT20	2.0	4.0

DIMENSIONS, SUPPORTS AND LOADINGS SPECIFIED BY FABRICATOR TO BE VERIFIED BY BUILDING DESIGNER

BEARINGS		FACTORED		MAXIMUM FACTORED		INPUT		REQRD	
JT	VERT	GROSS REACTION	HORZ	GROSS REACTION	HORZ	BRG	IN-SX	BRG	IN-SX
E	485	0	485	0	0	5-8	1-8		
C	96	0	96	0	0	1-8	1-8		
D	97	0	123	0	0	1-8	1-8		

SEE MITEK STANDARD DETAIL B97791H FOR CONNECTION TO JOINT(S) C, D

UNFACTORED REACTIONS		1ST LCASE		MAX/MIN COMPONENT REACTIONS	
JT	COMBINED	SNOW	LIVE	PERM. LIVE	WIND
E	350	183 / 0	74 / 0	0 / 0	0 / 0
C	86	54 / 0	0 / 0	0 / 0	0 / 0
D	88	0 / 0	52 / 0	0 / 0	0 / 0

BEARING MATERIAL TO BE SPF NO.2 OR BETTER AT JOINT(S) E, C

BRACING
TOP CHORD TO BE SHEATHED OR MAX. PURLIN SPACING = 8.25 FT.
MAX. UNBRACED BOTTOM CHORD LENGTH = 10.00 FT OR RIGID CEILING DIRECTLY APPLIED.

ALL PITCH BREAKS AND PERIMETER CORNER JOINTS MUST BE LATERALLY RESTRAINED.

LOADING
TOTAL LOAD CASES: (4)

CHORDS		WEBS	
MEMB.	MAX. FACTORED FORCE (LBS)	MEMB.	MAX. FACTORED FORCE (LBS)
FR-TO		FR-TO	
E-B	-327 / 0	E-B	7.81
A-B	0 / 38	A-B	10.00
B-C	-14 / 0	B-C	6.25
E-D	0 / 0	E-D	10.00

DESIGN CRITERIA

SPECIFIED LOADS:
TOP CH. LL = 34.8 PSF
DL = 8.0 PSF
BOT CH. LL = 10.5 PSF
DL = 7.3 PSF
TOTAL LOAD = 60.6 PSF

SPACING = 24.0 IN. C/C

THIS TRUSS IS DESIGNED FOR RESIDENTIAL OR SMALL BUILDING REQUIREMENTS OF PART 9, NBCC 2015

THIS DESIGN COMPLIES WITH:
- PART 9 OF BCBC 2018, ABC 2019
- PART 9 OF OBC 2012 (2019 AMENDMENT)
- CSA 086-14
- TPIC 2014

DESIGN ASSUMPTIONS
- OVERHANG NOT TO BE ALTERED OR CUT OFF.

(55 % OF 48.1 P.S.F. G.S.L. PLUS 8.4 P.S.F. RAIN LOAD)
EQUALS 34.8 P.S.F. SPECIFIED ROOF LIVE LOAD

ALLOWABLE DEFL.(LL)= L/360 (0.20")
CALCULATED VERT. DEFL.(LL) = L/ 999 (0.05")
ALLOWABLE DEFL.(TL)= L/360 (0.20")
CALCULATED VERT. DEFL.(TL) = L/ 874 (0.08")

CSI: TC=0.22/1.00 (B-E:3) , BC=0.22/1.00 (D-E:3) ,
WB=0.00/1.00 (n/a:0) , SSI=0.14/1.00 (D-E:3)

DOL LUMBER=1.00 NAIL=1.00 LS BEND=1.10 COMP=1.10
SHEAR=1.10 TENS= 1.10

COMPANION LIVE LOAD FACTOR = 1.00

TRUSS PLATE MANUFACTURER IS NOT RESPONSIBLE FOR QUALITY CONTROL IN THE TRUSS MANUFACTURING PLANT .

NAIL VALUES
PLATE GRIP(DRY) SHEAR SECTION
(PSI) (PLI) (PLI)
MAX MIN MAX MIN MAX MIN
MT20 650 371 1747 788 1987 1873

PLATE PLACEMENT TOL. = 0.250 inches

PLATE ROTATION TOL. = 5.0 Deg.

JSI GRIP= 0.18 (B) (INPUT = 0.90)
JSI METAL= 0.14 (B) (INPUT = 1.00)



READ ALL NOTES ON THIS PAGE AND ON ENGINEERING NOTE PAGE ENP-1. THIS NOTE PAGE IS AN INTEGRAL PART OF THIS DRAWING AS IT CONTAINS SPECIFICATIONS AND CRITERIA USED IN THE DESIGN OF THIS COMPONENT.




These plans have been reviewed for use with the corrections as noted. No other changes may be made without written approval of the Building Standards Branch. All work must comply with Zoning By-Law 2018-043, as amended, and the Ontario Building Code, as amended. These approved documents must be kept on site at all times. The building permit must be clearly posted on site at all times.

Discipline	Reviewer	BCIN	Date
Building Code	H. Authier	43236	2021-02-24
Sewage System			
Zoning			



Scale = 1:19.0



TOTAL WEIGHT = 2 X 15 = 29 lb

LUMBER				
N. L. G. A. RULES				
CHORDS	SIZE	LUMBER	DESCR.	
E - B	2x4	DRY	No.2	SPF
A - C	2x4	DRY	No.2	SPF
E - D	2x4	DRY	No.2	SPF

DRY: SEASONED LUMBER.

PLATES (table is in inches)				
JT	TYPE	PLATES	W	LEN Y X
B	TMV+p	MT20	2.0	4.0
E	BMV1+p	MT20	2.0	4.0

DIMENSIONS, SUPPORTS AND LOADINGS SPECIFIED BY FABRICATOR TO BE VERIFIED BY BUILDING DESIGNER

BEARINGS									
FACTORED GROSS REACTION		MAXIMUM FACTORED GROSS REACTION		INPUT BRG		REQRD BRG			
JT	VERT	HORZ	DOWN	HORZ	UPLIFT	IN-SX	IN-SX		
E	621	0	621	0	0	5-8	1-8		
C	188	0	188	0	0	1-8	1-8		
D	97	0	123	0	0	1-8	1-8		

SEE MITEK STANDARD DETAIL B97791H FOR CONNECTION TO JOINT(S) C, D

UNFACTORED REACTIONS							
JT	1ST LCASE	SNOW	LIVE	PERM. LIVE	WIND	DEAD	SOIL
E	458	270 / 0	74 / 0	0 / 0	0 / 0	114 / 0	0 / 0
C	130	105 / 0	0 / 0	0 / 0	0 / 0	24 / 0	0 / 0
D	88	0 / 0	52 / 0	0 / 0	0 / 0	36 / 0	0 / 0

BEARING MATERIAL TO BE SPF NO.2 OR BETTER AT JOINT(S) E, C

BRACING
TOP CHORD TO BE SHEATHED OR MAX. PURLIN SPACING = 8.25 FT.
MAX. UNBRACED BOTTOM CHORD LENGTH = 10.00 FT OR RIGID CEILING DIRECTLY APPLIED.

ALL PITCH BREAKS AND PERIMETER CORNER JOINTS MUST BE Laterally RESTRAINED.

LOADING
TOTAL LOAD CASES: (4)

CHORDS				WEBS			
MEMB.	MAX. FACTORED FORCE (LBS)	FACTORED VERT. LOAD (PLF)	FACTORED LC1 MAX. CSI (LC)	MEMB.	MAX. FACTORED FORCE (LBS)	MAX. FACTORED CSI (LC)	
FR-TO		FROM TO		FR-TO			
E-B	-483 / 0	0.0	0.0 0.23 (3)	E-B	7.81		
A-B	0 / 38	-124.4	-124.4 0.16 (1)	A-B	10.00		
B-C	-28 / 0	-124.4	-124.4 0.34 (1)	B-C	6.25		
E-D	0 / 0	-39.2	-39.2 0.23 (3)	E-D	10.00		

DESIGN CRITERIA

SPECIFIED LOADS:
TOP CH. LL = 34.8 PSF
DL = 8.0 PSF
BOT CH. LL = 10.5 PSF
DL = 7.3 PSF
TOTAL LOAD = 60.6 PSF

SPACING = 24.0 IN. C/C

THIS TRUSS IS DESIGNED FOR RESIDENTIAL OR SMALL BUILDING REQUIREMENTS OF PART 9, NBCC 2015

THIS DESIGN COMPLIES WITH:
- PART 9 OF CBC 2018, ABC 2019
- PART 9 OF OBC 2012 (2019 AMENDMENT)
- CSA 086-14
- TPIC 2014

DESIGN ASSUMPTIONS
- OVERHANG NOT TO BE ALTERED OR CUT OFF.

(55 % OF 48.1 P.S.F. G.S.L. PLUS 8.4 P.S.F. RAIN LOAD)
EQUALS 34.8 P.S.F. SPECIFIED ROOF LIVE LOAD

ALLOWABLE DEFL.(LL)= L/360 (0.20")
CALCULATED VERT. DEFL.(LL) = L/999 (0.05")
ALLOWABLE DEFL.(TL)= L/360 (0.20")
CALCULATED VERT. DEFL.(TL) = L/874 (0.08")

CSI: TC=0.34/1.00 (B-C:1), BC=0.23/1.00 (D-E:3),
WB=0.00/1.00 (n/a:0), SSI=0.22/1.00 (B-C:1)

DOL LUMBER=1.00 NAIL=1.00 LS BEND=1.10 COMP=1.10
SHEAR=1.10 TENS= 1.10

COMPANION LIVE LOAD FACTOR = 1.00

TRUSS PLATE MANUFACTURER IS NOT RESPONSIBLE FOR QUALITY CONTROL IN THE TRUSS MANUFACTURING PLANT.

NAIL VALUES
PLATE GRIP(DRY) SHEAR SECTION (PSI) (PLI) (PLI)
MAX MIN MAX MIN MAX MIN
MT20 650 371 1747 788 1987 1873

PLATE PLACEMENT TOL. = 0.250 inches

PLATE ROTATION TOL. = 5.0 Deg.

JSI GRIP= 0.27 (B) (INPUT = 0.90)
JSI METAL= 0.20 (B) (INPUT = 1.00)



READ ALL NOTES ON THIS PAGE AND ON ENGINEERING NOTE PAGE ENP-1. THIS NOTE PAGE IS AN INTEGRAL PART OF THIS DRAWING AS IT CONTAINS SPECIFICATIONS AND CRITERIA USED IN THE DESIGN OF THIS COMPONENT.




These plans have been reviewed for use with the corrections as noted. No other changes may be made without written approval of the Building Standards Branch. All work must comply with Zoning By-Law 2018-043, as amended, and the Ontario Building Code, as amended. These approved documents must be kept on site at all times. The building permit must be clearly posted on site at all times.

Discipline	Reviewer	BCIN	Date
Building Code	H. Authier	43236	2021-02-24
Sewage System			
Zoning			



Version 8.420 S Oct 9 2020 Mitek Industries, Inc. Sun Dec 20 11:35:31 2020 Page 1
ID:mCCrycxfAPc08wPaiNt0zHzlx-dibw3 jL59WiSimUP7 TFE6V?NA52U8eFulBpy75



Scale = 1:23.7

TOTAL WEIGHT = 10 X 17 = 171 lb

LUMBER					DESCR.
N. L. G. A. RULES	CHORDS	SIZE	LUMBER		
E - B	2x4	DRY	No.2		SPF
A - C	2x4	DRY	No.2		SPF
E - D	2x4	DRY	No.2		SPF

DRY: SEASONED LUMBER.

PLATES (table is in inches)					
JT	TYPE	PLATES	W	LEN	Y X
B	TMV+p	MT20	2.0	4.0	
E	BMV1+p	MT20	2.0	4.0	

DIMENSIONS, SUPPORTS AND LOADINGS SPECIFIED BY FABRICATOR TO BE VERIFIED BY BUILDING DESIGNER

BEARINGS									
JT	FACTORED GROSS REACTION	VERT	HORZ	MAXIMUM FACTORED GROSS REACTION	DOWN	HORZ	INPUT BRG	UPLIFT IN-SX	REQD BRG
E	774	0	0	774	0	0	5-8	1-8	
C	280	0	0	280	0	0	1-8	1-8	
D	97	0	0	123	0	0	1-8	1-8	

SEE MITEK STANDARD DETAIL B97791H FOR CONNECTION TO JOINT(S) C, D

UNFACTORED REACTIONS									
JT	1ST LCASE	SNOW	LIVE	PERM. LIVE	WIND	DEAD	SOIL		
E	563	355 / 0	74 / 0	0 / 0	0 / 0	133 / 0	0 / 0		
C	193	157 / 0	0 / 0	0 / 0	0 / 0	36 / 0	0 / 0		
D	88	0 / 0	52 / 0	0 / 0	0 / 0	36 / 0	0 / 0		

BEARING MATERIAL TO BE SPF NO.2 OR BETTER AT JOINT(S) E

BRACING
TOP CHORD TO BE SHEATHED OR MAX. PURLIN SPACING = 8.25 FT.
MAX. UNBRACED BOTTOM CHORD LENGTH = 10.00 FT OR RIGID CEILING DIRECTLY APPLIED.

ALL PITCH BREAKS AND PERIMETER CORNER JOINTS MUST BE Laterally RESTRAINED.

LOADING
TOTAL LOAD CASES: (4)

CHORDS				WEBS			
MEMB.	MAX. FACTORED FORCE (LBS)	FACTORED VERT. LOAD (PLF)	FACTORED LC1 MAX. CSI (LC)	MEMB.	MAX. FACTORED FORCE (LBS)	MAX. FACTORED UNBRACED LENGTH (FT)	FR-TO
E-B	-635 / 0	0.0	0.0 0.24 (3)	E-B	7.81	7.81	
A-B	0 / 38	-124.4	-124.4 0.18 (1)	A-B	10.00	10.00	
B-C	-42 / 0	-124.4	-124.4 0.76 (1)	B-C	6.25	6.25	
E-D	0 / 0	-39.2	-39.2 0.24 (3)	E-D	10.00	10.00	

DESIGN CRITERIA

SPECIFIED LOADS:
TOP CH. LL = 34.8 PSF
DL = 8.0 PSF
BOT CH. LL = 10.5 PSF
DL = 7.3 PSF
TOTAL LOAD = 60.6 PSF

SPACING = 24.0 IN. C/C

THIS TRUSS IS DESIGNED FOR RESIDENTIAL OR SMALL BUILDING REQUIREMENTS OF PART 9, NBCC 2015

THIS DESIGN COMPLIES WITH:
- PART 9 OF BCBC 2018, ABC 2019
- PART 9 OF OBC 2012 (2019 AMENDMENT)
- CSA 086-14
- TPIC 2014

DESIGN ASSUMPTIONS
- OVERHANG NOT TO BE ALTERED OR CUT OFF.

(55 % OF 48.1 P.S.F. G.S.L. PLUS 8.4 P.S.F. RAIN LOAD)
EQUALS 34.8 P.S.F. SPECIFIED ROOF LIVE LOAD

ALLOWABLE DEFL.(LL)= L/360 (0.20")
CALCULATED VERT. DEFL.(LL) = L/ 999 (0.05")
ALLOWABLE DEFL.(TL)= L/360 (0.20")
CALCULATED VERT. DEFL.(TL) = L/ 874 (0.08")

CSI: TC=0.76/1.00 (B-C:1) , BC=0.24/1.00 (D-E:3) ,
WB=0.00/1.00 (n/a:0) , SSI=0.33/1.00 (B-C:1)

DOL LUMBER=1.00 NAIL=1.00 LS BEND=1.10 COMP=1.10
SHEAR=1.10 TENS= 1.10

COMPANION LIVE LOAD FACTOR = 1.00

TRUSS PLATE MANUFACTURER IS NOT RESPONSIBLE FOR QUALITY CONTROL IN THE TRUSS MANUFACTURING PLANT .

NAIL VALUES
PLATE GRIP(DRY) SHEAR SECTION (PSI) (PLI) (PLI)
MAX MIN MAX MIN MAX MIN
MT20 650 371 1747 788 1987 1873

PLATE PLACEMENT TOL. = 0.250 inches

PLATE ROTATION TOL. = 5.0 Deg.

JSI GRIP= 0.36 (B) (INPUT = 0.90)
JSI METAL= 0.26 (B) (INPUT = 1.00)



READ ALL NOTES ON THIS PAGE AND ON ENGINEERING NOTE PAGE ENP-1. THIS NOTE PAGE IS AN INTEGRAL PART OF THIS DRAWING AS IT CONTAINS SPECIFICATIONS AND CRITERIA USED IN THE DESIGN OF THIS COMPONENT.




These plans have been reviewed for use with the corrections as noted. No other changes may be made without written approval of the Building Standards Branch. All work must comply with Zoning By-Law 2018-043, as amended, and the Ontario Building Code, as amended. These approved documents must be kept on site at all times. The building permit must be clearly posted on site at all times.

Discipline	Reviewer	BCIN	Date
Building Code	H. Authier	43236	2021-02-24
Sewage System			
Zoning			



Version 8.420 S Oct 9 2020 MiTek Industries, Inc. Sun Dec 20 11:35:32 2020 Page 1
ID:mCCrvcxnlfAPc08wPalNt0zHzlx-5u9IHJkzsSeZ4vLhvqVInSmQaPmedVkhHsvdJkFy7

Scale = 1:17.3



TOTAL WEIGHT = 8 lb

LUMBER				
N. L. G. A. RULES				
CHORDS	SIZE	LUMBER	DESCR.	
E - B	2x4	DRY	No.2	SPF
A - C	2x4	DRY	No.2	SPF
E - D	2x4	DRY	No.2	SPF

DRY: SEASONED LUMBER.

PLATES (table is in inches)					
JT	TYPE	PLATES	W	LEN	Y X
B	TMV+p	MT20	2.0	4.0	
E	BMV1+p	MT20	2.0	4.0	

DIMENSIONS, SUPPORTS AND LOADINGS SPECIFIED BY FABRICATOR TO BE VERIFIED BY BUILDING DESIGNER

BEARINGS		FACTORED		MAXIMUM FACTORED		INPUT		REQRD	
		GROSS REACTION		GROSS REACTION		BRG		BRG	
JT	VERT	HORZ	DOWN	HORZ	UPLIFT	IN-SX	IN-SX		
E	378	0	378	0	0	5-8	1-8		
C	100	0	100	0	0	1-8	1-8		
D	36	0	45	0	0	1-8	1-8		

SEE MITEK STANDARD DETAIL B97791H FOR CONNECTION TO JOINT(S) C, D

UNFACTORED REACTIONS							
JT	1ST LCASE	SNOW	LIVE	PERM.LIVE	WIND	DEAD	SOIL
E	270	188 / 0	23 / 0	0 / 0	0 / 0	59 / 0	0 / 0
C	69	56 / 0	0 / 0	0 / 0	0 / 0	13 / 0	0 / 0
D	32	0 / 0	19 / 0	0 / 0	0 / 0	13 / 0	0 / 0

BEARING MATERIAL TO BE SPF NO.2 OR BETTER AT JOINT(S) E

BRACING

TOP CHORD TO BE SHEATHED OR MAX. PURLIN SPACING = 8.25 FT.
MAX. UNBRACED BOTTOM CHORD LENGTH = 10.00 FT OR RIGID CEILING DIRECTLY APPLIED.

ALL PITCH BREAKS AND PERIMETER CORNER JOINTS MUST BE Laterally RESTRAINED.

LOADING

TOTAL LOAD CASES: (5)

CHORDS				WEBS			
MEMB.	MAX. FACTORED FORCE (LBS)	FACTORED VERT. LOAD (PLF)	FACTORED LC1 MAX (LC)	MEMB.	MAX. FACTORED FORCE (LBS)	FACTORED VERT. LOAD (PLF)	FACTORED LC1 MAX (LC)
FR-TO		FROM TO	LENGTH	FR-TO		FROM TO	LENGTH
E-B	-335 / 0	0.0	0.02 (3)	7.81			
A-B	0 / 47	-124.4	-124.4 0.17 (1)	10.00			
B-C	-18 / 0	-124.4	-124.4 0.09 (1)	6.25			
E-D	0 / 0	-39.2	-39.2 0.03 (3)	10.00			

CANTILEVER ANALYSIS HAS BEEN CONSIDERED IN THIS DESIGN

DESIGN CRITERIA

SPECIFIED LOADS:
TOP CH. LL = 34.8 PSF
DL = 8.0 PSF
BOT CH. LL = 10.5 PSF
DL = 7.3 PSF
TOTAL LOAD = 60.6 PSF

SPACING = 24.0 IN. C/C

THIS TRUSS IS DESIGNED FOR RESIDENTIAL OR SMALL BUILDING REQUIREMENTS OF PART 9, NBC2015

THIS DESIGN COMPLIES WITH:
- PART 9 OF BCBC 2018, ABC 2019
- PART 9 OF OBC 2012 (2019 AMENDMENT)
- CSA 086-14
- TPIC 2014

DESIGN ASSUMPTIONS
- OVERHANG NOT TO BE ALTERED OR CUT OFF.

(55 % OF 48.1 P.S.F. G.S.L. PLUS 8.4 P.S.F. RAIN LOAD)
EQUALS 34.8 P.S.F. SPECIFIED ROOF LIVE LOAD

ALLOWABLE DEFL.(LL)= L/360 (0.19")
CALCULATED VERT. DEFL.(LL) = L/ 999 (0.00")
ALLOWABLE DEFL.(TL)= L/360 (0.19")
CALCULATED VERT. DEFL.(TL) = L/ 999 (0.00")

CSI: TC=0.17/1.00 (A-B:1) , BC=0.03/1.00 (D-E:3) ,
WB=0.00/1.00 (n/a:0) , SSI=0.11/1.00 (A-B:1)

DOL LUMBER=1.00 NAIL=1.00 LS BEND=1.10 COMP=1.10
SHEAR=1.10 TENS= 1.10

COMPANION LIVE LOAD FACTOR = 1.00

TRUSS PLATE MANUFACTURER IS NOT RESPONSIBLE FOR QUALITY CONTROL IN THE TRUSS MANUFACTURING PLANT .

NAIL VALUES
PLATE GRIP(DRY) SHEAR SECTION
(PSI) (PLI) (PLI)
MAX MIN MAX MIN MAX MIN
MT20 650 371 1747 788 1987 1873

PLATE PLACEMENT TOL. = 0.250 inches

PLATE ROTATION TOL. = 5.0 Deg.

JSI GRIP= 0.21 (B) (INPUT = 0.90)
JSI METAL= 0.17 (B) (INPUT = 1.00)



READ ALL NOTES ON THIS PAGE AND ON ENGINEERING NOTE PAGE ENP-1. THIS NOTE PAGE IS AN INTEGRAL PART OF THIS DRAWING AS IT CONTAINS SPECIFICATIONS AND CRITERIA USED IN THE DESIGN OF THIS COMPONENT.




These plans have been reviewed for use with the corrections as noted. No other changes may be made without written approval of the Building Standards Branch. All work must comply with Zoning By-Law 2018-043, as amended, and the Ontario Building Code, as amended. These approved documents must be kept on site at all times. The building permit must be clearly posted on site at all times.

Discipline	Reviewer	BCIN	Date
Building Code	H. Authier	43236	2021-02-24
Sewage System			
Zoning			



Scale = 1:24.3



TOTAL WEIGHT = 11 lb

LUMBER					DESCR.
N. L. G. A. RULES	CHORDS	SIZE	LUMBER		
E - B	2x4	DRY	No.2		SPF
A - C	2x4	DRY	No.2		SPF
E - D	2x4	DRY	No.2		SPF

DRY: SEASONED LUMBER.

PLATES (table is in inches)					
JT TYPE	PLATES	W	LEN	Y	X
B	TMV+p	MT20	2.0	4.0	
E	BMV1+p	MT20	2.0	4.0	

DIMENSIONS, SUPPORTS AND LOADINGS SPECIFIED BY FABRICATOR TO BE VERIFIED BY BUILDING DESIGNER

BEARINGS

	FACTORED GROSS REACTION		MAXIMUM FACTORED GROSS REACTION			INPUT BRG	REQRD BRG
JT	VERT	HORZ	DOWN	HORZ	UPLIFT	IN-SX	IN-SX
E	534	0	534	0	0	5-8	1-8
C	193	0	193	0	0	1-8	1-8
D	36	0	45	0	0	1-8	1-8

SEE MITEK STANDARD DETAIL B97791H FOR CONNECTION TO JOINT(S) C, D

UNFACTORED REACTIONS

JT	1ST LCASE	SNOW	LIVE	PERM. LIVE	WIND	DEAD	SOIL
E	377	275 / 0	23 / 0	0 / 0	0 / 0	79 / 0	0 / 0
C	133	108 / 0	0 / 0	0 / 0	0 / 0	25 / 0	0 / 0
D	32	0 / 0	19 / 0	0 / 0	0 / 0	13 / 0	0 / 0

BEARING MATERIAL TO BE SPF NO.2 OR BETTER AT JOINT(S) E

BRACING

TOP CHORD TO BE SHEATHED OR MAX. PURLIN SPACING = 8.25 FT.
MAX. UNBRACED BOTTOM CHORD LENGTH = 10.00 FT OR RIGID CEILING DIRECTLY APPLIED.

ALL PITCH BREAKS AND PERIMETER CORNER JOINTS MUST BE Laterally RESTRAINED.

LOADING

TOTAL LOAD CASES: (4)

CHORDS				WEBS			
MEMB.	MAX. FACTORED FORCE (LBS)	FACTORED VERT. LOAD (PLF)	FACTORED LC1 MAX. CSI (LC)	MEMB.	MAX. FACTORED FORCE (LBS)	MAX. FACTORED CSI (LC)	
FR-TO		FROM TO		FR-TO			
E-B	-491 / 0	0.0	0.0 0.02 (3)	7.81			
A-B	0 / 47	-124.4	-124.4 0.17 (1)	10.00			
B-C	-36 / 0	-124.4	-124.4 0.36 (1)	6.25			
E-D	0 / 0	-39.2	-39.2 0.04 (3)	10.00			

DESIGN CRITERIA

SPECIFIED LOADS:

TOP CH.	LL = 34.8 PSF
	DL = 8.0 PSF
BOT CH.	LL = 10.5 PSF
	DL = 7.3 PSF
TOTAL LOAD	= 60.6 PSF

SPACING = 24.0 IN. C/C

THIS TRUSS IS DESIGNED FOR RESIDENTIAL OR SMALL BUILDING REQUIREMENTS OF PART 9, NBCC 2015

THIS DESIGN COMPLIES WITH:

- PART 9 OF BCBC 2018, ABC 2019
- PART 9 OF OBC 2012 (2019 AMENDMENT)
- CSA 086-14
- TPIC 2014

DESIGN ASSUMPTIONS

-OVERHANG NOT TO BE ALTERED OR CUT OFF.

(55 % OF 48.1 P.S.F. G.S.L. PLUS 8.4 P.S.F. RAIN LOAD)
EQUALS 34.8 P.S.F. SPECIFIED ROOF LIVE LOAD

ALLOWABLE DEFL.(LL)= L/360 (0.19")
CALCULATED VERT. DEFL.(LL) = L/ 999 (0.00")
ALLOWABLE DEFL.(TL)= L/360 (0.19")
CALCULATED VERT. DEFL.(TL) = L/ 999 (0.00")

CSI: TC=0.36/1.00 (B-C:1) , BC=0.04/1.00 (D-E:3) ,
WB=0.00/1.00 (n/a:0) , SSI=0.21/1.00 (B-C:1)

DOL LUMBER=1.00 NAIL=1.00 LS BEND=1.10 COMP=1.10
SHEAR=1.10 TENS= 1.10

COMPANION LIVE LOAD FACTOR = 1.00

TRUSS PLATE MANUFACTURER IS NOT RESPONSIBLE FOR QUALITY CONTROL IN THE TRUSS MANUFACTURING PLANT .

NAIL VALUES

PLATE	GRIP(DRY)	SHEAR	SECTION
(PSI)	(PLI)	(PLI)	(PLI)
MAX MIN	MAX MIN	MAX MIN	MAX MIN
MT20	650	371	1747 788 1987 1873

PLATE PLACEMENT TOL. = 0.250 inches

PLATE ROTATION TOL. = 5.0 Deg.

JSI GRIP= 0.30 (B) (INPUT = 0.90)
JSI METAL= 0.25 (B) (INPUT = 1.00)




READ ALL NOTES ON THIS PAGE AND ON ENGINEERING NOTE PAGE ENP-1. THIS NOTE PAGE IS AN INTEGRAL PART OF THIS DRAWING AS IT CONTAINS SPECIFICATIONS AND CRITERIA USED IN THE DESIGN OF THIS COMPONENT.



These plans have been reviewed for use with the corrections as noted. No other changes may be made without written approval of the Building Standards Branch. All work must comply with Zoning By-Law 2018-043, as amended, and the Ontario Building Code, as amended. These approved documents must be kept on site at all times. The building permit must be clearly posted on site at all times.

Discipline	Reviewer	BCN	Date
Building Code	H. Authier	43236	2021-02-24
Sewage System			
Zoning			





Scale: 1/2"=1'

TOTAL WEIGHT = 16 lb

LUMBER					DESCR.
N. L. G. A. RULES	CHORDS	SIZE	LUMBER	No.2	
E - B	2x4	DRY	No.2		SPF
A - C	2x4	DRY	No.2		SPF
E - D	2x4	DRY	No.2		SPF

DRY: SEASONED LUMBER.

PLATES (table is in inches)					
JT	TYPE	PLATES	W	LEN	X
B	TMV+p	MT20	2.0	4.0	
E	BMV1+p	MT20	2.0	4.0	

DIMENSIONS, SUPPORTS AND LOADINGS SPECIFIED BY FABRICATOR TO BE VERIFIED BY BUILDING DESIGNER

BEARINGS		FACTORED GROSS REACTION	MAXIMUM FACTORED GROSS REACTION	INPUT BRG	REQRD BRG
JT	VERT	HORZ	DOWN	HORZ	UPLIFT
E	628	0	628	0	0
C	193	0	193	0	0
D	99	0	125	0	0

BEVELED PLATE OR SHIM REQUIRED TO PROVIDE FULL BEARING SURFACE WITH TRUSS CHORD AT JT(S) C

SEE MITEK STANDARD DETAIL B97791H FOR CONNECTION TO JOINT(S) D

UNFACTORED REACTIONS

1ST LCASE	MAX	MIN	COMPONENT REACTIONS				
JT	COMBINED	SNOW	LIVE	PERM.LIVE	WIND	DEAD	SOIL
E	462	275 / 0	73 / 0	0 / 0	0 / 0	114 / 0	0 / 0
C	133	108 / 0	0 / 0	0 / 0	0 / 0	25 / 0	0 / 0
D	89	0 / 0	53 / 0	0 / 0	0 / 0	37 / 0	0 / 0

BEARING MATERIAL TO BE SPF NO.2 OR BETTER AT JOINT(S) E, C

BRACING

TOP CHORD TO BE SHEATHED OR MAX. PURLIN SPACING = 6.25 FT.
MAX. UNBRACED BOTTOM CHORD LENGTH = 10.00 FT OR RIGID CEILING DIRECTLY APPLIED.

ALL PITCH BREAKS AND PERIMETER CORNER JOINTS MUST BE Laterally RESTRAINED.

LOADING

TOTAL LOAD CASES: (4)

CHORDS		MAX. FACTORED	FACTORED	WEBS		MAX. FACTORED
MEMB.	FORCE (LBS)	VERT. LOAD (PLF)	LC1 MAX (LC)	MEMB.	FORCE (LBS)	MAX (LC)
FR-TO				FR-TO		
E-B	-491 / 0	0.0	0.0 0.21 (3)	7.81		
A-B	0 / 47	-124.4	-124.4 0.17 (1)	10.00		
B-C	-36 / 0	-124.4	-124.4 0.36 (1)	6.25		
E-D	0 / 0	-39.2	-39.2 0.23 (3)	10.00		

DESIGN CRITERIA

SPECIFIED LOADS:

TOP CH.	LL = 34.8	PSF
	DL = 8.0	PSF
BOT CH.	LL = 10.5	PSF
	DL = 7.3	PSF
TOTAL LOAD	= 60.6	PSF

SPACING = 24.0 IN. C/C

THIS TRUSS IS DESIGNED FOR RESIDENTIAL OR SMALL BUILDING REQUIREMENTS OF PART 9, NBCC 2015

THIS DESIGN COMPLIES WITH:

- PART 9 OF BCBC 2018, ABC 2019
- PART 9 OF OBC 2012 (2019 AMENDMENT)
- CSA 086-14
- TPIC 2014

DESIGN ASSUMPTIONS

-OVERHANG NOT TO BE ALTERED OR CUT OFF.

(55 % OF 48.1 P.S.F. G.S.L. PLUS 8.4 P.S.F. RAIN LOAD)
EQUALS 34.8 P.S.F. SPECIFIED ROOF LIVE LOAD

ALLOWABLE DEFL.(LL)= L/360 (0.20")
CALCULATED VERT. DEFL.(LL) = L/ 999 (0.05")
ALLOWABLE DEFL.(TL)= L/360 (0.20")
CALCULATED VERT. DEFL.(TL) = L/ 832 (0.09")

CSI: TC=0.36/1.00 (B-C:1) , BC=0.23/1.00 (D-E:3) ,
WB=0.00/1.00 (n/a:0) , SSI=0.21/1.00 (B-C:1)

DOL LUMBER=1.00 NAIL=1.00 LS BEND=1.10 COMP=1.10
SHEAR=1.10 TENS= 1.10

COMPANION LIVE LOAD FACTOR = 1.00

TRUSS PLATE MANUFACTURER IS NOT RESPONSIBLE FOR QUALITY CONTROL IN THE TRUSS MANUFACTURING PLANT .

NAIL VALUES

PLATE	GRIP(DRY)	SHEAR	SECTION
(PSI)	(PLI)	(PLI)	(PLI)
MAX MIN	MAX MIN	MAX MIN	MAX MIN
MT20	650	371	1747

PLATE PLACEMENT TOL. = 0.250 inches

PLATE ROTATION TOL. = 5.0 Deg.

JSI GRIP= 0.30 (B) (INPUT = 0.00)
JSI METAL= 0.25 (B) (INPUT = 1.00)



READ ALL NOTES ON THIS PAGE AND ON ENGINEERING NOTE PAGE ENP-1. THIS NOTE PAGE IS AN INTEGRAL PART OF THIS DRAWING AS IT CONTAINS SPECIFICATIONS AND CRITERIA USED IN THE DESIGN OF THIS COMPONENT.




These plans have been reviewed for use with the corrections as noted. No other changes may be made without written approval of the Building Standards Branch. All work must comply with Zoning By-Law 2018-043, as amended, and the Ontario Building Code, as amended. These approved documents must be kept on site at all times. The building permit must be clearly posted on site at all times.

Discipline	Reviewer	BCIN	Date
Building Code	H. Authier	43236	2021-02-24
Sewage System			
Zoning			



Version 8.420 S Oct 9 2020 Mitek Industries, Inc. Sun Dec 20 11:35:34 2020 Page 1
ID:mCCrycxlFAPc08wPaiNt0zHzlx-1HH2h?mDO4uHJDU34FXAttsdkCOsIPEaKD6Qo8y7



Scale = 1:30.0

TOTAL WEIGHT = 18 lb

LUMBER					DESCR.
N. L. G. A. RULES	CHORDS	SIZE	LUMBER		
E - B	2x4	DRY	No.2		SPF
A - C	2x4	DRY	No.2		SPF
E - D	2x4	DRY	No.2		SPF

DRY: SEASONED LUMBER.

PLATES (table is in inches)					
JT	TYPE	PLATES	W	LEN	Y X
B	TMV+p	MT20	2.0	4.0	
E	BMV1+p	MT20	2.0	4.0	

DIMENSIONS, SUPPORTS AND LOADINGS SPECIFIED BY FABRICATOR TO BE VERIFIED BY BUILDING DESIGNER

BEARINGS		FACTORED GROSS REACTION		MAXIMUM FACTORED GROSS REACTION		INPUT BRG		REQRD BRG	
JT	VERT	HORZ	DOWN	HORZ	UPLIFT	IN-SX	IN-SX		
E	790	0	790	0	0	5-8	1-8		
C	280	0	280	0	0	1-8	1-8		
D	99	0	125	0	0	1-8	1-8		

SEE MITEK STANDARD DETAIL B97791H FOR CONNECTION TO JOINT(S) C, D

UNFACTORED REACTIONS		1ST LCASE		MAX / MIN COMPONENT REACTIONS		WIND	DEAD	SOIL
JT	COMBINED	SNOW	LIVE	PERM. LIVE	UNBRAC			
E	573	365 / 0	73 / 0	0 / 0	0 / 0	135 / 0	0 / 0	0 / 0
C	193	157 / 0	0 / 0	0 / 0	0 / 0	38 / 0	0 / 0	0 / 0
D	89	0 / 0	53 / 0	0 / 0	0 / 0	37 / 0	0 / 0	0 / 0

BEARING MATERIAL TO BE SPF NO.2 OR BETTER AT JOINT(S) E

BRACING
TOP CHORD TO BE SHEATHED OR MAX. PURLIN SPACING = 8.25 FT.
MAX. UNBRACED BOTTOM CHORD LENGTH = 10.00 FT OR RIGID CEILING DIRECTLY APPLIED.

ALL PITCH BREAKS AND PERIMETER CORNER JOINTS MUST BE Laterally RESTRAINED.

LOADING
TOTAL LOAD CASES: (4)

CHORDS		WEBS	
MEMB.	MAX. FACTORED FORCE (LBS)	MEMB.	MAX. FACTORED FORCE (LBS)
FR-TO		FR-TO	
E-B	-853 / 0	E-B	7.81
A-B	0 / 52	A-B	10.00
B-C	-52 / 0	B-C	6.25
E-D	0 / 0	E-D	10.00

DESIGN CRITERIA

SPECIFIED LOADS:
TOP CH. LL = 34.8 PSF
DL = 8.0 PSF
BOT CH. LL = 10.5 PSF
DL = 7.3 PSF
TOTAL LOAD = 60.6 PSF

SPACING = 24.0 IN. C/C

THIS TRUSS IS DESIGNED FOR RESIDENTIAL OR SMALL BUILDING REQUIREMENTS OF PART 9, NBCC 2015

THIS DESIGN COMPLIES WITH:
- PART 9 OF BCBC 2018, ABC 2019
- PART 9 OF OBC 2012 (2019 AMENDMENT)
- CSA 086-14
- TPIC 2014

DESIGN ASSUMPTIONS
- OVERHANG NOT TO BE ALTERED OR CUT OFF.

(55 % OF 48.1 P.S.F. G.S.L. PLUS 8.4 P.S.F. RAIN LOAD)
EQUALS 34.8 P.S.F. SPECIFIED ROOF LIVE LOAD

ALLOWABLE DEFL.(LL)= L/360 (0.20")
CALCULATED VERT. DEFL.(LL) = L/999 (0.05")
ALLOWABLE DEFL.(TL)= L/360 (0.20")
CALCULATED VERT. DEFL.(TL) = L/832 (0.09")

CSI: TC=0.77/1.00 (B-C:1) , BC=0.24/1.00 (D-E:3) ,
WB=0.00/1.00 (n/a:0) , SSI=0.30/1.00 (B-C:1)

DOL LUMBER=1.00 NAIL=1.00 LS BEND=1.10 COMP=1.10
SHEAR=1.10 TENS= 1.10

COMPANION LIVE LOAD FACTOR = 1.00

TRUSS PLATE MANUFACTURER IS NOT RESPONSIBLE FOR QUALITY CONTROL IN THE TRUSS MANUFACTURING PLANT .

NAIL VALUES
PLATE GRIP(DRY) SHEAR SECTION
(PSI) (PLI) (PLI)
MAX MIN MAX MIN MAX MIN
MT20 650 371 1747 788 1987 1873

PLATE PLACEMENT TOL. = 0.250 inches

PLATE ROTATION TOL. = 5.0 Deg.

JSI GRIP= 0.40 (B) (INPUT = 0.90)
JSI METAL= 0.33 (B) (INPUT = 1.00)




READ ALL NOTES ON THIS PAGE AND ON ENGINEERING NOTE PAGE ENP-1. THIS NOTE PAGE IS AN INTEGRAL PART OF THIS DRAWING AS IT CONTAINS SPECIFICATIONS AND CRITERIA USED IN THE DESIGN OF THIS COMPONENT.



These plans have been reviewed for use with the corrections as noted. No other changes may be made without written approval of the Building Standards Branch. All work must comply with Zoning By-Law 2018-043, as amended, and the Ontario Building Code, as amended. These approved documents must be kept on site at all times. The building permit must be clearly posted on site at all times.

Discipline	Reviewer	BCIN	Date
Building Code	H. Authier	43236	2021-02-24
Sewage System			
Zoning			





LUMBER			
N. L. G. A. RULES			
CHORDS	SIZE	LUMBER	DESCR.
A - D	2x4	DRY	No.2
A - D	2x4	DRY	No.2
D - F	2x4	DRY	No.2
F - I	2x4	DRY	No.2
Q - B	2x4	DRY	No.2
J - H	2x4	DRY	No.2
Q - M	2x4	DRY	No.2
M - J	2x4	DRY	No.2

ALL WEBS 2x3 DRY
EXCEPT

DRY: SEASONED LUMBER.

PLATES (table is in inches)						
JT	TYPE	PLATES	W	LEN	Y	X
B	TMWV+	MT20	6.0	6.0	2.25	2.25
C	TMWV+	MT20	3.0	4.0	1.50	1.50
D	TTWV+m	MT20	6.0	6.0	Edge	2.50
E	TMW+u	MT20	2.0	4.0		
F	TTWV+m	MT20	6.0	6.0	Edge	2.50
G	TMWV+	MT20	3.0	4.0	1.50	1.50
H	TMWV+	MT20	6.0	6.0	2.25	2.25
J	BMV1+p	MT20	3.0	4.0	2.00	
K	BMWV+	MT20	3.0	8.0	1.50	2.50
L	BMWV+	MT20	3.0	4.0		
M	BMWV+	MT20	3.0	6.0		
N	BMWVWV+	MT20	4.0	6.0	1.50	3.00
O	BMWV+	MT20	3.0	4.0		
P	BMWV+	MT20	3.0	8.0	1.50	2.50
Q	BMV1+p	MT20	3.0	4.0	2.00	0.50

Edge - INDICATES REFERENCE CORNER OF PLATE TOUCHES
EDGE OF CHORD

DIMENSIONS, SUPPORTS AND LOADINGS SPECIFIED BY FABRICATOR TO BE VERIFIED BY BUILDING DESIGNER

BEARINGS			FACTORED GROSS REACTION		MAXIMUM FACTORED GROSS REACTION		INPUT BRG	REQRD BRG
JT	VERT	HORZ	DOWN	HORZ	UPLIFT	IN-SX	IN-SX	
Q	2544	0	2544	0	0	5-8	4-12	
J	2544	0	2544	0	0	5-8	4-12	

UNFACTORED REACTIONS

1ST LCASE		MAX/MIN COMPONENT REACTIONS					
JT	COMBINED	SNOW	LIVE	PERM.LIVE	WIND	DEAD	SOIL
Q	1875	1105 / 0	304 / 0	0 / 0	0 / 0	468 / 0	0 / 0
J	1875	1105 / 0	304 / 0	0 / 0	0 / 0	468 / 0	0 / 0

BEARING MATERIAL TO BE SPF NO.2 OR BETTER AT JOINT(S) Q, J

BRACING

TOP CHORD TO BE SHEATHED OR MAX. PURLIN SPACING = 3.10 FT.
MAX. UNBRACED BOTTOM CHORD LENGTH = 10.00 FT OR RIGID CEILING DIRECTLY APPLIED

ALL PITCH BREAKS AND PERIMETER CORNER JOINTS MUST BE LATERALLY RESTRAINED.

LOADING

TOTAL LOAD CASES: (4)

CHORDS					WEBS				
MAX. FACTORED		FACTORED			MAX. FACTORED				
MEMB.	FORCE	VERT. LOAD	LC1	MAX.	MEMB.	FORCE	MAX		
	(LBS)	(PLF)	CSI	(LBS)		(LBS)	CSI (LC)		
FR-TO		FROM TO		LENGTH	FR-TO				
A-B	0 / 47	-124.4	-124.4	0.17 (1)	10.00	P-C	-448 / 0	0.12 (1)	
-2683		-124.4	-124.4	0.33 (1)	3.95	C-O	-147 / 0	0.08 (1)	
D-E	2622 / 0	-124.4	-124.4	0.33 (1)	3.99	O-D	0 / 348	0.08 (2)	
C-D	-2760 / 0	-124.4	-124.4	0.82 (1)	3.10	D-N	0 / 891	0.20 (1)	
E-F	-2760 / 0	-124.4	-124.4	0.82 (1)	3.10	N-E	-962 / 0	0.75 (1)	
F-G	-2622 / 0	-124.4	-124.4	0.33 (1)	3.99	N-F	0 / 891	0.20 (1)	
G-H	-2683 / 0	-124.4	-124.4	0.33 (1)	3.95	L-F	0 / 348	0.08 (2)	
H-I	0 / 47	-124.4	-124.4	0.17 (1)	10.00	L-G	-147 / 0	0.08 (1)	
Q-B	-2471 / 0	0.0	0.0	0.25 (1)	5.45	O-B	-448 / 0	0.12 (1)	
J-H	-2471 / 0	0.0	0.0	0.25 (1)	5.45	B-P	0 / 2334	0.53 (1)	
						K-H	0 / 2334	0.53 (1)	
Q-P	0 / 0	-39.2	-39.2	0.12 (3)	10.00				
P-O	0 / 2257	-39.2	-39.2	0.50 (1)	10.00				
O-N	0 / 2157	-39.2	-39.2	0.54 (2)	10.00				
N-M	0 / 2157	-39.2	-39.2	0.54 (2)	10.00				
M-L	0 / 2157	-39.2	-39.2	0.54 (2)	10.00				
L-K	0 / 2257	-39.2	-39.2	0.50 (1)	10.00				
K-J	0 / 0	-39.2	-39.2	0.12 (3)	10.00				

DESIGN CRITERIA

SPECIFIED LOADS:

TOP	CH.	LL = 34.8	PSF
		DL = 8.0	PSF
BOT	CH.	LL = 10.5	PSF
		DL = 7.3	PSF
TOTAL LOAD		= 60.6	PSF

SPACING = 24.0 IN. C/C

LOADING IN FLAT SECTION BASED ON A SLOPE OF 2.00/12 MINIMUM

THIS TRUSS IS DESIGNED FOR RESIDENTIAL OR SMALL
BUILDING REQUIREMENTS OF PART 9, NBCC 2015

THIS DESIGN COMPLIES WITH:

- PART 9 OF BCBC 2018 , ABC 2019
- PART 9 OF OBC 2012 (2019 AMENDMENT)
- CSA 086-14
- TPIC 2014

(55 % OF 48.1 P.S.F. G.S.L. PLUS 8.4 P.S.F. RAIN LOAD)
EQUALS 34.8 P.S.F. SPECIFIED ROOF LIVE LOAD

ALLOWABLE DEFL.(LL)= L/360 (0.97")
CALCULATED VERT. DEFL.(LL)= L/999 (0.12")
ALLOWABLE DEFL.(TL)= L/360 (0.97")
CALCULATED VERT. DEFL.(TL)= L/999 (0.21")

CSI: TC=0.82/1.00 (D-E:1) , BC=0.54/1.00 (N-O:2) ,
WB=0.75/1.00 (E-N:1) , SSI=0.39/1.00 (D-E:1)

DOL LUMBER=1.00 NAIL=1.00 LS BEND=1.10 COMP=1.10
SHEAR=1.10 TENS= 1.10

COMPANION LIVE LOAD FACTOR = 1.00

TRUSS PLATE MANUFACTURER IS NOT RESPONSIBLE
FOR QUALITY CONTROL IN THE TRUSS
MANUFACTURING PLANT .

NAIL VALUES	PLATE GRIP(DRY)	SHEAR	SECTION
	(PSI)	(PLI)	(PLI)

	MAX	MIN	MAX	MIN	MAX	MIN
MT20	650	371	1747	788	1987	1873

PLATE PLACEMENT TOL. = 0.250 inches

PLATE ROTATION TOL. = 5.0 Deg.

JSI GRIP= 0.90 (D) (INPUT = 0.90)
JSI METAL= 0.62 (M) (INPUT = 1.00)



**READ ALL NOTES ON THIS PAGE AND ON
ENGINEERING NOTE PAGE ENP-1. THIS
NOTE PAGE IS AN INTEGRAL PART OF
THIS DRAWING AS IT CONTAINS
SPECIFICATIONS AND CRITERIA USED IN
THE DESIGN OF THIS COMPONENT.**




These plans have been reviewed for use with the corrections as noted. No other changes may be made without written approval of the Building Standards Branch. All work must comply with Zoning By-Law 2018-043, as amended, and the Ontario Building Code, as amended. These approved documents must be kept on site at all times. The building permit must be clearly posted on site at all times.

Discipline	Reviewer	BCIN	Date
Building Code	H. Authier	43236	2021-02-24
Sewage System			
Zoning			



Version 8.420 S Oct 9 2020 MiTek Industries, Inc. Sun Dec 20 11:35:35 2020 Page 1
ID:mCCrycxnlfAPc08wPalNt0zHzlx-VTqRvLms9N08xN3Fev2PP4OqicqF1fIKZtszKay7



LUMBER
N. L. G. A. RULES

CHORDS	SIZE	LUMBER	DESCR.
A - D	2x4	DRY No.2	SPF
E - F	2x4	DRY No.2	SPF
G - H	2x4	DRY No.2	SPF
I - J	2x4	DRY No.2	SPF
K - L	2x4	DRY No.2	SPF
M - N	2x4	DRY No.2	SPF
O - P	2x4	DRY No.2	SPF
Q - R	2x4	DRY No.2	SPF
S - T	2x4	DRY No.2	SPF
U - V	2x4	DRY No.2	SPF
W - X	2x4	DRY No.2	SPF
Y - Z	2x4	DRY No.2	SPF

ALL WEBS 2x3 DRY No.2
EXCEPT

DRY: SEASONED LUMBER.

PLATES (table is in inches)

JT	TYPE	PLATES	W	LEN	Y	X
B	TMVW+p	MT20	6.0	4.0	2.25	2.25
C	TMVW-t	MT20	3.0	4.0	1.50	1.50
D	TTWW+m	MT20	5.0	6.0	Edge	1.75
E	TMVW+w	MT20	2.0	4.0		
F	TTWW+m	MT20	5.0	6.0	Edge	1.75
G	TMVW-t	MT20	3.0	4.0	1.50	1.50
H	TMVW+p	MT20	6.0	4.0	2.25	2.25
J	BMV1+p	MT20	3.0	4.0	2.00	
K	BMVW-t	MT20	4.0	6.0	1.75	1.75
L	BMVW-t	MT20	3.0	4.0		
M	BS-t	MT20	3.0	6.0		
N	BMVW-w	MT20	3.0	8.0		
O	BMVW-t	MT20	3.0	4.0		
P	BMVW-t	MT20	4.0	6.0	1.75	1.75
Q	BMV1+p	MT20	3.0	4.0	2.00	0.50

Edge - INDICATES REFERENCE CORNER OF PLATE TOUCHES
EDGE OF CHORD.

DIMENSIONS, SUPPORTS AND LOADINGS SPECIFIED BY FABRICATOR TO BE VERIFIED BY BUILDING DESIGNER

BEARINGS

FACTORED GROSS REACTION	MAXIMUM FACTORED GROSS REACTION	INPUT BRG	REQRD BRG
JT VERT	DOWN	UPLIFT	IN-SX
Q 2544	0	0	5-8
J 2544	0	0	5-8

UNFACTORED REACTIONS

1ST LCASE	MAX	MIN	COMPONENT REACTIONS
JT COMBINED	SNOW	LIVE	PERM.LIVE WIND DEAD SOIL
Q 1875	1105 / 0	304 / 0	0 / 0 0 / 0 486 / 0 0 / 0
J 1875	1105 / 0	305 / 0	0 / 0 0 / 0 486 / 0 0 / 0

BEARING MATERIAL TO BE SPF NO.2 OR BETTER AT JOINT(S) Q, J

BRACING
TOP CHORD TO BE SHEATHED OR MAX. PURLIN SPACING = 3.69 FT.
MAX. UNBRACED BOTTOM CHORD LENGTH = 10.00 FT OR RIGID CEILING DIRECTLY APPLIED.
ALL PITCH BREAKS AND PERIMETER CORNER JOINTS MUST BE LATERALLY RESTRAINED.

LOADING
TOTAL LOAD CASES: (4)

CHORDS				WEBS			
MEMB.	MAX. FACTORED FORCE (LBS)	FACTORED VERT. LOAD (PLF)	LC1 MAX CSI (LC)	MEMB.	MAX. FACTORED FORCE (LBS)	MAX. FACTORED FORCE (LBS)	MAX. FACTORED FORCE (LBS)
FR-TO		FROM	TO	LENGTH	FR-TO		
A-B	0 / 47	-124.4	-124.4	0.17 (1)	10.00	P-C	-275 / 75
B-C	-2757 / 0	-124.4	-124.4	0.52 (1)	3.69	C-D	-429 / 0
C-D	-2457 / 0	-124.4	-124.4	0.49 (1)	3.91	O-D	0 / 472
D-E	-2257 / 0	-124.4	-124.4	0.37 (1)	4.19	D-N	0 / 488
E-F	-2257 / 0	-124.4	-124.4	0.37 (1)	4.19	N-E	-878 / 0
F-G	-2457 / 0	-124.4	-124.4	0.49 (1)	3.91	N-F	0 / 488
G-H	-2757 / 0	-124.4	-124.4	0.52 (1)	3.69	L-F	0 / 472
H-I	0 / 47	-124.4	-124.4	0.17 (1)	10.00	L-G	-429 / 0
Q-B	-2480 / 0	0.0	0.0	0.25 (1)	5.46	K-G	-275 / 75
J-H	-2480 / 0	0.0	0.0	0.25 (1)	5.46	B-P	0 / 2378
						K-H	0 / 2378
Q-P	0 / 0	-39.2	-39.2	0.19 (3)	10.00		
P-O	0 / 2327	-39.2	-39.2	0.49 (1)	10.00		
O-N	0 / 2013	-39.2	-39.2	0.42 (1)	10.00		
N-M	0 / 2013	-39.2	-39.2	0.42 (1)	10.00		
M-L	0 / 2013	-39.2	-39.2	0.42 (1)	10.00		
L-K	0 / 2327	-39.2	-39.2	0.49 (1)	10.00		
K-J	0 / 0	-39.2	-39.2	0.19 (3)	10.00		

DESIGN CRITERIA

SPECIFIED LOADS:

TOP CH.	LL = 34.8	PSF
	DL = 8.0	PSF
BOT CH.	LL = 10.5	PSF
	DL = 7.3	PSF
TOTAL LOAD	= 60.6	PSF

SPACING = 24.0 IN. C/C

LOADING IN FLAT SECTION BASED ON A SLOPE OF 2.00/12 MINIMUM

THIS TRUSS IS DESIGNED FOR RESIDENTIAL OR SMALL BUILDING REQUIREMENTS OF PART 9, NBCC 2015

THIS DESIGN COMPLIES WITH:
- PART 9 OF BCBC 2018, ABC 2019
- PART 9 OF OBC 2012 (2019 AMENDMENT)
- CSA 086-14
- TPIC 2014

(55 % OF 48.1 P.S.F. G.S.L. PLUS 8.4 P.S.F. RAIN LOAD)
EQUALS 34.8 P.S.F. SPECIFIED ROOF LIVE LOAD

ALLOWABLE DEFL.(LL) = L/360 (0.97")
CALCULATED VERT. DEFL.(LL) = L/999 (0.10")
ALLOWABLE DEFL.(TL) = L/360 (0.97")
CALCULATED VERT. DEFL.(TL) = L/999 (0.16")

CSI: TC=0.52/1.00 (B-C-1), BC=0.49/1.00 (O-P-1),
WB=0.84/1.00 (E-N-1), SSI=0.27/1.00 (D-E-1)

DOL LUMBER=1.00 NAIL=1.00 LS BEND=1.10 COMP=1.10
SHEAR=1.10 TENS= 1.10

COMPANION LIVE LOAD FACTOR = 1.00

TRUSS PLATE MANUFACTURER IS NOT RESPONSIBLE FOR QUALITY CONTROL IN THE TRUSS MANUFACTURING PLANT.

NAIL VALUES
PLATE GRIP(DRY) SHEAR SECTION (PSI) (PLI) (PLI)
MAX MIN MAX MIN MAX MIN
MT20 650 371 1747 788 1987 1873

PLATE PLACEMENT TOL. = 0.250 inches

PLATE ROTATION TOL. = 5.0 Deg.

JSI GRIP= 0.90 (H) (INPUT = 0.90)
JSI METAL = 0.62 (M) (INPUT = 1.00)




READ ALL NOTES ON THIS PAGE AND ON ENGINEERING NOTE PAGE ENP-1. THIS NOTE PAGE IS AN INTEGRAL PART OF THIS DRAWING AS IT CONTAINS SPECIFICATIONS AND CRITERIA USED IN THE DESIGN OF THIS COMPONENT.



These plans have been reviewed for use with the corrections as noted. No other changes may be made without written approval of the Building Standards Branch. All work must comply with Zoning By-Law 2018-043, as amended, and the Ontario Building Code, as amended. These approved documents must be kept on site at all times. The building permit must be clearly posted on site at all times.

Discipline	Reviewer	BCIN	Date
Building Code	H. Authier	43236	2021-02-24
Sewage System			
Zoning			





TOTAL WEIGHT = 130 lb

LUMBER				
N. L. G. A. RULES				
CHORDS	SIZE		LUMBER	DESCR.
A - C	2x4	DRY	No.2	SFF
C - E	2x4	DRY	No.2	SFF
E - F	2x4	DRY	No.2	SFF
F - H	2x4	DRY	No.2	SFF
H - J	2x4	DRY	No.2	SFF
Q - B	2x4	DRY	No.2	SFF
B - I	2x4	DRY	No.2	SFF
Q - N	2x4	DRY	No.2	SFF
N - K	2x4	DRY	No.2	SFF

ALL WEBS 2x3 DRY
EXCEPT

DRY: SEASONED LUMBER.

PLATES (table is in inches)					
JT	TYPE	PLATES	W	LEN	Y X
B	TMWV-p	MT20	6.0	6.0	2.25 2.50
C	TS-t		3.0	6.0	
D	TMWV-t	MT20	3.0	4.0	1.50 1.50
E	TTWV-m	MT20	4.0	6.0	1.75 2.50
F	TTW-m	MT20	4.0	4.0	2.00 1.75
G	TMWV-t	MT20	3.0	4.0	1.50 1.50
H	SA	MT20	3.0	6.0	
I	TMWV-p	MT20	6.0	2.25	2.50
K	BMV1-p	MT20	3.0	4.0	2.00
L	BMWV-t	MT20	4.0	5.0	1.50 1.50
M	BMWVW-t	MT20	4.0	6.0	
N	BS-t	MT20	3.0	6.0	
O	BMWVW+t	MT20	3.0	4.0	1.75 1.50
P	BMWV-t	MT20	4.0	5.0	1.50 1.50
Q	BMV1+p	MT20	3.0	4.0	2.00 1.50

DIMENSIONS, SUPPORTS AND LOADINGS SPECIFIED BY FABRICATOR TO BE VERIFIED BY BUILDING DESIGNER

BEARINGS

	FACTORED GROSS REACTION		MAXIMUM FACTORED GROSS REACTION		INPUT BRG	REQRD BRG
	VERT	HORZ	DOWN	HORZ	UPLIFT	IN-SX
JT						
Q	2544	0	2544	0	0	5-8
K	2544	0	2544	0	0	5-8

UNFACTORED REACTIONS

1ST LCASE		MAX/MIN. COMPONENT REACTIONS					
JT	COMBINED	SNOW	LIVE	PERM. LIVE	WIND	DEAD	SOIL
Q	1875	1105 / 0	304 / 0	0 / 0	0 / 0	468 / 0	0 / 0
K	1875	1105 / 0	305 / 0	0 / 0	0 / 0	468 / 0	0 / 0

BEARING MATERIAL TO BE SPF NO.2 OR BETTER AT JOINT(S) Q, K

BRACING

TOP CHORD TO BE SHEATHED OR MAX. PURLIN SPACING = 3.33 FT.

MAX. UNBRACED BOTTOM CHORD LENGTH = 10.00 FT OR RIGID CEILING DIRECTLY APPLIED.

ALL PITCH BREAKS AND PERIMETER CORNER JOINTS MUST BE Laterally RESTRAINED.

LOADING

TOTAL LOAD CASES: (4)

CHORDS					WEBS				
MEMB.	MAX. FACTORED (LBS)	FACTORED VERT. LOAD (PLF)	LC1 MAX CSI (LC)	MAX. UNBRAC	MEMB.	MAX. FACTORED (LBS)	FORCE MAX CSI (LC)		
FR-TO		FROM TO		LENGTH	FR-TO				
A-B	0 / 47	-124.4 -124.4	0.17 (1)	10.00	P-D	-147 / 170	0.07 (1)		
C-D	-2778 / 0	-124.4 -124.4	0.77 (1)	3.33	D-O	-877 / 0	0.88 (1)		
C-D	-2778 / 0	-124.4 -124.4	0.77 (1)	3.33	O-E	0 / 842	0.14 (1)		
D-E	-2268 / 0	-124.4 -124.4	0.68 (1)	3.75	E-M	0 / 7	0.00 (1)		
E-F	-1847 / 0	-124.4 -124.4	0.44 (1)	4.44	M-F	0 / 844	0.15 (1)		
F-G	-2864 / 0	-124.4 -124.4	0.88 (1)	3.75	M-G	-875 / 0	0.87 (1)		
G-H	-2777 / 0	-124.4 -124.4	0.77 (1)	3.33	L-G	-150 / 168	0.07 (1)		
H-I	-2777 / 0	-124.4 -124.4	0.77 (1)	3.33	B-F	0 / 2389	0.54 (1)		
I-J	0 / 47	-124.4 -124.4	0.17 (1)	10.00	L-I	0 / 2388	0.54 (1)		
Q-B	-2447 / 0	0.0 0.0	0.25 (1)	5.47					
K-I	-2446 / 0	0.0 0.0	0.25 (1)	5.48					
Q-P	0 / 0	-39.2 -39.2	0.29 (3)	10.00					
P-O	0 / 2352	-39.2 -39.2	0.57 (2)	10.00					
N-M	0 / 1846	-39.2 -39.2	0.42 (1)	10.00					
O-N	0 / 1846	-39.2 -39.2	0.43 (1)	10.00					
M-L	0 / 2352	-39.2 -39.2	0.57 (2)	10.00					
L-K	0 / 0	-39.2 -39.2	0.28 (3)	10.00					

DESIGN CRITERIA

SPECIFIED LOADS:

TOP	CH.	LL	= 34.8	PSF
		DL	= 8.0	PSF
BOT	CH.	LL	= 10.5	PSF
		DL	= 7.3	PSF
TOTAL		LOAD	= 60.6	PSF

SPACING = 24.0 IN. C/C

LOADING IN FLAT SECTION BASED ON A SLOPE OF 2.00/12 MINIMUM

THIS TRUSS IS DESIGNED FOR RESIDENTIAL OR SMALL BUILDING REQUIREMENTS OF PART 9, NBCC 2015

THIS DESIGN COMPLIES WITH:

- PART 9 OF BCBC 2018 , ABC 2019
- PART 9 OF OBC 2012 (2019 AMENDMENT)
- CSA 088-14
- TPIC 2014

(55 % OF 48.1 P.S.F. G.S.L. PLUS 8.4 P.S.F. RAIN LOAD)
EQUALS 34.8 P.S.F. SPECIFIED ROOF LIVE LOAD

ALLOWABLE DEFL.(LL)= L/360 (0.97")
CALCULATED VERT. DEFL.(LL) = L/ 999 (0.10")
ALLOWABLE DEFL.(TL)= L/360 (0.97")
CALCULATED VERT. DEFL.(TL) = L/ 999 (0.18")

CSI: TC=0.77/1.00 (B-D:1), BC=0.57/1.00 (O-P:2),
WB=0.88/1.00 (D-O:1), SSI=0.30/1.00 (B-D:1)

DOL LUMBER=1.00 NAIL=1.00 LS BEND=1.10 COMP=1.10
SHEAR=1.10 TENS= 1.10

COMPANION LIVE LOAD FACTOR = 1.00

TRUSS PLATE MANUFACTURER IS NOT RESPONSIBLE
FOR QUALITY CONTROL IN THE TRUSS
MANUFACTURING PLANT .

NAIL VALUES

	GRIP(DRY)		SHEAR		SECTION	
	(PSI)		(PLI)		(PLI)	
	MAX	MIN	MAX	MIN	MAX	MIN
MT20	650	371	1747	788	1987	1873

PLATE PLACEMENT TOL. = 0.250 inches

PLATE ROTATION TOL. = 5.0 Deg.

JSI GRIP= 0.89 (Q) (INPUT = 0.90)
JSI METAL= 0.67 (P) (INPUT = 1.00)




**READ ALL NOTES ON THIS PAGE AND ON
ENGINEERING NOTE PAGE ENP-1. THIS
NOTE PAGE IS AN INTEGRAL PART OF
THIS DRAWING AS IT CONTAINS
SPECIFICATIONS AND CRITERIA USED IN
THE DESIGN OF THIS COMPONENT.**



These plans have been reviewed for use with the corrections as noted. No other changes may be made without written approval of the Building Standards Branch. All work must comply with Zoning By-Law 2018-043, as amended, and the Ontario Building Code, as amended. These approved documents must be kept on site at all times. The building permit must be clearly posted on site at all times.

Discipline	Reviewer	BCIN	Date
Building Code	H. Authier	43236	2021-02-24
Sewage System			
Zoning			





LUMBER
N. L. G. A. RULES

CHORDS	SIZE	LUMBER	DESCR.
A - C	2x4	DRY	2100F 1.8E
C - E	2x4	DRY	2100F 1.8E
E - F	2x4	DRY	No.2
F - H	2x4	DRY	2100F 1.8E
H - J	2x4	DRY	2100F 1.8E
P - B	2x4	DRY	No.2
K - I	2x4	DRY	No.2
P - M	2x4	DRY	No.2
M - K	2x4	DRY	No.2
ALL WEBS EXCEPT	2x4	DRY	No.2
O - D	2x3	DRY	No.2
L - G	2x3	DRY	No.2
B - O	2x3	DRY	No.2
L - I	2x3	DRY	No.2

DRY: SEASONED LUMBER.

PLATES (table is in inches)

JT TYPE	PLATES	W	LEN	Y	X
B	TMVW-p	MT20	6.0	6.0	2.25 2.50
C	TS-t	MT20	3.0	6.0	
D	TMW+w	MT20	2.0	4.0	
E	TTWW+m	MT20	5.0	5.0	1.75 2.25
F	TTWW+m	MT20	5.0	5.0	1.75 2.25
G	TMW+w	MT20	2.0	4.0	
H	TS-t	MT20	3.0	6.0	
I	TMVW-p	MT20	6.0	6.0	2.25 2.50
K	BMV1+p	MT20	3.0	4.0	2.00
L	BMWWW-t	MT20	4.0	8.0	1.50 2.00
M	BS-t	MT20	3.0	6.0	
N	BMWW-t	MT20	3.0	4.0	
O	BMWWW-t	MT20	4.0	8.0	1.50 3.50
P	BMV1+p	MT20	3.0	4.0	2.00 0.50

DIMENSIONS, SUPPORTS AND LOADINGS SPECIFIED BY FABRICATOR TO BE VERIFIED BY BUILDING DESIGNER

BEARINGS

	FACTORED GROSS REACTION	MAXIMUM FACTORED GROSS REACTION	INPUT BRG	REQRD BRG
JT VERT	2544	0	5-8	4-12
P K	2544	0	5-8	4-12

UNFACTORED REACTIONS

1ST LCASE	MAX	MIN	COMPONENT REACTIONS
JT COMBINED	1105	0	PERM. LIVE WIND DEAD SOIL
P K	1105	0	0/0 486/0 0/0

BEARING MATERIAL TO BE SPF NO.2 OR BETTER AT JOINT(S) P, K

BRACING
TOP CHORD TO BE SHEATHED OR MAX. PURLIN SPACING = 4.28 FT.
MAX. UNBRACED BOTTOM CHORD LENGTH = 10.00 FT OR RIGID CEILING DIRECTLY APPLIED.

ALL PITCH BREAKS AND PERIMETER CORNER JOINTS MUST BE Laterally RESTRAINED.

LOADING
TOTAL LOAD CASES: (4)

CHORDS				WEBS			
MEMB.	MAX. FACTORED FORCE (LBS)	FACTORED VERT. LOAD (PLF)	LC1 MAX CSI (LC)	MEMB.	MAX. FACTORED FORCE (LBS)	MAX. FACTORED CSI (LC)	UNBRACED LENGTH
FR-TO				FR-TO			
A-B	0 / 47	-124.4	-124.4 0.11 (1)	10.00	O-D	-1064 / 0	0.63 (1)
B-C	-2777 / 0	-124.4	-124.4 0.63 (1)	4.33	O-E	0 / 1228	0.20 (1)
C-D	-2777 / 0	-124.4	-124.4 0.63 (1)	4.33	E-N	0 / 171	0.03 (3)
D-E	-2858 / 0	-124.4	-124.4 0.63 (1)	4.28	N-F	0 / 180	0.03 (3)
E-F	-1865 / 0	-124.4	-124.4 0.04 (1)	5.13	F-L	0 / 1218	0.20 (1)
F-G	-2858 / 0	-124.4	-124.4 0.63 (1)	4.28	L-G	-1064 / 0	0.63 (1)
G-H	-2775 / 0	-124.4	-124.4 0.63 (1)	4.33	B-O	0 / 2385	0.54 (1)
H-I	-2775 / 0	-124.4	-124.4 0.63 (1)	4.33	L-I	0 / 2383	0.54 (1)
I-J	0 / 47	-124.4	-124.4 0.11 (1)	10.00			
P-B	-2430 / 0	0.0	0.0 0.25 (1)	5.49			
K-I	-2429 / 0	0.0	0.0 0.25 (1)	5.49			
P-O	0 / 0	-39.2	-39.2 0.41 (3)	10.00			
O-N	0 / 1856	-39.2	-39.2 0.58 (2)	10.00			
N-M	0 / 1860	-39.2	-39.2 0.57 (2)	10.00			
M-L	0 / 1860	-39.2	-39.2 0.57 (2)	10.00			
L-K	0 / 0	-39.2	-39.2 0.39 (3)	10.00			

DESIGN CRITERIA

SPECIFIED LOADS:

TOP CH.	LL = 34.8	PSF
	DL = 8.0	PSF
BOT CH.	LL = 10.5	PSF
	DL = 7.3	PSF
TOTAL LOAD	= 60.6	PSF

SPACING = 24.0 IN. C/C

LOADING IN FLAT SECTION BASED ON A SLOPE OF 2.00/12 MINIMUM

THIS TRUSS IS DESIGNED FOR RESIDENTIAL OR SMALL BUILDING REQUIREMENTS OF PART 9, NBCC 2015

THIS DESIGN COMPLIES WITH:
- PART 9 OF BCBC 2018 , ABC 2019
- PART 9 OF OBC 2012 (2019 AMENDMENT)
- CSA 086-14
- TPIC 2014

(55 % OF 48.1 P.S.F. G.S.L. PLUS 8.4 P.S.F. RAIN LOAD)
EQUALS 34.8 P.S.F. SPECIFIED ROOF LIVE LOAD

ALLOWABLE DEFL.(LL)= L/360 (0.97")
CALCULATED VERT. DEFL.(LL) = L/999 (0.12")
ALLOWABLE DEFL.(TL)= L/360 (0.97")
CALCULATED VERT. DEFL.(TL) = L/999 (0.21")

CSI: TC=0.63/1.00 (D-E-1) , BC=0.58/1.00 (N-O-2) ,
WB=0.63/1.00 (G-L-1) , SSI=0.35/1.00 (G-I-1)

DOL LUMBER=1.00 NAIL=1.00 LS BEND=1.10 COMP=1.10
SHEAR=1.10 TENS= 1.10

COMPANION LIVE LOAD FACTOR = 1.00

TRUSS PLATE MANUFACTURER IS NOT RESPONSIBLE FOR QUALITY CONTROL IN THE TRUSS MANUFACTURING PLANT .

NAIL VALUES

PLATE GRIP(DRY)	SHEAR	SECTION (PSI)	(PLI)	(PLI)
MAX MIN	MAX MIN	MAX MIN	MAX MIN	MAX MIN
MT20	850	371	1747	788 1987 1873

PLATE PLACEMENT TOL. = 0.250 inches

PLATE ROTATION TOL. = 5.0 Deg.

JSI GRIP= 0.90 (F) (INPUT = 0.90)
JSI METAL = 0.55 (M) (INPUT = 1.00)



READ ALL NOTES ON THIS PAGE AND ON ENGINEERING NOTE PAGE ENP-1. THIS NOTE PAGE IS AN INTEGRAL PART OF THIS DRAWING AS IT CONTAINS SPECIFICATIONS AND CRITERIA USED IN THE DESIGN OF THIS COMPONENT.




These plans have been reviewed for use with the corrections as noted. No other changes may be made without written approval of the Building Standards Branch. All work must comply with Zoning By-Law 2018-043, as amended, and the Ontario Building Code, as amended. These approved documents must be kept on site at all times. The building permit must be clearly posted on site at all times.

Discipline	Reviewer	BCIN	Date
Building Code	H. Authier	43236	2021-02-24
Sewage System			
Zoning			



Version 8.420 S Oct 9 2020 MTEK Industries, Inc. Sun Dec 20 11:35:37 2020 Page 1
ID:mCCrvcxnlfAPc08wPaINt0zHzlx-SsyBK1o6h?GsAqDeIN4tUVUfdQQNVkv00BL4PTy7



TOTAL WEIGHT = 5 X 32 = 162 lb

LUMBER
N. L. G. A. RULES

CHORDS	SIZE	LUMBER	DESCR.
A - E	2x4	DRY	No.2
F - E	2x4	DRY	No.2
B - F	2x4	DRY	No.2

ALL WEBS 2x3 DRY No.2
SPF

DRY: SEASONED LUMBER.

PLATES (table is in inches)

JT	TYPE	PLATES	W	LEN	Y	X
B	TMW1-t	MT20	3.0	4.0		
C	TMW1-w	MT20	2.0	4.0		
D	TMW1-t	MT20	3.0	4.0		
E	TMV1-p	MT20	2.0	4.0		
F	BMV1-t	MT20	3.0	4.0		
G	BMW1-t	MT20	3.0	4.0		

DIMENSIONS, SUPPORTS AND LOADINGS SPECIFIED BY FABRICATOR TO BE VERIFIED BY BUILDING DESIGNER

BEARINGS

	FACTORED GROSS REACTION	MAXIMUM FACTORED GROSS REACTION	INPUT BRG	REQRD BRG
JT	VERT	HORZ	DOWN	HORZ
B	569	0	569	0
G	1084	0	1084	0

PROVIDE ANCHORAGE AT BEARING JOINT B FOR 150 LBS. FACTORED UPLIFT

UNFACTORED REACTIONS

JT	COMBINED	SNOW	LIVE	PERM. LIVE	WIND	DEAD	SOIL
B	413	264 / -46	52 / -14	0 / 0	0 / 0	97 / 0	0 / 0
G	803	461 / 0	139 / 0	0 / 0	0 / 0	203 / 0	0 / 0

BEARING MATERIAL TO BE SPF NO.2 OR BETTER AT JOINT(S) B, G

BRACING
TOP CHORD TO BE SHEATHED OR MAX. PURLIN SPACING = 6.25 FT.
MAX. UNBRACED BOTTOM CHORD LENGTH = 6.25 FT. OR RIGID CEILING DIRECTLY APPLIED.

ALL PITCH BREAKS AND PERIMETER CORNER JOINTS MUST BE Laterally RESTRAINED.

LOADING
TOTAL LOAD CASES: (5)

CHORDS				WEBS			
MEMB.	MAX. FORCE (LBS)	FACTORED VERT. LOAD (PLF)	MAX. CSI (LC)	MEMB.	MAX. FORCE (LBS)	FACTORED MAX. CSI (LC)	
FR-TO				FR-TO			
A-B	0 / 25	-124.4 -124.4	0.16 (1)	10.00	C-G	-834 / 0	0.13 (1)
B-I	-466 / 201	-124.4 -124.4	0.18 (3)	6.25	G-D	-595 / 0	0.09 (1)
I-C	-368 / 222	-124.4 -124.4	0.20 (1)	6.25	D-F	0 / 317	0.07 (5)
C-D	0 / 275	-124.4 -124.4	0.21 (1)	10.00	H-I	0 / 227	0.00 (1)
D-E	-11 / 0	-124.4 -124.4	0.14 (1)	6.25			
F-E	-152 / 0	0.0	0.03 (5)	7.81			
B-H	-206 / 375	-39.2 -39.2	0.10 (3)	6.25			
H-G	-206 / 375	-39.2 -39.2	0.25 (2)	6.25			
G-F	-255 / 0	-39.2 -39.2	0.21 (2)	6.25			

CANTILEVER ANALYSIS HAS BEEN CONSIDERED IN THIS DESIGN

DESIGN CRITERIA

SPECIFIED LOADS:
TOP CH. LL = 34.8 PSF
DL = 8.0 PSF
BOT CH. LL = 10.5 PSF
DL = 7.3 PSF
TOTAL LOAD = 60.6 PSF

SPACING = 24.0 IN. C/C

THIS TRUSS IS DESIGNED FOR RESIDENTIAL OR SMALL BUILDING REQUIREMENTS OF PART 9, NBCC 2015

THIS DESIGN COMPLIES WITH:
- PART 9 OF BCBC 2018, ABC 2019
- PART 9 OF OBC 2012 (2019 AMENDMENT)
- CSA 086-14
- TPIC 2014

(55 % OF 48.1 P.S.F. G.S.L. PLUS 8.4 P.S.F. RAIN LOAD)
EQUALS 34.8 P.S.F. SPECIFIED ROOF LIVE LOAD

ALLOWABLE DEFL.(LL)= L/360 (0.21")
CALCULATED VERT. DEFL.(LL) = L/999 (0.04")
ALLOWABLE DEFL.(TL)= L/360 (0.21")
CALCULATED VERT. DEFL.(TL) = L/999 (0.06")

CANTILEVER DEFLECTION:
ALLOWABLE DEFL.(LL)= L/120 (0.29")
CALCULATED VERT. DEFL.(LL) = L/999 (0.01")
ALLOWABLE DEFL.(TL)= L/120 (0.29")
CALCULATED VERT. DEFL.(TL) = L/999 (0.01")

CSI: TC=0.21/1.00 (C-D-1), BC=0.25/1.00 (G-H-2),
WB=0.13/1.00 (C-G-1), SSI=0.19/1.00 (C-I-1)

DOL LUMBER=1.00 NAIL=1.00 LS BEND=1.10 COMP=1.10
SHEAR=1.10 TENS=1.10

COMPANION LIVE LOAD FACTOR = 1.00

TRUSS PLATE MANUFACTURER IS NOT RESPONSIBLE FOR QUALITY CONTROL IN THE TRUSS MANUFACTURING PLANT.

NAIL VALUES

PLATE	GRIP(DRY)	SHEAR (PSI)	SECTION (PLI)
MT20	650	371	1747 788 1987 1873

PLATE PLACEMENT TOL. = 0.250 inches

PLATE ROTATION TOL. = 5.0 Deg.

JSI GRIP= 0.85 (G) (INPUT = 0.90)
JSI METAL = 0.32 (C) (INPUT = 1.00)



READ ALL NOTES ON THIS PAGE AND ON ENGINEERING NOTE PAGE ENP-1. THIS NOTE PAGE IS AN INTEGRAL PART OF THIS DRAWING AS IT CONTAINS SPECIFICATIONS AND CRITERIA USED IN THE DESIGN OF THIS COMPONENT.




These plans have been reviewed for use with the corrections as noted. No other changes may be made without written approval of the Building Standards Branch. All work must comply with Zoning By-Law 2018-043, as amended, and the Ontario Building Code, as amended. These approved documents must be kept on site at all times. The building permit must be clearly posted on site at all times.

Discipline	Reviewer	BCIN	Date
Building Code	H. Authier	43236	2021-02-24
Sewage System			
Zoning			



Version 8.420 S Oct 9 2020 MTEK Industries, Inc. Sun Dec 20 11:35:38 2020 Page 1



TOTAL WEIGHT = 71 lb

LUMBER				DESCR.
N. L. G. A. RULES	CHORDS	SIZE	LUMBER	
A - D	2x4	DRY	No.2	SPF
D - G	2x4	DRY	No.2	SPF
L - B	2x4	DRY	No.2	SPF
H - F	2x4	DRY	No.2	SPF
L - J	2x4	DRY	No.2	SPF
J - H	2x4	DRY	No.2	SPF
ALL WEBS 2x3 DRY No.2				SPF
EXCEPT				
ALL GABLE WEBS 2x3 DRY No.2				SPF
DRY: SEASONED LUMBER.				
GABLE STUDS SPACED AT 2'-0" OC.				

PLATES (table is in inches)					
JT	TYPE	PLATES	W	LEN	Y X
B	TMVW+p	MT20	5.0	6.0	2.00 2.50
C	TMVW-t	MT20	3.0	5.0	1.50 1.50
D	TTW+p	MT20	3.0	6.0	
E	TMVW-t	MT20	3.0	5.0	1.50 1.50
F	TMVW+p	MT20	5.0	6.0	2.00 2.50
H	BMV1+p	MT20	2.0	4.0	0.25 1.25
I	BMVW-t	MT20	4.0	4.0	1.75 1.50
J	BBVW-p	MT20	6.0	6.0	
K	BMVW-t	MT20	4.0	4.0	1.75 1.50
L	BMV1+p	MT20	2.0	4.0	0.25 1.25
M, N, O, P					
M	NP+w	MT20	2.0	4.0	

DIMENSIONS, SUPPORTS AND LOADINGS SPECIFIED BY FABRICATOR TO BE VERIFIED BY BUILDING DESIGNER

BEARINGS					
	FACTORED GROSS REACTION	MAXIMUM FACTORED GROSS REACTION	INPUT BRG	REQRD BRG	
JT	VERT	HORZ	DOWN	HORZ	UPLIFT IN-SX
L	1239	0	1239	0	5-8
H	1239	0	1239	0	5-8

UNFACTORED REACTIONS					
1ST LCASE	MAX/MIN COMPONENT REACTIONS				
JT	COMBINED	SNOW	LIVE	PERM.LIVE	WIND
L	908	551 / 0	136 / 0	0 / 0	0 / 0
H	908	551 / 0	137 / 0	0 / 0	0 / 0

BEARING MATERIAL TO BE SPF NO.2 OR BETTER AT JOINT(S) L, H

BRACING
TOP CHORD TO BE SHEATHED OR MAX. PURLIN SPACING = 4.82 FT.
MAX. UNBRACED BOTTOM CHORD LENGTH = 10.00 FT OR RIGID CEILING DIRECTLY APPLIED.

ALL PITCH BREAKS AND PERIMETER CORNER JOINTS MUST BE Laterally RESTRAINED.

LOADING					
TOTAL LOAD CASES: (4)					
CHORDS			WEBS		
MEMB.	MAX. FACTORED FORCE (LBS)	FACTORED VERT. LOAD (PLF)	LC1 MAX	MEMB.	MAX. FACTORED FORCE (LBS)
FR-TO		FROM TO	LENGTH	FR-TO	
A-B	0 / 70	-124.4 -124.4	0.18 (1)	J-D	0 / 1643
B-C	-1785 / 0	-124.4 -124.4	0.21 (1)	J-E	-329 / 0
C-D	-1320 / 0	-124.4 -124.4	0.28 (1)	I-E	-139 / 75
D-E	-1320 / 0	-124.4 -124.4	0.28 (1)	C-J	-329 / 0
E-F	-1785 / 0	-124.4 -124.4	0.21 (1)	K-C	-139 / 75
F-G	0 / 70	-124.4 -124.4	0.18 (1)	B-K	0 / 1228
L-B	-1198 / 0	0.0	0.0 0.12 (1)	I-F	0 / 1226
H-F	-1198 / 0	0.0	0.0 0.12 (1)		
L-K	0 / 14	-39.2	-39.2 0.09 (3)		
K-J	0 / 1364	-39.3	-39.3 0.30 (1)		
J-I	0 / 1364	-39.3	-39.3 0.30 (1)		
I-H	0 / 14	-39.2	-39.2 0.09 (3)		

DESIGN CRITERIA

SPECIFIED LOADS:
TOP CH. LL = 34.8 PSF
DL = 8.0 PSF
BOT CH. LL = 10.5 PSF
DL = 7.3 PSF
TOTAL LOAD = 60.6 PSF

SPACING = 24.0 IN. C/C

THIS TRUSS IS DESIGNED FOR RESIDENTIAL OR SMALL BUILDING REQUIREMENTS OF PART 9, NBCC 2015

THIS DESIGN COMPLIES WITH:
- PART 9 OF BCBC 2018 , ABC 2019
- PART 9 OF OBC 2012 (2019 AMENDMENT)
- CSA 086-14
- TPIC 2014

(55 % OF 48.1 P.S.F. G.S.L. PLUS 8.4 P.S.F. RAIN LOAD)
EQUALS 34.8 P.S.F. SPECIFIED ROOF LIVE LOAD

ALLOWABLE DEFL.(LL)= L/360 (0.43")
CALCULATED VERT. DEFL.(LL)= L/999 (0.06")
ALLOWABLE DEFL.(TL)= L/360 (0.43")
CALCULATED VERT. DEFL.(TL)= L/999 (0.10")

CSI: TC=0.28/1.00 (C-D-1) , BC=0.30/1.00 (J-K-1) ,
WB=0.37/1.00 (D-J-1) , SSI=0.14/1.00 (C-D-1)

DOL LUMBER=1.00 NAIL=1.00 LS BEND=1.10 COMP=1.10
SHEAR=1.10 TENS=1.10

COMPANION LIVE LOAD FACTOR = 1.00

TRUSS PLATE MANUFACTURER IS NOT RESPONSIBLE FOR QUALITY CONTROL IN THE TRUSS MANUFACTURING PLANT .

NAIL VALUES
PLATE GRIP(DRY) SHEAR SECTION
(PSI) (PLI) (PLI)
MAX MIN MAX MIN MAX MIN
MT20 650 371 1747 788 1987 1873

PLATE PLACEMENT TOL. = 0.250 inches

PLATE ROTATION TOL. = 5.0 Deg.

JSI GRIP= 0.89 (D) (INPUT = 0.90)
JSI METAL = 0.83 (L) (INPUT = 1.00)




READ ALL NOTES ON THIS PAGE AND ON ENGINEERING NOTE PAGE ENP-1. THIS NOTE PAGE IS AN INTEGRAL PART OF THIS DRAWING AS IT CONTAINS SPECIFICATIONS AND CRITERIA USED IN THE DESIGN OF THIS COMPONENT.



These plans have been reviewed for use with the corrections as noted. No other changes may be made without written approval of the Building Standards Branch. All work must comply with Zoning By-Law 2018-043, as amended, and the Ontario Building Code, as amended. These approved documents must be kept on site at all times. The building permit must be clearly posted on site at all times.

Discipline	Reviewer	BCIN	Date
Building Code	H. Aulstner	43236	2021-02-24
Sewage System			
Zoning			






LUMBER										DIMENSIONS, SUPPORTS AND LOADINGS SPECIFIED BY FABRICATOR TO BE VERIFIED BY BUILDING DESIGNER										DESIGN CRITERIA									
N. L. G. A. RULES										BEARINGS										SPECIFIED LOADS:									
CHORDS SIZE LUMBER DESCR.										FACTORED GROSS REACTION MAXIMUM FACTORED GROSS REACTION INPUT BRG REQRD BRG										TOP CH. LL = 34.8 PSF									
A - C 2x4 DRY No.2 SPF										JT VERT 1064 0 1064 0 0 5-8 1-8										DL = 8.0 PSF									
C - E 2x4 DRY No.2 SPF										J 1064 0 1064 0 0 5-8 1-8										BOT CH. LL = 10.5 PSF									
J - A 2x4 DRY No.2 SPF										F 1064 0 1064 0 0 5-8 1-8										DL = 7.3 PSF									
F - E 2x4 DRY No.2 SPF																				TOTAL LOAD = 60.6 PSF									
J - H 2x4 DRY No.2 SPF																													
H - F 2x4 DRY No.2 SPF																													
ALL WEBS 2x3 DRY No.2 SPF										UNFACTORED REACTIONS										SPACING = 24.0 IN. C/C									
EXCEPT										1ST LCASE MAX. MIN. COMPONENT REACTIONS										THIS TRUSS IS DESIGNED FOR RESIDENTIAL OR SMALL BUILDING REQUIREMENTS OF PART 9, NBCC 2015									
DRY: SEASONED LUMBER.										JT COMBINED SNOW LIVE PERM. LIVE WIND DEAD SOIL										THIS DESIGN COMPLIES WITH:									
										J 788 453 / 0 137 / 0 0 / 0 0 / 0 199 / 0 0 / 0										- PART 9 OF BCBC 2018 , ABC 2019									
										F 788 453 / 0 136 / 0 0 / 0 0 / 0 199 / 0 0 / 0										- PART 9 OF OBC 2012 (2019 AMENDMENT)									
										BEARING MATERIAL TO BE SPF NO.2 OR BETTER AT JOINT(S) J, F										- CSA 086-14									
										BRACING										- TPIC 2014									
										TOP CHORD TO BE SHEATHED OR MAX. PURLIN SPACING = 4.88 FT.										(55 % OF 48.1 P.S.F. G.S.L. PLUS 8.4 P.S.F. RAIN LOAD)									
										MAX. UNBRACED BOTTOM CHORD LENGTH = 10.00 FT OR RIGID CEILING DIRECTLY APPLIED.										EQUALS 34.8 P.S.F. SPECIFIED ROOF LIVE LOAD									
										ALL PITCH BREAKS AND PERIMETER CORNER JOINTS MUST BE LATERALLY RESTRAINED.										ALLOWABLE DEFL.(LL)= L/360 (0.43")									
										LOADING										CALCULATED VERT. DEFL.(LL) = L/ 999 (0.06")									
										TOTAL LOAD CASES: (4)										ALLOWABLE DEFL.(TL)= L/360 (0.43")									
																				CALCULATED VERT. DEFL.(TL) = L/ 999 (0.10")									
																				CSI: TC=0.20/1.00 (A-B-1), BC=0.26/1.00 (G-H-1),									
																				WB=0.39/1.00 (C-H-1), SSI=0.12/1.00 (A-B-1)									
																				DOL LUMBER=1.00 NAIL=1.00 LS BEND=1.10 COMP=1.10									
																				SHEAR=1.10 TENS= 1.10									
																				COMPANION LIVE LOAD FACTOR = 1.00									
																				TRUSS PLATE MANUFACTURER IS NOT RESPONSIBLE FOR QUALITY CONTROL IN THE TRUSS MANUFACTURING PLANT .									
																				NAIL VALUES									
																				PLATE GRIP(DRY) SHEAR SECTION									
																				(PSI) (PLI)									
																				MAX MIN MAX MIN MAX MIN									
																				MT20 650 371 1747 788 1987 1873									
																				PLATE PLACEMENT TOL. = 0.250 inches									

These plans have been reviewed for use with the corrections as noted. No other changes may be made without written approval of the Building Standards Branch. All work must comply with Zoning By-Law 2018-043, as amended, and the Ontario Building Code, as amended. These approved documents must be kept on site at all times. The building permit must be clearly posted on site at all times.

Discipline	Reviewer	BCIN	Date
Building Code	H. Aulstner	43236	2021-02-24
Sewage System			
Zoning			

READ ALL NOTES ON THIS PAGE AND ON ENGINEERING NOTE PAGE ENP-1. THIS NOTE PAGE IS AN INTEGRAL PART OF THIS DRAWING AS IT CONTAINS SPECIFICATIONS AND CRITERIA USED IN THE DESIGN OF THIS COMPONENT.



Scale = 1:57.4

TOTAL WEIGHT = 2 X 60 = 119 lb

LUMBER					DESCR.
N. L. G. A. RULES	CHORDS	SIZE	LUMBER		
A - C	2x4	DRY	No.2		SPF
C - E	2x4	DRY	No.2		SPF
A - E	2x4	DRY	No.2		SPF
ALL WEBS	2x3	DRY	No.2		SPF
DRY: SEASONED LUMBER.					

PLATES (table is in inches)					
JT	TYPE	PLATES	W	LEN	Y X
A	TMBH1-I	MT20	8.0	8.0	3.00
B	TMW+w	MT20	2.0	4.0	
C	TTW+p	MT20	3.0	6.0	
D	TMW+w	MT20	2.0	4.0	
E	TMBH1-I	MT20	8.0	8.0	3.00
F	BMWWW-I	MT20	4.0	6.0	

DIMENSIONS, SUPPORTS AND LOADINGS SPECIFIED BY FABRICATOR TO BE VERIFIED BY BUILDING DESIGNER

BEARINGS									
FACTORED GROSS REACTION	MAXIMUM FACTORED GROSS REACTION	INPUT BRG	REQRD BRG	HEEL					
JT	VERT	HORZ	DOWN	HORZ	UPLIFT	IN-SX	IN-SX	WEDGE	
A	1064	0	1064	0	0	MECHANICAL	2x10 L		
E	1064	0	1064	0	0	MECHANICAL	2x10 R		

A SUITABLE HANGER/MECHANICAL CONNECTION IS REQUIRED AT JOINT A, E. MINIMUM BEARING LENGTH AT JOINT A = 1-12, JOINT E = 1-12.

DESIGN CRITERIA

SPECIFIED LOADS:
 TOP CH. LL = 34.8 PSF
 DL = 8.0 PSF
 BOT CH. LL = 10.5 PSF
 DL = 7.3 PSF
 TOTAL LOAD = 60.6 PSF

SPACING = 24.0 IN. C/C

THIS TRUSS IS DESIGNED FOR RESIDENTIAL OR SMALL BUILDING REQUIREMENTS OF PART 9, NBCC 2015

THIS DESIGN COMPLIES WITH:
 - PART 9 OF BCBC 2018, ABC 2019
 - PART 9 OF OBC 2012 (2019 AMENDMENT)
 - CSA 086-14
 - TPIC 2014

(55 % OF 48.1 P.S.F. G.S.L. PLUS 8.4 P.S.F. RAIN LOAD)
 EQUALS 34.8 P.S.F. SPECIFIED ROOF LIVE LOAD

ALLOWABLE DEFL (LL) = $L/360$ (0.43")
 CALCULATED VERT. DEFL (LL) = $L/999$ (0.04")
 ALLOWABLE DEFL (TL) = $L/360$ (0.43")
 CALCULATED VERT. DEFL (TL) = $L/999$ (0.06")

CSI: TC=0.16/1.00 (B-C-1), BC=0.33/1.00 (F-G-3),
 WB=0.16/1.00 (C-F-1), SSI=0.49/1.00 (A-G-2)

DOL LUMBER=1.00 NAIL=1.00 LS BEND=1.10 COMP=1.10
 SHEAR=1.10 TENS=1.10

COMPANION LIVE LOAD FACTOR = 1.00

TRUSS PLATE MANUFACTURER IS NOT RESPONSIBLE FOR QUALITY CONTROL IN THE TRUSS MANUFACTURING PLANT.

NAIL VALUES
 PLATE GRIP(DRY) SHEAR SECTION
 (PSI) (PLI) (PLI)
 MAX MIN MAX MIN MAX MIN
 MT20 650 371 1747 788 1987 1873

PLATE PLACEMENT TOL. = 0.250 inches

PLATE ROTATION TOL. = 5.0 Deg.

JSI GRIP= 0.86 (E) (INPUT = 0.90)
 JSI METAL = 0.34 (A) (INPUT = 1.00)

UNFACTORED REACTIONS

1ST LCASE	MAX/MIN	COMPONENT REACTIONS					
JT	COMBINED	SNOW	LIVE	PERM.LIVE	WIND	DEAD	SOIL
A	788	453 / 0	136 / 0	0 / 0	0 / 0	199 / 0	0 / 0
E	788	453 / 0	136 / 0	0 / 0	0 / 0	199 / 0	0 / 0

BRACING

TOP CHORD TO BE SHEATHED OR MAX. PURLIN SPACING = 5.02 FT.
 MAX. UNBRACED BOTTOM CHORD LENGTH = 10.00 FT OR RIGID CEILING DIRECTLY APPLIED.

ALL PITCH BREAKS AND PERIMETER CORNER JOINTS MUST BE Laterally RESTRAINED.

LOADING

TOTAL LOAD CASES: (4)

CHORDS				WEBS			
MEMB.	FORCE (LBS)	FACTORED VERT. LOAD (PLF)	FACTORED LC1 MAX (LC) UNBRAC	MEMB.	FORCE (LBS)	FACTORED MAX (LC)	
FR-TO		FROM	TO	LENGTH	FR-TO		
A-H	-1708 / 0	-124.4	-124.4	0.10 (1)	5.02	F-C	0 / 719
H-B	-927 / 0	-124.4	-124.4	0.15 (1)	6.25	F-D	-284 / 0
B-C	-893 / 0	-124.4	-124.4	0.16 (1)	6.25	B-F	-284 / 0
C-D	-893 / 0	-124.4	-124.4	0.16 (1)	6.25	G-H	0 / 777
D-J	-927 / 0	-124.4	-124.4	0.15 (1)	6.25	I-J	0 / 777
J-E	-1708 / 0	-124.4	-124.4	0.10 (1)	5.02		
A-G	0 / 566	-39.2	-39.2	0.22 (1)	10.00		
G-F	0 / 566	-39.2	-39.2	0.33 (3)	10.00		
F-I	0 / 566	-39.2	-39.2	0.33 (3)	10.00		
I-E	0 / 566	-39.2	-39.2	0.22 (1)	10.00		




These plans have been reviewed for use with the corrections as noted. No other changes may be made without written approval of the Building Standards Branch. All work must comply with Zoning By-Law 2018-043, as amended, and the Ontario Building Code, as amended. These approved documents must be kept on site at all times. The building permit must be clearly posted on site at all times.

Discipline	Reviewer	BCIN	Date
Building Code	H. Authier	43236	2021-02-24
Sewage System			
Zoning			

READ ALL NOTES ON THIS PAGE AND ON ENGINEERING NOTE PAGE ENP-1. THIS NOTE PAGE IS AN INTEGRAL PART OF THIS DRAWING AS IT CONTAINS SPECIFICATIONS AND CRITERIA USED IN THE DESIGN OF THIS COMPONENT.





LUMBER
N. L. G. A. RULES

CHORDS	SIZE	LUMBER	DESCR.
A - D	2x4	DRY No.2	SPF
D - F	2x4	DRY No.2	SPF
F - I	2x4	DRY No.2	SPF
Q - B	2x4	DRY No.2	SPF
J - H	2x4	DRY No.2	SPF
Q - M	2x4	DRY No.2	SPF
M - J	2x4	DRY No.2	SPF
ALL WEBS EXCEPT	2x3	DRY No.2	SPF

DRY: SEASONED LUMBER.

PLATES (table is in inches)

JT	TYPE	PLATES	W	LEN	Y	X
B	TMVW-t	MT20	5.0	8.0	1.75	3.00
C	TMVW-t	MT20	3.0	4.0	1.50	1.75
D	TTWW-m	MT20	5.0	8.0	2.25	3.50
E	TMVW-t	MT20	2.0	4.0	1.50	1.75
F	TTWW-m	MT20	5.0	8.0	2.25	3.50
G	TMVW-t	MT20	3.0	4.0	1.50	1.75
H	TMVW-t	MT20	5.0	8.0	1.75	3.00
J	BMV1+p	MT20	3.0	4.0	2.00	2.50
K	BMVW-t	MT20	5.0	8.0	2.50	1.50
L	BMVW-t	MT20	3.0	4.0	2.00	2.50
M	BS-t	MT20	3.0	4.0	2.00	2.50
N	BMVW-t	MT20	3.0	4.0	2.00	2.50
O	BMVW-t	MT20	3.0	4.0	2.00	2.50
P	BMVW-t	MT20	5.0	8.0	2.50	1.50
Q	BMV1+p	MT20	3.0	4.0	2.00	2.50



READ ALL NOTES ON THIS PAGE AND ON ENGINEERING NOTE PAGE ENP-1. THIS NOTE PAGE IS AN INTEGRAL PART OF THIS DRAWING AS IT CONTAINS SPECIFICATIONS AND CRITERIA USED IN THE DESIGN OF THIS COMPONENT.

DIMENSIONS, SUPPORTS AND LOADINGS SPECIFIED BY FABRICATOR TO BE VERIFIED BY BUILDING DESIGNER

BEARINGS

FACTORED GROSS REACTION	MAXIMUM FACTORED GROSS REACTION	INPUT BRG	REQRD BRG
JT VERT	2542	0	5-8
Q VERT	2542	0	5-8
JT HORZ	0	0	4-12
Q HORZ	0	0	4-12

UNFACTORED REACTIONS

1ST LCASE	MAX	MIN	COMPONENT REACTIONS
JT COMBINED	1874	1104 / 0	304 / 0
Q COMBINED	1874	1104 / 0	304 / 0


BEARING MATERIAL TO BE SPF NO.2 OR BETTER AT JOINT(S) Q, J

BRACING
TOP CHORD TO BE SHEATHED OR MAX. PURLIN SPACING = 2.54 FT.
MAX. UNBRACED BOTTOM CHORD LENGTH = 10.00 FT OR RIGID CEILING DIRECTLY APPLIED.

ALL PITCH BREAKS AND PERIMETER CORNER JOINTS MUST BE LATERALLY RESTRAINED.

LOADING
TOTAL LOAD CASES: (4)

CHORDS				WEBS			
MEMB.	MAX. FACTORED FORCE (LBS)	FACTORED VERT. LOAD (PLF)	FACTORED LC1 MAX (LC)	MEMB.	MAX. FACTORED FORCE (LBS)	FACTORED VERT. LOAD (PLF)	FACTORED LC1 MAX (LC)
FR-TO				FR-TO			
A-B	0 / 38	-124.4	-124.4 0.16 (1)	10.00	P-C	-477 / 0	0.09 (1)
B-C	-3275 / 0	-124.4	-124.4 0.36 (1)	3.58	C-D	-132 / 0	0.05 (1)
C-D	-3205 / 0	-124.4	-124.4 0.35 (1)	3.83	D-E	0 / 334	0.08 (2)
D-E	-3684 / 0	-124.4	-124.4 0.63 (1)	2.54	E-F	0 / 1042	0.23 (1)
E-F	-3684 / 0	-124.4	-124.4 0.63 (1)	2.54	F-G	-962 / 0	0.39 (1)
F-G	-3205 / 0	-124.4	-124.4 0.35 (1)	3.83	G-H	0 / 1042	0.23 (1)
G-H	-3275 / 0	-124.4	-124.4 0.36 (1)	3.58	H-I	0 / 334	0.08 (2)
H-I	0 / 38	-124.4	-124.4 0.16 (1)	10.00	I-J	-132 / 0	0.05 (1)
I-J	-2465 / 0	0.0	0.0 0.25 (1)	5.46	J-K	-477 / 0	0.09 (1)
J-K	-2465 / 0	0.0	0.0 0.25 (1)	5.46	K-L	0 / 3014	0.68 (1)
K-L	0 / 0	-39.2	-39.2 0.12 (2)	10.00	L-M	0 / 3014	0.68 (1)
L-M	0 / 2950	-39.2	-39.2 0.62 (1)	10.00	M-N	0 / 2849	0.63 (1)
M-N	0 / 2849	-39.2	-39.2 0.63 (1)	10.00	N-O	0 / 2849	0.63 (1)
N-O	0 / 2849	-39.2	-39.2 0.63 (1)	10.00	O-P	0 / 2849	0.63 (1)
O-P	0 / 2849	-39.2	-39.2 0.63 (1)	10.00	P-Q	0 / 2950	0.62 (1)
P-Q	0 / 2950	-39.2	-39.2 0.62 (1)	10.00	Q-R	0 / 0	0.12 (2)
Q-R	0 / 0	-39.2	-39.2 0.12 (2)	10.00	R-S	0 / 0	0.12 (2)
R-S	0 / 0	-39.2	-39.2 0.12 (2)	10.00	S-T	0 / 0	0.12 (2)
S-T	0 / 0	-39.2	-39.2 0.12 (2)	10.00	T-U	0 / 0	0.12 (2)
T-U	0 / 0	-39.2	-39.2 0.12 (2)	10.00	U-V	0 / 0	0.12 (2)
U-V	0 / 0	-39.2	-39.2 0.12 (2)	10.00	V-W	0 / 0	0.12 (2)
V-W	0 / 0	-39.2	-39.2 0.12 (2)	10.00	W-X	0 / 0	0.12 (2)
W-X	0 / 0	-39.2	-39.2 0.12 (2)	10.00	X-Y	0 / 0	0.12 (2)
X-Y	0 / 0	-39.2	-39.2 0.12 (2)	10.00	Y-Z	0 / 0	0.12 (2)
Y-Z	0 / 0	-39.2	-39.2 0.12 (2)	10.00	Z-A	0 / 0	0.12 (2)
Z-A	0 / 0	-39.2	-39.2 0.12 (2)	10.00	A-B	0 / 0	0.12 (2)
A-B	0 / 0	-39.2	-39.2 0.12 (2)	10.00	B-C	0 / 0	0.12 (2)
B-C	0 / 0	-39.2	-39.2 0.12 (2)	10.00	C-D	0 / 0	0.12 (2)
C-D	0 / 0	-39.2	-39.2 0.12 (2)	10.00	D-E	0 / 0	0.12 (2)
D-E	0 / 0	-39.2	-39.2 0.12 (2)	10.00	E-F	0 / 0	0.12 (2)
E-F	0 / 0	-39.2	-39.2 0.12 (2)	10.00	F-G	0 / 0	0.12 (2)
F-G	0 / 0	-39.2	-39.2 0.12 (2)	10.00	G-H	0 / 0	0.12 (2)
G-H	0 / 0	-39.2	-39.2 0.12 (2)	10.00	H-I	0 / 0	0.12 (2)
H-I	0 / 0	-39.2	-39.2 0.12 (2)	10.00	I-J	0 / 0	0.12 (2)
I-J	0 / 0	-39.2	-39.2 0.12 (2)	10.00	J-K	0 / 0	0.12 (2)
J-K	0 / 0	-39.2	-39.2 0.12 (2)	10.00	K-L	0 / 0	0.12 (2)
K-L	0 / 0	-39.2	-39.2 0.12 (2)	10.00	L-M	0 / 0	0.12 (2)
L-M	0 / 0	-39.2	-39.2 0.12 (2)	10.00	M-N	0 / 0	0.12 (2)
M-N	0 / 0	-39.2	-39.2 0.12 (2)	10.00	N-O	0 / 0	0.12 (2)
N-O	0 / 0	-39.2	-39.2 0.12 (2)	10.00	O-P	0 / 0	0.12 (2)
O-P	0 / 0	-39.2	-39.2 0.12 (2)	10.00	P-Q	0 / 0	0.12 (2)
P-Q	0 / 0	-39.2	-39.2 0.12 (2)	10.00	Q-R	0 / 0	0.12 (2)
Q-R	0 / 0	-39.2	-39.2 0.12 (2)	10.00	R-S	0 / 0	0.12 (2)
R-S	0 / 0	-39.2	-39.2 0.12 (2)	10.00	S-T	0 / 0	0.12 (2)
S-T	0 / 0	-39.2	-39.2 0.12 (2)	10.00	T-U	0 / 0	0.12 (2)
T-U	0 / 0	-39.2	-39.2 0.12 (2)	10.00	U-V	0 / 0	0.12 (2)
U-V	0 / 0	-39.2	-39.2 0.12 (2)	10.00	V-W	0 / 0	0.12 (2)
V-W	0 / 0	-39.2	-39.2 0.12 (2)	10.00	W-X	0 / 0	0.12 (2)
W-X	0 / 0	-39.2	-39.2 0.12 (2)	10.00	X-Y	0 / 0	0.12 (2)
X-Y	0 / 0	-39.2	-39.2 0.12 (2)	10.00	Y-Z	0 / 0	0.12 (2)
Y-Z	0 / 0	-39.2	-39.2 0.12 (2)	10.00	Z-A	0 / 0	0.12 (2)
Z-A	0 / 0	-39.2	-39.2 0.12 (2)	10.00	A-B	0 / 0	0.12 (2)
A-B	0 / 0	-39.2	-39.2 0.12 (2)	10.00	B-C	0 / 0	0.12 (2)
B-C	0 / 0	-39.2	-39.2 0.12 (2)	10.00	C-D	0 / 0	0.12 (2)
C-D	0 / 0	-39.2	-39.2 0.12 (2)	10.00	D-E	0 / 0	0.12 (2)
D-E	0 / 0	-39.2	-39.2 0.12 (2)	10.00	E-F	0 / 0	0.12 (2)
E-F	0 / 0	-39.2	-39.2 0.12 (2)	10.00	F-G	0 / 0	0.12 (2)
F-G	0 / 0	-39.2	-39.2 0.12 (2)	10.00	G-H	0 / 0	0.12 (2)
G-H	0 / 0	-39.2	-39.2 0.12 (2)	10.00	H-I	0 / 0	0.12 (2)
H-I	0 / 0	-39.2	-39.2 0.12 (2)	10.00	I-J	0 / 0	0.12 (2)
I-J	0 / 0	-39.2	-39.2 0.12 (2)	10.00	J-K	0 / 0	0.12 (2)
J-K	0 / 0	-39.2	-39.2 0.12 (2)	10.00	K-L	0 / 0	0.12 (2)
K-L	0 / 0	-39.2	-39.2 0.12 (2)	10.00	L-M	0 / 0	0.12 (2)
L-M	0 / 0	-39.2	-39.2 0.12 (2)	10.00	M-N	0 / 0	0.12 (2)
M-N	0 / 0	-39.2	-39.2 0.12 (2)	10.00	N-O	0 / 0	0.12 (2)
N-O	0 / 0	-39.2	-39.2 0.12 (2)	10.00	O-P	0 / 0	0.12 (2)
O-P	0 / 0	-39.2	-39.2 0.12 (2)	10.00	P-Q	0 / 0	0.12 (2)
P-Q	0 / 0	-39.2	-39.2 0.12 (2)	10.00	Q-R	0 / 0	0.12 (2)
Q-R	0 / 0	-39.2	-39.2 0.12 (2)	10.00	R-S	0 / 0	0.12 (2)
R-S	0 / 0	-39.2	-39.2 0.12 (2)	10.00	S-T	0 / 0	0.12 (2)
S-T	0 / 0	-39.2	-39.2 0.12 (2)	10.00	T-U	0 / 0	0.12 (2)
T-U	0 / 0	-39.2	-39.2 0.12 (2)	10.00	U-V	0 / 0	0.12 (2)
U-V	0 / 0	-39.2	-39.2 0.12 (2)	10.00	V-W	0 / 0	0.12 (2)
V-W	0 / 0	-39.2	-39.2 0.12 (2)	10.00	W-X	0 / 0	0.12 (2)
W-X	0 / 0	-39.2	-39.2 0.12 (2)	10.00	X-Y	0 / 0	0.12 (2)
X-Y	0 / 0	-39.2	-39.2 0.12 (2)	10.00	Y-Z	0 / 0	0.12 (2)
Y-Z	0 / 0	-39.2	-39.2 0.12 (2)	10.00	Z-A	0 / 0	0.12 (2)
Z-A	0 / 0	-39.2	-39.2 0.12 (2)	10.00	A-B	0 / 0	0.12 (2)
A-B	0 / 0	-39.2	-39.2 0.12 (2)	10.00	B-C	0 / 0	0.12 (2)
B-C	0 / 0	-39.2	-39.2 0.12 (2)	10.00	C-D	0 / 0	0.12 (2)
C-D	0 / 0	-39.2	-39.2 0.12 (2)	10.00	D-E	0 / 0	0.12 (2)
D-E	0 / 0	-39.2	-39.2 0.12 (2)	10.00	E-F	0 / 0	0.12 (2)
E-F	0 / 0	-39.2	-39.2 0.12 (2)	10.00	F-G	0 / 0	0.12 (2)
F-G	0 / 0	-39.2	-39.2 0.12 (2)	10.00	G-H	0 / 0	0.12 (2)
G-H	0 / 0	-39.2	-39.2 0.12 (2)	10.00	H-I	0 / 0	0.12 (2)
H-I	0 / 0	-39.2	-39.2 0.12 (2)	10.00	I-J	0 / 0	0.12 (2)
I-J	0 / 0	-39.2	-39.2 0.12 (2)	10.00	J-K	0 / 0	0.12 (2)
J-K	0 / 0	-39.2	-39.2 0.12 (2)	10.00	K-L	0 / 0	0.12 (2)
K-L	0 / 0	-39.2	-39.2 0.12 (2)	10.00	L-M	0 / 0	0.12 (2)
L-M	0 / 0	-39.2	-39.2 0.12 (2)	10.00	M-N	0 / 0	0.12 (2)
M-N	0 / 0	-39.2	-39.2 0.12 (2)	10.00	N-O	0 / 0	0.12 (2)
N-O	0 / 0	-39.2	-39.2 0.12 (2)	10.00	O-P	0 / 0	0.12 (2)
O-P	0 / 0	-39.2	-39.2 0.12 (2)	10.00	P-Q	0 / 0	0.12 (2)
P-Q	0 / 0	-39.2	-39.2 0.12 (2)	10.00	Q-R	0 / 0	0.12 (2)
Q-R	0 / 0	-39.2	-39.2 0.12 (2)	10.00	R-S	0 / 0	0.12 (2)
R-S	0 / 0	-39.2	-39.				



LUMBER

N. L. G. A. RULES

CHORDS	SIZE	DRY	LUMBER	DESCR.
A - D	2x4	DRY	No.2	SPF
D - F	2x4	DRY	No.2	SPF
F - I	2x4	DRY	No.2	SPF
Q - B	2x4	DRY	No.2	SPF
J - H	2x4	DRY	No.2	SPF
Q - M	2x4	DRY	No.2	SPF
M - J	2x4	DRY	No.2	SPF
ALL WEBS EXCEPT	2x3	DRY	No.2	SPF

DRY: SEASONED LUMBER.

PLATES (table is in inches)

JT	TYPE	PLATES	W	LEN	Y	X
B	TMVW-t	MT20	5.0	8.0	1.75	3.00
C	TMVW-t	MT20	3.0	4.0	1.50	1.75
D	TTWW-m	MT20	5.0	6.0	2.50	2.00
E	TMVW-t	MT20	2.0	4.0		
F	TTWW-m	MT20	5.0	6.0	2.50	2.00
G	TMVW-t	MT20	3.0	4.0	1.50	1.75
H	TMVW-t	MT20	5.0	8.0	1.75	3.00
J	BMV1+p	MT20	3.0	4.0	2.00	
K	BMVW-t	MT20	5.0	6.0	2.50	1.75
L	BMVW-t	MT20	3.0	4.0		
M	BS-t	MT20	3.0	6.0		
N	BMVW-t	MT20	3.0	4.0		
O	BMVW-t	MT20	3.0	4.0		
P	BMVW-t	MT20	5.0	6.0	2.50	1.75
Q	BMV1+p	MT20	3.0	4.0	2.00	0.50



READ ALL NOTES ON THIS PAGE AND ON ENGINEERING NOTE PAGE ENP-1. THIS NOTE PAGE IS AN INTEGRAL PART OF THIS DRAWING AS IT CONTAINS SPECIFICATIONS AND CRITERIA USED IN THE DESIGN OF THIS COMPONENT.

DIMENSIONS, SUPPORTS AND LOADINGS SPECIFIED BY FABRICATOR TO BE VERIFIED BY BUILDING DESIGNER

BEARINGS

FACTORED GROSS REACTION	MAXIMUM FACTORED GROSS REACTION	INPUT BRG	REQRD BRG
JT VERT	DOWN	IN-SX	IN-SX
Q 2542	0	5-8	4-12
J 2542	0	5-8	4-12

UNFACTORED REACTIONS

1ST LCASE	MAX	MIN	COMPONENT REACTIONS
JT COMBINED	SNOW	LIVE	PERM. LIVE
Q 1874	1104 / 0	305 / 0	0 / 0
J 1874	1104 / 0	305 / 0	0 / 0

BEARING MATERIAL TO BE SPF NO.2 OR BETTER AT JOINT(S) Q, J

BRACING

TOP CHORD TO BE SHEATHED OR MAX. PURLIN SPACING = 3.33 FT.

MAX. UNBRACED BOTTOM CHORD LENGTH = 10.00 FT OR RIGID CEILING DIRECTLY APPLIED.

ALL PITCH BREAKS AND PERIMETER CORNER JOINTS MUST BE Laterally RESTRAINED.

LOADING

TOTAL LOAD CASES: (4)

CHORDS				WEBS			
MEMB.	MAX. FACTORED FORCE (LBS)	FACTORED VERT. LOAD (PLF)	FACTORED LC1 MAX CSI (LC)	MEMB.	MAX. FACTORED FORCE (LBS)	MAX. FACTORED FORCE (LBS)	MAX. FACTORED FORCE (LBS)
FR-TO				FR-TO			
A-B	0 / 38	-124.4	-124.4 0.16 (1)	10.00	P-C	-302 / 64	0.07 (1)
B-C	-3380 / 0	-124.4	-124.4 0.56 (1)	3.33	C-O	-477 / 0	0.31 (1)
C-D	-3004 / 0	-124.4	-124.4 0.51 (1)	3.56	O-D	0 / 461	0.10 (2)
D-E	-2686 / 0	-124.4	-124.4 0.42 (1)	3.66	D-N	0 / 528	0.12 (1)
E-F	-2686 / 0	-124.4	-124.4 0.42 (1)	3.66	N-E	-678 / 0	0.41 (1)
F-G	-3004 / 0	-124.4	-124.4 0.51 (1)	3.56	N-F	0 / 528	0.12 (1)
G-H	-3380 / 0	-124.4	-124.4 0.56 (1)	3.33	L-F	0 / 461	0.10 (2)
H-I	0 / 38	-124.4	-124.4 0.16 (1)	10.00	L-G	-477 / 0	0.31 (1)
Q-B	-2455 / 0	0.0	0.0 0.25 (1)	5.46	K-G	-302 / 64	0.07 (1)
J-H	-2455 / 0	0.0	0.0 0.25 (1)	5.46	B-P	0 / 3063	0.70 (1)
					K-H	0 / 3063	0.70 (1)
Q-P	0 / 0	-39.2	-39.2 0.18 (3)	10.00			
P-O	0 / 3051	-39.2	-39.2 0.59 (1)	10.00			
O-N	0 / 2664	-39.2	-39.2 0.53 (1)	10.00			
N-M	0 / 2664	-39.2	-39.2 0.53 (1)	10.00			
M-L	0 / 2664	-39.2	-39.2 0.53 (1)	10.00			
L-K	0 / 3051	-39.2	-39.2 0.59 (1)	10.00			
K-J	0 / 0	-39.2	-39.2 0.18 (3)	10.00			

DESIGN CRITERIA

SPECIFIED LOADS:

TOP CH.	LL	PSF
DL	8.0	PSF
BOT CH.	LL	PSF
DL	10.5	PSF
DL	7.3	PSF
TOTAL LOAD	80.8	PSF

SPACING = 24.0 IN. C/C

LOADING IN FLAT SECTION BASED ON A SLOPE OF 2.00/12 MINIMUM

THIS TRUSS IS DESIGNED FOR RESIDENTIAL OR SMALL BUILDING REQUIREMENTS OF PART 9, NBCC 2015

THIS DESIGN COMPLIES WITH:

- PART 9 OF BCBC 2018, ABC 2019
- PART 9 OF OBC 2012 (2019 AMENDMENT)
- CSA 086-14
- TPIC 2014

(55 % OF 48.1 P.S.F. G.S.L. PLUS 8.4 P.S.F. RAIN LOAD) EQUALS 34.8 P.S.F. SPECIFIED ROOF LIVE LOAD

ALLOWABLE DEFL.(LL)= L/360 (0.97")

CALCULATED VERT. DEFL.(LL) = L/999 (0.15")

ALLOWABLE DEFL.(TL)= L/360 (0.97")

CALCULATED VERT. DEFL.(TL) = L/999 (0.25")

CSI: TC=0.56/1.00 (G-H:1) , BC=0.59/1.00 (K-L:1) , WB=0.70/1.00 (H-K:1) , SSI=0.27/1.00 (G-H:1)

DOL LUMBER=1.00 NAIL=1.00 LS BEND=1.10 COMP=1.10 SHEAR=1.10 TENS= 1.10

COMPANION LIVE LOAD FACTOR = 1.00

TRUSS PLATE MANUFACTURER IS NOT RESPONSIBLE FOR QUALITY CONTROL IN THE TRUSS MANUFACTURING PLANT .

NAIL VALUES

PLATE GRIP(DRY) SHEAR SECTION (PSI) (PLI) (PLI)

MAX MIN MAX MIN MAX MIN

MT20 650 371 1747 768 1987 1873

PLATE PLACEMENT TOL. = 0.250 inches

PLATE ROTATION TOL. = 5.0 Deg.

JSI GRIP= 0.89 (K) (INPUT = 0.80)


JSI METAL = 0.82 (M) (INPUT = 1.00)



These plans have been reviewed for use with the corrections as noted. No other changes may be made without written approval of the Building Standards Branch. All work must comply with Zoning By-Law 2018-043, as amended, and the Ontario Building Code, as amended. These approved documents must be kept on site at all times. The building permit must be clearly posted on site at all times.

Discipline	Reviewer	BCIN	Date
Building Code	H. Authier	43236	2021-02-24
Sewage System			
Zoning			





LUMBER
N. L. G. A. RULES

CHORDS	SIZE	LUMBER	DESCR.
A - D	2x4	DRY No.2	SPF
D - E	2x4	DRY No.2	SPF
E - H	2x4	DRY No.2	SPF
O - B	2x4	DRY No.2	SPF
I - G	2x4	DRY No.2	SPF
O - L	2x4	DRY No.2	SPF
L - I	2x4	DRY No.2	SPF
ALL WEBS	2x3	DRY No.2	SPF

EXCEPT
DRY: SEASONED LUMBER.

PLATES (table is in inches)

JT	TYPE	PLATES	W	LEN	Y	X
B	TMVW-t	MT20	5.0	8.0	1.75	3.00
C	TMVW-t	MT20	3.0	4.0	1.50	1.75
D	TTW-m	MT20	4.0	6.0	1.75	2.25
E	TTW-m	MT20	4.0	5.0		
F	TMVW-t	MT20	3.0	4.0	1.50	1.75
G	TMVW-t	MT20	5.0	8.0	1.75	3.00
I	BMV1+p	MT20	3.0	4.0	2.00	
J	BMVW-t	MT20	5.0	6.0	2.50	1.75
K	BMVW-t	MT20	3.0	8.0		
L	BS-t	MT20	3.0	6.0		
M	BMVW-t	MT20	3.0	5.0		
N	BMVW-t	MT20	5.0	6.0	2.50	1.75
O	BMV1+p	MT20	3.0	4.0	2.00	0.50

DIMENSIONS, SUPPORTS AND LOADINGS SPECIFIED BY FABRICATOR TO BE VERIFIED BY BUILDING DESIGNER

BEARINGS

	FACTORED GROSS REACTION	MAXIMUM FACTORED GROSS REACTION	INPUT BRG	REQRD BRG
JT	VERT	DOWN	UPLIFT	IN-SX
O	2542	0	0	5-8
I	2542	0	0	5-8

UNFACTORED REACTIONS

1ST LCASE	MAX	MIN	COMPONENT REACTIONS
JT	COMBINED	SNOW	LIVE
O	1874	1104 / 0	305 / 0
I	1874	1104 / 0	305 / 0

BEARING MATERIAL TO BE SPF NO.2 OR BETTER AT JOINT(S) O, I

BRACING
TOP CHORD TO BE SHEATHED OR MAX. PURLIN SPACING = 2.95 FT.
MAX. UNBRACED BOTTOM CHORD LENGTH = 10.00 FT OR RIGID CEILING DIRECTLY APPLIED.
ALL PITCH BREAKS AND PERIMETER CORNER JOINTS MUST BE LATERALLY RESTRAINED.

LOADING
TOTAL LOAD CASES: (4)

CHORDS				WEBS			
MEMB.	MAX. FACTORED FORCE (LBS)	FACTORED VERT. LOAD (PLF)	FACTORED LC1 MAX (LC)	UNBRACED LENGTH	MEMB.	MAX. FACTORED FORCE (LBS)	MAX. FACTORED CSI (LC)
FR-TO					FR-TO		
A-B	0 / 38	-124.4	-124.4 0.16 (1)	10.00	N-C	-170 / 160	0.05 (1)
B-C	-3418 / 0	-124.4	-124.4 0.81 (1)	2.95	C-M	-783 / 0	0.77 (1)
C-D	-2785 / 0	-124.4	-124.4 0.71 (1)	3.39	M-D	0 / 631	0.14 (1)
D-E	-2446 / 0	-124.4	-124.4 0.48 (1)	3.90	D-K	0 / 2	0.00 (1)
E-F	-2786 / 0	-124.4	-124.4 0.71 (1)	3.39	K-E	0 / 633	0.14 (1)
F-G	-3417 / 0	-124.4	-124.4 0.81 (1)	2.95	K-F	-781 / 0	0.77 (1)
G-H	0 / 38	-124.4	-124.4 0.16 (1)	10.00	J-F	-172 / 159	0.05 (1)
O-B	-2442 / 0	0.0	0.0 0.25 (1)	5.48	B-N	0 / 3122	0.70 (1)
I-G	-2442 / 0	0.0	0.0 0.25 (1)	5.48	J-G	0 / 3121	0.70 (1)
O-N	0 / 0	-39.2	-39.2 0.28 (3)	10.00			
N-M	0 / 3091	-39.2	-39.2 0.66 (1)	10.00			
M-L	0 / 2445	-39.2	-39.2 0.52 (1)	10.00			
L-K	0 / 2445	-39.2	-39.2 0.52 (1)	10.00			
K-J	0 / 3091	-39.2	-39.2 0.66 (1)	10.00			
J-I	0 / 0	-39.2	-39.2 0.28 (3)	10.00			

DESIGN CRITERIA

SPECIFIED LOADS:
TOP CH. LL = 34.8 PSF
DL = 8.0 PSF
BOT CH. LL = 10.5 PSF
DL = 7.3 PSF
TOTAL LOAD = 60.6 PSF

SPACING = 24.0 IN. C/C

LOADING IN FLAT SECTION BASED ON A SLOPE OF 2.00/12 MINIMUM

THIS TRUSS IS DESIGNED FOR RESIDENTIAL OR SMALL BUILDING REQUIREMENTS OF PART 9, NBCC 2015

THIS DESIGN COMPLIES WITH:
- PART 9 OF BCBC 2018, ABC 2019
- PART 9 OF OBC 2012 (2019 AMENDMENT)
- CSA 086-14
- TPIC 2014

(55 % OF 48.1 P.S.F. G.S.L. PLUS 8.4 P.S.F. RAIN LOAD)
EQUALS 34.8 P.S.F. SPECIFIED ROOF LIVE LOAD

ALLOWABLE DEFL.(LL)= L/360 (0.97")
CALCULATED VERT. DEFL.(LL) = L/999 (0.15")
ALLOWABLE DEFL.(TL)= L/360 (0.97")
CALCULATED VERT. DEFL.(TL) = L/999 (0.26")

CSI: TC=0.81/1.00 (B-C-1), BC=0.66/1.00 (M-N-1),
WB=0.77/1.00 (C-M-1), SSI=0.33/1.00 (F-G-1)

DOL LUMBER=1.00 NAIL=1.00 LS BEND=1.10 COMP=1.10
SHEAR=1.10 TENS= 1.10

COMPANION LIVE LOAD FACTOR = 1.00

TRUSS PLATE MANUFACTURER IS NOT RESPONSIBLE FOR QUALITY CONTROL IN THE TRUSS MANUFACTURING PLANT .

NAIL VALUES
PLATE GRIP(DRY) SHEAR SECTION (PSI) (PLI) (PLI)
MAX MIN MAX MIN MAX MIN
MT20 650 371 1747 788 1987 1873

PLATE PLACEMENT TOL = 0.250 inches

PLATE ROTATION TOL = 5.0 Deg.

JSI GRIP= 0.90 (K) (INPUT = 0.90)
JSI METAL= 0.71 (L) (INPUT = 1.00)




READ ALL NOTES ON THIS PAGE AND ON ENGINEERING NOTE PAGE ENP-1. THIS NOTE PAGE IS AN INTEGRAL PART OF THIS DRAWING AS IT CONTAINS SPECIFICATIONS AND CRITERIA USED IN THE DESIGN OF THIS COMPONENT.



These plans have been reviewed for use with the corrections as noted. No other changes may be made without written approval of the Building Standards Branch. All work must comply with Zoning By-Law 2018-043, as amended, and the Ontario Building Code, as amended. These approved documents must be kept on site at all times. The building permit must be clearly posted on site at all times.

Discipline	Reviewer	BCIN	Date
Building Code	H. Authier	43236	2021-02-24
Sewage System			
Zoning			





TOTAL WEIGHT = 128 lb

LUMBER					DESCR.
N. L. G. A. RULES	CHORDS	SIZE	LUMBER		
A - C	2x4	DRY	2100F 1.8E		SPF
C - E	2x4	DRY	2100F 1.8E		SPF
E - F	2x4	DRY	No.2		SPF
F - H	2x4	DRY	2100F 1.8E		SPF
H - J	2x4	DRY	2100F 1.8E		SPF
P - B	2x4	DRY	No.2		SPF
K - I	2x4	DRY	No.2		SPF
P - M	2x4	DRY	No.2		SPF
M - K	2x4	DRY	No.2		SPF
ALL WEBS EXCEPT					SPF
O - E	2x4	DRY	No.2		SPF
F - L	2x4	DRY	No.2		SPF

DRY: SEASONED LUMBER.

PLATES (table is in inches)

JT TYPE	PLATES	W	LEN	Y	X
B TMVW-t	MT20	5.0	8.0	1.75	3.00
C TS-t	MT20	3.0	6.0		
D TMW+w	MT20	2.0	4.0		
E TTWW-m	MT20	5.0	5.0	2.00	2.50
F TTWW-m	MT20	5.0	5.0	2.00	2.50
G TMW+w	MT20	2.0	4.0		
H TS-t	MT20	3.0	6.0		
I TMVW-t	MT20	5.0	8.0	1.75	3.00
K BMV1+p	MT20	3.0	4.0	2.00	
L BMWWW-t	MT20	4.0	10.0	1.75	2.75
M BS-t	MT20	3.0	6.0		
N BMWW-t	MT20	3.0	4.0		
O BMWWW-t	MT20	4.0	10.0	1.75	4.75
P BMV1+p	MT20	3.0	4.0	2.00	0.50

DIMENSIONS, SUPPORTS AND LOADINGS SPECIFIED BY FABRICATOR TO BE VERIFIED BY BUILDING DESIGNER

BEARINGS

	FACTORED GROSS REACTION	MAXIMUM FACTORED GROSS REACTION	INPUT BRG	REQRD BRG
JT VERT	0	0	0	0
P 2542	0	2542	0	5-8
K 2542	0	2542	0	5-8

UNFACTORED REACTIONS

1ST LCASE	MAX	MIN	COMPONENT REACTIONS	
JT COMBINED	SNOW	LIVE	PERM.LIVE	WIND
P 1874	1104 / 0	305 / 0	0 / 0	0 / 0
K 1874	1104 / 0	305 / 0	0 / 0	0 / 0

BEARING MATERIAL TO BE SPF NO.2 OR BETTER AT JOINT(S) P, K

BRACING

TOP CHORD TO BE SHEATHED OR MAX. PURLIN SPACING = 3.95 FT.
MAX. UNBRACED BOTTOM CHORD LENGTH = 10.00 FT OR RIGID CEILING DIRECTLY APPLIED.

ALL PITCH BREAKS AND PERIMETER CORNER JOINTS MUST BE Laterally RESTRAINED.

LOADING

TOTAL LOAD CASES: (4)

CHORDS				WEBS			
MEMB.	MAX. FACTORED FORCE (LBS)	FACTORED VERT. LOAD (PLF)	LC1 MAX (LC)	MEMB.	MAX. FACTORED FORCE (LBS)	MAX. FACTORED FORCE (LBS)	MAX. FACTORED FORCE (LBS)
FR-TO				FROM			
A-B	0 / 38	-124.4	-124.4 0.11 (1)	10.00	O-D	-1061 / 0	0.35 (1)
B-C	-3425 / 0	-124.4	-124.4 0.64 (1)	3.97	O-E	0 / 1328	0.21 (1)
C-D	-3425 / 0	-124.4	-124.4 0.64 (1)	3.97	E-N	0 / 174	0.04 (3)
D-E	-3475 / 0	-124.4	-124.4 0.64 (1)	3.95	N-F	0 / 179	0.04 (3)
E-F	-2207 / 0	-124.4	-124.4 0.06 (1)	4.57	F-L	0 / 1321	0.21 (1)
F-G	-3473 / 0	-124.4	-124.4 0.64 (1)	3.95	L-G	-1061 / 0	0.35 (1)
G-H	-3424 / 0	-124.4	-124.4 0.64 (1)	3.97	B-O	0 / 3128	0.70 (1)
H-I	-3424 / 0	-124.4	-124.4 0.64 (1)	3.97	L-I	0 / 3125	0.70 (1)
I-J	0 / 38	-124.4	-124.4 0.11 (1)	10.00			
P-B	-2427 / 0	0.0	0.0 0.25 (1)	5.49			
K-I	-2426 / 0	0.0	0.0 0.25 (1)	5.49			
P-O	0 / 0	-39.2	-39.2 0.40 (3)	10.00			
O-N	0 / 2196	-39.2	-39.2 0.64 (2)	10.00			
N-M	0 / 2200	-39.2	-39.2 0.63 (2)	10.00			
M-L	0 / 2200	-39.2	-39.2 0.63 (2)	10.00			
L-K	0 / 0	-39.2	-39.2 0.39 (3)	10.00			

DESIGN CRITERIA

SPECIFIED LOADS:

TOP CH.	LL = 34.8	PSF
	DL = 8.0	PSF
BOT CH.	LL = 10.5	PSF
	DL = 7.3	PSF
TOTAL LOAD	= 60.6	PSF

SPACING = 24.0 IN. C/C

LOADING IN FLAT SECTION BASED ON A SLOPE OF 2.00/12 MINIMUM

THIS TRUSS IS DESIGNED FOR RESIDENTIAL OR SMALL BUILDING REQUIREMENTS OF PART 9, NBCC 2015

THIS DESIGN COMPLIES WITH:

- PART 9 OF BCBC 2018 , ABC 2019
- PART 9 OF OBC 2012 (2019 AMENDMENT)
- CSA 086-14
- TPIC 2014

(55 % OF 48.1 P.S.F. G.S.L. PLUS 8.4 P.S.F. RAIN LOAD)
EQUALS 34.8 P.S.F. SPECIFIED ROOF LIVE LOAD

ALLOWABLE DEFL.(LL)= L/360 (0.97")
CALCULATED VERT. DEFL.(LL) = L/ 999 (0.15")
ALLOWABLE DEFL.(TL)= L/360 (0.97")
CALCULATED VERT. DEFL.(TL) = L/ 999 (0.26")

CSI: TC=0.64/1.00 (B-D-1) , BC=0.64/1.00 (N-O-2) ,
WB=0.70/1.00 (B-O-1) , SSI=0.38/1.00 (G-I-1)

DOL LUMBER=1.00 NAIL=1.00 LS BEND=1.10 COMP=1.10
SHEAR=1.10 TENS= 1.10

COMPANION LIVE LOAD FACTOR = 1.00

TRUSS PLATE MANUFACTURER IS NOT RESPONSIBLE FOR QUALITY CONTROL IN THE TRUSS MANUFACTURING PLANT .

NAIL VALUES

PLATE GRIP(DRY) SHEAR	SECTION (PSI)	(PLI)	(PLI)
MAX MIN MAX MIN MAX MIN			
MT20	650	371	1747 768 1987 1873

PLATE PLACEMENT TOL. = 0.250 inches

PLATE ROTATION TOL. = 5.0 Deg.

JSI GRIP= 0.90 (F) (INPUT = 0.90)
JSI METAL = 0.69 (M) (INPUT = 1.00)



READ ALL NOTES ON THIS PAGE AND ON ENGINEERING NOTE PAGE ENP-1. THIS NOTE PAGE IS AN INTEGRAL PART OF THIS DRAWING AS IT CONTAINS SPECIFICATIONS AND CRITERIA USED IN THE DESIGN OF THIS COMPONENT.




These plans have been reviewed for use with the corrections as noted. No other changes may be made without written approval of the Building Standards Branch. All work must comply with Zoning By-Law 2018-043, as amended, and the Ontario Building Code, as amended. These approved documents must be kept on site at all times. The building permit must be clearly posted on site at all times.

Discipline	Reviewer	BCIN	Date
Building Code	H. Authier	43236	2021-02-24
Sewage System			
Zoning			



Version 8.420 S Oct 9 2020 Mitek Industries, Inc. Sun Dec 20 11:35:42 2020 Page 1
ID:mCCrycxnIfAPc08wPalNt0zHzlx-opm4NksFVXv9HS6cYwq2BYB eR TAtHtAT2r4dy75



LUMBER				
N. L. G. A. RULES	CHORDS	SIZE	LUMBER	DESCR.
A - C	2x4	DRY	2100F 1.8E	SPF
C - E	2x4	DRY	2100F 1.8E	SPF
E - G	2x4	DRY	2100F 1.8E	SPF
G - I	2x4	DRY	2100F 1.8E	SPF
O - B	2x4	DRY	No.2	SPF
J - H	2x4	DRY	No.2	SPF
O - L	2x4	DRY	No.2	SPF
L - J	2x4	DRY	No.2	SPF
ALL WEBS 2x3 DRY No.2 SPF				
EXCEPT				
DRY: SEASONED LUMBER.				

PLATES (table is in inches)				
JT TYPE	PLATES	W	LEN	Y X
B TMVW-t	MT20	5.0	8.0	1.75 3.00
C TS-t	MT20	3.0	6.0	
D TMVW-t	MT20	3.0	5.0	
E TTW+p	MT20	4.0	5.0	
F TMVW-t	MT20	3.0	5.0	
G TS-t	MT20	3.0	6.0	
H TMVW-t	MT20	5.0	8.0	1.75 3.00
J BMV1+p	MT20	3.0	4.0	2.00
K BMVW-t	MT20	5.0	6.0	2.50 1.75
L BS-t	MT20	3.0	6.0	
M BMVW-t	MT20	4.0	6.0	1.50 3.00
N BMVW-t	MT20	5.0	6.0	2.50 1.75
O BMV1+p	MT20	3.0	4.0	2.00 0.50

DIMENSIONS, SUPPORTS AND LOADINGS SPECIFIED BY FABRICATOR TO BE VERIFIED BY BUILDING DESIGNER

BEARINGS					
	FACTORED GROSS REACTION	MAXIMUM FACTORED GROSS REACTION	INPUT BRG	REQRD BRG	
JT VERT	2542	0	2542	0	5-8
O	2542	0	2542	0	4-12
J	2542	0	2542	0	5-8

UNFACTORED REACTIONS							
1ST LCASE MAX/MIN COMPONENT REACTIONS							
JT	COMBINED	SNOW	LIVE	PERM.LIVE	WIND	DEAD	SOIL
O	1874	1104 / 0	304 / 0	0 / 0	0 / 0	485 / 0	0 / 0
J	1874	1104 / 0	304 / 0	0 / 0	0 / 0	485 / 0	0 / 0

BEARING MATERIAL TO BE SPF NO.2 OR BETTER AT JOINT(S) O, J

BRACING
TOP CHORD TO BE SHEATHED OR MAX. PURLIN SPACING = 3.88 FT.
MAX. UNBRACED BOTTOM CHORD LENGTH = 10.00 FT OR RIGID CEILING DIRECTLY APPLIED.

ALL PITCH BREAKS AND PERIMETER CORNER JOINTS MUST BE LATERALLY RESTRAINED.

1 - 1x4 LATERAL BRACE(S) AT 1/2 LENGTH OF F-M, D-M, DBS = 20-0-0, CBF = 140 LBS.

DBS = DIAGONAL BRACE SPACING (MAX), CBF = CUMULATIVE BRACING FORCE (PER BRACE), FASTEN LATERAL BRACE(S) USING (0.122"x3") SPIRAL NAILS : 1 NAIL FOR 2x3 BRACE(S), 2 FOR 1x4, 2x4, 2x5, 3 FOR 2x6, 4 FOR 2x8, 5 FOR 2x10, AND 6 FOR 2x12.

END VERTICAL(S) MUST BE SHEATHED OR HAVE BRACES AS INDICATED IN THE MAX. UNBRACED LENGTH COLUMN OF THE TABLE BELOW

LOADING
TOTAL LOAD CASES: (4)

CHORDS				WEBS			
MEMB.	MAX. FACTORED FORCE (LBS)	FACTORED VERT. LOAD (PLF)	FACTORED LC1 MAX CSI (LC)	MEMB.	MAX. FACTORED FORCE (LBS)	MAX. FACTORED UNBRAC LENGTH (FT)	MAX. FACTORED UNBRAC LENGTH (FT)
FR-TO				FR-TO			
A-B	0 / 38	-124.4 -124.4	0.11 (1)	10.00	M-E	0 / 1470	0.33 (1)
B-C	-3403 / 0	-124.4 -124.4	0.71 (1)	3.88	M-F	-1120 / 0	0.55 (1)
C-D	-3403 / 0	-124.4 -124.4	0.71 (1)	3.88	K-F	-44 / 257	0.06 (3)
D-E	-2442 / 0	-124.4 -124.4	0.62 (1)	4.53	D-M	-1120 / 0	0.55 (1)
E-F	-2442 / 0	-124.4 -124.4	0.62 (1)	4.53	N-D	-44 / 257	0.06 (3)
F-G	-3403 / 0	-124.4 -124.4	0.71 (1)	3.88	B-N	0 / 3107	0.70 (1)
G-H	-3403 / 0	-124.4 -124.4	0.71 (1)	3.88	K-H	0 / 3107	0.70 (1)
H-I	0 / 38	-124.4 -124.4	0.11 (1)	10.00			
O-B	-2424 / 0	0.0	0.0 0.24 (1)	5.49			
J-H	-2424 / 0	0.0	0.0 0.24 (1)	5.49			
O-N	0 / 0	-39.2 -39.2	0.40 (3)	10.00			
N-M	0 / 3086	-39.2 -39.2	0.77 (2)	10.00			
M-L	0 / 3086	-39.2 -39.2	0.77 (2)	10.00			
L-K	0 / 3086	-39.2 -39.2	0.77 (2)	10.00			
K-J	0 / 0	-39.2 -39.2	0.40 (3)	10.00			

DESIGN CRITERIA

SPECIFIED LOADS:
TOP CH. LL = 34.8 PSF
DL = 8.0 PSF
BOT CH. LL = 10.5 PSF
DL = 7.3 PSF
TOTAL LOAD = 60.6 PSF

SPACING = 24.0 IN. C/C

THIS TRUSS IS DESIGNED FOR RESIDENTIAL OR SMALL BUILDING REQUIREMENTS OF PART 9, NBCC 2015

THIS DESIGN COMPLIES WITH:
- PART 9 OF BCBC 2018, ABC 2019
- PART 9 OF OBC 2012 (2019 AMENDMENT)
- CSA 086-14
- TPIC 2014

(55 % OF 48.1 P.S.F. G.S.L. PLUS 8.4 P.S.F. RAIN LOAD)
EQUALS 34.8 P.S.F. SPECIFIED ROOF LIVE LOAD

ALLOWABLE DEFL.(LL) = L/360 (0.97")
CALCULATED VERT. DEFL.(LL) = L/999 (0.15")
ALLOWABLE DEFL.(TL) = L/360 (0.97")
CALCULATED VERT. DEFL.(TL) = L/999 (0.27")

CSI: TC=0.71/1.00 (B-D:1), BC=0.77/1.00 (M-N:2),
WB=0.70/1.00 (B-N:1), SSI=0.39/1.00 (F-H:1)

DOL LUMBER=1.00 NAIL=1.00 LS BEND=1.10 COMP=1.10
SHEAR=1.10 TENS=1.10

COMPANION LIVE LOAD FACTOR = 1.00

TRUSS PLATE MANUFACTURER IS NOT RESPONSIBLE FOR QUALITY CONTROL IN THE TRUSS MANUFACTURING PLANT.

NAIL VALUES
PLATE GRIP(DRY) SHEAR SECTION
(PSI) (PLI) (PLI)
MAX MIN MAX MIN MAX MIN
MT20 650 371 1747 788 1987 1873

PLATE PLACEMENT TOL. = 0.250 inches

PLATE ROTATION TOL. = 5.0 Deg.

JSI GRIP= 0.89 (M) (INPUT = 0.90)
JSI METAL = 0.88 (L) (INPUT = 1.00)



READ ALL NOTES ON THIS PAGE AND ON ENGINEERING NOTE PAGE ENP-1. THIS NOTE PAGE IS AN INTEGRAL PART OF THIS DRAWING AS IT CONTAINS SPECIFICATIONS AND CRITERIA USED IN THE DESIGN OF THIS COMPONENT.




These plans have been reviewed for use with the corrections as noted. No other changes may be made without written approval of the Building Standards Branch. All work must comply with Zoning By-Law 2018-043, as amended, and the Ontario Building Code, as amended. These approved documents must be kept on site at all times. The building permit must be clearly posted on site at all times.

Discipline	Reviewer	BCIN	Date
Building Code	H. Authier	43236	2021-02-24
Sewage System			
Zoning			



Version 8.420 S Oct 9 2020 MITek Industries, Inc. Sun Dec 20 11:35:43 2020 Page 1
ID:mCCrycxnlfAPc08wPalNt0zHzlx-G0Jsa4ttGr17vbqo6eBHKmkHdqU3vTjvO7oOc6y75



Scale = 1:19.3

TOTAL WEIGHT = 3 X 20 = 59 lb

LUMBER					DESCR.
N. L. G. A. RULES	CHORDS	SIZE	LUMBER		
A - D	2x4	DRY	No.2		SPF
F - D	2x4	DRY	No.2		SPF
B - E	2x4	DRY	No.2		SPF
ALL WEBS	2x3	DRY	No.2		SPF
DRY: SEASONED LUMBER.					

PLATES (table is in inches)					
JT	TYPE	PLATES	W	LEN	Y X
B	TMB-I	MT20	3.0	4.0	
C	TMWW-t	MT20	3.0	4.0	1.50 1.75
D	TMV+p	MT20	2.0	4.0	
F	BMVW-t	MT20	3.0	4.0	
G	BMV1+w	MT20	2.0	4.0	

DIMENSIONS, SUPPORTS AND LOADINGS SPECIFIED BY FABRICATOR TO BE VERIFIED BY BUILDING DESIGNER

BEARINGS

	FACTORED GROSS REACTION	MAXIMUM FACTORED GROSS REACTION	INPUT BRG	REQRD BRG
JT	VERT	HORZ	DOWN	HORZ
E	158	0	158	0
G	796	0	796	0

PROVIDE ANCHORAGE AT BEARING JOINT E FOR 150 LBS. FACTORED UPLIFT

UNFACTORED REACTIONS

1ST LCASE	MAX	MIN	COMPONENT REACTIONS	
JT	COMBINED	SNOW	LIVE	PERM. LIVE
E	126	44 / -51	42 / -3	0 / 0
G	578	370 / 0	73 / 0	0 / 0

BEARING MATERIAL TO BE SPF NO.2 OR BETTER AT JOINT(S) E, G

BRACING

TOP CHORD TO BE SHEATHED OR MAX. PURLIN SPACING = 6.25 FT.
MAX. UNBRACED BOTTOM CHORD LENGTH = 6.25 FT OR RIGID CEILING DIRECTLY APPLIED.

ALL PITCH BREAKS AND PERIMETER CORNER JOINTS MUST BE Laterally RESTRAINED.

LOADING

TOTAL LOAD CASES: (5)

CHORDS				WEBS			
MEMB.	MAX. FORCE (LBS)	FACTORED VERT. LOAD (PLF)	LC1 MAX (LC)	MEMB.	MAX. FORCE (LBS)	FACTORED VERT. LOAD (PLF)	LC1 MAX (LC)
FR-TO				FR-TO			
A-B	0 / 41	-124.4	-124.4 0.16 (1)	10.00	C-F	-14 / 494	0.11 (5)
B-C	-16 / 533	-124.4	-124.4 0.24 (5)	6.25	G-C	-540 / 0	0.08 (1)
C-D	-21 / 0	-124.4	-124.4 0.19 (1)	6.25			
F-D	-172 / 0	0.0	0.0 0.03 (1)	7.81			
B-G	-484 / 14	-39.2	-39.2 0.16 (2)	6.25			
G-F	-484 / 14	-39.2	-39.2 0.17 (1)	6.25			
F-E	0 / 0	-39.2	-39.2 0.17 (1)	10.00			

CANTILEVER ANALYSIS HAS BEEN CONSIDERED IN THIS DESIGN

DESIGN CRITERIA

SPECIFIED LOADS:

TOP CH.	LL = 34.8	PSF
	DL = 8.0	PSF
BOT CH.	LL = 10.5	PSF
	DL = 7.3	PSF
TOTAL LOAD	= 60.6	PSF

SPACING = 24.0 IN. C/C

THIS TRUSS IS DESIGNED FOR RESIDENTIAL OR SMALL BUILDING REQUIREMENTS OF PART 9, NBCC 2015

THIS DESIGN COMPLIES WITH:

- PART 9 OF BCBC 2018, ABC 2019
- PART 9 OF OBC 2012 (2019 AMENDMENT)
- CSA 086-14
- TPIC 2014

DESIGN ASSUMPTIONS

-OVERHANG NOT TO BE ALTERED OR CUT OFF.

(55 % OF 48.1 P.S.F. G.S.L. PLUS 8.4 P.S.F. RAIN LOAD)
EQUALS 34.8 P.S.F. SPECIFIED ROOF LIVE LOAD

ALLOWABLE DEFL.(LL)= L/360 (0.19")
CALCULATED VERT. DEFL.(LL) = L/ 999 (0.02")
ALLOWABLE DEFL.(TL)= L/360 (0.19")
CALCULATED VERT. DEFL.(TL) = L/ 999 (0.03")

CANTILEVER DEFLECTION:

ALLOWABLE DEFL.(LL)= L/120 (0.19")
CALCULATED VERT. DEFL.(LL) = L/ 999 (0.01")
ALLOWABLE DEFL.(TL)= L/120 (0.19")
CALCULATED VERT. DEFL.(TL) = L/ 890 (0.02")

CSI: TC=0.24/1.00 (B-C-5) , BC=0.17/1.00 (F-G-1) ,
WB=0.11/1.00 (C-F-5) , SSI=0.17/1.00 (C-D-1)

DOL LUMBER=1.00 NAIL=1.00 LS BEND=1.10 COMP=1.10
SHEAR=1.10 TENS= 1.10

COMPANION LIVE LOAD FACTOR = 1.00

AUTOSOLVE LEFT HEEL ONLY

TRUSS PLATE MANUFACTURER IS NOT RESPONSIBLE FOR QUALITY CONTROL IN THE TRUSS MANUFACTURING PLANT .

NAIL VALUES

PLATE	GRIP(DRY)	SHEAR	SECTION
(PSI)	(PLI)	(PLI)	(PLI)
MAX	MIN	MAX	MIN
MT20	650	371	1747

PLATE PLACEMENT TOL. = 0.250 inches

PLATE ROTATION TOL. = 5.0 Deg.

JSI GRIP= 0.79 (F) (INPUT = 0.90)
JSI METAL= 0.20 (C) (INPUT = 1.00)




These plans have been reviewed for use with the corrections as noted. No other changes may be made without written approval of the Building Standards Branch. All work must comply with Zoning By-Law 2018-043, as amended, and the Ontario Building Code, as amended. These approved documents must be kept on site at all times. The building permit must be clearly posted on site at all times.

Discipline	Reviewer	BCIN	Date
Building Code	H. Authier	43236	2021-02-24
Sewage System			
Zoning			



READ ALL NOTES ON THIS PAGE AND ON ENGINEERING NOTE PAGE ENP-1. THIS NOTE PAGE IS AN INTEGRAL PART OF THIS DRAWING AS IT CONTAINS SPECIFICATIONS AND CRITERIA USED IN THE DESIGN OF THIS COMPONENT.

Version 8.420 S Oct 9 2020 Mitek Industries, Inc. Sun Dec 20 11:35:43 2020 Page 1
ID:mCCrvcxnlfAPc08wPaInt0zHzlx-G0Jsa4ttGr1?vbqo6eBHkmkDZqPdVHHvO7oOc6y75



LUMBER
N. L. G. A. RULES

CHORDS	SIZE	LUMBER	DESCR.
A - D	2x4	DRY No.2	SPF
D - F	2x4	DRY No.2	SPF
F - I	2x4	DRY No.2	SPF
J - B	2x4	DRY No.2	SPF
J - H	2x4	DRY No.2	SPF
K - M	2x4	DRY No.2	SPF
M - J	2x4	DRY No.2	SPF
ALL WEBS	2x3	DRY No.2	SPF

EXCEPT
DRY: SEASONED LUMBER.

PLATES (table is in inches)

JT	TYPE	PLATES	W	LEN	Y	X
B	TMVW+p	MT20	6.0	4.0	2.25	2.25
C	TMVW-t	MT20	3.0	4.0	1.50	1.50
D	TTWW+m	MT20	5.0	6.0	Edge	1.75
E	TMW+w	MT20	2.0	4.0		
F	TTWW+m	MT20	5.0	6.0	Edge	1.75
G	TMVW-t	MT20	3.0	4.0	1.50	1.50
H	TMVW+p	MT20	6.0	6.0	2.25	2.25
J	BMV1+p	MT20	3.0	4.0	2.00	
K	BMVW-t	MT20	4.0	6.0	1.75	1.75
L	BMVW-t	MT20	3.0	4.0		
M	BS-t	MT20	3.0	6.0		
N	BMVW-t	MT20	3.0	8.0		
O	BMVW-t	MT20	3.0	4.0		
P	BMVW-t	MT20	4.0	6.0	1.75	1.75
Q	BMV1+p	MT20	3.0	4.0	2.00	0.50

Edge - INDICATES REFERENCE CORNER OF PLATE TOUCHES
EDGE OF CHORD.

DIMENSIONS, SUPPORTS AND LOADINGS SPECIFIED BY FABRICATOR TO BE VERIFIED BY BUILDING DESIGNER

BEARINGS

FACTORED GROSS REACTION	MAXIMUM FACTORED GROSS REACTION	INPUT BRG	REQD BRG
JT VERT	DOWN	UPLIFT	IN-SX
Q 2544	0	2544	0
J 2544	0	2544	0

UNFACTORED REACTIONS

1ST LCASE	MAX	MIN	COMPONENT REACTIONS
JT COMBINED	SNOW	LIVE	PERM.LIVE WIND DEAD SOIL
Q 1875	1105 / 0	305 / 0	0 / 0 0 / 0 486 / 0 0 / 0
J 1875	1105 / 0	304 / 0	0 / 0 0 / 0 486 / 0 0 / 0

BEARING MATERIAL TO BE SPF NO.2 OR BETTER AT JOINT(S) Q, J

BRACING
TOP CHORD TO BE SHEATHED OR MAX. PURLIN SPACING = 3.72 FT.
MAX. UNBRACED BOTTOM CHORD LENGTH = 10.00 FT OR RIGID CEILING DIRECTLY APPLIED.
ALL PITCH BREAKS AND PERIMETER CORNER JOINTS MUST BE LATERALLY RESTRAINED.

LOADING
TOTAL LOAD CASES: (4)

CHORDS				WEBS			
MEMB.	MAX. FACTORED FORCE (LBS)	FACTORED VERT. LOAD (PLF)	FACTORED LC1 MAX CSI (LC)	UNBRACED LENGTH	MEMB.	MAX. FACTORED FORCE (LBS)	MAX. FACTORED CSI (LC)
FR-TO		FROM	TO		FR-TO		
A-B	0 / 47	-124.4	-124.4	0.17 (1)	10.00	P-C	-287 / 86
B-C	-2753 / 0	-124.4	-124.4	0.50 (1)	3.72	C-O	-407 / 0
C-D	-2472 / 0	-124.4	-124.4	0.47 (1)	3.92	O-D	0 / 461
D-E	-2264 / 0	-124.4	-124.4	0.40 (1)	4.12	D-N	0 / 513
E-F	-2264 / 0	-124.4	-124.4	0.40 (1)	4.12	N-E	-702 / 0
F-G	-2472 / 0	-124.4	-124.4	0.47 (1)	3.92	N-F	0 / 513
G-H	-2753 / 0	-124.4	-124.4	0.50 (1)	3.72	L-F	0 / 461
H-I	0 / 47	-124.4	-124.4	0.17 (1)	10.00	L-G	-407 / 0
Q-B	-2461 / 0	0.0	0.0	0.25 (1)	5.46	K-G	-287 / 86
J-H	-2461 / 0	0.0	0.0	0.25 (1)	5.46	B-P	0 / 2376
						K-H	0 / 2376
Q-P	0 / 0	-39.2	-39.2	0.18 (3)	10.00		
P-O	0 / 2323	-39.2	-39.2	0.48 (1)	10.00		
O-N	0 / 2027	-39.2	-39.2	0.42 (1)	10.00		
N-M	0 / 2027	-39.2	-39.2	0.42 (1)	10.00		
M-L	0 / 2027	-39.2	-39.2	0.42 (1)	10.00		
L-K	0 / 2323	-39.2	-39.2	0.48 (1)	10.00		
K-J	0 / 0	-39.2	-39.2	0.18 (3)	10.00		

DESIGN CRITERIA

SPECIFIED LOADS:

TOP CH.	LL = 34.8	PSF
	DL = 8.0	PSF
BOT CH.	LL = 10.5	PSF
	DL = 7.3	PSF
TOTAL LOAD	= 60.6	PSF

SPACING = 24.0 IN. C/C

LOADING IN FLAT SECTION BASED ON A SLOPE OF 2.00/12 MINIMUM

THIS TRUSS IS DESIGNED FOR RESIDENTIAL OR SMALL BUILDING REQUIREMENTS OF PART 9, NBCC 2015

THIS DESIGN COMPLIES WITH:
- PART 9 OF BCBC 2018, ABC 2019
- PART 9 OF OBC 2012 (2019 AMENDMENT)
- CSA 086-14
- TPIC 2014

(55 % OF 48.1 P.S.F. G.S.L. PLUS 8.4 P.S.F. RAIN LOAD)
EQUALS 34.8 P.S.F. SPECIFIED ROOF LIVE LOAD

ALLOWABLE DEFL.(LL)= L/360 (0.97")
CALCULATED VERT. DEFL.(LL) = L/ 999 (0.10")
ALLOWABLE DEFL.(TL)= L/360 (0.97")
CALCULATED VERT. DEFL.(TL) = L/ 999 (0.16")

CSI: TC=0.50/1.00 (B-C-1) , BC=0.48/1.00 (O-P-1) ,
WB=0.84/1.00 (E-N-1) , SSI=0.28/1.00 (D-E-1)

DOL LUMBER=1.00 NAIL=1.00 LS BEND=1.10 COMP=1.10
SHEAR=1.10 TENS= 1.10

COMPANION LIVE LOAD FACTOR = 1.00

TRUSS PLATE MANUFACTURER IS NOT RESPONSIBLE FOR QUALITY CONTROL IN THE TRUSS MANUFACTURING PLANT .

NAIL VALUES
PLATE GRIP(DRY) SHEAR SECTION
(PSI) (PLI) (PLI)
MAX MIN MAX MIN MAX MIN
MT20 650 371 1747 788 1987 1873

PLATE PLACEMENT TOL. = 0.250 inches

PLATE ROTATION TOL. = 5.0 Deg.

JSI GRIP= 0.89 (H) (INPUT = 0.80)
JSI METAL = 0.63 (M) (INPUT = 1.00)



READ ALL NOTES ON THIS PAGE AND ON ENGINEERING NOTE PAGE ENP-1. THIS NOTE PAGE IS AN INTEGRAL PART OF THIS DRAWING AS IT CONTAINS SPECIFICATIONS AND CRITERIA USED IN THE DESIGN OF THIS COMPONENT.




These plans have been reviewed for use with the corrections as noted. No other changes may be made without written approval of the Building Standards Branch. All work must comply with Zoning By-Law 2018-043, as amended, and the Ontario Building Code, as amended. These approved documents must be kept on site at all times. The building permit must be clearly posted on site at all times.

Discipline	Reviewer	BCIN	Date
Building Code	H. Authier	43236	2021-02-24
Sewage System			
Zoning			



Version 8.420 S Oct 9 2020 Mitek Industries, Inc. Sun Dec 20 11:35:44 2020 Page 1
ID:mCCrycxnlfAPc08wPalNt0zHzlx-kCtqoQV189sWIF 1LIWGzGKSEkEelu2dnXx92y75



TOTAL WEIGHT = 129 lb
[M]F

LUMBER				
N. L. G. A. RULES				
CHORDS		SIZE	LUMBER	DESCR.
A - C	2x4	DRY	No.2	SPF
C - E	2x4	DRY	No.2	SPF
E - F	2x4	DRY	No.2	SPF
F - H	2x4	DRY	No.2	SPF
H - J	2x4	DRY	No.2	SPF
Q - B	2x4	DRY	No.2	SPF
K - I	2x4	DRY	No.2	SPF
Q - N	2x4	DRY	No.2	SPF
N - K	2x4	DRY	No.2	SPF
ALL WEBS EXCEPT	2x3	DRY	No.2	SPF
DRY: SEASONED LUMBER				

PLATES (table is in inches)						
JT	TYPE	PLATES	W	LEN	Y	X
B	TMVW-p	MT20	6.0	6.0	2.25	2.50
C	TS-t	MT20	3.0	6.0		
D	TMVW-t	MT20	3.0	4.0	1.50	1.50
E	TTWW-m	MT20	4.0	6.0	1.75	2.50
F	TTWW-m	MT20	4.0	4.0	2.00	1.75
G	TMVW-t	MT20	3.0	4.0	1.50	1.50
H	TS-t	MT20	3.0	6.0		
I	TMVW-p	MT20	6.0	6.0	2.25	2.50
K	BMV1+p	MT20	3.0	4.0	2.00	
L	BMVW-t	MT20	4.0	5.0	1.50	1.50
M	BMVW-t	MT20	4.0	6.0		
N	BS-t	MT20	3.0	6.0		
O	BMVW-t	MT20	3.0	4.0	1.75	1.50
P	BMVW-t	MT20	4.0	5.0	1.50	1.50
Q	BMV1+p	MT20	3.0	4.0	2.00	0.50

DIMENSIONS, SUPPORTS AND LOADINGS SPECIFIED BY FABRICATOR TO BE VERIFIED BY BUILDING DESIGNER

BEARINGS					
	FACTORED GROSS REACTION	MAXIMUM FACTORED GROSS REACTION	INPUT BRG	REQRD BRG	
JT	VERT	HORZ	DOWN	HORZ	UPLIFT IN-SX
Q	2544	0	2544	0	0
K	2544	0	2544	0	0

UNFACTORED REACTIONS							
1ST LCASE MAX/MIN COMPONENT REACTIONS							
JT	COMBINED	SNOW	LIVE	PERM.LIVE	WIND	DEAD	SOIL
Q	1875	1105 / 0	305 / 0	0 / 0	0 / 0	466 / 0	0 / 0
K	1875	1105 / 0	305 / 0	0 / 0	0 / 0	466 / 0	0 / 0

BEARING MATERIAL TO BE SPF NO.2 OR BETTER AT JOINT(S) Q, K

BRACING
TOP CHORD TO BE SHEATHED OR MAX. PURLIN SPACING = 3.37 FT.
MAX. UNBRACED BOTTOM CHORD LENGTH = 10.00 FT OR RIGID CEILING DIRECTLY APPLIED.

ALL PITCH BREAKS AND PERIMETER CORNER JOINTS MUST BE Laterally RESTRAINED.

LOADING
TOTAL LOAD CASES: (4)

CHORDS				WEBS			
MEMB.	MAX. FACTORED FORCE (LBS)	FACTORED VERT. LOAD (PLF)	FACTORED LC1 MAX CSI (LC)	UNBRACED LENGTH	MEMB.	MAX. FACTORED FORCE (LBS)	MAX. FACTORED CSI (LC)
FR-TO					FR-TO		
A-B	0 / 47	-124.4	-124.4 0.17 (1)	10.00	P-D	-159 / 160	0.07 (1)
B-C	-2777 / 0	-124.4	-124.4 0.75 (1)	3.37	D-O	-856 / 0	0.82 (1)
C-D	-2777 / 0	-124.4	-124.4 0.75 (1)	3.37	O-E	0 / 636	0.14 (1)
D-E	-2281 / 0	-124.4	-124.4 0.67 (1)	3.77	E-M	0 / 2	0.00 (1)
E-F	-1862 / 0	-124.4	-124.4 0.50 (1)	4.33	M-F	0 / 636	0.14 (1)
F-G	-2282 / 0	-124.4	-124.4 0.67 (1)	3.77	M-G	-854 / 0	0.82 (1)
G-H	-2777 / 0	-124.4	-124.4 0.75 (1)	3.37	L-G	-161 / 159	0.07 (1)
H-I	-2777 / 0	-124.4	-124.4 0.75 (1)	3.37	B-P	0 / 2388	0.54 (1)
I-J	0 / 47	-124.4	-124.4 0.17 (1)	10.00	L-I	0 / 2388	0.54 (1)
Q-B	-2447 / 0	0.0	0.0 0.25 (1)	5.47			
K-I	-2447 / 0	0.0	0.0 0.25 (1)	5.47			
Q-P	0 / 0	-39.2	-39.2 0.27 (3)	10.00			
P-O	0 / 2351	-39.2	-39.2 0.56 (2)	10.00			
O-N	0 / 1861	-39.2	-39.2 0.43 (1)	10.00			
N-M	0 / 1861	-39.2	-39.2 0.43 (1)	10.00			
M-L	0 / 2351	-39.2	-39.2 0.56 (2)	10.00			
L-K	0 / 0	-39.2	-39.2 0.27 (3)	10.00			

DESIGN CRITERIA

SPECIFIED LOADS:
TOP CH. LL = 34.8 PSF
DL = 8.0 PSF
BOT CH. LL = 10.5 PSF
DL = 7.3 PSF
TOTAL LOAD = 60.6 PSF

SPACING = 24.0 IN. C/C

LOADING IN FLAT SECTION BASED ON A SLOPE OF 2.00/12 MINIMUM

THIS TRUSS IS DESIGNED FOR RESIDENTIAL OR SMALL BUILDING REQUIREMENTS OF PART 9, NBCC 2015

THIS DESIGN COMPLIES WITH:
- PART 9 OF CBC 2018, ABC 2019
- PART 9 OF OBC 2012 (2019 AMENDMENT)
- CSA 086-14
- TPIC 2014

(55 % OF 48.1 P.S.F. G.S.L. PLUS 8.4 P.S.F. RAIN LOAD)
EQUALS 34.8 P.S.F. SPECIFIED ROOF LIVE LOAD

ALLOWABLE DEFL.(LL)= L/360 (0.97")
CALCULATED VERT. DEFL.(LL) = L/999 (0.10")
ALLOWABLE DEFL.(TL)= L/360 (0.97")
CALCULATED VERT. DEFL.(TL) = L/999 (0.18")

CSI: TC=0.75/1.00 (B-D-1) , BC=0.56/1.00 (O-P-2) ,
WB=0.82/1.00 (D-O-1) , SSI=0.30/1.00 (B-D-1)

DOL LUMBER=1.00 NAIL=1.00 LS BEND=1.10 COMP=1.10
SHEAR=1.10 TENS= 1.10

COMPANION LIVE LOAD FACTOR = 1.00

TRUSS PLATE MANUFACTURER IS NOT RESPONSIBLE FOR QUALITY CONTROL IN THE TRUSS MANUFACTURING PLANT .

NAIL VALUES
PLATE GRIP(DRY) SHEAR SECTION (PSI) (PLI) (PLI)
MAX MIN MAX MIN MAX MIN
MT20 650 371 1747 768 1967 1873

PLATE PLACEMENT TOL. = 0.250 inches

PLATE ROTATION TOL. = 5.0 Deg.

JSI GRIP= 0.89 (Q) (INPUT = 0.90)
JSI METAL = 0.67 (P) (INPUT = 1.00)




READ ALL NOTES ON THIS PAGE AND ON ENGINEERING NOTE PAGE ENP-1. THIS NOTE PAGE IS AN INTEGRAL PART OF THIS DRAWING AS IT CONTAINS SPECIFICATIONS AND CRITERIA USED IN THE DESIGN OF THIS COMPONENT.



These plans have been reviewed for use with the corrections as noted. No other changes may be made without written approval of the Building Standards Branch. All work must comply with Zoning By-Law 2018-043, as amended, and the Ontario Building Code, as amended. These approved documents must be kept on site at all times. The building permit must be clearly posted on site at all times.

Discipline	Reviewer	BCIN	Date
Building Code	H. Authier	43236	2021-02-24
Sewage System			
Zoning			





TOTAL WEIGHT = 149 lb

LUMBER					DESCR.	
CHORDS	SIZE	LUMBER	SIZE			
A - C	2x4	DRY	2100F 1.8E		SPF	
C - E	2x4	DRY	2100F 1.8E		SPF	
E - F	2x4	DRY	No.2		SPF	
F - H	2x4	DRY	2100F 1.8E		SPF	
H - J	2x4	DRY	2100F 1.8E		SPF	
P - B	2x4	DRY	No.2		SPF	
K - I	2x4	DRY	No.2		SPF	
P - M	2x4	DRY	No.2		SPF	
M - K	2x4	DRY	No.2		SPF	
ALL WEBS EXCEPT					SPF	
O - D	2x3	DRY	No.2		SPF	
L - G	2x3	DRY	No.2		SPF	
B - O	2x3	DRY	No.2		SPF	
L - I	2x3	DRY	No.2		SPF	

DRY: SEASONED LUMBER.

PLATES (table is in inches)						
JT TYPE	PLATES	W	LEN	Y	X	
B TMVW-p	MT20	6.0	6.0	2.25	2.50	
C TS-t	MT20	3.0	8.0			
D TMW+w	MT20	2.0	4.0			
E TTWW+m	MT20	5.0	5.0	1.75	2.25	
F TTWW+m	MT20	5.0	5.0	1.75	2.25	
G TMW+w	MT20	2.0	4.0			
H TS-t	MT20	3.0	8.0			
I TMVW-p	MT20	6.0	6.0	2.25	2.50	
K BMV1+p	MT20	3.0	4.0	2.00		
L BMWWW-t	MT20	4.0	8.0	1.50	2.00	
M BS-t	MT20	3.0	6.0			
N BMWW-t	MT20	3.0	4.0			
O BMWWW-t	MT20	4.0	8.0	1.50	3.50	
P BMV1+p	MT20	3.0	4.0	2.00	0.50	

DIMENSIONS, SUPPORTS AND LOADINGS SPECIFIED BY FABRICATOR TO BE VERIFIED BY BUILDING DESIGNER

BEARINGS		FACTORED GROSS REACTION	MAXIMUM FACTORED GROSS REACTION	INPUT BRG	REQRD BRG
JT	VERT	HORZ	DOWN	HORZ	UPLIFT
P	2544	0	2544	0	0
K	2544	0	2544	0	0

UNFACTORED REACTIONS		1ST LCASE	MAX/MIN COMPONENT REACTIONS
JT	COMBINED	SNOW	LIVE
P	1875	1105 / 0	305 / 0
K	1875	1105 / 0	305 / 0

BEARING MATERIAL TO BE SPF NO.2 OR BETTER AT JOINT(S) P, K

BRACING
TOP CHORD TO BE SHEATHED OR MAX. PURLIN SPACING = 4.31 FT.
MAX. UNBRACED BOTTOM CHORD LENGTH = 10.00 FT OR RIGID CEILING DIRECTLY APPLIED.

ALL PITCH BREAKS AND PERIMETER CORNER JOINTS MUST BE Laterally RESTRAINED.

LOADING
TOTAL LOAD CASES: (4)

CHORDS				WEBS			
MEMB.	MAX. FACTORED FORCE (LBS)	FACTORED VERT. LOAD (PLF)	LC1 MAX (LC)	MEMB.	MAX. FACTORED FORCE (LBS)	MAX. UNBRACED LENGTH (FT)	MAX. FACTORED FORCE (LBS)
FR-TO		FROM	TO	FR-TO			
A-B	0 / 47	-124.4	-124.4 0.11 (1)	10.00	O-D	-1051 / 0	0.61 (1)
B-C	-2780 / 0	-124.4	-124.4 0.61 (1)	4.36	O-E	0 / 1205	0.19 (1)
C-D	-2780 / 0	-124.4	-124.4 0.61 (1)	4.36	E-N	0 / 175	0.03 (3)
D-E	-2860 / 0	-124.4	-124.4 0.61 (1)	4.31	N-F	0 / 184	0.03 (3)
E-F	-1682 / 0	-124.4	-124.4 0.06 (1)	5.00	F-L	0 / 1196	0.19 (1)
F-G	-2858 / 0	-124.4	-124.4 0.61 (1)	4.32	L-G	-1051 / 0	0.61 (1)
G-H	-2778 / 0	-124.4	-124.4 0.61 (1)	4.36	B-O	0 / 2387	0.54 (1)
H-I	-2778 / 0	-124.4	-124.4 0.61 (1)	4.36	L-I	0 / 2388	0.54 (1)
I-J	0 / 47	-124.4	-124.4 0.11 (1)	10.00			
P-B	-2432 / 0	0.0	0.0 0.25 (1)	5.49			
K-I	-2431 / 0	0.0	0.0 0.25 (1)	5.49			
P-O	0 / 0	-39.2	-39.2 0.40 (3)	10.00			
O-N	0 / 1671	-39.2	-39.2 0.58 (2)	10.00			
N-M	0 / 1675	-39.2	-39.2 0.56 (2)	10.00			
M-L	0 / 1675	-39.2	-39.2 0.56 (2)	10.00			
L-K	0 / 0	-39.2	-39.2 0.39 (3)	10.00			

DESIGN CRITERIA

SPECIFIED LOADS:
TOP CH. LL = 34.8 PSF
DL = 8.0 PSF
BOT CH. LL = 10.5 PSF
DL = 7.3 PSF
TOTAL LOAD = 60.6 PSF

SPACING = 24.0 IN. C/C

LOADING IN FLAT SECTION BASED ON A SLOPE OF 2.00/12 MINIMUM

THIS TRUSS IS DESIGNED FOR RESIDENTIAL OR SMALL BUILDING REQUIREMENTS OF PART 9, NBCC 2015

THIS DESIGN COMPLIES WITH:
- PART 9 OF BCBC 2018, ABC 2019
- PART 9 OF OBC 2012 (2019 AMENDMENT)
- CSA 086-14
- TPIC 2014

(55% OF 48.1 P.S.F. G.S.L. PLUS 8.4 P.S.F. RAIN LOAD)
EQUALS 34.8 P.S.F. SPECIFIED ROOF LIVE LOAD

ALLOWABLE DEFL.(LL)= L/360 (0.97")
CALCULATED VERT. DEFL.(LL) = L/999 (0.12")
ALLOWABLE DEFL.(TL)= L/360 (0.97")
CALCULATED VERT. DEFL.(TL) = L/999 (0.20")

CSI: TC=0.61/1.00 (D-E-1), BC=0.58/1.00 (N-O-2),
WB=0.61/1.00 (G-L-1), SSI=0.35/1.00 (G-L-1)

DOL LUMBER=1.00 NAIL=1.00 LS BEND=1.10 COMP=1.10
SHEAR=1.10 TENS= 1.10

COMPANION LIVE LOAD FACTOR = 1.00

TRUSS PLATE MANUFACTURER IS NOT RESPONSIBLE FOR QUALITY CONTROL IN THE TRUSS MANUFACTURING PLANT.

NAIL VALUES
PLATE GRIP(DRY) SHEAR SECTION (PSI) (PLI) (PLI)
MAX MIN MAX MIN MAX MIN
MT20 650 371 1747 768 1987 1873

PLATE PLACEMENT TOL. = 0.250 inches

PLATE ROTATION TOL. = 5.0 Deg.

JSI GRIP= 0.88 (P) (INPUT = 0.80)
JSI METAL = 0.56 (M) (INPUT = 1.00)





These plans have been reviewed for use with the corrections as noted. No other changes may be made without written approval of the Building Standards Branch. All work must comply with Zoning By-Law 2018-043, as amended, and the Ontario Building Code, as amended. These approved documents must be kept on site at all times. The building permit must be clearly posted on site at all times.

Discipline	Reviewer	BCIN	Date
Building Code	H. Aulst	43236	2021-02-24
Sewage System			
Zoning			



READ ALL NOTES ON THIS PAGE AND ON ENGINEERING NOTE PAGE ENP-1. THIS NOTE PAGE IS AN INTEGRAL PART OF THIS DRAWING AS IT CONTAINS SPECIFICATIONS AND CRITERIA USED IN THE DESIGN OF THIS COMPONENT.

- 1) ENSURE TRUSS HAS BEEN DESIGNED WITH ADDITIONAL TOP CHORD DEAD LOAD EQUAL TO OR GREATER THAN WEIGHT OF SOLAR PANELS BEING INSTALLED
- 2) ATTACH SOLAR PANELS TO EACH TRUSS LOCATED UNDER THE SOLAR PANELS (I.E. @ 24" C/C PERPENDICULAR TO THE TRUSS DIRECTION)
- 3) ATTACH A SPF No.1/2 SCAB OF THE SAME SIZE AS TRUSS CHORD ON ONE SIDE ALONG THE FULL LENGTH OF THE MEMBER UNDER THE SOLAR PANELS USING 2 ROWS OF 3" WIRE NAILS @ 6" C/C
- 4) ATTACH SOLAR PANELS TO SCAB AT A MAXIMUM SPACING OF 48" C/C ALONG THE MEMBER (PARALLEL TO TRUSS DIRECTION) AS PER MANUFACTURER'S INSTRUCTIONS
- 5) DO NOT USE LAG SCREWS IN TRUSS MEMBERS. LAG SCREWS SHOULD ATTACH TO SCABS ONLY
- 6) MAXIMUM NUMBER OF SCAB SPLICES IS TWO
- 7) THIS DETAIL IS APPLICABLE TO PART 9 BUILDINGS ONLY



These plans have been reviewed for use with the correction as noted. No other changes may be made without written approval of the Building Department. The Building Department is not responsible for the accuracy of the information provided on these plans. The building permit must be clearly posted on site at all times.

East Gwillimbury
Building Department (905) 882-1111 ext. 2222

Discipline	Reviewed	Date
Building Code	M. Adami	2020/02/24
Seismic System		
Zoning		

NE1220-147
GREENPARK - TRINAR HALL
- BRENTWOOD 4 EL 2

Detail for Installation of Solar Panels - Scab Method



NE1220-147
GREENPARK - TRINAR HALL -
BRENTWOOD 4 EL 2



BEARING ANCHORAGE BY TOE-NAILS FOR LATERAL CAPACITY

B97791H1

NAIL TYPE	LENGTH (IN)	DIAMETER (IN)	NAIL LATERAL CAPACITY (LB)	
			S-P-F	D. FIR
COMMON WIRE	3.00	0.144	132	147
	3.25	0.144	132	147
	3.50	0.160	159	177
COMMON SPIRAL	3.00	0.122	97	108
	3.25	0.122	97	108
	3.50	0.152	145	162

NOTES:

1. Rafter and ceiling members may be anchored to top and bottom chords of girder truss by toe-nailing rafter and ceiling members to girder chords provided the reaction does not exceed the lateral capacities in the table. Hangers (specified by others) are required for reactions higher than the maximum toe-nail capacity. Reactions are based on factored loads.
2. Toe nail capacities shown in the table are for **one** toe-nail. For additional toe-nails multiply values in table by the number of toe-nails used. Toe-nail capacities take into account toe-nailing factor J_A in CSA O86-14, section 12.9.4.1.
3. For 9- 3/4 gauge 3.25" common wire gun nails (diameter = 0.120") use 3" common spiral nail values.
4. Maximum number of toe-nails allowed depends on the lumber size & species to be toe-nailed to supporting member and nail diameter, as shown in tables below.
5. Nail values in table are based on the following relative lumber densities: G = 0.42 (SPF), G = 0.49 (D. Fir).
6. Toe-nails shall be driven at approximately 1/3 the nail length from the edge of the joist/truss chord and driven at an angle of 30° to the grain of the member (See next page for nailing on bearing plate).
7. For loads due to **wind** the nail lateral capacity in this table may be multiplied by 1.15 (K_D factor).
8. Lumber must be dry (< 19% moisture content) at the time of nail installation.
9. Nail values in this table comply with CSA O86-14, section 12.9.4
10. This design is not valid after March 31, 2021.



TOE-NAIL INSTALLATION

Nail type	Common wire	Common spiral	Common wire	Common spiral
Nail dia. (in)	0.160	0.152	0.144	0.122
	(3.5" nail)		(3" and 3.25" nail)	
LUMBER SIZE	MAXIMUM NUMBER OF TOE-NAILS			
2X4 SPF	2	2	3	3
2X4 D. Fir	2	2	2	2
2X6 SPF	4	4	4	5
2X6 D. Fir	3	3	3	4

MiTek MiTek Canada Inc
100 Industrial Rd.
Bradford, Ontario L3Z 3G7



Town of
East Gwillimbury
Building Standards Branch BCN #16487

December 2, 2021

These plans have been reviewed for use with the corrections as noted. No other changes may be made without written approval of the Building Standards Branch. All work must comply with Zoning By-Law 2018-043, as amended, and the Ontario Building Code, as amended. These approved documents must be kept on site at all times. The building permit must be clearly posted on site at all times.

Discipline	Reviewer	BCN	Date
Building Code	H. Author	43236	2021-02-24
Sewage System			
Zoning			

PEO
Certificate No. 10889485



NE1220-147
GREENPARK - TRINAR HALL -
BRENTWOOD 4 EL 2

BEARING ANCHORAGE BY TOE-NAILS FOR WIND LOADING

B97791H2



NAIL TYPE	LENGTH (IN)	DIAMETER (IN)	NAIL WITHDRAWAL CAPACITY (LB)	
			S-P-F	D. FIR
COMMON WIRE	3.00	0.144	30	42
	3.25	0.144	32	45
	3.50	0.160	38	52
COMMON SPIRAL	3.00	0.122	26	36
	3.25	0.122	28	40
	3.50	0.152	36	50

Note: If using truss with D. Fir lumber and S-P-F bearing plate, use values in table for S-P-F.



NOTES:

1. Truss chord, rafter, or ceiling members may be anchored to bearing plate by toe-nails, provided that the actual factored uplift force due to **wind** or **earthquake** load does not exceed the withdrawal capacities in the table. Hangers (specified by others) are required for uplift forces that are higher than the maximum toe-nail withdrawal capacity.
2. Toe nail capacities shown in the table are for **one** toe-nail. For additional toe-nails multiply values in table by the number of toe-nails used. Toe-nail capacities take into account toe-nailing factor J_A in CSA O86-14, section 12.9.5.2.
3. For 9- 3/4 gauge 3.25" common wire gun nails (diameter = 0.120") use 3" common spiral nail values.
4. Maximum number of toe-nails allowed depends on the lumber size & species to be toe-nailed to supporting member and nail diameter, as shown in table above.
5. Nail values in table are based on the following relative lumber densities: $G = 0.42$ (SPF), $G = 0.49$ (D. Fir).
6. Toe-nails shall be driven at approximately 1/3 the nail length from the edge of the joist/truss chord and driven at an angle of 30° to the grain of the member (See drawing on detail B37579H1).
7. Lumber must be dry (< 19% moisture content) at the time of nail installation.
8. Nail values in this table comply with CSA O86-14, section 12.9.5
9. This design is not valid after March 31, 2021.

Toe-nailing on 2x6 Bearing Plate



Toe-nailing on 2x4 Bearing Plate




MiTek

MiTek Canada Inc
100 Industrial Rd.
Bradford, Ontario L3Z 3G7



PEO
Certificate No. 10889485



Decem

These plans have been reviewed for use with the corrections as noted. No other changes may be made without written approval of the Building Standards Branch. All work must comply with Zoning By-Law 2018-043, as amended, and the Ontario Building Code, as amended. These approved documents must be kept on site at all times. The building permit must be clearly posted on site at all times.

Discipline	Reviewer	BCIN	Date
Building Code	H. Author	43236	2021-02-24
Sewage System			
Zoning			