

20.130096.000.00.CM

Issue Date: 02/10/21

LAMPONE INVESTMENT INC


ALL CONSTRUCTION SHALL COMPLY WITH THE
ONTARIO BUILDING CODE.

CITY OF MARKHAM

ROOF TRUSS SHOP DRAWINGS


MODEL NAME : PEYTON 2

ELEV 1, 2A, 2B & 3




EL.3-RIGHT : 410150

EL.3-LEFT : 410150



2B: 410148

2A : 410147



ASPHALT SHINGLES
FINISHED OVERHANG: 12"
2x6 EXTERIOR WALLS
2x6 FASCIA BOARD
HEEL: R.T.M.C.


All conventional framing to conform with Part 9 of O.B.C. 2012 (2019 amendment). Roof rafters that cross over or meet trusses to be min. 2x4 SPF #2 @ 24" o/c with a vertical post to the truss at each cross point. Vertical posts longer than 6' to have lateral bracing so that the distance between the post end points and lateral bracing does not exceed 6'.

DESIGN CONFORMS WITH OBC 2012
(2019 amendment) OCCUPANCY:
RESIDENTIAL | PART: 9
Ss = 31.35 psf | Sr = 8.4 psf

DESIGN LOADS:
TCSL = 25.6 psf
TCDL = 6.0 psf
BCLL = 0.0 psf
BCDL = 7.4 psf

HARDWARE:
LUS24 - (O)
LJS26DS - (V)
HGUS26-2 - (XX)
LUS26-2 - (VV)

 DENOTES:
CONVENTIONAL
FRAMING




Job Track: **51453**
Layout ID: **410146**
Plan Log: **202888**

Builder / Location: **GREEN PARK HOMES / MARKHAM**
Project: **LAMPONE INVESTMENTS INC**
Date: 2020-08-19 Designer: **JG**

Model / Elevation: **THE PEYTON 2 / 2A AND 2B** Mitek ver 8.3.3.247
THESE DRAWINGS CONSTITUTE THE PROPERTY OF TAMARACK ROOF TRUSSES INC., SHALL NOT BE REPRODUCED, PUBLISHED, OR REDISTRIBUTED IN ANY MANNER OR UTILIZED FOR ANY PURPOSE OTHER THAN THE MANUFACTURE OF TRUSSES BY TAMARACK ROOF TRUSSES INC AND WILL BE RETRACTED BY TAMARACK ROOF TRUSSES INC IF UTILIZED FOR ANY OTHER PURPOSE.

DELIVERY SHIPLIST




Lumber Yard: TAMARACK LUMBER
 Builder: GREEN PARK HOMES
 Project: LAMPONE INVESTMENTS INC
 Location: MARKHAM
 Model: THE PEYTON 2
 Lot #:
 Elevation: 1 / LEFT OR RIGHT

Job Track: 51453
 PlanLog: 202888
 Layout ID: 410144
 Ref #
 Page: 1 of 2
 Date: 07-27-2020
 Designer:
 Sales Rep: Mario DiCano

Roof Trusses

PROFILE	QTY PLY	MARK TYPE	PITCH	SPAN	HEIGHT	LUMBER	OVERHANG LEFT RIGHT	HEEL HEIGHT LEFT RIGHT	LBS. BFT.	BUNDLE # STACK #	LOAD BY REMARKS
	1 2-ply	T20 Flat Girder	0 /12	23-07-00	4-01-04	2 x 6		4-01-04 4-01-04	248.94 152.00		
	1 2-ply	T20Z Flat Girder	0 /12	23-07-00	4-01-04	2 x 6		4-01-04 4-01-04	248.94 152.00		
	2	T21 Flat	0 /12	23-07-00	5-01-04	2 x 4		5-01-04 5-01-04	197.15 124.33		
	2	T22 Flat	0 /12	23-07-00	6-01-04	2 x 4		6-01-04 6-01-04	210.94 130.00		
	9	T23 Flat	0 /12	23-07-00	7-01-04	2 x 4		7-01-04 7-01-04	1013.22 628.50		
	3	T24 Common	12 /12	13-06-00	8-07-08	2 x 4	1-03-08 1-03-08	1-10-08 1-10-08	209.98 132.00		
	3	T25 Common	12 /12	13-04-00	9-10-08	2 x 4		3-03-08 3-01-08	218.6 137.00		
	1	G26 GABLE	12 /12	8-04-00	6-00-08	2 x 4	1-03-08 1-03-08	1-10-08 1-10-08	44.8 30.67		
	2	G27 GABLE	6 /12	19-07-08	10-11-12	2 x 4	1-03-08	1-02-00 10-11-12	203 128.67		
	1 2-ply	T28 Jack-Closed Girder	6 /12	5-10-08	4-01-04	2 x 4 2 x 6		1-02-00 4-01-04	58.39 37.67		
	12	P20 Common	6 /12	15-06-12	3-10-12	2 x 4		0-01 0-01	536.86 344.00		
	18	J1 Jack-Open	6 /12	5-10-08	4-01-04	2 x 4	1-03-08	1-02-00 4-01-04	302.3 192.00		
	3	J3 Jack-Open	4.5 /12	5-04-08	2-09-12	2 x 4	1-03-08	4-00 2-04-03	43.12 28.00		
	5	J20 Jack-Open	4.5 /12	5-06-08	2-10-08	2 x 4	1-03-08	4-00 2-04-15	73.83 46.67		

DELIVERY SHIPLIST



Lumber Yard: TAMARACK LUMBER
 Builder: GREEN PARK HOMES
 Project: LAMPONE INVESTMENTS INC
 Location: MARKHAM
 Model: THE PEYTON 2
 Lot #:
 Elevation: 1 / LEFT OR RIGHT

Job Track: 51453
 PlanLog: 202888
 Layout ID: 410144
 Ref #
 Page: 2 of 2
 Date: 07-27-2020
 Designer:
 Sales Rep: Mario DiCano

Roof Trusses

PROFILE	QTY PLY	MARK TYPE	PITCH	SPAN	HEIGHT	LUMBER	OVERHANG LEFT RIGHT	HEEL HEIGHT LEFT RIGHT	LBS. BFT.	BUNDLE # STACK #	LOAD BY REMARKS
---------	------------	--------------	-------	------	--------	--------	---------------------------	------------------------------	--------------	---------------------	--------------------


TOTAL # TRUSS= 66 TOTAL BFT OF ALL TRUSSES= 2263.51 BFT. TOTAL WEIGHT OF ALL TRSSES 3610.08 LBS

HARDWARE

QTY	TYPE	MODEL	LENGTH
3	Hardware	LUS24	
1	Hardware	LUS26-2	

TOTAL NUMBER OF ITEMS= 4

DELIVERY SHIPLIST




Lumber Yard: TAMARACK LUMBER
 Builder: GREEN PARK HOMES
 Project: LAMPONE INVESTMENTS INC
 Location: MARKHAM
 Model: THE PEYTON 2
 Lot #:
 Elevation: 2A

Job Track: 51453
 PlanLog: 202888
 Layout ID: 410147
 Ref #
 Page: 1 of 2
 Date: 07-27-2020
 Designer:
 Sales Rep: Mario DiCano

Roof Trusses

PROFILE	QTY PLY	MARK TYPE	PITCH	SPAN	HEIGHT	LUMBER	OVERHANG LEFT RIGHT	HEEL HEIGHT LEFT RIGHT	LBS. BFT.	BUNDLE # STACK #	LOAD BY REMARKS
	1 2-ply	T1 Half Hip Girder	8 /12	23-09-00	4-01-04	2 x 4 2 x 6	1-03-08	1-04-13 4-01-04	221.21 135.33		
	1 2-ply	T1Z Half Hip Girder	8 /12	23-09-00	4-01-04	2 x 4 2 x 6	1-03-08	1-04-13 4-01-04	224.79 136.33		
	2	T2 Half Hip	8 /12	23-09-00	5-01-04	2 x 4	1-03-08	1-04-13 5-01-04	193.94 122.33		
	2	T3 Half Hip	8 /12	23-09-00	6-01-04	2 x 4	1-03-08	1-04-13 6-01-04	209.59 130.67		
	2	T4 Half Hip	8 /12	23-09-00	7-01-04	2 x 4	1-03-08	1-04-13 7-01-04	226.41 144.33		
	2	T5 Half Hip	8 /12	23-09-00	8-01-04	2 x 4	1-03-08	1-04-13 8-01-04	218.4 134.33		
	2	T6 Half Hip	8 /12	23-09-00	9-01-04	2 x 4	1-03-08	1-04-13 9-01-04	229.21 143.00		
	3	T7 Half Hip	8 /12	23-09-00	10-01-04	2 x 4	1-03-08	1-04-13 10-01-04	360.69 224.00		
	5	T8 Common	8 /12	13-06-00	5-10-13	2 x 4	1-03-08 1-03-08	1-04-13 1-04-13	293.15 185.00		
	1	T8S Roof Special	8 /12	13-06-00	5-10-13	2 x 4	1-03-08 1-03-08	1-04-13 1-04-13	64.79 42.00		
	1	T9S Roof Special	8 /12	8-04-00	4-02-02	2 x 4	1-03-08 1-03-08	1-04-13 1-04-13	42.27 28.17		
	1	T12 Hip Girder	8 /12	8-04-00	2-06-00	2 x 4 2 x 6	1-03-08 1-03-08	8-15 8-15	35.86 25.83		
	1 2-ply	T13 Jack-Closed Girder	6 /12	5-10-08	4-01-04	2 x 4 2 x 6		1-02-00 4-01-04	58.39 37.67		
	18	J1 Jack-Open	6 /12	5-10-08	4-01-04	2 x 4	1-03-08	1-02-00 4-01-04	302.3 192.00		

DELIVERY SHIPLIST



Lumber Yard: TAMARACK LUMBER
 Builder: GREEN PARK HOMES
 Project: LAMPONE INVESTMENTS INC
 Location: MARKHAM
 Model: THE PEYTON 2
 Lot #:
 Elevation: 2A

Job Track: 51453
 PlanLog: 202888
 Layout ID: 410147
 Ref #
 Page: 2 of 2
 Date: 07-27-2020
 Designer:
 Sales Rep: Mario DiCano

Roof Trusses

PROFILE	QTY PLY	MARK TYPE	PITCH	SPAN	HEIGHT	LUMBER	OVERHANG LEFT RIGHT	HEEL HEIGHT LEFT RIGHT	LBS. BFT.	BUNDLE # STACK #	LOAD BY REMARKS
	4	J2 Jack-Open	4.5 /12	4-06-08	2-06-00	2 x 4	1-03-08	4-00 2-00-07	49.63 32.00		
	3	J3 Jack-Open	4.5 /12	5-04-08	2-09-12	2 x 4	1-03-08	4-00 2-04-03	43.12 28.00		

TOTAL # TRUSS= 52


TOTAL BFT OF ALL TRUSSES= 1740.99 BFT. TOTAL WEIGHT OF ALL TRSSES 2773.74 LBS

HARDWARE

QTY	TYPE	MODEL	LENGTH
1	Hardware	LUS26-2	
3	Hardware	LUS24	

TOTAL NUMBER OF ITEMS= 4

DELIVERY SHIPLIST




Lumber Yard: TAMARACK LUMBER
 Builder: GREEN PARK HOMES
 Project: LAMPONE INVESTMENTS INC
 Location: MARKHAM
 Model: THE PEYTON 2
 Lot #:
 Elevation: 2B

Job Track: 51453
 PlanLog: 202888
 Layout ID: 410148
 Ref #
 Page: 1 of 2
 Date: 07-27-2020
 Designer:
 Sales Rep: Mario DiCano

Roof Trusses

PROFILE	QTY PLY	MARK TYPE	PITCH	SPAN	HEIGHT	LUMBER	OVERHANG LEFT RIGHT	HEEL HEIGHT LEFT RIGHT	LBS. BFT.	BUNDLE # STACK #	LOAD BY REMARKS
	1 2-ply	T1 Half Hip Girder	8 /12	23-09-00	4-01-04	2 x 4 2 x 6	1-03-08	1-04-13 4-01-04	221.21 135.33		
	2	T2 Half Hip	8 /12	23-09-00	5-01-04	2 x 4	1-03-08	1-04-13 5-01-04	193.94 122.33		
	2	T3 Half Hip	8 /12	23-09-00	6-01-04	2 x 4	1-03-08	1-04-13 6-01-04	209.59 130.67		
	2	T4 Half Hip	8 /12	23-09-00	7-01-04	2 x 4	1-03-08	1-04-13 7-01-04	226.41 144.33		
	2	T5 Half Hip	8 /12	23-09-00	8-01-04	2 x 4	1-03-08	1-04-13 8-01-04	218.4 134.33		
	2	T6 Half Hip	8 /12	23-09-00	9-01-04	2 x 4	1-03-08	1-04-13 9-01-04	229.21 143.00		
	3	T7 Half Hip	8 /12	23-09-00	10-01-04	2 x 4	1-03-08	1-04-13 10-01-04	360.69 224.00		
	2	T8 Common	8 /12	13-06-00	5-10-13	2 x 4	1-03-08 1-03-08	1-04-13 1-04-13	117.26 74.00		
	1	T8S Roof Special	8 /12	13-06-00	5-10-13	2 x 4	1-03-08 1-03-08	1-04-13 1-04-13	64.79 42.00		
	1	T9S Roof Special	8 /12	8-04-00	4-02-02	2 x 4	1-03-08 1-03-08	1-04-13 1-04-13	42.27 28.17		
	4	T10 Common	8 /12	23-09-00	9-05-02	2 x 4	1-03-08	1-04-13 1-07-08	403.69 251.33		
	1	G11 GABLE	8 /12	24-01-00	9-05-02	2 x 4	1-03-08 1-03-08	1-04-13 1-04-13	116.43 74.17		
	1	T12 Hip Girder	8 /12	8-04-00	2-06-00	2 x 4 2 x 6	1-03-08 1-03-08	8-15 8-15	35.86 25.83		
	12	J1 Jack-Open	6 /12	5-10-08	4-01-04	2 x 4	1-03-08	1-02-00 4-01-04	201.53 128.00		

DELIVERY SHIPLIST



Lumber Yard: TAMARACK LUMBER
 Builder: GREEN PARK HOMES
 Project: LAMPONE INVESTMENTS INC
 Location: MARKHAM
 Model: THE PEYTON 2
 Lot #:
 Elevation: 2B

Job Track: 51453
 PlanLog: 202888
 Layout ID: 410148
 Ref #
 Page: 2 of 2
 Date: 07-27-2020
 Designer:
 Sales Rep: Mario DiCano

Roof Trusses

PROFILE	QTY PLY	MARK TYPE	PITCH	SPAN	HEIGHT	LUMBER	OVERHANG LEFT RIGHT	HEEL HEIGHT LEFT RIGHT	LBS. BFT.	BUNDLE # STACK #	LOAD BY REMARKS
	4	J2 Jack-Open	4.5 /12	4-06-08	2-06-00	2 x 4	1-03-08	4-00 2-00-07	49.63 32.00		
	3	J3 Jack-Open	4.5 /12	5-04-08	2-09-12	2 x 4	1-03-08	4-00 2-04-03	43.12 28.00		

TOTAL # TRUSS= 44

TOTAL BFT OF ALL TRUSSES= 1717.49 BFT. TOTAL WEIGHT OF ALL TRSSES 2734.03 LBS

DELIVERY SHIPLIST




Lumber Yard: TAMARACK LUMBER
 Builder: GREEN PARK HOMES
 Project: LAMPONE INVESTMENTS INC
 Location: MARKHAM
 Model: THE PEYTON 2
 Lot #:
 Elevation: 3-LEFT OR RIGHT

Job Track: 51453
 PlanLog: 202888
 Layout ID: 410150
 Ref #
 Page: 1 of 2
 Date: 08-05-2020
 Designer:
 Sales Rep: Mario DiCano

Roof Trusses

PROFILE	QTY PLY	MARK TYPE	PITCH	SPAN	HEIGHT	LUMBER	OVERHANG LEFT RIGHT	HEEL HEIGHT LEFT RIGHT	LBS. BFT.	BUNDLE # STACK #	LOAD BY REMARKS
	1 2-ply	T30 Half Hip Girder	6 /12	23-09-00	4-01-04	2 x 4 2 x 6	1-03-08	1-02-00 4-01-04	223.61 138.33		
	1 2-ply	T30Z Half Hip Girder	6 /12	23-09-00	4-01-04	2 x 4 2 x 6	1-03-08	1-02-00 4-01-04	223.61 138.33		
	2	T31 Half Hip	6 /12	23-09-00	5-01-04	2 x 4	1-03-08	1-02-00 5-01-04	195.92 122.00		
	2	T32 Half Hip	6 /12	23-09-00	6-01-04	2 x 4	1-03-08	1-02-00 6-01-04	196.73 122.33		
	2	T33 Half Hip	6 /12	23-09-00	7-01-04	2 x 4	1-03-08	1-02-00 7-01-04	206.87 127.67		
	2	T34 Half Hip	6 /12	23-09-00	8-01-04	2 x 4	1-03-08	1-02-00 8-01-04	218.08 135.33		
	2	T35 Half Hip	6 /12	23-09-00	9-01-04	2 x 4	1-03-08	1-02-00 9-01-04	216.08 134.67		
	3	T36 Half Hip	6 /12	23-09-00	10-01-04	2 x 4	1-03-08	1-02-00 10-01-04	347.76 212.50		
	1	T37 Hip Girder	6 /12	13-06-00	3-07-04	2 x 4	1-03-08 1-03-08	1-02-00 1-02-00	53.45 35.50		
	3	T38 Common	6 /12	13-06-00	6-00-08	2 x 4	1-03-08 1-03-08	2-08-00 2-08-00	184.93 119.00		
	1	T39 Hip Girder	6 /12	8-04-00	1-07-04	2 x 4	1-03-08 1-03-08	1-02-00 1-02-00	33.55 24.00		
	1 2-ply	T40 Jack-Closed Girder	6 /12	5-10-08	4-01-04	2 x 4 2 x 6		1-02-00 4-01-04	58.39 37.67		
	1 2-ply	T40Z Jack-Closed Girder	6 /12	5-10-08	4-01-04	2 x 4 2 x 6		1-02-00 4-01-04	58.39 37.67		
	1 2-ply	T41 Flat Girder	0 /12	7-02-00	2-03-08	2 x 4 2 x 6		2-03-08 2-03-08	63.11 42.00		

DELIVERY SHIPLIST



Lumber Yard: TAMARACK LUMBER
 Builder: GREEN PARK HOMES
 Project: LAMPONE INVESTMENTS INC
 Location: MARKHAM
 Model: THE PEYTON 2
 Lot #:
 Elevation: 3-LEFT OR RIGHT

Job Track: 51453
 PlanLog: 202888
 Layout ID: 410150
 Ref #
 Page: 2 of 2
 Date: 08-05-2020
 Designer:
 Sales Rep: Mario DiCano

Roof Trusses

PROFILE	QTY PLY	MARK TYPE	PITCH	SPAN	HEIGHT	LUMBER	OVERHANG LEFT RIGHT	HEEL HEIGHT LEFT RIGHT	LBS. BFT.	BUNDLE # STACK #	LOAD BY REMARKS
	11	J1 Jack-Open	6 /12	5-10-08	4-01-04	2 x 4	1-03-08	1-02-00 4-01-04	184.74 117.33		
	3	J31 Jack-Open	6 /12	4-10-08	3-07-04	2 x 4		1-02-00 3-07-04	38.2 24.00		
	4	J32 Jack-Open	6 /12	10-08	1-07-04	2 x 4	1-03-08	1-02-00 1-07-04	18.87 13.33		
	4	J33 Jack-Open	6 /12	3-04-08	4-01-04	2 x 4		2-05-00 4-01-04	50.57 32.67		
	1	C30 Jack-Open	6 /12	3-09-07	3-00-12	2 x 4	1-03-08 2-01-01	1-02-00 3-00-12	14.13 8.67		
	1	C31 Jack-Open Girder	6 /12	1-09-07	2-00-12	2 x 4	1-03-08 4-01-01	1-02-00 2-00-12	11.58 7.33		
	3	C32 Jack-Open	6 /12	1-10-08	3-00-12	2 x 4	1-03-08 1-10-15	1-02-00 2-01-04	28.71 18.00		
	3	C33 Jack-Open	6 /12	1-09-07	2-00-12	2 x 4	1-03-08 1-01	1-02-00 2-00-12	21.06 14.00		
	2	C34 Jack-Open	6 /12	4-10-08	3-00-12	2 x 4		1-02-00 3-07-04	22.69 14.67		
	2	C35 Jack-Open	6 /12	1-09-07	2-00-12	2 x 4	1-03-08 3-01-01	1-02-00 2-00-12	20.88 13.33		


TOTAL # TRUSS= 62 TOTAL BFT OF ALL TRUSSES= 1690.33 BFT. TOTAL WEIGHT OF ALL TRSSES 2691.92 LBS

HARDWARE

QTY	TYPE	MODEL	LENGTH
10	Hardware	LUS24	
3	Hardware	LUS26-2	

TOTAL NUMBER OF ITEMS= 13

Version 8.330 S May 6 2020 MiTek Industries, Inc. Tue Aug 4 13:53:00 2020 Page 1
ID:W63xGm6okcO0SiyZ4EwBx6zA2m0-UCeDYIEBFqOtiuv45P0Ch_ZlcycsfPx3lB5Q1MyrDe1
13-10-5 4-10-3 18-8-9 4-2-11 22-11-4 23-9-0
9-12
Scale = 1:30



JOB NAME	TRUSS NAME	QUANTITY	PLY	JOB DESC.	DRWG NO.
410146	T1	2	2	GREEN PARK HOMES	
Tamarack Roof Truss, Burlington				TRUSS DESC.	

Version 8.330 S May 6 2020 MTEK Industries, Inc. Tue Aug 4 13:53:00 2020 Page 2
ID:W63xGm6okcO0SiyZ4EwBx6zA2m0-UCeDYfEBFqOtiu45P0Ch ZlcyctfPx3i85Q1MyrDe1

PLATES (table is in inches)

JT	TYPE	PLATES	W	LEN	Y	X
B	TMVW-t	MT20	5.0	6.0	2.50	1.75
C	TTWW-m	MT20	5.0	6.0	2.00	2.00
D	TMWW-t	MT20	4.0	4.0		
E	TS-t	MT20	3.0	6.0		
F	TMW-w	MT20	2.0	4.0		
G	TMWW-t	MT20	4.0	4.0		
H	TMVW-t	MT20	4.0	6.0		
I	BMV1+p	MT20	3.0	6.0		
J, M, N						
J	BMWW-t	MT20	5.0	6.0		
K	BS-t	MT20	5.0	6.0		
L	BMWWW-t	MT20	5.0	8.0		
O	BMV1+p	MT20	3.0	6.0		

FACTORED CONCENTRATED LOADS (LBS)

JT	LOC.	LC1	MAX-	MAX+	FACE	DIR.	TYPE	HEEL	CONN.
N	3-11-4	-26	-26	---	FRONT	VERT	TOTAL	---	C1
P	5-11-4	-110	-110	---	FRONT	VERT	TOTAL	---	C1
Q	7-11-4	-110	-110	---	FRONT	VERT	TOTAL	---	C1
R	9-11-4	-110	-110	---	FRONT	VERT	TOTAL	---	C1
S	15-11-4	-110	-110	---	FRONT	VERT	TOTAL	---	C1
T	17-11-4	-110	-110	---	FRONT	VERT	TOTAL	---	C1
U	19-11-4	-110	-110	---	FRONT	VERT	TOTAL	---	C1
V	21-11-4	-110	-110	---	FRONT	VERT	TOTAL	---	C1
W	22-11-4	-119	-119	---	FRONT	VERT	TOTAL	---	C1
X	1-11-4	-26	-26	---	FRONT	VERT	TOTAL	---	C1
Y	5-11-4	-26	-26	---	FRONT	VERT	TOTAL	---	C1
Z	7-11-4	-26	-26	---	FRONT	VERT	TOTAL	---	C1
AA	9-11-4	-26	-26	---	FRONT	VERT	TOTAL	---	C1
AB	11-11-4	-26	-26	---	FRONT	VERT	TOTAL	---	C1
AC	17-11-4	-26	-26	---	FRONT	VERT	TOTAL	---	C1
AD	19-11-4	-26	-26	---	FRONT	VERT	TOTAL	---	C1
AE	21-11-4	-26	-26	---	FRONT	VERT	TOTAL	---	C1
AF	22-11-4	-28	-28	---	FRONT	VERT	TOTAL	---	C1

CONNECTION REQUIREMENTS

- 1) C1: A SUITABLE HANGER/MECHANICAL CONNECTION IS REQUIRED.



Structural component only
DWG# T-2017154 2/2

JOB NAME	TRUSS NAME	QUANTITY	PLY	JOB DESC.	DRWG NO.
410146	T1Z	1	2	GREEN PARK HOMES	
Tamarack Roof Truss, Burlington				TRUSS DESC.	

Version 8.330 S May 6 2020 MiTek Industries, Inc. Tue Aug 4 13:53:01 2020 Page 2
ID:W63xGm6okcO0SiyZ4EwBx6zA2m0-yOCbm?Fp08WkK3THf6XRDC6R9LxGOqCDzorZoyrDe0

PLATES (table is in inches)

JT	TYPE	PLATES	W	LEN	Y	X
B	TMWW-t	MT20	5.0	6.0	2.25	1.75
C	TTWW-m	MT20	5.0	8.0	2.00	3.00
D	TMWW-t	MT20	4.0	4.0		
E	TS-t	MT20	3.0	6.0		
F	TMWW-w	MT20	2.0	4.0		
G	TMWW-t	MT20	4.0	6.0		
H	TMWW-t	MT20	5.0	6.0	2.50	2.75
I	BMV1-p	MT20	3.0	6.0		
K	BMWW-t	MT20	5.0	6.0	2.50	2.75
L	BS-t	MT20	5.0	6.0		
M	BMWW-t	MT20	5.0	8.0		
N	BMWW-t	MT20	5.0	6.0		
O	BMWW-t	MT20	5.0	6.0		
P	BMV1-p	MT20	3.0	6.0		

FACTORED CONCENTRATED LOADS (LBS)

JT	LOC.	LC1	MAX-	MAX+	FACE	DIR.	TYPE	HEEL	CONN.
V	23-3-12	-136	-136	---	FRONT	VERT	TOTAL	---	C1
W	14-6-12	-26	-26	---	FRONT	VERT	TOTAL	---	C1
X	15-6-12	-26	-26	---	FRONT	VERT	TOTAL	---	C1
Y	17-6-12	-26	-26	---	FRONT	VERT	TOTAL	---	C1
Z	19-6-12	-26	-26	---	FRONT	VERT	TOTAL	---	C1
AA	21-6-12	-26	-26	---	FRONT	VERT	TOTAL	---	C1
AB	23-3-12	-32	-32	---	FRONT	VERT	TOTAL	---	C1


CONNECTION REQUIREMENTS

- 1) C1: A SUITABLE HANGER/MECHANICAL CONNECTION IS REQUIRED.



Structural component only
DWG# T-2017155 2/2

JOB NAME 410110	TRUSS NAME T2	QUANTITY 4	PLY 1	JOB DESC. GREEN PARK HOMES	DRWG NO.
Tamarack Roof Truss, Burlington				TRUSS DESC.	



LUMBER
N. L. G. A. RULES
CHORDS SIZE LUMBER DESCR.
A - C 2x4 DRY No.2 SPF
C - E 2x4 DRY No.2 SPF
E - G 2x4 DRY No.2 SPF
H - G 2x4 DRY No.2 SPF
M - B 2x4 DRY No.2 SPF
M - J 2x4 DRY No.2 SPF
J - H 2x4 DRY No.2 SPF
ALL WEBS 2x3 DRY No.2 SPF
EXCEPT
DRY: SEASONED LUMBER.

CHORDS	SIZE	LUMBER	DESCR.
A - C	2x4	DRY No.2	SPF
C - E	2x4	DRY No.2	SPF
E - G	2x4	DRY No.2	SPF
H - G	2x4	DRY No.2	SPF
M - B	2x4	DRY No.2	SPF
M - J	2x4	DRY No.2	SPF
J - H	2x4	DRY No.2	SPF
ALL WEBS	2x3	DRY No.2	SPF
EXCEPT			
DRY: SEASONED LUMBER.			

CHORDS	SIZE	LUMBER	DESCR.
A - C	2x4	DRY No.2	SPF
C - E	2x4	DRY No.2	SPF
E - G	2x4	DRY No.2	SPF
H - G	2x4	DRY No.2	SPF
M - B	2x4	DRY No.2	SPF
M - J	2x4	DRY No.2	SPF
J - H	2x4	DRY No.2	SPF
ALL WEBS	2x3	DRY No.2	SPF
EXCEPT			
DRY: SEASONED LUMBER.			

PLATES (table is in inches)
JT TYPE PLATES W LEN Y X
B TMVW+p MT20 5.0 6.0 Edge
C TTVW+m MT20 5.0 6.0 2.00 1.50
D TMW+w MT20 2.0 4.0
E TS-t MT20 3.0 6.0
F TMVW-t MT20 4.0 4.0
G TMVW-t MT20 5.0 6.0
H BMV1+p MT20 3.0 4.0
I BMVW-t MT20 5.0 6.0
J BS-t MT20 3.0 6.0
K BMVW-t MT20 4.0 9.0
L BMVW-t MT20 4.0 6.0
M BMV1+p MT20 3.0 4.0
Edge - INDICATES REFERENCE CORNER OF PLATE TOUCHES EDGE OF CHORD.

DESIGN CRITERIA
SPECIFIED LOADS:
TOP CH. LL = 25.6 PSF
DL = 6.0 PSF
BOT CH. LL = 0.0 PSF
DL = 7.4 PSF
TOTAL LOAD = 39.0 PSF
SPACING = 24.0 IN. C/C
LOADING IN FLAT SECTION BASED ON A SLOPE OF 6.00/12
THIS TRUSS IS DESIGNED FOR RESIDENTIAL OR SMALL BUILDING REQUIREMENTS OF PART 9, NBCC 2015
THIS DESIGN COMPLIES WITH:
- PART 9 OF BCBC 2018, ABC 2019
- PART 9 OF OBC 2012 (2019 AMENDMENT)
- CSA 086-14
- TPIC 2014

BEARINGS
FACTORED MAXIMUM FACTORED INPUT REQD
GROSS REACTION GROSS REACTION BRG BRG
JT VERT HORZ DOWN HORZ UPLIFT IN-SX IN-SX
H 1309 0 1309 0 0 1-8 1-8
M 1435 0 1435 0 0 5-8 5-8

UNFACTORED REACTIONS
1ST LCASE MAX./MIN. COMPONENT REACTIONS
JT COMBINED SNOW LIVE PERM.LIVE WIND DEAD SOIL
H 926 608.0 0.0 0.0 0.0 318.0 0.0
M 1013 678.0 0.0 0.0 0.0 335.0 0.0

BEARING MATERIAL TO BE SPF NO.2 OR BETTER AT JOINT(S) H, M
BRACING
TOP CHORD TO BE SHEATHED OR MAX. PURLIN SPACING = 4.44 FT.
MAX. UNBRACED BOTTOM CHORD LENGTH = 10.00 FT OR RIGID CEILING DIRECTLY APPLIED
ALL PITCH BREAKS AND PERIMETER CORNER JOINTS MUST BE LATERALLY RESTRAINED.

LOADING
TOTAL LOAD CASES: (4)
CHORDS MAX. FACTORED FORCE (LBS) VERT. LOAD LC1 MAX. FACTORED (PLF) CSI (LC) UNBRAC LENGTH FR-TO MEMB. FORCE (LBS) MAX. FACTORED (LBS) CSI (LC)
A-B 0.35 -91.8 -91.8 0.12 (1) 10.00 L-C -102.59 0.04 (1)
B-C -1417.0 -91.8 -91.8 0.59 (1) 4.72 B-L 0.1199 0.27 (1)
C-D -1688.0 -91.8 -91.8 0.54 (1) 4.47 I-G 0.1679 0.38 (1)
D-E -1688.0 -91.8 -91.8 0.56 (1) 4.44 C-K 0.653 0.15 (1)
E-F -1688.0 -91.8 -91.8 0.56 (1) 4.44 I-F -907.0 0.35 (1)
F-G -1323.0 -91.8 -91.8 0.53 (1) 4.92 K-D -599.0 0.23 (1)
G-H -1263.0 0.0 0.0 0.56 (1) 7.16 K-F 0.469 0.11 (1)
H-I -1394.0 0.0 0.0 0.14 (1) 6.90

M-L 0.0 -18.5 -18.5 0.15 (4) 10.00
L-K 0.1176 -18.5 -18.5 0.27 (1) 10.00
K-J 0.1323 -18.5 -18.5 0.30 (1) 10.00
J-I 0.1323 -18.5 -18.5 0.30 (1) 10.00
I-H 0.0 -18.5 -18.5 0.16 (4) 10.00

(55% OF 31.3 P.S.F. G.S.L. PLUS 8.4 P.S.F. RAIN LOAD) EQUALS 25.6 P.S.F. SPECIFIED ROOF LIVE LOAD
ALLOWABLE DEFL.(LL) = L/360 (0.79")
CALCULATED VERT. DEFL.(LL) = L/999 (0.06")
ALLOWABLE DEFL.(TL) = L/360 (0.79")
CALCULATED VERT. DEFL.(TL) = L/999 (0.12")
CSI: TC=0.59/1.00 (B-C:1), BC=0.30/1.00 (H-K:1), WB=0.38/1.00 (G-I:1), SS=0.26/1.00 (F-G:1)
DOL LUMBER=1.00 NAIL=1.00 L5 BEND=1.10 COMP=1.10 SHEAR=1.10 TENS=1.10
COMPANION LIVE LOAD FACTOR = 1.00

TRUSS PLATE MANUFACTURER IS NOT RESPONSIBLE FOR QUALITY CONTROL IN THE TRUSS MANUFACTURING PLANT

NAIL VALUES
PLATE GRIP(DRY) SHEAR SECTION (PSI) (PLI) (PLI)
MAX MIN MAX MIN MAX MIN
MT20 650 371 1747 788 1987 1873
PLATE PLACEMENT TOL. = 0.250 inches
PLATE ROTATION TOL. = 5.0 Deg.

JSI GRIP= 0.85 (B) (INPUT = 0.90)
JSI METAL= 0.60 (B) (INPUT = 1.00)




Structural component only
DWG# T-2017080

Structural component only
DWG# T-2017081

JOB NAME 410110	TRUSS NAME T4	QUANTITY 4	PLY 1	JOB DESC. GREEN PARK HOMES	TRUSS DESC.	DRWG NO.
--------------------	------------------	---------------	----------	-------------------------------	-------------	----------

Tamarack Roof Truss, Burlington

Version 8.330 S May 6 2020 MiTek Industries, Inc. Tue Aug 4 12:11:20 2020 Page 1
ID:W63xGm6okc00SiyZ4EwBx6zA2m0-5f3AlsQtocsOuTZjllakSdwrR?iAQRRc26RwWyrF7L



LUMBER			
N. L. G. A. RULES			
CHORDS	SIZE	LUMBER	DESCR.
A - D	2x4	DRY	No.2
D - G	2x4	DRY	No.2
H - G	2x4	DRY	No.2
N - B	2x4	DRY	No.2
N - J	2x4	DRY	No.2
J - H	2x4	DRY	No.2

ALL WEBS 2x3 DRY No.2
EXCEPT
SPF
DRY: SEASONED LUMBER.

PLATES (table is in inches)					
JT	TYPE	PLATES	W	LEN	Y X
B	TMVW-p	MT20	5.0	6.0	Edge
C	TMVW-t	MT20	4.0	4.0	2.00 1.50
D	TTWW+m	MT20	5.0	6.0	2.00 1.50
E	TMVW-w	MT20	2.0	4.0	
F	TMVW-t	MT20	4.0	4.0	
G	TMVW-p	MT20	4.0	6.0	
H	BMV1+p	MT20	3.0	4.0	
I	BMVW-t	MT20	4.0	6.0	
J	BS-t	MT20	3.0	6.0	
K	BMVW-t	MT20	4.0	9.0	
L	BMVW-t	MT20	4.0	4.0	
M	BMVW-t	MT20	4.0	6.0	
N	BMV1+p	MT20	3.0	4.0	

Edge - INDICATES REFERENCE CORNER OF PLATE TOUCHES EDGE OF CHORD.

DIMENSIONS, SUPPORTS AND LOADINGS SPECIFIED BY FABRICATOR TO BE VERIFIED BY BUILDING DESIGNER

BEARINGS		FACTORED		MAXIMUM FACTORED		INPUT		REQD	
		GROSS REACTION		GROSS REACTION		BRG		BRG	
JT	VERT	HORZ		DOWN	HORZ	UPLIFT	IN-SX	IN-SX	
H	1309	0		1309	0	0	1-8	1-8	
N	1435	0		1435	0	0	5-8	5-8	

UNFACTORED REACTIONS							
1ST LCASE		MAX./MIN. COMPONENT REACTIONS					
JT	COMBINED	SNOW	LIVE	PERM.LIVE	WIND	DEAD	SOIL
H	926	608 0	0 0	0 0	0 0	318 0	0 0
N	1013	678 0	0 0	0 0	0 0	335 0	0 0

BEARING MATERIAL TO BE SPF NO.2 OR BETTER AT JOINT(S) H, N

BRACING
TOP CHORD TO BE SHEATHED OR MAX. PURLIN SPACING = 5.07 FT.
MAX. UNBRACED BOTTOM CHORD LENGTH = 10.00 FT OR RIGID CEILING DIRECTLY APPLIED.

ALL PITCH BREAKS AND PERIMETER CORNER JOINTS MUST BE Laterally RESTRAINED.

1 LATERAL BRACE(S) AT 1/2 LENGTH OF G-H.

END VERTICAL(S) MUST BE SHEATHED OR HAVE BRACES AS INDICATED IN THE MAX. UNBRACED LENGTH COLUMN OF THE TABLE BELOW

LOADING
TOTAL LOAD CASES: (4)

CHORDS				WEBS			
MEMB.	MAX. FACTORED FORCE (LBS)	FACTORED VERT. LOAD (PLF)	MAX. UNBRACED LENGTH (LC)	MEMB.	MAX. FACTORED FORCE (LBS)	MAX. UNBRACED LENGTH (LC)	
FR-TO		FROM TO		FR-TO			
A-B	0 35	-91.8 -91.8	0.12 (1)	10.00	M-C	-220 0	0.06 (1)
B-C	-1445 0	-91.8 -91.8	0.32 (1)	5.07	C-L	-229 0	0.13 (1)
C-D	-1298 0	-91.8 -91.8	0.31 (1)	5.30	L-D	0 247	0.06 (1)
D-E	-1152 0	-91.8 -91.8	0.34 (1)	5.49	B-M	0 1260	0.28 (1)
E-F	-1152 0	-91.8 -91.8	0.35 (1)	5.47	I-G	0 1353	0.30 (1)
F-G	-816 0	-91.8 -91.8	0.34 (1)	6.24	D-K	0 155	0.03 (1)
H-G	-1271 0	0.0 0.0	0.29 (1)	5.71	I-F	-972 0	0.85 (1)
N-B	-1399 0	0.0 0.0	0.14 (1)	6.88	K-E	-498 0	0.44 (1)
					K-F	0 570	0.13 (1)
N-M	0 0	-18.5 -18.5	0.07 (4)	10.00			
M-L	0 1223	-18.5 -18.5	0.24 (1)	10.00			
L-K	0 1060	-18.5 -18.5	0.22 (1)	10.00			
K-J	0 816	-18.5 -18.5	0.19 (1)	10.00			
J-I	0 816	-18.5 -18.5	0.19 (1)	10.00			
I-H	0 0	-18.5 -18.5	0.11 (4)	10.00			

DESIGN CRITERIA

SPECIFIED LOADS:
TOP CH. LL = 25.6 PSF
DL = 6.0 PSF
BOT CH. LL = 0.0 PSF
DL = 7.4 PSF
TOTAL LOAD = 39.0 PSF

SPACING = 24.0 IN./C/C

LOADING IN FLAT SECTION BASED ON A SLOPE OF 6.00/12

THIS TRUSS IS DESIGNED FOR RESIDENTIAL OR SMALL BUILDING REQUIREMENTS OF PART 9, NBCC 2015

THIS DESIGN COMPLIES WITH:
- PART 9 OF BCBC 2018, ABC 2019
- PART 9 OF OBC 2012 (2019 AMENDMENT)
- CSA 086-14
- TPIC 2014

(55 % OF 31.3 P.S.F. G.S.L. PLUS 8.4 P.S.F. RAIN LOAD) EQUALS 25.6 P.S.F. SPECIFIED ROOF LIVE LOAD

ALLOWABLE DEFL.(LL) = L/360 (0.79")
CALCULATED VERT. DEFL.(LL) = L/999 (0.05")
ALLOWABLE DEFL.(TL) = L/360 (0.79")
CALCULATED VERT. DEFL.(TL) = L/999 (0.09")

CSI: TC=0.35/1.00 (E-F:1), BC=0.24/1.00 (L-M:1), WB=0.85/1.00 (F-I:1), SSI=0.22/1.00 (F-G:1)

DOL LUMBER=1.00 NAIL=1.00 LS BEND=1.10
COMP=1.10 SHEAR=1.10 TENS=1.10

COMPANION LIVE LOAD FACTOR = 1.00


TRUSS PLATE MANUFACTURER IS NOT RESPONSIBLE FOR QUALITY CONTROL IN THE TRUSS MANUFACTURING PLANT.

NAIL VALUES	PLATE	GRIP(DRY)	SHEAR	SECTION
(PSI)	(PLI)	(PLI)	(PLI)	
MT20	650	371	1747	788 1987 1873

PLATE PLACEMENT TOL. = 0.250 inches

PLATE ROTATION TOL. = 5.0 Deg.

JSI GRIP= 0.85 (M) (INPUT = 0.90)
JSI METAL= 0.37 (G) (INPUT = 1.00)



Version 8.330 S May 6 2020 MiTek Industries, Inc. Tue Aug 4 12:11:21 2020 Page 1



Structural component only
DWG# T-2017083

rainrack roof truss, Burlington

Version 8.330 S May 6 2020 MiTek Industries, Inc. Tue Aug 4 12:11:22 2020 Page 1

ID:W63xGm6okcO0SiyZ4EwBx6zA2m0-12BwYR7KD667nj5sjdCXZ277WpN9uQSVWQwI?pyr7J

1-3-8 0-0 5-10-9 5-10-9 5-8-1 11-6-11 5-6-11 6-0-11 17-7-5 5-10-3 23-5-8 23-9-0 3-8




Structural component only
DWG# T-2017084

JOB NAME 410146	TRUSS NAME T8	QUANTITY 7	PLY 1	JOB DESC. GREEN PARK HOMES	DRWG NO.
--------------------	------------------	---------------	----------	-------------------------------	----------

Tamarack Roof Truss, Burlington

Version 8.330 S May 6 2020 MTek Industries, Inc. Tue Aug 4 13:53:02 2020 Page 1
ID:W63xGm6okcO0SiyZ4EwBx6zA2m0-Qbm_zLGRnRebyD2TcP3gmPhSII57KnMCSaX6FyrDe?



Scale = 1:33.1

TOTAL WEIGHT = 7 X 59 = 410 lb [M/F]

LUMBER

N. L. G. A. RULES	CHORDS	SIZE	LUMBER	DESCR.
A - D	2x4	DRY	No.2	SPF
D - G	2x4	DRY	No.2	SPF
J - B	2x4	DRY	No.2	SPF
H - F	2x4	DRY	No.2	SPF
J - H	2x4	DRY	No.2	SPF
ALL WEBS EXCEPT	2x3	DRY	No.2	SPF

DRY: SEASONED LUMBER.

PLATES (table is in inches)

JT	TYPE	PLATES	W	LEN	Y	X
B	TMV+p	MT20	3.0	4.0		
C	TMWW-t	MT20	4.0	4.0		
D	TTW-p	MT20	4.0	4.0	2.25	2.00
E	TMWW-t	MT20	4.0	4.0		
F	TMV+p	MT20	3.0	4.0		
H	BMVW1-t	MT20	4.0	4.0		
I	BMWWW-t	MT20	4.0	9.0		
J	BMVW1-t	MT20	4.0	4.0		

DIMENSIONS, SUPPORTS AND LOADINGS SPECIFIED BY FABRICATOR TO BE VERIFIED BY BUILDING DESIGNER

BEARINGS		FACTORED GROSS REACTION		MAXIMUM FACTORED GROSS REACTION		INPUT BRG		REQRD BRG	
JT	VERT	HORZ	DOWN	HORZ	UPLIFT	IN-SX	IN-SX	IN-SX	IN-SX
J	870	0	870	0	0	5-8	5-8	5-8	5-8
H	870	0	870	0	0	5-8	5-8	5-8	5-8

UNFACTORED REACTIONS

1ST LCASE	COMBINED	SNOW	LIVE	PERM.LIVE	WIND	DEAD	SOIL
J	613	416 / 0	0 / 0	0 / 0	0 / 0	197	0
H	613	416 / 0	0 / 0	0 / 0	0 / 0	197	0

BEARING MATERIAL TO BE SPF NO.2 OR BETTER AT JOINT(S) J, H

BRACING

TOP CHORD TO BE SHEATHED OR MAX. PURLIN SPACING = 6.25 FT.
MAX. UNBRACED BOTTOM CHORD LENGTH = 10.00 FT. OR RIGID CEILING DIRECTLY APPLIED.

ALL PITCH BREAKS AND PERIMETER CORNER JOINTS MUST BE Laterally RESTRAINED.

LOADING

TOTAL LOAD CASES: (4)

CHORDS		FACTORED		WEBS	
MEMB.	FORCE (LBS)	VERT. LOAD (PLF)	MAX. CSI (LC)	MEMB.	FORCE (LBS)
FR-TO		FROM	TO	FR-TO	
A-B	0 / 35	-91.8	-91.8 0.12 (1)	I-D	0 / 382
B-C	0 / 19	-91.8	-91.8 0.16 (1)	I-E	-163 / 0
C-D	-581 / 0	-91.8	-91.8 0.13 (1)	C-I	-163 / 0
D-E	-581 / 0	-91.8	-91.8 0.13 (1)	J-C	-821 / 0
E-F	0 / 19	-91.8	-91.8 0.16 (1)	E-H	-821 / 0
F-G	0 / 35	-91.8	-91.8 0.12 (1)		
J-B	-245 / 0	0.0	0.0 0.03 (1)		
H-F	-245 / 0	0.0	0.0 0.03 (1)		
J-I	0 / 584	-18.5	-18.5 0.29 (4)		
I-H	0 / 584	-18.5	-18.5 0.29 (4)		

DESIGN CRITERIA

SPECIFIED LOADS:
TOP CH. LL = 25.6 PSF
DL = 6.0 PSF
BOT CH. LL = 0.0 PSF
DL = 7.4 PSF
TOTAL LOAD = 39.0 PSF

SPACING = 24.0 IN. C/C

THIS TRUSS IS DESIGNED FOR RESIDENTIAL OR SMALL BUILDING REQUIREMENTS OF PART 9, NBCC 2015

THIS DESIGN COMPLIES WITH:
- PART 9 OF BCBC 2018, ABC 2019
- PART 9 OF OBC 2012 (2019 AMENDMENT)
- CSA 086-14
- TPIC 2014

(55 % OF 31.3 P.S.F. G.S.L. PLUS 8.4 P.S.F. RAIN LOAD) EQUALS 25.6 P.S.F. SPECIFIED ROOF LIVE LOAD

ALLOWABLE DEFL.(LL) = L/360 (0.45")
CALCULATED VERT. DEFL.(LL) = L/999 (0.01")
ALLOWABLE DEFL.(TL) = L/360 (0.45")
CALCULATED VERT. DEFL.(TL) = L/999 (0.05")

CSI: TC=0.16/1.00 (E-F:1), BC=0.29/1.00 (H-I:4), WB=0.29/1.00 (E-H:1), SSI=0.12/1.00 (D-E:1)

DOL LUMBER=1.00 NAIL=1.00 LS BEND=1.10
COMP=1.10 SHEAR=1.10 TENS=1.10

COMPANION LIVE LOAD FACTOR = 1.00

TRUSS PLATE MANUFACTURER IS NOT RESPONSIBLE FOR QUALITY CONTROL IN THE TRUSS MANUFACTURING PLANT

NAIL VALUES
PLATE GRIP(DRY) SHEAR SECTION
(PSI) (PLI) (PLI)
MAX MIN MAX MIN MAX MIN
MT20 650 371 1747 788 1987 1873

PLATE PLACEMENT TOL. = 0.250 inches

PLATE ROTATION TOL. = 5.0 Deg.


JSI GRIP= 0.68 (E) (INPUT = 0.90)
JSI METAL= 0.26 (C) (INPUT = 1.00)



Structural component only
DWG# T-2017156

JOB NAME 410146	TRUSS NAME T8S	QUANTITY 2	PLY 1	JOB DESC. GREEN PARK HOMES	DRWG NO.
Tamarack Roof Truss, Burlington				TRUSS DESC.	

Version 8.330 S May 6 2020 MTek Industries, Inc. Tue Aug 4 13:53:03 2020 Page 1
 ID:W63xGm6okcO0SiyZ4EwBx6zA2m0-unKMBhH3YImSaNdfrmXavldBp89e3sl8WR6K4ehyrDe



Scale = 1:33.1

LUMBER			
N. L. G. A. RULES	CHORDS	SIZE	LUMBER
A - E	2x4	DRY	No.2
E - H	2x4	DRY	No.2
O - B	2x4	DRY	No.2
I - G	2x4	DRY	No.2
O - M	2x4	DRY	No.2
M - D	2x4	DRY	No.2
L - K	2x4	DRY	No.2
J - F	2x4	DRY	No.2
J - I	2x4	DRY	No.2
ALL WEBS EXCEPT N - L	2x3	DRY	No.2

DRY: SEASONED LUMBER.

PLATES (table is in inches)				
JT	TYPE	PLATES	W	LEN Y X
B	TMVW+p	MT20	4.0	4.0 1.25 2.00
C	TMVW-t	MT20	4.0	4.0 2.00 1.50
D	TMV+p	MT20	3.0	4.0
E	TT-p	MT20	3.0	4.0 Edge 2.00
F	TMVW+p	MT20	4.0	4.0 1.25 2.00
G	TMVW-p	MT20	5.0	6.0 Edge
I	BMVW1-t	MT20	4.0	4.0
J	BMV+p	MT20	3.0	4.0
K	BMVWW1-t	MT20	4.0	12.0 3.00 7.00
L	BMVWWW1-t	MT20	6.0	9.0 Edge 3.00
M	BMV+p	MT20	3.0	4.0
N	BMVWW-t	MT20	4.0	9.0
O	BMV1+p	MT20	3.0	4.0

Edge - INDICATES REFERENCE CORNER OF PLATE TOUCHES EDGE OF CHORD.

DIMENSIONS, SUPPORTS AND LOADINGS SPECIFIED BY FABRICATOR TO BE VERIFIED BY BUILDING DESIGNER

FACTORED GROSS REACTION		MAXIMUM FACTORED GROSS REACTION		INPUT BRG		REQRD BRG	
JT	VERT	HORZ	DOWN	HORZ	UPLIFT	IN-SX	IN-SX
O	864	0	864	0	0	5-8	5-8
I	877	0	877	0	0	5-8	5-8

UNFACTORED REACTIONS		1ST LCASE		MAX/MIN. COMPONENT REACTIONS	
JT	COMBINED	SNOW	LIVE	PERM. LIVE	WIND
O	609	412 / 0	0 / 0	0 / 0	0 / 0
I	617	419 / 0	0 / 0	0 / 0	0 / 0

BEARING MATERIAL TO BE SPF NO.2 OR BETTER AT JOINT(S) O, I

BRACING
 TOP CHORD TO BE SHEATHED OR MAX. PURLIN SPACING = 5.20 FT.
 MAX. UNBRACED BOTTOM CHORD LENGTH = 10.00 FT OR RIGID CEILING DIRECTLY APPLIED.

ALL PITCH BREAKS AND PERIMETER CORNER JOINTS MUST BE Laterally RESTRAINED.

LOADING
 TOTAL LOAD CASES: (4)

CHORDS				WEBS			
MEMB.	MAX. FACTORED FORCE (LBS)	FACTORED VERT. LOAD (PLF)	LC1 MAX CSI (LC)	MAX. UNBRAC LENGTH	MEMB.	MAX. FACTORED FORCE (LBS)	MAX CSI (LC)
FR-TO		FROM	TO		FR-TO		
A-B	0 / 35	-91.8	-91.8 0.12 (1)	10.00	N-C	-316 / 0	0.07 (1)
B-C	-706 / 0	-91.8	-91.8 0.21 (1)	6.25	N-L	0 / 626	0.10 (1)
C-D	-685 / 0	-91.8	-91.8 0.24 (1)	6.25	C-L	-112 / 0	0.03 (1)
D-E	-372 / 0	-91.8	-91.8 0.23 (1)	6.25	L-F	-722 / 0	0.41 (1)
E-F	-659 / 0	-91.8	-91.8 0.36 (1)	6.25	B-N	0 / 636	0.14 (1)
F-G	-1343 / 0	-91.8	-91.8 0.30 (1)	5.20	K-I	-78 / 0	0.01 (1)
G-H	0 / 35	-91.8	-91.8 0.12 (1)	10.00	K-G	0 / 1161	0.26 (1)
O-B	-836 / 0	0.0	0.0 0.09 (1)	7.81			
I-G	-813 / 0	0.0	0.0 0.08 (1)	7.81			
O-N	0 / 0	-18.5	-18.5 0.05 (4)	10.00			
N-M	0 / 13	-18.5	-18.5 0.05 (4)	10.00			
M-L	0 / 23	0.0	0.0 0.02 (1)	10.00			
L-D	0 / 431	0.0	0.0 0.09 (1)	10.00			
L-K	0 / 1243	-18.5	-18.5 0.30 (1)	10.00			
J-K	0 / 14	0.0	0.0 0.09 (1)	10.00			
K-F	0 / 100	0.0	0.0 0.11 (1)	10.00			
J-I	0 / 59	-18.5	-18.5 0.01 (1)	10.00			

TOTAL WEIGHT = 2 X 66 = 131 lb

DESIGN CRITERIA

SPECIFIED LOADS:
 TOP CH. LL = 25.6 PSF
 DL = 6.0 PSF
 BOT CH. LL = 0.0 PSF
 DL = 7.4 PSF
 TOTAL LOAD = 39.0 PSF

SPACING = 24.0 IN. CC

THIS TRUSS IS DESIGNED FOR RESIDENTIAL OR SMALL BUILDING REQUIREMENTS OF PART 9, NBCC 2015

THIS DESIGN COMPLIES WITH:
 - PART 9 OF CBC 2018, ABC 2019
 - PART 9 OF OBC 2012 (2019 AMENDMENT)
 - CSA 086-14
 - TPIC 2014

DESIGN ASSUMPTIONS
 - OVERHANG NOT TO BE ALTERED OR CUT OFF.

(55 % OF 31.3 P.S.F. G.S.L. PLUS 8.4 P.S.F. RAIN LOAD) EQUALS 25.6 P.S.F. SPECIFIED ROOF LIVE LOAD

ALLOWABLE DEFL.(LL)= L/360 (0.45")
 CALCULATED VERT. DEFL.(LL) = L/999 (0.03")
 ALLOWABLE DEFL.(TL)= L/360 (0.45")
 CALCULATED VERT. DEFL.(TL) = L/999 (0.09")

CSI: TC=0.36/1.00 (E-F:1), BC=0.30/1.00 (K-L:1), WB=0.41/1.00 (F-L:1), SSI=0.32/1.00 (D-E:1)

DOL LUMBER=1.00 NAIL=1.00 LS BEND=1.10
 COMP=1.10 SHEAR=1.10 TENS=1.10

COMPANION LIVE LOAD FACTOR = 1.00

AUTOSOLVE LEFT HEEL ONLY

TRUSS PLATE MANUFACTURER IS NOT RESPONSIBLE FOR QUALITY CONTROL IN THE TRUSS MANUFACTURING PLANT.

NAIL VALUES		PLATE GRIP(DRY)		SHEAR		SECTION	
(PSI)	(PLI)	(PSI)	(PLI)	(PSI)	(PLI)	(PSI)	(PLI)
MAX	MIN	MAX	MIN	MAX	MIN	MAX	MIN
MT20	650	371	1747	788	1987	1873	

PLATE PLACEMENT TOL. = 0.250 inches

PLATE ROTATION TOL. = 5.0 Deg.

JSI GRIP= 0.64 (B) (INPUT = 0.90)
 JSI METAL= 0.26 (K) (INPUT = 1.00)




Structural component only
 DWG# T-2017157

JOB NAME 410146	TRUSS NAME T9S	QUANTITY 2	PLY 1	JOB DESC. GREEN PARK HOMES	DRWG NO.
Tamarack Roof Truss, Burlington					

Version 8.330 S May 6 2020 MTek Industries, Inc. Tue Aug 4 13:53:04 2020 Page 1
ID:W63xGm60kc00SiyZ4EwBx6zA2m0-MzukO1Hh13uJBWCrKE58rqk2YZ07bHsfm3d97yrDdz

Scale = 1:24.9



LUMBER	N. L. G. A. RULES	CHORDS	SIZE	LUMBER	DESCR.
A - D	2x4	DRY	No.2	SPF	
D - G	2x4	DRY	No.2	SPF	
N - B	2x4	DRY	No.2	SPF	
H - F	2x4	DRY	No.2	SPF	
N - M	2x4	DRY	No.2	SPF	
M - C	2x4	DRY	No.2	SPF	
L - J	2x4	DRY	No.2	SPF	
I - E	2x4	DRY	No.2	SPF	
I - H	2x4	DRY	No.2	SPF	
ALL WEBS EXCEPT	2x3	DRY	No.2	SPF	
N - L	2x4	DRY	No.2	SPF	
J - H	2x4	DRY	No.2	SPF	

DRY: SEASONED LUMBER.

PLATES (table is in inches)

JT TYPE	PLATES	W	LEN	Y	X
B TMVW+p	MT20	5.0	6.0	Edge	
C TMVW-t	MT20	4.0	4.0	2.00	1.00
D TTW-p	MT20	4.0	4.0	2.25	2.00
E TMVW-t	MT20	4.0	4.0	2.00	1.00
F TMVW+p	MT20	5.0	6.0	Edge	
H BMVW-t	MT20	4.0	4.0		
I BMV+p	MT20	3.0	4.0		
J BMVWV-t	MT20	6.0	9.0	4.50	5.50
K BMVWV-t	MT20	4.0	9.0		
L BMVWV-t	MT20	6.0	9.0	4.50	5.50
M BMV+p	MT20	3.0	4.0		
N BMVW-t	MT20	4.0	4.0		

Edge - INDICATES REFERENCE CORNER OF PLATE TOUCHES EDGE OF CHORD.

DIMENSIONS, SUPPORTS AND LOADINGS SPECIFIED BY FABRICATOR TO BE VERIFIED BY BUILDING DESIGNER

BEARINGS	FACTORED GROSS REACTION	MAXIMUM FACTORED GROSS REACTION	INPUT BRG	REQD BRG
JT VERT	585	585	0	0
N	585	585	0	0
H	585	585	0	0

UNFACTORED REACTIONS

1ST LCASE	MAX./MIN. COMPONENT REACTIONS	PERM. LIVE	WIND	DEAD	SOIL
JT COMBINED	283 / 0	0 / 0	0 / 0	128 / 0	0 / 0
N	283 / 0	0 / 0	0 / 0	128 / 0	0 / 0
H	283 / 0	0 / 0	0 / 0	128 / 0	0 / 0

BEARING MATERIAL TO BE SPF NO.2 OR BETTER AT JOINT(S) N, H

BRACING

TOP CHORD TO BE SHEATHED OR MAX. PURLIN SPACING = 6.25 FT.
MAX. UNBRACED BOTTOM CHORD LENGTH = 10.00 FT. OR RIGID CEILING DIRECTLY APPLIED.

ALL PITCH BREAKS AND PERIMETER CORNER JOINTS MUST BE LATERALLY RESTRAINED.

LOADING

TOTAL LOAD CASES: (4)

CHORDS	MAX. FACTORED	FACTORED	WEBS	MAX. FACTORED
MEMB.	FORCE (LBS)	VERT. LOAD (PLF)	MEMB.	FORCE (LBS)
FR-TO			FR-TO	
A-B	0 / 35	-91.8	K-D	0 / 170
B-C	-691 / 0	-91.8	K-E	-312 / 0
C-D	-378 / 0	-91.8	C-K	-312 / 0
D-E	-378 / 0	-91.8	N-L	-44 / 0
E-F	-691 / 0	-91.8	B-L	0 / 557
F-G	0 / 35	-91.8	J-H	-44 / 0
N-B	-543 / 0	0.0	J-F	0 / 557
H-F	-543 / 0	0.0		
N-M	0 / 32	-18.5		
M-L	0 / 14	0.0		
L-C	0 / 108	0.0		
L-K	0 / 608	-18.5		
K-J	0 / 608	-18.5		
I-J	0 / 14	0.0		
J-E	0 / 108	0.0		
I-H	0 / 32	-18.5		

TOTAL WEIGHT = 2 X 42 = 85 lb [M/F]

DESIGN CRITERIA

SPECIFIED LOADS:
TOP CH. LL = 25.6 PSF
DL = 6.0 PSF
BOT CH. LL = 0.0 PSF
DL = 7.4 PSF
TOTAL LOAD = 39.0 PSF

SPACING = 24.0 IN. C/C

THIS TRUSS IS DESIGNED FOR RESIDENTIAL OR SMALL BUILDING REQUIREMENTS OF PART 9, NBC 2015

THIS DESIGN COMPLIES WITH:
- PART 9 OF BCBC 2018, ABC 2019
- PART 9 OF OBC 2012 (2019 AMENDMENT)
- CSA 086-14
- TPIC 2014

DESIGN ASSUMPTIONS
- OVERHANG NOT TO BE ALTERED OR CUT OFF.

(55% OF 31.3 P.S.F. G.S.L. PLUS 8.4 P.S.F. RAIN LOAD) EQUALS 25.6 P.S.F. SPECIFIED ROOF LIVE LOAD

ALLOWABLE DEFL.(LL) = L/360 (0.28")
CALCULATED VERT. DEFL.(LL) = L/999 (0.01")
ALLOWABLE DEFL.(TL) = L/360 (0.28")
CALCULATED VERT. DEFL.(TL) = L/999 (0.02")

CSI: TC=0.12/1.00 (A-B:1), BC=0.12/1.00 (J-K:1), WB=0.13/1.00 (F-J:1), SSI=0.09/1.00 (C-D:1)

DOL LUMBER=1.00 NAIL=1.00 LS BEND=1.10
COMP=1.10 SHEAR=1.10 TENS=1.10

COMPANION LIVE LOAD FACTOR = 1.00

AUTOSOLVE HEELS OFF

TRUSS PLATE MANUFACTURER IS NOT RESPONSIBLE FOR QUALITY CONTROL IN THE TRUSS MANUFACTURING PLANT.

NAIL VALUES
PLATE GRIP(DRY) SHEAR SECTION
(PSI) (PLI) (PLI)
MAX MIN MAX MIN MAX MIN
MT20 650 371 1747 788 1987 1873

PLATE PLACEMENT TOL. = 0.250 inches


PLATE ROTATION TOL. = 5.0 Deg.

JSI GRIP = 0.48 (F) (INPUT = 0.90)
JSI METAL = 0.29 (F) (INPUT = 1.00)



Structural component only
DWG# T-2017158

JOB NAME	TRUSS NAME	QUANTITY	PLY	JOB DESC.	DRWG NO.
410146	T10	4	1	GREEN PARK HOMES	
Tamarack Roof Truss, Burlington					
Version 8.330 S May 6 2020 Mitek Industries, Inc. Tue Aug 4 13:53:05 2020 Page 1					
ID:W63xGm6okcO0SiyZ4EwBx6zA2m0-rAS6cMIK3M0Apgn2uycNO2G7ezJuKbzouQpBhayrDdy					
Scale = 1:52.8					



TOTAL WEIGHT = 4 X 101 = 404 lb [M/F]

LUMBER	N. L. G. A. RULES	CHORDS	SIZE	LUMBER	DESCR.
A - D	2x4	DRY	No.2	SPF	
D - E	2x4	DRY	No.2	SPF	
E - G	2x4	DRY	No.2	SPF	
M - B	2x4	DRY	No.2	SPF	
H - G	2x4	DRY	No.2	SPF	
M - J	2x4	DRY	No.2	SPF	
J - H	2x4	DRY	No.2	SPF	

ALL WEBS 2x3 DRY No.2 SPF
EXCEPT

DRY: SEASONED LUMBER.

PLATES (table is in inches)

JT	TYPE	PLATES	W	LEN	Y	X
B	TMVW-p	MT20	5.0	6.0	Edge	
C	TMVW-t	MT20	4.0	4.0	2.00	1.50
D	TS-t	MT20	3.0	6.0		
E	TTW-p	MT20	4.0	6.0	Edge	
F	TMVW-t	MT20	4.0	4.0	2.00	1.50
G	TMVW-p	MT20	5.0	6.0	Edge	
H	BMV1-p	MT20	3.0	4.0		
I	BMVW-t	MT20	4.0	6.0		
J	BS-t	MT20	3.0	6.0		
K	BMVW-t	MT20	4.0	9.0		
L	BMVW-t	MT20	4.0	6.0		
M	BMV1-p	MT20	3.0	4.0		

Edge - INDICATES REFERENCE CORNER OF PLATE TOUCHES EDGE OF CHORD.

DIMENSIONS, SUPPORTS AND LOADINGS SPECIFIED BY FABRICATOR TO BE VERIFIED BY BUILDING DESIGNER

BEARINGS		FACTORED	MAXIMUM FACTORED	INPUT	REQD
JT	VERT	GROSS REACTION	GROSS REACTION	BRG	BRG
M	1435	0	1435	0	5-8
H	1309	0	1309	0	1-8

UNFACTORED REACTIONS

JT	1ST LCASE	MAX./MIN.	COMPONENT REACTIONS	PERM.	LIVE	WIND	DEAD	SOIL
M	1013	678 / 0	0 / 0	0 / 0	0 / 0	0 / 0	335 / 0	0 / 0
H	926	608 / 0	0 / 0	0 / 0	0 / 0	0 / 0	318 / 0	0 / 0

BEARING MATERIAL TO BE SPF NO.2 OR BETTER AT JOINT(S) M, H

BRACING

TOP CHORD TO BE SHEATHED OR MAX. PURLIN SPACING = 4.85 FT.
MAX. UNBRACED BOTTOM CHORD LENGTH = 10.00 FT. OR RIGID CEILING DIRECTLY APPLIED.

ALL PITCH BREAKS AND PERIMETER CORNER JOINTS MUST BE LATERALLY RESTRAINED.

LOADING

TOTAL LOAD CASES: (4)

CHORDS		FACTORED		WEBS		FACTORED	
MEMB.	FORCE (LBS)	VERT. LOAD (PLF)	LC1 MAX (LC)	MEMB.	FORCE (LBS)	LC1 MAX (LC)	LC1 MAX (LC)
FR-TO		FROM	TO	FR-TO		FROM	TO
A-B	0 / 35	-91.8	-91.8	0.12 (1)	10.00	L-C	-96 / 67
B-C	-1456 / 0	-91.8	-91.8	0.49 (1)	4.85	C-K	-509 / 0
C-D	-1070 / 0	-91.8	-91.8	0.45 (1)	5.50	K-E	0 / 735
D-E	-1070 / 0	-91.8	-91.8	0.45 (1)	5.50	K-F	-446 / 0
E-F	-1068 / 0	-91.8	-91.8	0.43 (1)	5.54	F-G	-150 / 46
F-G	-1399 / 0	-91.8	-91.8	0.44 (1)	4.99	B-L	0 / 1261
M-B	-1388 / 0	0.0	0.0	0.14 (1)	6.90	I-G	0 / 1225
H-G	-1265 / 0	0.0	0.0	0.13 (1)	7.16		
M-L	0 / 0	-18.5	-18.5	0.16 (4)	10.00		
L-K	0 / 1242	-18.5	-18.5	0.28 (1)	10.00		
K-J	0 / 1195	-18.5	-18.5	0.27 (1)	10.00		
J-I	0 / 1195	-18.5	-18.5	0.27 (1)	10.00		
I-H	0 / 0	-18.5	-18.5	0.15 (4)	10.00		

DESIGN CRITERIA

SPECIFIED LOADS:
TOP CH. LL = 25.6 PSF
DL = 6.0 PSF
BOT CH. LL = 0.0 PSF
DL = 7.4 PSF
TOTAL LOAD = 39.0 PSF

SPACING = 24.0 IN. C/C

THIS TRUSS IS DESIGNED FOR RESIDENTIAL OR SMALL BUILDING REQUIREMENTS OF PART 9, NBC 2015

THIS DESIGN COMPLIES WITH:
- PART 9 OF BCBC 2018, ABC 2019
- PART 9 OF OBC 2012 (2019 AMENDMENT)
- CSA 086-14
- TPIC 2014

(55 % OF 31.3 P.S.F. G.S.L. PLUS 8.4 P.S.F. RAIN LOAD) EQUALS 25.6 P.S.F. SPECIFIED ROOF LIVE LOAD

ALLOWABLE DEFL.(LL) = L/360 (0.79")
CALCULATED VERT. DEFL.(LL) = L/999 (0.04")
ALLOWABLE DEFL.(TL) = L/360 (0.79")
CALCULATED VERT. DEFL.(TL) = L/999 (0.09")

CSI: TC=0.49/1.00 (B-C:1), BC=0.28/1.00 (K-L:1), WB=0.65/1.00 (C-K:1), SS=0.23/1.00 (B-C:1)

DOL LUMBER=1.00 NAIL=1.00 LS BEND=1.10
COMP=1.10 SHEAR=1.10 TENS=1.10

COMPANION LIVE LOAD FACTOR = 1.00

TRUSS PLATE MANUFACTURER IS NOT RESPONSIBLE FOR QUALITY CONTROL IN THE TRUSS MANUFACTURING PLANT.

NAIL VALUES
PLATE GRIP(DRY) SHEAR SECTION (PSI) (PLI) (PLI)
MAX MIN MAX MIN MAX MIN
MT20 650 371 1747 788 1987 1873

PLATE PLACEMENT TOL. = 0.250 inches

PLATE ROTATION TOL. = 5.0 Deg.


JSI GRIP= 0.85 (G) (INPUT = 0.90)
JSI METAL= 0.57 (G) (INPUT = 1.00)



Structural component only
DWG# T-2017159

JOB NAME 410146	TRUSS NAME G11	QUANTITY 1	PLY 1	JOB DESC. GREEN PARK HOMES	DRWG NO.
Tamarack Roof Truss, Burlington					

Version 8.330 S May 6 2020 MTek Industries, Inc. Tue Aug 4 13:52:57 2020 Page 1
ID:W63xGm6okc00SiyZ4EwBx6zA2m0-4dz5wdClyv0IsS9VQGTv3MxrJkf3S3_d2AtmQ1yrDe4



LUMBER			
N. L. G. A. RULES			
CHORDS	SIZE	LUMBER	DESCR.
A - F	2x4	DRY No.2	SPF
F - I	2x4	DRY No.2	SPF
I - L	2x4	DRY No.2	SPF
L - Q	2x4	DRY No.2	SPF
AE - B	2x4	DRY No.2	SPF
R - P	2x4	DRY No.2	SPF
AE - X	2x4	DRY No.2	SPF
X - R	2x4	DRY No.2	SPF
ALL WEBS	2x3	DRY No.2	SPF
ALL GABLE WEBS	2x3	DRY No.2	SPF
DRY: SEASONED LUMBER.			
GABLE STUDS SPACED AT 2'-0" OC.			

PLATES (table is in inches)				
JT	TYPE	PLATES	W	LEN Y X
B	TMVW+p	MT20	4.0	4.0 1.25 2.00
C, D, E, G, H, J, K, M, N, O				
C	TMVW+w	MT20	2.0	4.0
F	TS-1	MT20	3.0	6.0
I	TTW-p	MT20	4.0	4.0 2.25 2.00
L	TS-1	MT20	3.0	6.0
P	TMVW+p	MT20	4.0	4.0 1.25 2.00
R	BMV1+p	MT20	3.0	4.0
S	BMVW1-1	MT20	4.0	4.0
T, U, V, W, Y, Z, AA, AB, AC				
T	BMV1+w	MT20	2.0	4.0
X	BS-1	MT20	3.0	6.0
AD	BMVW1-1	MT20	4.0	4.0
AE	BMV1+p	MT20	3.0	4.0

DIMENSIONS, SUPPORTS AND LOADINGS SPECIFIED BY FABRICATOR TO BE VERIFIED BY BUILDING DESIGNER

BEARINGS

THIS TRUSS DESIGNED FOR CONTINUOUS BEARINGS.

THIS TRUSS REQUIRES RIGID SHEATHING ON EXPOSED FACE.

BEARING MATERIAL TO BE SPF NO.2 OR BETTER AT JOINT(S)

BRACING

TOP CHORD TO BE SHEATHED OR MAX. PURLIN SPACING = 6.25 FT.

MAX. UNBRACED BOTTOM CHORD LENGTH = 10.00 FT OR RIGID CEILING DIRECTLY APPLIED.

ALL PITCH BREAKS AND PERIMETER CORNER JOINTS MUST BE LATERALLY RESTRAINED.

1 LATERAL BRACE(S) AT 1/2 LENGTH OF I-Y.

END VERTICAL(S) MUST BE SHEATHED OR HAVE BRACES AS INDICATED IN THE MAX. UNBRACED LENGTH COLUMN OF THE TABLE BELOW

LOADING

TOTAL LOAD CASES: (4)

CHORDS				WEBS			
MEMB.	MAX. FACTORED FORCE (LBS)	FACTORED VERT. LOAD (PLF)	MAX. UNBRACED LENGTH (LC)	MEMB.	MAX. FACTORED FORCE (LBS)	MAX. UNBRACED LENGTH (LC)	
FR-TO		FROM TO		FR-TO			
A-B	0 / 35	-91.8 -91.8 0.12 (1)	10.00	Y-I	-133 / 0	0.08 (1)	
B-C	-30 / 0	-91.8 -91.8 0.05 (1)	6.25	Z-H	-208 / 0	0.26 (1)	
C-D	-35 / 0	-91.8 -91.8 0.05 (1)	6.25	AA-G	-177 / 0	0.14 (1)	
D-E	-27 / 0	-91.8 -91.8 0.04 (1)	6.25	AB-E	-183 / 0	0.08 (1)	
E-F	-25 / 0	-91.8 -91.8 0.04 (1)	6.25	AC-D	-176 / 0	0.04 (1)	
F-G	-25 / 0	-91.8 -91.8 0.04 (1)	6.25	AD-C	-200 / 0	0.03 (1)	
G-H	-19 / 0	-91.8 -91.8 0.05 (1)	6.25	W-J	-208 / 0	0.26 (1)	
H-I	-29 / 0	-91.8 -91.8 0.05 (1)	6.25	V-K	-177 / 0	0.14 (1)	
I-J	-29 / 0	-91.8 -91.8 0.05 (1)	6.25	U-M	-183 / 0	0.08 (1)	
J-K	-19 / 0	-91.8 -91.8 0.05 (1)	6.25	T-N	-176 / 0	0.04 (1)	
K-L	-25 / 0	-91.8 -91.8 0.04 (1)	6.25	S-O	-200 / 0	0.03 (1)	
L-M	-25 / 0	-91.8 -91.8 0.04 (1)	6.25	B-AD	0 / 38	0.01 (1)	
M-N	-27 / 0	-91.8 -91.8 0.04 (1)	6.25	S-P	0 / 38	0.01 (1)	
N-O	-35 / 0	-91.8 -91.8 0.05 (1)	6.25				
O-P	-30 / 0	-91.8 -91.8 0.05 (1)	6.25				
P-Q	0 / 35	-91.8 -91.8 0.12 (1)	10.00				
AE-B	-237 / 0	0.0 0.0 0.02 (1)	7.81				
R-P	-237 / 0	0.0 0.0 0.02 (1)	7.81				

AE-AD	0 / 0	-18.5 -18.5 0.02 (4)	10.00
AD-AC	0 / 27	-18.5 -18.5 0.02 (4)	10.00
AC-AB	0 / 23	-18.5 -18.5 0.02 (4)	10.00
AB-AA	0 / 20	-18.5 -18.5 0.02 (4)	10.00
AA-Z	0 / 18	-18.5 -18.5 0.02 (4)	10.00
Z-Y	0 / 16	-18.5 -18.5 0.02 (4)	10.00
Y-X	0 / 16	-18.5 -18.5 0.02 (4)	10.00
X-W	0 / 16	-18.5 -18.5 0.02 (4)	10.00
W-V	0 / 18	-18.5 -18.5 0.02 (4)	10.00
V-U	0 / 20	-18.5 -18.5 0.02 (4)	10.00
U-T	0 / 23	-18.5 -18.5 0.02 (4)	10.00
T-S	0 / 27	-18.5 -18.5 0.02 (4)	10.00
S-R	0 / 0	-18.5 -18.5 0.02 (4)	10.00

TOTAL WEIGHT = 116 lb [M]

DESIGN CRITERIA

SPECIFIED LOADS:

TOP CH.	LL	= 25.6	PSF
	DL	= 6.0	PSF
BOT CH.	LL	= 0.0	PSF
	DL	= 7.4	PSF
TOTAL LOAD		= 39.0	PSF

SPACING = 24.0 IN. CC

THIS TRUSS IS DESIGNED FOR RESIDENTIAL OR SMALL BUILDING REQUIREMENTS OF PART 9, NBCC 2015

THIS DESIGN COMPLIES WITH:
- PART 9 OF CBC 2018, ABC 2019
- PART 9 OF OBC 2012 (2019 AMENDMENT)
- CSA 086-14
- TPIC 2014

(55 % OF 31.3 P.S.F. G.S.L. PLUS 8.4 P.S.F. RAIN LOAD) EQUALS 25.6 P.S.F. SPECIFIED ROOF LIVE LOAD

CSI: TC=0.12/1.00 (P-Q:1) , BC=0.02/1.00 (AC-AD:4) , WB=0.26/1.00 (H-Z:1) , SS=0.08/1.00 (P-Q:1)

DOL LUMBER=1.00 NAIL=1.00 LS BEND=1.10
COMP=1.10 SHEAR=1.10 TENS=1.10

COMPANION LIVE LOAD FACTOR = 1.00

TRUSS PLATE MANUFACTURER IS NOT RESPONSIBLE FOR QUALITY CONTROL IN THE TRUSS MANUFACTURING PLANT.

NAIL VALUES					
PLATE	GRIP (DRY)	SHEAR	SECTION		
	(PSI)	(PLI)	(PLI)		
	MAX	MIN	MAX	MIN	MAX
MT20	650	371	1747	788	1987 1873


PLATE PLACEMENT TOL. = 0.250 inches

PLATE ROTATION TOL. = 5.0 Deg.

JSI GRIP= 0.54 (S) (INPUT = 0.90)
JSI METAL= 0.11 (J) (INPUT = 1.00)



Structural component only
DWG# T-2017151



LUMBER

N. L. G. A. RULES

CHORDS	SIZE	LUMBER	DESCR.
A - C	2x4	DRY No.2	SPF
C - D	2x4	DRY No.2	SPF
D - F	2x4	DRY No.2	SPF
B - E	2x6	DRY No.2	SPF
ALL WEBS	2x3	DRY No.2	SPF

DRY: SEASONED LUMBER.

PLATES (table is in inches)

JT	TYPE	PLATES	W	LEN	Y	X
B	TMBH1-m	MT20	5.0	6.0	2.50	0.50
C	TTWW-m	MT20	5.0	6.0	1.75	2.00
D	TTW-m	MT20	4.0	4.0		
E	TMBH1-m	MT20	5.0	6.0	2.50	0.50
G	BMW-w	MT20	5.0	6.0		
H	BMW-w	MT20	3.0	6.0		

DIMENSIONS, SUPPORTS AND LOADINGS SPECIFIED BY FABRICATOR TO BE VERIFIED BY BUILDING DESIGNER

BEARINGS

JT	VERT	HORZ	DOWN	HORZ	UPLIFT	IN-SX	BRG	REQRD	HEEL
B	1107	0	1107	0	0	5-8	5-8	5-8	2x4 L
E	1124	0	1124	0	0	5-8	5-8	5-8	2x4 R

UNFACTORED REACTIONS

JT	1ST LCASE	MAX./MIN. COMPONENT REACTIONS	SNOW	LIVE	PERM. LIVE	WIND	DEAD	SOIL
B	781	523 / 0	0 / 0	0 / 0	0 / 0	0 / 0	258 / 0	0 / 0
E	793	534 / 0	0 / 0	0 / 0	0 / 0	0 / 0	259 / 0	0 / 0

BEARING MATERIAL TO BE SPF NO.2 OR BETTER AT JOINT(S) B, E

BRACING

TOP CHORD TO BE SHEATHED OR MAX. PURLIN SPACING = 4.85 FT.

MAX. UNBRACED BOTTOM CHORD LENGTH = 10.00 FT OR RIGID CEILING DIRECTLY APPLIED.

ALL PITCH BREAKS AND PERIMETER CORNER JOINTS MUST BE Laterally RESTRAINED.

LOADING

TOTAL LOAD CASES: (4)

CHORDS				WEBS			
MEMB.	MAX. FACTORED FORCE (LBS)	FACTORED VERT. LOAD LC1 (PLF)	MAX. CSI (LC)	MAX. UNBRAC LENGTH	MEMB.	MAX. FACTORED FORCE (LBS)	MAX. CSI (LC)
FR-TO		FROM TO			FR-TO		
A-B	0 / 24	-91.8 -91.8	0.13 (1)	10.00	H-C	0 / 120	0.05 (4)
B-J	-1684 / 0	-91.8 -91.8	0.14 (1)	4.95	C-G	-33 / 0	0.01 (1)
J-C	-1245 / 0	-91.8 -91.8	0.13 (1)	5.59	G-D	0 / 124	0.05 (4)
C-M	-983 / 0	-139.5 -139.5	0.73 (1)	4.85	I-J	0 / 533	0.00 (1)
M-N	-983 / 0	-139.5 -139.5	0.73 (1)	4.85	K-L	0 / 438	0.00 (1)
N-D	-983 / 0	-139.5 -139.5	0.73 (1)	4.85			
D-O	-1201 / 0	-91.8 -91.8	0.14 (1)	5.65			
O-L	-1201 / 0	-91.8 -91.8	0.14 (1)	5.65			
L-E	-1608 / 0	-91.8 -91.8	0.15 (1)	5.03			
E-F	0 / 24	-91.8 -91.8	0.13 (1)	10.00			
B-I	0 / 1009	-28.1 -28.1	0.25 (1)	10.00			
I-H	0 / 1009	-28.1 -28.1	0.25 (1)	10.00			
H-P	0 / 1014	-28.1 -28.1	0.23 (1)	10.00			
P-Q	0 / 1014	-28.1 -28.1	0.23 (1)	10.00			
Q-G	0 / 1014	-28.1 -28.1	0.23 (1)	10.00			
G-R	0 / 977	-28.1 -28.1	0.22 (1)	10.00			
R-K	0 / 977	-28.1 -28.1	0.22 (1)	10.00			
K-E	0 / 977	-28.1 -28.1	0.22 (1)	10.00			

FACTORED CONCENTRATED LOADS (LBS)

JT	LOC.	LC1	MAX.	MAX+	FACE	DIR.	TYPE	HEEL	CONN.
C	1-11-4	-90	-90	---	FRONT	VERT	TOTAL	---	C1
C	1-11-4	-96	-96	---	BACK	VERT	TOTAL	---	C1
D	6-4-12	-90	-90	---	FRONT	VERT	TOTAL	---	C1
H	1-11-12	-51	-51	---	BACK	VERT	TOTAL	---	C1
M	2-11-12	-89	-89	---	BACK	VERT	TOTAL	---	C1
N	4-11-12	-89	-89	---	BACK	VERT	TOTAL	---	C1
O	6-11-12	-109	-109	---	BACK	VERT	TOTAL	---	C1
P	2-11-12	-51	-51	---	BACK	VERT	TOTAL	---	C1
Q	4-11-12	-51	-51	---	BACK	VERT	TOTAL	---	C1
R	6-11-12	-51	-51	---	BACK	VERT	TOTAL	---	C1

CONNECTION REQUIREMENTS

1) C1: A SUITABLE HANGER/MECHANICAL CONNECTION IS REQUIRED.

DESIGN CRITERIA

SPECIFIED LOADS:

TOP CH. LL = 25.6 PSF

DL = 6.0 PSF

BOT CH. LL = 0.0 PSF

DL = 7.4 PSF

TOTAL LOAD = 39.0 PSF

SPACING = 24.0 IN. C/C

LOADING IN FLAT SECTION BASED ON A SLOPE OF 6.00/12

GIRDER TYPE: CPrimeHip

SIDE SETBACK = 1-11-4

END SETBACK = 4-6-8

END WALL WIDTH = 5-8

CORNER FRAMING TYPE: CONVENTIONAL

END JACK TYPE: CONVENTIONAL

APPLIED TO FRONT SIDE

- ADD'L LOADS BASED ON 55 % OF GSL

THIS TRUSS IS DESIGNED FOR RESIDENTIAL OR SMALL BUILDING REQUIREMENTS OF PART 9, NBC 2015

THIS DESIGN COMPLIES WITH:

- PART 9 OF CBC 2018, ABC 2019
- PART 9 OF OBC 2012 (2019 AMENDMENT)
- CSA 086-14
- TPIC 2014

(55 % OF 31.3 P.S.F. G.S.L. PLUS 8.4 P.S.F. RAIN LOAD) EQUALS 25.6 P.S.F. SPECIFIED ROOF LIVE LOAD

ALLOWABLE DEFL.(LL) = L/360 (0.28")

CALCULATED VERT. DEFL.(LL) = L/999 (0.02")

ALLOWABLE DEFL.(TL) = L/360 (0.28")

CALCULATED VERT. DEFL.(TL) = L/999 (0.03")

CSI: TC=0.73/1.00 (C-D:1), BC=0.25/1.00 (B-I:1), WB=0.05/1.00 (D-G:4), SSI=0.35/1.00 (C-D:1)

DOL LUMBER=1.00 NAIL=1.00 LS BEND=1.00

COMP=1.00 SHEAR=1.00 TENS=1.00

COMPANION LIVE LOAD FACTOR = 1.00

TRUSS PLATE MANUFACTURER IS NOT RESPONSIBLE FOR QUALITY CONTROL IN THE TRUSS MANUFACTURING PLANT.

NAIL VALUES


PLATE	GRIP(DRY)	SHEAR	SECTION
(PSI)	(PLI)	(PLI)	
MT20	650	371	1747 788 1987 1873

PLATE PLACEMENT TOL. = 0.250 inches

PLATE ROTATION TOL. = 5.0 Deg.

JSI GRIP= 0.86 (D) (INPUT = 0.90)

JSI METAL= 0.28 (B) (INPUT = 1.00)




Structural component only
DWG# T-2017160

JOB NAME	TRUSS NAME	QUANTITY	PLY	JOB DESC.	DRWG NO.
410146	T13	1	2	GREEN PARK HOMES	

Tamarack Roof Truss, Burlington

Version 8.330 S May 6 2020 MTEK Industries, Inc. Tue Aug 4 13:53:06 2020 Page 1
ID:W63xGm60kc00SiyZ4EwBx6ZA2m0-JM?Upjyqg91RqLERi7cwFpP2MfO3ASy74YkE0yrDdx

Scale = 1:23.7



LUMBER	N. L. G. A. RULES	CHORDS	SIZE	LUMBER	DESCR.
F - A	2x6	DRY	No.2	SPF	
A - C	2x4	DRY	No.2	SPF	
D - C	2x4	DRY	No.2	SPF	
F - D	2x6	DRY	No.2	SPF	
ALL WEBS	2x3	DRY	No.2	SPF	
DRY: SEASONED LUMBER.					

DESIGN CONSISTS OF 2 TRUSSES BUILT SEPARATELY THEN FASTENED TOGETHER AS FOLLOWS:

CHORDS #ROWS	SURFACE SPACING (IN)	LOAD(PLF)
TOP CHORDS: (0.122"x3") SPIRAL NAILS		
F - A 2	12	TOP
A - C 1	12	TOP
C - D 1	12	TOP
BOTTOM CHORDS: (0.122"x3") SPIRAL NAILS		
F - D 2	12	TOP
WEBS: (0.122"x3") SPIRAL NAILS		
2x3 1	6	

NAILS TO BE DRIVEN FROM ONE SIDE ONLY.

TOP - COMPONENTS ARE LOADED FROM THE TOP AND MUST BE PLACED ON TOP EDGE OF ALL PLIES FOR THE LOAD TO BE TRANSFERRED TO EACH PLY.

PLATES (table is in inches)

JT TYPE	PLATES	W	LEN	Y	X
A	TMVW-p	MT20	4.0	6.0	1.00 3.00
B	TMVW-t	MT20	4.0	4.0	2.00 1.75
C	TMV+p	MT20	3.0	4.0	
D	BMVW1+p	MT20	4.0	6.0	
E	BMVW-t	MT20	5.0	6.0	
F	BMV1+p	MT20	3.0	6.0	

DIMENSIONS, SUPPORTS AND LOADINGS SPECIFIED BY FABRICATOR TO BE VERIFIED BY BUILDING DESIGNER

FACTORED	MAXIMUM FACTORED	INPUT	REQD
GROSS REACTION	BRG	BRG	
JT VERT	HORZ	DOWN	HORZ
F 1768	0	1768	0
D 1439	0	1439	0

A SUITABLE HANGER/MECHANICAL CONNECTION IS REQUIRED AT JOINT D. MINIMUM BEARING LENGTH AT JOINT D = 1-8.

UNFACTORED REACTIONS

1ST LCASE	MAX/MIN	COMPONENT REACTIONS
JT COMBINED	SNOW	LIVE
F 1244	853 / 0	0 / 0
D 1012	694 / 0	0 / 0

BEARING MATERIAL TO BE SPF NO.2 OR BETTER AT JOINT(S) F

BRACING

TOP CHORD TO BE SHEATHED OR MAX. PURLIN SPACING = 6.25 FT.
MAX. UNBRACED BOTTOM CHORD LENGTH = 10.00 FT OR RIGID CEILING DIRECTLY APPLIED.

ALL PITCH BREAKS AND PERIMETER CORNER JOINTS MUST BE LATERALLY RESTRAINED.

LOADING

TOTAL LOAD CASES: (4)

CHORDS	MEMB.	MAX. FACTORED FORCE (LBS)	FACTORED VERT. LOAD (PLF)	LC1	MAX	MAX. UNBRAC LENGTH	WEBS	MEMB.	MAX. FACTORED FORCE (LBS)	MAX
FR-TO							FR-TO			
F - A	-1047 / 0	0.0	0.0	0.04 (1)	7.81	A - E	0 / 1268	0.16 (1)		
A - B	-1360 / 0	-91.8	-91.8	0.06 (1)	6.25	E - B	0 / 1232	0.15 (1)		
B - C	-11 / 0	-91.8	-91.8	0.05 (1)	6.25	B - D	-1542 / 0	0.18 (1)		
D - C	-111 / 0	0.0	0.0	0.01 (1)	7.81					
F - G	0 / 0	-18.5	-18.5	0.15 (1)	10.00					
G - H	0 / 0	-18.5	-18.5	0.15 (1)	10.00					
H - E	0 / 0	-18.5	-18.5	0.15 (1)	10.00					
E - I	0 / 1226	-18.5	-18.5	0.26 (1)	10.00					
I - D	0 / 1226	-18.5	-18.5	0.26 (1)	10.00					

FACTORED CONCENTRATED LOADS (LBS)

JT	LOC.	LC1	MAX-	MAX+	FACE	DIR.	TYPE	HEEL	CONN.
G	6-12	-856	-856	---	TOP	VERT	TOTAL	---	C1
H	2-6-12	-852	-852	---	TOP	VERT	TOTAL	---	C1
I	4-6-12	-852	-852	---	TOP	VERT	TOTAL	---	C1

CONNECTION REQUIREMENTS

1) C1: A SUITABLE HANGER/MECHANICAL CONNECTION IS REQUIRED.

TOTAL WEIGHT = 2 X 29 = 58 lb [M]

DESIGN CRITERIA

SPECIFIED LOADS:

TOP CH.	LL =	25.6	PSF
	DL =	6.0	PSF
BOT CH.	LL =	0.0	PSF
	DL =	7.4	PSF
TOTAL LOAD	=	39.0	PSF

SPACING = 24.0 IN. C/C

THIS TRUSS IS DESIGNED FOR RESIDENTIAL OR SMALL BUILDING REQUIREMENTS OF PART 9, NBC 2015

THIS DESIGN COMPLIES WITH:

- PART 9 OF CBC 2018, ABC 2019
- PART 9 OF OBC 2012 (2019 AMENDMENT)
- CSA 086-14
- TPIC 2014

(55 % OF 31.3 P.S.F. G.S.L. PLUS 8.4 P.S.F. RAIN LOAD) EQUALS 25.6 P.S.F. SPECIFIED ROOF LIVE LOAD

ALLOWABLE DEFL.(LL) = L/360 (0.20")
CALCULATED VERT. DEFL.(LL) = L/999 (0.01")
ALLOWABLE DEFL.(TL) = L/360 (0.20")
CALCULATED VERT. DEFL.(TL) = L/999 (0.01")

CSI: TC=0.06/1.00 (A-B:1), BC=0.26/1.00 (D-E:1), WB=0.18/1.00 (B-D:1), SSI=0.35/1.00 (E-F:1)

DOL LUMBER=1.00 NAIL=1.00 LS BEND=1.00
COMP=1.00 SHEAR=1.00 TENS=1.00

COMPANION LIVE LOAD FACTOR = 1.00

TRUSS PLATE MANUFACTURER IS NOT RESPONSIBLE FOR QUALITY CONTROL IN THE TRUSS MANUFACTURING PLANT.

NAIL VALUES

PLATE	GRIP(DRY)	SHEAR	SECTION
(PSI)	(PLI)	(PLI)	
MAX	MIN	MAX	MIN
MT20	650	371	1747
	788	1987	1873

PLATE PLACEMENT TOL. = 0.250 inches

PLATE ROTATION TOL. = 5.0 Deg.

JSI GRIP= 0.80 (B) (INPUT = 0.90)
JSI METAL= 0.28 (D) (INPUT = 1.00)



Structural component only
DWG# T-2017161

JOB NAME	TRUSS NAME	QUANTITY	PLY	JOB DESC.	GREEN PARK HOMES	DRWG NO.
410143	T20	2	2	TRUSS DESC.		


Tamarack Roof Truss, Burlington

Version 8.330 S May 6 2020 MTek Industries, Inc. Tue Aug 4 13:08:55 2020 Page 1

ID:W63xGm6okc00SiY4EwBx6zA2m0-QLKIQEE3899AuQBkeP3x_DWJquqQ8mIX8zhAyrEHM

22-9-4 23-7-0 9-12

Scale = 1:36.7



JOB NAME	TRUSS NAME	QUANTITY	PLY	JOB DESC.	DRWG NO.
410143	T20	2	2	GREEN PARK HOMES	

Tamarack Roof Truss, Burlington

Version 8.330 S May 6 2020 MTEK Industries, Inc. Tue Aug 4 13:08:55 2020 Page 2
ID:W63xGm6okcO0SivZ4EwBx6zA2m0-QLKIQEE3899AuQBkeP3x DWJgkugQ8miX8tzhAyrEHM

PLATES (table is in inches)

JT	TYPE	PLATES	W	LEN	Y	X
C	TMW+w	MT20	3.0	6.0		
D	TS-t	MT20	5.0	6.0		
E	TMWW-t	MT20	5.0	6.0		
F	TMVW-t	MT20	5.0	6.0	2.50	2.75
G	BMV1+p	MT20	3.0	6.0		
H	BMWW-t	MT20	5.0	6.0	2.50	2.75
I	BMWWW-t	MT20	5.0	8.0		
J	BS-t	MT20	5.0	6.0		
K	BMWW-t	MT20	5.0	6.0	2.50	2.75
L	BMV1+p	MT20	3.0	6.0		

FACTORED CONCENTRATED LOADS (LBS)

JT	LOC.	LC1	MAX-	MAX+	FACE	DIR.	TYPE	HEEL	CONN.
P	7-9-4	-110	-110	---	FRONT	VERT	TOTAL	---	C1
Q	9-9-4	-110	-110	---	FRONT	VERT	TOTAL	---	C1
R	13-9-4	-110	-110	---	FRONT	VERT	TOTAL	---	C1
S	19-9-4	-110	-110	---	FRONT	VERT	TOTAL	---	C1
T	21-9-4	-110	-110	---	FRONT	VERT	TOTAL	---	C1
U	22-9-4	-119	-119	---	FRONT	VERT	TOTAL	---	C1
V	1-9-4	-26	-26	---	FRONT	VERT	TOTAL	---	C1
W	3-9-4	-26	-26	---	FRONT	VERT	TOTAL	---	C1
X	5-9-4	-26	-26	---	FRONT	VERT	TOTAL	---	C1
Y	9-9-4	-26	-26	---	FRONT	VERT	TOTAL	---	C1
Z	13-9-4	-26	-26	---	FRONT	VERT	TOTAL	---	C1
AA	15-9-4	-26	-26	---	FRONT	VERT	TOTAL	---	C1
AB	19-9-4	-26	-26	---	FRONT	VERT	TOTAL	---	C1
AC	21-9-4	-26	-26	---	FRONT	VERT	TOTAL	---	C1
AD	22-9-4	-28	-28	---	FRONT	VERT	TOTAL	---	C1

CONNECTION REQUIREMENTS


- 1) C1: A SUITABLE HANGER/MECHANICAL CONNECTION IS REQUIRED.



Structural component only
DWG# T-2017143 22

JOB NAME	TRUSS NAME	QUANTITY	PLY	JOB DESC.	DRWG NO.
410143	T20Z	2	2	GREEN PARK HOMES	
Tamarack Roof Truss, Burlington					

Version 8.330 S May 6 2020 Mitek Industries, Inc. Tue Aug 4 13:08:57 2020 Page 1
ID:W63xGm6okc00SiyZ4EwBx6zA2m0-NkR3rwFKgmPu7kL7mq6P3ebf5XUlu0W2_RM3m2yrEHK
23-1-12 23-7-0
Scale = 1:36.7



LUMBER			
N. L. G. A. RULES	CHORDS	SIZE	LUMBER
L - A	2x6	DRY	No.2
A - D	2x6	DRY	No.2
D - F	2x6	DRY	No.2
G - F	2x6	DRY	No.2
L - J	2x6	DRY	No.2
J - G	2x6	DRY	No.2

ALL WEBS 2x3 DRY No.2 SPF
DRY: SEASONED LUMBER.

DESIGN CONSISTS OF 2 TRUSSES BUILT SEPARATELY THEN FASTENED TOGETHER AS FOLLOWS:

CHORDS #ROWS	SURFACE SPACING (IN)	LOAD (PLF)
TOP CHORDS : (0.122"x3") SPIRAL NAILS		
L - A	2 12	TOP
A - D	2 12	SIDE(0.0)
D - F	2 12	SIDE(183.1)
F - G	2 12	TOP
BOTTOM CHORDS : (0.122"x3") SPIRAL NAILS		
L - J	2 12	TOP
J - G	2 12	SIDE(183.1)
WEBS : (0.122"x3") SPIRAL NAILS		
2x3	1 6	

NAILS TO BE DRIVEN FROM ONE SIDE ONLY.

GIRDER NAILING ASSUMES NAILED HANGERS ARE FASTENED WITH MIN. 3-0 INCH NAILS.

TOP - COMPONENTS ARE LOADED FROM THE TOP AND MUST BE PLACED ON TOP EDGE OF ALL PLIES FOR THE LOAD TO BE TRANSFERRED TO EACH PLY.

SIDE - PLF SHOWN IS THE EQUIVALENT UDL APPLIED TO ONE SIDE THAT THE CORRESPONDING NAILING PATTERN SHALL BE CAPABLE OF TRANSFERRING. REMAINING PLF MUST BE APPLIED ON THE OPPOSITE SIDE OR ON THE TOP.

PLATES (table is in inches)					
JT	TYPE	PLATES	W	LEN	Y X
A	TMWV-t	MT20	5.0	6.0	2.50 2.75
B	TMWV-t	MT20	5.0	6.0	

DIMENSIONS, SUPPORTS AND LOADINGS SPECIFIED BY FABRICATOR TO BE VERIFIED BY BUILDING DESIGNER

BEARINGS		FACTORED GROSS REACTION		MAXIMUM FACTORED DOWN		INPUT BRG		REQRD	
JT	VERT	HORZ	DOWN	HORZ	UPLIFT	IN-SX	BRG	IN-SX	BRG
L	1962	0	1962	0	0	3-8	3-8	1-8	
G	2624	0	2624	0	0	1-8			

UNFACTORED REACTIONS							
1ST LCASE MAX./MIN. COMPONENT REACTIONS							
JT	COMBINED	SNOW	LIVE	PERM.LIVE	WIND	DEAD	SOIL
L	1387	916 / 0	0 / 0	0 / 0	0 / 0	470 / 0	0 / 0
G	1855	1219 / 0	0 / 0	0 / 0	0 / 0	636 / 0	0 / 0

BEARING MATERIAL TO BE SPF NO.2 OR BETTER AT JOINT(S) L, G

BRACING
TOP CHORD TO BE SHEATHED OR MAX. PURLIN SPACING = 5.26 FT.
MAX. UNBRACED BOTTOM CHORD LENGTH = 10.00 FT OR RIGID CEILING DIRECTLY APPLIED.

ALL PITCH BREAKS AND PERIMETER CORNER JOINTS MUST BE LATERALLY RESTRAINED.

LOADING
TOTAL LOAD CASES: (4)

CHORDS		FACTORED		WEBS		FACTORED	
MEMB.	FORCE (LBS)	VERT. LOAD	MAX. CSI (LC)	MEMB.	FORCE (LBS)	MAX. CSI (LC)	
FR-TO		FROM	TO	FR-TO			
L - A	-1890 / 0	0.0	0.0 0.14 (1)	H - F	0 / 4150	0.51 (1)	
A - B	-2763 / 0	-91.8	-91.8 0.12 (1)	A - K	0 / 3223	0.40 (1)	
B - C	-4415 / 0	-91.8	-91.8 0.14 (1)	H - E	-1581 / 0	0.19 (1)	
C - M	-4415 / 0	-91.8	-91.8 0.22 (1)	K - B	-1664 / 0	0.20 (1)	
M - N	-4415 / 0	-91.8	-91.8 0.22 (1)	I - E	0 / 1016	0.13 (1)	
N - D	-4415 / 0	-91.8	-91.8 0.22 (1)	B - I	0 / 1959	0.24 (1)	
D - E	-4415 / 0	-91.8	-91.8 0.22 (1)	I - C	-544 / 0	0.07 (1)	
E - O	-3558 / 0	-91.8	-91.8 0.21 (1)				
O - P	-3558 / 0	-91.8	-91.8 0.21 (1)				
P - Q	-3558 / 0	-91.8	-91.8 0.21 (1)				
Q - F	-3558 / 0	-91.8	-91.8 0.21 (1)				
G - F	-2567 / 0	0.0	0.0 0.19 (1)				
L - K	0 / 0	-18.5	-18.5 0.05 (1)				
K - J	0 / 2763	-18.5	-18.5 0.35 (1)				
J - I	0 / 2763	-18.5	-18.5 0.35 (1)				
I - R	0 / 3558	-18.5	-18.5 0.60 (1)				
R - S	0 / 3558	-18.5	-18.5 0.60 (1)				
S - T	0 / 3558	-18.5	-18.5 0.60 (1)				
T - H	0 / 3558	-18.5	-18.5 0.60 (1)				
H - U	0 / 0	-18.5	-18.5 0.12 (1)				
U - V	0 / 0	-18.5	-18.5 0.12 (1)				
V - W	0 / 0	-18.5	-18.5 0.12 (1)				
W - G	0 / 0	-18.5	-18.5 0.12 (1)				

FACTORED CONCENTRATED LOADS (LBS)									
JT	LOC.	LC1	MAX.	MAX+	FACE	DIR.	TYPE	HEEL	CONN.
E	17-4-12	-110	-110	---	BACK	VERT	TOTAL	---	C1
H	17-4-12	-26	-26	---	BACK	VERT	TOTAL	---	C1
M	14-6-4	-110	-110	---	BACK	VERT	TOTAL	---	C1
N	15-4-12	-110	-110	---	BACK	VERT	TOTAL	---	C1
O	19-4-12	-110	-110	---	BACK	VERT	TOTAL	---	C1
P	21-4-12	-110	-110	---	BACK	VERT	TOTAL	---	C1
Q	23-1-12	-136	-136	---	BACK	VERT	TOTAL	---	C1
R	13-5-8	-1134	-1134	---	BACK	VERT	TOTAL	---	C1
S	14-6-4	-26	-26	---	BACK	VERT	TOTAL	---	C1
T	15-4-12	-26	-26	---	BACK	VERT	TOTAL	---	C1
U	19-4-12	-26	-26	---	BACK	VERT	TOTAL	---	C1
V	21-4-12	-26	-26	---	BACK	VERT	TOTAL	---	C1
W	23-1-12	-32	-32	---	BACK	VERT	TOTAL	---	C1

DESIGN CRITERIA

SPECIFIED LOADS:
TOP CH. LL = 25.6 PSF
DL = 6.0 PSF
BOT CH. LL = 0.0 PSF
DL = 7.4 PSF
TOTAL LOAD = 39.0 PSF

SPACING = 24.0 IN. C/C

LOADING IN FLAT SECTION BASED ON A SLOPE OF 6.00/12

THIS TRUSS IS DESIGNED FOR RESIDENTIAL OR SMALL BUILDING REQUIREMENTS OF PART 9, NBCC 2015

THIS DESIGN COMPLIES WITH:
- PART 9 OF BCBC 2018, ABC 2019
- PART 9 OF OBC 2012 (2019 AMENDMENT)
- CSA 086-14
- TPIC 2014

(55% OF 31.3 P.S.F. G.S.L. PLUS 8.4 P.S.F. RAIN LOAD) EQUALS 25.6 P.S.F. SPECIFIED ROOF LIVE LOAD

ALLOWABLE DEFL.(LL) = L/360 (0.79")
CALCULATED VERT. DEFL.(LL) = L/999 (0.10")
ALLOWABLE DEFL.(TL) = L/360 (0.79")
CALCULATED VERT. DEFL.(TL) = L/999 (0.19")

CSI: TC=0.22/1.00 (C-E:1), BC=0.60/1.00 (H-I:1), WB=0.51/1.00 (F-H:1), SSI=0.30/1.00 (H-I:1)

DOL LUMBER=1.00 NAIL=1.00 LS BEND=1.00
COMP=1.00 SHEAR=1.00 TENS=1.00

COMPANION LIVE LOAD FACTOR = 1.00

TRUSS PLATE MANUFACTURER IS NOT RESPONSIBLE FOR QUALITY CONTROL IN THE TRUSS MANUFACTURING PLANT

NAIL VALUES
PLATE GRIP(DRY) SHEAR SECTION
(P.S.I) (P.LI) (P.LI)
MAX MIN MAX MIN MAX MIN
MT20 650 371 1747 788 1987 1873

PLATE PLACEMENT TOL. = 0.250 inches

PLATE ROTATION TOL. = 5.0 Deg.

JSI GRIP= 0.86 (K) (INPUT = 0.90)
JSI METAL= 0.42 (J) (INPUT = 1.00)



Structural component only
DWG# T-2017144 1/2

JOB NAME 410143	TRUSS NAME T20Z	QUANTITY 2	PLY 2	JOB DESC. GREEN PARK HOMES	DRWG NO.
Tamarack Roof Truss, Burlington				TRUSS DESC.	


Version 8.330 S May 6 2020 MiTek Industries, Inc. Tue Aug 4 13:08:57 2020 Page 2
ID:W63xGm6okcO0SiyZ4EwBx6zA2m0-NkR3rwFKgmPu7kL7mq6P3ebf5XUiu0W2 RM3m2vrEHK

PLATES (table is in inches)

JT	TYPE	PLATES	W	LEN	Y	X
C	TMW+w	MT20	3.0	6.0		
D	TS-t	MT20	5.0	6.0		
E	TMWW-t	MT20	5.0	6.0		
F	TMVW-t	MT20	5.0	6.0	2.50	2.75
G	BMV1+p	MT20	3.0	6.0		
H	BMWW-t	MT20	5.0	6.0	2.50	2.75
I	BMWWW-t	MT20	5.0	8.0		
J	BS-t	MT20	5.0	6.0		
K	BMVW-t	MT20	5.0	6.0	2.50	2.75
L	BMV1+p	MT20	3.0	6.0		

CONNECTION REQUIREMENTS

- 1) C1: A SUITABLE HANGER/MECHANICAL CONNECTION IS REQUIRED.



Structural component only
DWG# T-2017144 2/2

Structural drawing of a roof truss system. The truss consists of a top chord with joints A, B, C, D, E, F and a bottom chord with joints L, B1, J, I, H, G. Vertical members connect A-L, B-B1, C-I, D-H, E-H, and F-G. Diagonal members connect A-B1, B-C, C-I, D-H, E-H, and F-G. Horizontal members connect B-B1, J-I, and I-H. The truss is supported by a wall at joint L and a roller support at joint G. Dimensions are given for members and spans. Members are labeled with their size and type: W1 (vertical), W2 (diagonal), W3 (vertical), T1 (top chord), T2 (top chord), B1 (bottom chord), J (bottom chord), I (bottom chord), H (bottom chord), G (bottom chord), L (bottom chord). The drawing includes a scale bar at the bottom with dimensions in feet and inches.

JSI GRIP= 0.76 (F) (INPUT = 0.90)
JSI METAL= 0.43 (J) (INPUT = 1.00)




Structural component only
DWG# T-2017145

JOB NAME	TRUSS NAME	QUANTITY	PLY	JOB DESC.	DRWG NO.
410143	T22	4	1	GREEN PARK HOMES	

Tamarack Roof Truss, Burlington

Version 8.330 S May 6 2020 MTek Industries, Inc. Tue Aug 4 13:08:59 2020 Page 1
ID:W63xGm6k0c00SiyZ4EwBx6zA2m0-J7ZpGcHaCnfcN2VvIF8t83hqqLEBMwhKSlrAqxyrEHl



LUMBER
N. L. G. A. RULES
CHORDS SIZE LUMBER DESCR.
L - A 2x4 DRY No.2 SPF
A - D 2x4 DRY No.2 SPF
D - F 2x4 DRY No.2 SPF
G - F 2x4 DRY No.2 SPF
L - J 2x4 DRY No.2 SPF
J - G 2x4 DRY No.2 SPF
ALL WEBS 2x3 DRY No.2 SPF
DRY: SEASONED LUMBER.

DIMENSIONS, SUPPORTS AND LOADINGS SPECIFIED BY FABRICATOR TO BE VERIFIED BY BUILDING DESIGNER									
BEARINGS									
	FACTORED	MAXIMUM FACTORED		INPUT	REQ'D				
	GROSS REACTION	GROSS REACTION		BRG	BRG				
JT	VERT	HORZ	DOWN	HORZ	UPLIFT	IN-SX	IN-SX		
L	1300	0	1300	0	0	3-8	3-8		
G	1300	0	1300	0	0	1-8	1-8		

UNFACTORED REACTIONS									
JT	1ST CASE	MAX./MIN. COMPONENT REACTIONS							
	COMBINED	SNOW	LIVE	PERM. LIVE	WIND	DEAD	SOIL		
L	919	603 / 0	0 / 0	0 / 0	0 / 0	316 / 0	0 / 0		
G	919	603 / 0	0 / 0	0 / 0	0 / 0	316 / 0	0 / 0		

BEARING MATERIAL TO BE SPF NO.2 OR BETTER AT JOINT(S) L, G

BRACING
TOP CHORD TO BE SHEATHED OR MAX. PURLIN SPACING = 4.85 FT.
MAX. UNBRACED BOTTOM CHORD LENGTH = 10.00 FT. OR RIGID CEILING DIRECTLY APPLIED.
ALL PITCH BREAKS AND PERIMETER CORNER JOINTS MUST BE LATERALLY RESTRAINED.

LOADING
TOTAL LOAD CASES: (4)

BS-t

MT20

3.0

6.0

BMVW-t

MT20

5.0

6.0

BMV1+p

MT20

3.0

4.0

CHORDS

MEMB.

MAX. FACTORED FORCE (LBS)

FACTORED VERT. LOAD (PLF)

LC1

MAX. CSI (LC)

MAX. UNBRACED LENGTH

FR-TO

L-A

-1255 / 0

0.0

0.0

0.91 (1)

7.17

H-F

A-B

-1068 / 0

-91.8

-91.8

0.52 (1)

5.35

A-K

B-C

-1360 / 0

-91.8

-91.8

0.54 (1)

4.85

H-E

C-D

-1360 / 0

-91.8

-91.8

0.54 (1)

4.85

K-B

D-E

-1360 / 0

-91.8

-91.8

0.54 (1)

4.85

I-E

E-F

-1068 / 0

-91.8

-91.8

0.52 (1)

5.35

B-I

G-F

-1255 / 0

0.0

0.0

0.91 (1)

7.17

I-C

L-K

0 / 0

-18.5

-18.5

0.16 (4)

10.00

K-J

0 / 1068

-18.5

-18.5

0.26 (1)

10.00

J-I

0 / 1068

-18.5

-18.5

0.26 (1)

10.00

I-H

0 / 1068

-18.5

-18.5

0.26 (1)

10.00

H-G

0 / 0

-18.5

-18.5

0.16 (4)

10.00

WEBS

MEMB.

MAX. FACTORED FORCE (LBS)

MAX. CSI (LC)

H-F

0 / 1489

0.34 (1)

A-K

0 / 1489

0.34 (1)

H-E

-912 / 0

0.53 (1)

K-B

-912 / 0

0.53 (1)

I-E

0 / 412

0.09 (1)

B-I

0 / 412

0.09 (1)

I-C

-487 / 0

0.28 (1)

(55% OF 31.3 P.S.F. G.S.L. PLUS 8.4 P.S.F. RAIN LOAD) EQUALS 25.6 P.S.F. SPECIFIED ROOF LIVE LOAD

ALLOWABLE DEFL.(LL)= L/360 (0.79")

CALCULATED VERT. DEFL.(LL) = L/ 999 (0.06")

ALLOWABLE DEFL.(TL)= L/360 (0.79")

CALCULATED VERT. DEFL.(TL) = L/ 999 (0.11")

CSI: TC=0.91/1.00 (A-L:1), BC=0.26/1.00 (H-I:1), WB=0.53/1.00 (E-H:1), SSI=0.26/1.00 (A-B:1)

DOL LUMBER=1.00 NAIL=1.00 LS BEND=1.10

COMP=1.10 SHEAR=1.10 TENS=1.10

COMPANION LIVE LOAD FACTOR = 1.00

TRUSS PLATE MANUFACTURER IS NOT

TRUSS PLATE MANUFACTURER IS NOT RESPONSIBLE FOR QUALITY CONTROL IN THE TRUSS MANUFACTURING PLANT.

NAIL VALUES
PLATE GRIP (DRY) SHEAR SECTION
(PSI) (PLI) (PLI)
MAX MIN MAX MIN MAX MIN
MT20 650 371 1747 788 1987 1873

PLATE PLACEMENT TOL. = 0.250 inches

PLATE ROTATION TOL. = 5.0 Deg.

JSI GRIP = 0.71 (H) (INPUT = 0.90)
JSI METAL = 0.32 (J) (INPUT = 1.00)




Structural component only
DWG# T-2017146

JOB NAME	TRUSS NAME	QUANTITY	PLY	JOB DESC.	DRWG NO.
410143	T23	18	1	GREEN PARK HOMES	

Tamarack Roof Truss, Burlington

Version 8.330 S May 6 2020 MTek Industries, Inc. Tue Aug 4 13:09:00 2020 Page 1
ID:W63xGm6okcO0SiyZ4EwBx6zA2m0-nJ7BTyHCzhnT_C4iRyf6hGD5Zlb5JpUgPbkNNyrEH



TOTAL WEIGHT = 18 X 113 = 2026 lb [M]

LUMBER				DESCR.	
N. L. G. A. RULES	CHORDS	SIZE	LUMBER	SPF	
L - A	2x4	DRY	No.2	SPF	
A - D	2x4	DRY	No.2	SPF	
D - F	2x4	DRY	No.2	SPF	
G - F	2x4	DRY	No.2	SPF	
L - J	2x4	DRY	No.2	SPF	
J - G	2x4	DRY	No.2	SPF	
ALL WEBS	2x3	DRY	No.2	SPF	
DRY: SEASONED LUMBER.					

PLATES (table is in inches)

JT	TYPE	PLATES	W	LEN	Y	X
A	TMVW+p	MT20	5.0	6.0		
B	TMVW-t	MT20	4.0	4.0		
C	TMVW-w	MT20	2.0	4.0		
D	TS-t	MT20	3.0	6.0		
E	TMVW-t	MT20	4.0	4.0		
F	TMVW+p	MT20	5.0	6.0		
G	BMV1+p	MT20	3.0	4.0		
H	BMVW-t	MT20	5.0	6.0		
I	BMVWW-t	MT20	4.0	9.0		
J	BS-t	MT20	3.0	6.0		
K	BMVW-t	MT20	5.0	6.0		
L	BMV1+p	MT20	3.0	4.0		

DIMENSIONS, SUPPORTS AND LOADINGS SPECIFIED BY FABRICATOR TO BE VERIFIED BY BUILDING DESIGNER

BEARINGS		FACTORED GROSS REACTION	MAXIMUM FACTORED GROSS REACTION	INPUT BRG	REQD BRG
JT	VERT	HORZ	DOWN	HORZ	UPLIFT
L	1300	0	1300	0	3-8
G	1300	0	1300	0	1-8

UNFACTORED REACTIONS

1ST LCASE	MAX./MIN. COMPONENT REACTIONS						
JT	COMBINED	SNOW	LIVE	PERM.LIVE	WIND	DEAD	SOIL
L	919	603 / 0	0 / 0	0 / 0	0 / 0	316 / 0	0 / 0
G	919	603 / 0	0 / 0	0 / 0	0 / 0	316 / 0	0 / 0

BEARING MATERIAL TO BE SPF NO.2 OR BETTER AT JOINT(S) L, G

BRACING

TOP CHORD TO BE SHEATHED OR MAX. PURLIN SPACING = 5.16 FT.
MAX. UNBRACED BOTTOM CHORD LENGTH = 10.00 FT OR RIGID CEILING DIRECTLY APPLIED.

ALL PITCH BREAKS AND PERIMETER CORNER JOINTS MUST BE Laterally RESTRAINED.

1 LATERAL BRACE(S) AT 1/2 LENGTH OF A-L, F-G.

END VERTICAL(S) MUST BE SHEATHED OR HAVE BRACES AS INDICATED IN THE MAX. UNBRACED LENGTH COLUMN OF THE TABLE BELOW

LOADING

TOTAL LOAD CASES: (4)

CHORDS				WEBS			
MEMB.	MAX. FACTORED FORCE (LBS)	FACTORED VERT. LOAD (PLF)	MAX. UNBRACED LENGTH (LC1)	MEMB.	MAX. FACTORED FORCE (LBS)	MAX. UNBRACED LENGTH (LC1)	
FR-TO		FROM TO		FR-TO			
L-A	-1255 / 0	0.0	0.0 0.29 (1)	5.74	H-F	0 / 1381	0.31 (1)
A-B	-912 / 0	-91.8	-91.8 0.51 (1)	5.68	A-K	0 / 1381	0.31 (1)
B-C	-1160 / 0	-91.8	-91.8 0.52 (1)	5.16	H-E	-912 / 0	0.80 (1)
C-D	-1160 / 0	-91.8	-91.8 0.52 (1)	5.16	K-B	-912 / 0	0.80 (1)
D-E	-1160 / 0	-91.8	-91.8 0.52 (1)	5.16	I-E	0 / 383	0.09 (1)
E-F	-912 / 0	-91.8	-91.8 0.51 (1)	5.68	B-I	0 / 383	0.09 (1)
G-F	-1255 / 0	0.0	0.0 0.29 (1)	5.74	I-C	-486 / 0	0.43 (1)
L-K	0 / 0	-18.5	-18.5 0.16 (4)	10.00			
K-J	0 / 912	-18.5	-18.5 0.24 (4)	10.00			
J-I	0 / 912	-18.5	-18.5 0.24 (4)	10.00			
I-H	0 / 912	-18.5	-18.5 0.24 (4)	10.00			
H-G	0 / 0	-18.5	-18.5 0.16 (4)	10.00			

DESIGN CRITERIA

SPECIFIED LOADS:

TOP CH.	LL =	25.6	PSF
	DL =	6.0	PSF
BOT CH.	LL =	0.0	PSF
	DL =	7.4	PSF
TOTAL LOAD	=	39.0	PSF

SPACING = 24.0 IN. C/C

LOADING IN FLAT SECTION BASED ON A SLOPE OF 6.00/12

THIS TRUSS IS DESIGNED FOR RESIDENTIAL OR SMALL BUILDING REQUIREMENTS OF PART 9, NBCC 2015

THIS DESIGN COMPLIES WITH:

- PART 9 OF CBC 2018, ABC 2019
- PART 9 OF OBC 2012 (2019 AMENDMENT)
- CSA 086-14
- TPIC 2014

(55 % OF 31.3 P.S.F. G.S.L. PLUS 8.4 P.S.F. RAIN LOAD) EQUALS 25.6 P.S.F. SPECIFIED ROOF LIVE LOAD

ALLOWABLE DEFL.(LL) = L/360 (0.79")
CALCULATED VERT. DEFL.(LL) = L/999 (0.05")
ALLOWABLE DEFL.(TL) = L/360 (0.79")
CALCULATED VERT. DEFL.(TL) = L/999 (0.10")

CSI: TC=0.52/1.00 (B-C:1), BC=0.24/1.00 (H-I:4), WB=0.80/1.00 (E-H:1), SI=0.26/1.00 (A-B:1)

DOL LUMBER=1.00 NAIL=1.00 LS BEND=1.10
COMP=1.10 SHEAR=1.10 TENS=1.10

COMPANION LIVE LOAD FACTOR = 1.00

TRUSS PLATE MANUFACTURER IS NOT RESPONSIBLE FOR QUALITY CONTROL IN THE TRUSS MANUFACTURING PLANT.

NAIL VALUES

PLATE	GRIP(DRY)	SHEAR	SECTION
	(PSI)	(PLI)	(PLI)
	MAX	MIN	MAX
MT20	650	371	1747

PLATE PLACEMENT TOL. = 0.250 inches

PLATE ROTATION TOL. = 5.0 Deg.

JSI GRIP= 0.64 (H) (INPUT = 0.90)
JSI METAL= 0.33 (A) (INPUT = 1.00)




Structural component only
DWG# T-2017147

JOB NAME	TRUSS NAME	QUANTITY	PLY	JOB DESC.	DRWG NO.
410143	T24	6	1	GREEN PARK HOMES	

Tamarack Roof Truss, Burlington

Version 8.330 S May 6 2020 Mitek Industries, Inc. Tue Aug 4 13:09:01 2020 Page 1
ID:W63xGm6okc00SiyZ4EwBx6zA2m0-FVhahllqk?vKcLeu?fALDUMs9wRqs3dv3KHvqyrEHG

Scale = 1:49.4



TOTAL WEIGHT = 6 X 70 = 420 lb [M][F]

LUMBER				DESCR.	
N. L. G. A. RULES	CHORDS	SIZE	LUMBER		
A - D	2x4	DRY	No.2	SPF	
D - G	2x4	DRY	No.2	SPF	
J - B	2x4	DRY	No.2	SPF	
H - F	2x4	DRY	No.2	SPF	
J - H	2x4	DRY	No.2	SPF	
ALL WEBS EXCEPT	2x3	DRY	No.2	SPF	

DRY: SEASONED LUMBER.

PLATES (table is in inches)

JT	TYPE	PLATES	W	LEN	Y	X
B	TMV+p	MT20	3.0	4.0		
C	TMWW-t	MT20	4.0	4.0	2.00	1.75
D	TTW+p	MT20	4.0	6.0		
E	TMWW-t	MT20	4.0	4.0	2.00	1.75
F	TMV+p	MT20	3.0	4.0		
H	BMVW1-t	MT20	4.0	4.0		
I	BMWWW-t	MT20	4.0	9.0		
J	BMVW1-t	MT20	4.0	4.0		

DIMENSIONS, SUPPORTS AND LOADINGS SPECIFIED BY FABRICATOR TO BE VERIFIED BY BUILDING DESIGNER

FACTORED GROSS REACTION		MAXIMUM FACTORED GROSS REACTION		INPUT BRG		REQRD BRG	
JT	VERT	HORZ	DOWN	HORZ	UPLIFT	IN-SX	IN-SX
J	872	0	872	0	0	5-8	5-8
H	872	0	872	0	0	5-8	5-8

UNFACTORED REACTIONS

JT	1ST CASE	MAX/MIN. COMPONENT REACTIONS	SNOW	LIVE	PERM. LIVE	WIND	DEAD	SOIL
J	614	417 / 0	0 / 0	0 / 0	0 / 0	0 / 0	198 / 0	0 / 0
H	614	417 / 0	0 / 0	0 / 0	0 / 0	0 / 0	198 / 0	0 / 0

BEARING MATERIAL TO BE SPF NO.2 OR BETTER AT JOINT(S) J, H

BRACING

TOP CHORD TO BE SHEATHED OR MAX. PURLIN SPACING = 6.25 FT.
MAX. UNBRACED BOTTOM CHORD LENGTH = 10.00 FT. OR RIGID CEILING DIRECTLY APPLIED.

ALL PITCH BREAKS AND PERIMETER CORNER JOINTS MUST BE Laterally RESTRAINED.

LOADING

TOTAL LOAD CASES: (4)

CHORDS				WEBS			
MEMB.	MAX. FACTORED FORCE (LBS)	FACTORED VERT. LOAD (PLF)	MAX. FACTORED VERT. LOAD (LC1)	MEMB.	MAX. FACTORED FORCE (LBS)	MAX. FACTORED VERT. LOAD (LC1)	MAX. FACTORED VERT. LOAD (LC1)
FR-TO		FROM	TO	FR-TO		FROM	TO
A-B	0.45	-91.8	-91.8 0.13 (1)	I-D	0.387	0.09 (1)	0.09 (1)
B-C	0.25	-91.8	-91.8 0.17 (1)	I-E	-143.0	0.09 (1)	0.09 (1)
C-D	-471.0	-91.8	-91.8 0.13 (1)	C-I	-143.0	0.09 (1)	0.09 (1)
D-E	-471.0	-91.8	-91.8 0.13 (1)	J-C	-703.0	0.41 (1)	0.41 (1)
E-F	0.25	-91.8	-91.8 0.17 (1)	E-H	-703.0	0.41 (1)	0.41 (1)
F-G	0.45	-91.8	-91.8 0.13 (1)				
J-B	-245.0	0.0	0.0 0.03 (1)				
H-F	-245.0	0.0	0.0 0.03 (1)				
J-I	0.398	-18.5	-18.5 0.27 (4)				
I-H	0.398	-18.5	-18.5 0.27 (4)				

DESIGN CRITERIA

SPECIFIED LOADS:
TOP CH. LL = 25.6 PSF
DL = 6.0 PSF
BOT CH. LL = 0.0 PSF
DL = 7.4 PSF
TOTAL LOAD = 39.0 PSF

SPACING = 24.0 IN. C/C

THIS TRUSS IS DESIGNED FOR RESIDENTIAL OR SMALL BUILDING REQUIREMENTS OF PART 9, NBC 2015

THIS DESIGN COMPLIES WITH:
- PART 9 OF BCBC 2018, ABC 2019
- PART 9 OF OBC 2012 (2019 AMENDMENT)
- CSA 086-14
- TPIC 2014

(55 % OF 31.3 P.S.F. G.S.L. PLUS 8.4 P.S.F. RAIN LOAD) EQUALS 25.6 P.S.F. SPECIFIED ROOF LIVE LOAD

ALLOWABLE DEFL.(LL)= L/360 (0.45")
CALCULATED VERT. DEFL.(LL)= L/999 (0.01")
ALLOWABLE DEFL.(TL)= L/360 (0.45")
CALCULATED VERT. DEFL.(TL)= L/999 (0.05")

CSI: TC=0.17/1.00 (E-F:1), BC=0.27/1.00 (H-I:4), WB=0.41/1.00 (C-J:1), SSI=0.11/1.00 (D-E:1)

DOL LUMBER=1.00 NAIL=1.00 LS BEND=1.10
COMP=1.10 SHEAR=1.10 TENS=1.10

COMPANION LIVE LOAD FACTOR = 1.00

TRUSS PLATE MANUFACTURER IS NOT RESPONSIBLE FOR QUALITY CONTROL IN THE TRUSS MANUFACTURING PLANT.

NAIL VALUES
PLATE GRIP(DRY) SHEAR SECTION
(PSI) (PLI) (PLI)
MAX MIN MAX MIN MAX MIN
MT20 650 371 1747 788 1987 1873

PLATE PLACEMENT TOL. = 0.250 inches

PLATE ROTATION TOL. = 5.0 Deg.

JSI GRIP= 0.73 (E) (INPUT = 0.90)
JSI METAL= 0.24 (C) (INPUT = 1.00)




Structural component only
DWG# T-2017148

JOB NAME	TRUSS NAME	QUANTITY	PLY	JOB DESC.	DRWG NO.
410143	T25	6	1	GREEN PARK HOMES	
Tamarack Roof Truss, Burlington				TRUSS DESC.	

Version 8.330 S May 6 2020 MTek Industries, Inc. Tue Aug 4 13:09:01 2020 Page 1
ID:W63xGm60kc00SiyZ4EwBx6zA2m0-FVhahllqk?vKcLeu?rALDUMr9wcqpQdv3KHvqyrEHG

Scale = 1:56.3



TOTAL WEIGHT = 6 X 73 = 437 lb
(M/F)

LUMBER				DESCR.
N. L. G. A. RULES	CHORDS	SIZE	LUMBER	
A - C	2x4	DRY	No.2	SPF
C - E	2x4	DRY	No.2	SPF
H - A	2x4	DRY	No.2	SPF
F - E	2x4	DRY	No.2	SPF
H - F	2x4	DRY	No.2	SPF

ALL WEBS 2x3 DRY No.2 SPF
EXCEPT

DRY: SEASONED LUMBER.

PLATES (table is in inches)

JT	TYPE	PLATES	W	LEN	Y	X
A	TMV+p	MT20	3.0	4.0		
B	TMWW-t	MT20	4.0	4.0	2.00	1.75
C	TTW+p	MT20	4.0	6.0		
D	TMWW-t	MT20	4.0	4.0	2.00	1.50
E	TMV+p	MT20	3.0	4.0		
F	BMVW1-t	MT20	4.0	4.0		
G	BMVWW-t	MT20	4.0	9.0		
H	BMVW1-t	MT20	4.0	4.0		

DIMENSIONS, SUPPORTS AND LOADINGS SPECIFIED BY FABRICATOR TO BE VERIFIED BY BUILDING DESIGNER

BEARINGS

	FACTORED GROSS REACTION	MAXIMUM FACTORED GROSS REACTION	INPUT BRG	REQD BRG
JT	VERT	HORZ	DOWN	HORZ
H	735	0	735	0
F	735	0	735	0

A SUITABLE HANGER/MECHANICAL CONNECTION IS REQUIRED AT JOINT F. MINIMUM BEARING LENGTH AT JOINT F = 1-8.

UNFACTORED REACTIONS

JT	1ST CASE	MAX./MIN. COMPONENT REACTIONS	SNOW	LIVE	PERM. LIVE	WIND	DEAD	SOIL
H	COMBINED	520	341 / 0	0 / 0	0 / 0	0 / 0	179 / 0	0 / 0
F	COMBINED	520	341 / 0	0 / 0	0 / 0	0 / 0	179 / 0	0 / 0

BEARING MATERIAL TO BE SPF NO.2 OR BETTER AT JOINT(S) H

BRACING

TOP CHORD TO BE SHEATHED OR MAX. PURLIN SPACING = 6.25 FT.
MAX. UNBRACED BOTTOM CHORD LENGTH = 10.00 FT. OR RIGID CEILING DIRECTLY APPLIED.

ALL PITCH BREAKS AND PERIMETER CORNER JOINTS MUST BE Laterally RESTRAINED.

LOADING

TOTAL LOAD CASES: (4)

CHORDS				WEBS			
MEMB.	MAX. FACTORED FORCE (LBS)	FACTORED VERT. LOAD (PLF)	MAX. CSI (LC)	MEMB.	MAX. FACTORED FORCE (LBS)	MAX. CSI (LC)	
FR-TO		FROM TO		FR-TO			
A-B	0 / 25	-91.8 -91.8	0.16 (1)	B-G	-72 / 13	0.07 (1)	
B-C	-402 / 0	-91.8 -91.8	0.12 (1)	G-C	0 / 299	0.07 (1)	
C-D	-404 / 0	-91.8 -91.8	0.13 (1)	G-D	-94 / 7	0.09 (1)	
D-E	0 / 25	-91.8 -91.8	0.17 (1)	H-B	-650 / 0	0.57 (1)	
H-A	-113 / 0	0.0 0.0	0.02 (1)	D-F	-646 / 0	0.58 (1)	
F-E	-121 / 0	0.0 0.0	0.02 (1)				
H-G	0 / 302	-18.5 -18.5	0.26 (4)				
G-F	0 / 312	-18.5 -18.5	0.26 (4)				

DESIGN CRITERIA

SPECIFIED LOADS:

TOP CH.	LL =	25.6	PSF
	DL =	6.0	PSF
BOT CH.	LL =	0.0	PSF
	DL =	7.4	PSF
TOTAL LOAD	=	39.0	PSF

SPACING = 24.0 IN. CC

THIS TRUSS IS DESIGNED FOR RESIDENTIAL OR SMALL BUILDING REQUIREMENTS OF PART 9, NBCC 2015

THIS DESIGN COMPLIES WITH:

- PART 9 OF BCBC 2018, ABC 2019
- PART 9 OF OBC 2012 (2019 AMENDMENT)
- CSA 086-14
- TPIC 2014

(55 % OF 31.3 P.S.F. G.S.L. PLUS 8.4 P.S.F. RAIN LOAD) EQUALS 25.6 P.S.F. SPECIFIED ROOF LIVE LOAD

ALLOWABLE DEFL.(LL) = L/360 (0.44")
CALCULATED VERT. DEFL.(LL) = L/999 (0.01")
ALLOWABLE DEFL.(TL) = L/360 (0.44")
CALCULATED VERT. DEFL.(TL) = L/999 (0.05")

CSI: TC=0.17/1.00 (D-E:1), BC=0.26/1.00 (F-G:4),
WB=0.58/1.00 (D-F:1), SSI=0.11/1.00 (D-E:1)

DOL LUMBER=1.00 NAIL=1.00 LS BEND=1.10
COMP=1.10 SHEAR=1.10 TENS=1.10

COMPANION LIVE LOAD FACTOR = 1.00

TRUSS PLATE MANUFACTURER IS NOT RESPONSIBLE FOR QUALITY CONTROL IN THE TRUSS MANUFACTURING PLANT.

NAIL VALUES

PLATE	GRIP (DRY)	SHEAR	SECTION
	(PSI)	(PLI)	(PLI)
	MAX	MIN	MAX MIN
MT20	650	371	1747 788 1987 1873

PLATE PLACEMENT TOL. = 0.250 inches

PLATE ROTATION TOL. = 5.0 Deg.

JSI GRIP= 0.67 (B) (INPUT = 0.90)
JSI METAL= 0.22 (D) (INPUT = 1.00)




Structural component only
DWG# T-2017149

JOB NAME	TRUSS NAME	QUANTITY	PLY	JOB DESC.	DRWG NO.
410143	G26	2	1	GREEN PARK HOMES	
Tamarack Roof Truss, Burlington				TRUSS DESC.	

Version 8.330 S May 6 2020 MTek Industries, Inc. Tue Aug 4 13:08:49 2020 Page 1
ID:W63xGm6okcO0SiyZ4EwBx6zA2m0-cBz1AB9JZJO1AVka8yXkyGJVuX0VYs8CQeUWYrEHS

Scale = 1:36.0



LUMBER				DESCR.	
N. L. G. A. RULES	SIZE	LUMBER			
CHORDS				SPF	
L - B	2x4	DRY	No.2	SPF	
A - D	2x4	DRY	No.2	SPF	
D - G	2x4	DRY	No.2	SPF	
H - F	2x4	DRY	No.2	SPF	
L - H	2x4	DRY	No.2	SPF	
ALL WEBS	2x3	DRY	No.2	SPF	
ALL GABLE WEBS	2x3	DRY	No.2	SPF	
DRY: SEASONED LUMBER.					
GABLE STUDS SPACED AT 2-0-0 OC.					

PLATES (table is in inches)					
JT	TYPE	PLATES	W	LEN	Y X
B	TMVW+p	MT20	4.0	6.0	2.75 2.00
C	TMW+w	MT20	2.0	4.0	
D	TTW+p	MT20	4.0	6.0	
E	TMW+w	MT20	2.0	4.0	
F	TMVW+p	MT20	4.0	6.0	2.75 2.00
H	BMV1+p	MT20	3.0	4.0	
I	BMW1-w	MT20	4.0	4.0	
J	BMW1-w	MT20	2.0	4.0	
K	BMW1-w	MT20	4.0	4.0	
L	BMV1+p	MT20	3.0	4.0	

DIMENSIONS, SUPPORTS AND LOADINGS SPECIFIED BY FABRICATOR TO BE VERIFIED BY BUILDING DESIGNER

BEARINGS
THIS TRUSS DESIGNED FOR CONTINUOUS BEARINGS.
THIS TRUSS REQUIRES RIGID SHEATHING ON EXPOSED FACE.
BEARING MATERIAL TO BE SPF NO.2 OR BETTER AT JOINT(S)

BRACING
TOP CHORD TO BE SHEATHED OR MAX. PURLIN SPACING = 6.25 FT.
MAX. UNBRACED BOTTOM CHORD LENGTH = 10.00 FT. OR RIGID CEILING DIRECTLY APPLIED.
ALL PITCH BREAKS AND PERIMETER CORNER JOINTS MUST BE Laterally RESTRAINED.

LOADING

CHORDS						WEBS					
MEMB.	MAX. FACTORED	FACTORED	VERT. LOAD	LC1	MAX	MAX.	MEMB.	MAX. FACTORED	FACTORED	VERT. LOAD	LC1
	(LBS)	(PLF)			(LC)	UNBRAC		(LBS)	(PLF)		(LC)
FR-TO						LENGTH	FR-TO				
L-B	-234 / 0	0.0	0.0	0.03	(1)	7.81	J-D	-120 / 0	0.06	(1)	
A-B	0 / 45	-91.8	-91.8	0.13	(1)	10.00	K-C	-231 / 0	0.06	(1)	
B-C	-13 / 0	-91.8	-91.8	0.07	(1)	6.25	I-E	-231 / 0	0.06	(1)	
C-D	-36 / 0	-91.8	-91.8	0.07	(1)	6.25	B-K	0 / 25	0.01	(1)	
D-E	-36 / 0	-91.8	-91.8	0.07	(1)	6.25	I-F	0 / 25	0.01	(1)	
E-F	-13 / 0	-91.8	-91.8	0.07	(1)	6.25					
F-G	0 / 45	-91.8	-91.8	0.13	(1)	10.00					
H-F	-234 / 0	0.0	0.0	0.03	(1)	7.81					
L-K	0 / 0	-18.5	-18.5	0.02	(4)	10.00					
K-J	0 / 14	-18.5	-18.5	0.02	(4)	10.00					
J-I	0 / 14	-18.5	-18.5	0.02	(4)	10.00					
I-H	0 / 0	-18.5	-18.5	0.02	(4)	10.00					

TOTAL WEIGHT = 2 X 45 = 90 lb

DESIGN CRITERIA

SPECIFIED LOADS:
TOP CH. LL = 25.6 PSF
DL = 6.0 PSF
BOT CH. LL = 0.0 PSF
DL = 7.4 PSF
TOTAL LOAD = 39.0 PSF

SPACING = 24.0 IN. C/C

THIS TRUSS IS DESIGNED FOR RESIDENTIAL OR SMALL BUILDING REQUIREMENTS OF PART 9, NBCC 2015

THIS DESIGN COMPLIES WITH:
- PART 9 OF CBC 2018, ABC 2019
- PART 9 OF CBC 2012 (2019 AMENDMENT)
- CSA 086-14
- TPIC 2014

(55 % OF 31.3 P.S.F. G.S.L. PLUS 8.4 P.S.F. RAIN LOAD) EQUALS 25.6 P.S.F. SPECIFIED ROOF LIVE LOAD

CSI: TC=0.13/1.00 (F-G:1), BC=0.02/1.00 (J-K:4), WB=0.06/1.00 (D-J:1), SSI=0.07/1.00 (F-G:1)

DOL LUMBER=1.00 NAIL=1.00 LS BEND=1.10
COMP=1.10 SHEAR=1.10 TENS=1.10

COMPANION LIVE LOAD FACTOR = 1.00

TRUSS PLATE MANUFACTURER IS NOT RESPONSIBLE FOR QUALITY CONTROL IN THE TRUSS MANUFACTURING PLANT.

NAIL VALUES					
PLATE	GRIP(DRY)	SHEAR	SECTION		
(PSI)	(PLI)	(PLI)			
	MAX	MIN	MAX	MIN	MAX
MT20	650	371	1747	788	1987

PLATE PLACEMENT TOL. = 0.250 inches


PLATE ROTATION TOL. = 5.0 Deg.

JSI GRIP= 0.18 (C) (INPUT = 0.90)
JSI METAL= 0.12 (E) (INPUT = 1.00)



Structural component only
DWG# T-2017137

JOB NAME 410143	TRUSS NAME G27	QUANTITY 4	PLY 1	JOB DESC. GREEN PARK HOMES	DRWG NO.
Tamarack Roof Truss, Burlington					



LUMBER			
N. L. G. A. RULES	CHORDS	SIZE	LUMBER
Y - B	2x4	DRY	No.2
A - I	2x4	DRY	No.2
I - M	2x4	DRY	No.2
N - M	2x4	DRY	No.2
Y - Q	2x4	DRY	No.2
Q - N	2x4	DRY	No.2

ALL WEBS	2x3	DRY	No.2
ALL GABLE WEBS	2x3	DRY	No.2
DRY: SEASONED LUMBER.			

GABLE STUDS SPACED AT 2'-0" OC.

PLATES (table is in inches)

JT	TYPE	PLATES	W	LEN	Y	X
B	TMV+p	MT20	3.0	4.0		
C, D, E, F, G, H, J, K, L						
C	TMW+w	MT20	2.0	4.0		
I	TS-t	MT20	3.0	6.0		
M	TMV+p	MT20	3.0	4.0		
N	BMV1+p	MT20	3.0	4.0		
O, P, R, S, T, U, V, W, X						
O	BMW1+w	MT20	2.0	4.0		
Q	BS-t	MT20	3.0	6.0		
Y	BMV1+p	MT20	3.0	4.0		

DIMENSIONS, SUPPORTS AND LOADINGS SPECIFIED BY FABRICATOR TO BE VERIFIED BY BUILDING DESIGNER

BEARINGS

THIS TRUSS DESIGNED FOR CONTINUOUS BEARINGS.

THIS TRUSS REQUIRES RIGID SHEATHING ON EXPOSED FACE.

BEARING MATERIAL TO BE SPF NO.2 OR BETTER AT JOINT(S)

BRACING

TOP CHORD TO BE SHEATHED OR MAX. PURLIN SPACING = 6.25 FT.
MAX. UNBRACED BOTTOM CHORD LENGTH = 10.00 FT. OR RIGID CEILING DIRECTLY APPLIED.

ALL PITCH BREAKS AND PERIMETER CORNER JOINTS MUST BE Laterally RESTRAINED.

1 LATERAL BRACE(S) AT 1/2 LENGTH OF M-N, L-O, K-P.

END VERTICAL(S) MUST BE SHEATHED OR HAVE BRACES AS INDICATED IN THE MAX. UNBRACED LENGTH COLUMN OF THE TABLE BELOW

LOADING

TOTAL LOAD CASES: (4)

MEMB.	FR-TO	MAX. FACTORED FORCE (LBS)	CHORDS		MAX. FACTORED UNBRACED LENGTH	MEMB.	FR-TO	MAX. FACTORED FORCE (LBS)	MAX. FACTORED CSI (LC)
			VERT. LOAD (PLF)	LC1 (LC)					
Y-B		-248 / 0	0.0	0.0 0.04 (1)	7.81	O-L		-198 / 0	0.13 (1)
A-B		0 / 28	-91.8	-91.8 0.12 (1)	10.00	P-K		-182 / 0	0.10 (1)
B-C		-45 / 0	-91.8	-91.8 0.10 (1)	6.25	R-J		-183 / 0	0.22 (1)
C-D		-17 / 0	-91.8	-91.8 0.05 (1)	6.25	S-H		-183 / 0	0.15 (1)
D-E		-18 / 0	-91.8	-91.8 0.05 (1)	6.25	T-G		-182 / 0	0.10 (1)
E-F		-13 / 0	-91.8	-91.8 0.04 (1)	6.25	U-F		-183 / 0	0.07 (1)
F-G		-10 / 0	-91.8	-91.8 0.04 (1)	6.25	V-E		-179 / 0	0.04 (1)
G-H		-8 / 0	-91.8	-91.8 0.04 (1)	10.00	W-D		-195 / 0	0.03 (1)
H-I		-6 / 0	-91.8	-91.8 0.04 (1)	10.00	X-C		-110 / 0	0.02 (1)
I-J		-6 / 0	-91.8	-91.8 0.04 (1)	10.00				
J-K		-4 / 0	-91.8	-91.8 0.04 (1)	10.00				
K-L		-2 / 0	-91.8	-91.8 0.04 (1)	10.00				
L-M		-7 / 0	-91.8	-91.8 0.04 (1)	10.00				
N-M		-83 / 0	0.0	0.0 0.01 (1)	6.25				
Y-X		0 / 24	-18.5	-18.5 0.05 (1)	10.00				
X-W		0 / 20	-18.5	-18.5 0.02 (4)	10.00				
W-V		0 / 15	-18.5	-18.5 0.02 (4)	10.00				
V-U		0 / 12	-18.5	-18.5 0.02 (4)	10.00				
U-T		0 / 9	-18.5	-18.5 0.01 (4)	10.00				
T-S		0 / 7	-18.5	-18.5 0.01 (4)	10.00				
S-R		0 / 5	-18.5	-18.5 0.01 (4)	10.00				
R-Q		0 / 4	-18.5	-18.5 0.01 (4)	10.00				
Q-P		0 / 4	-18.5	-18.5 0.01 (4)	10.00				
P-O		0 / 3	-18.5	-18.5 0.02 (4)	10.00				
O-N		0 / 1	-18.5	-18.5 0.02 (4)	10.00				

TOTAL WEIGHT = 4 X 102 = 406 lb [M]

DESIGN CRITERIA

SPECIFIED LOADS:

TOP CH.	LL	=	25.6	PSF
	DL	=	6.0	PSF
BOT CH.	LL	=	0.0	PSF
	DL	=	7.4	PSF
TOTAL LOAD		=	39.0	PSF

SPACING = 24.0 IN. C/C

THIS TRUSS IS DESIGNED FOR RESIDENTIAL OR SMALL BUILDING REQUIREMENTS OF PART 9, NBC 2015

THIS DESIGN COMPLIES WITH:

- PART 9 OF BCBC 2018, ABC 2019
- PART 9 OF OBC 2012 (2019 AMENDMENT)
- CSA 086-14
- TPIC 2014

DESIGN ASSUMPTIONS

- OVERHANG NOT TO BE ALTERED OR CUT OFF.

(55 % OF 31.3 P.S.F. G.S.L. PLUS 8.4 P.S.F. RAIN LOAD) EQUALS 25.6 P.S.F. SPECIFIED ROOF LIVE LOAD

CSI: TC=0.12/1.00 (A-B:1), BC=0.05/1.00 (X-Y:1), WB=0.22/1.00 (J-R:1), SSI=0.09/1.00 (A-B:1)

DOL LUMBER=1.00 NAIL=1.00 LS BEND=1.10 COMP=1.10 SHEAR=1.10 TENS=1.10

COMPANION LIVE LOAD FACTOR = 1.00

TRUSS PLATE MANUFACTURER IS NOT RESPONSIBLE FOR QUALITY CONTROL IN THE TRUSS MANUFACTURING PLANT.

NAIL VALUES

PLATE GRIP (DRY)	SHEAR (PSI)	SECTION (PLI)
MAX MIN	MAX MIN	MAX MIN
MT20	650 371	1747 788 1987 1873

PLATE PLACEMENT TOL. = 0.250 inches


PLATE ROTATION TOL. = 5.0 Deg.

JSI GRIP= 0.38 (C) (INPUT = 0.90)
JSI METAL= 0.08 (L) (INPUT = 1.00)



Structural component only
DWG# T-2017138

JOB NAME 410143	TRUSS NAME T28	QUANTITY 2	PLY 2	JOB DESC. GREEN PARK HOMES	DRWG NO.
Tamarack Roof Truss, Burlington					



LUMBER				
N. L. G. A. RULES	CHORDS	SIZE	LUMBER	DESCR.
F - A	2x6	DRY	No.2	SPF
A - C	2x4	DRY	No.2	SPF
D - C	2x4	DRY	No.2	SPF
F - D	2x6	DRY	No.2	SPF
ALL WEBS 2x3 DRY No.2 SPF				
DRY: SEASONED LUMBER.				

DESIGN CONSISTS OF 2 TRUSSES BUILT SEPARATELY THEN FASTENED TOGETHER AS FOLLOWS:

CHORDS #ROWS	SURFACE SPACING (IN)	LOAD (PLF)
TOP CHORDS : (0.122"x3") SPIRAL NAILS		
F - A	2 12	TOP
A - C	1 12	TOP
C - D	1 12	TOP
BOTTOM CHORDS : (0.122"x3") SPIRAL NAILS		
F - D	2 12	SIDE (0.0)
WEBS : (0.122"x3") SPIRAL NAILS		
2x3	1 6	

NAILS TO BE DRIVEN FROM ONE SIDE ONLY.

GIRDER NAILING ASSUMES NAILED HANGERS ARE FASTENED WITH MIN. 3-0 INCH NAILS.

TOP - COMPONENTS ARE LOADED FROM THE TOP AND MUST BE PLACED ON TOP EDGE OF ALL PLIES FOR THE LOAD TO BE TRANSFERRED TO EACH PLY.

SIDE - PLF SHOWN IS THE EQUIVALENT UDL APPLIED TO ONE SIDE THAT THE CORRESPONDING NAILING PATTERN SHALL BE CAPABLE OF TRANSFERRING. REMAINING PLF MUST BE APPLIED ON THE OPPOSITE SIDE OR ON THE TOP.

PLATES (table is in inches)

JT	TYPE	PLATES	W	LEN	Y	X
A	TMVW-p	MT20	4.0	6.0	1.00	3.00
B	TMVW-t	MT20	4.0	4.0	2.00	1.75
C	TMV+p	MT20	3.0	4.0		
D	BMVW1+p	MT20	4.0	6.0		
E	BMVW-t	MT20	5.0	6.0		
F	BMV1+p	MT20	3.0	6.0		

DIMENSIONS, SUPPORTS AND LOADINGS SPECIFIED BY FABRICATOR TO BE VERIFIED BY BUILDING DESIGNER

BEARINGS		FACTORED GROSS REACTION	MAXIMUM FACTORED GROSS REACTION	INPUT	REQRD
JT	VERT	HORZ	DOWN	HORZ	UPLIFT
F	929	0	929	0	5-8
D	1152	0	1152	0	MECHANICAL

A SUITABLE HANGER/MECHANICAL CONNECTION IS REQUIRED AT JOINT D. MINIMUM BEARING LENGTH AT JOINT D = 2-0.

UNFACTORED REACTIONS

JT	1ST CASE	SNOW	LIVE	PERM. LIVE	WIND	DEAD	SOIL
F	655	438 / 0	0 / 0	0 / 0	0 / 0	217 / 0	0 / 0
D	813	545 / 0	0 / 0	0 / 0	0 / 0	268 / 0	0 / 0

BEARING MATERIAL TO BE SPF NO.2 OR BETTER AT JOINT(S) F

BRACING

TOP CHORD TO BE SHEATHED OR MAX. PURLIN SPACING = 6.25 FT.
MAX. UNBRACED BOTTOM CHORD LENGTH = 10.00 FT OR RIGID CEILING DIRECTLY APPLIED.

ALL PITCH BREAKS AND PERIMETER CORNER JOINTS MUST BE Laterally RESTRAINED.

LOADING

TOTAL LOAD CASES: (4)

CHORDS		WEBS	
MEMB.	MAX. FACTORED FORCE (LBS)	MEMB.	MAX. FACTORED FORCE (LBS)
FR-TO		FR-TO	
F - A	-846 / 0	A - E	0 / 998
A - B	-1067 / 0	E - B	0 / 898
B - C	-12 / 0	B - D	-1214 / 0
D - C	-109 / 0		
F - G	0 / 0		
G - E	0 / 0		
E - H	0 / 965		
H - D	0 / 965		

FACTORED CONCENTRATED LOADS (LBS)

JT	LOC.	LC1	MAX-	MAX+	FACE	DIR.	TYPE	HEEL	CONN.
G	2-4-12	-717	-717	---	FRONT	VERT	TOTAL	---	C1
H	4-4-12	-717	-717	---	FRONT	VERT	TOTAL	---	C1

CONNECTION REQUIREMENTS

1) C1: A SUITABLE HANGER/MECHANICAL CONNECTION IS REQUIRED.

TOTAL WEIGHT = 4 X 29 = 117 lb [M]

DESIGN CRITERIA

SPECIFIED LOADS:
TOP CH. LL = 25.6 PSF
DL = 6.0 PSF
BOT CH. LL = 0.0 PSF
DL = 7.4 PSF
TOTAL LOAD = 39.0 PSF

SPACING = 24.0 IN. C/C

THIS TRUSS IS DESIGNED FOR RESIDENTIAL OR SMALL BUILDING REQUIREMENTS OF PART 9, NBC 2015

THIS DESIGN COMPLIES WITH:
- PART 9 OF BCBC 2018, ABC 2019
- PART 9 OF OBC 2012 (2019 AMENDMENT)
- CSA 086-14
- TPIC 2014

(55 % OF 31.3 P.S.F. G.S.L. PLUS 8.4 P.S.F. RAIN LOAD) EQUALS 25.6 P.S.F. SPECIFIED ROOF LIVE LOAD

ALLOWABLE DEFL.(LL)= L/360 (0.20")
CALCULATED VERT. DEFL.(LL) = L/999 (0.01")
ALLOWABLE DEFL.(TL)= L/360 (0.20")
CALCULATED VERT. DEFL.(TL) = L/999 (0.01")

CSI: TC=0.06/1.00 (A-B:1), BC=0.22/1.00 (D-E:1), WB=0.14/1.00 (B-D:1), SSI=0.23/1.00 (E-F:1)

DOL LUMBER=1.00 NAIL=1.00 LS BEND=1.00
COMP=1.00 SHEAR=1.00 TENS=1.00

COMPANION LIVE LOAD FACTOR = 1.00

TRUSS PLATE MANUFACTURER IS NOT RESPONSIBLE FOR QUALITY CONTROL IN THE TRUSS MANUFACTURING PLANT.

NAIL VALUES
PLATE GRIP(DRY) SHEAR SECTION
(PSI) (PLI) (PLI)
MAX MIN MAX MIN MAX MIN
MT20 650 371 1747 788 1987 1873

PLATE PLACEMENT TOL. = 0.250 inches

PLATE ROTATION TOL. = 5.0 Deg.


JSI GRIP= 0.58 (B) (INPUT = 0.90)
JSI METAL= 0.22 (D) (INPUT = 1.00)



Structural component only
DWG# T-2017150

JOB NAME	TRUSS NAME	QUANTITY	PLY	JOB DESC.	DRWG NO.
410149	T30	2	2	GREEN PARK HOMES	
Tamarack Roof Truss, Burlington					

Version 8.330 S May 6 2020 MTek Industries, Inc. Tue Aug 4 13:58:22 2020 Page 1
ID:pqvtrdsyU73tskbsq1clrEz7lfa-296y8m89QmzBLOWzy1oikuvJ1IW651vTnE5SKyrDZ?
23-3-12 23-9-0
Scale = 1:39.0



LUMBER			
N. L. G. A. RULES	CHORDS	SIZE	LUMBER
A - C	2x4	DRY	No.2
C - E	2x4	DRY	No.2
E - H	2x4	DRY	No.2
I - H	2x4	DRY	No.2
P - B	2x6	DRY	No.2
P - L	2x6	DRY	No.2
L - I	2x6	DRY	No.2

ALL WEBS EXCEPT	2x3	DRY	No.2	SPF
-----------------	-----	-----	------	-----

DRY: SEASONED LUMBER.

DESIGN CONSISTS OF 2 TRUSSES BUILT SEPARATELY THEN FASTENED TOGETHER AS FOLLOWS:

CHORDS #ROWS	SURFACE SPACING (IN)	LOAD(PLF)
TOP CHORDS : (0.122"x3") SPIRAL NAILS		
A - C	12	SIDE(61.0)
C - E	12	SIDE(61.0)
E - H	12	SIDE(61.0)
H - I	12	TOP
P - B	12	TOP
BOTTOM CHORDS : (0.122"x3") SPIRAL NAILS		
P - L	12	SIDE(183.1)
L - I	12	SIDE(183.1)
WEBS : (0.122"x3") SPIRAL NAILS		
2x3	6	

NAILS TO BE DRIVEN FROM ONE SIDE ONLY.

GIRDER NAILING ASSUMES NAILED HANGERS ARE FASTENED WITH MIN. 3-0 INCH NAILS.

TOP - COMPONENTS ARE LOADED FROM THE TOP AND MUST BE PLACED ON TOP EDGE OF ALL PLIES FOR THE LOAD TO BE TRANSFERRED TO EACH PLY.

SIDE - PLF SHOWN IS THE EQUIVALENT UDL APPLIED TO ONE SIDE THAT THE CORRESPONDING NAILING PATTERN SHALL BE CAPABLE OF TRANSFERRING. REMAINING PLF MUST BE APPLIED ON THE OPPOSITE SIDE OR ON THE TOP.

DIMENSIONS, SUPPORTS AND LOADINGS SPECIFIED BY FABRICATOR TO BE VERIFIED BY BUILDING DESIGNER

BEARINGS		FACTORED GROSS REACTION	MAXIMUM FACTORED GROSS REACTION	INPUT BRG	REQRD BRG
JT	VERT	HORZ	DOWN	HORZ	UPLIFT
I	2248	0	2248	0	1-8
P	2247	0	2247	0	5-8

UNFACTORED REACTIONS

1ST LCASE		MAX./MIN. COMPONENT REACTIONS					
JT	COMBINED	SNOW	LIVE	PERM.LIVE	WIND	DEAD	SOIL
I	1591	1034 / 0	0 / 0	0 / 0	0 / 0	558 / 0	0 / 0
P	1589	1041 / 0	0 / 0	0 / 0	0 / 0	549 / 0	0 / 0

BEARING MATERIAL TO BE SPF NO.2 OR BETTER AT JOINT(S) I, P

2x6 DRY SPF NO.2 BEARING BLOCK 12" LONG AT JT. I ATTACHED TO FRONT SIDE WITH 3 ROWS OF (0.122"x3") SPIRAL NAILS SPACED 3" C.C. 12 NAILS TOTAL.

BRACING

TOP CHORD TO BE SHEATHED OR MAX. PURLIN SPACING = 4.64 FT. MAX. UNBRACED BOTTOM CHORD LENGTH = 10.00 FT OR RIGID CEILING DIRECTLY APPLIED.

ALL PITCH BREAKS AND PERIMETER CORNER JOINTS MUST BE Laterally RESTRAINED.

LOADING

TOTAL LOAD CASES: (4)

CHORDS		WEBS	
MEMB.	MAX. FACTORED FORCE (LBS)	MEMB.	MAX. FACTORED FORCE (LBS)
FR-TO	FROM TO	FR-TO	FROM TO
A-B	0 / 28	O-C	-180 / 95
B-C	-3147 / 0	B-O	0 / 2837
C-Q	-3610 / 0	K-H	0 / 2922
Q-R	-3610 / 0	C-N	0 / 1041
R-D	-3610 / 0	K-G	-1683 / 0
D-S	-3356 / 0	N-D	-524 / 0
S-T	-3356 / 0	M-G	0 / 1428
T-E	-3356 / 0	D-M	-334 / 0
E-F	-3356 / 0	M-F	-591 / 0
F-U	-3356 / 0		
U-V	-3356 / 0		
V-G	-3356 / 0		
G-W	-2266 / 0		
W-X	-2266 / 0		
X-H	-2266 / 0		
I-H	-2166 / 0		
P-B	-2169 / 0		
P-Y	0 / 0		
Y-Z	0 / 0		
Z-O	0 / 0		
O-AA	0 / 2808		
AA-AB	0 / 2808		
AB-N	0 / 2808		
N-AC	0 / 3611		
AC-AD	0 / 3611		
AD-M	0 / 3611		
M-AE	0 / 2266		
AE-L	0 / 2266		
L-AF	0 / 2266		
AF-K	0 / 2266		
K-AG	0 / 0		
AG-J	0 / 0		
J-AH	0 / 0		
AH-I	0 / 0		

FACTORED CONCENTRATED LOADS (LBS)		FACE	DIR.	TYPE	HEEL	CONN.
JT	LOC.	LC1	MAX.	MAX+		
C	5-10-8	-411	-411	---	FRONT	VERT
G	19-3-12	-110	-110	---	FRONT	VERT

TOTAL WEIGHT = 4 X 112 = 447 lb

DESIGN CRITERIA

SPECIFIED LOADS:
TOP CH. LL = 25.6 PSF
DL = 6.0 PSF
BOT CH. LL = 0.0 PSF
DL = 7.4 PSF
TOTAL LOAD = 39.0 PSF

SPACING = 24.0 IN. C/C

LOADING IN FLAT SECTION BASED ON A SLOPE OF 6.00/12

THIS TRUSS IS DESIGNED FOR RESIDENTIAL OR SMALL BUILDING REQUIREMENTS OF PART 9, NBC 2015

THIS DESIGN COMPLIES WITH:
- PART 9 OF CBC 2018, ABC 2019
- PART 9 OF OBC 2012 (2019 AMENDMENT)
- CSA 086-14
- TPIC 2014

(55% OF 31.3 P.S.F. G.S.L. PLUS 8.4 P.S.F. RAIN LOAD) EQUALS 25.6 P.S.F. SPECIFIED ROOF LIVE LOAD

ALLOWABLE DEFL.(LL) = L/360 (0.79")
CALCULATED VERT. DEFL.(LL) = L/999 (0.07")
ALLOWABLE DEFL.(TL) = L/360 (0.79")
CALCULATED VERT. DEFL.(TL) = L/999 (0.13")

CSI: TC=0.40/1.00 (B-C:1), BC=0.28/1.00 (M-N:1), WB=0.36/1.00 (H-K:1), SSI=0.17/1.00 (C-D:1)

DOL LUMBER=1.00 NAIL=1.00 LS BEND=1.00
COMP=1.00 SHEAR=1.00 TENS=1.00

COMPANION LIVE LOAD FACTOR = 1.00

AUTOSOLVE RIGHT HEEL ONLY

TRUSS PLATE MANUFACTURER IS NOT RESPONSIBLE FOR QUALITY CONTROL IN THE TRUSS MANUFACTURING PLANT.

NAIL VALUES
PLATE GRIP(DRY) SHEAR SECTION (PSI) (PLI) (PLI)
MAX MIN MAX MIN MAX MIN
MT20 650 371 1747 788 1987 1873

PLATE PLACEMENT TOL. = 0.250 inches

PLATE ROTATION TOL. = 5.0 Deg.

JSI GRIP= 0.78 (B) (INPUT = 0.90)
JSI METAL= 0.34 (B) (INPUT = 1.00)



Structural component only
DWG# T-2017167 1/2

JOB NAME	TRUSS NAME	QUANTITY	PLY	JOB DESC.	GREEN PARK HOMES	DRWG NO.
410149	T30	2	2	TRUSS DESC.		

Tamarack Roof Truss, Burlington

Version 8.330 S May 6 2020 MiTek Industries, Inc. Tue Aug 4 13:58:22 2020 Page 2
ID:pqvtrdsyU73tskbsg1clrEz7lfa-296y8m89QmzBLOWzy1oikuvJ1IW651vTnE5SKivrDZ?

PLATES (table is in inches)

JT	TYPE	PLATES	W	LEN	Y	X
B	TMVW-p	MT20	4.0	6.0	1.00	3.25
C	TTWW-m	MT20	5.0	6.0	2.00	1.75
D	TMWW-t	MT20	4.0	4.0		
E	TS-t	MT20	3.0	6.0		
F	TMW-w	MT20	2.0	4.0		
G	TMWW-t	MT20	4.0	6.0		
H	TMVW-t	MT20	5.0	6.0	2.50	2.75
I	BMV1+p	MT20	3.0	6.0		
K	BMWW-t	MT20	5.0	6.0	2.50	2.75
L	BS-t	MT20	5.0	6.0		
M	BMWWW-t	MT20	5.0	8.0		
N	BMWW-t	MT20	5.0	6.0		
O	BMWW-t	MT20	5.0	6.0		
P	BMV1+p	MT20	3.0	6.0		

FACTORED CONCENTRATED LOADS (LBS)

JT	LOC.	LC1	MAX-	MAX+	FACE	DIR.	TYPE	HEEL	CONN.
K	19-3-12	-26	-26	---	FRONT	VERT	TOTAL	---	C1
O	5-11-4	-26	-26	---	FRONT	VERT	TOTAL	---	C1
Q	7-3-12	-110	-110	---	FRONT	VERT	TOTAL	---	C1
R	9-3-12	-110	-110	---	FRONT	VERT	TOTAL	---	C1
S	11-3-12	-110	-110	---	FRONT	VERT	TOTAL	---	C1
T	13-3-12	-110	-110	---	FRONT	VERT	TOTAL	---	C1
U	15-3-12	-110	-110	---	FRONT	VERT	TOTAL	---	C1
V	17-3-12	-110	-110	---	FRONT	VERT	TOTAL	---	C1
W	21-3-12	-110	-110	---	FRONT	VERT	TOTAL	---	C1
X	23-3-12	-136	-136	---	FRONT	VERT	TOTAL	---	C1
Y	1-11-4	-25	-26	---	FRONT	VERT	TOTAL	---	C1
Z	3-11-4	-26	-26	---	FRONT	VERT	TOTAL	---	C1
AA	7-3-12	-26	-26	---	FRONT	VERT	TOTAL	---	C1
AB	9-3-12	-26	-26	---	FRONT	VERT	TOTAL	---	C1
AC	11-3-12	-26	-26	---	FRONT	VERT	TOTAL	---	C1
AD	13-3-12	-26	-26	---	FRONT	VERT	TOTAL	---	C1
AE	15-3-12	-26	-26	---	FRONT	VERT	TOTAL	---	C1
AF	17-3-12	-26	-26	---	FRONT	VERT	TOTAL	---	C1
AG	21-3-12	-26	-26	---	FRONT	VERT	TOTAL	---	C1
AH	23-3-12	-32	-32	---	FRONT	VERT	TOTAL	---	C1

CONNECTION REQUIREMENTS

- 1) C1: A SUITABLE HANGER/MECHANICAL CONNECTION IS REQUIRED.




Structural component only
DWG# T-2017167 2/2

JOB NAME	TRUSS NAME	QUANTITY	PLY	JOB DESC.	DRWG NO.
410149	T30Z	2	2	GREEN PARK HOMES	

Tamarack Roof Truss, Burlington

Version 8.330 S May 6 2020 MTek Industries, Inc. Tue Aug 4 13:58:23 2020 Page 1
ID:pqvtrdsyU73tskbsg1clrEz7lfa-XLfKL68oA352zY49WkXjG6RUZ9nAqR3c0ur0t8yrDZ_



LUMBER			
N. L. G. A. RULES			
CHORDS	SIZE	LUMBER	DESCR.
A - C	2x4	DRY	No.2
C - E	2x4	DRY	No.2
E - H	2x4	DRY	No.2
I - J	2x4	DRY	No.2
P - B	2x6	DRY	No.2
P - L	2x6	DRY	No.2
L - I	2x6	DRY	No.2
ALL WEBS	2x3	DRY	No.2
EXCEPT			SPF

DRY: SEASONED LUMBER.

DESIGN CONSISTS OF 2 TRUSSES BUILT SEPARATELY THEN FASTENED TOGETHER AS FOLLOWS:

CHORDS #ROWS	SURFACE SPACING (IN)	LOAD(PLF)
TOP CHORDS : (0.122"x3") SPIRAL NAILS		
A - C	12	TOP
C - E	12	TOP
E - H	12	TOP
H - I	12	TOP
P - B	12	TOP
BOTTOM CHORDS : (0.122"x3") SPIRAL NAILS		
P - L	12	SIDE(0.0)
L - I	12	SIDE(0.0)
WEBS : (0.122"x3") SPIRAL NAILS		
2x3	6	

NAILS TO BE DRIVEN FROM ONE SIDE ONLY.

GIRDER NAILING ASSUMES NAILED HANGERS ARE FASTENED WITH MIN. 3-0 INCH NAILS.

TOP - COMPONENTS ARE LOADED FROM THE TOP AND MUST BE PLACED ON TOP EDGE OF ALL PLIES FOR THE LOAD TO BE TRANSFERRED TO EACH PLY.

SIDE - PLF SHOWN IS THE EQUIVALENT UDL APPLIED TO ONE SIDE THAT THE CORRESPONDING NAILING PATTERN SHALL BE CAPABLE OF TRANSFERRING. REMAINING PLF MUST BE APPLIED ON THE OPPOSITE SIDE OR ON THE TOP.

DIMENSIONS, SUPPORTS AND LOADINGS SPECIFIED BY FABRICATOR TO BE VERIFIED BY BUILDING DESIGNER

FACTORED		MAXIMUM FACTORED		INPUT		REQD	
GROSS REACTION		GROSS REACTION		BRG		BRG	
JT VERT	HORZ	DOWN	HORZ	UPLIFT	IN-SX	IN-SX	
I 3134	0	3134	0	0	1-8	1-8 & BLOCK	
P 2385	0	2385	0	0	5-8	5-8	

UNFACTORED REACTIONS

1ST LCASE	MAX./MIN. COMPONENT REACTIONS					
JT COMBINED	SNOW	LIVE	PERM.LIVE	WIND	DEAD	SOIL
I 2210	1484 / 0	0 / 0	0 / 0	0 / 0	727 / 0	0 / 0
P 1681	1137 / 0	0 / 0	0 / 0	0 / 0	544 / 0	0 / 0

BEARING MATERIAL TO BE SPF NO.2 OR BETTER AT JOINT(S) I, P

2x6 DRY SPF NO.2 BEARING BLOCK 12" LONG AT JT. I ATTACHED TO FRONT SIDE WITH 3 ROWS OF (0.122"x3") SPIRAL NAILS SPACED 3" C.C. 12 NAILS TOTAL.

BRACING

TOP CHORD TO BE SHEATHED OR MAX. PURLIN SPACING = 3.84 FT.
MAX. UNBRACED BOTTOM CHORD LENGTH = 10.00 FT OR RIGID CEILING DIRECTLY APPLIED.

ALL PITCH BREAKS AND PERIMETER CORNER JOINTS MUST BE Laterally RESTRAINED.

LOADING

TOTAL LOAD CASES: (4)

CHORDS		FACTORED		WEBS	
MEMB.	FORCE (LBS)	VERT. LOAD	MAX. (PLF)	MEMB.	FORCE (LBS)
FR-TO		FROM	TO	FR-TO	
A-B	0 / 28	-91.8	-91.8 0.07 (1)	O-C	-338 / 0
B-C	-3423 / 0	-91.8	-91.8 0.41 (1)	B-O	0 / 3085
C-D	-4773 / 0	-91.8	-91.8 0.23 (1)	K-H	0 / 4521
D-E	-5542 / 0	-91.8	-91.8 0.26 (1)	C-N	0 / 2236
E-F	-5542 / 0	-91.8	-91.8 0.26 (1)	K-G	-2393 / 0
F-Q	-5542 / 0	-91.8	-91.8 0.35 (1)	N-D	-1102 / 0
Q-R	-5542 / 0	-91.8	-91.8 0.35 (1)	M-G	0 / 2669
R-G	-5542 / 0	-91.8	-91.8 0.35 (1)	D-M	0 / 1008
G-S	-3507 / 0	-91.8	-91.8 0.27 (1)	M-F	-466 / 0
S-T	-3507 / 0	-91.8	-91.8 0.27 (1)		
T-U	-3507 / 0	-91.8	-91.8 0.27 (1)		
U-H	-3507 / 0	-91.8	-91.8 0.27 (1)		
I-H	-3109 / 0	0.0	0.0 0.39 (1)		
P-B	-2325 / 0	0.0	0.0 0.08 (1)		

P-O	0 / 0	-18.5	-18.5 0.04 (4)	10.00
O-N	0 / 3050	-18.5	-18.5 0.24 (1)	10.00
N-V	0 / 4773	-18.5	-18.5 0.54 (1)	10.00
V-M	0 / 4773	-18.5	-18.5 0.54 (1)	10.00
M-W	0 / 3507	-18.5	-18.5 0.49 (1)	10.00
W-L	0 / 3507	-18.5	-18.5 0.49 (1)	10.00
L-X	0 / 3507	-18.5	-18.5 0.49 (1)	10.00
X-Y	0 / 3507	-18.5	-18.5 0.49 (1)	10.00
Y-K	0 / 3507	-18.5	-18.5 0.49 (1)	10.00
K-Z	0 / 0	-18.5	-18.5 0.07 (1)	10.00
Z-AA	0 / 0	-18.5	-18.5 0.07 (1)	10.00
AA-J	0 / 0	-18.5	-18.5 0.07 (1)	10.00
J-AB	0 / 0	-18.5	-18.5 0.07 (1)	10.00
AB-I	0 / 0	-18.5	-18.5 0.07 (1)	10.00

FACTORED CONCENTRATED LOADS (LBS)

JT	LOC	LC1	MAX-	MAX+	FACE	DIR.	TYPE	HEEL	CONN.
Q	15-6-12	-110	-110	---	FRONT	VERT	TOTAL	---	C1
R	17-6-12	-63	-63	---	FRONT	VERT	TOTAL	---	C1
S	19-6-12	-63	-63	---	FRONT	VERT	TOTAL	---	C1
T	21-6-12	-63	-63	---	FRONT	VERT	TOTAL	---	C1
U	23-0-12	-77	-77	---	FRONT	VERT	TOTAL	---	C1
V	13-7-8	-1252	-1252	---	FRONT	VERT	TOTAL	---	C1
W	15-6-12	-26	-26	---	FRONT	VERT	TOTAL	---	C1
X	16-5-8	-1066	-1066	---	FRONT	VERT	TOTAL	---	C1

TOTAL WEIGHT = 4 X 112 = 447 lb [M]

DESIGN CRITERIA

SPECIFIED LOADS:

TOP CH.	LL = 25.6	PSF
DL = 6.0	PSF	
BOT CH.	LL = 0.0	PSF
DL = 7.4	PSF	
TOTAL LOAD	= 39.0	PSF

SPACING = 24.0 IN. C/C

LOADING IN FLAT SECTION BASED ON A SLOPE OF 6.00/12

THIS TRUSS IS DESIGNED FOR RESIDENTIAL OR SMALL BUILDING REQUIREMENTS OF PART 9, NBC 2015

THIS DESIGN COMPLIES WITH:

- PART 9 OF BCBC 2018, ABC 2019
- PART 9 OF OBC 2012 (2019 AMENDMENT)
- CSA 086-14
- TPIC 2014

(55% OF 31.3 P.S.F. G.S.L. PLUS 8.4 P.S.F. RAIN LOAD) EQUALS 25.6 P.S.F. SPECIFIED ROOF LIVE LOAD

ALLOWABLE DEFL.(LL)= L/360 (0.79")
CALCULATED VERT. DEFL.(LL)= L/999 (0.11")
ALLOWABLE DEFL.(TL)= L/360 (0.79")
CALCULATED VERT. DEFL.(TL)= L/999 (0.20")

CSI: TC=0.41/1.00 (B-C:1), BC=0.54/1.00 (M-N:1),
WB=0.56/1.00 (H-K:1), SSI=0.36/1.00 (M-N:1)

DOL LUMBER=1.00 NAIL=1.00 LS BEND=1.00
COMP=1.00 SHEAR=1.00 TENS=1.00

COMPANION LIVE LOAD FACTOR = 1.00

AUTOSOLVE RIGHT HEEL ONLY

TRUSS PLATE MANUFACTURER IS NOT RESPONSIBLE FOR QUALITY CONTROL IN THE TRUSS MANUFACTURING PLANT.

NAIL VALUES

PLATE	GRIP(DRY)	SHEAR	SECTION
(PSI)	(PLI)	(PLI)	
MAX MIN	MAX MIN	MAX MIN	
MT20	650 371	1747 788	1987 1873

PLATE PLACEMENT TOL. = 0.250 inches

PLATE ROTATION TOL. = 5.0 Deg.

JSI GRIP= 0.87 (H) (INPUT = 0.90)
JSI METAL= 0.46 (L) (INPUT = 1.00)

JOB NAME	TRUSS NAME	QUANTITY	PLY	JOB DESC.	DRWG NO.
410149	T30Z	2	2	GREEN PARK HOMES	

Tamarack Roof Truss, Burlington

Version 8.330 S May 6 2020 MITek Industries, Inc. Tue Aug 4 13:58:23 2020 Page 2
ID.pqvtrdsyU73tskbsq1clrEz7lfa-XLlKl68oA352zy49WkXjG6RUZ9nAqR3c0ur0t8yrDZ

PLATES (table is in inches)

JT	TYPE	PLATES	W	LEN	Y	X
B	TMVW-p	MT20	4.0	6.0	1.00	3.25
C	TTWW-m	MT20	5.0	6.0	1.75	1.75
D	TMWW-t	MT20	4.0	4.0		
E	TS-t	MT20	3.0	6.0		
F	TMW+w	MT20	2.0	4.0		
G	TMWW-t	MT20	4.0	6.0		
H	TMVW-t	MT20	5.0	6.0	2.50	2.25
I	BMV1+p	MT20	3.0	6.0		
K	BMWW-t	MT20	5.0	6.0	2.50	2.25
L	BS-t	MT20	5.0	6.0		
M	BMWWW-t	MT20	5.0	8.0		
N	BMWW-t	MT20	5.0	6.0		
O	BMWW-t	MT20	5.0	6.0		
P	BMV1+p	MT20	3.0	6.0		

FACTORED CONCENTRATED LOADS (LBS)

JT	LOC.	LC1	MAX-	MAX+	FACE	DIR.	TYPE	HEEL	CONN.
Y	17-6-12	-13	-13	---	FRONT	VERT	TOTAL	---	C1
Z	19-6-12	-13	-13	---	FRONT	VERT	TOTAL	---	C1
AA	21-6-12	-13	-13	---	FRONT	VERT	TOTAL	---	C1
AB	23-0-12	-16	-16	---	FRONT	VERT	TOTAL	---	C1

CONNECTION REQUIREMENTS


- 1) C1: A SUITABLE HANGER/MECHANICAL CONNECTION IS REQUIRED.



Structural component only
DWG# T-2017168 *2/2*

JOB NAME 410116	TRUSS NAME T31	QUANTITY 4	PLY 1	JOB DESC. GREEN PARK HOMES	DRWG NO.
Tamarack Roof Truss, Burlington					

Version 8.330 S May 6 2020 Mitek Industries, Inc. Tue Aug 4 12:39:40 2020 Page 1
ID:W63xGm6okc00SiyZ4EwBx6zA2m0-Jjnr58_DSww2BjWRKK4OL7KK9HstkkDQzbFcbOyrEin
Scale = 1:38.8



CHORDS	SIZE	LUMBER	DESCR.
A - D	2x4	DRY No.2	SPF
D - G	2x4	DRY No.2	SPF
H - G	2x4	DRY No.2	SPF
M - B	2x4	DRY No.2	SPF
M - J	2x4	DRY No.2	SPF
J - H	2x4	DRY No.2	SPF
ALL WEBS EXCEPT	2x3	DRY No.2	SPF

DRY: SEASONED LUMBER.

PLATES (table is in inches)	JT	TYPE	PLATES	W	LEN	Y	X
B	TMV+p	MT20	3.0	4.0			
C	TMWW-t	MT20	4.0	6.0			
D	TTWW-m	MT20	5.0	6.0	2.25	2.00	
E	TMWW-t	MT20	4.0	4.0			
F	TMW+w	MT20	2.0	4.0			
G	TMWW-t	MT20	5.0	6.0			
H	BMV1+p	MT20	3.0	4.0			
I	BMVWW-t	MT20	5.0	8.0			
J	BS-t	MT20	3.0	6.0			
K	BMWW-t	MT20	4.0	4.0			
L	BMWW-t	MT20	4.0	4.0			
M	BMVW1-t	MT20	5.0	6.0			

DIMENSIONS, SUPPORTS AND LOADINGS SPECIFIED BY FABRICATOR TO BE VERIFIED BY BUILDING DESIGNER

BEARINGS	FACTORED GROSS REACTION	MAXIMUM FACTORED GROSS REACTION	INPUT BRG	RECORD BRG
JT	VERT	HORZ	DOWN	UP
H	1309	0	1309	0
M	1434	0	1434	0

UNFACTORED REACTIONS	1ST LCASE	MAX. MIN. COMPONENT REACTIONS
JT	COMBINED	SNOW
H	926	608 0 0
M	1012	677 0 0

BEARING MATERIAL TO BE SPF NO.2 OR BETTER AT JOINT(S) H, M

BRACING
TOP CHORD TO BE SHEATHED OR MAX. PURLIN SPACING = 4.70 FT.
MAX. UNBRACED BOTTOM CHORD LENGTH = 10.00 FT OR RIGID CEILING DIRECTLY APPLIED.

ALL PITCH BREAKS AND PERIMETER CORNER JOINTS MUST BE Laterally RESTRAINED.

LOADING
TOTAL LOAD CASES: (4)

CHORDS	MEMB.	FORCE (LBS)	FACTORED VERT. LOAD (PLF)	MAX. LC1 (LC)	MAX. UNBRAC LENGTH FR-TO	WEBS	MEMB.	FORCE (LBS)	MAX. FACTORED MAX. CSI (LC)
A-B	0	28	-91.8	-91.8	0.12 (1)	10.00	C-L	-108	27
B-C	0	17	-91.8	-91.8	0.21 (1)	10.00	L-D	0	213
C-D	-1642	0	-91.8	-91.8	0.25 (1)	4.91	M-C	-1895	0
D-E	-1649	0	-91.8	-91.8	0.40 (1)	4.70	I-G	0	1601
E-F	-1194	0	-91.8	-91.8	0.38 (1)	5.35	D-K	0	261
F-G	-1194	0	-91.8	-91.8	0.38 (1)	5.35	I-F	-532	0
H-G	-1268	0	0.0	0.0	0.56 (1)	7.15	K-E	-102	43
M-B	-268	0	0.0	0.0	0.03 (1)	7.81	E-I	-621	0
M-L	0	1540	-18.5	-18.5	0.39 (1)	10.00			
L-K	0	1456	-18.5	-18.5	0.38 (4)	10.00			
K-J	0	1650	-18.5	-18.5	0.33 (1)	10.00			
J-I	0	1650	-18.5	-18.5	0.33 (1)	10.00			
I-H	0	0	-18.5	-18.5	0.13 (4)	10.00			

TOTAL WEIGHT = 4 X 98 = 392 lb

DESIGN CRITERIA

SPECIFIED LOADS:
TOP CH. LL = 25.6 PSF
DL = 6.0 PSF
BOT CH. LL = 0.0 PSF
DL = 7.4 PSF
TOTAL LOAD = 39.0 PSF

SPACING = 24.0 IN. C/C

LOADING IN FLAT SECTION BASED ON A SLOPE OF 6.00/12

THIS TRUSS IS DESIGNED FOR RESIDENTIAL OR SMALL BUILDING REQUIREMENTS OF PART 9, NBCC 2015

THIS DESIGN COMPLIES WITH:
- PART 9 OF CBC 2018, ABC 2019
- PART 9 OF OBC 2012 (2019 AMENDMENT)
- CSA 086-14
- TPIC 2014

55% OF 31.3 P.S.F. G.S.L. PLUS 8.4 P.S.F. RAIN LOAD) EQUALS 25.6 P.S.F. SPECIFIED ROOF LIVE LOAD

ALLOWABLE DEFL.(LL)= L/360 (0.79")
CALCULATED VERT. DEFL.(LL)= L/999 (0.06")
ALLOWABLE DEFL.(TL)= L/360 (0.79")
CALCULATED VERT. DEFL.(TL)= L/999 (0.16")

CSI: TC=0.56/1.00 (G-H:1), BC=0.39/1.00 (L-M:1), WB=0.73/1.00 (C-M:1), SS=0.23/1.00 (F-G:1)

DOL LUMBER=1.00 NAIL=1.00 LS BEND=1.10 COMP=1.10 SHEAR=1.10 TENS=1.10

COMPANION LIVE LOAD FACTOR = 1.00

TRUSS PLATE MANUFACTURER IS NOT RESPONSIBLE FOR QUALITY CONTROL IN THE TRUSS MANUFACTURING PLANT.

NAIL VALUES	PLATE GRIP(DRY)	SHEAR (PSI)	SECTION (PLI)
MT20	650	371	1747
	788	1987	1873

PLATE PLACEMENT TOL = 0.250 inches


PLATE ROTATION TOL = 5.0 Deg.

JSI GRIP = 0.81 (I) (INPUT = 0.90)
JSI METAL = 0.54 (J) (INPUT = 1.00)



Structural component only
DWG# T-2017121

JOB NAME	TRUSS NAME	QUANTITY	PLY	JOB DESC.	DRWG NO.
410116	T32	4	1	GREEN PARK HOMES	
Tamarack Roof Truss, Burlington					



LUMBER				N. L. G. A. RULES	
CHORDS	SIZE	LUMBER	DESCR.	SPF	
A - D	2x4	DRY	No.2	SPF	
D - F	2x4	DRY	No.2	SPF	
G - F	2x4	DRY	No.2	SPF	
L - B	2x4	DRY	No.2	SPF	
L - I	2x4	DRY	No.2	SPF	
I - G	2x4	DRY	No.2	SPF	
ALL WEBS	2x3	DRY	No.2	SPF	
EXCEPT					

DRY: SEASONED LUMBER.

PLATES (table is in inches)

JT	TYPE	PLATES	W	LEN	Y	X
B	TMVW-t	MT20	4.0	6.0	2.00	3.00
C	TMWW-t	MT20	4.0	4.0	2.00	1.75
D	TTWW-m	MT20	5.0	6.0	2.25	2.00
E	TMW-w	MT20	2.0	4.0		
F	TMVW-t	MT20	5.0	6.0		
G	BMV1+p	MT20	3.0	4.0		
H	BMWW-t	MT20	5.0	8.0		
I	BS-t	MT20	3.0	6.0		
J	BMWW-t	MT20	4.0	4.0		
K	BMWW-t	MT20	5.0	6.0		
L	BMV1+p	MT20	3.0	4.0		

DIMENSIONS, SUPPORTS AND LOADINGS SPECIFIED BY FABRICATOR TO BE VERIFIED BY BUILDING DESIGNER

BEARINGS		FACTORED		MAXIMUM FACTORED		INPUT		REQD	
JT	GROSS REACTION	VERT	HORZ	GROSS REACTION	DOWN	BRG	IN-SX	BRG	IN-SX
G	1309	0	0	1309	0	0	1-8	1-8	1-8
L	1434	0	0	1434	0	0	5-8	5-8	5-8

UNFACTORED REACTIONS

JT	1ST CASE	MAX.	MIN.	COMPONENT REACTIONS					
G	COMBINED	SNOW	LIVE	PERM.LIVE	WIND	DEAD	SOIL		
G	926	608	0	0	0	0	0	318	0
L	1012	677	0	0	0	0	0	335	0

BEARING MATERIAL TO BE SPF NO.2 OR BETTER AT JOINT(S) G, L

BRACING

TOP CHORD TO BE SHEATHED OR MAX. PURLIN SPACING = 4.27 FT.
MAX. UNBRACED BOTTOM CHORD LENGTH = 10.00 FT. OR RIGID CEILING DIRECTLY APPLIED.

ALL PITCH BREAKS AND PERIMETER CORNER JOINTS MUST BE LATERALLY RESTRAINED.

1 LATERAL BRACE(S) AT 1:2 LENGTH OF D-H.

END VERTICAL(S) MUST BE SHEATHED OR HAVE BRACES AS INDICATED IN THE MAX. UNBRACED LENGTH COLUMN OF THE TABLE BELOW

LOADING

TOTAL LOAD CASES: (4)

CHORDS		MAX. FACTORED		FACTORED		WEBS		MAX. FACTORED	
MEMB.	FORCE (LBS)	VERT	LOAD (PLF)	LC1	MAX	MEMB.	FORCE (LBS)	MAX	CSI (LC)
FR-TO						FR-TO			
A-B	0	28	-91.8	-91.8	0.12 (1)	10.00	K-C	-184	17
B-C	-1791	0	-91.8	-91.8	0.45 (1)	4.50	C-J	-385	0
C-D	-1484	0	-91.8	-91.8	0.42 (1)	4.88	J-D	0	326
D-E	-1217	0	-91.8	-91.8	0.85 (1)	4.27	B-K	0	1646
E-F	-1217	0	-91.8	-91.8	0.86 (1)	4.27	H-F	0	1584
G-F	-1257	0	0.0	0.0	0.91 (1)	7.17	D-H	-122	0
L-B	-1392	0	0.0	0.0	0.14 (1)	6.90	H-E	-790	0
L-K	0	0	-18.5	-18.5	0.10 (4)	10.00			
K-J	0	1623	-18.5	-18.5	0.33 (1)	10.00			
J-I	0	1311	-18.5	-18.5	0.33 (4)	10.00			
I-H	0	1311	-18.5	-18.5	0.33 (4)	10.00			
H-G	0	0	-18.5	-18.5	0.22 (4)	10.00			

TOTAL WEIGHT = 4 X 98 = 393 lb

DESIGN CRITERIA

SPECIFIED LOADS:
TOP CH. LL = 25.6 PSF
DL = 6.0 PSF
BOT CH. LL = 0.0 PSF
DL = 7.4 PSF
TOTAL LOAD = 39.0 PSF

SPACING = 24.0 IN. C/C

LOADING IN FLAT SECTION BASED ON A SLOPE OF 6.00/12

THIS TRUSS IS DESIGNED FOR RESIDENTIAL OR SMALL BUILDING REQUIREMENTS OF PART 9, NBC 2015

THIS DESIGN COMPLIES WITH:

- PART 9 OF BCBC 2018, ABC 2019
- PART 9 OF OBC 2012 (2019 AMENDMENT)
- CSA 086-14
- TPIC 2014

(55% OF 31.3 P.S.F. G.S.L. PLUS 8.4 P.S.F. RAIN LOAD) EQUALS 25.6 P.S.F. SPECIFIED ROOF LIVE LOAD

ALLOWABLE DEFL.(LL) = L/360 (0.79")
CALCULATED VERT. DEFL.(LL) = L/999 (0.06")
ALLOWABLE DEFL.(TL) = L/360 (0.79")
CALCULATED VERT. DEFL.(TL) = L/999 (0.12")

CSI: TC=0.91/1.00 (F-G:1), BC=0.33/1.00 (H-J:4), WB=0.46/1.00 (E-H:1), SSI=0.31/1.00 (E-F:1)

DOL LUMBER=1.00 NAIL=1.00 LS BEND=1.10
COMP=1.10 SHEAR=1.10 TENS=1.10

COMPANION LIVE LOAD FACTOR = 1.00

TRUSS PLATE MANUFACTURER IS NOT RESPONSIBLE FOR QUALITY CONTROL IN THE TRUSS MANUFACTURING PLANT

NAIL VALUES
PLATE GRIP(DRY) SHEAR SECTION
(PSI) (PLI) (PLI)
MAX MIN MAX MIN MAX MIN
MT20 650 371 1747 788 1987 1873

PLATE PLACEMENT TOL. = 0.250 inches

PLATE ROTATION TOL. = 5.0 Deg.

JSI GRIP = 0.83 (B) (INPUT = 0.90)
JSI METAL = 0.47 (I) (INPUT = 1.00)




Structural component only
DWG# T-2017122

Version 8.330 S May 6 2020 MTEK Industries, Inc. Tue Aug 4 12:39:42 2020 Page 1
ID:W63xGm60kc00SiyZ4EwBx6zA2m0-F5vbWq0T_Ylv41gqSk6sRYPdl5Z_CGrQvkiHyrEi



JOB NAME 410116	TRUSS NAME T34	QUANTITY 4	PLY 1	JOB DESC. GREEN PARK HOMES	DRWG NO.
Tamarack Roof Truss, Burlington				TRUSS DESC.	

Version 8.330 S May 6 2020 MiTek Industries, Inc. Tue Aug 4 12:39:43 2020 Page 1
ID:W63xGm60kc00SiyZ4EwBx6zA2m0-jITzjA15iRQmBF00Se5zlyobUvaxhEstZTGBjyrEik



LUMBER

N. L. G. A. RULES

CHORDS	SIZE	LUMBER	DESCR.
A - D	2x4	DRY	No.2
D - E	2x4	DRY	No.2
E - G	2x4	DRY	No.2
H - G	2x4	DRY	No.2
M - B	2x4	DRY	No.2
M - J	2x4	DRY	No.2
J - H	2x4	DRY	No.2
ALL WEBS EXCEPT	2x3	DRY	No.2

SPF

DRY: SEASONED LUMBER.

DIMENSIONS, SUPPORTS AND LOADINGS SPECIFIED BY FABRICATOR TO BE VERIFIED BY BUILDING DESIGNER

BEARINGS

JT	FACTORED GROSS REACTION		MAXIMUM FACTORED GROSS REACTION		INPUT BRG IN-SX	REQD BRG IN-SX
	VERT	HORZ	DOWN	HORZ		
H	1309	0	1309	0	1-8	1-8
M	1434	0	1434	0	5-8	5-8

UNFACTORED REACTIONS

JT	1ST LCASE COMBINED		MAX./MIN. COMPONENT REACTIONS		WIND	DEAD	SOIL
	SNOW	LIVE	PERM.LIVE	LIVE			
H	926	608	0	0	0	318	0
M	1012	677	0	0	0	335	0

BEARING MATERIAL TO BE SPF NO.2 OR BETTER AT JOINT(S) H, M

BRACING

TOP CHORD TO BE SHEATHED OR MAX. PURLIN SPACING = 4.17 FT.
MAX. UNBRACED BOTTOM CHORD LENGTH = 10.00 FT OR RIGID CEILING DIRECTLY APPLIED.

ALL PITCH BREAKS AND PERIMETER CORNER JOINTS MUST BE Laterally RESTRAINED.

1 LATERAL BRACE(S) AT 1/2 LENGTH OF G-H, C-K, E-I.

END VERTICAL(S) MUST BE SHEATHED OR HAVE BRACES AS INDICATED IN THE MAX. UNBRACED LENGTH COLUMN OF THE TABLE BELOW

LOADING

TOTAL LOAD CASES: (4)

CHORDS					WEBS				
MEMB.	MAX. FACTORED FORCE (LBS)	FACTORED VERT. LOAD (PLF)	LC1	MAX CSI (LC)	MAX. UNBRAC LENGTH	MEMB.	MAX. FACTORED FORCE (LBS)	MAX CSI (LC)	
FR-TO		FROM	TO			FR-TO			
A-B	0 28	-91.8	-91.8	0.12 (1)	10.00	L-C	-52 100	0.03 (4)	
B-C	-1780 0	-91.8	-91.8	0.67 (1)	4.17	C-K	-774 0	0.35 (1)	
C-D	-1118 0	-91.8	-91.8	0.60 (1)	5.11	K-E	0 520	0.12 (1)	
D-E	-1118 0	-91.8	-91.8	0.60 (1)	5.11	B-L	0 1634	0.37 (1)	
E-F	-698 0	-91.8	-91.8	0.29 (1)	6.25	I-G	0 1299	0.29 (1)	
F-G	-698 0	-91.8	-91.8	0.29 (1)	6.25	E-I	-521 0	0.30 (1)	
H-G	-1270 0	0.0	0.0	0.38 (1)	5.71	I-F	-560 0	0.71 (1)	
M-B	-1380 0	0.0	0.0	0.14 (1)	6.92				
M-L	0 0	-18.5	-18.5	0.22 (4)	10.00				
L-K	0 1622	-18.5	-18.5	0.37 (1)	10.00				
K-J	0 975	-18.5	-18.5	0.22 (1)	10.00				
J-I	0 975	-18.5	-18.5	0.22 (1)	10.00				
I-H	0 0	-18.5	-18.5	0.10 (4)	10.00				

TOTAL WEIGHT = 4 X 109 = 436 lb [M/F]

DESIGN CRITERIA

SPECIFIED LOADS:
TOP CH. LL = 25.6 PSF
DL = 6.0 PSF
BOT CH. LL = 0.0 PSF
DL = 7.4 PSF
TOTAL LOAD = 39.0 PSF

SPACING = 24.0 IN. C/C

LOADING IN FLAT SECTION BASED ON A SLOPE OF 6.00/12

THIS TRUSS IS DESIGNED FOR RESIDENTIAL OR SMALL BUILDING REQUIREMENTS OF PART 9, NBCC 2015

THIS DESIGN COMPLIES WITH:
- PART 9 OF CBC 2018, ABC 2019
- PART 9 OF OBC 2012 (2019 AMENDMENT)
- CSA 086-14
- TPIC 2014

155% OF 31.3 P.S.F. G.S.L. PLUS 8.4 P.S.F. RAIN LOAD) EQUALS 25.6 P.S.F. SPECIFIED ROOF LIVE LOAD

ALLOWABLE DEFL.(LL) = L/360 (0.79")
CALCULATED VERT. DEFL.(LL) = L/999 (0.06")
ALLOWABLE DEFL.(TL) = L/360 (0.79")
CALCULATED VERT. DEFL.(TL) = L/999 (0.14")

CSI: TC=0.67/1.00 (B-C:1), BC=0.37/1.00 (K-L:1), WB=0.71/1.00 (F-I:1), SSI=0.28/1.00 (B-C:1)

DOL LUMBER=1.00 NAIL=1.00 LS BEND=1.10
COMP=1.10 SHEAR=1.10 TENS=1.10

COMPANION LIVE LOAD FACTOR = 1.00

TRUSS PLATE MANUFACTURER IS NOT RESPONSIBLE FOR QUALITY CONTROL IN THE TRUSS MANUFACTURING PLANT.

NAIL VALUES
PLATE GRIP(DRY) SHEAR SECTION (PSI) (PLI) (PLI)
MAX MIN MAX MIN MAX MIN
MT20 650 371 1747 788 1987 1873

PLATE PLACEMENT TOL. = 0.250 inches

PLATE ROTATION TOL. = 5.0 Deg.

JSI GRIP= 0.81 (B) (INPUT = 0.90)
JSI METAL= 0.45 (B) (INPUT = 1.00)




Structural component only
DWG# T-2017124

JOB NAME	TRUSS NAME	QUANTITY	PLY	JOB DESC.	GREEN PARK HOMES	DRWG NO.
410116	T35	4	1	TRUSS DESC.		

Tamarack Roof Truss, Burlington

Version 8.330 S May 6 2020 MTek Industries, Inc. Tue Aug 4 12:39:44 2020 Page 1
ID:W63xGm6okcO0SiyZ4EwBx6zA2m0-CU0MxW1kW9YdKLqCZ99KWzV2CuF8q710uDDpk9yrEij



LUMBER

N. L. G. A. RULES

CHORDS	SIZE	LUMBER
A - E	2x4 DRY	No.2
E - F	2x4 DRY	No.2
F - H	2x4 DRY	No.2
I - H	2x4 DRY	No.2
N - B	2x4 DRY	No.2
N - K	2x4 DRY	No.2
K - I	2x4 DRY	No.2

ALL WEBS 2x3 DRY No.2
EXCEPT

DRY: SEASONED LUMBER.

DESCR.

SPF
SPF
SPF
SPF
SPF
SPF
SPF

SPF

DIMENSIONS, SUPPORTS AND LOADINGS SPECIFIED BY FABRICATOR TO BE VERIFIED BY BUILDING DESIGNER

BEARINGS

	FACTORED GROSS REACTION	MAXIMUM FACTORED GROSS REACTION	INPUT BRG	REQD BRG
JT	VERT	HORZ	DOWN	UPLIFT
I	1309	0	1309	0
N	1434	0	1434	0

UNFACTORED REACTIONS

1ST CASE	COMBINED	SNOW	MIN. LIVE	MAX. PERM. LIVE	WIND	DEAD	SOIL
JT	926	608	0	0	0	318	0
I	926	608	0	0	0	318	0
N	1012	677	0	0	0	335	0

BEARING MATERIAL TO BE SPF NO.2 OR BETTER AT JOINT(S) I, N

BRACING

TOP CHORD TO BE SHEATHED OR MAX. PURLIN SPACING = 4.64 FT.
MAX. UNBRACED BOTTOM CHORD LENGTH = 10.00 FT OR RIGID CEILING DIRECTLY APPLIED.

ALL PITCH BREAKS AND PERIMETER CORNER JOINTS MUST BE Laterally RESTRAINED.

1 LATERAL BRACE(S) AT 1/2 LENGTH OF H-I, D-J, G-I.

END VERTICAL(S) MUST BE SHEATHED OR HAVE BRACES AS INDICATED IN THE MAX. UNBRACED LENGTH COLUMN OF THE TABLE BELOW

LOADING

TOTAL LOAD CASES: (4)

CHORDS				WEBS			
MEMB.	MAX. FACTORED FORCE (LBS)	FACTORED VERT. LOAD (PLF)	MAX. UNBRACED LENGTH (LC)	MEMB.	MAX. FACTORED FORCE (LBS)	FACTORED VERT. LOAD (PLF)	MAX. UNBRACED LENGTH (LC)
FR-TO		FROM TO		FR-TO		FROM TO	
A-B	0 28	-91.8 -91.8	0.12 (1)	10.00	M-C	-145 41	0.03 (1)
B-C	-1785 0	-91.8 -91.8	0.36 (1)	4.64	C-L	-398 0	0.28 (1)
C-D	-1438 0	-91.8 -91.8	0.29 (1)	5.14	L-D	0 303	0.07 (1)
D-E	-901 0	-91.8 -91.8	0.29 (1)	6.12	D-J	-766 0	0.34 (1)
E-F	-901 0	-91.8 -91.8	0.29 (1)	6.12	J-G	0 78	0.03 (4)
F-G	-787 0	-91.8 -91.8	0.19 (1)	6.25	G-I	0 723	0.16 (1)
G-H	0 0	-91.8 -91.8	0.23 (1)	10.00	I-H	-1219 0	0.80 (1)
H-I	-139 0	0 0	0.05 (1)	6.25	B-M	0 1635	0.37 (1)
I-N	-1391 0	0 0	0.14 (1)	6.90			
N-M	0 0	-18.5 -18.5	0.13 (4)	10.00			
M-L	0 1615	-18.5 -18.5	0.31 (1)	10.00			
L-K	0 1286	-18.5 -18.5	0.35 (4)	10.00			
K-J	0 1286	-18.5 -18.5	0.35 (4)	10.00			
J-I	0 502	-18.5 -18.5	0.28 (4)	10.00			

TOTAL WEIGHT = 4 X 114 = 455 lb

DESIGN CRITERIA

SPECIFIED LOADS:

TOP CH. LL	= 25.6 PSF
DL	= 6.0 PSF
BOT CH. LL	= 0.0 PSF
DL	= 7.4 PSF
TOTAL LOAD	= 39.0 PSF

SPACING = 24.0 IN. C/C

LOADING IN FLAT SECTION BASED ON A SLOPE OF 6.00/12

THIS TRUSS IS DESIGNED FOR RESIDENTIAL OR SMALL BUILDING REQUIREMENTS OF PART 9, NBCC 2015

THIS DESIGN COMPLIES WITH:

- PART 9 OF BCBC 2018, ABC 2019
- PART 9 OF OBC 2012 (2019 AMENDMENT)
- CSA 086-14
- TPIC 2014

(55% OF 31.3 P.S.F. G.S.L. PLUS 8.4 P.S.F. RAIN LOAD) EQUALS 25.6 P.S.F. SPECIFIED ROOF LIVE LOAD

ALLOWABLE DEFL.(LL)= L/360 (0.79")
CALCULATED VERT. DEFL.(LL) = L/999 (0.06")
ALLOWABLE DEFL.(TL)= L/360 (0.79")
CALCULATED VERT. DEFL.(TL) = L/999 (0.13")

CSI: TC=0.36/1.00 (B-C:1), RC=0.35/1.00 (J-L:4),
WB=0.80/1.00 (G-I:1), SS=0.21/1.00 (B-C:1)

DOL LUMBER=1.00 NAIL=1.00 LS BEND=1.10
COMP=1.10 SHEAR=1.10 TENS=1.10

COMPANION LIVE LOAD FACTOR = 1.00

TRUSS PLATE MANUFACTURER IS NOT RESPONSIBLE FOR QUALITY CONTROL IN THE TRUSS MANUFACTURING PLANT

NAIL VALUES

PLATE	GRIP(DRY)	SHEAR	SECTION
(PSI)	(PLI)	(PLI)	
MAX MIN	MAX MIN	MAX MIN	
MT20	650 371	1747 788	1987 1873

PLATE PLACEMENT TOL. = 0.250 inches

PLATE ROTATION TOL. = 5.0 Deg.


JSI GRIP= 0.85 (J) (INPUT = 0.90)
JSI METAL= 0.48 (K) (INPUT = 1.00)



Structural component only
DWG# T-2017125

JOB NAME	TRUSS NAME	QUANTITY	PLY	JOB DESC.	DRWG NO.
410116	T36	6	1	GREEN PARK HOMES	
Tamarack Roof Truss, Burlington					

Version 8.330 S May 6 2020 Mitek Industries, Inc. Tue Aug 4 12:39:45 2020 Page 1
ID:W63xGm6okc00SiyZ4EwBx6zA2m0-ggak8s2MHTgUxUPP7tgZ2A19mlbgPee96tyNGcyEii



LUMBER

N. L. G. A. RULES

CHORDS	SIZE	LUMBER
A - E	2x4 DRY	No.2
F - G	2x4 DRY	No.2
H - I	2x4 DRY	No.2
M - B	2x4 DRY	No.2
M - J	2x4 DRY	No.2
J - H	2x4 DRY	No.2

ALL WEBS	2x3 DRY	No.2
EXCEPT		
I - G	2x4 DRY	No.2

DRY: SEASONED LUMBER.

PLATES (table is in inches)

JT TYPE	PLATES	W	LEN	Y	X
B TMVW-t	MT20	4.0	6.0	2.00	3.00
C TMWW-t	MT20	4.0	4.0	2.00	1.75
D TMWW-t	MT20	4.0	4.0	2.00	1.75
E TS-t	MT20	3.0	6.0		
F TTW-m	MT20	4.0	4.0		
G TMVW-t	MT20	4.0	6.0		
H BMV1-p	MT20	3.0	4.0		
I BMWW-t	MT20	4.0	9.0		
J BS-t	MT20	3.0	6.0		
K BMWW-t	MT20	4.0	4.0		
L BMWW-t	MT20	5.0	6.0		
M BMV1-p	MT20	3.0	4.0		

DIMENSIONS, SUPPORTS AND LOADINGS SPECIFIED BY FABRICATOR TO BE VERIFIED BY BUILDING DESIGNER

BEARINGS

	FACTORED GROSS REACTION	MAXIMUM FACTORED GROSS REACTION	INPUT BRG	REQRD BRG
JT	VERT	HORZ	DOWN	UPLIFT
H	1309	0	1309	0
M	1434	0	1434	0

UNFACTORED REACTIONS

	1ST LCASE	MAX. MIN. COMPONENT REACTIONS						
JT	COMBINED	SNOW	LIVE	PERM. LIVE	WIND	DEAD	SOIL	
H	926	608	0	0	0	318	0	0
M	1012	677	0	0	0	335	0	0

BEARING MATERIAL TO BE SPF NO.2 OR BETTER AT JOINT(S) H, M

BRACING

TOP CHORD TO BE SHEATHED OR MAX. PURLIN SPACING = 4.52 FT.
MAX. UNBRACED BOTTOM CHORD LENGTH = 10.00 FT OR RIGID CEILING DIRECTLY APPLIED.

ALL PITCH BREAKS AND PERIMETER CORNER JOINTS MUST BE Laterally RESTRAINED.

1 LATERAL BRACE(S) AT 1/2 LENGTH OF G-H, D-I, F-J.

END VERTICAL(S) MUST BE SHEATHED OR HAVE BRACES AS INDICATED IN THE MAX. UNBRACED LENGTH COLUMN OF THE TABLE BELOW

LOADING

TOTAL LOAD CASES: (4)

CHORDS				WEBS			
MEMB.	MAX. FACTORED FORCE (LBS)	FACTORED VERT. LOAD (PLF)	MAX. UNBRACED LENGTH (LC)	MEMB.	MAX. FACTORED FORCE (LBS)	MAX. UNBRACED LENGTH (LC)	
FR-TO		FROM TO		FR-TO			
A-B	0 28	-91.8 -91.8	0.12 (1)	10.00	L-C	-106 63	0.03 (1)
B-C	-1781 0	-91.8 -91.8	0.46 (1)	4.52	C-K	-512 0	0.49 (1)
C-D	-1327 0	-91.8 -91.8	0.37 (1)	5.20	K-D	0 388	0.09 (1)
D-E	-683 0	-91.8 -91.8	0.37 (1)	6.25	D-I	-908 0	0.52 (1)
E-F	-683 0	-91.8 -91.8	0.37 (1)	6.25	I-F	-192 14	0.13 (1)
F-G	-587 0	-91.8 -91.8	0.41 (1)	6.25	I-G	0 1158	0.19 (1)
G-H	-1267 0	0.0 0.0	0.63 (1)	5.73	B-L	0 1629	0.37 (1)
H-I	-1386 0	0.0 0.0	0.14 (1)	6.91			
M-L	0 0	-18.5 -18.5	0.15 (4)	10.00			
L-K	0 1614	-18.5 -18.5	0.33 (1)	10.00			
K-J	0 1187	-18.5 -18.5	0.28 (1)	10.00			
J-I	0 1187	-18.5 -18.5	0.28 (1)	10.00			
I-H	0 0	-18.5 -18.5	0.16 (4)	10.00			

TOTAL WEIGHT = 6 X 116 = 696 lb

DESIGN CRITERIA

SPECIFIED LOADS:

TOP CH.	LL = 25.6 PSF
	DL = 6.0 PSF
BOT CH.	LL = 0.0 PSF
	DL = 7.4 PSF
TOTAL LOAD	= 39.0 PSF

SPACING = 24.0 IN. C/C

LOADING IN FLAT SECTION BASED ON A SLOPE OF 6.00/12

THIS TRUSS IS DESIGNED FOR RESIDENTIAL OR SMALL BUILDING REQUIREMENTS OF PART 9, NBCC 2015

THIS DESIGN COMPLIES WITH:

- PART 9 OF BCBC 2018, ABC 2019
- PART 9 OF CBC 2012 (2019 AMENDMENT)
- CSA 086-14
- TPIC 2014

(55 % OF 31.3 P.S.F. G.S.L. PLUS 8.4 P.S.F. RAIN LOAD) EQUALS 25.6 P.S.F. SPECIFIED ROOF LIVE LOAD

ALLOWABLE DEFL.(LL) = L/360 (0.79")
CALCULATED VERT. DEFL.(LL) = L/999 (0.06")
ALLOWABLE DEFL.(TL) = L/360 (0.79")
CALCULATED VERT. DEFL.(TL) = L/999 (0.12")

CSI: TC=0.63/1.00 (G-H:1), BC=0.33/1.00 (K-L:1), WB=0.52/1.00 (D-I:1), SSI=0.23/1.00 (B-C:1)

DOL LUMBER=1.00 NAIL=1.00 LS BEND=1.10
COMP=1.10 SHEAR=1.10 TENS=1.10

COMPANION LIVE LOAD FACTOR = 1.00

TRUSS PLATE MANUFACTURER IS NOT RESPONSIBLE FOR QUALITY CONTROL IN THE TRUSS MANUFACTURING PLANT.


NAIL VALUES

PLATE	GRIP(DRY) SHEAR (PSI)	SECTION (PLI)
MT20	650 371 1747 788 1987 1873	

PLATE PLACEMENT TOL. = 0.250 inches

PLATE ROTATION TOL. = 5.0 Deg.


JSI GRIP= 0.83 (I) (INPUT = 0.90)
JSI METAL= 0.45 (B) (INPUT = 1.00)



Structural component only
DWG# T-2017126

Structural component only
DWG# T-2017169

JOB NAME	TRUSS NAME	QUANTITY	PLY	JOB DESC.	DRWG NO.
410149	T38	6	1	GREEN PARK HOMES	
Tamarack Roof Truss, Burlington					
Version 8.330 S May 6 2020 MiTek Industries, Inc. Tue Aug 4 13:58:25 2020 Page 1					
ID:pqvtrdsyU73tskbsg1clrEz7ifa-Tkn5mnA2ihLmCsEYd9LPMXXutyXIIOSvUCK7w1yrDYy					
Scale = 1:33.5					



LUMBER				DIMENSIONS, SUPPORTS AND LOADINGS SPECIFIED BY FABRICATOR TO BE VERIFIED BY				TOTAL WEIGHT = 6 X 62 = 370 lb			
N. L. G. A. RULES				BUILDING DESIGNER							
CHORDS SIZE				BEARINGS							
A - D	2x4	DRY	No.2	FACTORED							
D - G	2x4	DRY	No.2	GROSS REACTION							
H - F	2x4	DRY	No.2	MAXIMUM FACTORED							
J - H	2x4	DRY	No.2	INPUT							
ALL WEBS 2x3 DRY No.2				REQRD							
EXCEPT				BRG							
DRY: SEASONED LUMBER.				IN-SX							
				MECHANICAL							

PLATES (table is in inches)					
JT	TYPE	PLATES	W	LEN	Y X
B	TMV+p	MT20	3.0	4.0	
C	TMVW-t	MT20	4.0	4.0	
D	TTW-p	MT20	4.0	4.0	
E	TMVW-t	MT20	4.0	4.0	
F	TMV+p	MT20	3.0	4.0	
H	BMVW1-t	MT20	4.0	4.0	
I	BMVWW-t	MT20	4.0	9.0	
J	BMVW1-t	MT20	4.0	4.0	

UNFACTORED REACTIONS							
JT	1ST CASE	MAX/MIN	COMPONENT REACTIONS				
J	COMBINED	SNOW	LIVE	PERM. LIVE	WIND	DEAD	SOIL
J	612	415 / 0	0 / 0	0 / 0	0 / 0	197 / 0	0 / 0
H	612	415 / 0	0 / 0	0 / 0	0 / 0	197 / 0	0 / 0

BEARING MATERIAL TO BE SPF NO.2 OR BETTER AT JOINT(S) J

BRACING
TOP CHORD TO BE SHEATHED OR MAX. PURLIN SPACING = 6.25 FT.
MAX. UNBRACED BOTTOM CHORD LENGTH = 10.00 FT. OR RIGID CEILING DIRECTLY APPLIED.

ALL PITCH BREAKS AND PERIMETER CORNER JOINTS MUST BE Laterally RESTRAINED.

LOADING
TOTAL LOAD CASES: (4)

CHORDS				WEBS			
MAX. FACTORED				MAX. FACTORED			
MEMB.	FORCE	VERT. LOAD	LC1 MAX	MEMB.	FORCE	MAX	
	(LBS)	(PLF)	CSI (LC)		(LBS)	CSI (LC)	
FR-TO	FROM TO			FR-TO	FROM TO		
A-B	0 / 28	-91.8	-91.8 0.12 (1)	I-D	0 / 218	0.05 (1)	
B-C	0 / 16	-91.8	-91.8 0.17 (1)	I-E	-41 / 32	0.02 (1)	
C-D	-525 / 0	-91.8	-91.8 0.13 (1)	C-I	-41 / 32	0.02 (1)	
D-E	-525 / 0	-91.8	-91.8 0.13 (1)	J-C	-752 / 0	0.33 (1)	
E-F	0 / 16	-91.8	-91.8 0.17 (1)	E-H	-752 / 0	0.33 (1)	
F-G	0 / 28	-91.8	-91.8 0.12 (1)				
J-B	-244 / 0	0.0	0.0 0.03 (1)				
H-F	-244 / 0	0.0	0.0 0.03 (1)				
J-I	0 / 482	-18.5	-18.5 0.28 (4)				
I-H	0 / 482	-18.5	-18.5 0.28 (4)				

DESIGN CRITERIA

SPECIFIED LOADS:
TOP CH. LL = 25.6 PSF
DL = 8.0 PSF
BOT CH. LL = 0.0 PSF
DL = 7.4 PSF
TOTAL LOAD = 39.0 PSF

SPACING = 24.0 IN. C/C

THIS TRUSS IS DESIGNED FOR RESIDENTIAL OR SMALL BUILDING REQUIREMENTS OF PART 9, NBCC 2015

THIS DESIGN COMPLIES WITH:
- PART 9 OF BCBC 2018, ABC 2019
- PART 9 OF OBC 2012 (2019 AMENDMENT)
- CSA 086-14
- TPIC 2014

(55 % OF 31.3 P.S.F. G.S.L. PLUS 8.4 P.S.F. RAIN LOAD) EQUALS 25.6 P.S.F. SPECIFIED ROOF LIVE LOAD

ALLOWABLE DEFL.(LL)= L/360 (0.45")
CALCULATED VERT. DEFL.(LL) = L/999 (0.01")
ALLOWABLE DEFL.(TL)= L/360 (0.45")
CALCULATED VERT. DEFL.(TL) = L/999 (0.05")

CSI: TC=0.17/1.00 (E-F:1), BC=0.28/1.00 (I-J:4),
WB=0.33/1.00 (E-H:1), SSI=0.13/1.00 (E-F:1)

DOL LUMBER=1.00 NAIL=1.00 LS BEND=1.10
COMP=1.10 SHEAR=1.10 TENS=1.10

COMPANION LIVE LOAD FACTOR = 1.00

TRUSS PLATE MANUFACTURER IS NOT RESPONSIBLE FOR QUALITY CONTROL IN THE TRUSS MANUFACTURING PLANT.

NAIL VALUES
PLATE GRIP(DRY) SHEAR SECTION
(PSI) (PLI) (PLI)
MAX MIN MAX MIN MAX MIN
MT20 650 371 1747 788 1987 1873

PLATE PLACEMENT TOL. = 0.250 inches

PLATE ROTATION TOL. = 5.0 Deg.

JSI GRIP= 0.62 (E) (INPUT = 0.90)
JSI METAL= 0.23 (E) (INPUT = 1.00)




Structural component only
DWG# T-2017170

JOB NAME	TRUSS NAME	QUANTITY	PLY	JOB DESC.	DRWG NO.
410149	T39	2	1	GREEN PARK HOMES	

Tamarack Roof Truss, Burlington

Version 8.330 S May 6 2020 MTEK Industries, Inc. Tue Aug 4 13:58:26 2020 Page 1
ID:pqvtrdsyU73tskbsq1clREz7lfa-xwLTz7BgT_Tdq?pkBsteuk33VMs?1s22is3qSTyrDYx
8-4-0 8-4-12 9-7-8



LUMBER				
N. L. G. A. RULES	CHORDS	SIZE	LUMBER	DESCR.
A - C	2x4	DRY	No.2	SPF
C - E	2x4	DRY	No.2	SPF
E - G	2x4	DRY	No.2	SPF
L - B	2x4	DRY	No.2	SPF
H - F	2x4	DRY	No.2	SPF
L - H	2x4	DRY	No.2	SPF
ALL WEBS	2x3	DRY	No.2	SPF
EXCEPT				
DRY: SEASONED LUMBER.				

PLATES (table is in inches)				
JT	TYPE	PLATES	W	LEN Y X
B	TMVW+p	MT20	4.0	4.0 1.25 2.00
C	TTWW+m	MT20	5.0	8.0 2.00 3.00
D	TMVW+w	MT20	2.0	4.0
E	TTWW-m	MT20	5.0	8.0 2.00 3.00
F	TMVW+p	MT20	4.0	4.0 1.25 2.00
H	BMV1+p	MT20	3.0	4.0
I	BMVW-t	MT20	4.0	6.0
J	BMVWW-t	MT20	4.0	9.0
K	BMVW-t	MT20	4.0	6.0
L	BMV1+p	MT20	3.0	4.0

DIMENSIONS, SUPPORTS AND LOADINGS SPECIFIED BY FABRICATOR TO BE VERIFIED BY BUILDING DESIGNER

BEARINGS		FACTORED GROSS REACTION	MAXIMUM FACTORED GROSS REACTION	INPUT BRG	REQRD BRG
JT	VERT	HORZ	DOWN	HORZ	UPLIFT
L	1061	0	1061	0	5-8
H	1282	0	1282	0	5-8

UNFACTORED REACTIONS		1ST LCASE	MAX./MIN. COMPONENT REACTIONS
JT	COMBINED	SNOW	LIVE
L	741	539 / 0	0 / 0
H	892	667 / 0	0 / 0

BEARING MATERIAL TO BE SPF NO.2 OR BETTER AT JOINT(S) L, H

BRACING

TOP CHORD TO BE SHEATHED OR MAX. PURLIN SPACING = 4.93 FT.

MAX. UNBRACED BOTTOM CHORD LENGTH = 10.00 FT OR RIGID CEILING DIRECTLY APPLIED.

ALL PITCH BREAKS AND PERIMETER CORNER JOINTS MUST BE Laterally RESTRAINED.

LOADING

TOTAL LOAD CASES: (7)

CHORDS				WEBS			
MEMB.	MAX. FACTORED FORCE (LBS)	FACTORED VERT. LOAD (LBS)	MAX. FACTORED HORIZ. LOAD (LBS)	MEMB.	MAX. FACTORED FORCE (LBS)	MAX. FACTORED HORIZ. LOAD (LBS)	MAX. FACTORED VERT. LOAD (LBS)
FR-TO				FR-TO			
A-B	0 / 28	-91.8	-91.8 0.13 (1)	J-D	-294 / 0	0.05 (1)	10.00
B-C	-808 / 0	-91.8	-91.8 0.13 (1)	K-C	-113 / 55	0.02 (1)	10.00
C-M	-1676 / 0	-91.8	-91.8 0.17 (1)	I-E	-180 / 4	0.03 (1)	10.00
M-D	-1676 / 0	-91.8	-91.8 0.17 (1)	J-E	0 / 1160	0.29 (1)	10.00
D-N	-1676 / 0	-91.8	-91.8 0.17 (1)	I-F	0 / 813	0.20 (1)	10.00
N-O	-1676 / 0	-91.8	-91.8 0.17 (1)	C-J	0 / 1080	0.27 (1)	10.00
O-E	-1676 / 0	-91.8	-91.8 0.17 (1)	B-K	0 / 905	0.22 (1)	10.00
E-F	-731 / 0	-91.8	-91.8 0.13 (1)				
F-G	0 / 28	-91.8	-91.8 0.13 (1)				
L-B	-1205 / 0	0.0	0.0 0.13 (1)				
H-F	-1389 / 0	0.0	0.0 0.15 (1)				
L-K	0 / 0	-18.5	-18.5 0.22 (1)				
K-P	0 / 672	-18.5	-18.5 0.34 (1)				
P-Q	0 / 672	-18.5	-18.5 0.34 (1)				
Q-R	0 / 672	-18.5	-18.5 0.34 (1)				
R-J	0 / 672	-18.5	-18.5 0.34 (1)				
J-S	0 / 598	-18.5	-18.5 0.28 (1)				
S-T	0 / 598	-18.5	-18.5 0.28 (1)				
T-U	0 / 598	-18.5	-18.5 0.28 (1)				
U-I	0 / 598	-18.5	-18.5 0.28 (1)				
I-H	0 / 0	-18.5	-18.5 0.17 (1)				

FACTORED CONCENTRATED LOADS (LBS)				FACE			
JT	LOC.	LC1	MAX.	MAX+	FACE	DIR.	TYPE
C	10-8	13	1	150	FRONT	VERT	TOTAL
F	8-4-12	-280	-280	---	TOP	VERT	TOTAL
J	4-4-12	-202	-202	---	TOP	VERT	TOTAL
K	11-4	1	1	19	FRONT	VERT	TOTAL
M	2-11-4	20	1	159	FRONT	VERT	TOTAL
N	4-11-4	20	1	159	FRONT	VERT	TOTAL
O	6-11-4	17	1	137	FRONT	VERT	TOTAL
P	1-7-0	-250	-250	---	BACK	VERT	TOTAL
Q	2-11-4	1	1	19	FRONT	VERT	TOTAL
R	3-4-12	-250	-250	---	BACK	VERT	TOTAL
S	4-11-4	1	1	19	FRONT	VERT	TOTAL
T	6-4-12	-264	-264	---	TOP	VERT	TOTAL
U	6-11-4	1	1	19	FRONT	VERT	TOTAL

CONNECTION REQUIREMENTS

1) C1: A SUITABLE HANGER/MECHANICAL CONNECTION IS REQUIRED.

DESIGN CRITERIA

SPECIFIED LOADS:

TOP CH. LL = 25.6 PSF

DL = 6.0 PSF

BOT CH. LL = 0.0 PSF

DL = 7.4 PSF

TOTAL LOAD = 39.0 PSF

SPACING = 24.0 IN. C/C

LOADING IN FLAT SECTION BASED ON A SLOPE OF 6.00/12

THIS TRUSS IS DESIGNED FOR RESIDENTIAL OR SMALL BUILDING REQUIREMENTS OF PART 9, NBCC 2015

THIS DESIGN COMPLIES WITH:

- PART 9 OF CBC 2018, ABC 2019
- PART 9 OF OBC 2012 (2019 AMENDMENT)
- CSA 086-14
- TPIC 2014

DESIGN ASSUMPTIONS

-OVERHANG NOT TO BE ALTERED OR CUT OFF.

(55 % OF 31.3 P.S.F. G.S.L. PLUS 8.4 P.S.F. RAIN LOAD) EQUALS 25.6 P.S.F. SPECIFIED ROOF LIVE LOAD

ALLOWABLE DEFL.(LL)= L/360 (0.28")

CALCULATED VERT. DEFL.(LL)= L/999 (0.03")

ALLOWABLE DEFL.(TL)= L/360 (0.28")

CALCULATED VERT. DEFL.(TL)= L/999 (0.06")

CSI: TC=0.17/1.00 (C-D:1), BC=0.34/1.00 (J-K:1), WB=0.29/1.00 (E-J:1), SS=0.28/1.00 (J-K:1)

DOL LUMBER=1.00 NAIL=1.00 LS BEND=1.00 COMP=1.00 SHEAR=1.00 TENS=1.00

COMPANION LIVE LOAD FACTOR = 1.00

AUTOSOLVE HEELS OFF

TRUSS PLATE MANUFACTURER IS NOT RESPONSIBLE FOR QUALITY CONTROL IN THE TRUSS MANUFACTURING PLANT.

NAIL VALUES		PLATE GRIP(DRY)	SHEAR (PSI)	SECTION (PLI)
MT20	650	371	1747	788
				1987
				1873

PLATE PLACEMENT TOL. = 0.250 inches

PLATE ROTATION TOL. = 5.0 Deg.


JSI GRIP= 0.78 (C) (INPUT = 0.90)

JSI METAL= 0.24 (F) (INPUT = 1.00)



Structural component only
DWG# T-2017171

JOB NAME	TRUSS NAME	QUANTITY	PLY	JOB DESC.	GREEN PARK HOMES	DRWG NO.
410149	T40	2	2	TRUSS DESC.		



TOTAL WEIGHT = 4 X 29 = 117 lb

LUMBER						
N. L. G. A. RULES						
CHORDS		SIZE		LUMBER		DESCR.
F - A	2x6	DRY	No.2			SPF
A - C	2x4	DRY	No.2			SPF
D - C	2x4	DRY	No.2			SPF
F - D	2x6	DRY	No.2			SPF

ALL WEBS 2x3 DRY No.2 SPF
DRY: SEASONED LUMBER.

DESIGN CONSISTS OF 2 TRUSSES BUILT SEPARATELY THEN FASTENED TOGETHER AS FOLLOWS:

CHORDS #ROWS	SURFACE SPACING (IN)	LOAD(PLF)
TOP CHORDS : (0.122"x3") SPIRAL NAILS		
F - A 2 12	TOP	
A - C 1 12	TOP	
C - D 1 12	TOP	
BOTTOM CHORDS : (0.122"x3") SPIRAL NAILS		
F - D 2 12	SIDE(0.0)	
WEBS : (0.122"x3") SPIRAL NAILS		
2x3 1 6		

NAILS TO BE DRIVEN FROM ONE SIDE ONLY.

GIRDER NAILING ASSUMES NAILED HANGERS ARE FASTENED WITH MIN. 3-0 INCH NAILS.

TOP - COMPONENTS ARE LOADED FROM THE TOP AND MUST BE PLACED ON TOP EDGE OF ALL PLIES FOR THE LOAD TO BE TRANSFERRED TO EACH PLY.

SIDE - PLF SHOWN IS THE EQUIVALENT UDL APPLIED TO ONE SIDE THAT THE CORRESPONDING NAILING PATTERN SHALL BE CAPABLE OF TRANSFERRING. REMAINING PLF MUST BE APPLIED ON THE OPPOSITE SIDE OR ON THE TOP.

PLATES (table is in inches)	JT TYPE	PLATES	W	LEN	Y	X
A	TMVW-p	MT20	4.0	6.0	1.00	3.00
B	TMVW-t	MT20	4.0	4.0	2.00	1.75
C	TMV-p	MT20	3.0	4.0		
D	BMVW1+p	MT20	4.0	6.0		
E	BMVW-t	MT20	5.0	6.0		
F	BMV1+p	MT20	3.0	6.0		

DIMENSIONS, SUPPORTS AND LOADINGS SPECIFIED BY FABRICATOR TO BE VERIFIED BY BUILDING DESIGNER

JT	FACTORED GROSS REACTION		MAXIMUM FACTORED GROSS REACTION		INPUT BRG	REQD BRG
	VERT.	HORZ.	DOWN	HORZ.		
F	1078	0	1078	0	5-8	5-8
D	1271	0	1271	0	MECHANICAL	

A SUITABLE HANGER/MECHANICAL CONNECTION IS REQUIRED AT JOINT D. MINIMUM BEARING LENGTH AT JOINT D = 1-8.

UNFACTORED REACTIONS

1ST LCASE		MAX./MIN. COMPONENT REACTIONS					
JT	COMBINED	SNOW	LIVE	PERM.LIVE	WIND	DEAD	SOIL
F	758	518 / 0	0 / 0	0 / 0	0 / 0	240 / 0	0 / 0
D	894	612 / 0	0 / 0	0 / 0	0 / 0	282 / 0	0 / 0

BEARING MATERIAL TO BE SPF NO.2 OR BETTER AT JOINT(S) F

BRACING

TOP CHORD TO BE SHEATHED OR MAX. PURLIN SPACING = 6.25 FT.
MAX. UNBRACED BOTTOM CHORD LENGTH = 10.00 FT OR RIGID CEILING DIRECTLY APPLIED.

ALL PITCH BREAKS AND PERIMETER CORNER JOINTS MUST BE Laterally RESTRAINED.

LOADING

TOTAL LOAD CASES: (4)

MEMB.	CHORDS			WEBS		
	MAX. FACTORED FORCE (LBS)	FACTORED VERT. LOAD (PLF)	MAX. FACTORED CSI (LC)	MAX. FACTORED FORCE (LBS)	MAX. FACTORED CSI (LC)	MAX. FACTORED CSI (LC)
FR-TO		FROM TO		FR-TO		
F-A	-958 / 0	0.0	0.0 0.03 (1)	7.81	A-E	0.1148
A-B	-1230 / 0	-91.8	-91.8 0.06 (1)	6.25	E-B	0.1084
B-C	-11 / 0	-91.8	-91.8 0.05 (1)	6.25	B-D	-1397 / 0
D-C	-110 / 0	0.0	0.0 0.01 (1)	7.81		
F-G	0 / 0	-18.5	-18.5 0.11 (1)	10.00		
G-E	0 / 0	-18.5	-18.5 0.11 (1)	10.00		
E-H	0 / 1110	-18.5	-18.5 0.25 (1)	10.00		
H-D	0 / 1110	-18.5	-18.5 0.25 (1)	10.00		

FACTORED CONCENTRATED LOADS (LBS)

JT	LOC.	LC1	MAX	FACE	DIR.	TYPE	HEEL	CONN.
G	2-3-4	-850	-850	---	BACK	VERT	TOTAL	C1
H	4-3-4	-850	-850	---	BACK	VERT	TOTAL	C1

CONNECTION REQUIREMENTS

1) C1: A SUITABLE HANGER/MECHANICAL CONNECTION IS REQUIRED.

DESIGN CRITERIA

SPECIFIED LOADS:

TOP CH.	LL = 25.6	PSF
	DL = 6.0	PSF
BOT CH.	LL = 0.0	PSF
	DL = 7.4	PSF
TOTAL LOAD	= 39.0	PSF

SPACING = 24.0 IN. C/C

THIS TRUSS IS DESIGNED FOR RESIDENTIAL OR SMALL BUILDING REQUIREMENTS OF PART 9, NBCC 2015

THIS DESIGN COMPLIES WITH:
- PART 9 OF CBC 2018, ABC 2019
- PART 9 OF OBC 2012 (2019 AMENDMENT)
- CSA 086-14
- TPIC 2014

(55% OF 31.3 P.S.F. G.S.L. PLUS 8.4 P.S.F. RAIN LOAD) EQUALS 25.6 P.S.F. SPECIFIED ROOF LIVE LOAD

ALLOWABLE DEFL.(LL)= L/360 (0.20")
CALCULATED VERT. DEFL.(LL) = L/999 (0.01")
ALLOWABLE DEFL.(TL)= L/360 (0.20")
CALCULATED VERT. DEFL.(TL) = L/999 (0.01")

CSI: TC=0.06/1.00 (A-B:1), BC=0.25/1.00 (D-E:1), WB=0.17/1.00 (B-D:1), SSI=0.26/1.00 (E-F:1)

DOL LUMBER=1.00 NAIL=1.00 LS BEND=1.00
COMP=1.00 SHEAR=1.00 TENS=1.00

COMPANION LIVE LOAD FACTOR = 1.00

TRUSS PLATE MANUFACTURER IS NOT RESPONSIBLE FOR QUALITY CONTROL IN THE TRUSS MANUFACTURING PLANT.

NAIL VALUES

PLATE	GRIP(DRY)	SHEAR	SECTION
	(PSI)	(PLI)	(PLI)
	MAX MIN	MAX MIN	MAX MIN
MT20	650 371	1747 788	1987 1873

PLATE PLACEMENT TOL. = 0.250 inches

PLATE ROTATION TOL. = 5.0 Deg.

JSI GRIP= 0.70 (B) (INPUT = 0.90)
JSI METAL= 0.25 (D) (INPUT = 1.00)




Structural component only
DWG# T-2017172

JSI GRIP= 0.50 (B) (INPUT = 0.90)
JSI METAL= 0.19 (D) (INPUT = 1.00)

JOB NAME 410149	TRUSS NAME T41	QUANTITY 2	PLY 2	JOB DESC. GREEN PARK HOMES	DRWG NO.
---------------------------	--------------------------	----------------------	-----------------	--------------------------------------	----------

Tamarack Roof Truss, Burlington

Version 8.330 S May 6 2020 MiTek Industries, Inc. Tue Aug 4 13:58:28 2020 Page 1
ID:pqvtrdsyU73tskbsg1clrEz7lfa-lJTDOpCw?cJL3Jz7JHv6z99OMAcMvovLAAyNXLyDYv



Scale = 1:14.9

LUMBER			
N. L. G. A. RULES	CHORDS	SIZE	LUMBER
F - A	2x4	DRY	No.2
A - C	2x4	DRY	No.2
D - C	2x4	DRY	No.2
F - D	2x6	DRY	No.2
ALL WEBS	2x3	DRY	No.2
DRY: SEASONED LUMBER.			

DESIGN CONSISTS OF 2 TRUSSES BUILT SEPARATELY THEN FASTENED TOGETHER AS FOLLOWS:

CHORDS #ROWS	SURFACE SPACING (IN)	LOAD (PLF)
TOP CHORDS : (0.122"x3") SPIRAL NAILS		
F - A 1	12	TOP
A - C 1	12	SIDE(25.8)
C - D 1	12	TOP
BOTTOM CHORDS : (0.122"x3") SPIRAL NAILS		
F - D 2	12	SIDE(0.0)
WEBS : (0.122"x3") SPIRAL NAILS		
2x3 1	6	

NAILS TO BE DRIVEN FROM ONE SIDE ONLY.

GIRDER NAILING ASSUMES NAILED HANGERS ARE FASTENED WITH MIN. 3-0 INCH NAILS.

TOP - COMPONENTS ARE LOADED FROM THE TOP AND MUST BE PLACED ON TOP EDGE OF ALL PLIES FOR THE LOAD TO BE TRANSFERRED TO EACH PLY.

SIDE - PLF SHOWN IS THE EQUIVALENT UDL APPLIED TO ONE SIDE THAT THE CORRESPONDING NAILING PATTERN SHALL BE CAPABLE OF TRANSFERRING. REMAINING PLF MUST BE APPLIED ON THE OPPOSITE SIDE OR ON THE TOP.

PLATES (table is in inches)

JT TYPE	PLATES	W	LEN	Y	X
A	TMVW-t	MT20	4.0	4.0	
B	TMW-w	MT20	2.0	4.0	
C	TMVW-t	MT20	4.0	4.0	
D	BMV1-p	MT20	3.0	6.0	
E	BMVWW-t	MT20	5.0	8.0	
F	BMV1-p	MT20	3.0	6.0	

DIMENSIONS, SUPPORTS AND LOADINGS SPECIFIED BY FABRICATOR TO BE VERIFIED BY BUILDING DESIGNER

BEARINGS		FACTORED	MAXIMUM FACTORED	INPUT	REQD
JT	GROSS REACTION	DOWN	HORZ	UPLIFT	BRG
F	890	0	890	0	MECHANICAL
D	943	0	943	0	1-8

A SUITABLE HANGER/MECHANICAL CONNECTION IS REQUIRED AT JOINT F. MINIMUM BEARING LENGTH AT JOINT F = 1-8.

UNFACTORED REACTIONS

1ST LCASE	MAX./MIN. COMPONENT REACTIONS						
JT	COMBINED	SNOW	LIVE	PERM.LIVE	WIND	DEAD	SOIL
F	827	429 / 0	0 / 0	- 0 / 0	0 / 0	198 / 0	0 / 0
D	664	455 / 0	0 / 0	0 / 0	0 / 0	209 / 0	0 / 0

BEARING MATERIAL TO BE SPF NO.2 OR BETTER AT JOINT(S) D

BRACING

TOP CHORD TO BE SHEATHED OR MAX. PURLIN SPACING = 6.25 FT.
MAX. UNBRACED BOTTOM CHORD LENGTH = 10.00 FT OR RIGID CEILING DIRECTLY APPLIED.

ALL PITCH BREAKS AND PERIMETER CORNER JOINTS MUST BE Laterally RESTRAINED.

LOADING

TOTAL LOAD CASES: (4)

CHORDS				WEBS			
MEMB.	MAX. FACTORED FORCE (LBS)	FACTORED VERT. LOAD (PLF)	LC1 MAX CSI (LC)	MEMB.	MAX. FACTORED FORCE (LBS)	MAX. FACTORED VERT. LOAD (PLF)	LC1 MAX CSI (LC)
FR-TO		FROM TO		FR-TO			
F - A	-723 / 0	0.0	0.0 0.04 (1)	7.81	A - E	0 / 1103	0.14 (1)
A - B	-972 / 0	-143.4	-143.4 0.15 (1)	6.25	E - B	-623 / 0	0.05 (1)
B - C	-972 / 0	-143.4	-143.4 0.15 (1)	6.25	E - C	0 / 1103	0.14 (1)
D - C	-723 / 0	0.0	0.0 0.04 (1)	7.81			
F - G	0 / 0	-18.5	-18.5 0.06 (1)	10.00			
G - H	0 / 0	-18.5	-18.5 0.06 (1)	10.00			
H - E	0 / 0	-18.5	-18.5 0.06 (1)	10.00			
E - I	0 / 0	-18.5	-18.5 0.07 (1)	10.00			
I - J	0 / 0	-18.5	-18.5 0.07 (1)	10.00			
J - D	0 / 0	-18.5	-18.5 0.07 (1)	10.00			

FACTORED CONCENTRATED LOADS (LBS)

JT	LOC	LC1	MAX-	MAX+	FACE	DIR.	TYPE	HEEL	CONN.
G	11-12	-168	-168	---	BACK	VERT	TOTAL	---	C1
H	2-11-12	-168	-168	---	BACK	VERT	TOTAL	---	C1
I	4-11-12	-168	-168	---	BACK	VERT	TOTAL	---	C1
J	6-5-12	-170	-170	---	BACK	VERT	TOTAL	---	C1

CONNECTION REQUIREMENTS

1) C1: A SUITABLE HANGER/MECHANICAL CONNECTION IS REQUIRED.

DESIGN CRITERIA

SPECIFIED LOADS:

TOP CH.	LL	=	25.6	PSF
DL	=	6.0	PSF	
BOT CH.	LL	=	0.0	PSF
DL	=	7.4	PSF	
TOTAL LOAD	=	39.0	PSF	

SPACING = 24.0 IN. C/C

LOADING IN FLAT SECTION BASED ON A SLOPE OF 6.00/12

GIRDER TYPE: CStdGirder

START DISTANCE = 0-0

START SPAN CARRIED = 4-0-0

END DISTANCE = 7-2-0

END SPAN CARRIED = 4-0-0

END WALL WIDTH = 1-8

APPLIED TO FRONT SIDE OF TOP CHORD.

- ADDTL LOADS BASED ON 55 % OF GSL

THIS TRUSS IS DESIGNED FOR RESIDENTIAL OR SMALL BUILDING REQUIREMENTS OF PART 9, NBC 2015

THIS DESIGN COMPLIES WITH:

- PART 9 OF CBC 2018, ABC 2019
- PART 9 OF OBC 2012 (2019 AMENDMENT)
- CSA 086-14
- TPIC 2014

(55 % OF 31.3 P.S.F. G.S.L. PLUS 8.4 P.S.F. RAIN LOAD) EQUALS 25.6 P.S.F. SPECIFIED ROOF LIVE LOAD

ALLOWABLE DEFL.(LL) = L/360 (0.24")

CALCULATED VERT. DEFL.(LL) = L/999 (0.01")

ALLOWABLE DEFL.(TL) = L/360 (0.24")

CALCULATED VERT. DEFL.(TL) = L/999 (0.02")

CSI: TC=0.15/1.00 (B-C:1), BC=0.07/1.00 (D-E:1), WB=0.14/1.00 (A-E:1), SSI=0.13/1.00 (A-B:1)

DOL LUMBER=1.00 NAIL=1.00 LS BEND=1.00 COMP=1.00 SHEAR=1.00 TENS=1.00

COMPANION LIVE LOAD FACTOR = 1.00

TRUSS PLATE MANUFACTURER IS NOT RESPONSIBLE FOR QUALITY CONTROL IN THE TRUSS MANUFACTURING PLANT.

NAIL VALUES

PLATE	GRIP(DRY)	SHEAR	SECTION
(PS)	(PL)	(PL)	
MAX	MIN	MAX	MIN
MT20	650	371	1747
	788	788	1873

PLATE PLACEMENT TOL. = 0.250 inches

PLATE ROTATION TOL. = 5.0 Deg.

JSI GRIP= 0.57 (C) (INPUT = 0.90)
JSI METAL= 0.17 (C) (INPUT = 1.00)




Structural component only
DWG# T-2017173

JOB NAME 410143	TRUSS NAME P20	QUANTITY 24	PLY 1	JOB DESC. GREEN PARK HOMES	DRWG NO.
--------------------	-------------------	----------------	----------	-------------------------------	----------

Tamarack Roof Truss, Burlington

Version 8.330 S May 6 2020 Mitek Industries, Inc. Tue Aug 4 13:08:54 2020 Page 1
ID:W63xGm6okcO0SiyZ4EwBx6zA2m0-y9mwDuDRNr1JGHcy4hYir?z6AKYHhivbiU8P9kyrEHN
15-6-12



LUMBER				
N. L. G. A. RULES				
CHORDS		SIZE	LUMBER	DESCR
A - C	2x4	DRY	No.2	SPF
C - E	2x4	DRY	No.2	SPF
A - E	2x4	DRY	No.2	SPF
ALL WEBS		2x3	DRY	No.2
DRY: SEASONED LUMBER.				SPF

PLATES (table is in inches)	JT	TYPE	PLATES	W	LEN	Y	X
A	TBM1-h	MT20	3.0	4.0			
B	TMW+w	MT20	2.0	4.0			
C	TTW-p	MT20	4.0	4.0			
D	TMW+w	MT20	2.0	4.0			
E	TBM1-h	MT20	3.0	4.0			
F	BMWVW1-t	MT20	4.0	9.0			

DIMENSIONS, SUPPORTS AND LOADINGS SPECIFIED BY FABRICATOR TO BE VERIFIED BY BUILDING DESIGNER

BEARINGS	FACTORED GROSS REACTION	MAXIMUM FACTORED GROSS REACTION	INPUT BRG	REQD BRG
JT	VERT	HORZ	DOWN	HORZ
A	143	0	143	0
E	143	0	143	0
F	1430	0	1430	0

UNFACTORED REACTIONS

1ST CASE	MAX./MIN. COMPONENT REACTIONS	SNOW	LIVE	PERM. LIVE	WIND	DEAD	SOIL
JT	COMBINED						
A	99	76 / 0	0 / 0	0 / 0	0 / 0	23 / 0	0 / 0
E	99	76 / 0	0 / 0	0 / 0	0 / 0	23 / 0	0 / 0
F	1016	644 / 0	0 / 0	0 / 0	0 / 0	372 / 0	0 / 0

BEARING MATERIAL TO BE SPF NO.2 OR BETTER AT JOINT(S) A, E, F

BRACING

TOP CHORD TO BE SHEATHED OR MAX. PURLIN SPACING = 10.00 FT.
MAX. UNBRACED BOTTOM CHORD LENGTH = 6.25 FT. OR RIGID CEILING DIRECTLY APPLIED.

ALL PITCH BREAKS AND PERIMETER CORNER JOINTS MUST BE Laterally RESTRAINED.

LOADING

TOTAL LOAD CASES: (4)

CHORDS	MAX. FACTORED	FACTORED	WEBS	MAX. FACTORED
MEMB.	FORCE (LBS)	VERT. LOAD LC1 (PLF)	MAX. CSI (LC)	MEMB. FORCE (LBS)
FR-TO		FROM TO	LENGTH	FR-TO
A-H	0 / 164	-91.8 -91.8	0.15 (4)	10.00
H-B	0 / 235	-91.8 -91.8	0.26 (1)	10.00
B-C	0 / 629	-91.8 -91.8	0.32 (1)	10.00
C-D	0 / 629	-91.8 -91.8	0.32 (1)	10.00
D-J	0 / 235	-91.8 -91.8	0.26 (1)	10.00
J-E	0 / 164	-91.8 -91.8	0.15 (4)	10.00
A-G	-188 / 0	-18.5 -18.5	0.06 (1)	6.25
G-F	-180 / 0	-18.5 -18.5	0.24 (4)	6.25
F-I	-180 / 0	-18.5 -18.5	0.24 (4)	6.25
I-E	-188 / 0	-18.5 -18.5	0.06 (1)	6.25

DESIGN CRITERIA

SPECIFIED LOADS:
TOP CH. LL = 25.6 PSF
DL = 6.0 PSF
BOT CH. LL = 0.0 PSF
DL = 7.4 PSF
TOTAL LOAD = 39.0 PSF

SPACING = 24.0 IN. C/C

THIS TRUSS IS DESIGNED FOR RESIDENTIAL OR SMALL BUILDING REQUIREMENTS OF PART 9, NBC 2015

THIS DESIGN COMPLIES WITH:
- PART 9 OF CBC 2018, ABC 2019
- PART 9 OF CBC 2012 (2019 AMENDMENT)
- CSA 086-14
- TPIC 2014

(55 % OF 31.3 P.S.F. G.S.L. PLUS 8.4 P.S.F. RAIN LOAD) EQUALS 25.6 P.S.F. SPECIFIED ROOF LIVE LOAD

CSI: TC=0.32/1.00 (C-D:1), BC=0.24/1.00 (F-G:4), WB=0.18/1.00 (C-F:1), SS=0.16/1.00 (D-J:1)

DOL LUMBER=1.00 NAIL=1.00 LS BEND=1.10
COMP=1.10 SHEAR=1.10 TENS=1.10

COMPANION LIVE LOAD FACTOR = 1.00

TRUSS PLATE MANUFACTURER IS NOT RESPONSIBLE FOR QUALITY CONTROL IN THE TRUSS MANUFACTURING PLANT

NAIL VALUES
PLATE GRIP(DRY) SHEAR SECTION
(PSI) (PLI) (PLI)
MAX MIN MAX MIN MAX MIN
MT20 650 371 1747 788 1987 1873

PLATE PLACEMENT TOL. = 0.250 inches

PLATE ROTATION TOL. = 5.0 Deg.

JSI GRIP = 0.49 (C) (INPUT = 0.90)
JSI METAL = 0.23 (C) (INPUT = 1.00)




Structural component only
DWG# T-2017142

JOB NAME 410143	TRUSS NAME J1	QUANTITY 36	PLY 1	JOB DESC. GREEN PARK HOMES	DRWG NO.
Tamarack Roof Truss, Burlington					

Version 8.330 S May 6 2020 Mitek Industries, Inc. Tue Aug 4 13:08:51 2020 Page 1
ID:W63xGm6okcO0SiyZ4EwBx6zA2m0-Ya4obtBZ5wekPptzPZ??pNMZa7YIUQ29cWviYPyrEHQ

Scale = 1:22.9



TOTAL WEIGHT = 36 X 17 = 605 lb

LUMBER

N. L. G. A. RULES	CHORDS	SIZE	LUMBER	DESCR.
E - B	2x4	DRY	No.2	SPF
A - C	2x4	DRY	No.2	SPF
E - D	2x4	DRY	No.2	SPF

DRY: SEASONED LUMBER.

PLATES (table is in inches)

JT	TYPE	PLATES	W	LEN	Y	X
B	TMV+p	MT20	3.0	4.0		
E	BMV1+p	MT20	3.0	4.0		

DIMENSIONS, SUPPORTS AND LOADINGS SPECIFIED BY FABRICATOR TO BE VERIFIED BY BUILDING DESIGNER

BEARINGS	FACTORED GROSS REACTION	MAXIMUM FACTORED GROSS REACTION	INPUT BRG IN-SX	REQD BRG IN-SX
JT	VERT	HORZ	UP/LIFT	
E	525	0	0	5-8
C	202	0	0	1-8
D	45	0	0	1-8

SEE MITEK STANDARD DETAIL B97791H FOR CONNECTION TO JOINT(S) C, D

UNFACTORED REACTIONS

JT	1ST LCASE	SNOW	LIVE	PERM. LIVE	WIND	DEAD	SOIL
E	369	257 / 0	0 / 0	0 / 0	0 / 0	111 / 0	0 / 0
C	139	113 / 0	0 / 0	0 / 0	0 / 0	26 / 0	0 / 0
D	36	0 / 0	0 / 0	0 / 0	0 / 0	36 / 0	0 / 0

BEARING MATERIAL TO BE SPF NO.2 OR BETTER AT JOINT(S) E

BRACING

TOP CHORD TO BE SHEATHED OR MAX. PURLIN SPACING = 6.25 FT.
MAX. UNBRACED BOTTOM CHORD LENGTH = 10.00 FT OR RIGID CEILING DIRECTLY APPLIED.

ALL PITCH BREAKS AND PERIMETER CORNER JOINTS MUST BE Laterally RESTRAINED.

LOADING

TOTAL LOAD CASES: (4)

CHORDS	MAX. FACTORED	FACTORED	WEBS	MAX. FACTORED
MEMB.	FORCE (LBS)	VERT. LOAD LC1	MAX. CS1 (LC)	MEMB. FORCE (LBS)
FR-TO		FROM	TO	LENGTH FR-TO
E-B	-461 / 0	0.0	0.0	0.13 (4)
A-B	0 / 28	-91.8	-91.8	0.12 (1)
B-C	-30 / 0	-91.8	-91.8	0.54 (1)
E-D	0 / 0	-18.5	-18.5	0.13 (4)

DESIGN CRITERIA

SPECIFIED LOADS:
TOP CH. LL = 25.6 PSF
DL = 6.0 PSF
BOT CH. LL = 0.0 PSF
DL = 7.4 PSF
TOTAL LOAD = 39.0 PSF

SPACING = 24.0 IN. C/C

THIS TRUSS IS DESIGNED FOR RESIDENTIAL OR SMALL BUILDING REQUIREMENTS OF PART 9, NBC 2015

THIS DESIGN COMPLIES WITH:
- PART 9 OF BCBC 2018, ABC 2019
- PART 9 OF OBC 2012 (2019 AMENDMENT)
- CSA 086-14
- TPIC 2014

DESIGN ASSUMPTIONS
- OVERHANG NOT TO BE ALTERED OR CUT OFF.

(55 % OF 31.3 P.S.F. G.S.L. PLUS 8.4 P.S.F. RAIN LOAD) EQUALS 25.6 P.S.F. SPECIFIED ROOF LIVE LOAD

ALLOWABLE DEFL.(LL) = L/360 (0.20")
CALCULATED VERT. DEFL.(LL) = L/999 (0.00")
ALLOWABLE DEFL.(TL) = L/360 (0.20")
CALCULATED VERT. DEFL.(TL) = L/999 (0.03")

CSI: TG=0.54/1.00 (B-C:1), BC=0.13/1.00 (D-E:4), WB=0.00/1.00 (n/a:0), SSI=0.24/1.00 (B-C:1)

DOL LUMBER=1.00 NAIL=1.00 LS BEND=1.10
COMP=1.10 SHEAR=1.10 TENS=1.10

COMPANION LIVE LOAD FACTOR = 1.00

AUTOSOLVE RIGHT HEEL ONLY

TRUSS PLATE MANUFACTURER IS NOT RESPONSIBLE FOR QUALITY CONTROL IN THE TRUSS MANUFACTURING PLANT.

NAIL VALUES

PLATE	GRIP(DRY)	SHEAR	SECTION
(PSI)	(PLI)	(PLI)	
MAX	MIN	MAX	MIN
MT20	650	371	1747

PLATE PLACEMENT TOL. = 0.250 inches

PLATE ROTATION TOL. = 5.0 Deg.

JSI GRIP= 0.18 (E) (INPUT = 0.90)
JSI METAL= 0.13 (B) (INPUT = 1.00)



Structural component only
DWG# T-2017139

Version 8.330 S May 6 2020 MiTek Industries, Inc. Tue Aug 4 13:52:58 2020 Page 1
ID:W63xGm6okcO0SYz4EwBx6zA2m0-YpXT8zDxjD89Tbkiz_kbZU_B8ysBaKmHqcJzUyrDe3




[M]

Structural component only
DWG# T-2017152

JOB NAME 410143	TRUSS NAME J3	QUANTITY 6	PLY 1	JOB DESC. GREEN PARK HOMES	DRWG NO.
Tamarack Roof Truss, Burlington					

Version 8.330 S May 6 2020 MiTek Industries, Inc. Tue Aug 4 13:08:52 2020 Page 1
ID:W63xGm6okcO0SiyZ4EwBx6zA2m0-0meAoDBBsEmb1zS9zGWEMaumOWSoDtHlrAf4ryrEHP



LUMBER			
N. L. G. A. RULES			
CHORDS	SIZE	LUMBER	DESCR.
A - C	2x4	DRY	No.2
B - D	2x4	DRY	No.2

DRY: SEASONED LUMBER.

PLATES (table is in inches)				
JT	TYPE	PLATES	W	LEN Y X
B	TMB1-I	MT20	3.0	4.0

DIMENSIONS, SUPPORTS AND LOADINGS SPECIFIED BY FABRICATOR TO BE VERIFIED BY BUILDING DESIGNER

FACTORED GROSS REACTION		MAXIMUM FACTORED GROSS REACTION		INPUT		REQD	
JT	VERT	HORZ	DOWN	HORZ	UPLIFT	IN-SX	IN-SX
C	215	0	215	0	0	1-8	1-8
B	420	0	420	0	0	5-8	5-8
D	81	0	81	0	0	5-8	5-8

SEE MITEK STANDARD DETAIL B97791H FOR CONNECTION TO JOINT(S) C

UNFACTORED REACTIONS

JT	1ST LCASE	MAX. MIN. COMPONENT REACTIONS					
C	149	116 / 0	0 / 0	0 / 0	0 / 0	33 / 0	0 / 0
B	294	206 / 0	0 / 0	0 / 0	0 / 0	88 / 0	0 / 0
D	60	21 / 0	0 / 0	0 / 0	0 / 0	39 / 0	0 / 0

BEARING MATERIAL TO BE SPF NO.2 OR BETTER AT JOINT(S) B, D

BRACING

TOP CHORD TO BE SHEATHED OR MAX. PURLIN SPACING = 6.25 FT.
MAX. UNBRACED BOTTOM CHORD LENGTH = 10.00 FT OR RIGID CEILING DIRECTLY APPLIED.

ALL PITCH BREAKS AND PERIMETER CORNER JOINTS MUST BE Laterally RESTRAINED.

LOADING

TOTAL LOAD CASES: (4)

CHORDS		FACTORED		WEBS		FACTORED	
MEMB.	FORCE (LBS)	VERT. LOAD (PLF)	LC1 MAX	MAX. UNBRAC LENGTH	MEMB.	FORCE (LBS)	MAX
FR-TO					FR-TO		
A-B	0 / 20	-91.8	-91.8 0.12 (1)	10.00	E-F	-310 / 11	0.00 (1)
B-F	-20 / 23	-91.8	-91.8 0.06 (4)	6.25			
F-C	-2 / 2	-91.8	-91.8 0.34 (1)	10.00			
B-E	0 / 0	-18.5	-18.5 0.24 (1)	10.00			
E-D	0 / 0	-18.5	-18.5 0.24 (1)	10.00			

TOTAL WEIGHT = 6 X 14 = 86 lb

DESIGN CRITERIA

SPECIFIED LOADS:
TOP CH. LL = 25.6 PSF
DL = 6.0 PSF
BOT CH. LL = 0.0 PSF
DL = 7.4 PSF
TOTAL LOAD = 39.0 PSF

SPACING = 24.0 IN. C/C

THIS TRUSS IS DESIGNED FOR RESIDENTIAL OR SMALL BUILDING REQUIREMENTS OF PART 9, NBC 2015

THIS DESIGN COMPLIES WITH:
- PART 9 OF BCBC 2018, ABC 2019
- PART 9 OF OBC 2012 (2019 AMENDMENT)
- CSA 086-14
- TPIC 2014

(55 % OF 31.3 P.S.F. G.S.L. PLUS 8.4 P.S.F. RAIN LOAD) EQUALS 25.6 P.S.F. SPECIFIED ROOF LIVE LOAD

ALLOWABLE DEFL.(LL) = L/360 (0.19")
CALCULATED VERT. DEFL.(LL) = L/999 (0.05")
ALLOWABLE DEFL.(TL) = L/360 (0.19")
CALCULATED VERT. DEFL.(TL) = L/639 (0.10")

CSI: TC=0.34/1.00 (C-F:1), BC=0.24/1.00 (D-E:1),
WB=0.00/1.00 (E-F:1), SSI=0.26/1.00 (B-E:1)

DOL LUMBER=1.00 NAIL=1.00 LS BEND=1.10
COMP=1.10 SHEAR=1.10 TENS=1.10

COMPANION LIVE LOAD FACTOR = 1.00

TRUSS PLATE MANUFACTURER IS NOT RESPONSIBLE FOR QUALITY CONTROL IN THE TRUSS MANUFACTURING PLANT.

NAIL VALUES
PLATE GRIP(DRY) SHEAR SECTION
(PSI) (PLI) (PLI)
MAX MIN MAX MIN MAX MIN
MT20 650 371 1747 788 1987 1873

PLATE PLACEMENT TOL. = 0.250 inches

PLATE ROTATION TOL. = 5.0 Deg.


JSI GRIP= 0.29 (B) (INPUT = 0.90)
JSI METAL= 0.07 (B) (INPUT = 1.00)



Structural component only
DWG# T-2017140

JOB NAME 410143	TRUSS NAME J20	QUANTITY 10	PLY 1	JOB DESC. GREEN PARK HOMES	DRWG NO.
Tamarack Roof Truss, Burlington					

Version 8.330 S May 6 2020 Mitek Industries, Inc. Tue Aug 4 13:08:53 2020 Page 1
ID:W63xGm6okcO0SiyZ4EwBx6zA2m0-UzCY?ZCpdXvS71LX_1TvoRmwCpyKXS3qOsdHyrEHO



Scale = 1:14.5

TOTAL WEIGHT = 10 X 15 = 148 lb

LUMBER

N. L. G. A. RULES	LUMBER	DESCR.
CHORDS	SIZE	SPF
A - C	2x4	DRY
B - D	2x4	DRY
LUMBER No.2		
No.2		
SPF		
DRY: SEASONED LUMBER.		

PLATES (table is in inches)

JT	TYPE	PLATES	W	LEN	Y	X
B	TMB1-I	MT20	3.0	4.0		

DIMENSIONS, SUPPORTS AND LOADINGS SPECIFIED BY FABRICATOR TO BE VERIFIED BY BUILDING DESIGNER

FACTORED		MAXIMUM FACTORED		INPUT		REQD	
GROSS REACTION		GROSS REACTION		BRG		BRG	
JT	VERT	HORZ	DOWN	HORZ	UPLIFT	IN-SX	IN-SX
C	222	0	222	0	0	1-8	1-8
B	429	0	429	0	0	5-8	5-8
D	83	0	83	0	0	5-8	5-8

SEE MITEK STANDARD DETAIL B97791H FOR CONNECTION TO JOINT(S) C

UNFACTORED REACTIONS

1ST LCASE		MAX./MIN. COMPONENT REACTIONS					
JT	COMBINED	SNOW	LIVE	PERM. LIVE	WIND	DEAD	SOIL
C	154	120 / 0	0 / 0	0 / 0	0 / 0	34 / 0	0 / 0
B	301	210 / 0	0 / 0	0 / 0	0 / 0	90 / 0	0 / 0
D	62	22 / 0	0 / 0	0 / 0	0 / 0	40 / 0	0 / 0

BEARING MATERIAL TO BE SPF NO.2 OR BETTER AT JOINT(S) C, B, D

BRACING

TOP CHORD TO BE SHEATHED OR MAX. PURLIN SPACING = 6.25 FT.
MAX. UNBRACED BOTTOM CHORD LENGTH = 10.00 FT OR RIGID CEILING DIRECTLY APPLIED.

ALL PITCH BREAKS AND PERIMETER CORNER JOINTS MUST BE LATERALLY RESTRAINED.

LOADING

TOTAL LOAD CASES: (4)

CHORDS		FACTORED		WEBS		FACTORED	
MEMB.	FORCE (LBS)	VERT. LOAD	LC1 MAX	MEMB.	FORCE (LBS)	MAX	LC1 (LBS)
FR-TO		FROM	TO	FR-TO			
A-B	0 / 20	-91.8	-91.8	0.12 (1)	10.00	E-F	-328 / 11
B-F	-21 / 26	-91.8	-91.8	0.06 (4)	6.25		
F-C	-3 / 2	-91.8	-91.8	0.37 (1)	10.00		
B-E	0 / 0	-18.5	-18.5	0.25 (1)	10.00		
E-D	0 / 0	-18.5	-18.5	0.26 (1)	10.00		

DESIGN CRITERIA

SPECIFIED LOADS:
TOP CH. LL = 25.6 PSF
DL = 6.0 PSF
BOT CH. LL = 0.0 PSF
DL = 7.4 PSF
TOTAL LOAD = 39.0 PSF

SPACING = 24.0 IN. C/C

THIS TRUSS IS DESIGNED FOR RESIDENTIAL OR SMALL BUILDING REQUIREMENTS OF PART 9, NBC 2015

THIS DESIGN COMPLIES WITH:
- PART 9 OF CBC 2018, ABC 2019
- PART 9 OF OBC 2012 (2019 AMENDMENT)
- CSA 086-14
- TPIC 2014

(55 % OF 31.3 P.S.F. G.S.L. PLUS 8.4 P.S.F. RAIN LOAD) EQUALS 25.6 P.S.F. SPECIFIED ROOF LIVE LOAD

ALLOWABLE DEFL.(LL) = L/360 (0.19")
CALCULATED VERT. DEFL.(LL) = L/999 (0.06")
ALLOWABLE DEFL.(TL) = L/360 (0.19")
CALCULATED VERT. DEFL.(TL) = L/585 (0.11")

CSI: TC=0.37/1.00 (C-F:1), BC=0.26/1.00 (D-E:1), WB=0.00/1.00 (E-F:1), SSI=0.27/1.00 (B-E:1)

DOL LUMBER=1.00 NAIL=1.00 LS BEND=1.10
COMP=1.10 SHEAR=1.10 TENS=1.10

COMPANION LIVE LOAD FACTOR = 1.00

TRUSS PLATE MANUFACTURER IS NOT RESPONSIBLE FOR QUALITY CONTROL IN THE TRUSS MANUFACTURING PLANT

NAIL VALUES
PLATE GRIP (DRY) SHEAR SECTION
(PSI) (PLI) (PLI)
MAX MIN MAX MIN MAX MIN
MT20 650 371 1747 788 1987 1873

PLATE PLACEMENT TOL. = 0.250 inches

PLATE ROTATION TOL. = 5.0 Deg.


JSI GRIP= 0.30 (B) (INPUT = 0.90)
JSI METAL= 0.07 (B) (INPUT = 1.00)



Structural component only
DWG# T-2017141

Version 8.330 S May 6 2020 MiTek Industries, Inc. Tue Aug 4 16:45:33 2020 Page 1
ID:pqvtrdsyU73tskbsg1clrEz7lfa-ryj4QiXG5nmvGxsr4DG0nEsZ3J6qtqxpMUmvnvrB6G

Scale = 1:20.5



TOTAL WEIGHT = $6 \times 13 = 76 \text{ lb}$

LUMBER

N. L. G. A. RULES			
CHORDS	SIZE		LUMBER
D - A	2x4	DRY	No.2
A - B	2x4	DRY	No.2
D - C	2x4	DRY	No.2

DRY: SEASONED LUMBER.

PLATES (table is in inches)

JT	TYPE	PLATES	W	LEN	Y	X
A	TMV+p	MT20	3.0	4.0		
D	BMV1+p	MT20	3.0	4.0		

DIMENSIONS, SUPPORTS AND LOADINGS SPECIFIED BY FABRICATOR TO BE VERIFIED BY BUILDING DESIGNER

BUILDING BEARINGS

JT	FACTORED GROSS REACTION		MAXIMUM FACTORED GROSS REACTION			INPUT BRG	REQRD BRG
	VERT	HORZ	DOWN	HORZ	UPLIFT	IN-SX	IN-SX
D	269	0	269	0	0	MECHANICAL	
B	204	0	204	0	0	1-8	1-8
C	64	0	64	0	0	1-8	1-8

A SUITABLE HANGER/MECHANICAL CONNECTION IS REQUIRED AT JOINT D. MINIMUM BEARING LENGTH AT JOINT D = 1-8.

SEE MITEK STANDARD DETAIL B97791H FOR CONNECTION TO JOINT(S) B, C

UNFACTORED REACTIONS

1ST LCASE COMBINED		MAX./MIN. COMPONENT REACTIONS					
JT		SNOW	LIVE	PERM.LIVE	WIND	DEAD	SOIL
D	190	125 / 0	0 / 0	0 / 0	0 / 0	65 / 0	0 / 0
B	141	112 / 0	0 / 0	0 / 0	0 / 0	30 / 0	0 / 0
C	49	13 / 0	0 / 0	0 / 0	0 / 0	36 / 0	0 / 0

BRACING

TOP CHORD TO BE SHEATHED OR MAX. PURLIN SPACING = 10.00 FT.
MAX. UNBRACED BOTTOM CHORD LENGTH = 10.00 FT OR RIGID CEILING DIRECTLY APPLIED.

ALL PITCH BREAKS AND PERIMETER CORNER JOINTS MUST BE Laterally RESTRAINED.

LOADING

TOTAL LOAD CASES: (4)

C H O R D S				W E B S			
MEMB.	MAX. FACTORED FORCE (LBS)	FACTORED VERT. LOAD (PLF)	LC1 MAX CSI (LC)	MAX. UNBRAC LENGTH	MEMB. FR-TO	MAX. FACTORED FORCE (LBS)	MAX CSI (LC)
FR-TO		FROM TO					
D- A	-243 / 0	0.0 0.0	0.11 (1)	7.81			
A- B	-9 / 0	-91.8 -91.8	0.30 (1)	10.00			
D- C	0 / 0	-18.5 -18.5	0.15 (1)	10.00			

DESIGN CRITERIA

SPECIFIED LOADS:

TOP	CH.	LL =	25.6	PSF
		DL =	6.0	PSF
BOT	CH.	LL =	0.0	PSF
		DL =	7.4	PSF
TOTAL LOAD		=	39.0	PSF

SPACING = 24.0 IN. C/C

THIS TRUSS IS DESIGNED FOR RESIDENTIAL OR
SMALL BUILDING REQUIREMENTS OF PART 9,
NBCC 2015

THIS DESIGN COMPLIES WITH:

- PART 9 OF CBC 2018 , ABC 2019
- PART 9 OF OBC 2012 (2019 AMENDMENT)
- CSA 086-14
- TPIC 2014

(55 % OF 31.3 P.S.F. G.S.L. PLUS 8.4 P.S.F. RAIN LOAD) EQUALS 25.6 P.S.F. SPECIFIED ROOF LIVE LOAD

ALLOWABLE DEFL.(LL)= L/360 (0.19")
CALCULATED VERT. DEFL.(LL) = L/ 999 (0.02")
ALLOWABLE DEFL.(TL)= L/360 (0.19")
CALCULATED VERT. DEFL.(TL) = L/ 999 (0.06")

CSI: TC=0.30/1.00 (A-B:1), BC=0.15/1.00 (C-D:1), WB=0.00/1.00 (n/a:0), SSI=0.17/1.00 (A-B:1)

DOL LUMBER=1.00 NAIL=1.00 LS BEND=1.10
COMP=1.10 SHEAR=1.10 TENS= 1.10

COMPANION LIVE LOAD FACTOR = 1.00

TRUSS PLATE MANUFACTURER IS NOT RESPONSIBLE FOR QUALITY CONTROL IN THE TRUSS MANUFACTURING PLANT.

NAIL VALUES

PLATE	GRIP(DRY) (PSI)		SHEAR (PLI)		SECTION (PLI)	
	MAX	MIN	MAX	MIN	MAX	MIN
MT20	650	371	1747	788	1987	1873

PLATE PLACEMENT TOL. = 0.250 inches

PLATE ROTATION TOL. = 5.0 Deg.

JSI GRIP= 0.10 (D) (INPUT = 0.90)
JSI METAL= 0.07 (A) (INPUT = 1.00)




Structural component only
DWG# T-2017164

JOB NAME	TRUSS NAME	QUANTITY	PLY	JOB DESC.	DRWG NO.
410149	J32	8	1	GREEN PARK HOMES	
Tamarack Roof Truss, Burlington					

Version 8.330 S May 6 2020 MiTek Industries, Inc. Tue Aug 4 13:58:19 2020 Page 1
ID:pqvtrdsyU73tskbsg1clrEz7lfa-eaQpVks5H7racUxnOHuF?6GH7XYlulo05GtokNyrDZ2

Scale = 1:10.8



LUMBER

N. L. G. A. RULES				
CHORDS	SIZE	DRY	LUMBER	DESCR.
E - B	2x4	DRY	No.2	SPF
A - C	2x4	DRY	No.2	SPF
E - D	2x4	DRY	No.2	SPF

DRY: SEASONED LUMBER.

PLATES (table is in inches)

JT	TYPE	PLATES	W	LEN	Y	X
B	TMV+p	MT20	3.0	4.0		
E	BMV1+p	MT20	3.0	4.0		

DIMENSIONS, SUPPORTS AND LOADINGS SPECIFIED BY FABRICATOR TO BE VERIFIED BY BUILDING DESIGNER

BEARINGS

	FACTORED		MAXIMUM FACTORED		INPUT	REQRD
	GROSS REACTION		GROSS REACTION		BRG	BRG
JT	VERT	HORZ	DOWN	HORZ	UPLIFT	IN-SX
E	269	0	269	0	0	5-8
C	-35	0	0	0	-69	1-8
D	-13	0	5	0	-17	1-8

SEE MITEK STANDARD DETAIL B97791H FOR CONNECTION TO JOINT(S) C, D

PROVIDE ANCHORAGE AT BEARING JOINT C FOR 150 LBS. FACTORED UPLIFT

PROVIDE ANCHORAGE AT BEARING JOINT D FOR 150 LBS. FACTORED UPLIFT

UNFACTORED REACTIONS

JT	1ST LCASE COMBINED	MAX. SNOW	MIN. LIVE	MAX. PERM. LIVE	WIND	DEAD	SOIL
E	186	146 / 0	0 / 0	0 / 0	0 / 0	41 / 0	0 / 0
C	-24	0 / -41	0 / 0	0 / 0	0 / 0	0 / -4	0 / 0
D	-8	0 / -13	0 / 0	0 / 0	0 / 0	3 / 0	0 / 0

BEARING MATERIAL TO BE SPF NO.2 OR BETTER AT JOINT(S) E

BRACING

TOP CHORD TO BE SHEATHED OR MAX. PURLIN SPACING = 6.25 FT.
MAX. UNBRACED BOTTOM CHORD LENGTH = 10.00 FT. OR RIGID CEILING DIRECTLY APPLIED.

ALL PITCH BREAKS AND PERIMETER CORNER JOINTS MUST BE Laterally RESTRAINED.

LOADING

TOTAL LOAD CASES: (5)

CHORDS	MAX. FACTORED MEMB. FORCE (LBS)	FACTORED VERT. LOAD (PLF)	LC1 MAX	CS1 (LC)	UNBRAC LENGTH	FR-TO	WEBS	MAX. FACTORED MEMB. FORCE (LBS)	CS1 (LC)
E-B	-240 / 0	0.0	0.0	0.03 (5)	7.81				
A-B	0 / 28	-91.8	-91.8	0.12 (1)	10.00				
B-C	-34 / 0	-91.8	-91.8	0.09 (1)	6.25				
E-D	0 / 0	-18.5	-18.5	0.03 (5)	10.00				

CANTILEVER ANALYSIS HAS BEEN CONSIDERED IN THIS DESIGN

TOTAL WEIGHT = 8 X 5 = 38 lb

(M)

DESIGN CRITERIA

SPECIFIED LOADS:

TOP CH.	LL	=	25.6	PSF
	DL	=	6.0	PSF
BOT CH.	LL	=	0.0	PSF
	DL	=	7.4	PSF
TOTAL LOAD		=	39.0	PSF

SPACING = 24.0 IN. C/C

THIS TRUSS IS DESIGNED FOR RESIDENTIAL OR SMALL BUILDING REQUIREMENTS OF PART 9, NBC 2015

THIS DESIGN COMPLIES WITH:

- PART 9 OF BCBC 2018, ABC 2019
- PART 9 OF OBC 2012 (2019 AMENDMENT)
- CSA 086-14
- TPIC 2014

DESIGN ASSUMPTIONS

- OVERHANG NOT TO BE ALTERED OR CUT OFF.

(55 % OF 31.3 P.S.F. G.S.L. PLUS 8.4 P.S.F. RAIN LOAD) EQUALS 25.6 P.S.F. SPECIFIED ROOF LIVE LOAD

ALLOWABLE DEFL.(LL) = L/360 (0.19")
CALCULATED VERT. DEFL.(LL) = L/999 (0.00")
ALLOWABLE DEFL.(TL) = L/360 (0.19")
CALCULATED VERT. DEFL.(TL) = L/999 (0.00")

CSI: TC=0.12/1.00 (A-B:1), BC=0.03/1.00 (D-E:5),
WB=0.00/1.00 (n/a:0), SSI=0.09/1.00 (A-B:1)

DOL LUMBER=1.00 NAIL=1.00 LS BEND=1.10
COMP=1.10 SHEAR=1.10 TENS=1.10

COMPANION LIVE LOAD FACTOR = 1.00

AUTOSOLVE RIGHT HEEL ONLY

TRUSS PLATE MANUFACTURER IS NOT RESPONSIBLE FOR QUALITY CONTROL IN THE TRUSS MANUFACTURING PLANT.

NAIL VALUES

PLATE	GRIP(DRY)	SHEAR	SECTION
	(PSI)	(PLI)	(PLI)
	MAX	MIN	MAX
MT20	650	371	1747
	788	1987	1873

PLATE PLACEMENT TOL. = 0.250 inches

PLATE ROTATION TOL. = 5.0 Deg.

JSI GRIP = 0.10 (E) (INPUT = 0.90)
JSI METAL = 0.07 (B) (INPUT = 1.00)




Structural component only
DWG# T-2017165

JOB NAME 410149	TRUSS NAME J33	QUANTITY 8	PLY 1	JOB DESC. GREEN PARK HOMES	DRWG NO.
Tamarack Roof Truss, Burlington					

Version 8.330 S May 6 2020 MiTek Industries, Inc. Tue Aug 4 13:58:20 2020 Page 1
ID:pqvtrdsyU73tskbsg1clrEz7lfa-6m_Cj46vu8IT64MarcMEFTp1zXu_dC2AKwcMGpyrDZ1

Scale = 1:23.3



LUMBER

N. L. G. A. RULES	CHORDS	SIZE	LUMBER	DESCR.
E - A	2x4	DRY	No.2	SPF
A - B	2x4	DRY	No.2	SPF
E - C	2x4	DRY	No.2	SPF
ALL WEBS	2x3	DRY	No.2	SPF
DRY: SEASONED LUMBER.				

PLATES (table is in inches)

JT	TYPE	PLATES	W	LEN	Y	X
A	TMVW-t	MT20	4.0	4.0	2.00	1.25
D	BMW-w	MT20	2.0	4.0		
E	BMV1-p	MT20	3.0	4.0		

DIMENSIONS, SUPPORTS AND LOADINGS SPECIFIED BY FABRICATOR TO BE VERIFIED BY BUILDING DESIGNER

JT	FACTORED GROSS REACTION		MAXIMUM FACTORED GROSS REACTION		INPUT BRG	REQD BRG
	VERT	HORZ	DOWN	HORZ		
E	186	0	186	0	0	0
B	155	0	155	0	1-8	1-8
C	31	0	35	0	1-8	1-8

A SUITABLE HANGER/MECHANICAL CONNECTION IS REQUIRED AT JOINT E. MINIMUM BEARING LENGTH AT JOINT E = 1-8.

SEE MITEK STANDARD DETAIL B97791H FOR CONNECTION TO JOINT(S) B, C

UNFACTORED REACTIONS

JT	1ST LCASE COMBINED	MAX./MIN. COMPONENT REACTIONS					
		SNOW	LIVE	PERM.LIVE	WIND	DEAD	SOIL
E	132	86 / 0	0 / 0	0 / 0	0 / 0	45 / 0	0 / 0
B	107	86 / 0	0 / 0	0 / 0	0 / 0	20 / 0	0 / 0
C	25	0 / 0	0 / 0	0 / 0	0 / 0	25 / 0	0 / 0

BRACING

TOP CHORD TO BE SHEATHED OR MAX. PURLIN SPACING = 10.00 FT.
MAX. UNBRACED BOTTOM CHORD LENGTH = 10.00 FT OR RIGID CEILING DIRECTLY APPLIED.

ALL PITCH BREAKS AND PERIMETER CORNER JOINTS MUST BE Laterally RESTRAINED.

LOADING

TOTAL LOAD CASES: (4)

MEMB.	CHORDS	MAX. FACTORED FORCE (LBS)	FACTORED				MEMB.	WEBS	MAX. FACTORED FORCE (LBS)	MAX. CSI (LC)
			VERT. LOAD	LC1	MAX	UNBRAC LENGTH				
FR-TO										
E-A		-155 / 0	0.0	0.0	0.02 (1)	7.81	A-D	0 / 0	0.00 (1)	
A-B		0 / 0	-91.8	-91.8	0.18 (1)	10.00				
E-D		0 / 0	-18.5	-18.5	0.06 (4)	10.00				
D-C		0 / 0	-18.5	-18.5	0.06 (4)	10.00				

TOTAL WEIGHT = 8 X 13 = 101 lb
(M)(F)

DESIGN CRITERIA

SPECIFIED LOADS:

TOP CH.	LL	=	25.6	PSF
	DL	=	6.0	PSF
BOT CH.	LL	=	0.0	PSF
	DL	=	7.4	PSF
TOTAL LOAD		=	39.0	PSF

SPACING = 24.0 IN. C/C

THIS TRUSS IS DESIGNED FOR RESIDENTIAL OR SMALL BUILDING REQUIREMENTS OF PART 9, NBC 2015

THIS DESIGN COMPLIES WITH:

- PART 9 OF CBC 2018, ABC 2019
- PART 9 OF CBC 2012 (2019 AMENDMENT)
- CSA 086-14
- TPIC 2014

(55 % OF 31.3 P.S.F. G.S.L. PLUS 8.4 P.S.F. RAIN LOAD) EQUALS 25.6 P.S.F. SPECIFIED ROOF LIVE LOAD

ALLOWABLE DEFL.(LL)= L/360 (0.19")
CALCULATED VERT. DEFL.(LL)= L/999 (0.00")
ALLOWABLE DEFL.(TL)= L/360 (0.19")
CALCULATED VERT. DEFL.(TL)= L/999 (0.01")

CSI: TC=0.18/1.00 (A-B:1), BC=0.06/1.00 (D-E:4), WB=0.00/1.00 (A-D:1), SSI=0.11/1.00 (A-B:1)

DOL LUMBER=1.00 NAIL=1.00 LS BEND=1.10
COMP=1.10 SHEAR=1.10 TENS=1.10

COMPANION LIVE LOAD FACTOR = 1.00

TRUSS PLATE MANUFACTURER IS NOT RESPONSIBLE FOR QUALITY CONTROL IN THE TRUSS MANUFACTURING PLANT.

NAIL VALUES

PLATE	GRIP(DRY)	SHEAR	SECTION
	(PS)	(PL)	(PL)
	MAX	MIN	MAX
MT20	650	371	1747

PLATE PLACEMENT TOL. = 0.250 inches

PLATE ROTATION TOL. = 5.0 Deg.

JSI GRIP= 0.09 (A) (INPUT = 0.90)
JSI METAL= 0.02 (A) (INPUT = 1.00)




Structural component only
DWG# T-2017166

JOB NAME 409989	TRUSS NAME C30	QUANTITY 4	PLY 1	JOB DESC. GREENPARK HOMES	DRWG NO.
Tamarack Roof Truss, Burlington				TRUSS DESC.	

Version 8.330 S May 6 2020 MiTek Industries, Inc. Wed Aug 5 10:40:50 2020 Page 1
ID: nmPe4yMblTuNMWU5OprM1EzA_nL-JzaA7JJVFeDixqYV3REU6ZS4WVg8qrgH4RSDmyqxMB

Scale = 1/17.9



LUMBER			
N. L. G. A. RULES	CHORDS	SIZE	LUMBER
E - B	2x4	DRY	No.2
A - C	2x4	DRY	No.2
E - D	2x4	DRY	No.2

DESCR. SPF

DRY: SEASONED LUMBER.

PLATES (table is in inches)					
JT	TYPE	PLATES	W	LEN	Y X
B	TMV+p	MT20	3.0	4.0	
E	BMV1+p	MT20	3.0	4.0	

DIMENSIONS, SUPPORTS AND LOADINGS SPECIFIED BY FABRICATOR TO BE VERIFIED BY BUILDING DESIGNER

JT	FACTORED GROSS REACTION		MAXIMUM FACTORED GROSS REACTION		INPUT BRG IN-SX	REQD BRG IN-SX
	VERT	HORZ	DOWN	HORZ		
E	405	0	405	0	5-8	5-8
C	130	0	130	0	1-8	1-8
D	45	0	50	0	1-8	1-8

TOTAL WEIGHT = 4 X 14 = 57 lb

SEE MITTEK STANDARD DETAIL B97791H FOR CONNECTION TO JOINT(S) C, D

UNFACTORED REACTIONS

JT	1ST LCASE COMBINED	MAX./MIN. COMPONENT REACTIONS					
		SNOW	LIVE	PERM. LIVE	WIND	DEAD	SOIL
E	286	190 / 0	0 / 0	0 / 0	0 / 0	96 / 0	0 / 0
C	90	73 / 0	0 / 0	0 / 0	0 / 0	17 / 0	0 / 0
D	36	0 / 0	0 / 0	0 / 0	0 / 0	36 / 0	0 / 0

BEARING MATERIAL TO BE SPF NO.2 OR BETTER AT JOINT(S) E, C

BRACING

TOP CHORD TO BE SHEATHED OR MAX. PURLIN SPACING = 6.25 FT.
MAX. UNBRACED BOTTOM CHORD LENGTH = 10.00 FT OR RIGID CEILING DIRECTLY APPLIED.
ALL PITCH BREAKS AND PERIMETER CORNER JOINTS MUST BE LATERALLY RESTRAINED.

LOADING

TOTAL LOAD CASES: (4)

MEMB.	CHORDS		VERT LOAD	FACTORED		MAX	MAX	MEMB.	WEBS		MAX	MAX
	MAX.	FACTORED		FORCE	VERT	LOAD	LC1	MAX	FORCE	MAX	FACTORED	MAX
	(LBS)	(LBS)		(LBS)	(PLF)	CSI (LC)	UNBRAC		(LBS)	CSI (LC)		
FR-TO												
E-B	-342	0	0.0	0.0	0.13	(4)	7.81					
A-B	0	28	-91.8	-91.8	0.12	(1)	10.00					
B-C	-19	0	-91.8	-91.8	0.22	(1)	6.25					
E-D	0	0	-18.5	-18.5	0.13	(4)	10.00					

DESIGN CRITERIA

SPECIFIED LOADS:
TOP CH. LL = 25.6 PSF
DL = 5.0 PSF
BOT CH. LL = 0.0 PSF
DL = 7.4 PSF
TOTAL LOAD = 39.0 PSF

SPACING = 24.0 IN. C/C

THIS TRUSS IS DESIGNED FOR RESIDENTIAL OR SMALL BUILDING REQUIREMENTS OF PART 9, NBC 2015

THIS DESIGN COMPLIES WITH:
PART 9 OF CBC 2018, ABC 2019
PART 9 OF CBC 2012 (2019 AMENDMENT)
CSA 086-14
TPIC 2014

DESIGN ASSUMPTIONS
OVERHANG NOT TO BE ALTERED OR CUT OFF.

(55 % OF 31.3 P.S.F. G.S.L. PLUS 8.4 P.S.F. RAIN LOAD) EQUALS 25.6 P.S.F. SPECIFIED ROOF LIVE LOAD

ALLOWABLE DEFL.(LL)= L/360 (0.20")
CALCULATED VERT. DEFL.(LL) = L/999 (0.00")
ALLOWABLE DEFL.(TL)= L/360 (0.20")
CALCULATED VERT. DEFL.(TL) = L/999 (0.03")

CSI: TC=0.22/1.00 (B-C:1), BC=0.13/1.00 (D-E:4), WB=0.00/1.00 (n/a:0), SSI=0.15/1.00 (B-C:1)

DOL LUMBER=1.00 NAIL=1.00 LS BEND=1 10
COMP=1.10 SHEAR=1 10 TENS=1 10

COMPANION LIVE LOAD FACTOR = 1.00

AUTOSOLVE RIGHT HEEL ONLY

TRUSS PLATE MANUFACTURER IS NOT RESPONSIBLE FOR QUALITY CONTROL IN THE TRUSS MANUFACTURING PLANT

NAIL VALUES

PLATE	GRIP(DRY)	SHEAR	SECTION
(PSI)	(PLI)	(PLI)	
MAX	MIN	MAX	MIN
MT20	650	371	1747 788 1987 1873

PLATE PLACEMENT TOL. = 0.250 inches


PLATE ROTATION TOL. = 5.0 Deg.

JSI GRIP= 0.14 (E) (INPUT = 0.90)
JSI METAL= 0.09 (B) (INPUT = 1.00)



Structural component only
DWG# T-2017359

JOB NAME	TRUSS NAME	QUANTITY	PLY	JOB DESC.	GREENPARK HOMES	DRWG NO.
409989	C31	4	1	TRUSS DESC.		
Tamarack Roof Truss, Burlington						



LUMBER		
N. L. G. A. RULES		
CHORDS	SIZE	LUMBER
E - B	2x4	DRY No.2
A - C	2x4	DRY No.2
E - D	2x4	DRY No.2

DRY: SEASONED LUMBER.

PLATES (table is in inches)				
JT	TYPE	PLATES	W	LEN Y X
B	TMV+p	MT20	3.0	4.0
E	BMV1+p	MT20	3.0	4.0

DIMENSIONS, SUPPORTS AND LOADINGS SPECIFIED BY FABRICATOR TO BE VERIFIED BY BUILDING DESIGNER

JT	FACTORED GROSS REACTION		MAXIMUM FACTORED GROSS REACTION		INPUT BRG IN-SX	REQRD BRG IN-SX
	VERT	HORZ	DOWN	HORZ		
E	284	0	284	0	5-8	5-8
C	63	0	63	0	1-8	1-8
D	44	0	52	0	1-8	1-8

SEE MITEK STANDARD DETAIL B97791H FOR CONNECTION TO JOINT(S) C, D

UNFACTORED REACTIONS

JT	1ST LCASE COMBINED		MAX./MIN. COMPONENT REACTIONS		WIND	DEAD	SOIL
	SNOW	LIVE	PERM. LIVE	WIND			
E	200	137 / 0	0 / 0	0 / 0	62 / 0	0 / 0	0 / 0
C	46	21 / 0	0 / 0	0 / 0	25 / 0	0 / 0	0 / 0
D	35	0 / 3	0 / 0	0 / 0	37 / 0	0 / 0	0 / 0

BEARING MATERIAL TO BE SPF NO.2 OR BETTER AT JOINT(S) E, C

BRACING

TOP CHORD TO BE SHEATHED OR MAX. PURLIN SPACING = 10.00 FT
MAX. UNBRACED BOTTOM CHORD LENGTH = 10.00 FT OR RIGID CEILING DIRECTLY APPLIED.

ALL PITCH BREAKS AND PERIMETER CORNER JOINTS MUST BE Laterally RESTRAINED.

LOADING

TOTAL LOAD CASES: (7)

MEMB.	CHORDS		FACTORED		WEBS		FACTORED	
	MAX. FORCE (LBS)	VERT. LOAD (PLF)	MAX. LC1	MAX. UNBRACED LENGTH FR-TO	MAX. FORCE (LBS)	MAX. UNBRACED LENGTH FR-TO	MAX. FORCE (LBS)	MAX. UNBRACED LENGTH FR-TO
FR-TO								
E-B	-227	0	0.0	0.0 0.11 (4)	7.81			
A-B	0	28	-91.8	-91.8 0.12 (1)	10.00			
B-C	-9	9	-91.8	-91.8 0.08 (4)	10.00			
E-F	0	0	-18.5	-18.5 0.14 (4)	10.00			
F-G	0	0	-18.5	-18.5 0.14 (4)	10.00			
G-D	0	0	-18.5	-18.5 0.14 (4)	10.00			

FACTORED CONCENTRATED LOADS (LBS)

JT	LOC.	LC1	MAX.	FACE	DIR.	TYPE	HEEL	CONN.
F	1-11-4	7	1	12	FRONT	VERT	---	C1
G	3-11-4	1	1	---	FRONT	VERT	---	C1

CONNECTION REQUIREMENTS

- 1) C1: A SUITABLE HANGER/MECHANICAL CONNECTION IS REQUIRED.

TOTAL WEIGHT = 4 X 12 = 46 lb

DESIGN CRITERIA

SPECIFIED LOADS:

TOP CH.	LL	=	25.6	PSF
	DL	=	6.0	PSF
BOT CH.	LL	=	0.0	PSF
	DL	=	7.4	PSF
TOTAL LOAD		=	39.0	PSF

SPACING = 24.0 IN. C/C

THIS TRUSS IS DESIGNED FOR RESIDENTIAL OR SMALL BUILDING REQUIREMENTS OF PART 9, NBC 2015

THIS DESIGN COMPLIES WITH:

- PART 9 OF BCBC 2018, ABC 2019
- PART 9 OF OBC 2012 (2019 AMENDMENT)
- CSA 086-14
- TPIC 2014

DESIGN ASSUMPTIONS

OVERHANG NOT TO BE ALTERED OR CUT OFF.

(55 % OF 31.3 P.S.F. G.S.L. PLUS 8.4 P.S.F. RAIN LOAD) EQUALS 25.6 P.S.F. SPECIFIED ROOF LIVE LOAD

ALLOWABLE DEFL.(LL)= L/360 (0.20")
CALCULATED VERT. DEFL.(LL) = L/999 (0.01")
ALLOWABLE DEFL.(TL)= L/360 (0.20")
CALCULATED VERT. DEFL.(TL) = L/999 (0.04")

CSI: TC=0.12/1.00 (A-B:1) , BC=0.14/1.00 (D-E:4) ,
WB=0.00/1.00 (n/a:0) , SS=0.09/1.00 (A-B:1)

DOL LUMBER=0.99 NAIL=0.99 LS BEND=1.10
COMP=1.10 SHEAR=1.10 TENS=1.10

COMPANION LIVE LOAD FACTOR = 1.00

AUTOSOLVE RIGHT HEEL ONLY

TRUSS PLATE MANUFACTURER IS NOT RESPONSIBLE FOR QUALITY CONTROL IN THE TRUSS MANUFACTURING PLANT

NAIL VALUES

PLATE	GRIP(DRY)	SHEAR (PSI)	SECTION (PLI)
MT20	650	371	1747
			788
			1987
			1873

PLATE PLACEMENT TOL. = 0.250 inches

PLATE ROTATION TOL. = 5.0 Deg.


JSI GRIP = 0.09 (E) (INPUT = 0.90)

JSI METAL = 0.06 (B) (INPUT = 1.00)



Structural component only
DWG# T-2017360

JOB NAME 409989	TRUSS NAME C32	QUANTITY 4	PLY 1	JOB DESC. GREENPARK HOMES	DRWG NO.
Tamarack Roof Truss, Burlington				TRUSS DESC.	



LUMBER

N. L. G. A. RULES	CHORDS	SIZE	LUMBER	DESCR.
E - B	2x4	DRY	No. 2	SPF
A - C	2x4	DRY	No. 2	SPF
E - D	2x4	DRY	No. 2	SPF

DRY: SEASONED LUMBER.

PLATES (table is in inches)

JT	TYPE	PLATES	W	LEN	Y	X
B	TMV+p	MT20	3.0	4.0		
E	BMV1+p	MT20	3.0	4.0		

DIMENSIONS, SUPPORTS AND LOADINGS SPECIFIED BY FABRICATOR TO BE VERIFIED BY BUILDING DESIGNER

BEARINGS

JT	FACTORED GROSS REACTION		MAXIMUM FACTORED GROSS REACTION		INPUT BRG IN-SX	REORD BRG IN-SX
	VERT	HORZ	DOWN	HORZ		
E	361	0	361	0	5-8	5-8
C	130	0	130	0	1-8	1-8
D	16	0	17	0	1-8	1-8

SEE MITEK STANDARD DETAIL B97791H FOR CONNECTION TO JOINT(S) C, D

UNFACTORED REACTIONS

JT	1ST CASE COMBINED	MAX./MIN. COMPONENT REACTIONS					
		SNOW	LIVE	PERM. LIVE	WIND	DEAD	SOIL
E	250	190 / 0	0 / 0	0 / 0	0 / 0	60 / 0	0 / 0
C	90	73 / 0	0 / 0	0 / 0	0 / 0	17 / 0	0 / 0
D	12	0 / 0	0 / 0	0 / 0	0 / 0	12 / 0	0 / 0

BEARING MATERIAL TO BE SPF NO.2 OR BETTER AT JOINT(S) E

BRACING
TOP CHORD TO BE SHEATHED OR MAX. PURLIN SPACING = 6.25 FT.
MAX. UNBRACED BOTTOM CHORD LENGTH = 10.00 FT OR RIGID CEILING DIRECTLY APPLIED.

ALL PITCH BREAKS AND PERIMETER CORNER JOINTS MUST BE Laterally RESTRAINED.

LOADING
TOTAL LOAD CASES: (5)

CHORDS					WEBS				
MEMB.	MAX. FORCE (LBS)	FACTORED VERT. LOAD (PLF)	LC1	MAX. CSI (LC)	MAX. UNBRACED LENGTH	MEMB.	MAX. FORCE (LBS)	FACTORED MAX. CSI (LC)	
FR-TO		FROM	TO			FR-TO			
E-B	-342 0	0.0	0.0	0.01 (4)	7.81				
A-B	0 / 28	-91.8	-91.8	0.13 (5)	10.00				
B-C	-19 0	-91.8	-91.8	0.22 (1)	6.25				
E-D	0 0	-18.5	-18.5	0.02 (4)	10.00				

CANTILEVER ANALYSIS HAS BEEN CONSIDERED IN THIS DESIGN

TOTAL WEIGHT = 4 X 10 = 38 lb

DESIGN CRITERIA

SPECIFIED LOADS:
TOP CH. LL = 25.6 PSF
DL = 6.0 PSF
BOT CH. LL = 0.0 PSF
DL = 7.4 PSF
TOTAL LOAD = 39.0 PSF

SPACING = 24.0 IN. C/C

THIS TRUSS IS DESIGNED FOR RESIDENTIAL OR SMALL BUILDING REQUIREMENTS OF PART 9, NBC 2015

THIS DESIGN COMPLIES WITH:
- PART 9 OF BCBC 2018, ABC 2019
- PART 9 OF OBC 2012 (2019 AMENDMENT)
- CSA 086-14
- TPIC 2014

DESIGN ASSUMPTIONS
OVERHANG NOT TO BE ALTERED OR CUT OFF

(55 % OF 31.3 P.S.F. G.S.L. PLUS 8.4 P.S.F. RAIN LOAD) EQUALS 25.6 P.S.F. SPECIFIED ROOF LIVE LOAD

ALLOWABLE DEFL.(LL)= L/360 (0.19")
CALCULATED VERT. DEFL.(LL) = L/999 (0.00")
ALLOWABLE DEFL.(TL)= L/360 (0.19")
CALCULATED VERT. DEFL.(TL) = L/999 (0.00")

CSI: TC=0.22/1.00 (B-C:1), BC=0.02/1.00 (D-E:4), WB=0.00/1.00 (n/a:0), SSI=0.15/1.00 (B-C:1)

DOL LUMBER=1.00 NAIL=1.00 LS BEND=1.10
COMP=1.10 SHEAR=1.10 TENS=1.10

COMPANION LIVE LOAD FACTOR = 1.00

AUTOSOLVE RIGHT HEEL ONLY

TRUSS PLATE MANUFACTURER IS NOT RESPONSIBLE FOR QUALITY CONTROL IN THE TRUSS MANUFACTURING PLANT

NAIL VALUES
PLATE GRIP(DRY) SHEAR SECTION
(PSI) (PLI) (PLI)
MAX MIN MAX MIN MAX MIN
MT20 650 371 1747 788 1987 1873

PLATE PLACEMENT TOL. = 0.250 inches

PLATE ROTATION TOL. = 5.0 Deg.

JSI GRIP= 0.14 (E) (INPUT = 0.90)
JSI METAL= 0.09 (B) (INPUT = 1.00)




Structural component only
DWG# T-2017361

Tamarack Roof Truss, Burlington

Version 8.330 S May 6 2020 MiTek Industries, Inc. Wed Aug 5 10:40:52 2020 Page 1
ID:nmPe4yMblTuNMWU5OprM1EzA_nL-FLiwY_LmnFTQB7htBsGyB_XSeJN4IIAZXlxKvavoxMc

Scale = 1:13.1



N. L. G. A. RULES			
CHORDS	SIZE		LUMBER
E - B	2x4	DRY	No.2
A - C	2x4	DRY	No.2
E - D	2x4	DRY	No.2

DRY: SEASONED LUMBER.

JT	TYPE	PLATES	W	LEN	Y	X
B	TMV+p	MT20	3.0	4.0		
E	BMV1+p	MT20	3.0	4.0		

BEARINGS

JT E C D	FACTORED GROSS REACTION		MAXIMUM FACTORED GROSS REACTION		INPUT BRG	REQRD BRG
	VERT	HORZ	DOWN	UPLIFT	IN-SX	IN-SX
	271	0	271	0	0	5-8
	45	0	45	0	-23	1-8
	8	0	17	0	-2	1-8

SEE MITEK STANDARD DETAIL B97791H FOR CONNECTION TO JOINT(S) C . D

PROVIDE ANCHORAGE AT BEARING JOINT C FOR 150 LBS FACTORED UPLIFT
PROVIDE ANCHORAGE AT BEARING JOINT D FOR 150 LBS FACTORED UPLIFT

1ST LCASE	MAX./MIN. COMPONENT REACTIONS
-----------	-------------------------------

ST	COMBINED	SNOW	LIVE	PERM.LIVE	WIND	DEAD	SOIL
E	188	141 / 0	0 / 0	0 / 0	0 / 0	47 / 0	0 / 0
C	31	24 / -18	0 / 0	0 / 0	0 / 0	7 / 0	0 / 0
D	7	0 / -8	0 / 0	0 / 0	0 / 0	12 / 0	0 / 0

BEARING MATERIAL TO BE SPF NO.2 OR BETTER AT JOINT(S) E, C

TOP CHORD TO BE SHEATHED OR MAX. PURLIN SPACING = 6.25 FT.

MAX. UNBRACED BOTTOM CHORD LENGTH = 10.00 FT OR RIGID CEILING DIRECTLY APPLIED

ALL PITCH BREAKS AND PERIMETER CORNER JOINTS MUST BE Laterally RESTRAINED

TOTAL LOAD CASES: (5)

C H O R D S					W E B S				
MEMB.	MAX. FACTORED FORCE (LBS)	FACTORED			MAX. UNBRAC	MEMB.	MAX. FACTORED FORCE (LBS)	MAX CSI (LC)	
		VERT. LOAD	LC1	MAX (LC)					
FR-TO		PROM	TO	CSI (LC)	LENGTH	FR-TO			
E-B	-244.0	0.0	0.0	0.04 (5)	7.81				
A-B	0.28	-91.8	-91.8	0.12 (1)	10.00				
B-C	-17.0	-91.8	-91.8	0.09 (1)	6.25				
E-D	0.0	-18.5	-18.5	0.04 (5)	10.00				

CANTILEVER ANALYSIS HAS BEEN CONSIDERED IN THIS DESIGN

SPECIFIED LOADS:				
TOP	CH.	LL =	25.6	PSF
		DL =	6.0	PSF
BOT	CH.	LL =	0.0	PSF
		DL =	7.4	PSF
TOTAL LOAD		=	39.0	PSF

SPACING = 24.0 IN. C/C

THIS TRUSS IS DESIGNED FOR RESIDENTIAL OR
SMALL BUILDING REQUIREMENTS OF PART 9,
NBCC 2015

THIS DESIGN COMPLIES WITH:

- PART 9 OF BCBC 2018 , ABC 2019
- PART 9 OF OBC 2012 (2019 AMENDMENT)
- CSA 086-14
- TPIC 2014

OVERHANG NOT TO BE ALTERED OR CUT OFF.

(55 % OF 31.3 P.S.F. G.S.L. PLUS 8.4 P.S.F. RAIN LOAD) EQUALS 25.6 P.S.F. SPECIFIED ROOF LIVE LOAD

ALLOWABLE DEFL.(LL)= L/360 (0.19")
CALCULATED VERT. DEFL.(LL) = L/ 999 (0.00")
ALLOWABLE DEFL.(TL)= L/360 (0.19")
CALCULATED VERT. DEFL.(TL) = L/ 999 (0.00")

CSI: TC=0.12/1.00 (A-B:1), BC=0.04/1.00 (D-E:5),
WB=0.00/1.00 (n/a:0), SSI=0.09/1.00 (A-B:1)

DOL LUMBER=1.00 NAIL=1.00 LS BEND=1.10
COMP=1.10 SHEAR=1.10 TENS= 1.10

COMPANION LIVE LOAD FACTOR = 1.00

AUTOSOLVE RIGHT HEEL ONLY

TRUSS PLATE MANUFACTURER IS NOT RESPONSIBLE FOR QUALITY CONTROL IN THE TRUSS MANUFACTURING PLANT

PLATE	GRIP(DRY)		SHEAR		SECTION	
	(PSI)		(PLI)		(PLI)	
	MAX	MIN	MAX	MIN	MAX	MIN
MT20	650	371	1747	788	1987	1873

PLATE PLACEMENT TOL. = 0.250 inches

PLATE ROTATION TOL. = 5.0 Deg.

JSI GRIP= 0.10 (E) (INPUT = 0.90)

JSI METAL= 0.07 (B) (INPUT = 1.00)




Structural component only
DWG# T-2017362

JOB NAME 410149	TRUSS NAME C34	QUANTITY 4	PLY 1	JOB DESC. GREEN PARK HOMES	DRWG NO.
Tamarack Roof Truss, Burlington					

Version 8.330 S May 6 2020 Mitek Industries, Inc. Tue Aug 4 13:58:17 2020 Page 1
ID:pqvtrdsyU73tskbsq1clrEz7lfa-iB134241bDKvFdd?9TCX1rBWakrTQsJjezOhfUyrDZ4

Scale = 1:17.8



TOTAL WEIGHT = 4 X 11 = 45 lb [M][F]

LUMBER				DESCR.
N. L. G. A. RULES	CHORDS	SIZE	LUMBER	
D - A	2x4	DRY	No.2	SPF
A - B	2x4	DRY	No.2	SPF
D - C	2x4	DRY	No.2	SPF

DRY: SEASONED LUMBER.

PLATES (table is in inches)					
JT	TYPE	PLATES	W	LEN	Y X
A	TMV+p	MT20	3.0	4.0	
D	BMV1+p	MT20	3.0	4.0	

DIMENSIONS, SUPPORTS AND LOADINGS SPECIFIED BY FABRICATOR TO BE VERIFIED BY BUILDING DESIGNER

JT	FACTORED GROSS REACTION		MAXIMUM FACTORED GROSS REACTION		INPUT BRG IN-SX		REQD BRG IN-SX	
	VERT	HORZ	DOWN	HORZ	UPLIFT	IN-SX	IN-SX	
D	221	0	221	0	0	5-8	5-8	
B	164	0	164	0	0	1-8	1-8	
C	53	0	53	0	0	1-8	1-8	

SEE MITEK STANDARD DETAIL B97791H FOR CONNECTION TO JOINT(S) B, C.

UNFACTORED REACTIONS

JT	1ST LCASE		MAX/MIN. COMPONENT REACTIONS		WIND	DEAD	SOIL
	COMBINED	SNOW	LIVE	PERM. LIVE			
D	157	99 / 0	0 / 0	0 / 0	0 / 0	58 / 0	0 / 0
B	114	88 / 0	0 / 0	0 / 0	0 / 0	26 / 0	0 / 0
C	41	7 / 0	0 / 0	0 / 0	0 / 0	34 / 0	0 / 0

BEARING MATERIAL TO BE SPF NO.2 OR BETTER AT JOINT(S) D, B

BRACING

TOP CHORD TO BE SHEATHED OR MAX. PURLIN SPACING = 10.00 FT.
MAX. UNBRACED BOTTOM CHORD LENGTH = 10.00 FT OR RIGID CEILING DIRECTLY APPLIED.

ALL PITCH BREAKS AND PERIMETER CORNER JOINTS MUST BE Laterally RESTRAINED.

LOADING

TOTAL LOAD CASES: (4)

FR-TO	CHORDS		FACTORED		W E B S		FACTORED	
	MEMB.	FORCE (LBS)	VERT. LOAD	LC1 MAX (PLF)	MEMB.	FORCE (LBS)	MAX. UNBRAC LENGTH	FR-TO
D-A		-183 / 0	0.0	0.0	0.04 (1)	7.81		
A-B		-4 / 2	-91.8	-91.8	0.19 (1)	10.00		
D-C		0 / 0	-18.5	-18.5	0.11 (4)	10.00		

DESIGN CRITERIA

SPECIFIED LOADS:

TOP CH.	LL =	25.6	PSF
	DL =	6.0	PSF
BOT CH.	LL =	0.0	PSF
	DL =	7.4	PSF
TOTAL LOAD	=	39.0	PSF

SPACING = 24.0 IN. C/C

THIS TRUSS IS DESIGNED FOR RESIDENTIAL OR SMALL BUILDING REQUIREMENTS OF PART 9, NBC 2015

THIS DESIGN COMPLIES WITH:
- PART 9 OF BCBC 2018, ABC 2019
- PART 9 OF OBC 2012 (2019 AMENDMENT)
- CSA 086-14
- TPC 2014

(55 % OF 31.3 P.S.F. G.S.L. PLUS 8.4 P.S.F. RAIN LOAD) EQUALS 25.6 P.S.F. SPECIFIED ROOF LIVE LOAD

ALLOWABLE DEFL.(LL) = $L/360$ (0.19")
CALCULATED VERT. DEFL.(LL) = $L/999$ (0.01")
ALLOWABLE DEFL.(TL) = $L/360$ (0.19")
CALCULATED VERT. DEFL.(TL) = $L/999$ (0.04")

CSI: TC=0.19/1.00 (A-B:1), BC=0.11/1.00 (C-D:4), WB=0.00/1.00 (n/a:0), SS=0.13/1.00 (A-B:1)

DOL LUMBER=1.00 NAIL=1.00 LS BEND=1.10
COMP=1.10 SHEAR=1.10 TENS=1.10

COMPANION LIVE LOAD FACTOR = 1.00

TRUSS PLATE MANUFACTURER IS NOT RESPONSIBLE FOR QUALITY CONTROL IN THE TRUSS MANUFACTURING PLANT.

NAIL VALUES

PLATE	GRIP (DRY)	SHEAR	SECTION
	(PSI)	(PLI)	(PLI)
	MAX	MIN	MAX MIN
MT20	650	371	1747 788 1987 1873

PLATE PLACEMENT TOL. = 0.250 inches

PLATE ROTATION TOL. = 5.0 Deg.

JSI GRIP= 0.07 (D) (INPUT = 0.90)
JSI METAL= 0.05 (A) (INPUT = 1.00)




Structural component only
DWG# T-2017162

JOB NAME	TRUSS NAME	QUANTITY	PLY	JOB DESC.	DRWG NO.
410149	C35	4	1	GREEN PARK HOMES	
Tamarack Roof Truss, Burlington					

Version 8.330 S May 6 2020 MiTek Industries, Inc. Tue Aug 4 13:58:18 2020 Page 1
ID:pqvtrdsyU73tskbsg1clrEz7lfa-ANsRIO5fMXSmsnCCjBjmZ2kin8Bz9JYtd7FBwyrDZ3

Scale = 1:13.1



TOTAL WEIGHT = 4 X 10 = 42 lb

LUMBER

N. L. G. A. RULES	CHORDS	SIZE	LUMBER	DESCR.
E - B	2x4	DRY	No.2	SPF
A - C	2x4	DRY	No.2	SPF
E - D	2x4	DRY	No.2	SPF

DRY: SEASONED LUMBER.

PLATES (table is in inches)

JT	TYPE	PLATES	W	LEN	Y	X
B	TMV+p	MT20	3.0	4.0		
E	BMV1+p	MT20	3.0	4.0		

DIMENSIONS, SUPPORTS AND LOADINGS SPECIFIED BY FABRICATOR TO BE VERIFIED BY BUILDING DESIGNER

BEARINGS

JT	VERT	HORZ	DOWN	HORZ	UPLIFT	IN-SX	REQD BRG
E	282	0	282	0	0	5-8	5-8
C	55	0	55	0	0	1-8	1-8
D	35	0	44	0	0	1-8	1-8

SEE MITEK STANDARD DETAIL B97791H FOR CONNECTION TO JOINT(S) C, D

UNFACTORED REACTIONS

JT	1ST LCASE	SNOW	LIVE	PERM.LIVE	WIND	DEAD	SOIL
E	198	137 / 0	0 / 0	0 / 0	0 / 0	61 / 0	0 / 0
C	39	21 / 0	0 / 0	0 / 0	0 / 0	18 / 0	0 / 0
D	29	0 / 4	0 / 0	0 / 0	0 / 0	31 / 0	0 / 0

BEARING MATERIAL TO BE SPF NO.2 OR BETTER AT JOINT(S) E, C

BRACING

TOP CHORD TO BE SHEATHED OR MAX. PURLIN SPACING = 6.25 FT.
MAX. UNBRACED BOTTOM CHORD LENGTH = 10.00 FT. OR RIGID CEILING DIRECTLY APPLIED.

ALL PITCH BREAKS AND PERIMETER CORNER JOINTS MUST BE Laterally RESTRAINED.

LOADING

TOTAL LOAD CASES: (7)

CHORDS				WEBS			
MEMB.	MAX. FACTORED FORCE (LBS)	FACTORED VERT. LOAD (PLF)	MAX. LC1 (LC)	MEMB.	MAX. FACTORED FORCE (LBS)	MAX. LC1 (LC)	UNBRAC LENGTH FR-TO
FR-TO		FROM	TO				
E-B	-235 / 0	0.0	0.0	0.07 (4)	7.81		
A-B	0 / 28	-91.8	-91.8	0.12 (1)	10.00		
B-C	-13 / 5	-91.8	-91.8	0.07 (5)	6.25		
E-F	0 / 0	-18.5	-18.5	0.10 (4)	10.00		
F-G	0 / 0	-18.5	-18.5	0.10 (4)	10.00		
G-D	0 / 0	-18.5	-18.5	0.10 (4)	10.00		

FACTORED CONCENTRATED LOADS (LBS)

JT	LOC.	LC1	MAX-	MAX+	FACE	DIR.	TYPE	HEEL	CONN.
F	1-11-4	7	1	12	BACK	VERT	TOTAL	---	C1
G	3-11-4	1	1	---	BACK	VERT	TOTAL	---	C1

CONNECTION REQUIREMENTS

1) C1: A SUITABLE HANGER/MECHANICAL CONNECTION IS REQUIRED.

DESIGN CRITERIA

SPECIFIED LOADS:

TOP CH.	LL	= 25.6	PSF
	DL	= 6.0	PSF
BOT CH.	LL	= 0.0	PSF
	DL	= 7.4	PSF
TOTAL LOAD		= 39.0	PSF

SPACING = 24.0 IN. C/C

THIS TRUSS IS DESIGNED FOR RESIDENTIAL OR SMALL BUILDING REQUIREMENTS OF PART 9, NBCC 2015

THIS DESIGN COMPLIES WITH:

- PART 9 OF BCBC 2018, ABC 2019
- PART 9 OF OBC 2012 (2019 AMENDMENT)
- CSA 086-14
- TPIC 2014

DESIGN ASSUMPTIONS

- OVERHANG NOT TO BE ALTERED OR CUT OFF.

(55 % OF 31.3 P.S.F. G.S.L. PLUS 8.4 P.S.F. RAIN LOAD) EQUALS 25.6 P.S.F. SPECIFIED ROOF LIVE LOAD

ALLOWABLE DEFL.(LL)= L/360 (0.19")
CALCULATED VERT. DEFL.(LL) = L/999 (0.00")
ALLOWABLE DEFL.(TL)= L/360 (0.19")
CALCULATED VERT. DEFL.(TL) = L/999 (0.02")

CSI: TC=0.12/1.00 (A-B:1), BC=0.10/1.00 (D-E:4),
WB=0.00/1.00 (n/a:0), SSI=0.09/1.00 (A-B:1)

DOL LUMBER=1.00 NAIL=1.00 LS BEND=1.10
COMP=1.10 SHEAR=1.10 TENS=1.10

COMPANION LIVE LOAD FACTOR = 1.00

AUTOSOLVE RIGHT HEEL ONLY

TRUSS PLATE MANUFACTURER IS NOT RESPONSIBLE FOR QUALITY CONTROL IN THE TRUSS MANUFACTURING PLANT

NAIL VALUES

PLATE GRIP(DRY)	SHEAR	SECTION
(PSI)	(PLI)	(PLI)
MAX MIN	MAX MIN	MAX MIN
MT20	650 371	1747 788 1987 1873

PLATE PLACEMENT TOL. = 0.250 inches

PLATE ROTATION TOL. = 5.0 Deg.

JSI GRIP= 0.09 (E) (INPUT = 0.90)

JSI METAL= 0.07 (B) (INPUT = 1.00)



Structural component only
DWG# T-2017163

LUL/LUS/LJS/HUS/HHUS/HGUS

Standard and Double-Shear Joist Hangers



This product is preferable to similar connectors because of
a) easier installation, b) higher capacities, c) lower installed
cost, or a combination of these features.

Most hangers in this series have double-shear nailing — an innovation that distributes the load through two points on each joist nail for greater strength. This allows for fewer nails, faster installation, and the use of all common nails for the same connection. (Do not bend or remove tabs)

Double-shear hangers range from the light capacity LUS hangers to the highest capacity HGUS hangers. For medium load truss applications, the HUS offers a lower cost alternative and easier installation than the HGUS hangers, while providing greater load capacity and bearing than the LUS.

Material: See table on pp. 258–259.


Finish: Galvanized. Some products available in stainless steel or ZMAX® coating; see Corrosion Information, pp. 20–24.

Installation:


- Use all specified fasteners; see General Notes.
- Nails must be driven at an angle through the joist or truss into the header to achieve the tabulated resistances (except LUL).
- Where 16d commons are specified, 10d commons may be used at 0.83 of the tabulated factored resistance.
- Not designed for welded or nailer applications.
- With single ply 2x carrying members, use 10d x 1½" nails into the header and 10d commons into the joist, and reduce the resistance to 0.64 of the table value where 16d nails are specified and 0.77 where 10d nails are specified.

Options:


- LUS, LJS, LUL and HUS hangers cannot be modified.
- Other sizes available; consult your Simpson Strong-Tie representative.
- See Hanger Options information on p. 126.




Double-Shear
Nailing
Top View




Double-Shear
Nailing
Side View;
Do not
bend tab




Dome Double-Shear
Nailing Side View
(available on
some models)
U.S. Patent 5,603,580




LUS28




LU26L




HUS210
(HUS26, HUS28,
and HHUS similar)



HGUS28-2




HHUS210-2



LJS26DS

**Typical HUS26
Installation
with Reduced
Heel Height**
(Truss Designer
to provide
fastener quantity
for connecting
multiple members
together)



LUL/LUS/LJS/HUS/HHUS/HGUS**HHUS/HGUS**

See Hanger Options information on pp. 125–127.


HHUS — Sloped and/or Skewed Seat

- HHUS hangers can be skewed to a maximum of 45° and/or sloped to a maximum of 45°
- For skew only, maximum factored down resistance is 0.85 of the table value
- For sloped only or sloped and skewed hangers, the maximum factored down resistance is 0.72 of the table value
- Uplift resistances for sloped/skewed conditions are 0.62 of the table value
- The joist must be bevel-cut to allow for double-shear nailing

HGUS — Skewed Seat

- HGUS hangers can be skewed only to a maximum of 45°. Factored resistances are:

HGUS Seat Width	Joist	Down Resistance	Uplift
W < 2"	Bevel or square cut	0.62 of table value	0.46 of table value
2" < W < 6"	Bevel cut	0.67 of table value	0.41 of table value
2" < W < 6"	Square cut	0.46 of table value	0.41 of table value
W > 6"	Bevel cut	0.75 of table value	0.41 of table value

**Top View HHUS Hanger
Skewed Right**

(joist must be bevel cut)
All joist nails installed on the
outside angle (non-acute side).

Standard and Double-Shear Joist Hangers (cont.)

These products are available with additional corrosion protection. For more information, see p. 24.

These products are approved for installation with the Strong-Drive[®] SD Connector screw. See pp. 32–34 for more information.

Model No.	Ga.	Dimensions (in.)				Fasteners		Factored Resistance				
		W	H	B	d _e ³	Header	Joist	D.Fir-L		S-P-F		
								Uplift	Normal	Uplift	Normal	
								(K _D = 1.15)	(K _D = 1.00)	(K _D = 1.15)	(K _D = 1.00)	
								lb.	lb.	lb.	lb.	
								kN	kN	kN	kN	
Single 2x Sizes												
■	LUS24	18	1⅝	3⅝	1¾	2½	(4) 10d	(2) 10d	710	1625	645	1155
	LU24L	22	1⅝	3	1⅝	2⅞	(4) 10d	(2) 10d x 1½"	316	723	287	514
■	LU26L	22	1⅝	5	1⅝	4⅝	(6) 10d	(4) 10d x 1½"	360	1020	320	725
	LU26L	22	1⅝	5	1⅝	4⅝	(6) 10d	(4) 10d x 1½"	160	454	142	322
SS	LUS26	18	1⅝	4¾	1¾	3¾	(4) 10d	(4) 10d	720	1605	645	1140
	LUS26	18	1⅝	4¾	1¾	3¾	(4) 10d	(4) 10d	320	714	287	507
■	HUS26	16	1⅝	5⅝	3	3⅞	(14) 16d	(6) 16d	1420	2170	1290	1630
	HUS26	16	1⅝	5⅝	3	3⅞	(14) 16d	(6) 16d	632	965	574	725
■	LJS26DS	18	1⅝	5	3½	4⅝	(16) 16d	(6) 16d	2705	4940	2065	3875
	LJS26DS	18	1⅝	5	3½	4⅝	(16) 16d	(6) 16d	1130	2197	920	1724
■	HGUS26	12	1⅝	5⅝	5	4⅝	(20) 16d	(8) 16d	2055	4265	1460	4115
	HGUS26	12	1⅝	5⅝	5	4⅝	(20) 16d	(8) 16d	914	1897	649	1831
■	LU28L	20	1⅝	6⅝	1⅝	5⅝	(8) 10d	(6) 10d x 1½"	2685	6625	2685	5700
	LU28L	20	1⅝	6⅝	1⅝	5⅝	(8) 10d	(6) 10d x 1½"	1196	2951	1196	2535
SS	LUS28	18	1⅝	6⅝	1¾	3¾	(6) 10d	(4) 10d	1140	2185	1020	1550
	LUS28	18	1⅝	6⅝	1¾	3¾	(6) 10d	(4) 10d	507	972	454	689
■	HUS28	16	1⅝	7⅝	3	6⅞	(22) 16d	(8) 16d	632	1121	574	796
	HUS28	16	1⅝	7⅝	3	6⅞	(22) 16d	(8) 16d	3605	5365	2675	4345
■	HGUS28	12	1⅝	7⅝	5	6⅝	(36) 16d	(12) 16d	1604	2386	1190	1933
	HGUS28	12	1⅝	7⅝	5	6⅝	(36) 16d	(12) 16d	3310	7675	3310	6900
■	LU210L	20	1⅝	8	1⅝	7⅝	(10) 10d	(6) 10d x 1½"	1474	3419	1474	3073
	LU210L	20	1⅝	8	1⅝	7⅝	(10) 10d	(6) 10d x 1½"	1140	2495	1020	1770
SS	LUS210	18	1⅝	7⅞	1¾	3¾	(8) 10d	(4) 10d	507	1110	454	787
	LUS210	18	1⅝	7⅞	1¾	3¾	(8) 10d	(4) 10d	1420	2785	1290	2210
	LUS210	18	1⅝	7⅞	1¾	3¾	(8) 10d	(4) 10d	632	1239	574	983


1. Factored uplift resistances have been increased 15% for wind or earthquake loading; no further increase is allowed.
2. Designer must ensure that hanger is compatible with truss when reduced heel height is used.
3. d_e is the distance from the bearing seat to the top joist nail.
4. Resistances shown require a minimum 2-ply girder truss. For fastening to single-ply truss request technical bulletin T-C-N10TRSSCN and/or see installation notes.
5. Nails: 16d = 0.162" dia. x 3 1/2" long. See pp. 27–28 for other nail sizes and information.

Face-Mount Hangers

These products are available with additional corrosion protection. For more information, see p. 24.

These products are approved for installation with the Strong-Drive® SD Connector screw. See pp. 32-34 for more information.

Model No.	Ga.	Dimensions (in.)				Fasteners		Factored Resistance			
		W	H	B	d _e ³	Header	Joist	D-Fir-L		S-P-F	
								Uplift	Normal	Uplift	Normal
								(K _D = 1.15) lb.	(K _D = 1.00) lb.	(K _D = 1.15) lb.	(K _D = 1.00) lb.
								kN	kN	kN	kN
Double 2x Sizes											
■ LUS24-2	18	3 ¹ / ₁₆	3 ¹ / ₁₆	2	1 ¹ / ₂	(4) 16d	(2) 16d	835	2020	590	1435
SS LUS26-2	18	3 ¹ / ₁₆	4 ¹ / ₁₆	2	4	(4) 16d	(4) 16d	3.71	8.99	2.62	6.38
■ HHUS26-2	14	3 ¹ / ₁₆	5 ¹ / ₁₆	3	3 ¹ / ₁₆	(14) 16d	(6) 16d	1720	2595	1545	1920
■ HHUS26-2	14	3 ¹ / ₁₆	5 ¹ / ₁₆	3	3 ¹ / ₁₆	(14) 16d	(6) 16d	7.65	11.54	6.87	8.54
■ HHUS26-2	14	3 ¹ / ₁₆	5 ¹ / ₁₆	3	3 ¹ / ₁₆	(14) 16d	(6) 16d	2850	7335	2065	5205
■ HHUS26-2	14	3 ¹ / ₁₆	5 ¹ / ₁₆	3	3 ¹ / ₁₆	(14) 16d	(6) 16d	12.68	32.63	9.20	23.15
SS HGUS26-2	12	3 ¹ / ₁₆	5 ¹ / ₁₆	4	4 ¹ / ₁₆	(20) 16d	(8) 16d	4385	8950	3110	6355
SS LUS28-2	18	3 ¹ / ₁₆	7	2	4	(6) 16d	(4) 16d	19.51	39.81	13.83	28.27
■ HHUS28-2	14	3 ¹ / ₁₆	7 ¹ / ₁₆	3	6 ¹ / ₁₆	(22) 16d	(8) 16d	1720	3325	1545	2575
■ HHUS28-2	14	3 ¹ / ₁₆	7 ¹ / ₁₆	3	6 ¹ / ₁₆	(22) 16d	(8) 16d	7.65	14.79	6.87	11.45
■ HHUS28-2	14	3 ¹ / ₁₆	7 ¹ / ₁₆	3	6 ¹ / ₁₆	(22) 16d	(8) 16d	3765	8940	2675	6345
■ HHUS28-2	14	3 ¹ / ₁₆	7 ¹ / ₁₆	3	6 ¹ / ₁₆	(22) 16d	(8) 16d	16.75	39.77	11.90	28.22
■ HHUS28-2	14	3 ¹ / ₁₆	7 ¹ / ₁₆	3	6 ¹ / ₁₆	(22) 16d	(8) 16d	6070	12980	4310	9215
SS LUS210-2	18	3 ¹ / ₁₆	9	2	6	(8) 16d	(6) 16d	27.00	57.74	19.17	40.99
■ HHUS210-2	14	3 ¹ / ₁₆	9 ¹ / ₁₆	3	8	(30) 16d	(10) 16d	2580	4500	2320	3195
■ HHUS210-2	14	3 ¹ / ₁₆	9 ¹ / ₁₆	3	8	(30) 16d	(10) 16d	11.48	20.02	10.32	14.21
■ HHUS210-2	14	3 ¹ / ₁₆	9 ¹ / ₁₆	3	8	(30) 16d	(10) 16d	4670	9660	4235	7000
■ HHUS210-2	14	3 ¹ / ₁₆	9 ¹ / ₁₆	3	8	(30) 16d	(10) 16d	20.77	42.97	18.84	31.14
■ HHUS210-2	14	3 ¹ / ₁₆	9 ¹ / ₁₆	3	8	(30) 16d	(10) 16d	6840	14015	4855	10270
■ HHUS210-2	14	3 ¹ / ₁₆	9 ¹ / ₁₆	3	8	(30) 16d	(10) 16d	30.43	62.34	21.60	45.69
Triple 2x Sizes											
■ HHUS26-3	12	4 ¹ / ₁₆	5 ¹ / ₁₆	4	4 ¹ / ₁₆	(20) 16d	(8) 16d	4385	8950	3110	6355
■ HHUS26-3	12	4 ¹ / ₁₆	5 ¹ / ₁₆	4	4 ¹ / ₁₆	(20) 16d	(8) 16d	19.51	39.81	13.83	28.27
■ HHUS26-3	12	4 ¹ / ₁₆	5 ¹ / ₁₆	4	4 ¹ / ₁₆	(20) 16d	(8) 16d	6070	12980	4310	9215
■ HHUS26-3	12	4 ¹ / ₁₆	5 ¹ / ₁₆	4	4 ¹ / ₁₆	(20) 16d	(8) 16d	27.00	57.74	19.17	40.99
■ HHUS210-3	14	4 ¹ / ₁₆	9	3	7 ¹ / ₁₆	(30) 16d	(10) 16d	4670	9670	4235	6865
■ HHUS210-3	14	4 ¹ / ₁₆	9	3	7 ¹ / ₁₆	(30) 16d	(10) 16d	20.77	43.02	18.84	30.54
■ HHUS210-3	14	4 ¹ / ₁₆	9	3	7 ¹ / ₁₆	(30) 16d	(10) 16d	6840	14645	4855	10400
■ HHUS210-3	14	4 ¹ / ₁₆	9	3	7 ¹ / ₁₆	(30) 16d	(10) 16d	30.43	65.14	21.60	46.26
Quadruple 2x Sizes											
■ HHUS26-4	12	6 ¹ / ₁₆	5 ¹ / ₁₆	4	4 ¹ / ₁₆	(20) 16d	(8) 16d	4385	8950	3110	6355
■ HHUS26-4	12	6 ¹ / ₁₆	5 ¹ / ₁₆	4	4 ¹ / ₁₆	(20) 16d	(8) 16d	19.51	39.81	13.83	28.27
■ HHUS26-4	12	6 ¹ / ₁₆	5 ¹ / ₁₆	4	4 ¹ / ₁₆	(20) 16d	(8) 16d	6070	12980	4310	9215
■ HHUS26-4	12	6 ¹ / ₁₆	5 ¹ / ₁₆	4	4 ¹ / ₁₆	(20) 16d	(8) 16d	27.00	57.74	19.17	40.99
■ HHUS210-4	14	6 ¹ / ₁₆	8 ¹ / ₁₆	3	7 ¹ / ₁₆	(30) 16d	(10) 16d	4670	10155	4235	7210
■ HHUS210-4	14	6 ¹ / ₁₆	8 ¹ / ₁₆	3	7 ¹ / ₁₆	(30) 16d	(10) 16d	20.77	45.17	18.84	32.07
■ HHUS210-4	14	6 ¹ / ₁₆	8 ¹ / ₁₆	3	7 ¹ / ₁₆	(30) 16d	(10) 16d	6840	14645	4855	10400
■ HHUS210-4	14	6 ¹ / ₁₆	8 ¹ / ₁₆	3	7 ¹ / ₁₆	(30) 16d	(10) 16d	30.43	65.14	21.60	46.26
■ HHUS212-4	12	6 ¹ / ₁₆	10 ¹ / ₁₆	4	10 ¹ / ₁₆	(56) 16d	(20) 16d	7640	14995	5425	10645
■ HHUS212-4	12	6 ¹ / ₁₆	10 ¹ / ₁₆	4	10 ¹ / ₁₆	(56) 16d	(20) 16d	33.98	66.70	24.13	47.35
■ HHUS214-4	12	6 ¹ / ₁₆	12 ¹ / ₁₆	4	11 ¹ / ₁₆	(66) 16d	(22) 16d	10130	16400	7195	11645
■ HHUS214-4	12	6 ¹ / ₁₆	12 ¹ / ₁₆	4	11 ¹ / ₁₆	(66) 16d	(22) 16d	45.06	72.95	32.00	51.80
4x Sizes											
■ LUS46	18	3 ¹ / ₁₆	4 ¹ / ₁₆	2	3 ¹ / ₁₆	(4) 16d	(4) 16d	1720	2595	1545	1920
■ HHUS46	14	3 ¹ / ₁₆	5 ¹ / ₁₆	3	3 ¹ / ₁₆	(14) 16d	(6) 16d	7.65	11.54	6.87	8.54
■ HHUS46	14	3 ¹ / ₁₆	5 ¹ / ₁₆	3	3 ¹ / ₁₆	(14) 16d	(6) 16d	2540	7335	2065	5205
■ HHUS46	14	3 ¹ / ₁₆	5 ¹ / ₁₆	3	3 ¹ / ₁₆	(14) 16d	(6) 16d	11.30	32.63	9.20	23.15
■ HHUS46	12	3 ¹ / ₁₆	5 ¹ / ₁₆	4	4 ¹ / ₁₆	(20) 16d	(8) 16d	4385	8950	3110	6355
■ HHUS46	12	3 ¹ / ₁₆	5 ¹ / ₁₆	4	4 ¹ / ₁₆	(20) 16d	(8) 16d	19.51	39.81	13.83	28.27
■ LUS48	18	3 ¹ / ₁₆	6 ¹ / ₁₆	2	3 ¹ / ₁₆	(6) 16d	(4) 16d	1720	3325	1545	2575
■ HHUS48	14	3 ¹ / ₁₆	7 ¹ / ₁₆	3	6 ¹ / ₁₆	(22) 16d	(8) 16d	7.65	14.79	6.87	11.45
■ HHUS48	14	3 ¹ / ₁₆	7 ¹ / ₁₆	3	6 ¹ / ₁₆	(22) 16d	(8) 16d	3765	8940	2675	6345
■ HHUS48	14	3 ¹ / ₁₆	7 ¹ / ₁₆	3	6 ¹ / ₁₆	(22) 16d	(8) 16d	16.75	39.77	11.90	28.22
■ HHUS48	12	3 ¹ / ₁₆	7 ¹ / ₁₆	4	6 ¹ / ₁₆	(36) 16d	(12) 16d	6070	12980	4310	9215
■ HHUS48	12	3 ¹ / ₁₆	7 ¹ / ₁₆	4	6 ¹ / ₁₆	(36) 16d	(12) 16d	27.00	57.74	19.17	40.99
■ LUS410	18	3 ¹ / ₁₆	8 ¹ / ₁₆	2	5 ¹ / ₁₆	(8) 16d	(6) 16d	2580	4500	2320	3195
■ HHUS410	12	3 ¹ / ₁₆	9	4	8 ¹ / ₁₆	(46) 16d	(16) 16d	11.48	20.02	10.32	14.21
■ HHUS410	12	3 ¹ / ₁₆	9	4	8 ¹ / ₁₆	(46) 16d	(16) 16d	6840	14015	4855	10270
■ HHUS410	12	3 ¹ / ₁₆	9	4	8 ¹ / ₁₆	(46) 16d	(16) 16d	30.43	62.34	21.60	45.69
■ HHUS412	12	3 ¹ / ₁₆	10 ¹ / ₁₆	4	10 ¹ / ₁₆	(56) 16d	(20) 16d	7640	14995	5425	10645
■ HHUS412	12	3 ¹ / ₁₆	10 ¹ / ₁₆	4	10 ¹ / ₁₆	(56) 16d	(20) 16d	33.98	66.70	24.13	47.35
■ HHUS414	12	3 ¹ / ₁₆	12 ¹ / ₁₆	4	11 ¹ / ₁₆	(66) 16d	(22) 16d	10130	16400	7195	11645
■ HHUS414	12	3 ¹ / ₁₆	12 ¹ / ₁₆	4	11 ¹ / ₁₆	(66) 16d	(22) 16d	45.06	72.95	32.00	51.80



Plated Truss Connectors

See footnotes
on p. 258.

TC – Truss Connectors

SIMPSON
Strong-Tie

The TC truss connector is an ideal connector for scissor trusses and can allow horizontal movement up to 1¼". The TC also attaches plated trusses to top plates or sill plates to resist uplift forces. Typically used on one or both ends of truss as determined by the building designer.

Material: 16 gauge

Finish: G90 galvanized


Design: Factored resistances are in accordance with CSA 086-14

Installation:


- Use all specified fasteners.
- Nails: 10d = 0.148" dia. x 3" long common wire, 10d x 1½" = 0.148" dia. x 1½" long.
- Drive 10d nails into the truss at the inside end of the slotted holes (inside end is towards the centre of the truss) and clinch on the back side. Do not seat these nails into the truss—allow room under the nail head for movement of the truss with respect to the wall.

Optional TC Installation:


- Bend one flange up 90°. Drive specified nails into the top and face of the top plates or install Titen® screws into the top and face of masonry wall. See optional load tables and installation details.




TC24
U.S. Patent 4,932,173




TC26
(TC28 Similar)



Typical TC24 Installation



Optional TC26 Installation for Grouted Concrete Block using a Wood Nailer (8", 10", 12" Wall Installation Similar)



Optional TC26 Installation for Grouted Concrete Block using Titen Screws

Model No.	Fasteners		Factored Resistance	
	Truss	Wall Plates	D.Fir-L	S-P-F
			Uplift (K ₀ =1.15)	Uplift (K ₀ =1.15)
TC24	(4) 10d	(4) 10d	605	430
TC26	(5) 10d	(6) 10d	1015	720
TC28	(5) 10d	(6) 10d	1015	720

Optional TC Installation Table

Model No.	Fasteners		Factored Resistance	
	Truss	Wall Plates	D.Fir-L	S-P-F
			Uplift (K ₀ =1.15)	Uplift (K ₀ =1.15)
TC26	(5) 10d	(6) 10d x 1½"	810	660
	(5) 10d	(6) 10d	930	660

1. Factored resistances have been increased 15% for earthquake or wind loading; no further increase allowed; reduce where other loads govern.
2. Grout strength is 15 MPa minimum.
3. Optional TC26 installation with 10d nails requires minimum 3" top plate thickness.
4. TC26 fastened to grouted concrete block with (6) – ¾" x 2¼" Titen screws has a factored uplift resistance of 275 lb.



LIMIT
STATES
DESIGN

This technical bulletin is effective until June 30, 2019, and reflects information available as of March 11, 2017. This information is updated periodically and should not be relied upon after June 30, 2019. Contact Simpson Strong-Tie for current information and limited warranty of see strongtie.com.

© 2017 Simpson Strong-Tie Company Inc.

T-SPECT17 3/17 exp. 6/19

(800) 999-5099
strongtie.com

H/TSP

SIMPSON
Strong-Tie

Seismic and Hurricane Ties (cont.)

These products are available with additional corrosion protection. For more information, see p. 24.

These products are approved for installation with the Strong-Drive® SD Connector screw. See pp. 32–34 for more information.

Model No.	Ga.	Fasteners			Factored Resistance ($K_D = 1.15$)					
					D.Fir-L			S-P-F		
		To Rafters/ Truss	To Plates	To Studs	Uplift	Lateral		Uplift	Lateral	
						F ₁	F ₂		F ₁	F ₂
					lb.	lb.	lb.	lb.	lb.	lb.
					kN	kN	kN	kN	kN	kN
H1	18	(6) 8d x 1½"	(4) 8d	—	740	685	300	680	485	215
					3.29	3.05	1.33	3.02	2.16	0.96
SS H2A	18	(5) 8d x 1½"	(2) 8d x 1½"	(5) 8d x 1½"	830	220	75	590	155	55
					3.69	0.98	0.33	2.62	0.69	0.24
SS H2.5A	18	(5) 8d	(5) 8d	—	805	160	160	755	160	160
					3.58	0.71	0.71	3.36	0.71	0.71
H2.5T	18	(5) 8d	(5) 8d	—	835	175	210	740	160	210
					3.71	0.78	0.93	3.29	0.71	0.93
SS H3	18	(4) 8d	(4) 8d	—	740	180	265	615	125	190
					3.29	0.80	1.18	2.74	0.56	0.85
H6	16	—	(8) 8d	(8) 8d	1585	1085	—	1125	770	—
					7.05	4.83	—	5.00	3.43	—
H7Z	16	(4) 8d	(2) 8d	(8) 8d	1390	670	—	990	475	—
					6.18	2.98	—	4.40	2.11	—
SS H8 ³	18	(5) 10d x 1½"	(5) 10d x 1½"	—	1120	—	—	1025	—	—
					4.98	—	—	4.56	—	—
SS H10A ⁹	18	(9) 10d x 1½"	(9) 10d x 1½"	—	1735	795	410	1505	565	290
					7.72	3.54	1.82	6.69	2.51	1.29
H10AR	18	(9) 10d x 1½"	(9) 10d x 1½"	—	1485	690	430	1220	570	305
					6.61	3.07	1.91	5.43	2.54	1.36
H10A-2	18	(9) 10d x 1½"	(9) 10d x 1½"	—	1835	1275	430	1645	880	305
					8.16	5.67	1.91	7.32	3.91	1.36
H10S ^{7,8}	18	(8) 8d x 1½"	(8) 8d x 1½"	(8) 8d	1465	795	315	1040	565	225
					6.52	3.54	1.40	4.63	2.51	1.00
H11Z	18	(6) 16d x 2½"	(6) 16d x 2½"	—	1095	920	545	780	655	390
					4.87	4.09	2.42	3.47	2.91	1.73
H14	18	1 (12) 8d x 1½"	(13) 8d	—	2390	855	320	1805	610	230
					10.63	3.80	1.42	8.03	2.71	1.02
		2 (12) 8d x 1½"	(15) 8d	—	2390	855	320	1805	610	230
					10.63	3.80	1.42	8.03	2.71	1.02
TSP	16	(9) 10d x 1½"	(6) 10d x 1½"	—	1295	440	—	920	310	—
					5.76	1.96	—	4.09	1.38	—
		(9) 10d x 1½"	(6) 10d	—	1560	440	—	1105	310	—
					6.94	1.96	—	4.92	1.38	—

- Factored resistances have been increased 15% for short term loading; no further increase is allowed.
- Factored resistances are for one anchor. A minimum rafter thickness of 2½" must be used when framing anchors are installed on the same side of the plate (exception: H2.5A).
- H8 factored uplift resistances for stud-to-bottom plate installations are 595 lb. (2.65 kN) for D.Fir-L and 390 lb. (1.74 kN) for S-P-F.
- When cross-grain bending or cross-grain tension cannot be avoided, mechanical reinforcement to resist such forces should be considered.
- Hurricane ties are shown installed on the outside of the wall for clarity. Installation on the inside of the wall is acceptable. For a continuous load path, connections at the top and bottom of the wall must be on the same side of the wall (see technical bulletin T-HTIECONPATH).
- Factored resistances in the F₁ direction are not intended to replace diaphragm boundary members or prevent cross grain bending of the truss or rafter members. Additional shear transfer elements shall be considered where there may be effects of cross grain bending or tension.

- H10S can have the stud offset a maximum of 1" from the rafter (centre to centre) for a reduced uplift of 1435 lb. (6.38 kN) D.Fir-L and 1015 lb. (4.51 kN) S-P-F.
- H10S nails to plates are optional for uplift but required for lateral loads.
- H10A may be field-bent up to a slope of 6/12. Multiply the tabulated uplift value x 0.75. Full tabulated lateral resistances apply.
- The factored resistances of stainless-steel connectors match carbon-steel connectors when installed with Simpson Strong-Tie® stainless-steel, SCNR ring-shank nails. For more information, refer to engineering letter L-F-SSNAILS at strongtie.com.
- D.Fir-L/S-P-F factored uplift resistances for the H2.5A fastened to a 2x4 truss bottom chord and double top plates using (5) 8d x 1½" nails into the top plates and (3) 8d x 1½" nails into the lowest three flange holes into the truss bottom chord is 495 lb. (2.20 kN).
- Nails:** 16d x 2½" = 0.162" dia. x 2½" long, 10d = 0.148" dia. x 3" long, 10d x 1½" = 0.148" dia. x 1½" long, 8d = 0.131" dia. x 2½" long, 8d x 1½" = 0.131" dia. x 1½" long. See pp. 27–28 for other nail sizes and information.



BEARING ANCHORAGE BY TOE-NAILS FOR LATERAL CAPACITY

B97791H1

NAIL TYPE	LENGTH (IN)	DIAMETER (IN)	NAIL LATERAL CAPACITY (LB)	
			S-P-F	D. FIR
COMMON WIRE	3.00	0.144	132	147
	3.25	0.144	132	147
	3.50	0.160	159	177
COMMON SPIRAL	3.00	0.122	97	108
	3.25	0.122	97	108
	3.50	0.152	145	162

NOTES:

1. Rafter and ceiling members may be anchored to top and bottom chords of girder truss by toe-nailing rafter and ceiling members to girder chords provided the reaction does not exceed the lateral capacities in the table. Hangers (specified by others) are required for reactions higher than the maximum toe-nail capacity. Reactions are based on factored loads.
2. Toe nail capacities shown in the table are for **one** toe-nail. For additional toe-nails multiply values in table by the number of toe-nails used. Toe-nail capacities take into account toe-nailing factor J_A in CSA O86-14, section 12.9.4.1.
3. For 9- 3/4 gauge 3.25" common wire gun nails (diameter = 0.120") use 3" common spiral nail values.
4. Maximum number of toe-nails allowed depends on the lumber size & species to be toe-nailed to supporting member and nail diameter, as shown in tables below.
5. Nail values in table are based on the following relative lumber densities: $G = 0.42$ (SPF), $G = 0.49$ (D. Fir).
6. Toe-nails shall be driven at approximately 1/3 the nail length from the edge of the joist/truss chord and driven at an angle of 30° to the grain of the member (See next page for nailing on bearing plate).
7. For loads due to **wind** the nail lateral capacity in this table may be multiplied by 1.15 (K_D factor).
8. Lumber must be dry (< 19% moisture content) at the time of nail installation.
9. Nail values in this table comply with CSA O86-14, section 12.9.4
10. This design is not valid after March 31, 2021.



TOE-NAIL INSTALLATION

Nail type	Common wire	Common spiral	Common wire	Common spiral
Nail dia. (in)	0.160	0.152	0.144	0.122
	(3.5" nail)		(3" and 3.25" nail)	
LUMBER SIZE	MAXIMUM NUMBER OF TOE-NAILS			
2X4 SPF	2	2	3	3
2X4 D. Fir	2	2	2	2
2X6 SPF	4	4	4	5
2X6 D. Fir	3	3	3	4

MiTek® MiTek Canada Inc
100 Industrial Rd.
Bradford, Ontario L3Z 3G7

December 2, 2019



BEARING ANCHORAGE BY TOE-NAILS FOR WIND LOADING

B97791H2



NAIL TYPE	LENGTH (IN)	DIAMETER (IN)	NAIL WITHDRAWAL CAPACITY (LB)	
			S-P-F	D. FIR
COMMON WIRE	3.00	0.144	30	42
	3.25	0.144	32	45
	3.50	0.160	38	52
COMMON SPIRAL	3.00	0.122	26	36
	3.25	0.122	28	40
	3.50	0.152	36	50

Note: If using truss with D. Fir lumber and S-P-F bearing plate, use values in table for S-P-F.



NOTES:

1. Truss chord, rafter, or ceiling members may be anchored to bearing plate by toe-nails, provided that the actual factored uplift force due to **wind** or **earthquake** load does not exceed the withdrawal capacities in the table. Hangers (specified by others) are required for uplift forces that are higher than the maximum toe-nail withdrawal capacity.
2. Toe nail capacities shown in the table are for **one** toe-nail. For additional toe-nails multiply values in table by the number of toe-nails used. Toe-nail capacities take into account toe-nailing factor J_A in CSA O86-14, section 12.9.5.2.
3. For 9- 3/4 gauge 3.25" common wire gun nails (diameter = 0.120") use 3" common spiral nail values.
4. Maximum number of toe-nails allowed depends on the lumber size & species to be toe-nailed to supporting member and nail diameter, as shown in table above.
5. Nail values in table are based on the following relative lumber densities: G = 0.42(SPF), G = 0.49(D. Fir).
6. Toe-nails shall be driven at approximately 1/3 the nail length from the edge of the joist/truss chord and driven at an angle of 30° to the grain of the member (See drawing on detail B37579H1).
7. Lumber must be dry (< 19% moisture content) at the time of nail installation.
8. Nail values in this table comply with CSA O86-14, section 12.9.5
9. This design is not valid after March 31, 2021.

Toe-nailing on 2x6 Bearing Plate



Toe-nailing on 2x4 Bearing Plate



MiTek®

MiTek Canada Inc
100 Industrial Rd.
Bradford, Ontario L3Z 3G7


PEO
Certificate No. 10889485




December 2, 2019

Symbols

PLATE LOCATION AND ORIENTATION



Center plate on joint unless x, y offsets are indicated. Dimensions are in ft-in-sixteenths or mm. Apply plates to both sides of truss and fully embed teeth.



For 4 x 2 orientation, locate plates 0-1/8" from outside edge of truss.



This symbol indicates the required direction of slots in connector plates.

*Plate location details available in MiTek software or upon request.

PLATE SIZE

4 x 4

The first dimension is the plate width measured perpendicular to slots. Second dimension is the length parallel to slots.

LATERAL BRACING LOCATION



Indicated by symbol shown and/or by text in the bracing section of the output. Use T, I or Eliminator bracing if indicated.

BEARING




Indicates location where bearings (supports) occur. Icons vary but reaction section indicates joint number where bearings occur.


Industry Standards:

- TPIC: Truss Design Procedures and Specifications for Light Metal Plate Connected Wood Trusses
DSB-89: Design Standard for Bracing.
BCSI: Building Component Safety Information, Guide to Good Practice for Handling, Installing & Bracing of Metal Plate Connected Wood Trusses.

Numbering System



dimensions shown in ft-in-sixteenths or mm (Drawings not to scale)



JOINTS ARE GENERALLY NUMBERED/LETTERED CLOCKWISE AROUND THE TRUSS STARTING AT THE JOINT FARTHEST TO THE LEFT.

CHORDS AND WEBS ARE IDENTIFIED BY END JOINT NUMBERS/LETTERS.

PRODUCT CODE APPROVALS

CCMC Reports:

11996-L, 10319-L, 13270-L, 12691-R

© 2007 MiTek® All Rights Reserved

MiTek
POWER TO PERFORM.™

MiTek Engineering Reference Sheet: MII-7473C rev. 10-08



General Safety Notes

Failure to Follow Could Cause Property Damage or Personal Injury


1. Additional stability bracing for truss system, e.g. diagonal or X-bracing, is always required. See BCSI.
2. Truss bracing must be designed by an engineer. For wide truss spacing, individual lateral braces themselves may require bracing, or alternative T, I, or Eliminator bracing should be considered.
3. Never exceed the design loading shown and never stack materials on inadequately braced trusses.
4. Provide copies of this truss design to the building designer, erection supervisor, property owner and all other interested parties.
5. Cut members to bear tightly against each other.
6. Place plates on each face of truss at each joint and embed fully. Knots and wane at joint locations are regulated by TPIC.
7. Design assumes trusses will be suitably protected from the environment in accord with TPIC.
8. Unless otherwise noted, moisture content of lumber shall not exceed 19% at time of fabrication.
9. Unless expressly noted, this design is not applicable for use with fire retardant, preservative treated, or green lumber.
10. Camber is a non-structural consideration and is the responsibility of truss fabricator. General practice is to camber for dead load deflection.
11. Plate type, size, orientation and location dimensions indicated are minimum plating requirements.
12. Lumber used shall be of the species and size, and in all respects, equal to or better than that specified.
13. Top chords must be sheathed or purlins provided at spacing indicated on design.
14. Bottom chords require lateral bracing at 10 ft. spacing, or less, if no ceiling is installed, unless otherwise noted.
15. Connections not shown are the responsibility of others.
16. Do not cut or alter truss member or plate without prior approval of an engineer.
17. Install and load vertically unless indicated otherwise.
18. Use of green or treated lumber may pose unacceptable environmental, health or performance risks. Consult with project engineer before use.
19. Review all portions of this design (front, back, words and pictures) before use. Reviewing pictures alone is not sufficient.
20. Design assumes manufacture in accordance with TPIC Quality Criteria.

Overview:

Where piggybacks are connected overtop of base trusses, 2x4 purlins must be first added to the flat portion of the base truss at a spacing no more than 24" o/c. These purlins not only provide support for the piggyback trusses above, but are required to laterally support the top chord of the base truss which will not have the sheathing directly connected to the flat portion of the base truss. This ensures the top chord, most often in compression, will not buckle laterally.

Further, the purlins in the plane of the flat portion require diagonal bracing to prevent lateral displacement of the purlins themselves where under certain conditions, the trusses may in fact all buckle in the same direction if this additional bracing is not added in the plane of the purlins.

Detail:




NOTE: THE SLOPED PORTION OF THE TOP CHORD OF THE BASE TRUSS AND PIGGYBACK TRUSS IN THIS SKETCH IS ASSUMED TO BE SHEATHED IN ACCORDANCE WITH THE OBC.

SKETCH FROM BCSI-CANADA 2013

Disclaimer:

OWTFA Tech Notes are intended to provide guidance to the design community both within the membership as well as to third party designers who might benefit from the information. The details have been developed by the OWTFA technical committee and although there may be professional engineers involved in development, the information contained in the tech-note are not intended to be used without having a professional engineer review the information for a specific application. The OWTFA takes no responsibility with respect to the information provided but has developed this tech-note to offer guidance where it is not currently readily available.



Alves Engineering Services Inc.

5208 Easton road
Burlington, Ontario L7L 6N6
(289) 259 5455

RESPONSABILITIES

- 1-Alves Engineering Services Inc. is responsible for the design of trusses as individual components
- 2-It is the responsibility of others to ascertain that the design loads utilized on this drawing meet or exceed the actual dead load imposed by the structure and the live load imposed by the local building code or the authorities having jurisdictions.
- 3- All dimensions are to be verified by owner, contractor, architect or other authority before manufacture.
- 4- Alves Engineering Services Inc. bears no responsibility for the erection of the trusses. Persons erecting trusses are cautioned to seek professional advice regarding temporary and permanent bracing system. Bracing shown on Alves Engineering Services Inc. drawings is specified for the truss as a single component and forms an integral part of the truss design, but is not meant to represent the only required bracing for that truss when trusses are installed in a series of trusses forming a roof truss system.
- 5- It is the manufactures responsibility to ensure that the trusses are manufactured in conformance with Alves Engineering Services Inc. specifications outlined below.

SPECIFICATIONS

- 1-Truss components sealed by Alves Engineering Services Inc. conform to the relevant sections of the current Building Code of Ontario and Canada (part 4 or part 9) or the current Canadian code for Farm Buildings in accordance with the application specified on the sealed truss component drawing. All truss component design procedures must conform to the current design standard issued by the truss plate institute of Canada (TPIC). All lumber and nailing stresses to conform to the current CSA wood design standard identified on the current Building Code and TPIC.
- 2- Lumber is to be the sizes and grade specified on the truss drawing.
- 3- Moist content of lumber is not to exceed 19% in service unless otherwise specified.
- 4- Plates shall be applied to both faces of the each truss joint and shall be positioned as shown on the truss drawings
- 5- Lumber used on manufacture of trusses is not to be treated with chemicals unless otherwise specified on the truss drawings.
- 6- The top chord is assumed to be continuously laterally braced by the roof sheathing or purlins at intervals specified on the truss drawing but not exceeding 24" c/c for (part 9) and not exceeding 48" for (part 4 or farm design)
- 7- When rigid ceiling is not attached directly to the bottom chord, lateral bracing is required and it should not exceed more than 3m or 10' intervals.
- 8-Refer to Mitek sheet MII7473C REV.10-08 attached for information on symbols, numbering system and General Safety notes.

T-1900219

Feb 09, 2018