

20.130122.000.00.CM

Issue Date: 02/19/21

LAMPONE INVESTMENT INC

ALL CONSTRUCTION SHALL COMPLY WITH THE
ONTARIO BUILDING CODE.

CITY OF MARKHAM


ROOF TRUSS SHOP DRAWINGS

MODEL NAME : PEYTON 3

ELEV 1A, 1B, 2, 3A & 3B

1B: 410171

1A : 410170



ASPHALT SHINGLES
FINISHED OVERHANG: 12"
2x6 EXTERIOR WALLS
2x6 FASCIA BOARD
HEEL: R.T.M.C.


All conventional framing to conform with Part 9 of O.B.C. 2012 (2019 amendment). Roof rafters that cross over or meet trusses to be min. 2x4 SPF #2 @ 24" o/c with a vertical post to the truss at each cross point. Vertical posts longer than 6' to have lateral bracing so that the distance between the post end points and lateral bracing does not exceed 6'.

DESIGN CONFORMS WITH OBC 2012
(2019 amendment) OCCUPANCY:
RESIDENTIAL | PART: 9
Ss = 31.35 psf | Sr = 8.4 psf

DESIGN LOADS:
TCSL = 25.6 psf
TCDL = 6.0 psf
BCLL = 0.0 psf
BCDL = 7.4 psf

HARDWARE:
LUS24 - (O)
LUS26-2 - (VV)

 DENOTES:
CONVENTIONAL
FRAMING




Job Track: **51453**
Layout ID: **410169**
Plan Log: **202893**

Builder / Location: **GREEN PARK HOMES / MARKHAM**
Project: **LAMPONE INVESTMENTS INC**
Date: 2020-08-19 Designer: **JG**

Model / Elevation: **THE PEYTON 3 / 1A AND 1B**
Milek ver 8.3.3.247
THESE DRAWINGS CONSTITUTE THE PROPERTY OF TAMARACK ROOF TRUSSES INC. SHALL NOT BE REPRODUCED, PUBLISHED, OR REDISTRIBUTED IN ANY MANNER OR UTILIZED FOR ANY PURPOSE OTHER THAN THE MANUFACTURE OF TRUSSES BY TAMARACK ROOF TRUSSES INC AND WILL BE RETRACTED BY TAMARACK ROOF TRUSSES INC IF UTILIZED FOR ANY OTHER PURPOSE.

EL.2-RIGHT: 410173

EL.2-LEFT : 410173



ASPHALT SHINGLES
FINISHED OVERHANG: 12"
2x6 EXTERIOR WALLS
2x6 FASCIA BOARD
HEEL: R.T.M.C.


All conventional framing to conform with Part 9 of O.B.C. 2012 (2019 amendment). Roof rafters that cross over or meet trusses to be min. 2x4 SPF #2 @ 24" o/c with a vertical post to the truss at each cross point. Vertical posts longer than 6' to have lateral bracing so that the distance between the post end points and lateral bracing does not exceed 6'.

DESIGN CONFORMS WITH OBC 2012
(2019 amendment) OCCUPANCY:
RESIDENTIAL | PART: 9
Ss = 31.35 psf | Sr = 8.4 psf

DESIGN LOADS:
TCSL = 25.6 psf
TCDL = 6.0 psf
BCLL = 0.0 psf
BCDL = 7.4 psf

HARDWARE:
LUS24 - (O)
LJS26DS - (V)
HGUS26-2 - (XX)
LUS26-2 - (VV)


 DENOTES:
CONVENTIONAL
FRAMING



Job Track: **51453**
Layout ID: **410172**
Plan Log: **202893**

Builder / Location: **GREEN PARK HOMES / MARKHAM**
Project: **LAMPONE INVESTMENTS INC**
Date: 2020-08-19 Designer: **JG**

Model / Elevation: **THE PEYTON 3 / EL.2 - LEFT PAIR WITH RIGHT**
Mitek ver 8.3.3.247
THESE DRAWINGS CONSTITUTE THE PROPERTY OF TAMARACK ROOF TRUSSES INC., SHALL NOT BE REPRODUCED, PUBLISHED, OR REDISTRIBUTED IN ANY MANNER OR UTILIZED FOR ANY PURPOSE OTHER THAN THE MANUFACTURE OF TRUSSES BY TAMARACK ROOF TRUSSES INC AND WILL BE RETRACTED BY TAMARACK ROOF TRUSSES INC IF UTILIZED FOR ANY OTHER PURPOSE.



ASPHALT SHINGLES
FINISHED OVERHANG: 12"
2x6 EXTERIOR WALLS
2x6 FASCIA BOARD
HEEL: R.T.M.C.

All conventional framing to conform with Part 9 of O.B.C. 2012 (2019 amendment). Roof rafters that cross over or meet trusses to be min. 2x4 SPF #2 @ 24" o/c with a vertical post to the truss at each cross point. Vertical posts longer than 6' to have lateral bracing so that the distance between the post end points and lateral bracing does not exceed 6'.

DESIGN CONFORMS WITH OBC 2012
(2019 amendment) OCCUPANCY:
RESIDENTIAL | PART: 9
Ss = 31.35 psf | Sr = 8.4 psf

DESIGN LOADS:
TCSL = 25.6 psf
TCDL = 6.0 psf
BCLL = 0.0 psf
BCDL = 7.4 psf

HARDWARE:
LUS24 - (O)
LJS26DS - (V)
HGUS26-2 - (XX)
LUS26-2 - (VV)

 DENOTES:
CONVENTIONAL
FRAMING




Job Track: **51453**
Layout ID: **410174**
Plan Log: **202893**

Builder / Location: **GREEN PARK HOMES / MARKHAM**
Project: **LAMPONE INVESTMENTS INC**
Date: 2020-08-19 Designer: **JG**

Model / Elevation: **THE PEYTON 3 / 3A AND 3B** Mitek ver 8.3.3.247
THESE DRAWINGS CONSTITUTE THE PROPERTY OF TAMARACK ROOF TRUSSES INC. SHALL NOT BE REPRODUCED, PUBLISHED, OR REDISTRIBUTED IN ANY MANNER OR UTILIZED FOR ANY PURPOSE OTHER THAN THE MANUFACTURE OF TRUSSES BY TAMARACK ROOF TRUSSES INC AND WILL BE RETRACTED BY TAMARACK ROOF TRUSSES INC IF UTILIZED FOR ANY OTHER PURPOSE.

DELIVERY SHIPLIST




Lumber Yard: TAMARACK LUMBER
 Builder: GREEN PARK HOMES
 Project: LAMPONE INVESTMENTS INC
 Location: MARKHAM
 Model: THE PEYTON 3
 Lot #:
 Elevation: 1A

Job Track: 51453
 PlanLog: 202893
 Layout ID: 410170
 Ref #
 Page: 1 of 2
 Date: 08-11-2020
 Designer:
 Sales Rep: Mario DiCano

Roof Trusses

PROFILE	QTY PLY	MARK TYPE	PITCH	SPAN	HEIGHT	LUMBER	OVERHANG LEFT RIGHT	HEEL HEIGHT LEFT RIGHT	LBS. BFT.	BUNDLE # STACK #	LOAD BY REMARKS
	1 2-ply	T1 Half Hip Girder	8 /12	23-09-00	4-01-04	2 x 4 2 x 6	1-03-08	1-04-13 4-01-04	221.21 135.33		
	1 2-ply	T1Z Half Hip Girder	8 /12	23-09-00	4-01-04	2 x 4 2 x 6	1-03-08	1-04-13 4-01-04	224.79 136.33		
	2	T2 Half Hip	8 /12	23-09-00	5-01-04	2 x 4	1-03-08	1-04-13 5-01-04	193.94 122.33		
	2	T3 Half Hip	8 /12	23-09-00	6-01-04	2 x 4	1-03-08	1-04-13 6-01-04	209.59 130.67		
	2	T4 Half Hip	8 /12	23-09-00	7-01-04	2 x 4	1-03-08	1-04-13 7-01-04	226.41 144.33		
	2	T5 Half Hip	8 /12	23-09-00	8-01-04	2 x 4	1-03-08	1-04-13 8-01-04	218.4 134.33		
	2	T6 Half Hip	8 /12	23-09-00	9-01-04	2 x 4	1-03-08	1-04-13 9-01-04	229.21 143.00		
	2	T7 Half Hip	8 /12	23-09-00	10-01-04	2 x 4	1-03-08	1-04-13 10-01-04	254.47 156.67		
	2	T8 Half Hip	8 /12	23-09-00	11-01-04	2 x 4	1-03-08	1-04-13 11-01-04	280.46 173.33		
	4	T9 Common	8 /12	13-05-00	5-10-08	2 x 4	1-03-08 1-03-08	1-04-13 1-04-13	233.27 148.00		
	2	T9S Roof Special	8 /12	13-05-00	5-10-08	2 x 4	1-03-08 1-03-08	1-04-13 1-04-13	123.94 80.33		
	1	T11 Hip Girder	4.5 /12	6-11-00	1-08-04	2 x 4	1-03-08 1-03-08	5-05 5-05	24.08 16.67		
	1	T12 Common	4.5 /12	6-11-00	2-01-02	2 x 4	1-03-08 1-03-08	5-05 5-05	22.41 15.00		
	1 2-ply	T13 Jack-Closed Girder	6 /12	5-10-08	4-01-04	2 x 4 2 x 6		1-02-00 4-01-04	54.54 34.67		

DELIVERY SHIPLIST



Lumber Yard: TAMARACK LUMBER
 Builder: GREEN PARK HOMES
 Project: LAMPONE INVESTMENTS INC
 Location: MARKHAM
 Model: THE PEYTON 3
 Lot #:
 Elevation: 1A

Job Track: 51453
 PlanLog: 202893
 Layout ID: 410170
 Ref #
 Page: 2 of 2
 Date: 08-11-2020
 Designer:
 Sales Rep: Mario DiCano

Roof Trusses

PROFILE	QTY PLY	MARK TYPE	PITCH	SPAN	HEIGHT	LUMBER	OVERHANG LEFT RIGHT	HEEL HEIGHT LEFT RIGHT	LBS. BFT.	BUNDLE # STACK #	LOAD BY REMARKS
	18	J1 Jack-Open	6 /12	5-10-08	4-01-04	2 x 4	1-03-08	1-02-00 4-01-04	302.3 192.00		
	3	J2 Jack-Open	4.5 /12	2-04-08	1-08-04	2 x 4	1-03-08	5-05 1-04-00	24.56 18.00		
	4	J3 Jack-Open	3.5 /12	4-06-08	2-00-01	2 x 4	1-03-08	3-14 1-07-13	48.82 32.00		
	2	C1 Jack-Open	4.5 /12	1-09-07	1-05-09	2 x 4	1-03-08 7-01	5-05 1-01-06	14.94 10.67		
	2	C2 Jack-Open	4.5 /12	1-10-08	1-05-09	2 x 4	1-03-08	5-05 1-01-12	13.8 9.33		

TOTAL # TRUSS= 57

TOTAL BFT OF ALL TRUSSES= 1832.99

BFT.


TOTAL WEIGHT OF ALL TRSSES 2921.12 LBS

HARDWARE

QTY	TYPE	MODEL	LENGTH
3	Hardware	LUS24	
1	Hardware	LUS26-2	

TOTAL NUMBER OF ITEMS= 4

DELIVERY SHIPLIST




Lumber Yard: TAMARACK LUMBER
 Builder: GREEN PARK HOMES
 Project: LAMPONE INVESTMENTS INC
 Location: MARKHAM
 Model: THE PEYTON
 Lot #:
 Elevation: 1B

Job Track: 51453
 PlanLog: 202893
 Layout ID: 410171
 Ref #
 Page: 1 of 2
 Date: 08-11-2020
 Designer:
 Sales Rep: Mario DiCano

Roof Trusses

PROFILE	QTY PLY	MARK TYPE	PITCH	SPAN	HEIGHT	LUMBER	OVERHANG LEFT RIGHT	HEEL HEIGHT LEFT RIGHT	LBS. BFT.	BUNDLE # STACK #	LOAD BY REMARKS
	1 2-ply	T1 Half Hip Girder	8 /12	23-09-00	4-01-04	2 x 4 2 x 6	1-03-08	1-04-13 4-01-04	221.21 135.33		
	2	T2 Half Hip	8 /12	23-09-00	5-01-04	2 x 4	1-03-08	1-04-13 5-01-04	193.94 122.33		
	2	T3 Half Hip	8 /12	23-09-00	6-01-04	2 x 4	1-03-08	1-04-13 6-01-04	209.59 130.67		
	2	T4 Half Hip	8 /12	23-09-00	7-01-04	2 x 4	1-03-08	1-04-13 7-01-04	226.41 144.33		
	2	T5 Half Hip	8 /12	23-09-00	8-01-04	2 x 4	1-03-08	1-04-13 8-01-04	218.4 134.33		
	2	T6 Half Hip	8 /12	23-09-00	9-01-04	2 x 4	1-03-08	1-04-13 9-01-04	229.21 143.00		
	2	T7 Half Hip	8 /12	23-09-00	10-01-04	2 x 4	1-03-08	1-04-13 10-01-04	254.47 156.67		
	2	T8 Half Hip	8 /12	23-09-00	11-01-04	2 x 4	1-03-08	1-04-13 11-01-04	280.46 173.33		
	2	T9 Common	8 /12	13-05-00	5-10-08	2 x 4	1-03-08 1-03-08	1-04-13 1-04-13	116.63 74.00		
	2	T9S Roof Special	8 /12	13-05-00	5-10-08	2 x 4	1-03-08 1-03-08	1-04-13 1-04-13	123.94 80.33		
	4	T10 Common	8 /12	23-09-00	9-05-02	2 x 4	1-03-08	1-04-13 1-07-08	403.69 251.33		
	1	G10 GABLE	8 /12	23-09-00	9-05-02	2 x 4	1-03-08	1-04-13 1-07-08	113.97 72.83		
	1	T11 Hip Girder	4.5 /12	6-11-00	1-08-04	2 x 4	1-03-08 1-03-08	5-05 5-05	24.08 16.67		
	1	T12 Common	4.5 /12	6-11-00	2-01-02	2 x 4	1-03-08 1-03-08	5-05 5-05	22.41 15.00		

DELIVERY SHIPLIST



Lumber Yard: TAMARACK LUMBER
 Builder: GREEN PARK HOMES
 Project: LAMPONE INVESTMENTS INC
 Location: MARKHAM
 Model: THE PEYTON
 Lot #:
 Elevation: 1B

Job Track: 51453
 PlanLog: 202893
 Layout ID: 410171
 Ref #
 Page: 2 of 2
 Date: 08-11-2020
 Designer:
 Sales Rep: Mario DiCano

Roof Trusses

PROFILE	QTY PLY	MARK TYPE	PITCH	SPAN	HEIGHT	LUMBER	OVERHANG LEFT RIGHT	HEEL HEIGHT LEFT RIGHT	LBS. BFT.	BUNDLE # STACK #	LOAD BY REMARKS
	12	J1 Jack-Open	6 /12	5-10-08	4-01-04	2 x 4	1-03-08	1-02-00 4-01-04	201.53 128.00		
	2	J2 Jack-Open	4.5 /12	2-04-08	1-08-04	2 x 4	1-03-08	5-05 1-04-00	16.37 12.00		
	4	J3 Jack-Open	3.5 /12	4-06-08	2-00-01	2 x 4	1-03-08	3-14 1-07-13	48.82 32.00		
	2	C1 Jack-Open	4.5 /12	1-09-07	1-05-09	2 x 4	1-03-08 7-01	5-05 1-01-06	14.94 10.67		
	2	C2 Jack-Open	4.5 /12	1-10-08	1-05-09	2 x 4	1-03-08	5-05 1-01-12	13.8 9.33		


TOTAL # TRUSS= 49

TOTAL BFT OF ALL TRUSSES= 1842.15

BFT.

TOTAL WEIGHT OF ALL TRSSES 2933.87 LBS

DELIVERY SHIPLIST




Lumber Yard: TAMARACK LUMBER
 Builder: GREEN PARK HOMES
 Project: LAMPONE INVESTMENTS INC
 Location: MARKHAM
 Model: THE PEYTON 3
 Lot #:
 Elevation: 2 - Left or right

Job Track: 51453
 PlanLog: 202893
 Layout ID: 410173
 Ref #
 Page: 1 of 2
 Date: 08-05-2020
 Designer:
 Sales Rep: Mario DiCano

Roof Trusses

PROFILE	QTY PLY	MARK TYPE	PITCH	SPAN	HEIGHT	LUMBER	OVERHANG LEFT RIGHT	HEEL HEIGHT LEFT RIGHT	LBS. BFT.	BUNDLE # STACK #	LOAD BY REMARKS
	1 2-ply	T20 Flat Girder	0 /12	23-07-00	4-01-04	2 x 6		4-01-04 4-01-04	248.94 152.00		
	1 2-ply	T20Z Flat Girder	0 /12	23-07-00	4-01-04	2 x 6		4-01-04 4-01-04	248.94 152.00		
	2	T21 Flat	0 /12	23-07-00	5-01-04	2 x 4		5-01-04 5-01-04	197.15 124.33		
	2	T22 Flat	0 /12	23-07-00	6-01-04	2 x 4		6-01-04 6-01-04	210.94 130.00		
	10	T23 Flat	0 /12	23-07-00	7-01-04	2 x 4		7-01-04 7-01-04	1125.8 698.33		
	1 2-ply	T24 Hip Girder	11 /12	13-05-00	5-03-11	2 x 4 2 x 6	1-03-08 1-03-08	1-09-01 1-09-01	147.58 95.33		
	1	T25 Hip	11 /12	13-03-00	8-07-11	2 x 4	1-03-08	3-04-14 3-03-01	83.44 53.83		
	2	T26 Common	11 /12	13-03-00	9-04-14	2 x 4		3-04-14 3-03-01	142.21 90.33		
	1	T27 Hip Girder	11 /12	6-11-00	4-04-11	2 x 4	1-03-08 1-03-08	1-09-01 1-09-01	39.86 25.67		
	1 2-ply	T28 Jack-Closed Girder	6 /12	5-10-08	4-01-04	2 x 4		1-02-00 4-01-04	51.25 34.00		
	2	G28 GABLE	6 /12	20-02-08	11-03-04	2 x 4	1-03-08	1-02-00 11-03-04	210.76 131.33		
	1 2-ply	T29 Jack-Closed Girder	11 /12	3-10-08	5-03-11	2 x 4		1-09-01 5-03-11	40.8 26.67		
	12	P1 Common	6 /12	16-08-12	4-02-04	2 x 4		0-01 0-01	613 376.00		
	18	J1 Jack-Open	6 /12	5-10-08	4-01-04	2 x 4	1-03-08	1-02-00 4-01-04	302.3 192.00		

DELIVERY SHIPLIST



Lumber Yard: TAMARACK LUMBER
 Builder: GREEN PARK HOMES
 Project: LAMPONE INVESTMENTS INC
 Location: MARKHAM
 Model: THE PEYTON 3
 Lot #:
 Elevation: 2

Job Track: 51453
 PlanLog: 202893
 Layout ID: 410173
 Ref #
 Page: 2 of 2
 Date: 08-05-2020
 Designer:
 Sales Rep: Mario DiCano

Roof Trusses

PROFILE	QTY PLY	MARK TYPE	PITCH	SPAN	HEIGHT	LUMBER	OVERHANG LEFT RIGHT	HEEL HEIGHT LEFT RIGHT	LBS. BFT.	BUNDLE # STACK #	LOAD BY REMARKS
	2	J20 Jack-Open	11 /12	3-10-08	5-03-11	2 x 4	1-03-08	1-09-01 5-03-11	32.23 21.67		
	2	J22 Jack-Open	11 /12	2-10-08	4-04-11	2 x 4	1-03-08	1-09-01 4-04-11	26.85 17.67		
	4	J23 Jack-Open	4 /12	6-02-08	2-09-11	2 x 4	1-03-08	3-15 2-04-12	64.82 42.67		
	4	J24 Jack-Open	4 /12	5-04-08	2-06-06	2 x 4	1-03-08	3-15 2-01-07	57.01 37.33		
	1	C20 Jack-Open	11 /12	1-09-07	3-04-11	2 x 4	1-03-08 2-01-01	1-09-01 3-04-11	12.46 8.33		
	3	C21 Jack-Open	11 /12	1-10-08	3-04-11	2 x 4	1-03-08	1-09-01 3-05-11	30.47 21.00		
	2	C22 Jack-Open	11 /12	1-09-07	3-04-11	2 x 4	1-03-08 1-01-01	1-09-01 3-04-11	22.63 15.33		

TOTAL # TRUSS= 78

TOTAL BFT OF ALL TRUSSES= 2445.82

BFT.


TOTAL WEIGHT OF ALL TRSSES 3909.44 LBS

HARDWARE

QTY	TYPE	MODEL	LENGTH
5	Hardware	LUS24	
2	Hardware	LUS26-2	

TOTAL NUMBER OF ITEMS= 7

DELIVERY SHIPLIST




Lumber Yard: TAMARACK LUMBER
 Builder: GREEN PARK HOMES
 Project: LAMPONE INVESTMENTS INC
 Location: MARKHAM
 Model: THE PEYTON 3
 Lot #:
 Elevation: 3A

Job Track: 51453
 PlanLog: 202893
 Layout ID: 410175
 Ref #
 Page: 1 of 2
 Date: 08-05-2020
 Designer:
 Sales Rep: Mario DiCano

Roof Trusses

PROFILE	QTY PLY	MARK TYPE	PITCH	SPAN	HEIGHT	LUMBER	OVERHANG LEFT RIGHT	HEEL HEIGHT LEFT RIGHT	LBS. BFT.	BUNDLE # STACK #	LOAD BY REMARKS
	1 2-ply	T30 Half Hip Girder	6 /12	23-09-00	4-01-04	2 x 4 2 x 6	1-03-08	1-02-00 4-01-04	211.72 130.33		
	2	T31 Half Hip	6 /12	23-09-00	5-01-04	2 x 4	1-03-08	1-02-00 5-01-04	195.92 122.00		
	2	T32 Half Hip	6 /12	23-09-00	6-01-04	2 x 4	1-03-08	1-02-00 6-01-04	196.73 122.33		
	2	T33 Half Hip	6 /12	23-09-00	7-01-04	2 x 4	1-03-08	1-02-00 7-01-04	206.87 127.67		
	2	T34 Half Hip	6 /12	23-09-00	8-01-04	2 x 4	1-03-08	1-02-00 8-01-04	218.08 135.33		
	2	T35 Half Hip	6 /12	23-09-00	9-01-04	2 x 4	1-03-08	1-02-00 9-01-04	216.08 134.67		
	2	T36 Half Hip	6 /12	23-09-00	10-01-04	2 x 4	1-03-08	1-02-00 10-01-04	231.84 141.67		
	2	T37 Half Hip	6 /12	23-09-00	11-01-04	2 x 4	1-03-08	1-02-00 11-01-04	248.8 153.00		
	1	T38 Hip Girder	6 /12	13-05-00	3-01-04	2 x 4	1-03-08 1-03-08	1-02-00 1-02-00	52.83 33.67		
	1	T39 Hip	6 /12	13-00-08	4-01-04	2 x 4	1-03-08	1-02-00 1-04-04	52.71 34.67		
	2	T40 Common	6 /12	13-00-08	4-06-04	2 x 4	1-03-08	1-02-00 1-04-04	101.8 65.33		
	3	T43S Jack-Closed	6 /12	6-04-08	5-10-04	2 x 4	1-03-08	1-02-00 5-10-04	113.19 73.50		
	1	T44S Half Hip	6 /12	6-04-08	4-10-07	2 x 4	1-03-08	1-02-00 4-10-07	38.87 25.33		
	1	T45S Half Hip Girder	6 /12	6-04-08	3-10-07	2 x 4	1-03-08	1-02-00 3-10-07	34.73 23.67		

DELIVERY SHIPLIST



Lumber Yard: TAMARACK LUMBER
 Builder: GREEN PARK HOMES
 Project: LAMPONE INVESTMENTS INC
 Location: MARKHAM
 Model: THE PEYTON 3
 Lot #:
 Elevation: 3A

Job Track: 51453
 PlanLog: 202893
 Layout ID: 410175
 Ref #
 Page: 2 of 2
 Date: 08-05-2020
 Designer:
 Sales Rep: Mario DiCano

Roof Trusses

PROFILE	QTY PLY	MARK TYPE	PITCH	SPAN	HEIGHT	LUMBER	OVERHANG LEFT RIGHT	HEEL HEIGHT LEFT RIGHT	LBS. BFT.	BUNDLE # STACK #	LOAD BY REMARKS
	1 2-ply	T47 Jack-Closed Girder	6 /12	6-04-08	5-10-04	2 x 4 2 x 6		2-08-00 5-10-04	68.35 45.67		
	1 2-ply	T300 Hip Girder	6 /12	23-09-00	5-10-04	2 x 4 2 x 6	1-03-08	1-02-00 2-10-00	237.13 148.67		
	10	J1 Jack-Open	6 /12	5-10-08	4-01-04	2 x 4	1-03-08	1-02-00 4-01-04	167.94 106.67		
	4	J30 Jack-Open	6 /12	3-10-08	3-01-04	2 x 4	1-03-08	1-02-00 3-01-04	47.86 29.33		
	1	J31 Jack-Open	6 /12	2-00-14	3-10-07	2 x 4		2-10-00 3-10-07	10.06 7.50		
	1	J32 Jack-Open	6 /12	2-00-14	2-04-07	2 x 4	1-03-08	1-04-00 2-04-07	7.8 5.33		
	1	C30 Jack-Open	6 /12	3-09-07	3-00-12	2 x 4	1-03-08 2-01-01	1-02-00 3-00-12	14.13 8.67		
	1	C31 Jack-Open	6 /12	1-09-07	2-00-12	2 x 4	1-03-08 4-01-01	1-02-00 2-00-12	11.58 7.33		
	1	C32 Jack-Open	6 /12	1-10-08	3-00-12	2 x 4	1-03-08 1-10-15	1-02-00 2-01-04	9.57 6.00		
	3	C33 Jack-Open	6 /12	1-09-07	2-00-12	2 x 4	1-03-08 1-01	1-02-00 2-00-12	21.06 14.00		
	2	C34 Jack-Open	6 /12	1-09-07	2-00-12	2 x 4	1-03-08 2-01-01	1-02-00 2-00-12	18.6 12.00		

TOTAL # TRUSS= 53

TOTAL BFT OF ALL TRUSSES= 1714.34

BFT.


TOTAL WEIGHT OF ALL TRSSES 2734.27 LBS

HARDWARE

QTY	TYPE	MODEL	LENGTH
5	Hardware	LUS24	
1	Hardware	LUS26-2	

TOTAL NUMBER OF ITEMS= 6

DELIVERY SHIPLIST




Lumber Yard: TAMARACK LUMBER
 Builder: GREEN PARK HOMES
 Project: LAMPONE INVESTMENTS INC
 Location: MARKHAM
 Model: THE PEYTON 3
 Lot #:
 Elevation: 3B

Job Track: 51453
 PlanLog: 202893
 Layout ID: 410176
 Ref #
 Page: 1 of 2
 Date: 08-05-2020
 Designer:
 Sales Rep: Mario DiCano

Roof Trusses

PROFILE	QTY PLY	MARK TYPE	PITCH	SPAN	HEIGHT	LUMBER	OVERHANG LEFT RIGHT	HEEL HEIGHT LEFT RIGHT	LBS. BFT.	BUNDLE # STACK #	LOAD BY REMARKS
	1 2-ply	T30 Half Hip Girder	6 /12	23-09-00	4-01-04	2 x 4 2 x 6	1-03-08	1-02-00 4-01-04	211.72 130.33		
	1 2-ply	T30Z Half Hip Girder	6 /12	23-09-00	4-01-04	2 x 4 2 x 6	1-03-08	1-02-00 4-01-04	211.72 130.33		
	2	T31 Half Hip	6 /12	23-09-00	5-01-04	2 x 4	1-03-08	1-02-00 5-01-04	195.92 122.00		
	2	T32 Half Hip	6 /12	23-09-00	6-01-04	2 x 4	1-03-08	1-02-00 6-01-04	196.73 122.33		
	2	T33 Half Hip	6 /12	23-09-00	7-01-04	2 x 4	1-03-08	1-02-00 7-01-04	206.87 127.67		
	2	T34 Half Hip	6 /12	23-09-00	8-01-04	2 x 4	1-03-08	1-02-00 8-01-04	218.08 135.33		
	2	T35 Half Hip	6 /12	23-09-00	9-01-04	2 x 4	1-03-08	1-02-00 9-01-04	216.08 134.67		
	2	T36 Half Hip	6 /12	23-09-00	10-01-04	2 x 4	1-03-08	1-02-00 10-01-04	231.84 141.67		
	2	T37 Half Hip	6 /12	23-09-00	11-01-04	2 x 4	1-03-08	1-02-00 11-01-04	248.8 153.00		
	1	T38 Hip Girder	6 /12	13-05-00	3-01-04	2 x 4	1-03-08 1-03-08	1-02-00 1-02-00	52.83 33.67		
	1	T41 Hip	6 /12	13-05-00	5-07-04	2 x 4	1-03-08 1-03-08	2-08-00 2-08-00	62.97 41.67		
	2	T42 Common	6 /12	13-05-00	6-00-04	2 x 4	1-03-08	2-08-00 2-08-00	119.42 76.67		
	1 2-ply	T46 Jack-Closed Girder	6 /12	5-10-08	4-01-04	2 x 4 2 x 6		1-02-00 4-01-04	54.54 34.67		
	16	J1 Jack-Open	6 /12	5-10-08	4-01-04	2 x 4	1-03-08	1-02-00 4-01-04	268.71 170.67		

DELIVERY SHIPLIST



Lumber Yard: TAMARACK LUMBER
 Builder: GREEN PARK HOMES
 Project: LAMPONE INVESTMENTS INC
 Location: MARKHAM
 Model: THE PEYTON 3
 Lot #:
 Elevation: 3B

Job Track: 51453
 PlanLog: 202893
 Layout ID: 410176
 Ref #
 Page: 2 of 2
 Date: 08-05-2020
 Designer:
 Sales Rep: Mario DiCano

Roof Trusses


PROFILE	QTY PLY	MARK TYPE	PITCH	SPAN	HEIGHT	LUMBER	OVERHANG LEFT RIGHT	HEEL HEIGHT LEFT RIGHT	LBS. BFT.	BUNDLE # STACK #	LOAD BY REMARKS
	4	J30 Jack-Open	6 /12	3-10-08	3-01-04	2 x 4	1-03-08	1-02-00 3-01-04	47.86 29.33		
	1	C30 Jack-Open	6 /12	3-09-07	3-00-12	2 x 4	1-03-08 2-01-01	1-02-00 3-00-12	14.13 8.67		
	1	C31 Jack-Open	6 /12	1-09-07	2-00-12	2 x 4	1-03-08 4-01-01	1-02-00 2-00-12	11.58 7.33		
	1	C32 Jack-Open	6 /12	1-10-08	3-00-12	2 x 4	1-03-08 1-10-15	1-02-00 2-01-04	9.57 6.00		
	3	C33 Jack-Open	6 /12	1-09-07	2-00-12	2 x 4	1-03-08 1-01	1-02-00 2-00-12	21.06 14.00		
	2	C34 Jack-Open	6 /12	1-09-07	2-00-12	2 x 4	1-03-08 2-01-01	1-02-00 2-00-12	18.6 12.00		

TOTAL # TRUSS= 52 TOTAL BFT OF ALL TRUSSES= 1632.01 BFT. TOTAL WEIGHT OF ALL TRSSES 2619.03 LBS

HARDWARE

QTY	TYPE	MODEL	LENGTH
2	Hardware	LUS24	
1	Hardware	LUS26-2	

TOTAL NUMBER OF ITEMS= 3



LUMBER

N. L. G. A. RULES	CHORDS	SIZE	LUMBER	DESCR.
A - C	2x4	DRY	No.2	SPF
C - E	2x4	DRY	No.2	SPF
E - H	2x4	DRY	No.2	SPF
I - H	2x4	DRY	No.2	SPF
O - B	2x6	DRY	No.2	SPF
O - K	2x6	DRY	No.2	SPF
K - I	2x6	DRY	No.2	SPF

ALL WEBS 2x3 DRY No.2 SPF
EXCEPT

DRY: SEASONED LUMBER.

DESIGN CONSISTS OF 2 TRUSSES BUILT SEPARATELY THEN FASTENED TOGETHER AS FOLLOWS:

CHORDS #ROWS	SURFACE SPACING (IN)	LOAD(PLF)
TOP CHORDS : (0.122"x3") SPIRAL NAILS		
A - C	12	SIDE(61.0)
C - E	12	SIDE(61.0)
E - H	12	SIDE(61.0)
H - I	12	TOP
O - B	12	TOP
BOTTOM CHORDS : (0.122"x3") SPIRAL NAILS		
O - K	12	SIDE(183.1)
K - I	12	SIDE(0.0)
WEBS : (0.122"x3") SPIRAL NAILS		
2x3	6	

NAILS TO BE DRIVEN FROM ONE SIDE ONLY.

GIRDER NAILING ASSUMES NAILED HANGERS ARE FASTENED WITH MIN. 3-0 INCH NAILS.

TOP - COMPONENTS ARE LOADED FROM THE TOP AND MUST BE PLACED ON TOP EDGE OF ALL PLIES FOR THE LOAD TO BE TRANSFERRED TO EACH PLY.

SIDE - PLF SHOWN IS THE EQUIVALENT UDL APPLIED TO ONE SIDE THAT THE CORRESPONDING NAILING PATTERN SHALL BE CAPABLE OF TRANSFERING. REMAINING PLF MUST BE APPLIED ON THE OPPOSITE SIDE OR ON THE TOP.

DIMENSIONS, SUPPORTS AND LOADINGS SPECIFIED BY FABRICATOR TO BE VERIFIED BY BUILDING DESIGNER

BEARINGS

FACTORED GROSS REACTION	MAXIMUM FACTORED GROSS REACTION	INPUT BRG	REQRD BRG
JT VERT HORZ	DOWN HORZ UPLIFT	IN-SX	IN-SX
I 2253 0	2253 0	1-8	1-8
O 2351 0	2351 0	5-8	5-8

UNFACTORED REACTIONS

1ST LCASE	MAX./MIN. COMPONENT REACTIONS
JT COMBINED	SNOW LIVE PERM.LIVE WIND DEAD SOIL
I 1595 1036 0	0 0 0 0 0 0
O 1660 1104 0	0 0 0 0 0 0

BEARING MATERIAL TO BE SPF NO.2 OR BETTER AT JOINT(S) I, O

BRACING
TOP CHORD TO BE SHEATHED OR MAX. PURLIN SPACING = 4.61 FT.
MAX. UNBRACED BOTTOM CHORD LENGTH = 10.00 FT OR RIGID CEILING DIRECTLY APPLIED.

ALL PITCH BREAKS AND PERIMETER CORNER JOINTS MUST BE Laterally RESTRAINED.

LOADING

TOTAL LOAD CASES: (4)

CHORDS				WEBS			
MEMB.	MAX. FACTORED FORCE (LBS)	FACTORED VERT. LOAD LC1 (PLF)	MAX. CSI (LC)	MEMB.	MAX. FACTORED FORCE (LBS)	MAX. CSI (LC)	
FR-TO		FROM TO		FR-TO			
A-B	0 35	-91.8 -91.8 0.07 (1)	10.00	N-C	-364 0	0.05 (1)	
B-C	-2640 0	-91.8 -91.8 0.18 (1)	5.42	B-N	0 2255	0.28 (1)	
C-P	-3469 0	-91.8 -91.8 0.35 (1)	4.64	J-H	0 3052	0.38 (1)	
P-Q	-3469 0	-91.8 -91.8 0.35 (1)	4.64	C-M	0 1608	0.20 (1)	
Q-D	-3469 0	-91.8 -91.8 0.35 (1)	4.64	J-G	-1636 0	0.21 (1)	
D-R	-3464 0	-91.8 -91.8 0.35 (1)	4.65	M-D	-812 0	0.10 (1)	
R-E	-3464 0	-91.8 -91.8 0.35 (1)	4.65	L-G	0 1276	0.16 (1)	
E-F	-3464 0	-91.8 -91.8 0.35 (1)	4.65	D-L	-6 16	0.00 (4)	
F-S	-3464 0	-91.8 -91.8 0.38 (1)	4.61	L-F	-641 0	0.08 (1)	
S-T	-3464 0	-91.8 -91.8 0.38 (1)	4.61				
T-G	-3464 0	-91.8 -91.8 0.38 (1)	4.61				
G-U	-2453 0	-91.8 -91.8 0.35 (1)	5.33				
U-V	-2453 0	-91.8 -91.8 0.35 (1)	5.33				
V-W	-2453 0	-91.8 -91.8 0.35 (1)	5.33				
W-H	-2453 0	-91.8 -91.8 0.35 (1)	5.33				
I-H	-2165 0	0.0 0.0 0.27 (1)	7.55				
O-B	-2307 0	0.0 0.0 0.08 (1)	7.81				

O-X	0 0	-18.5 -18.5 0.03 (4)	10.00
X-N	0 0	-18.5 -18.5 0.03 (4)	10.00
N-Y	0 2183	-18.5 -18.5 0.17 (1)	10.00
Y-Z	0 2183	-18.5 -18.5 0.17 (1)	10.00
Z-M	0 2183	-18.5 -18.5 0.17 (1)	10.00
M-AA	0 3469	-18.5 -18.5 0.27 (1)	10.00
AA-AB	0 3469	-18.5 -18.5 0.27 (1)	10.00
AB-L	0 3469	-18.5 -18.5 0.27 (1)	10.00
L-K	0 2453	-18.5 -18.5 0.20 (1)	10.00
K-AC	0 2453	-18.5 -18.5 0.20 (1)	10.00
AC-J	0 2453	-18.5 -18.5 0.20 (1)	10.00
J-AD	0 0	-18.5 -18.5 0.05 (4)	10.00
AD-AE	0 0	-18.5 -18.5 0.05 (4)	10.00
AE-AF	0 0	-18.5 -18.5 0.05 (4)	10.00
AF-I	0 0	-18.5 -18.5 0.05 (4)	10.00

FACTORED CONCENTRATED LOADS (LBS)

JT	LOC.	LC1	MAX-	MAX+	FACE	DIR.	TYPE	HEEL	CONN.
JT	4-0-11	-51	-57	---	FRONT	VERT	DEAD	---	C1
C	4-0-11	-117	-117	---	FRONT	VERT	TOTAL	---	C1
C	4-0-11	-260	-260	---	FRONT	VERT	SNOW	---	C1
E	11-11-4	-110	-110	---	FRONT	VERT	TOTAL	---	C1
F	13-11-4	-110	-110	---	FRONT	VERT	TOTAL	---	C1
K	15-11-4	-26	-26	---	FRONT	VERT	TOTAL	---	C1
L	13-11-4	-26	-26	---	FRONT	VERT	TOTAL	---	C1

DESIGN CRITERIA

*** SPECIAL LOADS ANALYSIS ***
GEOMETRY AND/OR BASIC LOADS CHANGED BY USER.
LOADS WERE DERIVED FROM USER INPUT
NO FURTHER MODIFICATIONS WERE MADE

SPECIFIED LOADS:
TOP CH. LL = 25.6 PSF
DL = 6.0 PSF
BOT CH. LL = 0.0 PSF
DL = 7.4 PSF
TOTAL LOAD = 39.0 PSF

SPACING = 24.0 IN. C/C

LOADING IN FLAT SECTION BASED ON A SLOPE OF 6.00/12

*** NON STANDARD GIRDER ***
ADDTL USER-DEFINED LOADS APPLIED TO ALL LOAD CASES.

THIS TRUSS IS DESIGNED FOR RESIDENTIAL OR SMALL BUILDING REQUIREMENTS OF PART 9, NBCC 2015

THIS DESIGN COMPLIES WITH:
- PART 9 OF BCBC 2018, ABC 2019
- PART 9 OF OBC 2012 (2019 AMENDMENT)
- CSA 086-14
- TPIC 2014

(55% OF 31.3 P.S.F. G.S.L. PLUS 8.4 P.S.F. RAIN LOAD) EQUALS 25.6 P.S.F. SPECIFIED ROOF LIVE LOAD

ALLOWABLE DEFL.(LL) = L/360 (0.79")
CALCULATED VERT. DEFL.(LL) = L/999 (0.07")
ALLOWABLE DEFL.(TL) = L/360 (0.79")
CALCULATED VERT. DEFL.(TL) = L/999 (0.13")

CSI: TC=0.38/1.00 (F-G:1), BC=0.27/1.00 (L-M:1), WB=0.38/1.00 (H-J:1), SSI=0.19/1.00 (G-H:1)

DOL LUMBER=1.00 NAIL=1.00 LS BEND=1.00
COMP=1.00 SHEAR=1.00 TENS=1.00

COMPANION LIVE LOAD FACTOR = 1.00

AUTOSOLVE RIGHT HEEL ONLY

TRUSS PLATE MANUFACTURER IS NOT RESPONSIBLE FOR QUALITY CONTROL IN THE TRUSS MANUFACTURING PLANT

NAIL VALUES
PLATE GRIP(DRY) SHEAR SECTION (PSI) (PLI) (PLI)
MAX MIN MAX MIN
MT20 650 371 1747 788 1987 1873

PLATE PLACEMENT TOL. = 0.250 inches

PLATE ROTATION TOL. = 5.0 Deg.

JSI GRIP= 0.87 (H) (INPUT = 0.90)
JSI METAL= 0.34 (H) (INPUT = 1.00)



Structural component only
DWG# T-2018275

JOB NAME	TRUSS NAME	QUANTITY	PLY	JOB DESC.	DRWG NO.
410169	T1	2	2	GREEN PARK HOMES	
Tamarack Roof Truss, Burlington				TRUSS DESC.	

Version 8.330 S May 6 2020 MiTek Industries, Inc. Fri Aug 14 14:44:57 2020 Page 2
ID:W63xGm6okcO0SiyZ4EwBx6zA2m0-5HkDP25EzZ746Ca1MzALsRQqH4Or7Hm6 xGvqRynvxK

PLATES (table is in inches)

JT	TYPE	PLATES	W	LEN	Y	X
B	TMVW-t	MT20	5.0	6.0	2.50	1.75
C	TTWW-m	MT20	5.0	6.0	2.00	2.00
D	TMVW-t	MT20	4.0	4.0		
E	TS-t	MT20	3.0	6.0		
F	TMW+w	MT20	2.0	4.0		
G	TMVW-t	MT20	4.0	4.0		
H	TMVW-t	MT20	4.0	6.0		
I	BMV1+p	MT20	3.0	6.0		
J, M, N						
J	BMVW-t	MT20	5.0	6.0		
K	BS-t	MT20	5.0	6.0		
L	BMVW-t	MT20	5.0	8.0		
O	BMV1+p	MT20	3.0	6.0		

FACTORED CONCENTRATED LOADS (LBS)

JT	LOC.	LC1	MAX-	MAX+	FACE	DIR.	TYPE	HEEL	CONN.
N	3-11-4	-26	-26	---	FRONT	VERT	TOTAL	---	C1
P	5-11-4	-110	-110	---	FRONT	VERT	TOTAL	---	C1
Q	7-11-4	-110	-110	---	FRONT	VERT	TOTAL	---	C1
R	9-11-4	-110	-110	---	FRONT	VERT	TOTAL	---	C1
S	15-11-4	-110	-110	---	FRONT	VERT	TOTAL	---	C1
T	17-11-4	-110	-110	---	FRONT	VERT	TOTAL	---	C1
U	19-11-4	-110	-110	---	FRONT	VERT	TOTAL	---	C1
V	21-11-4	-110	-110	---	FRONT	VERT	TOTAL	---	C1
W	22-11-4	-119	-119	---	FRONT	VERT	TOTAL	---	C1
X	1-11-4	-26	-26	---	FRONT	VERT	TOTAL	---	C1
Y	5-11-4	-26	-26	---	FRONT	VERT	TOTAL	---	C1
Z	7-11-4	-26	-26	---	FRONT	VERT	TOTAL	---	C1
AA	9-11-4	-26	-26	---	FRONT	VERT	TOTAL	---	C1
AB	11-11-4	-26	-26	---	FRONT	VERT	TOTAL	---	C1
AC	17-11-4	-26	-26	---	FRONT	VERT	TOTAL	---	C1
AD	19-11-4	-26	-26	---	FRONT	VERT	TOTAL	---	C1
AE	21-11-4	-26	-26	---	FRONT	VERT	TOTAL	---	C1
AF	22-11-4	-28	-28	---	FRONT	VERT	TOTAL	---	C1


CONNECTION REQUIREMENTS

- 1) C1: A SUITABLE HANGER/MECHANICAL CONNECTION IS REQUIRED.



Structural component only
DWG# T-2018275

Version 8.330 S May 6 2020 MiTek Industries, Inc. Fri Aug 14 14:44:58 2020 Page 1
ID:W63xGm6okcO0SiyZ4EwBx6zA2m0-ZTlbcO6ksk7xkM9DwghaPezanUJTsidFDb?VNuynvxJ
13-10-5 18.8.8



LUMBER		RULES			
N L G A	CHORDS	SIZE		LUMBER	DESCR
A - C	2x4	DRY	No.2		SPF
C - E	2x4	DRY	No.2		SPF
E - H	2x4	DRY	No.2		SPF
I - H	2x4	DRY	No.2		SPF
P - B	2x6	DRY	No.2		SPF
P - L	2x6	DRY	No.2		SPF
L - I	2x6	DRY	No.2		SPF
ALL WEBS	2x3	DRY	No.2		SPF

DRY: SEASONED LUMBER.

DESIGN CONSISTS OF 2 TRUSSES BUILT SEPARATELY THEN FASTENED TOGETHER AS FOLLOWS:

CHORDS	#ROWS	SURFACE SPACING (IN)	LOAD(PLF)
TOP CHORDS : (0.122"x3") SPIRAL NAILS			
A-C	1	12	TOP
C-E	1	12	TOP
E-H	1	12	SIDE(61.0)
H-I	1	12	TOP
P-B	2	12	TOP
BOTTOM CHORDS : (0.122"x3") SPIRAL NAILS			
P-L	2	12	SIDE(183.1)
L-I	2	12	SIDE(183.1)
WEBS : (0.122"x3") SPIRAL NAILS			
2x3	1	6	
M-F	1	6	SIDE(152.0)

NAILS TO BE DRIVEN FROM ONE SIDE ONLY.

GIRDER NAILING ASSUMES NAILED HANGERS ARE FASTENED WITH MIN. 3-0 INCH NAILS.

TOP - COMPONENTS ARE LOADED FROM THE TOP AND MUST BE PLACED ON TOP EDGE OF ALL PLIES FOR THE LOAD TO BE TRANSFERRED TO EACH PLY.

SIDE - PLF SHOWN IS THE EQUIVALENT UDL APPLIED TO ONE SIDE THAT THE CORRESPONDING NAILING PATTERN SHALL BE CAPABLE OF TRANSFERRING. REMAINING PLF MUST BE APPLIED ON THE OPPOSITE SIDE OR ON THE TOP

DIMENSIONS, SUPPORTS AND LOADINGS SPECIFIED BY FABRICATOR TO BE VERIFIED BY
BUILDING DESIGNER
BEARINGS

JT	FACTORED GROSS REACTION		MAXIMUM FACTORED GROSS REACTION			INPUT BRG	REQRD BRG
	VERT	HORZ	DOWN	HORZ	UPLIFT	IN-SX	IN-SX
I	2720	0	2720	0	0	1-8	1-8 & BLOCK
P	2143	0	2143	0	0	5-8	5-8

UNFACTORED REACTIONS

1ST LCASE		MAX./MIN. COMPONENT REACTIONS					
JT	COMBINED	SNOW	LIVE	PERM.LIVE	WIND	DEAD	SOIL
I	1922	1271.0	0.0	0.0	0.0	650.0	0.0
P	1511	1018.0	0.0	0.0	0.0	493.0	0.0

BEARING MATERIAL TO BE SPF NO.2 OR BETTER AT JOINT(S) I. P

2x6 DRY SPF No.2 BEARING BLOCK 12" LONG AT JT. I ATTACHED TO FRONT SIDE WITH 3 ROWS OF (0.122"x3") SPIRAL NAILS SPACED 3" C.C. 12 NAILS TOTAL.

BRACING

TOP CHORD TO BE SHEATHED OR MAX. PURLIN SPACING = 4.06 FT.
MAX. UNBRACED BOTTOM CHORD LENGTH = 10.00 FT OR RIGID CEILING DIRECTLY APPLIED

ALL PITCH BREAKS AND PERIMETER CORNER JOINTS MUST BE Laterally RESTRAINED

LOADING

TOTAL LOAD CASES: (4)

CHORDS				WEBS			
MAX. FACTORED		FACTORED		MAX. FACTORED			
MEMB.	FORCE (LBS)	VERT. LOAD (LBS)	LC1 MAX CSI (LC)	MAX UNBRAC LENGTH	MEMB.	FORCE (LBS)	MAX CSI (LC)
FR-TO		FROM TO			FR-TO		
A-B	0.35	-91.8	-91.8 0.07 (1)	10.00	O-C	-392.0	0.05 (1)
B-C	-2377.0	-91.8	-91.8 0.17 (1)	5.65	B-O	0.2031	0.25 (1)
C-D	-3743.0	-91.8	-91.8 0.24 (1)	4.67	K-H	0.3768	0.47 (1)
D-E	-4596.0	-91.8	-91.8 0.27 (1)	4.26	C-N	0.2224	0.28 (1)
E-F	-4596.0	-91.8	-91.8 0.27 (1)	4.26	K-G	-2090.0	0.27 (1)
F-Q	-4596.0	-91.8	-91.8 0.42 (1)	4.06	N-D	-1151.0	0.15 (1)
Q-R	-4596.0	-91.8	-91.8 0.42 (1)	4.06	M-G	0.1977	0.24 (1)
R-G	-4596.0	-91.8	-91.8 0.42 (1)	4.06	D-M	0.1076	0.13 (1)
G-S	-3029.0	-91.8	-91.8 0.36 (1)	4.90	M-F	-528.0	0.07 (1)
S-T	-3029.0	-91.8	-91.8 0.36 (1)	4.90			
T-U	-3029.0	-91.8	-91.8 0.36 (1)	4.90			
U-H	-3029.0	-91.8	-91.8 0.36 (1)	4.90			
I-H	-2619.0	0.0	0.0 0.33 (1)	7.03			
P-B	-2109.0	0.0	0.0 0.08 (1)	7.81			

P-O	0 0	-18.5	-18.5	0.02 (4)	10.00
O-N	0 1964	-18.5	-18.5	0.15 (1)	10.00
N-V	0 3743	-18.5	-18.5	0.37 (1)	10.00
V-M	0 3743	-18.5	-18.5	0.37 (1)	10.00
M-W	0 3029	-18.5	-18.5	0.23 (1)	10.00
W-L	0 3029	-18.5	-18.5	0.23 (1)	10.00
L-X	0 3029	-18.5	-18.5	0.23 (1)	10.00
X-K	0 3029	-18.5	-18.5	0.23 (1)	10.00
K-Y	0 0	-18.5	-18.5	0.05 (4)	10.00
Y-J	0 0	-18.5	-18.5	0.05 (4)	10.00
J-I	0 0	-18.5	-18.5	0.05 (4)	10.00

FACTORED CONCENTRATED LOADS (LBS)

J	LOC.	LC1	MAX-	MAX+	FACE	DIR.	TYPE	HEEL	CONN.
G	18-5-12	-110	-110	---	FRONT	VERT	TOTAL	---	C1
J	22-5-12	-26	-26	---	FRONT	VERT	TOTAL	---	C1
K	22-11-12	-29	-29	---	FRONT	VERT	TOTAL	---	C1
Q	18-5-12	-26	-26	---	FRONT	VERT	TOTAL	---	C1
K	14-5-12	-110	-110	---	FRONT	VERT	TOTAL	---	C1
R	16-5-12	-110	-110	---	FRONT	VERT	TOTAL	---	C1
S	20-5-12	-110	-110	---	FRONT	VERT	TOTAL	---	C1
T	22-5-12	-110	-110	---	FRONT	VERT	TOTAL	---	C1
U	22-11-12	-121	-121	---	FRONT	VERT	TOTAL	---	C1
V	13-6-8	-1285	-1285	---	FRONT	VERT	TOTAL	---	C1
W	14-5-12	-26	-26	---	FRONT	VERT	TOTAL	---	C1

TOTAL WEIGHT = $2 \times 112 = 225$ lb

DESIGN CRITERIA

*** SPECIAL LOADS ANALYSIS ***
GEOMETRY AND/OR BASIC LOADS CHANGED BY
USER.
LOADS WERE DERIVED FROM USER INPUT
NO FURTHER MODIFICATIONS WERE MADE

SPECIFIED LOADS:

TOP	CH.	LL =	25.6	PSF
		DL =	6.0	PSF
BOT	CH.	LL =	0.0	PSF
		DL =	7.4	PSF
TOTAL LOAD		=	39.0	PSF

SPACING = 24.0 IN. C/C

LOADING IN FLAT SECTION BASED ON A SLOPE
OF 6.00/12

THIS TRUSS IS DESIGNED FOR RESIDENTIAL OR
SMALL BUILDING REQUIREMENTS OF PART 9,
NBCC 2015

THIS DESIGN COMPLIES WITH:

- PART 9 OF BCBC 2018 , ABC 2019
- PART 9 OF OBC 2012 (2019 AMENDMENT)
- CSA 086-14
- TPIC 2014

(55 % OF 31.3 P.S.F. G.S.L. PLUS 8.4 P.S.F. RAIN LOAD) EQUALS 25.6 P.S.F. SPECIFIED ROOF LIVE LOAD

ALLOWABLE DEFL.(LL)= $L/360$ (0.79")
 CALCULATED VERT. DEFL.(LL) = $L/999$ (0.09")
 ALLOWABLE DEFL.(TL)= $L/360$ (0.79")
 CALCULATED VERT. DEFL.(TL) = $L/999$ (0.16")

CSI: TC=0.42/1.00 (F-G:1), BC=0.37/1.00 (M-N:1),
WB=0.47/1.00 (H-K:1), SSI=0.41/1.00 (M-N:1)

DOL LUMBER=1.00 NAIL=1.00 LS BEND=1.00
COMP=1.00 SHEAR=1.00 TENS= 1.00

COMPANION LIVE LOAD FACTOR = 1.00

AUTOSOLVE RIGHT HEEL ONLY

TRUSS PLATE MANUFACTURER IS NOT RESPONSIBLE FOR QUALITY CONTROL IN THE TRUSS MANUFACTURING PLANT.


NAIL VALUES

PLATE	GRIP(DRY)		SHEAR		SECTION	
	(PSI)		(PLI)		(PLI)	
	MAX	MIN	MAX	MIN	MAX	MIN
MT20	650	371	1747	788	1987	1873

PLATE PLACEMENT TOL. = 0.250 inches

PLATE ROTATION TOL. = 5.0 Deg.

JSI GRIP= 0.87 (C) (INPUT = 0.90)
JSI METAL= 0.36 (H) (INPUT = 1.00)



Structural component only
DWG# T-2018276 1/2

JOB NAME 410169	TRUSS NAME T1Z	QUANTITY 1	PLY 2	JOB DESC. GREEN PARK HOMES	DRWG NO.
Tamarack Roof Truss, Burlington				TRUSS DESC.	

PLATES (table is in inches)

JT	TYPE	PLATES	W	LEN	Y	X
B	TMW-t	MT20	5.0	6.0	2.25	1.75
C	TTWW-m	MT20	5.0	6.0	2.00	1.50
D	TMWW-t	MT20	4.0	4.0		
E	TS-t	MT20	3.0	6.0		
F	TMW-w	MT20	2.0	4.0		
G	TMWW-t	MT20	4.0	6.0		
H	TMW-t	MT20	5.0	6.0	2.50	2.75
I	BMV1+p	MT20	3.0	6.0		
K	BMWW-t	MT20	5.0	6.0	2.50	2.75
L	BS-t	MT20	5.0	6.0		
M	BMWWW-t	MT20	5.0	8.0		
N	BMWW-t	MT20	5.0	6.0		
O	BMWW-t	MT20	5.0	6.0		
P	BMV1+p	MT20	3.0	6.0		

FACTORED CONCENTRATED LOADS (LBS)

JT	LOC.	LC1	MAX-	MAX+	FACE	DIR.	TYPE	HEEL	CONN.
X	16-5-12	-26	-26	---	FRONT	VERT	TOTAL	---	C1
Y	20-5-12	-26	-26	---	FRONT	VERT	TOTAL	---	C1


CONNECTION REQUIREMENTS

- 1) C1: A SUITABLE HANGER/MECHANICAL CONNECTION IS REQUIRED.



Structural component only
DWG# T-2018276 22

JOB NAME 410110	TRUSS NAME T2	QUANTITY 4	PLY 1	JOB DESC. GREEN PARK HOMES	DRWG NO.
Tamarack Roof Truss, Burlington				Version 8.330 S May 6 2020 Mitek Industries, Inc. Tue Aug 4 12:11:19 2020 Page 1	
ID:W63xGm6okc00SiyZ4EwBx6zA2m0-dTVo5WPE2IkYGJ_WBa3VvPnd_bL1h6a2qSi5OUyrf7M				Scale = 1:38.8	



LUMBER
N. L. G. A. RULES

CHORDS	SIZE	LUMBER
A - C	2x4	DRY No.2
C - E	2x4	DRY No.2
E - G	2x4	DRY No.2
H - G	2x4	DRY No.2
M - B	2x4	DRY No.2
M - J	2x4	DRY No.2
J - H	2x4	DRY No.2

ALL WEBS 2x3 DRY No.2
EXCEPT
SPF

DRY: SEASONED LUMBER.

PLATES (table is in inches)

JT	TYPE	PLATES	W	LEN	Y	X
B	TMVW+p	MT20	5.0	6.0	Edge	
C	TTWW+m	MT20	5.0	6.0	2.00	1.50
D	TMW+w	MT20	2.0	4.0		
F	TS-t	MT20	3.0	6.0		
G	TMVW-t	MT20	4.0	4.0		
H	TMVW-t	MT20	5.0	6.0		
I	BMV1+p	MT20	3.0	4.0		
J	BMVW-t	MT20	5.0	6.0		
K	BS-t	MT20	3.0	6.0		
L	BMVW-t	MT20	4.0	9.0		
M	BMV1+p	MT20	4.0	6.0		
M	BMV1+p	MT20	3.0	4.0		

Edge - INDICATES REFERENCE CORNER OF PLATE TOUCHES EDGE OF CHORD.

DIMENSIONS, SUPPORTS AND LOADINGS SPECIFIED BY FABRICATOR TO BE VERIFIED BY BUILDING DESIGNER

BEARINGS

JT	FACTORED GROSS REACTION		MAXIMUM FACTORED GROSS REACTION		INPUT BRG	REQD BRG
	VERT	HORZ	DOWN	HORZ		
H	1309	0	1309	0	1-8	1-8
M	1435	0	1435	0	5-8	5-8

UNFACTORED REACTIONS

JT	1ST LOASE COMBINED	MAX./MIN. COMPONENT REACTIONS					
		SNOW	LIVE	PERM.LIVE	WIND	DEAD	SOIL
H	926	608.0	0/0	0/0	0/0	318.0	0/0
M	1013	678.0	0/0	0/0	0/0	335.0	0/0

BEARING MATERIAL TO BE SPF NO.2 OR BETTER AT JOINT(S) H, M

BRACING
TOP CHORD TO BE SHEATHED OR MAX. PURLIN SPACING = 4.44 FT.
MAX. UNBRACED BOTTOM CHORD LENGTH = 10.00 FT. OR RIGID CEILING DIRECTLY APPLIED.

ALL PITCH BREAKS AND PERIMETER CORNER JOINTS MUST BE LATERALLY RESTRAINED.

LOADING
TOTAL LOAD CASES: (4)

CHORDS				WEBS			
MEMB.	MAX. FACTORED FORCE (LBS)	FACTORED VERT. LOAD (PLF)	MAX. FACTORED CSI (LC)	MEMB.	MAX. FACTORED FORCE (LBS)	MAX. FACTORED CSI (LC)	
FR-TO		FROM TO		FR-TO			
A-B	0.35	-91.8	-91.8 0.12 (1)	10.00	L-C	-102.59	0.04 (1)
B-C	-1417.0	-91.8	-91.8 0.59 (1)	4.72	B-L	0.1199	0.27 (1)
C-D	-1688.0	-91.8	-91.8 0.54 (1)	4.47	I-G	0.1679	0.38 (1)
D-E	-1688.0	-91.8	-91.8 0.56 (1)	4.44	C-K	0.653	0.15 (1)
E-F	-1688.0	-91.8	-91.8 0.56 (1)	4.44	I-F	-907.0	0.35 (1)
F-G	-1323.0	-91.8	-91.8 0.53 (1)	4.92	K-D	-599.0	0.23 (1)
H-G	-1263.0	0.0	0.0 0.56 (1)	7.16	K-F	0.469	0.11 (1)
M-B	-1394.0	0.0	0.0 0.14 (1)	6.90			
M-L	0.0	-18.5	-18.5 0.15 (4)	10.00			
L-K	0.1176	-18.5	-18.5 0.27 (1)	10.00			
K-J	0.1323	-18.5	-18.5 0.30 (1)	10.00			
J-I	0.1323	-18.5	-18.5 0.30 (1)	10.00			
I-H	0.0	-18.5	-18.5 0.16 (4)	10.00			

TOTAL WEIGHT = 4 X 97 = 388 lb

DESIGN CRITERIA

SPECIFIED LOADS:
TOP CH. LL = 25.6 PSF
DL = 6.0 PSF
BOT CH. LL = 0.0 PSF
DL = 7.4 PSF
TOTAL LOAD = 39.0 PSF

SPACING = 24.0 IN. C/C

LOADING IN FLAT SECTION BASED ON A SLOPE OF 6.00/12

THIS TRUSS IS DESIGNED FOR RESIDENTIAL OR SMALL BUILDING REQUIREMENTS OF PART 9, NBCC 2015

THIS DESIGN COMPLIES WITH:
- PART 9 OF CBC 2018, ABC 2019
- PART 9 OF OBC 2012 (2019 AMENDMENT)
- CSA 086-14
- TPIC 2014

(55% OF 31.3 P.S.F. G.S.L. PLUS 8.4 P.S.F. RAIN LOAD) EQUALS 25.6 P.S.F. SPECIFIED ROOF LIVE LOAD

ALLOWABLE DEFL.(LL) = L/360 (0.79")
CALCULATED VERT. DEFL.(LL) = L/999 (0.06")
ALLOWABLE DEFL.(TL) = L/360 (0.79")
CALCULATED VERT. DEFL.(TL) = L/999 (0.12")

CSI: TC=0.59/1.00 (B-C:1), BC=0.30/1.00 (I-K:1), WB=0.38/1.00 (G-I:1), SSI=0.26/1.00 (F-G:1)

DOL LUMBER=1.00 NAIL=1.00 LS BEND=1.10
COMP=1.10 SHEAR=1.10 TENS=1.10

COMPANION LIVE LOAD FACTOR = 1.00

TRUSS PLATE MANUFACTURER IS NOT RESPONSIBLE FOR QUALITY CONTROL IN THE TRUSS MANUFACTURING PLANT

NAIL VALUES


PLATE	GRIP(DRY)	SHEAR (PSI)	SECTION (PLI)
MT20	650	371	1747 788 1987 1873

PLATE PLACEMENT TOL. = 0.250 inches

PLATE ROTATION TOL. = 5.0 Deg.

JSI GRIP = 0.85 (B) (INPUT = 0.90)
JSI METAL = 0.60 (B) (INPUT = 1.00)






LUMBER

N. L. G. A. RULES

CHORDS	SIZE	LUMBER	DESCR.
A - D	2x4	DRY No.2	SPF
D - F	2x4	DRY No.2	SPF
F - H	2x4	DRY No.2	SPF
H - I	2x4	DRY No.2	SPF
I - B	2x4	DRY No.2	SPF
N - K	2x4	DRY No.2	SPF
K - I	2x4	DRY No.2	SPF

JOB NAME	TRUSS NAME	QUANTITY	PLY	JOB DESC.	DRWG NO.
410110	T4	4	1	GREEN PARK HOMES	
Tamarack Roof Truss, Burlington					
Version 8.330 S May 6 2020 MiTek Industries, Inc. Tue Aug 4 12:11:20 2020 Page 1					
ID:W63xGm6okcO0SiYz4EwBx6zA2m0-5f3AlsQtocsOuTZjllakSdwrR?iAQRRc26RwWyrF7L					
Scale = 1:40.8					



LUMBER			
N. L. G. A. RULES	CHORDS	SIZE	LUMBER
A - D	2x4	DRY	No.2
D - G	2x4	DRY	No.2
H - G	2x4	DRY	No.2
N - B	2x4	DRY	No.2
N - J	2x4	DRY	No.2
J - H	2x4	DRY	No.2
ALL WEBS	2x3	DRY	No.2
EXCEPT			

DRY: SEASONED LUMBER.

PLATES (table is in inches)

JT	TYPE	PLATES	W	LEN	Y	X
B	TMVW-p	MT20	5.0	6.0	Edge	
C	TMVW-t	MT20	4.0	4.0	2.00	1.50
D	TTWW+m	MT20	5.0	6.0	2.00	1.50
E	TMVW-w	MT20	2.0	4.0		
F	TMVW-t	MT20	4.0	4.0		
G	TMVW-p	MT20	4.0	6.0		
H	BMV1-p	MT20	3.0	4.0		
I	BMVW-t	MT20	4.0	6.0		
J	BS-t	MT20	3.0	6.0		
K	BMVW-w	MT20	4.0	9.0		
L	BMVW-t	MT20	4.0	4.0		
M	BMVW-t	MT20	4.0	6.0		
N	BMV1-p	MT20	3.0	4.0		

Edge - INDICATES REFERENCE CORNER OF PLATE TOUCHES EDGE OF CHORD.

DIMENSIONS, SUPPORTS AND LOADINGS SPECIFIED BY FABRICATOR TO BE VERIFIED BY BUILDING DESIGNER

BEARINGS		FACTORED	MAXIMUM FACTORED	INPUT	REQD
JT	GROSS REACTION	GROSS REACTION	DOWN	UPLIFT	BRG
H	1309	0	1309	0	1-8
N	1435	0	1435	0	5-8

UNFACTORED REACTIONS

JT	COMBINED	SNOW	LIVE	PERM.LIVE	WIND	DEAD	SOIL
H	926	608	0	0	0	318	0
N	1013	678	0	0	0	335	0

BEARING MATERIAL TO BE SPF NO.2 OR BETTER AT JOINT(S) H, N

BRACING

TOP CHORD TO BE SHEATHED OR MAX. PURLIN SPACING = 5.07 FT.
MAX. UNBRACED BOTTOM CHORD LENGTH = 10.00 FT OR RIGID CEILING DIRECTLY APPLIED.

ALL PITCH BREAKS AND PERIMETER CORNER JOINTS MUST BE Laterally RESTRAINED.

1 LATERAL BRACE(S) AT 1/2 LENGTH OF G-H.

END VERTICAL(S) MUST BE SHEATHED OR HAVE BRACES AS INDICATED IN THE MAX. UNBRACED LENGTH COLUMN OF THE TABLE BELOW

LOADING

TOTAL LOAD CASES: (4)

CHORDS		MAX. FACTORED	FACTORED	VERT. LOAD	LC1	MAX	MAX.	MEMB.	MAX. FACTORED	MAX.
MEMB.	FORCE (LBS)	FROM	TO	PLF	CSI (LC)	UNBRAC	LENGTH	FR-TO	FORCE (LBS)	CSI (LC)
A-B	0 35	-91.8	-91.8	0.12 (1)	10.00	M-C	-220	0	0.06 (1)	
B-C	-1445 0	-91.8	-91.8	0.32 (1)	5.07	C-L	-229	0	0.13 (1)	
C-D	-1298 0	-91.8	-91.8	0.31 (1)	5.30	L-D	0	247	0.06 (1)	
D-E	-1152 0	-91.8	-91.8	0.34 (1)	5.49	B-M	0	1260	0.28 (1)	
E-F	-1152 0	-91.8	-91.8	0.35 (1)	5.47	I-G	0	1353	0.30 (1)	
F-G	-816 0	-91.8	-91.8	0.34 (1)	6.24	D-K	0	155	0.03 (1)	
H-G	-1271 0	0.0	0.0	0.29 (1)	5.71	I-F	-972	0	0.85 (1)	
N-B	-1399 0	0.0	0.0	0.14 (1)	6.88	K-E	-498	0	0.44 (1)	
N-M	0 0	-18.5	-18.5	0.07 (4)	10.00	K-F	0	570	0.13 (1)	
M-L	0 1223	-18.5	-18.5	0.24 (1)	10.00					
L-K	0 1060	-18.5	-18.5	0.22 (1)	10.00					
K-J	0 816	-18.5	-18.5	0.19 (1)	10.00					
J-I	0 816	-18.5	-18.5	0.19 (1)	10.00					
I-H	0 0	-18.5	-18.5	0.11 (4)	10.00					

TOTAL WEIGHT = 4 X 113 = 453 lb

DESIGN CRITERIA

SPECIFIED LOADS:

TOP CH. LL	= 25.6	PSF
DL	= 6.0	PSF
BOT CH. LL	= 0.0	PSF
DL	= 7.4	PSF
TOTAL LOAD	= 39.0	PSF

SPACING = 24.0 IN. C/C

LOADING IN FLAT SECTION BASED ON A SLOPE OF 6.00/12

THIS TRUSS IS DESIGNED FOR RESIDENTIAL OR SMALL BUILDING REQUIREMENTS OF PART 9, NBCC 2015

THIS DESIGN COMPLIES WITH:

- PART 9 OF CBC 2018, ABC 2019
- PART 9 OF OBC 2012 (2019 AMENDMENT)
- CSA 086-14
- TPIC 2014

(55% OF 31.3 P.S.F. G.S.L. PLUS 8.4 P.S.F. RAIN LOAD) EQUALS 25.6 P.S.F. SPECIFIED ROOF LIVE LOAD

ALLOWABLE DEFL.(LL)= L/360 (0.79")
CALCULATED VERT. DEFL.(LL)= L/999 (0.05")
ALLOWABLE DEFL.(TL)= L/360 (0.79")
CALCULATED VERT. DEFL.(TL)= L/999 (0.09")

CSI: TC=0.35/1.00 (E-F:1) , BC=0.24/1.00 (L-M:1) , WB=0.85/1.00 (F-I:1) , SS=0.22/1.00 (F-G:1)

DOL LUMBER=1.00 NAIL=1.00 LS BEND=1.10
COMP=1.10 SHEAR=1.10 TENS=1.10

COMPANION LIVE LOAD FACTOR = 1.00

TRUSS PLATE MANUFACTURER IS NOT RESPONSIBLE FOR QUALITY CONTROL IN THE TRUSS MANUFACTURING PLANT

NAIL VALUES

PLATE	GRIP(DRY)	SHEAR	SECTION
(PSI)	(PLI)	(PLI)	(PLI)
MT20	650	371	1747 788 1987 1873

PLATE PLACEMENT TOL. = 0.250 inches

PLATE ROTATION TOL. = 5.0 Deg.


JSI GRIP= 0.85 (M) (INPUT = 0.90)
JSI METAL= 0.37 (G) (INPUT = 1.00)



Structural component only
DWG# T-2017082

JOB NAME	TRUSS NAME	QUANTITY	PLY	JOB DESC.	DRWG NO.
410110	T5	4	1	GREEN PARK HOMES	
Tamarack Roof Truss, Burlington					

Version 8.330 S May 6 2020 MiTek Industries, Inc. Tue Aug 4 12:11:21 2020 Page 1
ID:W63xGm60kc00SiyZ4EwBx6zA2m0-ZsdYVCQVZv_FWd8vl?5z_qTvFP1U9sXLHmBBTNyrF7K



Scale = 1:45.6

LUMBER	N. L. G. A. RULES	CHORDS	SIZE	LUMBER	DESCR.
A - D	2x4	DRY	No.2	SPF	
D - F	2x4	DRY	No.2	SPF	
G - F	2x4	DRY	No.2	SPF	
L - B	2x4	DRY	No.2	SPF	
L - I	2x4	DRY	No.2	SPF	
I - G	2x4	DRY	No.2	SPF	
ALL WEBS	2x3	DRY	No.2	SPF	
EXCEPT					

DRY: SEASONED LUMBER.

PLATES (table is in inches)

JT	TYPE	PLATES	W	LEN	Y	X
B	TMVW-p	MT20	5.0	6.0	Edge	
C	TMVW-i	MT20	4.0	4.0	2.00	1.50
D	TTWW+m	MT20	5.0	6.0	2.00	1.50
E	TMVW-w	MT20	2.0	4.0		
F	TMVW-p	MT20	4.0	6.0		
G	BMV1-p	MT20	3.0	4.0		
H	BMVWW-i	MT20	5.0	8.0		
I	BS-i	MT20	3.0	6.0		
J	BMVW-i	MT20	4.0	4.0		
K	BMVW-i	MT20	4.0	6.0		
L	BMV1-p	MT20	3.0	4.0		

Edge - INDICATES REFERENCE CORNER OF PLATE TOUCHES EDGE OF CHORD.

DIMENSIONS, SUPPORTS AND LOADINGS SPECIFIED BY FABRICATOR TO BE VERIFIED BY BUILDING DESIGNER

JT	FACTORED GROSS REACTION		MAXIMUM FACTORED GROSS REACTION		INPUT BRG	REQD BRG
	VERT	HORZ	DOWN	HORZ		
G	1309	0	1309	0	1-8	1-8
L	1435	0	1435	0	5-8	5-8

UNFACTORED REACTIONS

JT	1ST LCASE COMBINED	MAX./MIN. COMPONENT REACTIONS					
		SNOW	LIVE	PERM.LIVE	WIND	DEAD	SOIL
G	926	608	0	0	0	0	0
L	1013	678	0	0	0	0	0

BEARING MATERIAL TO BE SPF NO.2 OR BETTER AT JOINT(S) G, L

BRACING

TOP CHORD TO BE SHEATHED OR MAX. PURLIN SPACING = 4.86 FT.
MAX. UNBRACED BOTTOM CHORD LENGTH = 10.00 FT OR RIGID CEILING DIRECTLY APPLIED.

ALL PITCH BREAKS AND PERIMETER CORNER JOINTS MUST BE Laterally RESTRAINED

1 LATERAL BRACE(S) AT 1/2 LENGTH OF F-G, D-H.

END VERTICAL(S) MUST BE SHEATHED OR HAVE BRACES AS INDICATED IN THE MAX. UNBRACED LENGTH COLUMN OF THE TABLE BELOW

LOADING

TOTAL LOAD CASES: (4)

CHORDS				WEBS			
MEMB.	MAX. FACTORED FORCE (LBS)	FACTORED VERT. LOAD (PLF)	MAX. CSI (LC)	MEMB.	MAX. FACTORED FORCE (LBS)	MAX. CSI (LC)	
FR-TO		FROM	TO	FR-TO			
A-B	0 35	-91.8	-91.8 0.12 (1)	10.00	K-C	-163 26	0.06 (1)
B-C	-1459 0	-91.8	-91.8 0.46 (1)	4.86	C-J	-354 0	0.30 (1)
C-D	-1206 0	-91.8	-91.8 0.43 (1)	5.26	J-D	0 341	0.08 (1)
D-E	-898 0	-91.8	-91.8 0.79 (1)	4.96	B-K	0 1266	0.28 (1)
E-F	-898 0	-91.8	-91.8 0.79 (1)	4.96	H-F	0 1358	0.31 (1)
G-F	-1258 0	0.0	0.0 0.37 (1)	5.74	D-H	-125 0	0.10 (1)
L-B	-1394 0	0.0	0.0 0.14 (1)	6.90	H-E	-780 0	0.99 (1)
L-K	0 0	-18.5	-18.5 0.10 (4)	10.00			
K-J	0 1239	-18.5	-18.5 0.26 (1)	10.00			
J-I	0 980	-18.5	-18.5 0.30 (4)	10.00			
I-H	0 980	-18.5	-18.5 0.30 (4)	10.00			
H-G	0 0	-18.5	-18.5 0.22 (4)	10.00			

TOTAL WEIGHT = 4 X 109 = 437 lb

DESIGN CRITERIA

SPECIFIED LOADS:

TOP CH.	LL = 25.6 PSF
	DL = 6.0 PSF
BOT CH.	LL = 0.0 PSF
	DL = 7.4 PSF
TOTAL LOAD	= 39.0 PSF

SPACING = 24.0 IN./C

LOADING IN FLAT SECTION BASED ON A SLOPE OF 6.00/12

THIS TRUSS IS DESIGNED FOR RESIDENTIAL OR SMALL BUILDING REQUIREMENTS OF PART 9, NBCC 2015

THIS DESIGN COMPLIES WITH:

- PART 9 OF BCBC 2018, ABC 2019
- PART 9 OF OBC 2012 (2019 AMENDMENT)
- CSA 086-14
- TPIC 2014

(55 % OF 31.3 P.S.F. G.S.L. PLUS 8.4 P.S.F. RAIN LOAD) EQUALS 25.6 P.S.F. SPECIFIED ROOF LIVE LOAD

ALLOWABLE DEFL.(LL) = L/360 (0.79")
CALCULATED VERT. DEFL.(LL) = L/999 (0.04")
ALLOWABLE DEFL.(TL) = L/360 (0.79")
CALCULATED VERT. DEFL.(TL) = L/999 (0.09")

CSI: TC=0.79/1.00 (E-F:1), BC=0.30/1.00 (H-J:4), WB=0.99/1.00 (E-H:1), SS=0.31/1.00 (E-F:1)

DOL LUMBER=1.00 NAIL=1.00 LS BEND=1.10
COMP=1.10 SHEAR=1.10 TENS=1.10

COMPANION LIVE LOAD FACTOR = 1.00

TRUSS PLATE MANUFACTURER IS NOT RESPONSIBLE FOR QUALITY CONTROL IN THE TRUSS MANUFACTURING PLANT.

NAIL VALUES

PLATE	GRIP(DRY)	SHEAR (PSI)	SECTION (PLI)
MT20	650	371	1747
	788	1987	1873

PLATE PLACEMENT TOL. = 0.250 inches


PLATE ROTATION TOL. = 5.0 Deg.

JSI GRIP = 0.83 (F) (INPUT = 0.90)
JSI METAL = 0.40 (F) (INPUT = 1.00)



Structural component only
DWG# T-2017083

JOB NAME	TRUSS NAME	QUANTITY	PLY	JOB DESC.	DRWG NO.
410110	T6	4	1	GREEN PARK HOMES	
Tamarack Roof Truss, Burlington					



LUMBER			
N. L. G. A. RULES	CHORDS	SIZE	LUMBER
A - D	2x4	DRY	No.2
D - F	2x4	DRY	No.2
G - F	2x4	DRY	No.2
L - B	2x4	DRY	No.2
L - I	2x4	DRY	No.2
I - G	2x4	DRY	No.2
ALL WEBS	2x3	DRY	No.2
EXCEPT			
H - F	2x4	DRY	No.2
D - H	2x4	DRY	No.2

PLATES (table is in inches)					
JT	TYPE	PLATES	W	LEN	Y X
B	TMVW+p	MT20	5.0	6.0	Edge
C	TMVW-t	MT20	4.0	4.0	2.00 1.50
D	TTWW+m	MT20	5.0	6.0	2.00 1.50
E	TMVW+w	MT20	2.0	4.0	
F	TMVW-t	MT20	4.0	6.0	
G	BMV1+p	MT20	3.0	4.0	
H	BMVWW-t	MT20	4.0	9.0	
I	BS-t	MT20	3.0	6.0	
J	BMVW-t	MT20	4.0	4.0	
K	BMVW-t	MT20	4.0	6.0	
L	BMV1+p	MT20	3.0	4.0	

Edge - INDICATES REFERENCE CORNER OF PLATE TOUCHES EDGE OF CHORD.

DIMENSIONS, SUPPORTS AND LOADINGS SPECIFIED BY FABRICATOR TO BE VERIFIED BY BUILDING DESIGNER

BEARINGS		FACTORED GROSS REACTION	MAXIMUM FACTORED GROSS REACTION	INPUT BRG	REQD BRG
JT	VERT	HORZ	HORZ	UPLIFT	IN-SX
G	1309	0	1309	0	1-8
L	1435	0	1435	0	5-8

UNFACTORED REACTIONS							
JT	COMBINED	SNOW	LIVE	PERM.LIVE	WIND	DEAD	SOIL
G	926	608.0	0.0	0.0	0.0	318.0	0.0
L	1013	678.0	0.0	0.0	0.0	335.0	0.0

BEARING MATERIAL TO BE SPF NO.2 OR BETTER AT JOINT(S) G, L.
 BRACING
 TOP CHORD TO BE SHEATHED OR MAX. PURLIN SPACING = 4.61 FT.
 MAX. UNBRACED BOTTOM CHORD LENGTH = 10.00 FT. OR RIGID CEILING DIRECTLY APPLIED.

ALL PITCH BREAKS AND PERIMETER CORNER JOINTS MUST BE Laterally RESTRAINED.
 1 LATERAL BRACE(S) AT 1/2 LENGTH OF F-G, D-H, E-H.
 END VERTICAL(S) MUST BE SHEATHED OR HAVE BRACES AS INDICATED IN THE MAX. UNBRACED LENGTH COLUMN OF THE TABLE BELOW

LOADING			
TOTAL LOAD CASES: (4)			
CHORDS		WEBS	
MEMB.	MAX. FACTORED FORCE (LBS)	MEMB.	MAX. FACTORED FORCE (LBS)
FR-TO		FR-TO	
A-B	0 35	K-C	-110 59
B-C	-1459 0	C-J	-476 0
C-D	-1100 0	J-D	0 414
D-E	-731 0	B-K	0 1264
E-F	-731 0	H-F	0 1279
G-F	-1263 0	D-H	-278 0
L-B	-1390 0	H-E	-694 0
L-K	0 0		
K-J	0 1243		
J-I	0 889		
I-H	0 889		
H-G	0 0		

DESIGN CRITERIA

SPECIFIED LOADS:
 TOP CH. LL = 25.6 PSF
 DL = 6.0 PSF
 BOT CH. LL = 0.0 PSF
 DL = 7.4 PSF
 TOTAL LOAD = 39.0 PSF

SPACING = 24.0 IN. C/C

LOADING IN FLAT SECTION BASED ON A SLOPE OF 6.00/12

THIS TRUSS IS DESIGNED FOR RESIDENTIAL OR SMALL BUILDING REQUIREMENTS OF PART 9, NBCC 2015

THIS DESIGN COMPLIES WITH:
 - PART 9 OF CBC 2018, ABC 2019
 - PART 9 OF OBC 2012 (2019 AMENDMENT)
 - CSA 086-14
 - TPIC 2014

(55% OF 31.3 P.S.F. G.S.L. PLUS 8.4 P.S.F. RAIN LOAD) EQUALS 25.6 P.S.F. SPECIFIED ROOF LIVE LOAD

ALLOWABLE DEFL.(LL)= L/360 (0.79")
 CALCULATED VERT. DEFL.(LL) = L 999 (0.04")
 ALLOWABLE DEFL.(TL)= L/360 (0.79")
 CALCULATED VERT. DEFL.(TL) = L 999 (0.08")

CSI: TC=0.63/1.00 (B-C:1) . BC=0.27/1.00 (J-K:1) . WB=0.56/1.00 (C-J:1) . SI=0.27/1.00 (E-F:1)

DOL LUMBER=1.00 NAIL=1.00 LS BEND=1.10
 COMP=1.10 SHEAR=1.10 TENS=1.10

COMPANION LIVE LOAD FACTOR = 1.00

TRUSS PLATE MANUFACTURER IS NOT RESPONSIBLE FOR QUALITY CONTROL IN THE TRUSS MANUFACTURING PLANT.

NAIL VALUES			
PLATE	GRIP(DRY)	SHEAR	SECTION
(PSI)	(PLI)	(PLI)	(PLI)
MT20	650	371	1747 788 1987 1873

PLATE PLACEMENT TOL. = 0.250 inches


PLATE ROTATION TOL. = 5.0 Deg.

JSI GRIP= 0.90 (B) (INPUT = 0.90)
 JSI METAL= 0.62 (B) (INPUT = 1.00)



Structural component only
 DWG# T-2017084

JOB NAME	TRUSS NAME	QUANTITY	PLY	JOB DESC.	DRWG NO.
410110	T7	6	1	GREEN PARK HOMES	
Tamarack Roof Truss, Burlington					



LUMBER			
N. L. G. A. RULES			
CHORDS	SIZE	LUMBER	DESCR.
A - D	2x4	DRY	No.2
D - E	2x4	DRY	No.2
E - G	2x4	DRY	No.2
H - G	2x4	DRY	No.2
M - B	2x4	DRY	No.2
M - J	2x4	DRY	No.2
J - H	2x4	DRY	No.2
ALL WEBS	2x3	DRY	No.2
EXCEPT			
I - G	2x4	DRY	No.2
E - I	2x4	DRY	No.2

DRY: SEASONED LUMBER.

PLATES (table in inches)

JT	TYPE	PLATES	W	LEN	Y	X
B	TMVW+p	MT20	5.0	6.0	Edge	
C	TMVW-t	MT20	4.0	4.0	2.00	1.50
D	TS-t	MT20	3.0	6.0		
E	TTVW+m	MT20	5.0	6.0	2.00	1.50
F	TMVW-w	MT20	2.0	4.0		
G	TMVW+p	MT20	4.0	6.0		
H	BMV1+p	MT20	3.0	4.0		
I	BMVWW-t	MT20	5.0	8.0		
J	BS-t	MT20	3.0	6.0		
K	BMVW-t	MT20	4.0	4.0		
L	BMVW-t	MT20	4.0	6.0		
M	BMV1+p	MT20	3.0	4.0		

Edge - INDICATES REFERENCE CORNER OF PLATE TOUCHES EDGE OF CHORD.

DIMENSIONS, SUPPORTS AND LOADINGS SPECIFIED BY FABRICATOR TO BE VERIFIED BY BUILDING DESIGNER

JT	FACTORED GROSS REACTION		MAXIMUM FACTORED GROSS REACTION		INPUT BRG IN-SX	REQD BRG IN-SX
	VERT	HORZ	DOWN	HORZ		
H	1309	0	1309	0	1-8	1-8
M	1435	0	1435	0	5-8	5-8

UNFACTORED REACTIONS

JT	1ST LCASE		MAX. MIN. COMPONENT REACTIONS		WIND	DEAD	SOIL
	COMBINED	SNOW	LIVE	PERM. LIVE			
H	926	608	0	0	0	318	0
M	1013	678	0	0	0	335	0

BEARING MATERIAL TO BE SPF NO.2 OR BETTER AT JOINT(S) H, M

BRACING

TOP CHORD TO BE SHEATHED OR MAX. PURLIN SPACING = 4.70 FT.
MAX. UNBRACED BOTTOM CHORD LENGTH = 10.00 FT OR RIGID CEILING DIRECTLY APPLIED.

ALL PITCH BREAKS AND PERIMETER CORNER JOINTS MUST BE Laterally RESTRAINED.

1 LATERAL BRACE(S) AT 1/2 LENGTH OF G-H, C-K, E-I, F-I.

END VERTICAL(S) MUST BE SHEATHED OR HAVE BRACES AS INDICATED IN THE MAX. UNBRACED LENGTH COLUMN OF THE TABLE BELOW

LOADING

TOTAL LOAD CASES: (4)

CHORDS				WEBS			
MEMB.	MAX. FACTORED FORCE (LBS)	FACTORED VERT. LOAD (PLF)	MAX. UNBRACED LENGTH (LC)	MEMB.	MAX. FACTORED FORCE (LBS)	FACTORED VERT. LOAD (PLF)	MAX. UNBRACED LENGTH (LC)
FR-TO		FROM TO		FR-TO		FROM TO	
A-B	0 35	-91.8 -91.8	0.12 (1)	L-C	-64 89	0.03 (1)	
B-C	-1448 0	-91.8 -91.8	0.58 (1)	C-K	-592 0	0.30 (1)	
C-D	-986 0	-91.8 -91.8	0.53 (1)	K-E	0 485	0.11 (1)	
D-E	-986 0	-91.8 -91.8	0.53 (1)	B-L	0 1255	0.28 (1)	
E-F	-593 0	-91.8 -91.8	0.34 (1)	I-G	0 1232	0.20 (1)	
F-G	-593 0	-91.8 -91.8	0.34 (1)	E-I	-415 0	0.28 (1)	
H-G	-1268 0	0.0 0.0	0.63 (1)	I-F	-607 0	0.42 (1)	
M-B	-1385 0	0.0 0.0	0.14 (1)				
M-L	0 0	-18.5 -18.5	0.20 (4)				
L-K	0 1239	-18.5 -18.5	0.30 (1)				
K-J	0 791	-18.5 -18.5	0.19 (1)				
J-I	0 791	-18.5 -18.5	0.19 (1)				
I-H	0 0	-18.5 -18.5	0.12 (4)				

TOTAL WEIGHT = 6 X 127 = 763 lb
(M/F)

DESIGN CRITERIA

SPECIFIED LOADS:

TOP CH. LL = 25.6 PSF
DL = 6.0 PSF
BOT CH. LL = 0.0 PSF
DL = 7.4 PSF
TOTAL LOAD = 39.0 PSF

SPACING = 24.0 IN. CC

LOADING IN FLAT SECTION BASED ON A SLOPE OF 6.00/12

THIS TRUSS IS DESIGNED FOR RESIDENTIAL OR SMALL BUILDING REQUIREMENTS OF PART 9, NBCC 2015

THIS DESIGN COMPLIES WITH:

- PART 9 OF CBC 2018, ABC 2019
- PART 9 OF CBC 2012 (2019 AMENDMENT)
- CSA 086-14
- TPIC 2014

(55 % OF 31.3 P.S.F. G.S.L. PLUS 8.4 P.S.F. RAIN LOAD) EQUALS 25.6 P.S.F. SPECIFIED ROOF LIVE LOAD

ALLOWABLE DEFL.(LL) = L/360 (0.79")
CALCULATED VERT. DEFL.(LL) = L/999 (0.04")
ALLOWABLE DEFL.(TL) = L/360 (0.79")
CALCULATED VERT. DEFL.(TL) = L/999 (0.10")

CSI: TC=0.63/1.00 (G-H:1) , BC=0.30/1.00 (K-L:1) , WB=0.42/1.00 (F-I:1) , SI=0.24/1.00 (B-C:1)

DOL LUMBER=1.00 NAIL=1.00 LS BEND=1.10
COMP=1.10 SHEAR=1.10 TENS=1.10

COMPANION LIVE LOAD FACTOR = 1.00

TRUSS PLATE MANUFACTURER IS NOT RESPONSIBLE FOR QUALITY CONTROL IN THE TRUSS MANUFACTURING PLANT

NAIL VALUES

PLATE GRIP (DRY)	SHEAR (PSI)	SECTION (PLI)
MAX MIN	MAX MIN	MAX MIN
MT20	650 371	1747 788

PLATE PLACEMENT TOL. = 0.250 inches

PLATE ROTATION TOL. = 5.0 Deg.


JSI GRIP= 0.90 (B) (INPUT = 0.90)
JSI METAL= 0.62 (B) (INPUT = 1.00)



Structural component only
DWG# T-2017085

JOB NAME	TRUSS NAME	QUANTITY	PLY	JOB DESC.	DRWG NO.
410169	T8	4	1	GREEN PARK HOMES	
Tamarack Roof Truss, Burlington					

Version 8.330 S May 6 2020 Mitek Industries, Inc. Fri Aug 14 14:44:59 2020 Page 1
ID:W63xGm60kc00SiyZ4EwBx6zA2m0-1fs_qk7VVAf0LWkQTOCpxsWf0u3_bAEOSFI3vKynvxl



LUMBER					DIMENSIONS, SUPPORTS AND LOADINGS SPECIFIED BY FABRICATOR TO BE VERIFIED BY BUILDING DESIGNER										TOTAL WEIGHT = 4 X 140 = 561 lb			
N. L. G. A. RULES		CHORDS		SIZE	LUMBER	DESCR.	BEARINGS				DESIGN CRITERIA						(M/F)	
A - D	2x4	DRY	No.2	SPF	FACTORED		MAXIMUM FACTORED		INPUT	REQRD		SPECIFIED LOADS:						
D - E	2x4	DRY	No.2	SPF	GROSS REACTION		GROSS REACTION		BRG	BRG		TOP CH. LL = 25.6			PSF			
E - G	2x4	DRY	No.2	SPF	VERT		DOWN		UPLIFT	IN-SX		DL = 6.0			PSF			
H - G	2x4	DRY	No.2	SPF	H		1309		0	1-8		BOT CH. LL = 0.0			PSF			
M - B	2x4	DRY	No.2	SPF	M		1435		0	5-8		DL = 7.4			PSF			
M - J	2x4	DRY	No.2	SPF								TOTAL LOAD = 39.0			PSF			
J - H	2x4	DRY	No.2	SPF														

ALL WEBS EXCEPT				UNFACTORED REACTIONS				SPACING = 24.0 IN. C/C				
L - C	2x3	DRY	No.2	SPF	1ST LCASE	MAX./MIN. COMPONENT REACTIONS						
C - K	2x3	DRY	No.2	SPF	JT COMBINED	SNOW	LIVE	PERM. LIVE	WIND	DEAD	SOIL	
B - L	2x3	DRY	No.2	SPF	H	926	608 / 0	0 / 0	0 / 0	318 / 0	0 / 0	
				SPF	M	1013	678 / 0	0 / 0	0 / 0	335 / 0	0 / 0	
				SPF								

LOADING IN FLAT SECTION BASED ON A SLOPE OF 6.00/12

DRY: SEASONED LUMBER.

PLATES (table is in inches)						LOADING									
JT	TYPE	PLATES	W	LEN	Y	X	CHORDS				WEBS				
B	TMVW-p	MT20	5.0	6.0	Edge		MEMB.	FORCE	VERT. LOAD	LC1	MAX.	MAX.	MEMB.	FORCE	MAX.
C	TMVW-t	MT20	4.0	4.0	2.00	1.50	(1.9S)								
D	TS-t	MT20	3.0	6.0											
E	TTWW-m	MT20	5.0	8.0	2.00	3.00									
F	TMVW-w	MT20	2.0	4.0											
G	TMVW-p	MT20	4.0	6.0											
H	BMV1-p	MT20	3.0	4.0											
I	BMVWW-t	MT20	5.0	8.0											
J	BS-t	MT20	3.0	6.0											
K	BMVW-t	MT20	4.0	4.0											
L	BMVW-t	MT20	4.0	6.0											
M	BMV1-p	MT20	3.0	4.0											

ALL PITCH BREAKS AND PERIMETER CORNER JOINTS MUST BE Laterally RESTRAINED.

1 LATERAL BRACE(S) AT 1/2 LENGTH OF G-H, C-K, E-I, F-L

END VERTICAL(S) MUST BE SHEATHED OR HAVE BRACES AS INDICATED IN THE MAX. UNBRACED LENGTH COLUMN OF THE TABLE BELOW

LOADING

TOTAL LOAD CASES: (4)

DESIGN COMPLIES WITH:

- PART 9 OF CBC 2018 , ABC 2019
- PART 9 OF OBC 2012 (2019 AMENDMENT)
- CSA 086-14
- TPIC 2014

(55 % OF 31.3 P.S.F. G.S.L. PLUS 8.4 P.S.F. RAIN LOAD) EQUALS 25.6 P.S.F. SPECIFIED ROOF LIVE LOAD

ALLOWABLE DEFL.(LL)= L/360 (0.79")

CALCULATED VERT. DEFL.(LL)= L/ 999 (0.05")

ALLOWABLE DEFL.(TL)= L/360 (0.79")

CALCULATED VERT. DEFL.(TL)= L/ 999 (0.11")

Edge - INDICATES REFERENCE CORNER OF PLATE TOUCHES EDGE OF CHORD.

LOADING									
TOTAL LOAD CASES: (4)									
C H O R D S				W E B S					
MEMB.	MAX. FACTORED FORCE (LBS)	FACTORED VERT. LOAD (PLF)	LC1 MAX CSI (LC)	MAX. UNBRAC LENGTH	MEMB. FR-TO	MAX. FORCE (LBS)	FACTORED MAX CSI (LC)		
FR-TO		FROM	TO						
A-B	0 / 35	-91.8	-91.8	0.12 (1)	10.00	L-C	-23 / 116	0.04 (4)	
B-C	-1429 / 0	-91.8	-91.8	0.74 (1)	4.41	C-K	-705 / 0	0.44 (1)	
C-D	-866 / 0	-91.8	-91.8	0.67 (1)	5.44	K-E	0 / 555	0.09 (1)	
D-E	-866 / 0	-91.8	-91.8	0.67 (1)	5.44	E-I	-552 / 0	0.42 (1)	
E-F	-473 / 0	-91.8	-91.8	0.25 (1)	6.25	I-F	-521 / 0	0.33 (1)	
F-G	-473 / 0	-91.8	-91.8	0.25 (1)	6.25	I-G	0 / 1208	0.19 (1)	
H-G	-1272 / 0	0.0	0.0	0.81 (1)	5.71	B-L	0 / 1239	0.28 (1)	
M-B	-1380 / 0	0.0	0.0	0.14 (1)	6.92				
M-L	0 / 0	-18.5	-18.5	0.25 (4)	10.00				
L-K	0 / 1226	-18.5	-18.5	0.36 (4)	10.00				
K-J	0 / 689	-18.5	-18.5	0.18 (4)	10.00				
J-I	0 / 689	-18.5	-18.5	0.18 (4)	10.00				
I-H	0 / 0	-18.5	-18.5	0.08 (4)	10.00				


ALLOWABLE DEFL.(LL)= L/360 (0.79")	
CALCULATED VERT. DEFL.(LL) = L/ 999 (0.05")	
ALLOWABLE DEFL.(TL)= L/360 (0.79")	
CALCULATED VERT. DEFL.(TL) = L/ 999 (0.11")	
CSI: TC=0.81/1.00 (G-H:1) , BC=0.36/1.00 (K-L:4) .	
WB=0.44/1.00 (C-K:1) , S2I=0.27/1.00 (B-C:1)	
DOL LUMBER=1.00 NAIL=1.00 L5S BEND=1.10	
COMP=1.10 SHEAR=1.10 TENS= 1.10	
COMPANION LIVE LOAD FACTOR = 1.00	
TRUSS PLATE MANUFACTURER IS NOT RESPONSIBLE FOR QUALITY CONTROL IN THE TRUSS MANUFACTURING PLANT .	
NAIL VALUES	
PLATE GRIP(DRY) SHEAR SECTION	



Structural component only
DWG# T-2018277

Structural component only
DWG# T-2018278

JOB NAME	TRUSS NAME	QUANTITY	PLY	JOB DESC.	DRWG NO.
410169	T9S	4	1	GREEN PARK HOMES	
Tamarack Roof Truss, Burlington					



LUMBER					DIMENSIONS, SUPPORTS AND LOADINGS SPECIFIED BY FABRICATOR TO BE VERIFIED BY BUILDING DESIGNER										TOTAL WEIGHT = 4 X 62 = 248 lb		
N. L. G. A. RULES					BEARINGS										(M/F)		
CHORDS		SIZE	LUMBER	DESCR.	FACTORED		MAXIMUM FACTORED		INPUT		REQRD		DESIGN CRITERIA				
A - D		2x4	DRY	No.2	GROSS REACTION		GROSS REACTION		BRG		BRG		SPECIFIED LOADS:				
D - G		2x4	DRY	No.2	JT	VERT	HORZ	DOWN	HORZ	UPLIFT	IN-SX	IN-SX	TOP CH. LL = 25.6 PSF				
N - B		2x4	DRY	No.2									DL = 6.0 PSF				
H - F		2x4	DRY	No.2	N	866	0	866	0	0	5-8	5-8	BOT CH. LL = 0.0 PSF				
N - M		2x4	DRY	No.2	H	866	0	866	0	0	5-8	5-8	DL = 7.4 PSF				
M - C		2x4	DRY	No.2	UNFACTORED REACTIONS								TOTAL LOAD = 39.0 PSF				
L - J		2x4	DRY	No.2	1ST LCASE								SPACING = 24.0 IN. C/C				
I - E		2x4	DRY	No.2	JT	COMBINED	SNOW	LIVE	PERM.LIVE	WIND	DEAD	SOIL	THIS TRUSS IS DESIGNED FOR RESIDENTIAL OR SMALL BUILDING REQUIREMENTS OF PART 9, NBCC 2015				
I - H		2x4	DRY	No.2	N	610	413 / 0	0 / 0	0 / 0	0 / 0	196 / 0	0 / 0	THIS DESIGN COMPLIES WITH:				
ALL WEBS EXCEPT					SPF	H	610	413 / 0	0 / 0	0 / 0	0 / 0	196 / 0	0 / 0	- PART 9 OF CBC 2018 , ABC 2019			
N - L					SPF	BEARING MATERIAL TO BE SPF NO.2 OR BETTER AT JOINT(S) N, H											
J - H					SPF	BRACING											
DRY: SEASONED LUMBER.																	

PLATES (table is in inches)

JT	TYPE	PLATES	W	LEN	Y	X
B	TMVW+p	MT20	5.0	6.0	Edge	
C	TMVW-t	MT20	4.0	4.0	2.00	1.00
D	TTW-p	MT20	4.0	4.0	2.25	2.00
E	TMVW-t	MT20	4.0	4.0	2.00	1.00
F	TMVW+p	MT20	5.0	6.0	Edge	
H	BMVW1-t	MT20	4.0	4.0		
I	BMV+p	MT20	3.0	4.0		
J	BMVWV-t	MT20	5.0	8.0	3.50	5.50
K	BMVWV-t	MT20	4.0	9.0		
L	BMVWV-t	MT20	5.0	8.0	3.50	5.50
M	BMV+p	MT20	3.0	4.0		
N	BMVW1-t	MT20	4.0	4.0		

Edge - INDICATES REFERENCE CORNER OF PLATE TOUCHES EDGE OF CHORD.

BRACING
TOP CHORD TO BE SHEATHED OR MAX. PURLIN SPACING = 5.63 FT.
MAX. UNBRACED BOTTOM CHORD LENGTH = 10.00 FT. OR RIGID CEILING DIRECTLY APPLIED.

ALL PITCH BREAKS AND PERIMETER CORNER JOINTS MUST BE Laterally RESTRAINED.

LOADING
TOTAL LOAD CASES: (4)

CHORDS				WEBS			
MEMB.	FORCE (LBS)	FACTORED VERT. LOAD (PLF)	MAX. FACTORED VERT. LOAD (LC1)	MEMB.	FORCE (LBS)	MAX. FACTORED VERT. LOAD (LC1)	MAX. FACTORED VERT. LOAD (LC1)
FR-TO		FROM TO		FR-TO			
A-B	0.35	-91.8	-91.8 0.12 (1)	10.00	K-D	0.335	0.08 (1)
B-C	-1200.0	-91.8	-91.8 0.19 (1)	5.63	K-E	-541.0	0.23 (1)
C-D	-665.0	-91.8	-91.8 0.27 (1)	6.25	C-K	-541.0	0.23 (1)
D-E	-665.0	-91.8	-91.8 0.19 (1)	5.63	N-L	-51.0	0.01 (1)
E-F	-1200.0	-91.8	-91.8 0.19 (1)	5.63	B-L	0.1019	0.23 (1)
F-G	0.35	-91.8	-91.8 0.12 (1)	19.00	J-H	-51.0	0.01 (1)
N-B	-822.0	0.0	0.0 0.08 (1)	7.81	J-F	0.1019	0.23 (1)
H-F	-822.0	0.0	0.0 0.08 (1)	7.81			
N-M	0.44	-18.5	-18.5 0.02 (4)	10.00			
M-L	0.19	0.0	0.0 0.07 (1)	10.00			
L-C	0.73	0.0	0.0 0.08 (1)	10.00			
L-K	0.1061	-18.5	-18.5 0.24 (1)	10.00			
K-J	0.1061	-18.5	-18.5 0.24 (1)	10.00			
I-J	0.19	0.0	0.0 0.07 (1)	10.00			
J-E	0.73	0.0	0.0 0.08 (1)	10.00			
I-H	0.44	-18.5	-18.5 0.02 (4)	10.00			

DESIGN CRITERIA

SPECIFIED LOADS:
TOP CH. LL = 25.6 PSF
DL = 6.0 PSF
BOT CH. LL = 0.0 PSF
DL = 7.4 PSF
TOTAL LOAD = 39.0 PSF

SPACING = 24.0 IN. C/C

THIS TRUSS IS DESIGNED FOR RESIDENTIAL OR SMALL BUILDING REQUIREMENTS OF PART 9, NBC 2015

THIS DESIGN COMPLIES WITH:
- PART 9 OF CBC 2018, ABC 2019
- PART 9 OF OBC 2012 (2019 AMENDMENT)
- CSA 086-14
- TPIC 2014

DESIGN ASSUMPTIONS
- OVERHANG NOT TO BE ALTERED OR CUT OFF.

(55% OF 31.3 P.S.F. G.S.L. PLUS 8.4 P.S.F. RAIN LOAD) EQUALS 25.6 P.S.F. SPECIFIED ROOF LIVE LOAD

ALLOWABLE DEFL.(LL) = L/360 (0.45")
CALCULATED VERT. DEFL.(LL) = L/999 (0.02")
ALLOWABLE DEFL.(TL) = L/360 (0.45")
CALCULATED VERT. DEFL.(TL) = L/999 (0.05")

CSI: TC=0.27/1.00 (D-E:1), BC=0.24/1.00 (K-L:1), WB=0.23/1.00 (C-K:1), SSI=0.17/1.00 (D-E:1)

DOL LUMBER=1.00 NAIL=1.00 LS BEND=1.10
COMP=1.10 SHEAR=1.10 TENS=1.10

COMPANION LIVE LOAD FACTOR = 1.00

AUTOSOLVE HEELS OFF

TRUSS PLATE MANUFACTURER IS NOT RESPONSIBLE FOR QUALITY CONTROL IN THE TRUSS MANUFACTURING PLANT.

NAIL VALUES
PLATE GRIP(DRY) SHEAR SECTION
(PSI) (PLI) (PLI)
MAX MIN MAX MIN MAX MIN
MT20 650 371 1747 788 1987 1873

PLATE PLACEMENT TOL. = 0.250 inches

PLATE ROTATION TOL. = 5.0 Deg.

JSI GRIP= 0.81 (B) (INPUT = 0.90)
JSI METAL= 0.48 (B) (INPUT = 1.00)




Structural component only
DWG# T-2018279

JOB NAME	TRUSS NAME	QUANTITY	PLY	JOB DESC.	GREEN PARK HOMES	DRWG NO.
410169	T10	4	1	TRUSS DESC.		

Tamarack Roof Truss, Burlington

Version 8.330 S May 6 2020 MiTek Industries, Inc. Fri Aug 14 14:45:02 2020 Page 1

ID:W63xGm6okcO0SiyZ4EwBx6zA2m0-SEX6SI9No5dNCzT?9WmWZU8F56toTor8DzWfynvxF



TOTAL WEIGHT = 4 X 101 = 404 lb

LUMBER	N. L. G. A. RULES	CHORDS	SIZE	LUMBER	DESCR.
A - D	2x4	DRY	No.2	SPF	
D - E	2x4	DRY	No.2	SPF	
E - G	2x4	DRY	No.2	SPF	
M - B	2x4	DRY	No.2	SPF	
H - G	2x4	DRY	No.2	SPF	
M - J	2x4	DRY	No.2	SPF	
J - H	2x4	DRY	No.2	SPF	
ALL WEBS	2x3	DRY	No.2	SPF	
EXCEPT					
DRY: SEASONED LUMBER.					

DIMENSIONS, SUPPORTS AND LOADINGS SPECIFIED BY FABRICATOR TO BE VERIFIED BY BUILDING DESIGNER

BEARINGS		FACTORED		MAXIMUM FACTORED		INPUT		REQ'D	
JT	VERT	GROSS REACTION	DOWN	GROSS REACTION	DOWN	BRG	IN-SX	BRG	IN-SX
M	1435	0	1435	0	0	5-8	5-8		
H	1309	0	1309	0	0	1-8	1-8		

UNFACTORED REACTIONS

1ST LCASE	COMBINED	SNOW	LIVE	PERM.LIVE	WIND	DEAD	SOIL
M	1013	678 / 0	0 / 0	0 / 0	0 / 0	335 / 0	0 / 0
H	926	608 / 0	0 / 0	0 / 0	0 / 0	318 / 0	0 / 0

BEARING MATERIAL TO BE SPF NO.2 OR BETTER AT JOINT(S) M, H

BRACING

TOP CHORD TO BE SHEATHED OR MAX. PURLIN SPACING = 4.85 FT.
MAX. UNBRACED BOTTOM CHORD LENGTH = 10.00 FT OR RIGID CEILING DIRECTLY APPLIED.

ALL PITCH BREAKS AND PERIMETER CORNER JOINTS MUST BE LATERALLY RESTRAINED.

LOADING

TOTAL LOAD CASES: (4)

CHORDS				WEBS			
MEMB.	FORCE (LBS)	VERT. LOAD (PLF)	MAX LC1 (CS1 (LC))	MEMB.	FORCE (LBS)	MAX LC1 (CS1 (LC))	UNBRACED LENGTH (FR-TO)
A-B	0 / 35	-91.8	-91.8 0.12 (1)	L-C	-96 / 67	0.04 (1)	10.00
B-C	-1456 / 0	-91.8	-91.8 0.49 (1)	C-K	-509 / 0	0.65 (1)	4.85
C-D	-1070 / 0	-91.8	-91.8 0.45 (1)	K-E	0 / 735	0.17 (1)	5.50
D-E	-1070 / 0	-91.8	-91.8 0.45 (1)	E-F	-446 / 0	0.57 (1)	5.50
E-F	-1068 / 0	-91.8	-91.8 0.43 (1)	F-G	-150 / 46	0.07 (1)	5.54
F-G	-1399 / 0	-91.8	-91.8 0.44 (1)	G-H	0 / 1261	0.28 (1)	4.99
G-H	-1388 / 0	0.0	0.0 0.14 (1)	H-I	0 / 1225	0.28 (1)	6.90
H-I	-1265 / 0	0.0	0.0 0.13 (1)	I-J			7.16
M-L	0 / 0	-18.5	-18.5 0.16 (4)				10.00
L-K	0 / 1242	-18.5	-18.5 0.28 (1)				10.00
K-J	0 / 1195	-18.5	-18.5 0.27 (1)				10.00
J-I	0 / 1195	-18.5	-18.5 0.27 (1)				10.00
I-H	0 / 0	-18.5	-18.5 0.15 (4)				10.00

DESIGN CRITERIA

SPECIFIED LOADS:
TOP CH. LL = 25.6 PSF
DL = 6.0 PSF
BOT CH. LL = 0.0 PSF
DL = 7.4 PSF
TOTAL LOAD = 39.0 PSF

SPACING = 24.0 IN. C/C

THIS TRUSS IS DESIGNED FOR RESIDENTIAL OR SMALL BUILDING REQUIREMENTS OF PART 9, NBC 2015

THIS DESIGN COMPLIES WITH:
- PART 9 OF BCBC 2018, ABC 2019
- PART 9 OF OBC 2012 (2019 AMENDMENT)
- CSA 086-14
- TPIC 2014

(55 % OF 31.3 P.S.F. G.S.L. PLUS 8.4 P.S.F. RAIN LOAD) EQUALS 25.6 P.S.F. SPECIFIED ROOF LIVE LOAD

ALLOWABLE DEFL.(LL)= L/360 (0.79")
CALCULATED VERT. DEFL.(LL)= L/999 (0.04")
ALLOWABLE DEFL.(TL)= L/360 (0.79")
CALCULATED VERT. DEFL.(TL)= L/999 (0.09")

CSI: TC=0.49/1.00 (B-C:1), BC=0.28/1.00 (K-L:1),
WB=0.65/1.00 (C-K:1), SSI=0.23/1.00 (B-C:1)

DOL LUMBER=1.00 NAIL=1.00 LS BEND=1.10
COMP=1.10 SHEAR=1.10 TENS=1.10

COMPANION LIVE LOAD FACTOR = 1.00

TRUSS PLATE MANUFACTURER IS NOT RESPONSIBLE FOR QUALITY CONTROL IN THE TRUSS MANUFACTURING PLANT.

NAIL VALUES
PLATE GRIP(DRY) SHEAR SECTION
(PSI) (PLI) (PLI)
MAX MIN MAX MIN MAX MIN
MT20 650 371 1747 788 1987 1873

PLATE PLACEMENT TOL. = 0.250 inches

PLATE ROTATION TOL. = 5.0 Deg.

JSI GRIP= 0.85 (G) (INPUT = 0.90)
JSI METAL= 0.57 (G) (INPUT = 1.00)



Structural component only
DWG# T-2018280

JOB NAME
410169

TRUSS NAME
G10

QUANTITY
1

PLY
1

JOB DESC.
GREEN PARK HOMES

TRUSS DESC.

DRWG NO.

Tamarack Roof Truss, Burlington

Version 8.330 S May 6 2020 Mitek Industries, Inc. Fri Aug 14 14:44:52 2020 Page 1


ID:W63xGm6okcO0SiYz4EwBx6zA2m0-LjxKML1690Nn?Ri4ZPaA9Njev3laS1JMrfYB9EynvxP

1-3-8 0-0 2-0-8 2-0-0 4-0-8 6-0-8 8-0-8 10-0-8 12-0-8 14-0-8 16-0-8 18-0-8 20-0-8 22-0-8 23-5-8 23-9-0

1-3-8 0-0 2-0-8 2-0-0 4-0-8 6-0-8 8-0-8 10-0-8 12-0-8 14-0-8 16-0-8 18-0-8 20-0-8 22-0-8 23-5-8 23-9-0

4x4 =

Scale = 1:53.2



LUMBER N. L. G. A. RULES CHORDS SIZE A - F 2x4 DRY F - I 2x4 DRY I - O 2x4 DRY AC- B 2x4 DRY P - O 2x4 DRY AC- U 2x4 DRY U - P 2x4 DRY ALL WEBS 2x3 DRY ALL GABLE WEBS 2x3 DRY DRY: SEASONED LUMBER. GABLE STUDS SPACED AT 2-0-0 OC.				DESIGN CRITERIA SPECIFIED LOADS: TOP CH. LL = 25.6 PSF DL = 6.0 PSF BOT CH. LL = 0.0 PSF DL = 7.4 PSF TOTAL LOAD = 39.0 PSF SPACING = 24.0 IN. C/C THIS TRUSS IS DESIGNED FOR RESIDENTIAL OR SMALL BUILDING REQUIREMENTS OF PART 9, NBCC 2015 THIS DESIGN COMPLIES WITH: - PART 9 OF CBC 2018, ABC 2019 - PART 9 OF OBC 2012 (2019 AMENDMENT) - CSA 086-14 - TPIC 2014 (55% OF 31.3 P.S.F. G.S.L. PLUS 8.4 P.S.F. RAIN LOAD) EQUALS 25.6 P.S.F. SPECIFIED ROOF LIVE LOAD CSI: TC=0.12/1.00 (A-B:1), BC=0.02/1.00 (AA-AB:4), WB=0.26/1.00 (H-X:1), SSI=0.08/1.00 (A-B:1) DOL LUMBER=1.00 NAIL=1.00 LS BEND=1.10 COMP=1.10 SHEAR=1.10 TENS=1.10 COMPANION LIVE LOAD FACTOR = 1.00 TRUSS PLATE MANUFACTURER IS NOT RESPONSIBLE FOR QUALITY CONTROL IN THE TRUSS MANUFACTURING PLANT. NAIL VALUES PLATE GRIP(DRY) SHEAR SECTION (PSI) (PLI) (PLI) MAX MIN MAX MIN MAX MIN MT20 650 371 1747 788 1987 1873 PLATE PLACEMENT TOL. = 0.250 inches PLATE ROTATION TOL. = 5.0 Deg. JSI GRIP= 0.54 (AB) (INPUT = 0.90) JSI METAL= 0.11 (H) (INPUT = 1.00)				PLATES (table is in inches) JT TYPE PLATES W LEN Y X B TMVW+p MT20 4.0 4.0 1.25 2.00 C, D, E, G, H, J, K, L, M, N C TMW+w MT20 2.0 4.0 F TS-t MT20 3.0 6.0 I TTW-p MT20 4.0 4.0 2.25 2.00 O TMVW+p MT20 4.0 4.0 1.25 2.00 P BMV1+p MT20 3.0 4.0 Q BMW1+t MT20 4.0 4.0 R, S, T, V, W, X, Y, Z, AA R BMW1+w MT20 2.0 4.0 U BS-t MT20 3.0 6.0 AB BMW1+t MT20 4.0 4.0 AC BMV1+p MT20 3.0 4.0				BEARINGS THIS TRUSS DESIGNED FOR CONTINUOUS BEARINGS. THIS TRUSS REQUIRES RIGID SHEATHING ON EXPOSED FACE. BEARING MATERIAL TO BE SPF NO.2 OR BETTER AT JOINT(S) BRACING TOP CHORD TO BE SHEATHED OR MAX. PURLIN SPACING = 6.25 FT. MAX. UNBRACED BOTTOM CHORD LENGTH = 10.00 FT OR RIGID CEILING DIRECTLY APPLIED. ALL PITCH BREAKS AND PERIMETER CORNER JOINTS MUST BE Laterally RESTRAINED. 1 LATERAL BRACE(S) AT 1/2 LENGTH OF I-W. END VERTICAL(S) MUST BE SHEATHED OR HAVE BRACES AS INDICATED IN THE MAX. UNBRACED LENGTH COLUMN OF THE TABLE BELOW LOADING TOTAL LOAD CASES: (4) CHORDS MEMB. MAX. FACTORED FORCE (LBS) FACTORED VERT. LOAD LC1 (PLF) MAX UNBRACED LENGTH FR-TO FROM TO CSI (LC) A-B 0/35 -91.8 -91.8 0.12 (1) 10.00 B-C -32/0 -91.8 -91.8 0.05 (1) 6.25 C-D -36/0 -91.8 -91.8 0.05 (1) 6.25 D-E -29/0 -91.8 -91.8 0.04 (1) 6.25 E-F -26/0 -91.8 -91.8 0.04 (1) 6.25 F-G -26/0 -91.8 -91.8 0.04 (1) 6.25 G-H -21/0 -91.8 -91.8 0.05 (1) 6.25 H-I -31/0 -91.8 -91.8 0.05 (1) 6.25 I-J -31/0 -91.8 -91.8 0.05 (1) 6.25 J-K -21/0 -91.8 -91.8 0.05 (1) 6.25 K-L -26/0 -91.8 -91.8 0.04 (1) 6.25 L-M -29/0 -91.8 -91.8 0.04 (1) 6.25 M-N -34/0 -91.8 -91.8 0.04 (1) 6.25 N-O -31/0 -91.8 -91.8 0.04 (1) 6.25 AC-B -239/0 0.0 0.0 0.02 (1) 7.81 P-O -105/0 0.0 0.0 0.01 (1) 7.81 WEBS MEMB. MAX. FACTORED FORCE (LBS) MAX UNBRACED LENGTH FR-TO FROM TO CSI (LC) W-I -132/0 0.08 (1) X-H -208/0 0.26 (1) Y-G -177/0 0.14 (1) Z-E -183/0 0.08 (1) AA-D -176/0 0.04 (1) AB-C -200/0 0.03 (1) V-J -208/0 0.26 (1) T-K -177/0 0.14 (1) S-L -182/0 0.08 (1) R-M -181/0 0.05 (1) Q-N -180/0 0.03 (1) Q-O 0/43 0.01 (1) B-AB 0/40 0.01 (1) AC-AB 0/0 -18.5 -18.5 0.02 (4) 10.00 AB-AA 0/28 -18.5 -18.5 0.02 (4) 10.00 AA-Z 0/24 -18.5 -18.5 0.02 (4) 10.00 Z-Y 0/21 -18.5 -18.5 0.02 (4) 10.00 Y-X 0/19 -18.5 -18.5 0.02 (4) 10.00 X-W 0/17 -18.5 -18.5 0.02 (4) 10.00 W-V 0/17 -18.5 -18.5 0.02 (4) 10.00 V-U 0/19 -18.5 -18.5 0.02 (4) 10.00 U-T 0/19 -18.5 -18.5 0.02 (4) 10.00 T-S 0/21 -18.5 -18.5 0.02 (4) 10.00 S-R 0/24 -18.5 -18.5 0.02 (4) 10.00 R-Q 0/28 -18.5 -18.5 0.02 (4) 10.00 Q-P 0/0 -18.5 -18.5 0.02 (4) 10.00				DESIGN CRITERIA TOTAL WEIGHT = 114 lb [M]			
--	--	--	--	--	--	--	--	---	--	--	--	---	--	--	--	---	--	--	--




Structural component only
DWG# T-2018271

JOB NAME	TRUSS NAME	QUANTITY	PLY	JOB DESC.	GREEN PARK HOMES	DRWG NO.
410169	T11	2	1	TRUSS DESC.		

Tamarack Roof Truss, Burlington

Version 8.330 S May 6 2020 MiTek Industries, Inc. Fri Aug 14 14:45:03 2020 Page 1
ID:W63xGm6okcO0SiyZ4EwBx6zA2m0-wQ5Uf5A?ZPIEq72BiDHl6igW4VUzX4v_NtiG25ynvxE

Scale = 1:16.8



LUMBER	N. L. G. A. RULES	CHORDS	SIZE	LUMBER	DESCR.
A - C	2x4 DRY	No.2	SPF		
C - D	2x4 DRY	No.2	SPF		
D - F	2x4 DRY	No.2	SPF		
B - E	2x4 DRY	No.2	SPF		
ALL WEBS	2x3 DRY	No.2	SPF		
DRY: SEASONED LUMBER.					

PLATES (table is in inches)

JT	TYPE	PLATES	W	LEN	Y	X
B	TMBH1-m	MT20	4.0	6.0	2.00	0.25
C	TTWW-m	MT20	5.0	6.0	2.25	1.75
D	TTW-m	MT20	4.0	4.0		
E	TMBH1-m	MT20	4.0	6.0	2.00	0.25
G	BMWw-t	MT20	4.0	4.0		
H	BMW+w	MT20	2.0	4.0		

DIMENSIONS, SUPPORTS AND LOADINGS SPECIFIED BY FABRICATOR TO BE VERIFIED BY BUILDING DESIGNER

BEARINGS	FACTORED GROSS REACTION	MAXIMUM FACTORED GROSS REACTION	INPUT BRG	REQD BRG	HEEL WEDGE
JT	VERT	HORZ	DOWN	HORZ	UPLIFT
B	573	0	573	0	0
E	573	0	573	0	0

UNFACTORED REACTIONS

1ST LCASE	COMBINED	SNOW	LIVE	PERM.LIVE	WIND	DEAD	SOIL
B	404	275.0	0.0	0.0	0.0	129.0	0.0
E	404	275.0	0.0	0.0	0.0	129.0	0.0

BEARING MATERIAL TO BE SPF NO.2 OR BETTER AT JOINT(S) B, E

BRACING

TOP CHORD TO BE SHEATHED OR MAX. PURLIN SPACING = 6.25 FT.
MAX. UNBRACED BOTTOM CHORD LENGTH = 10.00 FT OR RIGID CEILING DIRECTLY APPLIED.

ALL PITCH BREAKS AND PERIMETER CORNER JOINTS MUST BE Laterally RESTRAINED.

LOADING

TOTAL LOAD CASES: (7)

MEMB.	CHORDS MAX. FACTORED FORCE (LBS)	FACTORED VERT. LOAD LC1 (PLF)	MAX. CS1 (LC)	MAX. UNBRAC LENGTH	MEMB.	WEBS MAX. FACTORED FORCE (LBS)	MAX. CS1 (LC)
FR-TO		FROM	TO		FR-TO		
A-B	0.16	-91.8	-91.8	0.13 (1)	10.00	H-C	0.55
B-J	-818.0	-91.8	-91.8	0.02 (1)	6.25	C-G	0.0
J-C	-772.0	-91.8	-91.8	0.04 (1)	6.25	G-D	0.56
C-D	-728.0	-91.8	-91.8	0.09 (1)	6.25	I-J	-16.23
D-L	-773.0	-91.8	-91.8	0.04 (1)	6.25	K-L	-16.23
L-E	-818.0	-91.8	-91.8	0.02 (1)	6.25		
E-F	0.16	-91.8	-91.8	0.13 (1)	10.00		
B-I	0.722	-18.5	-18.5	0.15 (1)	10.00		
I-M	0.722	-18.5	-18.5	0.15 (1)	10.00		
M-H	0.722	-18.5	-18.5	0.15 (1)	10.00		
H-G	0.728	-18.5	-18.5	0.16 (1)	10.00		
G-N	0.723	-18.5	-18.5	0.15 (1)	10.00		
N-K	0.723	-18.5	-18.5	0.15 (1)	10.00		
K-E	0.723	-18.5	-18.5	0.15 (1)	10.00		

FACTORED CONCENTRATED LOADS (LBS)

JT	LOC.	LC1	MAX-	MAX+	FACE	DIR.	TYPE	HEEL	CONN.
C	2-4-8	-51	-51		FRONT	VERT	TOTAL		C1
D	4-6-8	-51	-51		FRONT	VERT	TOTAL		C1
G	4-5-12	-26	-26		FRONT	VERT	TOTAL		C1
H	2-5-4	-26	-26		FRONT	VERT	TOTAL		C1
M	1-11-4	9	1	23	FRONT	VERT	TOTAL		C1
N	4-11-12	9	1	23	FRONT	VERT	TOTAL		C1

CONNECTION REQUIREMENTS

1) C1: A SUITABLE HANGER/MECHANICAL CONNECTION IS REQUIRED.

DESIGN CRITERIA

SPECIFIED LOADS:

TOP CH.	LL	=	25.6	PSF
	DL	=	6.0	PSF
BOT CH.	LL	=	0.0	PSF
	DL	=	7.4	PSF
TOTAL LOAD		=	39.0	PSF

SPACING = 24.0 IN. C/C

LOADING IN FLAT SECTION BASED ON A SLOPE OF 6.00/12

THIS TRUSS IS DESIGNED FOR RESIDENTIAL OR SMALL BUILDING REQUIREMENTS OF PART 9, NBCC 2015

THIS DESIGN COMPLIES WITH:

- PART 9 OF BCBC 2018, ABC 2019
- PART 9 OF OBC 2012 (2019 AMENDMENT)
- CSA 086-14
- TPIC 2014

(55% OF 31.3 P.S.F. G.S.L. PLUS 8.4 P.S.F. RAIN LOAD) EQUALS 25.6 P.S.F. SPECIFIED ROOF LIVE LOAD

ALLOWABLE DEFL.(LL) = $L/360$ (0.23")
CALCULATED VERT. DEFL.(LL) = $L/999$ (0.01")
ALLOWABLE DEFL.(TL) = $L/360$ (0.23")
CALCULATED VERT. DEFL.(TL) = $L/999$ (0.02")

CSI: TC=0.13/1.00 (E-F:1), BC=0.16/1.00 (G-H:1), WB=0.02/1.00 (D-G:4), SSI=0.10/1.00 (A-B:1)

DOL LUMBER=1.00 NAIL=1.00 LS BEND=1.00
COMP=1.00 SHEAR=1.00 TENS=1.00

COMPANION LIVE LOAD FACTOR = 1.00


TRUSS PLATE MANUFACTURER IS NOT RESPONSIBLE FOR QUALITY CONTROL IN THE TRUSS MANUFACTURING PLANT.

NAIL VALUES
PLATE GRIP(DRY) SHEAR SECTION
(PSI) (PLI) (PLI)
MAX MIN MAX MIN MAX MIN
MT20 650 371 1747 788 1987 1873

PLATE PLACEMENT TOL. = 0.250 inches

PLATE ROTATION TOL. = 5.0 Deg.

JSI GRIP= 0.39 (D) (INPUT = 0.90)
JSI METAL= 0.18 (E) (INPUT = 1.00)




Structural component only
DWG# T-2018281

JOB NAME	TRUSS NAME	QUANTITY	PLY	JOB DESC.	GREEN PARK HOMES	DRWG NO.
410169	T12	2	1	TRUSS DESC.		

Tamarack Roof Truss, Burlington

Version 8.330 S May 6 2020 MiTek Industries, Inc. Fri Aug 14 14:45:04 2020 Page 1
ID:W63xGm6okcO0SiyZ4EwBx6zA2m0-OdftrRBdKit4SHcNGxo_evDh?vp3GXv7cXSqaXynvxD



Scale = 1:16.6

LUMBER N. L. G. A. RULES CHORDS SIZE LUMBER DESCR. TOTAL WEIGHT = 2 X 22 = 45 lb [M/F]

A - C	2x4	DRY	No.2	SPF
C - E	2x4	DRY	No.2	SPF
B - D	2x4	DRY	No.2	SPF
ALL WEBS	2x3	DRY	No.2	SPF
DRY: SEASONED LUMBER.				

PLATES (table is in inches)

JT	TYPE	PLATES	W	LEN	Y	X
B	TMBH1-m	MT20	4.0	6.0	2.00	0.25
C	TTW-p	MT20	4.0	4.0		
D	TMBH1-m	MT20	4.0	6.0	2.00	0.25
F	BMW +w	MT20	2.0	4.0		

DIMENSIONS, SUPPORTS AND LOADINGS SPECIFIED BY FABRICATOR TO BE VERIFIED BY BUILDING DESIGNER

BEARINGS		FACTORED		MAXIMUM FACTORED		INPUT		REQ'D		HEEL	
JT	GROSS REACTION	VERT	HORZ	GROSS REACTION	DOWN	HORZ	UPLIFT	BRG	IN-SX	WEDGE	
B	505	0	0	505	0	0	0	5-8	5-8	2x4 L	
D	505	0	0	505	0	0	0	5-8	5-8	2x4 R	

UNFACTORED REACTIONS

JT	COMBINED	SNOW	LIVE	PERM. LIVE	WIND	DEAD	SOIL
B	354	246 / 0	0 / 0	0 / 0	0 / 0	109 / 0	0 / 0
D	354	246 / 0	0 / 0	0 / 0	0 / 0	109 / 0	0 / 0

BEARING MATERIAL TO BE SPF NO.2 OR BETTER AT JOINT(S) B, D

BRACING

TOP CHORD TO BE SHEATHED OR MAX. PURLIN SPACING = 6.25 FT.
MAX. UNBRACED BOTTOM CHORD LENGTH = 10.00 FT OR RIGID CEILING DIRECTLY APPLIED.

ALL PITCH BREAKS AND PERIMETER CORNER JOINTS MUST BE LATERALLY RESTRAINED.

LOADING

TOTAL LOAD CASES: (4)

CHORDS				WEBS			
MEMB.	MAX. FACTORED FORCE (LBS)	FACTORED VERT. LOAD (PLF)	MAX. LC1 (LC)	MEMB.	MAX. FACTORED FORCE (LBS)	MAX. UNBRACED LENGTH	MAX. LC1 (LC)
FR-TO		FROM TO		FR-TO			
A-B	0 / 16	-91.8	-91.8 0.12 (1)	10.00	F-C	0 / 138	0.03 (1)
B-H	-558 / 0	-91.8	-91.8 0.01 (4)	6.25	G-H	-86 / 7	0.00 (1)
H-C	-528 / 0	-91.8	-91.8 0.09 (1)	6.25	I-J	-86 / 7	0.00 (1)
C-J	-528 / 0	-91.8	-91.8 0.09 (1)	6.25			
J-D	-558 / 0	-91.8	-91.8 0.01 (4)	6.25			
D-E	0 / 16	-91.8	-91.8 0.12 (1)	10.00			
B-G	0 / 494	-18.5	-18.5 0.17 (1)	10.00			
G-F	0 / 494	-18.5	-18.5 0.17 (1)	10.00			
F-I	0 / 494	-18.5	-18.5 0.17 (1)	10.00			
I-D	0 / 494	-18.5	-18.5 0.17 (1)	10.00			

DESIGN CRITERIA

SPECIFIED LOADS:
TOP CH. LL = 25.6 PSF
DL = 6.0 PSF
BOT CH. LL = 0.0 PSF
DL = 7.4 PSF
TOTAL LOAD = 39.0 PSF

SPACING = 24.0 IN. C/C

THIS TRUSS IS DESIGNED FOR RESIDENTIAL OR SMALL BUILDING REQUIREMENTS OF PART 9, NBC 2015

THIS DESIGN COMPLIES WITH:
- PART 9 OF BCBC 2018, ABC 2019
- PART 9 OF OBC 2012 (2019 AMENDMENT)
- CSA 086-14
- TPIC 2014

(55 % OF 31.3 P.S.F. G.S.L. PLUS 8.4 P.S.F. RAIN LOAD) EQUALS 25.6 P.S.F. SPECIFIED ROOF LIVE LOAD

ALLOWABLE DEFL.(LL) = L/360 (0.23")
CALCULATED VERT. DEFL.(LL) = L/999 (0.01")
ALLOWABLE DEFL.(TL) = L/360 (0.23")
CALCULATED VERT. DEFL.(TL) = L/999 (0.02")

CSI: TC=0.12/1.00 (A-B:1), BC=0.17/1.00 (F-I:1),
WB=0.03/1.00 (C-F:1), SSI=0.09/1.00 (A-B:1)

DOL LUMBER=1.00 NAIL=1.00 LS BEND=1.10
COMP=1.10 SHEAR=1.10 TENS=1.10

COMPANION LIVE LOAD FACTOR = 1.00

TRUSS PLATE MANUFACTURER IS NOT RESPONSIBLE FOR QUALITY CONTROL IN THE TRUSS MANUFACTURING PLANT.

NAIL VALUES
PLATE GRIP(DRY) SHEAR SECTION
(PSI) (PLI) (PLI)
MAX MIN MAX MIN MAX MIN
MT20 650 371 1747 788 1987 1873

PLATE PLACEMENT TOL. = 0.250 inches

PLATE ROTATION TOL. = 5.0 Deg.

JSI GRIP= 0.24 (D) (INPUT = 0.90)
JSI METAL= 0.13 (B) (INPUT = 1.00)




Structural component only
DWG# T-2018282

JOB NAME	TRUSS NAME	QUANTITY	PLY	JOB DESC.	GREEN PARK HOMES	DRWG NO.
410169	T13	1	2	TRUSS DESC.		

Tamarack Roof Truss, Burlington

Version 8.330 S May 6 2020 MiTek Industries, Inc. Fri Aug 14 14:45:05 2020 Page 1
ID:W63xGm6okcO0SiyZ4EwBx6zA2m0-spDF4nBF50?x3RBAqeJDB7mpw11e?_eHqBCN6_ynvxC

Scale = 1:23.4



LUMBER	N. L. G. A. RULES	CHORDS	SIZE	LUMBER	DESCR.
D - A	2x6	DRY	No.2	SPF	
A - B	2x4	DRY	No.2	SPF	
C - B	2x4	DRY	No.2	SPF	
D - C	2x6	DRY	No.2	SPF	
ALL WEBS	2x3	DRY	No.2	SPF	
DRY:	SEASONED LUMBER.				

DESIGN CONSISTS OF 2 TRUSSES BUILT SEPARATELY THEN FASTENED TOGETHER AS FOLLOWS:

CHORDS #ROWS	SURFACE SPACING (IN)	LOAD(PLF)
TOP CHORDS : (0.122"x3") SPIRAL NAILS		
D - A 2	12	TOP
A - B 1	12	TOP
B - C 1	12	TOP
BOTTOM CHORDS : (0.122"x3") SPIRAL NAILS		
D - C 2	12	SIDE(0.0)
WEBS : (0.122"x3") SPIRAL NAILS		
2x3 1	6	

NAILS TO BE DRIVEN FROM ONE SIDE ONLY.

GIRDER NAILING ASSUMES NAILED HANGERS ARE FASTENED WITH MIN. 3-0 INCH NAILS.

TOP - COMPONENTS ARE LOADED FROM THE TOP AND MUST BE PLACED ON TOP EDGE OF ALL PLIES FOR THE LOAD TO BE TRANSFERRED TO EACH PLY.

SIDE - PLF SHOWN IS THE EQUIVALENT UDL APPLIED TO ONE SIDE THAT THE CORRESPONDING NAILING PATTERN SHALL BE CAPABLE OF TRANSFERRING. REMAINING PLF MUST BE APPLIED ON THE OPPOSITE SIDE OR ON THE TOP.

PLATES (table is in inches)	JT TYPE	PLATES	W	LEN	Y	X
A	TMVW-p	MT20	4.0	6.0	1.00	3.00
B	TMV-p	MT20	3.0	4.0		
C	BMVW1+p	MT20	4.0	6.0		
D	BMV1+p	MT20	3.0	6.0		

DIMENSIONS, SUPPORTS AND LOADINGS SPECIFIED BY FABRICATOR TO BE VERIFIED BY BUILDING DESIGNER

BEARINGS	FACTORED	MAXIMUM FACTORED	INPUT	REQD
GROSS REACTION	GROSS REACTION	BRG	BRG	
JT VERT HORZ	DOWN HORZ UPLIFT	IN-SX	IN-SX	
D 1039 0	1039 0 0	5-8	5-8	
C 1303 0	1303 0 0	MECHANICAL		

A SUITABLE HANGER/MECHANICAL CONNECTION IS REQUIRED AT JOINT C. MINIMUM BEARING LENGTH AT JOINT C = 2-0.

UNFACTORED REACTIONS

1ST LCASE	MAX./MIN. COMPONENT REACTIONS						
JT COMBINED	SNOW	LIVE	PERM.LIVE	WIND	DEAD	SOIL	
D 731	499 / 0	0 / 0	0 / 0	0 / 0	232 / 0	0 / 0	
C 917	628 / 0	0 / 0	0 / 0	0 / 0	289 / 0	0 / 0	

BEARING MATERIAL TO BE SPF NO.2 OR BETTER AT JOINT(S) D

BRACING

TOP CHORD TO BE SHEATHED OR MAX. PURLIN SPACING = 10.00 FT.
MAX. UNBRACED BOTTOM CHORD LENGTH = 10.00 FT OR RIGID CEILING DIRECTLY APPLIED.

ALL PITCH BREAKS AND PERIMETER CORNER JOINTS MUST BE Laterally RESTRAINED.

LOADING

TOTAL LOAD CASES: (4)

CHORDS	MAX. FACTORED	FACTORED	WEBS	MAX. FACTORED
MEMB.	FORCE (LBS)	VERT. LOAD LC1 MAX (PLF)	CS1 (LC)	UNBRAC LENGTH FR-TO
FR-TO		FROM	TO	
D-A	-270 / 0	0.0	0.0 0.01 (1)	7.81
A-B	0 / 0	-91.8	-91.8 0.30 (1)	10.00
C-B	-270 / 0	0.0	0.0 0.03 (1)	7.81
D-E	0 / 0	-18.5	-18.5 0.66 (1)	10.00
E-F	0 / 0	-18.5	-18.5 0.66 (1)	10.00
F-C	0 / 0	-18.5	-18.5 0.66 (1)	10.00

FACTORED CONCENTRATED LOADS (LBS)

JT	LOC.	LC1	MAX-	MAX+	FACE	DIR.	TYPE	HEEL	CONN.
E	2-4-12	-847	-847	---	BACK	VERT	TOTAL	---	C1
F	4-4-12	-847	-847	---	BACK	VERT	TOTAL	---	C1

CONNECTION REQUIREMENTS

1) C1: A SUITABLE HANGER/MECHANICAL CONNECTION IS REQUIRED.

TOTAL WEIGHT = 2 X 27 = 55 lb

DESIGN CRITERIA

SPECIFIED LOADS:
TOP CH. LL = 25.6 PSF
DL = 6.0 PSF
BOT CH. LL = 0.0 PSF
DL = 7.4 PSF
TOTAL LOAD = 39.0 PSF

SPACING = 24.0 IN. C/C

THIS TRUSS IS DESIGNED FOR RESIDENTIAL OR SMALL BUILDING REQUIREMENTS OF PART 9, NBCC 2015

THIS DESIGN COMPLIES WITH:
- PART 9 OF BCBC 2018, ABC 2019
- PART 9 OF OBC 2012 (2019 AMENDMENT)
- CSA 086-14
- TPIC 2014

(55 % OF 31.3 P.S.F. G.S.L. PLUS 8.4 P.S.F. RAIN LOAD) EQUALS 25.6 P.S.F. SPECIFIED ROOF LIVE LOAD

ALLOWABLE DEFL.(LL)= L/360 (0.20")
CALCULATED VERT. DEFL.(LL) = L/814 (0.09")
ALLOWABLE DEFL.(TL)= L/360 (0.20")
CALCULATED VERT. DEFL.(TL) = L/440 (0.16")

CSI: TC=0.30/1.00 (A-B:1), BC=0.66/1.00 (C-D:1), WB=0.00/1.00 (A-C:1), SSI=0.34/1.00 (C-D:1)

DOL LUMBER=1.00 NAIL=1.00 LS BEND=1.00
COMP=1.00 SHEAR=1.00 TENS=1.00

COMPANION LIVE LOAD FACTOR = 1.00

TRUSS PLATE MANUFACTURER IS NOT RESPONSIBLE FOR QUALITY CONTROL IN THE TRUSS MANUFACTURING PLANT.

NAIL VALUES
PLATE GRIP(DRY) SHEAR SECTION
(PSI) (PLI) (PLI)
MAX MIN MAX MIN MAX MIN
MT20 650 371 1747 788 1987 1873

PLATE PLACEMENT TOL. = 0.250 inches


PLATE ROTATION TOL. = 5.0 Deg.

JSI GRIP= 0.06 (A) (INPUT = 0.90)
JSI METAL= 0.04 (B) (INPUT = 1.00)



Structural component only
DWG# T-2018283

JOB NAME	TRUSS NAME	QUANTITY	PLY	JOB DESC.	DRWG NO.
410172	T20	2	2	GREEN PARK HOMES	
Tamarack Roof Truss, Burlington					
Version 8.330 S May 6 2020 MTEK Industries, Inc. Thu Jul 30 08:32:20 2020 Page 1					
ID:W63xGm6okcO0SiYz4EwBx6zA2m0-e1zuA2KAvKva?_bMvxTIDbadvM3WMfUUG6eHwysxof					
23-7-0					
Scale = 1:36.7					



LUMBER	CHORDS	SIZE	LUMBER	DESCR.
N. L. G. A. RULES	L - A	2x6	DRY	No.2
	A - D	2x6	DRY	No.2
	D - F	2x6	DRY	No.2
	G - F	2x6	DRY	No.2
	L - J	2x6	DRY	No.2
	J - G	2x6	DRY	No.2

ALL WEBS 2x3 DRY: SEASONED LUMBER. No.2

DESIGN CONSISTS OF 2 TRUSSES BUILT SEPARATELY THEN FASTENED TOGETHER AS FOLLOWS:

CHORDS #ROWS	SURFACE SPACING (IN)	LOAD (PLF)
TOP CHORDS : (0.122"x3") SPIRAL NAILS		
L - A	2 12	TOP
A - D	2 12	SIDE(0.0)
D - F	2 12	SIDE(183.1)
F - G	2 12	TOP
BOTTOM CHORDS : (0.122"x3") SPIRAL NAILS		
L - J	2 12	SIDE(0.0)
J - G	2 12	SIDE(183.1)
WEBS : (0.122"x3") SPIRAL NAILS		
2x3	1 6	

NAILS TO BE DRIVEN FROM ONE SIDE ONLY.

GIRDER NAILING ASSUMES NAILED HANGERS ARE FASTENED WITH MIN. 3-0 INCH NAILS.

TOP - COMPONENTS ARE LOADED FROM THE TOP AND MUST BE PLACED ON TOP EDGE OF ALL PLIES FOR THE LOAD TO BE TRANSFERRED TO EACH PLY.

SIDE - PLF SHOWN IS THE EQUIVALENT UDL APPLIED TO ONE SIDE THAT THE CORRESPONDING NAILING PATTERN SHALL BE CAPABLE OF TRANSFERRING. REMAINING PLF MUST BE APPLIED ON THE OPPOSITE SIDE OR ON THE TOP.

PLATES (table is in inches)	JT	TYPE	PLATES	W	LEN	Y	X
A	TMVW-t	MT20	5.0	8.0			
B	TMVW-t	MT20	5.0	6.0			

DIMENSIONS, SUPPORTS AND LOADINGS SPECIFIED BY FABRICATOR TO BE VERIFIED BY BUILDING DESIGNER

BEARINGS				FACTORED				MAXIMUM FACTORED				INPUT				RECORD			
JT	GROSS REACTION	VERT	HORZ	JT	GROSS REACTION	VERT	HORZ	JT	GROSS REACTION	VERT	HORZ	JT	GROSS REACTION	VERT	HORZ	JT	GROSS REACTION	VERT	HORZ
L	2077	0	0	L	2077	0	0	L	2077	0	0	L	2077	0	0	L	2077	0	0
G	2210	0	0	G	2210	0	0	G	2210	0	0	G	2210	0	0	G	2210	0	0

UNFACTORED REACTIONS							
JT	COMBINED	SNOW	LIVE	PERM.LIVE	WIND	DEAD	SOIL
L	1471	953 / 0	0 / 0	0 / 0	0 / 0	518 / 0	0 / 0
G	1565	1013 / 0	0 / 0	0 / 0	0 / 0	552 / 0	0 / 0

BEARING MATERIAL TO BE SPF NO.2 OR BETTER AT JOINT(S) L, G

BRACING
TOP CHORD TO BE SHEATHED OR MAX. PURLIN SPACING = 5.77 FT.
MAX. UNBRACED BOTTOM CHORD LENGTH = 10.00 FT OR RIGID CEILING DIRECTLY APPLIED.

ALL PITCH BREAKS AND PERIMETER CORNER JOINTS MUST BE LATERALLY RESTRAINED.

LOADING
TOTAL LOAD CASES: (4)

CHORDS				WEBS			
MEMB.	MAX. FACTORED FORCE (LBS)	FACTORED VERT. LOAD (PLF)	MAX. UNBRACED LENGTH (FT)	MEMB.	MAX. FACTORED FORCE (LBS)	FACTORED VERT. LOAD (PLF)	MAX. UNBRACED LENGTH (FT)
FR-TO				FR-TO			
L - A	-1995 / 0	0.0	0.0 0.15 (1)	H - F	0 / 3197	0.40 (1)	7.81
A - M	-2749 / 0	-91.8	-91.8 0.20 (1)	A - K	0 / 3206	0.40 (1)	7.81
M - N	-2749 / 0	-91.8	-91.8 0.20 (1)	H - E	-1443 / 0	0.17 (1)	7.81
N - O	-2749 / 0	-91.8	-91.8 0.20 (1)	K - B	-1447 / 0	0.17 (1)	7.81
O - B	-2749 / 0	-91.8	-91.8 0.21 (1)	E - I	0 / 867	0.11 (1)	7.81
B - P	-3473 / 0	-91.8	-91.8 0.21 (1)	B - I	0 / 858	0.11 (1)	7.81
P - Q	-3473 / 0	-91.8	-91.8 0.21 (1)	I - C	-764 / 0	0.09 (1)	7.81
Q - R	-3473 / 0	-91.8	-91.8 0.21 (1)				
R - C	-3473 / 0	-91.8	-91.8 0.21 (1)				
C - S	-3473 / 0	-91.8	-91.8 0.19 (1)				
S - T	-3473 / 0	-91.8	-91.8 0.19 (1)				
T - D	-3473 / 0	-91.8	-91.8 0.19 (1)				
D - E	-3473 / 0	-91.8	-91.8 0.19 (1)				
E - U	-2741 / 0	-91.8	-91.8 0.19 (1)				
U - V	-2741 / 0	-91.8	-91.8 0.19 (1)				
V - F	-2741 / 0	-91.8	-91.8 0.19 (1)				
G - F	-2102 / 0	0.0	0.0 0.15 (1)				

FACTORED CONCENTRATED LOADS (LBS)			
JT	LOC.	LC1	MAX. MAX+
E	17-4-12	-110	-110
F	23-7-0	-148	-148
G	23-7-0	-34	-34
H	17-4-12	-26	-26
J	7-4-12	-26	-26
M	1-4-12	-110	-110
N	3-4-12	-110	-110
O	5-4-12	-110	-110

JT	LOC.	LC1	MAX. MAX+	FACE	DIR.	TYPE	HEEL	CONN.
E	17-4-12	-110	-110	FRONT	VERT	TOTAL	---	C1
F	23-7-0	-148	-148	FRONT	VERT	TOTAL	---	C1
G	23-7-0	-34	-34	FRONT	VERT	TOTAL	---	C1
H	17-4-12	-26	-26	FRONT	VERT	TOTAL	---	C1
J	7-4-12	-26	-26	FRONT	VERT	TOTAL	---	C1
M	1-4-12	-110	-110	FRONT	VERT	TOTAL	---	C1
N	3-4-12	-110	-110	FRONT	VERT	TOTAL	---	C1
O	5-4-12	-110	-110	FRONT	VERT	TOTAL	---	C1

DESIGN CRITERIA

SPECIFIED LOADS:
TOP CH. LL = 25.6 PSF
DL = 6.0 PSF
BOT CH. LL = 0.0 PSF
DL = 7.4 PSF
TOTAL LOAD = 39.0 PSF

SPACING = 24.0 IN. C/C

LOADING IN FLAT SECTION BASED ON A SLOPE OF 6.00/12

THIS TRUSS IS DESIGNED FOR RESIDENTIAL OR SMALL BUILDING REQUIREMENTS OF PART 9, NBCC 2015

THIS DESIGN COMPLIES WITH:
- PART 9 OF BCBC 2018, ABC 2019
- PART 9 OF OBC 2012 (2019 AMENDMENT)
- CSA 086-14
- TPIC 2014

(55% OF 31.3 P.S.F. G.S.L. PLUS 8.4 P.S.F. RAIN LOAD) EQUALS 25.6 P.S.F. SPECIFIED ROOF LIVE LOAD

ALLOWABLE DEFL.(LL)= L/360 (0.79")
CALCULATED VERT. DEFL.(LL)= L/999 (0.06")
ALLOWABLE DEFL.(TL)= L/360 (0.79")
CALCULATED VERT. DEFL.(TL)= L/999 (0.12")

CSI: TC=0.21/1.00 (B-C:1), BC=0.22/1.00 (H-K:1), WB=0.40/1.00 (A-K:1), SS=0.18/1.00 (A-B:1)

DOL LUMBER=1.00 NAIL=1.00 LS BEND=1.00 COMP=1.00 SHEAR=1.00 TENS=1.00

COMPANION LIVE LOAD FACTOR = 1.00

TRUSS PLATE MANUFACTURER IS NOT RESPONSIBLE FOR QUALITY CONTROL IN THE TRUSS MANUFACTURING PLANT

NAIL VALUES
PLATE GRIP(DRY) SHEAR SECTION (PSI) (PLI) (PLI)
MAX MIN MAX MIN MAX MIN
MT20 650 371 1747 788 1987 1873

PLATE PLACEMENT TOL. = 0.250 inches

PLATE ROTATION TOL. = 5.0 Deg.

JSI GRIP= 0.61 (K) (INPUT = 0.90)
JSI METAL= 0.31 (H) (INPUT = 1.00)



Structural component only
DWG# T-2016975 /L

JOB NAME	TRUSS NAME	QUANTITY	PLY	JOB DESC.	GREEN PARK HOMES	DRWG NO.
410172	T20	2	2	TRUSS DESC.		

Tamarack Roof Truss, Burlington

Version 8.330 S May 6 2020 MiTek Industries, Inc. Thu Jul 30 08:32:20 2020 Page 2
ID:W63xGm6okcO0SiYz4EwBx6zA2m0-e1zuA2KAvKva? bMvxTIDbadvM3WMfUUG6eoHwysxof

PLATES (table is in inches)

JT	TYPE	PLATES	W	LEN	Y	X
C	TMW-w	MT20	3.0	6.0		
D	TS-t	MT20	5.0	6.0		
E	TMWW-t	MT20	5.0	6.0		
F	TMWW-t	MT20	5.0	8.0		
G	BMV1+p	MT20	3.0	6.0		
H	BMWW-t	MT20	5.0	6.0	2.50	2.50
I	BMWW-t	MT20	5.0	8.0		
J	BS-t	MT20	5.0	6.0		
K	BMWW-t	MT20	5.0	6.0	2.50	2.50
L	BMV1+p	MT20	3.0	6.0		

FACTORED CONCENTRATED LOADS (LBS)

JT	LOC.	LC1	MAX-	MAX+	FACE	DIR.	TYPE	HEEL	CONN.
P	7-4-12	-110	-110	---	FRONT	VERT	TOTAL	---	C1
Q	9-4-12	-110	-110	---	FRONT	VERT	TOTAL	---	C1
R	11-4-12	-110	-110	---	FRONT	VERT	TOTAL	---	C1
S	13-4-12	-110	-110	---	FRONT	VERT	TOTAL	---	C1
T	15-4-12	-110	-110	---	FRONT	VERT	TOTAL	---	C1
U	19-4-12	-110	-110	---	FRONT	VERT	TOTAL	---	C1
V	21-4-12	-110	-110	---	FRONT	VERT	TOTAL	---	C1
W	1-4-12	-26	-26	---	FRONT	VERT	TOTAL	---	C1
X	3-4-12	-26	-26	---	FRONT	VERT	TOTAL	---	C1
Y	5-4-12	-26	-26	---	FRONT	VERT	TOTAL	---	C1
Z	9-4-12	-26	-26	---	FRONT	VERT	TOTAL	---	C1
AA	11-4-12	-26	-26	---	FRONT	VERT	TOTAL	---	C1
AB	13-4-12	-26	-26	---	FRONT	VERT	TOTAL	---	C1
AC	15-4-12	-26	-26	---	FRONT	VERT	TOTAL	---	C1
AD	19-4-12	-26	-26	---	FRONT	VERT	TOTAL	---	C1
AE	21-4-12	-26	-26	---	FRONT	VERT	TOTAL	---	C1

CONNECTION REQUIREMENTS

1) C1: A SUITABLE HANGER/MECHANICAL CONNECTION IS REQUIRED.





Structural component only
DWG# T-2016975 *2/2*

JOB NAME	TRUSS NAME	QUANTITY	PLY	JOB DESC.	GREEN PARK HOMES	DRWG NO.
410172	T20Z	2	2	TRUSS DESC.		

Tamarack Roof Truss, Burlington

Version 8.330 S May 6 2020 Mitek Industries, Inc. Thu Jul 30 08:32:21 2020 Page 1

ID:W63xGm6okcO0SiyZ4EwBx6zA2m0-6EXGNLogd1Rd89ZTe?_mp6oTmIF54HeVmNLPMysoe



LUMBER

N. L. G. A. RULES

CHORDS	SIZE	LUMBER
L - A	2x6 DRY	No.2
A - D	2x6 DRY	No.2
D - F	2x6 DRY	No.2
G - F	2x6 DRY	No.2
L - J	2x6 DRY	No.2
J - G	2x6 DRY	No.2

ALL WEBS 2x3 DRY
DRY: SEASONED LUMBER.

DESIGN CONSISTS OF 2 TRUSSES BUILT
SEPARATELY THEN FASTENED TOGETHER AS
FOLLOWS:

CHORDS #ROWS	SURFACE SPACING (IN)	LOAD (PLF)
TOP CHORDS : (0.122"x3") SPIRAL NAILS		
L - A	2 12	TOP
A - D	2 12	SIDE(0.0)
D - F	2 12	SIDE(183.1)
F - G	2 12	TOP
BOTTOM CHORDS : (0.122"x3") SPIRAL NAILS		
L - J	2 12	TOP
J - G	2 12	SIDE(183.1)
WEBS : (0.122"x3") SPIRAL NAILS		
2x3	1 6	

NAILS TO BE DRIVEN FROM ONE SIDE ONLY.

GIRDER NAILING ASSUMES NAILED HANGERS ARE
FASTENED WITH MIN. 3-0 INCH NAILS.

TOP - COMPONENTS ARE LOADED FROM THE TOP AND
MUST BE PLACED ON TOP EDGE OF ALL PLIES FOR THE
LOAD TO BE TRANSFERRED TO EACH PLY.

SIDE - PLF SHOWN IS THE EQUIVALENT UDL APPLIED TO
ONE SIDE THAT THE CORRESPONDING NAILING
PATTERN SHALL BE CAPABLE OF TRANSFERRING.
REMAINING PLF MUST BE APPLIED ON THE OPPOSITE
SIDE OR ON THE TOP.

PLATES (table is in inches)

JT	TYPE	PLATES	W	LEN	Y	X
A	TMW-t	MT20	5.0	8.0		
B	TMWW-t	MT20	5.0	6.0		

DIMENSIONS, SUPPORTS AND LOADINGS SPECIFIED BY FABRICATOR TO BE VERIFIED BY BUILDING DESIGNER

BEARINGS

JT	FACTORED		MAXIMUM FACTORED			INPUT	REQ'D
	GROSS REACTION		GROSS REACTION			BRG	BRG
	VERT	HORZ	DOWN	HORZ	UPLIFT	IN-SX	IN-SX
L	2097	0	2097	0	0	3-8	3-8
G	2809	0	2809	0	0	1-8	1-8

UNFACTORED REACTIONS

JT	MAX./MIN. COMPONENT REACTIONS						
	1ST LCASE	COMBINED	SNOW	LIVE	PERM.LIVE	WIND	DEAD
L	1481	981 / 0	0 / 0	0 / 0	0 / 0	500 / 0	0 / 0
G	1985	1308 / 0	0 / 0	0 / 0	0 / 0	678 / 0	0 / 0

BEARING MATERIAL TO BE SPF NO.2 OR BETTER AT JOINT(S) L, G

BRACING

TOP CHORD TO BE SHEATHED OR MAX. PURLIN SPACING = 5.05 FT.
MAX. UNBRACED BOTTOM CHORD LENGTH = 10.00 FT OR RIGID CEILING DIRECTLY APPLIED.

ALL PITCH BREAKS AND PERIMETER CORNER JOINTS MUST BE LATERALLY RESTRAINED.

LOADING

TOTAL LOAD CASES: (4)

MEMB.	CHORDS		WEBS	
	MAX. FACTORED	FACTORED	MAX. FACTORED	FACTORED
FR-TO	FORCE (LBS)	VERT. LOAD LC1	MAX. UNBRACED LENGTH	FORCE (LBS)
L-A	-2020 / 0	0.0	0.0	0.15 (1)
A-B	-2979 / 0	-91.8	-91.8	0.13 (1)
B-C	-4877 / 0	-91.8	-91.8	0.15 (1)
C-M	-4877 / 0	-91.8	-91.8	0.22 (1)
M-N	-4877 / 0	-91.8	-91.8	0.22 (1)
N-D	-4877 / 0	-91.8	-91.8	0.22 (1)
D-E	-4877 / 0	-91.8	-91.8	0.22 (1)
E-O	-3832 / 0	-91.8	-91.8	0.20 (1)
O-P	-3832 / 0	-91.8	-91.8	0.20 (1)
P-F	-3832 / 0	-91.8	-91.8	0.20 (1)
G-F	-2756 / 0	0.0	0.0	0.20 (1)

MEMB.	MAX. FACTORED	FACTORED	MAX. UNBRACED LENGTH	FORCE (LBS)
L-K	0 / 0	-18.5	-18.5	0.06 (1)
K-J	0 / 2979	-18.5	-18.5	0.41 (1)
J-I	0 / 2979	-18.5	-18.5	0.41 (1)
I-Q	0 / 3832	-18.5	-18.5	0.70 (1)
Q-R	0 / 3832	-18.5	-18.5	0.70 (1)
R-S	0 / 3832	-18.5	-18.5	0.70 (1)
S-H	0 / 3832	-18.5	-18.5	0.70 (1)
H-T	0 / 0	-18.5	-18.5	0.14 (1)
T-U	0 / 0	-18.5	-18.5	0.14 (1)
U-G	0 / 0	-18.5	-18.5	0.14 (1)

FACTORED CONCENTRATED LOADS (LBS)

JT	LOC.	LC1	MAX-	MAX+	FACE	DIR.	TYPE	HEEL	CONN.
E	17-4-12	-110	-110	---	FRONT	VERT	TOTAL	---	C1
F	23-7-0	-148	-148	---	FRONT	VERT	TOTAL	---	C1
G	23-7-0	-34	-34	---	FRONT	VERT	TOTAL	---	C1
H	17-4-12	-26	-26	---	FRONT	VERT	TOTAL	---	C1
M	14-3-12	-110	-110	---	FRONT	VERT	TOTAL	---	C1
N	15-4-12	-110	-110	---	FRONT	VERT	TOTAL	---	C1
O	19-4-12	-110	-110	---	FRONT	VERT	TOTAL	---	C1
P	21-4-12	-110	-110	---	FRONT	VERT	TOTAL	---	C1
Q	13-4-8	-1439	-1439	---	FRONT	VERT	TOTAL	---	C1
R	14-3-12	-26	-26	---	FRONT	VERT	TOTAL	---	C1
S	15-4-12	-26	-26	---	FRONT	VERT	TOTAL	---	C1
T	19-4-12	-26	-26	---	FRONT	VERT	TOTAL	---	C1
U	21-4-12	-26	-26	---	FRONT	VERT	TOTAL	---	C1

CONNECTION REQUIREMENTS

1) C1: A SUITABLE HANGER/MECHANICAL CONNECTION IS REQUIRED.

TOTAL WEIGHT = 4 X 124 = 498 lb

DESIGN CRITERIA

SPECIFIED LOADS:

TOP CH.	LL = 25.6 PSF
	DL = 6.0 PSF
BOT CH.	LL = 0.0 PSF
	DL = 7.4 PSF
TOTAL LOAD	= 39.0 PSF

SPACING = 24.0 IN. C/C

LOADING IN FLAT SECTION BASED ON A SLOPE
OF 6.00/12

THIS TRUSS IS DESIGNED FOR RESIDENTIAL OR
SMALL BUILDING REQUIREMENTS OF PART 9,
NBCC 2015

THIS DESIGN COMPLIES WITH:
- PART 9 OF BCBC 2018, ABC 2019
- PART 9 OF OBC 2012 (2019 AMENDMENT)
- CSA 086-14
- TPIC 2014

(55% OF 31.3 P.S.F. G.S.L. PLUS 8.4 P.S.F. RAIN
LOAD) EQUALS 25.6 P.S.F. SPECIFIED ROOF
LIVE LOAD

ALLOWABLE DEFL.(LL)= L/360 (0.79")
CALCULATED VERT. DEFL.(LL) = L/999 (0.12")
ALLOWABLE DEFL.(TL)= L/360 (0.79")
CALCULATED VERT. DEFL.(TL) = L/999 (0.21")

CSI: TC=0.22/1.00 (C-E:1), BC=0.70/1.00 (H-I:1),
WB=0.55/1.00 (F-H:1), SS=0.38/1.00 (H-I:1)

DOL LUMBER=1.00 NAIL=1.00 LS BEND=1.00
COMP=1.00 SHEAR=1.00 TENS=1.00

COMPANION LIVE LOAD FACTOR = 1.00

TRUSS PLATE MANUFACTURER IS NOT
RESPONSIBLE FOR QUALITY CONTROL IN THE
TRUSS MANUFACTURING PLANT.

NAIL VALUES

PLATE	GRIP(DRY)	SHEAR	SECTION
	(PSI)	(PLI)	(PLI)
MT20	650	371	1747
	788	1987	1873

PLATE PLACEMENT TOL. = 0.250 inches

PLATE ROTATION TOL. = 5.0 Deg.

JSI GRIP= 0.85 (K) (INPUT = 1.00)
JSI METAL= 0.46 (J) (INPUT = 1.00)



Structural component only
DWG# T-2016976 /12

CONTINUED ON PAGE 2

JOB NAME	TRUSS NAME	QUANTITY	PLY	JOB DESC.	DRWG NO.
410172	T20Z	2	2	GREEN PARK HOMES	
Tamarack Roof Truss, Burlington				TRUSS DESC.	

Version 8.330 S May 6 2020 MiTek Industries, Inc. Thu Jul 30 08:32:21 2020 Page 2

ID:W63xGm6okcO0SivZ4EwBx6zA2m0-6EXGNOLogd1Rd89ZTe? mp6oTmIF54HeVmNlpMysxoe

PLATES (table is in inches)

JT	TYPE	PLATES	W	LEN	Y	X
C	TMW+w	MT20	3.0	6.0		
D	TS-t	MT20	5.0	6.0		
E	TMWW-t	MT20	5.0	6.0		
F	TMVW-t	MT20	5.0	8.0		
G	BMV1+p	MT20	3.0	6.0		
H	BMWW-t	MT20	5.0	6.0	2.50	2.50
I	BMWW-t	MT20	5.0	8.0		
J	BS-t	MT20	5.0	6.0		
K	BMWW-t	MT20	5.0	6.0	2.50	2.50
L	BMV1+p	MT20	3.0	6.0		


CONNECTION REQUIREMENTS

- 1) C1: A SUITABLE HANGER/MECHANICAL CONNECTION IS REQUIRED.



Structural component only
DWG# T-2016976 72

JOB NAME 410143	TRUSS NAME T21	QUANTITY 4	PLY 1	JOB DESC. GREEN PARK HOMES	DRWG NO.
Tamarack Roof Truss, Burlington				Version 8.330 S May 6 2020 MiTek Industries, Inc. Tue Aug 4 13:08:58 2020 Page 1 ID:W63xGm6okc00SiyZ4EwBx6zA2m0-nw?R3GGyR4XlluwJJXdecr8IVxvRdWzBD56dIVrEHJ	
Scale = 1:37.5					



LUMBER			
N. L. G. A. RULES	CHORDS	SIZE	LUMBER
L - A	2x4	DRY	No.2
A - D	2x4	DRY	No.2
D - F	2x4	DRY	No.2
G - F	2x4	DRY	No.2
L - J	2x4	DRY	No.2
J - G	2x4	DRY	No.2
ALL WEBS	2x3	DRY	No.2
DRY: SEASONED LUMBER.			

PLATES (table is in inches)					
JT	TYPE	PLATES	W	LEN	Y X
A	TMVW-t	MT20	5.0	6.0	
B	TMVW-t	MT20	4.0	4.0	
C	TMVW-t	MT20	2.0	4.0	
D	TS-t	MT20	3.0	6.0	
E	TMVW-t	MT20	4.0	4.0	
F	TMVW-t	MT20	5.0	6.0	
G	BMV1-p	MT20	3.0	4.0	
H	BMVW-t	MT20	5.0	6.0	
I	BMVW-t	MT20	4.0	9.0	
J	BS-t	MT20	3.0	6.0	
K	BMVW-t	MT20	5.0	6.0	
L	BMV1-p	MT20	3.0	4.0	

DIMENSIONS, SUPPORTS AND LOADINGS SPECIFIED BY FABRICATOR TO BE VERIFIED BY BUILDING DESIGNER

FACTORED GROSS REACTION		MAXIMUM FACTORED GROSS REACTION		INPUT BRG		RECORD BRG	
JT	VERT	HORZ	DOWN	HORZ	UPLIFT	IN-SX	IN-SX
L	1300	0	1300	0	0	3-8	1-8
G	1300	0	1300	0	0	1-8	1-8

UNFACTORED REACTIONS

1ST LCASE		MAX./MIN. COMPONENT REACTIONS		PERM.LIVE		WIND		DEAD		SOIL	
JT	COMBINED	SNOW	LIVE	PERM.LIVE	WIND	DEAD	SOIL	COMBINED	SNOW	LIVE	PERM.LIVE
L	919	603 / 0	0 / 0	0 / 0	0 / 0	316 / 0	0 / 0	919	603 / 0	0 / 0	0 / 0
G	919	603 / 0	0 / 0	0 / 0	0 / 0	316 / 0	0 / 0	919	603 / 0	0 / 0	0 / 0

BEARING MATERIAL TO BE SPF NO.2 OR BETTER AT JOINT(S) L, G

BRACING

TOP CHORD TO BE SHEATHED OR MAX. PURLIN SPACING = 4.48 FT.
MAX. UNBRACED BOTTOM CHORD LENGTH = 10.00 FT OR RIGID CEILING DIRECTLY APPLIED.

ALL PITCH BREAKS AND PERIMETER CORNER JOINTS MUST BE Laterally RESTRAINED.

LOADING

TOTAL LOAD CASES: (4)

CHORDS		FACTORED		WEBS		FACTORED	
MEMB.	FORCE (LBS)	VERT. LOAD (PLF)	MAX. LC1 (LC)	MEMB.	FORCE (LBS)	MAX. LC1 (LC)	MEMB.
FR-TO		FROM	TO	FR-TO		FROM	TO
L-A	-1255 / 0	0.0	0.0 0.55 (1)	H-F	0 / 1654	0.37 (1)	
A-B	-1290 / 0	-91.8	-91.8 0.53 (1)	A-K	0 / 1654	0.37 (1)	
B-C	-1642 / 0	-91.8	-91.8 0.56 (1)	H-E	-912 / 0	0.35 (1)	
C-D	-1642 / 0	-91.8	-91.8 0.56 (1)	K-B	-912 / 0	0.35 (1)	
D-E	-1642 / 0	-91.8	-91.8 0.56 (1)	I-E	0 / 457	0.10 (1)	
E-F	-1230 / 0	-91.8	-91.8 0.53 (1)	B-I	0 / 457	0.10 (1)	
G-F	-1255 / 0	0.0	0.0 0.55 (1)	I-C	-487 / 0	0.19 (1)	
L-K	0 / 0	-18.5	-18.5 0.16 (4)				
K-J	0 / 1290	-18.5	-18.5 0.29 (1)				
J-I	0 / 1290	-18.5	-18.5 0.29 (1)				
I-H	0 / 1290	-18.5	-18.5 0.29 (1)				
H-G	0 / 0	-18.5	-18.5 0.16 (4)				

TOTAL WEIGHT = 4 X 99 = 394 lb

DESIGN CRITERIA

SPECIFIED LOADS:
TOP CH. LL = 25.6 PSF
DL = 6.0 PSF
BOT CH. LL = 0.0 PSF
DL = 7.4 PSF
TOTAL LOAD = 39.0 PSF

SPACING = 24.0 IN. C/C

LOADING IN FLAT SECTION BASED ON A SLOPE OF 6.00/12

THIS TRUSS IS DESIGNED FOR RESIDENTIAL OR SMALL BUILDING REQUIREMENTS OF PART 9, NBCC 2015

THIS DESIGN COMPLIES WITH:
- PART 9 OF NBC 2015, ABC 2019
- PART 9 OF OBC 2012 (2019 AMENDMENT)
- CSA 086-14
- TPIC 2014

(55% OF 31.3 P.S.F. G.S.L. PLUS 8.4 P.S.F. RAIN LOAD) EQUALS 25.6 P.S.F. SPECIFIED ROOF LIVE LOAD

ALLOWABLE DEFL.(LL) = L/360 (0.79")
CALCULATED VERT. DEFL.(LL) = L/999 (0.07")
ALLOWABLE DEFL.(TL) = L/360 (0.79")
CALCULATED VERT. DEFL.(TL) = L/999 (0.13")

CSI: TC=0.56/1.00 (B-C:1), BC=0.29/1.00 (H-K:1), WB=0.37/1.00 (F-H:1), SSI=0.26/1.00 (A-B:1)

DOL LUMBER=1.00 NAIL=1.00 LS BEND=1.10
COMP=1.10 SHEAR=1.10 TENS=1.10

COMPANION LIVE LOAD FACTOR = 1.00

TRUSS PLATE MANUFACTURER IS NOT RESPONSIBLE FOR QUALITY CONTROL IN THE TRUSS MANUFACTURING PLANT

NAIL VALUES
PLATE GRIP(DRY) SHEAR SECTION (PSI) (PLI) (PLI)
MAX MIN MAX MIN MAX MIN
MT20 650 371 1747 788 1987 1873

PLATE PLACEMENT TOL. = 0.250 inches

PLATE ROTATION TOL. = 5.0 Deg.

JSI GRIP = 0.76 (F) (INPUT = 0.90)
JSI METAL = 0.43 (J) (INPUT = 1.00)




Structural component only
DWG# T-2017145

JOB NAME 410143	TRUSS NAME T23	QUANTITY 18	PLY 1	JOB DESC. GREEN PARK HOMES	TRUSS DESC.	DRWG NO.
--------------------	-------------------	----------------	----------	-------------------------------	-------------	----------

Tamarack Roof Truss, Burlington

Version 8.330 S May 6 2020 MiTek Industries, Inc. Tue Aug 4 13:09:00 2020 Page 1
ID:W63xGm60kc00SiyZ4EwBx6zA2m0-nJ7BTyHCzhnT_C4iRy6hGD5Zlb5JpUgPbkNNyrEHH



LUMBER

N. L. G. A. RULES	CHORDS	SIZE	LUMBER	DESCR.
L - A	2x4	DRY	No.2	SPF
A - D	2x4	DRY	No.2	SPF
D - F	2x4	DRY	No.2	SPF
G - F	2x4	DRY	No.2	SPF
L - J	2x4	DRY	No.2	SPF
J - G	2x4	DRY	No.2	SPF
ALL WEBS	2x3	DRY	No.2	SPF
DRY: SEASONED LUMBER.				

PLATES (table is in inches)

JT	TYPE	PLATES	W	LEN	Y	X
A	TMVW+p	MT20	5.0	6.0		
B	TMVW-t	MT20	4.0	4.0		
C	TMVW+w	MT20	2.0	4.0		
D	TS-t	MT20	3.0	6.0		
E	TMVW-t	MT20	4.0	4.0		
F	TMVW+p	MT20	5.0	6.0		
G	BMV1+p	MT20	3.0	4.0		
H	BMVW-t	MT20	5.0	6.0		
I	BMVW-w	MT20	4.0	9.0		
J	BS-t	MT20	3.0	6.0		
K	BMVW-t	MT20	5.0	6.0		
L	BMV1+p	MT20	3.0	4.0		

DIMENSIONS, SUPPORTS AND LOADINGS SPECIFIED BY FABRICATOR TO BE VERIFIED BY BUILDING DESIGNER

FACTORED	MAXIMUM FACTORED	INPUT	RECORD
GROSS REACTION	GROSS REACTION	BRG	BRG
JT	VERT	HORIZ	UPLIFT
L	1300	0	0
G	1300	0	0

UNFACTORED REACTIONS

1ST CASE	MAX./MIN.	COMPONENT REACTIONS
JT	COMBINED	SNOW
L	919	603 / 0
G	919	603 / 0

BEARING MATERIAL TO BE SPF NO.2 OR BETTER AT JOINT(S) L, G

BRACING

TOP CHORD TO BE SHEATHED OR MAX. PURLIN SPACING = 5.16 FT.
MAX. UNBRACED BOTTOM CHORD LENGTH = 10.00 FT. OR RIGID CEILING DIRECTLY APPLIED.

ALL PITCH BREAKS AND PERIMETER CORNER JOINTS MUST BE Laterally RESTRAINED

1 LATERAL BRACE(S) AT 1/2 LENGTH OF A-L, F-G.

END VERTICAL(S) MUST BE SHEATHED OR HAVE BRACES AS INDICATED IN THE MAX. UNBRACED LENGTH COLUMN OF THE TABLE BELOW

LOADING

TOTAL LOAD CASES: (4)

CHORDS	MAX. FACTORED	FACTORED	MAX.	MEMB.	MAX. FACTORED	MAX.
MEMB.	FORCE	VERT. LOAD LC1	CS (LC)	UNBRAC	FORCE	CS (LC)
FR-TO	(LBS)	FROM TO	LENGTH	FR-TO	(LBS)	CS (LC)
L-A	-1255.0	0.0	0.0 0.29 (1)	5.74	H-F	0 1381
A-B	-912.0	-91.8	-91.8 0.51 (1)	5.68	A-K	0 1381
B-C	-1160.0	-91.8	-91.8 0.52 (1)	5.16	H-E	-912.0
C-D	-1160.0	-91.8	-91.8 0.52 (1)	5.16	K-B	-912.0
D-E	-1160.0	-91.8	-91.8 0.52 (1)	5.16	I-E	0 383
E-F	-912.0	-91.8	-91.8 0.51 (1)	5.68	B-I	0 383
G-F	-1255.0	0.0	0.0 0.29 (1)	5.74	I-C	-486 0
L-K	0 0	-18.5	-18.5 0.16 (4)	10.00		
K-J	0 912	-18.5	-18.5 0.24 (4)	10.00		
J-I	0 912	-18.5	-18.5 0.24 (4)	10.00		
I-H	0 912	-18.5	-18.5 0.24 (4)	10.00		
H-G	0 0	-18.5	-18.5 0.16 (4)	10.00		

TOTAL WEIGHT = 18 X 113 = 2026 lb

DESIGN CRITERIA

SPECIFIED LOADS:
TOP CH. LL = 25.6 PSF
DL = 6.0 PSF
BOT CH. LL = 0.0 PSF
DL = 7.4 PSF
TOTAL LOAD = 39.0 PSF

SPACING = 24.0 IN. C/C

LOADING IN FLAT SECTION BASED ON A SLOPE OF 6.00/12

THIS TRUSS IS DESIGNED FOR RESIDENTIAL OR SMALL BUILDING REQUIREMENTS OF PART 9, NBC 2015

THIS DESIGN COMPLIES WITH:
- PART 9 OF CBC 2018, ABC 2019
- PART 9 OF OBC 2012 (2019 AMENDMENT)
- CSA 086-14
- TPIC 2014

(55 % OF 31.3 P.S.F. G.S.L. PLUS 8.4 P.S.F. RAIN LOAD) EQUALS 25.6 P.S.F. SPECIFIED ROOF LIVE LOAD

ALLOWABLE DEFL.(LL) = L/360 (0.79")
CALCULATED VERT. DEFL.(LL) = L/999 (0.05")
ALLOWABLE DEFL.(TL) = L/360 (0.79")
CALCULATED VERT. DEFL.(TL) = L/999 (0.10")

CSI: TC=0.52/1.00 (B-C:1), BC=0.24/1.00 (H-I:4), WB=0.80/1.00 (E-H:1), SSI=0.26/1.00 (A-B:1)

DOL LUMBER=1.00 NAIL=1.00 LS BEND=1.10
COMP=1.10 SHEAR=1.10 TENS=1.10

COMPANION LIVE LOAD FACTOR = 1.00

TRUSS PLATE MANUFACTURER IS NOT RESPONSIBLE FOR QUALITY CONTROL IN THE TRUSS MANUFACTURING PLANT

NAIL VALUES
PLATE GRIP(DRY) SHEAR SECTION
(PSI) (PLI) (PLI)
MAX MIN MAX MIN MAX MIN
MT20 650 371 1747 788 1987 1873

PLATE PLACEMENT TOL. = 0.250 inches

PLATE ROTATION TOL. = 5.0 Deg.

JSI GRIP = 0.64 (H) (INPUT = 0.90)
JSI METAL = 0.33 (A) (INPUT = 1.00)



Structural component only
DWG# T-2017147

JOB NAME	TRUSS NAME	QUANTITY	PLY	JOB DESC.	DRWG NO.
410172	T24	2	2	GREEN PARK HOMES	
Tamarack Roof Truss, Burlington		TRUSS DESC.			

Version 8.330 S May 6 2020 MiTek Industries, Inc. Thu Jul 30 08:32:22 2020 Page 2
ID:W63xGm6okcO0SivZ4EwBx6zA2m0-aQ5ebkMQQx9IEIk0MWDI0f QAktgeFniQ7vLoysxod

PLATES (table is in inches)

JT	TYPE	PLATES	W	LEN	Y	X
B	TMVW+p	MT20	5.0	6.0	1.75	2.75
C	TTW-m	MT20	4.0	4.0		
D	TMWW-t	MT20	4.0	4.0		
E	TTW-m	MT20	4.0	4.0		
F	TMVW+p	MT20	5.0	6.0	1.75	2.75
H	BMV1+p	MT20	3.0	6.0		
I	BMWW-t	MT20	5.0	8.0		
J	BMWW-t	MT20	5.0	8.0		
K	BMV1+p	MT20	3.0	6.0		




Structural component only
DWG# T-2016977 *1/2*

JOB NAME	TRUSS NAME	QUANTITY	PLY	JOB DESC.	DRWG NO.
410172	T25	2	1	GREEN PARK HOMES	
Tamarack Roof Truss, Burlington					

Version 8.330 S May 6 2020 MITek Industries, Inc. Thu Jul 30 08:32:23 2020 Page 1

ID:W63xGm6okc00SiyZ4EwBx6zA2m0-2ce0o3M3BFH9sSjxa31SrEBANa55Z?Owy3sSuFysxoc

Scale = 1:47.3



LUMBER

N. L. G. A. RULES

CHORDS SIZE

A - C 2x4 DRY

C - D 2x4 DRY

D - G 2x4 DRY

K - A 2x4 DRY

H - F 2x4 DRY

K - H 2x4 DRY

ALL WEBS 2x3 DRY

EXCEPT

DRY: SEASONED LUMBER.

PLATES (table is in inches)

JT	TYPE	PLATES	W	LEN	Y	X
A	TMV+p	MT20	3.0	4.0		
B	TMWW-t	MT20	4.0	4.0	2.00	1.75
C	TTW+h	MT20	3.0	4.0		
D	TTWW+m	MT20	5.0	6.0	2.00	1.75
E	TMWW-t	MT20	4.0	4.0	2.00	1.75
F	TMV+p	MT20	3.0	4.0		
H	BMVW1-t	MT20	4.0	4.0		
I	BMVW1-t	MT20	4.0	4.0		
J	BMVW1-t	MT20	4.0	6.0	2.00	2.00
K	BMVW1-t	MT20	4.0	4.0		

DIMENSIONS, SUPPORTS AND LOADINGS SPECIFIED BY FABRICATOR TO BE VERIFIED BY BUILDING DESIGNER

BEARINGS

JT	FACTORED GROSS REACTION	MAXIMUM FACTORED GROSS REACTION	INPUT BRG	RECORD BRG
K	730	730	0	0
H	858	858	0	0

A SUITABLE HANGER/MECHANICAL CONNECTION IS REQUIRED AT JOINT H. MINIMUM BEARING LENGTH AT JOINT H = 1-8.

UNFACTORED REACTIONS

JT	1ST LCASE	MAX./MIN. COMPONENT REACTIONS	PERM. LIVE	WIND	DEAD	SOIL
K	517	339 / 0	0 / 0	0 / 0	178 / 0	0 / 0
H	604	410 / 0	0 / 0	0 / 0	194 / 0	0 / 0

BEARING MATERIAL TO BE SPF NO.2 OR BETTER AT JOINT(S) K

BRACING

TOP CHORD TO BE SHEATHED OR MAX. PURLIN SPACING = 6.25 FT.
MAX. UNBRACED BOTTOM CHORD LENGTH = 10.00 FT OR RIGID CEILING DIRECTLY APPLIED.

ALL PITCH BREAKS AND PERIMETER CORNER JOINTS MUST BE Laterally RESTRAINED.

1 LATERAL BRACE(S) AT 1/2 LENGTH OF D-J.

END VERTICAL(S) MUST BE SHEATHED OR HAVE BRACES AS INDICATED IN THE MAX. UNBRACED LENGTH COLUMN OF THE TABLE BELOW

LOADING

TOTAL LOAD CASES: (4)

CHORDS	MEMB.	MAX. FACTORED FORCE (LBS)	FACTORED VERT. LOAD (PLF)	LC1	MAX. CS1 (LC)	UNBRACED LENGTH	WEBS	MEMB.	MAX. FACTORED FORCE (LBS)	MAX. CS1 (LC)
FR-TO							FR-TO			
A-B		0 / 20	-91.8	-91.8	0.12 (1)	10.00	B-J		-3 / 30	0.01 (4)
B-C		-416 / 0	-91.8	-91.8	0.09 (1)	6.25	J-C		0 / 89	0.02 (4)
C-D		-292 / 0	-91.8	-91.8	0.03 (1)	6.25	J-D		-9 / 0	0.00 (1)
D-E		-420 / 0	-91.8	-91.8	0.10 (1)	6.25	I-D		0 / 101	0.02 (4)
E-F		0 / 21	-91.8	-91.8	0.13 (1)	10.00	I-E		-27 / 24	0.02 (1)
F-G		0 / 43	-91.8	-91.8	0.13 (1)	10.00	K-B		-656 / 0	0.44 (1)
K-A		-98 / 0	0.0	0.0	0.02 (1)	7.81	E-H		-654 / 0	0.45 (1)
H-F		-233 / 0	0.0	0.0	0.04 (1)	7.81				
K-J		0 / 293	-18.5	-18.5	0.16 (4)	10.00				
J-I		0 / 294	-18.5	-18.5	0.16 (4)	10.00				
I-H		0 / 305	-18.5	-18.5	0.16 (4)	10.00				

TOTAL WEIGHT = 2 X 83 = 167 lb

(M)(F)

DESIGN CRITERIA

SPECIFIED LOADS:

TOP CH.	LL = 25.6 PSF
	DL = 6.0 PSF
BOT CH.	LL = 0.0 PSF
	DL = 7.4 PSF
TOTAL LOAD =	39.0 PSF

SPACING = 24.0 IN. C/C

LOADING IN FLAT SECTION BASED ON A SLOPE OF 6.00/12

THIS TRUSS IS DESIGNED FOR RESIDENTIAL OR SMALL BUILDING REQUIREMENTS OF PART 9, NBCC 2015

THIS DESIGN COMPLIES WITH:

- PART 9 OF BCBC 2018, ABC 2019
- PART 9 OF OBC 2012 (2019 AMENDMENT)
- CSA 086-14
- TPIC 2014

(55 % OF 31.3 P.S.F. G.S.L. PLUS 8.4 P.S.F. RAIN LOAD) EQUALS 25.6 P.S.F. SPECIFIED ROOF LIVE LOAD

ALLOWABLE DEFL.(LL) = L/360 (0.44")
CALCULATED VERT. DEFL.(LL) = L/999 (0.01")
ALLOWABLE DEFL.(TL) = L/360 (0.44")
CALCULATED VERT. DEFL.(TL) = L/999 (0.04")

CSI: TC=0.13/1.00 (F-G:1), BC=0.16/1.00 (I-J:4), WB=0.45/1.00 (E-H:1), SSI=0.10/1.00 (E-F:1)

DOL LUMBER=1.00 NAIL=1.00 LS BEND=1.10 COMP=1.10 SHEAR=1.10 TENS=1.10

COMPANION LIVE LOAD FACTOR = 1.00

TRUSS PLATE MANUFACTURER IS NOT RESPONSIBLE FOR QUALITY CONTROL IN THE TRUSS MANUFACTURING PLANT.

NAIL VALUES

PLATE	GRIP(DRY)	SHEAR	SECTION
	(PSI)	(PLI)	(PLI)
MT20	650	371	1747
	788	1987	1873

PLATE PLACEMENT TOL. = 0.250 inches


PLATE ROTATION TOL. = 5.0 Deg.

JSI GRIP= 0.72 (C) (INPUT = 0.90)
JSI METAL= 0.21 (E) (INPUT = 1.00)



Structural component only
DWG# T-2016978

JOB NAME	TRUSS NAME	QUANTITY	PLY	JOB DESC.	DRWG NO.
410172	T26	4	1	GREEN PARK HOMES	
Tamarack Roof Truss, Burlington					



LUMBER

N. L. G. A. RULES

CHORDS SIZE

A - C 2x4 DRY No.2

C - E 2x4 DRY No.2

H - A 2x4 DRY No.2

F - E 2x4 DRY No.2

H - F 2x4 DRY No.2

ALL WEBS 2x3 DRY No.2

EXCEPT

DRY: SEASONED LUMBER.

PLATES (table is in inches)

JT	TYPE	PLATES	W	LEN	Y	X
A	TMV+p	MT20	3.0	4.0		
B	TMVW-t	MT20	4.0	4.0	2.00	1.75
C	TTW+p	MT20	4.0	6.0	Edge	
D	TMVW-t	MT20	4.0	4.0	2.00	1.75
E	TMV+p	MT20	3.0	4.0		
F	BMVW1-t	MT20	4.0	4.0		
G	BMVW1-t	MT20	4.0	9.0		
H	BMVW1-t	MT20	4.0	4.0		

Edge - INDICATES REFERENCE CORNER OF PLATE TOUCHES EDGE OF CHORD.

DIMENSIONS, SUPPORTS AND LOADINGS SPECIFIED BY FABRICATOR TO BE VERIFIED BY BUILDING DESIGNER

BEARINGS

JT	FACTORED GROSS REACTION	MAXIMUM FACTORED GROSS REACTION	INPUT BRG	REQD BRG
H	730	0	0	0
F	730	0	0	0

A SUITABLE HANGER/MECHANICAL CONNECTION IS REQUIRED AT JOINT F. MINIMUM BEARING LENGTH AT JOINT F = 1-8.

UNFACTORED REACTIONS

JT	1ST LCASE	MAX./MIN. COMPONENT REACTIONS	PERM. LIVE	WIND	DEAD	SOIL
H	517	339 / 0	0 / 0	0 / 0	178 / 0	0 / 0
F	517	339 / 0	0 / 0	0 / 0	178 / 0	0 / 0

BEARING MATERIAL TO BE SPF NO.2 OR BETTER AT JOINT(S) H

BRACING

TOP CHORD TO BE SHEATHED OR MAX. PURLIN SPACING = 6.25 FT.
MAX. UNBRACED BOTTOM CHORD LENGTH = 10.00 FT. OR RIGID CEILING DIRECTLY APPLIED.

ALL PITCH BREAKS AND PERIMETER CORNER JOINTS MUST BE Laterally RESTRAINED.

LOADING

TOTAL LOAD CASES: (4)

CHORDS				WEBS			
MEMB.	MAX. FACTORED FORCE (LBS)	FACTORED VERT. LOAD (PLF)	MAX. LC1 (LC)	MEMB.	MAX. FACTORED FORCE (LBS)	MAX. LC1 (LC)	
FR-TO		FROM TO		FR-TO			
A-B	0 / 24	-91.8	-91.8 0.16 (1)	B-G	-59 / 18	0.05 (1)	
B-C	-400 / 0	-91.8	-91.8 0.12 (1)	G-C	0 / 274	0.06 (1)	
C-D	-401 / 0	-91.8	-91.8 0.13 (1)	G-D	-81 / 12	0.07 (1)	
D-E	0 / 24	-91.8	-91.8 0.17 (1)	H-B	-849 / 0	0.54 (1)	
H-A	-113 / 0	0.0	0.0 0.02 (1)	D-F	-846 / 0	0.55 (1)	
F-E	-120 / 0	0.0	0.0 0.02 (1)				
H-G	0 / 306	-18.5	-18.5 0.26 (4)				
G-F	0 / 317	-18.5	-18.5 0.26 (4)				

TOTAL WEIGHT = 4 X 71 = 284 lb

DESIGN CRITERIA

SPECIFIED LOADS:

TOP CH.	LL = 25.6	PSF
	DL = 6.0	PSF
BOT CH.	LL = 0.0	PSF
	DL = 7.4	PSF
TOTAL LOAD	= 39.0	PSF

SPACING = 24.0 IN./C

THIS TRUSS IS DESIGNED FOR RESIDENTIAL OR SMALL BUILDING REQUIREMENTS OF PART 9, NBCC 2015

THIS DESIGN COMPLIES WITH:

- PART 9 OF CBC 2018, ABC 2019
- PART 9 OF OBC 2012 (2019 AMENDMENT)
- CSA 088-14
- TPIC 2014

(55 % OF 31.3 P.S.F. G.S.L. PLUS 8.4 P.S.F. RAIN LOAD) EQUALS 25.6 P.S.F. SPECIFIED ROOF LIVE LOAD

ALLOWABLE DEFL.(LL) = $L/360$ (0.44")
CALCULATED VERT. DEFL.(LL) = $L/999$ (0.01")
ALLOWABLE DEFL.(TL) = $L/360$ (0.44")
CALCULATED VERT. DEFL.(TL) = $L/999$ (0.05")

CSI: TC=0.17/1.00 (D-E:1), BC=0.26/1.00 (F-G:4), WB=0.55/1.00 (D-F:1), SSI=0.11/1.00 (D-E:1)

DOL LUMBER=1.00 NAIL=1.00 LS BEND=1.10
COMP=1.10 SHEAR=1.10 TENS=1.10

COMPANION LIVE LOAD FACTOR = 1.00

TRUSS PLATE MANUFACTURER IS NOT RESPONSIBLE FOR QUALITY CONTROL IN THE TRUSS MANUFACTURING PLANT.

NAIL VALUES

PLATE	GRIP(DRY)	SHEAR	SECTION
	(PSI)	(PLI)	(PLI)
	MAX MIN	MAX MIN	MAX MIN
MT20	650 371	1747 788	1987 1873

PLATE PLACEMENT TOL. = 0.250 inches


PLATE ROTATION TOL. = 5.0 Deg.

JSI GRIP= 0.64 (D) (INPUT = 0.90)
JSI METAL= 0.22 (D) (INPUT = 1.00)



Structural component only
DWG# T-2016979

JOB NAME	TRUSS NAME	QUANTITY	PLY	JOB DESC.	GREEN PARK HOMES	DRWG NO.
410172	T27	2	1	TRUSS DESC.		
Tamarack Roof Truss, Burlington						



LUMBER

N. L. G. A. RULES	CHORDS	SIZE	LUMBER	DESCR.
A - C	2x4	DRY	No.2	SPF
C - D	2x4	DRY	No.2	SPF
D - F	2x4	DRY	No.2	SPF
J - B	2x4	DRY	No.2	SPF
G - E	2x4	DRY	No.2	SPF
J - G	2x4	DRY	No.2	SPF
ALL WEBS EXCEPT	2x3	DRY	No.2	SPF

DRY: SEASONED LUMBER.

PLATES (table is in inches)

JT	TYPE	PLATES	W	LEN	Y	X
B	TMVW+p	MT20	4.0	6.0	Edge	
C	TTWW+m	MT20	5.0	6.0	2.00	1.75
D	TTW+h	MT20	3.0	4.0		
E	TMVW+p	MT20	4.0	6.0	Edge	
G	BMV1+p	MT20	3.0	4.0		
H	BMVWW-t	MT20	4.0	6.0	2.00	1.50
I	BMVWW-t	MT20	4.0	4.0		
J	BMV1+p	MT20	3.0	4.0		

Edge - INDICATES REFERENCE CORNER OF PLATE TOUCHES EDGE OF CHORD.

DIMENSIONS, SUPPORTS AND LOADINGS SPECIFIED BY FABRICATOR TO BE VERIFIED BY BUILDING DESIGNER

BEARINGS	FACTORED GROSS REACTION	MAXIMUM FACTORED GROSS REACTION	INPUT BRG	REQD BRG
JT	VERT	HORZ	DOWN	HORZ
J	676	0	676	0
G	676	0	676	0

A SUITABLE HANGER/MECHANICAL CONNECTION IS REQUIRED AT JOINT G. MINIMUM BEARING LENGTH AT JOINT G = 1-8.

UNFACTORED REACTIONS

JT	1ST LOASE	MAX./MIN. COMPONENT REACTIONS	SNOW	LIVE	PERM.LIVE	WIND	DEAD	SOIL
J	475	328 / 0	0 / 0	0 / 0	0 / 0	0 / 0	147 / 0	0 / 0
G	475	328 / 0	0 / 0	0 / 0	0 / 0	0 / 0	147 / 0	0 / 0

BEARING MATERIAL TO BE SPF NO.2 OR BETTER AT JOINT(S) J

BRACING

TOP CHORD TO BE SHEATHED OR MAX. PURLIN SPACING = 6.25 FT.
MAX. UNBRACED BOTTOM CHORD LENGTH = 10.00 FT. OR RIGID CEILING DIRECTLY APPLIED.

ALL PITCH BREAKS AND PERIMETER CORNER JOINTS MUST BE Laterally RESTRAINED.

LOADING

TOTAL LOAD CASES: (4)

CHORDS	MAX. FACTORED	FACTORED	WEBS	MAX. FACTORED
MEMB.	FORCE (LBS)	VERT. LOAD (PLF)	MEMB.	FORCE (LBS)
FR-TO		FROM TO	FR-TO	
A-B	0 / 43	-91.8 -91.8 0.14 (1)	I-C	-73 / 16
B-C	-380 / 0	-91.8 -91.8 0.15 (1)	C-H	-5 / 1
C-D	-276 / 0	-91.8 -91.8 0.02 (1)	H-D	-79 / 18
D-E	-379 / 0	-91.8 -91.8 0.15 (1)	B-I	0 / 309
E-F	0 / 43	-91.8 -91.8 0.14 (1)	H-E	0 / 308
J-B	-650 / 0	0.0 0.0 0.08 (1)		
G-E	-648 / 0	0.0 0.0 0.08 (1)		
J-K	0 / 0	-18.5 -18.5 0.04 (4)		
K-I	0 / 0	-18.5 -18.5 0.04 (4)		
I-H	0 / 277	-18.5 -18.5 0.07 (1)		
H-L	0 / 0	-18.5 -18.5 0.04 (4)		
L-G	0 / 0	-18.5 -18.5 0.04 (4)		

FACTORED CONCENTRATED LOADS (LBS)

JT	LOC.	LC1	MAX-	MAX+	FACE	DIR.	TYPE	HEEL	CONN.
C	2-10-8	-151	-151	---	FRONT	VERT	TOTAL	---	C1
D	4-0-8	-151	-151	---	FRONT	VERT	TOTAL	---	C1
H	3-11-12	-8	-8	---	FRONT	VERT	TOTAL	---	C1
I	2-11-4	-8	-8	---	FRONT	VERT	TOTAL	---	C1
K	1-11-4	-8	-8	---	FRONT	VERT	TOTAL	---	C1
L	4-11-12	-8	-8	---	FRONT	VERT	TOTAL	---	C1

CONNECTION REQUIREMENTS

1) C1: A SUITABLE HANGER/MECHANICAL CONNECTION IS REQUIRED.

TOTAL WEIGHT = 2 X 40 = 80 lb

DESIGN CRITERIA

SPECIFIED LOADS:

TOP CH.	LL	= 25.6	PSF
	DL	= 6.0	PSF
BOT CH.	LL	= 0.0	PSF
	DL	= 7.4	PSF
TOTAL LOAD	=	39.0	PSF

SPACING = 24.0 IN. C/C

LOADING IN FLAT SECTION BASED ON A SLOPE OF 6.00/12

THIS TRUSS IS DESIGNED FOR RESIDENTIAL OR SMALL BUILDING REQUIREMENTS OF PART 9, NBCC 2015

THIS DESIGN COMPLIES WITH:

- PART 9 OF BCBC 2018, ABC 2019
- PART 9 OF OBC 2012 (2019 AMENDMENT)
- CSA 086-14
- TPIC 2014

(55 % OF 31.3 P.S.F. G.S.L. PLUS 8.4 P.S.F. RAIN LOAD) EQUALS 25.6 P.S.F. SPECIFIED ROOF LIVE LOAD

ALLOWABLE DEFL.(LL)= L/360 (0.23")
CALCULATED VERT. DEFL.(LL) = L/999 (0.00")
ALLOWABLE DEFL.(TL)= L/360 (0.23")
CALCULATED VERT. DEFL.(TL) = L/999 (0.01")

CSI: TC=0.15/1.00 (B-C-1), BC=0.07/1.00 (H-I-1),
WB=0.08/1.00 (B-I-1), SSI=0.08/1.00 (B-C-1)

DOL LUMBER=1.00 NAIL=1.00 LS BEND=1.00
COMP=1.00 SHEAR=1.00 TENS=1.00

COMPANION LIVE LOAD FACTOR = 1.00

TRUSS PLATE MANUFACTURER IS NOT RESPONSIBLE FOR QUALITY CONTROL IN THE TRUSS MANUFACTURING PLANT.

NAIL VALUES

PLATE	GRIP(DRY)	SHEAR	SECTION
(PSI)	(PLI)	(PLI)	(PLI)
MT20	650	371	1747
	788	1987	1873

PLATE PLACEMENT TOL. = 0.250 inches


PLATE ROTATION TOL. = 5.0 Deg.

JSI GRIP= 0.65 (D) (INPUT = 0.90)
JSI METAL= 0.22 (B) (INPUT = 1.00)



Structural component only
DWG# T-2016980

JOB NAME	TRUSS NAME	QUANTITY	PLY	JOB DESC.	DRWG NO.
410172	T28	2	2	GREEN PARK HOMES	
Tamarack Roof Truss, Burlington		Version 8.330 S May 6 2020 MiTek Industries, Inc. Thu Jul 30 08:32:26 2020 Page 1			
		ID:W63xGm6okc00SiyZ4EwBx6zA2m0-SBK9R5PxAUAgjv2WFCa9Tsphgn4imRNNe156UZysxoZ			
		Scale = 1:23.7			



LUMBER

N. L. G. A. RULES	CHORDS	SIZE	LUMBER	DESCR.
F - A	2x4	DRY	No.2	SPF
A - C	2x4	DRY	No.2	SPF
D - C	2x4	DRY	No.2	SPF
F - D	2x4	DRY	No.2	SPF
ALL WEBS	2x3	DRY	No.2	SPF
DRY: SEASONED LUMBER.				

DESIGN CONSISTS OF 2 TRUSSES BUILT SEPARATELY THEN FASTENED TOGETHER AS FOLLOWS:

CHORDS #ROWS	SURFACE SPACING (IN)	LOAD (PLF)
TOP CHORDS : (0.122"x3") SPIRAL NAILS		
F - A	12	TOP
A - C	12	TOP
C - D	12	TOP
BOTTOM CHORDS : (0.122"x3") SPIRAL NAILS		
F - D	12	SIDE(61.0)
WEBS : (0.122"x3") SPIRAL NAILS		
B - E	5	SIDE(124.7)
2x3	6	

NAILS TO BE DRIVEN FROM ONE SIDE ONLY.

GIRDER NAILING ASSUMES NAILED HANGERS ARE FASTENED WITH MIN. 3-0 INCH NAILS.

TOP - COMPONENTS ARE LOADED FROM THE TOP AND MUST BE PLACED ON TOP EDGE OF ALL PLIES FOR THE LOAD TO BE TRANSFERRED TO EACH PLY.

SIDE - PLF SHOWN IS THE EQUIVALENT UDL APPLIED TO ONE SIDE THAT THE CORRESPONDING NAILING PATTERN SHALL BE CAPABLE OF TRANSFERRING. REMAINING PLF MUST BE APPLIED ON THE OPPOSITE SIDE OR ON THE TOP.

PLATES (table is in inches)

JT	TYPE	PLATES	W	LEN	Y	X
A	TMWV+p	MT20	4.0	4.0	1.50	2.00
B	TMWV-t	MT20	4.0	4.0	2.00	1.75
C	TMV+p	MT20	3.0	4.0		
D	BMWV1-t	MT20	4.0	4.0		
E	BMWV+t	MT20	4.0	4.0		

DIMENSIONS, SUPPORTS AND LOADINGS SPECIFIED BY FABRICATOR TO BE VERIFIED BY BUILDING DESIGNER

BEARINGS

	FACTORED GROSS REACTION	MAXIMUM FACTORED GROSS REACTION	INPUT BRG	REQRD BRG
JT	VERT	HORZ	DOWN	HORZ
F	1455	0	1455	0
D	1458	0	1458	0

A SUITABLE HANGER/MECHANICAL CONNECTION IS REQUIRED AT JOINT D. MINIMUM BEARING LENGTH AT JOINT D = 1-8.

UNFACTORED REACTIONS

JT	1ST LOASE COMBINED	MAX/MIN. COMPONENT REACTIONS	SNOW	LIVE	PERM. LIVE	WIND	DEAD	SOIL
F	1025	697 / 0	0 / 0	0 / 0	0 / 0	0 / 0	327 / 0	0 / 0
D	1028	691 / 0	0 / 0	0 / 0	0 / 0	0 / 0	337 / 0	0 / 0

BEARING MATERIAL TO BE SPF NO.2 OR BETTER AT JOINT(S) F

BRACING

TOP CHORD TO BE SHEATHED OR MAX. PURLIN SPACING = 6.25 FT.
MAX. UNBRACED BOTTOM CHORD LENGTH = 10.00 FT OR RIGID CEILING DIRECTLY APPLIED.

ALL PITCH BREAKS AND PERIMETER CORNER JOINTS MUST BE LATERALLY RESTRAINED.

LOADING

TOTAL LOAD CASES: (4)

CHORDS	MAX. FACTORED FORCE (LBS)	FACTORED VERT. LOAD (PLF)	MAX. FACTORED VERT. LOAD (LC1)	MAX. FACTORED VERT. LOAD (LC)	MAX. FACTORED VERT. LOAD (LC)	MAX. FACTORED VERT. LOAD (LC)	MAX. FACTORED VERT. LOAD (LC)
FR-TO							
F - A	-1007 / 0	0.0	0.0	0.06 (1)	7.81	A - E	0 / 1179
A - B	-1255 / 0	-91.8	-91.8	0.06 (1)	6.25	E - B	0 / 1145
B - C	-11 / 0	-91.8	-91.8	0.05 (1)	6.25	B - D	-1444 / 0
D - C	-111 / 0	0.0	0.0	0.01 (1)	7.81		
F - G	0 / 0	-18.5	-18.5	0.36 (1)	10.00		
G - E	0 / 0	-18.5	-18.5	0.36 (1)	10.00		
E - H	0 / 1132	-18.5	-18.5	0.36 (1)	10.00		
H - D	0 / 1132	-18.5	-18.5	0.36 (1)	10.00		

FACTORED CONCENTRATED LOADS (LBS)

JT	LOC.	LC1	MAX-	MAX+	FACE	DIR.	TYPE	HEEL	CONN.
E	3-1-4	-712	-712	---	FRONT	VERT	TOTAL	---	C1
G	1-1-4	-839	-839	---	FRONT	VERT	TOTAL	---	C1
H	5-1-4	-714	-714	---	FRONT	VERT	TOTAL	---	C1

CONNECTION REQUIREMENTS

1) C1: A SUITABLE HANGER/MECHANICAL CONNECTION IS REQUIRED.

TOTAL WEIGHT = 4 X 26 = 102 lb

DESIGN CRITERIA

SPECIFIED LOADS:

TOP CH.	LL	= 25.6	PSF
	DL	= 8.0	PSF
BOT CH.	LL	= 0.0	PSF
	DL	= 7.4	PSF
TOTAL LOAD	=	39.0	PSF

SPACING = 24.0 IN. C/C

THIS TRUSS IS DESIGNED FOR RESIDENTIAL OR SMALL BUILDING REQUIREMENTS OF PART 9, NBCC 2015

THIS DESIGN COMPLIES WITH:

- PART 9 OF BCBC 2018, ABC 2019
- PART 9 OF OBC 2012 (2019 AMENDMENT)
- CSA 086-14
- TPIC 2014

(55 % OF 31.3 P.S.F. G.S.L. PLUS 8.4 P.S.F. RAIN LOAD) EQUALS 25.6 P.S.F. SPECIFIED ROOF LIVE LOAD

ALLOWABLE DEFL.(LL)= L/360 (0.20")
CALCULATED VERT. DEFL.(LL) = L/999 (0.02")
ALLOWABLE DEFL.(TL)= L/360 (0.20")
CALCULATED VERT. DEFL.(TL) = L/999 (0.03")

CSI: TC=0.06/1.00 (A-B:1), BC=0.36/1.00 (E-F:1), WB=0.18/1.00 (B-D:1), SSI=0.19/1.00 (D-E:1)

DOL LUMBER=1.00 NAIL=1.00 LS BEND=1.00
COMP=1.00 SHEAR=1.00 TENS=1.00

COMPANION LIVE LOAD FACTOR = 1.00

TRUSS PLATE MANUFACTURER IS NOT RESPONSIBLE FOR QUALITY CONTROL IN THE TRUSS MANUFACTURING PLANT.

NAIL VALUES

PLATE GRIP(DRY)	SHEAR (PS)	SECTION (PLI)
MT20	650	371
	1747	788
	1987	1873

PLATE PLACEMENT TOL. = 0.250 inches

PLATE ROTATION TOL. = 5.0 Deg.

JSI GRIP= 0.78 (E) (INPUT = 0.90)
JSI METAL= 0.25 (E) (INPUT = 1.00)



Structural component only
DWG# T-2016981 1/2

CONTINUED ON PAGE 2

JOB NAME	TRUSS NAME	QUANTITY	PLY	JOB DESC.	DRWG NO.
410172	T28	2	2	GREEN PARK HOMES	
Tamarack Roof Truss, Burlington				TRUSS DESC.	

Version 8.330 S May 6 2020 MiTek Industries, Inc. Thu Jul 30 08:32:26 2020 Page 2
ID:W63xGm6okcO0SivZ4EwBx6zA2m0-SBK9R5PxUAqiv2WFCa9Tspgqn4imRNNe156UZysxoZ


PLATES (table is in inches)

JT	TYPE	PLATES	W	LEN	Y	X
F	BMV1-p	MT20	3.0	4.0		



Structural component only
DWG# T-2016981 *yr*

JOB NAME	TRUSS NAME	QUANTITY	PLY	JOB DESC.	DRWG NO.
410172	G28	4	1	GREEN PARK HOMES	
Tamarack Roof Truss, Burlington					



LUMBER

N. L. G. A. RULES	CHORDS	SIZE	LUMBER	DESCR.
Y - B	2x4	DRY	No.2	SPF
A - I	2x4	DRY	No.2	SPF
I - M	2x4	DRY	No.2	SPF
N - M	2x4	DRY	No.2	SPF
Y - Q	2x4	DRY	No.2	SPF
Q - N	2x4	DRY	No.2	SPF
ALL WEBS	2x3	DRY	No.2	SPF
ALL GABLE WEBS	2x3	DRY	No.2	SPF
DRY: SEASONED LUMBER.				

GABLE STUDS SPACED AT 2-0-0 OC.

PLATES (table is in inches)

JT TYPE	PLATES	W	LEN	Y	X
B TMV+p	MT20	3.0	4.0		
C, D, E, F, G, H, J, K, L					
C TMW+w	MT20	2.0	4.0		
I TS-I	MT20	3.0	6.0		
M TMV+p	MT20	3.0	4.0		
N BMV1+p	MT20	3.0	4.0		
O, P, R, S, T, U, V, W, X					
O BMW1+w	MT20	2.0	4.0		
Q BS-I	MT20	3.0	6.0		
Y BMV1+p	MT20	3.0	4.0		

DIMENSIONS, SUPPORTS AND LOADINGS SPECIFIED BY FABRICATOR TO BE VERIFIED BY BUILDING DESIGNER

BEARINGS

THIS TRUSS DESIGNED FOR CONTINUOUS BEARINGS.
THIS TRUSS REQUIRES RIGID SHEATHING ON EXPOSED FACE.
BEARING MATERIAL TO BE SPF NO.2 OR BETTER AT JOINT(S)

BRACING

TOP CHORD TO BE SHEATHED OR MAX. PURLIN SPACING = 6.25 FT.
MAX. UNBRACED BOTTOM CHORD LENGTH = 10.00 FT OR RIGID CEILING DIRECTLY APPLIED.
ALL PITCH BREAKS AND PERIMETER CORNER JOINTS MUST BE Laterally RESTRAINED.

1 LATERAL BRACE(S) AT 1/2 LENGTH OF M-N, L-O, K-P.

END VERTICAL(S) MUST BE SHEATHED OR HAVE BRACES AS INDICATED IN THE MAX. UNBRACED LENGTH COLUMN OF THE TABLE BELOW

LOADING

TOTAL LOAD CASES: (4)

CHORDS				WEBS			
MEMB.	MAX. FACTORED FORCE (LBS)	VERT. LOAD (PLF)	LC1 MAX CSI (LC)	MEMB.	MAX. FACTORED FORCE (LBS)	MAX. UNBRACED LENGTH	FR-TO
FR-TO				FR-TO			
Y-B	-238 / 0	0.0	0.02 (1)	O-L	-198 / 0	7.81	0.14 (1)
A-B	0 / 28	-91.8	-91.8 0.12 (1)	P-K	-182 / 0	10.00	0.10 (1)
B-C	-29 / 0	-91.8	-91.8 0.05 (1)	R-J	-183 / 0	6.25	0.25 (1)
C-D	-21 / 0	-91.8	-91.8 0.04 (1)	S-H	-183 / 0	6.25	0.17 (1)
D-E	-16 / 0	-91.8	-91.8 0.04 (1)	T-G	-183 / 0	6.25	0.12 (1)
E-F	-13 / 0	-91.8	-91.8 0.04 (1)	U-F	-182 / 0	6.25	0.08 (1)
F-G	-10 / 0	-91.8	-91.8 0.04 (1)	V-E	-182 / 0	6.25	0.05 (1)
G-H	-8 / 0	-91.8	-91.8 0.04 (1)	W-D	-180 / 0	10.00	0.03 (1)
H-I	-6 / 0	-91.8	-91.8 0.04 (1)	X-C	-186 / 0	10.00	0.03 (1)
I-J	-6 / 0	-91.8	-91.8 0.04 (1)				
J-K	-4 / 0	-91.8	-91.8 0.04 (1)				
K-L	-2 / 0	-91.8	-91.8 0.04 (1)				
L-M	-6 / 0	-91.8	-91.8 0.04 (1)				
N-M	-83 / 0	0.0	0.02 (1)				
Y-X	0 / 25	-18.5	-18.5 0.02 (4)				
X-W	0 / 19	-18.5	-18.5 0.02 (4)				
W-V	0 / 15	-18.5	-18.5 0.02 (4)				
V-U	0 / 12	-18.5	-18.5 0.02 (4)				
U-T	0 / 9	-18.5	-18.5 0.01 (4)				
T-S	0 / 7	-18.5	-18.5 0.01 (4)				
S-R	0 / 5	-18.5	-18.5 0.01 (4)				
R-Q	0 / 4	-18.5	-18.5 0.01 (4)				
Q-P	0 / 4	-18.5	-18.5 0.01 (4)				
P-O	0 / 3	-18.5	-18.5 0.02 (4)				
O-N	0 / 1	-18.5	-18.5 0.02 (4)				

TOTAL WEIGHT = 4 X 105 = 422 lb

DESIGN CRITERIA

SPECIFIED LOADS:

TOP CH. LL	= 25.6 PSF
DL	= 6.0 PSF
BOT CH. LL	= 0.0 PSF
DL	= 7.4 PSF
TOTAL LOAD	= 39.0 PSF

SPACING = 24.0 IN/C

THIS TRUSS IS DESIGNED FOR RESIDENTIAL OR SMALL BUILDING REQUIREMENTS OF PART 9, NBCC 2015

THIS DESIGN COMPLIES WITH:

- PART 9 OF CBC 2018, ABC 2019
- PART 9 OF OBC 2012 (2019 AMENDMENT)
- CSA 088-14
- TPIC 2014

DESIGN ASSUMPTIONS

OVERHANG NOT TO BE ALTERED OR CUT OFF.

(55 % OF 31.3 P.S.F. G.S.L. PLUS 8.4 P.S.F. RAIN LOAD) EQUALS 25.6 P.S.F. SPECIFIED ROOF LIVE LOAD

CSI: TC=0.12/1.00 (A-B:1), BC=0.02/1.00 (X-Y:4), WB=0.25/1.00 (J-R:1), SS=0.09/1.00 (A-B:1)

DOL LUMBER=1.00 NAIL=1.00 LS BEND=1.10
COMP=1.10 SHEAR=1.10 TENS=1.10

COMPANION LIVE LOAD FACTOR = 1.00

TRUSS PLATE MANUFACTURER IS NOT RESPONSIBLE FOR QUALITY CONTROL IN THE TRUSS MANUFACTURING PLANT.

NAIL VALUES

PLATE	GRIP(DRY)	SHEAR	SECTION
	(PSI)	(PLI)	(PLI)
	MAX	MIN	MAX MIN
MT20	650	371	1747 788 1987 1873

PLATE PLACEMENT TOL = 0.250 inches

PLATE ROTATION TOL = 5.0 Deg.

JSI GRIP = 0.38 (H) (INPUT = 0.90)

JSI METAL = 0.08 (L) (INPUT = 1.00)



Structural component only
DWG# T-2016969


JOB NAME	TRUSS NAME	QUANTITY	PLY	JOB DESC.	GREEN PARK HOMES	DRWG NO.
410174	T30	2	2	TRUSS DESC.		

Tamarack Roof Truss, Burlington

Version 8.330 S May 6 2020 MiTek Industries, Inc. Thu Jul 30 08:42:27 2020 Page 1

ID:W63xGm6okcO0SiyZ4EwBx6zA2m0-Mp8MZbgwyQSKHU1zws5KbCi?2EL4BYqr2AP5EysxfA

1-3-8 0-0 5-10-8 5-10-8 5-11-9 11-10-1 5-10-5 17-8-7 5-4-5 23-0-1223-9-0 8-4
Scale = 1:39.0



LUMBER

N. L. G. A. RULES	CHORDS	SIZE	DRY	LUMBER	DESCR.
A - C	2x4	DRY	No.2	SPF	
C - E	2x4	DRY	No.2	SPF	
E - G	2x4	DRY	No.2	SPF	
H - G	2x4	DRY	No.2	SPF	
M - B	2x6	DRY	No.2	SPF	
M - J	2x6	DRY	No.2	SPF	
J - H	2x6	DRY	No.2	SPF	

ALL WEBS 2x3 DRY No.2 SPF
EXCEPT

DRY: SEASONED LUMBER.

DESIGN CONSISTS OF 2 TRUSSES BUILT SEPARATELY THEN FASTENED TOGETHER AS FOLLOWS:

CHORDS #ROWS	SURFACE SPACING (IN)	LOAD(PLF)
TOP CHORDS : (0.122"x3") SPIRAL NAILS		
A - C	12	SIDE(61.0)
C - E	12	SIDE(61.0)
E - G	12	SIDE(0.0)
G - H	12	TOP
M - B	12	TOP
BOTTOM CHORDS : (0.122"x3") SPIRAL NAILS		
M - J	12	SIDE(183.1)
J - H	12	SIDE(0.0)
WEBS : (0.122"x3") SPIRAL NAILS		
2x3	6	

NAILS TO BE DRIVEN FROM ONE SIDE ONLY.

GIRDER NAILING ASSUMES NAILED HANGERS ARE FASTENED WITH MIN. 3-0 INCH NAILS.

TOP - COMPONENTS ARE LOADED FROM THE TOP AND MUST BE PLACED ON TOP EDGE OF ALL PLIES FOR THE LOAD TO BE TRANSFERRED TO EACH PLY.

SIDE - PLF SHOWN IS THE EQUIVALENT UDL APPLIED TO ONE SIDE THAT THE CORRESPONDING NAILING PATTERN SHALL BE CAPABLE OF TRANSFERING. REMAINING PLF MUST BE APPLIED ON THE OPPOSITE SIDE OR ON THE TOP.

DIMENSIONS, SUPPORTS AND LOADINGS SPECIFIED BY FABRICATOR TO BE VERIFIED BY BUILDING DESIGNER

BEARINGS

	FACTORED GROSS REACTION	MAXIMUM FACTORED GROSS REACTION	INPUT BRG	REQ'D BRG
JT	VERT	HORZ	UPLIFT	IN-SX
H	2221	0	0	1-8
M	2257	0	0	5-8

UNFACTORED REACTIONS

	1ST LCASE	MAX./MIN. COMPONENT REACTIONS					
JT	COMBINED	SNOW	LIVE	PERM.LIVE	WIND	DEAD	SOIL
H	1573	1022 / 0	0 / 0	0 / 0	0 / 0	551 / 0	0 / 0
M	1597	1045 / 0	0 / 0	0 / 0	0 / 0	551 / 0	0 / 0

BEARING MATERIAL TO BE SPF NO.2 OR BETTER AT JOINT(S) H, M

BRACING

TOP CHORD TO BE SHEATHED OR MAX. PURLIN SPACING = 4.33 FT.
MAX. UNBRACED BOTTOM CHORD LENGTH = 10.00 FT OR RIGID CEILING DIRECTLY APPLIED.

ALL PITCH BREAKS AND PERIMETER CORNER JOINTS MUST BE Laterally RESTRAINED.

LOADING

TOTAL LOAD CASES: (4)

CHORDS	MEMB.	MAX. FACTORED FORCE (LBS)	FACTORED VERT. LOAD (PLF)	MAX. LC1 MAX. CSI (LC)	WEBS	MEMB.	MAX. FACTORED FORCE (LBS)	MAX. UNBRACED LENGTH FR-TO	MAX. FACTORED FORCE (LBS)	MAX. CSI (LC)
A-B	0 / 28	-91.8	-91.8	0.07 (1)	10.00	L - C	-145 / 123	0.02 (4)		
B-C	-3176 / 0	-91.8	-91.8	0.40 (1)	4.80	B - L	0 / 2863	0.35 (1)		
C-N	-3700 / 0	-91.8	-91.8	0.49 (1)	4.37	I - G	0 / 3311	0.41 (1)		
N-O	-3700 / 0	-91.8	-91.8	0.49 (1)	4.37	C - K	0 / 1019	0.13 (1)		
O-P	-3700 / 0	-91.8	-91.8	0.49 (1)	4.37	F - F	-1528 / 0	0.19 (1)		
P-D	-3700 / 0	-91.8	-91.8	0.49 (1)	4.37	K - D	-941 / 0	0.12 (1)		
D-Q	-3700 / 0	-91.8	-91.8	0.51 (1)	4.33	K - F	0 / 1044	0.13 (1)		
Q-E	-3700 / 0	-91.8	-91.8	0.51 (1)	4.33					
E-R	-3700 / 0	-91.8	-91.8	0.51 (1)	4.33					
R-S	-3700 / 0	-91.8	-91.8	0.51 (1)	4.33					
S-F	-3700 / 0	-91.8	-91.8	0.51 (1)	4.33					
F-T	-2819 / 0	-91.8	-91.8	0.47 (1)	4.88					
T-U	-2819 / 0	-91.8	-91.8	0.47 (1)	4.88					
U-V	-2819 / 0	-91.8	-91.8	0.47 (1)	4.88					
V-G	-2819 / 0	-91.8	-91.8	0.47 (1)	4.88					
H-G	-2127 / 0	0.0	0.0	0.27 (1)	7.61					
M-B	-2185 / 0	0.0	0.0	0.28 (1)	7.81					

LOC.	LC1	MAX-	MAX+	FACE	DIR.	TYPE	HEEL	CONN.
JT	5-10-8	-409	-409	---	FRONT	VERT	---	C1
C	5-11-4	-26	-26	---	FRONT	VERT	---	C1
N	7-0-12	-110	-110	---	FRONT	VERT	---	C1
O	9-0-12	-110	-110	---	FRONT	VERT	---	C1
P	11-0-12	-110	-110	---	FRONT	VERT	---	C1
Q	13-0-12	-110	-110	---	FRONT	VERT	---	C1

FACTORED CONCENTRATED LOADS (LBS)

LOC.	LC1	MAX-	MAX+	FACE	DIR.	TYPE	HEEL	CONN.
JT	5-10-8	-409	-409	---	FRONT	VERT	---	C1
C	5-11-4	-26	-26	---	FRONT	VERT	---	C1
N	7-0-12	-110	-110	---	FRONT	VERT	---	C1
O	9-0-12	-110	-110	---	FRONT	VERT	---	C1
P	11-0-12	-110	-110	---	FRONT	VERT	---	C1
Q	13-0-12	-110	-110	---	FRONT	VERT	---	C1

TOTAL WEIGHT = 4 X 106 = 423 lb

DESIGN CRITERIA

SPECIFIED LOADS:

TOP CH.	LL	=	25.6	PSF
	DL	=	6.0	PSF
BOT CH.	LL	=	0.0	PSF
	DL	=	7.4	PSF
TOTAL LOAD	=	39.0	PSF	

SPACING = 24.0 IN. CC

LOADING IN FLAT SECTION BASED ON A SLOPE OF 6.00/12

THIS TRUSS IS DESIGNED FOR RESIDENTIAL OR SMALL BUILDING REQUIREMENTS OF PART 9, NBCC 2015

THIS DESIGN COMPLIES WITH:

- PART 9 OF CBC 2018, ABC 2019
- PART 9 OF CBC 2012 (2019 AMENDMENT)
- CSA 086-14
- TPIC 2014

(55% OF 31.3 P.S.F. G.S.L. PLUS 8.4 P.S.F. RAIN LOAD) EQUALS 25.6 P.S.F. SPECIFIED ROOF LIVE LOAD

ALLOWABLE DEFL.(LL) = $L/360$ (0.79")
CALCULATED VERT. DEFL.(LL) = $L/999$ (0.08")
ALLOWABLE DEFL.(TL) = $L/360$ (0.79")
CALCULATED VERT. DEFL.(TL) = $L/999$ (0.14")

CSI: TC=0.51/1.00 (D-F:1), BC=0.23/1.00 (K-L:1), WB=0.41/1.00 (G-I:1), SSI=0.23/1.00 (C-D:1)

DOL LUMBER=1.00 NAIL=1.00 LS BEND=1.00
COMP=1.00 SHEAR=1.00 TENS=1.00

COMPANION LIVE LOAD FACTOR = 1.00

AUTOSOLVE RIGHT HEEL ONLY

TRUSS PLATE MANUFACTURER IS NOT RESPONSIBLE FOR QUALITY CONTROL IN THE TRUSS MANUFACTURING PLANT

NAIL VALUES

PLATE GRIP(DRY)	SHEAR	SECTION
(PSI)	(PLI)	(PLI)
MAX MIN	MAX MIN	MAX MIN
MT20	650 371	1747 788 1987 1873

PLATE PLACEMENT TOL. = 0.250 inches

PLATE ROTATION TOL. = 5.0 Deg.

JSI GRIP= 0.79 (B) (INPUT = 0.90)
JSI METAL= 0.34 (B) (INPUT = 1.00)



Structural component only
DWG# T-2016987 1/2

CONTINUED ON PAGE 2

JOB NAME	TRUSS NAME	QUANTITY	PLY	JOB DESC.	GREEN PARK HOMES	DRWG NO.
410174	T30	2	2	TRUSS DESC.		

Tamarack Roof Truss, Burlington

Version 8.330 S May 6 2020 MiTek Industries, Inc. Thu Jul 30 08:42:27 2020 Page 2

ID:W63xGm6okcO0SiyZ4EwBx6zA2m0-Mp8MZbqwgqOSKHU1zws5KbCI?2EL4BYqr2AP5EysxfA

PLATES (table is in inches)

JT	TYPE	PLATES	W	LEN	Y	X
B	TMVW-p	MT20	4.0	6.0	1.00	3.25
C	TTWW-m	MT20	5.0	6.0	2.25	2.00
D	TMW+w	MT20	2.0	4.0		
E	TS-t	MT20	3.0	6.0		
F	TMWW-t	MT20	4.0	4.0		
G	TMVW-t	MT20	5.0	6.0		
H	BMV1+p	MT20	3.0	6.0		
I	BMWW-t	MT20	5.0	6.0		
J	BS-t	MT20	5.0	6.0		
K	BMWWW-t	MT20	5.0	8.0		
L	BMWW-t	MT20	5.0	6.0		
M	BMV1+p	MT20	3.0	6.0		

FACTORED CONCENTRATED LOADS (LBS)

JT	LOC.	LC1	MAX-	MAX+	FACE	DIR.	TYPE	HEEL	CONN.
R	15-0-12	-110	-110	---	FRONT	VERT	TOTAL	---	C1
S	17-0-12	-110	-110	---	FRONT	VERT	TOTAL	---	C1
T	19-0-12	-110	-110	---	FRONT	VERT	TOTAL	---	C1
U	21-0-12	-110	-110	---	FRONT	VERT	TOTAL	---	C1
V	23-0-12	-125	-125	---	FRONT	VERT	TOTAL	---	C1
W	1-11-4	-25	-25	---	FRONT	VERT	TOTAL	---	C1
X	3-11-4	-26	-26	---	FRONT	VERT	TOTAL	---	C1
Y	7-0-12	-26	-26	---	FRONT	VERT	TOTAL	---	C1
Z	9-0-12	-26	-26	---	FRONT	VERT	TOTAL	---	C1
AA	11-0-12	-26	-26	---	FRONT	VERT	TOTAL	---	C1
AB	13-0-12	-26	-26	---	FRONT	VERT	TOTAL	---	C1
AC	15-0-12	-26	-26	---	FRONT	VERT	TOTAL	---	C1
AD	17-0-12	-26	-26	---	FRONT	VERT	TOTAL	---	C1
AE	19-0-12	-26	-26	---	FRONT	VERT	TOTAL	---	C1
AF	21-0-12	-26	-26	---	FRONT	VERT	TOTAL	---	C1
AG	23-0-12	-29	-29	---	FRONT	VERT	TOTAL	---	C1

CONNECTION REQUIREMENTS

- 1) C1: A SUITABLE HANGER/MECHANICAL CONNECTION IS REQUIRED.




Structural component only
DWG# T-2016987 *7/2*

JOB NAME 410174	TRUSS NAME T30Z	QUANTITY 1	PLY 2	JOB DESC. GREEN PARK HOMES	DRWG NO.
--------------------	--------------------	---------------	----------	-------------------------------	----------

Tamarack Roof Truss, Burlington

Version 8.330 S May 6 2020 Mitek Industries, Inc. Thu Jul 30 08:42:28 2020 Page 1
ID:W63xGm6okc00SiyZ4EwBx6zA2m0-g?iknXhYj7WJxQ3DWdOKspIS4SUpdL_4iwydgysxf9



LUMBER

N. L. G. A. RULES

CHORDS	SIZE	LUMBER	DESCR.
A - C	2x4	DRY No.2	SPF
C - E	2x4	DRY No.2	SPF
E - G	2x4	DRY No.2	SPF
H - G	2x4	DRY No.2	SPF
M - B	2x6	DRY No.2	SPF
M - J	2x6	DRY No.2	SPF
J - H	2x6	DRY No.2	SPF

ALL WEBS 2x3 DRY No.2 SPF
EXCEPT

DRY: SEASONED LUMBER.

DESIGN CONSISTS OF 2 TRUSSES BUILT SEPARATELY THEN FASTENED TOGETHER AS FOLLOWS:

CHORDS #ROWS	SURFACE SPACING (IN)	LOAD(PLF)
TOP CHORDS : (0.122"x3") SPIRAL NAILS		
A - C	12	TOP
C - E	12	TOP
E - G	12	TOP
G - H	12	TOP
M - B	12	TOP
BOTTOM CHORDS : (0.122"x3") SPIRAL NAILS		
M - J	12	SIDE(0.0)
J - H	12	SIDE(183.1)
WEBS : (0.122"x3") SPIRAL NAILS		
2x3	6	

NAILS TO BE DRIVEN FROM ONE SIDE ONLY.

GIRDER NAILING ASSUMES NAILED HANGERS ARE FASTENED WITH MIN. 3-0 INCH NAILS.

TOP - COMPONENTS ARE LOADED FROM THE TOP AND MUST BE PLACED ON TOP EDGE OF ALL PLIES FOR THE LOAD TO BE TRANSFERRED TO EACH PLY.

SIDE - PLF SHOWN IS THE EQUIVALENT UDL APPLIED TO ONE SIDE THAT THE CORRESPONDING NAILING PATTERN SHALL BE CAPABLE OF TRANSFERRING. REMAINING PLF MUST BE APPLIED ON THE OPPOSITE SIDE OR ON THE TOP.

DIMENSIONS, SUPPORTS AND LOADINGS SPECIFIED BY FABRICATOR TO BE VERIFIED BY BUILDING DESIGNER

BEARINGS

	FACTORED GROSS REACTION	MAXIMUM FACTORED GROSS REACTION	INPUT BRG	RECORD BRG
JT	VERT	HORZ	DOWN	UPLIFT
H	2629	0	2629	0
M	2084	0	2084	0

UNFACTORED REACTIONS

	1ST LOASE	MAX./MIN. COMPONENT REACTIONS					
JT	COMBINED	SNOW	LIVE	PERM.LIVE	WIND	DEAD	SOIL
H	1859	1221 / 0	0 / 0	0 / 0	0 / 0	637 / 0	0 / 0
M	1470	984 / 0	0 / 0	0 / 0	0 / 0	486 / 0	0 / 0

BEARING MATERIAL TO BE SPF NO.2 OR BETTER AT JOINT(S) H, M

BRACING

TOP CHORD TO BE SHEATHED OR MAX. PURLIN SPACING = 4.00 FT.
MAX. UNBRACED BOTTOM CHORD LENGTH = 10.00 FT OR RIGID CEILING DIRECTLY APPLIED.

ALL PITCH BREAKS AND PERIMETER CORNER JOINTS MUST BE Laterally RESTRAINED.

LOADING

TOTAL LOAD CASES: (4)

CHORDS	MAX. FACTORED	FACTORED	W E B S	MAX. FACTORED
MEMB.	FORCE (LBS)	VERT. LOAD LC1 (PLF)	MAX. UNBRAC LENGTH FR-TO	MEMB. FORCE (LBS)
FR-TO		FROM TO		
A-B	0 / 28	-91.8 -91.8 0.07 (1)	10.00	L-C -324 / 0 0.04 (1)
B-C	-2875 / 0	-91.8 -91.8 0.38 (1)	5.00	B-L 0 / 2592 0.32 (1)
C-D	-4357 / 0	-91.8 -91.8 0.40 (1)	4.23	I-G 0 / 4064 0.50 (1)
D-E	-4357 / 0	-91.8 -91.8 0.55 (1)	4.00	C-K 0 / 2117 0.26 (1)
E-N	-4357 / 0	-91.8 -91.8 0.55 (1)	4.00	I-F -1583 / 0 0.20 (1)
N-O	-4357 / 0	-91.8 -91.8 0.55 (1)	4.00	K-F -665 / 0 0.08 (1)
O-F	-4357 / 0	-91.8 -91.8 0.55 (1)	4.00	K-F 0 / 1064 0.13 (1)
F-P	-3459 / 0	-91.8 -91.8 0.51 (1)	4.46	
P-Q	-3459 / 0	-91.8 -91.8 0.51 (1)	4.46	
Q-G	-3459 / 0	-91.8 -91.8 0.51 (1)	4.46	
H-G	-2569 / 0	0.0 0.0 0.32 (1)	7.08	
M-B	-2016 / 0	0.0 0.0 0.07 (1)	7.81	
M-L	0 / 0	-18.5 -18.5 0.05 (1)	10.00	
L-K	0 / 2561	-18.5 -18.5 0.33 (1)	10.00	
K-R	0 / 3459	-18.5 -18.5 0.61 (1)	10.00	
R-S	0 / 3459	-18.5 -18.5 0.61 (1)	10.00	
S-T	0 / 3459	-18.5 -18.5 0.61 (1)	10.00	
T-J	0 / 3459	-18.5 -18.5 0.61 (1)	10.00	
J-I	0 / 3459	-18.5 -18.5 0.61 (1)	10.00	
I-U	0 / 0	-18.5 -18.5 0.12 (1)	10.00	
U-V	0 / 0	-18.5 -18.5 0.12 (1)	10.00	
V-H	0 / 0	-18.5 -18.5 0.12 (1)	10.00	

FACTORED CONCENTRATED LOADS (LBS)

JT	LOC.	LC1	MAX-	MAX+	FACE	DIR.	TYPE	HEEL	CONN.
F	17-5-12	-110	-110	---	BACK	VERT	TOTAL	---	C1
G	23-9-0	-144	-144	---	BACK	VERT	TOTAL	---	C1
H	23-9-0	-33	-33	---	BACK	VERT	TOTAL	---	C1
I	17-5-12	-26	-26	---	BACK	VERT	TOTAL	---	C1
N	14-5-12	-110	-110	---	BACK	VERT	TOTAL	---	C1
O	15-5-12	-110	-110	---	BACK	VERT	TOTAL	---	C1
P	19-5-12	-110	-110	---	BACK	VERT	TOTAL	---	C1
Q	21-5-12	-110	-110	---	BACK	VERT	TOTAL	---	C1
R	13-8-8	-1108	-1108	---	BACK	VERT	TOTAL	---	C1
S	14-5-12	-26	-26	---	BACK	VERT	TOTAL	---	C1
T	15-5-12	-26	-26	---	BACK	VERT	TOTAL	---	C1
U	19-5-12	-26	-26	---	BACK	VERT	TOTAL	---	C1
V	21-5-12	-26	-26	---	BACK	VERT	TOTAL	---	C1

CONNECTION REQUIREMENTS

1) C1: A SUITABLE HANGER/MECHANICAL CONNECTION IS REQUIRED.

TOTAL WEIGHT = 2 X 106 = 212 lb

DESIGN CRITERIA

SPECIFIED LOADS:

TOP CH.	LL = 25.6	PSF
	DL = 6.0	PSF
BOT CH.	LL = 0.0	PSF
	DL = 7.4	PSF
TOTAL LOAD	= 39.0	PSF

SPACING = 24.0 IN.C/C

LOADING IN FLAT SECTION BASED ON A SLOPE OF 6.00/12

THIS TRUSS IS DESIGNED FOR RESIDENTIAL OR SMALL BUILDING REQUIREMENTS OF PART 9, NBCC 2015

THIS DESIGN COMPLIES WITH:

- PART 9 OF BCBC 2018, ABC 2019
- PART 9 OF OBC 2012 (2019 AMENDMENT)
- CSA 088-14
- TPIC 2014

(55 % OF 31.3 P.S.F. G.S.L. PLUS 8.4 P.S.F. RAIN LOAD) EQUALS 25.6 P.S.F. SPECIFIED ROOF LIVE LOAD

ALLOWABLE DEFL.(LL)= L/360 (0.79")
CALCULATED VERT. DEFL.(LL) = L/999 (0.11")
ALLOWABLE DEFL.(TL)= L/360 (0.79")
CALCULATED VERT. DEFL.(TL) = L/999 (0.21")

CSI: TC=0.55/1.00 (D-F:1), BC=0.61/1.00 (I-K:1), WB=0.50/1.00 (G-I:1), SS=0.29/1.00 (I-K:1)

DOL LUMBER=1.00 NAIL=1.00 LS BEND=1.00
COMP=1.00 SHEAR=1.00 TENS= 1.00

COMPANION LIVE LOAD FACTOR = 1.00

AUTOSOLVE RIGHT HEEL ONLY

TRUSS PLATE MANUFACTURER IS NOT RESPONSIBLE FOR QUALITY CONTROL IN THE TRUSS MANUFACTURING PLANT.

NAIL VALUES

PLATE	GRIP(DRY)	SHEAR	SECTION
(PSI)	(PLI)	(PLI)	(PLI)
MAX	MIN	MAX	MIN
MT20	650	371	1747
	788	1987	1873

PLATE PLACEMENT TOL. = 0.250 inches

PLATE ROTATION TOL. = 5.0 Deg.

JSI GRIP= 0.84 (I) (INPUT = 0.90)
JSI METAL= 0.44 (J) (INPUT = 1.00)



Structural component only
DWG# T-2016988 1/2

JOB NAME	TRUSS NAME	QUANTITY	PLY	JOB DESC.	DRWG NO.
410174	T30Z	1	2	GREEN PARK HOMES	
Tamarack Roof Truss, Burlington				TRUSS DESC.	

Version 8.330 S May 6 2020 MiTek Industries, Inc. Thu Jul 30 08:42:28 2020 Page 2

ID:W63xGm6okcO0SivZ4EwBx6zA2m0-q?iknXhYj7WJxQ3DWdOKspIS4SUipdL_4iwvdqvsxf9

PLATES (table is in inches)

JT	TYPE	PLATES	W	LEN	Y	X
B	TMVW-p	MT20	4.0	6.0	1.00	3.00
C	TTWW-m	MT20	5.0	8.0	2.25	3.25
D	TMW-w	MT20	2.0	4.0		
E	TS-t	MT20	3.0	6.0		
F	TMVW-t	MT20	4.0	4.0		
G	TMVW-t	MT20	4.0	9.0		Edge
H	BMV1+p	MT20	3.0	6.0		
I	BMVW-t	MT20	5.0	6.0	2.50	2.75
J	BS-t	MT20	5.0	6.0		
K	BMVWW-t	MT20	5.0	8.0		
L	BMVW-t	MT20	5.0	6.0		
M	BMV1+p	MT20	3.0	6.0		


Edge - INDICATES REFERENCE CORNER OF PLATE TOUCHES EDGE OF CHORD.

CONNECTION REQUIREMENTS

- 1) C1: A SUITABLE HANGER/MECHANICAL CONNECTION IS REQUIRED.



Structural component only
DWG# T-2016988 *me*



LUMBER			
N. L. G. A. RULES			
CHORDS	SIZE	LUMBER	DESCR.
A - D	2x4	DRY	No.2
D - G	2x4	DRY	No.2
H - G	2x4	DRY	No.2
M - B	2x4	DRY	No.2
M - J	2x4	DRY	No.2
J - H	2x4	DRY	No.2

ALL WEBS 2x3 DRY No.2 SPF

EXCEPT DRY: SEASONED LUMBER.

PLATES (table is in inches)

JT	TYPE	PLATES	W	LEN	Y	X
B	TMV+p	MT20	3.0	4.0		
C	TMVW-t	MT20	4.0	6.0		
D	TTWW-m	MT20	5.0	6.0	2.25	2.00
E	TMVW-t	MT20	4.0	4.0		
F	TMVW-w	MT20	2.0	4.0		
G	TMVW-t	MT20	5.0	6.0		
H	BMV1+p	MT20	3.0	4.0		
I	BMVWW-t	MT20	5.0	8.0		
J	BS-t	MT20	3.0	6.0		
K	BMVW-t	MT20	4.0	4.0		
L	BMVW-t	MT20	4.0	4.0		
M	BMVW-t	MT20	5.0	6.0		

DIMENSIONS, SUPPORTS AND LOADINGS SPECIFIED BY FABRICATOR TO BE VERIFIED BY BUILDING DESIGNER

BEARINGS		FACTORED		MAXIMUM FACTORED		INPUT		RECORD	
JT	GROSS REACTION	VERT	HORZ	DOWN	HORZ	BRG	IN-SX	BRG	IN-SX
H	1309	0	0	1309	0	0	1-8	1-8	
M	1434	0	0	1434	0	0	5-8	5-8	

UNFACTORED REACTIONS

1ST LCASE		MAX. MIN. COMPONENT REACTIONS							
JT	COMBINED	SNOW	LIVE	PERM. LIVE	WIND	DEAD	SOIL		
H	926	608 / 0	0 / 0	0 / 0	0 / 0	318 / 0	0 / 0		
M	1012	677 / 0	0 / 0	0 / 0	0 / 0	335 / 0	0 / 0		

BEARING MATERIAL TO BE SPF NO.2 OR BETTER AT JOINT(S) H, M

BRACING

TOP CHORD TO BE SHEATHED OR MAX. PURLIN SPACING = 4.70 FT.
MAX. UNBRACED BOTTOM CHORD LENGTH = 10.00 FT OR RIGID CEILING DIRECTLY APPLIED.

ALL PITCH BREAKS AND PERIMETER CORNER JOINTS MUST BE Laterally RESTRAINED.

LOADING

TOTAL LOAD CASES: (4)

CHORDS				WEBS			
MEMB.	MAX. FACTORED FORCE (LBS)	FACTORED VERT. LOAD (PLF)	MAX. CSI (LC)	MEMB.	MAX. FACTORED FORCE (LBS)	MAX. CSI (LC)	
FR-TO		FROM TO		FR-TO			
A-B	0 28	-91.8 -91.8 0.12 (1)	10.00	C-L	-108 27	0.04 (1)	
B-C	0 17	-91.8 -91.8 0.21 (1)	10.00	L-D	0 213	0.05 (4)	
C-D	-1642 0	-91.8 -91.8 0.25 (1)	4.91	M-C	-1895 0	0.73 (1)	
D-E	-1649 0	-91.8 -91.8 0.40 (1)	4.70	I-G	0 1601	0.36 (1)	
E-F	-1194 0	-91.8 -91.8 0.38 (1)	5.35	D-K	0 261	0.06 (1)	
F-G	-1194 0	-91.8 -91.8 0.38 (1)	5.35	I-F	-532 0	0.20 (1)	
H-G	-1268 0	0.0 0.0 0.56 (1)	7.15	K-E	-102 43	0.04 (1)	
M-B	-268 0	0.0 0.0 0.03 (1)	7.81	E-I	-621 0	0.59 (1)	
M-L	0 1540	-18.5 -18.5 0.39 (1)	10.00				
L-K	0 1456	-18.5 -18.5 0.38 (4)	10.00				
K-J	0 1650	-18.5 -18.5 0.33 (1)	10.00				
J-I	0 1650	-18.5 -18.5 0.33 (1)	10.00				
I-H	0 0	-18.5 -18.5 0.13 (4)	10.00				

TOTAL WEIGHT = 4 X 98 = 392 lb

DESIGN CRITERIA

SPECIFIED LOADS:

TOP CH.	LL = 25.6	PSF
	DL = 6.0	PSF
BOT CH.	LL = 0.0	PSF
	DL = 7.4	PSF
TOTAL LOAD	= 39.0	PSF

SPACING = 24.0 IN. C/C

LOADING IN FLAT SECTION BASED ON A SLOPE OF 6.00/12

THIS TRUSS IS DESIGNED FOR RESIDENTIAL OR SMALL BUILDING REQUIREMENTS OF PART 9, NBC 2015

THIS DESIGN COMPLIES WITH:

- PART 9 OF CBC 2018, ABC 2019
- PART 9 OF OBC 2012 (2019 AMENDMENT)
- CSA 086-14
- TPIC 2014

(55 % OF 31.3 P.S.F. G.S.L. PLUS 8.4 P.S.F. RAIN LOAD) EQUALS 25.6 P.S.F. SPECIFIED ROOF LIVE LOAD

ALLOWABLE DEFL.(LL)= L/360 (0.79")
CALCULATED VERT. DEFL.(LL)= L/999 (0.06")
ALLOWABLE DEFL.(TL)= L/360 (0.79")
CALCULATED VERT. DEFL.(TL)= L/999 (0.16")

CSI: TC=0.56/1.00 (G-H:1), BC=0.39/1.00 (L-M:1)
WB=0.73/1.00 (C-M:1), SS=0.23/1.00 (F-G:1)

DOL LUMBER=1.00 NAIL=1.00 LS BEND=1.10
COMP=1.10 SHEAR=1.10 TENS=1.10

COMPANION LIVE LOAD FACTOR = 1.00

TRUSS PLATE MANUFACTURER IS NOT RESPONSIBLE FOR QUALITY CONTROL IN THE TRUSS MANUFACTURING PLANT.

NAIL VALUES

PLATE	GRIP(DRY)	SHEAR	SECTION
	(PSI)	(PLI)	(PLI)
MT20	650	371	1747 788 1987 1873


PLATE PLACEMENT TOL. = 0.250 inches

PLATE ROTATION TOL. = 5.0 Deg.

JSI GRIP= 0.81 (I) (INPUT = 0.90)
JSI METAL= 0.54 (J) (INPUT = 1.00)




Structural component only
DWG# T-2017121



JOB NAME	TRUSS NAME	QUANTITY	PLY	JOB DESC.	GREEN PARK HOMES	DRWG NO.
410116	T33	4	1	TRUSS DESC.		

Tamarack Roof Truss, Burlington

Version 8.330 S May 6 2020 MTek Industries, Inc. Tue Aug 4 12:39:42 2020 Page 1
ID:W63xGm60kc00SiyZ4EwBx6zA2m0-F5vbWq0T_Ylv41ggSk6sRYPdISZ_CGrQvkiHyrEil
23-9-0



LUMBER
N. L. G. A. RULES
CHORDS SIZE LUMBER DESCR.
A - D 2x4 DRY No.2 SPF
D - F 2x4 DRY No.2 SPF
G - F 2x4 DRY No.2 SPF
L - B 2x4 DRY No.2 SPF
L - I 2x4 DRY No.2 SPF
I - G 2x4 DRY No.2 SPF
ALL WEBS 2x3 DRY No.2 SPF
EXCEPT
DRY: SEASONED LUMBER.

JT	TYPE	PLATES	W	LEN	Y	X
B	TMVW-t	MT20	4.0	6.0	2.00	3.00
C	TMVW-t	MT20	4.0	4.0	2.00	1.75
D	TTWW-m	MT20	5.0	6.0	2.25	2.00
E	TMVW-t	MT20	2.0	4.0		
F	TMVW-t	MT20	5.0	6.0		
G	BMV1+p	MT20	3.0	4.0		
H	BMVWW-t	MT20	5.0	8.0		
I	BS-t	MT20	3.0	6.0		
J	BMVWW-t	MT20	4.0	4.0		
K	BMVWW-t	MT20	5.0	6.0		
L	BMV1+p	MT20	3.0	4.0		

PLATES (table is in inches)

JT	TYPE	PLATES	W	LEN	Y	X
B	TMVW-t	MT20	4.0	6.0	2.00	3.00
C	TMVW-t	MT20	4.0	4.0	2.00	1.75
D	TTWW-m	MT20	5.0	6.0	2.25	2.00
E	TMVW-t	MT20	2.0	4.0		
F	TMVW-t	MT20	5.0	6.0		
G	BMV1+p	MT20	3.0	4.0		
H	BMVWW-t	MT20	5.0	8.0		
I	BS-t	MT20	3.0	6.0		
J	BMVWW-t	MT20	4.0	4.0		
K	BMVWW-t	MT20	5.0	6.0		
L	BMV1+p	MT20	3.0	4.0		

DIMENSIONS, SUPPORTS AND LOADINGS SPECIFIED BY FABRICATOR TO BE VERIFIED BY BUILDING DESIGNER

JT	FACTORED GROSS REACTION		MAXIMUM FACTORED GROSS REACTION		INPUT BRG IN-SX	REQD BRG IN-SX
	VERT	HORZ	DOWN	HORZ		
G	1309	0	1309	0	1-8	1-8
L	1434	0	1434	0	5-8	5-8

UNFACTORED REACTIONS

JT	COMBINED	SNOW	LIVE	PERM.LIVE	WIND	DEAD	SOIL
G	926	608	0	0	0	318	0
L	1012	677	0	0	0	335	0

BEARING MATERIAL TO BE SPF NO.2 OR BETTER AT JOINT(S) G, L

BRACING
TOP CHORD TO BE SHEATHED OR MAX. PURLIN SPACING = 4.15 FT.
MAX. UNBRACED BOTTOM CHORD LENGTH = 10.00 FT OR RIGID CEILING DIRECTLY APPLIED

ALL PITCH BREAKS AND PERIMETER CORNER JOINTS MUST BE Laterally RESTRAINED.

1 LATERAL BRACE(S) AT 1/2 LENGTH OF F-G, D-H.

END VERTICAL(S) MUST BE SHEATHED OR HAVE BRACES AS INDICATED IN THE MAX. UNBRACED LENGTH COLUMN OF THE TABLE BELOW

LOADING
TOTAL LOAD CASES: (4)

CHORDS				WEBS						
MEMB.	MAX. FACTORED FORCE (LBS)	FACTORED			MAX. UNBRACED LENGTH	MEMB.	MAX. FACTORED FORCE (LBS)	MAX CS(I/LC)		
		VERT. LOAD	PLF	CS(I/LC)						
FR-TO		FROM	TO		FR-TO					
A-B	0 28	-91.8	-91.8	0.12 (1)	10.00	K-C	-117 60	0.03 (1)		
B-C	-1802 0	-91.8	-91.8	0.68 (1)	4.15	C-J	-584 0	0.58 (1)		
C-D	-1309 0	-91.8	-91.8	0.62 (1)	4.78	J-D	0 420	0.09 (1)		
D-E	-926 0	-91.8	-91.8	0.58 (1)	5.47	B-K	0 1654	0.37 (1)		
E-F	-926 0	-91.8	-91.8	0.58 (1)	5.47	H-F	0 1404	0.32 (1)		
G-F	-1264 0	0.0	0.0	0.29 (1)	5.73	D-H	-343 0	0.19 (1)		
L-B	-1387 0	0.0	0.0	0.14 (1)	6.90	H-E	-676 0	0.59 (1)		
L-K	0 0	-18.5	-18.5	0.15 (4)	10.00					
K-J	0 1637	-18.5	-18.5	0.33 (1)	10.00					
J-I	0 1150	-18.5	-18.5	0.26 (1)	10.00					
I-H	0 1150	-18.5	-18.5	0.26 (1)	10.00					
H-G	0 0	-18.5	-18.5	0.16 (4)	10.00					

DESIGN CRITERIA

SPECIFIED LOADS:
TOP CH. LL = 25.6 PSF
DL = 6.0 PSF
BOT CH. LL = 0.0 PSF
DL = 7.4 PSF
TOTAL LOAD = 39.0 PSF

SPACING = 24.0 IN. C/C

LOADING IN FLAT SECTION BASED ON A SLOPE OF 6.00/12

THIS TRUSS IS DESIGNED FOR RESIDENTIAL OR SMALL BUILDING REQUIREMENTS OF PART 9, NBCC 2015

THIS DESIGN COMPLIES WITH:
- PART 9 OF BCBC 2018, ABC 2019
- PART 9 OF OBC 2012 (2019 AMENDMENT)
- CSA 086-14
- TPIC 2014

(55% OF 31.3 P.S.F. G.S.L. PLUS 8.4 P.S.F. RAIN LOAD) EQUALS 25.6 P.S.F. SPECIFIED ROOF LIVE LOAD

ALLOWABLE DEFL.(LL) = L/360 (0.79")
CALCULATED VERT. DEFL.(LL) = L/999 (0.06")
ALLOWABLE DEFL.(TL) = L/360 (0.79")
CALCULATED VERT. DEFL.(TL) = L/999 (0.12")

CSI: TC=0.68/1.00 (B-C:1), BC=0.33/1.00 (J-K:1), WB=0.59/1.00 (E-H:1), SSI=0.27/1.00 (E-F:1)

DOL LUMBER=1.00 NAIL=1.00 LS BEND=1.10
COMP=1.10 SHEAR=1.10 TENS=1.10

COMPANION LIVE LOAD FACTOR = 1.00


TRUSS PLATE MANUFACTURER IS NOT RESPONSIBLE FOR QUALITY CONTROL IN THE TRUSS MANUFACTURING PLANT

NAIL VALUES
PLATE GRIP(DRY) SHEAR SECTION (PSI) (PLI) (PLI)
MAX MIN MAX MIN MAX MIN
MT20 650 371 1747 788 1987 1873

PLATE PLACEMENT TOL. = 0.250 inches

PLATE ROTATION TOL. = 5.0 Deg.


JSI GRIP= 0.83 (B) (INPUT = 0.90)
JSI METAL= 0.45 (B) (INPUT = 1.00)



Structural component only
DWG# T-2017123

JOB NAME	TRUSS NAME	QUANTITY	PLY	JOB DESC.	DRWG NO.
410116	T34	4	1	GREEN PARK HOMES	
Tamarack Roof Truss, Burlington					

Version 8.330 S May 6 2020 MTek Industries, Inc. Tue Aug 4 12:39:43 2020 Page 1
ID:W63xGm60kc00SiyZ4EwBx6Z2m0-jITziA15rQmBF00Se5zlyobUvaxhEsfZTGBjyrEik
13-10-8 18-9-4 23-9-0
Scale = 1:4.2



LUMBER				DESCR.	
N. L. G. A. RULES	CHORDS	SIZE	LUMBER	SPF	
A - D	2x4	DRY	No.2	SPF	
D - E	2x4	DRY	No.2	SPF	
E - G	2x4	DRY	No.2	SPF	
H - G	2x4	DRY	No.2	SPF	
M - B	2x4	DRY	No.2	SPF	
M - J	2x4	DRY	No.2	SPF	
J - H	2x4	DRY	No.2	SPF	
ALL WEBS EXCEPT	2x3	DRY	No.2	SPF	
DRY: SEASONED LUMBER.					

DIMENSIONS, SUPPORTS AND LOADINGS SPECIFIED BY FABRICATOR TO BE VERIFIED BY BUILDING DESIGNER

BEARINGS		FACTORED		MAXIMUM FACTORED		INPUT		REQD	
JT	VERT	GROSS REACTION	HORZ	GROSS REACTION	HORZ	BRG	IN-SX	BRG	IN-SX
H	1309	0	1309	0	0	1-8	1-8		
M	1434	0	1434	0	0	5-8	5-8		

UNFACTORED REACTIONS

JT	COMBINED	SNOW	MIN. LIVE	PERM. LIVE	WIND	DEAD	SOIL
H	926	608	0	0	0	318	0
M	1012	677	0	0	0	335	0

BEARING MATERIAL TO BE SPF NO.2 OR BETTER AT JOINT(S) H, M

BRACING

TOP CHORD TO BE SHEATHED OR MAX. PURLIN SPACING = 4.17 FT.
MAX. UNBRACED BOTTOM CHORD LENGTH = 10.00 FT OR RIGID CEILING DIRECTLY APPLIED.

ALL PITCH BREAKS AND PERIMETER CORNER JOINTS MUST BE Laterally RESTRAINED.

1 LATERAL BRACE(S) AT 1/2 LENGTH OF G-H, C-K, E-I.

END VERTICAL(S) MUST BE SHEATHED OR HAVE BRACES AS INDICATED IN THE MAX. UNBRACED LENGTH COLUMN OF THE TABLE BELOW

LOADING

TOTAL LOAD CASES: (4)

CHORDS		FACTORED		FACTORED		WEBS		FACTORED	
MEMB.	FORCE (LBS)	VERT. LOAD (PLF)	LC1	MAX	UNBRAC LENGTH	MEMB.	FORCE (LBS)	MAX	CSI (LC)
FR-TO		FROM	TO			FR-TO			
A-B	0	-91.8	-91.8	0.12 (1)	10.00	L-C	-52	100	0.03 (4)
B-C	-1780	-91.8	-91.8	0.67 (1)	4.17	C-K	-774	0	0.35 (1)
C-D	-1118	-91.8	-91.8	0.60 (1)	5.11	K-E	0	520	0.12 (1)
D-E	-1118	-91.8	-91.8	0.60 (1)	5.11	B-L	0	1634	0.37 (1)
E-F	-698	-91.8	-91.8	0.29 (1)	6.25	I-G	0	1299	0.29 (1)
F-G	-698	-91.8	-91.8	0.29 (1)	6.25	E-I	-521	0	0.30 (1)
H-G	-1270	0	0	0.38 (1)	5.71	I-F	-560	0	0.71 (1)
M-B	-1380	0	0	0.14 (1)	6.92				
M-L	0	-18.5	-18.5	0.22 (4)	10.00				
L-K	0	-18.5	-18.5	0.37 (1)	10.00				
K-J	0	-18.5	-18.5	0.22 (1)	10.00				
J-I	0	-18.5	-18.5	0.22 (1)	10.00				
I-H	0	-18.5	-18.5	0.10 (4)	10.00				

TOTAL WEIGHT = 4 X 109 = 436 lb (M/F)

DESIGN CRITERIA

SPECIFIED LOADS:
TOP CH. LL = 25.6 PSF
DL = 8.0 PSF
BOT CH. LL = 0.0 PSF
DL = 7.4 PSF
TOTAL LOAD = 39.0 PSF

SPACING = 24.0 IN. C/C

LOADING IN FLAT SECTION BASED ON A SLOPE OF 6.00/12

THIS TRUSS IS DESIGNED FOR RESIDENTIAL OR SMALL BUILDING REQUIREMENTS OF PART 9, NBCC 2015

THIS DESIGN COMPLIES WITH:
PART 9 OF BCBC 2018, ABC 2019
PART 9 OF OBC 2012 (2019 AMENDMENT)
CSA 086-14
TPIC 2014

55% OF 31.3 P.S.F. G.S.L. PLUS 8.4 P.S.F. RAIN LOAD) EQUALS 25.6 P.S.F. SPECIFIED ROOF LIVE LOAD

ALLOWABLE DEFL.(LL) = L/360 (0.79")
CALCULATED VERT. DEFL.(LL) = L/999 (0.06")
ALLOWABLE DEFL.(TL) = L/360 (0.79")
CALCULATED VERT. DEFL.(TL) = L/999 (0.14")

CSI: TC=0.67/1.00 (B-C:1), BC=0.37/1.00 (K-L:1), WB=0.71/1.00 (F-I:1), SSI=0.28/1.00 (B-C:1)

DOL LUMBER=1.00 NAIL=1.00 LS BEND=1.10
COMP=1.10 SHEAR=1.10 TENS=1.10

COMPANION LIVE LOAD FACTOR = 1.00


TRUSS PLATE MANUFACTURER IS NOT RESPONSIBLE FOR QUALITY CONTROL IN THE TRUSS MANUFACTURING PLANT

NAIL VALUES
PLATE GRIP(DRY) SHEAR SECTION (PSI) (PLI) (PLI)
MAX MIN MAX MIN MAX MIN
MT20 650 371 1747 788 1987 1873

PLATE PLACEMENT TOL. = 0.250 inches

PLATE ROTATION TOL. = 5.0 Deg.

JSI GRIP= 0.81 (B) (INPUT = 0.90)
JSI METAL= 0.45 (B) (INPUT = 1.00)



Structural component only
DWG# T-2017124


Tamarack Roof Truss, Burlington




Structural component only
DWG# T-2017125

JOB NAME 410116	TRUSS NAME T36	QUANTITY 6	PLY 1	JOB DESC. GREEN PARK HOMES	DRWG NO.
Tamarack Roof Truss, Burlington					

Version 8.330 S May 6 2020 MiTek Industries, Inc. Tue Aug 4 12:39:45 2020 Page 1
ID:W63xGm60kc00SiyZ4EwBx6zA2m0-ggak8s2MHTgUxUPP7tgZ2A19mlbgPee96tyNGcyrEii



JOB NAME	TRUSS NAME	QUANTITY	PLY	JOB DESC.	DRWG NO.
410174	T37	4	1	GREEN PARK HOMES	
Tamarack Roof Truss, Burlington					



LUMBER

N. L. G. A. RULES

CHORDS	SIZE	LUMBER	DESCR.
A - D	2x4	DRY	No.2
D - F	2x4	DRY	No.2
F - G	2x4	DRY	No.2
H - G	2x4	DRY	No.2
M - B	2x4	DRY	No.2
M - J	2x4	DRY	No.2
J - H	2x4	DRY	No.2
ALL WEBS EXCEPT	2x3	DRY	No.2
I - F	2x4	DRY	No.2
I - G	2x4	DRY	No.2

DRY: SEASONED LUMBER.

PLATES (table is in inches)

JT	TYPE	PLATES	W	LEN	Y	X
B	TMVW-t	MT20	4.0	6.0	2.00	3.00
C	TMVW-t	MT20	4.0	4.0	2.00	1.75
D	TS-t	MT20	3.0	6.0		
E	TMVW-t	MT20	4.0	4.0	2.00	1.75
F	TTW-m	MT20	4.0	4.0		
G	TMVW-p	MT20	4.0	6.0		
H	BMV1-p	MT20	3.0	4.0		
I	BMVWW-t	MT20	5.0	8.0		
J	BS-t	MT20	3.0	6.0		
K	BMVW-t	MT20	4.0	4.0		
L	BMVW-t	MT20	5.0	8.0		
M	BMV1-p	MT20	3.0	4.0		

DIMENSIONS, SUPPORTS AND LOADINGS SPECIFIED BY FABRICATOR TO BE VERIFIED BY BUILDING DESIGNER

BEARINGS

	FACTORED GROSS REACTION	MAXIMUM FACTORED GROSS REACTION	INPUT BRG IN-SX	REQD BRG IN-SX
JT	VERT	HORZ		
H	1309	0	1309	0
M	1434	0	1434	0

UNFACTORED REACTIONS

	1ST LCASE	MAX/MIN	COMPONENT REACTIONS					
JT	COMBINED	SNOW	LIVE	PERM.LIVE	WIND	DEAD	SOIL	
H	926	608 / 0	0 / 0	0 / 0	0 / 0	318 / 0	0 / 0	
M	1012	677 / 0	0 / 0	0 / 0	0 / 0	335 / 0	0 / 0	

BEARING MATERIAL TO BE SPF NO.2 OR BETTER AT JOINT(S) H, M

BRACING

TOP CHORD TO BE SHEATHED OR MAX. PURLIN SPACING = 4.37 FT.
MAX. UNBRACED BOTTOM CHORD LENGTH = 10.00 FT OR RIGID CEILING DIRECTLY APPLIED.

ALL PITCH BREAKS AND PERIMETER CORNER JOINTS MUST BE Laterally RESTRAINED.

1 LATERAL BRACE(S) AT 1/2 LENGTH OF G-H, E-I, F-I.

END VERTICAL(S) MUST BE SHEATHED OR HAVE BRACES AS INDICATED IN THE MAX. UNBRACED LENGTH COLUMN OF THE TABLE BELOW

LOADING

TOTAL LOAD CASES: (4)

CHORDS				WEBS			
MEMB.	MAX. FACTORED FORCE (LBS)	FACTORED VERT. LOAD (PLF)	MAX. UNBRACED LENGTH (LC)	MEMB.	MAX. FACTORED FORCE (LBS)	MAX. UNBRACED LENGTH (LC)	
FR-TO		FROM TO		FR-TO			
A-B	0 / 28	-91.8 -91.8	0.12 (1)	10.00	L-C	-69 / 85	0.03 (4)
B-C	1786 / 0	-91.8 -91.8	0.58 (1)	4.37	C-K	-624 / 0	0.78 (1)
C-D	-1207 / 0	-91.8 -91.8	0.45 (1)	5.26	K-E	0 / 464	0.10 (1)
D-E	-1207 / 0	-91.8 -91.8	0.45 (1)	5.26	E-I	-1042 / 0	0.76 (1)
E-F	-458 / 0	-91.8 -91.8	0.46 (1)	6.25	I-F	-226 / 0	0.14 (1)
F-G	-383 / 0	-91.8 -91.8	0.18 (1)	6.25	I-G	0 / 1175	0.19 (1)
H-G	-1287 / 0	0.0 0.0	0.82 (1)	5.69	B-L	0 / 1616	0.36 (1)
M-B	-1381 / 0	0.0 0.0	0.14 (1)	6.92			
M-L	0 / 0	-18.5 -18.5	0.19 (4)	10.00			
L-K	0 / 1603	-18.5 -18.5	0.35 (1)	10.00			
K-J	0 / 1079	-18.5 -18.5	0.26 (1)	10.00			
J-I	0 / 1079	-18.5 -18.5	0.26 (1)	10.00			
I-H	0 / 0	-18.5 -18.5	0.13 (4)	10.00			

TOTAL WEIGHT = 4 X 124 = 496 lb

DESIGN CRITERIA

SPECIFIED LOADS:

TOP CH.	LL = 25.6	PSF
	DL = 6.0	PSF
BOT CH.	LL = 0.0	PSF
	DL = 7.4	PSF
TOTAL LOAD	= 39.0	PSF

SPACING = 24.0 IN./C

LOADING IN FLAT SECTION BASED ON A SLOPE OF 6.00/12

THIS TRUSS IS DESIGNED FOR RESIDENTIAL OR SMALL BUILDING REQUIREMENTS OF PART 9, NBCC 2015

THIS DESIGN COMPLIES WITH:

- PART 9 OF BCBC 2018, ABC 2019
- PART 9 OF OBC 2012 (2019 AMENDMENT)
- CSA 086-14
- TPIC 2014

(55 % OF 31.3 P.S.F. G.S.L. PLUS 8.4 P.S.F. RAIN LOAD) EQUALS 25.6 P.S.F. SPECIFIED ROOF LIVE LOAD

ALLOWABLE DEFL.(LL) = L/360 (0.79")
CALCULATED VERT. DEFL.(LL) = L/999 (0.06")
ALLOWABLE DEFL.(TL) = L/360 (0.79")
CALCULATED VERT. DEFL.(TL) = L/999 (0.13")

CSI: TC=0.82/1.00 (G-H:1), BC=0.35/1.00 (K-L:1), WB=0.78/1.00 (C-K:1), SSI=0.26/1.00 (B-C:1)

DOL LUMBER=1.00 NAIL=1.00 LS BEND=1.10
COMP=1.10 SHEAR=1.10 TENS=1.10

COMPANION LIVE LOAD FACTOR = 1.00

TRUSS PLATE MANUFACTURER IS NOT RESPONSIBLE FOR QUALITY CONTROL IN THE TRUSS MANUFACTURING PLANT.

NAIL VALUES

PLATE GRIP(DRY)	SHEAR (PSI)	SECTION (PLI)
MAX MIN	MAX MIN	MAX MIN
MT20	650 371	1747 788

PLATE PLACEMENT TOL. = 0.250 inches

PLATE ROTATION TOL. = 5.0 Deg.

JSI GRIP = 0.81 (B) (INPUT = 0.90)
JSI METAL = 0.45 (B) (INPUT = 1.00)




Structural component only
DWG# T-2016989

JOB NAME	TRUSS NAME	QUANTITY	PLY	JOB DESC.	GREEN PARK HOMES	DRWG NO.
410174	T38	2	1	TRUSS DESC.		

Tamarack Roof Truss, Burlington

Version 8.330 S May 6 2020 Mitek Industries, Inc. Thu Jul 30 08:42:30 2020 Page 1

ID:W63xGm60kc00SiyZ4EwBx6zA2m0-mOqUCdipFim1BkDbe2QoxEqrbFEzHaBHX?P3iZysxf7



TOTAL WEIGHT = 2 X 53 = 106 lb

LUMBER

N. L. G. A. RULES

CHORDS	SIZE	LUMBER
A - C	2x4	DRY No.2
C - E	2x4	DRY No.2
E - G	2x4	DRY No.2
K - B	2x4	DRY No.2
H - F	2x4	DRY No.2
K - H	2x4	DRY No.2

ALL WEBS 2x3 DRY No.2
EXCEPT

DRY: SEASONED LUMBER.

PLATES (table is in inches)

JT	TYPE	PLATES	W	LEN	Y	X
B	TMWV-t	MT20	4.0	6.0	2.00	3.00
C	TTW-m	MT20	4.0	4.0		
D	TMWV-t	MT20	4.0	4.0		
E	TTW-m	MT20	4.0	4.0		
F	TMWV-t	MT20	4.0	6.0	2.00	3.00
H	BMV1+p	MT20	3.0	4.0		
I	BMWVW-t	MT20	4.0	9.0		
J	BMWVW-t	MT20	4.0	9.0		
K	BMV1+p	MT20	3.0	4.0		

DIMENSIONS, SUPPORTS AND LOADINGS SPECIFIED BY FABRICATOR TO BE VERIFIED BY BUILDING DESIGNER

BEARINGS

JT	FACTORED GROSS REACTION		MAXIMUM FACTORED GROSS REACTION		INPUT BRG	RECORD BRG
	VERT	HORZ	DOWN	HORZ		
K	1149	0	1149	0	5-8	5-8
H	1145	0	1145	0	5-8	5-8

UNFACTORED REACTIONS

JT	COMBINED	MAX./MIN. COMPONENT REACTIONS					
		SNOW	LIVE	PERM.LIVE	WIND	DEAD	SOIL
K	810	546 / 0	0 / 0	0 / 0	0 / 0	263 / 0	0 / 0
H	807	545 / 0	0 / 0	0 / 0	0 / 0	262 / 0	0 / 0

BEARING MATERIAL TO BE SPF NO.2 OR BETTER AT JOINT(S) K, H

BRACING

TOP CHORD TO BE SHEATHED OR MAX. PURLIN SPACING = 5.32 FT.
MAX. UNBRACED BOTTOM CHORD LENGTH = 10.00 FT OR RIGID CEILING DIRECTLY APPLIED.

ALL PITCH BREAKS AND PERIMETER CORNER JOINTS MUST BE Laterally RESTRAINED.

LOADING

TOTAL LOAD CASES: (4)

MEMB.	FR-TO	CHORDS		MAX. UNBRACED LENGTH	MEMB.	WEBS	
		MAX. FACTORED FORCE (LBS)	FACTORED VERT. LOAD (PLF)			MAX. FACTORED FORCE (LBS)	FACTORED VERT. LOAD (PLF)
A-B	0 / 28	-91.8	-91.8	0.13 (1)	10.00	J-C	0 / 95
B-C	-1277 / 0	-91.8	-91.8	0.29 (1)	5.32	I-E	0 / 96
C-L	-1146 / 0	-91.8	-91.8	0.17 (1)	5.72	B-J	0 / 1166
L-D	-1146 / 0	-91.8	-91.8	0.17 (1)	5.72	I-F	0 / 1161
D-M	-1140 / 0	-91.8	-91.8	0.17 (1)	5.73	J-D	-255 / 0
M-E	-1140 / 0	-91.8	-91.8	0.17 (1)	5.73	D-I	-262 / 0
E-F	-1271 / 0	-91.8	-91.8	0.29 (1)	5.32		
F-G	0 / 28	-91.8	-91.8	0.13 (1)	10.00		
K-B	-1117 / 0	0.0	0.0	0.12 (1)	7.47		
H-F	-1113 / 0	0.0	0.0	0.12 (1)	7.48		
K-N	0 / 0	-18.5	-18.5	0.13 (4)	10.00		
N-J	0 / 0	-18.5	-18.5	0.13 (4)	10.00		
J-O	0 / 1321	-18.5	-18.5	0.30 (1)	10.00		
O-P	0 / 1321	-18.5	-18.5	0.30 (1)	10.00		
P-I	0 / 1321	-18.5	-18.5	0.30 (1)	10.00		
I-Q	0 / 0	-18.5	-18.5	0.13 (4)	10.00		
Q-H	0 / 0	-18.5	-18.5	0.13 (4)	10.00		

FACTORED CONCENTRATED LOADS (LBS)

JT	LOC.	LC1	MAX.	MAX+	FACE	DIR.	TYPE	HEEL	CONN.
C	3-10-8	-209	-209	---	FRONT	VERT	TOTAL	---	C1
E	9-6-8	-209	-209	---	FRONT	VERT	TOTAL	---	C1
I	9-5-12	-12	-12	---	FRONT	VERT	TOTAL	---	C1
J	3-11-4	-12	-12	---	FRONT	VERT	TOTAL	---	C1
L	5-5-12	-42	-42	---	FRONT	VERT	TOTAL	---	C1
M	7-5-12	-42	-42	---	FRONT	VERT	TOTAL	---	C1
N	1-11-4	-8	-10	---	FRONT	VERT	TOTAL	---	C1
O	5-5-12	-12	-12	---	FRONT	VERT	TOTAL	---	C1
P	7-5-12	-12	-12	---	FRONT	VERT	TOTAL	---	C1
Q	11-5-12	-8	-10	---	FRONT	VERT	TOTAL	---	C1

CONNECTION REQUIREMENTS

1) C1: A SUITABLE HANGER/MECHANICAL CONNECTION IS REQUIRED.

DESIGN CRITERIA

SPECIFIED LOADS:

TOP CH. LL = 25.6 PSF
DL = 6.0 PSF
BOT CH. LL = 0.0 PSF
DL = 7.4 PSF
TOTAL LOAD = 39.0 PSF

SPACING = 24.0 IN. C/C

LOADING IN FLAT SECTION BASED ON A SLOPE OF 6.00/12

THIS TRUSS IS DESIGNED FOR RESIDENTIAL OR SMALL BUILDING REQUIREMENTS OF PART 9, NBCC 2015

THIS DESIGN COMPLIES WITH:

- PART 9 OF BCBC 2018, ABC 2019
- PART 9 OF OBC 2012 (2019 AMENDMENT)
- CSA 086-14
- TPIC 2014

(55 % OF 31.3 P.S.F. G.S.L. PLUS 8.4 P.S.F. RAIN LOAD) EQUALS 25.6 P.S.F. SPECIFIED ROOF LIVE LOAD

ALLOWABLE DEFL.(LL)= L/360 (0.45")
CALCULATED VERT. DEFL.(LL) = L/999 (0.03")
ALLOWABLE DEFL.(TL)= L/360 (0.45")
CALCULATED VERT. DEFL.(TL) = L/999 (0.06")

CSI: TC=0.29/1.00 (B-C:1), BC=0.30/1.00 (I-J:1), WB=0.29/1.00 (B-J:1), SS=0.17/1.00 (D-E:1)

DOL LUMBER=1.00 NAIL=1.00 LS BEND=1.00
COMP=1.00 SHEAR=1.00 TENS=1.00

COMPANION LIVE LOAD FACTOR = 1.00

TRUSS PLATE MANUFACTURER IS NOT RESPONSIBLE FOR QUALITY CONTROL IN THE TRUSS MANUFACTURING PLANT.

NAIL VALUES

PLATE	GRIP(DRY)	SHEAR (PSI)	SECTION (PLI)
MT20	650	371	1747

PLATE PLACEMENT TOL. = 0.250 inches

PLATE ROTATION TOL. = 5.0 Deg.

JSI GRIP= 0.67 (I) (INPUT = 0.90)
JSI METAL= 0.32 (F) (INPUT = 1.00)




Structural component only
DWG# T-2016990

JOB NAME 410174	TRUSS NAME T39	QUANTITY 1	PLY 1	JOB DESC. GREEN PARK HOMES	TRUSS DESC.	DRWG NO.
--------------------	-------------------	---------------	----------	-------------------------------	-------------	----------

Tamarack Roof Truss, Burlington

Version 8.330 S May 6 2020 Mitek Industries, Inc. Thu Jul 30 08:42:31 2020 Page 1
ID:W63xGm6okcO0SiyZ4EwBx6zA2m0-FaOtPzjR02uuouooCmx1URN_T1br03jQmf8cE?ysxf6



TOTAL WEIGHT = 53 lb

LUMBER

N. L. G. A. RULES	CHORDS	SIZE	LUMBER	DESCR.
A - C	2x4	DRY	No.2	SPF
C - D	2x4	DRY	No.2	SPF
D - E	2x4	DRY	No.2	SPF
I - B	2x4	DRY	No.2	SPF
F - E	2x4	DRY	No.2	SPF
I - F	2x4	DRY	No.2	SPF

ALL WEBS EXCEPT	2x3	DRY	No.2	SPF
-----------------	-----	-----	------	-----

DRY: SEASONED LUMBER.

PLATES (table is in inches)

JT	TYPE	PLATES	W	LEN	Y	X
B	TMVW+p	MT20	4.0	4.0	1.50	2.00
C	TTWV-m	MT20	5.0	6.0	2.25	2.00
D	TTW-m	MT20	4.0	4.0		
E	TMVW+p	MT20	4.0	4.0	1.50	2.00
F	BMV1+p	MT20	3.0	4.0		
G	BMVWW-t	MT20	4.0	9.0		
H	BMVWW-t	MT20	4.0	4.0		
I	BMV1+p	MT20	3.0	4.0		

DIMENSIONS, SUPPORTS AND LOADINGS SPECIFIED BY FABRICATOR TO BE VERIFIED BY BUILDING DESIGNER

BEARINGS	FACTORED	MAXIMUM FACTORED	INPUT	REQ'D
JT	VERT	HORZ	DOWN	HORZ
I	843	0	843	0
F	719	0	719	0

A SUITABLE HANGER/MECHANICAL CONNECTION IS REQUIRED AT JOINT F. MINIMUM BEARING LENGTH AT JOINT F = 1-8.

UNFACTORED REACTIONS

1ST LCASE		MAX./MIN. COMPONENT REACTIONS					
JT	COMBINED	SNOW	LIVE	PERM.LIVE	WIND	DEAD	SOIL
I	594	403 / 0	0 / 0	0 / 0	0 / 0	191 / 0	0 / 0
F	508	334 / 0	0 / 0	0 / 0	0 / 0	175 / 0	0 / 0

BEARING MATERIAL TO BE SPF NO.2 OR BETTER AT JOINT(S) I

BRACING

TOP CHORD TO BE SHEATHED OR MAX. PURLIN SPACING = 6.25 FT.
MAX. UNBRACED BOTTOM CHORD LENGTH = 10.00 FT OR RIGID CEILING DIRECTLY APPLIED.

ALL PITCH BREAKS AND PERIMETER CORNER JOINTS MUST BE Laterally RESTRAINED.

LOADING

TOTAL LOAD CASES: (4)

CHORDS	MEMB.	MAX. FACTORED FORCE (LBS)	FACTORED VERT. LOAD (PLF)	MAX. FACTORED VERT. LOAD (LC1)	MAX. FACTORED VERT. LOAD (LC2)	MAX. FACTORED VERT. LOAD (LC3)	MAX. FACTORED VERT. LOAD (LC4)	MAX. FACTORED VERT. LOAD (LC5)	MAX. FACTORED VERT. LOAD (LC6)	MAX. FACTORED VERT. LOAD (LC7)	MAX. FACTORED VERT. LOAD (LC8)	MAX. FACTORED VERT. LOAD (LC9)	MAX. FACTORED VERT. LOAD (LC10)
FR-TO													
A-B		0 / 28	-91.8	-91.8	0.12 (1)	10.00	H-C	-8 / 60	0.02 (4)				
B-C		-699 / 0	-91.8	-91.8	0.41 (1)	6.25	C-G	-26 / 0	0.01 (1)				
C-D		-616 / 0	-91.8	-91.8	0.04 (1)	6.25	G-D	-19 / 50	0.02 (4)				
D-E		-690 / 0	-91.8	-91.8	0.36 (1)	6.25	B-H	0 / 632	0.14 (1)				
E-F		-797 / 0	0.0	0.0	0.08 (1)	7.81	G-E	0 / 627	0.14 (1)				
F-G		-675 / 0	0.0	0.0	0.07 (1)	7.81							
H-I		0 / 0	-18.5	-18.5	0.14 (4)	10.00							
H-G		0 / 625	-18.5	-18.5	0.20 (4)	10.00							
G-F		0 / 0	-18.5	-18.5	0.13 (4)	10.00							

DESIGN CRITERIA

SPECIFIED LOADS:

TOP CH.	LL	=	25.6	PSF
	DL	=	6.0	PSF
BOT CH.	LL	=	0.0	PSF
	DL	=	7.4	PSF
TOTAL LOAD	=	39.0	PSF	

SPACING = 24.0 IN./C/C

LOADING IN FLAT SECTION BASED ON A SLOPE OF 6.00/12

THIS TRUSS IS DESIGNED FOR RESIDENTIAL OR SMALL BUILDING REQUIREMENTS OF PART 9, NBC 2015

THIS DESIGN COMPLIES WITH:

- PART 9 OF BCBC 2018, ABC 2019
- PART 9 OF OBC 2012 (2019 AMENDMENT)
- CSA 086-14
- TPIC 2014

(55 % OF 31.3 P.S.F. G.S.L. PLUS 8.4 P.S.F. RAIN LOAD) EQUALS 25.6 P.S.F. SPECIFIED ROOF LIVE LOAD

ALLOWABLE DEFL.(LL)= L/360 (0.43")
CALCULATED VERT. DEFL.(LL) = L/999 (0.01")
ALLOWABLE DEFL.(TL)= L/360 (0.43")
CALCULATED VERT. DEFL.(TL) = L/999 (0.05")

CSI: TC=0.41/1.00 (B-C:1), BC=0.20/1.00 (G-H:4), WB=0.14/1.00 (B-H:1), SSI=0.19/1.00 (B-C:1)

DOL LUMBER=1.00 NAIL=1.00 LS BEND=1.10
COMP=1.10 SHEAR=1.10 TENS=1.10

COMPANION LIVE LOAD FACTOR = 1.00

TRUSS PLATE MANUFACTURER IS NOT RESPONSIBLE FOR QUALITY CONTROL IN THE TRUSS MANUFACTURING PLANT

NAIL VALUES

PLATE	GRIP(DRY)	SHEAR	SECTION
	(PSI)	(PLI)	(PLI)
MT20	650	371	1747
	788	1987	1873

PLATE PLACEMENT TOL. = 0.250 inches


PLATE ROTATION TOL. = 5.0 Deg.

JSI GRIP= 0.76 (B) (INPUT = 0.90)
JSI METAL= 0.22 (B) (INPUT = 1.00)



Structural component only
DWG# T-2016991

JOB NAME	TRUSS NAME	QUANTITY	PLY	JOB DESC.	DRWG NO.
410174	T40	2	1	GREEN PARK HOMES	
Tamarack Roof Truss, Burlington					



LUMBER

N. L. G. A. RULES	CHORDS	SIZE	LUMBER	DESCR.
A - D	2x4	DRY	No.2	SPF
D - F	2x4	DRY	No.2	SPF
I - B	2x4	DRY	No.2	SPF
G - F	2x4	DRY	No.2	SPF
I - G	2x4	DRY	No.2	SPF
ALL WEBS EXCEPT	2x3	DRY	No.2	SPF

DRY: SEASONED LUMBER.

PLATES (table is in inches)

JT	TYPE	PLATES	W	LEN	Y	X
B	TMV+p	MT20	3.0	4.0		
C	TMVWW-t	MT20	4.0	4.0	2.00	1.75
D	TTW-p	MT20	4.0	4.0		
E	TMVWW-t	MT20	4.0	4.0	2.00	1.75
F	TMV+p	MT20	3.0	4.0		
G	BMVWW-t	MT20	4.0	4.0		
H	BMVWW-t	MT20	4.0	9.0		
I	BMVWW-t	MT20	4.0	4.0		

DIMENSIONS, SUPPORTS AND LOADINGS SPECIFIED BY FABRICATOR TO BE VERIFIED BY BUILDING DESIGNER

BEARINGS	FACTORED GROSS REACTION	MAXIMUM FACTORED GROSS REACTION	INPUT BRG	REQD BRG
JT	VERT	DOWN	HORIZ	UPLIFT
I	843	0	0	5-8
G	719	0	0	MECHANICAL

A SUITABLE HANGER/MECHANICAL CONNECTION IS REQUIRED AT JOINT G. MINIMUM BEARING LENGTH AT JOINT G = 1-8.

UNFACTORED REACTIONS

1ST LOASE	COMBINED	SNOW	LIVE	PERM.LIVE	WIND	DEAD	SOIL
JT	594	403 / 0	0 / 0	0 / 0	0 / 0	191 / 0	0 / 0
G	508	334 / 0	0 / 0	0 / 0	0 / 0	175 / 0	0 / 0

BEARING MATERIAL TO BE SPF NO.2 OR BETTER AT JOINT(S) I

BRACING

TOP CHORD TO BE SHEATHED OR MAX. PURLIN SPACING = 6.25 FT.
MAX. UNBRACED BOTTOM CHORD LENGTH = 10.00 FT OR RIGID CEILING DIRECTLY APPLIED.

ALL PITCH BREAKS AND PERIMETER CORNER JOINTS MUST BE Laterally RESTRAINED.

LOADING

TOTAL LOAD CASES: (4)

CHORDS				WEBS			
MEMB.	MAX. FACTORED FORCE (LBS)	FACTORED VERT. LOAD (PLF)	MAX. LC1 (LC)	MEMB.	MAX. FACTORED FORCE (LBS)	MAX. LC1 (LC)	
FR-TO		FROM	TO	FR-TO			
A-B	0 / 28	-91.8	-91.8	0.12 (1)	C-H	-189 / 0	0.06 (1)
B-C	0 / 15	-91.8	-91.8	0.15 (1)	H-D	0 / 334	0.08 (1)
C-D	-680 / 0	-91.8	-91.8	0.12 (1)	E-E	-119 / 9	0.04 (1)
D-E	-659 / 0	-91.8	-91.8	0.11 (1)	I-C	-911 / 0	0.27 (1)
E-F	0 / 15	-91.8	-91.8	0.14 (1)	E-G	-881 / 0	0.23 (1)
F-B	-246 / 0	0.0	0.0	0.02 (1)			
G-F	-104 / 0	0.0	0.0	0.01 (1)			
I-H	0 / 727	-18.5	-18.5	0.28 (4)			
H-G	0 / 672	-18.5	-18.5	0.28 (4)			

TOTAL WEIGHT = 2 X 51 = 102 lb

DESIGN CRITERIA

SPECIFIED LOADS:

TOP CH.	LL	=	25.6	PSF
	DL	=	6.0	PSF
BOT CH.	LL	=	0.0	PSF
	DL	=	7.4	PSF
TOTAL LOAD	=	39.0	PSF	

SPACING = 24.0 IN./C

THIS TRUSS IS DESIGNED FOR RESIDENTIAL OR SMALL BUILDING REQUIREMENTS OF PART 9, NBCC 2015

THIS DESIGN COMPLIES WITH:

- PART 9 OF CBC 2018, ABC 2019
- PART 9 OF OBC 2012 (2019 AMENDMENT)
- CSA 086-14
- TPIC 2014

(55 % OF 31.3 P.S.F. G.S.L. PLUS 8.4 P.S.F. RAIN LOAD) EQUALS 25.6 P.S.F. SPECIFIED ROOF LIVE LOAD

ALLOWABLE DEFL.(LL) = L/360 (0.43")
CALCULATED VERT. DEFL.(LL) = L/999 (0.01")
ALLOWABLE DEFL.(TL) = L/360 (0.43")
CALCULATED VERT. DEFL.(TL) = L/999 (0.06")

CSI: TC=0.15/1.00 (B-C:1), BC=0.28/1.00 (H-I:4), WB=0.27/1.00 (C-I:1), SS=0.13/1.00 (B-C:1)

DOL LUMBER=1.00 NAIL=1.00 LS BEND=1.10 COMP=1.10 SHEAR=1.10 TENS=1.10

COMPANION LIVE LOAD FACTOR = 1.00

TRUSS PLATE MANUFACTURER IS NOT RESPONSIBLE FOR QUALITY CONTROL IN THE TRUSS MANUFACTURING PLANT.


NAIL VALUES

PLATE	GRIP(DRY)	SHEAR	SECTION
	(PSI)	(PLI)	(PLI)
	MAX	MIN	MAX
MT20	650	371	1747
	788	1987	1873

PLATE PLACEMENT TOL. = 0.250 inches

PLATE ROTATION TOL. = 5.0 Deg.

JSI GRIP= 0.78 (I) (INPUT = 0.90)
JSI METAL= 0.28 (C) (INPUT = 1.00)




Structural component only
DWG# T-2016992

JOB NAME	TRUSS NAME	QUANTITY	PLY	JOB DESC.	GREEN PARK HOMES	DRWG NO.
410174	T41	1	1	TRUSS DESC.		

Tamarack Roof Truss, Burlington

Version 8.330 S May 6 2020 MTek Industries, Inc. Thu Jul 30 08:42:33 2020 Page 1

ID:W63xGm6okc00SiyZ4EwBx6zA2m0-BzVdqfihXg8b2CyAJAzVZsSK1TIWU_ejDzdjluysxf4



Scale = 1:31.5

TOTAL WEIGHT = 63 lb

LUMBER

N. L. G. A. RULES

CHORDS SIZE

A - C 2x4 DRY No.2

C - D 2x4 DRY No.2

D - F 2x4 DRY No.2

J - B 2x4 DRY No.2

G - E 2x4 DRY No.2

J - G 2x4 DRY No.2

ALL WEBS 2x3 DRY No.2

EXCEPT

DRY: SEASONED LUMBER.

PLATES (table is in inches)

JT	TYPE	PLATES	W	LEN	Y	X
B	TMVW-t	MT20	4.0	4.0	2.00	1.25
C	TTWW-m	MT20	5.0	6.0	2.25	2.00
D	TTWW-m	MT20	4.0	4.0		
E	TMVW-t	MT20	4.0	4.0	2.00	1.25
G	BMV1+p	MT20	3.0	4.0		
H	BMWWW-t	MT20	4.0	9.0		
I	BMWWW-t	MT20	4.0	4.0		
J	BMV1+p	MT20	3.0	4.0		

DIMENSIONS, SUPPORTS AND LOADINGS SPECIFIED BY FABRICATOR TO BE VERIFIED BY BUILDING DESIGNER

BEARINGS

	FACTORED		MAXIMUM FACTORED			INPUT	REQD
JT	GROSS REACTION		GROSS REACTION			BRG	BRG
	VERT	HORZ	DOWN	HORZ	UPLIFT	IN-SX	IN-SX
J	864	0	864	0	0	5-8	5-8
G	864	0	864	0	0	5-8	5-8

UNFACTORED REACTIONS

JT	1ST LCASE	MAX/MIN. COMPONENT REACTIONS	SNOW	LIVE	PERM. LIVE	WIND	DEAD	SOIL
JT	COMBINED							
J	609	413 / 0	0 / 0	0 / 0	0 / 0	0 / 0	196 / 0	0 / 0
G	609	413 / 0	0 / 0	0 / 0	0 / 0	0 / 0	196 / 0	0 / 0

BEARING MATERIAL TO BE SPF NO.2 OR BETTER AT JOINT(S) J, G

BRACING

TOP CHORD TO BE SHEATHED OR MAX. PURLIN SPACING = 6.25 FT.
MAX. UNBRACED BOTTOM CHORD LENGTH = 10.00 FT OR RIGID CEILING DIRECTLY APPLIED.

ALL PITCH BREAKS AND PERIMETER CORNER JOINTS MUST BE Laterally RESTRAINED.

LOADING

TOTAL LOAD CASES: (4)

CHORDS				WEBS			
MEMB.	MAX. FACTORED FORCE (LBS)	FACTORED VERT. LOAD (LBS)	MAX. CS (LC)	MEMB.	MAX. FACTORED FORCE (LBS)	MAX. CS (LC)	
FR-TO		FROM	TO	FR-TO			
A-B	0 / 28	-91.8	-91.8 0.12 (1)	I-C	-106 / 21	0.05 (1)	
B-C	-530 / 0	-91.8	-91.8 0.41 (1)	C-H	-2 / 0	0.00 (1)	
C-D	-471 / 0	-91.8	-91.8 0.03 (1)	H-D	-109 / 22	0.05 (1)	
D-E	-529 / 0	-91.8	-91.8 0.41 (1)	B-I	0 / 509	0.11 (1)	
E-F	0 / 28	-91.8	-91.8 0.12 (1)	H-E	0 / 509	0.11 (1)	
J-B	-818 / 0	0.0	0.0 0.11 (1)				
G-E	-818 / 0	0.0	0.0 0.11 (1)				
J-I	0 / 0	-18.5	-18.5 0.14 (4)				
I-H	0 / 472	-18.5	-18.5 0.18 (4)				
H-G	0 / 0	-18.5	-18.5 0.14 (4)				

DESIGN CRITERIA

SPECIFIED LOADS:

TOP CH.	LL	=	25.6	PSF
	DL	=	6.0	PSF
BOT CH.	LL	=	0.0	PSF
	DL	=	7.4	PSF
TOTAL LOAD	=	39.0	PSF	

SPACING = 24.0 IN./C

LOADING IN FLAT SECTION BASED ON A SLOPE OF 6.00/12

THIS TRUSS IS DESIGNED FOR RESIDENTIAL OR SMALL BUILDING REQUIREMENTS OF PART 9, NBCC 2015

THIS DESIGN COMPLIES WITH:

- PART 9 OF BCBC 2018, ABC 2019
- PART 9 OF OBC 2012 (2019 AMENDMENT)
- CSA 086-14
- TPIC 2014

(55 % OF 31.3 P.S.F. G.S.L. PLUS 8.4 P.S.F. RAIN LOAD) EQUALS 25.6 P.S.F. SPECIFIED ROOF LIVE LOAD

ALLOWABLE DEFL.(LL)= L/360 (0.45")
CALCULATED VERT. DEFL.(LL) = L/999 (0.01")
ALLOWABLE DEFL.(TL)= L/360 (0.45")
CALCULATED VERT. DEFL.(TL) = L/999 (0.04")

CSI: TC=0.41/1.00 (B-C:1), BC=0.18/1.00 (H-I:4), WB=0.11/1.00 (B-I:1), SI=0.19/1.00 (D-E:1)

DOL LUMBER=1.00 NAIL=1.00 LS BEND=1.10
COMP=1.10 SHEAR=1.10 TENS=1.10

COMPANION LIVE LOAD FACTOR = 1.00

TRUSS PLATE MANUFACTURER IS NOT RESPONSIBLE FOR QUALITY CONTROL IN THE TRUSS MANUFACTURING PLANT.

NAIL VALUES

PLATE	GRIP(DRY)	SHEAR (PSI)	SECTION (PLI)
MT20	650	371	1747
	788	1987	1873

PLATE PLACEMENT TOL. = 0.250 inches

PLATE ROTATION TOL. = 5.0 Deg.

JSI GRIP= 0.77 (B) (INPUT = 0.90)
JSI METAL= 0.24 (B) (INPUT = 1.00)




Structural component only
DWG# T-2016993

JOB NAME	TRUSS NAME	QUANTITY	PLY	JOB DESC.	DRWG NO.
410174	T42	2	1	GREEN PARK HOMES	
Tamarack Roof Truss, Burlington					

Version 8.330 S May 6 2020 MiTek Industries, Inc. Thu Jul 30 08:42:34 2020 Page 1

ID:W63xGm6okcO0SiyZ4EwBx6zA2m0-f93?1?mJlZGSfLXNtuUk64?ZctcHDNZsSdNGrKysxf3

Scale = 1:33.4



TOTAL WEIGHT = 2 X 60 = 119 lb

LUMBER

N. L. G. A. RULES

CHORDS	SIZE	LUMBER
A - D	2x4 DRY	No.2
D - F	2x4 DRY	No.2
I - B	2x4 DRY	No.2
G - F	2x4 DRY	No.2
I - G	2x4 DRY	No.2

ALL WEBS 2x3 DRY No.2
EXCEPT

DRY: SEASONED LUMBER.

PLATES (table is in inches)

JT	TYPE	PLATES	W	LEN	Y	X
B	TMV+p	MT20	3.0	4.0		
C	TMVW-t	MT20	4.0	4.0		
D	TTW-p	MT20	4.0	4.0		
E	TMVW-t	MT20	4.0	4.0		
F	TMV+p	MT20	3.0	4.0		
G	BMVW1-t	MT20	4.0	4.0		
H	BMVW1-t	MT20	4.0	9.0		
I	BMVW1-t	MT20	4.0	4.0		

DIMENSIONS, SUPPORTS AND LOADINGS SPECIFIED BY FABRICATOR TO BE VERIFIED BY BUILDING DESIGNER

BEARINGS

	FACTORED	MAXIMUM FACTORED	INPUT	REQD
	GROSS REACTION	GROSS REACTION	BRG	BRG
JT	VERT	HORZ	DOWN	HORZ
I	864	0	864	0
G	740	0	740	0

A SUITABLE HANGER/MECHANICAL CONNECTION IS REQUIRED AT JOINT G. MINIMUM BEARING LENGTH AT JOINT G = 1-8.

UNFACTORED REACTIONS

1ST LCASE		MAX./MIN. COMPONENT REACTIONS					
JT	COMBINED	SNOW	LIVE	PERM.LIVE	WIND	DEAD	SOIL
I	609	413 / 0	0 / 0	0 / 0	0 / 0	196 / 0	0 / 0
G	523	343 / 0	0 / 0	0 / 0	0 / 0	180 / 0	0 / 0

BEARING MATERIAL TO BE SPF NO.2 OR BETTER AT JOINT(S) I

BRACING

TOP CHORD TO BE SHEATHED OR MAX. PURLIN SPACING = 6.25 FT
MAX. UNBRACED BOTTOM CHORD LENGTH = 10.00 FT OR RIGID CEILING DIRECTLY APPLIED.

ALL PITCH BREAKS AND PERIMETER CORNER JOINTS MUST BE Laterally RESTRAINED.

LOADING

TOTAL LOAD CASES: (4)

CHORDS				WEBS			
MEMB.	MAX. FACTORED FORCE (LBS)	FACTORED VERT. LOAD (PLF)	MAX. LC1 (LC)	MEMB.	MAX. FACTORED FORCE (LBS)	MAX. LC1 (LC)	
FR-TO		FROM TO		FR-TO			
A-B	0 / 28	-91.8 -91.8	0.12 (1)	H-D	0 / 215	0.05 (1)	
B-C	0 / 16	-91.8 -91.8	0.16 (1)	H-E	-40 / 32	0.02 (1)	
C-D	-521 / 0	-91.8 -91.8	0.13 (1)	C-H	-40 / 32	0.02 (1)	
D-E	-521 / 0	-91.8 -91.8	0.13 (1)	I-C	-746 / 0	0.33 (1)	
E-F	0 / 16	-91.8 -91.8	0.16 (1)	E-G	-746 / 0	0.33 (1)	
I-B	-243 / 0	0.0 0.0	0.03 (1)				
G-F	-119 / 0	0.0 0.0	0.02 (1)				
I-H	0 / 477	-18.5 -18.5	0.28 (4)				
H-G	0 / 477	-18.5 -18.5	0.28 (4)				

DESIGN CRITERIA

SPECIFIED LOADS:

TOP CH.	LL	=	25.6	PSF
	DL	=	6.0	PSF
BOT CH.	LL	=	0.0	PSF
	DL	=	7.4	PSF
TOTAL LOAD		=	39.0	PSF

SPACING = 24.0 IN/C

THIS TRUSS IS DESIGNED FOR RESIDENTIAL OR SMALL BUILDING REQUIREMENTS OF PART 9, NBC 2015

THIS DESIGN COMPLIES WITH:

- PART 9 OF CBC 2018, ABC 2019
- PART 9 OF OBC 2012 (2019 AMENDMENT)
- CSA 086-14
- TPIC 2014

(55 % OF 31.3 P.S.F. G.S.L. PLUS 8.4 P.S.F. RAIN LOAD) EQUALS 25.6 P.S.F. SPECIFIED ROOF LIVE LOAD

ALLOWABLE DEFL.(LL) = L/360 (0.45")
CALCULATED VERT. DEFL.(LL) = L/999 (0.01")
ALLOWABLE DEFL.(TL) = L/360 (0.45")
CALCULATED VERT. DEFL.(TL) = L/999 (0.05")

CSI: TC=0.16/1.00 (B-C:1), BC=0.28/1.00 (H-I:4), WB=0.33/1.00 (C-I:1), SSI=0.13/1.00 (B-C:1)

DOL LUMBER=1.00 NAIL=1.00 LS BEND=1.10
COMP=1.10 SHEAR=1.10 TENS=1.10

COMPANION LIVE LOAD FACTOR = 1.00

TRUSS PLATE MANUFACTURER IS NOT RESPONSIBLE FOR QUALITY CONTROL IN THE TRUSS MANUFACTURING PLANT.

NAIL VALUES

PLATE	GRIP(DRY)	SHEAR	SECTION
	(PSI)	(PLI)	(PLI)
	MAX MIN	MAX MIN	MAX MIN
MT20	650 371	1747 788	1987 1873

PLATE PLACEMENT TOL. = 0.250 inches

PLATE ROTATION TOL. = 5.0 Deg.


JSI GRIP= 0.61 (E) (INPUT = 0.90)
JSI METAL= 0.23 (C) (INPUT = 1.00)



Structural component only
DWG# T-2016994

JOB NAME	TRUSS NAME	QUANTITY	PLY	JOB DESC.	DRWG NO.
410174	T43S	3	1	GREEN PARK HOMES	
Tamarack Roof Truss, Burlington					

Version 8.330 S May 6 2020 MTEK Industries, Inc. Thu Jul 30 08:42:34 2020 Page 1
ID:W63xGm6okcO0SiyZ4EwBx6zA2m0-f93?1?mJlZGSfLXNtuUk64?Y1tUDRCsSdNGrKysxf3



Scale: 3/8"=1'

TOTAL WEIGHT = 3 X 38 = 113 lb

LUMBER

N. L. G. A. RULES	CHORDS	SIZE	LUMBER	DESCR.
H - B	2x4	DRY	No 2	SPF
A - D	2x4	DRY	No 2	SPF
E - D	2x4	DRY	No 2	SPF
H - G	2x4	DRY	No 2	SPF
F - C	2x4	DRY	No 2	SPF
F - E	2x4	DRY	No 2	SPF
ALL WEBS EXCEPT	2x3	DRY	No 2	SPF
G - E	2x4	DRY	No 2	SPF

DRY: SEASONED LUMBER.

PLATES (table is in inches)

JT	TYPE	PLATES	W	LEN	Y	X
B	TMVW-I	MT20	4.0	4.0	2.00	1.25
C	TMVW-I	MT20	3.0	4.0		
D	TMVW-I	MT20	4.0	4.0	2.00	1.75
E	BMVW-I	MT20	4.0	4.0		
F	BMVW-I	MT20	3.0	4.0		
G	BMVW-I	MT20	6.0	12.0	3.00	4.50
H	BMVW-I	MT20	3.0	4.0		

DIMENSIONS, SUPPORTS AND LOADINGS SPECIFIED BY FABRICATOR TO BE VERIFIED BY BUILDING DESIGNER

BEARINGS	FACTORED	MAXIMUM FACTORED	INPUT	REQD
JT	GROSS REACTION	GROSS REACTION	BRG	BRG
	VERT	HORZ	DOWN	HORZ
H	476	0	476	0
E	351	0	351	0

A SUITABLE HANGER/MECHANICAL CONNECTION IS REQUIRED AT JOINT E. MINIMUM BEARING LENGTH AT JOINT E = 1-8.

UNFACTORED REACTIONS

JT	1ST LCASE	MAX / MIN. COMPONENT REACTIONS	SNOW	LIVE	PERM. LIVE	WIND	DEAD	SOIL
H	334	233 / 0	0 / 0	0 / 0	0 / 0	0 / 0	102 / 0	0 / 0
E	249	163 / 0	0 / 0	0 / 0	0 / 0	0 / 0	85 / 0	0 / 0

BEARING MATERIAL TO BE SPF NO.2 OR BETTER AT JOINT(S) H

BRACING

TOP CHORD TO BE SHEATHED OR MAX. PURLINE SPACING = 6.25 FT.
MAX. UNBRACED BOTTOM CHORD LENGTH = 7.81 FT. OR RIGID CEILING DIRECTLY APPLIED.

ALL PITCH BREAKS AND PERIMETER CORNER JOINTS MUST BE LATERALLY RESTRAINED.

LOADING

TOTAL LOAD CASES: (4)

CHORDS	MAX. FACTORED	FACTORED	VERT. LOAD	LC1	MAX	MAX.	MEMB.	MAX. FACTORED	WEBS
MEMB.	FORCE (LBS)	VERT. LOAD	LC1	MAX	MAX.	MEMB.	FORCE (LBS)	MAX	
FR-TO		FROM	TO	CS1 (LC)	UNBRAC	FR-TO		CS1 (LC)	
H-B	-443 / 0	0.0	0.0	0.04 (1)	7.81	B-G	0 / 260	0.06 (1)	
A-B	0 / 28	-91.8	-91.8	0.12 (1)	10.00	G-E	-12 / 0	0.00 (1)	
B-C	-269 / 0	-91.8	-91.8	0.12 (1)	6.25	G-D	0 / 421	0.09 (1)	
C-D	-283 / 0	-91.8	-91.8	0.12 (1)	6.25				
E-D	-320 / 0	0.0	0.0	0.20 (1)	7.81				
H-G	0 / 0	-18.5	-18.5	0.07 (4)	10.00				
F-G	0 / 29	0.0	0.0	0.03 (1)	10.00				
G-C	-355 / 0	0.0	0.0	0.02 (1)	7.81				
F-E	0 / 11	-18.5	-18.5	0.04 (4)	10.00				

DESIGN CRITERIA

SPECIFIED LOADS:

TOP CH. LL	=	25.6	PSF
DL	=	6.0	PSF
BOT CH. LL	=	0.0	PSF
DL	=	7.4	PSF
TOTAL LOAD	=	39.0	PSF

SPACING = 24.0 IN/C

THIS TRUSS IS DESIGNED FOR RESIDENTIAL OR SMALL BUILDING REQUIREMENTS OF PART 9, NBCC 2015

THIS DESIGN COMPLIES WITH:

- PART 9 OF BCBC 2018, ABC 2019
- PART 9 OF OBC 2012 (2019 AMENDMENT)
- CSA 086-14
- TPIC 2014

(55 % OF 31.3 P.S.F. G.S.L. PLUS 8.4 P.S.F. RAIN LOAD) EQUALS 25.6 P.S.F. SPECIFIED ROOF LIVE LOAD

ALLOWABLE DEFL.(LL) = L/360 (0.21")
CALCULATED VERT. DEFL.(LL) = L/999 (0.01")
ALLOWABLE DEFL.(TL) = L/360 (0.21")
CALCULATED VERT. DEFL.(TL) = L/999 (0.01")

CSI: TC=0.20/1.00 (D-E:1), BC=0.07/1.00 (G-H:4), WB=0.09/1.00 (D-G:1), SS=0.13/1.00 (B-C:1)

DOL LUMBER=1.00 NAIL=1.00 LS BEND=1.10
COMP=1.10 SHEAR=1.10 TENS=1.10

COMPANION LIVE LOAD FACTOR = 1.00

TRUSS PLATE MANUFACTURER IS NOT RESPONSIBLE FOR QUALITY CONTROL IN THE TRUSS MANUFACTURING PLANT.

NAIL VALUES

PLATE	GRIP(DRY)	SHEAR	SECTION
(PSI)	(PLI)	(PLI)	
MAX	MIN	MAX	MIN
MT20	650	371	1747
	788	1987	1873

PLATE PLACEMENT TOL. = 0.250 inches

PLATE ROTATION TOL. = 5.0 Deg.

JSI GRIP= 0.43 (D) (INPUT = 0.90)

JSI METAL= 0.14 (B) (INPUT = 1.00)




Structural component only
DWG# T-2016995

JOB NAME 410174	TRUSS NAME T44S	QUANTITY 1	PLY 1	JOB DESC. GREEN PARK HOMES	DRWG NO.
--------------------	--------------------	---------------	----------	-------------------------------	----------

Tamarack Roof Truss, Burlington

Version 8.330 S May 6 2020 MiTek Industries, Inc. Thu Jul 30 08:42:35 2020 Page 1
ID:W63xGm6okc00SiyZ4EwBx6zA2m0-7MdNFKmx3HOJHV6ZRb0zeHYIxG_jyu10hH6qNmvsxf2

Scale = 1:27.9



LUMBER

N. L. G. A. RULES	CHORDS	SIZE	LUMBER	DESCR.
A - D	2x4	DRY	No.2	SPF
D - E	2x4	DRY	No.2	SPF
F - E	2x4	DRY	No.2	SPF
I - B	2x4	DRY	No.2	SPF
I - H	2x4	DRY	No.2	SPF
G - C	2x4	DRY	No.2	SPF
G - F	2x4	DRY	No.2	SPF
ALL WEBS	2x3	DRY	No.2	SPF
EXCEPT				
H - F	2x4	DRY	No.2	SPF

DRY: SEASONED LUMBER.

PLATES (table is in inches)

JT	TYPE	PLATES	W	LEN	Y	X
B	TMVW-t	MT20	4.0	4.0	2.00	1.25
C	TMV+p	MT20	3.0	4.0		
D	TTWW+m	MT20	5.0	6.0	Edge	
E	TMV+p	MT20	3.0	4.0		
F	BMVWW1+p	MT20	4.0	9.0	Edge	
G	BMV+p	MT20	3.0	4.0		
H	BVMWWW-I	MT20	6.0	12.0	3.25	5.00
I	BMV1+p	MT20	3.0	4.0		

Edge - INDICATES REFERENCE CORNER OF PLATE TOUCHES EDGE OF CHORD.

DIMENSIONS, SUPPORTS AND LOADINGS SPECIFIED BY FABRICATOR TO BE VERIFIED BY BUILDING DESIGNER

BEARINGS

JT	FACTORED GROSS REACTION	MAXIMUM FACTORED GROSS REACTION	INPUT BRG	REQD BRG
I	476	0	476	0
F	351	0	351	0

A SUITABLE HANGER/MECHANICAL CONNECTION IS REQUIRED AT JOINT F. MINIMUM BEARING LENGTH AT JOINT F = 1-8.

UNFACTORED REACTIONS

JT	1ST CASE	MAX/MIN. COMPONENT REACTIONS	SNOW	LIVE	PERM. LIVE	WIND	DEAD	SOIL
I	334	233 / 0	0 / 0	0 / 0	0 / 0	0 / 0	102 / 0	0 / 0
F	249	163 / 0	0 / 0	0 / 0	0 / 0	0 / 0	85 / 0	0 / 0

BEARING MATERIAL TO BE SPF NO.2 OR BETTER AT JOINT(S) I

BRACING

TOP CHORD TO BE SHEATHED OR MAX. PURLIN SPACING = 6.25 FT.
MAX. UNBRACED BOTTOM CHORD LENGTH = 7.81 FT. OR RIGID CEILING DIRECTLY APPLIED.

ALL PITCH BREAKS AND PERIMETER CORNER JOINTS MUST BE Laterally RESTRAINED.

LOADING

TOTAL LOAD CASES: (4)

MEMB.	CHORDS	MAX. FACTORED FORCE (LBS)	FACTORED VERT. LOAD (PLF)	MAX. LC1 (LC)	MAX. UNBRACED LENGTH	MEMB.	WEBS	MAX. FACTORED FORCE (LBS)	MAX. CS (LC)
FR-TO						FR-TO			
A-B	0 / 28	-91.8	-91.8	0.12 (1)	10.00	H-F	0 / 135	0.02 (1)	
B-C	-265 / 0	-91.8	-91.8	0.13 (1)	6.25	H-D	0 / 413	0.09 (1)	
C-D	-312 / 0	-91.8	-91.8	0.10 (1)	6.25	D-F	-326 / 0	0.12 (1)	
D-E	0 / 0	-91.8	-91.8	0.06 (1)	10.00	B-H	0 / 255	0.06 (1)	
E-F	-90 / 0	0.0	0.0	0.04 (1)	7.81				
I-B	-443 / 0	0.0	0.0	0.04 (1)	7.81				
I-H	0 / 0	-18.5	-18.5	0.07 (4)	10.00				
G-H	0 / 29	0.0	0.0	0.03 (1)	10.00				
H-C	-335 / 0	0.0	0.0	0.02 (1)	7.81				
G-F	0 / 11	-18.5	-18.5	0.04 (4)	10.00				

TOTAL WEIGHT = 39 lb

DESIGN CRITERIA

SPECIFIED LOADS:

TOP CH.	LL	=	25.6	PSF
	DL	=	6.0	PSF
BOT CH.	LL	=	0.0	PSF
	DL	=	7.4	PSF
TOTAL LOAD	=	39.0	PSF	

SPACING = 24.0 IN./C

LOADING IN FLAT SECTION BASED ON A SLOPE OF 6.00/12

THIS TRUSS IS DESIGNED FOR RESIDENTIAL OR SMALL BUILDING REQUIREMENTS OF PART 9, NBCC 2015

THIS DESIGN COMPLIES WITH:
- PART 9 OF BCBC 2019, ABC 2019
- PART 9 OF CBC 2012 (2019 AMENDMENT)
- CSA 086-14
- TPIC 2014

(55 % OF 31.3 P.S.F. G.S.L. PLUS 8.4 P.S.F. RAIN LOAD) EQUALS 25.6 P.S.F. SPECIFIED ROOF LIVE LOAD

ALLOWABLE DEFL.(LL) = L/360 (0.21")
CALCULATED VERT. DEFL.(LL) = L/999 (0.01")
ALLOWABLE DEFL.(TL) = L/360 (0.21")
CALCULATED VERT. DEFL.(TL) = L/999 (0.01")

CSI: TC=0.13/1.00 (B-C:1), BC=0.07/1.00 (H-I:4), WB=0.12/1.00 (D-F:1), SS=0.13/1.00 (B-C:1)

DOL LUMBER=1.00 NAIL=1.00 LS BEND=1.10
COMP=1.10 SHEAR=1.10 TENS=1.10

COMPANION LIVE LOAD FACTOR = 1.00

AUTOSOLVE RIGHT HEEL ONLY

TRUSS PLATE MANUFACTURER IS NOT RESPONSIBLE FOR QUALITY CONTROL IN THE TRUSS MANUFACTURING PLANT

NAIL VALUES

PLATE	GRIP (DRY)	SHEAR	SECTION
	(PSI)	(PLI)	(PLI)
	MAX	MIN	MAX MIN
MT20	650	371	1747 788 1987 1873

PLATE PLACEMENT TOL. = 0.250 inches

PLATE ROTATION TOL. = 5.0 Deg.

JSI GRIP= 0.42 (B) (INPUT = 0.90)
JSI METAL= 0.13 (B) (INPUT = 1.00)




Structural component only
DWG# T-2016996

JOB NAME	TRUSS NAME	QUANTITY	PLY	JOB DESC.	GREEN PARK HOMES	DRWG NO.
410174	T45S	1	1	TRUSS DESC.		

Tamarack Roof Truss, Burlington

Version 8.330 S May 6 2020 MTek Industries, Inc. Thu Jul 30 08:42:36 2020 Page 1
ID:W63xGm6okc00SiyZ4EwBx6zA2m0-bYBmSgnZqbWAVtgi_JXCbV4vcgKrhLU9wxsNvDysxf1



Scale = 1:23.4

LUMBER


N. L. G. A. RULES	CHORDS	SIZE	LUMBER	DESCR.
A - C	2x4	DRY	No.2	SPF
C - E	2x4	DRY	No.2	SPF
E - H	2x4	DRY	No.2	SPF
H - I	2x4	DRY	No.2	SPF
I - J	2x4	DRY	No.2	SPF
J - K	2x4	DRY	No.2	SPF
K - L	2x4	DRY	No.2	SPF
L - M	2x4	DRY	No.2	SPF
M - N	2x4	DRY	No.2	SPF
N - O	2x4	DRY	No.2	SPF
O - P	2x4	DRY	No.2	SPF
P - Q	2x4	DRY	No.2	SPF
Q - R	2x4	DRY	No.2	SPF
R - S	2x4	DRY	No.2	SPF
S - T	2x4	DRY	No.2	SPF
T - U	2x4	DRY	No.2	SPF
U - V	2x4	DRY	No.2	SPF
V - W	2x4	DRY	No.2	SPF
W - X	2x4	DRY	No.2	SPF
X - Y	2x4	DRY	No.2	SPF
Y - Z	2x4	DRY	No.2	SPF
Z - AA	2x4	DRY	No.2	SPF
AA - AB	2x4	DRY	No.2	SPF
AB - AC	2x4	DRY	No.2	SPF
AC - AD	2x4	DRY	No.2	SPF
AD - AE	2x4	DRY	No.2	SPF
AE - AF	2x4	DRY	No.2	SPF
AF - AG	2x4	DRY	No.2	SPF
AG - AH	2x4	DRY	No.2	SPF
AH - AI	2x4	DRY	No.2	SPF
AI - AJ	2x4	DRY	No.2	SPF
AJ - AK	2x4	DRY	No.2	SPF
AK - AL	2x4	DRY	No.2	SPF
AL - AM	2x4	DRY	No.2	SPF
AM - AN	2x4	DRY	No.2	SPF
AN - AO	2x4	DRY	No.2	SPF
AO - AP	2x4	DRY	No.2	SPF
AP - AQ	2x4	DRY	No.2	SPF
AQ - AR	2x4	DRY	No.2	SPF
AR - AS	2x4	DRY	No.2	SPF
AS - AT	2x4	DRY	No.2	SPF
AT - AU	2x4	DRY	No.2	SPF
AU - AV	2x4	DRY	No.2	SPF
AV - AW	2x4	DRY	No.2	SPF
AW - AX	2x4	DRY	No.2	SPF
AX - AY	2x4	DRY	No.2	SPF
AY - AZ	2x4	DRY	No.2	SPF
AZ - BA	2x4	DRY	No.2	SPF
BA - BB	2x4	DRY	No.2	SPF
BB - BC	2x4	DRY	No.2	SPF
BC - BD	2x4	DRY	No.2	SPF
BD - BE	2x4	DRY	No.2	SPF
BE - BF	2x4	DRY	No.2	SPF
BF - BG	2x4	DRY	No.2	SPF
BG - BH	2x4	DRY	No.2	SPF
BH - BI	2x4	DRY	No.2	SPF
BI - BJ	2x4	DRY	No.2	SPF
BJ - BK	2x4	DRY	No.2	SPF
BK - BL	2x4	DRY	No.2	SPF
BL - BM	2x4	DRY	No.2	SPF
BM - BN	2x4	DRY	No.2	SPF
BN - BO	2x4	DRY	No.2	SPF
BO - BP	2x4	DRY	No.2	SPF
BP - BQ	2x4	DRY	No.2	SPF
BQ - BR	2x4	DRY	No.2	SPF
BR - BS	2x4	DRY	No.2	SPF
BS - BT	2x4	DRY	No.2	SPF
BT - BU	2x4	DRY	No.2	SPF
BU - BV	2x4	DRY	No.2	SPF
BV - BW	2x4	DRY	No.2	SPF
BW - BX	2x4	DRY	No.2	SPF
BX - BY	2x4	DRY	No.2	SPF
BY - BZ	2x4	DRY	No.2	SPF
BZ - CA	2x4	DRY	No.2	SPF
CA - CB	2x4	DRY	No.2	SPF
CB - CC	2x4	DRY	No.2	SPF
CC - CD	2x4	DRY	No.2	SPF
CD - CE	2x4	DRY	No.2	SPF
CE - CF	2x4	DRY	No.2	SPF
CF - CG	2x4	DRY	No.2	SPF
CG - CH	2x4	DRY	No.2	SPF
CH - CI	2x4	DRY	No.2	SPF
CI - CJ	2x4	DRY	No.2	SPF
CJ - CK	2x4	DRY	No.2	SPF
CK - CL	2x4	DRY	No.2	SPF
CL - CM	2x4	DRY	No.2	SPF
CM - CN	2x4	DRY	No.2	SPF
CN - CO	2x4	DRY	No.2	SPF
CO - CP	2x4	DRY	No.2	SPF
CP - CQ	2x4	DRY	No.2	SPF
CQ - CR	2x4	DRY	No.2	SPF
CR - CS	2x4	DRY	No.2	SPF
CS - CT	2x4	DRY	No.2	SPF
CT - CU	2x4	DRY	No.2	SPF
CU - CV	2x4	DRY	No.2	SPF
CV - CW	2x4	DRY	No.2	SPF
CW - CX	2x4	DRY	No.2	SPF
CX - CY	2x4	DRY	No.2	SPF
CY - CZ	2x4	DRY	No.2	SPF
CZ - DA	2x4	DRY	No.2	SPF
DA - DB	2x4	DRY	No.2	SPF
DB - DC	2x4	DRY	No.2	SPF
DC - DD	2x4	DRY	No.2	SPF
DD - DE	2x4	DRY	No.2	SPF
DE - DF	2x4	DRY	No.2	SPF
DF - DG	2x4	DRY	No.2	SPF
DG - DH	2x4	DRY	No.2	SPF
DH - DI	2x4	DRY	No.2	SPF
DI - DJ	2x4	DRY	No.2	SPF
DJ - DK	2x4	DRY	No.2	SPF
DK - DL	2x4	DRY	No.2	SPF
DL - DM	2x4	DRY	No.2	SPF
DM - DN	2x4	DRY	No.2	SPF
DN - DO	2x4	DRY	No.2	SPF
DO - DP	2x4	DRY	No.2	SPF
DP - DQ	2x4	DRY	No.2	SPF
DQ - DR	2x4	DRY	No.2	SPF
DR - DS	2x4	DRY	No.2	SPF
DS - DT	2x4	DRY	No.2	SPF
DT - DU	2x4	DRY	No.2	SPF
DU - DV	2x4	DRY	No.2	SPF
DV - DW	2x4	DRY	No.2	SPF
DW - DX	2x4	DRY	No.2	SPF
DX - DY	2x4	DRY	No.2	SPF
DY - DZ	2x4	DRY	No.2	SPF
DZ - EA	2x4	DRY	No.2	SPF
EA - EB	2x4	DRY	No.2	SPF
EB - EC	2x4	DRY	No.2	SPF
EC - ED	2x4	DRY	No.2	SPF
ED - EE	2x4	DRY	No.2	SPF
EE - EF	2x4	DRY	No.2	SPF
EF - EG	2x4	DRY	No.2	SPF
EG - EH	2x4	DRY	No.2	SPF
EH - EI	2x4	DRY	No.2	SPF
EI - EJ	2x4	DRY	No.2	SPF
EJ - EK	2x4	DRY	No.2	SPF
EK - EL	2x4	DRY	No.2	SPF
EL - EM	2x4	DRY	No.2	SPF
EM - EN	2x4	DRY	No.2	SPF
EN - EO	2x4	DRY	No.2	SPF
EO - EP	2x4	DRY	No.2	SPF
EP - EQ	2x4	DRY	No.2	SPF
EQ - ER	2x4	DRY	No.2	SPF
ER - ES	2x4	DRY	No.2	SPF
ES - ET	2x4	DRY	No.2	SPF
ET - EU	2x4	DRY	No.2	SPF
EU - EV	2x4	DRY	No.2	SPF
EV - EW	2x4	DRY	No.2	SPF
EW - EX	2x4	DRY	No.2	SPF
EX - EY	2x4	DRY	No.2	SPF
EY - EZ	2x4	DRY	No.2	SPF
EZ - FA	2x4	DRY	No.2	SPF
FA - FB	2x4	DRY	No.2	SPF
FB - FC	2x4	DRY	No.2	SPF
FC - FD	2x4	DRY	No.2	SPF
FD - FE	2x4	DRY	No.2	SPF
FE - FG	2x4	DRY	No.2	SPF
FG - FH	2x4	DRY	No.2	SPF
FH - FI	2x4	DRY	No.2	SPF
FI - FJ	2x4	DRY	No.2	SPF
FJ - FK	2x4	DRY	No.2	SPF
FK - FL	2x4	DRY	No.2	SPF
FL - FM	2x4	DRY	No.2	SPF
FM - FN	2x4	DRY	No.2	SPF
FN - FO	2x4	DRY	No.2	SPF
FO - FP	2x4	DRY	No.2	SPF
FP - FQ	2x4	DRY	No.2	SPF
FQ - FR	2x4	DRY	No.2	SPF
FR - FS	2x4	DRY	No.2	SPF
FS - FT	2x4	DRY	No.2	SPF
FT - FU	2x4	DRY	No.2	SPF
FU - FV	2x4	DRY	No.2	SPF
FV - FW	2x4	DRY	No.2	SPF
FW - FX	2x4	DRY	No.2	SPF
FX - FY	2x4	DRY	No.2	SPF
FY - FZ	2x4	DRY	No.2	SPF
FZ - GA	2x4	DRY	No.2	SPF
GA - GB	2x4	DRY	No.2	SPF
GB - GC	2x4	DRY	No.2	SPF
GC - GD	2x4	DRY	No.2	SPF
GD - GE	2x4	DRY	No.2	SPF
GE - GF	2x4	DRY	No.2	SPF
GF - GG	2x4	DRY	No.2	SPF
GG - GH	2x4	DRY	No.2	SPF
GH - GI	2x4	DRY	No.2	SPF
GI - GJ	2x4	DRY	No.2	SPF
GJ - GK	2x4	DRY	No.2	SPF
GK - GL	2x4	DRY	No.2	SPF
GL - GM	2x4	DRY	No.2	SPF
GM - GN	2x4	DRY	No.2	SPF
GN - GO	2x4	DRY	No.2	SPF
GO - GP	2x4	DRY	No.2	SPF
GP - GQ	2x4	DRY	No.2	SPF
GQ - GR	2x4	DRY	No.2	SPF
GR - GS	2x4	DRY	No.2	SPF
GS - GT	2x4	DRY	No.2	SPF
GT - GU	2x4	DRY	No.2	SPF
GU - GV	2x4	DRY	No.2	SPF
GV - GW	2x4	DRY	No.2	SPF
GW - GX	2x4	DRY	No.2	SPF
GX - GY	2x4	DRY	No.2	SPF
GY - GZ	2x4	DRY	No.2	SPF
GZ - HA	2x4	DRY	No.2	SPF
HA - HB	2x4	DRY	No.2	SPF
HB - HC	2x4	DRY	No.2	SPF
HC - HD	2x4	DRY	No.2	SPF
HD - HE	2x4	DRY	No.2	SPF
HE - HF	2x4	DRY	No.2	SPF
HF - HG	2x4	DRY	No.2	SPF
HG - HH	2x4	DRY	No.2	SPF
HH - HI	2x4	DRY	No.2	SPF
HI - HJ	2x4	DRY	No.2	SPF
HJ - HK	2x4	DRY	No.2	SPF
HK - HL	2x4	DRY	No.2	SPF
HL - HM	2x4	DRY	No.2	SPF
HM - HN	2x4	DRY	No.2	SPF
HN - HO	2x4	DRY	No.2	SPF
HO - HP	2x4	DRY	No.2	SPF
HP - HQ	2x4	DRY	No.2	SPF
HQ - HR	2x4	DRY	No.2	SPF
HR - HS	2x4	DRY	No.2	SPF
HS - HT	2x4	DRY	No.2	SPF
HT - HU	2x4	DRY	No.2	SPF
HU - HV	2x4	DRY	No.2	SPF
HV - HW	2x4	DRY	No.2	SPF
HW - HX	2x4	DRY	No.2	SPF
HX - HY	2x4	DRY	No.2	SPF
HY - HZ	2x4	DRY	No.2	SPF
HZ - IA	2x4	DRY	No.2	SPF
IA - IB	2x4	DRY	No.2	SPF
IB - IC	2x4	DRY	No.2	SPF
IC - ID	2x4	DRY	No.2	SPF
ID - IE	2x4	DRY	No.2	SPF
IE - IF	2x4	DRY	No.2	SPF
IF - IG	2x4	DRY	No.2	SPF

JOB NAME	TRUSS NAME	QUANTITY	PLY	JOB DESC.	DRWG NO.
410174	T46	1	2	GREEN PARK HOMES	
Tamarack Roof Truss, Burlington					

Version 8.330 S May 6 2020 MiTek Industries, Inc. Thu Jul 30 08:42:37 2020 Page 1

ID:W63xGm6okcO0SiyZ4EwBx6zA2m0-3kl8g0oCbue1WpFyY02Rkid2n4ZWQpQl8bbxRfysxf0

Scale = 1:23.7



LUMBER

CHORDS	SIZE	LUMBER	DESCR.
D - A	2x6 DRY	No.2	SPF
A - B	2x4 DRY	No.2	SPF
C - B	2x4 DRY	No.2	SPF
D - C	2x6 DRY	No.2	SPF
ALL WEBS	2x3 DRY	No.2	SPF
DRY: SEASONED LUMBER.			

DESIGN CONSISTS OF 2 TRUSSES BUILT SEPARATELY THEN FASTENED TOGETHER AS FOLLOWS:

CHORDS #ROWS	SURFACE SPACING (IN)	LOAD(PLF)
TOP CHORDS : (0.122"x3") SPIRAL NAILS		
D-A 2	12	TOP
A-B 1	12	TOP
B-C 1	12	TOP
BOTTOM CHORDS : (0.122"x3") SPIRAL NAILS		
D-C 2	12	SIDE(0.0)
WEBS : (0.122"x3") SPIRAL NAILS		
2x3 1	6	

NAILS TO BE DRIVEN FROM ONE SIDE ONLY.

GIRDER NAILING ASSUMES NAILED HANGERS ARE FASTENED WITH MIN. 3-0 INCH NAILS.

TOP - COMPONENTS ARE LOADED FROM THE TOP AND MUST BE PLACED ON TOP EDGE OF ALL PLIES FOR THE LOAD TO BE TRANSFERRED TO EACH PLY.

SIDE - PLF SHOWN IS THE EQUIVALENT UDL APPLIED TO ONE SIDE THAT THE CORRESPONDING NAILING PATTERN SHALL BE CAPABLE OF TRANSFERRING. REMAINING PLF MUST BE APPLIED ON THE OPPOSITE SIDE OR ON THE TOP.

PLATES (table is in inches)

JT	TYPE	PLATES	W	LEN	Y	X
A	TMVW-p	MT20	4.0	6.0	1.00	3.00
B	TMV+p	MT20	3.0	4.0		
C	BMVW1+p	MT20	4.0	6.0		
D	BMV1+p	MT20	3.0	6.0		

DIMENSIONS, SUPPORTS AND LOADINGS SPECIFIED BY FABRICATOR TO BE VERIFIED BY BUILDING DESIGNER

BEARINGS	FACTORED GROSS REACTION	MAXIMUM FACTORED GROSS REACTION	INPUT BRG	REQD BRG
JT	VERT	DOWN	UPLIFT	IN-SX
D	963	0	0	5-8
C	1127	0	0	MECHANICAL

A SUITABLE HANGER/MECHANICAL CONNECTION IS REQUIRED AT JOINT C. MINIMUM BEARING LENGTH AT JOINT C = 1-8.

UNFACTORED REACTIONS

1ST CASE	MAX./MIN. COMPONENT REACTIONS
JT	COMBINED
D	680 455 / 0 0 / 0 0 / 0 0 / 0 0 / 0 0
C	795 533 / 0 0 / 0 0 / 0 0 262 / 0 0 / 0

BEARING MATERIAL TO BE SPF NO.2 OR BETTER AT JOINT(S) D

BRACING

TOP CHORD TO BE SHEATHED OR MAX. PURLIN SPACING = 10.00 FT. MAX. UNBRACED BOTTOM CHORD LENGTH = 10.00 FT OR RIGID CEILING DIRECTLY APPLIED.

ALL PITCH BREAKS AND PERIMETER CORNER JOINTS MUST BE Laterally RESTRAINED.

LOADING

TOTAL LOAD CASES: (4)

CHORDS	MAX. FACTORED FORCE (LBS)	FACTORED VERT. LOAD (PLF)	LC1	MAX. CSI (LC)	UNBRAC LENGTH	WEBS	MAX. FACTORED FORCE (LBS)	MAX. CSI (LC)
FR-TO		FROM TO				FR-TO		
D-A	-270 / 0	0.0	0.0	0.01 (1)	7.81	A-C	0 / 0	0.00 (1)
A-B	0 / 0	-91.8	-91.8	0.30 (1)	10.00			
C-B	-270 / 0	0.0	0.0	0.03 (1)	7.81			
D-E	0 / 0	-18.5	-18.5	0.56 (1)	10.00			
E-F	0 / 0	-18.5	-18.5	0.56 (1)	10.00			
F-C	0 / 0	-18.5	-18.5	0.56 (1)	10.00			

FACTORED CONCENTRATED LOADS (LBS)

JT	LOC.	LC1	MAX-	MAX+	FACE	DIR.	TYPE	HEEL	CONN.
E	2-3-4	-721	-721	--	FRONT	VERT	TOTAL	--	C1
F	4-3-4	-721	-721	--	FRONT	VERT	TOTAL	--	C1

CONNECTION REQUIREMENTS

1) C1: A SUITABLE HANGER/MECHANICAL CONNECTION IS REQUIRED.

TOTAL WEIGHT = 2 X 27 = 55 lb

DESIGN CRITERIA

SPECIFIED LOADS:

TOP CH.	LL = 25.6 PSF
	DL = 6.0 PSF
BOT CH.	LL = 0.0 PSF
	DL = 7.4 PSF
TOTAL LOAD	= 39.0 PSF

SPACING = 24.0 IN./C

THIS TRUSS IS DESIGNED FOR RESIDENTIAL OR SMALL BUILDING REQUIREMENTS OF PART 9, NBCC 2015

THIS DESIGN COMPLIES WITH:

- PART 9 OF CBC 2018, ABC 2019
- PART 9 OF OBC 2012 (2019 AMENDMENT)
- CSA 086-14
- TPIC 2014

(55 % OF 31.3 P.S.F. G.S.L. PLUS 8.4 P.S.F. RAIN LOAD) EQUALS 25.6 P.S.F. SPECIFIED ROOF LIVE LOAD

ALLOWABLE DEFL.(LL)= L/360 (0.20")
CALCULATED VERT. DEFL.(LL) = L/968 (0.07")
ALLOWABLE DEFL.(TL)= L/360 (0.20")
CALCULATED VERT. DEFL.(TL) = L/507 (0.14")

CSI: TC=0.30/1.00 (A-B:1), BC=0.56/1.00 (C-D:1), WB=0.00/1.00 (A-C:1), SSI=0.28/1.00 (C-D:1)

DOL LUMBER=1.00 NAIL=1.00 LS BEND=1.00
COMP=1.00 SHEAR=1.00 TENS=1.00

COMPANION LIVE LOAD FACTOR = 1.00

TRUSS PLATE MANUFACTURER IS NOT RESPONSIBLE FOR QUALITY CONTROL IN THE TRUSS MANUFACTURING PLANT.

NAIL VALUES

PLATE	GRIP(DRY)	SHEAR	SECTION
	(PSI)	(PLI)	(PLI)
MT20	650	371	1747
	788	1987	1873

PLATE PLACEMENT TOL. = 0.250 inches

PLATE ROTATION TOL. = 5.0 Deg.

JSI GRIP= 0.06 (A) (INPUT = 0.90)


JSI METAL= 0.04 (B) (INPUT = 1.00)



Structural component only
DWG# T-2016998

JOB NAME	TRUSS NAME	QUANTITY	PLY	JOB DESC.	DRWG NO.
410174	T47	1	2	GREEN PARK HOMES	
Tamarack Roof Truss, Burlington		TRUSS DESC.			

Version 8.330 S May 6 2020 MiTek Industries, Inc. Thu Jul 30 08:42:38 2020 Page 1
ID:W63xGm60kcO0SiyZ4EwBx6zA2m0-XxJwIMpQMCmu8zq86kZgGwACjUs69GgSNFLU_5ysxf?



Scale = 1:33.0

LUMBER			
N. L. G. A. RULES	CHORDS	SIZE	LUMBER
D - A	2x6	DRY	No.2
A - B	2x4	DRY	No.2
C - B	2x4	DRY	No.2
D - C	2x6	DRY	No.2
ALL WEBS	2x3	DRY	No.2
SPF SEASONED LUMBER.			

DESIGN CONSISTS OF 2 TRUSSES BUILT SEPARATELY THEN FASTENED TOGETHER AS FOLLOWS:

CHORDS #ROWS	SURFACE SPACING (IN)	LOAD(PLF)
TOP CHORDS : (0.122"x3") SPIRAL NAILS		
D - A 2	12	TOP
A - B 1	12	TOP
B - C 1	12	TOP
BOTTOM CHORDS : (0.122"x3") SPIRAL NAILS		
D - C 2	12	SIDE(0.0)
WEBS : (0.122"x3") SPIRAL NAILS		
2x3 1	6	

NAILS TO BE DRIVEN FROM ONE SIDE ONLY.

GIRDER NAILING ASSUMES NAILED HANGERS ARE FASTENED WITH MIN. 3-0 INCH NAILS.

TOP - COMPONENTS ARE LOADED FROM THE TOP AND MUST BE PLACED ON TOP EDGE OF ALL PLIES FOR THE LOAD TO BE TRANSFERRED TO EACH PLY.

SIDE - PLF SHOWN IS THE EQUIVALENT UDL APPLIED TO ONE SIDE THAT THE CORRESPONDING NAILING PATTERN SHALL BE CAPABLE OF TRANSFERING. REMAINING PLF MUST BE APPLIED ON THE OPPOSITE SIDE OR ON THE TOP.

PLATES (table is in inches)					
JT	TYPE	PLATES	W	LEN	Y X
A	TMVW-p	MT20	4.0	6.0	1.00 3.00
B	TMV+p	MT20	3.0	4.0	
C	BMVW1+p	MT20	4.0	6.0	
D	BMV1+p	MT20	3.0	6.0	

DIMENSIONS, SUPPORTS AND LOADINGS SPECIFIED BY FABRICATOR TO BE VERIFIED BY BUILDING DESIGNER

BEARINGS		FACTORED GROSS REACTION	MAXIMUM FACTORED GROSS REACTION	INPUT BRG	REQD BRG
JT	VERT	HORZ	DOWN	UP	IN-SX
D	1541	0	1541	0	5-8
C	1265	0	1265	0	MECHANICAL

A SUITABLE HANGER/MECHANICAL CONNECTION IS REQUIRED AT JOINT C. MINIMUM BEARING LENGTH AT JOINT C = 1-8.

UNFACTORED REACTIONS		1ST LCASE	MAX. MIN. COMPONENT REACTIONS
JT	COMBINED	SNOW	LIVE
D	1087	729 / 0	0 / 0
C	892	598 / 0	0 / 0

BEARING MATERIAL TO BE SPF NO.2 OR BETTER AT JOINT(S) D

BRACING
TOP CHORD TO BE SHEATHED OR MAX. PURLIN SPACING = 10.00 FT.
MAX. UNBRACED BOTTOM CHORD LENGTH = 10.00 FT OR RIGID CEILING DIRECTLY APPLIED.
ALL PITCH BREAKS AND PERIMETER CORNER JOINTS MUST BE LATERALLY RESTRAINED.

LOADING

TOTAL LOAD CASES: (4)

CHORDS		MAX. FACTORED	FACTORED	WEBS	MAX. FACTORED
MEMB.	FORCE (LBS)	VERT. LOAD (PLF)	LC1 MAX	MEMB.	FORCE (LBS)
FR-TO		FROM	TO	FR-TO	
D - A	-292 / 0	0.0	0.0 0.01 (1)	A - C	0 / 0
A - B	0 / 0	-91.8	-91.8 0.35 (1)		0.00 (1)
C - B	-292 / 0	0.0	0.0 0.09 (1)		
D - E	0 / 0	-18.5	-18.5 0.73 (1)		10.00
E - F	0 / 0	-18.5	-18.5 0.73 (1)		10.00
F - G	0 / 0	-18.5	-18.5 0.73 (1)		10.00
G - C	0 / 0	-18.5	-18.5 0.73 (1)		10.00

FACTORED CONCENTRATED LOADS (LBS)		LOC.	LC1	MAX-	MAX+	FACE	DIR.	TYPE	HEEL	CONN.
E	9-4	-703	-703	---	---	BACK	VERT	TOTAL	---	C1
F	2-9-4	-700	-700	---	---	BACK	VERT	TOTAL	---	C1
G	4-9-4	-700	-700	---	---	BACK	VERT	TOTAL	---	C1

CONNECTION REQUIREMENTS

1) C1: A SUITABLE HANGER/MECHANICAL CONNECTION IS REQUIRED.

TOTAL WEIGHT = 2 X 34 = 68 lb

DESIGN CRITERIA

SPECIFIED LOADS:
TOP CH. LL = 25.6 PSF
DL = 8.0 PSF
BOT CH. LL = 0.0 PSF
DL = 7.4 PSF
TOTAL LOAD = 39.0 PSF

SPACING = 24.0 IN.C/C

THIS TRUSS IS DESIGNED FOR RESIDENTIAL OR SMALL BUILDING REQUIREMENTS OF PART 9, NBCC 2015

THIS DESIGN COMPLIES WITH:
- PART 9 OF BCBC 2018, ABC 2019
- PART 9 OF OBC 2012 (2019 AMENDMENT)
- CSA 086-14
- TPIC 2014

(55 % OF 31.3 P.S.F. G.S.L. PLUS 8.4 P.S.F. RAIN LOAD) EQUALS 25.6 P.S.F. SPECIFIED ROOF LIVE LOAD

ALLOWABLE DEFL.(LL)= L/360 (0.21")
CALCULATED VERT. DEFL.(LL) = L/697 (0.11")
ALLOWABLE DEFL.(TL)= L/360 (0.21")
CALCULATED VERT. DEFL.(TL) = L/366 (0.21")

CSI: TC=0.35/1.00 (A-B:1), BC=0.73/1.00 (C-D:1), WB=0.00/1.00 (A-C:1), SSI=0.41/1.00 (C-D:1)

DOL LUMBER=1.00 NAIL=1.00 LS BEND=1.00
COMP=1.00 SHEAR=1.00 TENS= 1.00

COMPANION LIVE LOAD FACTOR = 1.00

TRUSS PLATE MANUFACTURER IS NOT RESPONSIBLE FOR QUALITY CONTROL IN THE TRUSS MANUFACTURING PLANT

NAIL VALUES			
PLATE	GRIP(DRY)	SHEAR	SECTION
(PSI)	(PLI)	(PLI)	(PLI)
MT20	650	371	1747
	788	1987	1873

PLATE PLACEMENT TOL. = 0.250 inches

PLATE ROTATION TOL. = 5.0 Deg.

JSI GRIP = 0.07 (A) (INPUT = 0.90)
JSI METAL = 0.04 (B) (INPUT = 1.00)



Structural component only
DWG# T-2016999

JOB NAME	TRUSS NAME	QUANTITY	PLY	JOB DESC.	DRWG NO.
410174	T300	1	2	GREEN PARK HOMES	
Tamarack Roof Truss, Burlington		TRUSS DESC.			

Version 8.330 S May 6 2020 MiTek Industries, Inc. Thu Jul 30 08:42:39 2020 Page 2

ID:W63xGm6okcC0SivZ4EwBx6zA2m0-07tu4ipS7Wulm7PKgR4vp7iM8uHRudhbcv41WXysxf

PLATES (table is in inches)

JT	TYPE	PLATES	W	LEN	Y	X
B	TMVW-p	MT20	4.0	6.0	1.00	3.25
C	TMWW-t	MT20	4.0	4.0	2.00	1.75
D	TTWW-m	MT20	5.0	6.0	2.25	2.00
E	TMW-w	MT20	2.0	4.0		
F	TTWW-m	MT20	5.0	6.0	2.25	2.00
G	TMVW-p	MT20	4.0	6.0	1.00	3.25
H	BMV1+p	MT20	3.0	6.0		
J, M, N						
J	BMWW-t	MT20	5.0	6.0		
K	BS-t	MT20	5.0	6.0		
L	BMWWW-t	MT20	5.0	8.0		
O	BMV1+p	MT20	3.0	6.0		




Structural component only
DWG# T-2017000 *yl*

JOB NAME 410172	TRUSS NAME P1	QUANTITY 24	PLY 1	JOB DESC. GREEN PARK HOMES	TRUSS DESC.	DRWG NO.
--------------------	------------------	----------------	----------	-------------------------------	-------------	----------

Tamarack Roof Truss, Burlington

Version 8.330 S May 6 2020 MiTek Industries, Inc. Thu Jul 30 08:32:19 2020 Page 1
ID:W63xGm60kc00SiyZ4EwBx6zA2m0-9rPWYjY80njNr0ALEyWh01R7ykgdHpL1SuEITysxog



LUMBER

N. L. G. A. RULES

CHORDS	SIZE	LUMBER
A - C	2x4 DRY	No.2
C - E	2x4 DRY	No.2
A - G	2x4 DRY	No.2
G - E	2x4 DRY	No.2

ALL WEBS 2x3 DRY
DRY: SEASONED LUMBER.

DESCR.

SPF

SPF

SPF

SPF

DIMENSIONS, SUPPORTS AND LOADINGS SPECIFIED BY FABRICATOR TO BE VERIFIED BY BUILDING DESIGNER

BEARINGS

JT	FACTORED GROSS REACTION		MAXIMUM FACTORED GROSS REACTION		INPUT BRG	REQD BRG
	VERT	HORZ	DOWN	HORZ		
A	124	0	124	0	16-8-12 (9-11-12)	16-8-12
E	124	0	124	0	16-8-12 (9-11-12)	16-8-12
H	377	0	377	0	16-8-12 (9-11-12)	16-8-12
F	609	0	609	0	16-8-12 (9-11-12)	16-8-12
I	609	0	609	0	16-8-12 (9-11-12)	16-8-12

VALUE IN PARENTHESIS INDICATES EFFECTIVE BEARING LENGTH

UNFACTORED REACTIONS

JT	1ST LCASE	MAX./MIN. COMPONENT REACTIONS					
		SNOW	LIVE	PERM.LIVE	WIND	DEAD	SOIL
A	88	59/0	0/0	0/0	0/0	28/0	0/0
E	88	59/0	0/0	0/0	0/0	28/0	0/0
H	267	175/0	0/0	0/0	0/0	92/0	0/0
F	431	281/0	0/0	0/0	0/0	150/0	0/0
I	431	281/0	0/0	0/0	0/0	150/0	0/0

BEARING MATERIAL TO BE SPF NO.2 OR BETTER AT JOINT(S) A, E, H, F, I

BRACING

TOP CHORD TO BE SHEATHED OR MAX. PURLIN SPACING = 10.00 FT.
MAX. UNBRACED BOTTOM CHORD LENGTH = 6.25 FT. OR RIGID CEILING DIRECTLY APPLIED.

ALL PITCH BREAKS AND PERIMETER CORNER JOINTS MUST BE Laterally RESTRAINED.

LOADING

TOTAL LOAD CASES: (4)

CHORDS				WEBS			
MAX. FACTORED		FACTORED		MAX. FACTORED			
MEMB.	FORCE (LBS)	VERT. LOAD (PLF)	LC1 MAX CSI (LC)	MAX. UNBRACED LENGTH	MEMB.	FORCE (LBS)	MAX CSI (LC)
FR-TO		FROM TO			FR-TO		
A-K	0 / 211	-91.8	-91.8 0.07 (1)	10.00	H-C	-399 / 0	0.10 (1)
K-B	0 / 253	-91.8	-91.8 0.27 (1)	10.00	H-D	0 / 45	0.01 (1)
B-C	0 / 165	-91.8	-91.8 0.26 (1)	10.00	F-D	-476 / 0	0.07 (1)
C-D	0 / 165	-91.8	-91.8 0.26 (1)	10.00	B-H	0 / 45	0.01 (1)
D-M	0 / 253	-91.8	-91.8 0.27 (1)	10.00	I-B	-476 / 0	0.07 (1)
M-E	0 / 211	-91.8	-91.8 0.07 (1)	10.00	J-K	-118 / 5	0.00 (1)
					L-M	-118 / 5	0.00 (1)
A-J	-220 / 0	-18.5	-18.5 0.13 (1)	6.25			
J-I	-206 / 0	-18.5	-18.5 0.13 (1)	6.25			
I-H	-206 / 0	-18.5	-18.5 0.10 (1)	6.25			
H-G	-206 / 0	-18.5	-18.5 0.10 (1)	6.25			
G-F	-206 / 0	-18.5	-18.5 0.10 (1)	6.25			
F-L	-206 / 0	-18.5	-18.5 0.13 (1)	6.25			
L-E	-220 / 0	-18.5	-18.5 0.13 (1)	6.25			

TOTAL WEIGHT = 24 X 51 = 1226 lb

DESIGN CRITERIA

SPECIFIED LOADS:

TOP CH.	LL = 25.6 PSF
	DL = 6.0 PSF
BOT CH.	LL = 0.0 PSF
	DL = 7.4 PSF
TOTAL LOAD	= 39.0 PSF

SPACING = 24.0 IN./C

THIS TRUSS IS DESIGNED FOR RESIDENTIAL OR SMALL BUILDING REQUIREMENTS OF PART 9, NBCC 2015

THIS DESIGN COMPLIES WITH:

- PART 9 OF BCBC 2018, ABC 2019
- PART 9 OF OBC 2012 (2019 AMENDMENT)
- CSA 086-14
- TPIC 2014

(55% OF 31.3 P.S.F. G.S.L. PLUS 8.4 P.S.F. RAIN LOAD) EQUALS 25.6 P.S.F. SPECIFIED ROOF LIVE LOAD

CSI: TC=0.27/1.00 (B-K:1), BC=0.13/1.00 (F-L:1), WB=0.10/1.00 (C-H:1), SSI=0.16/1.00 (B-K:1)

DOL LUMBER=1.00 NAIL=1.00 LS BEND=1.10 COMP=1.10 SHEAR=1.10 TENS=1.10

COMPANION LIVE LOAD FACTOR = 1.00

TRUSS PLATE MANUFACTURER IS NOT RESPONSIBLE FOR QUALITY CONTROL IN THE TRUSS MANUFACTURING PLANT

NAIL VALUES

PLATE	GRIP(DRY)	SHEAR	SECTION
	(PSI)	(PLI)	(PLI)
MT20	650	371	1747
	788	1987	1873

PLATE PLACEMENT TOL. = 0.250 inches

PLATE ROTATION TOL. = 5.0 Deg.

JSI GRIP= 0.40 (B) (INPUT = 0.90)

JSI METAL= 0.12 (C) (INPUT = 1.00)




Structural component only
DWG# T-2016974

JOB NAME	TRUSS NAME	QUANTITY	PLY	JOB DESC.	GREEN PARK HOMES	DRWG NO.
410169	J1	30	1	TRUSS DESC.		

Tamarack Roof Truss, Burlington

Version 8.330 S May 6 2020 MiTek Industries, Inc. Fri Aug 14 14:44:53 2020 Page 1
ID:W63xGm6okcO0SiyZ4EwBx6zA2m0-DVVIZg2kwKVedbHG775PibGi8T35BYgW4JHkhgynvxO

Scale = 1:22.9



LUMBER			
N. L. G. A. RULES	CHORDS	SIZE	LUMBER
E - B	2x4	DRY	No.2
A - C	2x4	DRY	No.2
E - D	2x4	DRY	No.2

DRY: SEASONED LUMBER.

PLATES (table is in inches)					
JT	TYPE	PLATES	W	LEN	Y X
B	TMV+p	MT20	3.0	4.0	
E	BMV1+p	MT20	3.0	4.0	

DIMENSIONS, SUPPORTS AND LOADINGS SPECIFIED BY FABRICATOR TO BE VERIFIED BY BUILDING DESIGNER

BEARINGS		FACTORED GROSS REACTION	MAXIMUM FACTORED GROSS REACTION	INPUT BRG	REQD BRG
JT	VERT	HORZ	DOWN	UP	IN-SX
E	525	0	525	0	5-8
C	202	0	202	0	1-8
D	45	0	50	0	1-8

SEE MITTEK STANDARD DETAIL B97791H FOR CONNECTION TO JOINT(S) C, D

UNFACTORED REACTIONS

1ST LCASE		MAX./MIN. COMPONENT REACTIONS				DEAD	SOIL
JT	COMBINED	SNOW	LIVE	PERM.LIVE	WIND		
E	369	257.0	0.0	0.0	0.0	111.0	0.0
C	139	113.0	0.0	0.0	0.0	26.0	0.0
D	36	0.0	0.0	0.0	0.0	36.0	0.0

BEARING MATERIAL TO BE SPF NO.2 OR BETTER AT JOINT(S) E

BRACING

TOP CHORD TO BE SHEATHED OR MAX. PURLIN SPACING = 6.25 FT.
MAX. UNBRACED BOTTOM CHORD LENGTH = 10.00 FT OR RIGID CEILING DIRECTLY APPLIED.

ALL PITCH BREAKS AND PERIMETER CORNER JOINTS MUST BE LATERALLY RESTRAINED.

LOADING

TOTAL LOAD CASES: (4)

CHORDS		WEBS			
MEMB.	MAX. FACTORED FORCE (LBS)	FACTORED VERT. LOAD (PLF)	MAX. UNBRACED LENGTH (FT)	MEMB.	MAX. FACTORED FORCE (LBS)
FR-TO		FROM TO		FR-TO	
E-B	-461.0	0.0	0.0 0.13 (4)	7.81	
A-B	0.28	-91.8	-91.8 0.12 (1)	10.00	
B-C	-30.0	-91.8	-91.8 0.54 (1)	6.25	
E-D	0.0	-18.5	-18.5 0.13 (4)	10.00	

DESIGN CRITERIA

SPECIFIED LOADS:
TOP CH. LL = 25.6 PSF
DL = 6.0 PSF
BOT CH. LL = 0.0 PSF
DL = 7.4 PSF
TOTAL LOAD = 39.0 PSF

SPACING = 24.0 IN. C/C

THIS TRUSS IS DESIGNED FOR RESIDENTIAL OR SMALL BUILDING REQUIREMENTS OF PART 9, NBCC 2015

THIS DESIGN COMPLIES WITH:
- PART 9 OF BCBC 2018, ABC 2019
- PART 9 OF OBC 2012 (2019 AMENDMENT)
- CSA 086-14
- TPIC 2014

DESIGN ASSUMPTIONS
- OVERHANG NOT TO BE ALTERED OR CUT OFF.

(55% OF 31.3 P.S.F. G.S.L. PLUS 8.4 P.S.F. RAIN LOAD) EQUALS 25.6 P.S.F. SPECIFIED ROOF LIVE LOAD

ALLOWABLE DEFL.(LL) = L/360 (0.20")
CALCULATED VERT. DEFL.(LL) = L/999 (0.00")
ALLOWABLE DEFL.(TL) = L/360 (0.20")
CALCULATED VERT. DEFL.(TL) = L/999 (0.03")

CSI: TC=0.54/1.00 (B-C:1), BC=0.13/1.00 (D-E:4).
WB=0.00/1.00 (n/a:0), SSI=0.24/1.00 (B-C:1)

DOL LUMBER=1.00 NAIL=1.00 LS BEND=1.10
COMP=1.10 SHEAR=1.10 TENS=1.10

COMPANION LIVE LOAD FACTOR = 1.00

AUTOSOLVE RIGHT HEEL ONLY

TRUSS PLATE MANUFACTURER IS NOT RESPONSIBLE FOR QUALITY CONTROL IN THE TRUSS MANUFACTURING PLANT.

NAIL VALUES
PLATE GRIP(DRY) SHEAR SECTION
(PSI) (PLI) (PLI)
MAX MIN MAX MIN MAX MIN
MT20 650 371 1747 788 1987 1873

PLATE PLACEMENT TOL. = 0.250 inches

PLATE ROTATION TOL. = 5.0 Deg.

JSI GRIP= 0.18 (E) (INPUT = 0.90)
JSI METAL= 0.13 (B) (INPUT = 1.00)




Structural component only
DWG# T-2018272

JOB NAME 410169	TRUSS NAME J2	QUANTITY 5	PLY 1	JOB DESC. GREEN PARK HOMES	TRUSS DESC.	DRWG NO.
--------------------	------------------	---------------	----------	-------------------------------	-------------	----------

Tamarack Roof Truss, Burlington

Version 8.330 S May 6 2020 MiTek Industries, Inc. Fri Aug 14 14:44:54 2020 Page 1
ID:W63xGm6okcO0SiyZ4EwBx6zA2m0-hi25m03MgedVFlsShqdeEoo_TtRow?wflz1ID7ynvxN

Scale = 1:9.3



TOTAL WEIGHT = 5 X 8 = 41 lb

LUMBER

N. L. G. A. RULES

CHORDS	SIZE	DRY	LUMBER
A - C	2x4	DRY	No.2
B - D	2x4	DRY	No.2

DRY: SEASONED LUMBER.

PLATES (table is in inches)

JT TYPE	PLATES	W	LEN	Y	X
B	TMBH1-m	MT20	4.0	6.0	2.00 0.25

DIMENSIONS, SUPPORTS AND LOADINGS SPECIFIED BY FABRICATOR TO BE VERIFIED BY BUILDING DESIGNER

BEARINGS

JT	FACTORED GROSS REACTION	MAXIMUM FACTORED GROSS REACTION	INPUT BRG	REQD BRG	HEEL WEDGE
	VERT	DOWN	UP	IN-SX	
C	86	0	0	1-8	
B	254	0	0	5-8	2x4 L
D	45	0	0	1-8	

SEE MITTEK STANDARD DETAIL B97791H FOR CONNECTION TO JOINT(S) C, D

UNFACTORED REACTIONS

JT	1ST LCASE	MAX/MIN. COMPONENT REACTIONS	SNOW	LIVE	PERM. LIVE	WIND	DEAD	SOIL
	COMBINED							
C	60	45 / 0	0 / 0	0 / 0	0 / 0	15 / 0	0 / 0	0 / 0
B	177	129 / 0	0 / 0	0 / 0	0 / 0	48 / 0	0 / 0	0 / 0
D	33	16 / 0	0 / 0	0 / 0	0 / 0	17 / 0	0 / 0	0 / 0

BEARING MATERIAL TO BE SPF NO.2 OR BETTER AT JOINT(S) B, D

BRACING

TOP CHORD TO BE SHEATHED OR MAX. PURLIN SPACING = 6.25 FT.
MAX. UNBRACED BOTTOM CHORD LENGTH = 10.00 FT OR RIGID CEILING DIRECTLY APPLIED.

ALL PITCH BREAKS AND PERIMETER CORNER JOINTS MUST BE Laterally RESTRAINED.

LOADING

TOTAL LOAD CASES: (5)

FR-TO	CHORDS				WEBS			
	MEMB.	FORCE (LBS)	FACTORED VERT. LOAD (PLF)	MAX. CSI (LC)	MEMB.	FORCE (LBS)	FACTORED MAX. CSI (LC)	
A-B	0	16	-91.8	-91.8 0.12 (5)	10.00	E-F	-60	2 0.00 (1)
B-F	-14	0	-91.8	-91.8 0.04 (1)	6.25			
F-C	0	7	-91.8	-91.8 0.06 (1)	10.00			
B-E	0	0	-18.5	-18.5 0.06 (1)	10.00			
E-D	0	0	-18.5	-18.5 0.06 (1)	10.00			

CANTILEVER ANALYSIS HAS BEEN CONSIDERED IN THIS DESIGN

DESIGN CRITERIA

SPECIFIED LOADS:

TOP CH.	LL = 25.6 PSF
	DL = 6.0 PSF
BOT CH.	LL = 0.0 PSF
	DL = 7.4 PSF
TOTAL LOAD	= 39.0 PSF

SPACING = 24.0 IN. C/C

THIS TRUSS IS DESIGNED FOR RESIDENTIAL OR SMALL BUILDING REQUIREMENTS OF PART 9, NBC 2015

THIS DESIGN COMPLIES WITH:

- PART 9 OF BCBC 2018, ABC 2019
- PART 9 OF OBC 2012 (2019 AMENDMENT)
- CSA 086-14
- TPIC 2014

(55 % OF 31.3 P.S.F. G.S.L. PLUS 8.4 P.S.F. RAIN LOAD) EQUALS 25.6 P.S.F. SPECIFIED ROOF LIVE LOAD

ALLOWABLE DEFL.(LL) = L/360 (0.19")
CALCULATED VERT. DEFL.(LL) = L/999 (0.00")
ALLOWABLE DEFL.(TL) = L/360 (0.19")
CALCULATED VERT. DEFL.(TL) = L/999 (0.00")

CSI: TC=0.12/1.00 (A-B:5), BC=0.06/1.00 (B-E:1), WB=0.00/1.00 (E-F:1), SSI=0.10/1.00 (A-B:5)

DOL LUMBER=1.00 NAIL=1.00 LS BEND=1.10
COMP=1.10 SHEAR=1.10 TENS=1.10

COMPANION LIVE LOAD FACTOR = 1.00

TRUSS PLATE MANUFACTURER IS NOT RESPONSIBLE FOR QUALITY CONTROL IN THE TRUSS MANUFACTURING PLANT.


NAIL VALUES

PLATE	GRIP(DRY)	SHEAR	SECTION
(PSI)	(PLI)	(PLI)	
MAX	MIN	MAX	MIN
MT20	650	371	1747 788 1987 1873

PLATE PLACEMENT TOL. = 0.250 inches

PLATE ROTATION TOL. = 5.0 Deg.

JSI GRIP= 0.08 (B) (INPUT = 0.90)
JSI METAL= 0.02 (B) (INPUT = 1.00)



Structural component only
DWG# T-2018273

DRWG NO.	
----------	--


TRUSS DESC.

Scale = 1:10.8



Structural component only
DWG# T-2018274

JOB NAME	TRUSS NAME	QUANTITY	PLY	JOB DESC.	DRWG NO.
410172	J20	4	1	GREEN PARK HOMES	
Tamarack Roof Truss, Burlington					



Version 8.330 S May 6 2020 Mitek Industries, Inc. Thu Jul 30 08:32:15 2020 Page 1
ID:W63xGm6okcO0SiyZ4EwBx6zA2m0-H4977KG14nHHvDiP6OuaWYsmjLOVhVRl6qw1ciysxok

Scale = 1:29.2

LUMBER

N. L. G. A. RULES

CHORDS	SIZE	LUMBER
F - B	2x4	DRY No.2
A - C	2x4	DRY No.2
F - D	2x4	DRY No.2

ALL WEBS 2x3 DRY No.2
DRY: SEASONED LUMBER.

PLATES (table is in inches)

JT	TYPE	PLATES	W	LEN	Y	X
B	TMVW+p	MT20	4.0	6.0	Edge	
E	BMV+w	MT20	2.0	4.0		
F	BMV1+p	MT20	3.0	4.0		

Edge - INDICATES REFERENCE CORNER OF PLATE TOUCHES EDGE OF CHORD.

DIMENSIONS, SUPPORTS AND LOADINGS SPECIFIED BY FABRICATOR TO BE VERIFIED BY BUILDING DESIGNER

BEARINGS

JT	FACTORED GROSS REACTION		MAXIMUM FACTORED GROSS REACTION		INPUT BRG	REQD BRG
	VERT	HORZ	DOWN	HORZ		
F	341	0	341	0	5-8	5-8
C	178	0	178	0	1-8	1-8
D	36	0	40	0	1-8	1-8

SEE MITEK STANDARD DETAIL B97791H FOR CONNECTION TO JOINT(S) C, D

UNFACTORED REACTIONS

JT	1ST LCASE	MAX./MIN. COMPONENT REACTIONS				WIND	DEAD	SOIL
		COMBINED	SNOW	LIVE	PERM.LIVE			
F	239	170 / 0	0 / 0	0 / 0	0 / 0	69 / 0	0 / 0	0 / 0
C	122	99 / 0	0 / 0	0 / 0	0 / 0	23 / 0	0 / 0	0 / 0
D	29	0 / 0	0 / 0	0 / 0	0 / 0	29 / 0	0 / 0	0 / 0

BEARING MATERIAL TO BE SPF NO.2 OR BETTER AT JOINT(S) F

BRACING

TOP CHORD TO BE SHEATHED OR MAX. PURLIN SPACING = 10.00 FT.
MAX. UNBRACED BOTTOM CHORD LENGTH = 10.00 FT OR RIGID CEILING DIRECTLY APPLIED.

ALL PITCH BREAKS AND PERIMETER CORNER JOINTS MUST BE Laterally RESTRAINED.

LOADING

TOTAL LOAD CASES: (5)

CHORDS					WEBS				
MEMB.	MAX. FACTORED FORCE (LBS)	FACTORED VERT. LOAD (PLF)	LC1	MAX. CSI (LC)	MAX. UNBRAC LENGTH	MEMB.	MAX. FACTORED FORCE (LBS)	MAX. CSI (LC)	
FR-TO		FROM	TO		FR-TO				
F-B	-305 / 0	0.0	0.0	0.03 (1)	7.81	B-E	0 / 0	0.00 (1)	
A-B	0 / 43	-91.8	-91.8	0.14 (5)	10.00				
B-C	0 / 0	-91.8	-91.8	0.23 (1)	10.00				
F-E	0 / 0	-18.5	-18.5	0.08 (4)	10.00				
E-D	0 / 0	-18.5	-18.5	0.08 (4)	10.00				

CANTILEVER ANALYSIS HAS BEEN CONSIDERED IN THIS DESIGN

TOTAL WEIGHT = 4 X 16 = 64 lb [M]

DESIGN CRITERIA

SPECIFIED LOADS:

TOP CH.	LL = 25.6	PSF
	DL = 6.0	PSF
BOT CH.	LL = 0.0	PSF
	DL = 7.4	PSF
TOTAL LOAD	= 39.0	PSF

SPACING = 24.0 IN. C/C

THIS TRUSS IS DESIGNED FOR RESIDENTIAL OR SMALL BUILDING REQUIREMENTS OF PART 9, NBCC 2015

THIS DESIGN COMPLIES WITH:

- PART 9 OF BCBC 2018, ABC 2019
- PART 9 OF OBC 2012 (2019 AMENDMENT)
- CSA 088-14
- TPIC 2014

(55 % OF 31.3 P.S.F. G.S.L. PLUS 8.4 P.S.F. RAIN LOAD) EQUALS 25.6 P.S.F. SPECIFIED ROOF LIVE LOAD

ALLOWABLE DEFL.(LL) = $L/360$ (0.19")
CALCULATED VERT. DEFL.(LL) = $L/999$ (0.00")
ALLOWABLE DEFL.(TL) = $L/360$ (0.19")
CALCULATED VERT. DEFL.(TL) = $L/999$ (0.01")

CSI: TC=0.23/1.00 (B-C:1), BC=0.08/1.00 (E-F:4), WB=0.00/1.00 (B-E:1), SSI=0.10/1.00 (B-C:1)

DOL LUMBER=1.00 NAIL=1.00 LS BEND=1.10
COMP=1.10 SHEAR=1.10 TENS=1.10

COMPANION LIVE LOAD FACTOR = 1.00

AUTOSOLVE RIGHT HEEL ONLY

TRUSS PLATE MANUFACTURER IS NOT RESPONSIBLE FOR QUALITY CONTROL IN THE TRUSS MANUFACTURING PLANT

NAIL VALUES

PLATE	GRIP(DRY)	SHEAR	SECTION
(PSI)	(PLI)	(PLI)	(PLI)
MAX	MIN	MAX	MIN
MT20	650	371	1747
		788	1987

PLATE PLACEMENT TOL. = 0.250 inches

PLATE ROTATION TOL. = 5.0 Deg.

JSI GRIP= 0.21 (B) (INPUT = 0.90)
JSI METAL= 0.08 (B) (INPUT = 1.00)



Structural component only
DWG# T-2016970


JOB NAME 410172	TRUSS NAME J22	QUANTITY 4	PLY 1	JOB DESC. GREEN PARK HOMES	TRUSS DESC.	DRWG NO.
--------------------	-------------------	---------------	----------	-------------------------------	-------------	----------

Tamarack Roof Truss, Burlington

ID:W63xGm6okc00SiyZ4EwBx6zA2m0-IGjNKgHgr5P8WNHbg5Pp3IPy0IJyhuLUga88ysxoi

Version 8.330 S May 6 2020 MTEK Industries, Inc. Thu Jul 30 08:32:16 2020 Page 1

Scale = 1:24.8



LUMBER

N. L. G. A. RULES	CHORDS	SIZE	LUMBER	DESCR.
F - B	2x4	DRY	No.2	SPF
A - C	2x4	DRY	No.2	SPF
F - D	2x4	DRY	No.2	SPF
ALL WEBS	2x3	DRY	No.2	SPF
DRY: SEASONED LUMBER.				

PLATES (table is in inches)

JT	TYPE	PLATES	W	LEN	Y	X
B	TMVW+p	MT20	4.0	6.0	Edge	
E	BMW+w	MT20	2.0	4.0		
F	BMV1+p	MT20	3.0	4.0		

Edge - INDICATES REFERENCE CORNER OF PLATE TOUCHES EDGE OF CHORD.

DIMENSIONS, SUPPORTS AND LOADINGS SPECIFIED BY FABRICATOR TO BE VERIFIED BY BUILDING DESIGNER

BEARINGS	FACTORED GROSS REACTION	FACTORED GROSS REACTION	INPUT BRG	REQD BRG
JT	VERT	HORZ	DOWN	HORZ
F	286	0	286	0
C	132	0	132	0
D	27	0	30	0

SEE MITEK STANDARD DETAIL B97791H FOR CONNECTION TO JOINT(S) C, D

UNFACTORED REACTIONS

1ST LCASE	MAX. MIN. COMPONENT REACTIONS	SNOW	LIVE	PERM. LIVE	WIND	DEAD	SOIL
JT	COMBINED						
F	200	145 / 0	0 / 0	0 / 0	0 / 0	55 / 0	0 / 0
C	91	74 / 0	0 / 0	0 / 0	0 / 0	17 / 0	0 / 0
D	21	0 / 0	0 / 0	0 / 0	0 / 0	21 / 0	0 / 0

BEARING MATERIAL TO BE SPF NO.2 OR BETTER AT JOINT(S) F

BRACING

TOP CHORD TO BE SHEATHED OR MAX. PURLIN SPACING = 10.00 FT.
MAX. UNBRACED BOTTOM CHORD LENGTH = 10.00 FT OR RIGID CEILING DIRECTLY APPLIED.

ALL PITCH BREAKS AND PERIMETER CORNER JOINTS MUST BE Laterally RESTRAINED.

LOADING

TOTAL LOAD CASES: (5)

CHORDS	MAX. FACTORED FORCE (LBS)	FACTORED VERT. LOAD (PLF)	FACTORED LC1 MAX CS1 (LC)	MAX. UNBRAC LENGTH	WEBS	MAX. FACTORED FORCE (LBS)	MAX. CS1 (LC)
MEMB.					MEMB.		
FR-TO		FROM	TO		FR-TO		
F-B	-259 / 0	0.0	0.0	0.03 (1)	7.81	B-E	0 / 0
A-B	0 / 43	-91.8	-91.8	0.14 (5)	10.00		
B-C	0 / 0	-91.8	-91.8	0.13 (1)	10.00		
F-E	0 / 0	-18.5	-18.5	0.04 (4)	10.00		
E-D	0 / 0	-18.5	-18.5	0.04 (4)	10.00		

CANTILEVER ANALYSIS HAS BEEN CONSIDERED IN THIS DESIGN

TOTAL WEIGHT = 4 X 13 = 54 lb

DESIGN CRITERIA

SPECIFIED LOADS:

TOP CH.	LL	=	25.6	PSF
	DL	=	6.0	PSF
BOT CH.	LL	=	0.0	PSF
	DL	=	7.4	PSF
TOTAL LOAD		=	39.0	PSF

SPACING = 24.0 IN. C/C

THIS TRUSS IS DESIGNED FOR RESIDENTIAL OR SMALL BUILDING REQUIREMENTS OF PART 9, NBCC 2015

THIS DESIGN COMPLIES WITH:

- PART 9 OF BCBC 2018, ABC 2019
- PART 9 OF OBC 2012 (2019 AMENDMENT)
- CSA 086-14
- TPIC 2014

(55 % OF 31.3 P.S.F. G.S.L. PLUS 8.4 P.S.F. RAIN LOAD) EQUALS 25.6 P.S.F. SPECIFIED ROOF LIVE LOAD

ALLOWABLE DEFL.(LL)= L/360 (0.19")
CALCULATED VERT. DEFL.(LL) = L/999 (0.00")
ALLOWABLE DEFL.(TL)= L/360 (0.19")
CALCULATED VERT. DEFL.(TL) = L/999 (0.00")

CS1: TC=0.14/1.00 (A-B-5), BC=0.04/1.00 (E-F-4), WB=0.00/1.00 (B-E-1), SS=0.08/1.00 (A-B-5)

DOL LUMBER=1.00 NAIL=1.00 LS BEND=1.10
COMP=1.10 SHEAR=1.10 TENS=1.10

COMPANION LIVE LOAD FACTOR = 1.00

AUTOSOLVE RIGHT HEEL ONLY

TRUSS PLATE MANUFACTURER IS NOT RESPONSIBLE FOR QUALITY CONTROL IN THE TRUSS MANUFACTURING PLANT

NAIL VALUES

PLATE	GRIP (DRY) (PSI)	SHEAR (PLI)	SECTION (PLI)
	MAX	MIN	MAX
MT20	650	371	1747

PLATE PLACEMENT TOL. = 0.250 inches

PLATE ROTATION TOL. = 5.0 Deg.

JSI GRIP= 0.18 (B) (INPUT = 0.90)


JSI METAL= 0.07 (B) (INPUT = 1.00)



Structural component only
DWG# T-2016971

JOB NAME 410172	TRUSS NAME J23	QUANTITY 8	PLY 1	JOB DESC. GREEN PARK HOMES	DRWG NO.
Tamarack Roof Truss, Burlington				TRUSS DESC.	

Version 8.330 S May 6 2020 MiTek Industries, Inc. Thu Jul 30 08:32:17 2020 Page 1
ID:W63xGm6kC00SiyZ4EwBx6zA2m0-DTHIY0IicPX?8XsnEpw2bzy2m90G9Px2a8P8gbysxoi



LUMBER
N. L. G. A. RULES
CHORDS SIZE LUMBER
A - C 2x4 DRY No.2
B - D 2x4 DRY No.2

DRY: SEASONED LUMBER.

PLATES (table is in inches)

JT	TYPE	PLATES	W	LEN	Y	X
B	TMB1-I	MT20	3.0	4.0		

DIMENSIONS, SUPPORTS AND LOADINGS SPECIFIED BY FABRICATOR TO BE VERIFIED BY BUILDING DESIGNER

BEARINGS

JT	FACTORED GROSS REACTION		MAXIMUM FACTORED GROSS REACTION		INPUT BRG IN-SX	REQD BRG IN-SX
	VERT	HORZ	DOWN	HORZ		
C	249	0	249	0	4-8	4-8
B	465	0	465	0	5-8	5-8
D	93	0	93	0	5-8	5-8

BEVELED PLATE OR SHIM REQUIRED TO PROVIDE FULL BEARING SURFACE WITH TRUSS CHORD AT JT(S): C

UNFACTORED REACTIONS

JT	1ST LCASE COMBINED	MAX./MIN. COMPONENT REACTIONS					
		SNOW	LIVE	PERM. LIVE	WIND	DEAD	SOIL
C	173	134 / 0	0 / 0	0 / 0	0 / 0	38 / 0	0 / 0
B	327	227 / 0	0 / 0	0 / 0	0 / 0	99 / 0	0 / 0
D	70	25 / 0	0 / 0	0 / 0	0 / 0	45 / 0	0 / 0

BEARING MATERIAL TO BE SPF NO.2 OR BETTER AT JOINT(S) C, B, D

BRACING
TOP CHORD TO BE SHEATHED OR MAX. PURLIN SPACING = 6.25 FT.
MAX. UNBRACED BOTTOM CHORD LENGTH = 10.00 FT OR RIGID CEILING DIRECTLY APPLIED.

ALL PITCH BREAKS AND PERIMETER CORNER JOINTS MUST BE Laterally RESTRAINED.

LOADING
TOTAL LOAD CASES: (4)

MEMB.	CHORDS			WEBS		
	MAX. FACTORED FORCE (LBS)	FACTORED VERT. LOAD (PLF)	MAX. FACTORED CSI (LC)	MAX. FACTORED FORCE (LBS)	MAX. FACTORED CSI (LC)	MAX. FACTORED CSI (LC)
FR-TO		FROM TO		FR-TO		
A-B	0 / 18	-91.8 -91.8	0.11 (1)	10.00	E-F	-363 / 14
B-F	-21 / 25	-91.8 -91.8	0.06 (1)	6.25		
F-C	-2 / 2	-91.8 -91.8	0.46 (1)	10.00		
B-E	0 / 0	-18.5 -18.5	0.31 (1)	10.00		
E-D	0 / 0	-18.5 -18.5	0.32 (1)	10.00		

DESIGN CRITERIA

SPECIFIED LOADS:
TOP CH. LL = 25.6 PSF
DL = 6.0 PSF
BOT CH. LL = 0.0 PSF
DL = 7.4 PSF
TOTAL LOAD = 39.0 PSF

SPACING = 24.0 IN. C/C

THIS TRUSS IS DESIGNED FOR RESIDENTIAL OR SMALL BUILDING REQUIREMENTS OF PART 9, NBCC 2015

THIS DESIGN COMPLIES WITH:
- PART 9 OF BCBC 2018, ABC 2019
- PART 9 OF OBC 2012 (2019 AMENDMENT)
- CSA 086-14
- TPIC 2014

(55 % OF 31.3 P.S.F. G.S.L. PLUS 8.4 P.S.F. RAIN LOAD) EQUALS 25.6 P.S.F. SPECIFIED ROOF LIVE LOAD

ALLOWABLE DEFL.(LL)= L/360 (0.21")
CALCULATED VERT. DEFL.(LL) = L/ 857 (0.09")
ALLOWABLE DEFL.(TL)= L/360 (0.21")
CALCULATED VERT. DEFL.(TL) = L/ 418 (0.18")

CSI: TC=0.46/1.00 (C-F:1) , BC=0.32/1.00 (D-E:1) , WB=0.00/1.00 (E-F:1) , SSI=0.30/1.00 (B-E:1)

DOL LUMBER=1.00 LAIL=1.00 LS BEND=1.10
COMP=1.10 SHEAR=1.10 TENS=1.10

COMPANION LIVE LOAD FACTOR = 1.00

TRUSS PLATE MANUFACTURER IS NOT RESPONSIBLE FOR QUALITY CONTROL IN THE TRUSS MANUFACTURING PLANT .

NAIL VALUES
PLATE GRIP(DRY) SHEAR SECTION (PSI) (PLI) (PLI)
MAX MIN MAX MIN MAX MIN
MT20 650 371 1747 788 1987 1873

PLATE PLACEMENT TOL. = 0.250 inches

PLATE ROTATION TOL. = 5.0 Deg.


JSI GRIP= 0.31 (B) (INPUT = 0.90)
JSI METAL= 0.08 (B) (INPUT = 1.00)



Structural component only
DWG# T-2016972

JOB NAME 410172	TRUSS NAME J24	QUANTITY 8	PLY 1	JOB DESC. GREEN PARK HOMES	DRWG NO.
Tamarack Roof Truss, Burlington				Version 8.330 S May 6 2020 Mitek Industries, Inc. Thu Jul 30 08:32:18 2020 Page 1	

ID: W63xGm6okc00SiyZ4EwBx6zA2m0-hfr7IMlwNfsmhR_nWRH8AUFHZNqusBBpo9hC1ysxoh



LUMBER
N. L. G. A. RULES
CHORDS SIZE LUMBER DESCR.
A - C 2x4 DRY No.2
B - D 2x4 DRY No.2
SPF
SPF

DRY: SEASONED LUMBER.

PLATES (table is in inches)
JT TYPE PLATES W LEN Y X
B TMB1-I MT20 3.0 4.0

DIMENSIONS, SUPPORTS AND LOADINGS SPECIFIED BY FABRICATOR TO BE VERIFIED BY BUILDING DESIGNER

JT	FACTORED GROSS REACTION		FACTORED GROSS REACTION		INPUT BRG		REQD BRG	
	VERT	HORZ	DOWN	HORZ	IN-SX	IN-SX	IN-SX	IN-SX
C	215	0	215	0	1-8	1-8	1-8	1-8
B	419	0	419	0	5-8	5-8	5-8	5-8
D	81	0	81	0	5-8	5-8	5-8	5-8

SEE MITEK STANDARD DETAIL B97791H FOR CONNECTION TO JOINT(S) C

UNFACTORED REACTIONS

JT	1ST LCASE COMBINED	MAX / MIN. COMPONENT REACTIONS		PERM. LIVE	WIND	DEAD	SOIL
		SNOW	LIVE				
C	149	116 / 0	0 / 0	0 / 0	0 / 0	33 / 0	0 / 0
B	294	206 / 0	0 / 0	0 / 0	0 / 0	88 / 0	0 / 0
D	61	22 / 0	0 / 0	0 / 0	0 / 0	39 / 0	0 / 0

BEARING MATERIAL TO BE SPF NO.2 OR BETTER AT JOINT(S) B, D

BRACING

TOP CHORD TO BE SHEATHED OR MAX. PURLIN SPACING = 6.25 FT
MAX. UNBRACED BOTTOM CHORD LENGTH = 10.00 FT OR RIGID CEILING DIRECTLY APPLIED.

ALL PITCH BREAKS AND PERIMETER CORNER JOINTS MUST BE LATERALLY RESTRAINED.

LOADING

TOTAL LOAD CASES: (4)

MEMB.	CHORDS MAX. FACTORED FORCE (LBS)		FACTORED VERT. LOAD LC1 MAX (PLF)		MAX. UNBRACED LENGTH FR-TO		WEBS MAX. FACTORED FORCE (LBS)	
	FR-TO	FROM TO	FR-TO	FROM TO	FR-TO	FROM TO	FR-TO	FROM TO
A-B	0 / 18	-91.8	-91.8	0.11 (1)	10.00	E-F	-280 / 11	0.00 (1)
B-F	-18 / 10	-91.8	-91.8	0.06 (4)	6.25			
F-C	-1 / 2	-91.8	-91.8	0.34 (1)	10.00			
B-E	0 / 0	-18.5	-18.5	0.24 (1)	10.00			
E-D	0 / 0	-18.5	-18.5	0.24 (1)	10.00			

TOTAL WEIGHT = 8 X 14 = 114 lb

DESIGN CRITERIA

SPECIFIED LOADS:
TOP CH. LL = 25.6 PSF
DL = 6.0 PSF
BOT CH. LL = 0.0 PSF
DL = 7.4 PSF
TOTAL LOAD = 39.0 PSF

SPACING = 24.0 IN./C

THIS TRUSS IS DESIGNED FOR RESIDENTIAL OR SMALL BUILDING REQUIREMENTS OF PART 9, NBCC 2015

THIS DESIGN COMPLIES WITH:
- PART 9 OF CBC 2018, ABC 2019
- PART 9 OF OBC 2012 (2019 AMENDMENT)
- CSA 086-14
- TPIC 2014

(55 % OF 31.3 P.S.F. G.S.L. PLUS 8.4 P.S.F. RAIN LOAD) EQUALS 25.6 P.S.F. SPECIFIED ROOF LIVE LOAD

ALLOWABLE DEFL.(LL) = L/360 (0.19")
CALCULATED VERT. DEFL.(LL) = L/999 (0.05")
ALLOWABLE DEFL.(TL) = L/360 (0.19")
CALCULATED VERT. DEFL.(TL) = L/634 (0.10")

CSI: TC=0.34/1.00 (C-F:1), BC=0.24/1.00 (D-E:1), WB=0.00/1.00 (E-F:1), SSI=0.23/1.00 (B-E:1)

DOL LUMBER=1.00 NAIL=1.00 LS BEND=1.10
COMP=1.10 SHEAR=1.10 TENS=1.10

COMPANION LIVE LOAD FACTOR = 1.00

TRUSS PLATE MANUFACTURER IS NOT RESPONSIBLE FOR QUALITY CONTROL IN THE TRUSS MANUFACTURING PLANT.

NAIL VALUES

PLATE	GRIP(DRY)	SHEAR (PSI)	SECTION (PLI)
MT20	650	371	1747
	788	1987	1873

PLATE PLACEMENT TOL. = 0.250 inches

PLATE ROTATION TOL. = 5.0 Deg.

JSI GRIP = 0.27 (B) (INPUT = 0.90)
JSI METAL = 0.07 (B) (INPUT = 1.00)




Structural component only
DWG# T-2016973

JOB NAME 410174	TRUSS NAME J30	QUANTITY 8	PLY 1	JOB DESC. GREEN PARK HOMES	TRUSS DESC.	DRWG NO.
--------------------	-------------------	---------------	----------	-------------------------------	-------------	----------

Tamarack Roof Truss, Burlington

Version 8.330 S May 6 2020 Mitek Industries, Inc. Thu Jul 30 08:42:24 2020 Page 1
ID:W63xGm6okc00SiyZ4EwBx6zA2m0-yETDxae2fv?TpmSHnJOizbr2rFLtwCO94ykUvysxfD

Scale = 1:18.1



LUMBER

N. L. G. A. RULES	CHORDS	SIZE	LUMBER	DESCR.
E - B	2x4	DRY	No.2	SPF
A - C	2x4	DRY	No.2	SPF
E - D	2x4	DRY	No.2	SPF

DRY: SEASONED LUMBER.

PLATES (table is in inches)

JT	TYPE	PLATES	W	LEN	Y	X
B	TMV+p	MT20	3.0	4.0		
E	BMV1+p	MT20	3.0	4.0		

DIMENSIONS, SUPPORTS AND LOADINGS SPECIFIED BY FABRICATOR TO BE VERIFIED BY BUILDING DESIGNER

BEARINGS

JT	FACTORED GROSS REACTION	MAXIMUM FACTORED GROSS REACTION	INPUT BRG	REQD BRG
E	388	388	5-8	5-8
C	133	133	1-8	1-8
D	30	34	1-8	1-8

SEE MITEK STANDARD DETAIL B97791H FOR CONNECTION TO JOINT(S) C, D

UNFACTORED REACTIONS

JT	1ST LCASE	MAX/MIN. COMPONENT REACTIONS	SNOW	LIVE	PERM. LIVE	WIND	DEAD	SOIL
E	272	193 / 0	0 / 0	0 / 0	0 / 0	78 / 0	0 / 0	0 / 0
C	92	74 / 0	0 / 0	0 / 0	0 / 0	17 / 0	0 / 0	0 / 0
D	24	0 / 0	0 / 0	0 / 0	0 / 0	24 / 0	0 / 0	0 / 0

BEARING MATERIAL TO BE SPF NO.2 OR BETTER AT JOINT(S) E

BRACING

TOP CHORD TO BE SHEATHED OR MAX. PURLIN SPACING = 6.25 FT.
MAX. UNBRACED BOTTOM CHORD LENGTH = 10.00 FT OR RIGID CEILING DIRECTLY APPLIED.

ALL PITCH BREAKS AND PERIMETER CORNER JOINTS MUST BE Laterally RESTRAINED.

LOADING

TOTAL LOAD CASES: (5)

CHORDS	MAX. FACTORED	FACTORED	W E B S	MAX. FACTORED
MEMB.	FORCE (LBS)	VERT. LOAD LC1 (PLF)	MAX. UNBRACED LENGTH FR-TO	MEMB. FORCE (LBS)
FR-TO		FROM TO		
E-B	-347 / 0	0.0	0.0 0.05 (4)	7.81
A-B	0 / 28	-91.8	-91.8 0.14 (5)	10.00
B-C	-20 / 0	-91.8	-91.8 0.23 (1)	6.25
E-D	0 / 0	-18.5	-18.5 0.06 (4)	10.00

CANTILEVER ANALYSIS HAS BEEN CONSIDERED IN THIS DESIGN

TOTAL WEIGHT = 8 X 12 = 96 lb

DESIGN CRITERIA

SPECIFIED LOADS:

TOP CH.	LL	= 25.6	PSF
	DL	= 6.0	PSF
BOT CH.	LL	= 0.0	PSF
	DL	= 7.4	PSF
TOTAL LOAD		= 39.0	PSF

SPACING = 24.0 IN. C/C

THIS TRUSS IS DESIGNED FOR RESIDENTIAL OR SMALL BUILDING REQUIREMENTS OF PART 9, NBCC 2015

THIS DESIGN COMPLIES WITH:

- PART 9 OF BCBC 2018, ABC 2019
- PART 9 OF OBC 2012 (2019 AMENDMENT)
- CSA 086-14
- TPIC 2014

DESIGN ASSUMPTIONS

- OVERHANG NOT TO BE ALTERED OR CUT OFF.

(55 % OF 31.3 P.S.F. G.S.L. PLUS 8.4 P.S.F. RAIN LOAD) EQUALS 25.6 P.S.F. SPECIFIED ROOF LIVE LOAD

ALLOWABLE DEFL.(LL) = $L/360$ (0.19")
CALCULATED VERT. DEFL.(LL) = $L/999$ (0.00")
ALLOWABLE DEFL.(TL) = $L/360$ (0.19")
CALCULATED VERT. DEFL.(TL) = $L/999$ (0.01")

CSI: $TC=0.23/1.00$ (B-C:1), $BC=0.06/1.00$ (D-E:4),
 $WB=0.00/1.00$ (n/a:0), $SSI=0.16/1.00$ (B-C:1)

DOL LUMBER=1.00 NAIL=1.00 LS BEND=1.10
COMP=1.10 SHEAR=1.10 TENS=1.10

COMPANION LIVE LOAD FACTOR = 1.00

AUTOSOLVE RIGHT HEEL ONLY

TRUSS PLATE MANUFACTURER IS NOT RESPONSIBLE FOR QUALITY CONTROL IN THE TRUSS MANUFACTURING PLANT.

NAIL VALUES

PLATE	GRIP(DRY)	SHEAR	SECTION
(PSI)	(PLI)	(PLI)	
MAX	MIN	MAX	MIN
MT20	650	371	1747 788 1987 1873

PLATE PLACEMENT TOL. = 0.250 inches

PLATE ROTATION TOL. = 5.0 Deg.

JSI GRIP = 0.14 (E) (INPUT = 0.90)
JSI METAL = 0.10 (B) (INPUT = 1.00)




Structural component only
DWG# T-2016984

JOB NAME	TRUSS NAME	QUANTITY	PLY	JOB DESC.	GREEN PARK HOMES	DRWG NO.
410174	J32	1	1	TRUSS DESC.		

Tamarack Roof Truss, Burlington

Version 8.330 S May 6 2020 Mitek Industries, Inc. Thu Jul 30 08:42:26 2020 Page 1
ID:W63xGm6okcOOSiyZ4EwBx6zA2m0-uda_MF7IBWGb7vqPCLsnOgDJexRLqihcORrZoysxIB

Scale = 1:14.5



LUMBER

N. L. G. A. RULES	CHORDS	SIZE	LUMBER	DESCR.
E - B	2x4	DRY	No.2	SPF
A - C	2x4	DRY	No.2	SPF
E - D	2x4	DRY	No.2	SPF

DRY: SEASONED LUMBER.

PLATES (table is in inches)

JT	TYPE	PLATES	W	LEN	Y	X
B	TMV+p	MT20	3.0	4.0		
E	BMV1+p	MT20	3.0	4.0		

DIMENSIONS, SUPPORTS AND LOADINGS SPECIFIED BY FABRICATOR TO BE VERIFIED BY BUILDING DESIGNER

BEARINGS

	FACTORED		MAXIMUM FACTORED			INPUT	REQRD
	GROSS REACTION		GROSS REACTION			BRG	BRG
JT	VERT	HORZ	DOWN	HORZ	UPLIFT	IN-SX	IN-SX
E	264	0	264	0	0	1-8	1-8
C	72	0	72	0	0	1-8	1-8
D	17	0	19	0	0	1-8	1-8

SEE MITEK STANDARD DETAIL B97791H FOR CONNECTION TO JOINT(S) C, D

UNFACTORED REACTIONS

1ST LCASE		MAX./MIN. COMPONENT REACTIONS					
JT	COMBINED	SNOW	LIVE	PERM.LIVE	WIND	DEAD	SOIL
E	184	135 / 0	0 / 0	0 / 0	0 / 0	49 / 0	0 / 0
C	49	40 / 0	0 / 0	0 / 0	0 / 0	9 / 0	0 / 0
D	14	0 / 0	0 / 0	0 / 0	0 / 0	14 / 0	0 / 0

BEARING MATERIAL TO BE SPF NO.2 OR BETTER AT JOINT(S) E

BRACING

TOP CHORD TO BE SHEATHED OR MAX. PURLIN SPACING = 6.25 FT.
MAX. UNBRACED BOTTOM CHORD LENGTH = 10.00 FT OR RIGID CEILING DIRECTLY APPLIED.

ALL PITCH BREAKS AND PERIMETER CORNER JOINTS MUST BE Laterally RESTRAINED.

LOADING

TOTAL LOAD CASES: (5)

CHORDS			WEBS		
MEMB.	MAX. FACTORED FORCE (LBS)	FACTORED VERT. LOAD (PLF)	LC1 MAX (LC)	MEMB.	MAX. FACTORED FORCE (LBS)
FR-TO		FROM TO	UNBRAC LENGTH	FR-TO	MAX CSI (LC)
E-B	-243 / 0	0.0 0.0	0.01 (4) 7.81		
A-B	0 / 28	-91.8 -91.8	0.12 (5) 10.00		
B-C	-10 / 0	-91.8 -91.8	0.07 (1) 6.25		
E-D	0 / 0	-18.5 -18.5	0.02 (4) 10.00		

CANTILEVER ANALYSIS HAS BEEN CONSIDERED IN THIS DESIGN

TOTAL WEIGHT = 8 lb

DESIGN CRITERIA

SPECIFIED LOADS:

TOP CH.	LL	=	25.6	PSF
	DL	=	6.0	PSF
BOT CH.	LL	=	0.0	PSF
	DL	=	7.4	PSF
TOTAL LOAD		=	39.0	PSF

SPACING = 24.0 IN. C/C

THIS TRUSS IS DESIGNED FOR RESIDENTIAL OR SMALL BUILDING REQUIREMENTS OF PART 9, NBCC 2015

THIS DESIGN COMPLIES WITH:

- PART 9 OF BCBC 2018, ABC 2019
- PART 9 OF OBC 2012 (2019 AMENDMENT)
- CSA 086-14
- TPIC 2014

DESIGN ASSUMPTIONS

- OVERHANG NOT TO BE ALTERED OR CUT OFF.

(55 % OF 31.3 P.S.F. G.S.L. PLUS 8.4 P.S.F. RAIN LOAD) EQUALS 25.6 P.S.F. SPECIFIED ROOF LIVE LOAD

ALLOWABLE DEFL.(LL) = L/360 (0.19")
CALCULATED VERT. DEFL.(LL) = L/999 (0.00")
ALLOWABLE DEFL.(TL) = L/360 (0.19")
CALCULATED VERT. DEFL.(TL) = L/999 (0.00")

CSI: TC=0.12/1.00 (A-B:5), BC=0.02/1.00 (D-E:4),
WB=0.00/1.00 (n/a:0), SSI=0.09/1.00 (A-B:5)

DOL LUMBER=1.00 NAIL=1.00 LS BEND=1.10
COMP=1.10 SHEAR=1.10 TENS=1.10

COMPANION LIVE LOAD FACTOR = 1.00

TRUSS PLATE MANUFACTURER IS NOT RESPONSIBLE FOR QUALITY CONTROL IN THE TRUSS MANUFACTURING PLANT.

NAIL VALUES

PLATE	GRIP(DRY)	SHEAR	SECTION
(PSI)	(PLI)	(PLI)	
MAX	MIN	MAX	MIN
MT20	650	371	1747 788 1987 1873

PLATE PLACEMENT TOL. = 0.250 inches


PLATE ROTATION TOL. = 5.0 Deg.

JSI GRIP= 0.10 (E) (INPUT = 0.90)
JSI METAL= 0.07 (B) (INPUT = 1.00)



Structural component only
DWG# T-2016986

JOB NAME	TRUSS NAME	QUANTITY	PLY	JOB DESC.	DRWG NO.
410169	C1	4	1	GREEN PARK HOMES	
Tamarack Roof Truss, Burlington					
Version 8.330 S May 6 2020 Mitek Industries, Inc. Fri Aug 14 14:44:51 2020 Page 1					
ID:W63xGm6okcO0SiyZ4EwBx6zA2m0-G7Ny8?1TOjEwOH71?3xcAAT6fP7jeADc?oedoynvxQ					
Scale = 1:8.2					



LUMBER				DESIGN CRITERIA	
N. L. G. A. RULES				SPECIFIED LOADS:	
CHORDS	SIZE	DRY	LUMBER	TOP CH. LL = 25.6 PSF	
A - C	2x4	DRY	No.2	DL = 6.0 PSF	
B - D	2x4	DRY	No.2	BOT CH. LL = 0.0 PSF	
DRY: SEASONED LUMBER.				DL = 7.4 PSF	
				TOTAL LOAD = 39.0 PSF	

PLATES (table is in inches)				SPACING = 24.0 IN. C/C	
JT TYPE	PLATES	W	LEN Y X	THIS TRUSS IS DESIGNED FOR RESIDENTIAL OR	
B	TMBH1-m	MT20	4.0 6.0 2.00 0.25	SMALL BUILDING REQUIREMENTS OF PART 9,	
				NBCC 2015	

FACTORED REACTIONS				DESIGN ASSUMPTIONS	
JT	VERT	HORZ	UP/LIFT	OVERHANG NOT TO BE ALTERED OR CUT OFF.	
C	61	0	3	(55 % OF 31.3 P.S.F. G.S.L. PLUS 8.4 P.S.F. RAIN	
B	269	0	5-8	LOAD) EQUALS 25.6 P.S.F. SPECIFIED ROOF	
D	5	0	1-8	LIVE LOAD	

UNFACTORED REACTIONS				ALLOWABLE DEFL.(LL)= L/360 (0.19")	
JT	1ST LCASE	MAX./MIN. COMPONENT REACTIONS		CALCULATED VERT. DEFL.(LL)= L/ 999 (0.00")	
C	44	26 / -12	0/0	ALLOWABLE DEFL.(TL)= L/360 (0.19")	
B	187	139 / 0	0/0	CALCULATED VERT. DEFL.(TL)= L/ 999 (0.00")	
D	5	0 / -15	0/0		

BEARING MATERIAL TO BE SPF NO.2 OR BETTER AT JOINT(S) C, B				CSI: TC=0.13/1.00 (A-B:5) , BC=0.03/1.00 (D-E:5) ,	
BRACING				WB=0.00/1.00 (E-F:1) , SSI=0.10/1.00 (A-B:5)	
TOP CHORD TO BE SHEATHED OR MAX. PURLIN SPACING = 6.25 FT.				DOL LUMBER=1.00 NAIL=1.00 LS BEND=1.10	
MAX. UNBRACED BOTTOM CHORD LENGTH = 10.00 FT. OR RIGID CEILING DIRECTLY APPLIED.				COMP=1.10 SHEAR=1.10 TENS= 1.10	

ALL PITCH BREAKS AND PERIMETER CORNER JOINTS MUST BE Laterally RESTRAINED.				COMPANION LIVE LOAD FACTOR = 1.00	
LOADING				TRUSS PLATE MANUFACTURER IS NOT	
TOTAL LOAD CASES: (9)				RESPONSIBLE FOR QUALITY CONTROL IN THE	
				TRUSS MANUFACTURING PLANT .	

CHORDS				WEBS	
MEMB.	MAX. FACTORED FORCE (LBS)	FACTORED VERT. LOAD (PLF)	MAX. FACTORED LC1 (LC)	MEMB.	MAX. FACTORED FORCE (LBS)
FR-TO		FROM TO	LENGTH FR-TO	E-F	
A-B	0 / 16	-91.8 -91.8	0.13 (5)	0.57	0.00 (1)
B-F	-47 / 0	-91.8 -91.8	0.12 (5)		
F-C	-4 / 4	-91.8 -91.8	0.02 (4)		
B-E	0 / 0	-18.5 -18.5	0.03 (5)		
E-G	0 / 0	-18.5 -18.5	0.03 (5)		
G-D	0 / 0	-18.5 -18.5	0.03 (5)		

FACTORED CONCENTRATED LOADS (LBS)				HEEL	
JT	LOC.	LC1	MAX- MAX+	FACE	CONN.
C	1-9-7	-11	-11	FRONT	C1
G	1-11-4	7	1	FRONT	C1

CONNECTION REQUIREMENTS				NAIL VALUES	
1) C1: A SUITABLE HANGER/MECHANICAL CONNECTION IS REQUIRED.				PLATE GRIP(DRY) SHEAR SECTION	
CANTILEVER ANALYSIS HAS BEEN CONSIDERED IN THIS DESIGN				(PSI) (PLI) (PLI)	
				MAX MIN MAX MIN MAX MIN	

				MT20 650 371 1747 788 1987 1873	
				PLATE PLACEMENT TOL. = 0.250 inches	
				PLATE ROTATION TOL. = 5.0 Deg.	
				JSI GRIP= 0.08 (B) (INPUT = 0.90)	

				JSI METAL= 0.02 (B) (INPUT = 1.00)	
--	--	--	--	--	--




Structural component only
DWG# T-2018269

JOB NAME	TRUSS NAME	QUANTITY	PLY	JOB DESC.	GREEN PARK HOMES	DRWG NO.
410169	C2	4	1	TRUSS DESC.		

Tamarack Roof Truss, Burlington

Version 8.330 S May 6 2020 MiTek Industries, Inc. Fri Aug 14 14:44:51 2020 Page 1
ID:W63xGm6okcO0SiyZ4EwBx6zA2m0-G7Ny8?1TOjEwOH7i?i3xcAATHfP5jeADc?oedoynvxQ

Scale = 1:8.2



LUMBER			
N. L. G. A. RULES	CHORDS	SIZE	LUMBER
A - C	2x4	DRY	No.2
B - D	2x4	DRY	No.2

DRY: SEASONED LUMBER.

PLATES (table is in inches)

JT	TYPE	PLATES	W	LEN	Y	X
B	TMBH1-m	MT20	4.0	6.0	2.00	0.25

DIMENSIONS, SUPPORTS AND LOADINGS SPECIFIED BY FABRICATOR TO BE VERIFIED BY BUILDING DESIGNER

FACTORED		MAXIMUM FACTORED		INPUT		REQ'D		HEEL
GROSS REACTION	VERT	GROSS REACTION	DOWN	UP	BRG	BRG	WEDGE	
JT	50	50	0	-2	1-8	1-8		
C	268	268	0	0	5-8	5-8		
B	4	12	0	-21	1-8	1-8	2x4 L	
D								

SEE MITTEK STANDARD DETAIL B97791H FOR CONNECTION TO JOINT(S) C, D

PROVIDE ANCHORAGE AT BEARING JOINT C FOR 150 LBS. FACTORED UPLIFT
PROVIDE ANCHORAGE AT BEARING JOINT D FOR 150 LBS. FACTORED UPLIFT

UNFACTORED REACTIONS

JT	1ST LCASE	MAX./MIN. COMPONENT REACTIONS					
		SNOW	LIVE	PERM.LIVE	WIND	DEAD	SOIL
C	35	25 / -7	0 / 0	0 / 0	0 / 0	10 / 0	0 / 0
B	187	140 / 0	0 / 0	0 / 0	0 / 0	47 / 0	0 / 0
D	4	0 / -18	0 / 0	0 / 0	0 / 0	9 / 0	0 / 0

BEARING MATERIAL TO BE SPF NO.2 OR BETTER AT JOINT(S) C, B

BRACING

TOP CHORD TO BE SHEATHED OR MAX. PURLIN SPACING = 6.25 FT.
MAX. UNBRACED BOTTOM CHORD LENGTH = 10.00 FT OR RIGID CEILING DIRECTLY APPLIED.

ALL PITCH BREAKS AND PERIMETER CORNER JOINTS MUST BE Laterally RESTRAINED.

LOADING

TOTAL LOAD CASES: (5)

CHORDS				WEBS			
MEMB.	FORCE (LBS)	VERT. LOAD (PLF)	MAX. CS (LC)	MEMB.	FORCE (LBS)	MAX. CS (LC)	
FR-TO		FROM	TO	FR-TO			
A-B	0 / 16	-91.8	-91.8 0.12 (1)	10.00	E-F	0 / 69	0.00 (1)
B-F	-47 / 0	-91.8	-91.8 0.11 (1)	6.25			
F-C	-2 / 3	-91.8	-91.8 0.02 (1)	10.00			
B-E	0 / 0	-18.5	-18.5 0.04 (5)	10.00			
E-D	0 / 0	-18.5	-18.5 0.04 (5)	10.00			

CANTILEVER ANALYSIS HAS BEEN CONSIDERED IN THIS DESIGN

TOTAL WEIGHT = 4 X 7 = 28 lb

DESIGN CRITERIA

SPECIFIED LOADS:	
TOP CH. LL	= 25.6 PSF
DL	= 6.0 PSF
BOT CH. LL	= 0.0 PSF
DL	= 7.4 PSF
TOTAL LOAD	= 39.0 PSF

SPACING = 24.0 IN. C/C

THIS TRUSS IS DESIGNED FOR RESIDENTIAL OR SMALL BUILDING REQUIREMENTS OF PART 9, NBCC 2015

THIS DESIGN COMPLIES WITH:

- PART 9 OF BCBC 2018, ABC 2019
- PART 9 OF OBC 2012 (2019 AMENDMENT)
- CSA 086-14
- TPIC 2014

DESIGN ASSUMPTIONS

- OVERHANG NOT TO BE ALTERED OR CUT OFF.

(55 % OF 31.3 P.S.F. G.S.L. PLUS 8.4 P.S.F. RAIN LOAD) EQUALS 25.6 P.S.F. SPECIFIED ROOF LIVE LOAD

ALLOWABLE DEFL.(LL)= L/360 (0.19")
CALCULATED VERT. DEFL.(LL) = L/999 (0.00")
ALLOWABLE DEFL.(TL)= L/360 (0.19")
CALCULATED VERT. DEFL.(TL) = L/999 (0.00")

CSI: TC=0.12/1.00 (A-B:1), BC=0.04/1.00 (B-E:5)
WB=0.00/1.00 (E-F:1), SSI=0.10/1.00 (B-F:1)

DOL LUMBER=1.00 NAIL=1.00 LS BEND=1.10
COMP=1.10 SHEAR=1.10 TENS=1.10

COMPANION LIVE LOAD FACTOR = 1.00

TRUSS PLATE MANUFACTURER IS NOT RESPONSIBLE FOR QUALITY CONTROL IN THE TRUSS MANUFACTURING PLANT.

NAIL VALUES

PLATE	GRIP(DRY)	SHEAR	SECTION
(PS)	(PL)	(PL)	
MAX MIN	MAX MIN	MAX MIN	
MT20	650 371	1747 788	1987 1873

PLATE PLACEMENT TOL. = 0.250 inches

PLATE ROTATION TOL. = 5.0 Deg.

JSI GRIP= 0.08 (B) (INPUT = 0.90)
JSI METAL= 0.02 (B) (INPUT = 1.00)




Structural component only
DWG# T-2018270

JOB NAME	TRUSS NAME	QUANTITY	PLY	JOB DESC.	DRWG NO.
410172	C20	2	1	GREEN PARK HOMES	
Tamarack Roof Truss, Burlington					

Version 8.330 S May 6 2020 MITek Industries, Inc. Thu Jul 30 08:32:11 2020 Page 1

ID:W63xGm6okcO0SiyZ4EwBx6zA2m0-OJwUHxDX0ZnsQcOetYpeMii58k0ZlhS9CCypTxyxoo

Scale = 1:19.5



LUMBER

N. L. G. A. RULES	CHORDS	SIZE	LUMBER
F - B	2x4	DRY	No.2
A - C	2x4	DRY	No.2
F - D	2x4	DRY	No.2
ALL WEBS	2x3	DRY	No.2
DRY: SEASONED LUMBER.			

PLATES (table is in inches)

JT	TYPE	PLATES	W	LEN	Y	X
B	TMVW+p	MT20	4.0	6.0	Edge	
E	BMW+w	MT20	2.0	4.0		
F	BMV1+p	MT20	3.0	4.0		

Edge - INDICATES REFERENCE CORNER OF PLATE TOUCHES EDGE OF CHORD.

DIMENSIONS, SUPPORTS AND LOADINGS SPECIFIED BY FABRICATOR TO BE VERIFIED BY BUILDING DESIGNER

BEARINGS	FACTORED GROSS REACTION	MAXIMUM FACTORED GROSS REACTION	INPUT BRG	REQD BRG
JT	VERT	HORZ	DOWN	HORZ
F	295	0	295	0
C	32	0	32	0
D	36	0	40	0

SEE MITEK STANDARD DETAIL B97791H FOR CONNECTION TO JOINT(S) C, D

PROVIDE ANCHORAGE AT BEARING JOINT C FOR 150 LBS FACTORED UPLIFT

UNFACTORED REACTIONS

JT	COMBINED	1ST LCASE	SNOW	LIVE	PERM.LIVE	WIND	DEAD	SOIL
F	207	145 / 0	0 / 0	0 / 0	0 / 0	63 / 0	0 / 0	0 / 0
C	22	18 / -28	0 / 0	0 / 0	0 / 0	4 / 0	0 / 0	0 / 0
D	29	0 / 0	0 / 0	0 / 0	0 / 0	29 / 0	0 / 0	0 / 0

BEARING MATERIAL TO BE SPF NO.2 OR BETTER AT JOINT(S) F, C

BRACING

TOP CHORD TO BE SHEATHED OR MAX. PURLIN SPACING = 6.25 FT.
MAX. UNBRACED BOTTOM CHORD LENGTH = 10.00 FT OR RIGID CEILING DIRECTLY APPLIED.

ALL PITCH BREAKS AND PERIMETER CORNER JOINTS MUST BE LATERALLY RESTRAINED.

LOADING

TOTAL LOAD CASES: (5)

MEMB.	CHORDS	MAX. FACTORED FORCE (LBS)	FACTORED VERT. LOAD (PLF)	MAX. LC1 MAX CSI (LC)	MAX. UNBRAC LENGTH	MEMB.	WEBS	MAX. FACTORED FORCE (LBS)	MAX. CSI (LC)
FR-TO						FR-TO			
F-B	-259 / 0	0.0	0.0	0.03 (1)	7.81	B-E	0 / 0	0.00 (1)	
A-B	0 / 43	-91.8	-91.8	0.14 (5)	10.00				
B-C	-34 / 0	-91.8	-91.8	0.14 (5)	6.25				
F-E	0 / 0	-18.5	-18.5	0.07 (4)	10.00				
E-G	0 / 0	-18.5	-18.5	0.08 (4)	10.00				
G-D	0 / 0	-18.5	-18.5	0.08 (4)	10.00				

FACTORED CONCENTRATED LOADS (LBS)

JT	LOC.	LC1	MAX	MAX+	FACE	DIR.	TYPE	HEEL	CONN.
G	1-11.4	1	1	---	BACK	VERT	TOTAL	---	C1

CONNECTION REQUIREMENTS

1) C1: A SUITABLE HANGER/MECHANICAL CONNECTION IS REQUIRED.

CANTILEVER ANALYSIS HAS BEEN CONSIDERED IN THIS DESIGN

TOTAL WEIGHT = 2 X 12 = 25 lb

DESIGN CRITERIA

SPECIFIED LOADS:

TOP CH. LL	=	25.6	PSF
DL	=	6.0	PSF
BOT CH. LL	=	0.0	PSF
DL	=	7.4	PSF
TOTAL LOAD	=	39.0	PSF

SPACING = 24.0 IN. C/C

THIS TRUSS IS DESIGNED FOR RESIDENTIAL OR SMALL BUILDING REQUIREMENTS OF PART 9, NBCC 2015

THIS DESIGN COMPLIES WITH:

- PART 9 OF BCBC 2018, ABC 2019
- PART 9 OF OBC 2012 (2019 AMENDMENT)
- CSA 086-14
- TPIC 2014

DESIGN ASSUMPTIONS

- OVERHANG NOT TO BE ALTERED OR CUT OFF.

(55 % OF 31.3 P.S.F. G.S.L. PLUS 8.4 P.S.F. RAIN LOAD) EQUALS 25.6 P.S.F. SPECIFIED ROOF LIVE LOAD

ALLOWABLE DEFL.(LL)= L/360 (0.19")
CALCULATED VERT. DEFL.(LL) = L/999 (0.00")
ALLOWABLE DEFL.(TL)= L/360 (0.19")
CALCULATED VERT. DEFL.(TL) = L/999 (0.01")

CSI: TC=0.14/1.00 (A-B:5), BC=0.08/1.00 (D-E:4),
WB=0.00/1.00 (B-E:1), SSI=0.08/1.00 (A-B:5)

DOL LUMBER=1.00 NAIL=1.00 LS BEND=1.10
COMP=1.10 SHEAR=1.10 TENS=1.10

COMPANION LIVE LOAD FACTOR = 1.00

AUTOSOLVE RIGHT HEEL ONLY

TRUSS PLATE MANUFACTURER IS NOT RESPONSIBLE FOR QUALITY CONTROL IN THE TRUSS MANUFACTURING PLANT.

NAIL VALUES

PLATE	GRIP(DRY)	SHEAR	SECTION
	(PSI)	(PLI)	(PLI)
MAX MIN	MAX MIN	MAX MIN	MAX MIN
MT20	650 371	1747 788	1987 1873

PLATE PLACEMENT TOL = 0.250 inches

PLATE ROTATION TOL = 5.0 Deg.

JSI GRIP= 0.18 (B) (INPUT = 0.90)

JSI METAL= 0.07 (B) (INPUT = 1.00)



Structural component only
DWG# T-2016966


JOB NAME 410172	TRUSS NAME C21	QUANTITY 6	PLY 1	JOB DESC. GREEN PARK HOMES	DRWG NO.
--------------------	-------------------	---------------	----------	-------------------------------	----------

Tamarack Roof Truss, Burlington

Version 8.330 S May 6 2020 Mitek Industries, Inc. Thu Jul 30 09:09:31 2020 Page 1

ID:W63xGm60kc00SiyZ4EwBx6zA2m0-pFGIPvKbVo_19re85_?w83Tw6hYbbm_tHial.46ysxFo

Scale = 1:19.9



LUMBER

N. L. G. A. RULES	CHORDS	SIZE	LUMBER	DESCR.
F - B	2x4	DRY	No.2	SPF
A - C	2x4	DRY	No.2	SPF
F - D	2x4	DRY	No.2	SPF
ALL WEBS	2x3	DRY	No.2	SPF
DRY: SEASONED LUMBER.				

PLATES (table is in inches)

JT	TYPE	PLATES	W	LEN	Y	X
B	TMVW+p	MT20	4.0	6.0	Edge	
E	BMW+w	MT20	2.0	4.0		
F	BMV1+p	MT20	3.0	4.0		

Edge - INDICATES REFERENCE CORNER OF PLATE TOUCHES EDGE OF CHORD.

DIMENSIONS, SUPPORTS AND LOADINGS SPECIFIED BY FABRICATOR TO BE VERIFIED BY BUILDING DESIGNER

BEARINGS

JT	FACTORED GROSS REACTION	MAXIMUM FACTORED GROSS REACTION	INPUT BRG	REQD BRG
F	276	276	0	0
C	32	32	0	0
D	17	19	0	0

A SUITABLE HANGER/MECHANICAL CONNECTION IS REQUIRED AT JOINT F. MINIMUM BEARING LENGTH AT JOINT F = 1-8.

SEE MITEK STANDARD DETAIL B97791H FOR CONNECTION TO JOINT(S) C, D

PROVIDE ANCHORAGE AT BEARING JOINT C FOR 150 LBS. FACTORED UPLIFT

UNFACTORED REACTIONS

JT	1ST LCASE	COMBINED	SNOW	LIVE	PERM. LIVE	WIND	DEAD	SOIL
F	192	145 / 0	0 / 0	0 / 0	0 / 0	0 / 0	48 / 0	0 / 0
C	22	18 / -28	0 / 0	0 / 0	0 / 0	0 / 0	4 / 0	0 / 0
D	14	0 / 0	0 / 0	0 / 0	0 / 0	0 / 0	14 / 0	0 / 0

BRACING

TOP CHORD TO BE SHEATHED OR MAX. PURLIN SPACING = 6.25 FT.
MAX. UNBRACED BOTTOM CHORD LENGTH = 10.00 FT OR RIGID CEILING DIRECTLY APPLIED.

ALL PITCH BREAKS AND PERIMETER CORNER JOINTS MUST BE Laterally RESTRAINED.

LOADING

TOTAL LOAD CASES: (5)

MEMB.	CHORDS	MAX. FACTORED FORCE (LBS)	FACTORED VERT. LOAD (PLF)	LC1 MAX	CS1 (LC)	MEMB.	WEBS	MAX. FACTORED FORCE (LBS)	MAX. CS1 (LC)
FR-TO						FR-TO			
F-B	-259 / 0	0.0	0.0	0.03 (1)	7.81	B-E	0 / 0	0.00 (1)	
A-B	0 / 43	-91.8	-91.8	0.13 (1)	10.00				
B-C	-34 / 0	-91.8	-91.8	0.12 (1)	6.25				
F-E	0 / 0	-18.5	-18.5	0.02 (4)	10.00				
E-D	0 / 0	-18.5	-18.5	0.02 (4)	10.00				

CANTILEVER ANALYSIS HAS BEEN CONSIDERED IN THIS DESIGN

TOTAL WEIGHT = 6 X 10 = 61 b

DESIGN CRITERIA

SPECIFIED LOADS:

TOP CH.	LL	=	25.6	PSF
	DL	=	6.0	PSF
BOT CH.	LL	=	0.0	PSF
	DL	=	7.4	PSF
TOTAL LOAD	=	39.0	PSF	

SPACING = 24.0 IN. C/C

THIS TRUSS IS DESIGNED FOR RESIDENTIAL OR SMALL BUILDING REQUIREMENTS OF PART 9, NBCC 2015

THIS DESIGN COMPLIES WITH:

- PART 9 OF BCBC 2018, ABC 2019
- PART 9 OF OBC 2012 (2019 AMENDMENT)
- CSA 086-14
- TPIC 2014

DESIGN ASSUMPTIONS

- OVERHANG NOT TO BE ALTERED OR CUT OFF.

(55 % OF 31.3 P.S.F. G.S.L. PLUS 8.4 P.S.F. RAIN LOAD) EQUALS 25.6 P.S.F. SPECIFIED ROOF LIVE LOAD

ALLOWABLE DEFL.(LL) = $L/360$ (0.19")
CALCULATED VERT. DEFL.(LL) = $L/999$ (0.00")
ALLOWABLE DEFL.(TL) = $L/360$ (0.19")
CALCULATED VERT. DEFL.(TL) = $L/999$ (0.00")

CSI: TC=0.13/1.00 (A-B:1), BC=0.02/1.00 (E-F:4),
WB=0.00/1.00 (B-E:1), SSI=0.08/1.00 (B-C:1)

DOL LUMBER=1.00 NAIL=1.00 LS BEND=1.10
COMP=1.10 SHEAR=1.10 TENS=1.10

COMPANION LIVE LOAD FACTOR = 1.00

AUTOSOLVE RIGHT HEEL ONLY

TRUSS PLATE MANUFACTURER IS NOT RESPONSIBLE FOR QUALITY CONTROL IN THE TRUSS MANUFACTURING PLANT.

NAIL VALUES

PLATE	GRIP(DRY)	SHEAR	SECTION
	(PSI)	(PLI)	(PLI)
MT20	650	371	1747
	788	1987	1873

PLATE PLACEMENT TOL. = 0.250 inches

PLATE ROTATION TOL. = 5.0 Deg.

JSI GRIP = 0.18 (B) (INPUT = 0.90)
JSI METAL = 0.07 (B) (INPUT = 1.00)




Structural component only
DWG# T-2016967

JOB NAME	TRUSS NAME	QUANTITY	PLY	JOB DESC.	GREEN PARK HOMES	DRWG NO.
410172	C22	4	1	TRUSS DESC.		

Tamarack Roof Truss, Burlington

Version 8.330 S May 6 2020 MITek Industries, Inc. Thu Jul 30 08:32:13 2020 Page 1
ID:W63xGm6okcO0SiyZ4EwBx6zA2m0-Lh2EiFnyYA1aWY07zr6R7nRhYjcDxbSIWRwXqysxm



Scale = 1:19.9

LUMBER

N. L. G. A. RULES

CHORDS	SIZE	LUMBER
F - B	2x4	DRY No.2
A - C	2x4	DRY No.2
F - D	2x4	DRY No.2

ALL WEBS 2x3 DRY No.2
DRY: SEASONED LUMBER.

PLATES (table is in inches)

JT	TYPE	PLATES	W	LEN	Y	X
B	TMVW+p	MT20	4.0	6.0	Edge	
E	BMW+w	MT20	2.0	4.0		
F	BMV1+p	MT20	3.0	4.0		

Edge - INDICATES REFERENCE CORNER OF PLATE TOUCHES EDGE OF CHORD.

DIMENSIONS, SUPPORTS AND LOADINGS SPECIFIED BY FABRICATOR TO BE VERIFIED BY BUILDING DESIGNER

JT	FACTORED GROSS REACTION		MAXIMUM FACTORED GROSS REACTION		INPUT BRG	RECORD BRG
	VERT	HORZ	DOWN	HORZ		
F	286	0	286	0	5-8	5-8
C	32	0	32	0	1-8	1-8
D	27	0	30	0	1-8	1-8

SEE MITEK STANDARD DETAIL B97791H FOR CONNECTION TO JOINT(S) C, D

PROVIDE ANCHORAGE AT BEARING JOINT C FOR 150 LBS. FACTORED UPLIFT

UNFACTORED REACTIONS

JT	1ST LCASE	MAX./MIN. COMPONENT REACTIONS					
		SNOW	LIVE	PERM.LIVE	WIND	DEAD	SOIL
F	200	145 / 0	0 / 0	0 / 0	0 / 0	55 / 0	0 / 0
C	22	18 / -28	0 / 0	0 / 0	0 / 0	4 / 0	0 / 0
D	21	0 / 0	0 / 0	0 / 0	0 / 0	21 / 0	0 / 0

BEARING MATERIAL TO BE SPF NO.2 OR BETTER AT JOINT(S) F, C

BRACING

TOP CHORD TO BE SHEATHED OR MAX. PURLIN SPACING = 6.25 FT.
MAX. UNBRACED BOTTOM CHORD LENGTH = 10.00 FT OR RIGID CEILING DIRECTLY APPLIED.

ALL PITCH BREAKS AND PERIMETER CORNER JOINTS MUST BE Laterally RESTRAINED.

LOADING

TOTAL LOAD CASES: (5)

MEMB.	CHORDS				WEBS			
	MAX. FACTORED FORCE (LBS)	VERT. LOAD (PLF)	LC1 MAX	CS1 (LC)	MAX. UNBRACED LENGTH	MEMB. MAX. FACTORED FORCE (LBS)	CS1 (LC)	
FR-TO								
F-B	-259 / 0	0.0	0.0	0.03 (1)	7.81	B-E	0 / 0	0.00 (1)
A-B	0 / 43	-91.8	-91.8	0.14 (5)	10.00			
B-C	-34 / 0	-91.8	-91.8	0.13 (5)	6.25			
F-E	0 / 0	-18.5	-18.5	0.04 (4)	10.00			
E-G	0 / 0	-18.5	-18.5	0.04 (4)	10.00			
G-D	0 / 0	-18.5	-18.5	0.04 (4)	10.00			

FACTORED CONCENTRATED LOADS (LBS)

JT	LOC.	LC1	MAX-	MAX+	FACE	DIR.	TYPE	HEEL	CONN.
G	1-11-4	1	1	---	FRONT	VERT	TOTAL	---	C1

CONNECTION REQUIREMENTS

1) C1: A SUITABLE HANGER/MECHANICAL CONNECTION IS REQUIRED.

CANTILEVER ANALYSIS HAS BEEN CONSIDERED IN THIS DESIGN

TOTAL WEIGHT = 4 X 11 = 45 lb

[M]

DESIGN CRITERIA

SPECIFIED LOADS:

TOP CH. LL = 25.6 PSF
DL = 6.0 PSF
BOT CH. LL = 0.0 PSF
DL = 7.4 PSF
TOTAL LOAD = 39.0 PSF

SPACING = 24.0 IN. C/C

THIS TRUSS IS DESIGNED FOR RESIDENTIAL OR SMALL BUILDING REQUIREMENTS OF PART 9, NBCC 2015

THIS DESIGN COMPLIES WITH:

- PART 9 OF BCBC 2018, ABC 2019
- PART 9 OF OBC 2012 (2019 AMENDMENT)
- CSA 088-14
- TPIC 2014

DESIGN ASSUMPTIONS

OVERHANG NOT TO BE ALTERED OR CUT OFF.

(55% OF 31.3 P.S.F. G.S.L. PLUS 8.4 P.S.F. RAIN LOAD) EQUALS 25.6 P.S.F. SPECIFIED ROOF LIVE LOAD

ALLOWABLE DEFL.(LL) = $L/360$ (0.19")
CALCULATED VERT. DEFL.(LL) = $L/999$ (0.00")
ALLOWABLE DEFL.(TL) = $L/360$ (0.19")
CALCULATED VERT. DEFL.(TL) = $L/999$ (0.00")

CSI: TC=0.14/1.00 (A-B:5), BC=0.04/1.00 (D-E:4), WB=0.00/1.00 (B-E:1), SS=0.08/1.00 (A-B:5)

DOL LUMBER=1.00 NAIL=1.00 LS BEND=1.10
COMP=1.10 SHEAR=1.10 TENS=1.10

COMPANION LIVE LOAD FACTOR = 1.00

AUTOSOLVE RIGHT HEEL ONLY

TRUSS PLATE MANUFACTURER IS NOT RESPONSIBLE FOR QUALITY CONTROL IN THE TRUSS MANUFACTURING PLANT.

NAIL VALUES

PLATE	GRIP(DRY)	SHEAR	SECTION
(PSI)	(PLI)	(PLI)	
MAX	MIN	MAX	MIN
MT20	650	371	1747 788 1987 1873


PLATE PLACEMENT TOL. = 0.250 inches

PLATE ROTATION TOL. = 5.0 Deg.

JSI GRIP= 0.18 (B) (INPUT = 0.90)
JSI METAL= 0.07 (B) (INPUT = 1.00)



Structural component only
DWG# T-2016968



LUMBER

N. L. G. A. RULES

CHORDS		SIZE		LUMBER
E - B	2x4	DRY		No.2
A - C	2x4	DRY		No.2
E - D	2x4	DRY		No.2

DRY: SEASONED LUMBER.

PLATES (table is in inches)

JT	TYPE	PLATES	W	LEN	Y	X
B	TMV+p	MT20	3.0	4.0		
E	BMV1+p	MT20	3.0	4.0		

DIMENSIONS, SUPPORTS AND LOADINGS SPECIFIED BY FABRICATOR TO BE VERIFIED BY BUILDING DESIGNER

BEARINGS

JT	FACTORED GROSS REACTION	MAXIMUM FACTORED GROSS REACTION	INPUT BRG	REQD BRG
E	405	405	5-8	5-8
C	130	130	1-8	1-8
D	45	50	1-8	1-8

SEE MITEK STANDARD DETAIL B97791H FOR CONNECTION TO JOINT(S) C, D

UNFACTORED REACTIONS

JT	1ST LCASE	SNOW	LIVE	PERM.LIVE	WIND	DEAD	SOIL
E	286	190.0	0.0	0.0	0.0	96.0	0.0
C	90	73.0	0.0	0.0	0.0	17.0	0.0
D	36	0.0	0.0	0.0	0.0	36.0	0.0

BEARING MATERIAL TO BE SPF NO.2 OR BETTER AT JOINT(S) E, C

BRACING

TOP CHORD TO BE SHEATHED OR MAX. PURLIN SPACING = 6.25 FT.
MAX. UNBRACED BOTTOM CHORD LENGTH = 10.00 FT OR RIGID CEILING DIRECTLY APPLIED.

ALL PITCH BREAKS AND PERIMETER CORNER JOINTS MUST BE Laterally RESTRAINED.

LOADING

TOTAL LOAD CASES: (4)

CHORDS					WEBS				
MEMB.	MAX. FORCE (LBS)	VERT (PLF)	LOAD LC1	MAX CSI (LC)	MAX. UNBRAC LENGTH	MEMB.	MAX. FORCE (LBS)	FACTORED MAX CSI (LC)	
FR-TO		FROM	TO			FR-TO			
E-B	-342	0.0	0.0	0.13 (4)	7.81				
A-B	0 28	-91.8	-91.8	0.12 (1)	10.00				
B-C	-19 0	-91.8	-91.8	0.22 (1)	6.25				
E-D	0 0	-18.5	-18.5	0.13 (4)	10.00				

DESIGN CRITERIA

SPECIFIED LOADS:
TOP CH. LL = 25.6 PSF
DL = 6.0 PSF
BOT CH. LL = 0.0 PSF
DL = 7.4 PSF
TOTAL LOAD = 39.0 PSF

SPACING = 24.0 IN./C

THIS TRUSS IS DESIGNED FOR RESIDENTIAL OR SMALL BUILDING REQUIREMENTS OF PART 9, NBC 2015

THIS DESIGN COMPLIES WITH:
- PART 9 OF CBC 2018, ABC 2019
- PART 9 OF CBC 2012 (2019 AMENDMENT)
- CSA 086-14
- TPIC 2014

DESIGN ASSUMPTIONS
- OVERHANG NOT TO BE ALTERED OR CUT OFF.

(55 % OF 31.3 P.S.F. G.S.L. PLUS 8.4 P.S.F. RAIN LOAD) EQUALS 25.6 P.S.F. SPECIFIED ROOF LIVE LOAD

ALLOWABLE DEFL.(LL) = L/360 (0.20")
CALCULATED VERT. DEFL.(LL) = L/999 (0.00")
ALLOWABLE DEFL.(TL) = L/360 (0.20")
CALCULATED VERT. DEFL.(TL) = L/999 (0.03")

CSI: TC=0.22/1.00 (B-C:1), BC=0.13/1.00 (D-E:4), WB=0.00/1.00 (n/a:0), SSI=0.15/1.00 (B-C:1)

DOL LUMBER=1.00 NAIL=1.00 LS BEND=1 10
COMP=1.10 SHEAR=1 10 TENS=1 10

COMPANION LIVE LOAD FACTOR = 1.00

AUTOSOLVE RIGHT HEEL ONLY

TRUSS PLATE MANUFACTURER IS NOT RESPONSIBLE FOR QUALITY CONTROL IN THE TRUSS MANUFACTURING PLANT

NAIL VALUES
PLATE GRIP(DRY) SHEAR SECTION (PSI) (PLI) (PLI)
MAX MIN MAX MIN MAX MIN
MT20 650 371 1747 768 1987 1873

PLATE PLACEMENT TOL. = 0.250 inches


PLATE ROTATION TOL. = 5.0 Deg.

JSI GRIP= 0.14 (E) (INPUT = 0.90)
JSI METAL= 0.09 (B) (INPUT = 1.00)



Version 8.330 S May 6 2020 MiTek Industries, Inc. Wed Aug 5 10:40:51 2020 Page 1
ID:nmPe4yMblTuNMWU5OprM1EzA_nL-n98YKfK80xLZZz6hd8ljfm?Htv?HZlwQ15CmNDyqxMA

Scale = 1:13.1



DRY: SEASONED LUMBER.

DIMENSIONS, SUPPORTS AND LOADINGS SPECIFIED BY FABRICATOR TO BE VERIFIED BY
BUILDING DESIGNER
BEARINGS

TOTAL WEIGHT = $4 \times 12 = 48$ lb

SEE MITEK STANDARD DETAIL B97791H FOR CONNECTION TO JOINT(S) C . D

UNFACTORED REACTIONS

DESIGN CRITERIA

SPECIFIED LOADS:

TOP	CH.	LL =	25.6	PSF
		DL =	6.0	PSF
BOT	CH.	LL =	0.0	PSF
		DL =	7.4	PSF
TOTAL LOAD		=	39.0	PSF

SPACING = 24.0 IN. C/C

THIS TRUSS IS DESIGNED FOR RESIDENTIAL OR
SMALL BUILDING REQUIREMENTS OF PART 9,
NBCC 2015

THIS DESIGN COMPLIES WITH:

- PART 9 OF BCBC 2018 , ABC 2019
- PART 9 OF OBC 2012 (2019 AMENDMENT)
- CSA 086-14
- TPIC 2014

DESIGN ASSUMPTIONS

OVERHANG NOT TO BE ALTERED OR CUT OFF

(55 % OF 31.3 P.S.F. G.S.L. PLUS 8.4 P.S.F. RAIN LOAD) EQUALS 25.6 P.S.F. SPECIFIED ROOF LIVE LOAD

ALLOWABLE DEFL.(LL)= $L/360$ (0.20")
CALCULATED VERT. DEFL.(LL) = $L/999$ (0.01")
ALLOWABLE DEFL.(TL)= $L/360$ (0.20")
CALCULATED VERT. DEFL.(TL) = $L/999$ (0.04")

CSI: TC=0.12/1.00 (A-B:1) , BC=0.14/1.00 (D-E:4) .
WB=0.00/1.00 (n/a:0) . SSf=0.09/1.00 (A-B:1)

DOL LUMBER=0.99 NAIL=0.99 LS BEND=1.10
COMP=1.10 SHEAR=1.10 TENS= 1.10

COMPANION LIVE LOAD FACTOR = 1.00

AUTOSOLVE RIGHT HEEL ONLY

TRUSS PLATE MANUFACTURER IS NOT RESPONSIBLE FOR QUALITY CONTROL IN THE TRUSS MANUFACTURING PLANT

NAIL VALUES

PLATE	GRIP(DRY)		SHEAR		SECTION	
	(PSI)		(PLI)		(PLI)	
	MAX	MIN	MAX	MIN	MAX	MIN
MT20	650	371	1747	788	1987	1873


PLATE PLACEMENT TOL. = 0.250 inches

PLATE ROTATION TOL. = 5.0 Deg

JSI GRIP= 0.09 (E) (INPUT = 0.90)
JSI METAL= 0.06 (B) (INPUT = 1.00)



Structural component only
DWG# T-2017360



LUMBER
N. L. G. A. RULES
CHORDS SIZE LUMBER DESCR.
E - B 2x4 DRY No.2 SPF
A - C 2x4 DRY No.2 SPF
E - D 2x4 DRY No.2 SPF

DRY: SEASONED LUMBER.

PLATES (table is in inches)

JT	TYPE	PLATES	W	LEN	Y	X
B	TMV+p	MT20	3.0	4.0		
E	BMV1+p	MT20	3.0	4.0		

DIMENSIONS, SUPPORTS AND LOADINGS SPECIFIED BY FABRICATOR TO BE VERIFIED BY BUILDING DESIGNER

BEARINGS

JT	FACTORED GROSS REACTION		MAXIMUM FACTORED GROSS REACTION		INPUT BRG IN-SX	RECORD BRG IN-SX
	VERT	HORZ	DOWN	HORZ		
E	361	0	361	0	5-8	5-8
C	130	0	130	0	1-8	1-8
D	16	0	17	0	1-8	1-8

SEE MITEK STANDARD DETAIL 897791H FOR CONNECTION TO JOINT(S) C, D

UNFACTORED REACTIONS							
JT	1ST LCASE	MAX./MIN. COMPONENT REACTIONS					
	COMBINED	SNOW	LIVE	PERM. LIVE	WIND	DEAD	SC
E	250	190 / 0	0 / 0	0 / 0	0 / 0	60 / 0	0 / 0
C	90	73 / 0	0 / 0	0 / 0	0 / 0	17 / 0	0 / 0
D	12	0 / 0	0 / 0	0 / 0	0 / 0	12 / 0	0 / 0

BEARING MATERIAL TO BE SPF NO.2 OR BETTER AT JOINT(S) E

BRACING
TOP CHORD TO BE SHEATHED OR MAX. PURLIN SPACING = 6.25 FT.
MAX. UNBRACED BOTTOM CHORD LENGTH = 10.00 FT OR RIGID CEILING DIRECTLY APPLIED.

ALL PITCH BREAKS AND PERIMETER CORNER JOINTS MUST BE Laterally RESTRAINED.

LOADING
TOTAL LOAD CASES: (5)

CHORDS					WEBS				
MEMB.	MAX. FACTORED FORCE (LBS)	FACTORED VERT. LOAD (PLF)	LC1 MAX (LC)	MAX. UNBRAC (LBS)	MEMB.	MAX. FACTORED FORCE (LBS)	MAX (LC)		
FR-TO		FROM	TO	LENGTH	FR-TO				
E-B	-342	0	0	0.01 (4)	7.81				
A-B	0' 28	-91.8	-91.8	0.13 (5)	10.00				
B-C	-19	0	-91.8	0.22 (1)	6.25				
E-D	0	0	-18.5	-18.5	0.02 (4)	10.00			

CANTILEVER ANALYSIS HAS BEEN CONSIDERED IN THIS DESIGN

TOTAL WEIGHT = 4 X 10 = 38 lb

DESIGN CRITERIA

SPECIFIED LOADS:
TOP CH. LL = 25.6 PSF
DL = 6.0 PSF
BOT CH. LL = 0.0 PSF
DL = 7.4 PSF
TOTAL LOAD = 39.0 PSF

SPACING = 24.0 IN. C/C

THIS TRUSS IS DESIGNED FOR RESIDENTIAL OR SMALL BUILDING REQUIREMENTS OF PART 9, NBCC 2015

THIS DESIGN COMPLIES WITH:
- PART 9 OF BCBC 2018, ABC 2019
- PART 9 OF OBC 2012 (2019 AMENDMENT)
- CSA 086-14
- TPIC 2014

DESIGN ASSUMPTIONS
- OVERHANG NOT TO BE ALTERED OR CUT OFF
(55 % OF 31.3 P.S.F. G.S.L. PLUS 8.4 P.S.F. RAIN LOAD) EQUALS 25.6 P.S.F. SPECIFIED ROOF LIVE LOAD

ALLOWABLE DEFL. (LL) = $L/360$ (0.19")
CALCULATED VERT. DEFL. (LL) = $L/999$ (0.00")
ALLOWABLE DEFL. (TL) = $L/360$ (0.19")
CALCULATED VERT. DEFL. (TL) = $L/999$ (0.00")

CSI: TC=0.22/1.00 (B-C:1) . BC=0.02/1.00 (D-E:4) .
WB=0.00/1.00 (n/a:0) . SSI=0.15/1.00 (B-C:1)

DOL LUMBER=1.00 NAIL=1.00 LS BEND=1 10
COMP=1 10 SHEAR=1.10 TENS= 1.10

COMPANION LIVE LOAD FACTOR = 1.00

AUTOSOLVE RIGHT HEEL ONLY

TRUSS PLATE MANUFACTURER IS NOT RESPONSIBLE FOR QUALITY CONTROL IN THE TRUSS MANUFACTURING PLANT

NAIL VALUES
PLATE GRIP(DRY) SHEAR SECTION
(PSI) (PLI) (PLI)
MAX MIN MAX MIN MAX MIN
MT20 650 371 1747 788 1987 1873


PLATE PLACEMENT TOL. = 0.250 inches

PLATE ROTATION TOL. = 5.0 Deg.

JSI GRIP= 0.14 (E) (INPUT = 0.90)
JSI METAL= 0.09 (B) (INPUT = 1.00)



JOB NAME 409989	TRUSS NAME C33	QUANTITY 6	PLY 1	JOB DESC. GREENPARK HOMES	DRWG NO.
Tamarack Roof Truss, Burlington		TRUSS DESC.			



LUMBER			
N. L. G. A. RULES	SIZE	DRY	LUMBER
E - B	2x4	DRY	No.2
A - C	2x4	DRY	No.2
E - D	2x4	DRY	No.2

DRY: SEASONED LUMBER.

PLATES (table is in inches)

JT	TYPE	PLATES	W	LEN	Y	X
B	TMV+p	MT20	3.0	4.0		
E	BMV1+p	MT20	3.0	4.0		

DIMENSIONS, SUPPORTS AND LOADINGS SPECIFIED BY FABRICATOR TO BE VERIFIED BY BUILDING DESIGNER

JT	FACTORED GROSS REACTION		MAXIMUM FACTORED GROSS REACTION		INPUT BRG IN-SX	REQD BRG IN-SX
	VERT	HORZ	DOWN	HORZ		
E	271	0	271	0	5-8	5-8
C	45	0	45	0	1-8	1-8
D	8	0	17	0	1-8	1-8

SEE MITEK STANDARD DETAIL B97791H FOR CONNECTION TO JOINT(S) C, D

PROVIDE ANCHORAGE AT BEARING JOINT C FOR 150 LBS FACTORED UPLIFT
PROVIDE ANCHORAGE AT BEARING JOINT D FOR 150 LBS FACTORED UPLIFT

UNFACTORED REACTIONS

1ST CASE	MAX. MIN. COMPONENT REACTIONS						
JT	COMBINED	SNOW	LIVE	PERM. LIVE	WIND	DEAD	SOIL
E	188	141 / 0	0 / 0	0 / 0	0 / 0	47 / 0	0 / 0
C	31	24 / -18	0 / 0	0 / 0	0 / 0	7 / 0	0 / 0
D	7	0 / -8	0 / 0	0 / 0	0 / 0	12 / 0	0 / 0

BEARING MATERIAL TO BE SPF NO.2 OR BETTER AT JOINT(S) E, C

BRACING

TOP CHORD TO BE SHEATHED OR MAX. PURLIN SPACING = 6.25 FT.
MAX. UNBRACED BOTTOM CHORD LENGTH = 10.00 FT. OR RIGID CEILING DIRECTLY APPLIED.
ALL PITCH BREAKS AND PERIMETER CORNER JOINTS MUST BE Laterally RESTRAINED.

LOADING

TOTAL LOAD CASES: (5)

MEMB.	CHORDS		FACTORED		WEBS		FACTORED	
	FORCE (LBS)	VERT. LOAD (PLF)	MAX	CS1 (LC)	MEMB. FORCE (LBS)	MAX	CS1 (LC)	MEMB. FORCE (LBS)
FR-TO								
E-B	-244 / 0	0.0	0.0	0.04 (5)	7.81			
A-B	0 / 28	-91.8	-91.8	0.12 (1)	10.00			
B-C	-17 / 0	-91.8	-91.8	0.09 (1)	6.25			
E-D	0 / 0	-18.5	-18.5	0.04 (5)	10.00			

CANTILEVER ANALYSIS HAS BEEN CONSIDERED IN THIS DESIGN

TOTAL WEIGHT = 6 X 7 = 42 lb

DESIGN CRITERIA

SPECIFIED LOADS:

TOP CH.	LL = 25.6 PSF
	DL = 6.0 PSF
BOT CH.	LL = 0.0 PSF
	DL = 7.4 PSF
TOTAL LOAD	= 39.0 PSF

SPACING = 24.0 IN. O.C

THIS TRUSS IS DESIGNED FOR RESIDENTIAL OR SMALL BUILDING REQUIREMENTS OF PART 9, NBCC 2015

THIS DESIGN COMPLIES WITH:

- PART 9 OF BCBC 2018, ABC 2019
- PART 9 OF OBC 2012 (2019 AMENDMENT)
- CSA 086-14
- TPIC 2014

DESIGN ASSUMPTIONS

OVERHANG NOT TO BE ALTERED OR CUT OFF

(55 % OF 31.3 P.S.F. G.S.L. PLUS 8.4 P.S.F. RAIN LOAD) EQUALS 25.6 P.S.F. SPECIFIED ROOF LIVE LOAD

ALLOWABLE DEFL.(LL) = L/360 (0.19")
CALCULATED VERT. DEFL.(LL) = L/999 (0.00")
ALLOWABLE DEFL.(TL) = L/360 (0.19")
CALCULATED VERT. DEFL.(TL) = L/999 (0.00")

CSI: TC=0.12/1.00 (A-B:1), BC=0.04/1.00 (D-E:5), WB=0.00/1.00 (in/a:0), SSI=0.09/1.00 (A-B:1)

DOL LUMBER=1.00 NAIL=1.00 LS BEND=1.10
COMP=1.10 SHEAR=1.10 TENS=1.10

COMPANION LIVE LOAD FACTOR = 1.00

AUTOSOLVE RIGHT HEEL ONLY

TRUSS PLATE MANUFACTURER IS NOT RESPONSIBLE FOR QUALITY CONTROL IN THE TRUSS MANUFACTURING PLANT

NAIL VALUES

PLATE GRIP(DRY)	SHEAR	SECTION
(PSI)	(PLI)	(PLI)
MAX	MIN	MAX
MT20	650	371
	1747	788
	1987	1873

PLATE PLACEMENT TOL. = 0.250 inches


PLATE ROTATION TOL. = 5.0 Deg.

JSI GRIP= 0.10 (E) (INPUT = 0.90)
JSI METAL= 0.07 (B) (INPUT = 1.00)



Structural component only
DWG# T-2017362

JOB NAME	TRUSS NAME	QUANTITY	PLY	JOB DESC.	DRWG NO.
410174	C34	4	1	GREEN PARK HOMES	
Tamarack Roof Truss, Burlington					
Version 8.330 S May 6 2020 MiTek Industries, Inc. Thu Jul 30 08:42:23 2020 Page 1					
ID:W63xGm6okcO0SiyZ4EwBx6zA2m0-U2vrkEdPubt0rBfK4o99I2hgRv38TyFwQCByTysxE					
Scale = 1:13.1					



LUMBER			
N. L. G. A. RULES	SIZE	DRY	LUMBER
CHORDS	2x4	DRY	No.2
E - B	2x4	DRY	No.2
A - C	2x4	DRY	No.2
E - D	2x4	DRY	No.2

DRY: SEASONED LUMBER.

PLATES (table is in inches)

JT	TYPE	PLATES	W	LEN	Y	X
B	TMV+p	MT20	3.0	4.0		
E	BMV1+p	MT20	3.0	4.0		

DIMENSIONS, SUPPORTS AND LOADINGS SPECIFIED BY FABRICATOR TO BE VERIFIED BY BUILDING DESIGNER

BEARINGS

JT	FACTORED GROSS REACTION	MAXIMUM FACTORED GROSS REACTION	INPUT BRG	REQD BRG
	VERT	HORZ	DOWN	HORZ
E	279	0	279	0
C	49	0	49	0
D	26	0	35	0

SEE MITEK STANDARD DETAIL B97791H FOR CONNECTION TO JOINT(S) C, D

PROVIDE ANCHORAGE AT BEARING JOINT C FOR 150 LBS. FACTORED UPLIFT

UNFACTORED REACTIONS

JT	1ST CASE	MAX. MIN. COMPONENT REACTIONS	SNOW	LIVE	PERM. LIVE	WIND	DEAD	SOIL
E	195	138 / 0	0 / 0	0 / 0	0 / 0	58 / 0	0 / 0	0 / 0
C	35	22 / -20	0 / 0	0 / 0	0 / 0	13 / 0	0 / 0	0 / 0
D	21	0 / -5	0 / 0	0 / 0	0 / 0	25 / 0	0 / 0	0 / 0

BEARING MATERIAL TO BE SPF NO.2 OR BETTER AT JOINT(S) E, C

BRACING

TOP CHORD TO BE SHEATHED OR MAX. PURLIN SPACING = 6.25 FT.
MAX. UNBRACED BOTTOM CHORD LENGTH = 10.00 FT OR RIGID CEILING DIRECTLY APPLIED.

ALL PITCH BREAKS AND PERIMETER CORNER JOINTS MUST BE LATERALLY RESTRAINED.

LOADING

TOTAL LOAD CASES: (9)

CHORDS				WEBS			
MEMB.	FORCE (LBS)	FACTORED VERT. LOAD (PLF)	MAX. LC1 (LC)	MEMB.	FORCE (LBS)	FACTORED VERT. LOAD (PLF)	MAX. LC1 (LC)
FR-TO		FROM	TO	FR-TO		FROM	TO
E-B	-241 / 0	0.0	0.0	0.05 (5)	7.81		
A-B	0 / 28	-91.8	-91.8	0.14 (5)	10.00		
B-C	-15 / 1	-91.8	-91.8	0.08 (5)	6.25		
E-F	0 / 0	-18.5	-18.5	0.06 (4)	10.00		
F-D	0 / 0	-18.5	-18.5	0.06 (4)	10.00		

FACTORED CONCENTRATED LOADS (LBS)

JT	LOC.	LC1	MAX-	MAX+	FACE	DIR.	TYPE	HEEL	CONN.
F	1-11.4	7	1	12	BACK	VERT	TOTAL		C1

CONNECTION REQUIREMENTS

1) C1: A SUITABLE HANGER/MECHANICAL CONNECTION IS REQUIRED.

CANTILEVER ANALYSIS HAS BEEN CONSIDERED IN THIS DESIGN

TOTAL WEIGHT = 4 X 9 = 37 lb

DESIGN CRITERIA

SPECIFIED LOADS:

TOP CH.	LL	=	25.6	PSF
	DL	=	6.0	PSF
BOT CH.	LL	=	0.0	PSF
	DL	=	7.4	PSF
TOTAL LOAD	=	39.0	PSF	

SPACING = 24.0 IN. C/C

THIS TRUSS IS DESIGNED FOR RESIDENTIAL OR SMALL BUILDING REQUIREMENTS OF PART 9, NBCC 2015

THIS DESIGN COMPLIES WITH:

- PART 9 OF BCBC 2018, ABC 2019
- PART 9 OF OBC 2012 (2019 AMENDMENT)
- CSA 086-14
- TPIC 2014

DESIGN ASSUMPTIONS

- OVERHANG NOT TO BE ALTERED OR CUT OFF.

(55 % OF 31.3 P.S.F. G.S.L. PLUS 8.4 P.S.F. RAIN LOAD) EQUALS 25.6 P.S.F. SPECIFIED ROOF LIVE LOAD

ALLOWABLE DEFL.(LL)= L/360 (0.19")
CALCULATED VERT. DEFL.(LL) = L/999 (0.00")
ALLOWABLE DEFL.(TL)= L/360 (0.19")
CALCULATED VERT. DEFL.(TL) = L/999 (0.01")

CSI: TC=0.14/1.00 (A-B:5), BC=0.06/1.00 (D-E:4),
WB=0.00/1.00 (n/a:0), SSL=0.10/1.00 (A-B:5)

DOL LUMBER=1.00 NAIL=1.00 LS BEND=1.10
COMP=1.10 SHEAR=1.10 TENS=1.10

COMPANION LIVE LOAD FACTOR = 1.00

AUTOSOLVE RIGHT HEEL ONLY

TRUSS PLATE MANUFACTURER IS NOT RESPONSIBLE FOR QUALITY CONTROL IN THE TRUSS MANUFACTURING PLANT.

NAIL VALUES

PLATE	GRIP(DRY)	SHEAR	SECTION
(PSI)	(PLI)	(PLI)	(PLI)
MT20	650	371	1747
	788	1987	1873

PLATE PLACEMENT TOL. = 0.250 inches

PLATE ROTATION TOL. = 5.0 Deg.

JSI GRIP= 0.10 (E) (INPUT = 0.90)
JSI METAL= 0.07 (B) (INPUT = 1.00)



Structural component only
DWG# T-2016983

LUL/LUS/LJS/HUS/HHUS/HGUS

Standard and Double-Shear Joist Hangers



This product is preferable to similar connectors because of
a) easier installation, b) higher capacities, c) lower installed
cost, or a combination of these features.

Most hangers in this series have double-shear nailing — an innovation that distributes the load through two points on each joist nail for greater strength. This allows for fewer nails, faster installation, and the use of all common nails for the same connection. (Do not bend or remove tabs)

Double-shear hangers range from the light capacity LUS hangers to the highest capacity HGUS hangers. For medium load truss applications, the HUS offers a lower cost alternative and easier installation than the HGUS hangers, while providing greater load capacity and bearing than the LUS.

Material: See table on pp. 258–259.


Finish: Galvanized. Some products available in stainless steel or ZMAX® coating; see Corrosion Information, pp. 20–24.

Installation:


- Use all specified fasteners; see General Notes.
- Nails must be driven at an angle through the joist or truss into the header to achieve the tabulated resistances (except LUL).
- Where 16d commons are specified, 10d commons may be used at 0.83 of the tabulated factored resistance.
- Not designed for welded or nailer applications.
- With single ply 2x carrying members, use 10d x 1½" nails into the header and 10d commons into the joist, and reduce the resistance to 0.64 of the table value where 16d nails are specified and 0.77 where 10d nails are specified.

Options:


- LUS, LJS, LUL and HUS hangers cannot be modified.
- Other sizes available; consult your Simpson Strong-Tie representative.
- See Hanger Options information on p. 126.




Double-Shear
Nailing
Top View




Double-Shear
Nailing
Side View;
Do not
bend tab




Dome Double-Shear
Nailing Side View
(available on
some models)
U.S. Patent 5,603,580




LUS28




LU26L




HUS210
(HUS26, HUS28,
and HHUS similar)



HGUS28-2




HHUS210-2



LJS26DS

**Typical HUS26
Installation
with Reduced
Heel Height**
(Truss Designer
to provide
fastener quantity
for connecting
multiple members
together)



LUL/LUS/LJS/HUS/HHUS/HGUS**HHUS/HGUS**

See Hanger Options information on pp. 125–127.


HHUS — Sloped and/or Skewed Seat

- HHUS hangers can be skewed to a maximum of 45° and/or sloped to a maximum of 45°
- For skew only, maximum factored down resistance is 0.85 of the table value
- For sloped only or sloped and skewed hangers, the maximum factored down resistance is 0.72 of the table value
- Uplift resistances for sloped/skewed conditions are 0.62 of the table value
- The joist must be bevel-cut to allow for double-shear nailing

HGUS — Skewed Seat

- HGUS hangers can be skewed only to a maximum of 45°. Factored resistances are:

HGUS Seat Width	Joist	Down Resistance	Uplift
W < 2"	Bevel or square cut	0.62 of table value	0.46 of table value
2" < W < 6"	Bevel cut	0.67 of table value	0.41 of table value
2" < W < 6"	Square cut	0.46 of table value	0.41 of table value
W > 6"	Bevel cut	0.75 of table value	0.41 of table value



Top View HHUS Hanger Skewed Right
(joist must be bevel cut)
All joist nails installed on the outside angle (non-acute side).

Standard and Double-Shear Joist Hangers (cont.)

These products are available with additional corrosion protection. For more information, see p. 24.

These products are approved for installation with the Strong-Drive® SD Connector screw. See pp. 32–34 for more information.

Model No.	Ga.	Dimensions (in.)				Fasteners		Factored Resistance			
		W	H	B	d _e ³	Header	Joist	D.Fir-L		S-P-F	
								Uplift	Normal	Uplift	Normal
								(K _D = 1.15)	(K _D = 1.00)	(K _D = 1.15)	(K _D = 1.00)
								lb.	lb.	lb.	lb.
								kN	kN	kN	kN
Single 2x Sizes											
LUS24	18	1 1/8	3 1/4	1 1/4	2 1/4	(4) 10d	(2) 10d	710	1625	645	1155
LU24L	22	1 1/8	3	1 1/4	2 1/4	(4) 10d	(2) 10d x 1 1/2"	3.16	7.23	2.87	5.14
LU26L	22	1 1/8	5	1 1/4	4 5/8	(6) 10d	(4) 10d x 1 1/2"	360	1020	320	725
								1.60	4.54	1.42	3.22
								720	1605	645	1140
								3.20	7.14	2.87	5.07
LUS26	18	1 1/8	4 3/4	1 1/4	3 3/4	(4) 10d	(4) 10d	1420	2170	1290	1630
								6.32	9.65	5.74	7.25
HUS28	16	1 1/8	5 3/8	3	3 3/4	(14) 16d	(6) 16d	2705	4940	2065	3875
								11.30	21.97	9.20	17.24
LJS26DS	18	1 1/8	5	3 1/2	4 5/8	(16) 16d	(6) 16d	2055	4265	1460	4115
								9.14	18.97	6.49	18.31
HGUS26	12	1 1/8	5 3/8	5	4 1/4	(20) 16d	(8) 16d	2685	6625	2685	5700
								11.96	29.51	11.96	25.35
LU28L	20	1 1/8	6 3/4	1 1/4	5 3/8	(8) 10d	(6) 10d x 1 1/2"	1140	2185	1020	1550
								5.07	9.72	4.54	6.89
LUS28	18	1 1/8	6 3/8	1 1/4	3 3/4	(6) 10d	(4) 10d	1420	2520	1290	1790
								6.32	11.21	5.74	7.96
HUS28	16	1 1/8	7 1/8	3	6 1/8	(22) 16d	(8) 16d	3605	5365	2675	4345
								16.04	23.86	11.90	19.33
HGUS28	12	1 1/8	7 1/8	5	6 1/8	(36) 16d	(12) 16d	3310	7675	3310	6900
								14.74	34.19	14.74	30.73
LU210L	20	1 1/8	8	1 1/4	7 3/8	(10) 10d	(6) 10d x 1 1/2"	1140	2495	1020	1770
								5.07	11.10	4.54	7.87
LUS210	18	1 1/8	7 1/8	1 1/4	3 3/4	(8) 10d	(4) 10d	1420	2785	1290	2210
								6.32	12.39	5.74	9.83

1. Factored uplift resistances have been increased 15% for wind or earthquake loading; no further increase is allowed.
2. Designer must ensure that hanger is compatible with truss when reduced heel height is used.
3. d_e is the distance from the bearing seat to the top joist nail.
4. Resistances shown require a minimum 2-ply girder truss. For fastening to single-ply truss request technical bulletin T-C-N10TRSSCN and/or see installation notes.
5. Nails: 16d = 0.162" dia. x 3 1/2" long. See pp. 27–28 for other nail sizes and information.


Face-Mount Hangers

SIMPSON
Strong-Tie

These products are available with additional corrosion protection. For more information, see p. 24.

These products are approved for installation with the Strong-Drive® SD Connector screw. See pp. 32-34 for more information.

Model No.	Ga.	Dimensions (in.)				Fasteners		Factored Resistance			
		W	H	B	d _o ³	Header	Joist	D.Fir-L		S-P-F	
								Uplift	Normal	Uplift	Normal
								(K _D = 1.15)	(K _D = 1.00)	(K _D = 1.15)	(K _D = 1.00)
								lb.	lb.	lb.	lb.
								kN	kN	kN	kN
Double 2x Sizes											
LUS24-2	18	3 1/8	3 1/8	2	1 1/2	(4) 16d	(2) 16d	835	2020	590	1435
SS LUS26-2	18	3 1/8	4 7/8	2	4	(4) 16d	(4) 16d	3.71	8.99	2.62	6.38
HHUS26-2	14	3 1/8	5 3/8	3	3 15/16	(14) 16d	(6) 16d	1720	2595	1545	1920
HGUS26-2	12	3 1/8	5 7/8	4	4 1/4	(20) 16d	(8) 16d	7.65	11.54	6.87	8.54
SS LUS28-2	18	3 1/8	7	2	4	(6) 16d	(4) 16d	2850	7335	2065	5205
HHUS28-2	14	3 1/8	7 1/8	3	6 1/8	(22) 16d	(8) 16d	12.68	32.63	9.20	23.15
HGUS28-2	12	3 1/8	7 3/8	4	6 1/4	(36) 16d	(12) 16d	4385	8950	3110	6355
SS LUS210-2	18	3 1/8	9	2	6	(8) 16d	(6) 16d	19.51	39.81	13.83	28.27
HHUS210-2	14	3 1/8	9 3/8	3	8	(30) 16d	(10) 16d	1720	3325	1545	2575
HGUS210-2	12	3 1/8	9 3/8	4	8 1/4	(46) 16d	(16) 16d	7.65	14.79	6.87	11.45
								3765	8940	2675	6345
								16.75	39.77	11.90	28.22
								6070	12980	4310	9215
								27.00	57.74	19.17	40.99
								2580	4500	2320	3195
								11.48	20.02	10.32	14.21
								4670	9660	4235	7000
								20.77	42.97	18.84	31.14
								6840	14015	4855	10270
								30.43	62.34	21.60	45.69
Triple 2x Sizes											
HGUS26-3	12	4 1/8	5 1/2	4	4 1/4	(20) 16d	(8) 16d	4385	8950	3110	6355
HGUS28-3	12	4 1/8	7 1/4	4	6 1/4	(36) 16d	(12) 16d	19.51	39.81	13.83	28.27
HHUS210-3	14	4 1/8	9	3	7 15/16	(30) 16d	(10) 16d	6070	12980	4310	9215
HGUS210-3	12	4 1/8	9 1/4	4	8 3/4	(46) 16d	(16) 16d	27.00	57.74	19.17	40.99
								4670	9670	4235	6865
								20.77	43.02	18.84	30.54
								6840	14645	4855	10400
								30.43	65.14	21.60	46.26
Quadruple 2x Sizes											
HGUS26-4	12	6 1/8	5 7/8	4	4 1/4	(20) 16d	(8) 16d	4385	8950	3110	6355
HGUS28-4	12	6 1/8	7 3/8	4	6 1/4	(36) 16d	(12) 16d	19.51	39.81	13.83	28.27
HHUS210-4	14	6 1/8	8 3/8	3	7 15/16	(30) 16d	(10) 16d	6070	12980	4310	9215
HGUS210-4	12	6 1/8	9 3/8	4	8 3/4	(46) 16d	(16) 16d	27.00	57.74	19.17	40.99
								4670	10155	4235	7210
								20.77	45.17	18.84	32.07
								6840	14645	4855	10400
								30.43	65.14	21.60	46.26
								7640	14995	5425	10645
								33.98	66.70	24.13	47.35
								10130	16400	7195	11645
								45.06	72.95	32.00	51.80
4x Sizes											
LUS46	18	3 1/8	4 3/4	2	3 3/8	(4) 16d	(4) 16d	1720	2595	1545	1920
HHUS46	14	3 1/8	5 1/4	3	3 15/16	(14) 16d	(6) 16d	7.65	11.54	6.87	8.54
HGUS46	12	3 1/8	5 3/4	4	4 1/8	(20) 16d	(8) 16d	2540	7335	2065	5205
LUS48	18	3 1/8	6 3/4	2	3 3/8	(6) 16d	(4) 16d	11.30	32.63	9.20	23.15
HHUS48	14	3 1/8	7 1/4	3	6 1/8	(22) 16d	(8) 16d	4385	8950	3110	6355
HGUS48	12	3 1/8	7 1/8	4	6 1/4	(36) 16d	(12) 16d	19.51	39.81	13.83	28.27
LUS410	18	3 1/8	8 3/4	2	5 3/8	(8) 16d	(6) 16d	1720	3325	1545	2575
HHUS410	14	3 1/8	9 1/4	3	8 1/8	(30) 16d	(10) 16d	7.65	14.79	6.87	11.45
HGUS410	12	3 1/8	9 3/8	4	8 3/4	(46) 16d	(16) 16d	3765	8940	2675	6345
								16.75	39.77	11.90	28.22
								6070	12980	4310	9215
								27.00	57.74	19.17	40.99
								2580	4500	2320	3195
								11.48	20.02	10.32	14.21
								6840	14015	4855	10270
								30.43	62.34	21.60	45.69
								7640	14995	5425	10645
								33.98	66.70	24.13	47.35
								10130	16400	7195	11645
								45.06	72.95	32.00	51.80



Plated Truss Connectors

See footnotes
on p. 258.

TC – Truss Connectors

SIMPSON
Strong-Tie

The TC truss connector is an ideal connector for scissor trusses and can allow horizontal movement up to 1¼". The TC also attaches plated trusses to top plates or sill plates to resist uplift forces. Typically used on one or both ends of truss as determined by the building designer.

Material: 16 gauge

Finish: G90 galvanized


Design: Factored resistances are in accordance with CSA 086-14

Installation:

- Use all specified fasteners.
- Nails: 10d = 0.148" dia. x 3" long common wire, 10d x 1½" = 0.148" dia. x 1½" long.
- Drive 10d nails into the truss at the inside end of the slotted holes (inside end is towards the centre of the truss) and clinch on the back side. Do not seat these nails into the truss—allow room under the nail head for movement of the truss with respect to the wall.


Optional TC Installation:

- Bend one flange up 90°. Drive specified nails into the top and face of the top plates or install Titen® screws into the top and face of masonry wall. See optional load tables and installation details.




TC24

U.S. Patent 4,932,173




TC26


(TC28 Similar)



Typical TC24 Installation



Optional TC26 Installation for Grouted Concrete Block using a Wood Nailer
(8", 10", 12" Wall Installation Similar)



Optional TC26 Installation for Grouted Concrete Block using Titen Screws

Model No.	Fasteners		Factored Resistance	
	Truss	Wall Plates	D.Fir-L	S-P-F
			Uplift (K ₀ =1.15)	Uplift (K ₀ =1.15)
TC24	(4) 10d	(4) 10d	605	430
TC26	(5) 10d	(6) 10d	1015	720
TC28	(5) 10d	(6) 10d	1015	720

Optional TC Installation Table

Model No.	Fasteners		Factored Resistance	
	Truss	Wall Plates	D.Fir-L	S-P-F
			Uplift (K ₀ =1.15)	Uplift (K ₀ =1.15)
TC26	(5) 10d	(6) 10d x 1½"	810	660
	(5) 10d	(6) 10d	930	660

1. Factored resistances have been increased 15% for earthquake or wind loading; no further increase allowed; reduce where other loads govern.
2. Grout strength is 15 MPa minimum.
3. Optional TC26 installation with 10d nails requires minimum 3" top plate thickness.
4. TC26 fastened to grouted concrete block with (6) – ¾" x 2¼" Titen screws has a factored uplift resistance of 275 lb.



LIMIT
STATES
DESIGN

This technical bulletin is effective until June 30, 2019 and reflects information available as of March 1, 2017. This information is updated periodically and should not be relied upon after June 30, 2019. Contact Simpson Strong-Tie for current information and limited warranty or see strongtie.com.

© 2017 Simpson Strong-Tie Company Inc.

TSPECTC17 3/17 exp. 6/19

(800) 999-5099
strongtie.com

H/TSP

Seismic and Hurricane Ties (cont.)

These products are available with additional corrosion protection. For more information, see p.24.

These products are approved for installation with the Strong-Drive® SD Connector screw. See pp. 32–34 for more information.

Model No.	Ga.	Fasteners			Factored Resistance ($K_D = 1.15$)					
					D.Fir-L			S-P-F		
		To Rafters/ Truss	To Plates	To Studs	Uplift	Lateral		Uplift	Lateral	
						F ₁	F ₂		F ₁	F ₂
					lb.	lb.	lb.	lb.	lb.	lb.
					kN	kN	kN	kN	kN	kN
H1	18	(6) 8d x 1½"	(4) 8d	—	740	685	300	680	485	215
					3.29	3.05	1.33	3.02	2.16	0.96
SS H2A	18	(5) 8d x 1½"	(2) 8d x 1½"	(5) 8d x 1½"	830	220	75	590	155	55
					3.69	0.98	0.33	2.62	0.69	0.24
SS H2.5A	18	(5) 8d	(5) 8d	—	805	160	160	755	160	160
					3.58	0.71	0.71	3.36	0.71	0.71
H2.5T	18	(5) 8d	(5) 8d	—	835	175	210	740	160	210
					3.71	0.78	0.93	3.29	0.71	0.93
SS H3	18	(4) 8d	(4) 8d	—	740	180	265	615	125	190
					3.29	0.80	1.18	2.74	0.56	0.85
H6	16	—	(8) 8d	(8) 8d	1585	1085	—	1125	770	—
					7.05	4.83	—	5.00	3.43	—
H7Z	16	(4) 8d	(2) 8d	(8) 8d	1390	670	—	990	475	—
					6.18	2.98	—	4.40	2.11	—
SS H8 ³	18	(5) 10d x 1½"	(5) 10d x 1½"	—	1120	—	—	1025	—	—
					4.98	—	—	4.56	—	—
SS H10A ⁹	18	(9) 10d x 1½"	(9) 10d x 1½"	—	1735	795	410	1505	565	290
					7.72	3.54	1.82	6.69	2.51	1.29
H10AR	18	(9) 10d x 1½"	(9) 10d x 1½"	—	1485	690	430	1220	570	305
					6.61	3.07	1.91	5.43	2.54	1.36
H10A-2	18	(9) 10d x 1½"	(9) 10d x 1½"	—	1835	1275	430	1645	880	305
					8.16	5.67	1.91	7.32	3.91	1.36
H10S ^{7,3}	18	(8) 8d x 1½"	(8) 8d x 1½"	(8) 8d	1465	795	315	1040	565	225
					6.52	3.54	1.40	4.63	2.51	1.00
H11Z	18	(6) 16d x 2½"	(6) 16d x 2½"	—	1095	920	545	780	655	390
					4.87	4.09	2.42	3.47	2.91	1.73
H14	18	1 (12) 8d x 1½"	(13) 8d	—	2390	855	320	1805	610	230
					10.63	3.80	1.42	8.03	2.71	1.02
		2 (12) 8d x 1½"	(15) 8d	—	2390	855	320	1805	610	230
					10.63	3.80	1.42	8.03	2.71	1.02
TSP	16	(9) 10d x 1½"	(6) 10d x 1½"	—	1295	440	—	920	310	—
					5.76	1.96	—	4.09	1.38	—
		(9) 10d x 1½"	(6) 10d	—	1560	440	—	1105	310	—
					6.94	1.96	—	4.92	1.38	—

- Factored resistances have been increased 15% for short term loading; no further increase is allowed.
- Factored resistances are for one anchor. A minimum rafter thickness of 2½" must be used when framing anchors are installed on the same side of the plate (exception: H2.5A).
- H8 factored uplift resistances for stud-to-bottom plate installations are 595 lb. (2.65 kN) for D.Fir-L and 390 lb. (1.74 kN) for S-P-F.
- When cross-grain bending or cross-grain tension cannot be avoided, mechanical reinforcement to resist such forces should be considered.
- Hurricane ties are shown installed on the outside of the wall for clarity. Installation on the inside of the wall is acceptable. For a continuous load path, connections at the top and bottom of the wall must be on the same side of the wall (see technical bulletin T-HTIECONPATH).
- Factored resistances in the F₁ direction are not intended to replace diaphragm boundary members or prevent cross grain bending of the truss or rafter members. Additional shear transfer elements shall be considered where there may be effects of cross grain bending or tension.

- H10S can have the stud offset a maximum of 1" from the rafter (centre to centre) for a reduced uplift of 1435 lb. (6.38 kN) D.Fir-L and 1015 lb. (4.51 kN) S-P-F.
- H10S nails to plates are optional for uplift but required for lateral loads.
- H10A may be field-bent up to a slope of 6/12. Multiply the tabulated uplift value x 0.75. Full tabulated lateral resistances apply.
- The factored resistances of stainless-steel connectors match carbon-steel connectors when installed with Simpson Strong-Tie® stainless-steel, SCNR ring-shank nails. For more information, refer to engineering letter L-F-SSNAILS at strongtie.com.
- D.Fir-L/S-P-F factored uplift resistances for the H2.5A fastened to a 2x4 truss bottom chord and double top plates using (5) 8d x 1½" nails into the top plates and (3) 8d x 1½" nails into the lowest three flange holes into the truss bottom chord is 495 lb. (2.20 kN).
- Nails:** 16d x 2½" = 0.162" dia. x 2½" long, 10d = 0.148" dia. x 3" long, 10d x 1½" = 0.148" dia. x 1½" long, 8d = 0.131" dia. x 2½" long, 8d x 1½" = 0.131" dia. x 1½" long. See pp. 27–28 for other nail sizes and information.



BEARING ANCHORAGE BY TOE-NAILS FOR LATERAL CAPACITY

B97791H1

NAIL TYPE	LENGTH (IN)	DIAMETER (IN)	NAIL LATERAL CAPACITY (LB)	
			S-P-F	D. FIR
COMMON WIRE	3.00	0.144	132	147
	3.25	0.144	132	147
	3.50	0.160	159	177
COMMON SPIRAL	3.00	0.122	97	108
	3.25	0.122	97	108
	3.50	0.152	145	162

NOTES:

1. Rafter and ceiling members may be anchored to top and bottom chords of girder truss by toe-nailing rafter and ceiling members to girder chords provided the reaction does not exceed the lateral capacities in the table. Hangers (specified by others) are required for reactions higher than the maximum toe-nail capacity. Reactions are based on factored loads.
2. Toe nail capacities shown in the table are for **one** toe-nail. For additional toe-nails multiply values in table by the number of toe-nails used. Toe-nail capacities take into account toe-nailing factor J_A in CSA O86-14, section 12.9.4.1.
3. For 9- 3/4 gauge 3.25" common wire gun nails (diameter = 0.120") use 3" common spiral nail values.
4. Maximum number of toe-nails allowed depends on the lumber size & species to be toe-nailed to supporting member and nail diameter, as shown in tables below.
5. Nail values in table are based on the following relative lumber densities: $G = 0.42$ (SPF), $G = 0.49$ (D. Fir).
6. Toe-nails shall be driven at approximately 1/3 the nail length from the edge of the joist/truss chord and driven at an angle of 30° to the grain of the member (See next page for nailing on bearing plate).
7. For loads due to **wind** the nail lateral capacity in this table may be multiplied by 1.15 (K_D factor).
8. Lumber must be dry (< 19% moisture content) at the time of nail installation.
9. Nail values in this table comply with CSA O86-14, section 12.9.4
10. This design is not valid after March 31, 2021.




TOE-NAIL INSTALLATION

Nail type	Common wire	Common spiral	Common wire	Common spiral
Nail dia. (in)	0.160	0.152	0.144	0.122
	(3.5" nail)		(3" and 3.25" nail)	
LUMBER SIZE	MAXIMUM NUMBER OF TOE-NAILS			
2X4 SPF	2	2	3	3
2X4 D. Fir	2	2	2	2
2X6 SPF	4	4	4	5
2X6 D. Fir	3	3	3	4

MiTek® MiTek Canada Inc
100 Industrial Rd.
Bradford, Ontario L3Z 3G7

December 2, 2019



BEARING ANCHORAGE BY TOE-NAILS FOR WIND LOADING

B97791H2



NAIL TYPE	LENGTH (IN)	DIAMETER (IN)	NAIL WITHDRAWAL CAPACITY (LB)	
			S-P-F	D. FIR
COMMON WIRE	3.00	0.144	30	42
	3.25	0.144	32	45
	3.50	0.160	38	52
COMMON SPIRAL	3.00	0.122	26	36
	3.25	0.122	28	40
	3.50	0.152	36	50

Note: If using truss with D. Fir lumber and S-P-F bearing plate, use values in table for S-P-F.



NOTES:

1. Truss chord, rafter, or ceiling members may be anchored to bearing plate by toe-nails, provided that the actual factored uplift force due to **wind** or **earthquake** load does not exceed the withdrawal capacities in the table. Hangers (specified by others) are required for uplift forces that are higher than the maximum toe-nail withdrawal capacity.
2. Toe nail capacities shown in the table are for **one** toe-nail. For additional toe-nails multiply values in table by the number of toe-nails used. Toe-nail capacities take into account toe-nailing factor J_A in CSA O86-14, section 12.9.5.2.
3. For 9- 3/4 gauge 3.25" common wire gun nails (diameter = 0.120") use 3" common spiral nail values.
4. Maximum number of toe-nails allowed depends on the lumber size & species to be toe-nailed to supporting member and nail diameter, as shown in table above.
5. Nail values in table are based on the following relative lumber densities: G = 0.42(SPF), G = 0.49(D. Fir).
6. Toe-nails shall be driven at approximately 1/3 the nail length from the edge of the joist/truss chord and driven at an angle of 30° to the grain of the member (See drawing on detail B37579H1).
7. Lumber must be dry (< 19% moisture content) at the time of nail installation.
8. Nail values in this table comply with CSA O86-14, section 12.9.5
9. This design is not valid after March 31, 2021.

Toe-nailing on 2x6 Bearing Plate



Toe-nailing on 2x4 Bearing Plate



MiTek®

MiTek Canada Inc
100 Industrial Rd.
Bradford, Ontario L3Z 3G7




PEO
Certificate No. 10889485



December 2, 2019

Symbols

PLATE LOCATION AND ORIENTATION



*Plate location details available in MiTek software or upon request.

PLATE SIZE

4 x 4

The first dimension is the plate width measured perpendicular to slots. Second dimension is the length parallel to slots.

LATERAL BRACING LOCATION



Indicated by symbol shown and/or by text in the bracing section of the output. Use T, I or Eliminator bracing if indicated.

BEARING





Indicates location where bearings (supports) occur. Icons vary but reaction section indicates joint number where bearings occur.

Industry Standards:

- TPIC: Truss Design Procedures and Specifications for Light Metal Plate Connected Wood Trusses
DSB-89: Design Standard for Bracing.
BCSI: Building Component Safety Information, Guide to Good Practice for Handling, Installing & Bracing of Metal Plate Connected Wood Trusses.

Numbering System



JOINTS ARE GENERALLY NUMBERED/LETTERED CLOCKWISE AROUND THE TRUSS STARTING AT THE JOINT FARTHEST TO THE LEFT.

CHORDS AND WEBS ARE IDENTIFIED BY END JOINT NUMBERS/LETTERS.

PRODUCT CODE APPROVALS

CCMC Reports:

11996-L, 10319-L, 13270-L, 12691-R

© 2007 MiTek® All Rights Reserved

MiTek
POWER TO PERFORM.™

MiTek Engineering Reference Sheet: MII-7473C rev. 10-'08

General Safety Notes

Failure to Follow Could Cause Property Damage or Personal Injury


1. Additional stability bracing for truss system, e.g. diagonal or X-bracing, is always required. See BCSI.
2. Truss bracing must be designed by an engineer. For wide truss spacing, individual lateral braces themselves may require bracing, or alternative T, I, or Eliminator bracing should be considered.
3. Never exceed the design loading shown and never stack materials on inadequately braced trusses.
4. Provide copies of this truss design to the building designer, erection supervisor, property owner and all other interested parties.
5. Cut members to bear tightly against each other.
6. Place plates on each face of truss at each joint and embed fully. Knots and wane at joint locations are regulated by TPIC.
7. Design assumes trusses will be suitably protected from the environment in accord with TPIC.
8. Unless otherwise noted, moisture content of lumber shall not exceed 19% at time of fabrication.
9. Unless expressly noted, this design is not applicable for use with fire retardant, preservative treated, or green lumber.
10. Camber is a non-structural consideration and is the responsibility of truss fabricator. General practice is to camber for dead load deflection.
11. Plate type, size, orientation and location dimensions indicated are minimum plating requirements.
12. Lumber used shall be of the species and size, and in all respects, equal to or better than that specified.
13. Top chords must be sheathed or purlins provided at spacing indicated on design.
14. Bottom chords require lateral bracing at 10 ft. spacing, or less, if no ceiling is installed, unless otherwise noted.
15. Connections not shown are the responsibility of others.
16. Do not cut or alter truss member or plate without prior approval of an engineer.
17. Install and load vertically unless indicated otherwise.
18. Use of green or treated lumber may pose unacceptable environmental, health or performance risks. Consult with project engineer before use.
19. Review all portions of this design (front, back, words and pictures) before use. Reviewing pictures alone is not sufficient.
20. Design assumes manufacture in accordance with TPIC Quality Criteria.

Overview:

Where piggybacks are connected overtop of base trusses, 2x4 purlins must be first added to the flat portion of the base truss at a spacing no more than 24" o/c. These purlins not only provide support for the piggyback trusses above, but are required to laterally support the top chord of the base truss which will not have the sheathing directly connected to the flat portion of the base truss. This ensures the top chord, most often in compression, will not buckle laterally.

Further, the purlins in the plane of the flat portion require diagonal bracing to prevent lateral displacement of the purlins themselves where under certain conditions, the trusses may in fact all buckle in the same direction if this additional bracing is not added in the plane of the purlins.

Detail:




NOTE: THE SLOPED PORTION OF THE TOP CHORD OF THE BASE TRUSS AND PIGGYBACK TRUSS IN THIS SKETCH IS ASSUMED TO BE SHEATHED IN ACCORDANCE WITH THE OBC.

SKETCH FROM BCSI-CANADA 2013

Disclaimer:

OWTFA Tech Notes are intended to provide guidance to the design community both within the membership as well as to third party designers who might benefit from the information. The details have been developed by the OWTFA technical committee and although there may be professional engineers involved in development, the information contained in the tech-note are not intended to be used without having a professional engineer review the information for a specific application. The OWTFA takes no responsibility with respect to the information provided but has developed this tech-note to offer guidance where it is not currently readily available.



Alves Engineering Services Inc.

5208 Easton road
Burlington, Ontario L7L 6N6
(289) 259 5455

RESPONSABILITIES

- 1-Alves Engineering Services Inc. is responsible for the design of trusses as individual components
- 2-It is the responsibility of others to ascertain that the design loads utilized on this drawing meet or exceed the actual dead load imposed by the structure and the live load imposed by the local building code or the authorities having jurisdictions.
- 3- All dimensions are to be verified by owner, contractor, architect or other authority before manufacture.
- 4- Alves Engineering Services Inc. bears no responsibility for the erection of the trusses. Persons erecting trusses are cautioned to seek professional advice regarding temporary and permanent bracing system. Bracing shown on Alves Engineering Services Inc. drawings is specified for the truss as a single component and forms an integral part of the truss design, but is not meant to represent the only required bracing for that truss when trusses are installed in a series of trusses forming a roof truss system.
- 5- It is the manufactures responsibility to ensure that the trusses are manufactured in conformance with Alves Engineering Services Inc. specifications outlined below.

SPECIFICATIONS

- 1-Truss components sealed by Alves Engineering Services Inc. conform to the relevant sections of the current Building Code of Ontario and Canada (part 4 or part 9) or the current Canadian code for Farm Buildings in accordance with the application specified on the sealed truss component drawing. All truss component design procedures must conform to the current design standard issued by the truss plate institute of Canada (TPIC). All lumber and nailing stresses to conform to the current CSA wood design standard identified on the current Building Code and TPIC.
- 2- Lumber is to be the sizes and grade specified on the truss drawing.
- 3- Moist content of lumber is not to exceed 19% in service unless otherwise specified.
- 4- Plates shall be applied to both faces of the each truss joint and shall be positioned as shown on the truss drawings
- 5- Lumber used on manufacture of trusses is not to be treated with chemicals unless otherwise specified on the truss drawings.
- 6- The top chord is assumed to be continuously laterally braced by the roof sheathing or purlins at intervals specified on the truss drawing but not exceeding 24" c/c for (part 9) and not exceeding 48" for (part 4 or farm design)
- 7- When rigid ceiling is not attached directly to the bottom chord, lateral bracing is required and it should not exceed more than 3m or 10' intervals.
- 8-Refer to Mitek sheet MII7473C REV.10-08 attached for information on symbols, numbering system and General Safety notes.

T-1900213

Feb 09, 2018