

CONSTRUCTION SUMMARY

Mountainview Heights 3 (G) - Russell Gardens Building Ltd.

PURCHASERS: MUBASHRA SIDDIQA and IJAZ MIRZA AHMAD

TEL:

LOT / PHASE 181 / 3	REG. PLAN # 62M-1266	HOUSE TYPE Mountainash Five (4 Bedroom) Elev 1		
------------------------	-------------------------	---	--	--

CABINETRY

1 - KITCHEN - DELETE CABINETS ABOVE STOVE - VENDOR WILL SUPPLY 6 INCH VENT AS PER CONSTRUCTION SPECIFICATIONS AND VENT MAY NOT BE IN THE APPROPRIATE LOCATION FOR INSTALLATION OF PURCHASER SUPPLIED VENT - PURCHASER TO SUPPLY OWN FAN AFTER CLOSING 09Aug21 Note: TEMPORARY HOOD FAN MAY BE PROVIDED	
1 - CABINETRY - KITCHEN - LIGHT VALENCE 09Aug21 Note:	
1 - CABINETRY - KITCHEN - UPGRADE 5 ON PERIMETER AND WET BAR WITH UPGRADE 4 ON ISLAND 09Aug21 Note:	

CABINETRY ACCESSORIES

1 - KITCHEN - DELETE PANTRY TO ACCOMMODATE LARGER FRIDGE 09Aug21 Note:	
2 - CABINETRY DECORATIVE ITEMS - LEGS - TRAFALGAR BASE LEGS - INSTALLED ON ISLAND - KICTHEN 09Aug21 Note:	
1 - KITCHEN - CREATE OPENING ON WET BAR FOR FUTURE BEVERAGE FRIDGE 09Aug21 Note:	
1 - KITCHEN CABINETRY - BUILT-IN FRIDGE CABINET - PRICE IS EACH 09Aug21 Note:	
1 - KITCHEN CABINETRY UPPER - FULL DEPTH ABOVE FRIDGE - WITH GABLES - 600MM - PRICE IS EACH - UPGRADE 5 09Aug21 Note:	
1 - KITCHEN - BLU MOTION DRAWERS 09Aug21 Note:	
1 - KITCHEN - SOFT CLOSING CABINETRY 09Aug21 Note:	
4 - KITCHEN CABINETRY UPPER - GLASS DOOR - WATERFALL - FINISHED INTERIOR - FITS TALL UPPER CABINETS - PRICE IS PER DOOR - UPGRADE 5 09Aug21 Note:	
1 - KITCHEN CABINETRY BASE - PULLOUT RECYCLE 4 BIN - PRICE IS EACH 09Aug21 Note:	
1 - KITCHEN CABINETRY - BUILT-IN MICROWAVE/OVEN COMBO - UPGRADE 5 09Aug21 Note:	

CERAMIC TILE

1 - TILE - UPGRADE 4 WALL TILE - - ENSUITE WALL TILE - SHOWER 09Aug21 Note:	
1 - TILE - UPGRADE 4 FLOOR TILE - - ENSUITE BATHROOM - FLOOR 09Aug21 Note:	
1 - DELETE ALL CERAMIC BATHROOM ACCESSORIES - DELETE TOWEL BAR, PAPER HOLDER & SOAP DISH THROUGHOUT 09Aug21 Note:	

CONSTRUCTION SUMMARY

Mountainview Heights 3 (G) - Russell Gardens Building Ltd.

PURCHASERS: MUBASHRA SIDDIQA and IJAZ MIRZA AHMAD

TEL:

LOT / PHASE	REG. PLAN #	HOUSE TYPE		
181 / 3	62M-1266	Mountainash Five (4 Bedroom) Elev 1		
1 - TILE - UPGRADE 4 WALL TILE - - BATHROOM 3/4 - TUB AREA 09Aug21 Note:				
1 - TILE - UPGRADE 4 FLOOR TILE - - BATHROOM 3/4 - FLOOR 09Aug21 Note:				
1 - TILE - UPGRADE 4 WALL TILE - - BATHROOM 2 - SHOWER 09Aug21 Note:				
1 - TILE - UPGRADE 4 FLOOR TILE - - BATHROOM 2 - FLOOR 09Aug21 Note:				
1 - TILE - UPGRADE 4 FLOOR TILE - - POWDER ROOM 09Aug21 Note:				
1 - TILE - UPGRADE 4 FLOOR TILE - - MUD ROOM 09Aug21 Note:				
1 - TILE - UPGRADE 4 FLOOR TILE - - KITCHEN 09Aug21 Note:				
1 - TILE - UPGRADE 4 FLOOR TILE - - FOYER 09Aug21 Note:				

CONSTRUCTION

1 - FAMILY ROOM - WAFFLE CEILING - 9 BOXES 09Aug21 Note:				
1 - SMOOTH CEILINGS ON FIRST FLOOR ONLY - DET 09Aug21 Note:				
1 - KITCHEN – PROVISIONS FOR POT FILLER 09Aug21 Note:				

COUNTER TOP

1 - QUARTZ BACKSPLASH - FULL HEIGHT - INCLUDES BEHIND FUTURE CHIMNEY HOOD - KITCHEN 09Aug21 Note:				
1 - COUNTER TOP - UPGRADE - KITCHEN COUNTER TOP 09Aug21 Note:				
1 - COUNTER TOP - UPGRADE - POWER ROOM VANITY COUNTER TOP 09Aug21 Note:				
1 - COUNTER TOP - UPGRADE - ENSUITE BATHROOM VANITY COUNTER TOP 09Aug21 Note:				
1 - COUNTER TOP - UPGRADE - ENSUITE BATHROOM 3/4 VANITY COUNTER TOP 09Aug21 Note:				
1 - COUNTER TOP - UPGRADE - ENSUITE BATHROOM 2 VANITY COUNTER TOP 09Aug21 Note:				

DOORS AND TRIM

CONSTRUCTION SUMMARY

Mountainview Heights 3 (G) - Russell Gardens Building Ltd.

PURCHASERS: MUBASHRA SIDDIQA and IJAZ MIRZA AHMAD

TEL:

LOT / PHASE 181 / 3	REG. PLAN # 62M-1266	HOUSE TYPE Mountainash Five (4 Bedroom) Elev 1		
------------------------	-------------------------	---	--	--

1 - TRIM - UPGRADE 2- 7-¼” BASEBOARD AND 3” CASING

09Aug21 Note:

ELECTRICAL

1 - 200 AMP ELECTRICAL SERVICE

09Aug21 Note:

1 - PLUG - ELECTRICAL PLUG - FOR BEVERAGE FRIDGE

09Aug21 Note:

1 - KITCHEN - CANOPY HOOD FAN - 36" CYCLONE 550 CFM #SC51336

09Aug21 Note:

1 - KITCHEN - VALANCE LIGHTING - LED LIGHTING

09Aug21 Note:

1 - BUILT IN OVEN AND MICROWAVE PROVISION - PROVISION ONLY - ELECTRICAL ONLY

09Aug21 Note:

1 - LIGHT - EXTERIOR WITH INTERIOR SWITCH - REAR ELEVATION - INSTALLED ON SAME SWITCH AS STANDARD LIGHT

09Aug21 Note:

1 - LIGHT - EXTERIOR WITH INTERIOR SWITCH - FRONT PORCH - WIRED TO SAME SWITCH AS STANDARD LIGHT

09Aug21 Note:

3 - FAN - BATHROOM EXHAUST FAN - ENERGY STAR 80 CFM - IN LIEU OF STANDARD FAN - ALL ENSUITE BATHROOMS

09Aug21 Note:

1 - ABOVE KITCHEN ISLAND - ADD LIGHT AND SWITCH - NO FIXTURE INCLUDED

09Aug21 Note:

1 - PLUG - ELECTRICAL PLUG - TO BE INSTALLED OVER FIREPLACE

09Aug21 Note:

1 - LIGHT AND SWITCH - NO FIXTURE INCLUDED - LIVING ROOM

09Aug21 Note:

FIREPLACE AND ACCESSORIES

1 - FIREPLACE SURROUND - UPGRADE TO GRANITE IN LIEU OF MARBLE

09Aug21 Note:

1 - GAS LINE ROUGH-IN FOR BARBECUE - FIRST FLOOR

09Aug21 Note:

1 - GAS LINE ROUGH-IN FOR STOVE (INCLUDES ELECTRICAL OUTLET) - FIRST FLOOR

09Aug21 Note:

HARDWOOD FLOORING

1 - LAMINATE – UPGRADE TO FJORD SERIES IN LIEU OF STANDARD LAMINATE

09Aug21 Note:

1 - HARDWOOD - GROUP B SERIES 6 1/2 INCH - - UPPER HALL

09Aug21 Note:

CONSTRUCTION SUMMARY

Mountainview Heights 3 (G) - Russell Gardens Building Ltd.

PURCHASERS: MUBASHRA SIDDIQA and IJAZ MIRZA AHMAD

TEL:

LOT / PHASE	REG. PLAN #	HOUSE TYPE		
181 / 3	62M-1266	Mountainash Five (4 Bedroom) Elev 1		
1 - HARDWOOD - GROUP B SERIES 6 1/2 INCH - IN LIEU OF 2 1/4 INCH NATURAL RED OAK - - MAIN HALL 09Aug21 Note:				
1 - HARDWOOD - GROUP B SERIES 6 1/2 INCH - IN LIEU OF 2 1/4 INCH NATURAL RED OAK - - LIVING AND DINING ROOM 09Aug21 Note:				
1 - HARDWOOD - GROUP B SERIES 6 1/2 INCH - IN LIEU OF 2 1/4 INCH NATURAL RED OAK - - LIBRARY/DEN 09Aug21 Note:				
1 - HARDWOOD - GROUP B SERIES 6 1/2 INCH - IN LIEU OF 2 1/4 INCH NATURAL RED OAK - - FAMILY ROOM 09Aug21 Note:				

PLUMBING

1 - SINK - UNDERMOUNT SINK - BLANCO QUATRUS R15 U BAR #401515 09Aug21 Note:				
4 - SINK - UNDERMOUNT SINK - TECO BATH #4815 - ENSUITE BATHROOMS 09Aug21 Note:				
1 - SINK - UNDERMOUNT SINK - CONTRAC EMERY #4220CGY - POWDER ROOM 09Aug21 Note:				
4 - MOEN BATHROOM ACCESSORIES - MASON CHROME - TOWEL BAR 24" #YB8094/YB8000 - ALL BATHROOMS 09Aug21 Note:				
4 - MOEN BATHROOM ACCESSORIES - MASON CHROME - PAPER HOLDER #YB8099/YB8000 -ALL BATHROOMS 09Aug21 Note:				
1 - SOAP DISPENSER - CHROME FINISH - MOEN S3948C - KITCHEN 09Aug21 Note:				
1 - SINK - UNDERMOUNT SINK - BLANCO QUATRUS R15 U SUPER SINGLE #401518 09Aug21 Note:				
1 - KITCHEN – POT FILLER – MOEN TRADITIONAL TWO HANDLE POT FILLER FAUCET WITH DUAL SHUT OFFS – #S664 CHROME 09Aug21 Note:				
1 - WATER LINE FOR FRIDGE - ROUGH-IN ONLY 09Aug21 Note:				

PROMOTIONAL

1 - LESS CREDIT FROM PURCHASER EXTRA SHEET IN OFFER 09Aug21 Note:				
--	--	--	--	--

STAIRS AND RAILINGS

1 - STAINED STAIRS – STANDARD STAIRCASE - PRICE IS PER SET 09Aug21 Note:				
1 - STAIRCASE - V GROOVE HANDRAIL 09Aug21 Note:				
1 - STAIRCASE - 4 X 4 POSTS 09Aug21 Note:				

CONSTRUCTION SUMMARY

Mountainview Heights 3 (G) - Russell Gardens Building Ltd.

PURCHASERS: MUBASHRA SIDDIQA and IJAZ MIRZA AHMAD

TEL:

LOT / PHASE 181 / 3	REG. PLAN # 62M-1266	HOUSE TYPE Mountainash Five (4 Bedroom) Elev 1		
1 - STAIRCASE - EUROLINE 1 IRON PICKETS - BLACK 09Aug21 Note:				

EXTRAS AS PER OFFER

(1) The Vendor agrees that notwithstanding any other term or provision in this Agreement included in the Purchase Price and in addition to those items detailed in Schedule GP to the Agreement of Purchase and Sale, the Purchaser is entitled to a credit of Worksheet Note:	
10 foot ceiling height on Main Floor. The Purchaser acknowledges that as a result of the increased ceiling height from the Vendor?s standard ceiling height, various modifications to the interior and exterior of the dwelling unit may be made, including bu Worksheet Note:	
Purchase Price includes 3 enlarged basement windows, and the obligation to construct the house with the enlarged basement windows is subject to the Vendor?s approval, in its sole and unfettered discretion The Purchaser acknowledges and agrees that the lo Worksheet Note:	
PURCHASER(S) ACKNOWLEDGES THAT THE PURCHASE PRICE IS INCLUSIVE OF ALL CREDITS AND PROMOTIONAL PACKAGES AVAILABLE AT TIME OF PURCHASE. Worksheet Note:	

This Document is Extremely Time Sensitive - Printed 9 Aug 21 at 16:25

Purchasers:
Telephone Res. / Bus:
Decor Advisor:
Lock Date:

MUBASHRA SIDDIQA & IJAZ MIRZA AHMAD
/
Candace Forza
9-Aug-21

Property: 181
Project: Russell Gardens Building Ltd.
Model and Elevation: Mountainash Five (4 Bedroom) Elev 1
9-Aug-21
Plan #: 62M-1266

Layout Changes: ☒ Yes ☐ No

Sketch Attached: ☒ Yes ☐ No

Exterior Colour Scheme:

1. Cabinetry

	Style and Colour	Hardware
Kitchen / Breakfast	SEE BELOW	446SA
Laundry Room	ELISSE	Standard
Powder Room	EVEREST WHITE	431SA
Master Ensuite Bathroom	CONTINENTAL 823 DRIFTWOOD	431SA
Ensuite Bath - Bedroom 2	CONTINENTAL 350 PLATINUM SILVER	431SA
Ensuite Bath - Bedroom 3/4	CONTINENTAL 350 PLATINUM SILVER	431SA
	N/A	N/A
	N/A	N/A
	N/A	N/A

Appliances:

Built In Appliances ☒ Yes ☐ No

Slide In Stove ☐ Yes ☒ No

Dishwasher Cabinet

☐ Closed ☒ Open

41" Upper Cabinets ☒ Yes ☐ No

Please NOTE: Standard Cabinet Height is 30"

Stove Opening NOTE: If not specified, opening will be set to builder's standard opening of approximately 30" width

Fridge Opening NOTE: If not specified, opening will be set to builder's standard opening of approximately 37" width x 74" height

KITCHEN - PERIMETER & WET BAR - NINA 614 CRISP WHITE *** ISLAND - LEXINGTON 903 CHICKORY

** Refer to Construction Summary

2. Counters

	Counter	Edge
Kitchen / Breakfast	QUARTZITE-TERRA BIANCA	#360
Laundry Room	N/A	
Powder Room	MARBLE-SILVER PORTORO	#360
Master Ensuite Bathroom	QUARTZ-VICTORIA	#360
Ensuite Bath - Bedroom 2	QUARTZ-VICTORIA	#360
Ensuite Bath - Bedroom 3/4	QUARTZ-MISTRAL	#360
	N/A	
	N/A	
	N/A	

** Refer to Construction Summary

Purchasers:

MUBASHRA SIDDIQA & IJAZ MIRZA AHMAD

Property: 181

Telephone Res. / Bus:

/

Project: Russell Gardens Building Ltd.

Decor Advisor:

Candace Forza

Model and Elevation: Mountainash Five (4 Bedroom) Elev 1

Lock Date:

9-Aug-21

9-Aug-21

Plan #: 62M-1266

3. Ceramic Flooring

		At a 45	Threshold-If App.
Entrance Vestibule	TILE-CALACATTA POLISHED (CA6083P)-24X24	☐	metal strip where applicable
Main Hall	STRIP	☐	
Kitchen / Breakfast	TILE-CALACATTA POLISHED (CA6083P)-24X24	☐	
Laundry Room	TILE-ESSENZE BIANCO-13X13	☐	
Powder Room	TILE-CALACATTA POLISHED (CA6083P)-24X24	☐	
Master Ensuite Bathroom	TILE-VARENNA CARRARA POLISHED-24X24	☐	
Ensuite Bath - Bedroom 2	TILE-VARENNA CARRARA POLISHED-12X24	☐	
Ensuite Bath - Bedroom 3/4	TILE-TRAVERTINO MEM BIANCO POL-24X24	☐	
Mud Room	TILE-CALACATTA POLISHED (CA6083P)-24X24	☐	
	N/A	☐	
	N/A	☐	

** Refer to Construction Summary

4. Ceramic Wall Tile

	Selection	Describe
Master Ensuite Bathroom		
Tub Deck Wall	N/A	
Tub Deck	N/A	
Tub Deck Skirt	N/A	
Shower Stall	TILE-VARENNA CARRARA POLISHED-12X24	
Bathtub Enclosure Walls	N/A	
Ensuite Bath - Bedroom 2	TILE-VARENNA CARRARA POLISHED-12X24	
Ensuite Bath - Bedroom 3/4	TILE-TRAVERTINO MEM BIANCO POL-12X24	
Mud Room	N/A	
	N/A	
	N/A	
Kitchen Backsplash	QUARTZITE-TERRA BIANCA	FULL HEIGHT

** Refer to Construction Summary - STANDARD GROUT THROUGHOUT UNLESS SPECIFIED

5. Plumbing Fixtures

All Bathrooms

White

N/A

N/A

N/A

N/A

N/A

Whirlpool

N/A

☐ Yes ☒ No

Dishwasher Rough-In

☒ Yes ☐ No

Waterline for Fridge

☒ Yes ☐ No

** Refer to Construction Summary

6. Trim Carpentry

Interior Doors	CARRARA-SMOOTH
Interior Trim	3" BB CASING WITH 7 1/4" BASEBOARD - COLONIAL
Door Handles	As Per Construction Specifications
Exterior Front Door Handle	As Per Construction Specifications

** Refer to Construction Summary

Initials:

I.J.

MS

Purchasers:

MUBASHRA SIDDIQA & IJAZ MIRZA AHMAD

Property: 181

Telephone Res. / Bus:

/

Project: Russell Gardens Building Ltd.

Decor Advisor:

Candace Forza

Model and Elevation: Mountainash Five (4 Bedroom) Elev 1

Lock Date:

9-Aug-21

9-Aug-21

Plan #: 62M-1266

7. Other Flooring

Main Hall	STRIP-VINTAGE-NORTHERN SOLID SAWN-CHARACTER-PEARL-WHITE OAK-GOTHAM-3/4 X 6 1/2"
Living Room	STRIP-VINTAGE-NORTHERN SOLID SAWN-CHARACTER-PEARL-WHITE OAK-GOTHAM-3/4 X 6 1/2"
Dining Room	STRIP-VINTAGE-NORTHERN SOLID SAWN-CHARACTER-PEARL-WHITE OAK-GOTHAM-3/4 X 6 1/2"
Family Room	STRIP-VINTAGE-NORTHERN SOLID SAWN-CHARACTER-PEARL-WHITE OAK-GOTHAM-3/4 X 6 1/2"
Den / Library / Study	STRIP-VINTAGE-NORTHERN SOLID SAWN-CHARACTER-PEARL-WHITE OAK-GOTHAM-3/4 X 6 1/2"
Basement Landing(If Applies)	N/A
Lower Landing (If Applies)	STRIP-VINTAGE-NORTHERN SOLID SAWN-CHARACTER-PEARL-WHITE OAK-GOTHAM-3/4 X 6 1/2"
Upper Landing	STRIP-VINTAGE-NORTHERN SOLID SAWN-CHARACTER-PEARL-WHITE OAK-GOTHAM-3/4 X 6 1/2"
Upper Hall	STRIP-VINTAGE-NORTHERN SOLID SAWN-CHARACTER-PEARL-WHITE OAK-GOTHAM-3/4 X 6 1/2"
Master Bedroom	LAMINATE-FJORD-ASTRID OAK-TL-NEUM06
Bedroom #2	LAMINATE-FJORD-ASTRID OAK-TL-NEUM06
Bedroom #3	LAMINATE-FJORD-ASTRID OAK-TL-NEUM06
Bedroom #4	LAMINATE-FJORD-ASTRID OAK-TL-NEUM06LAMINATE-FJORD-ASTRID OAK-TL-NEUM06
Bedroom #5	N/A
	N/A
	N/A
	N/A
Underpad	TypeArea
	N/AN/A

** Refer to Construction Summary

8. Railings and Pickets

Railing Type	4X4 POSTS & V-GROOVE	Colour	VINTAGE GOTHAM WHITE OAK COLOUR
Picket Type	EUROLINE 1	Colour	BLACK
Stringer / Riser	AS PER CONSTRUCTION SPECIFICATIO	Colour	VINTAGE GOTHAM WHITE OAK COLOUR
Treads	AS PER CONSTRUCTION SPECIFICATIO	Colour	VINTAGE GOTHAM WHITE OAK COLOUR
Red Oak Stairs with Semi Gloss Finish		☒ Yes ☐ No	

** Refer to Construction Summary THE STAIN COLOURS OR FINISH AVAILABLE ON RISERS, TREADS, PICKETS AND RAILS (STAIRCASES), WILL NOT BE AN EXACT MATCH TO PREFINISHED HARDWOOD OR LAMINATE FLOORS.

9. Wall Paint Flat Finish

Main & Upper Hall	22 WARM GREY	Master Bedroom	22 WARM GREY
Living Room	22 WARM GREY	Bedroom #2	22 WARM GREY
Dining Room	22 WARM GREY	Bedroom #3	22 WARM GREY
Kitchen / Breakfast	22 WARM GREY	Bedroom #4	22 WARM GREY
Family Room	22 WARM GREY	Bedroom #5	N/A
Powder Room	22 WARM GREY	Master Ensuite	22 WARM GREY
Laundry Room	22 WARM GREY	Ensuite Bath - Bedroom 2	22 WARM GREY
Den/Library	22 WARM GREY	Ensuite Bath - Bedroom 3/4	22 WARM GREY
Trim Paint-Semi Gloss	BIRCH WHITE	MUD ROOM	22 WARM GREY
	N/A		N/A
	N/A		N/A

Smooth Ceilings First Floor ☒ Yes ☐ No

** Refer to Construction Summary

Initials: I.J M.S

Purchasers: MUBASHRA SIDDIQA & IJAZ MIRZA AHMAD **Property:** 181
Telephone Res. / Bus: / **Project:** Russell Gardens Building Ltd.
Decor Advisor: Candace Forza **Model and Elevation:** Mountainash Five (4 Bedroom) Elev 1
Lock Date: 9-Aug-21 9-Aug-21 **Plan #:** 62M-1266

10. Plaster Mouldings and Medallions

Entrance Vestibule	N/A	N/A	Kitchen/Breakfast	N/A	N/A
Main Hall	N/A	N/A	Den/Library	N/A	N/A
Living Room	N/A	N/A	Lower Landing	N/A	N/A
Dining Room	N/A	N/A		N/A	N/A
Family Room	N/A	N/A		N/A	N/A

** Refer to Construction Summary

11. Fireplace

	Living Room			Family Room			Other Room - Specify		
	Purchased	As Per Plan	N/A	Purchased	As Per Plan	N/A	Purchased	As Per Plan	N/A
Fireplace Type	☐	☐	☒	☐	☒	☐	☐	☐	☒
Mantle Type	N/A			FLAT ON WALL			N/A		
Colour / Stain	N/A			MANTLE M2-STANDARD			N/A		
Surround	N/A			AS PER CONSTRUCTION SPECIFICATIONS			N/A		
Hearth	N/A			GRANITE-ALASKA WHITE			N/A		
				NO			N/A		

** Refer to Construction Summary

12. Heating and Air Conditioning

Air Conditioning	NO	Gas Provisions Stove	YES
Gas Provisions Dryer	NO	Gas Provisions Barbecue	YES
Comment			

** Refer to Construction Summary

13. Electrical

Plugs and Switches	☒ White	DECOR	Above Kitchen Cabinet Light	☐ Yes	☒ No
Hood Fan	CYCLONE CHIMNEY 36" #SC51336		Below Kitchen Cabinet Light	☒ Yes	☐ No
Appliances	Built in Cooktop	Built in Oven	Gas Stove	Microwave	
	☒ Yes ☐ No	☒ Yes ☐ No	☒ Yes ☐ No	☒ Yes ☐ No	
Dishwasher Rough-in	Yes				


** Refer to Construction Summary

14. General Comments

** Refer to Construction Summary

Disclaimers and Notes

- Colours of all materials are as close as possible to builder's selection, but not necessarily identical due to variances in manufacturing.
- Any extras listed above are null and void unless accompanied by a separate invoice/amendment. Said invoice must be paid in full.
- The Purchaser agrees that this colour selection is final and that no changes will be permitted, unless required by the Vendor.
- The Purchaser acknowledges reading and accepting document which contains other miscellaneous disclaimers.

Signature:  Date: Aug 9/21 Signature:  Date: Aug-09-2021

Lot 181
Russell Gardens.






Add Exterior Light
Add Life Line for BBQ

Provisions for Pet Filler.

Add Plug Above Fireplace

Waffle Ceiling & Boxes

Add Light Above Island



Electrical for B.I. Oven/micro
Electrical for Beverage fridge

Enlarge Basement Windows
200 AMP

10' Ceiling
Smooth ceilings
Additional Exterior Light

7.5 m.s


MOUNTAINASH FIVE ELEV. 1 • 3,288 sq.ft. | ELEV. 2 • 3,291 sq.ft. | ELEV. 3 • 3,298 sq.ft.

Orientation of home may be reversed and purchaser agrees to accept the same. Steps and porches may vary at any exterior entrance ways due to grading variance. Actual usable floor space may vary from the stated floor areas. All renderings are artist's concept. Dimensions, specifications and architectural detailing subject to modifications. Roofline and adjoining model types may vary due to siting. E. & D. E. May 2020


Kitchen

- Perimeter + Wet Bar
- upg 5 Nina
- Island
- upg 4 Lexington
- Light Valance
- Soft closing Cabinetry
- Blu motion Drawers
- Trafalgar Legs on Island

Create opening for Beverage Fridge



Waterfall Glass Doors



Selba Industries J#

W WDTH _____ W HGHT _____ W CNT _____
FLOOR HGHT _____ DOOR HGHT _____
ST. CENT _____ 2X4 _____ VENT BOX COVER _____

This drawing is the intellectual property of SELBA INDUSTRIES INC. and is an original design which must not be released or copied unless applicable fee has been paid or job order placed.



DESIGNER: KS
DATE: MAY 13 20


JOB NUMBER:
BUILDER: GREENPARK
SITE: RUSSELL GARDENS PH.3
MODEL: MOUNTAINASH 5X EL 1,2,3
LOT #:

27" (68.6 CM) AND 30" (76.2 CM) ELECTRIC SINGLE AND DOUBLE BUILT-IN OVEN

PRODUCT MODEL SERIES		
KODE300E	KODT100E	KOSE507E
KODE307E	KODT107E	KOST100E
KODE500E	WOD97EC0E	KOST107E
KODE507E	KOSE500E	WOS97EC0E

Electrical:
To properly install your oven, you must determine the type of electrical connection you will be using and follow the instructions provided for it here.

- Oven must be connected to the proper electrical voltage and frequency as specified on the model/serial number rating plate. The model/serial number rating plate is located under the control panel on single ovens and under the control panel on the upper oven cavity on double ovens. See the following illustrations.



- Single Oven**

A. Model/serial number plate


Double Oven

A. Model/serial number plate
- Models rated from 7.3 to 9.6 kW at 240 volts (5.4 to 7.4 kW at 208 volts) require a separate 40-amp circuit. Models rated at 4.8 kW and below at 240 volts (3.6 kW and below at 208 volts) require a separate 20-amp circuit.
 - A circuit breaker is recommended.
 - Connect directly to the circuit breaker box (or fused disconnect) through flexible, armored or nonmetallic sheathed, copper cable (with grounding wire). See "Make Electrical Connection" section.
 - Flexible conduit from the oven should be connected directly to the junction box.
 - Fuse both sides of the line.
 - Do not cut the conduit. The length of conduit provided is for serviceability of the oven.
 - A UL listed or CSA approved conduit connector must be provided.
 - If the house has aluminum wiring, follow the procedure below:
 - Connect a section of solid copper wire to the ends of the flexible conduit leads.
 - Connect the aluminum wiring to the added section of copper wire using special connectors and/or tools designed and UL listed for joining copper to aluminum.
 Follow the electrical connector manufacturer's recommended procedure. Aluminum/copper connection must conform with local codes and industry accepted wiring practices.

For power requirements for models MEW7527, MEW7530, MEW7627, MEW7630, MEW9537, MEW9627, MEW9530 and MEW9630, refer to the following table.

Voltage	Single Thermal	Single Convector	Double Thermal	Double Convector	Double Convector Thermal
240 VAC	4083 W	4141 W	8163 W	8279 W	8221 W
208 VAC	3088 W	3145 W	6172 W	6288 W	6230 W
240 VAC	17.4 A	17.8 A	34.7 A	35.7 A	35.2 A
208 VAC	15.1 A	15.6 A	30.2 A	31.2 A	30.7 A

PRODUCT DIMENSIONS



- 27" (68.6 cm) models**

A. 28 1/4" (72.8 cm) max. overall height

B. 25 1/8" (64.6 cm) max. recessed width

C. 26 3/4" (67.9 cm) recessed height

D. 23 1/4" (59.1 cm) max. recessed depth

E. 27" (68.6 cm) overall width

F. 12" (30.5 cm) from back of control panel to start of strain relief

G. 48" (121.9 cm) flexible conduit length
- 30" (76.2 cm) models**

A. 28 1/4" (72.8 cm) max. overall height

B. 28 1/4" (72.4 cm) max. recessed width


C. 26 3/4" (67.9 cm) recessed height

D. 23 1/4" (59.1 cm) max. recessed depth

E. 30" (76.2 cm) overall width

F. 12" (30.5 cm) from back of control panel to start of strain relief

G. 48" (121.9 cm) flexible conduit length



- 27" (68.6 cm) models**

A. 51 3/4" (130.0 cm) max. overall height

B. 25 1/8" (64.6 cm) max. recessed width

C. 48 9/16" (124.0 cm) recessed height

D. 23 1/4" (59.1 cm) max. recessed depth

E. 27" (68.6 cm) overall width

F. 12" (30.5 cm) from back of control panel to start of strain relief

G. 66" (167.6 cm) flexible conduit length
- 30" (76.2 cm) models**

A. 51 3/4" (130.0 cm) max. overall height

B. 28 1/4" (72.4 cm) max. recessed width

C. 48 9/16" (124.0 cm) recessed height

D. 23 1/4" (59.1 cm) max. recessed depth


E. 30" (76.2 cm) overall width

F. 12" (30.5 cm) from back of control panel to start of strain relief

G. 66" (167.6 cm) flexible conduit length

CABINET DIMENSIONS - SINGLE OVENS

Single Oven Undercounter (without cooktop installed above)




27" (68.6 cm) models

- A. 27" (68.6 cm) min. cabinet width
- B. 1 1/2" (3.8 cm) min. top of cutout to underside of countertop
- C. 5 1/2" (13.9 cm) bottom of cutout to floor
- D. 25 1/2" (64.8 cm) cutout width
- E. 28" (71.2 cm) min. cutout height

30" (76.2 cm) models

- A. 30" (76.2 cm) min. cabinet width
- B. 1 1/2" (3.8 cm) min. top of cutout to underside of countertop
- C. 5 1/2" (13.9 cm) bottom of cutout to floor
- D. 28 1/2" (72.4 cm) cutout width
- E. 28" (71.2 cm) min. cutout height

Single Ovens Installed in Cabinet



27" (68.6 cm) models

- A. 27" (68.6 cm) min. cabinet width
- B. 1" (2.5 cm) top of cutout to bottom of upper cabinet door
- C. 32" (81.3 cm) bottom of cutout to floor
- D. 25 1/2" (64.8 cm) cutout width
- E. 1 1/2" (3.8 cm) min. bottom of cutout to top of cabinet door
- F. 28" (71.2 cm)* recommended cutout height
- G. 24" (60.7 cm) cutout depth


30" (76.2 cm) models

- A. 30" (76.2 cm) min. cabinet width
- B. 1" (2.5 cm) top of cutout to bottom of upper cabinet door
- C. 32" (81.3 cm) bottom of cutout to floor
- D. 28 1/2" (72.4 cm) cutout width
- E. 1 1/2" (3.8 cm) min. bottom of cutout to top of cabinet door
- F. 28" (71.2 cm)* recommended cutout height
- G. 24" (60.7 cm) cutout depth

*NOTE: The cutout height can be between 26 1/4" (66.4 cm) and 29 1/16" (74.8 cm) for single ovens.

CABINET DIMENSIONS - DOUBLE OVENS

Double Ovens Installed in Cabinet



27" (68.6 cm) models

- A. 27" (68.6 cm) min. cabinet width
- B. 1" (2.5 cm) top of cutout to bottom of upper cabinet door
- C. 14 3/4" (37.5 cm) bottom of cutout to floor is recommended. 4"-14 3/4" (10.2-37.5 cm) bottom of cutout to floor is acceptable.
- D. 25 1/2" (64.8 cm) cutout width
- E. 1 1/2" (3.8 cm) min. bottom of cutout to top of cabinet door
- F. 50 1/2" (127.6 cm)* recommended cutout height
- G. 24" (60.7 cm) cutout depth

30" (76.2 cm) models

- A. 30" (76.2 cm) min. cabinet width
- B. 1" (2.5 cm) top of cutout to bottom of upper cabinet door
- C. 14 3/4" (37.5 cm) bottom of cutout to floor is recommended. 4"-14 3/4" (10.2-37.5 cm) bottom of cutout to floor is acceptable.
- D. 28 1/2" (72.4 cm) cutout width
- E. 1 1/2" (3.8 cm) min. bottom of cutout to top of cabinet door
- F. 50 1/2" (127.6 cm)* recommended cutout height
- G. 24" (60.7 cm) cutout depth

*NOTE: The cutout height can be between 48 1/2" (124.1 cm) and 52 1/16" (132.6 cm) for double ovens.

KitchenAid®


27" (68.6 cm) and 30" (76.2 cm) Electric Built-In Convection Microwave Oven

PRODUCT MODEL NUMBERS

KMBP100E KMBP107E

ELECTRICAL CONNECTION

- Microwave oven must be connected to the proper electrical voltage and frequency as specified on the model/serial number rating plate. The model/serial number rating plate is located underneath the control panel, along the oven vent.




A. Model/serial number rating plate

- The microwave oven rated 120/240 volt, 20-amp, has 4 wires (L1, L2, N and G) in the flex conduit and should be connected to a 20-amp maximum rated circuit, overcurrent protected on both the L1 and L2 circuits.
- A time-delay fuse or circuit breaker is recommended.

PRODUCT DIMENSIONS

27" (68.6 cm) and 30" (76.2 cm) Microwave Ovens




27" (68.6 cm) models

- A. 23 1/2" (59.5 cm)
- B. 18 1/4" (47.3 cm) overall height
- C. 26 1/4" (67.5 cm) overall width
- D. 21 1/2" (54.6 cm)
- E. 17 1/2" (44.7 cm)

30" (76.2 cm) models

- A. 28 1/2" (72.7 cm)
- B. 18 1/4" (47.3 cm) overall height
- C. 29 1/4" (75.6 cm) overall width
- D. 21 1/2" (54.6 cm)
- E. 17 1/2" (44.7 cm)

27" (68.6 cm) and 30" (76.2 cm) Microwave Oven Spacer Kit



27" (68.6 cm) models

- A. 26 1/4" (67.5 cm) overall width

30" (76.2 cm) models

- A. 29 1/4" (75.6 cm) overall width

NOTE: The microwave oven spacer kit will allow the microwave oven to be installed in a 17 1/2"-17 3/4" (44.1-45.1 cm) maximum cutout height.


A microwave oven spacer kit is available from your dealer that will allow the microwave oven to be installed in a 19"-19 1/2" (48.3-50.2 cm) maximum cutout height. Match the oven size to the following kits:

- 27" (68.6 cm) Stainless Steel - Model W10469901
- 30" (76.2 cm) Stainless Steel - Model W10469903

To order, see the "Assistance or Service" section of the Use and Care Guide.

CABINET DIMENSIONS

27" (68.6 cm) and 30" (76.2 cm) Microwave Ovens



27" (68.6 cm) models

- A. 27" (68.6 cm) min. cabinet width
- B. 18 1/4" (47.3 cm) from bottom of cutout to bottom of upper cabinet door
- C. 40" (101.6 cm) bottom of cutout to floor (recommended)
- D. 25 1/2" (64.8 cm) cutout width
- E. 1 1/2" (3.8 cm) min. bottom of cutout to top of cabinet door
- F. 17 1/2" (44.7 cm) recommended cutout height (will fit cutout height from 17 1/2" (44.1 cm) to 17 3/4" (45.1 cm))
- G. 21 1/2" (55.5 cm) min. cutout depth


30" (76.2 cm) models

- A. 30" (76.2 cm) min. cabinet width
- B. 18 1/4" (47.3 cm) from bottom of cutout to bottom of upper cabinet door
- C. 40" (101.6 cm) bottom of cutout to floor (recommended)
- D. 28 1/2" (72.4 cm) cutout width
- E. 1 1/2" (3.8 cm) min. bottom of cutout to top of cabinet door
- F. 17 1/2" (44.7 cm) recommended cutout height (will fit cutout height from 17 1/2" (44.1 cm) to 17 3/4" (45.1 cm))
- G. 21 1/2" (55.5 cm) min. cutout depth

MINIMUM INSTALLATION CLEARANCES

For proper installation, the following minimum clearances must exist above and below the cabinet opening.

Installation Above Single Built-In Oven



- A. Upper cabinet
- B. Lower single oven

Approved models: KMBP100E and KMBP107E.

Because Whirlpool Corporation includes a continuous commitment to improve our products, we reserve the right to change materials and specifications without notice.

Dimensions are for planning purposes only. For complete details, see installation instructions packed with product. Specifications subject to change without notice.

Ref. W107257306
2/10/15

KitchenAid®

FOR THE WAY IT'S MADE®

Undercounter Dishwasher

PRODUCT MODEL NUMBERS

KDFE204E, KDTE104E, KDTE204E, KDTE254E, KDTM354E, KDTM384E, KDTM404E, KDTM504E, KDTM704E, KDTM804E

Electrical Requirements: 120-volt, 60 Hz, AC-only, 15- or 20-amp. fused electrical supply. Copper wire only. A time delay fuse or circuit breaker and separate circuit is recommended.

If direct wiring dishwasher: Use flexible, armored or nonmetallic, sheathed copper wire with grounding wire that meets the wiring requirements for your home and local codes and ordinances.

Use a UL Listed or CSA Approved conduit connector.

If connecting dishwasher with a power supply cord:

Use power supply cord kit (Part Number 4317824) marked for use with dishwashers. Follow the kit instructions for installing the power supply cord.

Power supply cord must plug into a grounded three-prong outlet located in the cabinet next to the dishwasher opening. Outlet must meet all local codes and ordinances.

Water Supply Requirements: A hot water line with 20 to 120 psi (138 to 862 kPa) water pressure. Water temperature must be 120°F (49°C) water at dishwasher. Use 3/8" O.D. copper tubing with compression fitting or flexible braided water supply line.

Note: 1/2" minimum plastic tubing is not recommended.

Use a 90° elbow with 1/2" hose connection with rubber washer (part number W10273460). Do not solder within 6" (15.2 cm) from water inlet valve.

Drain Requirements: A new drain hose is supplied with your dishwasher. If this is not long enough, use a new drain hose with a maximum length of 12' (3.7 m) (Part No. 3385556) that meets all current AHAM/IAPMO test standards, is resistant to heat and detergent, and fits the 1" (2.5 cm) drain connector of the dishwasher.


Make sure to connect the drain hose to waste tee or disposer inlet above drain trap in house plumbing and 20" (50.8 cm) minimum above the floor. It is recommended

that the drain hose either be looped up and securely fastened to the underside of the counter, or be connected to an air gap.


Make sure to use an air gap if the drain hose is connected to house plumbing lower than 20" (50.8 cm) above subfloor or floor.

Use 1/2" (1.3 cm) minimum I.D. drain line fittings.

If required, the air gap should be installed in accordance with the air gap installation instructions. When connecting the air gap a rubber hose (not provided) will be needed to connect to the waste tee or disposer inlet.



PRODUCT DIMENSIONS




- A. Insulation may be compressed (not used on all models).
- B. For panel-ready models, dishwasher depth is 24" (60 cm) not including the 1/4" (1.9 cm) custom door panel.
- C. Door handles may protrude forward of the face of the dishwasher; varies by model.

CABINET CUTOUT DIMENSIONS

NOTE: Shaded areas of cabinet walls show where utility connections may be installed.

*Measure from the lowest point on the underside of the countertop. May be reduced to 33½" (85.1 cm) by removing the rear leveling legs from dishwasher.

*Minimum, measured from narrowest point of opening.



KitchenAid®

FOR THE WAY IT'S MADE®

Side By Side Built-In Refrigerator

PRODUCT MODEL NUMBERS

KBSD602E KBSD606E KBSD608E KBSN602E KBSN608E

Electrical: A 115 volt, 60 Hz., AC only, 15- or 20-amp fused, grounded electrical supply is required. It is recommended that a separate circuit serving only your refrigerator be provided. Use an outlet that cannot be turned off by a switch. Do not use an extension cord.

Water Pressure: A cold water supply with water pressure between 30 and 120 psi (207 and 827 kPa) is required to operate the water dispenser and ice maker. If you have questions about your water pressure, call a licensed, qualified plumber.

Reverse Osmosis Water Supply:

IMPORTANT: The pressure of the water supply coming out of a reverse osmosis system going to the water inlet valve of the refrigerator needs to be between 30 and 120 psi (207 and 827 kPa).


IMPORTANT:

- It is recommended that you do not install the refrigerator near an oven, radiator, or other heat source.
- Do not install in a location where the temperature will fall below 55°F (13°C).
- Floor must support the refrigerator weight, more than 600 lbs (272 kg), door panels and contents of the refrigerator.

PRODUCT DIMENSIONS

- The depth from the front of the top grille to the back of the refrigerator cabinet is 5 3/4" (64.5 cm).
- The power cord is 64" (213 cm) long.
- Height dimensions are shown with leveling legs extended 1/4" (3 mm) below the rollers.

SIDE VIEW




*When leveling legs are fully extended to 1 3/4" (3.2 cm) below rollers, add 1 1/4" (2.9 cm) to the height dimensions.

OPENING DIMENSIONS

To avoid tipping during use, the solid sillit must be within 1" (2.5 cm) maximum above the refrigerator. If the solid sillit is higher than 1" (2.5 cm) or one is not available, then the refrigerator must be braced. If the anti-tip boards are needed, they must be attached to the rear wall studs 80" to 90" (203 cm to 229 cm) above the floor. See "Install Anti-Tip Boards" for more information.

NOTE: A clearance of 1/2" (1.3 cm) above the top grille must be maintained in order for the top grille to be removed.




Model	Width A (as shown above)	Dimension B (as shown above)
35	35 1/2" to 36 1/4" (90.2 cm to 90.8 cm)	4" (10.2 cm)
42	41 1/2" to 41 3/4" (105.4 cm to 106.1 cm)	7 1/8" (18.1 cm)
46	47 1/2" to 47 3/4" (120.7 cm to 121.3 cm)	10 1/2" (26.3 cm)

NOTE: Flooring under refrigerator must be at same level as the room. Face of cabinet must be plumb.

Because Whirlpool Corporation policy includes a continuous commitment to improve our products, we reserve the right to change materials and specifications without notice.

Dimensions are for planning purposes only. For complete details, see Installation Instructions, packed with product. Specifications subject to change without notice.


TOP VIEW



Model	Width A
36	35" (88.9 cm)
42	41" (104.1 cm)
48	47" (119.4 cm)

FRONT VIEW

- Width dimensions were measured from trim edge to trim edge.
- Height dimensions are shown with leveling legs extended $\frac{1}{8}$ " (3 mm) below the rollers.



Model	Width A (Trim edge to trim edge)
36	36 1/32" (92.3 cm)
42	42 1/32" (107.5 cm)
48	48 1/32" (122.8 cm)

*When leveling legs are fully extended to $1 \frac{1}{4}$ " (3.2 cm) below rollers, add $1 \frac{1}{8}$ " (2.9 cm) to the height dimensions.


DOOR SWING DIMENSIONS

The location must permit both doors to open to a minimum of 90°. Allow 5" (12.7 cm) minimum space between the side of the refrigerator and a corner wall.


NOTE: More clearance may be required if you are using overlay panels, custom handles, or extended handles on a Classic model.

To adjust the door swings, see "Adjust Doors."


36" (91.4 cm) Models



42" (106.7 cm) Models



48" (121.9 cm) Models




DIMENSIONS

COMMERCIAL-STYLE RANGES

PRODUCT DIMENSIONS

MODEL #	30" (76.2 cm) RANGES DUAL-FUEL/GAS KFDC500J/KFGC500J		36" (91.4 cm) RANGES DUAL-FUEL/GAS KFDC506J/KFGC506J	
	in	cm	in	cm
Overall Width (A)	29 ⁷ / ₈	75.9	35 ⁷ / ₈	91.1
Bullnose Height (B)	2 ³ / ₈	5.6	2 ⁷ / ₁₆	5.8
Control Panel Height (C)	5 ⁵ / ₁₆	13.5	5 ⁵ / ₈	13.5
Door Height (D)	20 ¹¹ / ₁₆	52.6	20 ¹¹ / ₁₆	52.6
Door Bottom to Handle Top (E)	20	50.8	20	50.8
Top-Kick Height (F)	5 ¹ / ₂	14	5 ¹ / ₂	14




FRONT VIEW

IMPORTANT: Dimensional specifications are provided for planning purposes only. Do not make any cutouts based on this information. Refer to the Installation Guide before selecting cabinetry, verifying electrical/gas connections, making cutouts or beginning installation. All KitchenAid® appliances are appropriately UL, CUL or CSA approved.

FRIGIDAIRE GALLERY

FGBC5334VS

**CENTRE DE
BOISSONS**
165 BOÎTES DE 350 ML



COULEURS
OFFERTES



inoxycolor

DIMENSIONS DU PRODUIT

Hauteur	86,65 à 89 cm (34 1/8 à 35 po)
Largeur	59,53 cm (23 7/16 po)
Profondeur	59,05 cm (23 1/4 po)
Profondeur avec porte ouverte à 90°	114,3 cm (45 po)

AVANTAGE DE CARACTÉRISTIQUES CONVIVIALES

Installation encastrée ou pas
Installez ce centre de boissons à l'endroit idéal dans votre maison, avec notre système frontal de refroidissement par ventilation qui permet l'installation encastrée ou non-encastrée et des pieds réglables pour s'adapter à vos besoins en hauteur.

Porte réversible

La porte peut être installée pour s'ouvrir à gauche ou à droite, selon vos besoins.

CARACTÉRISTIQUES EXCLUSIVES

Contrôle précis de la température avec affichage DEL pour rafraîchir les boissons jusqu'à 1 °C (34°F)

Conservez vos boissons à la température idéale avec les contrôles et l'affichage DEL, facilement réglable de 1 à 10 °C (34 à 50 °F) d'une pression sur une touche.

Porte d'acier inoxydable aux lignes élégantes avec vitre teintée et clayettes de verre réglables. Profitez de l'élégance contemporaine de ce centre de boissons avec sa poignée contemporaine, sa porte en acier inoxydable à vitre teintée et ses clayettes pleine largeur réglables à bord en acier inoxydable.

Possibilité de stocker jusqu'à 165 boîtes de 350 ml
Conservez vos rafraîchissements favoris à la température idéale sans sacrifier de place dans le réfrigérateur avec ce centre de boissons intégré de 5,3 pi3 pouvant facilement recevoir 165 boîtes de 350 ml et jusqu'à 195 boîtes de 350 ml en pleine capacité.

Alarme de porte

Surveillez l'environnement idéal pour vos boissons et évitez de boire tiède grâce à notre alarme sonore qui vous prévient si la porte a été laissée ouverte par erreur.

FGBC5334VS
CENTRE DE BOISSONS
165 BOÎTES DE 350 ML

FRIGIDAIRE
GALLERY

CARACTÉRISTIQUES

Pieds cubés (p. 1)	5,3
Capacité en bouteilles/boîtes	165 boîtes de 350 ml

EXTÉRIEUR

Couleur de la porte	En acier inoxydable
Couleur du placard	Noir
Type de fenêtre	Vitre teintée
Poignée du porte	En acier inoxydable
Porte réversible	Oui
Pieds de nivellement	4

INTÉRIEUR



Type de commande	Électronique
Affichage	P* ou C*
Éclairage	DEL
Sans givre	Oui
Condenseur	Dynamique
Alarme sonore de température élevée	Oui
Commande Marche/arrêt	Oui
Zones de température	1
Plage de température	1 à 10 °C (34 à 50 °F)
Étagères réglables	Oui
Bord de clayette en acier inoxydable	Oui
Revêtement du placard	Noir

SPECIFICATIONS

Emplacement du raccordement électrique	Côté inférieur droit
Tension nominale	115V/60 Hz
Circuit minimum requis (ampères)	15
Poids d'expédition (approx.)	54 kg (119 lb)
Type d'installation	Encastré ou pas

DIMENSIONS DU PRODUIT

A - Hauteur	86,65 à 112 cm (34 1/8 à 35 po)
B - Largeur	59,53 cm (23 7/16 po)
C - Profondeur	59,65 cm (23 1/4 po)
D - Profondeur avec porte ouverte à 90°	114,3 cm (45 po)



Remarque : Aux fins de planification seulement. Consulter systématiquement les codes locaux et nationaux d'électricité et de plomberie. Reportez-vous au guide d'installation du produit pour des instructions d'installation détaillées sur le web à frigidaire.com/frigidaire.ca

Spécifications sujettes à modification. Informations sur les accessoires offerts sur le web à frigidaire.com/frigidaire.ca

FRIGIDAIRE

É.-U. : 10200 David Taylor Drive • Charlotte, NC 28262 • 1-800-FRIGIDAIRE • frigidaire.com
CANADA : 5855 Terry Fox Way • Mississauga, ON L5V 3E4 • 1-800-265-0352 • frigidaire.ca

FGBC5334VS 01/19
© 2019 Electrolux Home Products, Inc.