


Schedule 1: Designer Information

Use one form for each individual who reviews and takes responsibility for design activities with respect to the project.

A. Project Information				
Building number, street name			Unit no.	Lot/con.
Municipality HAMILTON	Postal code	Plan number/ other description		
B. Individual who reviews and takes responsibility for design activities				
Name MICHAEL O'ROURKE		Firm HVAC DESIGNS LTD.		
Street address 375 FINLEY AVE			Unit no. 202	Lot/con. N/A
Municipality AJAX	Postal code L1S 2E2	Province ONTARIO	E-mail info@hvacdesigns.ca	
Telephone number (905) 619-2300	Fax number (905) 619-2375	Cell number ()		
C. Design activities undertaken by individual identified in Section B. [Building Code Table 3.5.2.1 OF Division C]				
☐ House ☐ Small Buildings ☐ Large Buildings ☐ Complex Buildings ☒ HVAC – House ☐ Building Services ☐ Detection, Lighting and Power ☐ Fire Protection ☐ Building Structural ☐ Plumbing – House ☐ Plumbing – All Buildings ☐ On-site Sewage Systems				
Description of designer's work HEAT LOSS / GAIN CALCULATIONS DUCT SIZING RESIDENTIAL MECHANICAL VENTILATION DESIGN SUMMARY RESIDENTIAL SYSTEM DESIGN per CSA-F280-12			Model: VALLEYCREEK 5A Project: RUSSELL GARDENS PH 4	
D. Declaration of Designer				
I <u>MICHAEL O'ROURKE</u> (print name) declare that (choose one as appropriate):				
☐ I review and take responsibility for the design work on behalf of a firm registered under subsection 3.2.4. of Division C, of the Building Code. I am qualified, and the firm is registered, in the appropriate classes/categories. Individual BCIN: _____ Firm BCIN: _____				
☒ I review and take responsibility for the design and am qualified in the appropriate category as an "other designer" under subsection 3.2.5. of Division C, of the Building Code. Individual BCIN: 19669 Basis for exemption from registration and qualification: O.B.C SENTENCE 3.2.4.1 (4)				
☐ The design work is exempt from the registration and qualification requirements of the Building Code. Basis for exemption from registration and qualification: _____				
I certify that:				
1. The information contained in this schedule is true to the best of my knowledge. 2. I have submitted this application with the knowledge and consent of the firm.				
April 5, 2021 Date			 Signature of Designer	

NOTE:

- For the purposes of this form, "individual" means the "person" referred to in Clause 3.2.4.7(1) d) of Division C, Article 3.2.5.1. of Division C, and all other persons who are exempt from qualification under Subsections 3.2.4. and 3.2.5. of Division C.
- Schedule 1 is not required to be completed by a holder of a license, temporary license, or a certificate of authorization, issued by the Ontario Association of Architects. Schedule 1 is also not required to be completed by a holder of a license to practise, a limited license to practise, or a certificate of authorization, issued by the Association of Professional Engineers of Ontario.

SITE NAME: RUSSELL GARDENS PH 4
BUILDER: GREENPARK HOMES

TYPE: VALLEYCREEK 5A DATE: Apr-21 GFA: 2922 LO# 90138

HEATING CFM 1131 COOLING CFM 1131
TOTAL HEAT GAIN 34,958
AIR FLOW RATE CFM 32,35#GOODMAN
GMEC960603BNA 60
FAN SPEED LOWAFUE = 96 %
INPUT (BTU/H) = 60,000
OUTPUT (BTU/H) = 57,600

RUN COUNT	4th	3rd	2nd	1st	Bas
S/A	0	0	14	8	4
R/A	0	0	5	2	1

All S/A diffusers 4"x10" unless noted otherwise on layout.

All S/A runs 5'Ø unless noted otherwise on layout.

RUN #	1	2	3	4	5	6	7	8	9	10	11	12	13	14	15	16	17	18	19	20	21	22	23	24
ROOM NAME	MBR	ENS	WIC	BED-2	BED-3	BED-4	S-ENS	WIC-4	BED-3	MBR	ENS-4	FAM	DIN	KT7BF	KT7BF	LIB	LAUN	W/R	FOY	BED-4	BAS	BAS	BAS	BAS
RM LOSS MBH	1.40	1.10	1.51	1.18	1.91	1.49	0.48	0.83	1.91	1.40	0.50	2.79	1.13	1.86	1.86	1.45	2.50	0.37	3.34	1.49	4.32	4.32	4.32	4.32
CFM PER RUN HEAT	32	25	35	27	44	34	11	19	44	32	12	64	26	43	43	33	57	8	77	34	99	99	99	99
RM GAIN MBH	2.06	0.80	0.99	1.83	2.45	2.18	0.20	0.95	2.45	2.06	0.34	2.98	1.61	2.50	2.50	1.52	1.46	0.27	0.94	2.18	0.42	0.42	0.42	0.42
CFM PER RUN COOLING	67	26	32	59	79	70	6	31	79	67	11	96	52	81	81	49	47	9	31	70	14	14	14	14
ADJUSTED PRESSURE	0.17	0.17	0.17	0.17	0.17	0.17	0.17	0.17	0.17	0.17	0.17	0.16	0.17	0.16	0.16	0.16	0.17	0.17	0.17	0.17	0.16	0.16	0.16	0.16
ACTUAL DUCT LGH	50	36	31	27	44	58	36	39	50	36	44	27	19	26	32	37	20	37	44	47	28	19	13	34
EQUIVALENT LENGTH	190	150	170	130	130	160	150	120	140	120	200	130	130	120	140	150	130	150	120	130	90	100	160	140
TOTAL EFFECTIVE LENGTH	240	186	201	157	174	218	186	159	190	156	244	157	149	146	172	187	150	187	164	177	118	119	173	174
ADJUSTED PRESSURE	0.07	0.09	0.09	0.11	0.11	0.08	0.09	0.11	0.09	0.11	0.07	0.1	0.12	0.11	0.09	0.09	0.11	0.09	0.1	0.1	0.14	0.14	0.09	0.09
ROUND DUCT SIZE	6	4	4	6	6	6	4	4	6	6	4	6	5	5	6	5	5	4	5	6	6	6	6	6
HEATING VELOCITY (ft/min)	163	287	402	138	224	173	126	218	224	163	138	326	191	316	219	242	419	92	565	173	505	505	505	505
COOLING VELOCITY (ft/min)	342	298	367	301	403	357	69	356	403	342	126	489	382	595	413	360	345	103	228	357	71	71	71	71
OUTLET GRILL SIZE	4X10	3X10	3X10	4X10	4X10	4X10	3X10	3X10	4X10	4X10	3X10	4X10	3X10	3X10	4X10	3X10	3X10	3X10	3X10	4X10	4X10	4X10	4X10	4X10
TRUNK	A	A	D	B	D	C	D	D	D	A	C	A	B	A	A	C	B	C	C	C	B	B	D	C

RUN #	25	26
ROOM NAME	ENS	S-ENS
RM LOSS MBH	1.10	0.48
CFM PER RUN HEAT	25	11
RM GAIN MBH	0.80	0.20
CFM PER RUN COOLING	26	6
ADJUSTED PRESSURE	0.17	0.17
ACTUAL DUCT LGH	58	32
EQUIVALENT LENGTH	190	180
TOTAL EFFECTIVE LENGTH	248	212
ADJUSTED PRESSURE	0.07	0.08
ROUND DUCT SIZE	4	4
HEATING VELOCITY (ft/min)	287	126
COOLING VELOCITY (ft/min)	298	69
OUTLET GRILL SIZE	3X10	3X10
TRUNK	A	D

SUPPLY AIR TRUNK SIZE	TRUNK	STATIC	ROUND	RECT	VELOCITY	TRUNK	STATIC	ROUND	RECT	VELOCITY	TRUNK	STATIC	ROUND	RECT	VELOCITY	TRUNK	STATIC	ROUND	RECT	VELOCITY
TRUNK A	264	0.07	8.8	14	8	339	0.00	0	0	8	0	0.00	0	0	8	0	0.00	0	0	8
TRUNK B	572	0.07	11.8	18	8	572	0.00	0	0	8	0	0.00	0	0	8	0	0.00	0	0	8
TRUNK C	297	0.07	9.2	10	8	535	0.00	0	0	8	0	0.00	0	0	8	0	0.00	0	0	8
TRUNK D	560	0.07	11.7	16	8	630	0.00	0	0	8	0	0.00	0	0	8	0	0.00	0	0	8
TRUNK E	0	0.00	0	0	8	0	0.00	0	0	8	0	0.00	0	0	8	0	0.00	0	0	8
TRUNK F	0	0.00	0	0	8	0	0.00	0	0	8	0	0.00	0	0	8	0	0.00	0	0	8

RETURN AIR #	1	2	3	4	5	6	7	8	9	10	11	12	13	14	15	16	17	18	19	20	21	22	23	24
AIR VOLUME	155	170	85	75	170	235	85	0	0	0	0	0	0	0	0	0	0	0	0	0	0	0	0	0
PLENUM PRESSURE	0.15	0.15	0.15	0.15	0.15	0.15	0.15	0.15	0.15	0.15	0.15	0.15	0.15	0.15	0.15	0.15	0.15	0.15	0.15	0.15	0.15	0.15	0.15	0.15
ACTUAL DUCT LGH	38	36	53	57	25	40	34	1	1	1	1	1	1	1	1	1	1	1	1	1	1	1	1	1
EQUIVALENT LENGTH	150	135	185	225	145	230	205	0	0	0	0	0	0	0	0	0	0	0	0	0	0	0	0	0
TOTAL EFFECTIVE LH	188	171	238	282	170	270	239	1	1	1	1	1	1	1	1	1	1	1	1	1	1	1	1	1
ADJUSTED PRESSURE	0.08	0.09	0.06	0.05	0.09	0.05	0.06	0.06	0.06	0.06	0.06	0.06	0.06	0.06	0.06	0.06	0.06	0.06	0.06	0.06	0.06	0.06	0.06	0.06
ROUND DUCT SIZE	7	7	6	6	7	9.2	6	0	0	0	0	0	0	0	0	0	0	0	0	0	0	0	0	0
INLET GRILL SIZE	X	X	X	X	X	X	X	X	X	X	X	X	X	X	X	X	X	X	X	X	X	X	X	X
INLET GRILL SIZE	14	14	14	14	14	30	14	0	0	0	0	0	0	0	0	0	0	0	0	0	0	0	0	0

TYPE: VALLEYCREEK 5A
SITE NAME: RUSSELL GARDENS PH 4

LO # 90138

RESIDENTIAL MECHANICAL VENTILATION DESIGN SUMMARY

COMBUSTION APPLIANCES		9.32.3.1(1)
a)	☒ Direct vent (sealed combustion) only	
b)	☐ Positive venting induced draft (except fireplaces)	
c)	☐ Natural draft, B-vent or induced draft gas fireplace	
d)	☐ Solid Fuel (including fireplaces)	
e)	☐ No Combustion Appliances	

HEATING SYSTEM	
☒ Forced Air	☐ Non Forced Air
☐ Electric Space Heat	

HOUSE TYPE		9.32.1(2)
☒ I	Type a) or b) appliance only, no solid fuel	
☐ II	Type I except with solid fuel (including fireplaces)	
☐ III	Any Type c) appliance	
☐ IV	Type I, or II with electric space heat	
☐	Other: Type I, II or IV no forced air	

SYSTEM DESIGN OPTIONS		O.N.H.W.P.
☐ 1	Exhaust only/Forced Air System	
☐ 2	HRV with Ducting/Forced Air System	
☒ 3	HRV Simplified/connected to forced air system	
☐ 4	HRV with Ducting/non forced air system	
☐	Part 6 Design	

TOTAL VENTILATION CAPACITY		9.32.3.3(1)
Basement + Master Bedroom	<u>2</u> @ 21.2 cfm	<u>42.4</u> cfm
Other Bedrooms	<u>3</u> @ 10.6 cfm	<u>31.8</u> cfm
Kitchen & Bathrooms	<u>5</u> @ 10.6 cfm	<u>53</u> cfm
Other Rooms	<u>5</u> @ 10.6 cfm	<u>53.0</u> cfm
Table 9.32.3.A. TOTAL		<u>180.2</u> cfm

PRINCIPAL VENTILATION CAPACITY REQUIRED		9.32.3.4.(1)
1 Bedroom	31.8	cfm
2 Bedroom	47.7	cfm
3 Bedroom	63.6	cfm
4 Bedroom	79.5	cfm
5 Bedroom	95.4	cfm
TOTAL		<u>79.5</u> cfm

SUPPLEMENTAL VENTILATION CAPACITY		9.32.3.5.
Total Ventilation Capacity	<u>180.2</u>	cfm
Less Principal Ventil. Capacity	<u>79.5</u>	cfm
Required Supplemental Capacity	<u>100.7</u>	cfm

PRINCIPAL EXHAUST FAN CAPACITY			
Model:	VANEE V150H		
Location:	BSMT		
<u>79.5</u> cfm	<u>3.0</u> sones		
☒ HVI Approved			
PRINCIPAL EXHAUST HEAT LOSS CALCULATION			
CFM	ΔT °F	FACTOR	% LOSS
79.5 CFM	X 71 F	X 1.08	X 0.25

SUPPLEMENTAL FANS		PANASONIC	
Location	Model	cfm	Sones
ENS	FV-05-11VK1	50	✓ 0.3
S- ENS	FV-05-11VK1	50	✓ 0.3
ENS-4	FV-05-11VK1	50	✓ 0.3
W/R	FV-05-11VK1	50	✓ 0.3

HEAT RECOVERY VENTILATOR		9.32.3.11.
Model:	VANEE V150H	
<u>150</u> cfm high	<u>35</u> cfm low	
<u>75</u> % Sensible Efficiency	☒ HVI Approved	
@ 32 deg F (0 deg C)		

LOCATION OF INSTALLATION	
Lot:	Concession
Township	Plan:
Address	
Roll #	Building Permit #

BUILDER:	
GREENPARK HOMES	
Name:	
Address:	
City:	
Telephone #:	Fax #:

INSTALLING CONTRACTOR	
Name:	
Address:	
City:	
Telephone #:	Fax #:

DESIGNER CERTIFICATION	
I hereby certify that this ventilation system has been designed in accordance with the Ontario Building Code.	
Name:	HVAC Designs Ltd.
Signature:	<i>Michael O'Rourke</i>
HRAI #	001820
Date:	April-21

CSA F280-12 Residential Heat Loss and Heat Gain Calculations																																																																							
Formula Sheet (For Air Leakage / Ventilation Calculation)																																																																							
LO#: 90138	Model: VALLEYCREEK 5A	Builder: GREENPARK HOMES	Date: 05/04/2021																																																																				
Volume Calculation		Air Change & Delta T Data																																																																					
<table border="1" style="width: 100%; border-collapse: collapse;"> <tr> <th>House Volume</th> <th>Floor Area (ft²)</th> <th>Floor Height (ft)</th> <th>Volume (ft³)</th> </tr> <tr> <td>Level</td> <td></td> <td></td> <td></td> </tr> <tr> <td>Bsmt</td> <td>1276</td> <td>9</td> <td>11484</td> </tr> <tr> <td>First</td> <td>1276</td> <td>10</td> <td>12760</td> </tr> <tr> <td>Second</td> <td>1646</td> <td>9</td> <td>14814</td> </tr> <tr> <td>Third</td> <td>0</td> <td>9</td> <td>0</td> </tr> <tr> <td>Fourth</td> <td>0</td> <td>9</td> <td>0</td> </tr> <tr> <td>Total:</td> <td></td> <td></td> <td>39,058.0 ft³</td> </tr> <tr> <td>Total:</td> <td></td> <td></td> <td>1106.0 m³</td> </tr> </table>		House Volume	Floor Area (ft²)	Floor Height (ft)	Volume (ft³)	Level				Bsmt	1276	9	11484	First	1276	10	12760	Second	1646	9	14814	Third	0	9	0	Fourth	0	9	0	Total:			39,058.0 ft³	Total:			1106.0 m³	<table border="1" style="width: 100%; border-collapse: collapse;"> <tr> <td>WINTER NATURAL AIR CHANGE RATE</td> <td>0.338</td> </tr> <tr> <td>SUMMER NATURAL AIR CHANGE RATE</td> <td>0.121</td> </tr> </table> <table border="1" style="width: 100%; border-collapse: collapse;"> <tr> <th colspan="4">Design Temperature Difference</th> </tr> <tr> <th></th> <th>Tin °C</th> <th>Tout °C</th> <th>ΔT °C</th> </tr> <tr> <td>Winter DTDh</td> <td>22</td> <td>-17</td> <td>39</td> </tr> <tr> <td>Summer DTDc</td> <td>24</td> <td>31</td> <td>7</td> </tr> <tr> <td></td> <td></td> <td></td> <td>ΔT °F</td> </tr> <tr> <td></td> <td></td> <td></td> <td>71</td> </tr> <tr> <td></td> <td></td> <td></td> <td>13</td> </tr> </table>		WINTER NATURAL AIR CHANGE RATE	0.338	SUMMER NATURAL AIR CHANGE RATE	0.121	Design Temperature Difference					Tin °C	Tout °C	ΔT °C	Winter DTDh	22	-17	39	Summer DTDc	24	31	7				ΔT °F				71				13
House Volume	Floor Area (ft²)	Floor Height (ft)	Volume (ft³)																																																																				
Level																																																																							
Bsmt	1276	9	11484																																																																				
First	1276	10	12760																																																																				
Second	1646	9	14814																																																																				
Third	0	9	0																																																																				
Fourth	0	9	0																																																																				
Total:			39,058.0 ft³																																																																				
Total:			1106.0 m³																																																																				
WINTER NATURAL AIR CHANGE RATE	0.338																																																																						
SUMMER NATURAL AIR CHANGE RATE	0.121																																																																						
Design Temperature Difference																																																																							
	Tin °C	Tout °C	ΔT °C																																																																				
Winter DTDh	22	-17	39																																																																				
Summer DTDc	24	31	7																																																																				
			ΔT °F																																																																				
			71																																																																				
			13																																																																				
5.2.3.1 Heat Loss due to Air Leakage																																																																							
$HL_{airb} = LR_{airh} \times \frac{V_b}{3.6} \times DTD_h \times 1.2$																																																																							
0.338	x	307.22	x																																																																				
		39 °C	x																																																																				
		1.2	x																																																																				
			=																																																																				
			4885 W																																																																				
			=																																																																				
			16668 Btu/h																																																																				
5.2.3.2 Heat Loss due to Mechanical Ventilation																																																																							
$HL_{vaib} = PVC \times DTD_h \times 1.08 \times (1 - E)$																																																																							
80 CFM	x	71 °F	x																																																																				
		1.08	x																																																																				
		0.25	x																																																																				
			=																																																																				
			1515 Btu/h																																																																				
5.2.3.3 Calculation of Air Change Heat Loss for Each Room (Floor Multiplier Section)																																																																							
$HL_{airr} = Level Factor \times HL_{airbv} \times \{(HL_{agcr} + HL_{bgcr}) \div (HL_{agcleve} + HL_{bgcleve})\}$																																																																							
<table border="1" style="width: 100%; border-collapse: collapse;"> <tr> <th>Level</th> <th>Level Factor (LF)</th> <th>HLairbv Air Leakage + Ventilation Heat Loss (Btu/h)</th> <th>Level Conductive Heat Loss: (HL_{cleve})</th> <th>Air Leakage Heat Loss Multiplier (LF x HLairbv / HLlevel)</th> </tr> <tr> <td>1</td> <td>0.5</td> <td rowspan="5" style="text-align: center; vertical-align: middle;">16,668</td> <td>8,959</td> <td>0.930</td> </tr> <tr> <td>2</td> <td>0.3</td> <td>10,301</td> <td>0.485</td> </tr> <tr> <td>3</td> <td>0.2</td> <td>12,929</td> <td>0.258</td> </tr> <tr> <td>4</td> <td>0</td> <td>0</td> <td>0.000</td> </tr> <tr> <td>5</td> <td>0</td> <td>0</td> <td>0.000</td> </tr> </table>				Level	Level Factor (LF)	HLairbv Air Leakage + Ventilation Heat Loss (Btu/h)	Level Conductive Heat Loss: (HL _{cleve})	Air Leakage Heat Loss Multiplier (LF x HLairbv / HLlevel)	1	0.5	16,668	8,959	0.930	2	0.3	10,301	0.485	3	0.2	12,929	0.258	4	0	0	0.000	5	0	0	0.000																																										
Level	Level Factor (LF)	HLairbv Air Leakage + Ventilation Heat Loss (Btu/h)	Level Conductive Heat Loss: (HL _{cleve})	Air Leakage Heat Loss Multiplier (LF x HLairbv / HLlevel)																																																																			
1	0.5	16,668	8,959	0.930																																																																			
2	0.3		10,301	0.485																																																																			
3	0.2		12,929	0.258																																																																			
4	0		0	0.000																																																																			
5	0		0	0.000																																																																			
*HLairbv = Air leakage heat loss + ventilation heat loss *For a balanced or supply only ventilation system HLairve = 0																																																																							

HEAT LOSS AND GAIN SUMMARY SHEET**MODEL:** VALLEYCREEK 5A**BUILDER:** GREENPARK HOMES**SFQT:** 2922**LO#** 90138**SITE:** RUSSELL GARDENS PH 4**DESIGN ASSUMPTIONS**

HEATING	°F	COOLING	°F
OUTDOOR DESIGN TEMP.	1	OUTDOOR DESIGN TEMP.	88
INDOOR DESIGN TEMP.	72	INDOOR DESIGN TEMP. (MAX 75°F)	75

BUILDING DATA

ATTACHMENT:	DETACHED	# OF STORIES (+BASEMENT):	3
FRONT FACES:	EAST	ASSUMED (Y/N):	Y
AIR CHANGES PER HOUR:	3.57	ASSUMED (Y/N):	Y
AIR TIGHTNESS CATEGORY:	AVERAGE	ASSUMED (Y/N):	Y
WIND EXPOSURE:	SHELTERED	ASSUMED (Y/N):	Y
HOUSE VOLUME (ft³):	39058.0	ASSUMED (Y/N):	Y
INTERNAL SHADING:	BLINDS/CURTAINS	ASSUMED OCCUPANTS:	5
INTERIOR LIGHTING LOAD (Btu/h/ft²):	1.50	DC BRUSHLESS MOTOR (Y/N):	Y
FOUNDATION CONFIGURATION	BCIN_1	DEPTH BELOW GRADE:	6.0 ft
LENGTH: 57.0 ft	WIDTH: 33.0 ft	EXPOSED PERIMETER:	180.0 ft

2012 OBC - COMPLIANCE PACKAGE		
Component	Compliance Package A1	
	Nominal	Min. Eff.
Ceiling with Attic Space Minimum RSI (R)-Value	60	59.22
Ceiling Without Attic Space Minimum RSI (R)-Value	31	27.65
Exposed Floor Minimum RSI (R)-Value	31	29.80
Walls Above Grade Minimum RSI (R)-Value	22	17.03
Basement Walls Minimum RSI (R)-Value	20 ci	21.12
Below Grade Slab Entire surface > 600 mm below grade Minimum RSI (R)-Value	-	-
Edge of Below Grade Slab ≤ 600 mm Below Grade Minimum RSI (R)-Value	10	10
Heated Slab or Slab ≤ 600 mm below grade Minimum RSI (R)-Value	10	11.13
Windows and Sliding Glass Doors Maximum U-Value	0.28	-
Skylights Maximum U-Value	0.49	-
Space Heating Equipment Minimum AFUE	0.96	-
HRV Minimum Efficiency	75%	-
Domestic Hot Water Heater Minimum EF	0.8	-


INDIVIDUAL BCIN: 19669

MICHAEL O'ROURKE



Residential Foundation Thermal Load Calculator

Supplemental tool for CAN/CSA-F280

Weather Station Description		
Province:	Ontario	
Region:	Hamilton	
Site Description		
Soil Conductivity:	Normal conductivity: dry sand, loam, clay	
Water Table:	Normal (7-10 m, 23-33 ft)	
Foundation Dimensions		
Floor Length (m):	17.4	 Insulation Configuration
Floor Width (m):	10.1	
Exposed Perimeter (m):	0.0	
Wall Height (m):	2.7	
Depth Below Grade (m):	1.83	
Window Area (m ²):	2.1	
Door Area (m ²):	1.9	
Radiant Slab		
Heated Fraction of the Slab:	0	
Fluid Temperature (°C):	33	
Design Months		
Heating Month	1	
Foundation Loads		
Heating Load (Watts):		1737


TYPE: VALLEYCREEK 5A
LO# 90138

Air Infiltration Residential Load Calculator

Supplemental tool for CAN/CSA-F280

Weather Station Description				
Province:	Ontario			
Region:	Hamilton			
Weather Station Location:	Open flat terrain, grass			
Anemometer height (m):	10			
Local Shielding				
Building Site:	Suburban, forest			
Walls:	Heavy			
Flue:	Heavy			
Highest Ceiling Height (m):	7.62			
Building Configuration				
Type:	Detached			
Number of Stories:	Two			
Foundation:	Full			
House Volume (m ³):	1106.0			
Air Leakage/Ventilation				
Air Tightness Type:	Present (1961-) (3.57 ACH)			
Custom BDT Data:	ELA @ 10 Pa.	1474.3 cm ²		
	3.57	ACH @ 50 Pa		
Mechanical Ventilation (L/s):	Total Supply	Total Exhaust		
	37.5	37.5		
Flue Size				
Flue #:	#1	#2	#3	#4
Diameter (mm):	0	0	0	0
Natural Infiltration Rates				
Heating Air Leakage Rate (ACH/H):	0.338			
Cooling Air Leakage Rate (ACH/H):	0.121			

TYPE: VALLEYCREEK 5A
LO# 90138



I MICHAEL O'ROURKE HAVE REVIEWED AND TAKE RESPONSIBILITY FOR THE DESIGN WORK AND AM QUALIFIED UNDER DIVISION C, 3.2.5 OF THE BUILDING CODE.


Michael O'Rourke
Michael O'Rourke, BCIN# 19669
HVAC DESIGNS LTD.

WOD
CSA-F280-12
PACKAGE A1

HVAC LEGEND						3.		
SYMBOL	DESCRIPTION	SYMBOL	DESCRIPTION	SYMBOL	DESCRIPTION	SYMBOL	DESCRIPTION	
	SUPPLY AIR GRILLE		6" SUPPLY AIR BOOT ABOVE		14"x8" RETURN AIR GRILLE		RETURN AIR STACK ABOVE	2.
	SUPPLY AIR GRILLE 6" BOOT		SUPPLY AIR STACK FROM 2nd FLOOR		30"x8" RETURN AIR GRILLE		RETURN AIR STACK 2nd FLOOR	1.
	SUPPLY AIR BOOT ABOVE		6" SUPPLY AIR STACK 2nd FLOOR		FRA- FLOOR RETURN AIR GRILLE		REDUCER	No. Description Date
REVISIONS								

ALL DRAWINGS, CALCULATIONS AND SPECIFICATIONS ARE THE PROPERTY OF HVAC DESIGNS LTD.© AND MAY NOT BE REPRODUCED, MODIFIED OR ALTERED WITHOUT EXPRESSED WRITTEN CONSENT. THE DRAWINGS ARE DATED AND USE OF THESE DRAWINGS AFTER ONE YEAR FROM THE DATED NOTED IS NOT AUTHORIZED. CONTRACTOR SHALL CHECK ALL CONDITIONS BEFORE PROCEEDING WITH WORK. LATEST MUNICIPAL APPROVED DRAWINGS ONLY TO BE USED DURING INSTALLATION OF HEATING SYSTEM. HVAC DESIGNS LTD. IS NOT LIABLE FOR ANY CLAIMS ARISING FROM UNAUTHORIZED USE OF THE DRAWINGS OR FROM ANY CHANGES TO ACCEPTED STANDARDS AND/OR THE ONTARIO BUILDING CODE.

Client GREENPARK HOMES		 375 Finley Ave. Suite 202 - Ajax, Ontario L1S 2E2 Tel. 905.619.2300 - 905.420.5300 Fax 905.619.2375 Email: info@hvacdesigns.ca Web: www.hvacdesigns.ca Specializing in Residential Mechanical Design Services Installation to comply with the latest Ontario Building Code. All supply branch outlets shall be equipped with a manual balancing damper. Ductwork which passes through the garage or unheated spaces shall be adequately insulated and be gas-proofed.	Sheet Title FIRST FLOOR HEATING LAYOUT	
Project Name RUSSELL GARDENS PH 4 HAMILTON, ONTARIO			Date APRIL/2021	
VALLEYCREEK 5A 2922 sqft			Scale 3/16" = 1'-0"	
			BCIN# 19669	
			LO#	90138



I MICHAEL O'ROURKE HAVE REVIEW AND TAKE RESPONSIBILITY FOR THE DESIGN WORK AND AM QUALIFIED UNDER DIVISION C, 3.2.3 OF THE BUILDING CODE.

Michael O'Rourke
Michael O'Rourke, BCIN# 19669
HVAC DESIGNS LTD.

WOD
CSA-F280-12
PACKAGE A1

HVAC LEGEND							3.		
SYMBOL	DESCRIPTION	SYMBOL	DESCRIPTION	SYMBOL	DESCRIPTION	SYMBOL	DESCRIPTION	2.	
	SUPPLY AIR GRILLE		6" SUPPLY AIR BOOT ABOVE		14"x8" RETURN AIR GRILLE		RETURN AIR STACK ABOVE	1.	
	SUPPLY AIR GRILLE 6" BOOT		SUPPLY AIR STACK FROM 2nd FLOOR		30"x8" RETURN AIR GRILLE		RETURN AIR STACK 2nd FLOOR	No.	Description
	SUPPLY AIR BOOT ABOVE		6" SUPPLY AIR STACK 2nd FLOOR		FRA- FLOOR RETURN AIR GRILLE		REDUCER	REVISIONS	

ALL DRAWINGS, CALCULATIONS AND SPECIFICATIONS ARE THE PROPERTY OF HVAC DESIGNS LTD.© AND MAY NOT BE REPRODUCED, MODIFIED OR ALTERED WITHOUT EXPRESSED WRITTEN CONSENT. THE DRAWINGS ARE DATED AND USE OF THESE DRAWINGS AFTER ONE YEAR FROM THE DATED NOTED IS NOT AUTHORIZED. CONTRACTOR SHALL CHECK ALL CONDITIONS BEFORE PROCEEDING WITH WORK. LATEST MUNICIPAL APPROVED DRAWINGS ONLY TO BE USED DURING INSTALLATION OF HEATING SYSTEM. HVAC DESIGNS LTD. IS NOT LIABLE FOR ANY CLAIMS ARISING FROM UNAUTHORIZED USE OF THE DRAWINGS OR FROM ANY CHANGES TO ACCEPTED STANDARDS AND/OR THE ONTARIO BUILDING CODE.

Client		 375 Finley Ave. Suite 202 - Ajax, Ontario L1S 2E2 Tel. 905.619.2300 - 905.420.5300 Fax 905.619.2375 Email: info@hvacdesigns.ca Web: www.hvacdesigns.ca Specializing in Residential Mechanical Design Services Installation to comply with the latest Ontario Building Code. All supply branch outlets shall be equipped with a manual balancing damper. Ductwork which passes through the garage or unheated spaces shall be adequately insulated and be gas-proofed.	Sheet Title	
GREENPARK HOMES			SECOND FLOOR HEATING LAYOUT	
Project Name			Date	APRIL/2021
RUSSELL GARDENS PH 4 HAMILTON, ONTARIO			Scale	3/16" = 1'-0"
VALLEYCREEK 5A 2922 sqft			BCIN# 19669	LO# 90138