

CONSTRUCTION SUMMARY

Mountainview Heights 3 (G) - Russell Gardens Building Ltd.

PURCHASERS: Taiwo Adelaja ROLUGA and Adenike Basirat ROLUGA

TEL:

| | | | |
|------------------------|-------------------------|--|---------------------|
| LOT / PHASE 374 / 4 | REG. PLAN # 62M-1266 | HOUSE TYPE Springfield Three (5 Bedroom) Elev 2 | Appliance Spec's |
|------------------------|-------------------------|--|---------------------|

CABINETRY

| | |
|---|--|
| 1 - CABINETRY PROVISION - PROVISION FOR PLUG ON ISLAND (PLUG EXTRA ORDERED SEPARATELY) 26Jan22 Note: | |
| 1 - VANITY - POWDER ROOM - UPGRADE 1 26Jan22 Note: | |
| 1 - KITCHEN - LIGHT VALANCE 26Jan22 Note: | |
| 1 - KITCHEN - CM 11 MOULDING 26Jan22 Note: | |
| 1 - KITCHEN CABINETRY - DIFFERENT COLOUR ISLAND - FLAT FEE 26Jan22 Note: | |
| 1 - CABINETRY - KITCHEN - UPGRADE 2 26Jan22 Note: | |
| 1 - VANITY - ENSUITE - UPGRADE 1 26Jan22 Note: | |

CABINETRY ACCESSORIES

| | | |
|---|-----|---|
| 1 - KITCHEN CABINETRY - BUILT-IN FRIDGE CABINET - PRICE IS EACH 18Feb22 Note: | New | ★ |
| 1 - CABINETRY FEE FOR FLUSH CUTOUT ON WALL OVEN/MICROWAVE COMBO CABINET ONLY 18Feb22 Note: | New | ★ |
| 1 - KITCHEN CABINETRY BASE - BANK OF DRAWERS - UPGRADE 2 26Jan22 Note: | | |
| 1 - KITCHEN - SOFT CLOSING CABINETRY 26Jan22 Note: | | |
| 1 - KITCHEN - BLU MOTION DRAWERS 26Jan22 Note: | | |
| 6 - KITCHEN CABINETRY ACCESSORY - GLASS SHELVES - STRAIGHT 26Jan22 Note: | | |
| 4 - KITCHEN CABINETRY UPPER - GLASS DOOR - BEVELED - FINISHED INTERIOR - FITS TALL UPPER CABINETS - PRICE IS PER DOOR - UPGRADE 2 26Jan22 Note: BAROQUE B;L 306 | | |
| 4 - KITCHEN CABINETRY UPPER - GLASS DOOR FOR MINI UPPER - GROUP 1 GLASS - PRICE IS PER DOOR - UPGRADE 2 26Jan22 Note: BAROQUE BLK 306 | | |
| 1 - VANITY CABINETRY - RAISE VANITY TO 36" HIGH VANITY IN LIEU OF STANDARD HEIGHT - ENSUITE 3/4 BATHROOM 26Jan22 Note: | | |
| 1 - VANITY CABINETRY - RAISE VANITY TO 36" HIGH VANITY IN LIEU OF STANDARD HEIGHT - ENSUITE 2/5 BATHROOM 26Jan22 Note: | | |

Purchasers:

Telephone Res. / Bus:

Decor Advisor:

Lock Date:

Taiwo Adelaja ROLUGA & Adenike Basirat ROLU

/

Candace Forza

10-Mar-22

Property: 374

Project: Russell Gardens Building Ltd.

Model and Elevation: Springfield Three (5 Bedroom) Elev 2

Plan #: 62M-1266

3. Ceramic Flooring

At a 45 Threshold-If App.

| | | | |
|----------------------------|---|--------------------------|------------------------------|
| Entrance Vestibule | * TILE-LITIUM PEARL POLISHED-24X24 | <input type="checkbox"/> | metal strip where applicable |
| Main Hall | STRIP | <input type="checkbox"/> | |
| Kitchen / Breakfast | * TILE-LITIUM PEARL POLISHED-24X24 | <input type="checkbox"/> | |
| Laundry Room | TILE-RAINBOW LIGHT GREY-13X13 | <input type="checkbox"/> | |
| Powder Room | * TILE-LITIUM PEARL POLISHED-24X24 | <input type="checkbox"/> | |
| Master Ensuite Bathroom | TILE-TRAVERTINO MEM BIANCO POLISHED-24X24 | <input type="checkbox"/> | |
| Ensuite Bath - Bed 2/5 | TILE-RAINBOW LIGHT GREY-13X13 | <input type="checkbox"/> | |
| Ensuite Bath - Bedroom 3/4 | TILE-RAINBOW LIGHT GREY-13X13 | <input type="checkbox"/> | |
| MUD ROOM | * TILE-LITIUM PEARL POLISHED-24X24 | <input type="checkbox"/> | |
| | N/A | <input type="checkbox"/> | |
| | N/A | <input type="checkbox"/> | |

** Refer to Construction Summary

4. Ceramic Wall Tile

| Master Ensuite Bathroom | Selection | Describe |
|----------------------------|---|----------|
| Tub Deck Wall | N/A | |
| Tub Deck | N/A | |
| Tub Deck Skirt | N/A | |
| Shower Stall | TILE-TRAVERTINO MEM BIANCO POLISHED-12X24 | |
| Bathtub Enclosure Walls | N/A | |
| Ensuite Bath - Bed 2/5 | TILE-SILVIA WHITE-8X16 | |
| Ensuite Bath - Bedroom 3/4 | TILE-SILVIA WHITE-8X16 | |
| MUD ROOM | N/A | |
| | N/A | |
| | N/A | |
| | N/A | |
| Kitchen Backsplash | N/A | |

** Refer to Construction Summary - STANDARD GROUT THROUGHOUT UNLESS SPECIFIED

5. Plumbing Fixtures

| | | |
|---------------|-------|--|
| All Bathrooms | White | Whirlpool |
| | N/A | <input type="checkbox"/> N/A <input type="radio"/> Yes <input checked="" type="radio"/> No |
| | N/A | |
| | N/A | |
| | N/A | |
| | N/A | |

Dishwasher Rough-In ☒ Yes ☐ No

Waterline for Fridge ☒ Yes ☐ No

** Refer to Construction Summary

6. Trim Carpentry

| | |
|----------------------------|---|
| Interior Doors | CARRARA-SMOOTH |
| Interior Trim | 3" BB CASING WITH 7 1/4" BASEBOARD - COLONIAL |
| Door Handles | As Per Construction Specifications |
| Exterior Front Door Handle | As Per Construction Specifications |

** Refer to Construction Summary

INSTALLATION INSTRUCTIONS 27" (68.6 CM)
AND 30" (76.2 CM) ELECTRIC SINGLE
AND DOUBLE BUILT-IN OVEN FLUSH
INSTALLATION KIT

INSTRUCTIONS D'INSTALLATION ENSEMBLE
D'INSTALLATION EN AFFLEUREMENT POUR
FOUR ÉLECTRIQUE ENCASTRÉ SIMPLE ET
DOUBLE DE 27" (68,6 CM) ET 30" (76,2 CM)

27" (68.6 cm) Flush Installation Kits
Ensembles d'installation en affleurement de 27" (68,6 cm)

| | Black Noir | Stainless Steel Acier inoxydable | Stainless Steel/ Acier inoxydable, RISE™/NOIR™ |
|---|--|--|--|
| Model# Modèle n° | Kit PN/ Ensemble référence: W10791232 | Kit PN/ Ensemble référence: W10791228 | Kit PN/ Ensemble référence: W11357761 |
| JJW2427DB, JJW2827DB | ★★ | * | * |
| JJW2427DS, JJW2827DS, JJW2727DS | * | ★★ | * |
| JJW2427IM, JJW2427IL, JJW2827IM, JJW2827IL | * | * | ★★ |

30" (76.2 cm) Flush Installation Kits
Ensembles d'installation en affleurement de 30" (76,2 cm)

| | Black Noir | | Stainless Steel Acier inoxydable | | Stainless Steel/ Acier inoxydable, RISE™/NOIR™ | |
|---|---|---|---|---|--|---|
| Model# Modèle n° | Kit PN Ensemble référence: W10791233 | Kit PN Ensemble référence: W10837578 | Kit PN Ensemble référence: W10791229 | Kit PN Ensemble référence: W10837579 | Kit PN Ensemble référence: W11357756 | Kit PN Ensemble référence: W11357769 |
| JJW2430DS, JJW2430DP, JJW2830DS, JJW2830DP, JJW2730DS | * | | ★★ | | * | |
| JJW2430DB, JJW2830DB | ★★ | | * | | * | |
| JJW2430IM, JJW2430IL, JJW2830IM, JJW2830IL | * | | * | | ★★ | |
| JJW3430DS, JJW3430DP, JJW3830DS, JJW3830DP | | * | | ★★ | | * |
| JJW3430IM, JJW3430IL, JJW3830IM, JJW3830IL | | * | | * | | ★★ |
| JJW3430DB, JJW3830DB | | ★★ | | * | | * |

- ★ Approved for use.
- ★★ Recommended color and approved for use.
- ★ Approuvé pour l'utilisation.
- ★★ Couleur recommandée et approuvé pour l'utilisation.

IMPORTANT:
Save for local electrical inspector's use.
IMPORTANT:
À conserver pour consultation par l'inspecteur local des installations électriques.

W11356314A

Parts Supplied

- Deflector bracket



- Plastic spacers - (4) single ovens, (6) double ovens



- #8-18 x 1/4" (6.3 mm) screws - (2) for 27" (68.6 cm) models; (4) for 30" (76.2 cm) models

Location Requirements


IMPORTANT: Observe all governing codes and ordinances.

NOTE: Refer to the following "Location Requirements" and the "Location Requirements" section of the Installation Instructions provided with your built-in oven.

- Cabinet opening dimensions that are shown must be used. Given dimensions provide minimum clearance with oven.
- Recessed installation area must provide complete enclosure around the recessed portion of the oven.
- Oven support surface must be solid, level, and flush with bottom of the cabinet cutout.
- Floor must be able to support a single oven weight of 180 lbs (82 kg).
- Floor must be able to support a double oven weight of 357 lbs (162 kg)

IMPORTANT: To avoid damage to your cabinets, check with your builder or cabinet supplier to make sure that the materials used will not discolor, delaminate, or sustain other damage. This oven has been designed in accordance with the requirements of UL and CSA International and complies with the maximum allowable wood cabinet temperatures of 194°F (90°C).

Deflector Bracket Dimensions



27" (68.6 cm) Models

A. 26 13/16" (68.4 cm) overall width

30" (76.2 cm) Models

A. 29 15/16" (76.0 cm) overall width


Cabinet Dimensions - Single Ovens, Flush Installations

A 25" (63.5 cm) minimum cutout depth is required.

These dimensions will result in a 1/4" (6.3 mm) reveal on the top, a 1/4" (6.3 mm) reveal on the sides, and a 1/8" (3.1 mm) reveal on the bottom of the wall oven.

The front face of the cleats and platform will be visible and should be treated as a finished surface.

Single Ovens Installed in Cabinet - Flush Installation



Front View

Side View

27" (68.6 cm) Models

- A. 3/4" (19 mm) top cleat*
- B. 27 1/4" (69.2 cm) minimum width of flush inset cutout
- C. 25 7/8" (65.7 cm) minimum width of opening
- D. 30 7/16" (77.3 cm) minimum height of flush inset cutout
- E. 29 11/16" (75.4 cm) recommended cutout height
- F. 1 1/16" (1.7 cm) side cleat*
- G. 1/2" x 2" (1.3 cm x 5.1 cm) spacer the entire depth of the cutout*
- H. Recommended junction box location
- I. 4 5/8" - 32" (11.7 cm - 81.3 cm) bottom of cutout to floor
- J. 25" (63.5 cm) minimum depth of cutout

30" (76.2 cm) Models

- A. 3/4" (19 mm) top cleat*
- B. 30 1/4" (76.8 cm) minimum width of flush inset cutout
- C. 28 7/8" (73.3 cm) minimum width of opening
- D. 30 7/16" (77.3 cm) minimum height of flush inset cutout
- E. 29 11/16" (75.4 cm) recommended cutout height
- F. 1 1/16" (1.7 cm) side cleat*
- G. 1/2" x 2" (1.3 cm x 5.1 cm) spacer the entire depth of the cutout*
- H. Recommended junction box location
- I. 4 5/8" - 32" (11.7 cm - 81.3 cm) bottom of cutout to floor
- J. 25" (63.5 cm) minimum depth of cutout

*Cleats and spacers must be recessed 1 3/8" (3.5 cm) from the front of the cabinet.

INSTALLATION INSTRUCTIONS
27" (68.6 CM) AND 30" (76.2 CM) ELECTRIC
BUILT-IN MICROWAVE OVEN FLUSH
INSTALLATION KIT

INSTRUCTIONS D'INSTALLATION
POUR ENSEMBLE D'INSTALLATION EN
AFFLEUREMENT DE FOUR À MICRO-ONDES
ÉLECTRIQUE ENCASTRÉ DE 27" (68,6 CM)
ET 30" (76,2 CM)

27" (68.6 cm) Flush Installation Kits
Ensembles d'installation en affleurement de 27" (68,6 cm)

| | Stainless Steel Acier inoxydable | Stainless Steel/ Acier inoxydable, RISE™/NOIR™ |
|----------------------|---------------------------------------|---|
| Model#/ Modèle n° | Kit PN/ Ensemble référence: W10801485 | Kit PN/ Ensemble référence: W11358283 |
| JMC2427DS | ★★ | ★ |
| JMC2427IM, JMC2427IL | ★ | ★★ |

30" (76.2 cm) Flush Installation Kits
Ensembles d'installation en affleurement de 30" (76,2 cm)

| | Black Noir | Stainless Steel/ Acier inoxydable | Stainless Steel/ Acier inoxydable, RISE™/NOIR™ |
|----------------------|--|--|---|
| Model#/ Modèle n° | Kit PN/ Ensemble référence: W10801487 | Kit PN/ Ensemble référence: W10801486 | Kit PN/ Ensemble référence: W11358282 |
| JMC2430DB | ★★ | ★ | ★ |
| JMC2430DP, JMC2430DS | ★ | ★★ | ★ |
| JMC2430IM, JMC2430IL | ★ | ★ | ★★ |

- ★ Approved for use.
★★ Recommended color and approved for use.
★ Approuvé pour l'utilisation.
★★ Couleur recommandée et approuvé pour l'utilisation.

Table of Contents/Table des matières

| | | | |
|--------------------------------------|---|---|---|
| BUILT-IN MICROWAVE OVEN SAFETY | 2 | SÉCURITÉ DU FOUR À MICRO-ONDES ENCASTRÉ | 5 |
| INSTALLATION REQUIREMENTS..... | 2 | EXIGENCES D'INSTALLATION | 5 |
| Tools and Parts..... | 2 | Outillage et pièces..... | 5 |
| Location Requirements..... | 2 | Exigences d'emplacement..... | 5 |
| INSTALLATION INSTRUCTIONS..... | 4 | INSTRUCTIONS D'INSTALLATION..... | 7 |
| Prepare Built-In Oven..... | 4 | Assemblage de la trousse d'entretoise | 7 |
| Install Spacer Kit | 4 | Installation de la trousse d'entretoise | 7 |
| Install Microwave Oven | 4 | Installation du four à micro-ondes | 7 |
| Complete Installation | 4 | Achever l'installation | 7 |


IMPORTANT:
Save for local electrical inspector's use.

IMPORTANT:
À conserver pour consultation par l'inspecteur local des installations électriques.

W11356316A

Cabinet Dimensions - Flush Installation

A 23³/₄" (59 cm) minimum cutout depth is required. These dimensions will result in a 1/4" (6.3 mm) reveal on the top, a 1/4" (6.3 mm) reveal on the sides, and a 1/8" (3.1 mm) reveal on the bottom of the microwave oven. The front face of the cleats and platform will be visible and should be treated as a finished surface.



27" (68.6 cm) Models

- A. 1³/₁₆" (4.7 cm) top cleat*
- B. 27¹/₄" (69.2 cm) minimum width of flush inset cutout
- C. 25⁷/₈" (65.7 cm) minimum width of opening
- D. 20³/₁₆" (51.3 cm) minimum height of flush inset cutout
- E. 17⁵/₈" (44.7 cm) recommended cutout height
- F. 11/16" (1.7 cm) side cleat*
- G. 3/4" (1.9 cm) bottom cleat*
- H. Recommended junction box location
- I. 40" (101.6 cm) bottom of cutout to floor (recommended)
- J. 23¹/₄" (59.0 cm) minimum depth of cutout
- K. 1³/₈" (3.5 cm) recess from front of cabinet

30" (76.2 cm) Models


- A. 1³/₁₆" (4.7 cm) top cleat*
- B. 30¹/₄" (76.8 cm) minimum width of flush inset cutout
- C. 28⁷/₈" (70.8 cm) minimum width of opening
- D. 20³/₁₆" (51.3 cm) minimum height of flush inset cutout
- E. 17⁵/₈" (44.7 cm) recommended cutout height
- F. 11/16" (1.7 cm) side cleat*
- G. 3/4" (1.9 cm) bottom cleat*
- H. Recommended junction box location
- I. 40" (101.6 cm) bottom of cutout to floor (recommended)
- J. 23¹/₄" (59.0 cm) minimum depth of cutout
- K. 1³/₈" (3.5 cm) recess from front of cabinet

*Cleats must be recessed 1³/₈" (3.5 cm) from the front of the cabinet.

Minimum Installation Clearances

For proper installation, the following minimum clearances must exist below the cabinet opening.

Installation Above Single Built-In Oven



- A. Upper cabinet
- B. Lower single oven*
- C. 1" (2.5 cm) from top of oven


JENN-AIR® DETAILED PLANNING DIMENSIONS

42" SIDE-BY-SIDE REFRIGERATORS WITH DISPENSER

JS42PPDUDE – 42³/₈" x 83³/₈" x 27³/₄" (with handles)

JS42SSDUDE – 42³/₈" x 83³/₈" x 27¹/₈" (with handles)

PRODUCT DIMENSIONS



| MODEL # | | JS42PPDUDE JS42SSDUDE | |
|---------|---|--------------------------|-------|
| | | in | cm |
| A | Width of freezer door (including hinge side offset) | 17½ | 44.4 |
| B | Width of refrigerator door (including hinge side offset) | 23½ | 59.7 |
| C | Space between doors | ¾ | 1.0 |
| D | Overall width (including side trim) | 42¾ | 107.6 |
| E | Height of top grille | 8¾ | 21.7 |
| F | Space between doors and top grille | ¾ | 1.0 |
| G | Height of handles | | |
| | Pro-Style® Stainless | 45⅙ | 115.7 |
| | Euro Style Stainless | 50 | 127.1 |
| H | Height to top of handles | | |
| | Pro-Style® Stainless | 63⅙ | 163.5 |
| | Euro Style Stainless | 65¾ | 167.0 |
| I | Height of doors | 71 | 180.2 |
| J | Height of bottom grille | 3 | 7.6 |
| K | Width of recessed refrigerator | 41 | 104.1 |
| L | Width from side of refrigerator to freezer handle – door fully open 110° | | |
| | Pro-Style® Stainless | 7⅙ | 18.1 |
| | Euro Style Stainless | 6¾ | 17.1 |
| M | Width from side of refrigerator to handle – door open 90° | | |
| | Pro-Style® Stainless | 2⅝ | 6.7 |
| | Euro Style Stainless | 2 | 5.1 |
| N | Width from side of refrigerator to refrigerator handle – door fully open 110° | | |
| | Pro-Style® Stainless | 9⅝ | 24.4 |
| | Euro Style Stainless | 9⅝ | 23.1 |
| O | Depth without doors | 22⅝ | 56.2 |
| P | Depth with doors | 25⅝ | 63.8 |
| Q | Depth with handles | | |
| | Pro-Style® Stainless | 27¾ | 70.5 |
| | Euro Style Stainless | 27⅞ | 68.8 |
| R | Depth with refrigerator door open 90° | 47⅙ | 120.1 |

IMPORTANT: Dimensional specifications are provided for planning purposes only.
Do not make any cutouts based on this information. Refer to the Installation or Use & Care Guide before selecting cabinetry, verifying electrical/gas connections, making cutouts or beginning installation.
All Jenn-Air® appliances are appropriately UL, CUL or CSA approved.




JENN-AIR® DETAILED PLANNING DIMENSIONS

42" SIDE-BY-SIDE REFRIGERATORS WITH DISPENSER

JS42PPDUDE – 42^{3⁄8}" x 83^{3⁄8}" x 27^{3⁄4}" (with handles)

JS42SSDUDE – 42^{3⁄8}" x 83^{3⁄8}" x 27^{1⁄8}" (with handles)

DIMENSIONS AS INSTALLED



SIDE VIEW

| MODEL # | | JS42PPDUDE | JS42SSDUDE |
|---------|--|-------------------|------------|
| | | in | cm |
| A* | Height without compressor (min.) | 74 ^{3⁄8} | 188.9 |
| B* | Height of recessed refrigerator (min.) | 83 ^{3⁄8} | 211.8 |
| C | Depth with refrigerator door open 90° (min.) | 47 ^{1⁄4} | 120.0 |
| D | Depth with handles (min.) | 27 ^{3⁄4} | 70.5 |
| | Pro-Style® Stainless | | |
| D | Euro Style Stainless | 27 ^{1⁄8} | 68.8 |
| E | Depth with doors (min.) | 25 ^{1⁄8} | 63.8 |
| F | Depth without doors (min.) | 22 ^{1⁄8} | 56.2 |
| G | Depth of compressor (min.) | 19 ^{7⁄8} | 50.6 |

*Add 1^{1⁄4}" (3.2 cm) to the height dimension when leveling legs are fully extended.

IMPORTANT: Dimensional specifications are provided for planning purposes only.
Do not make any cutouts based on this information. Refer to the Installation or Use & Care Guide before selecting cabinetry, verifying electrical/gas connections, making cutouts or beginning installation.
All Jenn-Air® appliances are appropriately UL, CUL or CSA approved.




JENN-AIR® DETAILED PLANNING DIMENSIONS

42" SIDE-BY-SIDE REFRIGERATORS WITH DISPENSER


JS42PPDUDE – 42^{3⁄8}" x 83^{3⁄8}" x 27^{3⁄4}" (with handles)

JS42SSDUDE – 42^{3⁄8}" x 83^{3⁄8}" x 27^{1⁄8}" (with handles)

OPENING/CLEARANCE DIMENSIONS



FRONT VIEW



BACK VIEW

| MODEL # | | JS42PPDUDE JS42SSDUDE | |
|---------|--|--------------------------|-------|
| | | in | cm |
| A | Width (min.) | 41½ | 105.4 |
| B | Width of recommended electrical location | 7½ | 19.1 |
| C | Distance from side of cabinet to recommended water connection location | 6 | 15.2 |
| D | Height (min.) | 84 | 213.4 |
| E | Height to recommended electrical location | 77 | 195.6 |
| F | Depth of recommended water connection location (max.) | 1 | 2.5 |
| e | Recommended electrical connection location | | |
| w | Recommended water connection location | | |

ELECTRICAL REQUIREMENTS

115 volt, 60 Hz, AC only, 15- or 20-amp fused, grounded circuit is required. A dedicated circuit is recommended. Use an outlet that cannot be turned off by a switch.
Minimum length of power cord is 84" (213.4 cm). Do not use an extension cord.

WATER PRESSURE REQUIREMENTS

A cold water supply with water pressure between 30 and 120 psi (207 and 827 kPa) is required to operate the water dispenser and ice maker. Call a licensed, qualified plumber with any questions about the water pressure.

Reverse Osmosis Water Supply

IMPORTANT: The pressure of the water coming out of a reverse osmosis system going to the water inlet valve of the refrigerator needs to be between 30 and 120 psi (207 and 827 kPa).
If a reverse osmosis water filtration system is connected to the cold water supply, the water pressure to the reverse osmosis system needs to be a minimum of 40 to 60 psi (276 to 414 kPa).

LOCATION REQUIREMENTS

Floor must be able to support refrigerator (more than 600 lb [272 kg]) and contents of the refrigerator and must be at the same level as flooring in the room.

IMPORTANT: Dimensional specifications are provided for planning purposes only.
Do not make any cutouts based on this information. Refer to the Installation or Use & Care Guide before selecting cabinetry, verifying electrical/gas connections, making cutouts or beginning installation.
All Jenn-Air® appliances are appropriately UL, CUL or CSA approved.




8115AdZw915


JENN-AIR® DETAILED PLANNING DIMENSIONS

36" INDUCTION COOKTOP
JIC4536X – 36¼" x 4⅛" x 21⅜"


PRODUCT DIMENSIONS



TOP VIEW



FRONT VIEW



SIDE VIEW


| MODEL # | | JIC4536X | |
|---------|--|----------|------|
| | | in | cm |
| A | Overall width | 36¼ | 92.2 |
| B | Overall depth | 21⅜ | 54.1 |
| C | Width of recessed cooktop | 32½ | 82.6 |
| D | Height of recessed cooktop | 3⅛ | 8.0 |
| E | Recessed height including front flange | 3⅞ | 9.8 |
| F | Height of cooking surface | | |
| | Euro-Style Stainless (including trim) | ¼ | 0.6 |
| | Floating Glass | ⅛ | 0.4 |
| G | Depth of recessed cooktop | 18⅞ | 47.9 |
| H | Recessed height including electrical conduit | 4⅛ | 10.5 |

Product dimension, cutout and installation specifications are provided for planning purposes only. Before installing any product, be sure to verify cutout dimensions and electrical/gas connections as actual product dimensions may vary.


JENN-AIR® DETAILED PLANNING DIMENSIONS

36" INDUCTION COOKTOP
JIC4536X – 36¼" x 4⅛" x 21⅜"


OPENING/CLEARANCE DIMENSIONS



FRONT VIEW



SIDE VIEW



TOP VIEW – CUTOUT

| MODEL # | | JIC4536X | |
|---------|---|----------|------|
| | | in | cm |
| A | Width of combustable area above cooking surface (min.) | 33⅛ | 84.0 |
| B | Width from cooktop to fixed wall or other combustable material (min.) | 1 | 2.5 |
| C | Width to outer edge of outlet (min.) | 10 | 25.4 |
| D* | Height to bottom of uncovered wood or metal cabinet above cooking surface (min.) | 30 | 76.2 |
| E | Height to bottom of uncovered wood or metal cabinet (min.) | 18 | 45.7 |
| F | Required height of ventilation opening in front cabinet under countertop for proper ventilation – full width of cooktop | ⅜ | 0.5 |
| G | Height to top edge of outlet (min.) | 12 | 30.5 |
| H | Depth of upper cabinet (recommended) | 13 | 33.0 |
| I | Depth from cutout to wall (min.) | 1 | 2.5 |
| J | Width of cutout | 33⅛ | 84.0 |
| K | Depth of cutout | 19¼ | 49.0 |
| L | Depth from cutout to front of countertop | 2 | 5.1 |
| e | Recommended electrical access location | | |

*Dimension can be reduced by 6" (15.2 cm) when bottom of wood or metal cabinet is covered by not less than ¼" (0.6 cm) flame retardant millboard covered with not less than No. 28 MSG sheet metal, 0.015" (0.4 mm) stainless steel, 0.024" (0.6 mm) aluminum or 0.020" (0.5 mm) copper.
If installing a hood or microwave hood combination above the cooktop, follow the hood or microwave hood combination instructions for dimensional clearances above the cooking surface.

ELECTRICAL REQUIREMENTS

240 volt, 60 Hz, AC only, 50-amp fused, grounded circuit is required. A dedicated circuit is recommended. The length of conduit provided is for serviceability to the cooktop.

LOCATION REQUIREMENTS

- To ensure cooktop base clearance, cabinet side walls need to be wider than the cutout.
- If cabinet has a drawer, allow a 5⅞" (13.0 cm) minimum clearance between countertop and top of drawer.

COOKTOP OVER SINGLE WALL OVEN INSTALLATION REQUIREMENTS

- For approved model number combinations, refer to the under counter label on the bottom of the cooktop burner box.
- To install a cooktop over a single wall oven, refer to page 3.

Product dimension, cutout and installation specifications are provided for planning purposes only. Before installing any product, be sure to verify cutout dimensions and electrical/gas connections as actual product dimensions may vary.



JENN-AIR® DETAILED PLANNING DIMENSIONS

SINGLE WALL OVEN AND COOKTOP COMBINATIONS

For the approved model number combinations, refer to the under counter label located on top of the oven chassis and on the bottom of the cooktop burner box.

APPROVED MODEL NUMBER COMBINATIONS

SINGLE WALL OVENS

30-Inch: JJW3430W, JJW2430W, JJW2330W
27-Inch: JJW2427W, JJW2327W

INDUCTION COOKTOPS

36-Inch: JIC4536X
30-Inch: JIC4430X


GAS COOKTOPS

36-Inch: JGC9536BD, JGC1536AD, JGC8536BD
30-Inch: JGC9430BD, JGC1430AD, JGC8430CD


ELECTRIC COOKTOPS

36-Inch: JEC4536Y, JEC9536BD, JEC8536BD
30-Inch: JEC4530Y, JEC9530BD, JEC8430BD

OPENING/CLEARANCE DIMENSIONS



FRONT VIEW –
UNDER COUNTER INSTALLATION
(with cooktop installed above)



SIDE VIEW –
UNDER COUNTER INSTALLATION
(with cooktop installed above)

| MODEL # | | JJW3430W JJW2430W JJW2330W | | JJW2427W JJW2327W | |
|---------|--|----------------------------------|------|----------------------|------|
| | | in | cm | in | cm |
| A | Width of cabinet (min.) | 30 | 76.2 | 27 | 68.6 |
| B | Width of cutout (recommended) | 28½ | 72.4 | 25½ | 64.8 |
| C | Oven trim overlap | ⅝ | 1.6 | ⅝ | 1.6 |
| D | Bottom of countertop to floor | 34½ | 87.6 | 34½ | 87.6 |
| E | Bottom of countertop to bottom of cutout | | | | |
| | Induction cooktop combination | 30⅞ | 78.4 | 30⅞ | 78.4 |
| | Gas cooktop combination | 29⅞ | 75.9 | 29⅞ | 75.9 |
| F | Height of cutout (recommended) | 27¾ | 70.5 | 27¾ | 70.5 |
| | Bottom of cutout to floor | | | | |
| | Induction cooktop combination | 3⅝ | 9.2 | 3⅝ | 9.2 |
| G | Gas cooktop combination | 4⅝ | 11.7 | 4⅝ | 11.7 |
| | Electric cooktop combination | 4⅝ | 11.7 | 4⅝ | 11.7 |
| H | Depth of cabinet (min.) | 24 | 61.0 | 24 | 61.0 |
| e | Recommended junction box location | | | | |
| g | Recommended gas supply line location for gas cooktop | | | | |

NOTE: For under counter installation, the junction box should be located in the adjacent right or left cabinet. Drill a 1" (2.5 cm) minimum diameter hole in an upper corner of the side wall for access to the junction box.

CABINET REQUIREMENTS

NOTE: When using under counter installation, check cabinet manufacturer's specifications to verify fit.