

CONSTRUCTION SUMMARY

Mountainview Heights 3 (G) - Russell Gardens Building Ltd.

PURCHASERS: Neil SURI and Kirstin Ellen SURI

TEL: RES.: 905-890-1010 BUS.: 416-573-3254

LOT / PHASE 367 / 4	REG. PLAN # 62M-1266	HOUSE TYPE Mountainash Five (4 Bedroom) Elev 1		
------------------------	-------------------------	---	--	--

CABINETRY

1 - KITCHEN CABINETRY - TWO COLOUR KITCHEN - FLAT FEE 24Mar22 Note:	
1 - CABINETRY - KITCHEN - HARDWARE UPGRADE 1 24Mar22 Note:	
1 - VANITY - ENSUITE BATHROOM - UPGRADE 2 24Mar22 Note:	
1 - VANITY - POWDER ROOM - UPGRADE 2 24Mar22 Note:	
1 - CABINETRY PROVISION - FARMERS SINK PROVISION 24Mar22 Note:	
1 - CABINETRY - KITCHEN - UPGRADE 5 24Mar22 Note:	
1 - CABINETRY - KITCHEN - LIGHT VALENCE 24Mar22 Note:	

CABINETRY ACCESSORIES

1 - ***** DELETE ***** CABINETRY FEE FOR FLUSH CUTOUT ON WALL OVEN/MICROWAVE COMBO CABINET ONLY 14Apr22 Note:	
1 - MASTER ENSUITE - SOFT CLOSE DOORS AND DRAWERS 14Apr22 Note:	
1 - POWDER - SOFT CLOSE DOORS 14Apr22 Note:	
1 - KITCHEN - SOFT CLOSE DRAWERS AND DOORS 14Apr22 Note:	
2 - KITCHEN CABINETRY BASE - DUMMY DOOR FOR BASE CABINETRY - PRICE IS PER DOOR - UPGRADE 5 14Apr22 Note:	
1 - PANTRY UNIT UPGRADE - TO GO FROM 300MM TO 600MM DEEP - PRICE IS PER FOOT - UPGRADE 5 24Mar22 Note:	
4 - KITCHEN CABINETRY BASE - DUMMY DOOR FOR BASE CABINETRY - PRICE IS PER DOOR - UPGRADE 5 24Mar22 Note: ISLAND - REFER TO SKETCH	
1 - KITCHEN HOOD CABINETS - TRANSITIONAL WOOD HOOD (DHB) 800-1000 WIDE - UPGRADE 5 24Mar22 Note:	
1 - KITCHEN CABINETRY BASE - BEVERAGE FRIDGE PROVISION 24Mar22 Note: SERVERY WALL - REFER TO SKETCH	
1 - KITCHEN CABINETRY BASE - BUILT-IN - MICROWAVE BASE CABINET WITH SINGLE POT DRAWER - 800MM WIDE - PRICE IS EACH - UPGRADE 5 24Mar22 Note: ISLAND	

CONSTRUCTION SUMMARY

Mountainview Heights 3 (G) - Russell Gardens Building Ltd.

PURCHASERS: Neil SURI and Kirstin Ellen SURI

TEL: RES.: 905-890-1010 BUS.: 416-573-3254

LOT / PHASE	REG. PLAN #	HOUSE TYPE		
367 / 4	62M-1266	Mountainash Five (4 Bedroom) Elev 1		
1 - KITCHEN CABINETRY BASE - PULLOUT RECYCLE 2 BIN - PRICE IS EACH 24Mar22 Note:				
1 - KITCHEN CABINETRY UPPER - ANGLED CORNER CABINET - FITS TALL UPPER CABINETS - PER UNIT - UPGRADE 5 24Mar22 Note:				
1 - KITCHEN CABINETRY BASE - PIE CUT CORNER CABINET - BASE CABINETRY - UPGRADE 5 24Mar22 Note:				
1 - CABINETRY FEE FOR FLUSH CUTOUT MICROWAVE CABINET ONLY 24Mar22 Note:				
2 - KITCHEN CABINETRY BASE - POT/PAN DRAWERS (CABINET) - UPGRADE 5 24Mar22 Note:				
1 - KITCHEN CABINETRY BASE - PULLOUT WIRE SPICE RACK - PRICE IS EACH 24Mar22 Note:				
1 - KITCHEN CABINETRY UPPER - FULL DEPTH ABOVE FRIDGE - WITH GABLES - 600MM - PRICE IS EACH - UPGRADE 5 24Mar22 Note:				

CERAMIC TILE

1 - HEATED FLOORING - MASTER ENSUITE, ENSUITE 2 AND ENSUITE 3/4 24Mar22 Note:	
1 - TILE - UPGRADE 4 FLOOR TILE - - LAUNDRY ROOM - 2ND FLOOR - FLOOR 24Mar22 Note:	
1 - TILE - UPGRADE 4 FLOOR TILE - - BATHROOM 2 - FLOOR 24Mar22 Note:	
1 - TILE - UPGRADE 2 FLOOR TILE - - BATHROOM 3/4 - FLOOR 24Mar22 Note:	
1 - DELETE ALL CERAMIC BATHROOM ACCESSORIES - DELETE TOWEL BAR, PAPER HOLDER & SOAP DISH THROUGHOUT 24Mar22 Note:	
1 - TILE - UPGRADE 4 WALL TILE - - ENSUITE WALL TILE - SHOWER 24Mar22 Note:	
1 - TILE - UPGRADE 4 FLOOR TILE - - ENSUITE BATHROOM - FLOOR 24Mar22 Note:	
1 - TILE - UPGRADE 4 FLOOR TILE - - MUD ROOM 24Mar22 Note:	
1 - TILE - UPGRADE 4 FLOOR TILE - - POWDER ROOM 24Mar22 Note:	
1 - TILE - UPGRADE 4 FLOOR TILE - - FOYER 24Mar22 Note:	

CONSTRUCTION

CONSTRUCTION SUMMARY

Mountainview Heights 3 (G) - Russell Gardens Building Ltd.

PURCHASERS: Neil SURI and Kirstin Ellen SURI

TEL: RES.: 905-890-1010 BUS.: 416-573-3254

LOT / PHASE	REG. PLAN #	HOUSE TYPE		
367 / 4	62M-1266	Mountainash Five (4 Bedroom) Elev 1		
1 - SMOOTH CEILINGS ON FIRST FLOOR ONLY - DET 24Mar22 Note:				
1 - PROVISION FOR SHAMPOO NICHE APPROX. 14" WIDE X 20" HIGH AS PER SKETCH – IF CONSTRUCTION PERMITS 24Mar22 Note:				
1 - PROVISION FOR SHAMPOO NICHE APPROX. 24" WIDE X 20" HIGH AS PER SKETCH – IF CONSTRUCTION PERMITS 30Aug21 Note:				
1 - PROVISION FOR SHAMPOO NICHE APPROX. 14" WIDE X 20" HIGH AS PER SKETCH – IF CONSTRUCTION PERMITS 30Aug21 Note:				
1 - MASTER BEDROOM- CLOSET MADE SMALLER-SEE SKETCH 27May21 Note:				

COUNTER TOP

1 - COUNTERTOP - UPGRADE - KITCHEN - BACKSPLASH 14Apr22 Note: INCLUDES SERVERY	
1 - SHOWER SEAT – UPGRADE MATERIAL IN LIEU OF STANDARD MATERIAL 24Mar22 Note: MASTER ENSUITE	
1 - SHOWER JAMS – UPGRADE MATERIAL IN LIEU OF STANDARD MATERIAL 24Mar22 Note: MASTER ENSUITE	
1 - COUNTER TOP - UPGRADE - ENSUITE BATHROOM VANITY COUNTER TOP 24Mar22 Note:	
1 - COUNTER TOP - UPGRADE - POWER ROOM VANITY COUNTER TOP 24Mar22 Note:	
1 - COUNTER TOP - UPGRADE - KITCHEN COUNTER TOP 24Mar22 Note:	
1 - SHAMPOO NICHE 14" WIDE X 20" HIGH AS PER SKETCH – MARBLE, GRANITE OR QUARTZ – IF CONSTRUCTION PERMITS - REQUIRES PROVISION FROM CONSTRUCTION 24Mar22 Note: SUPPLY & INSTALL ENSUITE 3/4	
1 - SHAMPOO NICHE 24" WIDE X 20" HIGH AS PER SKETCH – MARBLE, GRANITE OR QUARTZ – IF CONSTRUCTION PERMITS - REQUIRES PROVISION FROM CONSTRUCTION 30Aug21 Note: SUPPLY & INSTALL	
MASTER ENSUITE SHOWER	
1 - SHAMPOO NICHE 14" WIDE X 20" HIGH AS PER SKETCH – MARBLE, GRANITE OR QUARTZ – IF CONSTRUCTION PERMITS - REQUIRES PROVISION FROM CONSTRUCTION 30Aug21 Note: SUPPLY & INSTALL	
BED 2 ENSUITE SHOWER	

DOORS AND TRIM

1 - DOOR HANDLES - FRONT EXTERIOR DOOR (TAVARIS 11P) AND INTERIOR DOORS (LISBON SQT 514) THROUGH OUT 24Mar22 Note:	
24 - DOORS INTERIOR - FOR 8 OR 9 FOOT CEILING - LOGAN SMOOTH HALLOW IN LIEU OF STANDARD SERIES - PRICE IS PER DOOR 24Mar22 Note:	

ELECTRICAL

CONSTRUCTION SUMMARY

Mountainview Heights 3 (G) - Russell Gardens Building Ltd.

PURCHASERS: Neil SURI and Kirstin Ellen SURI

TEL: RES.: 905-890-1010 BUS.: 416-573-3254

LOT / PHASE	REG. PLAN #	HOUSE TYPE		
367 / 4	62M-1266	Mountainash Five (4 Bedroom) Elev 1		
1 - KITCHEN - FAN INSERT FOR UPGRADE 30" HOOD - CYCLONE BX21528 24Mar22 Note:				
1 - ENSUITE 3/4 - HEATED FLOOR 24Mar22 Note:				
1 - ENSUITE 2 - HEATED FLOOR 24Mar22 Note:				
1 - MASTER ENSUITE - HEATED FLOOR 24Mar22 Note:				
1 - RELOCATE STANDARD KITCHEN LIGHT TO BE CENTERED OVER ISLAND 24Mar22 Note:				
1 - PLUG - ELECTRICAL PLUG - TO BE INSTALLED OVER FIREPLACE 24Mar22 Note:				
1 - PLUG - ELECTRICAL PLUG - FOR BUILT-IN MICROWAVE 24Mar22 Note:				

HARDWOOD

1 - INTERGRATED VENTS - 1ST FLOOR ONLY 14Apr22 Note:	
---	--

HARDWOOD FLOORING

1 - HARDWOOD - GROUP B SERIES 5 INCH - IN LIEU OF STANDARD TILE- KITCHEN 24Mar22 Note:	
1 - HARDWOOD - GROUP B SERIES 5 INCH - IN LIEU OF 2 1/4 INCH NATURAL RED OAK - - FAMILY ROOM 24Mar22 Note:	
1 - HARDWOOD - GROUP B SERIES 5 INCH - IN LIEU OF 2 1/4 INCH NATURAL RED OAK - - LIBRARY/DEN 24Mar22 Note:	
1 - HARDWOOD - GROUP B SERIES 5 INCH - IN LIEU OF 2 1/4 INCH NATURAL RED OAK - - LIVING AND DINING ROOM 24Mar22 Note:	
1 - HARDWOOD - GROUP B SERIES 5 INCH - IN LIEU OF 2 1/4 INCH NATURAL RED OAK - - MAIN HALL 24Mar22 Note:	

MIRRORS AND GLASS

1 - DELETE STANDARD MIRRORS THROUGHOUT 24Mar22 Note:	
1 - FRAMELESS GLASS SHOWER DOOR FOR 5 FOOT PAN - INCLUDES CHROME KNOB & HINGES 27May21 Note:	

MISCELLANEOUS

1 - GARAGE DOOR OPENER -- LIFE MASTER 8355 WITH BELT DRIVE -- INLCUDES 1 KEYPAD & 2 HANDHELD CONTROL 24Mar22 Note:	
---	--

PLUMBING

CONSTRUCTION SUMMARY

Mountainview Heights 3 (G) - Russell Gardens Building Ltd.

PURCHASERS: Neil SURI and Kirstin Ellen SURI

TEL: RES.: 905-890-1010 BUS.: 416-573-3254

LOT / PHASE	REG. PLAN #	HOUSE TYPE		
367 / 4	62M-1266	Mountainash Five (4 Bedroom) Elev 1		
3 - SINK - UNDERMOUNT SINK - CONTRAC EMERY #4220CGY 24Mar22 Note: POWDER MASTER ENSUITE - X2				
1 - SINK - UNDERMOUNT SINK - BLANCO - CERANA - FIRECLAY - CERAMIC WHITE - 401428 24Mar22 Note: KITCHEN				
1 - MASTER ENSUITE- ENLARGE SHOWER TO A 5FT SHOWER-SEE SKETCH 27May21 Note:				

PROMOTIONAL

1 - LESS BALANCE OF CREDIT FROM PURCHASER EXTRA SHEET IN OFFER 24Mar22 Note:	
1 - LESS CREDIT FROM PURCHASER EXTRA SHEET IN OFFER 30Aug21 Note:	
1 - LESS BALANCE OF CREDIT FROM PURCHASER EXTRA SHEET IN OFFER 30Aug21 Note: NEW PROMO BALANCE \$2800.00	
1 - LESS CREDIT FROM PURCHASER EXTRA SHEET IN OFFER 27May21 Note: NEW PROMO BALANCE \$5650.00	

STAIRS AND RAILINGS

1 - V GROOVE HANDRAIL 24Mar22 Note:	
1 - EUROLINE 0 24Mar22 Note: BLACK IRON PICKET	
1 - STAINED STAIRS – STANDARD STAIRCASE - PRICE IS PER SET 24Mar22 Note:	

EXTRAS AS PER OFFER


PURCHASER(S) ACKNOWLEDGES THAT THE PURCHASE PRICE IS INCLUSIVE OF ALL CREDITS AND PROMOTIONAL PACKAGES AVAILABLE AT TIME OF PURCHASE. Worksheet Note:	
The Vendor agrees that notwithstanding any other term or provision in this Agreement included in the Purchase Price and in addition to those items detailed in Schedule GP to the Agreement of Purchase and Sale, the Purchaser is entitled to a credit of Ten Worksheet Note:	
Granite kitchen counter top, from Vendor's standard samples Worksheet Note:	



Revised



Greenpark



INTERIOR COLOUR SCHEME



Purchasers: Neil SURR & Kirstin Ellen SURR
Telephone Res. / Bus: (905) 890-1010 / (416) 573-3254
Decor Advisor: Aly Averna
Lock Date: 14-Apr-22

Property: 567
Project: Russell Gardens Building Ltd.
Model and Elevation: Mountcrest Five (4 Bedroom) Elev 1
Plan #: 62M-1266

3. Ceramic Flooring

Entrance Vestibule TILE-NANTES WHITE POLISHED 24X24
Main Hall HARDWOOD
Kitchen / Breakfast HARDWOOD
Laundry Room TILE-CRAFT COTTON 12X24
Powder Room TILE-NANTES WHITE POLISHED 24X24
Master Ensuite Bathroom TILE-AGATA WHITE POLISHED 24X24
Ensuite Bath - Bedroom 2 TILE-CRAFT COTTON 12X24
Ensuite Bath - Bedroom 3/4 TILE-MARMANI BIANCO 12X24
MUD ROOM TILE-NANTES WHITE POLISHED 24X24

As per 45 Threshold & App.

Metals: Same as App.

** Refer to Construction Summary

4. Ceramic Wall Tile

Master Ensuite Bathroom

Selection

Describe

Tub Deck Wall N/A

Tub Deck N/A

Tub Deck Skirt N/A

Shower Stall TILE-AGATA WHITE POLISHED 12X24

Bathtub Enclosure Walls N/A

Ensuite Bath - Bedroom 2

TILE-CONCEPT PLUS GREY POLISHED 8X16

Ensuite Bath - Bedroom 3/4

TILE-BIANCO LUCIDO 8X16

MUD ROOM

SHAMPOO NICHE: JAMBS/SEAT (STRA) (C)

SHAMPOO NICHE: VEGA (C)

SHAMPOO NICHE: VEGA (C)

Kitchen Backsplash

QUARTZ-GRECALE (C)

** Refer to Construction Summary - STANDARD GROUT THROUGHOUT UNLESS SPECIFIED

5. Plumbing Fixtures

All Bathrooms

White

Whirlpool

☐ Yes ☒ No

Dishwasher Rough-In ☒ Yes ☐ No

Waterline for Fridge ☐ Yes ☒ No

** Refer to Construction Summary

6. Trim Carpentry

Interior Doors

LOGAN-SMOOTH

Interior Trim

As Per Construction Specifications

Door Handles

LISBON SQT 514


Exterior Front Door Handle TAVARIS 11P

** Refer to Construction Summary

Initials:




Page 2 of 4



NS
KS

This drawing is the intellectual property of SEIDA INDUSTRIES INC. and is an artistic interpretation of the general appearance of the design. It is not meant to be an exact rendition.	 SEIDA - Your Design	Design: NS102023
		Printed: 4/22/2023
RUSSELL GARDENS LOT 367 P144		LAYOUT Drawing #:



15
18

This drawing is the intellectual property of
SELBA INDUSTRIES INC. and is an
artistic
interpretation of the general
appearance of the design. It is
not meant to be an exact rendition.


Selba
written - ink design

Design: 3/31/2022
Printed: 3/31/2022

RUSSELL GARDENS LOT 367 PH4


LAYOUT


Sheet # 1



NS
15


<p>This drawing is the intellectual property of SELBA INDUSTRIES INC. and is an artistic interpretation of the general appearance of the design. It is not meant to be an exact rendition.</p>	<p><i>[Signature]</i> Kitchen + Bath Design</p>	<p>Designated: 11/31/2022 Project: 103170021</p>
<p>RUSSELL GARDENS LOT 367 B14</p>		<p>LAYOUT Drawing 2 of 1</p>





This drawing is the intellectual property of SELBA INDUSTRIES INC. and is an artistic interpretation of the general appearance of the design. It is not meant to be an exact rendition.	 Selba Industries Inc. Interior • Bath • Design	Designed: 1/11/2022	
		Printed: 2/11/2022	
		RUSSELL GARDENS LOT 367 PH-4	
		LAYOUT	Drawing #

Café™ 5.7 Cu. Ft.
Built-In Dual-Drawer Refrigerator
CDE06RP3ND1 / CDE06RP2NS1



CDE06RP3ND1
Matte Black with Brushed
Stainless handles

ALSO
AVAILABLE IN



CDE06RP2NS1
Stainless Steel with
Brushed Stainless
handle and knobs



FEATURES & BENEFITS

Impress your guests every time you open the drawers with an attractive **stainless steel interior** that is also easy to clean.

Never let grabbing a quick snack interrupt your conversations, thanks to **soft-close drawers** that slide quietly closed.

Favorite wines are always perfectly chilled and ready to serve with a large **5.7 cu. ft. capacity** that easily holds upright bottles.

Keep all your fresh foods and drinks organized with an **adjustable divider** that maximizes flexibility and storage capacity in both drawers.

Fresh vegetables and craft beers are always stored in their ideal climate, thanks to an **exact temperature control** that chills items between 34° and 45° F.

Sharable foods are easy to find and easy to serve with **LED lighting** that provides clear, bright light throughout the drawers.

APPEARANCE

Exterior design	Flat doors
Handle design	Café

FEATURES

Control Type	Electronic
Interior Lighting	LED
Leveling System	Leveling Legs
Defrost Type	Auto
Defrost Water Drain	Yes
Sabbath Mode	Yes
Sort Capacity	5.7

CAPACITY

Total Capacity (cubic feet)	5.7 cu ft
-----------------------------	-----------

WEIGHTS & DIMENSIONS

Approximate Shipping Weight	135 lb
Net Weight	126 lb
Depth Without Handle	23 3/4 in
Overall Depth	26 in
Overall Height	33 7/8 in
Overall Width	23 7/8 in


Café™ 5.7 Cu. Ft.
Built-In Dual-Drawer Refrigerator
CDE06RP3ND1 / CDE06RP2NS1



WARRANTY

Parts warranty	Limited 1-year entire appliance
Labor warranty	Limited 1-year entire appliance
Warranty notes	See written warranty for full details

DIMENSIONS



ADDITIONAL ACCESSORIES



CXQD2H2PNBZ
Brushed Bronze
2 handles




CXQD2H2PNBT
Brushed Black
2 handles



CXQD2N2PNCU
Brushed Copper
2 handles

Café™ Energy Star® 22.2 Cu. Ft. Counter-Depth
French-Door Refrigerator with Hot Water Dispenser
CYE22TP4MW2 / CYE22TP2MS1 / CYE22TP3MD1



CYE22TP4MW2
Matte White with
Brushed Bronze handles



FEATURES & BENEFITS

Create a built-in look with **counter-depth design** that fits flush with surrounding cabinetry.

Steep a relaxing herbal tea or prepare light & fluffy couscous with an adjustable **hot water dispenser** that provides precise temperatures and measurements.

Use your voice or **smart device** to preheat water from your refrigerator while you relax in another part of the house.

Leave the measuring cups in the drawer with a **Precise Fill setting** that dispenses an exact amount of water with just a touch.

Food remains fresh longer with **TwinChill™ evaporators** that accurately maintain and control separate freezer and refrigerator environments.

Keep key ingredients fresh and within sight with a full-width, electronic, **temperature-controlled drawer** that uses an LED colored lighting system.

Display groceries like a gallery with **showcase LED lighting** positioned throughout the interior to spotlight your favorite foods and containers.

Protect your family and guests with an **advanced water filtration system** that uses RPWFE replacement filters to remove 98% of pharmaceuticals from ice and water*.

*Removes 98% of ibuprofen, atenolol, fluoxetine, progesterone and trimethoprim. These pharmaceuticals are not necessarily in all users' water.

APPEARANCE

Counter-depth design	Yes
Exterior design	Flat doors
Handle design	GE Café
Hidden door hinge(s)	Yes
Textured steel case	Case only—Dark gray

FEATURES

Configuration	French door
WiFi connect	Built-in
Connected capabilities	Amazon Alexa; The Google Assistant; IFTTT
Temperature management features	Turbo Cool setting
Temperature management system	TwinChill™ evaporators
Defrost type	Frost Guard
Control type	External touch color LCD
Dispenser	Large stainless steel; cubes, crushed ice and water
Dispenser features	Hot water; Precise Fill; LCD screen controls; Door alarm; LED dispenser light; Water filter indicator light
Icemaker	Space saving ice
Water filtration	Advanced filtration system (RPWFE); Removes pharmaceuticals; Water filter indicator light
Filter location	Left wall
Fresh food cabinet drawers	3 total; 2 adjustable humidity drawers; 1 full-width, adjustable temperature with LED lighting
Fresh food cabinet shelves	5 total—glass with silver trim; 4 split adjustable; 1 full-width; 3 spill proof; 1 Quick Space shelf
Fresh food door bins	6 total (2 adjustable with gallon storage)
Fresh food door features	Dairy compartment; Drop down tray
Fresh food features	Showcase LED lighting (7); Deli pan
Freezer storage baskets	2 full-width
Freezer features	Turbo Freeze; Interior lighting—showcase LED (2)
Exterior style	Counter-depth
Leveling system	2 front leveling legs
Performance features	Easily removable door gaskets; Sabbath Mode capable

CAPACITY

Total capacity (cubic feet)	22.2 cu. ft.
Fresh food capacity	15.0 cu. ft.
Freezer capacity	7.2 cu. ft.

WEIGHTS & DIMENSIONS

Overall depth	31-1/4 in.
Overall height	69-7/8 in.
Overall width	35-3/4 in.
Case depth without door	24-3/8 in.
Depth with door open 90°	43-3/8 in.
Depth without handle	30-1/4 in.
Height to top of case	69 in.
Width with door open 90° including handle	44-3/4 in.
Approximate shipping weight	393 lb.
Net weight	365 lb.


Café™ Energy Star® 22.2 Cu. Ft. Counter-Depth
French-Door Refrigerator with Hot Water Dispenser
CYE22TP4MW2 / CYE22TP2MS1 / CYE22TP3MD1



WARRANTY

Parts warranty	Limited 1-year entire appliance; Limited 5-year sealed refrigerating system
Labor warranty	Limited 1-year entire appliance; Limited 5-year sealed refrigerating system
Warranty notes	See written warranty for full details


DIMENSIONS




Height to top of door (in.) A	70-1/2
Height to top of hinge (in.) B	69-7/8
Height to top of case (in.) C	69
Case depth without door (in.) D**	24-3/8
Case depth less door handle (in.) E**	30-1/4*
Case depth with door handle (in.) F**	31-1/4
Depth with fresh food door open 90° (in.) G**	43-3/8
Width (in.) H	35-3/4
Width with door open 90° with door handle (in.) I	44-3/4
Width with doors open fully (in.) J	61-5/8
Min distance between side of case and wall, in either direction, to allow doors to open fully (in.) K	13-1/8
Depth with FZ door completely open (w/o handle) (in.) X	44-1/4
Depth with FZ door completely open (w/ handle) (in.) Y	46-3/4

*Includes hot water knob.
**Water hookup fits in back air clearance when calculating installation depth.


ADDITIONAL ACCESSORIES




CXLB3H3PMBZ
Brushed Bronze
3 handles
(Standard on Matte White)



CXLB3H3PMSS
Brushed Stainless
3 handles
(Standard on Matte Black and Stainless Steel)




CXLB3H3PMBT
Brushed Black
3 handles



CXLB3H3PMCU
Brushed Copper
3 handles

For answers to your Café™ product questions, visit our website at cafeappliances.com.


Café™ 30" Slide-In Front Control Dual-Fuel Convection Range with Warming Drawer
C2S900P4MW2 / C2S900P3MD1 / C2S900P2MS1



ALSO
AVAILABLE IN



C2S900P2MS1
Stainless Steel with
Brushed Stainless
handles and knobs



C2S900P4MW2
Matte White with
Brushed Bronze
handles and knobs



FEATURES & BENEFITS

Expansive six-burner cooktop helps you entertain with ease - Entertaining for large groups is easy with the industry's first six burner, edge-to-edge cooktop that can accommodate cookware of all sizes and a cast-iron integrated griddle that provides enough room to perfectly flip crab cakes, arepas and other crowd favorites

Enjoy total control in the kitchen and beyond - Control your oven with your smart device or simply your voice using WiF Connect

An attractive appearance at all times - Every detail of your kitchen is designed to delight, thanks to a sleek backlit glass touch control panel that visually disappears when not in use and wakes up when prompted

Share favorite creations with your favorite people - Create an unforgettable dinner, using a 21K tri-ring burner to do everything from searing scallops to simmering a lemon caper white wine sauce and a 15K power boil burner to boil water quickly for al dente angel hair pasta

Treat yourself to the best of both worlds - Get the precision you need to pull off a multi-course dinner party with Dual Fuel, which boasts a gas-powered cooktop for precise heat control and electric True European Convection with Precise Air in the oven for even baking results.

Never scrub, smooth-glide racks - Easily remove heavy dishes with a roller rack that is specially designed to glide smoothly and stay in the oven during the self-clean cycle, so you never have to handle cumbersome racks again

Create a look that matches your personal style - Select any combination of premium finishes and hardware options to create a stunning look customized to any owner's taste

Prepare foods to perfect doneness - Get roasts and meats just right with a temperature probe that lets you monitor progress without opening the oven door

APPEARANCE

Cooktop Burner Grate Color	Matte Black
Installation	Power Cord Not Included
Oven Door Features	Big Clear View Oven Window
Handle	Professional Style; Customizable; Consumer Removable
Handle Design	Café

FEATURES

Configuration	Range with Warming Drawer
Cooking Technology	Convection
Cooking System	True European Precise Air Reversing
Oven Cleaning Type	Self-Clean with Steam Clean Option
Burner - Left Front	21,000 BTU Tri-ring Burner
Burner - Left Rear	5,000 BTU Precise Simmer
Burner - Right Front	15,000 BTU
Burner - Right Rear	12,000 BTU
Burner - Center	9,500 BTU Front / 9,500 BTU Rear
Cooktop Burner Type	Sealed
Cooktop Surface	Deep Recessed; Porcelain-Enamel; Gray
Dishwasher Safe Knobs	Yes
Control Location	Front controls
Control Type	Backlit; Glass Touch
Valves (Degree of Turn)	270
Oven Control Features	Audible Preheat Signal; Automatic Oven Timer (Time Bake); Auto Oven Shut-Off; Auto Self Clean; Certified Sabbath Mode; Chef Connect; Control Lock Capability; Delay Bake Option (Time Bake); Delay Clean Option; Digipad Numeric Entry; Electronic Clock and Timer; Front Controls; In-Oven Broiling; Temperature Probe; Self-Clean Cool Down Time Display
Oven Cooking Modes	Convection Bake; Convection Roast
Oven Features	8-Pass Broil Element
Cooktop Burner Grate Features	Heavy-Cast Edge-to-Edge Grates
Cooktop Burner Grate Material	Cast-Iron
Cleaning Time	Variable with Delay Clean Option
Self-Clean Oven Door Lock	Automatic
Oven Rack Features	2 Self-Clean Oven Racks; 1 Roller Rack; 6 Rack Positions
Fuel Type	240V Electric and Natural Gas
Ignition System	Electronic w/Auto Reignition
Leveling System	4 Leveling Legs
Style	Commercial
Oven Interior	1 Incandescent; Hidden Bake; Black
Connected Capabilities	Amazon Alexa; The Google Assistant; IFTTT; Nest; Drop; Innit; DiGiorno

CAPACITY

Total Capacity (cubic feet)	5.7 cu ft
-----------------------------	-----------

ACCESSORIES

Grates	Included Center Grate
Grill	Optional; Integrated Cast Iron; JXCGRILL1
LP Conversion Kit	Included
Trim Kit	Optional; JXFILLR1DD
Griddle	Included; Integrated Cast Iron

WEIGHTS & DIMENSIONS

Cabinet Opening	30 in
Depth with Door Open	47-1/2 in
Approximate Shipping Weight	244 lb
Net Weight	224 lb
Height to Top of Rear Vent Trim	37-3/8 in
Overall Height	37-3/8 in
Height to Cooking Surface (in.)	36-1/4 +/- 1/4
Overall Width	29-7/8 in
Cabinet Width	30 in
Overall Depth	29-1/2 in
Depth Without Handle	26-7/8 in
Oven Interior Dimensions (W x H x D) (in.)	24 x 19-7/8 x 20-5/8

Café™ 30" Slide-In Front Control Dual-Fuel
Convection Range with Warming Drawer
C2S900P4MW2 / C2S900P3MD1 / C2S900P2MS1



POWER / RATINGS	
Amp Rating at 208V	30
Amp Rating at 240V	30
Bake/Broil Wattage - Main Oven	2850/4000W
Convection Wattage	2500W
Top Burner BTU Rating - LP (000's BTU's)	(1) 18.0 Tri-Ring; (1) 15.0; (1) 12.0; (2) 9.5; (1) 5.0
Top Burner BTU Rating - Nat. Gas (000's BTU's)	(1) 21.0 Tri-Ring; (1) 15.0; (1) 12.0; (2) 9.5; (1) 5.0
Volts/Hertz/Amps	208/240V; 60Hz; 30A
Power Connection	Power Cord - Not Included



WARRANTY	
Parts warranty	Limited 1-year entire appliance
Labor warranty	Limited 1-year entire appliance

DIMENSIONS


Electrical Requirements:
240v/208v; 60Hz, 30A

Installation information:
Before installing, consult
installation instructions
packed with product for
current dimensional data.


For all installations, install
the required rear trim
to back of range with 4
screws provided.




ADDITIONAL ACCESSORIES




CXFCGHKPMBZ
Brushed Bronze
2 handles; 6 knobs



CXFCGHKPMSS
Brushed Stainless
2 handles; 6 knobs




CXFCGHKPMBT
Brushed Black
2 handles; 6 knobs



CXFCGHKPMCU
Brushed Copper
2 handles; 6 knobs

Café™ Stainless Interior Built-In
Dishwasher with Hidden Controls

CDT875P4NW2 / CDT875P3ND1 / CDT875P2NS1



CDT875P4NW2
Matte White with Brushed
Bronze handles



ALSO
AVAILABLE IN



CDT875P3ND1
Matte Black with
Brushed Stainless
handles



CDT875P2NS1
Stainless Steel with
Brushed Stainless
handles

FEATURES & BENEFITS

Ultra Wash & Dry Plus – Expect precision cleaning and superior dryness on fine china, dinnerware and even dishwasher-safe plastics, with exceptional features like Variable-Pressure Jets and Dual-Convection Ultra Dry

Loading Flexibility – Clean up quickly after hosting any event with a dishwasher that accommodates large items – like charcuterie platters – and dishwasher-safe plastics, like storage containers, conveniently in the lower rack

Status Center – Continue conversations without interruption and easily know when extra dinnerware is available via an LCD screen that displays the dishwasher cycle status

Adjustable Upper Racks – You'll have room for your finest stemware and space for tall bakeware with a rack that can be moved two inches up or down, creating ultimate loading flexibility

WiFi – Always have clean dishes ready for surprise guests with WiFi Connect, which lets you operate your dishwasher from your smartphone. Track and automatically reorder detergent and rinse aid with just the tap of an app

Create a look that matches your personal style – Select any combination of premium finishes and hardware options to create a stunning look customized to any owner's taste

APPEARANCE

Door Style	Long Door with Top Controls
Installation	Side Installation or Top Installation Included; Built-Up Floor Capable; Flush Cabine; Installation
Door Appearance	Full-length flat door

FEATURES

Style	Built-In
Tub and Door Liner	Stainless Steel
Tub Type	Tall Tub
Control Type	Cap Touch Controls; 12 Touchpads
Dishwasher Control Features	Cycle Countdown with LCD Status Center on door; Multi function display; Last Cycle Memory; Audible End-of-Cycle Signal
Wash System	3-Level; 800 Series
Wash System Features	Variable Speed Dual Pumps and Motors; Automatic Temperature Control; Drain Pump; Hard Food Disposer with removable filter; Reversing Quad Blade Lower Wash Arm; Quad Blade Middle Wash Arm; Deep Clean Silverware Jets; Side Jets; 90+ Spray Jet Wash System; Hidden Heater; Automatic HotStart; Bottle Jets (4)
Sensor	Clean Sensor
Wash Arms	3 Wash Levels; Lower- Reversing Quad Blade; Middle - Quad Blade; Bottle Jets; Jets - Variable Pressure; Deep Clean Silverware Jets
Water Filtration System	100% Filtration with Hard Food Disposer and Removable Filter
Dispenser	Rinse Aid with Indicator and Adjustment; Electronic Low Rinse Aid Sensor
Number of Cycles	5
Dishwasher Cycles	Auto; Pots; Normal; China; Express
Number of Options	10
Dishwasher Options	Delay Start 1-12 Hr.; Hi-Temp Wash; Presoak + Sanitize (NSF Certified); Heated Dry Off; Normal Dry; Dual Convection Ultra Dry; Wash Zone Upper Only; Wash Zone Lower Only; Start/Reset; Bottle Wash; Lock Controls
Rack Features	2 Utility Shelves with Stem Safe and Chop-stick slots - Upper Ball-Tipped Tines; Adjustable Upper Rack; 3-Piece Silverware Basket with Cell Covers; Full Extension Slides - Upper
Racking Material	Nylon
Rack Color	Black Pearl
Number of Place Settings	Up to 16
Upper Rack	Premium Height Adjustable; Ball-Tip Tines; 2 Stem Safe Shelves; Chop stick slots; 1/2 fixed tines, 1/2 fold down tines
Lower Rack	Fixed tines with Bottle Jets; 1 Rack handle
Additional Protection	Ball-Tip Tines; 1/2 fixed tines, 1/2 fold down tines
Dishwasher Drying Features	Active Flood Protection
Floor Protection	Dual Convection Ultra Dry; Ultra/Normal/Off; Fan Assist Dry
Leveling System	Leak Pan w/ Sensor; Active Flood Protection
Latch	3 Leveling Legs
Showroom Power Mode	Pull with Handle
WiFi Connect	Yes
Exterior Style	Built-In
Racking System	Traditional
	Full 3rd Rack

ECONOMICAL/QUIET

Quiet Package	39 dBA
Quiet Features	Quiet Water Valve; Sealed Toe Kick; Tub Collar Trim
Motor Type	Variable Speed
Outer Wrap	Full-wrap Blanket; Bitumen
Door Insulation	Insulation; Mastic

WEIGHTS & DIMENSIONS

Cabinet Width	24 in
Approximate Shipping Weight	137 lb
Net Weight	124 lb
Overall Height	34 in
Height w/ Legs Retracted - Minimum Height	33-3/8 in
Height w/Legs Extended - Maximum Height	34-5/8 in
Overall Depth	24 in
Overall Width	23-3/4 in

Café™ Stainless Interior Built-In
Dishwasher with Hidden Controls

CDT875P4NW2 / CDT875P3ND1 / CDT875P2NS1




TECHNICAL DETAILS

Calrod Heater Watts	400/1200
Power Connection	Optional cord kit (GPFCORD - WX09X70910, WX09X70911)
Volts/Hertz/Amps	120 V, 60 Hz, 10.2 A


WARRANTY

Parts warranty	Limited 1-year entire appliance
Labor warranty	Limited 1-year entire appliance
Warranty notes	See written warranty for full details


DIMENSIONS




INSTALLATION DIMENSIONS




ADDITIONAL ACCESSORIES




Brushed Bronze
CXADTH1PMBZ
(Standard on Matte White)



Brushed Stainless
CXADTH1PMSS
(Standard on Matte Black and Stainless steel)




Brushed Black
CXADTH1PMBT



Brushed Copper
CXADTH1PMCU

Electrolux



Control Turntable Required. EMTRK201-AS Sold Separately.

Built-In Microwave

30" Built-In Side Swing Microwave Oven

EMBS2411AB

Available Colors : Black

Version : 04/21

Cooking Controls

Convection	Yes
Cooking Power	900 Watts
Number of Power Levels	10
Defrost Weight	Yes

Oven

Convection Type	Fan
Convection Element	1,400 Watts

Microwave Cooking

Bacon	Yes
Defrost	Yes
Melt / Soften	Yes
Multi-Stage Cooking	Yes
Popcorn	Yes
Potato	Yes
Sensor Cooking	Yes
Sensor Reheat	Yes

Convection Cooking

Broil / Grill	Yes
Combi Cooking - Bake	Yes
Combi Cooking - Roast	Yes
Convection Cooking - Roast	Yes
Convection Cooking - Bake	Yes
Keep Warm	Yes

Controls

Wi-Fi Enabled	No
---------------	----

Microwave Control Features

+ 30 Seconds	Yes - One Touch
--------------	-----------------

Additional Settings

Control Location	Bottom
------------------	--------

Child Lock	Yes
Clock Display On / Off	Yes
Demo On / Off	Yes
Language Options	English and French
Setting Turntable On / Off	No
Setting Weight Lb / Kg	Yes
Timer On / Off	Yes
Volume # of Settings	4 (Includes Off)

Exterior	
Door Finish	Edge to Edge Glass
Door Swing	Side-Swing Door

Internal Specifications

Interior Color	Stainless Steel
Interior Light Quantity	1
Interior Light Type	LED
Rack	Yes
Turntable Diameter	16 1/2"
Turntable Material	Glass

Dimensions and Volume

Height	12 7/8"
Width	21 3/4"
Depth	17 1/4"
Microwave Interior Height	10 1/4"
Microwave Interior Width	15 1/2"
Microwave Interior Depth	16 1/4"
Microwave Capacity	1.5 Cu. Ft.

Electrical Specifications

Amps @ 120 Volts	14.5 Amps
Voltage Rating	120 V

Installation

Power Supply Connection Location	Top Left
----------------------------------	----------

High standards of quality at Electrolux Home Products, Inc. mean we are constantly working to improve our products. We reserve the right to change specifications or discontinue models without notice.

Electrolux Major Appliances, N.A.

USA • 10200 David Taylor Drive • Charlotte, NC 28262 • Charlotte, NC 28262 • 1-877-4electrolux (1-877-435-3287) • electroluxappliances.com

CANADA • 5855 Terry Fox Way • Mississauga, ON L5V 3E4 • 1-800-265-8352 • electroluxappliances.ca

Electrolux

30" Built-In Side Swing Microwave Oven

EMBS2411AB

Version : 04/21

General Specifications

Product Weight	47 lbs
Prop 65 Label	Yes
Warranty - Labor	1 Year
Warranty - Parts	1 Year

Safety Certifications and Approvals

UL Listed	Yes
cUL Listed	Yes

High standards of quality at Electrolux Home Products, Inc. mean we are constantly working to improve our products. We reserve the right to change specifications or discontinue models without notice.



Electrolux Major Appliances, N.A.
USA • 10200 David Taylor Drive • Charlotte, NC 28262 • Charlotte, NC 28262 • 1-877-4electrolux (1-877-435-3287) • electroluxappliances.com
CANADA • 5855 Terry Fox Way • Mississauga, ON L5V 3E4 • 1-800-265-8352 • electroluxappliances.ca

Electrolux

30" Built-In Side Swing Microwave Oven

EMBS2411AB

Version : 04/21



CABINET OR WALL CUTOUT

Height (A)	
Minimum	17-1/64" (432 mm)
Maximum	17-1/4" (438 mm)
Width (B)	
Minimum	24-49/64" (629 mm)
Maximum	25" (635 mm)
Depth (C)	
Minimum	23-1/2" (597 mm)
	Min.depth with receptacle outside cutout – 22" (559 mm)
	Min.depth with receptacle inside cutout – 23-1/2" (597 mm)

Trim Kit Overall Dimensions	
	30"
Height	18-7/64" (460 mm)
Width	29-55/64" (758 mm)
Depth	1-5/8" (41.6 mm)

High standards of quality at Electrolux Home Products, Inc. mean we are constantly working to improve our products. We reserve the right to change specifications or discontinue models without notice.

Electrolux Major Appliances, N.A.
USA • 10200 David Taylor Drive • Charlotte, NC 28262 • Charlotte, NC 28262 • 1-877-4electrolux (1-877-435-3287) • electroluxappliances.com
CANADA • 5855 Terry Fox Way • Mississauga, ON L5V 3E4 • 1-800-265-8352 • electroluxappliances.ca

HOME APPLIANCES



LG LAUNDRY

WM4500HBA

5.0 cu.ft. Front Load Washer with TurboWash™ 360° and Built-In Intelligence

KEY FEATURES

- 5.0 cu. ft. Mega Capacity
- TurboWash™ 360° Technology
- AI Fabric Sensor/ Smart Pairing™
- ezDispense™ Automatic Dispenser
- AAFA Certified LG washer
- LG ThinQ® Technology / Proactive Customer Care
- ColdWash™ Technology
- Direct Drive Motor 10-Year Limited Warranty
- ENERGY STAR® Certified
- Closet Depth
- NeveRust™ Stainless Steel Tub and Lifters

AVAILABLE COLORS





BLACK STEEL



Enjoy new ways to control your home with LG smart appliances

- Use the ThinQ® app to start the laundry while you're out
- Get alerts when the cycle is finished
- With Smart Pairing™, the washer can tell the dryer to select a compatible drying cycle

LG ThinQ®



SMART APPLIANCE

PRODUCT FEATURES

SUMMARY

Type	Front Load Washer
Capacity (cu.ft.)	5.0 cu. ft.
Matching Electric Dryer	DLEX4500B
Matching Gas Dryer	DLGX4501B
Color	Black Steel (B)

APPEARANCE

Hard Buttons	Yes
Touch Buttons	Yes
Dial-A-Cycle™	Yes

ENERGY

ENERGY STAR® Most Efficient 2019	Yes
ENERGY STAR® Qualified	Yes
CEE Tier	Advanced
IMEF	3.1
IWF	2.9

WASH PROGRAMS

No. of Programs	14
Wash Programs	Normal, Heavy Duty, Bedding, Sanitary, Allergiene™, Bright White, Tub Clean, Delicates, Perm. Press, Sportswear, Towels, Speed Wash, Rinse+Spin, Downloaded

WASH OPTIONS

No. of Options	15
Options	TurboWash®, Steam, Fresh Care, Pre-wash, Remote Start, Delay Wash, Wi-Fi, Add Item, Extra Rinse, Control Lock, Drum Light, ColdWash, Spin Only, Detergent Level, Softener Level

WASH DETAILS

No. of Wash/Rinse Temps	5
Wash/Rinse Temps	Extra Hot, Hot, Warm, Cold, Tap Cold

No. of Spin Speeds	5
Spin Speeds	Extra High, High, Medium, Low, No Spin
Max RPM	1300
Water Levels	Load Sensing
No. of Soil Levels	5

FABRIC CARE FEATURES

AI DD™	Yes
TurboWash™ 360 Technology	Yes
Steam Technology	Yes
Allergiene™ Cycle	Yes
Sanitary Cycle	Yes
ColdWash™ Option	Yes
SenseClean™ System	Yes

CONVENIENCE FEATURES

TrueBalance™ Anti-Vibration System	Yes
4 Tray Dispenser	ezDispense cartridge(Detergent, Softener), Main Wash, Bleach(cup)
LoDecibel™ Quiet Operation	Yes
End of Cycle Signal	Yes
LoadSense	Yes
Child Lock	Yes
Auto Suds Removal	Yes
Leveling Legs	4 Adjustable Legs
Easy Loading TilTub™	Yes

ThinQ® TECHNOLOGY

SmartDiagnosis™ (v3.0)	Yes
Wi-Fi	Yes
Remote Start and Cycle Monitor	Yes
Energy Monitoring	Yes

MOTOR AND AGITATOR

Motor Type	Inverter Direct Drive Motor
Axis	Horizontal

MATERIALS AND FINISHES

NeveRust™ Stainless Steel Drum	Yes
Cabinet	PCM
Control Panel	Plastic
Top Plate	Painted
Door / Rim	Glass/Chrome
Door Cover	Dark Black Tinted Square Cover
All Available Colors	Black Steel (B)

CERTIFICATION

AAFA	Yes
------	-----

POWER SOURCE

Ratings	UL Listed
Electrical Requirements	120V, 10 Amps
Type	Electric

OPTIONS/ACCESSORIES

Pedestal	WDP4B
Pedestal (WxHxD)	27 x 14 1/8 x 30 3/4 (50 9/16 D with door open)
LG Sidekick™ Pedestal Washer	WD100CB
LG Sidekick™ Pedestal Washer (WxHxD)	27 x 14 1/8 x 30 3/4 (50 9/16 D with door open)
Stacking Kit	KSTK1

DIMENSIONS

Product (WxHxD)	27" x 39" x 33 1/4"
Depth with Door Open	(53 1/4" D with door open)
Carton (WxHxD)	29 23/32" x 43 4/32" x 33 28/32"
Weight (Product/Carton)	201.5 / 215.2 lbs

LIMITED WARRANTY

Parts and Labor	1 Year
Direct Drive Motor	10 Years
Drum	3 Years

UPC CODES

WM4500HBA (Black Steel)	048231026772
-------------------------	--------------

LG LAUNDRY

DLEX4500B / DLGX4501B


7.4 cu.ft. Front Load Dryer with TurboSteam™ and Built-In Intelligence

- KEY FEATURES
- 7.4 cu. ft. Ultra Large Capacity
 - TurboSteam™ Technology
 - AI Fabric Sensor/ Smart Pairing™
 - LG ThinQ® Technology / Proactive Customer Care
 - FlowSense™ Duct Clogging and Lint Filter Indicators
 - ENERGY STAR® Certified
 - Closet Depth
 - LoDecibel™ Quiet Operation
 - Reversible Door
 - Wrinkle Care Option

AVAILABLE COLORS



BLACK STEEL



LG ThinQ®

Enjoy new ways to control your home with LG smart appliances

- Use the ThinQ® app to start the laundry while you're out
- Get alerts when the cycle is finished
- With Smart Pairing™, the washer can tell the dryer to select a compatible drying cycle

works with the Google Assistant

WORKS WITH alexa

SUMMARY

Type	Front Load Dryer
Capacity	7.4 cu. ft.
Matching Washer	WM4500HBA
Sensor Dry	Yes
Steam	Yes
Color	Black Steel (B)
APPEARANCE	
Intelligent Electronic Controls with LED Display	Yes
Dial-A-Cycle™	Yes
Touch Buttons	Yes
DRYER PROGRAMS	
No. of Programs	14
Programs (Sensor Dry)	Normal, Heavy Duty, Bedding, Small Load, Anti Bacterial, Steam-Sanitary™, SteamFresh™, Perm Press, Delicates, Sportswear, Towels, Speed Dry (Manual Dry), Air Dry (Manual Dry), Downloaded
No. of Options	12
Options	More Time, Less Time, Damp Dry Signal, Wrinkle Care, Control Lock, Wi-Fi, Energy Saver, TurboSteam™, Reduce Static, Remote Start, Drum Light, Signal
Temperature Settings	High, Med. High, Medium, Low, Ultra Low
Drying Levels	Very Dry, More Dry, Normal Dry, Less Dry, Damp Dry
Manual Dry Times	60 min., 50 min., 40 min., 30 min., 20 min., More Time/Less Time

FABRIC CARE FEATURES

A.I Dry	Yes
Sensor Dry	Yes
Precise Temperature Control with Variable Heater	Yes
Steam	TurboSteam™
CONVENIENCE FEATURES	
3 Minute Installation Check	Yes
LoDecibel™ Quiet Operation	Yes
End of Cycle Signal	Yes
Drum Light	Yes
Reversible Door	Yes
FlowSense™ Duct Clogging Indicator	Yes
Wrinkle Care Option	Yes
Child Lock	Yes
Venting Option	Electric: 4 Way Venting / Gas: 3 Way Venting
4 Adjustable Legs	Yes
Remaining Time Display/Status Indicator(s)	Yes

ThinQ® TECHNOLOGY

SmartDiagnosis™ (v3.0)	Yes
Wi-Fi	Yes
Remote Start and Cycle Monitor	Yes
Energy Monitoring	Yes (Wi-Fi)

ENERGY

ENERGY STAR® Certified	Yes
CEF	Electric: 3.94 / Gas: 3.49

MATERIALS AND FINISHES

NeveRust® Stainless Steel Drum	Yes
Tub Rear	Painted
Cabinet	Painted Steel
Door	Dark Black Tinted Square Cover
All Available Colors	Black Steel (B)

POWER SOURCE

Ratings	CSA Listed
Electrical Requirements	120V, 15 Amps (Gas) / 240V 30 Amps (Electric)
Type	Electric, Gas
BTU Rating	10,000 Feet

OPTIONS

LP Conversion Kit	383EEL3002D
Side Venting Kit	383EEL9001B
Pedestal	WDP4B
Pedestal (WxHxD)	27 x 14 1/8 x 30 3/4 (50 1/2 D with door open)

DIMENSIONS (ELECTRIC)

Product (WxHxD)	27" x 39" x 30"
Depth with Door Open	51"
Carton (WxHxD)	29 1/2" x 42 1/4" x 31 1/4"
Weight (Product)	133.4 lbs
Weight (Carton)	150.1 lbs

DIMENSIONS (GAS)

Product (WxHxD)	27" x 39" x 30"
Depth with Door Open	51"
Carton (WxHxD)	29 1/2" x 42 1/4" x 31 1/4"
Weight (Product)	140.4 lbs
Weight (Carton)	153.0 lbs

LIMITED WARRANTY

Parts & Labor	1 Year
Drum	3 Years

UPC CODES

DLEX4500B (Black Steel)	048231026789
DLGX4501B (Black Steel)	048231026796
WM4500HBA (Black Steel)	048231026772



(<https://www.canadianappliance.ca/air-miles>)

Find a product...

▼ Categories



▼ Showrooms

Shop In Store, For Lower Prices Than On Website:* [Info >>](#)

BUNDLE & SAVE UP TO
25% OFF* - Chat + In
Store Only

Buy x2 **Save 10%**,
Buy x3 **Save 15%**,
Buy x4+ **Save 20%**
on LG Studio!* [Info](#)

>>

Buy 3+ & **Save**
\$300!* [Info >>](#)

Washer & Dryer or
WashTower + S3CW
= **Save \$300!*** [Info](#)
>>

Home (<https://www.canadianappliance.ca/>) > Product Accessories (<https://www.canadianappliance.ca/Product-Accessories-232/>) > Laundry Accessories (<https://www.canadianappliance.ca/Product-Accessories-232/Laundry-Accessories-92/>) > Pedestals (<https://www.canadianappliance.ca/Product-Accessories-232/Laundry-Accessories-92/Pedestals-263/>) > LG (<https://www.canadianappliance.ca/LG/Product-Accessories-232/Laundry-Accessories-92/Pedestals-263/>)

Availability: Ottawa, ON

▼ - Ⓢ *4-12 Business Days




(<https://www.canadianappliance.ca/LG-Appliances-Canada-B24/>)

LG WDP4B

Authorized Dealer

LG WDP4B Pedestal, 27" Width, Black Stainless Steel colour for WM3998HBA, WM4100HBA, WM4500HBA

Up to 3 years
FREE extended
warranty!
i



(/img/xxlarge/lg/product-accessorie/WDP4B_2.jpg)



/product-accessorie/WDP4B_3.jpg)(/img/xxlarge/lg/product-accessorie/WDP4B_5.jpg)(/img/xxlarge/lg/product-accessorie/WDP4B_6.jpg)(/img/xxlarge/lg/laundry-pedes

\$844

Ratings & Reviews

Description & Features

84%

of respondents would
recommend this to a friend

Video

Reviews

Related products

Warranty

Financing

Installation

FAQ

WD100CB

Warranty (https://www.canadianappliance.ca/product/LG_WDP4B_Pedestal_LG_WDP4B.html#tab-warranty)

Financing (https://www.canadianappliance.ca/product/LG_WDP4B_Pedestal_LG_WDP4B.html#tab-financing)

Install (https://www.canadianappliance.ca/product/LG_WDP4B_Pedestal_LG_WDP4B.html#tab-installation)

FAQ (https://www.canadianappliance.ca/product/LG_WDP4B_Pedestal_LG_WDP4B.html#tab-faq)

DIMENSIONS
Dimensions (WxHxD) 27" x 14 1/8" x 28 2/5"
Weight (Product/Carton) 51 lbs/61 lbs
UPC CODE
WDP4B 048231026451