

CONSTRUCTION SUMMARY - PARTIAL ONLY

Mountainview Heights 3 (G) - Russell Gardens Building Ltd.

RECEIVED

OCT - 5 2022

PURCHASERS: Taiwo Adelaja ROLUGA and Adenike Basirat ROLUGA

TEL:

LOT NUMBER	PHASE	HOUSE TYPE	REG. PLAN #		
374	4	Springfield Three (5 Bedroom) Elev 2	62M-1266		

INV#	QTY	EXTRA / CHANGE
------	-----	----------------

CABINETRY

26,612 26Jan22	1 - VANITY - ENSUITE - UPGRADE 1 Note:
26,612 26Jan22	1 - CABINETRY - KITCHEN - UPGRADE 2 Note:
26,612 26Jan22	1 - KITCHEN CABINETRY - DIFFERENT COLOUR ISLAND - FLAT FEE Note:
26,612 26Jan22	1 - KITCHEN - CM 11 MOULDING Note:
26,612 26Jan22	1 - KITCHEN - LIGHT VALANCE Note:
26,612 26Jan22	1 - VANITY - POWDER ROOM - UPGRADE 1 Note:
26,612 26Jan22	1 - CABINETRY PROVISION - PROVISION FOR PLUG ON ISLAND (PLUG EXTRA ORDERED SEPARATELY) Note:

CABINETRY ACCESSORIES

26,718 18Feb22	1 - CABINETRY FEE FOR FLUSH CUTOUT ON WALL OVEN/MICROWAVE COMBO CABINET ONLY Note:
26,718 18Feb22	1 - KITCHEN CABINETRY - BUILT-IN FRIDGE CABINET - PRICE IS EACH Note:
26,612 26Jan22	1 - KITCHEN - ISLAND - CREATE OPENING FOR FUTURE WINE FRIDGE Note:
26,612 26Jan22	1 - KITCHEN CABINETRY BASE - COOKTOP CABINET WITH POT DRAWERS (2 DRAWERS) - UPGRADE 2 Note:
26,612 26Jan22	1 - KITCHEN CABINETRY - BUILT-IN MICROWAVE/OVEN COMBO - UPGRADE 2 Note:
26,612 26Jan22	1 - KITCHEN CABINETRY UPPER - FULL DEPTH ABOVE FRIDGE - WITH GABLES - 600MM - PRICE IS EACH - UPGRADE 2 Note:
26,612 26Jan22	1 - PANTRY UNIT UPGRADE - TO GO FROM 300MM TO 600MM DEEP - PRICE IS PER FOOT - UPGRADE 2 Note:
26,612 26Jan22	1 - KITCHEN CABINETRY BASE - PULLOUT RECYCLE 4 BIN - PRICE IS EACH Note:
26,612 26Jan22	1 - KITCHEN CABINETRY – MINI STACKED UPPER CABINETS – UPGRADE 2 CABINETRY Note:


CONSTRUCTION SUMMARY - PARTIAL ONLY
Mountainview Heights 3 (G) - Russell Gardens Building Ltd.

PURCHASERS: Taiwo Adelaja ROLUGA and Adenike Basirat ROLUGA

TEL:


LOT NUMBER	PHASE	HOUSE TYPE	REG. PLAN #		
374	4	Springfield Three (5 Bedroom) Elev 2	62M-1266		
INV#	QTY	EXTRA / CHANGE			

CABINETRY ACCESSORIES

26,612 26Jan22	1 - KITCHEN HOOD CABINETS - CONTEMPORARY WOOD HOOD – UPGRADE 2 NotePURCHASER TO SUPPLY AND INSTALL HOOD FAN AFTER CLOSING	 New SPEC ATTACHED
26,612 26Jan22	1 - VANITY CABINETRY - RAISE VANITY TO 36" HIGH VANITY IN LIEU OF STANDARD HEIGHT - POWDER ROOM Note:	
26,612 26Jan22	1 - VANITY CABINETRY - RAISE VANITY TO 36" HIGH VANITY IN LIEU OF STANDARD HEIGHT - MASTER ENSUITE BATHROOM Note:	
26,612 26Jan22	1 - KITCHEN CABINETRY BASE - POT/PAN DRAWERS (CABINET) - UPGRADE 2 Note:	
26,612 26Jan22	1 - VANITY CABINETRY - RAISE VANITY TO 36" HIGH VANITY IN LIEU OF STANDARD HEIGHT - ENSUITE 2/5 BATHROOM Note:	
26,612 26Jan22	1 - VANITY CABINETRY - RAISE VANITY TO 36" HIGH VANITY IN LIEU OF STANDARD HEIGHT - ENSUITE 3/4 BATHROOM Note:	
26,612 26Jan22	4 - KITCHEN CABINETRY UPPER – GLASS DOOR FOR MINI UPPER – GROUP 1 GLASS – PRICE IS PER DOOR – UPGRADE 2 CABINETRY Note: BAROQUE BLK 306	
26,612 26Jan22	4 - KITCHEN CABINETRY UPPER - GLASS DOOR - BEVELED - FINISHED INTERIOR - FITS TALL UPPER CABINETS - PRICE IS PER DOOR - UPGRADE 2 Note: BAROQUE B;L 306	
26,612 26Jan22	6 - KITCHEN CABINETRY ACCESSORY - GLASS SHELVES - STRAIGHT Note:	
26,612 26Jan22	1 - KITCHEN - BLU MOTION DRAWERS Note:	
26,612 26Jan22	1 - KITCHEN - SOFT CLOSING CABINETRY Note:	
26,612 26Jan22	1 - KITCHEN CABINETRY BASE - BANK OF DRAWERS - UPGRADE 2 Note:	

This Document is Extremely Time Sensitive - Printed 5 Oct 22 at 15:37

VCIN36GWS
36-INCH CUSTOM INSERT
PROFESSIONAL® SERIES



FEATURES & BENEFITS

- Revel in creative freedom with Professional® Series custom inserts that can blend in with cabinetry or make a bold statement
- ★- Equipped with the Thermador Connected Experience by Home Connect™
- Powerfully Quiet® system accepts integral, inline, and remote blowers
- Beautiful illumination with multi-level, vivid LED lights
- Features automatic mode, delay shut-off, and check filter light

ACCESSORIES (OPTIONAL)

25 ft. Blower Connector Cable - EXTNCB25W

For use with the following inline and remote blowers: VTR630W, VTR1030W, VTR1330W, VTi610W, VTi1010W

Roofplates

RFPLT600P - For use with 600 CFM remote blower VTR630W

RFPLT1000P - For use with 1000 CFM remote blower VTR1030W and 1300 CFM blower VTR1330W

VCIN Trim Notes

NOTE: VCIN_GWS series custom insert models include hood trim pieces to complete the installation.

Remote Control Panel

REMCPW - Ability to vertically install on cabinetry or wall to control hood in a convenient location



GENERAL PROPERTIES

Features	
Multi-Level LED Lights with Fading Transitions, Automatic Mode, Check Filter Reminder Light, Delay Shut-Off	
Operating Mode	Ducted
Maximum CFM	Blower Sold Separately
Number of Speed Settings	4-Stage
Number of Lights	2
Bulb Type	LED
Total Power of the Lamps (W)	2.4 W
Damper Included	Yes
Grease Filter Material	Washable Stainless Steel
Grease Filter Type	Stainless-Steel Commercial Style Baffle Filter
Home Connect™ (Wi-Fi Enabled)	Yes

TECHNICAL DETAILS

Watts (W)	See Chart on Page 3
Current (A)	See Chart on Page 3
Volts (V)	120 V
Frequency (Hz)	60 Hz
Plug Type	Fixed Connection
Power Cord / Conduit Length (in)	Direct Wire at Junction Box

DIMENSIONS & WEIGHT

Overall Appliance Dimensions (Width of Canopy Included) (HxWxD) (in)	12 13/16" x 33 3/4" x 22"
Minimum Required Distance Above Gas / Electric Cooking Surface	30" Electric / 30" Gas
Diameter of Air Duct (in.) Top	10"
Net Weight (lbs)	54 lbs

ACCESSORIES (REQUIRED)

Blower (Sold Separately)

BLOWER OPTIONS

Remote Blowers (Mounted to Roof or External Wall)	VTR630W - 600 CFM
	VTR1030W - 1000 CFM
	VTR1330W - 1300 CFM
Inline Blowers (Mounted Between Kitchen and External Wall)	VTi610W - 600 CFM
	VTi1010W - 1000 CFM
Integrated Blower (Mounted in Hood)	VTN630W - 600 CFM
	VTN1090R - 1000 CFM

WARRANTY

Limited Warranty Parts and Labor	2 Year
----------------------------------	--------

★ THERMADOR® EXCLUSIVE


VCIN36GWS
36-INCH CUSTOM INSERT
PROFESSIONAL® SERIES



HOOD DIMENSIONS

NOTE: VCIN Custom Insert models include hood trim pieces.

Cut-out for insert without
liner accessory



measurements in inches (mm)

OPTIONAL ACCESSORIES

REMOTE CONTROL PANEL
REMCPW



Convenience at your fingertips: The remote control accessory offers the freedom to extend your hood controls to a more reachable spot


VCIN36GWS
36-INCH CUSTOM INSERT
PROFESSIONAL® SERIES



MODEL	DESCRIPTION		ELECTRIC LOAD						
			VTN630W	VTN1090R	VTI610W	VTI1010W	VTR630W	VTR1030W	VTR1330W
VCIN36GWS	36" Custom Insert	Amps	4.0	7.4	5.9	7.8	5.9	7.8	11.3
		Watts	480	888	708	936	708	936	1,356


REMOTE BLOWERS (MOUNTED TO ROOF OR EXTERNAL WALL)

VTR630W-600 CFM




measurements in inches and mm

VTR1030W-1000 CFM



measurements in inches and mm

VTR1330W-1300 CFM




measurements in inches and mm

VCIN36GWS
36-INCH CUSTOM INSERT
 PROFESSIONAL® SERIES




INLINE BLOWERS (MOUNTED BETWEEN KITCHEN AND EXTERNAL WALL)

VTI610W-600 CFM



measurements in inches and mm


VTI1010W-1000 CFM



measurements in inches and mm


INTEGRATED BLOWERS (MOUNTED IN HOOD)

VTN630W-600 CFM



measurements in inches (mm)

VTN1090R-1000 CFM




measurements in inches and mm

VCIN36GWS
36-INCH CUSTOM INSERT
PROFESSIONAL® SERIES




REMOTE BLOWER ACCESSORIES

ROOFPLATE-RFPLT600P



ROOFPLATE-RFPLT1000P



EXTNCB25W

For use with the following Inline and Remote Blowers: VTR630W, VTR1030W, VTR1330W, VTI610W, VTI1010W

These warranties give you specific legal rights and you may have other rights that vary from state to state. Full warranty and limited warranty from date of installation. For complete warranty details, refer to your Use & Care manual, or ask your dealer.

Specifications are for planning purposes only. Refer to installation instructions and consult your countertop supplier prior to making counter opening. Consult with a heating and ventilation engineer for your specific ventilation requirements. For the most detailed information, refer to installation instructions accompanying product or write to Thermador indicating the model number. Specifications are correct at time of printing. Thermador reserves the right to change product specifications or design without notice. Some models are certified for use in Canada. Thermador is not responsible for products that are transported from the U.S. for use in Canada.

1 800 735 4328 | USA.THERMADOR.COM | CANADA.THERMADOR.CA | ©2019 BSH HOME APPLIANCES CORPORATION. ALL RIGHTS RESERVED.