

Hanger Name	Symbol	QTY
LUS24	▲	2
LJS26DS	■	6



CONVENTIONAL
FRAMING BY OTHERS

ALL CONVENTIONAL FRAMING TO CONFORM WITH PART 9 OF THE OBC. ROOF RAFTERS THAT CROSS OVER TRUSSES TO BE MIN. 2x4 SPF @ 24" C/C WITH A 2x4 VERTICAL POST TO THE TRUSS BELOW. VERTICAL POSTS TO BE Laterally BRACED SO THAT UNBRACED LENGTH DOES NOT EXCEED 6'. DESIGN OF CONVENTIONAL FRAMING IS THE RESPONSIBILITY OF THE PROJECT ENGINEER.

JOB INFORMATION

Customer	ROUNDEL HOMES INC
Job #	21-00085R0
Address	PINETREE 3 RICHMOND HILL,ON
Model	38-03 ELEV 1
Sales Rep	RALPH MIRIGELLO
Designer	KR
Date	3/11/2021
Path	C:\MITEK\CA\JOBS\GREENPARK GROUP\ROUNDEL HOMES INC\T-PT38-03-1\

DESIGN INFORMATION

Code	NBCC 2015
Bldg	Residential - HSB (NBCC Part 9)
TC LL	25.6 lb/ft²
TC DL	3.0 lb/ft²
BC LL	0.0 lb/ft²
BC DL	7.3 lb/ft²
Deflection	LL=L/360 TL=L/360
Spacing	24" O/C unless otherwise noted
Complies With	OBC 2012 (2019 Amendment) CSA O86-14 and TPIC 2014

IMPORTANT INFORMATION

Refer to truss drawings in the Truss Engineering Package for ply-to-ply attachment notes

For site-framed valleys: top chords of all roof trusses must be laterally supported using 2x4 continuous bracing @24 O/C - all bracing must be anchored at ends as per TPIC Installation Guidelines

Read all notes on this page in addition to those shown on the KOTT Truss Engineering package

Field erection, handling and bracing are not the responsibility of KOTT, or KOTT Engineering

Unless noted otherwise, hurricane ties are to be installed at the bearings of all trusses > 40 ft clear span, and any girder or beam supporting trusses with a clear span >40 ft. See hanger legend for type.

Unless noted otherwise, for Part 9 bldgs, all trusses are to be anchored to the top of supporting walls as follows: trusses with a clear span <40 ft use 3-1/4" nails @ each bearing, trusses with a clear span >40 ft use 3-1/4" nails @ each bearing in addition to the appropriate hurricane tie.

KOTT Inc.
14 Anderson Blvd.
Uxbridge, ON
905.642.4400

09/22/2022
RECEIVED
Per: joshua.nabua

ENGINEERING NOTE PAGE (ENP-1)

PLEASE READ PRIOR TO INSTALLATION

RESPONSIBILITIES

THIS DESIGN IS FOR AN INDIVIDUAL BUILDING COMPONENT AND HAS BEEN BASED ON INFORMATION PROVIDED BY KOTT DESIGN. THE UNDERSIGNED ENGINEER DISCLAIMS ANY RESPONSIBILITY FOR DAMAGES AS A RESULT OF FAULTY OR INCORRECT INFORMATION, SPECIFICATION AND/OR DESIGNS FURNISHED TO THE ENGINEER. THE UNDERSIGNED ENGINEER IS ONLY RESPONSIBLE FOR THE STRUCTURAL INTEGRITY OF THIS BUILDING COMPONENT FOR THE CONDITIONS AND LOADS SHOWN ON THIS DRAWING. THE STRUCTURAL INTEGRITY OF THE BUILDING AND THE VERIFICATION OF THE DIMENSIONS AND THE DESIGN LOADS USED ARE THE RESPONSIBILITY OF THE BUILDING DESIGNER.

TRUSSES ARE DESIGNED IN CONFORMANCE WITH THE RELEVANT SECTIONS OF THE NATIONAL BUILDING CODE OF CANADA OR THE CANADIAN CODE FOR FARM BUILDINGS, WHICHEVER APPLIES TO THE BUILDING TYPE INDICATED ON THE DRAWING

IT IS THE RESPONSIBILITY OF KOTT TO ENSURE THAT TRUSSES ARE MANUFACTURED IN CONFORMANCE WITH THESE DESIGNS AND WITH THE SPECIFICATIONS OUTLINED BELOW. THE UNDERSIGNED ENGINEER IS NOT RESPONSIBLE FOR QUALITY CONTROL IN THE TRUSS MANUFACTURING PLANT.

USE AND OCCUPANCY

- The building is of the type indicated on the drawing

LOADING

- The truss loading intensity and distribution as well as load transfer mechanism is that indicated on the drawing
- No buildings, trees, parapets or other projections higher than the roof for which the trusses are used are located within a distance less than ten (10) times the difference in height, or five metres (16 ft) whichever is greater, unless the drawing indicates that the snow drifting has been taken into account

HANDLING, INSTALLATION AND BRACING

- The trusses must be handled and installed by a qualified professional as per the supplied document titled *Information for Truss Installers* and the BCSI-B1 and BCSI-B3 Summary Sheets
- The compression chords are laterally braced by continuous rigid diaphragm sheathing or as specified on the drawing
- Temporary and permanent bracing must be installed as indicated on the truss drawing and according to the BCSI-B1 and BCSI-B3 Summary Sheets. Bracing for the lateral stability of the truss is to be provided by the building designer
- **It is recommended that a Professional Engineer's advice be obtained for the bracing of trusses spanning more than 12.37m (40'-7")**

SUPPORTS

- The trusses are to be supported at the bearing points indicated and anchored to the supports where considered necessary by the designer of the overall structure
- Bearing sizes shown are the minimum required to prevent crushing of the truss members and do not necessarily take into account stability of the overall building structure
- Elevation of bearings must be carefully checked and shimmed to alignment for solid bearings
- Adequate wood truss bearing is the responsibility of the building designer.

DIMENSIONS

- Geometry of the truss and dimensions indicated on the drawing are identical to those of the installed truss.



CITY OF RICHMOND HILL
BUILDING DIVISION

09/22/2022


2020/04/22

RECEIVED

Per: joshua.nabua

JOB NAME	TRUSS NAME	QUANTITY	PLY	JOB DESC.	DRWG NO.
IM0621-169	G01	1	1	TRUSS DESC.	

Version 8.420 S Apr 29 2021 MiTek Industries, Inc. Tue Jun 29 13:08:01 2021 Page 1
ID:6C5231FijGTY_39enVU3pLzc1B6-vhvRPC27masZWmmDslSdeaVabT4882kp4jbsLgz1QmC



LUMBER

N. L. G. A. RULES	CHORDS	SIZE	LUMBER	DESCR.
A - D	2x4	DRY	No.2	SPF
D - G	2x4	DRY	2100F 1.8E	SPF
G - I	2x4	DRY	2100F 1.8E	SPF
I - L	2x4	DRY	No.2	SPF
U - B	2x8	DRY	No.2	SPF
M - K	2x6	DRY	No.2	SPF
U - P	2x6	DRY	No.2	SPF
P - M	2x6	DRY	No.2	SPF
ALL WEBS	2x3	DRY	No.2	SPF
EXCEPT				
J - M	2x4	DRY	No.2	SPF

DRY: SEASONED LUMBER.

PLATES (table is in inches)

JT	TYPE	PLATES	W	LEN	Y	X
B	TMVW-p	MT20	6.0	8.0	1.50	3.75
C	TMWW-t	MT20	4.0	4.0	2.00	1.50
D	TTWW-m	MT20	6.0	8.0	Edge	
E	TMWW-t	MT20	4.0	4.0	1.50	1.50
F	TMW-w	MT20	2.0	4.0		
G	TS-t	MT20	3.0	8.0		
H	TMWW-t	MT20	4.0	4.0	1.50	1.75
I	TTWW+m	MT20	6.0	6.0	Edge	2.50
J	TMWW-t	MT20	5.0	5.0	2.00	1.75
K	TMV-p	MT20	2.0	4.0		
M	BMVW-t	MT20	5.0	6.0	2.00	3.00
N	BMWW-t	MT20	3.0	4.0		
O	BMWW-t	MT20	5.0	5.0	2.00	1.50
P	BS-t	MT20	5.0	6.0		
Q	BMWWW-t	MT20	8.0	8.0	4.25	4.00
R	BMWW-t	MT20	4.0	6.0	2.50	1.50
S	BMWW-t	MT20	3.0	4.0		
T	BMWW-t	MT20	6.0	6.0	3.00	1.50
U	BMV1+p	MT20	3.0	5.0		

Edge - INDICATES REFERENCE CORNER OF PLATE TOUCHES EDGE OF CHORD.

DIMENSIONS, SUPPORTS AND LOADINGS SPECIFIED BY FABRICATOR TO BE VERIFIED BY BUILDING DESIGNER

BEARINGS

	FACTORED GROSS REACTION	MAXIMUM FACTORED GROSS REACTION	INPUT BRG	REQRD BRG
JT	VERT	DOWN	IN-SX	IN-SX
U	3438	0	5-8	3-15
M	2570	0	5-8	2-13

UNFACTORED REACTIONS

1ST LCASE	MAX/MIN. COMPONENT REACTIONS						
JT	COMBINED	SNOW	LIVE	PERM.LIVE	WIND	DEAD	SOIL
U	2407	1718 / 0	0 / 0	0 / 0	0 / 0	689 / 0	0 / 0
M	1796	1299 / 0	0 / 0	0 / 0	0 / 0	497 / 0	0 / 0

BEARING MATERIAL TO BE SPF NO.2 OR BETTER AT JOINT(S) U, M

BRACING

TOP CHORD TO BE SHEATHED OR MAX. PURLIN SPACING = 3.11 FT.
MAX. UNBRACED BOTTOM CHORD LENGTH = 10.00 FT OR RIGID CEILING DIRECTLY APPLIED.

ALL FITCH BREAKS AND PERIMETER CORNER JOINTS MUST BE Laterally RESTRAINED.

LOADING

TOTAL LOAD CASES: (4)

CHORDS				WEBS			
MEMB.	MAX. FACTORED FORCE (LBS)	FACTORED VERT. LOAD (PLF)	MAX. LC1 (LC)	MEMB.	MAX. FACTORED FORCE (LBS)	MAX. LC1 (LC)	
FR-TO		FROM TO	LENGTH	FR-TO			
A-B	0 / 32	-84.3 -84.3	0.12 (1)	10.00	T-C	-1005 / 0	0.21 (1)
B-C	-3790 / 0	-84.3 -84.3	0.32 (1)	3.34	C-S	0 / 583	0.14 (1)
C-D	-4295 / 0	-84.3 -84.3	0.35 (1)	3.11	S-D	-261 / 35	0.11 (1)
D-E	-4770 / 0	-158.9 -158.9	0.26 (1)	3.80	D-R	0 / 2281	0.56 (1)
E-F	-5572 / 0	-158.9 -158.9	0.31 (1)	3.49	R-E	-1783 / 0	0.75 (1)
F-G	-5572 / 0	-84.3 -84.3	0.74 (1)	3.19	E-Q	0 / 1514	0.37 (1)
G-H	-5572 / 0	-84.3 -84.3	0.74 (1)	3.19	Q-F	-499 / 0	0.21 (1)
H-I	-4558 / 0	-84.3 -84.3	0.63 (1)	3.57	Q-H	0 / 1291	0.32 (1)
I-J	-3116 / 0	-84.3 -84.3	0.24 (1)	3.74	O-H	-1414 / 0	0.59 (1)
J-K	0 / 12	-84.3 -84.3	0.10 (1)	10.00	O-I	0 / 2518	0.62 (1)
K-L	0 / 32	-84.3 -84.3	0.12 (1)	10.00	N-I	-155 / 32	0.06 (1)
U-B	-3352 / 0	0.0 0.0	0.18 (1)	6.46	N-J	0 / 391	0.10 (1)
M-K	-220 / 0	0.0 0.0	0.02 (1)	7.81	B-T	0 / 3322	0.82 (1)
					J-M	-3261 / 0	0.66 (1)
U-T	0 / 0	-34.4 -34.4	0.08 (1)	10.00			
T-S	0 / 3163	-34.4 -34.4	0.49 (1)	10.00			
S-R	0 / 3561	-34.4 -34.4	0.50 (1)	10.00			
R-Q	0 / 4770	-34.4 -34.4	0.72 (1)	10.00			
Q-P	0 / 4559	-18.2 -18.2	0.71 (1)	10.00			
P-O	0 / 4559	-18.2 -18.2	0.71 (1)	10.00			
O-N	0 / 2580	-18.2 -18.2	0.38 (1)	10.00			
N-M	0 / 2305	-18.2 -18.2	0.34 (1)	10.00			

FACTORED CONCENTRATED LOADS (LBS)

JT	LOC.	LC1	MAX-	MAX+	FACE	DIR.	TYPE	HEEL	CONN.
D	6-0-0	-379	-379	---	FRONT	VERT	TOTAL	---	C1
Q	12-3-4	-390	-437	---	FRONT	VERT	DEAD	---	C1
Q	12-3-4	-1164	-1164	---	FRONT	VERT	SNOW	---	C1

CONNECTION REQUIREMENTS

1) C1: A SUITABLE HANGER/MECHANICAL CONNECTION IS REQUIRED.

DESIGN CRITERIA

*** SPECIAL LOADS ANALYSIS ***
GEOMETRY AND/OR BASIC LOADS CHANGED BY USER.
LOADS WERE DERIVED FROM USER INPUT
NO FURTHER MODIFICATIONS WERE MADE

SPECIFIED LOADS:

TOP CH.	LL	=	25.6	PSF
	DL	=	3.0	PSF
BOT CH.	LL	=	0.0	PSF
	DL	=	7.3	PSF
TOTAL LOAD	=	35.9	PSF	

SPACING = 24.0 IN. C/C

LOADING IN FLAT SECTION BASED ON A SLOPE OF 2.00/12 MINIMUM

GIRDER TYPE: CPrimeHip
SIDE SETBACK = 6-0-0
END SETBACK = 6-0-0
END WALL WIDTH = 5-8
CORNER FRAMING TYPE: CONVENTIONAL
END JACK TYPE: CONVENTIONAL
APPLIED TO FRONT SIDE
- ADDTL LOADS BASED ON 55 % OF GSL.
LOADS APPLIED TO FIRST 12-3-4 OF SPAN MEASURED FROM THE LEFT.

*** NON STANDARD GIRDER ***
ADDTL USER-DEFINED LOADS APPLIED TO ALL LOAD CASES.

THIS TRUSS IS DESIGNED FOR RESIDENTIAL OR SMALL BUILDING REQUIREMENTS OF PART 9, NBCC 2015

THIS DESIGN COMPLIES WITH:
- PART 9 OF CBC 2018, ABC 2019
- PART 9 OF OBC 2012 (2019 AMENDMENT)
- CSA 086-14
- TPIC 2014

(55 % OF 31.3 P.S.F. G.S.L. PLUS 8.4 P.S.F. RAIN LOAD) EQUALS 25.6 P.S.F. SPECIFIED ROOF LIVE LOAD

ALLOWABLE DEFL. (LL) = L/360 (1.03")
CALCULATED VERT. DEFL. (LL) = L/999 (0.21")
ALLOWABLE DEFL. (TL) = L/360 (1.03")
CALCULATED VERT. DEFL. (TL) = L/996 (0.37")

CSI: TC=0.74/1.00 (F-H:1), BC=0.72/1.00 (Q-R:1)
WB=0.82/1.00 (B-T:1), SSI=0.28/1.00 (H-I:1)

DOL LUMBER=1.00 NAIL=1.00 LS BEND=1.00
COMP=1.00 SHEAR=1.00 TENS=1.00

CITY OF RICHMOND HILL
BUILDING DIVISION
09/22/2022
KOTT
RECEIVED
Per: joshua.nabua



June 29, 2021

READ ALL NOTES ON THIS PAGE AND ON THE ENGINEERING NOTE PAGE ENP-1. THE NOTE PAGE IS AN INTEGRAL PART OF THIS DRAWING AS IT CONTAINS SPECIFICATIONS AND CRITERIA USED IN THE DESIGN OF THIS COMPONENT.

JOB NAME	TRUSS NAME	QUANTITY	PLY	JOB DESC.	DRWG NO.
IM0621-169	G01	1	1	TRUSS DESC.	

Version 8.420 S Apr 29 2021 MiTek Industries, Inc. Tue Jun 29 13:08:01 2021 Page 2
 ID:6C523IFljGTY_39enVU3pLzc1B6-vhvRPC27masZWMMdsIdeaVabT4882kp4jbsLgz1QmC

COMPANION LIVE LOAD FACTOR = 1.00

AUTOSOLVE LEFT HEEL ONLY

TRUSS PLATE MANUFACTURER IS NOT
RESPONSIBLE FOR QUALITY CONTROL IN
THE TRUSS MANUFACTURING PLANT .

NAIL VALUES

PLATE	GRIP(DRY) (PSI)	SHEAR (PLI)	SECTION (PLI)
MT20	MAX MIN	MAX MIN	MAX MIN
	650 371	1747 788	1987 1873

PLATE PLACEMENT TOL. = 0.250 inches

PLATE ROTATION TOL. = 5.0 Deg.

JSI GRIP= 0.90 (B) (INPUT = 0.90)

JSI METAL= 0.89 (P) (INPUT = 1.00)



June 29, 2021

READ ALL NOTES ON THIS PAGE AND ON THE
ENGINEERING NOTE PAGE ENP-1. THE NOTE PAGE
IS AN INTEGRAL PART OF THIS DRAWING AS IT
CONTAINS SPECIFICATIONS AND CRITERIA USED
IN THE DESIGN OF THIS COMPONENT.


CITY OF RICHMOND HILL
BUILDING DIVISION

09/22/2022



RECEIVED

Per: joshua.nabua



TOTAL WEIGHT = 147 lb

LUMBER

N. L. G. A. RULES

CHORDS	SIZE	DRY	LUMBER	DESCR.
A - D	2x4	DRY	No.2	SPF
D - G	2x4	DRY	2100F 1.8E	SPF
G - I	2x4	DRY	2100F 1.8E	SPF
I - L	2x4	DRY	No.2	SPF
U - B	2x6	DRY	No.2	SPF
M - K	2x6	DRY	No.2	SPF
U - Q	2x6	DRY	2100F 1.8E	SPF
Q - M	2x6	DRY	2100F 1.8E	SPF

ALL WEBS 2x3 DRY No.2 SPF

EXCEPT

B - T 2x4 DRY No.2 SPF

J - M 2x4 DRY No.2 SPF

DRY: SEASONED LUMBER.

PLATES (table is in inches)

JT	TYPE	PLATES	W	LEN	Y	X
B	TMVW-t	MT20	5.0	8.0	1.75	4.00
C	TMVW-t	MT20	4.0	4.0	2.00	1.50
D	TTWW-m	MT20	6.0	8.0	2.25	3.75
E	TMVW-t	MT20	4.0	4.0	1.50	1.75
F	TMVW-t	MT20	2.0	4.0		
G	TS-t	MT20	3.0	10.0		
H	TMVW-t	MT20	4.0	6.0	1.50	2.50
I	TTWW-m	MT20	6.0	8.0	Edge	
J	TMVW-t	MT20	4.0	10.0	1.75	3.75
K	TMVW-t	MT20	2.0	4.0		
M	BMVW-t	MT20	5.0	8.0	2.25	3.50
N	BMVW-t	MT20	3.0	4.0	1.75	1.50
O	BMVW-t	MT20	5.0	6.0	2.00	1.75
P	BMVW-t	MT20	8.0	8.0	4.25	2.50
Q	BS-t	MT20	10.0	10.0		
R	BMVW-t	MT20	5.0	6.0	2.25	1.50
S	BMVW-t	MT20	4.0	4.0		
T	BMVW-t	MT20	4.0	8.0	1.75	2.25
U	BMVW-t	MT20	3.0	5.0		

Edge - INDICATES REFERENCE CORNER OF PLATE TOUCHES EDGE OF CHORD.

WB - INDICATES BLOCKING REQUIRED



DIMENSIONS, SUPPORTS AND LOADINGS SPECIFIED BY FABRICATOR TO BE VERIFIED BY BUILDING DESIGNER

BEARINGS

JT	FACTORED GROSS REACTION		MAXIMUM FACTORED GROSS REACTION		INPUT BRG	REQRD BRG
	VERT	HORZ	DOWN	HORZ		
U	3440	0	3440	0	5-8	3-12
M	2910	0	2910	0	5-8	3-2

UNFACTORED REACTIONS

JT	1ST LCASE		MAX/MIN. COMPONENT REACTIONS		WIND	DEAD	SOIL
	COMBINED	SNOW	LIVE	PERM. LIVE			
U	2409	1718 / 0	0 / 0	0 / 0	0 / 0	690 / 0	0 / 0
M	2035	1467 / 0	0 / 0	0 / 0	0 / 0	567 / 0	0 / 0

BEARING MATERIAL TO BE SPF NO.2 OR BETTER AT JOINT(S) U, M

BRACING

TOP CHORD TO BE SHEATHED OR MAX. PURLIN SPACING = 2.36 FT.

MAX. UNBRACED BOTTOM CHORD LENGTH = 10.00 FT OR RIGID CEILING DIRECTLY APPLIED.

ALL FITCH BREAKS AND PERIMETER CORNER JOINTS MUST BE Laterally RESTRAINED.

LOADING

TOTAL LOAD CASES: (4)

CHORDS					WEBS				
MEMB.	MAX. FACTORED FORCE (LBS)	FACTORED VERT. LOAD (PLF)	LOAD LC1	MAX CSI (LC)	MAX. UNBRACED LENGTH	MEMB.	MAX. FACTORED FORCE (LBS)	MAX. CSI (LC)	
FR-TO		FROM	TO			FR-TO			
A-B	0 / 26	-84.3	-84.3	0.12 (1)	10.00	T-C	-1107 / 0	0.19 (1)	
B-C	-4602 / 0	-84.3	-84.3	0.42 (1)	2.94	C-S	0 / 788	0.19 (1)	
C-D	-5299 / 0	-84.3	-84.3	0.48 (1)	2.65	S-D	-233 / 67	0.06 (1)	
D-E	-7100 / 0	-158.9	-158.9	0.81 (1)	2.62	D-R	0 / 2974	0.74 (1)	
E-F	-8014 / 0	-158.9	-158.9	0.91 (1)	2.36	R-E	-1608 / 0	0.42 (1)	
F-G	-8014 / 0	-84.3	-84.3	0.54 (1)	2.79	E-P	0 / 1150	0.28 (1)	
G-H	-8014 / 0	-84.3	-84.3	0.54 (1)	2.79	P-F	-534 / 0	0.14 (1)	
H-I	-6300 / 0	-84.3	-84.3	0.40 (1)	3.26	P-H	0 / 2235	0.55 (1)	
I-J	-4422 / 0	-84.3	-84.3	0.37 (1)	3.03	O-H	-1834 / 0	0.48 (1)	
J-K	0 / 8	-84.3	-84.3	0.11 (1)	10.00	O-I	0 / 3061	0.76 (1)	
K-L	0 / 26	-84.3	-84.3	0.12 (1)	10.00	N-I	-259 / 0	0.07 (1)	
U-B	-3319 / 0	0.0	0.0	0.23 (1)	5.78	N-J	0 / 587	0.15 (1)	
M-K	-224 / 0	0.0	0.0	0.02 (1)	7.81	B-T	0 / 4249	0.75 (1)	
						J-M	-4368 / 0	0.77 (1)	
U-T	0 / 0	-34.4	-34.4	0.08 (1)	10.00				
T-S	0 / 4122	-34.4	-34.4	0.30 (1)	10.00				
S-R	0 / 4734	-34.4	-34.4	0.29 (1)	10.00				
R-Q	0 / 7100	-34.4	-34.4	0.48 (1)	10.00				
Q-P	0 / 7100	-34.4	-34.4	0.48 (1)	10.00				
P-O	0 / 6300	-18.2	-18.2	0.43 (1)	10.00				
O-N	0 / 3950	-18.2	-18.2	0.23 (1)	10.00				
N-M	0 / 3484	-18.2	-18.2	0.21 (1)	10.00				

FACTORED CONCENTRATED LOADS (LBS)

JT	LOC.	LC1	MAX-	MAX+	FACE	DIR.	TYPE	HEEL	CONN.
D	6-0-0	-379	-379	---	FRONT	VERT	TOTAL	---	C1
P	15-11-4	-396	-444	---	FRONT	VERT	DEAD	---	C1
P	15-11-4	-1170	-1170	---	FRONT	VERT	SNOW	---	C1

CONNECTION REQUIREMENTS

1) C1: A SUITABLE HANGER/MECHANICAL CONNECTION IS REQUIRED.

READ ALL NOTES ON THIS PAGE AND ON THE ENGINEERING NOTE PAGE ENP-1. THE NOTE PAGE IS AN INTEGRAL PART OF THIS DRAWING AS IT CONTAINS SPECIFICATIONS AND CRITERIA USED IN THE DESIGN OF THIS COMPONENT.

DESIGN CRITERIA

*** SPECIAL LOADS ANALYSIS ***

GEOMETRY AND/OR BASIC LOADS CHANGED BY USER.

LOADS WERE DERIVED FROM USER INPUT NO FURTHER MODIFICATIONS WERE MADE

SPECIFIED LOADS:

TOP CH. LL = 25.6 PSF

DL = 3.0 PSF

BOT CH. LL = 0.0 PSF

DL = 7.3 PSF

TOTAL LOAD = 35.9 PSF

SPACING = 24.0 IN. C/C

LOADING IN FLAT SECTION BASED ON A SLOPE OF 6.00/12

GIRDER TYPE: CPrimeHip

SIDE SETBACK = 6-0-0

END SETBACK = 6-0-0

END WALL WIDTH = 5-8

CORNER FRAMING TYPE: CONVENTIONAL

END JACK TYPE: CONVENTIONAL

APPLIED TO FRONT SIDE

- ADDTL LOADS BASED ON 55 % OF GSL.

LOADS APPLIED TO FIRST 15-11-4 OF SPAN MEASURED FROM THE LEFT.

*** NON STANDARD GIRDER ***

ADDTL USER-DEFINED LOADS APPLIED TO ALL LOAD CASES.

THIS TRUSS IS DESIGNED FOR RESIDENTIAL OR SMALL BUILDING REQUIREMENTS OF PART 9, NBCC 2015

THIS DESIGN COMPLIES WITH:

- PART 9 OF BCBC 2018, ABC 2019

- PART 9 OF OBC 2012 (2019 AMENDMENT)

- CSA 086-14

- TPIC 2014

(55 % OF 31.3 P.S.F. G.S.L. PLUS 8.4 P.S.F. RAIN LOAD) EQUALS 25.6 P.S.F. SPECIFIED ROOF LIVE LOAD

ALLOWABLE DEFL.(LL) = L/360 (1.03")

CALCULATED VERT. DEFL.(LL) = L/999 (0.33")

ALLOWABLE DEFL.(TL) = L/360 (1.03")

CALCULATED VERT. DEFL.(TL) = L/647 (0.57")

CSI: TC=0.91/1.00 (E-F:1), BC=0.48/1.00 (P-R:1), WB=0.77/1.00 (J-M:1), SSI=0.41/1.00 (D-E:1)

DOL LUMBER=1.00 NAIL=1.00 LS BEND=1.00 COMP=1.00 SHEAR=1.00 TENS=1.00

CITY OF RICHMOND HILL BUILDING DIVISION

CONTINUED ON PAGE 2

09/22/2022

KOTT RECEIVED

Per: joshua.nabua

JOB NAME	TRUSS NAME	QUANTITY	PLY	JOB DESC.	DRWG NO.
IM0621-169	G02	1	1	TRUSS DESC.	

Version 8.420 S Apr 29 2021 MiTek Industries, Inc. Tue Jun 29 13:08:09 2021 Page 2
ID:6C523IFjGTY_39enVU3pLzc1B6-gEOT4x88t2tQTbOIK_bVyGquwhl0ha_wzXHdDz1Qm4

COMPANION LIVE LOAD FACTOR = 1.00

AUTOSOLVE LEFT HEEL ONLY

TRUSS PLATE MANUFACTURER IS NOT RESPONSIBLE FOR QUALITY CONTROL IN THE TRUSS MANUFACTURING PLANT .

NAIL VALUES

PLATE	GRIP(DRY)	SHEAR	SECTION
	(PSI)	(PLI)	(PLI)
	MAX MIN	MAX MIN	MAX MIN
MT20	650 371	1747 788	1987 1873

PLATE PLACEMENT TOL. = 0.250 inches

PLATE ROTATION TOL. = 5.0 Deg.

JSI GRIP= 0.90 (M) (INPUT = 0.90)

JSI METAL= 1.00 (Q) (INPUT = 1.00)



June 29, 2021

READ ALL NOTES ON THIS PAGE AND ON THE ENGINEERING NOTE PAGE ENP-1. THE NOTE PAGE IS AN INTEGRAL PART OF THIS DRAWING AS IT CONTAINS SPECIFICATIONS AND CRITERIA USED IN THE DESIGN OF THIS COMPONENT.

CITY OF RICHMOND HILL
BUILDING DIVISION

09/22/2022



RECEIVED

Per: joshua.nabua

JOB NAME	TRUSS NAME	QUANTITY	PLY	JOB DESC.	DRWG NO.
IM0621-169	G03	1	1	TRUSS DESC.	

Version 8.420 S Apr 29 2021 MiTek Industries, Inc. Tue Jun 29 13:08:17 2021 Page 2
 ID:6C523IFijGTy_39enVU3pLzc1B6-RmtVmgE9_VtHRq?lofkOHY9QJvf9uNE9mCTiulz1Qly

PLATE PLACEMENT TOL. = 0.250 inches

PLATE ROTATION TOL. = 5.0 Deg.

JSI GRIP= 0.90 (B) (INPUT = 0.90)

JSI METAL= 0.42 (B) (INPUT = 1.00)



June 29, 2021

READ ALL NOTES ON THIS PAGE AND ON THE
 ENGINEERING NOTE PAGE ENP-1. THE NOTE PAGE
 IS AN INTEGRAL PART OF THIS DRAWING AS IT
 CONTAINS SPECIFICATIONS AND CRITERIA USED
 IN THE DESIGN OF THIS COMPONENT.

CITY OF RICHMOND HILL
 BUILDING DIVISION

09/22/2022



RECEIVED

Per: joshua.nabua

Version 8.420 S Apr 29 2021 MiTek Industries, Inc. Tue Jun 29 13:08:24 2021 Page 1
ID:6C523IFII GTY 39enVU3pLzc1B6-k6o8E3KYLflmv1eieM13Rvd6k431bGBNofaerz1Ql

Per: joshua.nabua

JOB NAME	TRUSS NAME	QUANTITY	PLY	JOB DESC.	DRWG NO.
IM0621-169	G04	1	1	TRUSS DESC.	

Version 8.420 S Apr 29 2021 MiTek Industries, Inc. Tue Jun 29 13:08:24 2021 Page 2
ID:6C523IFIJGTy_39enVU3pLzc1B6-k6o8E3KYLflmv1ejem13Ryd6k431bGBNofaerz1Qlr

NAIL VALUES
PLATE GRIP(DRY) SHEAR SECTION
(Psi) (PLI) (PLI)
MAX MIN MAX MIN MAX MIN
MT20 650 371 1747 788 1987 1873
PLATE PLACEMENT TOL. = 0.250 inches
PLATE ROTATION TOL. = 5.0 Deg.
JSI GRIP= 0.89 (H) (INPUT = 0.90)
JSI METAL= 0.22 (I) (INPUT = 1.00)



June 29, 2021

READ ALL NOTES ON THIS PAGE AND ON THE
ENGINEERING NOTE PAGE ENP-1. THE NOTE PAGE
IS AN INTEGRAL PART OF THIS DRAWING AS IT
CONTAINS SPECIFICATIONS AND CRITERIA USED
IN THE DESIGN OF THIS COMPONENT.

CITY OF RICHMOND HILL
BUILDING DIVISION

09/22/2022




RECEIVED

Per: joshua.nabua

JOB NAME	TRUSS NAME	QUANTITY	PLY	JOB DESC.	DRWG NO.
IM0621-169	G05	1	1	TRUSS DESC.	

Version 8.420 S Apr 29 2021 MiTek Industries, Inc. Tue Jun 29 13:08:30 2021 Page 1
ID:6C523IFlJGTy_39enVU3pLzc1B6-ZGAPU6OJxVVRUqUo3uTRJJCgJ94MRHt4Ik6vrVz1QII



Scale = 1:32.4

TOTAL WEIGHT = 33 lb [M]

LUMBER

N. L. G. A. RULES

CHORDS	SIZE	LUMBER	DESCR.
F - A	2x4	DRY	No.2
A - C	2x4	DRY	No.2
D - C	2x4	DRY	No.2
F - D	2x6	DRY	No.2
ALL WEBS	2x3	DRY	No.2
DRY: SEASONED LUMBER.			

PLATES (table is in inches)

JT	TYPE	PLATES	W	LEN	Y	X
A	TMVW-p	MT20	4.0	4.0	1.25	2.00
B	TMWW-t	MT20	4.0	4.0	1.50	1.00
C	TMV+p	MT20	2.0	4.0		
D	BMVW1-t	MT20	4.0	4.0	2.00	1.75
E	BMVW1-t	MT20	6.0	6.0	4.00	3.00
F	BMV1+p	MT20	2.0	4.0		

DIMENSIONS, SUPPORTS AND LOADINGS SPECIFIED BY FABRICATOR TO BE VERIFIED BY BUILDING DESIGNER**BEARINGS**

JT	FACTORED GROSS REACTION	MAXIMUM FACTORED GROSS REACTION	INPUT BRG	REQRD BRG
	VERT	DOWN	IN-SX	IN-SX
F	1554	0	5-8	1-11
D	1554	0	0	MECHANICAL

A SUITABLE HANGER/MECHANICAL CONNECTION IS REQUIRED AT JOINT D. MINIMUM BEARING LENGTH AT JOINT D = 1-11.

UNFACTORED REACTIONS

JT	1ST LCASE	MAX/MIN. COMPONENT REACTIONS	SNOW	LIVE	PERM.LIVE	WIND	DEAD	SOIL
F	1088	776 / 0	0 / 0	0 / 0	0 / 0	0 / 0	312 / 0	0 / 0
D	1088	776 / 0	0 / 0	0 / 0	0 / 0	0 / 0	312 / 0	0 / 0

BEARING MATERIAL TO BE SPF NO.2 OR BETTER AT JOINT(S) F

BRACING

TOP CHORD TO BE SHEATHED OR MAX. PURLIN SPACING = 5.88 FT.
MAX. UNBRACED BOTTOM CHORD LENGTH = 10.00 FT OR RIGID CEILING DIRECTLY APPLIED.

ALL FITCH BREAKS AND PERIMETER CORNER JOINTS MUST BE Laterally RESTRAINED.

LOADING

TOTAL LOAD CASES: (4)

CHORDS				WEBS			
MEMB.	MAX. FACTORED FORCE (LBS)	FACTORED VERT. LOAD (PLF)	MAX. FACTORED CSI (LC)	MEMB.	MAX. FACTORED FORCE (LBS)	MAX. FACTORED CSI (LC)	
FR-TO		FROM TO		FR-TO			
F-A	-1018 / 0	0.0 0.0 0.11 (1)	7.74	A-E	0 / 967	0.24 (1)	
A-B	-1089 / 0	-84.3 -84.3 0.14 (1)	5.88	E-B	0 / 1224	0.30 (1)	
B-C	-14 / 0	-84.3 -84.3 0.12 (1)	6.25	B-D	-1297 / 0	0.38 (1)	
D-C	-101 / 0	0.0 0.0 0.05 (1)	7.81				
F-E	0 / 0	-433.6 -433.6 0.25 (1)	10.00				
E-D	0 / 918	-433.6 -433.6 0.37 (1)	10.00				

DESIGN CRITERIA**SPECIFIED LOADS:**

TOP CH.	LL	=	25.6	PSF
	DL	=	3.0	PSF
BOT CH.	LL	=	0.0	PSF
	DL	=	7.3	PSF
TOTAL LOAD	=	35.9	PSF	

SPACING = 24.0 IN. C/C

GIRDER TYPE: CStdGirder
START DISTANCE = 0-0
START SPAN CARRIED = 18-8-0
END DISTANCE = 6-0-0
END SPAN CARRIED = 18-8-0
END WALL WIDTH = 5-8
APPLIED TO FRONT SIDE OF BOTTOM CHORD.
- ADDTL LOADS BASED ON 55 % OF GSL.

THIS TRUSS IS DESIGNED FOR RESIDENTIAL OR SMALL BUILDING REQUIREMENTS OF PART 9, NBCC 2015

THIS DESIGN COMPLIES WITH:
- PART 9 OF BCBC 2018, ABC 2019
- PART 9 OF OBC 2012 (2019 AMENDMENT)
- CSA 086-14
- TPIC 2014

(55 % OF 31.3 P.S.F. G.S.L. PLUS 8.4 P.S.F. RAIN LOAD) EQUALS 25.6 P.S.F. SPECIFIED ROOF LIVE LOAD

ALLOWABLE DEFL.(LL) = L/360 (0.20")
CALCULATED VERT. DEFL.(LL) = L/999 (0.01")
ALLOWABLE DEFL.(TL) = L/360 (0.20")
CALCULATED VERT. DEFL.(TL) = L/999 (0.03")

CSI: TC=0.14/1.00 (A-B:1), BC=0.37/1.00 (D-E:1), WB=0.38/1.00 (B-D:1), SSI=0.51/1.00 (E-F:1)

DOL LUMBER=1.00 NAIL=1.00 LS BEND=1.00
COMP=1.00 SHEAR=1.00 TENS=1.00

COMPANION LIVE LOAD FACTOR = 1.00

TRUSS PLATE MANUFACTURER IS NOT RESPONSIBLE FOR QUALITY CONTROL IN THE TRUSS MANUFACTURING PLANT.

NAIL VALUES	PLATE GRIP(DRY)	SHEAR (PSI)	SECTION (PLI)
	MAX MIN	MAX MIN	MAX MIN
MT20	650 371	1747 788	1987 1873

PLATE PLACEMENT TOL = 0.250 inches

CITY OF RICHMOND HILL
BUILDING DIVISION
CONTINUED ON PAGE 2

09/22/2022
KOTT
RECEIVED
Per: joshua.nabua



June 29, 2021

READ ALL NOTES ON THIS PAGE AND ON THE ENGINEERING NOTE PAGE ENP-1. THE NOTE PAGE IS AN INTEGRAL PART OF THIS DRAWING AS IT CONTAINS SPECIFICATIONS AND CRITERIA USED IN THE DESIGN OF THIS COMPONENT.

JOB NAME	TRUSS NAME	QUANTITY	PLY	JOB DESC.	DRWG NO.
IM0621-169	G05	1	1	TRUSS DESC.	

Version 8.420 S Apr 29 2021 MiTek Industries, Inc. Tue Jun 29 13:08:30 2021 Page 2
 ID:6C523IFljGTY_39enVU3pLzc1B6-ZGAPU6OJxVWRUqUo3uTRJiCgj94MRHt4lk6vrVz1Qll

JSI GRIP= 0.87 (D) (INPUT = 0.90)
 JSI METAL= 0.32 (B) (INPUT = 1.00)



June 29, 2021

READ ALL NOTES ON THIS PAGE AND ON THE
 ENGINEERING NOTE PAGE ENP-1. THE NOTE PAGE
 IS AN INTEGRAL PART OF THIS DRAWING AS IT
 CONTAINS SPECIFICATIONS AND CRITERIA USED
 IN THE DESIGN OF THIS COMPONENT.

CITY OF RICHMOND HILL
 BUILDING DIVISION

09/22/2022




RECEIVED

Per: joshua.nabua

JOB NAME	TRUSS NAME	QUANTITY	PLY	JOB DESC.	DRWG NO.
IM0621-169	G06	1	1	TRUSS DESC.	

Version 8.420 S Apr 29 2021 MiTek Industries, Inc. Tue Jun 29 13:08:37 2021 Page 1
ID:6C523IFIGTY 39enVU3pLzc1B6-sc52yWUiHeOSQuX8zs545A sLzJmJLZ6MJmbbz1Qle



Scale = 1:24.6

TOTAL WEIGHT = 28 lb [M]

LUMBER

N. L. G. A. RULES	CHORDS	SIZE	LUMBER	DESCR.
F - A	2x4	DRY	No.2	SPF
A - C	2x4	DRY	No.2	SPF
D - C	2x4	DRY	No.2	SPF
F - D	2x6	DRY	No.2	SPF
ALL WEBS	2x3	DRY	No.2	SPF
DRY: SEASONED LUMBER.				

PLATES (table is in inches)

JT TYPE	PLATES	W	LEN	Y	X
A	TMVW-t	MT20	5.0	6.0	2.00 2.75
B	TMVW-t	MT20	4.0	6.0	1.75 2.75
C	TMV+p	MT20	2.0	4.0	
D	BMVW1-t	MT20	4.0	6.0	2.00 2.00
E	BMVW+t	MT20	6.0	8.0	4.25 2.25
F	BMV1+p	MT20	2.0	4.0	2.25 1.00

DIMENSIONS, SUPPORTS AND LOADINGS SPECIFIED BY FABRICATOR TO BE VERIFIED BY BUILDING DESIGNER

BEARINGS	FACTORED GROSS REACTION	MAXIMUM FACTORED GROSS REACTION	INPUT BRG	REQRD BRG
JT	VERT	HORZ	DOWN	HORZ
F	1856	0	1856	0
D	1566	0	1566	0

A SUITABLE HANGER/MECHANICAL CONNECTION IS REQUIRED AT JOINT D. MINIMUM BEARING LENGTH AT JOINT D = 1-11.

UNFACTORED REACTIONS

JT	1ST LCASE	MAX./MIN.	COMPONENT REACTIONS
F	COMBINED	SNOW	LIVE PERM.LIVE WIND DEAD SOIL
D	1300	921 / 0	0 / 0 0 / 0 379 / 0 0 / 0
D	1097	780 / 0	0 / 0 0 / 0 317 / 0 0 / 0

BEARING MATERIAL TO BE SPF NO.2 OR BETTER AT JOINT(S) F

BRACING

TOP CHORD TO BE SHEATHED OR MAX. PURLIN SPACING = 4.30 FT.
MAX. UNBRACED BOTTOM CHORD LENGTH = 10.00 FT OR RIGID CEILING DIRECTLY APPLIED.

ALL FITCH BREAKS AND PERIMETER CORNER JOINTS MUST BE Laterally RESTRAINED.

LOADING

TOTAL LOAD CASES: (4)

MEMB.	CHORDS	MAX. FACTORED FORCE (LBS)	FACTORED VERT. LOAD (PLF)	MAX. FACTORED VERT. LOAD (PLF)	MAX. FACTORED VERT. LOAD (PLF)	MAX. FACTORED VERT. LOAD (PLF)	MAX. FACTORED VERT. LOAD (PLF)	MAX. FACTORED VERT. LOAD (PLF)	MAX. FACTORED VERT. LOAD (PLF)
FR-TO									
F-A	-2036 / 0	0.0	0.0	0.22 (1)	5.87	A-E	0 / 2283	0.57 (1)	
A-B	-2257 / 0	-84.3	-84.3	0.22 (1)	4.30	E-B	0 / 1398	0.35 (1)	
B-C	-10 / 0	-84.3	-84.3	0.24 (1)	6.25	B-D	-2167 / 0	0.76 (1)	
D-C	-164 / 0	0.0	0.0	0.04 (1)	7.81				
F-E	0 / 0	-18.2	-18.2	0.22 (1)	10.00				
E-D	0 / 2045	-339.6	-339.6	0.77 (1)	10.00				

FACTORED CONCENTRATED LOADS (LBS)

JT	LOC.	LC1	MAX-	MAX+	FACE	DIR.	TYPE	HEEL	CONN.
E	1-6-12	-358	-400	---	FRONT	VERT	DEAD	---	C1
E	1-6-12	-1023	-1023	---	FRONT	VERT	SNOW	---	C1

CONNECTION REQUIREMENTS

1) C1: A SUITABLE HANGER/MECHANICAL CONNECTION IS REQUIRED.

DESIGN CRITERIA

*** SPECIAL LOADS ANALYSIS ***
GEOMETRY AND/OR BASIC LOADS CHANGED BY USER.
LOADS WERE DERIVED FROM USER INPUT
NO FURTHER MODIFICATIONS WERE MADE

SPECIFIED LOADS:

TOP CH.	LL	=	25.6	PSF
	DL	=	3.0	PSF
BOT CH.	LL	=	0.0	PSF
	DL	=	7.3	PSF
TOTAL LOAD	=	35.9	PSF	

SPACING = 24.0 IN. C/C

GIRDER TYPE: CStdGirder
START DISTANCE = 1-6-12
START SPAN CARRIED = 15-0-0
END DISTANCE = 6-0-0
END SPAN CARRIED = 15-0-0
END WALL WIDTH = 5-8
APPLIED TO FRONT SIDE OF BOTTOM CHORD.
- ADDTL LOADS BASED ON 55 % OF GSL.

*** NON STANDARD GIRDER ***

ADDTL USER-DEFINED LOADS APPLIED TO ALL LOAD CASES.

THIS TRUSS IS DESIGNED FOR RESIDENTIAL OR SMALL BUILDING REQUIREMENTS OF PART 9, NBCC 2015

THIS DESIGN COMPLIES WITH:

- PART 9 OF CBC 2018, ABC 2019
- PART 9 OF OBC 2012 (2019 AMENDMENT)
- CSA 086-14
- TPIC 2014

(55 % OF 31.3 P.S.F. G.S.L. PLUS 8.4 P.S.F. RAIN LOAD) EQUALS 25.6 P.S.F. SPECIFIED ROOF LIVE LOAD

ALLOWABLE DEFL.(LL)= L/360 (0.20")
CALCULATED VERT. DEFL.(LL) = L/999 (0.05")
ALLOWABLE DEFL.(TL)= L/360 (0.20")
CALCULATED VERT. DEFL.(TL) = L/806 (0.09")

CSI: TC=0.24/1.00 (B-C:1), BC=0.77/1.00 (D-E:1), WB=0.76/1.00 (B-D:1), SSI=0.55/1.00 (D-E:1)

DOL LUMBER=1.00 NAIL=1.00 LS BEND=1.00 COMP=1.00 SHEAR=1.00 TENS=1.00

COMPANION LIVE LOAD FACTOR = 1.00



June 29, 2021

READ ALL NOTES ON THIS PAGE AND ON THE ENGINEERING NOTE PAGE ENP-1. THE NOTE PAGE IS AN INTEGRAL PART OF THIS DRAWING AS IT CONTAINS SPECIFICATIONS AND CRITERIA USED IN THE DESIGN OF THIS COMPONENT.

TRUSS PLATE MANUFACTURER IS NOT RESPONSIBLE FOR QUALITY CONTROL IN THE TRUSS MANUFACTURING PLANT.
BUILDING DIVISION
09/22/2022
KOTT
RECEIVED
Per: joshua.nabua

JOB NAME	TRUSS NAME	QUANTITY	PLY	JOB DESC.	DRWG NO.
IM0621-169	G06	1	1	TRUSS DESC.	

Version 8.420 S Apr 29 2021 MiTek Industries, Inc. Tue Jun 29 13:08:37 2021 Page 2
ID:6C523IFljGTy_39enVU3pLzc1B6-sc52yWUiHeOSquX8zs545A_sLzMjaLZ6MJJmbbz1Qle

NAIL VALUES
PLATE GRIP(DRY) SHEAR SECTION
(Psi) (PLI) (PLI)
MAX MIN MAX MIN MAX MIN
MT20 650 371 1747 788 1987 1873
PLATE PLACEMENT TOL. = 0.250 inches
PLATE ROTATION TOL. = 5.0 Deg.
JSI GRIP= 0.87 (F) (INPUT = 0.90)
JSI METAL= 0.61 (E) (INPUT = 1.00)



June 29, 2021

READ ALL NOTES ON THIS PAGE AND ON THE
ENGINEERING NOTE PAGE ENP-1. THE NOTE PAGE
IS AN INTEGRAL PART OF THIS DRAWING AS IT
CONTAINS SPECIFICATIONS AND CRITERIA USED
IN THE DESIGN OF THIS COMPONENT.


CITY OF RICHMOND HILL
BUILDING DIVISION

09/22/2022



RECEIVED

Per: joshua.nabua



TOTAL WEIGHT = 87 lb

LUMBER

N. L. G. A. RULES

CHORDS	SIZE	LUMBER	DESCR.
A - D	2x4	DRY	No.2
D - F	2x4	DRY	No.2
K - B	2x4	DRY	No.2
G - F	2x4	DRY	No.2
K - I	2x4	DRY	No.2
I - G	2x4	DRY	No.2

ALL WEBS 2x3 DRY No.2 SPF

ALL GABLE WEBS 2x3 DRY No.2 SPF
DRY: SEASONED LUMBER.

GABLE STUDS SPACED AT 2'-0" OC.

PLATES (table is in inches)

JT	TYPE	PLATES	W	LEN	Y	X
B	TMVW-t	MT20	3.0	5.0	1.50	2.00
C	TMVW-t	MT20	3.0	4.0	1.50	1.50
D	TTW+p	MT20	3.0	4.0	2.25	1.50
E	TMVW-t	MT20	4.0	4.0	2.00	1.50
F	TMV+p	MT20	2.0	4.0		
G	BMV1+p	MT20	2.0	4.0		
H	BMV1+w	MT20	2.0	4.0		
I	BSWWW-I	MT20	5.0	6.0	3.00	3.00
J	BMVW+t	MT20	3.0	4.0	1.50	1.50
K	BMV1+p	MT20	2.0	4.0		
L, M, N, O, P, Q, R, S						
L	NP+w	MT20	2.0	4.0		

DIMENSIONS, SUPPORTS AND LOADINGS SPECIFIED BY FABRICATOR TO BE VERIFIED BY BUILDING DESIGNER**BEARINGS**

	FACTORED GROSS REACTION	MAXIMUM FACTORED GROSS REACTION	INPUT BRG	REQRD BRG
JT	VERT	HORZ	UPLIFT	IN-SX
G	227	0	0	6-1-8
H	1100	0	0	6-1-8
K	790	0	0	5-8
T	21	0	-4	6-1-8

PROVIDE ANCHORAGE AT BEARING JOINT T FOR 150 LBS. FACTORED UPLIFT

UNFACTORED REACTIONS

JT	1ST LCASE	MAX / MIN	COMPONENT REACTIONS	PERM.LIVE	WIND	DEAD	SOIL
G	COMBINED	SNOW	LIVE	0/0	0/0	51/0	0/0
H	780	501/0	0/0	0/0	0/0	279/0	0/0
K	552	399/0	0/0	0/0	0/0	153/0	0/0
T	14	16/0	0/0	0/0	0/0	0/-3	0/0

BEARING MATERIAL TO BE SPF NO.2 OR BETTER AT JOINT(S) G, H, K, T

BRACINGTOP CHORD TO BE SHEATHED OR MAX. PURLIN SPACING = 6.25 FT.
MAX. UNBRACED BOTTOM CHORD LENGTH = 10.00 FT OR RIGID CEILING DIRECTLY APPLIED.

ALL FITCH BREAKS AND PERIMETER CORNER JOINTS MUST BE Laterally RESTRAINED.

LOADING

TOTAL LOAD CASES: (4)

MEMB.	CHORDS MAX. FACTORED FORCE (LBS)	FACTORED VERT. LOAD (PLF)	LC1 MAX	MAX. UNBRAC LENGTH	MEMB.	WEBS MAX. FACTORED FORCE (LBS)	MAX. CSI (LC)
FR-TO		FROM TO			FR-TO		
A-B	0/32	-84.3 -84.3	0.12 (1)	10.00	I-D	0/76	0.02 (1)
B-C	-603/0	-84.3 -84.3	0.39 (1)	6.25	I-E	0/379	0.09 (1)
C-U	-328/0	-84.3 -84.3	0.37 (1)	6.25	H-E	-1008/0	0.38 (1)
U-D	-328/0	-84.3 -100.0	0.37 (1)	6.25	C-I	-421/0	0.28 (1)
D-E	-334/0	-100.0 -94.5	0.41 (1)	6.25	J-C	-1/87	0.03 (4)
E-F	0/30	-94.5 -87.3	0.41 (1)	10.00	B-J	0/534	0.13 (1)
K-B	-750/0	0.0	0.0	0.08 (1)			
G-F	-189/0	0.0	0.0	0.02 (1)			
K-J	0/0	-18.2 -18.2	0.13 (4)	10.00			
J-I	0/523	-18.2 -18.2	0.17 (4)	10.00			
I-T	0/0	-18.2 -18.2	0.05 (1)	10.00			
T-H	0/0	-18.2 -18.2	0.14 (4)	10.00			
H-G	0/0	-18.2 -18.2	0.14 (4)	10.00			

DESIGN CRITERIA*** SPECIAL LOADS ANALYSIS ***
GEOMETRY AND/OR BASIC LOADS CHANGED BY USER.
LOADS WERE DERIVED FROM USER INPUT
NO FURTHER MODIFICATIONS WERE MADE**SPECIFIED LOADS:**TOP CH. LL = 25.6 PSF
DL = 3.0 PSF
BOT CH. LL = 0.0 PSF
DL = 7.3 PSF
TOTAL LOAD = 35.9 PSF**SPACING = 24.0 IN./C**

*** NON STANDARD GIRDER ***

ADDTL USER-DEFINED LOADS APPLIED TO ALL LOAD CASES.

THIS TRUSS IS DESIGNED FOR RESIDENTIAL OR SMALL BUILDING REQUIREMENTS OF PART 9, NBCC 2015

THIS DESIGN COMPLIES WITH:

- PART 9 OF CBC 2018, ABC 2019
- PART 9 OF OBC 2012 (2019 AMENDMENT)
- CSA 086-14
- TPIC 2014

(55 % OF 31.3 P.S.F. G.S.L. PLUS 8.4 P.S.F. RAIN LOAD) EQUALS 25.6 P.S.F. SPECIFIED ROOF LIVE LOAD

ALLOWABLE DEFL.(LL)= L/360 (0.42")
CALCULATED VERT. DEFL.(LL) = L/999 (0.01")
ALLOWABLE DEFL.(TL)= L/360 (0.42")
CALCULATED VERT. DEFL.(TL) = L/999 (0.03")CSI: TC=0.41/1.00 (D-E:1), BC=0.17/1.00 (I-J:4),
WB=0.38/1.00 (E-H:1), SSI=0.21/1.00 (E-F:1)DOL LUMBER=1.00 NAIL=1.00 LS BEND=1.00
COMP=1.00 SHEAR=1.00 TENS=1.00

COMPANION LIVE LOAD FACTOR = 1.00

TRUSS PLATE MANUFACTURER IS NOT RESPONSIBLE FOR QUALITY CONTROL IN THE TRUSS MANUFACTURING PLANT.

NAIL VALUES

PLATE	GRIP(DRY)	SHEAR	SECTION
(PSI)	(PLI)	(PLI)	(PLI)
MAX MIN	MAX MIN	MAX MIN	MAX MIN
MT20	650 371	1747 788	1987 1873



June 29, 2021

READ ALL NOTES ON THIS PAGE AND ON THE
ENGINEERING NOTE PAGE ENP-1. THE NOTE PAGE
IS AN INTEGRAL PART OF THIS DRAWING AS IT
CONTAINS SPECIFICATIONS AND CRITERIA USED
IN THE DESIGN OF THIS COMPONENT.CITY OF RICHMOND HILL
BUILDING DIVISION

CONTINUED ON PAGE 2

09/22/2022

KOTT

RECEIVED

Per: joshua.nabua

JOB NAME	TRUSS NAME	QUANTITY	PLY	JOB DESC.	DRWG NO.
IM0621-169	GE01	1	1	TRUSS DESC.	

Version 8.420 S Apr 29 2021 MiTek Industries, Inc. Tue Jun 29 13:08:44 2021 Page 2
ID:6C523IFjGTY_39enVU3pLzc1B6-8y0iQvZ5eoHSAzZUuqijten?vovjcl8zvVeLhz1QIX

PLATE PLACEMENT TOL. = 0.250 inches

PLATE ROTATION TOL. = 5.0 Deg.

JSI GRIP= 0.85 (E) (INPUT = 0.90)

JSI METAL= 0.31 (J) (INPUT = 1.00)



June 29, 2021

READ ALL NOTES ON THIS PAGE AND ON THE
ENGINEERING NOTE PAGE ENP-1. THE NOTE PAGE
IS AN INTEGRAL PART OF THIS DRAWING AS IT
CONTAINS SPECIFICATIONS AND CRITERIA USED
IN THE DESIGN OF THIS COMPONENT.

CITY OF RICHMOND HILL
BUILDING DIVISION

09/22/2022




RECEIVED

Per: joshua.nabua

JOB NAME	TRUSS NAME	QUANTITY	PLY	JOB DESC.	DRWG NO.
IM0621-169	GE02	1	1	TRUSS DESC.	

Version 8.420 S Apr 29 2021 MiTek Industries, Inc. Tue Jun 29 13:08:51 2021 Page 1
ID:6C5231F1jGTy_39enVU3pLzc1B6-RJxLuIfU_y9TW2bqoolLM7aHmdJisrkAaViW5nz1QIQ



Scale: 3/8"=1'

TOTAL WEIGHT = 53 lb [M]

LUMBER
N. L. G. A. RULES

CHORDS	SIZE	LUMBER	DESCR.
P - B	2x4	DRY No.2	SPF
A - E	2x4	DRY No.2	SPF
E - I	2x4	DRY No.2	SPF
J - H	2x4	DRY No.2	SPF
P - J	2x4	DRY No.2	SPF

ALL WEBS 2x3 DRY No.2 SPF
ALL GABLE WEBS 2x3 DRY No.2 SPF
DRY: SEASONED LUMBER.

GABLE STUDS SPACED AT 2'-0" O.C.

DIMENSIONS, SUPPORTS AND LOADINGS SPECIFIED BY FABRICATOR TO BE VERIFIED BY BUILDING DESIGNER

BEARINGS
THIS TRUSS DESIGNED FOR CONTINUOUS BEARINGS.
THIS TRUSS REQUIRES RIGID SHEATHING ON EXPOSED FACE.
BEARING MATERIAL TO BE SPF NO.2 OR BETTER AT JOINT(S)

BRACING
TOP CHORD TO BE SHEATHED OR MAX. PURLIN SPACING = 6.25 FT.
MAX. UNBRACED BOTTOM CHORD LENGTH = 10.00 FT OR RIGID CEILING DIRECTLY APPLIED.
ALL FITCH BREAKS AND PERIMETER CORNER JOINTS MUST BE Laterally RESTRAINED.

LOADING
TOTAL LOAD CASES: (4)

CHORDS				WEBS			
MEMB.	MAX. FACTORED FORCE (LBS)	FACTORED VERT. LOAD (PLF)	MAX. UNBRACED LENGTH (LC)	MEMB.	MAX. FACTORED FORCE (LBS)	MAX. UNBRACED LENGTH (LC)	
FR-TO		FROM TO		FR-TO			
P-B	-237 / 0	0.0 0.0 0.02 (1)	7.81	M-E	-162 / 0	0.08 (1)	
A-B	0 / 32	-84.3 -84.3 0.11 (1)	10.00	N-D	-166 / 0	0.05 (1)	
B-C	-28 / 0	-84.3 -84.3 0.06 (1)	6.25	O-C	-180 / 0	0.03 (1)	
C-D	-20 / 0	-84.3 -84.3 0.05 (1)	6.25	L-F	-166 / 0	0.05 (1)	
D-E	-14 / 0	-84.3 -84.3 0.04 (1)	6.25	K-G	-180 / 0	0.03 (1)	
E-F	-14 / 0	-84.3 -84.3 0.04 (1)	6.25				
F-G	-20 / 0	-84.3 -84.3 0.05 (1)	6.25				
G-H	-28 / 0	-84.3 -84.3 0.06 (1)	6.25				
H-I	0 / 32	-84.3 -84.3 0.11 (1)	10.00				
J-H	-237 / 0	0.0 0.0 0.02 (1)	7.81				
P-O	0 / 21	-18.2 -18.2 0.02 (4)	10.00				
O-N	0 / 15	-18.2 -18.2 0.02 (4)	10.00				
N-M	0 / 12	-18.2 -18.2 0.02 (4)	10.00				
M-L	0 / 12	-18.2 -18.2 0.02 (4)	10.00				
L-K	0 / 15	-18.2 -18.2 0.02 (4)	10.00				
K-J	0 / 21	-18.2 -18.2 0.02 (4)	10.00				

DESIGN CRITERIA

SPECIFIED LOADS:
TOP CH. LL = 25.6 PSF
DL = 3.0 PSF
BOT CH. LL = 0.0 PSF
DL = 7.3 PSF
TOTAL LOAD = 35.9 PSF

SPACING = 24.0 IN. C/C

THIS TRUSS IS DESIGNED FOR RESIDENTIAL OR SMALL BUILDING REQUIREMENTS OF PART 9, NBCC 2015

THIS DESIGN COMPLIES WITH:
- PART 9 OF BCBC 2018, ABC 2019
- PART 9 OF OBC 2012 (2019 AMENDMENT)
- CSA 086-14
- TPIC 2014

DESIGN ASSUMPTIONS
- OVERHANG NOT TO BE ALTERED OR CUT OFF.

(55% OF 31.3 P.S.F. G.S.L. PLUS 8.4 P.S.F. RAIN LOAD) EQUALS 25.6 P.S.F. SPECIFIED ROOF LIVE LOAD

CSI: TC=0.11/1.00 (A-B:1), BC=0.02/1.00 (O-P:4), WB=0.08/1.00 (E-M:1), SSI=0.08/1.00 (A-B:1)

DOL LUMBER=1.00 NAIL=1.00 LS BEND=1.10 COMP=1.10 SHEAR=1.10 TENS=1.10

COMPANION LIVE LOAD FACTOR = 1.00

TRUSS PLATE MANUFACTURER IS NOT RESPONSIBLE FOR QUALITY CONTROL IN THE TRUSS MANUFACTURING PLANT.

NAIL VALUES
PLATE GRIP(DRY) SHEAR SECTION (PSI) (PLI) (PLI)
MAX MIN MAX MIN MAX MIN
MT20 650 371 1747 788 1987 1873

PLATE PLACEMENT TOL. = 0.250 inches

PLATE ROTATION TOL. = 5.0 Deg.

JSI GRIP= 0.16 (H) (INPUT = 0.90)
JSI METAL= 0.14 (H) (INPUT = 1.00)



June 29, 2021

READ ALL NOTES ON THIS PAGE AND ON THE ENGINEERING NOTE PAGE ENP-1. THE NOTE PAGE IS AN INTEGRAL PART OF THIS DRAWING AS IT CONTAINS SPECIFICATIONS AND CRITERIA USED IN THE DESIGN OF THIS COMPONENT.

CITY OF RICHMOND HILL
BUILDING DIVISION


09/22/2022

KOTT
RECEIVED

Per: joshua.nabua

JOB NAME	TRUSS NAME	QUANTITY	PLY	JOB DESC.	DRWG NO.
IM0621-169	J01	4	1	TRUSS DESC.	

Version 8.420 S Apr 29 2021 MiTek Industries, Inc. Tue Jun 29 13:09:01 2021 Page 1
ID:6C523IFijGTY 39enVU3pLzc1B6-9EX77jmm0Q2ibMINvXi3E twfiICNRet271SCz1QIG



Scale = 1:31.6

TOTAL WEIGHT = 4 X 18 = 73 lb [M]

LUMBER

N. L. G. A. RULES

CHORDS	SIZE	DRY	LUMBER	DESCR.
E - B	2x4	DRY	No.2	SPF
A - C	2x4	DRY	No.2	SPF
E - D	2x4	DRY	No.2	SPF

DRY: SEASONED LUMBER.

PLATES (table is in inches)

JT	TYPE	PLATES	W	LEN	Y	X
B	TMV+p	MT20	2.0	4.0		
E	BMV1+p	MT20	2.0	4.0		

DIMENSIONS, SUPPORTS AND LOADINGS SPECIFIED BY FABRICATOR TO BE VERIFIED BY BUILDING DESIGNER**BEARINGS**

	FACTORED GROSS REACTION	MAXIMUM FACTORED GROSS REACTION	INPUT BRG	REQRD BRG
JT	VERT	HORZ	DOWN	HORZ
E	495	0	495	0
C	190	0	190	0
D	46	0	51	0

SEE MITEK STANDARD DETAIL MSD2015-H FOR CONNECTION TO JOINT(S) C, D

UNFACTORED REACTIONS

JT	1ST LCASE	SNOW	LIVE	PERM.LIVE	WIND	DEAD	SOIL
E	344	262 / 0	0 / 0	0 / 0	0 / 0	82 / 0	0 / 0
C	129	115 / 0	0 / 0	0 / 0	0 / 0	14 / 0	0 / 0
D	37	0 / 0	0 / 0	0 / 0	0 / 0	37 / 0	0 / 0

BEARING MATERIAL TO BE SPF NO.2 OR BETTER AT JOINT(S) E

BRACING

TOP CHORD TO BE SHEATHED OR MAX. PURLIN SPACING = 6.25 FT.
MAX. UNBRACED BOTTOM CHORD LENGTH = 10.00 FT OR RIGID CEILING DIRECTLY APPLIED.

ALL FITCH BREAKS AND PERIMETER CORNER JOINTS MUST BE Laterally RESTRAINED.

LOADING

TOTAL LOAD CASES: (4)

MEMB.	CHORDS	MAX. FACTORED FORCE (LBS)	FACTORED VERT. LOAD (PLF)	LC1 MAX	MAX	MAX. UNBRACED LENGTH	MEMB.	WEBS	MAX. FACTORED FORCE (LBS)	MAX
FR-TO										
E-B		-432 / 0	0.0	0.0	0.13 (4)	7.81				
A-B		0 / 32	-84.3	-84.3	0.11 (1)	10.00				
B-C		-35 / 0	-84.3	-84.3	0.52 (1)	6.25				
E-D		0 / 0	-18.2	-18.2	0.14 (4)	10.00				

DESIGN CRITERIA**SPECIFIED LOADS:**

TOP CH.	LL	=	25.6	PSF
DL	=	3.0	PSF	
BOT CH.	LL	=	0.0	PSF
DL	=	7.3	PSF	
TOTAL LOAD	=	35.9	PSF	

SPACING = 24.0 IN. C/C

THIS TRUSS IS DESIGNED FOR RESIDENTIAL OR SMALL BUILDING REQUIREMENTS OF PART 9, NBCC 2015

THIS DESIGN COMPLIES WITH:

- PART 9 OF BCBC 2018, ABC 2019
- PART 9 OF OBC 2012 (2019 AMENDMENT)
- CSA 086-14
- TPIC 2014

DESIGN ASSUMPTIONS

-OVERHANG NOT TO BE ALTERED OR CUT OFF.

(55 % OF 31.3 P.S.F. G.S.L. PLUS 8.4 P.S.F. RAIN LOAD) EQUALS 25.6 P.S.F. SPECIFIED ROOF LIVE LOAD

ALLOWABLE DEFL.(LL) = L/360 (0.20")
CALCULATED VERT. DEFL.(LL) = L/999 (0.00")
ALLOWABLE DEFL.(TL) = L/360 (0.20")
CALCULATED VERT. DEFL.(TL) = L/999 (0.04")

CSI: TC=0.52/1.00 (B-C:1), BC=0.14/1.00 (D-E:4), WB=0.00/1.00 (n/a:0), SSI=0.21/1.00 (B-C:1)

DOL LUMBER=1.00 NAIL=1.00 LS BEND=1.10 COMP=1.10 SHEAR=1.10 TENS=1.10

COMPANION LIVE LOAD FACTOR = 1.00

TRUSS PLATE MANUFACTURER IS NOT RESPONSIBLE FOR QUALITY CONTROL IN THE TRUSS MANUFACTURING PLANT.

NAIL VALUES

PLATE	GRIP(DRY)	SHEAR (PSI)	SECTION (PLI)	MAX MIN	MAX MIN	MAX MIN
MT20	650	371	1747	788	1987	1873

PLATE PLACEMENT TOL. = 0.250 inches

PLATE ROTATION TOL. = 5.0 Deg.

JSI GRIP= 0.27 (B) (INPUT = 0.90)

JSI METAL= 0.22 (B) (INPUT = 1.00)

CITY OF RICHMOND HILL
BUILDING DIVISION

09/22/2022

KOTT
RECEIVED

Per: joshua.nabua




June 29, 2021

READ ALL NOTES ON THIS PAGE AND ON THE ENGINEERING NOTE PAGE ENP-1. THE NOTE PAGE IS AN INTEGRAL PART OF THIS DRAWING AS IT CONTAINS SPECIFICATIONS AND CRITERIA USED IN THE DESIGN OF THIS COMPONENT.

JOB NAME	TRUSS NAME	QUANTITY	PLY	JOB DESC.	DRWG NO.
IM0621-169	J02	1	1	TRUSS DESC.	

Version 8.420 S Apr 29 2021 MiTek Industries, Inc. Tue Jun 29 13:09:16 2021 Page 1
ID:6C523IFijGTy 39enVU3pLzc1B6-D6xo8ryA5dJw0u7emYIDA06WphqoD99rKuFKUqz1QI1



Scale = 1:23.6

TOTAL WEIGHT = 15 lb [M]

LUMBER

N. L. G. A. RULES

CHORDS	SIZE	DRY	LUMBER	DESCR.
E - B	2x4	DRY	No.2	SPF
A - C	2x4	DRY	No.2	SPF
E - D	2x4	DRY	No.2	SPF

DRY: SEASONED LUMBER.

PLATES (table is in inches)

JT	TYPE	PLATES	W	LEN	Y	X
B	TMV+p	MT20	2.0	4.0		
E	BMV1+p	MT20	2.0	4.0		

DIMENSIONS, SUPPORTS AND LOADINGS SPECIFIED BY FABRICATOR TO BE VERIFIED BY BUILDING DESIGNER**BEARINGS**

JT	FACTORED GROSS REACTION	MAXIMUM FACTORED GROSS REACTION	INPUT BRG	REQRD BRG
	VERT	HORZ	DOWN	HORZ
E	385	0	385	0
C	124	0	124	0
D	46	0	51	0

SEE MITEK STANDARD DETAIL MSD2015-H FOR CONNECTION TO JOINT(S) C, D

UNFACTORED REACTIONS

JT	1ST LCASE	SNOW	LIVE	PERM.LIVE	WIND	DEAD	SOIL
E	269	195 / 0	0 / 0	0 / 0	0 / 0	74 / 0	0 / 0
C	84	75 / 0	0 / 0	0 / 0	0 / 0	9 / 0	0 / 0
D	37	0 / 0	0 / 0	0 / 0	0 / 0	37 / 0	0 / 0

BEARING MATERIAL TO BE SPF NO.2 OR BETTER AT JOINT(S) E, C

BRACING

TOP CHORD TO BE SHEATHED OR MAX. PURLIN SPACING = 6.25 FT.
MAX. UNBRACED BOTTOM CHORD LENGTH = 10.00 FT OR RIGID CEILING DIRECTLY APPLIED.

ALL FITCH BREAKS AND PERIMETER CORNER JOINTS MUST BE Laterally RESTRAINED.

LOADING

TOTAL LOAD CASES: (4)

MEMB.	CHORDS	MAX. FACTORED FORCE (LBS)	FACTORED VERT. LOAD (PLF)	LC1	MAX	MAX. UNBRACED LENGTH	MEMB.	WEBS	MAX. FACTORED FORCE (LBS)	MAX. UNBRACED LENGTH
FR-TO							FR-TO			
E-B		-322 / 0	0.0	0.0	0.12 (4)	7.81				
A-B		0 / 32	-84.3	-84.3	0.11 (1)	10.00				
B-C		-23 / 0	-84.3	-84.3	0.22 (1)	6.25				
E-D		0 / 0	-18.2	-18.2	0.14 (4)	10.00				

DESIGN CRITERIA**SPECIFIED LOADS:**

TOP CH.	LL	=	25.6	PSF
	DL	=	3.0	PSF
BOT CH.	LL	=	0.0	PSF
	DL	=	7.3	PSF
TOTAL LOAD	=	35.9	PSF	

SPACING = 24.0 IN. C/C

THIS TRUSS IS DESIGNED FOR RESIDENTIAL OR SMALL BUILDING REQUIREMENTS OF PART 9, NBCC 2015

THIS DESIGN COMPLIES WITH:

- PART 9 OF BCBC 2018, ABC 2019
- PART 9 OF OBC 2012 (2019 AMENDMENT)
- CSA 086-14
- TPIC 2014

DESIGN ASSUMPTIONS

-OVERHANG NOT TO BE ALTERED OR CUT OFF.

(55 % OF 31.3 P.S.F. G.S.L. PLUS 8.4 P.S.F. RAIN LOAD) EQUALS 25.6 P.S.F. SPECIFIED ROOF LIVE LOAD

ALLOWABLE DEFL.(LL) = L/360 (0.20")
CALCULATED VERT. DEFL.(LL) = L/999 (0.00")
ALLOWABLE DEFL.(TL) = L/360 (0.20")
CALCULATED VERT. DEFL.(TL) = L/999 (0.04")

CSI: TC=0.22/1.00 (B-C:1), BC=0.14/1.00 (D-E:4), WB=0.00/1.00 (n/a:0), SSI=0.13/1.00 (B-C:1)

DOL LUMBER=1.00 NAIL=1.00 LS BEND=1.10 COMP=1.10 SHEAR=1.10 TENS=1.10

COMPANION LIVE LOAD FACTOR = 1.00

TRUSS PLATE MANUFACTURER IS NOT RESPONSIBLE FOR QUALITY CONTROL IN THE TRUSS MANUFACTURING PLANT.

NAIL VALUES

PLATE	GRIP(DRY)	SHEAR	SECTION
(PSI)	(PLI)	(PLI)	(PLI)
MT20	650	371	1747
	788	1987	1873

PLATE PLACEMENT TOL. = 0.250 inches

PLATE ROTATION TOL. = 5.0 Deg.

JSI GRIP= 0.20 (B) (INPUT = 0.90)

JSI METAL= 0.16 (B) (INPUT = 1.00)

CITY OF RICHMOND HILL
BUILDING DIVISION

09/22/2022
KOTT

RECEIVED

Per: joshua.nabua



June 29, 2021

READ ALL NOTES ON THIS PAGE AND ON THE ENGINEERING NOTE PAGE ENP-1. THE NOTE PAGE IS AN INTEGRAL PART OF THIS DRAWING AS IT CONTAINS SPECIFICATIONS AND CRITERIA USED IN THE DESIGN OF THIS COMPONENT.


Version 8.420 S Apr 29 2021 MiTek Industries, Inc. Tue Jun 29 13:09:26 2021 Page 1
ID:6C5231FIIGTY 39enVU3plzc1B6-w2YaFG4RIIzVCQmZLTZaVWGwIE ZhdJdRaspFz1Qkt



**READ ALL NOTES ON THIS PAGE AND ON THE
ENGINEERING NOTE PAGE ENP-1. THE NOTE PAGE
IS AN INTEGRAL PART OF THIS DRAWING AS IT
CONTAINS SPECIFICATIONS AND CRITERIA USED
IN THE DESIGN OF THIS COMPONENT.**

JOB NAME	TRUSS NAME	QUANTITY	PLY	JOB DESC.	DRWG NO.
IM0621-169	J04	1	1	TRUSS DESC.	

Version 8.420 S Apr 29 2021 MiTek Industries, Inc. Tue Jun 29 13:09:37 2021 Page 1
ID:6C523FIjGTY_39enVU3pLzc1B6-59jY1CL94yx176gUTA8XqT6W90Zeflx9frxi6z1Qki



Scale: 1/2"=1'

TOTAL WEIGHT = 11 lb [M]

LUMBER

N. L. G. A. RULES

CHORDS	SIZE	LUMBER	DESCR.
E - B	2x4	DRY	No.2
A - C	2x4	DRY	No.2
E - D	2x4	DRY	No.2

DRY: SEASONED LUMBER.

PLATES (table is in inches)

JT	TYPE	PLATES	W	LEN	Y	X
B	TMV+p	MT20	2.0	4.0		
E	BMV1+p	MT20	2.0	4.0		

DIMENSIONS, SUPPORTS AND LOADINGS SPECIFIED BY FABRICATOR TO BE VERIFIED BY BUILDING DESIGNER**BEARINGS**

JT	FACTORED GROSS REACTION		MAXIMUM FACTORED GROSS REACTION		INPUT BRG IN-SX	REQRD BRG IN-SX
	VERT	HORZ	DOWN	HORZ		
E	341	0	341	0	5-8	1-8
C	124	0	124	0	1-8	1-8
D	17	0	18	0	1-8	1-8

SEE MITEK STANDARD DETAIL MSD2015-H FOR CONNECTION TO JOINT(S) C, D

UNFACTORED REACTIONS

JT	1ST LCASE COMBINED	MAX / MIN COMPONENT REACTIONS					
		SNOW	LIVE	PERM.LIVE	WIND	DEAD	SOIL
E	234	195 / 0	0 / 0	0 / 0	0 / 0	39 / 0	0 / 0
C	84	75 / 0	0 / 0	0 / 0	0 / 0	9 / 0	0 / 0
D	13	0 / 0	0 / 0	0 / 0	0 / 0	13 / 0	0 / 0

BEARING MATERIAL TO BE SPF NO.2 OR BETTER AT JOINT(S) E

BRACING

TOP CHORD TO BE SHEATHED OR MAX. PURLIN SPACING = 6.25 FT.
MAX. UNBRACED BOTTOM CHORD LENGTH = 10.00 FT OR RIGID CEILING DIRECTLY APPLIED.

ALL FITCH BREAKS AND PERIMETER CORNER JOINTS MUST BE Laterally RESTRAINED.

LOADING

TOTAL LOAD CASES: (5)

MEMB.	CHORDS		FACTORED		MAX. CSI (LC)	UNBRAC LENGTH	MEMB.	WEBS	
	MAX. FACTORED FORCE (LBS)	VERT. LOAD (PLF)	VERT. LOAD (PLF)	MAX. CSI (LC)				MAX. FACTORED FORCE (LBS)	MAX. CSI (LC)
FR-TO									
E-B	-322 / 0	0.0	0.0	0.01 (4)	7.81				
A-B	0 / 32	-84.3	-84.3	0.11 (1)	10.00				
B-C	-23 / 0	-84.3	-84.3	0.22 (1)	6.25				
E-D	0 / 0	-18.2	-18.2	0.02 (4)	10.00				

CANTILEVER ANALYSIS HAS BEEN CONSIDERED IN THIS DESIGN

PATTERN-LOADING CHECK APPLIED TO THIS TRUSS.

DESIGN CRITERIA**SPECIFIED LOADS:**

TOP CH.	LL	=	25.6	PSF
DL	=	3.0	PSF	
BOT CH.	LL	=	0.0	PSF
DL	=	7.3	PSF	
TOTAL LOAD	=	35.9	PSF	

SPACING = 24.0 IN. C/C

THIS TRUSS IS DESIGNED FOR RESIDENTIAL OR SMALL BUILDING REQUIREMENTS OF PART 9, NBCC 2015

THIS DESIGN COMPLIES WITH:

- PART 9 OF BCBC 2018, ABC 2019
- PART 9 OF OBC 2012 (2019 AMENDMENT)
- CSA 086-14
- TPIC 2014

DESIGN ASSUMPTIONS

- OVERHANG NOT TO BE ALTERED OR CUT OFF.

(55 % OF 31.3 P.S.F. G.S.L. PLUS 8.4 P.S.F. RAIN LOAD) EQUALS 25.6 P.S.F. SPECIFIED ROOF LIVE LOAD

ALLOWABLE DEFL.(LL) = $L/360$ (0.19")
CALCULATED VERT. DEFL.(LL) = $L/999$ (0.00")
ALLOWABLE DEFL.(TL) = $L/360$ (0.19")
CALCULATED VERT. DEFL.(TL) = $L/999$ (0.00")

CSI: TC=0.22/1.00 (B-C:1), BC=0.02/1.00 (D-E:4), WB=0.00/1.00 (n/a:0), SSI=0.13/1.00 (B-C:1)

DOL LUMBER=1.00 NAIL=1.00 LS BEND=1.10 COMP=1.10 SHEAR=1.10 TENS=1.10

COMPANION LIVE LOAD FACTOR = 1.00

TRUSS PLATE MANUFACTURER IS NOT RESPONSIBLE FOR QUALITY CONTROL IN THE TRUSS MANUFACTURING PLANT.

NAIL VALUES

PLATE	GRIP(DRY)	SHEAR (PSI)	SECTION (PLI)
MT20	650	371	1747
	788	1987	1873

PLATE PLACEMENT TOL. = 0.250 inches

PLATE ROTATION TOL. = 5.0 Deg.

JSI GRIP= 0.20 (B) (INPUT = 0.90)

JSI METAL= 0.16 (B) (INPUT = 1.00)

CITY OF RICHMOND HILL
BUILDING DIVISION

09/22/2022
KOTT

RECEIVED

Per: joshua.nabua




June 29, 2021

READ ALL NOTES ON THIS PAGE AND ON THE ENGINEERING NOTE PAGE ENP-1. THE NOTE PAGE IS AN INTEGRAL PART OF THIS DRAWING AS IT CONTAINS SPECIFICATIONS AND CRITERIA USED IN THE DESIGN OF THIS COMPONENT.

JOB NAME	TRUSS NAME	QUANTITY	PLY	JOB DESC.	DRWG NO.
IM0621-169	J05	1	1	TRUSS DESC.	

Version 8.420 S Apr 29 2021 MiTek Industries, Inc. Tue Jun 29 13:09:47 2021 Page 1
ID:6C523IFIJGTy_39enVU3pLzc1B6-o4JWfSKco9DWEftb4ZMUxxurdBRe_AqPSCGT3Xz1QKy



Scale = 1:16.8

TOTAL WEIGHT = 8 lb [M]

LUMBER

N. L. G. A. RULES

CHORDS	SIZE	LUMBER	DESCR.
E - B	2x4	DRY	No.2
A - C	2x4	DRY	No.2
E - D	2x4	DRY	No.2

DRY: SEASONED LUMBER.

PLATES (table is in inches)

JT	TYPE	PLATES	W	LEN	Y	X
B	TMV+p	MT20	2.0	4.0		
E	BMV1+p	MT20	2.0	4.0		

DIMENSIONS, SUPPORTS AND LOADINGS SPECIFIED BY FABRICATOR TO BE VERIFIED BY BUILDING DESIGNER**BEARINGS**

	FACTORED GROSS REACTION		MAXIMUM FACTORED GROSS REACTION			INPUT BRG	REQRD BRG
JT	VERT	HORZ	DOWN	HORZ	UPLIFT	IN-SX	IN-SX
E	256	0	256	0	0	5-8	1-8
C	47	0	47	0	-23	1-8	1-8
D	11	0	18	0	0	1-8	1-8

SEE MITEK STANDARD DETAIL MSD2015-H FOR CONNECTION TO JOINT(S) C, D

PROVIDE ANCHORAGE AT BEARING JOINT C FOR 150 LBS. FACTORED UPLIFT

UNFACTORED REACTIONS

JT	1ST LCASE	MAX / MIN.	COMPONENT REACTIONS	SNOW	LIVE	PERM. LIVE	WIND	DEAD	SOIL
E	176	144 / 0	0 / 0	0 / 0	0 / 0	0 / 0	0 / 0	31 / 0	0 / 0
C	32	28 / -17	0 / 0	0 / 0	0 / 0	0 / 0	0 / 0	4 / 0	0 / 0
D	9	0 / -7	0 / 0	0 / 0	0 / 0	0 / 0	0 / 0	13 / 0	0 / 0

BEARING MATERIAL TO BE SPF NO.2 OR BETTER AT JOINT(S) E, C

BRACINGTOP CHORD TO BE SHEATHED OR MAX. PURLIN SPACING = 6.25 FT.
MAX. UNBRACED BOTTOM CHORD LENGTH = 10.00 FT. OR RIGID CEILING DIRECTLY APPLIED.

ALL FITCH BREAKS AND PERIMETER CORNER JOINTS MUST BE Laterally RESTRAINED.

LOADING

TOTAL LOAD CASES: (5)

MEMB.	CHORDS	MAX. FACTORED FORCE (LBS)	FACTORED VERT. LOAD (PLF)	LC1 MAX	MAX. UNBRACED LENGTH	FR-TO	WEBS	MAX. FACTORED FORCE (LBS)	MAX. CSI (LC)
E-B	-230 / 0	0.0	0.0	0.03 (5)	7.81				
A-B	0 / 32	-84.3	-84.3	0.11 (1)	10.00				
B-C	-19 / 0	-84.3	-84.3	0.09 (1)	6.25				
E-D	0 / 0	-18.2	-18.2	0.03 (5)	10.00				

CANTILEVER ANALYSIS HAS BEEN CONSIDERED IN THIS DESIGN

PATTERN-LOADING CHECK APPLIED TO THIS TRUSS.

DESIGN CRITERIA**SPECIFIED LOADS:**

TOP CH.	LL	=	25.6	PSF
DL	=	3.0	PSF	
BOT CH.	LL	=	0.0	PSF
DL	=	7.3	PSF	
TOTAL LOAD	=	35.9	PSF	

SPACING = 24.0 IN. C/C

THIS TRUSS IS DESIGNED FOR RESIDENTIAL OR SMALL BUILDING REQUIREMENTS OF PART 9, NBCC 2015

THIS DESIGN COMPLIES WITH:

- PART 9 OF BCBC 2018, ABC 2019
- PART 9 OF OBC 2012 (2019 AMENDMENT)
- CSA 086-14
- TPIC 2014

DESIGN ASSUMPTIONS

-OVERHANG NOT TO BE ALTERED OR CUT OFF.

(55 % OF 31.3 P.S.F. G.S.L. PLUS 8.4 P.S.F. RAIN LOAD) EQUALS 25.6 P.S.F. SPECIFIED ROOF LIVE LOAD

ALLOWABLE DEFL.(LL)= L/360 (0.19")
CALCULATED VERT. DEFL.(LL)= L/999 (0.00")
ALLOWABLE DEFL.(TL)= L/360 (0.19")
CALCULATED VERT. DEFL.(TL)= L/999 (0.00")CSI: TC=0.11/1.00 (A-B:1), BC=0.03/1.00 (D-E:5),
WB=0.00/1.00 (n/a:0), SSI=0.08/1.00 (A-B:1)DOL LUMBER=1.00 NAIL=1.00 LS BEND=1.10
COMP=1.10 SHEAR=1.10 TENS=1.10

COMPANION LIVE LOAD FACTOR = 1.00

TRUSS PLATE MANUFACTURER IS NOT RESPONSIBLE FOR QUALITY CONTROL IN THE TRUSS MANUFACTURING PLANT.

NAIL VALUES

PLATE	GRIP(DRY)	SHEAR (PSI)	SECTION (PLI)
MT20	MAX MIN	MAX MIN	MAX MIN
	650 371	1747 788	1987 1873

PLATE PLACEMENT TOL. = 0.250 inches

PLATE ROTATION TOL. = 5.0 Deg.

JSI GRIP= 0.14 (B) (INPUT = 0.90)

JSI METAL= 0.12 (B) (INPUT = 1.00)

CITY OF RICHMOND HILL
BUILDING DIVISION

09/22/2022

KOTT


RECEIVED

Per: joshua.nabua



June 29, 2021

READ ALL NOTES ON THIS PAGE AND ON THE
ENGINEERING NOTE PAGE ENP-1. THE NOTE PAGE
IS AN INTEGRAL PART OF THIS DRAWING AS IT
CONTAINS SPECIFICATIONS AND CRITERIA USED
IN THE DESIGN OF THIS COMPONENT.



TOTAL WEIGHT = 8 X 17 = 137 lb

LUMBER

N. L. G. A. RULES

CHORDS	SIZE	LUMBER	DESCR.
E - B	2x4	DRY	No.2
A - C	2x4	DRY	No.2
E - D	2x4	DRY	No.2

DRY: SEASONED LUMBER.

PLATES (table is in inches)

JT	TYPE	PLATES	W	LEN	Y	X
B	TMV+p	MT20	2.0	4.0		
E	BMV1+p	MT20	2.0	4.0		

DIMENSIONS, SUPPORTS AND LOADINGS SPECIFIED BY FABRICATOR TO BE VERIFIED BY BUILDING DESIGNER**BEARINGS**

	FACTORED GROSS REACTION	MAXIMUM FACTORED GROSS REACTION	INPUT BRG	REQRD BRG
JT	VERT	HORZ	DOWN	HORZ
E	495	0	495	0
C	190	0	190	0
D	45	0	51	0

SEE MITEK STANDARD DETAIL MSD2015-H FOR CONNECTION TO JOINT(S) C, D

UNFACTORED REACTIONS

JT	1ST LCASE	SNOW	LIVE	PERM.LIVE	WIND	DEAD	SOIL
E	343	261 / 0	0 / 0	0 / 0	0 / 0	82 / 0	0 / 0
C	129	115 / 0	0 / 0	0 / 0	0 / 0	14 / 0	0 / 0
D	36	0 / 0	0 / 0	0 / 0	0 / 0	36 / 0	0 / 0

BEARING MATERIAL TO BE SPF NO.2 OR BETTER AT JOINT(S) E, C

BRACING

TOP CHORD TO BE SHEATHED OR MAX. PURLIN SPACING = 6.25 FT.
MAX. UNBRACED BOTTOM CHORD LENGTH = 10.00 FT OR RIGID CEILING DIRECTLY APPLIED.

ALL FITCH BREAKS AND PERIMETER CORNER JOINTS MUST BE Laterally RESTRAINED.

LOADING

TOTAL LOAD CASES: (4)

MEMB.	CHORDS	MAX. FACTORED FORCE (LBS)	FACTORED VERT. LOAD (PLF)	MAX. VERT. LOAD LC1	MAX. UNBRACED LENGTH	MEMB.	WEBS	MAX. FACTORED FORCE (LBS)	MAX. UNBRACED LENGTH
FR-TO						FR-TO			
E-B		-430 / 0	0.0	0.0	0.13 (4)				
A-B		0 / 26	-84.3	-84.3	0.11 (1)				
B-C		-28 / 0	-84.3	-84.3	0.52 (1)				
E-D		0 / 0	-18.2	-18.2	0.13 (4)				

DESIGN CRITERIA**SPECIFIED LOADS:**

TOP CH.	LL	=	25.6	PSF
	DL	=	3.0	PSF
BOT CH.	LL	=	0.0	PSF
	DL	=	7.3	PSF
TOTAL LOAD		=	35.9	PSF

SPACING = 24.0 IN. C/C

THIS TRUSS IS DESIGNED FOR RESIDENTIAL OR SMALL BUILDING REQUIREMENTS OF PART 9, NBCC 2015

THIS DESIGN COMPLIES WITH:

- PART 9 OF BCBC 2018, ABC 2019
- PART 9 OF OBC 2012 (2019 AMENDMENT)
- CSA 086-14
- TPIC 2014

DESIGN ASSUMPTIONS

-OVERHANG NOT TO BE ALTERED OR CUT OFF.

(55 % OF 31.3 P.S.F. G.S.L. PLUS 8.4 P.S.F. RAIN LOAD) EQUALS 25.6 P.S.F. SPECIFIED ROOF LIVE LOAD

ALLOWABLE DEFL.(LL) = L/360 (0.20")
CALCULATED VERT. DEFL.(LL) = L/999 (0.00")
ALLOWABLE DEFL.(TL) = L/360 (0.20")
CALCULATED VERT. DEFL.(TL) = L/999 (0.03")

CSI: TC=0.52/1.00 (B-C:1), BC=0.13/1.00 (D-E:4), WB=0.00/1.00 (n/a:0), SSI=0.22/1.00 (B-C:1)

DOL LUMBER=1.00 NAIL=1.00 LS BEND=1.10 COMP=1.10 SHEAR=1.10 TENS=1.10

COMPANION LIVE LOAD FACTOR = 1.00

TRUSS PLATE MANUFACTURER IS NOT RESPONSIBLE FOR QUALITY CONTROL IN THE TRUSS MANUFACTURING PLANT.

NAIL VALUES

PLATE	GRIP(DRY)	SHEAR (PSI)	SECTION (PLI)
MT20	650	371	1747

PLATE PLACEMENT TOL. = 0.250 inches

PLATE ROTATION TOL. = 5.0 Deg.

JSI GRIP= 0.24 (B) (INPUT = 0.90)

JSI METAL= 0.18 (B) (INPUT = 1.00)

**CITY OF RICHMOND HILL
BUILDING DIVISION**

09/22/2022

**KOTT
RECEIVED**


Per: joshua.nabua

June 29, 2021

READ ALL NOTES ON THIS PAGE AND ON THE ENGINEERING NOTE PAGE ENP-1. THE NOTE PAGE IS AN INTEGRAL PART OF THIS DRAWING AS IT CONTAINS SPECIFICATIONS AND CRITERIA USED IN THE DESIGN OF THIS COMPONENT.

JOB NAME	TRUSS NAME	QUANTITY	PLY	JOB DESC.	DRWG NO.
IM0621-169	J07	3	1	TRUSS DESC.	

Version 8.420 S Apr 29 2021 MiTek Industries, Inc. Tue Jun 29 13:10:08 2021 Page 1
ID:6C523IFIJGTy_39enVU3pLzc1B6-h75S3danrcsYFu_dpTEPHMGPhZ_Pg1VH_r4lpz1QkD



Scale = 1:18.9

TOTAL WEIGHT = 3 X 14 = 43 lb [M]

LUMBER

N. L. G. A. RULES

CHORDS	SIZE	LUMBER	DESCR.
E - B	2x4	DRY	No.2
A - C	2x4	DRY	No.2
E - D	2x4	DRY	No.2

DRY: SEASONED LUMBER.

PLATES (table is in inches)

JT	TYPE	PLATES	W	LEN	Y	X
B	TMV+p	MT20	2.0	4.0		
E	BMV1+p	MT20	2.0	4.0		

DIMENSIONS, SUPPORTS AND LOADINGS SPECIFIED BY FABRICATOR TO BE VERIFIED BY BUILDING DESIGNER**BEARINGS**

	FACTORED GROSS REACTION	MAXIMUM FACTORED GROSS REACTION	INPUT BRG	REQRD BRG
JT	VERT	HORZ	DOWN	HORZ
E	385	0	385	0
C	124	0	124	0
D	45	0	51	0

SEE MITEK STANDARD DETAIL MSD2015-H FOR CONNECTION TO JOINT(S) C, D

UNFACTORED REACTIONS

JT	1ST LCASE	SNOW	LIVE	PERM.LIVE	WIND	DEAD	SOIL
E	269	194 / 0	0 / 0	0 / 0	0 / 0	74 / 0	0 / 0
C	84	75 / 0	0 / 0	0 / 0	0 / 0	9 / 0	0 / 0
D	36	0 / 0	0 / 0	0 / 0	0 / 0	36 / 0	0 / 0

BEARING MATERIAL TO BE SPF NO.2 OR BETTER AT JOINT(S) E, C

BRACING

TOP CHORD TO BE SHEATHED OR MAX. PURLIN SPACING = 6.25 FT.
MAX. UNBRACED BOTTOM CHORD LENGTH = 10.00 FT OR RIGID CEILING DIRECTLY APPLIED.

ALL FITCH BREAKS AND PERIMETER CORNER JOINTS MUST BE Laterally RESTRAINED.

LOADING

TOTAL LOAD CASES: (4)

MEMB.	CHORDS	MAX. FACTORED FORCE (LBS)	FACTORED VERT. LOAD (PLF)	MAX. VERT. LOAD LC1	MAX. UNBRACED LENGTH	MEMB.	WEBS	MAX. FACTORED FORCE (LBS)	MAX. UNBRACED LENGTH
FR-TO						FR-TO			
E-B		-320 / 0	0.0	0.0	0.13 (4)	7.81			
A-B		0 / 26	-84.3	-84.3	0.11 (1)	10.00			
B-C		-18 / 0	-84.3	-84.3	0.22 (1)	6.25			
E-D		0 / 0	-18.2	-18.2	0.13 (4)	10.00			

DESIGN CRITERIA**SPECIFIED LOADS:**

TOP CH.	LL	=	25.6	PSF
DL	=	3.0	PSF	
BOT CH.	LL	=	0.0	PSF
DL	=	7.3	PSF	
TOTAL LOAD	=	35.9	PSF	

SPACING = 24.0 IN. C/C

THIS TRUSS IS DESIGNED FOR RESIDENTIAL OR SMALL BUILDING REQUIREMENTS OF PART 9, NBCC 2015

THIS DESIGN COMPLIES WITH:

- PART 9 OF BCBC 2018, ABC 2019
- PART 9 OF OBC 2012 (2019 AMENDMENT)
- CSA 086-14
- TPIC 2014

DESIGN ASSUMPTIONS

-OVERHANG NOT TO BE ALTERED OR CUT OFF.

(55 % OF 31.3 P.S.F. G.S.L. PLUS 8.4 P.S.F. RAIN LOAD) EQUALS 25.6 P.S.F. SPECIFIED ROOF LIVE LOAD

ALLOWABLE DEFL.(LL) = L/360 (0.20")
CALCULATED VERT. DEFL.(LL) = L/999 (0.00")
ALLOWABLE DEFL.(TL) = L/360 (0.20")
CALCULATED VERT. DEFL.(TL) = L/999 (0.03")

CSI: TC=0.22/1.00 (B-C:1), BC=0.13/1.00 (D-E:4), WB=0.00/1.00 (n/a:0), SSI=0.14/1.00 (B-C:1)

DOL LUMBER=1.00 NAIL=1.00 LS BEND=1.10 COMP=1.10 SHEAR=1.10 TENS=1.10

COMPANION LIVE LOAD FACTOR = 1.00

TRUSS PLATE MANUFACTURER IS NOT RESPONSIBLE FOR QUALITY CONTROL IN THE TRUSS MANUFACTURING PLANT.

NAIL VALUES

PLATE	GRIP(DRY)	SHEAR (PSI)	SECTION (PLI)	MAX MIN	MAX MIN	MAX MIN
MT20	650	371	1747	788	1987	1873

PLATE PLACEMENT TOL. = 0.250 inches

PLATE ROTATION TOL. = 5.0 Deg.

JSI GRIP= 0.18 (B) (INPUT = 0.90)

JSI METAL= 0.13 (B) (INPUT = 1.00)

CITY OF RICHMOND HILL
BUILDING DIVISION

09/22/2022

KOTT

RECEIVED

Per: joshua.nabua



June 29, 2021

READ ALL NOTES ON THIS PAGE AND ON THE ENGINEERING NOTE PAGE ENP-1. THE NOTE PAGE IS AN INTEGRAL PART OF THIS DRAWING AS IT CONTAINS SPECIFICATIONS AND CRITERIA USED IN THE DESIGN OF THIS COMPONENT.

Version 8.420 S Apr 29 2021 MiTek Industries, Inc. Tue Jun 29 13:10:17 2021 Page 1
ID:6C523IFljGTY 39enVU3pLzc1B6-ws7syihRkN?GqGAMqsuW8G8ykHe50IFqMtX37oz1Qk4




**READ ALL NOTES ON THIS PAGE AND ON THE
ENGINEERING NOTE PAGE ENP-1. THE NOTE PAGE
IS AN INTEGRAL PART OF THIS DRAWING AS IT
CONTAINS SPECIFICATIONS AND CRITERIA USED
IN THE DESIGN OF THIS COMPONENT.**

Per: joshua.nabua

JOB NAME	TRUSS NAME	QUANTITY	PLY	JOB DESC.	DRWG NO.
IM0621-169	J09	3	1	TRUSS DESC.	

Version 8.420 S Apr 29 2021 MiTek Industries, Inc. Tue Jun 29 13:10:27 2021 Page 1
ID:6C523IFIJGTy_39enVU3pLzc1B6-dnke27piNRFR1oxHQz3tYNYfuJ4HLGkIfRybSDz1Qjw



TOTAL WEIGHT = 3 X 10 = 30 lb [M]

LUMBER

N. L. G. A. RULES

CHORDS	SIZE	LUMBER
E - B	2x4 DRY	No.2
A - C	2x4 DRY	No.2
E - D	2x4 DRY	No.2

DRY: SEASONED LUMBER.

DESCR.
SPF
SPF
SPF

DIMENSIONS, SUPPORTS AND LOADINGS SPECIFIED BY FABRICATOR TO BE VERIFIED BY BUILDING DESIGNER**BEARINGS**

	FACTORED GROSS REACTION	MAXIMUM FACTORED GROSS REACTION	INPUT BRG	REQRD BRG
JT	VERT	HORZ	DOWN	HORZ
E	340	0	340	0
C	124	0	124	0
D	16	0	16	0

SEE MITEK STANDARD DETAIL MSD2015-H FOR CONNECTION TO JOINT(S) C, D

UNFACTORED REACTIONS

JT	1ST LCASE	MAX / MIN	COMPONENT REACTIONS	WIND	DEAD	SOIL
	COMBINED	SNOW	LIVE	PERM.LIVE		
E	233	194 / 0	0 / 0	0 / 0	39 / 0	0 / 0
C	84	75 / 0	0 / 0	0 / 0	9 / 0	0 / 0
D	13	0 / 0	0 / 0	0 / 0	13 / 0	0 / 0

BEARING MATERIAL TO BE SPF NO.2 OR BETTER AT JOINT(S) E

BRACING

TOP CHORD TO BE SHEATHED OR MAX. PURLIN SPACING = 6.25 FT.
MAX. UNBRACED BOTTOM CHORD LENGTH = 10.00 FT OR RIGID CEILING DIRECTLY APPLIED.

ALL FITCH BREAKS AND PERIMETER CORNER JOINTS MUST BE Laterally RESTRAINED.

LOADING

TOTAL LOAD CASES: (5)

CHORDS				WEBS			
MEMB.	MAX. FACTORED FORCE (LBS)	FACTORED VERT. LOAD (PLF)	LC1 MAX CSI (LC)	MEMB.	MAX. FACTORED FORCE (LBS)	MAX CSI (LC)	
FR-TO				FR-TO			
E-B	-320 / 0	0.0	0.0 0.01 (4)	7.81			
A-B	0 / 26	-84.3	-84.3 0.11 (1)	10.00			
B-C	-18 / 0	-84.3	-84.3 0.22 (1)	6.25			
E-D	0 / 0	-18.2	-18.2 0.02 (4)	10.00			

CANTILEVER ANALYSIS HAS BEEN CONSIDERED IN THIS DESIGN

PATTERN-LOADING CHECK APPLIED TO THIS TRUSS.

DESIGN CRITERIA**SPECIFIED LOADS:**

TOP CH.	LL = 25.6 PSF
DL = 3.0 PSF	
BOT CH.	LL = 0.0 PSF
DL = 7.3 PSF	
TOTAL LOAD	= 35.9 PSF

SPACING = 24.0 IN. C/C

THIS TRUSS IS DESIGNED FOR RESIDENTIAL OR SMALL BUILDING REQUIREMENTS OF PART 9, NBCC 2015

THIS DESIGN COMPLIES WITH:

- PART 9 OF BCBC 2018, ABC 2019
- PART 9 OF OBC 2012 (2019 AMENDMENT)
- CSA 086-14
- TPIC 2014

DESIGN ASSUMPTIONS

-OVERHANG NOT TO BE ALTERED OR CUT OFF.

(55% OF 31.3 P.S.F. G.S.L. PLUS 8.4 P.S.F. RAIN LOAD) EQUALS 25.6 P.S.F. SPECIFIED ROOF LIVE LOAD

ALLOWABLE DEFL.(LL) = L/360 (0.19")
CALCULATED VERT. DEFL.(LL) = L/999 (0.00")
ALLOWABLE DEFL.(TL) = L/360 (0.19")
CALCULATED VERT. DEFL.(TL) = L/999 (0.00")

CSI: TC=0.22/1.00 (B-C:1), BC=0.02/1.00 (D-E:4), WB=0.00/1.00 (n/a:0), SSI=0.14/1.00 (B-C:1)

DOL LUMBER=1.00 NAIL=1.00 LS BEND=1.10 COMP=1.10 SHEAR=1.10 TENS=1.10

COMPANION LIVE LOAD FACTOR = 1.00

TRUSS PLATE MANUFACTURER IS NOT RESPONSIBLE FOR QUALITY CONTROL IN THE TRUSS MANUFACTURING PLANT.

NAIL VALUES

PLATE	GRIP(DRY)	SHEAR (PSI)	SECTION (PLI)
MT20	650	371	1747
	788	1987	1873

PLATE PLACEMENT TOL. = 0.250 inches

PLATE ROTATION TOL. = 5.0 Deg.

JSI GRIP= 0.18 (B) (INPUT = 0.90)

JSI METAL= 0.13 (B) (INPUT = 1.00)

CITY OF RICHMOND HILL
BUILDING DIVISION

09/22/2022

KOTT
RECEIVED


Per: joshua.nabua



June 29, 2021


READ ALL NOTES ON THIS PAGE AND ON THE ENGINEERING NOTE PAGE ENP-1. THE NOTE PAGE IS AN INTEGRAL PART OF THIS DRAWING AS IT CONTAINS SPECIFICATIONS AND CRITERIA USED IN THE DESIGN OF THIS COMPONENT.

Version 8.420 S Apr 29 2021 MiTek Industries, Inc. Tue Jun 29 13:10:34 2021 Page 1
ID:6C5231FIIGTY 39enVU3plzc1B6-w7fHWWu5kb8rMtzdKxhWKRlq8TvyURTKG09SCJz1Qjg




TOTAL WEIGHT = $3 \times 7 = 22 \text{ lb}$

Per: joshua.nabua



**READ ALL NOTES ON THIS PAGE AND ON THE
ENGINEERING NOTE PAGE ENP-1. THE NOTE PAGE
IS AN INTEGRAL PART OF THIS DRAWING AS IT
CONTAINS SPECIFICATIONS AND CRITERIA USED
IN THE DESIGN OF THIS COMPONENT.**



TOTAL WEIGHT = 2 X 12 = 25 lb [M]

LUMBER

N. L. G. A. RULES

CHORDS	SIZE	DRY	LUMBER	DESCR.
E - B	2x8	DRY	No.2	SPF
A - C	2x4	DRY	No.2	SPF
E - D	2x4	DRY	No.2	SPF

DRY: SEASONED LUMBER.

PLATES (table is in inches)

JT	TYPE	PLATES	W	LEN	Y	X
B	TMV+p	MT20	2.0	4.0		
E	BMV1+p	MT20	2.0	4.0		

DIMENSIONS, SUPPORTS AND LOADINGS SPECIFIED BY FABRICATOR TO BE VERIFIED BY BUILDING DESIGNER**BEARINGS**

JT	FACTORED GROSS REACTION		MAXIMUM FACTORED GROSS REACTION		INPUT BRG IN-SX	REQRD BRG IN-SX
	VERT	HORZ	DOWN	HORZ		
E	335	0	335	0	4-8	1-12
C	126	0	126	0	1-8	1-8
D	28	0	31	0	1-8	1-8

SEE MITEK STANDARD DETAIL MSD2015-H FOR CONNECTION TO JOINT(S) C, D

UNFACTORED REACTIONS

JT	1ST LCASE COMBINED	MAX./MIN. COMPONENT REACTIONS					SOIL
		SNOW	LIVE	PERM.LIVE	WIND	DEAD	
E	233	176 / 0	0 / 0	0 / 0	0 / 0	57 / 0	0 / 0
C	86	77 / 0	0 / 0	0 / 0	0 / 0	9 / 0	0 / 0
D	22	0 / 0	0 / 0	0 / 0	0 / 0	22 / 0	0 / 0

BEARING MATERIAL TO BE SPF NO.2 OR BETTER AT JOINT(S) E

BRACING

TOP CHORD TO BE SHEATHED OR MAX. PURLIN SPACING = 6.25 FT.
MAX. UNBRACED BOTTOM CHORD LENGTH = 10.00 FT OR RIGID CEILING DIRECTLY APPLIED.

ALL FITCH BREAKS AND PERIMETER CORNER JOINTS MUST BE Laterally RESTRAINED.

LOADING

TOTAL LOAD CASES: (7)

MEMB.	CHORDS		FACTORED		MAX. CSI (LC)	UNBRAC LENGTH	FR-TO	MEMB.	WEBS	
	MAX. FACTORED FORCE (LBS)	VERT. LOAD (PLF)	VERT. LOAD LC1 (PLF)	MAX. CSI (LC)					MAX. FACTORED FORCE (LBS)	MAX. CSI (LC)
E-B	-290 / 0	0.0	0.0	0.03 (4)	7.81					
A-B	0 / 18	-84.3	-84.3	0.06 (7)	10.00					
B-F	-19 / 0	-84.3	-84.3	0.23 (1)	6.25					
F-C	-19 / 0	-84.3	-84.3	0.23 (1)	6.25					
E-D	0 / 0	-18.2	-18.2	0.08 (4)	10.00					

CANTILEVER ANALYSIS HAS BEEN CONSIDERED IN THIS DESIGN

PATTERN-LOADING CHECK APPLIED TO THIS TRUSS.

DESIGN CRITERIA**SPECIFIED LOADS:**

TOP CH.	LL	=	25.6	PSF
	DL	=	3.0	PSF
BOT CH.	LL	=	0.0	PSF
	DL	=	7.3	PSF
TOTAL LOAD	=	35.9	PSF	

SPACING = 24.0 IN. C/C

THIS TRUSS IS DESIGNED FOR RESIDENTIAL OR SMALL BUILDING REQUIREMENTS OF PART 9, NBCC 2015

THIS DESIGN COMPLIES WITH:

- PART 9 OF BCBC 2018, ABC 2019
- PART 9 OF OBC 2012 (2019 AMENDMENT)
- CSA 086-14
- TPIC 2014

DESIGN ASSUMPTIONS

-OVERHANG NOT TO BE ALTERED OR CUT OFF.

(55% OF 31.3 P.S.F. G.S.L. PLUS 8.4 P.S.F. RAIN LOAD) EQUALS 25.6 P.S.F. SPECIFIED ROOF LIVE LOAD

ALLOWABLE DEFL.(LL) = $L/360$ (0.19")
CALCULATED VERT. DEFL.(LL) = $L/999$ (0.00")
ALLOWABLE DEFL.(TL) = $L/360$ (0.19")
CALCULATED VERT. DEFL.(TL) = $L/999$ (0.01")

CSI: TC=0.23/1.00 (B-C:1), BC=0.08/1.00 (D-E:4), WB=0.00/1.00 (n/a:0), SSI=0.15/1.00 (B-C:1)

DOL LUMBER=1.00 NAIL=1.00 LS BEND=1.10 COMP=1.10 SHEAR=1.10 TENS=1.10

COMPANION LIVE LOAD FACTOR = 1.00

AUTOSOLVE RIGHT HEEL ONLY

TRUSS PLATE MANUFACTURER IS NOT RESPONSIBLE FOR QUALITY CONTROL IN THE TRUSS MANUFACTURING PLANT.

NAIL VALUES

PLATE	GRIP(DRY)	SHEAR	SECTION
(PSI)	(PLI)	(PLI)	(PLI)
MAX	MIN	MAX	MIN
MT20	650	371	1747
		788	1987

PLATE PLACEMENT TOL. = 0.250 inches

PLATE ROTATION TOL. = 5.0 Deg.

JSI GRIP=0.16 (B) (INPUT = 0.90)

JSI METAL=0.12 (B) (INPUT = 1.00)

OFFICE OF RICHMOND HILL
BUILDING DIVISION

09/22/2022
KOTT


RECEIVED

Per: joshua.nabua



June 29, 2021

READ ALL NOTES ON THIS PAGE AND ON THE ENGINEERING NOTE PAGE ENP-1. THE NOTE PAGE IS AN INTEGRAL PART OF THIS DRAWING AS IT CONTAINS SPECIFICATIONS AND CRITERIA USED IN THE DESIGN OF THIS COMPONENT.



TOTAL WEIGHT = 2 X 10 = 20 lb [M]

LUMBER

N. L. G. A. RULES

CHORDS	SIZE	DRY	LUMBER	DESCR.
E - B	2x8	DRY	No.2	SPF
A - C	2x4	DRY	No.2	SPF
E - D	2x4	DRY	No.2	SPF

DRY: SEASONED LUMBER.

PLATES (table is in inches)

JT	TYPE	PLATES	W	LEN	Y	X
B	TMV+p	MT20	2.0	4.0		
E	BMV1+p	MT20	2.0	4.0		

DIMENSIONS, SUPPORTS AND LOADINGS SPECIFIED BY FABRICATOR TO BE VERIFIED BY BUILDING DESIGNER**BEARINGS**

JT	FACTORED GROSS REACTION		MAXIMUM FACTORED GROSS REACTION		INPUT BRG IN-SX	REQRD BRG IN-SX
	VERT	HORZ	DOWN	HORZ		
E	225	0	225	0	4-8	1-12
C	61	0	61	0	1-8	1-8
D	28	0	31	0	1-8	1-8

SEE MITEK STANDARD DETAIL MSD2015-H FOR CONNECTION TO JOINT(S) C, D

UNFACTORED REACTIONS

JT	1ST LCASE COMBINED		MAX./MIN. COMPONENT REACTIONS			
	SNOW	LIVE	PERM.LIVE	WIND	DEAD	SOIL
E	158	109 / 0	0 / 0	0 / 0	49 / 0	0 / 0
C	41	37 / 0	0 / 0	0 / 0	4 / 0	0 / 0
D	22	0 / 0	0 / 0	0 / 0	22 / 0	0 / 0

BEARING MATERIAL TO BE SPF NO.2 OR BETTER AT JOINT(S) E, C

BRACING

TOP CHORD TO BE SHEATHED OR MAX. PURLIN SPACING = 6.25 FT.
MAX. UNBRACED BOTTOM CHORD LENGTH = 10.00 FT OR RIGID CEILING DIRECTLY APPLIED.

ALL FITCH BREAKS AND PERIMETER CORNER JOINTS MUST BE Laterally RESTRAINED.

LOADING

TOTAL LOAD CASES: (11)

CHORDS				WEBS			
MEMB.	MAX. FACTORED FORCE (LBS)	FACTORED VERT. LOAD (PLF)	FACTORED HORIZ. LOAD (LC1)	MEMB.	MAX. FACTORED FORCE (LBS)	FACTORED VERT. LOAD (PLF)	FACTORED HORIZ. LOAD (LC1)
FR-TO				FR-TO			
E-B	-180 / 0	0.0	0.0 0.03 (4)	7.81			
A-B	0 / 18	-84.3	-84.3 0.06 (11)	10.00			
B-F	-10 / 0	-84.3	-84.3 0.05 (1)	6.25			
F-C	-10 / 0	-84.3	-84.3 0.05 (1)	6.25			
E-D	0 / 0	-18.2	-18.2 0.08 (4)	10.00			

CANTILEVER ANALYSIS HAS BEEN CONSIDERED IN THIS DESIGN

PATTERN-LOADING CHECK APPLIED TO THIS TRUSS.

DESIGN CRITERIA**SPECIFIED LOADS:**

TOP CH.	LL	=	25.6	PSF
	DL	=	3.0	PSF
BOT CH.	LL	=	0.0	PSF
	DL	=	7.3	PSF
TOTAL LOAD	=	35.9	PSF	

SPACING = 24.0 IN. C/C

THIS TRUSS IS DESIGNED FOR RESIDENTIAL OR SMALL BUILDING REQUIREMENTS OF PART 9, NBCC 2015

THIS DESIGN COMPLIES WITH:

- PART 9 OF BCBC 2018, ABC 2019
- PART 9 OF OBC 2012 (2019 AMENDMENT)
- CSA 086-14
- TPIC 2014

DESIGN ASSUMPTIONS

-OVERHANG NOT TO BE ALTERED OR CUT OFF.

(55 % OF 31.3 P.S.F. G.S.L. PLUS 8.4 P.S.F. RAIN LOAD) EQUALS 25.6 P.S.F. SPECIFIED ROOF LIVE LOAD

ALLOWABLE DEFL.(LL) = L/360 (0.19")
CALCULATED VERT. DEFL.(LL) = L/999 (0.00")
ALLOWABLE DEFL.(TL) = L/360 (0.19")
CALCULATED VERT. DEFL.(TL) = L/999 (0.01")

CSI: TC=0.06/1.00 (A-B:11), BC=0.08/1.00 (D-E:4)
WB=0.00/1.00 (n/a:0), SSI=0.07/1.00 (B-C:1)

DOL LUMBER=1.00 NAIL=1.00 LS BEND=1.10
COMP=1.10 SHEAR=1.10 TENS=1.10

COMPANION LIVE LOAD FACTOR = 1.00

AUTOSOLVE RIGHT HEEL ONLY

TRUSS PLATE MANUFACTURER IS NOT RESPONSIBLE FOR QUALITY CONTROL IN THE TRUSS MANUFACTURING PLANT.

NAIL VALUES

PLATE	GRIP(DRY)	SHEAR	SECTION
(PSI)	(PLI)	(PLI)	(PLI)
MAX	MIN	MAX	MIN
MT20	650	371	1747
		788	1987

PLATE PLACEMENT TOL. = 0.250 inches

PLATE ROTATION TOL. = 5.0 Deg.

JSI GRIP = 0.10 (B) (INPUT = 0.90)

JSI METAL = 0.07 (B) (INPUT = 1.00)

OFFICE OF RICHMOND HILL
BUILDING DIVISION

09/22/2022
KOTT

RECEIVED

Per: joshua.nabua




June 29, 2021

READ ALL NOTES ON THIS PAGE AND ON THE ENGINEERING NOTE PAGE ENP-1. THE NOTE PAGE IS AN INTEGRAL PART OF THIS DRAWING AS IT CONTAINS SPECIFICATIONS AND CRITERIA USED IN THE DESIGN OF THIS COMPONENT.

JOB NAME	TRUSS NAME	QUANTITY	PLY	JOB DESC.	DRWG NO.
IM0621-169	J13	2	1	TRUSS DESC.	

Version 8.420 S Apr 29 2021 MiTek Industries, Inc. Tue Jun 29 13:11:02 2021 Page 1
ID:6C523IFIJGTy 39enVU3pLzc1B6-6WLT05E8CftjB6?zpC4TIVheQ1Q25OSiNxxBhz1QjN



Scale = 1:12.8

TOTAL WEIGHT = 2 X 8 = 15 lb [M]

LUMBER

N. L. G. A. RULES

CHORDS	SIZE	DRY	LUMBER	DESCR.
E - B	2x8	DRY	No.2	SPF
A - C	2x4	DRY	No.2	SPF
E - D	2x4	DRY	No.2	SPF

DRY: SEASONED LUMBER.

PLATES (table is in inches)

JT	TYPE	PLATES	W	LEN	Y	X
B	TMV+p	MT20	2.0	4.0		
E	BMV1+p	MT20	2.0	4.0		

DIMENSIONS, SUPPORTS AND LOADINGS SPECIFIED BY FABRICATOR TO BE VERIFIED BY BUILDING DESIGNER**BEARINGS**

JT	FACTORED GROSS REACTION		MAXIMUM FACTORED GROSS REACTION		INPUT BRG IN-SX	REQRD BRG IN-SX
	VERT	HORZ	DOWN	HORZ		
E	202	0	202	0	4-8	1-12
C	61	0	61	0	1-8	1-8
D	14	0	16	0	1-8	1-8

SEE MITEK STANDARD DETAIL MSD2015-H FOR CONNECTION TO JOINT(S) C, D

UNFACTORED REACTIONS

JT	1ST LCASE COMBINED		MAX /MIN SNOW		LIVE		PERM.LIVE		WIND	DEAD	SOIL
	VERT	HORZ	DOWN	HORZ	DOWN	HORZ	DOWN	HORZ			
E	140	109 / 0	0 / 0	0 / 0	0 / 0	0 / 0	0 / 0	0 / 0	31 / 0	0 / 0	0 / 0
C	41	37 / 0	0 / 0	0 / 0	0 / 0	0 / 0	0 / 0	0 / 0	4 / 0	0 / 0	0 / 0
D	11	0 / 0	0 / 0	0 / 0	0 / 0	0 / 0	0 / 0	0 / 0	11 / 0	0 / 0	0 / 0

BEARING MATERIAL TO BE SPF NO.2 OR BETTER AT JOINT(S) E, C

BRACING

TOP CHORD TO BE SHEATHED OR MAX. PURLIN SPACING = 10.00 FT.
MAX. UNBRACED BOTTOM CHORD LENGTH = 10.00 FT OR RIGID CEILING DIRECTLY APPLIED.

ALL FITCH BREAKS AND PERIMETER CORNER JOINTS MUST BE Laterally RESTRAINED.

LOADING

TOTAL LOAD CASES: (5)

CHORDS				WEBS				
MEMB.	MAX. FACTORED FORCE (LBS)	FACTORED VERT. LOAD (PLF)	LOAD LC1	MAX CSI (LC)	MAX. UNBRAC	MEMB.	MAX. FACTORED FORCE (LBS)	MAX CSI (LC)
FR-TO		FROM	TO		LENGTH	FR-TO		
E-B	-180 / 0	0.0	0.0	0.01 (4)	7.81			
A-B	0 / 18	-84.3	-84.3	0.05 (1)	10.00			
B-C	-9 / 0	-84.3	-84.3	0.05 (1)	10.00			
E-D	0 / 0	-18.2	-18.2	0.02 (4)	10.00			

CANTILEVER ANALYSIS HAS BEEN CONSIDERED IN THIS DESIGN

PATTERN-LOADING CHECK APPLIED TO THIS TRUSS.

DESIGN CRITERIA**SPECIFIED LOADS:**

TOP CH.	LL	=	25.6	PSF
DL	=	3.0	PSF	
BOT CH.	LL	=	0.0	PSF
DL	=	7.3	PSF	
TOTAL LOAD	=	35.9	PSF	

SPACING = 24.0 IN. C/C

THIS TRUSS IS DESIGNED FOR RESIDENTIAL OR SMALL BUILDING REQUIREMENTS OF PART 9, NBCC 2015

THIS DESIGN COMPLIES WITH:

- PART 9 OF BCBC 2018, ABC 2019
- PART 9 OF OBC 2012 (2019 AMENDMENT)
- CSA 086-14
- TPIC 2014

DESIGN ASSUMPTIONS

-OVERHANG NOT TO BE ALTERED OR CUT OFF.

(55 % OF 31.3 P.S.F. G.S.L. PLUS 8.4 P.S.F. RAIN LOAD) EQUALS 25.6 P.S.F. SPECIFIED ROOF LIVE LOAD

ALLOWABLE DEFL.(LL) = L/360 (0.19")
CALCULATED VERT. DEFL.(LL) = L/999 (0.00")
ALLOWABLE DEFL.(TL) = L/360 (0.19")
CALCULATED VERT. DEFL.(TL) = L/999 (0.00")

CSI: TC=0.05/1.00 (A-B:1), BC=0.02/1.00 (D-E:4), WB=0.00/1.00 (n/a:0), SSI=0.07/1.00 (B-C:1)

DOL LUMBER=1.00 NAIL=1.00 LS BEND=1.10 COMP=1.10 SHEAR=1.10 TENS=1.10

COMPANION LIVE LOAD FACTOR = 1.00

AUTOSOLVE RIGHT HEEL ONLY

TRUSS PLATE MANUFACTURER IS NOT RESPONSIBLE FOR QUALITY CONTROL IN THE TRUSS MANUFACTURING PLANT.

NAIL VALUES

PLATE	GRIP(DRY)	SHEAR	SECTION
(PSI)	(PLI)	(PLI)	(PLI)
MAX	MIN	MAX	MIN
MT20	650	371	1747
		788	1987

PLATE PLACEMENT TOL. = 0.250 inches

PLATE ROTATION TOL. = 5.0 Deg.

JSI GRIP = 0.10 (B) (INPUT = 0.90)

JSI METAL = 0.07 (B) (INPUT = 1.00)

OFFICE OF RICHMOND HILL
BUILDING DIVISION

09/22/2022

KOTT


RECEIVED

Per: joshua.nabua



June 29, 2021

READ ALL NOTES ON THIS PAGE AND ON THE ENGINEERING NOTE PAGE ENP-1. THE NOTE PAGE IS AN INTEGRAL PART OF THIS DRAWING AS IT CONTAINS SPECIFICATIONS AND CRITERIA USED IN THE DESIGN OF THIS COMPONENT.



LUMBER

N. L. G. A. RULES

CHORDS	SIZE	LUMBER	DESCR.
A - D	2x4	DRY	No.2
D - F	2x4	DRY	No.2
F - I	2x4	DRY	No.2
P - B	2x4	DRY	No.2
J - H	2x4	DRY	No.2
P - M	2x4	DRY	No.2
M - J	2x4	DRY	No.2
ALL WEBS EXCEPT	2x3	DRY	No.2

DRY: SEASONED LUMBER.

PLATES (table is in inches)

JT	TYPE	PLATES	W	LEN	Y	X
B	TMVW-t	MT20	4.0	6.0	1.75	3.00
C	TMVW-t	MT20	3.0	4.0	1.50	1.50
D	TTWW+m	MT20	5.0	5.0	2.50	1.50
E	TMW+w	MT20	2.0	4.0		
F	TTWW+m	MT20	5.0	5.0	2.50	1.50
G	TMVW-t	MT20	3.0	4.0	1.50	1.50
H	TMVW-t	MT20	4.0	6.0	1.75	3.00
J	BMV1+p	MT20	2.0	4.0		
K	BMVW-t	MT20	4.0	5.0	2.00	1.50
L	BMVW-t	MT20	3.0	4.0		
M	BSWWW-l	MT20	5.0	6.0	3.00	3.00
N	BMVW-t	MT20	3.0	4.0		
O	BMVW-t	MT20	4.0	5.0	2.00	1.50
P	BMV1+p	MT20	2.0	4.0		

DIMENSIONS, SUPPORTS AND LOADINGS SPECIFIED BY FABRICATOR TO BE VERIFIED BY BUILDING DESIGNER

BEARINGS

JT	FACTORED GROSS REACTION		MAXIMUM FACTORED GROSS REACTION		INPUT BRG IN-SX	REQRD BRG IN-SX
	VERT	HORZ	DOWN	HORZ		
P	1704	0	1704	0	5-8	2-1
J	1704	0	1704	0	5-8	2-1

UNFACTORED REACTIONS

JT	1ST LCASE COMBINED		MAX/MIN. COMPONENT REACTIONS		WIND	DEAD	SOIL
	SNOW	LIVE	PERM. LIVE	WIND			
P	1191	863 / 0	0 / 0	0 / 0	0 / 0	328 / 0	0 / 0
J	1191	863 / 0	0 / 0	0 / 0	0 / 0	328 / 0	0 / 0

BEARING MATERIAL TO BE SPF NO.2 OR BETTER AT JOINT(S) P, J

BRACING

TOP CHORD TO BE SHEATHED OR MAX. PURLIN SPACING = 4.62 FT.
MAX. UNBRACED BOTTOM CHORD LENGTH = 10.00 FT OR RIGID CEILING DIRECTLY APPLIED.

ALL FITCH BREAKS AND PERIMETER CORNER JOINTS MUST BE Laterally RESTRAINED.

LOADING

TOTAL LOAD CASES: (4)

CHORDS					WEBS				
MEMB.	FACTORED FORCE (LBS)	FACTORED VERT. LOAD (PLF)	LC1	MAX CSI (LC)	MAX. UNBRACED LENGTH	MEMB.	MAX. FACTORED FORCE (LBS)	MAX CSI (LC)	
FR-TO		FROM	TO			FR-TO			
A-B	0 / 32	-84.3	-84.3	0.11 (1)	10.00	O-C	-240 / 17	0.08 (1)	
B-C	-1863 / 0	-84.3	-84.3	0.32 (1)	4.62	C-N	-245 / 0	0.20 (1)	
C-D	-1701 / 0	-84.3	-84.3	0.31 (1)	4.80	N-D	0 / 272	0.06 (1)	
D-E	-1622 / 0	-84.3	-84.3	0.36 (1)	4.81	D-M	0 / 395	0.09 (1)	
E-F	-1622 / 0	-84.3	-84.3	0.36 (1)	4.81	M-E	-566 / 0	0.71 (1)	
F-G	-1701 / 0	-84.3	-84.3	0.31 (1)	4.80	M-F	0 / 395	0.09 (1)	
G-H	-1863 / 0	-84.3	-84.3	0.32 (1)	4.62	L-F	0 / 272	0.06 (1)	
H-I	0 / 32	-84.3	-84.3	0.11 (1)	10.00	L-G	-245 / 0	0.20 (1)	
P-B	-1664 / 0	0.0	0.0	0.17 (1)	6.43	K-G	-240 / 17	0.08 (1)	
J-H	-1664 / 0	0.0	0.0	0.17 (1)	6.43	B-O	0 / 1607	0.36 (1)	
						K-H	0 / 1607	0.36 (1)	
P-O	0 / 0	-18.2	-18.2	0.10 (4)	10.00				
O-N	0 / 1572	-18.2	-18.2	0.32 (1)	10.00				
N-M	0 / 1394	-18.2	-18.2	0.29 (1)	10.00				
M-L	0 / 1394	-18.2	-18.2	0.29 (1)	10.00				
L-K	0 / 1572	-18.2	-18.2	0.32 (1)	10.00				
K-J	0 / 0	-18.2	-18.2	0.10 (4)	10.00				

DESIGN CRITERIA

SPECIFIED LOADS:

TOP CH. LL = 25.6 PSF
DL = 3.0 PSF

BOT CH. LL = 0.0 PSF
DL = 7.3 PSF

TOTAL LOAD = 35.9 PSF

SPACING = 24.0 IN. C/C

LOADING IN FLAT SECTION BASED ON A SLOPE OF 8.00/12

THIS TRUSS IS DESIGNED FOR RESIDENTIAL OR SMALL BUILDING REQUIREMENTS OF PART 9, NBCC 2015

THIS DESIGN COMPLIES WITH:

- PART 9 OF CBC 2018, ABC 2019
- PART 9 OF OBC 2012 (2019 AMENDMENT)
- CSA 086-14
- TPIC 2014

(55 % OF 31.3 P.S.F. G.S.L. PLUS 8.4 P.S.F. RAIN LOAD) EQUALS 25.6 P.S.F. SPECIFIED ROOF LIVE LOAD

ALLOWABLE DEFL.(LL)= L/360 (1.03")
CALCULATED VERT. DEFL.(LL)= L/999 (0.07")
ALLOWABLE DEFL.(TL)= L/360 (1.03")
CALCULATED VERT. DEFL.(TL)= L/999 (0.14")

CSI: TC=0.36/1.00 (E-F:1), BC=0.32/1.00 (N-O:1),
WB=0.71/1.00 (E-M:1), SSI=0.22/1.00 (E-F:1)

DOL LUMBER=1.00 NAIL=1.00 LS BEND=1.10
COMP=1.10 SHEAR=1.10 TENS=1.10

COMPANION LIVE LOAD FACTOR = 1.00

TRUSS PLATE MANUFACTURER IS NOT RESPONSIBLE FOR QUALITY CONTROL IN THE TRUSS MANUFACTURING PLANT.

NAIL VALUES

PLATE	GRIP(DRY)	SHEAR (PSI)	SECTION (PLI)
MT20	650	371	1747

PLATE PLACEMENT TOL. = 0.250 inches

PLATE ROTATION TOL. = 5.0 Deg.

JSI GRIP= 0.88 (K) (INPUT = 0.90)

JSI METAL= 0.49 (B) (INPUT = 1.00)

**CITY OF RICHMOND HILL
BUILDING DIVISION**

09/22/2022

RECEIVED

Per: joshua.nabua




June 29, 2021

READ ALL NOTES ON THIS PAGE AND ON THE ENGINEERING NOTE PAGE ENP-1. THE NOTE PAGE IS AN INTEGRAL PART OF THIS DRAWING AS IT CONTAINS SPECIFICATIONS AND CRITERIA USED IN THE DESIGN OF THIS COMPONENT.

JOB NAME	TRUSS NAME	QUANTITY	PLY	JOB DESC.	DRWG NO.
IM0621-169	T03	1	1	TRUSS DESC.	

Version 8.420 S Apr 29 2021 MiTek Industries, Inc. Tue Jun 29 13:11:33 2021 Page 1
ID:6C523IFIJGTy_39enVU3pLzc1B6-iTjbuhc6qjZUxy_zHqFLDHHpQwWKpuRQix4mOz1Qiu



TOTAL WEIGHT = 128 lb
[M][F]

LUMBER

N. L. G. A. RULES

CHORDS SIZE

A - D 2x4 DRY No.2

D - F 2x4 DRY No.2

F - I 2x4 DRY No.2

N - B 2x4 DRY No.2

J - H 2x4 DRY No.2

N - L 2x4 DRY No.2

L - J 2x4 DRY No.2

ALL WEBS 2x3 DRY No.2

EXCEPT

DRY: SEASONED LUMBER.

PLATES (table is in inches)

JT TYPE PLATES

B TMV+p MT20 2.0 4.0

C TMWW-t MT20 4.0 5.0 1.75 2.00

D TTWW+m MT20 5.0 6.0 2.50 1.50

E TMW+w MT20 2.0 4.0

F TTWW+m MT20 5.0 6.0 2.50 1.50

G TMWW-t MT20 4.0 5.0 1.75 2.00

H TMV+p MT20 2.0 4.0

J BMVW1-t MT20 4.0 5.0 1.75 2.00

K BMWW-t MT20 3.0 4.0

L BSWWW-t MT20 5.0 6.0 3.00 3.00

M BMWW-t MT20 3.0 4.0

N BMVW1-t MT20 4.0 5.0 1.75 2.00

DIMENSIONS, SUPPORTS AND LOADINGS SPECIFIED BY FABRICATOR TO BE VERIFIED BY BUILDING DESIGNER**BEARINGS**

	FACTORED GROSS REACTION	MAXIMUM FACTORED GROSS REACTION	INPUT BRG	REQRD BRG
JT	VERT	HORZ	DOWN	UP
N	1704	0	1704	0
J	1704	0	1704	0

UNFACTORED REACTIONS

1ST LCASE	MAX/MIN. COMPONENT REACTIONS						
JT	COMBINED	SNOW	LIVE	PERM. LIVE	WIND	DEAD	SOIL
N	1191	863 / 0	0 / 0	0 / 0	0 / 0	328 / 0	0 / 0
J	1191	863 / 0	0 / 0	0 / 0	0 / 0	328 / 0	0 / 0

BEARING MATERIAL TO BE SPF NO.2 OR BETTER AT JOINT(S) N, J

BRACING

TOP CHORD TO BE SHEATHED OR MAX. PURLIN SPACING = 3.87 FT.
MAX. UNBRACED BOTTOM CHORD LENGTH = 10.00 FT OR RIGID CEILING DIRECTLY APPLIED.

ALL FITCH BREAKS AND PERIMETER CORNER JOINTS MUST BE Laterally RESTRAINED.

LOADING

TOTAL LOAD CASES: (4)

CHORDS				WEBS			
MEMB.	MAX. FACTORED FORCE (LBS)	FACTORED VERT. LOAD (PLF)	MAX. FACTORED HORIZ. LOAD (LC)	MEMB.	MAX. FACTORED FORCE (LBS)	MAX. FACTORED HORIZ. LOAD (LC)	
FR-TO		FROM	TO	FR-TO		FROM	TO
A-B	0 / 32	-84.3	-84.3 0.11 (1)	10.00	C-M	-9 / 57	0.02 (4)
B-C	0 / 20	-84.3	-84.3 0.20 (1)	10.00	M-D	0 / 181	0.06 (4)
C-D	-1808 / 0	-84.3	-84.3 0.20 (1)	4.81	D-L	0 / 675	0.15 (1)
D-E	-2000 / 0	-84.3	-84.3 0.72 (1)	3.87	L-E	-778 / 0	0.59 (1)
E-F	-2000 / 0	-84.3	-84.3 0.72 (1)	3.87	L-F	0 / 675	0.15 (1)
F-G	-1808 / 0	-84.3	-84.3 0.20 (1)	4.81	K-F	0 / 181	0.06 (4)
G-H	0 / 20	-84.3	-84.3 0.20 (1)	10.00	K-G	-9 / 57	0.02 (4)
H-I	0 / 32	-84.3	-84.3 0.11 (1)	10.00	N-C	-2045 / 0	1.00 (1)
N-B	-247 / 0	0.0	0.0 0.03 (1)	7.81	G-J	-2045 / 0	1.00 (1)
J-H	-247 / 0	0.0	0.0 0.03 (1)	7.81			
N-M	0 / 1492	-18.2	-18.2 0.42 (1)	10.00			
M-L	0 / 1488	-18.2	-18.2 0.43 (4)	10.00			
L-K	0 / 1488	-18.2	-18.2 0.43 (4)	10.00			
K-J	0 / 1492	-18.2	-18.2 0.42 (1)	10.00			

DESIGN CRITERIA**SPECIFIED LOADS:**

TOP CH.	LL	=	25.6	PSF
	DL	=	3.0	PSF
BOT CH.	LL	=	0.0	PSF
	DL	=	7.3	PSF
TOTAL LOAD	=	35.9	PSF	

SPACING = 24.0 IN. C/C

LOADING IN FLAT SECTION BASED ON A SLOPE OF 8.00/12

THIS TRUSS IS DESIGNED FOR RESIDENTIAL OR SMALL BUILDING REQUIREMENTS OF PART 9, NBCC 2015

THIS DESIGN COMPLIES WITH:

- PART 9 OF BCBC 2018, ABC 2019
- PART 9 OF OBC 2012 (2019 AMENDMENT)
- CSA 086-14
- TPIC 2014

(55 % OF 31.3 P.S.F. G.S.L. PLUS 8.4 P.S.F. RAIN LOAD) EQUALS 25.6 P.S.F. SPECIFIED ROOF LIVE LOAD

ALLOWABLE DEFL.(LL)= L/360 (1.03")
CALCULATED VERT. DEFL.(LL) = L/999 (0.09")
ALLOWABLE DEFL.(TL)= L/360 (1.03")
CALCULATED VERT. DEFL.(TL) = L/999 (0.20")

CSI: TC=0.72/1.00 (E-F:1), BC=0.43/1.00 (L-M:4),
WB=1.00/1.00 (C-N:1), SSI=0.31/1.00 (E-F:1)

DOL LUMBER=1.00 NAIL=1.00 LS BEND=1.10
COMP=1.10 SHEAR=1.10 TENS=1.10

COMPANION LIVE LOAD FACTOR = 1.00

TRUSS PLATE MANUFACTURER IS NOT RESPONSIBLE FOR QUALITY CONTROL IN THE TRUSS MANUFACTURING PLANT.

NAIL VALUES

PLATE	GRIP(DRY)	SHEAR (PSI)	SECTION (PLI)
MT20	650	371	1747
	MAX MIN	MAX MIN	MAX MIN
	650	371	1747

PLATE PLACEMENT TOL. = 0.250 inches

PLATE ROTATION TOL. = 5.0 Deg.

JSI GRIP= 0.90 (N) (INPUT = 0.90)

JSI METAL= 0.55 (G) (INPUT = 1.00)

CITY OF RICHMOND HILL
BUILDING DIVISION

09/22/2022

KOTT
RECEIVED

Per: joshua.nabua




June 29, 2021

READ ALL NOTES ON THIS PAGE AND ON THE
ENGINEERING NOTE PAGE ENP-1. THE NOTE PAGE
IS AN INTEGRAL PART OF THIS DRAWING AS IT
CONTAINS SPECIFICATIONS AND CRITERIA USED
IN THE DESIGN OF THIS COMPONENT.

JOB NAME	TRUSS NAME	QUANTITY	PLY	JOB DESC.	DRWG NO.
IM0621-169	T04	8	1	TRUSS DESC.	


Version 8.420 S Apr 29 2021 MiTek Industries, Inc. Tue Jun 29 13:11:45 2021 Page 1
ID:6C523IFIJGTy_39enVU3pLzc1B6-LnS7Qold?P4nOouG_LT9jpnqemb2dRcnbZrjChz1Qii



Version 8.420 S Apr 29 2021 MiTek Industries, Inc. Tue Jun 29 13:12:01 2021 Page 1
ID:6C523FfjGTY 39enVU3pLzc1B6-tsQAnGvgEK5VIF7LwlvMBRfgC4vNga8G3iZmmz1Qis



**READ ALL NOTES ON THIS PAGE AND ON THE
ENGINEERING NOTE PAGE ENP-1. THE NOTE PAGE
IS AN INTEGRAL PART OF THIS DRAWING AS IT
CONTAINS SPECIFICATIONS AND CRITERIA USED
IN THE DESIGN OF THIS COMPONENT.**



TOTAL WEIGHT = 127 lb

[M][F]

LUMBER

N. L. G. A. RULES

CHORDS	SIZE	LUMBER	DESCR.
A - D	2x4	DRY	No.2
D - F	2x4	DRY	No.2
F - I	2x4	DRY	No.2
P - B	2x4	DRY	No.2
J - H	2x4	DRY	No.2
P - M	2x4	DRY	No.2
M - J	2x4	DRY	No.2

ALL WEBS 2x3 DRY No.2 SPF

EXCEPT

DRY: SEASONED LUMBER.

DIMENSIONS, SUPPORTS AND LOADINGS SPECIFIED BY FABRICATOR TO BE VERIFIED BY BUILDING DESIGNER**BEARINGS**

	FACTORED GROSS REACTION	MAXIMUM FACTORED GROSS REACTION	INPUT BRG	REQRD BRG
JT	VERT	HORZ	DOWN	HORZ
P	1703	0	1703	0
J	1703	0	1703	0

UNFACTORED REACTIONS

1ST LCASE	MAX/MIN. COMPONENT REACTIONS						
JT	COMBINED	SNOW	LIVE	PERM.LIVE	WIND	DEAD	SOIL
P	1190	863 / 0	0 / 0	0 / 0	0 / 0	327 / 0	0 / 0
J	1190	863 / 0	0 / 0	0 / 0	0 / 0	327 / 0	0 / 0

BEARING MATERIAL TO BE SPF NO.2 OR BETTER AT JOINT(S) P, J

BRACINGTOP CHORD TO BE SHEATHED OR MAX. PURLIN SPACING = 4.24 FT.
MAX. UNBRACED BOTTOM CHORD LENGTH = 10.00 FT OR RIGID CEILING DIRECTLY APPLIED.

ALL FITCH BREAKS AND PERIMETER CORNER JOINTS MUST BE Laterally RESTRAINED.

LOADING

TOTAL LOAD CASES: (4)

CHORDS				WEBS			
MEMB.	MAX. FACTORED FORCE (LBS)	FACTORED VERT. LOAD (PLF)	MAX. UNBRACED LENGTH (LC)	MEMB.	MAX. FACTORED FORCE (LBS)	MAX. UNBRACED LENGTH (LC)	
FR-TO		FROM TO		FR-TO			
A-B	0 / 26	-84.3 -84.3	0.11 (1)	10.00	O-C	-257 / 12	0.06 (1)
B-C	-2285 / 0	-84.3 -84.3	0.34 (1)	4.24	C-N	-269 / 0	0.17 (1)
C-D	-2080 / 0	-84.3 -84.3	0.32 (1)	4.42	N-D	0 / 263	0.06 (1)
D-E	-2147 / 0	-84.3 -84.3	0.39 (1)	4.27	D-M	0 / 443	0.10 (1)
E-F	-2147 / 0	-84.3 -84.3	0.39 (1)	4.27	M-E	-567 / 0	0.34 (1)
F-G	-2080 / 0	-84.3 -84.3	0.32 (1)	4.42	M-F	0 / 443	0.10 (1)
G-H	-2285 / 0	-84.3 -84.3	0.34 (1)	4.24	L-F	0 / 263	0.06 (1)
H-I	0 / 26	-84.3 -84.3	0.11 (1)	10.00	L-G	-269 / 0	0.17 (1)
P-B	-1660 / 0	0.0 0.0	0.17 (1)	6.44	K-G	-257 / 12	0.06 (1)
J-H	-1660 / 0	0.0 0.0	0.17 (1)	6.44	B-O	0 / 2091	0.47 (1)
					K-H	0 / 2091	0.47 (1)
P-O	0 / 0	-18.2 -18.2	0.10 (4)	10.00			
O-N	0 / 2062	-18.2 -18.2	0.40 (1)	10.00			
N-M	0 / 1844	-18.2 -18.2	0.37 (1)	10.00			
M-L	0 / 1844	-18.2 -18.2	0.37 (1)	10.00			
L-K	0 / 2062	-18.2 -18.2	0.40 (1)	10.00			
K-J	0 / 0	-18.2 -18.2	0.10 (4)	10.00			

DESIGN CRITERIA**SPECIFIED LOADS:**

TOP CH.	LL	=	25.6	PSF
DL	=	3.0	PSF	
BOT CH.	LL	=	0.0	PSF
DL	=	7.3	PSF	
TOTAL LOAD	=	35.9	PSF	

SPACING = 24.0 IN. C/C

LOADING IN FLAT SECTION BASED ON A SLOPE OF 6.00/12

THIS TRUSS IS DESIGNED FOR RESIDENTIAL OR SMALL BUILDING REQUIREMENTS OF PART 9, NBC 2015

THIS DESIGN COMPLIES WITH:

- PART 9 OF CBC 2015, ABC 2019
- PART 9 OF OBC 2012 (2019 AMENDMENT)
- CSA 086-14
- TPIC 2014

(55 % OF 31.3 P.S.F. G.S.L. PLUS 8.4 P.S.F. RAIN LOAD) EQUALS 25.6 P.S.F. SPECIFIED ROOF LIVE LOAD

ALLOWABLE DEFL.(LL) = L/360 (1.03")
CALCULATED VERT. DEFL.(LL) = L/999 (0.11")
ALLOWABLE DEFL.(TL) = L/360 (1.03")
CALCULATED VERT. DEFL.(TL) = L/999 (0.21")CSI: TC=0.39/1.00 (D-E:1), BC=0.40/1.00 (K-L:1),
WB=0.47/1.00 (H-K:1), SSI=0.22/1.00 (D-E:1)DOL LUMBER=1.00 NAIL=1.00 LS BEND=1.10
COMP=1.10 SHEAR=1.10 TENS=1.10

COMPANION LIVE LOAD FACTOR = 1.00

TRUSS PLATE MANUFACTURER IS NOT RESPONSIBLE FOR QUALITY CONTROL IN THE TRUSS MANUFACTURING PLANT.

NAIL VALUES

PLATE	GRIP(DRY)	SHEAR (PSI)	SECTION (PLI)
MT20	650	371	1747
	788	1987	1873

PLATE PLACEMENT TOL. = 0.250 inches

PLATE ROTATION TOL. = 5.0 Deg.

JSI GRIP= 0.89 (H) (INPUT = 0.90)

JSI METAL= 0.58 (H) (INPUT = 1.00)

CITY OF RICHMOND HILL
BUILDING DIVISION

09/22/2022


KOTT
RECEIVED

Per: joshua.nabua



June 29, 2021

READ ALL NOTES ON THIS PAGE AND ON THE ENGINEERING NOTE PAGE ENP-1. THE NOTE PAGE IS AN INTEGRAL PART OF THIS DRAWING AS IT CONTAINS SPECIFICATIONS AND CRITERIA USED IN THE DESIGN OF THIS COMPONENT.



TOTAL WEIGHT = 118 lb
[M][F]

LUMBER

N. L. G. A. RULES	CHORDS	SIZE	LUMBER	DESCR.
A - D	2x4	DRY	No.2	SPF
D - F	2x4	DRY	No.2	SPF
F - I	2x4	DRY	No.2	SPF
N - B	2x4	DRY	No.2	SPF
J - H	2x4	DRY	No.2	SPF
N - L	2x4	DRY	No.2	SPF
L - J	2x4	DRY	No.2	SPF

ALL WEBS 2x3 DRY No.2
EXCEPT

DRY: SEASONED LUMBER.

PLATES (table is in inches)

JT	TYPE	PLATES	W	LEN	Y	X
B	TMV+p	MT20	2.0	4.0		
C	TMWW-t	MT20	4.0	5.0	1.50	2.50
D	TTWW-m	MT20	5.0	6.0	2.25	1.75
E	TMW-w	MT20	2.0	4.0		
F	TTWW-m	MT20	5.0	6.0	2.25	1.75
G	TMWW-t	MT20	4.0	5.0	1.50	2.50
H	TMV+p	MT20	2.0	4.0		
J	BMVW1-t	MT20	4.0	5.0	1.50	1.75
K	BMWW-t	MT20	3.0	4.0		
L	BSWWW-t	MT20	5.0	8.0	3.00	4.00
M	BMWW-t	MT20	3.0	4.0		
N	BMVW1-t	MT20	4.0	5.0	1.50	1.75

DIMENSIONS, SUPPORTS AND LOADINGS SPECIFIED BY FABRICATOR TO BE VERIFIED BY BUILDING DESIGNER

BEARINGS

	FACTORED GROSS REACTION	MAXIMUM FACTORED GROSS REACTION	INPUT BRG	REQRD BRG
JT	VERT	HORZ	DOWN	HORZ
N	1703	0	1703	0
J	1703	0	1703	0

UNFACTORED REACTIONS

1ST LCASE	MAX/MIN. COMPONENT REACTIONS						
JT	COMBINED	SNOW	LIVE	PERM.LIVE	WIND	DEAD	SOIL
N	1190	863 / 0	0 / 0	0 / 0	0 / 0	327 / 0	0 / 0
J	1190	863 / 0	0 / 0	0 / 0	0 / 0	327 / 0	0 / 0

BEARING MATERIAL TO BE SPF NO.2 OR BETTER AT JOINT(S) N, J

BRACING

TOP CHORD TO BE SHEATHED OR MAX. PURLIN SPACING = 3.36 FT.
MAX. UNBRACED BOTTOM CHORD LENGTH = 10.00 FT OR RIGID CEILING DIRECTLY APPLIED.

ALL FITCH BREAKS AND PERIMETER CORNER JOINTS MUST BE Laterally RESTRAINED.

LOADING

TOTAL LOAD CASES: (4)

CHORDS				WEBS			
MEMB.	MAX. FACTORED FORCE (LBS)	FACTORED VERT. LOAD (PLF)	MAX. UNBRACED LENGTH (LC)	MEMB.	MAX. FACTORED FORCE (LBS)	MAX. UNBRACED LENGTH (LC)	
FR-TO		FROM TO		FR-TO			
A-B	0 / 26	-84.3 -84.3	0.11 (1)	C-M	0 / 73	0.03 (4)	
B-C	0 / 15	-84.3 -84.3	0.19 (1)	M-D	0 / 169	0.05 (4)	
C-D	-2210 / 0	-84.3 -84.3	0.21 (1)	D-L	0 / 808	0.18 (1)	
D-E	-2643 / 0	-84.3 -84.3	0.79 (1)	L-E	-778 / 0	0.31 (1)	
E-F	-2643 / 0	-84.3 -84.3	0.79 (1)	L-F	0 / 808	0.18 (1)	
F-G	-2210 / 0	-84.3 -84.3	0.21 (1)	K-F	0 / 169	0.05 (4)	
G-H	0 / 15	-84.3 -84.3	0.19 (1)	K-G	0 / 73	0.03 (4)	
H-I	0 / 26	-84.3 -84.3	0.11 (1)	N-C	-2401 / 0	0.95 (1)	
N-B	-250 / 0	0.0 0.0	0.03 (1)	G-J	-2401 / 0	0.95 (1)	
J-H	-250 / 0	0.0 0.0	0.03 (1)				
N-M	0 / 1955	-18.2 -18.2	0.48 (1)				
M-L	0 / 1965	-18.2 -18.2	0.49 (1)				
L-K	0 / 1965	-18.2 -18.2	0.49 (1)				
K-J	0 / 1955	-18.2 -18.2	0.48 (1)				

DESIGN CRITERIA

SPECIFIED LOADS:

TOP CH.	LL	=	25.6	PSF
	DL	=	3.0	PSF
BOT CH.	LL	=	0.0	PSF
	DL	=	7.3	PSF
TOTAL LOAD	=	35.9	PSF	

SPACING = 24.0 IN. C/C

LOADING IN FLAT SECTION BASED ON A SLOPE OF 6.00/12

THIS TRUSS IS DESIGNED FOR RESIDENTIAL OR SMALL BUILDING REQUIREMENTS OF PART 9, NBCC 2015

THIS DESIGN COMPLIES WITH:

- PART 9 OF CBC 2018, ABC 2019
- PART 9 OF OBC 2012 (2019 AMENDMENT)
- CSA 086-14
- TPIC 2014

(55 % OF 31.3 P.S.F. G.S.L. PLUS 8.4 P.S.F. RAIN LOAD) EQUALS 25.6 P.S.F. SPECIFIED ROOF LIVE LOAD

ALLOWABLE DEFL.(LL) = L/360 (1.03")
CALCULATED VERT. DEFL.(LL) = L/999 (0.15")
ALLOWABLE DEFL.(TL) = L/360 (1.03")
CALCULATED VERT. DEFL.(TL) = L/999 (0.28")

CSI: TC=0.79/1.00 (E-F:1), BC=0.49/1.00 (K-L:1),
WB=0.95/1.00 (G-J:1), SSI=0.31/1.00 (D-E:1)

DOL LUMBER=1.00 NAIL=1.00 LS BEND=1.10
COMP=1.10 SHEAR=1.10 TENS=1.10

COMPANION LIVE LOAD FACTOR = 1.00

TRUSS PLATE MANUFACTURER IS NOT RESPONSIBLE FOR QUALITY CONTROL IN THE TRUSS MANUFACTURING PLANT.

NAIL VALUES

PLATE	GRIP(DRY)	SHEAR (PSI)	SECTION (PLI)
MT20	650	371	1747
	MAX	MIN	MAX
	650	371	1747

PLATE PLACEMENT TOL. = 0.250 inches

PLATE ROTATION TOL. = 5.0 Deg.

JSI GRIP= 0.89 (N) (INPUT = 0.90)

JSI METAL= 0.88 (G) (INPUT = 1.00)

CITY OF RICHMOND HILL
BUILDING DIVISION

09/22/2022

RECEIVED

Per: joshua.nabua




June 29, 2021

READ ALL NOTES ON THIS PAGE AND ON THE ENGINEERING NOTE PAGE ENP-1. THE NOTE PAGE IS AN INTEGRAL PART OF THIS DRAWING AS IT CONTAINS SPECIFICATIONS AND CRITERIA USED IN THE DESIGN OF THIS COMPONENT.

JOB NAME	TRUSS NAME	QUANTITY	PLY	JOB DESC.	DRWG NO.
IM0621-169	T09	3	1	TRUSS DESC.	

Version 8.420 S Apr 29 2021 MiTek Industries, Inc. Tue Jun 29 13:12:26 2021 Page 1
ID:6C5231FijGTy 39enVU3pLzc1B6-egQd0pFLM?Fyo5X9uSintTzzdHbOkwOp0SHO8pz1Qi3



TOTAL WEIGHT = 3 X 76 = 229 lb
[M][F]

LUMBER	N. L. G. A. RULES	CHORDS	SIZE	LUMBER	DESCR.
A - D	2x4	DRY	No.2	SPF	
D - F	2x4	DRY	No.2	SPF	
J - B	2x4	DRY	No.2	SPF	
G - F	2x4	DRY	No.2	SPF	
J - H	2x4	DRY	No.2	SPF	
H - G	2x4	DRY	No.2	SPF	

ALL WEBS 2x3 DRY No.2 SPF

DRY: SEASONED LUMBER.

PLATES (table is in inches)

JT	TYPE	PLATES	W	LEN	Y	X
B	TMV+p	MT20	2.0	4.0		
C	TMWW-t	MT20	3.0	5.0	1.50	2.00
D	TTW+p	MT20	3.0	4.0	2.25	1.50
E	TMWW-t	MT20	3.0	5.0	1.50	2.00
F	TMV+p	MT20	2.0	4.0		
G	BMVW1-t	MT20	4.0	4.0		
H	BS-t	MT20	3.0	4.0		
I	BMVWW-t	MT20	3.0	8.0		
J	BMVW1-t	MT20	4.0	4.0		

DIMENSIONS, SUPPORTS AND LOADINGS SPECIFIED BY FABRICATOR TO BE VERIFIED BY BUILDING DESIGNER

BEARINGS

	FACTORED GROSS REACTION	MAXIMUM FACTORED GROSS REACTION	INPUT BRG	REQRD BRG
JT	VERT	HORZ	DOWN	UPLIFT
J	1072	0	1072	0
G	957	0	957	0

A SUITABLE HANGER/MECHANICAL CONNECTION IS REQUIRED AT JOINT G. MINIMUM BEARING LENGTH AT JOINT G = 1-8.

UNFACTORED REACTIONS

JT	1ST LCASE	MAX /MIN.	COMPONENT REACTIONS				
JT	COMBINED	SNOW	LIVE	PERM.LIVE	WIND	DEAD	SOIL
J	748	548 / 0	0 / 0	0 / 0	0 / 0	201 / 0	0 / 0
G	670	478 / 0	0 / 0	0 / 0	0 / 0	192 / 0	0 / 0

BEARING MATERIAL TO BE SPF NO.2 OR BETTER AT JOINT(S) J

BRACING

TOP CHORD TO BE SHEATHED OR MAX. PURLIN SPACING = 6.25 FT.
MAX. UNBRACED BOTTOM CHORD LENGTH = 10.00 FT OR RIGID CEILING DIRECTLY APPLIED.

ALL FITCH BREAKS AND PERIMETER CORNER JOINTS MUST BE Laterally RESTRAINED.

LOADING

TOTAL LOAD CASES: (4)

CHORDS				WEBS			
MEMB.	MAX. FACTORED FORCE (LBS)	FACTORED VERT. LOAD (PLF)	MAX. FACTORED HORIZ. LOAD (LC)	MEMB.	MAX. FACTORED FORCE (LBS)	MAX. FACTORED HORIZ. LOAD (LC)	
FR-TO				FR-TO			
A-B	0 / 32	-84.3	-84.3 0.11 (1)	I-D	0 / 548	0.12 (1)	
B-C	0 / 26	-84.3	-84.3 0.30 (1)	I-E	-252 / 0	0.18 (1)	
C-D	-792 / 0	-84.3	-84.3 0.24 (1)	C-I	-252 / 0	0.18 (1)	
D-E	-792 / 0	-84.3	-84.3 0.24 (1)	J-C	-1110 / 0	0.76 (1)	
E-F	0 / 26	-84.3	-84.3 0.30 (1)	E-G	-1110 / 0	0.76 (1)	
J-B	-266 / 0	0.0	0.0 0.03 (1)				
G-F	-150 / 0	0.0	0.0 0.02 (1)				
J-I	0 / 825	-18.2	-18.2 0.51 (4)				
I-H	0 / 825	-18.2	-18.2 0.51 (4)				
H-G	0 / 825	-18.2	-18.2 0.51 (4)				

DESIGN CRITERIA

SPECIFIED LOADS:

TOP CH.	LL	=	25.6	PSF
	DL	=	3.0	PSF
BOT CH.	LL	=	0.0	PSF
	DL	=	7.3	PSF
TOTAL LOAD	=		35.9	PSF

SPACING = 24.0 IN. C/C

THIS TRUSS IS DESIGNED FOR RESIDENTIAL OR SMALL BUILDING REQUIREMENTS OF PART 9, NBC 2015

THIS DESIGN COMPLIES WITH:

- PART 9 OF CBC 2018, ABC 2019
- PART 9 OF OBC 2012 (2019 AMENDMENT)
- CSA 086-14
- TPIC 2014

(55 % OF 31.3 P.S.F. G.S.L. PLUS 8.4 P.S.F. RAIN LOAD) EQUALS 25.6 P.S.F. SPECIFIED ROOF LIVE LOAD

ALLOWABLE DEFL.(LL)= L/360 (0.62")
CALCULATED VERT. DEFL.(LL)= L/999 (0.03")
ALLOWABLE DEFL.(TL)= L/360 (0.62")
CALCULATED VERT. DEFL.(TL)= L/999 (0.17")

CSI: TC=0.30/1.00 (B-C:1), BC=0.51/1.00 (I-J:4), WB=0.76/1.00 (C-J:1), SSI=0.16/1.00 (C-D:1)

DOL LUMBER=1.00 NAIL=1.00 LS BEND=1.10 COMP=1.10 SHEAR=1.10 TENS=1.10

COMPANION LIVE LOAD FACTOR = 1.00

TRUSS PLATE MANUFACTURER IS NOT RESPONSIBLE FOR QUALITY CONTROL IN THE TRUSS MANUFACTURING PLANT.

NAIL VALUES

PLATE	GRIP(DRY)	SHEAR	SECTION
(PSI)	(PLI)	(PLI)	
MAX	MIN	MAX	MIN
MT20	650	371	1747 788 1987 1873

PLATE PLACEMENT TOL. = 0.250 inches

PLATE ROTATION TOL. = 5.0 Deg.

JSI GRIP= 0.90 (G) (INPUT = 0.90)
JSI METAL= 0.30 (H) (INPUT = 1.00)



June 29, 2021


READ ALL NOTES ON THIS PAGE AND ON THE ENGINEERING NOTE PAGE ENP-1. THE NOTE PAGE IS AN INTEGRAL PART OF THIS DRAWING AS IT CONTAINS SPECIFICATIONS AND CRITERIA USED IN THE DESIGN OF THIS COMPONENT.

CITY OF RICHMOND HILL
BUILDING DIVISION

09/22/2022

KOTT
RECEIVED

Per: joshua.nabua

**LUMBER**

N. L. G. A. RULES
CHORDS SIZE
A - D 2x4 DRY
D - F 2x4 DRY
I - B 2x4 DRY
G - F 2x4 DRY
I - F 2x4 DRY

LUMBER

DESCR.

SPF No.2
SPF No.2
SPF No.2
SPF No.2
SPF No.2

ALL WEBS 2x3 DRY
EXCEPT

DRY: SEASONED LUMBER.

PLATES (table is in inches)

JT	TYPE	PLATES	W	LEN	Y	X
B	TMV+p	MT20	2.0	4.0		
C	TMWW-t	MT20	3.0	5.0		
D	TTW+p	MT20	3.0	4.0		
E	TMWW-t	MT20	3.0	5.0		
F	TMV+p	MT20	2.0	4.0		
G	BMVW1-t	MT20	3.0	5.0	1.50	2.25
H	BMVW1-t	MT20	3.0	6.0		
I	BMVW1-t	MT20	3.0	5.0	1.50	2.25

DIMENSIONS, SUPPORTS AND LOADINGS SPECIFIED BY FABRICATOR TO BE VERIFIED BY BUILDING DESIGNER**BEARINGS**

JT	FACTORED GROSS REACTION	MAXIMUM FACTORED GROSS REACTION	INPUT BRG	REQRD BRG
	VERT	DOWN	IN-SX	IN-SX
I	883	0	5-8	1-8
G	769	0	0	MECHANICAL

A SUITABLE HANGER/MECHANICAL CONNECTION IS REQUIRED AT JOINT G. MINIMUM BEARING LENGTH AT JOINT G = 1-8.

UNFACTORED REACTIONS

JT	1ST LCASE	MAX / MIN	COMPONENT REACTIONS
	COMBINED	SNOW	LIVE PERM.LIVE WIND DEAD SOIL
I	616	453 / 0	0 / 0 0 / 0 0 / 0 163 / 0 0 / 0
G	538	384 / 0	0 / 0 0 / 0 0 / 0 155 / 0 0 / 0

BEARING MATERIAL TO BE SPF NO.2 OR BETTER AT JOINT(S) I

BRACING

TOP CHORD TO BE SHEATHED OR MAX. PURLIN SPACING = 6.25 FT.
MAX. UNBRACED BOTTOM CHORD LENGTH = 10.00 FT OR RIGID CEILING DIRECTLY APPLIED.

ALL FITCH BREAKS AND PERIMETER CORNER JOINTS MUST BE Laterally RESTRAINED.

LOADING

TOTAL LOAD CASES: (4)

CHORDS				WEBS			
MEMB.	MAX. FACTORED FORCE (LBS)	FACTORED VERT. LOAD (PLF)	MAX. FACTORED CS (LC)	MEMB.	MAX. FACTORED FORCE (LBS)	MAX. FACTORED CS (LC)	
FR-TO		FROM TO	LENGTH	FR-TO			
A-B	0 / 26	-84.3 -84.3	0.11 (1)	10.00	H-D	0 / 406	0.09 (1)
B-C	0 / 16	-84.3 -84.3	0.18 (1)	10.00	H-E	-201 / 8	0.07 (1)
C-D	-744 / 0	-84.3 -84.3	0.14 (1)	6.25	C-H	-201 / 8	0.07 (1)
D-E	-744 / 0	-84.3 -84.3	0.14 (1)	6.25	I-C	-1006 / 0	0.35 (1)
E-F	0 / 16	-84.3 -84.3	0.18 (1)	10.00	E-G	-1006 / 0	0.35 (1)
I-B	-238 / 0	0.0 0.0	0.02 (1)	7.81			
G-F	-124 / 0	0.0 0.0	0.01 (1)	7.81			
I-H	0 / 814	-18.2 -18.2	0.34 (4)	10.00			
H-G	0 / 814	-18.2 -18.2	0.34 (4)	10.00			

DESIGN CRITERIA**SPECIFIED LOADS:**

TOP CH.	LL	=	25.6	PSF
	DL	=	3.0	PSF
BOT CH.	LL	=	0.0	PSF
	DL	=	7.3	PSF
TOTAL LOAD	=		35.9	PSF

SPACING = 24.0 IN. C/C

THIS TRUSS IS DESIGNED FOR RESIDENTIAL OR SMALL BUILDING REQUIREMENTS OF PART 9, NBCC 2015

THIS DESIGN COMPLIES WITH:

- PART 9 OF CBC 2018, ABC 2019
- PART 9 OF OBC 2012 (2019 AMENDMENT)
- CSA 086-14
- TPIC 2014

(55 % OF 31.3 P.S.F. G.S.L. PLUS 8.4 P.S.F. RAIN LOAD) EQUALS 25.6 P.S.F. SPECIFIED ROOF LIVE LOAD

ALLOWABLE DEFL.(LL)= L/360 (0.50")
CALCULATED VERT. DEFL.(LL)= L/999 (0.02")
ALLOWABLE DEFL.(TL)= L/360 (0.50")
CALCULATED VERT. DEFL.(TL)= L/999 (0.08")

CSI: TC=0.18/1.00 (B-C:1), BC=0.34/1.00 (H-I:4), WB=0.35/1.00 (C-I:1), SSI=0.13/1.00 (B-C:1)

DOL LUMBER=1.00 NAIL=1.00 LS BEND=1.10 COMP=1.10 SHEAR=1.10 TENS=1.10

COMPANION LIVE LOAD FACTOR = 1.00

TRUSS PLATE MANUFACTURER IS NOT RESPONSIBLE FOR QUALITY CONTROL IN THE TRUSS MANUFACTURING PLANT.

NAIL VALUES

PLATE	GRIP(DRY)	SHEAR	SECTION
	(PSI)	(PLI)	(PLI)
MT20	650	371	1747 788 1987 1873

PLATE PLACEMENT TOL. = 0.250 inches

PLATE ROTATION TOL. = 5.0 Deg.

JSI GRIP= 0.82 (I) (INPUT = 0.90)
JSI METAL= 0.26 (E) (INPUT = 1.00)



June 29, 2021


READ ALL NOTES ON THIS PAGE AND ON THE ENGINEERING NOTE PAGE ENP-1. THE NOTE PAGE IS AN INTEGRAL PART OF THIS DRAWING AS IT CONTAINS SPECIFICATIONS AND CRITERIA USED IN THE DESIGN OF THIS COMPONENT.

CITY OF RICHMOND HILL
BUILDING DIVISION

09/22/2022

KOTT
RECEIVED

Per: joshua.nabua



TOTAL WEIGHT = 51 lb

LUMBER

N. L. G. A. RULES

CHORDS	SIZE	DRY	LUMBER	DESCR.
A - C	2x4	DRY	No.2	SPF
C - D	2x4	DRY	No.2	SPF
D - F	2x4	DRY	No.2	SPF
J - B	2x4	DRY	No.2	SPF
G - E	2x4	DRY	No.2	SPF
J - G	2x4	DRY	No.2	SPF

ALL WEBS
EXCEPT

DRY: SEASONED LUMBER.

PLATES (table is in inches)

JT	TYPE	PLATES	W	LEN	Y	X
B	TMVW-t	MT20	3.0	5.0	1.50	2.25
C	TTWW-m	MT20	4.0	5.0	1.75	1.25
D	TTWW-m	MT20	3.0	4.0		
E	TMVW-t	MT20	3.0	5.0	1.50	2.25
G	BMV1+p	MT20	2.0	4.0		
H	BMVWW-t	MT20	3.0	8.0		
I	BMVW-t	MT20	3.0	4.0	1.50	1.50
J	BMV1+p	MT20	2.0	4.0		

DIMENSIONS, SUPPORTS AND LOADINGS SPECIFIED BY FABRICATOR TO BE VERIFIED BY BUILDING DESIGNER

BEARINGS

	FACTORED GROSS REACTION	MAXIMUM FACTORED GROSS REACTION	INPUT BRG	REQRD BRG
JT	VERT	HORZ	DOWN	HORZ
J	781	0	781	0
G	781	0	781	0

UNFACTORED REACTIONS

JT	COMBINED	SNOW	LIVE	PERM.LIVE	WIND	DEAD	SOIL
J	544	402 / 0	0 / 0	0 / 0	0 / 0	142 / 0	0 / 0
G	544	402 / 0	0 / 0	0 / 0	0 / 0	142 / 0	0 / 0

BEARING MATERIAL TO BE SPF NO.2 OR BETTER AT JOINT(S) J, G

BRACING

TOP CHORD TO BE SHEATHED OR MAX. PURLIN SPACING = 6.25 FT.
MAX. UNBRACED BOTTOM CHORD LENGTH = 10.00 FT OR RIGID CEILING DIRECTLY APPLIED.

ALL FITCH BREAKS AND PERIMETER CORNER JOINTS MUST BE Laterally RESTRAINED.

LOADING

TOTAL LOAD CASES: (4)

CHORDS				WEBS			
MEMB.	MAX. FACTORED FORCE (LBS)	FACTORED VERT. LOAD (PLF)	MAX. UNBRACED LENGTH (LC)	MEMB.	MAX. FACTORED FORCE (LBS)	MAX. UNBRACED LENGTH (LC)	
FR-TO		FROM TO		FR-TO			
A-B	0 / 26	-84.3 -84.3	0.11 (1)	I-C	-40 / 57	0.02 (4)	
B-C	-719 / 0	-84.3 -84.3	0.22 (1)	C-H	0 / 2	0.00 (4)	
C-D	-643 / 0	-84.3 -84.3	0.19 (1)	H-D	-38 / 59	0.02 (4)	
D-E	-722 / 0	-84.3 -84.3	0.22 (1)	B-I	0 / 654	0.15 (1)	
E-F	0 / 26	-84.3 -84.3	0.11 (1)	H-E	0 / 656	0.15 (1)	
J-B	-745 / 0	0.0 0.0	0.08 (1)				
G-E	-744 / 0	0.0 0.0	0.08 (1)				
J-I	0 / 0	-18.2 -18.2	0.08 (4)				
I-H	0 / 641	-18.2 -18.2	0.14 (1)				
H-G	0 / 0	-18.2 -18.2	0.08 (4)				

DESIGN CRITERIA

SPECIFIED LOADS:

TOP CH.	LL	=	25.6	PSF
	DL	=	3.0	PSF
BOT CH.	LL	=	0.0	PSF
	DL	=	7.3	PSF
TOTAL LOAD		=	35.9	PSF

SPACING = 24.0 IN. C/C

LOADING IN FLAT SECTION BASED ON A SLOPE OF 3.50/12

THIS TRUSS IS DESIGNED FOR RESIDENTIAL OR SMALL BUILDING REQUIREMENTS OF PART 9, NBCC 2015

THIS DESIGN COMPLIES WITH:

- PART 9 OF CBC 2018, ABC 2019
- PART 9 OF OBC 2012 (2019 AMENDMENT)
- CSA 086-14
- TPIC 2014

(55 % OF 31.3 P.S.F. G.S.L. PLUS 8.4 P.S.F. RAIN LOAD) EQUALS 25.6 P.S.F. SPECIFIED ROOF LIVE LOAD

ALLOWABLE DEFL.(LL) = L/360 (0.43")
CALCULATED VERT. DEFL.(LL) = L/999 (0.01")
ALLOWABLE DEFL.(TL) = L/360 (0.43")
CALCULATED VERT. DEFL.(TL) = L/999 (0.03")

CSI: TC=0.22/1.00 (D-E:1), BC=0.14/1.00 (H-I:1), WB=0.15/1.00 (E-H:1), SSI=0.14/1.00 (C-D:1)

DOL LUMBER=1.00 NAIL=1.00 LS BEND=1.10 COMP=1.10 SHEAR=1.10 TENS=1.10

COMPANION LIVE LOAD FACTOR = 1.00

TRUSS PLATE MANUFACTURER IS NOT RESPONSIBLE FOR QUALITY CONTROL IN THE TRUSS MANUFACTURING PLANT.

NAIL VALUES

PLATE	GRIP(DRY)	SHEAR (PSI)	SECTION (PLI)
MT20	650	371	1747

PLATE PLACEMENT TOL. = 0.250 inches

PLATE ROTATION TOL. = 5.0 Deg.

JSI GRIP= 0.86 (D) (INPUT = 0.90)

JSI METAL= 0.24 (E) (INPUT = 1.00)

**CITY OF RICHMOND HILL
BUILDING DIVISION**

09/22/2022

RECEIVED

Per: joshua.nabua



June 29, 2021

READ ALL NOTES ON THIS PAGE AND ON THE ENGINEERING NOTE PAGE ENP-1. THE NOTE PAGE IS AN INTEGRAL PART OF THIS DRAWING AS IT CONTAINS SPECIFICATIONS AND CRITERIA USED IN THE DESIGN OF THIS COMPONENT.

Version 8.420 S Apr 29 2021 MiTek Industries, Inc. Tue Jun 29 13:12:48 2021 Page 1
ID:6C523IFljGTY_39enVU3pLzc1B6~v?lxeKW8Am0rRTDNA45xm6uec9Aru0C24tcYvYz1Qhj



DRY: SEASONED LUMBER.

PLATES (table is in inches)						
JT	TYPE	PLATES	W	LEN	Y	X
B	TMVW-t	MT20	3.0	5.0	1.50	2.25
C	TTWW-m	MT20	4.0	5.0	1.75	1.25
D	TTWW-m	MT20	3.0	4.0	2.00	1.25
E	TMVW-t	MT20	3.0	5.0	1.50	2.25
G	BMV1+p	MT20	2.0	4.0		
H	BMWWWW-t	MT20	3.0	8.0		
I	BMWW-t	MT20	3.0	4.0	1.50	1.75
J	BMV1+p	MT20	2.0	4.0		

DIMENSIONS, SUPPORTS AND LOADINGS SPECIFIED BY FABRICATOR TO BE VERIFIED BY BUILDING DESIGNER

BEARINGS							
	FACTORED		MAXIMUM FACTORED			INPUT	REQRD
	GROSS REACTION		GROSS REACTION			BRG	BRG
	VERT	HORZ	DOWN	HORZ	UPLIFT	IN-SX	IN-SX
JT	781	0	781	0	0	5-8	1-8
G	781	0	781	0	0	5-8	1-8

UNFACTORED REACTIONS

1ST LCASE		MAX./MIN. COMPONENT REACTIONS					
JT	COMBINED	SNOW	LIVE	PERM.LIVE	WIND	DEAD	SOIL
J	544	402 / 0	0 / 0	0 / 0	0 / 0	142 / 0	0 / 0
G	544	402 / 0	0 / 0	0 / 0	0 / 0	142 / 0	0 / 0

BEARING MATERIAL TO BE SPF NO.2 OR BETTER AT JOINT(S) J, G

BRACING

TOP CHORD TO BE SHEATHED OR MAX. PURLIN SPACING = 5.98 FT.
MAX. UNBRACED BOTTOM CHORD LENGTH = 10.00 FT OR RIGID CEILING DIRECTLY
APPLIED.

ALL FITCH BREAKS AND PERIMETER CORNER JOINTS MUST BE Laterally RESTRAINED.

LOADING

TOTAL LOAD CASES: (4)

C H O R D S					W E B S			
MAX. FACTORED		FACTORED			MAX. FACTORED			
MEMB.	FORCE (LBS)	VERT. LOAD (PLF)	LC1 MAX CSI (LC)	MAX. UNBRAC LENGTH	MEMB.	FORCE (LBS)	MAX CSI (LC)	
FR-TO		FROM	TO		FR-TO			
A-B	0 / 26	-84.3	-84.3	0.11 (1)	10.0	I-C	-72 / 62	0.02 (4)
B-C	-755 / 0	-84.3	-84.3	0.16 (1)	6.25	C-H	0 / 0	0.00 (1)
C-D	-672 / 0	-84.3	-84.3	0.65 (1)	5.98	H-D	-72 / 62	0.02 (4)
D-E	-755 / 0	-84.3	-84.3	0.16 (1)	6.25	B-I	0 / 697	0.16 (1)
E-F	0 / 26	-84.3	-84.3	0.11 (1)	10.00	H-E	0 / 697	0.16 (1)
J-B	-763 / 0	0.0	0.0	0.08 (1)	7.81			
G-E	-763 / 0	0.0	0.0	0.08 (1)	7.81			
J-I	0 / 0	-18.2	-18.2	0.11 (4)	10.00			
I-H	0 / 672	-18.2	-18.2	0.17 (1)	10.00			
H-G	0 / 0	-18.2	-18.2	0.12 (4)	10.00			

DESIGN CRITERIA

SPECIFIED LOADS:				
TOP	CH.	LL =	25.6	PSF
		DL =	3.0	PSF
BOT	CH.	LL =	0.0	PSF
		DL =	7.3	PSF
TOTAL LOAD		=	35.9	PSF

SPACING = 24.0 IN. C/C

LOADING IN FLAT SECTION BASED ON A
SLOPE OF 3.50/12

THIS TRUSS IS DESIGNED FOR RESIDENTIAL
OR SMALL BUILDING REQUIREMENTS OF
PART 9, NBCC 2015

THIS DESIGN COMPLIES WITH:

- PART 9 OF BCBC 2018 , ABC 2019
- PART 9 OF OBC 2012 (2019 AMENDMENT)
- CSA 086-14
- TPIC 2014

(55 % OF 31.3 P.S.F. G.S.L. PLUS 8.4 P.S.F. RAIN LOAD) EQUALS 25.6 P.S.F. SPECIFIED ROOF LIVE LOAD

ALLOWABLE DEFL.(LL)= L/360 (0.43")
CALCULATED VERT. DEFL.(LL) = L/ 999 (0.02")
ALLOWABLE DEFL.(TL)= L/360 (0.43")
CALCULATED VERT. DEFL.(TL) = L/ 999 (0.05")

CSI: TC=0.65/1.00 (C-D:1) , BC=0.17/1.00 (H-I:1) ,
WB=0.16/1.00 (B-I:1) , SSI=0.21/1.00 (C-D:1)

DOL LUMBER=1.00 NAIL=1.00 LS BEND=1.10
COMP=1.10 SHEAR=1.10 TENS= 1.10

COMPANION LIVE LOAD FACTOR = 1.00

TRUSS PLATE MANUFACTURER IS NOT RESPONSIBLE FOR QUALITY CONTROL IN THE TRUSS MANUFACTURING PLANT.

NAIL VALUES						
PLATE	GRIP(DRY)		SHEAR		SECTION	
	(PSI)		(PLI)		(PLI)	
	MAX	MIN	MAX	MIN	MAX	MIN
MT20	650	371	1747	788	1987	1873

PLATE PLACEMENT TOL. = 0.250 inches

PLATE ROTATION TOL. = 5.0 Deg.

JSI GRIP= 0.82 (I) (INPUT = 0.90)
JSI METAL= 0.25 (B) (INPUT = 1.00)

CITY OF RICHMOND HILL
BUILDING DIVISION

09/22/2022
KOTT
RECEIVED


Per: joshua.nabua



June 29, 2021

**READ ALL NOTES ON THIS PAGE AND ON THE
ENGINEERING NOTE PAGE ENP-1. THE NOTE PAGE
IS AN INTEGRAL PART OF THIS DRAWING AS IT
CONTAINS SPECIFICATIONS AND CRITERIA USED
IN THE DESIGN OF THIS COMPONENT.**

Version 8.420 S Apr 29 2021 MiTek Industries, Inc. Tue Jun 29 13:12:56 2021 Page 1
ID:6C523IFljGTY_39enVU3pLzc1B6-mREzJ4cAHD1iPiqwemFp5oD5RNvDmdCEw6YzB4z1Qhb

Per: joshua.nabua

Per: joshua.nabua

TOE-NAIL CAPACITY DETAILS

LATERAL AND WITHDRAWAL RESISTANCE OF BEARING ANCHORAGE BY TOE-NAILS

NAIL TYPE	Length (in)	Diameter (in)	LATERAL Resistance per nail (Lbs.)		WITHDRAWAL Resistance per nail (Lbs.)	
			SPF	D. FIR	SPF	D. FIR
COMMON WIRE	3.00	0.144	122	139	30	42
	3.25	0.144	127	144	32	45
	3.50	0.160	152	173	38	52
COMMON SPIRAL	3.00	0.122	96	108	26	36
	3.25	0.122	97	108	28	40
	3.50	0.152	142	161	36	50
3.25" Gun nail	3.25	0.120	94	105	28	39

Note: If using truss with D. Fir lumber and SPF bearing plate, use tabulated SPF values in table.

Nail type:	Common wire	Common spiral	Common wire	Common spiral	Gun Nail
Diameter (in.)	0.160	0.152	0.144	0.122	0.120
Length (in.)	3.50	3.50	3.00	3.00	3.25
LUMBER	MAXIMUM NUMBER OF TOE-NAILS				
2x4 SPF	2	2	3	3	3
2x6 SPF	4	4	4	5	5
2x4 D. FIR	2	2	2	2	2
2x6 D. FIR	3	3	3	4	4





Figure 1: Toe-Nailing Rafter / Ceiling Member to Girder Truss

PEO
Certificate No. 10889485



TOE-NAIL CAPACITY DETAILS

Figure 2: Toe-Nail Anchorage to Bearing Plate for Uplift



NOTES:


1. Rafter and ceiling members may be connected to top and bottom chords of girder truss by toe-nailing the members into the girder chords (see fig. 1), provided the factored vertical reactions of the supported members do not exceed the lateral resistance of the toe-nails. Mechanical connectors (hangers) are required if factored vertical reactions exceed the toe-nail capacity, or if the connection must resist horizontal loads (loads perpendicular to the face of girder or rafter).
2. Trusses, rafters or ceiling members may be anchored to the bearing plate with toe-nails (see fig. 2), provided that the factored uplift reactions due to **wind or earthquake loads** do not exceed the **withdrawal resistance of the toe-nails**. Mechanical anchors (tie-downs) are required for reactions that exceed the toe-nail withdrawal capacity. Toe-nail anchorage to bearing plates is **NOT** permitted if uplift reactions are generated from gravity loads (snow, floor live, dead).
3. Tabulated toe-nail resistances on page 1 are for **one** toe-nail. Multiply unit values by the number of nails used in the connection. Maximum number of nails in a connection shall not exceed the tabulated limits shown on page 1 for a given lumber size /species.
4. Nail values are based on specific gravity of $G = 0.42$ (SPF) and $G = 0.49$ (D. Fir).
5. Toe-nails shall be driven at approximately $1/3$ the nail length from the edge of the joist/truss chord and driven at an angle of 30° to the grain of the member.
6. For wind / earthquake loads, tabulated lateral resistances may be multiplied by 1.15 (K_D factor). No increases are permitted for tabulated withdrawal resistances.
7. Lumber must be dry ($< 19\%$ moisture content) at the time of nail installation.
8. Nail values in this table comply with CSA O86-19, Clause 12.9.

PEO
Certificate No. 10889485




STANDARD HIP END FRAMING


PLAN VIEW




HEEL DETAIL 'A' Standard Heel



DETAIL 'B': Raised Heel




HEEL DETAIL 'C' Cantilever




CANTILEVER DETAIL "C"

SLOPE	MAX CANT.	WEDGE PLATE	WEDGE SIZE
3/12	17"	3 X 5	2 X 3
4/12	14"	3 X 5	2 X 3
5/12	12"	3 X 5	2 X 4
6/12	10"	3 X 5	2 X 4
7/12	9"	3 X 5	2 X 6
8/12	8.5"	3 X 5	2 X 6
9/12	8"	3 X 5	2 X 6
10/12	7.5"	3 X 5	2 X 6

S Trusses




L Trusses



Specified Load Rating:

Top chord Live:	51.0 PSF or less
Top chord Dead:	6.0 PSF or less
Bottom chord Live:	0.0 PSF
Bottom chord Dead:	7.3 PSF or less

J Trusses



NOTES:

1. This detail is valid only for projects conforming to **PART 9 NBCC 2015** that do not require a wind analysis to be incorporated into the design of the trusses.
2. Overhang length shall not exceed 24 inches.
3. All lumber shall be 2x4 SPF (or D-Fir) DRY No. 2 grade or better.
4. All plates specified are MITEK MT20, pressed into both faces of each truss. Heel plates of all trusses shall conform to heel details 'A', 'B' or 'C'.
5. Diagonal hip rafter design shall conform to section 9.23.14.6 of NBCC 2015.
6. For 6.0 ft. or less span, diagonal web on truss 'J' is optional. Girder design must reflect choice of partial jack ('J' with diagonal web) or open jack ('J' without diagonal web)
7. All truss-to-rafter and truss-to-truss connections shall be specified as per MITEK standard detail 'MSD2015-H: Toe-Nail Capacity Details'

PEO
Certificate No. 10889485




09/22/2022

RECEIVED

Per: joshua.nabua


STANDARD GABLE END DETAIL



SCAB BRACE DETAIL (Section B-B)


Gable Web

SPF No. 2 DRY Scab, same size as web. Scab brace must cover 90% of web length



2x4 SPF No. 2
DRY L-Brace

L BRACE DETAIL (Section A-A)



Fasten L-Brace to narrow edge of web with one row of 0.122" x 3.0" nails spaced at 6.0" c/c along entire length of web. Brace must cover 90% of the web length. Respect a 2.5" minimum end distance.

Notes:

1. This detail is only valid for projects conforming to **Part 9, NBCC 2015** that do not require a wind analysis to be incorporated into the design of the truss.
2. This detail is for vertical (gravity) load rating of the truss only. Truss must be continuously supported over the entire length of bottom chord.
3. Maximum web length not to exceed 12.0 ft. Spacing of gable stud webs in the truss not to exceed 24 inches cc.
4. Splice joints shall not be located in the first panel adjacent to the heel joint or peak joint.
5. Lateral restraint required at half-length of all webs over 6.0 ft. long. Alternatively install an L-Brace or scab brace as shown above. Scab braces shall be limited to 10 ft. long webs or less.
6. All plates are MITEK MT20 pressed into both faces of truss.
7. All lumber to be SPF (or D-Fir) DRY and of No.2 grade or better.
8. Additional building bracing is typically installed to brace the face of the end wall assembly. See BCSI Canada 'Building Designer Responsibilities for Gable End Frame Bracing' for additional information on building bracing for gable-end assemblies.

PEO
Certificate No. 10889485



RECEIVED
Per: joshua.nabua