


| | | Products | | |
|--------|----------|--|-------|---------|
| PlotID | Length | Product | Plies | Net Qty |
| J1 | 12-00-00 | 9 1/2" NI-40x | 1 | 23 |
| J1DJ | 12-00-00 | 9 1/2" NI-40x | 2 | 12 |
| J2 | 10-00-00 | 9 1/2" NI-40x | 1 | 31 |
| J3 | 4-00-00 | 9 1/2" NI-40x | 1 | 3 |
| J4 | 18-00-00 | 9 1/2" NI-80 | 1 | 1 |
| B2 | 6-00-00 | 1 3/4" x 9 1/2" (2.0E 3100) WestFraser LVL | 1 | 1 |
| B3 | 4-00-00 | 1 3/4" x 9 1/2" (2.0E 3100) WestFraser LVL | 1 | 1 |
| B1 | 4-00-00 | 1 3/4" x 9 1/2" (2.0E 3100) WestFraser LVL | 2 | 2 |

| Connector Summary | | | | | | | | | |
|-------------------|-----------|--|--|--|--|--|--|--|--|
| Qty | Manuf | Product | | | | | | | |
| 5 | H1 | IUS2.56/9.5 | | | | | | | |
| 6 | H1 | IUS2.56/9.5 | | | | | | | |
| 6 | H1 | IUS2.56/9.5 | | | | | | | |
| 2 | H3 | HU310-2 | | | | | | | |
| | Qty 5 6 6 | Qty Manuf 5 H1 6 H1 6 H1 | | | | | | | |



THIS IS A FLOOR COMPONENT PLACEMENT PLAN ONLY.

The wood beams and joists outlined on this plan are designed as individual building components to be incorporated into the design of the building at the specification of the building designer. Please see the individual beam reports, joist reports, and/or joist span tables for each component identified on this placement plan. The supporting structure is to be specified by the building designer prior to the

The supporting structure is to be specified by the building designer prior to the installation of joist(s) and/or beam(s). The building designer is responsible for the bracing of the floor system and its integration into the bracing of the overall structure. All components labelled "by others" or "as per plan", and all steel beams, and within the scope of work of this seal.

are not within the scope of work of this seal.

The building designer must review and approve this plan to acertain conformity to the overall structural plan of the building. All dimensions to be verified on site.

DATE: 2022-07-18

1st FLOOR FRAMING



FROM PLAN DATED: 2022/05
BUILDER: GREENPARK HOMES
SITE: BARLASSINA CONSTRUCTION

MODEL: GARDEN 11 ELEVATION: 1

L**OT**: 65

UI: 65

CITY: CAMBRIDGE

SALESMAN: RICK DICIANO

DESIGNER: AJ REVISION:

REFER TO THE NORDIC INSTALLATION GUIDE FOR PROPER STORAGE AND INSTALLATION. SQUASH BLOCKS OF 2x4, 2x6, 2x8 SPF #2 REQ'D UNDER INTERIOR UNIFORM LOAD BEARING WALLS. MULTIPLE SQUASH BLOCKS REQ'D UNDER CONCENTRATED LOADS. SEE FIGURE 1. CANTILEVERED JOISTS INCLUDING CANT' OVER

BRICK REQ. I-JOIST BLOCKING ALONG BEARING AND RIMBOARD CLOSURE AT ENDS. SEE FIGURES 4/5 FOR REINFORCEMENT REQUIREMENTS. FOR HOLES INCLUDING DUCT CHASE AND FIELD CUT OPENINGS SEE FIGURE 6 AND TABLES 6.1/6.2. CERAMIC TILE APPLICATION AS PER OBC 9.30.6.

ALL CONNECTORS MUST BE INSTALLED AS PER THE MANUFACTURER'S SPECIFICATIONS USING THE MANUFACTURER SPECIFIED FASTENERS.


ALL BEAM HANGER FASTENERS INSTALLED INTO THE SUPPORTING MEMBER MUST BE A MINIMUM OF 3.5" IN LENGTH UNLESS OTHERWISE SPECIFIED BY THE SUPPORTING MEMBER ENGINEER OF RECORD

LOADING:

LIVE LOAD: 40.0 lb/ft²
DEAD LOAD: 15.0 lb/ft²
TILE LOAD: +5.0 lb/ft²

JOIST LL DEFLECTION LIMIT: L/480

SUBFLOOR: 3/4" GLUED AND NAILED



| | | Products | | |
|--------|----------|--|-------|---------|
| PlotID | Length | Product | Plies | Net Qty |
| J1 | 12-00-00 | 9 1/2" NI-40x | 1 | 54 |
| J2 | 10-00-00 | 9 1/2" NI-40x | 1 | 27 |
| J3 | 6-00-00 | 9 1/2" NI-40x | 1 | 1 |
| B5 | 10-00-00 | 1 3/4" x 9 1/2" (2.0E 3100) WestFraser LVL | 2 | 2 |
| B7 | 6-00-00 | 1 3/4" x 9 1/2" (2.0E 3100) WestFraser LVL | 1 | 1 |
| B6 | 2-00-00 | 1 3/4" x 9 1/2" (2.0E 3100) WestFraser LVL | 1 | 1 |
| B4 DR | 20-00-00 | 1 3/4" x 14" (2.0E 3100) WestFraser LVL | 3 | 3 |

| | Connector | Summary | | | | |
|-----|-----------|-------------|--|--|--|--|
| Qty | Product | | | | | |
| 1 | H1 | IUS2.56/9.5 | | | | |
| 9 | H1 | IUS2.56/9.5 | | | | |
| 1 | H2 | HUS1.81/10 | | | | |
| 9 | H1 | IUS2.56/9.5 | | | | |



THIS IS A FLOOR COMPONENT PLACEMENT PLAN ONLY.

The wood beams and joists outlined on this plan are designed as individual building components to be incorporated into the design of the building at the specification of the building designer. Please see the individual beam reports, joist reports, and/or joist span tables for each component identified on this placement plan.

joist span tables for each component identified on this placement plan.

The supporting structure is to be specified by the building designer prior to the installation of joist(s) and/or beam(s). The building designer is responsible for the bracing of the floor system and its integration into the bracing of the overall structure. All components labelled "by others" or "as per plan", and all steel beams, are not within the scone of work of this seal.

are not within the scope of work of this seal.

The building designer must review and approve this plan to acertain conformity to the overall structural plan of the building. All dimensions to be verified on site.

DATE: 2022-07-18

2nd FLOOR FRAMING



FROM PLAN DATED: 2022/05
BUILDER: GREENPARK HOMES
SITE: BARLASSINA CONSTRUCTION

MODEL: GARDEN 11 ELEVATION: 1

L**OT**: 65

CITY: CAMBRIDGE

SALESMAN: RICK DICIANO

DESIGNER: AJ REVISION:

REFER TO THE NORDIC INSTALLATION GUIDE FOR PROPER STORAGE AND INSTALLATION. SQUASH BLOCKS OF 2x4, 2x6, 2x8 SPF #2 REQ'D UNDER INTERIOR UNIFORM LOAD BEARING WALLS. MULTIPLE SQUASH BLOCKS REQ'D UNDER CONCENTRATED LOADS. SEE FIGURE 1. CANTILEVERED JOISTS INCLUDING CANT' OVER BRICK REQ. I-JOIST BLOCKING ALONG BEARING

AND RIMBOARD CLOSURE AT ENDS. SEE FIGURES 4/5 FOR REINFORCEMENT REQUIREMENTS. FOR HOLES INCLUDING DUCT CHASE AND FIELD CUT OPENINGS SEE FIGURE 6 AND TABLES 6.1/6.2. CERAMIC TILE APPLICATION AS PER OBC 9.30.6.

ALL CONNECTORS MUST BE INSTALLED AS PER THE MANUFACTURER'S SPECIFICATIONS USING THE MANUFACTURER SPECIFIED FASTENERS.

ALL BEAM HANGER FASTENERS INSTALLED INTO THE SUPPORTING MEMBER MUST BE A MINIMUM OF 3.5" IN LENGTH UNLESS OTHERWISE SPECIFIED BY THE SUPPORTING MEMBER ENGINEER OF RECORD

LOADING:

LIVE LOAD: 40.0 lb/ft²
DEAD LOAD: 15.0 lb/ft²
TILE LOAD: +5.0 lb/ft²

JOIST LL DEFLECTION LIMIT: L/480

SUBFLOOR: 5/8" GLUED AND NAILED

NORDIC

INSTALLATION GUIDE NORDIC JOIST NS-GI33 **■**◆■

VERSION 2020-10-01

Engineered Wood Products

BASIC INSTALLATION **GUIDE FOR RESIDENTIAL FLOORS**

NORDIC **U**JOIST

NORDIC **STRUCTURES**

WEB STIFFENERS

nordic.ca

INSTALLING NORDIC I-JOISTS

- Except for cutting to length, I-joist flanges should never be cut, drilled or notched
- Install I-joists so that top and bottom flanges are within 1/2 inch of true vertical alignment
- Concentrated loads should only be applied to the top surface of the top flange. Concentrated loads should not be suspended from the bottom flange with the exception of light loads, such as ceiling fans or light fixtures.
- I-joists must be protected from the weather prior to installation.
- I-joists must not be used in applications where they will be permanently exposed to weather, or will reach a moisture content of 15 percent or greater, such as in swimming pool or hot tub areas. They must not be installed where they will remain in direct contact with
- End bearing length must be at least 1-3/4 inch. For multiple-span joists, intermediate bearing length must be at least 3-1/2 inches.
- I-joists installed beneath bearing walls perpendicular to the joists shall have full-depth blocking panels, rim board, or squash blocks (cripple blocks) to transfer gravity loads from above the floor system to the wall or foundation below.
- For I-inists installed directly beneath bearing walls parallel to the joists or used as rim board or blocking panels, the using a single I-joist is 3.300 plf, and 6.600 plf if double I-joists are used.
- . Continuous lateral support of the I-joist's compression flange is required to prevent rotation and buckling. In simple span uses, lateral support of the top flange is normally supplied by the floor sheathing. In multiple-span or cantilever applications, bracing of the I-joist's bottom flange is also required at interior supports of multiple-span joists, and at the end support next to the cantilever extension. The ends of all cantilever extensions must be laterally braced as shown in details 3, 4, or 5,
- . Nails installed in flange face or edge shall be spaced in accordance with the applicable building code requirements or approved building plans, but should not be closer than those specified on page 3.3 of the Nordic Joist Technical Guide (NS-GT3).
- B. Details 1 show only I-joist-specific fastener requirements. For other fastener requirements, see the applicable building code.
- 4. For proper temporary bracing of wood I-joists and placement of temporary construction loads, see APA Technical Note: Temporary Construction Loads over I-Joist Roofs and Floors, Form J735.

All nails shown in the details are assumed to be common nails unless otherwise noted. Nails shall have a diameter not less than 0.128 inch for 2-1/2-inch nails, or 0.144 inch for 3-inch nails. ndividual components not shown to scale for clarity.

1b

1

2×3 S-P-F No. 2


NORDIC I-JOIST SERIES RESIDENTIAL SERIES

2x3 1950f MSR 3/8 in. web 33 pieces per unit



1d

1k



2x plate flush with inside face of wall or beam. 1/8" overhang allowed past inside face of wall or beam.

SAFETY AND CONSTRUCTION PRECAUTIONS

Avoid Accidents by Following these Important Guidelines

of I-ioists at the end of the bay.

rim board, or cross-bridging.

Never install a damaged I-joist

-joists are not stable until completely installed, and will not carry any load until fully brace

I. Brace and nail each I-joist as it is installed, using hangers, blocking panels, rim board, and

or cross-bridging at joist ends. When I-joists are applied continuous over interior supports

2. When the building is completed, the floor sheathing will provide lateral support for the top

or temporary sheathing must be applied to prevent I-joist rollover or buckling. Temporary bracing or struts must be 1x4 inch minimum, at least 8 feet long and spaced

system. Then, stack building materials over beams or walls only.

flanges of the I-joists. Until this sheathing is applied, temporary bracing, often called struts,

no more than 8 feet on centre, and must be secured with a minimum of two 2-1/2-inch nails fastened to the top surface of each I-joist. Nail the bracing to a lateral restraint at the end of each bay. Lap ends of adjoining bracing over at least two I-joists.

Or, sheathing (temporary or permanent) can be nailed to the top flange of the first 4 feet

3. For cantilevered I-joists, brace top and bottom flanges, and brace ends with closure panels

Improper storage or installation, failure to follow applicable building codes, failure to follow span ratings for Nordic I-joists, failure to follow allowable hole sizes and locations, or failure

to use web stiffeners when required can result in serious accidents. Follow these installation

aring wall is planned at that location, blocking will be required at the interior

NI-90 2x4 2400f MSR 7/16 in. web

Width 1-1/8 in. APA Rim Board Plus

RIM BOARDS

Do not walk on I-joist

Never stack building

braced or serious


until fully fastened an

WEB HOLES AND OPENINGS

WEB HOLES IN I-JOISTS

- Rules for Cutting Holes in I-Joists The distance between the inside edge of the support and the centreline of any hole shall be in compliance with the requirement of Table 6.1.

- A 1-1/2 inch hole or smaller can be placed anywhere in the web provide
- materials over unsheathed I-joists Once sheathed, do no overstress I-joist with



DUCT CHASE OPENINGS


6b

Rules for Cutting Duct Chase Openings in I-joists

- The distance between the inside edge of the support and the co duct chase opening shall be in compliance with the requiremen
- I-joist top and bottom flanges must never be cut, notched or otherwise mo
- The maximum depth of a duct chase opening that can be cut into an I-joist web shall equal the clear distance between the flanges of the I-joist minus 1/4 inch. A minimum of 1/8 inch should always be maintained between the top or bottom of the opening and the adjacent I-joist flange. Holes cut into the blocking panels are subject to the following limitations The top and bottom flanges of an I-joist blocking panel must never be cut,
- All openings shall be cut in accordance with the restrictions listed above and as illustrated in detail 6b.


Allowable Hole Size in Lateral-restraint-only Blocking Panels

HOLES IN BLOCKING PANELS



| I-joist or rim board blocking depth (in.) | Maximum allowable hole diameter (in.) ^(a) |
|--|---|
| 9-1/2 | 6-1/4 |
| 11-7/8 | 7-3/4 |
| 14 | 9-1/4 |
| | |

TABLE 6.1 - LOCATION OF WEB HOLES



| I-joist depth (in.) | Maximum depth of the opening (in.) |
|---------------------|------------------------------------|
| 9-1/2 | 6-1/4 |
| 11-7/8 | 8-5/8 |
| 14 | 10-3/4 |
| 16 | 12-3/4 |

Minimum 1/8" space between top or bottom flange and openin

| | imple or multiple span Inimum distance from inside face of any support to centre of hole (ft-in.) | | | | | | | | | | | | | | Simple spa Minimum di | | |
|---------|--|-------------------------------|--------|--------|-------|--------|-------|-------|--------|--------|-------|--------|--------|---|--------------------------|--------|---------|
| Joist | Joist | ist Round hole diameter (in.) | | | | | | | | | | | Joist | | | | |
| depth | series | | | | | | 6-1/4 | | | 8-5/8 | | 10 | 10-3/4 | | 12 | 12-3/4 | depth : |
| | NI-20 | 0'-7" | 1'-6" | 2'-10" | 4'-3" | 5'-8" | 6'-0" | - | - | - | - | - | - | - | - | - | |
| 0.4/07 | NI-40x | 0'-7" | 1'-6" | 3'-0" | 4'-4" | 6'-0" | 6'-4" | - | - | - | - | - | - | - | - | - | 9-1/2" |
| 9-1/2" | NI-60 | 1'-3" | 2'-6" | 4'-0" | 5'-4" | 7'-0" | 7'-5" | - | - | - | - | - | - | - | - | - | 9-1/2 |
| | NI-80 | 2'-3" | 3'-6" | 5'-0" | 6'-6" | 8'-2" | 8'-8" | - | - | - | - | - | - | - | - | - | |
| | NI-20 | 0'-7" | 0'-8" | 1'-0" | 2'-4" | 3'-8" | 4'-0" | 5'-0" | 6'-6" | 7'-9" | - | - | - | - | - | - | |
| | NI-40x | 0'-7" | 0'-8" | 1'-3" | 2'-8" | 4'-0" | 4'-4" | 5'-5" | 7'-0" | 8'-4" | - | - | - | - | - | - | |
| 11-7/8" | NI-60 | 0'-7" | 1'-8" | 3'-0" | 4'-3" | 5'-9" | 6'-0" | 7'-3" | 8'-10" | 10'-0" | - | - | - | - | - | - | 11-7/8" |
| | NI-80 | 1'-6" | 2'-10" | 4'-2" | 5'-6" | 7'-0" | 7'-5" | 8'-6" | 10'-3" | 11'-4" | - | - | - | - | - | - | |
| | NI-90 | 0'-7" | 0'-8" | 1'-5" | 3'-2" | 4"-10" | 5'-4" | 6'-9" | 8'-9" | 10'-2" | - | - | - | - | - | - | |
| | NI-40x | 0'-7" | 0"-8" | 0'-8" | 1'-0" | 2'-4" | 2'-9" | 3'-9" | 5'-2" | 6'-0" | 6'-6" | 8'-3" | 10'-2" | - | - | - | |
| | NI-60 | 0'-7" | 0'-8" | 1'-8" | 3'-0" | 4'-3" | 4'-8" | 5'-8" | 7'-2" | 8'-0" | 8'-8" | 10'-4" | 11'-9" | - | - | - | |

| Design Criteria | | |
|-------------------|--|--|
| Joist spacing | Up to 24 inches | |
| Loads | Live load = 40 psf and dead load = 15 psf | |
| Deflection limits | L/480 under live load and L/240 under total load | |


TABLE 6.2 - LOCATION OF DUCT CHASE OPENINGS


| aeptn | series | 8 | 10 | 12 | 14 | 16 | 18 | 20 | 22 | 24 |
|---------|--------|----------|---------|--------|---------|---------|--------|--------|--------|-------|
| | NI-20 | 4'-1" | 4'-5" | 4'-10" | - | - | - | - | - | - |
| 0.4/01 | NI-40x | 5'-3" | 5'-8" | 6'-0" | 6'-5" | 6'-10" | 7'-3" | 7'-8" | - | - |
| 9-1/2" | NI-60 | 5'-4" | 5'-9" | 6'-2" | 6'-7" | 7'-1" | 7'-5" | 8'-0" | - | - |
| | NI-80 | 5'-3" | 5'-8" | 6'-0" | 6'-5" | 6'-10" | 7'-3" | 7'-8" | 8'-2" | 8'-6" |
| | NI-20 | 5'-9" | 6'-2" | 6'-6" | - | - | - | - | - | - |
| | NI-40x | 6'-8" | 7'-2" | 7'-6" | 8'-1" | 8'-6" | 9'-1" | 9'-6" | - | - |
| 11-7/8" | NI-60 | 7'-3" | 7'-8" | 8'-0" | 8'-6" | 9'-0" | 9'-3" | 9'-9" | - | - |
| | NI-80 | 7'-2" | 7'-7" | 8'-0" | 8'-5" | 8'-10" | 9'-3" | 9'-8" | 10'-2" | 10'-8 |
| | NI-90 | 7'-6" | 7'-11" | 8'-4" | 8'-9" | 9'-2" | 9'-7" | 10'-1" | 10'-7" | 10'-1 |
| 14" | NI-40x | 8'-1" | 8'-7" | 9'-0" | 9'-6" | 10'-1" | 10'-7" | 11'-2" | - | - |
| | NI-60 | 8'-9" | 9'-3" | 9'-8" | 10'-11" | 10'-6" | 11'-1" | 11'-6" | - | - |
| 14" | NI-80 | 9'-0" | 9'-3" | 9'-9" | 10'-1" | 10'-7" | 11'-1" | 11'-6" | 12'-1" | 12'-€ |
| | NI-90 | 9'-2" | 9'-8" | 10'-0" | 10'-6" | 10'-11" | 11'-5" | 11'-9" | 12'-4" | 12'-1 |
| | NI-60 | 10'-3" | 10'-8" | 11'-2" | 11'-6" | 12'-1" | 12'-6" | 13'-2" | - | - |
| 16" | NI-80 | 10'-4" | 10'-9" | 11'-3" | 11'-9" | 12'-1" | 12'-7" | 13'-1" | 13'-8" | 14'-4 |
| | NI-90 | 10'-9" | 11'-2" | 11'-8" | 12'-0" | 12'-6" | 13'-0" | 13'-6" | 14'-2" | 14'-1 |
| | | D! 0 | | | | | | | | |
| | | Design C | riteria | | | | | | | |


RIM BOARDS 8a


8f

















-JOIST MARKING

| Flange width (in.) | Material thickness required (in.) (a) | Minimum depth (in.) |
|--------------------|--|---------------------|
| 2-1/2 | 1 | 5-1/2 |
| 3-1/2 | 1-1/2 | 7-1/4 |








2-1/8 to 2-1/4 x 6 2x6 + 5/8" or 3/4" she 2-1/8 to 2-1/4 x 8 2x8 + 5/8" or 3/4" she 2-1/8 to 2-1/4 x 10 2x10 + 5/8" or 3/4" she 2-1/8 to 2-1/4 x 12 2x12 + 5/8" or 3/4" sheathing 2 x 2x10 2 x 2x12

1s-1

FOR ALL construction details \rightarrow DC3


Certified by APA Number I JOIST AGA



NAIL SPACING

1h

1 x 2-5/16 Minimum width 1-1/2 x 2-5/16 Minimum width



1g



CITY:

GREENPARK HOMES BARLASSINA CONSTRUCTION

> **GARDEN 11 CAMBRIDGE**

Job Name: GARDEN 11 EL 1 Level: 2ND FLR FRAMING

Label: B4 DR - i578


Type: **Beam**

3 Ply Member 1 3/4" x 14" (2.0E 3100) WestFraser LVL

Status: Design Passed

Designed by Single Member Design Engine in MiTek® Structure Version Illustration Not to Scale. Pitch: 0/12 8.5.3.233.Update5.15

Report Version: 2021.03.26 06-24-2022 07:42



DESIGN INFORMATION

Building Code: NBCC 2015, Part9, BCBC 2018, ABC 2019, OBC 2012 (2019

Amendment)

Design Methodology: LSD Service Condition: Dry LL Deflection Limit: L/360, TL Deflection Limit: L/240.

Lateral Restraint Requirements:

Both ends of the member and the outer supports must be laterally restrained. Top and bottom edges of the member must be fully restrained or have the following maximum unbraced length:

Top: 1'- 2 5/8" Bottom: 18'- 7'

Factored Resistance of Support Material:

- 812 psi Wall @ 0'- 2 1/2"
- 812 psi Wall @ 18'- 4 9/16"

PLY TO PLY CONNECTION: 5 ROWS OF 3.25" PNEUMATIC GUN NAILS (0.120"x3.25") @ 12" O/C

NAIL FROM BOTH FACES (STAGGER 1/2 SPACE)

PLY TO PLY CONNECTION ASSUMES ANY SUPPORTED BEAM HANGERS ARE FASTENED TO THIS BEAM WITH MIN. 3.5" FASTENERS.



| l | ANALYSIS RESULTS | | | | | | |
|---|-----------------------------|--------------|------------------|------|-------------|-------------|----------------|
| 1 | Design Criteria | Location | Load Combination | LDF | Design | Limit | Result |
| l | Factored Pos. Moment: | 9'- 3 3/8" | 1.25D + 1.5L | 1.00 | 36779 lb ft | 72216 lb ft | Passed - 51% |
| l | Factored Shear: | 17'- 1 9/16" | 1.25D + 1.5L | 1.00 | 7470 lb | 24431 lb | Passed - 31% |
| l | Live Load (LL) Pos. Defl.: | 9'- 3 9/16" | L | | 0.429" | L/360 | Passed - L/504 |
| l | Total Load (TL) Pos. Defl.: | 9'- 3 9/16" | D + L | | 0.665" | L/240 | Passed - L/325 |
| ١ | Permanent Deflection: | 9'- 3 9/16" | | | - | L/360 | Passed - L/943 |

| St | JPPORT ANI | D REACTION INFORM | IATION | | | | | |
|----|----------------------------|---------------------------------|--------|----------------------------------|--------------------------------|-------------------------------------|--------------------------------------|--------------|
| ID | Input Bearing Length | Controlling Load Combination | LDF | Factored Downward Reaction | Factored Uplift Reaction | Factored Resistance of Member | Factored Resistance of Support | Result |
| 1 | 3-08 | 1.25D + 1.5L | 1.00 | 8438 lb | | 19110 lb | 14920 lb | Passed - 57% |
| 2 | 3-07 | 1.25D + 1.5L | 1.00 | 8119 lb | | 18655 lb | 14565 lb | Passed - 56% |
| CI | | ADC | | | | | | |

| SPI | ECIFIED LOA | กร | | | | | | |
|-----------|-----------------|-------------|---------------|------|-----------|-----------|----------|----------|
| Ту | pe Start Loc | End Loc | Source | Face | Dead (D) | Live (L) | Snow (S) | Wind (W) |
| Se Wei | | 18'- 7" | Self Weight | Тор | 21 lb/ft | - | - | - |
| Unifo | orm 1'- 1" | 13'- 9 3/8" | Smoothed Load | Top | 211 lb/ft | 422 lb/ft | - | - |
| Unifo | orm 13'- 9 3/8" | 18'- 5" | Smoothed Load | Top | 93 lb/ft | 187 lb/ft | - | - |
| Poi | int 0'- 3 3/8" | 0'- 3 3/8" | J2(i679) | Тор | 95 lb | 190 lb | - | - |
| Poi | int 0'- 5" | 0'- 5" | J1(i656) | Top | 134 lb | 267 lb | - | - |
| Poi | int 14'- 3 3/8" | 14'- 3 3/8" | J2(i999) | Top | 86 lb | 171 lb | - | - |
| Poi | int 15'- 1" | 15'- 1" | J2(i641) | Top | 102 lb | 203 lb | - | - |
| Poi | int 16'- 5" | 16'- 5" | J2(i621) | Top | 127 lb | 254 lb | - | - |
| Poi | int 17'- 9" | 17'- 9" | J2(i662) | Тор | 127 lb | 254 lb | - | - |

| ı | UNFA | CTORED RE | ACTIONS | | | | | |
|---|------|--------------|------------|----------|----------|----------|----------|----------|
| ı | ID | Start Loc | End Loc | Source | Dead (D) | Live (L) | Snow (S) | Wind (W) |
| ı | 1 | 0' | 0'- 3 1/2" | 13(i393) | 2117 lb | 3850 lb | - | - |
| l | 2 | 18'- 3 9/16" | 18'- 7" | 12(i391) | 2049 lb | 3716 lb | - | - |

DESIGN NOTES

- · The dead loads used in the design of this member were applied to the structure as sloped dead loads.
- Lateral stability factor (KL) was based on user preference to use the width of all plies. (Consult with manufacturer for guideline pertaining to this design option.)
- Analysis and Design has been performed using precision loading from actual modeled conditions. Some loads may have been modified to simplify reporting.
- Tributary Loads have been generated based on actual spacing between members in the model which may differ from the default system spacing. The actual loads applied to the member are shown in the Specified Loads table.
- Transfer reactions may differ from design results as allowed per building codes and standard load distribution practices.
- This report is based on modeled conditions input by the user. Source information for the loads and supports are provided for reference only. Verify that all loads and support conditions are correct.
- Review all loads and reactions to ensure that the member/bearing/connector/structure can resist adequately. Unless already specified on this report, anchorage for uplift reactions to be specified by others. Installation of member and accessories (if required) as per manufacturer's instruction.
- When the applied loads are coming from a member/post/wall above that does not sit directly on this beam, adequate load transfer elements, such as squash blocks, wall studs, or beveled plates are required to transfer the loads to this beam.

PLY TO PLY CONNECTION

Member design assumed proper ply to ply connection by others. Fastener spacing along length of member must not exceed 4 times depth of member. Verify connection between plies according to code specification and follow the manufacturer's installation instruction. Loads assumed to be distributed equally to each ply.



CITY:

GREENPARK HOMES BARLASSINA CONSTRUCTION


GARDEN 11 CAMBRIDGE Job Name: GARDEN 11 EL 1 Level:

Label: B5 - i1104 Type: **Beam**

2ND FLR FRAMING

2 Ply Member 1 3/4" x 9 1/2" (2.0E 3100) WestFraser LVL

Status: Design Passed



DESIGN INFORMATION

Building Code: NBCC 2015, Part9, BCBC 2018, ABC 2019, OBC 2012 (2019

Amendment)

Design Methodology: LSD Service Condition: Dry LL Deflection Limit: L/360, TL Deflection Limit: L/240.

Lateral Restraint Requirements:

Both ends of the member and the outer supports must be laterally restrained. Top and bottom edges of the member must be fully restrained or have the following maximum unbraced length:

Bottom: 0'- 9 1/2" Top: 0'

Factored Resistance of Support Material:

- 615 psi Wall @ 0'- 2 1/2"
- 615 psi Wall @ 9'- 6"

| PLY TO PLY CONNECTION: |
|-------------------------------|
| 3 ROWS OF 3.25" PNEUMATIC GUN |
| NAILS (0.120"x3.25") @ 8" O/C |

PLY TO PLY CONNECTION ASSUMES ANY SUPPORTED BEAM HANGERS ARE FASTENED TO THIS BEAM WITH MIN. 3.5" FASTENERS.



| 1 | ANALYSIS RESULTS | | | | | | |
|--------------|----------------------------|-------------|------------------|------|------------|-------------|----------------|
| \mathbb{H} | Design Criteria | Location | Load Combination | LDF | Design | Limit | Result |
| F | actored Pos. Moment: | 4'- 10" | 1.25D + 1.5L | 1.00 | 5593 lb ft | 23299 lb ft | Passed - 24% |
| F | actored Shear: | 8'- 7 1/2" | 1.25D + 1.5L | 1.00 | 2275 lb | 11052 lb | Passed - 21% |
| Li | ive Load (LL) Pos. Defl.: | 4'- 10 1/2" | L | | 0.081" | L/360 | Passed - L/999 |
| To | otal Load (TL) Pos. Defl.: | 4'- 10 1/2" | D + L | | 0.126" | L/240 | Passed - L/870 |

| l | SUP | PORT AND | REACTION INFORM | ATION | | | | | |
|---|-----|----------------------------|---------------------------------|-------|----------------------------------|--------------------------------|-------------------------------------|--------------------------------------|--------------|
| | ID | Input Bearing Length | Controlling Load Combination | LDF | Factored Downward Reaction | Factored Uplift Reaction | Factored Resistance of Member | Factored Resistance of Support | Result |
| l | 1 | 3-08 | 1.25D + 1.5L | 1.00 | 2263 lb | | 12740 lb | 7536 lb | Passed - 30% |
| ١ | 2 | 5-08 | 1.25D + 1.5L | 1.00 | 2328 lb | | 20020 lb | 11842 lb | Passed - 20% |
| l | SPE | CIFIED LO | ADS | | | | | | |

| Туре | Start Loc | End Loc | Source | Face | Dead (D) | Live (L) | Snow (S) | Wind (W) |
|----------------|------------|-------------|---------------------------------------|-------|------------------|------------------|----------|----------|
| Self Weight | 0' | 9'- 10 1/2" | Self Weight | Тор | 9 lb/ft | - | - | - |
| Uniform | 0'- 3 1/2" | 0'- 10" | FC2 Floor Decking (Plan View Fill) | Тор | 3 lb/ft | 6 lb/ft | - | - |
| Uniform | 4'- 10" | 5'- 7 1/4" | FC2 Floor Decking (Plan View Fill) | Тор | 3 lb/ft | 6 lb/ft | - | - |
| Uniform | 5'- 7 1/4" | 9'- 7 7/8" | FC2 Floor Decking (Plan View Fill) | Тор | 9 lb/ft | 18 lb/ft | - | - |
| Tapered | 0'- 4" | 9'- 4" | Smoothed Load | Front | 111 To 108 lb/ft | 220 To 217 lb/ft | - | - |
| Point | 5'- 8 1/8" | 5'- 8 1/8" | B6(i1192) | Back | 31 lb | 54 lb | - | - |
| Point | 0'- 3 1/2" | 0'- 3 1/2" | FC2 Floor Decking (Plan View Fill) | Тор | 1 lb | 1 lb | - | - |

| l | UNFAC | CTORED RI | EACTIONS | , | | | | |
|---|-------|-----------|-------------|----------|----------|----------|----------|----------|
| l | ID | Start Loc | End Loc | Source | Dead (D) | Live (L) | Snow (S) | Wind (W) |
| l | 1 | 0' | 0'- 3 1/2" | 11(i392) | 569 lb | 1042 lb | - | - |
| l | 2 | 9'- 5" | 9'- 10 1/2" | 10(i390) | 580 lb | 1060 lb | - | - |

DESIGN NOTES

- The dead loads used in the design of this member were applied to the structure as sloped dead loads.
- Lateral stability factor (KL) was based on user preference to use the width of all plies. (Consult with manufacturer for guideline pertaining to this design option.)
- Analysis and Design has been performed using precision loading from actual modeled conditions. Some loads may have been modified to simplify reporting.
- Tributary Loads have been generated based on actual spacing between members in the model which may differ from the default system spacing. The actual loads applied to the member are shown in the Specified Loads table.
- Transfer reactions may differ from design results as allowed per building codes and standard load distribution practices.
- This report is based on modeled conditions input by the user. Source information for the loads and supports are provided for reference only. Verify that all loads and support conditions are correct.
- Review all loads and reactions to ensure that the member/bearing/connector/structure can resist adequately. Unless already specified on this report, anchorage for uplift reactions to be specified by others. Installation of member and accessories (if required) as per manufacturer's instruction.
- When the applied loads are coming from a member/post/wall above that does not sit directly on this beam, adequate load transfer elements, such as squash blocks, wall studs, or beveled plates are required to transfer the loads to this beam.

PLY TO PLY CONNECTION

Member design assumed proper ply to ply connection by others. Fastener spacing along length of member must not exceed 4 times depth of member. Verify connection between plies according to code specification and follow the manufacturer's installation instruction. Loads assumed to be distributed equally to each ply.



CITY:

GREENPARK HOMES
BARLASSINA CONSTRUCTION

GARDEN 11 CAMBRIDGE Job Name: **GARDEN 11 EL 1**Level: **2ND FLR FRAMING**

Label: **B6 - i1192** Type: **Beam**


1 Ply Member 1 3/4" x 9 1/2" (2.0E 3100) WestFraser LVL Status:

Design
Passed

Illustration Not to Scale. Pitch: 0/12

Designed by Single Member Design Engine in MiTek® Structure Version 8.5.3.233.Update5.15

Report Version: 2021.03.26 06-24-2022 07:42



DESIGN INFORMATION

Building Code: NBCC 2015, Part9, BCBC 2018, ABC 2019, OBC 2012 (2019

Amendment)

Design Methodology: LSD
Service Condition: Dry
LL Deflection Limit: L/360,
TL Deflection Limit: L/240,

Lateral Restraint Requirements:

Both ends of the member and the outer supports must be laterally restrained. Top and bottom edges of the member must be fully restrained or have the following maximum unbraced length:

Top: 0' Bottom: 1'- 1"

Factored Resistance of Support Material:

- 615 psi Beam @ 0'
- 615 psi Column @ 1'- 10 3/8"

| ı | ANALYSIS RESULTS | | | | | | | |
|---|-----------------------|-------------|------------------|------|----------|-------------|-------------|--|
| 1 | Design Criteria | Location | Load Combination | LDF | Design | Limit | Result | |
| l | Factored Pos. Moment: | 0'- 8 7/8" | 1.25D + 1.5L | 1.00 | 88 lb ft | 11650 lb ft | Passed - 1% | |
| l | Factored Shear: | 0'- 9 1/2" | 1.25D + 1.5L | 1.00 | 116 lb | 5526 lb | Passed - 2% | |
| ı | SUBBORT AND DEAC | TION INFORM | AATION | | | | | |

| l | SUP | PORT AND | REACTION INFORM | NOITAN | | | | | |
|---|-----|----------------------------|------------------------------|--------|----------------------------------|--------------------------------|-------------------------------------|--------------------------------------|-------------|
| | ID | Input Bearing Length | Controlling Load Combination | LDF | Factored Downward Reaction | Factored Uplift Reaction | Factored Resistance of Member | Factored Resistance of Support | Result |
| l | 1 | 1-08 | 1.25D + 1.5L | 1.00 | 121 lb | | 2730 lb | - | Passed - 4% |
| l | 2 | 1-12 | 1.25D + 1.5L | 1.00 | 82 lb | | 3185 lb | 1883 lb | Passed - 4% |

| ECTOR I | |
|---------|--|
| | |
| | |

| ın | Part No. | Manufacturar | Na | iling Requirem | ents | Other Information or Requirement for |
|----|------------|--------------|-----|----------------|--------|---|
| טו | Part No. | Manufacturer | Тор | Face | Member | Reinforcement Accessories |
| 1 | HUS1.81/10 | | - | - | - | Connector manually specified by the user. |

* Connectors: Refer to manufacturer's specifications, fasteners requirements and installation instruction. Where header fasteners are longer than the width of the supporting member, install backer block or clinch header nails.

| SPECIF | IED LOAD |)S | | | | | | | | | | | |
|----------------|----------------------|---------------|---------------------|-------|-------------------|-------------------|----------|----------|--|--|--|--|--|
| Туре | Start Loc | End Loc | Source | Face | Dead (D) | Live (L) | Snow (S) | Wind (W) | | | | | |
| Self Weight | 0' | 1'- 11 1/8" | Self Weight | Тор | 5 lb/ft | - | - | - | | | | | |
| Point | 0'- 8 7/8" | 0'- 8 7/8" | J3(i1197) | Front | 45 lb | 90 lb | - | - | | | | | |
| UNFAC | UNFACTORED REACTIONS | | | | | | | | | | | | |
| | | | | | | | | | | | | | |
| ID | Start Loc | End Loc | Source | | Dead (D) | Live (L) | Snow (S) | Wind (W) | | | | | |
| ID 1 | Start Loc 0' | End Loc 0' | Source B5(i1104) | | Dead (D) 31 lb | Live (L) 54 lb | Snow (S) | Wind (W) | | | | | |

DESIGN NOTES

- The dead loads used in the design of this member were applied to the structure as sloped dead loads.
- Analysis and Design has been performed using precision loading from actual modeled conditions. Some loads may have been modified to simplify reporting.
- Tributary Loads have been generated based on actual spacing between members in the model which may differ from the
 default system spacing. The actual loads applied to the member are shown in the Specified Loads table.
- · Transfer reactions may differ from design results as allowed per building codes and standard load distribution practices.
- This report is based on modeled conditions input by the user. Source information for the loads and supports are provided for reference only. Verify that all loads and support conditions are correct.
- Review all loads and reactions to ensure that the member/bearing/connector/structure can resist adequately. Unless already
 specified on this report, anchorage for uplift reactions to be specified by others. Installation of member and accessories (if
 required) as per manufacturer's instruction.
- When the applied loads are coming from a member/post/wall above that does not sit directly on this beam, adequate load transfer elements, such as squash blocks, wall studs, or beveled plates are required to transfer the loads to this beam.





BUILDER: SITE: MODEL: CITY: GREENPARK HOMES
BARLASSINA CONSTRUCTION

GARDEN 11 CAMBRIDGE Job Name: GARDEN 11 EL 1 Level: 2ND FLR FRAMING

Label: B7 - i1196 Type: Beam 1 Ply Member 1 3/4" x 9 1/2" (2.0E 3100) WestFraser LVL

Report Version: 2021.03.26


Status:

Design
Passed

06-24-2022 07:42

Illustration Not to Scale. Pitch: 0/12

Designed by Single Member Design Engine in MiTek® Structure Version 8.5.3.233.Update5.15



DESIGN INFORMATION

Building Code: NBCC 2015, Part9, BCBC 2018, ABC 2019, OBC 2012 (2019

Amendment)

Design Methodology: LSD
Service Condition: Dry
LL Deflection Limit: L/360,
TL Deflection Limit: L/240,

Lateral Restraint Requirements:

Both ends of the member and the outer supports must be laterally restrained. Top and bottom edges of the member must be fully restrained or have the following maximum unbraced length:

Top: 0'- 1 3/4" Bottom: 3'- 8"

Factored Resistance of Support Material:


- 615 psi Column @ 0'- 2 1/2"
- 615 psi Wall @ 4'- 1/2"

| AIVAL | TOIS IXESSE | 10 | | | | | | | |
|----------------|----------------------------|------------------------|---------------------------|---------|----------------------------------|--------------------------------|-------------------------------------|-------------|--------------|
| | Design Criteria | Loc | cation | Load | Combinatio | n LDF | Design | Limit | Result |
| Factore | d Pos. Moment | 2'- 1 | I 5/16" | 1.2 | 25D + 1.5L | 1.00 | 1033 lb ft | 11650 lb ft | Passed - 9% |
| Factore | d Shear: | 3 | '- 2" | 1.2 | 25D + 1.5L | 1.00 | 605 lb | 5526 lb | Passed - 11% |
| SUPP | ORT AND RE | ACTION | INFORM | TION | | | | | |
| ID | Input Bearing Length | Controlling Combina | | LDF | Factored Downward Reaction | Factored Uplift Reaction | Factored Resistance of Member | | Result |
| 1 | 3-08 | 1.25D + | 1.5L | 1.00 | 1051 lb | | 6370 lb | 3767 lb | Passed - 28% |
| 2 | 5-08 | 1.25D + | 1.5L | 1.00 | 1297 lb | | 10010 lb | 5921 lb | Passed - 22% |
| SPEC | IFIED LOADS | 6 | | | | | | | |
| Туре | Start Loc | End Loc | Source | | Face | Dead (D) | Live (L) | Snow (S) | Wind (W) |
| Self Weight | 0' | 4'- 5" | Self Wei | | Тор | 5 lb/ft | - | - | - |
| Uniform | 0'- 1 3/4" | 3'- 11 1/2" | FC2 Floor D (Plan View | | Тор | 13 lb/ft | 27 lb/ft | - | - |
| Uniform | 0'- 3 1/2" | 4'- 5" | ` User Lo | ad | Тор | 120 lb/ft | 240 lb/ft | - | - |
| Point | 3'- 11 1/2" | 3'- 11 1/2" | FC2 Floor D (Plan View | | Тор | 0 lb | 1 lb | - | - |
| UNFA | CTORED RE | ACTIONS | ; | | | | | | |
| ID | Start Loc | End Loc | Sc | urce | | Dead (D) | Live (L) | Snow (S) | Wind (W) |
| 1 | 0' | 0'- 3 1/2" | PBC | 1(i398) | | 258 lb | 496 lb | - | - |
| 2 | 3'- 11 1/2" | 4'- 5" | 7(| i354) | | 309 lb | 596 lb | <u> </u> | - |
| DESIG | GN NOTES | | | | | | | | |

DESIGN NOTES

ANALYSIS RESULTS

- The dead loads used in the design of this member were applied to the structure as sloped dead loads.
- Analysis and Design has been performed using precision loading from actual modeled conditions. Some loads may have been modified to simplify reporting.
- Tributary Loads have been generated based on actual spacing between members in the model which may differ from the
 default system spacing. The actual loads applied to the member are shown in the Specified Loads table.
- Transfer reactions may differ from design results as allowed per building codes and standard load distribution practices.
- This report is based on modeled conditions input by the user. Source information for the loads and supports are provided for reference only. Verify that all loads and support conditions are correct.
- Review all loads and reactions to ensure that the member/bearing/connector/structure can resist adequately. Unless already
 specified on this report, anchorage for uplift reactions to be specified by others. Installation of member and accessories (if
 required) as per manufacturer's instruction.
- When the applied loads are coming from a member/post/wall above that does not sit directly on this beam, adequate load
 transfer elements, such as squash blocks, wall studs, or beveled plates are required to transfer the loads to this beam.





CITY:

GREENPARK HOMES BARLASSINA CONSTRUCTION

GARDEN 11 CAMBRIDGE Job Name: GARDEN 11 EL 1

Type:

Level: **1ST FLR FRAMING**

Label: B1 - i1248 **Beam**

2 Ply Member 1 3/4" x 9 1/2" (2.0E 3100) WestFraser LVL


Report Version: 2021.03.26

Status: Design Passed

06-24-2022 07:42

Illustration Not to Scale. Pitch: 0/12

Designed by Single Member Design Engine in MiTek® Structure Version 8.5.3.233.Update5.15



DESIGN INFORMATION

Building Code: NBCC 2015, Part9, BCBC 2018, ABC 2019, OBC 2012 (2019

Amendment)

Design Methodology: LSD Service Condition: Dry LL Deflection Limit: L/360, TL Deflection Limit: L/240.

Lateral Restraint Requirements:

Both ends of the member and the outer supports must be laterally restrained. Top and bottom edges of the member must be fully restrained or have the following maximum unbraced length:

Bottom: 3'- 1" Top: 0'

Factored Resistance of Support Material:

- 615 psi Wall @ 0'- 2 1/2"
- 615 psi Wall @ 2'- 10 1/2"

PLY TO PLY CONNECTION: 3 ROWS OF 3.25" PNEUMATIC GUN NAILS (0.120"x3.25") @ 4" O/C

PLY TO PLY CONNECTION ASSUMES ANY SUPPORTED BEAM HANGERS ARE FASTENED TO THIS BEAM WITH MIN. 3.5" FASTENERS.



| ANALYSIS RESUL | .15 | | | | | |
|----------------------|------------------|------------------|----------|-----------|-------------|-------------|
| Design Criteria | Location | Load Combination | LDF | Design | Limit | Result |
| Factored Pos. Moment | : 1'- 6 1/2" | 1.25D + 1.5L | 0.72 | 192 lb ft | 16807 lb ft | Passed - 1% |
| Factored Shear: | 2' | 1.25D + 1.5L | 0.72 | 102 lb | 7972 lb | Passed - 1% |
| SUPPORT AND RI | EACTION INFORM | IATION | | | | |
| Input | Controlling Load | Factored | Factored | Factored | Factored | |

| l | ID | Bearing Length | Combina | | F Downwa Reaction | · | Resistance of Member | Resistance of Support | Result |
|---|----------------|-------------------|------------------------|-------------|----------------------|-----------|-------------------------|--------------------------|----------------------------|
| | 1 2 | 3-08 3-08 | 1.25D + 1 1.25D + 1 | | | | 9190 lb 9190 lb | 5436 lb 5436 lb | Passed - 6% Passed - 6% |
| ı | SPEC | IFIED LOAI | os | | | | | | |
| ı | Туре | Start Loc | End Loc | Source | Face | Dead (D) | Live (L) | Snow (S) | Wind (W) |
| ١ | Self Weight | 0' | 3'- 1" | Self Weight | Тор | 9 lb/ft | - | - | - |
| ı | Uniform | ո 0' | 3'- 1" | E8(i353) | Тор | 120 lb/ft | 29 lb/ft | - | - |

| Uniform | 0' | 3'- 1" | FC1 Floor Decking (Plan View Fill) | Тор | 4 lb/ft | 8 lb/ft | - | - |
|---------|------------|------------|---------------------------------------|-----|----------|----------|----------|----------|
| UNFAC | TORED RE | EACTIONS | S | | | | | |
| ID | Start Loc | End Loc | Source | | Dead (D) | Live (L) | Snow (S) | Wind (W) |
| 1 | 0' | 0'- 3 1/2" | W27(i27) | | 205 lb | 57 lb | - | - |
| 2 | 2'- 9 1/2" | 3'- 1" | W14(i13) | | 205 lb | 57 lb | - | - |
| DEGLON | LNOTEO | | | | | | | |

DESIGN NOTES

- The dead loads used in the design of this member were applied to the structure as sloped dead loads.
- · Lateral stability factor (KL) was based on user preference to use the width of all plies. (Consult with manufacturer for guideline pertaining to this design option.)
- Analysis and Design has been performed using precision loading from actual modeled conditions. Some loads may have been modified to simplify reporting.
- Tributary Loads have been generated based on actual spacing between members in the model which may differ from the default system spacing. The actual loads applied to the member are shown in the Specified Loads table.
- Transfer reactions may differ from design results as allowed per building codes and standard load distribution practices.
- This report is based on modeled conditions input by the user. Source information for the loads and supports are provided for reference only. Verify that all loads and support conditions are correct.
- Review all loads and reactions to ensure that the member/bearing/connector/structure can resist adequately. Unless already specified on this report, anchorage for uplift reactions to be specified by others. Installation of member and accessories (if required) as per manufacturer's instruction.
- When the applied loads are coming from a member/post/wall above that does not sit directly on this beam, adequate load transfer elements, such as squash blocks, wall studs, or beveled plates are required to transfer the loads to this beam.

PLY TO PLY CONNECTION

Member design assumed proper ply to ply connection by others. Fastener spacing along length of member must not exceed 4 times depth of member. Verify connection between plies according to code specification and follow the manufacturer's installation instruction. Loads assumed to be distributed equally to each ply.



CITY:

GREENPARK HOMES

GARDEN 11 CAMBRIDGE

BARLASSINA CONSTRUCTION

1ST FLR FRAMING Level: Label: B2 - i631

Job Name: GARDEN 11 EL 1

Type: **Beam**

1 Ply Member 1 3/4" x 9 1/2" (2.0E 3100) WestFraser LVL

Report Version: 2021.03.26

Status: Design Passed

06-24-2022 07:42

Illustration Not to Scale. Pitch: 0/12

Designed by Single Member Design Engine in MiTek® Structure Version 8.5.3.233.Update5.15

> 2 3-08 3-08-00

> > 4-05-00

DESIGN INFORMATION

NBCC 2015, Part9, BCBC 2018, **Building Code:** ABC 2019, OBC 2012 (2019

Amendment) Design Methodology: LSD Dry

Service Condition: LL Deflection Limit: L/360, TL Deflection Limit: L/240.

Lateral Restraint Requirements:

Both ends of the member and the outer supports must be laterally restrained. Top and bottom edges of the member must be fully restrained or have the following maximum unbraced length:

Bottom: 1'- 1 1/2" Top: 0'

Factored Resistance of Support Material:

- 615 psi Wall @ 0'- 2 1/2"
- 615 psi Wall @ 4'- 1/2"

| ANALYSIS RESULTS | | | | | | |
|-----------------------------|------------|------------------|------|------------|-------------|----------------|
| Design Criteria | Location | Load Combination | LDF | Design | Limit | Result |
| Factored Pos. Moment: | 2'- 6 1/4" | 1.25D + 1.5L | 1.00 | 1905 lb ft | 11650 lb ft | Passed - 16% |
| Factored Neg. Moment: | 4'- 1/2" | 1.25D + 1.5L | 1.00 | 123 lb ft | 11650 lb ft | Passed - 1% |
| Factored Shear: | 3'- 2" | 1.25D + 1.5L | 1.00 | 1791 lb | 5526 lb | Passed - 32% |
| Live Load (LL) Pos. Defl.: | 2'- 1 7/8" | L | | 0.010" | L/360 | Passed - L/999 |
| Total Load (TL) Pos. Defl.: | 2'- 1 7/8" | D + L | | 0.015" | L/240 | Passed - L/999 |
| SUPPORT AND REACT | ION INFOR | MATION | | | | |

| SUP | PORT AND | D REACTION INFORM | ATION | | | | | |
|-----|----------------------------|---------------------------------|-------|----------------------------------|--------------------------------|-------------------------------------|--------------------------------------|--------------|
| ID | Input Bearing Length | Controlling Load Combination | LDF | Factored Downward Reaction | Factored Uplift Reaction | Factored Resistance of Member | Factored Resistance of Support | Result |
| 1 | 3-08 | 1.25D + 1.5L | 1.00 | 2238 lb | | 6370 lb | 3768 lb | Passed - 59% |
| 2 | 5-08 | 1.25D + 1.5L | 1.00 | 3102 lb | | 10010 lb | 5921 lb | Passed - 52% |
| CDE | CIFIED I O | ADC | | | | | | |

| Ш | SPECIF | IED LOAD | S | | | | | | |
|------|----------------|------------|------------|---------------------------------------|-------|-----------|-----------|----------|----------|
| Ш | Туре | Start Loc | End Loc | Source | Face | Dead (D) | Live (L) | Snow (S) | Wind (W) |
| II | Self Weight | 0' | 4'- 5" | Self Weight | Тор | 5 lb/ft | - | - | - |
| Ш | Uniform | 0' | 4'- 11/16" | User Load | Top | 120 lb/ft | 240 lb/ft | - | - |
| $\ $ | Uniform | 3'- 3 1/2" | 4'- 5" | FC1 Floor Decking (Plan View Fill) | Тор | 4 lb/ft | 9 lb/ft | - | - |
| Ш | Point | 0'- 4 1/2" | 0'- 4 1/2" | J1DJ(i575) | Front | 112 lb | 225 lb | - | - |
| Ш | Point | 1'- 2 1/2" | 1'- 2 1/2" | J2(i1057) | Front | 108 lb | 216 lb | - | - |
| Ш | Point | 2'- 6 1/2" | 2'- 6 1/2" | J2(i1108) | Front | 104 lb | 208 lb | - | - |
| Ш | Point | 3'- 3 1/2" | 3'- 3 1/2" | J1DJ(i603) | Front | 257 lb | 462 lb | - | - |
| $\ $ | Point | 0'- 3 1/2" | 0'- 3 1/2" | FC1 Floor Decking (Plan View Fill) | Тор | 0 lb | 1 lb | - | - |
| $\ $ | Point | 0'- 4" | 0'- 4" | FC1 Floor Decking (Plan View Fill) | Тор | 0 lb | 0 lb | - | - |
| Ш | Point | 4'- 2 1/4" | 4'- 2 1/4" | 10(i390) | Top | 145 lb | 243 lb | - | - |
| IL | Point | 4'- 2 1/4" | 4'- 2 1/4" | FC1 Floor Decking (Plan View Fill) | Тор | 75 lb | 126 lb | - | - |

| UNFAC | TORED RE | EACTIONS | | | | | |
|-------|-------------|------------|----------|----------|----------|----------|----------|
| ID | Start Loc | End Loc | Source | Dead (D) | Live (L) | Snow (S) | Wind (W) |
| 1 | 0' | 0'- 3 1/2" | 4(i33) | 549 lb | 1070 lb | - | - |
| 2 | 3'- 11 1/2" | 4'- 5" | W24(i24) | 765 lb | 1395 lb | - | - |

DESIGN NOTES

- The dead loads used in the design of this member were applied to the structure as sloped dead loads.
- Analysis and Design has been performed using precision loading from actual modeled conditions. Some loads may have been modified to simplify reporting.
- Tributary Loads have been generated based on actual spacing between members in the model which may differ from the default system spacing. The actual loads applied to the member are shown in the Specified Loads table.
 - Transfer reactions may differ from design results as allowed per building codes and standard load distribution practices.
- This report is based on modeled conditions input by the user. Source information for the loads and supports are provided for reference only. Verify that all loads and support conditions are correct.
- Review all loads and reactions to ensure that the member/bearing/connector/structure can resist adequately. Unless already specified on this report, anchorage for uplift reactions to be specified by others. Installation of member and accessories (if required) as per manufacturer's instruction.
- When the applied loads are coming from a member/post/wall above that does not sit directly on this beam, adequate load transfer elements, such as squash blocks, wall studs, or beveled plates are required to transfer the loads to this beam.





CITY:

GREENPARK HOMES BARLASSINA CONSTRUCTION

GARDEN 11 CAMBRIDGE

1ST FLR FRAMING Label: B3 - i635 Type: **Beam**

Level:

Job Name: GARDEN 11 EL 1

1 Ply Member 1 3/4" x 9 1/2" (2.0E 3100) WestFraser LVL

Report Version: 2021.03.26

Status: Design Passed

06-24-2022 07:42

Illustration Not to Scale. Pitch: 0/12

Designed by Single Member Design Engine in MiTek® Structure Version 8.5.3.233.Update5.15

> 1 3-08 3-02-08

> > 3-09-08

DESIGN INFORMATION

NBCC 2015, Part9, BCBC 2018, **Building Code:** ABC 2019, OBC 2012 (2019

Amendment)

Design Methodology: LSD Service Condition: Dry LL Deflection Limit: L/360, TL Deflection Limit: L/240.

Lateral Restraint Requirements:

Both ends of the member and the outer supports must be laterally restrained. Top and bottom edges of the member must be fully restrained or have the following maximum unbraced length:

Bottom: 1'- 1 1/2" Top: 0'

Factored Resistance of Support Material:

- 615 psi Wall @ 0'- 2 1/2"
- 615 psi Wall @ 3'- 7"

| ANALI | SIS KESUL | 13 | | | | | | | |
|----------------|----------------------------|------------------------------|----------------|-------|----------------------------------|--------------------------------|------------|-------------|--------------|
| De | sign Criteria | Locat | ion | Load | Combinatio | n LDF | Design | Limit | Result |
| Factored | Pos. Moment: | 2'- 2 | 2" | 1.2 | 25D + 1.5L | 1.00 | 1327 lb ft | 11650 lb ft | Passed - 11% |
| Factored | Shear: | 1'- 1 | 1" | 1.2 | 25D + 1.5L | 1.00 | 1111 lb | 5526 lb | Passed - 20% |
| SUPPO | ORT AND RE | ACTION IN | IFORM <i>A</i> | TION | | | | | |
| ID B | Input searing ₋ength | Controlling L Combination | | LDF | Factored Downward Reaction | Factored Uplift Reaction | Resistance | | Result |
| 1 | 3-08 | 1.25D + 1. | 5L | 1.00 | 1670 lb | | 6370 lb | 3768 lb | Passed - 44% |
| 2 | 3-08 | 1.25D + 1. | 5L | 1.00 | 1935 lb | | 6370 lb | 3768 lb | Passed - 51% |
| SPECIF | FIED LOADS | 6 | | | | | | | |
| Туре | Start Loc | End Loc | Source | | Face | Dead (D) | Live (L) | Snow (S) | Wind (W) |
| Self Weight | 0' | 3'- 9 1/2" | Self Wei | ght | Тор | 5 lb/ft | - | - | - |
| Uniform | 0' | 3'- 9 1/2" | User Lo | ad | Тор | 120 lb/ft | 240 lb/ft | - | - |
| Point | 0'- 10" | 0'- 10" | J2(i660 |)) | Front | 129 lb | 259 lb | - | - |
| Point | 2'- 2" | 2'- 2" | J2(i638 | 3) | Front | 129 lb | 259 lb | - | - |
| Point | 3'- 6" | 3'- 6" | J2(i606 | i) | Front | 129 lb | 259 lb | - | - |
| UNFAC | TORED REA | ACTIONS | | | | | | | |
| ID | Start Loc | End Loc | Sc | urce | | Dead (D) | Live (L) | Snow (S) | Wind (W) |
| 1 | 0' | 0'- 3 1/2" | 1 | (i29) | | 396 lb | 775 lb | - | - |
| 2 | 3'- 6" | 3'- 9 1/2" | 2 | (i31) | | 464 lb | 912 lb | - | - |
| DESIG | N NOTES | | | | | | | | |

ANALYSIS RESULTS

- The dead loads used in the design of this member were applied to the structure as sloped dead loads.
- Analysis and Design has been performed using precision loading from actual modeled conditions. Some loads may have been modified to simplify reporting.
- Tributary Loads have been generated based on actual spacing between members in the model which may differ from the default system spacing. The actual loads applied to the member are shown in the Specified Loads table.
- Transfer reactions may differ from design results as allowed per building codes and standard load distribution practices.
- This report is based on modeled conditions input by the user. Source information for the loads and supports are provided for reference only. Verify that all loads and support conditions are correct.
- Review all loads and reactions to ensure that the member/bearing/connector/structure can resist adequately. Unless already specified on this report, anchorage for uplift reactions to be specified by others. Installation of member and accessories (if required) as per manufacturer's instruction.
- When the applied loads are coming from a member/post/wall above that does not sit directly on this beam, adequate load transfer elements, such as squash blocks, wall studs, or beveled plates are required to transfer the loads to this beam.





Maximum Floor Spans - S2.1

Design Criteria

Spans: Simple span

Live load = 40 psf and dead load = 15 psf

Deflection limits: L/480 under live load and L/240 under total load

Sheathing: 5/8 in. nailed-glued oriented strand board (OSB) sheathing

Maximum Floor Spans

| | | | В | are | | | 1/2 in. gyp | sum ceiling | |
|-------------|--------------|---------|---------|------------|-----|---------|-------------|-------------|-----|
| Joist depth | Joist series | | On cent | re spacing | | | On cent | re spacing | |
| | | 12" | 16" | 19.2" | 24" | 12" | 16" | 19.2" | 24" |
| | NI-20 | 15'-1" | 14'-3" | 13'-10" | - | 15'-7" | 14'-9" | 14'-3" | - |
| 9-1/2" | NI-40x | 16'-2" | 15'-3" | 14'-8" | - | 16'-7" | 15'-8" | 15'-1" | - |
| 9-1/2 | NI-60 | 16'-4" | 15'-4" | 14'-10" | - | 16'-9" | 15'-9" | 15'-3" | - |
| | NI-80 | 17'-3" | 16'-3" | 15'-8" | - | 17'-8" | 16'-7" | 16'-0" | - |
| | NI-20 | 17'-0" | 16'-0" | 15'-6" | - | 17'-6" | 16'-7" | 16'-0" | - |
| | NI-40x | 18'-2" | 17'-1" | 16'-6" | - | 18'-9" | 17'-6" | 16'-11" | - |
| 11-7/8" | NI-60 | 18'-5" | 17'-3" | 16'-8" | - | 19'-0" | 17'-8" | 17'-1" | - |
| | NI-80 | 19'-9" | 18'-3" | 17'-7" | - | 20'-4" | 18'-10" | 18'-0" | - |
| | NI-90 | 20'-2" | 18'-8" | 17'-10" | - | 20'-9" | 19'-2" | 18'-4" | - |
| | NI-40x | 20'-1" | 18'-8" | 17'-10" | - | 20'-10" | 19'-4" | 18'-6" | - |
| 14" | NI-60 | 20'-6" | 18'-11" | 18'-2" | - | 21'-2" | 19'-8" | 18'-9" | - |
| 14 | NI-80 | 21'-11" | 20'-3" | 19'-4" | - | 22'-7" | 20'-11" | 20'-0" | - |
| | NI-90 | 22'-5" | 20'-8" | 19'-9" | - | 23'-0" | 21'-4" | 20'-4" | - |
| | NI-60 | 22'-4" | 20'-8" | 19'-9" | - | 23'-1" | 21'-5" | 20'-6" | - |
| 16" | NI-80 | 23'-11" | 22'-1" | 21'-1" | - | 24'-8" | 22'-10" | 21'-9" | - |
| | NI-90 | 24'-5" | 22'-6" | 21'-6" | - | 25'-1" | 23'-2" | 22'-2" | - |

| | | Mi | d-span blocking | g with 1x4 inch s | trap | Mid-sp | oan blocking an | d 1/2 in. gypsum | ceiling |
|-------------|--------------|---------|-----------------|-------------------|------|---------|-----------------|------------------|---------|
| Joist depth | Joist series | | On cent | re spacing | | | On cent | re spacing | |
| | | 12" | 16" | 19.2" | 24" | 12" | 16" | 19.2" | 24" |
| | NI-20 | 16'-8" | 15'-3" | 14'-5" | - | 16'-8" | 15'-3" | 14'-5" | - |
| 9-1/2" | NI-40x | 17'-11" | 17'-0" | 16'-1" | - | 18'-5" | 17'-1" | 16'-1" | - |
| 9-1/2 | NI-60 | 18'-2" | 17'-1" | 16'-4" | - | 18'-8" | 17'-4" | 16'-4" | - |
| | NI-80 | 19'-5" | 18'-0" | 17'-5" | - | 19'-10" | 18'-5" | 17'-8" | - |
| | NI-20 | 19'-7" | 18'-2" | 17'-3" | - | 19'-11" | 18'-3" | 17'-3" | - |
| | NI-40x | 21'-1" | 19'-7" | 18'-8" | - | 21'-8" | 20'-2" | 19'-2" | - |
| 11-7/8" | NI-60 | 21'-4" | 19'-9" | 18'-11" | - | 21'-11" | 20'-5" | 19'-6" | - |
| | NI-80 | 22'-9" | 21'-1" | 20'-2" | - | 23'-3" | 21'-8" | 20'-8" | - |
| | NI-90 | 23'-3" | 21'-6" | 20'-6" | - | 23'-9" | 22'-0" | 21'-0" | - |
| | NI-40x | 23'-8" | 21'-11" | 20'-11" | - | 24'-4" | 22'-8" | 21'-8" | - |
| 14" | NI-60 | 24'-0" | 22'-3" | 21'-3" | - | 24'-8" | 22'-11" | 21'-11" | - |
| 14 | NI-80 | 25'-7" | 23'-9" | 22'-7" | - | 26'-2" | 24'-4" | 23'-3" | - |
| | NI-90 | 26'-1" | 24'-2" | 23'-0" | - | 26'-8" | 24'-9" | 23'-7" | - |
| | NI-60 | 26'-5" | 24'-6" | 23'-5" | - | 27'-2" | 25'-3" | 24'-2" | - |
| 16" | NI-80 | 28'-2" | 26'-1" | 24'-10" | - | 28'-10" | 26'-9" | 25'-6" | - |
| | NI-90 | 28'-8" | 26'-6" | 25'-3" | - | 29'-3" | 27'-2" | 25'-11" | _ |

- 1. The tabulated clear spans are based on CSA O86-14 and NBC 2015, and are applicable to residential floor construction meeting the above design criteria.
- 2. For multiple-span applications, the end spans shall be 40% or more of the adjacent span.
- 3. Minimum bearing length shall be 1-3/4 inch for end bearings, and 3-1/2 inches for intermediate bearings.
- 4. Bearing stiffeners are not required when I-joists are used in accordance with this table, except as required for hangers.
- 5. Nordic I-joists are listed in CCMC Evaluation Report 13032-R and APA Product Report PR-L274C.



Maximum Floor Spans - S4.1

Design Criteria

Spans: Simple span

Live load = 40 psf and dead load = 15 psf

Deflection limits: L/480 under live load and L/240 under total load

Sheathing: 3/4 in. nailed-glued oriented strand board (OSB) sheathing

Maximum Floor Spans

| | | | В | are | | | 1/2 in. gy | osum ceiling | |
|-------------|--------------|---------|---------|------------|---------|---------|------------|--------------|--------|
| Joist depth | Joist series | | On cent | re spacing | | | On cent | re spacing | |
| | | 12" | 16" | 19.2" | 24" | 12" | 16" | 19.2" | 24" |
| | NI-20 | 15'-11" | 15'-0" | 14'-6" | 13'-5" | 16'-5" | 15'-5" | 14'-6" | 13'-5" |
| 0.4/0" | NI-40x | 17'-0" | 16'-0" | 15'-5" | 14'-10" | 17'-5" | 16'-5" | 15'-10" | 15'-2" |
| 9-1/2" | NI-60 | 17'-2" | 16'-2" | 15'-7" | 14'-11" | 17'-7" | 16'-7" | 16'-0" | 15'-4" |
| | NI-80 | 18'-3" | 17'-1" | 16'-5" | 15'-9" | 18'-8" | 17'-5" | 16'-9" | 16'-1" |
| | NI-20 | 17'-11" | 16'-11" | 16'-3" | 15'-8" | 18'-7" | 17'-5" | 16'-10" | 16'-2" |
| | NI-40x | 19'-4" | 17'-11" | 17'-3" | 16'-7" | 19'-11" | 18'-6" | 17'-9" | 17'-0" |
| 11-7/8" | NI-60 | 19'-7" | 18'-2" | 17'-6" | 16'-9" | 20'-2" | 18'-9" | 17'-11" | 17'-2" |
| | NI-80 | 21'-1" | 19'-6" | 18'-6" | 17'-7" | 21'-7" | 20'-0" | 19'-0" | 18'-0" |
| | NI-90 | 21'-6" | 19'-10" | 18'-11" | 17'-11" | 22'-0" | 20'-4" | 19'-5" | 18'-4" |
| | NI-40x | 21'-5" | 19'-11" | 18'-11" | 18'-0" | 22'-1" | 20'-7" | 19'-7" | 18'-7" |
| 14" | NI-60 | 21'-10" | 20'-2" | 19'-3" | 18'-3" | 22'-6" | 20'-10" | 19'-11" | 18'-10 |
| 14 | NI-80 | 23'-5" | 21'-7" | 20'-7" | 19'-5" | 24'-0" | 22'-3" | 21'-2" | 20'-0" |
| | NI-90 | 23'-10" | 22'-1" | 21'-0" | 19'-10" | 24'-5" | 22'-7" | 21'-6" | 20'-4" |
| | NI-60 | 23'-9" | 22'-0" | 21'-0" | 19'-10" | 24'-6" | 22'-9" | 21'-8" | 20'-7" |
| 16" | NI-80 | 25'-6" | 23'-7" | 22'-5" | 21'-2" | 26'-2" | 24'-3" | 23'-1" | 21'-10 |
| | NI-90 | 26'-0" | 24'-0" | 22'-10" | 21'-6" | 26'-7" | 24'-8" | 23'-5" | 22'-2" |

| | | Mi | d-span blocking | with 1x4 inch | strap | Mid-sp | oan blocking an | d 1/2 in. gypsui | m ceiling |
|-------------|--------------|---------|-----------------|---------------|---------|---------|-----------------|------------------|-----------|
| Joist depth | Joist series | | On cent | re spacing | | | On cent | re spacing | |
| | | 12" | 16" | 19.2" | 24" | 12" | 16" | 19.2" | 24" |
| | NI-20 | 16'-10" | 15'-5" | 14'-6" | 13'-5" | 16'-10" | 15'-5" | 14'-6" | 13'-5" |
| 9-1/2" | NI-40x | 18'-8" | 17'-2" | 16'-3" | 15'-2" | 18'-10" | 17'-2" | 16'-3" | 15'-2" |
| 9-1/2 | NI-60 | 18'-11" | 17'-6" | 16'-6" | 15'-5" | 19'-2" | 17'-6" | 16'-6" | 15'-5" |
| | NI-80 | 20'-3" | 18'-10" | 17'-11" | 16'-10" | 20'-8" | 19'-3" | 18'-2" | 16'-10' |
| | NI-20 | 20'-1" | 18'-5" | 17'-5" | 16'-2" | 20'-1" | 18'-5" | 17'-5" | 16'-2" |
| | NI-40x | 21'-10" | 20'-4" | 19'-4" | 17'-8" | 22'-5" | 20'-6" | 19'-4" | 17'-8" |
| 11-7/8" | NI-60 | 22'-1" | 20'-7" | 19'-8" | 18'-4" | 22'-8" | 20'-10" | 19'-8" | 18'-4" |
| | NI-80 | 23'-8" | 22'-0" | 20'-11" | 19'-10" | 24'-1" | 22'-6" | 21'-6" | 20'-0" |
| | NI-90 | 24'-1" | 22'-5" | 21'-4" | 20'-2" | 24'-7" | 22'-11" | 21'-10" | 20'-7" |
| | NI-40x | 24'-5" | 22'-9" | 21'-9" | 19'-5" | 25'-1" | 23'-2" | 21'-9" | 19'-5" |
| 14" | NI-60 | 24'-10" | 23'-2" | 22'-1" | 20'-10" | 25'-6" | 23'-8" | 22'-4" | 20'-10' |
| 14 | NI-80 | 26'-6" | 24'-8" | 23'-6" | 22'-2" | 27'-1" | 25'-3" | 24'-1" | 22'-9" |
| | NI-90 | 27'-0" | 25'-1" | 23'-11" | 22'-7" | 27'-6" | 25'-8" | 24'-6" | 23'-2" |
| | NI-60 | 27'-3" | 25'-5" | 24'-3" | 22'-11" | 28'-0" | 26'-2" | 24'-9" | 23'-1" |
| 16" | NI-80 | 29'-1" | 27'-1" | 25'-9" | 24'-4" | 29'-8" | 27'-9" | 26'-5" | 25'-0" |
| | NI-90 | 29'-7" | 27'-6" | 26'-2" | 24'-9" | 30'-2" | 28'-2" | 26'-10" | 25'-5" |

- 1. The tabulated clear spans are based on CSA 086-14 and NBC 2015, and are applicable to residential floor construction meeting the above design criteria.
- 2. For multiple-span applications, the end spans shall be 40% or more of the adjacent span.
- 3. Minimum bearing length shall be 1-3/4 inch for end bearings, and 3-1/2 inches for intermediate bearings.
- 4. Bearing stiffeners are not required when I-joists are used in accordance with this table, except as required for hangers.
- 5. Nordic I-joists are listed in CCMC Evaluation Report 13032-R and APA Product Report PR-L274C.



Maximum Floor Spans - S6.1

Design Criteria

Spans: Simple span

Loads: Live load = 40 psf and dead load = 15 psf

Deflection limits: L/480 under live load and L/240 under total load

Sheathing: 5/8 in. nailed-glued Canadian softwood plywood

Maximum Floor Spans

| | | | В | are | | | 1/2 in. gyp | sum ceiling | |
|-------------|--------------|---------|---------|------------|-----|---------|-------------|-------------|-----|
| Joist depth | Joist series | | On cent | re spacing | | | On cent | re spacing | |
| | | 12" | 16" | 19.2" | 24" | 12" | 16" | 19.2" | 24" |
| | NI-20 | 14'-11" | 14'-1" | 13'-7" | - | 15'-4" | 14'-6" | 14'-1" | - |
| 0.4/0" | NI-40x | 15'-11" | 15'-0" | 14'-6" | - | 16'-4" | 15'-5" | 14'-11" | - |
| 9-1/2" | NI-60 | 16'-1" | 15'-2" | 14'-8" | - | 16'-6" | 15'-7" | 15'-1" | - |
| | NI-80 | 17'-1" | 16'-1" | 15'-6" | - | 17'-5" | 16'-5" | 15'-10" | - |
| | NI-20 | 16'-9" | 15'-10" | 15'-4" | - | 17'-4" | 16'-4" | 15'-10" | - |
| | NI-40x | 17'-10" | 16'-10" | 16'-3" | - | 18'-6" | 17'-4" | 16'-9" | - |
| 11-7/8" | NI-60 | 18'-1" | 17'-0" | 16'-5" | - | 18'-9" | 17'-6" | 16'-11" | - |
| | NI-80 | 19'-6" | 18'-0" | 17'-4" | - | 20'-1" | 18'-7" | 17'-9" | - |
| | NI-90 | 19'-11" | 18'-4" | 17'-8" | - | 20'-5" | 18'-11" | 18'-1" | - |
| | NI-40x | 19'-10" | 18'-4" | 17'-8" | - | 20'-6" | 19'-1" | 18'-3" | - |
| 14" | NI-60 | 20'-2" | 18'-8" | 17'-11" | - | 20'-10" | 19'-4" | 18'-6" | - |
| 14 | NI-80 | 21'-8" | 20'-0" | 19'-1" | - | 22'-4" | 20'-8" | 19'-9" | - |
| | NI-90 | 22'-1" | 20'-5" | 19'-6" | - | 22'-9" | 21'-0" | 20'-1" | - |
| | NI-60 | 22'-0" | 20'-4" | 19'-6" | - | 22'-9" | 21'-1" | 20'-2" | - |
| 16" | NI-80 | 23'-7" | 21'-10" | 20'-10" | - | 24'-4" | 22'-6" | 21'-6" | - |
| | NI-90 | 24'-1" | 22'-2" | 21'-2" | - | 24'-9" | 22'-11" | 21'-10" | - |

| | · | Mi | d-span blocking | with 1x4 inch st | trap | Mid-sp | an blocking an | d 1/2 in. gypsum | ceiling |
|-------------|--------------|---------|-----------------|------------------|------|---------|----------------|------------------|---------|
| Joist depth | Joist series | | On cent | re spacing | | | On cent | re spacing | |
| | | 12" | 16" | 19.2" | 24" | 12" | 16" | 19.2" | 24" |
| | NI-20 | 16'-6" | 15'-1" | 14'-3" | - | 16'-6" | 15'-1" | 14'-3" | - |
| 0.4/0" | NI-40x | 17'-9" | 16'-10" | 15'-11" | - | 18'-2" | 16'-11" | 15'-11" | - |
| 9-1/2" | NI-60 | 17'-11" | 16'-11" | 16'-2" | - | 18'-5" | 17'-2" | 16'-2" | - |
| | NI-80 | 19'-3" | 17'-10" | 17'-3" | - | 19'-8" | 18'-3" | 17'-7" | - |
| | NI-20 | 19'-4" | 18'-0" | 17'-1" | - | 19'-9" | 18'-1" | 17'-1" | - |
| | NI-40x | 20'-10" | 19'-4" | 18'-6" | - | 21'-5" | 19'-11" | 19'-0" | - |
| 11-7/8" | NI-60 | 21'-1" | 19'-7" | 18'-8" | - | 21'-8" | 20'-2" | 19'-3" | - |
| | NI-80 | 22'-6" | 20'-10" | 19'-11" | - | 23'-1" | 21'-5" | 20'-5" | - |
| | NI-90 | 23'-0" | 21'-3" | 20'-4" | - | 23'-6" | 21'-10" | 20'-10" | - |
| | NI-40x | 23'-5" | 21'-8" | 20'-9" | - | 24'-0" | 22'-5" | 21'-5" | - |
| 14" | NI-60 | 23'-9" | 22'-0" | 21'-0" | - | 24'-5" | 22'-8" | 21'-8" | - |
| 14 | NI-80 | 25'-4" | 23'-6" | 22'-5" | - | 25'-11" | 24'-1" | 23'-0" | - |
| | NI-90 | 25'-10" | 23'-11" | 22'-9" | - | 26'-5" | 24'-6" | 23'-4" | - |
| | NI-60 | 26'-2" | 24'-3" | 23'-2" | - | 26'-11" | 25'-0" | 23'-11" | - |
| 16" | NI-80 | 27'-11" | 25'-10" | 24'-7" | - | 28'-7" | 26'-6" | 25'-3" | - |
| | NI-90 | 28'-5" | 26'-3" | 25'-0" | - | 29'-0" | 26'-11" | 25'-8" | - |

- 1. The tabulated clear spans are based on CSA O86-14 and NBC 2015, and are applicable to residential floor construction meeting the above design criteria.
- 2. For multiple-span applications, the end spans shall be 40% or more of the adjacent span.
- 3. Minimum bearing length shall be 1-3/4 inch for end bearings, and 3-1/2 inches for intermediate bearings.
- 4. Bearing stiffeners are not required when I-joists are used in accordance with this table, except as required for hangers.
- 5. Nordic I-joists are listed in CCMC Evaluation Report 13032-R and APA Product Report PR-L274C.



Maximum Floor Spans - S7.1

Design Criteria

Spans: Simple span

 Loads:
 Live load = 40 psf and dead load = 15 psf

 Deflection limits:
 L/480 under live load and L/240 under total load

 Sheathing:
 3/4 in. nailed-glued Canadian softwood plywood

Maximum Floor Spans

| | | | В | are | | | 1/2 in. gy | sum ceiling | |
|-------------|--------------|---------|---------|------------|---------|---------|------------|-------------|--------|
| Joist depth | Joist series | | On cent | re spacing | | | On cent | re spacing | |
| | | 12" | 16" | 19.2" | 24" | 12" | 16" | 19.2" | 24" |
| | NI-20 | 15'-10" | 15'-0" | 14'-5" | 13'-5" | 16'-4" | 15'-5" | 14'-6" | 13'-5" |
| 0.4/0" | NI-40x | 16'-11" | 15'-11" | 15'-4" | 14'-9" | 17'-4" | 16'-4" | 15'-9" | 15'-1" |
| 9-1/2" | NI-60 | 17'-1" | 16'-1" | 15'-6" | 14'-10" | 17'-6" | 16'-6" | 15'-11" | 15'-3" |
| | NI-80 | 18'-1" | 17'-0" | 16'-4" | 15'-8" | 18'-7" | 17'-4" | 16'-8" | 16'-0" |
| | NI-20 | 17'-10" | 16'-10" | 16'-2" | 15'-7" | 18'-5" | 17'-4" | 16'-9" | 16'-1" |
| | NI-40x | 19'-3" | 17'-10" | 17'-2" | 16'-6" | 19'-10" | 18'-5" | 17'-8" | 16'-11 |
| 11-7/8" | NI-60 | 19'-6" | 18'-1" | 17'-4" | 16'-8" | 20'-1" | 18'-8" | 17'-10" | 17'-1" |
| | NI-80 | 20'-11" | 19'-4" | 18'-5" | 17'-7" | 21'-5" | 19'-10" | 18'-11" | 17'-11 |
| | NI-90 | 21'-4" | 19'-9" | 18'-9" | 17'-10" | 21'-10" | 20'-3" | 19'-3" | 18'-3" |
| | NI-40x | 21'-4" | 19'-9" | 18'-10" | 17'-11" | 22'-0" | 20'-5" | 19'-6" | 18'-6" |
| 14" | NI-60 | 21'-8" | 20'-1" | 19'-2" | 18'-2" | 22'-4" | 20'-9" | 19'-9" | 18'-9" |
| 14 | NI-80 | 23'-3" | 21'-6" | 20'-5" | 19'-4" | 23'-10" | 22'-1" | 21'-0" | 19'-11 |
| | NI-90 | 23'-9" | 21'-11" | 20'-10" | 19'-8" | 24'-3" | 22'-6" | 21'-5" | 20'-3" |
| | NI-60 | 23'-7" | 21'-10" | 20'-10" | 19'-9" | 24'-4" | 22'-7" | 21'-7" | 20'-5" |
| 16" | NI-80 | 25'-4" | 23'-5" | 22'-3" | 21'-1" | 26'-0" | 24'-1" | 22'-11" | 21'-8" |
| | NI-90 | 25'-10" | 23'-10" | 22'-8" | 21'-5" | 26'-5" | 24'-6" | 23'-4" | 22'-0" |

| | | Mi | d-span blocking | with 1x4 inch | strap | Mid-sp | an blocking an | d 1/2 in. gypsu | ım ceiling |
|-------------|--------------|---------|-----------------|---------------|---------|---------|----------------|-----------------|------------|
| Joist depth | Joist series | | On cent | re spacing | | | On cent | re spacing | |
| | | 12" | 16" | 19.2" | 24" | 12" | 16" | 19.2" | 24" |
| | NI-20 | 16'-10" | 15'-5" | 14'-6" | 13'-5" | 16'-10" | 15'-5" | 14'-6" | 13'-5" |
| 9-1/2" | NI-40x | 18'-7" | 17'-2" | 16'-3" | 15'-2" | 18'-10" | 17'-2" | 16'-3" | 15'-2" |
| 9-1/2 | NI-60 | 18'-10" | 17'-6" | 16'-6" | 15'-5" | 19'-1" | 17'-6" | 16'-6" | 15'-5" |
| | NI-80 | 20'-2" | 18'-9" | 17'-11" | 16'-10" | 20'-7" | 19'-2" | 18'-2" | 16'-10' |
| | NI-20 | 20'-1" | 18'-5" | 17'-5" | 16'-2" | 20'-1" | 18'-5" | 17'-5" | 16'-2" |
| | NI-40x | 21'-9" | 20'-3" | 19'-4" | 17'-8" | 22'-4" | 20'-5" | 19'-4" | 17'-8" |
| 11-7/8" | NI-60 | 22'-0" | 20'-6" | 19'-7" | 18'-4" | 22'-7" | 20'-10" | 19'-8" | 18'-4" |
| | NI-80 | 23'-6" | 21'-10" | 20'-10" | 19'-9" | 24'-0" | 22'-5" | 21'-4" | 20'-0" |
| | NI-90 | 24'-0" | 22'-4" | 21'-3" | 20'-1" | 24'-6" | 22'-10" | 21'-9" | 20'-7" |
| | NI-40x | 24'-4" | 22'-8" | 21'-8" | 19'-5" | 25'-0" | 23'-2" | 21'-9" | 19'-5" |
| 14" | NI-60 | 24'-9" | 23'-0" | 22'-0" | 20'-9" | 25'-5" | 23'-8" | 22'-4" | 20'-10' |
| 14 | NI-80 | 26'-5" | 24'-6" | 23'-4" | 22'-1" | 27'-0" | 25'-2" | 24'-0" | 22'-8" |
| | NI-90 | 26'-11" | 25'-0" | 23'-10" | 22'-6" | 27'-5" | 25'-7" | 24'-5" | 23'-1" |
| | NI-60 | 27'-2" | 25'-4" | 24'-2" | 22'-10" | 27'-11" | 26'-1" | 24'-9" | 23'-1" |
| 16" | NI-80 | 29'-0" | 26'-11" | 25'-8" | 24'-3" | 29'-7" | 27'-7" | 26'-4" | 24'-11' |
| | NI-90 | 29'-6" | 27'-5" | 26'-1" | 24'-8" | 30'-1" | 28'-1" | 26'-9" | 25'-4" |

- 1. The tabulated clear spans are based on CSA 086-14 and NBC 2015, and are applicable to residential floor construction meeting the above design criteria.
- 2. For multiple-span applications, the end spans shall be 40% or more of the adjacent span.
- 3. Minimum bearing length shall be 1-3/4 inch for end bearings, and 3-1/2 inches for intermediate bearings.
- 4. Bearing stiffeners are not required when I-joists are used in accordance with this table, except as required for hangers.
- 5. Nordic I-joists are listed in CCMC Evaluation Report 13032-R and APA Product Report PR-L274C.



Maximum Floor Spans - M2.1

Design Criteria

Spans: Simple span

Live load = 40 psf and dead load = 20 psf

Deflection limits: L/480 under live load and L/240 under total load

Sheathing: 5/8 in. nailed-glued oriented strand board (OSB) sheathing

Maximum Floor Spans

| | | | В | are | | | 1/2 in. gyp | sum ceiling | |
|-------------|--------------|---------|---------|------------|-----|---------|-------------|-------------|-----|
| Joist depth | Joist series | | On cent | re spacing | | | On cent | re spacing | |
| | | 12" | 16" | 19.2" | 24" | 12" | 16" | 19.2" | 24" |
| | NI-20 | 15'-1" | 14'-3" | 13'-10" | - | 15'-7" | 14'-9" | 14'-3" | - |
| 0.4/0" | NI-40x | 16'-2" | 15'-3" | 14'-8" | - | 16'-7" | 15'-8" | 15'-1" | - |
| 9-1/2" | NI-60 | 16'-4" | 15'-4" | 14'-10" | - | 16'-9" | 15'-9" | 15'-3" | - |
| | NI-80 | 17'-3" | 16'-3" | 15'-8" | - | 17'-8" | 16'-7" | 16'-0" | - |
| | NI-20 | 17'-0" | 16'-0" | 15'-6" | - | 17'-6" | 16'-7" | 16'-0" | - |
| | NI-40x | 18'-2" | 17'-1" | 16'-6" | - | 18'-9" | 17'-6" | 16'-11" | - |
| 11-7/8" | NI-60 | 18'-5" | 17'-3" | 16'-8" | - | 19'-0" | 17'-8" | 17'-1" | - |
| | NI-80 | 19'-9" | 18'-3" | 17'-7" | - | 20'-4" | 18'-10" | 18'-0" | - |
| | NI-90 | 20'-2" | 18'-8" | 17'-10" | - | 20'-9" | 19'-2" | 18'-4" | - |
| | NI-40x | 20'-1" | 18'-8" | 17'-10" | - | 20'-10" | 19'-4" | 18'-6" | - |
| 14" | NI-60 | 20'-6" | 18'-11" | 18'-2" | - | 21'-2" | 19'-8" | 18'-9" | - |
| 14 | NI-80 | 21'-11" | 20'-3" | 19'-4" | - | 22'-7" | 20'-11" | 20'-0" | - |
| | NI-90 | 22'-5" | 20'-8" | 19'-9" | - | 23'-0" | 21'-4" | 20'-4" | - |
| | NI-60 | 22'-4" | 20'-8" | 19'-9" | - | 23'-1" | 21'-5" | 20'-6" | - |
| 16" | NI-80 | 23'-11" | 22'-1" | 21'-1" | - | 24'-8" | 22'-10" | 21'-9" | - |
| | NI-90 | 24'-5" | 22'-6" | 21'-6" | - | 25'-1" | 23'-2" | 22'-2" | - |

| | | Mi | d-span blocking | g with 1x4 inch s | trap | Mid-sp | oan blocking an | d 1/2 in. gypsum | ceiling |
|-------------|--------------|---------|-----------------|-------------------|------|---------|-----------------|------------------|---------|
| Joist depth | Joist series | | On cent | re spacing | | | On cent | re spacing | |
| | | 12" | 16" | 19.2" | 24" | 12" | 16" | 19.2" | 24" |
| | NI-20 | 16'-8" | 15'-3" | 14'-5" | - | 16'-8" | 15'-3" | 14'-5" | - |
| 9-1/2" | NI-40x | 17'-11" | 17'-0" | 16'-1" | - | 18'-5" | 17'-1" | 16'-1" | - |
| 9-1/2 | NI-60 | 18'-2" | 17'-1" | 16'-4" | - | 18'-8" | 17'-4" | 16'-4" | - |
| | NI-80 | 19'-5" | 18'-0" | 17'-5" | - | 19'-10" | 18'-5" | 17'-8" | - |
| | NI-20 | 19'-7" | 18'-2" | 17'-3" | - | 19'-11" | 18'-3" | 17'-3" | - |
| | NI-40x | 21'-1" | 19'-7" | 18'-8" | - | 21'-8" | 20'-2" | 19'-0" | - |
| 11-7/8" | NI-60 | 21'-4" | 19'-9" | 18'-11" | - | 21'-11" | 20'-5" | 19'-6" | - |
| | NI-80 | 22'-9" | 21'-1" | 20'-2" | - | 23'-3" | 21'-8" | 20'-8" | - |
| | NI-90 | 23'-3" | 21'-6" | 20'-6" | - | 23'-9" | 22'-0" | 21'-0" | - |
| | NI-40x | 23'-8" | 21'-11" | 20'-11" | - | 24'-4" | 22'-8" | 20'-11" | - |
| 14" | NI-60 | 24'-0" | 22'-3" | 21'-3" | - | 24'-8" | 22'-11" | 21'-11" | - |
| 14 | NI-80 | 25'-7" | 23'-9" | 22'-7" | - | 26'-2" | 24'-4" | 23'-3" | - |
| | NI-90 | 26'-1" | 24'-2" | 23'-0" | - | 26'-8" | 24'-9" | 23'-7" | - |
| | NI-60 | 26'-5" | 24'-6" | 23'-5" | - | 27'-2" | 25'-3" | 24'-2" | - |
| 16" | NI-80 | 28'-2" | 26'-1" | 24'-10" | - | 28'-10" | 26'-9" | 25'-6" | - |
| | NI-90 | 28'-8" | 26'-6" | 25'-3" | - | 29'-3" | 27'-2" | 25'-11" | _ |

- 1. The tabulated clear spans are based on CSA O86-14 and NBC 2015, and are applicable to residential floor construction meeting the above design criteria.
- 2. For multiple-span applications, the end spans shall be 40% or more of the adjacent span.
- 3. Minimum bearing length shall be 1-3/4 inch for end bearings, and 3-1/2 inches for intermediate bearings.
- 4. Bearing stiffeners are not required when I-joists are used in accordance with this table, except as required for hangers.
- 5. Nordic I-joists are listed in CCMC Evaluation Report 13032-R and APA Product Report PR-L274C.



Maximum Floor Spans - M4.1

Design Criteria

Spans: Simple span

Live load = 40 psf and dead load = 20 psf

Deflection limits: L/480 under live load and L/240 under total load

Sheathing: 3/4 in. nailed-glued oriented strand board (OSB) sheathing

Maximum Floor Spans

| | | | В | are | | | 1/2 in. gy | sum ceiling | |
|-------------|--------------|---------|---------|------------|---------|---------|------------|-------------|---------|
| Joist depth | Joist series | | On cent | re spacing | | | On cent | re spacing | |
| | | 12" | 16" | 19.2" | 24" | 12" | 16" | 19.2" | 24" |
| | NI-20 | 15'-11" | 15'-0" | 14'-6" | 13'-5" | 16'-5" | 15'-5" | 14'-6" | 13'-5" |
| 0.4/0" | NI-40x | 17'-0" | 16'-0" | 15'-5" | 14'-10" | 17'-5" | 16'-5" | 15'-10" | 14'-11' |
| 9-1/2" | NI-60 | 17'-2" | 16'-2" | 15'-7" | 14'-11" | 17'-7" | 16'-7" | 16'-0" | 15'-4" |
| | NI-80 | 18'-3" | 17'-1" | 16'-5" | 15'-9" | 18'-8" | 17'-5" | 16'-9" | 16'-1" |
| | NI-20 | 17'-11" | 16'-11" | 16'-3" | 15'-8" | 18'-7" | 17'-5" | 16'-10" | 16'-1" |
| | NI-40x | 19'-4" | 17'-11" | 17'-3" | 16'-7" | 19'-11" | 18'-6" | 17'-9" | 17'-0" |
| 11-7/8" | NI-60 | 19'-7" | 18'-2" | 17'-6" | 16'-9" | 20'-2" | 18'-9" | 17'-11" | 17'-2" |
| | NI-80 | 21'-1" | 19'-6" | 18'-6" | 17'-7" | 21'-7" | 20'-0" | 19'-0" | 18'-0" |
| | NI-90 | 21'-6" | 19'-10" | 18'-11" | 17'-11" | 22'-0" | 20'-4" | 19'-5" | 18'-4" |
| | NI-40x | 21'-5" | 19'-11" | 18'-11" | 18'-0" | 22'-1" | 20'-7" | 19'-7" | 18'-7" |
| 14" | NI-60 | 21'-10" | 20'-2" | 19'-3" | 18'-3" | 22'-6" | 20'-10" | 19'-11" | 18'-10' |
| 14 | NI-80 | 23'-5" | 21'-7" | 20'-7" | 19'-5" | 24'-0" | 22'-3" | 21'-2" | 20'-0" |
| | NI-90 | 23'-10" | 22'-1" | 21'-0" | 19'-10" | 24'-5" | 22'-7" | 21'-6" | 20'-4" |
| | NI-60 | 23'-9" | 22'-0" | 21'-0" | 19'-10" | 24'-6" | 22'-9" | 21'-8" | 20'-7" |
| 16" | NI-80 | 25'-6" | 23'-7" | 22'-5" | 21'-2" | 26'-2" | 24'-3" | 23'-1" | 21'-10' |
| | NI-90 | 26'-0" | 24'-0" | 22'-10" | 21'-6" | 26'-7" | 24'-8" | 23'-5" | 22'-2" |

| | | Mi | d-span blocking | with 1x4 inch | strap | Mid-sp | oan blocking an | d 1/2 in. gypsur | n ceiling |
|-------------|--------------|---------|-----------------|---------------|---------|---------|-----------------|------------------|-----------|
| Joist depth | Joist series | | On cent | re spacing | | | On cent | re spacing | |
| | | 12" | 16" | 19.2" | 24" | 12" | 16" | 19.2" | 24" |
| | NI-20 | 16'-10" | 15'-5" | 14'-6" | 13'-5" | 16'-10" | 15'-5" | 14'-6" | 13'-5" |
| 0.4/0!! | NI-40x | 18'-8" | 17'-2" | 16'-3" | 14'-11" | 18'-10" | 17'-2" | 16'-3" | 14'-11' |
| 9-1/2" | NI-60 | 18'-11" | 17'-6" | 16'-6" | 15'-5" | 19'-2" | 17'-6" | 16'-6" | 15'-5" |
| | NI-80 | 20'-3" | 18'-10" | 17'-11" | 16'-10" | 20'-8" | 19'-3" | 18'-2" | 16'-10' |
| | NI-20 | 20'-1" | 18'-5" | 17'-5" | 16'-1" | 20'-1" | 18'-5" | 17'-5" | 16'-1" |
| | NI-40x | 21'-10" | 20'-4" | 19'-0" | 17'-0" | 22'-5" | 20'-6" | 19'-0" | 17'-0" |
| 11-7/8" | NI-60 | 22'-1" | 20'-7" | 19'-8" | 18'-4" | 22'-8" | 20'-10" | 19'-8" | 18'-4" |
| | NI-80 | 23'-8" | 22'-0" | 20'-11" | 19'-10" | 24'-1" | 22'-6" | 21'-6" | 20'-0" |
| | NI-90 | 24'-1" | 22'-5" | 21'-4" | 20'-2" | 24'-7" | 22'-11" | 21'-10" | 20'-7" |
| | NI-40x | 24'-5" | 22'-9" | 20'-11" | 18'-8" | 25'-1" | 22'-11" | 20'-11" | 18'-8" |
| 14" | NI-60 | 24'-10" | 23'-2" | 22'-1" | 20'-10" | 25'-6" | 23'-8" | 22'-4" | 20'-10' |
| 14 | NI-80 | 26'-6" | 24'-8" | 23'-6" | 22'-2" | 27'-1" | 25'-3" | 24'-1" | 22'-9" |
| | NI-90 | 27'-0" | 25'-1" | 23'-11" | 22'-7" | 27'-6" | 25'-8" | 24'-6" | 23'-2" |
| | NI-60 | 27'-3" | 25'-5" | 24'-3" | 22'-11" | 28'-0" | 26'-2" | 24'-9" | 23'-1" |
| 16" | NI-80 | 29'-1" | 27'-1" | 25'-9" | 24'-4" | 29'-8" | 27'-9" | 26'-5" | 25'-0" |
| | NI-90 | 29'-7" | 27'-6" | 26'-2" | 24'-9" | 30'-2" | 28'-2" | 26'-10" | 25'-5" |

- 1. The tabulated clear spans are based on CSA 086-14 and NBC 2015, and are applicable to residential floor construction meeting the above design criteria.
- 2. For multiple-span applications, the end spans shall be 40% or more of the adjacent span.
- 3. Minimum bearing length shall be 1-3/4 inch for end bearings, and 3-1/2 inches for intermediate bearings.
- 4. Bearing stiffeners are not required when I-joists are used in accordance with this table, except as required for hangers.
- 5. Nordic I-joists are listed in CCMC Evaluation Report 13032-R and APA Product Report PR-L274C.



Maximum Floor Spans - M6.1

Design Criteria

Spans: Simple span

Loads: Live load = 40 psf and dead load = 20 psf
Deflection limits: L/480 under live load and L/240 under total load
Sheathing: 5/8 in. nailed-glued Canadian softwood plywood

Maximum Floor Spans

| | | | В | are | | | 1/2 in. gyp | sum ceiling | |
|-------------|--------------|---------|---------|------------|-----|---------|-------------|-------------|-----|
| Joist depth | Joist series | | On cent | re spacing | | | On cent | re spacing | |
| | | 12" | 16" | 19.2" | 24" | 12" | 16" | 19.2" | 24" |
| | NI-20 | 14'-11" | 14'-1" | 13'-7" | - | 15'-4" | 14'-6" | 14'-1" | - |
| 9-1/2" | NI-40x | 15'-11" | 15'-0" | 14'-6" | - | 16'-4" | 15'-5" | 14'-11" | - |
| 9-1/2 | NI-60 | 16'-1" | 15'-2" | 14'-8" | - | 16'-6" | 15'-7" | 15'-1" | - |
| | NI-80 | 17'-1" | 16'-1" | 15'-6" | - | 17'-5" | 16'-5" | 15'-10" | - |
| | NI-20 | 16'-9" | 15'-10" | 15'-4" | - | 17'-4" | 16'-4" | 15'-10" | - |
| | NI-40x | 17'-10" | 16'-10" | 16'-3" | - | 18'-6" | 17'-4" | 16'-9" | - |
| 11-7/8" | NI-60 | 18'-1" | 17'-0" | 16'-5" | - | 18'-9" | 17'-6" | 16'-11" | - |
| | NI-80 | 19'-6" | 18'-0" | 17'-4" | - | 20'-1" | 18'-7" | 17'-9" | - |
| | NI-90 | 19'-11" | 18'-4" | 17'-8" | - | 20'-5" | 18'-11" | 18'-1" | - |
| | NI-40x | 19'-10" | 18'-4" | 17'-8" | - | 20'-6" | 19'-1" | 18'-3" | - |
| 14" | NI-60 | 20'-2" | 18'-8" | 17'-11" | - | 20'-10" | 19'-4" | 18'-6" | - |
| 14 | NI-80 | 21'-8" | 20'-0" | 19'-1" | - | 22'-4" | 20'-8" | 19'-9" | - |
| | NI-90 | 22'-1" | 20'-5" | 19'-6" | - | 22'-9" | 21'-0" | 20'-1" | - |
| | NI-60 | 22'-0" | 20'-4" | 19'-6" | - | 22'-9" | 21'-1" | 20'-2" | - |
| 16" | NI-80 | 23'-7" | 21'-10" | 20'-10" | - | 24'-4" | 22'-6" | 21'-6" | - |
| | NI-90 | 24'-1" | 22'-2" | 21'-2" | - | 24'-9" | 22'-11" | 21'-10" | - |

| | | Mi | d-span blocking | with 1x4 inch st | rap | Mid-sp | an blocking an | d 1/2 in. gypsum | ceiling |
|-------------|--------------|---------|-----------------|------------------|-----|---------|----------------|------------------|---------|
| Joist depth | Joist series | | On cent | re spacing | | | On cent | re spacing | |
| | | 12" | 16" | 19.2" | 24" | 12" | 16" | 19.2" | 24" |
| | NI-20 | 16'-6" | 15'-1" | 14'-3" | - | 16'-6" | 15'-1" | 14'-3" | - |
| 0.4/0" | NI-40x | 17'-9" | 16'-10" | 15'-11" | - | 18'-2" | 16'-11" | 15'-11" | - |
| 9-1/2" | NI-60 | 17'-11" | 16'-11" | 16'-2" | - | 18'-5" | 17'-2" | 16'-2" | - |
| | NI-80 | 19'-3" | 17'-10" | 17'-3" | - | 19'-8" | 18'-3" | 17'-7" | - |
| | NI-20 | 19'-4" | 18'-0" | 17'-1" | - | 19'-9" | 18'-1" | 17'-1" | - |
| | NI-40x | 20'-10" | 19'-4" | 18'-6" | - | 21'-5" | 19'-11" | 19'-0" | - |
| 11-7/8" | NI-60 | 21'-1" | 19'-7" | 18'-8" | - | 21'-8" | 20'-2" | 19'-3" | - |
| | NI-80 | 22'-6" | 20'-10" | 19'-11" | - | 23'-1" | 21'-5" | 20'-5" | - |
| | NI-90 | 23'-0" | 21'-3" | 20'-4" | - | 23'-6" | 21'-10" | 20'-10" | - |
| | NI-40x | 23'-5" | 21'-8" | 20'-9" | - | 24'-0" | 22'-5" | 20'-11" | - |
| 14" | NI-60 | 23'-9" | 22'-0" | 21'-0" | - | 24'-5" | 22'-8" | 21'-8" | - |
| 14 | NI-80 | 25'-4" | 23'-6" | 22'-5" | - | 25'-11" | 24'-1" | 23'-0" | - |
| | NI-90 | 25'-10" | 23'-11" | 22'-9" | - | 26'-5" | 24'-6" | 23'-4" | - |
| | NI-60 | 26'-2" | 24'-3" | 23'-2" | - | 26'-11" | 25'-0" | 23'-11" | - |
| 16" | NI-80 | 27'-11" | 25'-10" | 24'-7" | - | 28'-7" | 26'-6" | 25'-3" | - |
| | NI-90 | 28'-5" | 26'-3" | 25'-0" | _ | 29'-0" | 26'-11" | 25'-8" | _ |

- 1. The tabulated clear spans are based on CSA O86-14 and NBC 2015, and are applicable to residential floor construction meeting the above design criteria.
- 2. For multiple-span applications, the end spans shall be 40% or more of the adjacent span.
- 3. Minimum bearing length shall be 1-3/4 inch for end bearings, and 3-1/2 inches for intermediate bearings.
- 4. Bearing stiffeners are not required when I-joists are used in accordance with this table, except as required for hangers.
- 5. Nordic I-joists are listed in CCMC Evaluation Report 13032-R and APA Product Report PR-L274C.



Maximum Floor Spans - M7.1

Design Criteria

Spans: Simple span


Loads: Live load = 40 psf and dead load = 20 psf
Deflection limits: L/480 under live load and L/240 under total load
Sheathing: 3/4 in. nailed-glued Canadian softwood plywood

Maximum Floor Spans

| | | | В | are | | | 1/2 in. gyp | osum ceiling | |
|-------------|--------------|---------|---------|------------|---------|---------|-------------|--------------|---------|
| Joist depth | Joist series | | On cent | re spacing | | | On cent | re spacing | |
| | | 12" | 16" | 19.2" | 24" | 12" | 16" | 19.2" | 24" |
| | NI-20 | 15'-10" | 15'-0" | 14'-5" | 13'-5" | 16'-4" | 15'-5" | 14'-6" | 13'-5" |
| 0.4/0" | NI-40x | 16'-11" | 15'-11" | 15'-4" | 14'-9" | 17'-4" | 16'-4" | 15'-9" | 14'-11' |
| 9-1/2" | NI-60 | 17'-1" | 16'-1" | 15'-6" | 14'-10" | 17'-6" | 16'-6" | 15'-11" | 15'-3" |
| | NI-80 | 18'-1" | 17'-0" | 16'-4" | 15'-8" | 18'-7" | 17'-4" | 16'-8" | 16'-0" |
| | NI-20 | 17'-10" | 16'-10" | 16'-2" | 15'-7" | 18'-5" | 17'-4" | 16'-9" | 16'-1" |
| | NI-40x | 19'-3" | 17'-10" | 17'-2" | 16'-6" | 19'-10" | 18'-5" | 17'-8" | 16'-11' |
| 11-7/8" | NI-60 | 19'-6" | 18'-1" | 17'-4" | 16'-8" | 20'-1" | 18'-8" | 17'-10" | 17'-1" |
| | NI-80 | 20'-11" | 19'-4" | 18'-5" | 17'-7" | 21'-5" | 19'-10" | 18'-11" | 17'-11' |
| | NI-90 | 21'-4" | 19'-9" | 18'-9" | 17'-10" | 21'-10" | 20'-3" | 19'-3" | 18'-3" |
| | NI-40x | 21'-4" | 19'-9" | 18'-10" | 17'-11" | 22'-0" | 20'-5" | 19'-6" | 18'-6" |
| 14" | NI-60 | 21'-8" | 20'-1" | 19'-2" | 18'-2" | 22'-4" | 20'-9" | 19'-9" | 18'-9" |
| 14 | NI-80 | 23'-3" | 21'-6" | 20'-5" | 19'-4" | 23'-10" | 22'-1" | 21'-0" | 19'-11' |
| | NI-90 | 23'-9" | 21'-11" | 20'-10" | 19'-8" | 24'-3" | 22'-6" | 21'-5" | 20'-3" |
| | NI-60 | 23'-7" | 21'-10" | 20'-10" | 19'-9" | 24'-4" | 22'-7" | 21'-7" | 20'-5" |
| 16" | NI-80 | 25'-4" | 23'-5" | 22'-3" | 21'-1" | 26'-0" | 24'-1" | 22'-11" | 21'-8" |
| | NI-90 | 25'-10" | 23'-10" | 22'-8" | 21'-5" | 26'-5" | 24'-6" | 23'-4" | 22'-0" |

| Joist depth | Joist series | Mid-span blocking with 1x4 inch strap On centre spacing | | | | Mid-span blocking and 1/2 in. gypsum ceiling On centre spacing | | | |
|-------------|--------------|--|---------|---------|---------|---|---------|---------|---------|
| | | | | | | | | | |
| | | 9-1/2" | NI-20 | 16'-10" | 15'-5" | 14'-6" | 13'-5" | 16'-10" | 15'-5" |
| NI-40x | 18'-7" | | 17'-2" | 16'-3" | 14'-11" | 18'-10" | 17'-2" | 16'-3" | 14'-11' |
| NI-60 | 18'-10" | | 17'-6" | 16'-6" | 15'-5" | 19'-1" | 17'-6" | 16'-6" | 15'-5" |
| NI-80 | 20'-2" | | 18'-9" | 17'-11" | 16'-10" | 20'-7" | 19'-2" | 18'-2" | 16'-10' |
| 11-7/8" | NI-20 | 20'-1" | 18'-5" | 17'-5" | 16'-1" | 20'-1" | 18'-5" | 17'-5" | 16'-1" |
| | NI-40x | 21'-9" | 20'-3" | 19'-0" | 17'-0" | 22'-4" | 20'-5" | 19'-0" | 17'-0" |
| | NI-60 | 22'-0" | 20'-6" | 19'-7" | 18'-4" | 22'-7" | 20'-10" | 19'-8" | 18'-4" |
| | NI-80 | 23'-6" | 21'-10" | 20'-10" | 19'-9" | 24'-0" | 22'-5" | 21'-4" | 20'-0" |
| | NI-90 | 24'-0" | 22'-4" | 21'-3" | 20'-1" | 24'-6" | 22'-10" | 21'-9" | 20'-7" |
| 14" | NI-40x | 24'-4" | 22'-8" | 20'-11" | 18'-8" | 25'-0" | 22'-11" | 20'-11" | 18'-8" |
| | NI-60 | 24'-9" | 23'-0" | 22'-0" | 20'-9" | 25'-5" | 23'-8" | 22'-4" | 20'-10' |
| | NI-80 | 26'-5" | 24'-6" | 23'-4" | 22'-1" | 27'-0" | 25'-2" | 24'-0" | 22'-8" |
| | NI-90 | 26'-11" | 25'-0" | 23'-10" | 22'-6" | 27'-5" | 25'-7" | 24'-5" | 23'-1" |
| 16" | NI-60 | 27'-2" | 25'-4" | 24'-2" | 22'-10" | 27'-11" | 26'-1" | 24'-9" | 23'-1" |
| | NI-80 | 29'-0" | 26'-11" | 25'-8" | 24'-3" | 29'-7" | 27'-7" | 26'-4" | 24'-11' |
| | NI-90 | 29'-6" | 27'-5" | 26'-1" | 24'-8" | 30'-1" | 28'-1" | 26'-9" | 25'-4" |

- 1. The tabulated clear spans are based on CSA 086-14 and NBC 2015, and are applicable to residential floor construction meeting the above design criteria.
- 2. For multiple-span applications, the end spans shall be 40% or more of the adjacent span.
- 3. Minimum bearing length shall be 1-3/4 inch for end bearings, and 3-1/2 inches for intermediate bearings.
- 4. Bearing stiffeners are not required when I-joists are used in accordance with this table, except as required for hangers.
- 5. Nordic I-joists are listed in CCMC Evaluation Report 13032-R and APA Product Report PR-L274C.



Notes:


- 1. To prevent interference with plumbing, a joist may be shifted up to 3 inches if the edge of the floor panel is supported and the span rating is not exceeded.
- 2. In all other cases, an additional joist is required.


All nails shown in the details are assumed to be common nails unless otherwise noted. Nails shall have a diameter not less than 0.128 inch for 2-1/2-inch nails, or 0.144 inch for 3-inch nails. Individual components not shown to scale for clarity.





| Allowance for Piping | | 7c | | | |
|---|-------|-----------------|--------------|--|--|
| CATEGORY Openings for Vertical Elements | SCALE | DATE 2020-10-01 | PAGE 3.10 | | |
| Openings for Vertical Elements | - | 2020-10-01 | 3.10 | | |





Notes:

- 1. Blocking required at bearing for lateral support, not shown for clarity.
- 2. The maximum dimensions for a notch on the side of the top flange are 4-inch length by 1/2-inch depth for flange width of 2-1/2 inches, and 4-inch length by 1-inch depth for flange width of 3-1/2 inches.
- 3. This detail applies to simple-span joists and multiple-span joists where the notch is located at the end half-span.
- 4. For other applications, contact Nordic Structures.

All nails shown in the details are assumed to be common nails unless otherwise noted. Nails shall have a diameter not less than 0.128 inch for 2-1/2-inch nails, or 0.144 inch for 3-inch nails. Individual components not shown to scale for clarity.





| TITLE | DRAWING | DRAWING | | | | |
|------------------------------------|---------|------------|------|--|--|--|
| Notch in I-joist for Heat Register | | 7d | | | | |
| | | | _ | | | |
| CATEGORY | SCALE | DATE | PAGE | | | |
| Openings for Vertical Elements | - | 2020-10-01 | 3.11 | | | |