


MHP 23030



| Hanger Name | Symbol | QTY |
|-------------|--------|-----|
| LUS24 | ▲ | 2 |
| LJS26DS | ■ | 21 |
| | ● | 0 |
| | ◆ | 0 |
| H2.5A | △ | 6 |
| | □ | 0 |
| | ◊ | 0 |
| | ○ | 0 |

BOTTOM OF BEAM INSTALLED AT 7' 10 1/2"



CONVENTIONAL FRAMING BY OTHERS

ALL CONVENTIONAL FRAMING TO CONFORM WITH PART 9 OF THE OBC. ROOF RAFTERS THAT CROSS OVER TRUSSES TO BE MIN. 2x4 SPF @ 24" C/C WITH A 2x4 VERTICAL POST TO THE TRUSS BELOW. VERTICAL POSTS TO BE LATERALLY BRACED SO THAT UNBRACED LENGTH DOES NOT EXCEED 6'. DESIGN OF CONVENTIONAL FRAMING IS THE RESPONSIBILITY OF THE PROJECT ENGINEER.

JOB INFORMATION

| | |
|-----------|---|
| Customer | GREENPARK HOMES |
| Job # | 23-00116R0 |
| Address | ZADORRA ESTATES ROSE 6 EL 2 OSHAWA,ON |
| Model | ROSE 6 EL 2 |
| Sales Rep | RALPH MIRIGELLO |
| Designer | BB |
| Date | 6/2/2023 |
| Path | S:\DESIGN\KLU\CUSTOMERS\GREENPARK\ZADORRA ESTATES\MODELS\ROSE 6\ROSE 6-2\T-ROSE |

DESIGN INFORMATION

| | |
|---------------|---|
| Code | NBCC 2015 |
| Bldg | Residential - HSB (NBCC Part 9) |
| TC LL | 34.8 lb/ft² |
| TC DL | 6.0 lb/ft² |
| BC LL | 0.0 lb/ft² |
| BC DL | 7.3 lb/ft² |
| Deflection | LL=L/360 TL=L/360 |
| Spacing | 24" O/C unless otherwise noted |
| Complies With | OBC 2012 (2019 Amendment) CSA O86-14 and TPIC 2014 |

IMPORTANT INFORMATION

- Hangers and Fasteners to be installed as per manufacturer
- Refer to truss drawings in the Truss Engineering Package for ply-to-ply attachment notes
- For site-framed valleys: top chords of all roof trusses must be laterally supported using 2x4 continuous bracing @24 O/C - all bracing must be anchored at ends as per TPIC Installation Guidelines
- Read all notes on this page in addition to those shown on the KOTT Truss Engineering package
- Field erection, handling and bracing are not the responsibility of KOTT, or KOTT Engineering
- Unless noted otherwise, hurricane ties are to be installed at the bearings of all trusses > 40 ft clear span, and any girder or beam supporting trusses with a clear span >40 ft. See hanger legend for type.
- Unless noted otherwise, for Part 9 bldgs, all trusses are to be anchored to the top of supporting walls as follows: trusses with a clear span <40 ft use 3-1/4" nails @ each bearing; trusses with a clear span >40 ft use 3-1/4" nails @ each bearing in addition to the appropriate hurricane tie.

KOTT Inc.
14 Anderson Blvd.
Uxbridge, ON
905.642.4400



PLEASE READ ALL NOTES PRIOR TO INSTALLATION OF THE COMPONENT

RESPONSIBILITIES

THE UNDERSIGNED ENGINEER IS ONLY RESPONSIBLE FOR THE STRUCTURAL INTEGRITY OF THIS BUILDING COMPONENT FOR THE CONDITIONS AND LOADS SHOWN ON CALCULATION PAGE. THE STRUCTURAL INTEGRITY OF THE BUILDING AND THE VERIFICATION OF THE DIMENSIONS AND THE DESIGN LOADS USED ARE THE RESPONSIBILITY OF THE BUILDING DESIGNER. THE UNDERSIGNED ENGINEER DISCLAIMS ANY RESPONSIBILITY FOR DAMAGES AS A RESULT OF FAULTY OR INCORRECT INFORMATION, SPECIFICATION AND/OR DESIGNS FURNISHED TO THE ENGINEER.

IT IS THE RESPONSIBILITY OF KOTT Inc. TO ENSURE THAT TRUSSES ARE MANUFACTURED IN CONFORMANCE WITH THESE DESIGNS AND WITH THE SPECIFICATIONS OUTLINED BELOW. THE UNDERSIGNED ENGINEER IS NOT RESPONSIBLE FOR QUALITY CONTROL IN THE TRUSS MANUFACTURING PLANT.

DESIGN INFORMATION

THIS DESIGN IS FOR AN INDIVIDUAL BUILDING COMPONENT AND HAS BEEN BASED ON INFORMATION PROVIDED BY KOTT DESIGN.

1. THE BUILDING USE AND OCCUPANCY TYPE IS AS INDICATED ON THE DRAWING.
2. GEOMETRY OF THE TRUSS AND DIMENSIONS INDICATED ON THE DRAWING ARE IDENTICAL TO THOSE OF THE INSTALLED TRUSS.
3. THE TRUSS LOADING INTENSITY AND DISTRIBUTION AS WELL AS LOAD TRANSFER MECHANISM IS THAT INDICATED ON THE DRAWING. NO BUILDINGS, TREES, PARAPETS OR OTHER PROJECTIONS HIGHER THAN THE ROOF FOR WHICH THE TRUSSES ARE USED ARE LOCATED WITHIN A DISTANCE LESS THAN TEN (10) TIMES THE DIFFERENCE IN HEIGHT, OR FIVE METERS (16 FT) WHICHEVER IS GREATER, UNLESS THE DRAWING INDICATES THAT THE SNOW DRIFTING HAS BEEN TAKEN INTO ACCOUNT.
4. THE TRUSSES ARE TO BE SUPPORTED AT THE BEARING POINTS INDICATED AND ANCHORED TO THE SUPPORTS WHERE CONSIDERED NECESSARY BY THE DESIGNER OF THE OVERALL STRUCTURE. BEARING SIZES SHOWN ARE THE MINIMUM REQUIRED TO PREVENT CRUSHING OF THE TRUSS MEMBERS AND DO NOT NECESSARILY TAKE INTO ACCOUNT STABILITY OF THE OVERALL BUILDING STRUCTURE. ELEVATION OF BEARINGS MUST BE CAREFULLY CHECKED AND SHIMMED TO ALIGNMENT FOR SOLID BEARINGS. ADEQUATE WOOD TRUSS BEARING IS THE RESPONSIBILITY OF THE BUILDING DESIGNER.


CODE

TRUSSES ARE DESIGNED IN CONFORMANCE WITH THE RELEVANT SECTIONS OF THE NATIONAL BUILDING CODE OF CANADA OR THE CANADIAN CODE FOR FARM BUILDINGS, WHICHEVER APPLIES TO THE BUILDING TYPE INDICATED ON THE DRAWING, THE ONTARIO BUILDING CODE, TPIC AND CANADIAN STANDARDS ASSOCIATION GUIDELINES.

HANDLING, INSTALLATION AND BRACING


1. THE TRUSSES MUST BE HANDLED AND INSTALLED BY A QUALIFIED PROFESSIONAL AS PER THE SUPPLIED DOCUMENT TITLED INFORMATION FOR TRUSS INSTALLERS AND THE BCSI-B1 AND BCSI-B3 SUMMARY SHEETS.
2. THE COMPRESSION CHORDS ARE Laterally Braced by continuous rigid diaphragm sheathing or as specified on the drawing.
3. TEMPORARY AND PERMANENT BRACING MUST BE INSTALLED AS INDICATED ON THE TRUSS DRAWING AND ACCORDING TO THE BCSI-B1 AND BCSI-B3 SUMMARY SHEETS. BRACING FOR THE LATERAL STABILITY OF THE TRUSS IS TO BE PROVIDED BY THE BUILDING DESIGNER.
4. IT IS RECOMMENDED THAT A PROFESSIONAL ENGINEER'S ADVICE BE OBTAINED FOR THE BRACING OF TRUSSES SPANNING MORE THAN 12.37M (40'-7").

| JOB NAME | TRUSS NAME | QUANTITY | PLY | JOB DESC. | DRWG NO. |
|------------|--|----------|-----|-------------|-----------|
| IM0723-092 | TRUSS NAME OF PERMIT PLANS Oct 30 2023 | 1 | 1 | TRUSS DESC. | MHP 23030 |

PER: 
CHIEF BUILDING OFFICIALVersion 8.630 S Mar 22 2023 MiTek Industries, Inc. Fri Jul 14 07:33:46 2023 Page 1
ID:bcGHXsLhLjMpVeVc_4eeDgzAk?y-QVc3ID9Jb8zgVbY1BbKa4bCe20YIN564q9?PRbyyE9Z

| | | | | | |
|------------|---------------------------|----------|-----|-------------|------------------|
| JOB NAME | TRUSS NAME | QUANTITY | PLY | JOB DESC. | DRWG NO. |
| IM0723-092 | TRUSS NAME Oct 30 2023 | 1 | 1 | TRUSS DESC. | MHP 23030 |

PER: 
CHIEF BUILDING OFFICIAL



TOTAL WEIGHT = 32 lb

LUMBER

| N. L. G. A. RULES | CHORDS | SIZE | LUMBER | DESCR. |
|-----------------------|--------|------|--------|--------|
| H - A | 2x4 | DRY | No.2 | SPF |
| A - D | 2x4 | DRY | No.2 | SPF |
| E - D | 2x4 | DRY | No.2 | SPF |
| H - E | 2x6 | DRY | No.2 | SPF |
| ALL WEBS | 2x3 | DRY | No.2 | SPF |
| DRY: SEASONED LUMBER. | | | | |

PLATES (table is in inches)

| JT | TYPE | PLATES | W | LEN | Y | X |
|----|---------|--------|-----|------|------|------|
| A | TMVW-t | MT20 | 4.0 | 5.0 | 1.75 | 2.25 |
| B | TMWW-t | MT20 | 3.0 | 4.0 | 1.50 | 1.75 |
| C | TMWW-t | MT20 | 4.0 | 5.0 | 1.75 | 1.00 |
| D | TMV+p | MT20 | 2.0 | 4.0 | | |
| E | BMVW1+t | MT20 | 6.0 | 10.0 | Edge | 2.50 |
| F | BMVW1+t | MT20 | 3.0 | 10.0 | | |
| G | BMVW-t | MT20 | 4.0 | 5.0 | 2.00 | 2.00 |
| H | BMV1+p | MT20 | 2.0 | 4.0 | | |

Edge - INDICATES REFERENCE CORNER OF PLATE TOUCHES EDGE OF CHORD.

DIMENSIONS, SUPPORTS AND LOADINGS SPECIFIED BY FABRICATOR TO BE VERIFIED BY BUILDING DESIGNER**BEARINGS**

| | FACTORED | MAXIMUM FACTORED | INPUT | REQD |
|----|----------------|------------------|-------|--------|
| | GROSS REACTION | GROSS REACTION | BRG | BRG |
| JT | VERT | HORZ | DOWN | UPLIFT |
| H | 1423 | 0 | 1423 | 0 |
| E | 1944 | 0 | 1944 | 0 |

A SUITABLE HANGER/MECHANICAL CONNECTION IS REQUIRED AT JOINT E. MINIMUM BEARING LENGTH AT JOINT E = 3-8.

UNFACTORED REACTIONS

| JT | 1ST LCASE | MAX./MIN. | COMPONENT REACTIONS |
|----|-----------|-----------|---------------------|
| | COMBINED | SNOW | LIVE |
| H | 994 | 720 / 0 | 0 / 0 |
| E | 1359 | 983 / 0 | 0 / 0 |

BEARING MATERIAL TO BE SPF NO.2 OR BETTER AT JOINT(S) H

BRACING

TOP CHORD TO BE SHEATHED OR MAX. PURLIN SPACING = 5.14 FT.
MAX. UNBRACED BOTTOM CHORD LENGTH = 10.00 FT OR RIGID CEILING DIRECTLY APPLIED.

ALL PITCH BREAKS AND PERIMETER CORNER JOINTS MUST BE Laterally RESTRAINED.

LOADING

TOTAL LOAD CASES: (4)

| C H O R D S | | | | W E B S | | | |
|-------------|---------------------------|---------------------------|--------------|---------------------|-------|---------------------------|--------------|
| MEMB. | MAX. FACTORED FORCE (LBS) | FACTORED VERT. LOAD (PLF) | MAX LC1 (LC) | MAX UNBRACED LENGTH | MEMB. | MAX. FACTORED FORCE (LBS) | MAX LC1 (LC) |
| FR-TO | | FROM | TO | | FR-TO | | |
| H-A | -1364 / 0 | 0.0 | 0.0 | 0.15 (1) | A-G | 0 / 1406 | 0.35 (1) |
| A-B | -1464 / 0 | -238.9 | -238.9 | 0.19 (1) | G-B | -313 / 0 | 0.05 (1) |
| B-C | -1318 / 0 | -238.9 | -238.9 | 0.12 (1) | B-F | -202 / 0 | 0.04 (1) |
| C-D | -11 / 0 | -119.4 | -119.4 | 0.07 (1) | F-C | 0 / 1929 | 0.48 (1) |
| E-D | -91 / 0 | 0.0 | 0.0 | 0.02 (1) | C-E | -2069 / 0 | 0.45 (1) |
| H-G | 0 / 0 | -36.5 | -36.5 | 0.03 (1) | | | |
| G-F | 0 / 1321 | -36.5 | -36.5 | 0.36 (1) | | | |
| F-E | 0 / 1175 | -18.2 | -18.2 | 0.34 (1) | | | |

SPECIFIED CONCENTRATED LOADS (LBS)

| JT | LOC. | LC1 | MAX- | MAX+ | FACE | DIR. | TYPE | HEEL | CONN. |
|----|--------|-------|-------|------|-------|------|-------|------|-------|
| F | 4-0-12 | -1385 | -1385 | --- | FRONT | VERT | TOTAL | --- | C1 |

CONNECTION REQUIREMENTS

1) C1: A SUITABLE HANGER/MECHANICAL CONNECTION IS REQUIRED.

DESIGN CRITERIA

*** SPECIAL LOADS ANALYSIS ***
GEOMETRY AND/OR BASIC LOADS CHANGED BY USER.
LOADS WERE DERIVED FROM USER INPUT
NO FURTHER MODIFICATIONS WERE MADE

SPECIFIED LOADS:

| | | | | |
|------------|----|------|------|-----|
| TOP CH. | LL | = | 34.8 | PSF |
| | DL | = | 6.0 | PSF |
| BOT CH. | LL | = | 0.0 | PSF |
| | DL | = | 7.3 | PSF |
| TOTAL LOAD | = | 48.1 | PSF | |

SPACING = 24.0 IN./C

GIRDER TYPE: CPrimeHip
SIDE SETBACK = 0-0
END SETBACK = 6-0-0
END WALL WIDTH = 0-0
CORNER FRAMING TYPE: CONVENTIONAL
END JACK TYPE: CONVENTIONAL
APPLIED TO FRONT SIDE
- ADDTL LOADS BASED ON 55 % OF GSL.
LOADS APPLIED TO FIRST 4-0-12 OF SPAN
MEASURED FROM THE LEFT.

***** NON STANDARD GIRDER *****

ADDTL USER-DEFINED LOADS APPLIED TO ALL LOAD CASES.

THIS TRUSS IS DESIGNED FOR RESIDENTIAL OR SMALL BUILDING REQUIREMENTS OF PART 9, NBCC 2015

THIS DESIGN COMPLIES WITH:

- PART 9 OF BCBC 2018, NBC-2019AE
- PART 9 OF OBC 2012 (2019 AMENDMENT)
- CSA 086-14
- TPIC 2014

(55 % OF 48.1 P.S.F. G.S.L. PLUS 8.4 P.S.F. RAIN LOAD) EQUALS 34.8 P.S.F. SPECIFIED ROOF LIVE LOAD

ALLOWABLE DEFL.(LL)= L/360 (0.20")
CALCULATED VERT. DEFL.(LL)= L/ 999 (0.02")
ALLOWABLE DEFL.(TL)= L/360 (0.20")
CALCULATED VERT. DEFL.(TL)= L/ 999 (0.03")

CSI: TC=0.19/0.97 (A-B:1) , BC=0.36/0.97 (F-G:1) ,
WB=0.48/0.97 (C-F:1) , SSI=0.22/1.00 (A-B:1)

DOL LUMBER=1.00 NAIL=1.00 LS BEND=1.00
COMP=1.00 SHEAR=1.00 TENS= 1.00

COMPANION LIVE LOAD FACTOR = 1.00

TRUSS PLATE MANUFACTURER IS NOT RESPONSIBLE FOR QUALITY CONTROL IN THE TRUSS MANUFACTURING PLANT .

NAIL VALUES

| PLATE | GRIP(DRY) | SHEAR | SECTION |
|-------|-----------|-------|---------|
| (PSI) | (PLI) | (PLI) | |
| MAX | MIN | MAX | MIN |
| MT20 | 650 | 371 | 1747 |

CONTINUED ON PAGE 2



JULY 14, 2023

READ ALL NOTES ON THIS PAGE AND ON THE ENGINEERING NOTES: TRUSSES. THE NOTE PAGE IS AN INTEGRAL PART OF THIS DRAWING AS IT CONTAINS SPECIFICATIONS AND CRITERIA USED IN THE DESIGN OF THIS COMPONENT.

| JOB NAME | TRUSS NAME | QUANTITY | PLY | JOB DESC. | DRWG NO. |
|------------|------------|----------|-----|-------------|----------|
| IM0723-092 | TRUSS NAME | 1 | 1 | TRUSS DESC. | |

OF PERMIT PLANS

Oct 30 2023

PER:

CHIEF BUILDING OFFICIAL

MHP 23030

Version 8.630 S Mar 22 2023 MiTek Industries, Inc. Fri Jul 14 07:33:47 2023 Page 2

ID:bcGHXsLhLjMpVeVc 4eeDgzAk?y-uhARzZAxMR5XWI7DIlrcplzRPvD6a2D3ply 1yyE9Y

PLATE PLACEMENT TOL. = 0.250 inches

PLATE ROTATION TOL. = 5.0 Deg.

JSI GRIP= 0.89 (A) (INPUT = 0.90)

JSI METAL= 0.51 (C) (INPUT = 1.00)



JULY 14, 2023


READ ALL NOTES ON THIS PAGE AND ON THE
ENGINEERING NOTES: TRUSSES. THE NOTE PAGE
IS AN INTEGRAL PART OF THIS DRAWING AS IT
CONTAINS SPECIFICATIONS AND CRITERIA USED
IN THE DESIGN OF THIS COMPONENT.



| | | | | | |
|------------|------------|----------|-----|-------------|------------------|
| JOB NAME | TRUSS NAME | QUANTITY | PLY | JOB DESC. | DRWG NO. |
| IM0723-092 | TRUSS NAME | 1 | 1 | TRUSS DESC. | MHP 23030 |

Version 8.630 S Mar 22 2023 MiTek Industries, Inc. Fri Jul 14 07:33:48 2023 Page 2

ID:bcGHXsLhLjMpVeVc_4eeDgzAk?y-MtkpAvBa7IDO8uiQJ0M290I3npBorwWMITUWWUyyE9X

PER: 
CHIEF BUILDING OFFICIAL

NAIL VALUES
 PLATE GRIP(DRY) SHEAR SECTION
 (PSI) (PLI) (PLI)
 MAX MIN MAX MIN MAX MIN
 MT20 650 371 1747 788 1987 1873
 MT18HS 586 403 2455 1382 3163 3004

PLATE PLACEMENT TOL. = 0.250 inches

PLATE ROTATION TOL. = 5.0 Deg.

JSI GRIP= 0.90 (U) (INPUT = 0.90)
 JSI METAL= 0.98 (R) (INPUT = 1.00)



JULY 14, 2023


READ ALL NOTES ON THIS PAGE AND ON THE
 ENGINEERING NOTES: TRUSSES. THE NOTE PAGE
 IS AN INTEGRAL PART OF THIS DRAWING AS IT
 CONTAINS SPECIFICATIONS AND CRITERIA USED
 IN THE DESIGN OF THIS COMPONENT.



| JOB NAME | TRUSS NAME | QUANTITY | PLY | JOB DESC. | DRWG NO. |
|------------|--|----------|-----|-------------|------------------|
| IM0723-092 | TRUSS NAME OF PERMIT PLANS Oct 30 2023 | 1 | 3 | TRUSS DESC. | MHP 23030 |

Version 8.630 S Mar 22 2023 MiTek Industries, Inc. Fri Jul 14 07:33:49 2023 Page 2

ID:bcGHXsLhLjMpVeVc 4eeDgzAk?y-q3lBNFBCu3MFm2HcsjthIEq99DTWaO6WW7E32wyyE9W

PER: 
CHIEF BUILDING OFFICIAL**PLATES (table is in inches)**

| JT | TYPE | PLATES | W | LEN | Y | X |
|----|---------|--------|-----|------|------|------|
| A | TMVW-t | MT20 | 6.0 | 8.0 | 2.25 | 3.75 |
| B | TMWW-t | MT20 | 3.0 | 5.0 | | |
| C | TS-t | MT20 | 3.0 | 8.0 | | |
| D | TMWW+t | MT20 | 3.0 | 4.0 | 1.75 | 0.75 |
| E | TMWW+t | MT20 | 4.0 | 4.0 | 1.50 | 1.00 |
| F | TTW+p | MT20 | 6.0 | 8.0 | Edge | |
| G | TMWW-t | MT20 | 4.0 | 5.0 | 1.50 | 1.25 |
| H | TMWW+t | MT20 | 3.0 | 5.0 | 1.75 | 0.75 |
| I | TMWW-t | MT20 | 3.0 | 4.0 | 1.50 | 1.75 |
| J | TS-t | MT20 | 3.0 | 8.0 | | |
| K | TMVW-t | MT20 | 5.0 | 10.0 | 1.75 | 4.50 |
| L | BMV1+p | MT20 | 4.0 | 4.0 | 2.25 | 2.00 |
| L | TP-t | MT20 | 3.0 | 6.0 | 2.50 | 2.75 |
| M | BMWW-t | MT20 | 8.0 | 8.0 | 4.00 | 3.50 |
| N | BMWW+t | MT20 | 3.0 | 5.0 | 2.00 | 1.50 |
| O | BMWW+t | MT20 | 3.0 | 6.0 | 1.75 | 1.50 |
| P | BSWWW+t | MT20 | 6.0 | 10.0 | Edge | 3.00 |
| Q | BMWW+t | MT20 | 4.0 | 5.0 | 2.50 | 1.75 |
| R | BMWW-t | MT20 | 4.0 | 4.0 | | |
| S | BMWW-t | MT20 | 6.0 | 8.0 | 3.00 | 2.75 |
| T | BMV1+p | MT20 | 4.0 | 4.0 | 2.25 | 2.00 |
| T | TP-t | MT20 | 3.0 | 6.0 | 2.50 | 2.75 |

Edge - INDICATES REFERENCE CORNER OF PLATE
TOUCHES EDGE OF CHORD.DOL LUMBER=1.00 NAIL=1.00 LS BEND=1.10
COMP=1.10 SHEAR=1.10 TENS= 1.10

COMPANION LIVE LOAD FACTOR = 1.00

TRUSS PLATE MANUFACTURER IS NOT
RESPONSIBLE FOR QUALITY CONTROL IN
THE TRUSS MANUFACTURING PLANT .

NAIL VALUES

| PLATE | GRIP(DRY) | SHEAR | SECTION |
|-------|-----------|-------|---------|
| | (PSI) | (PLI) | (PLI) |
| | MAX | MIN | MAX |
| | MIN | MAX | MIN |
| MT20 | 650 | 371 | 1747 |
| | | | 788 |
| | | | 1987 |
| | | | 1873 |

PLATE PLACEMENT TOL. = 0.250 inches

PLATE ROTATION TOL. = 5.0 Deg.

JSI GRIP= 0.90 (A) (INPUT = 0.90)
JSI METAL= 0.93 (M) (INPUT = 1.00)

JULY 14, 2023

READ ALL NOTES ON THIS PAGE AND ON THE
ENGINEERING NOTES: TRUSSES. THE NOTE PAGE
IS AN INTEGRAL PART OF THIS DRAWING AS IT
CONTAINS SPECIFICATIONS AND CRITERIA USED
IN THE DESIGN OF THIS COMPONENT.



| | | | | | |
|--|------------|----------|-----|-------------|-----------|
| JOB NAME | TRUSS NAME | QUANTITY | PLY | JOB DESC. | DRWG NO. |
| IM0723-092 | TRUSS NAME | 1 | 2 | TRUSS DESC. | MHP 23030 |
| Version 8.630 S Mar 22 2023 MiTek Industries, Inc. Fri Jul 14 07:33:50 2023 Page 2 | | | | | |
| ID:bcGHXsLhLjMpVeVc_4eeDgzAk?y-IGrabbCqfMU6NCsoQROWERNRIdvoJv0finzcaMyyE9V | | | | | |

PER: 
CHIEF BUILDING OFFICIAL

PLATES (table is in inches)

| JT | TYPE | PLATES | W | LEN | Y | X |
|----|---------|--------|-----|-----|------|------|
| I | BMWVW+t | MT20 | 6.0 | 6.0 | 2.75 | 3.00 |
| J | BMWVW-t | MT20 | 6.0 | 6.0 | 3.50 | 2.50 |
| K | BMV1+p | MT20 | 3.0 | 4.0 | | |


JSI GRIP= 0.89 (H) (INPUT = 0.90)
JSI METAL= 0.46 (H) (INPUT = 1.00)




JULY 14, 2023

READ ALL NOTES ON THIS PAGE AND ON THE
ENGINEERING NOTES: TRUSSES. THE NOTE PAGE
IS AN INTEGRAL PART OF THIS DRAWING AS IT
CONTAINS SPECIFICATIONS AND CRITERIA USED
IN THE DESIGN OF THIS COMPONENT.








TOTAL WEIGHT = 92 lb

JSI GRIP= 0.90 (B) (INPUT = 0.90)
JSI METAL= 0.67 (I) (INPUT = 1.00)



**READ ALL NOTES ON THIS PAGE AND ON THE
ENGINEERING NOTES: TRUSSES. THE NOTE PAGE
IS AN INTEGRAL PART OF THIS DRAWING AS IT
CONTAINS SPECIFICATIONS AND CRITERIA USED
IN THE DESIGN OF THIS COMPONENT.**




| | | | | | |
|------------|------------|----------|-----|-------------|------------------|
| JOB NAME | TRUSS NAME | QUANTITY | PLY | JOB DESC. | DRWG NO. |
| IM0723-092 | CE04 | 1 | 1 | TRUSS DESC. | MHP 23030 |

Oct 30 2023

 PER: CHIEF BUILDING OFFICIAL

Version 8.630 S Mar 22 2023 MiTek Industries, Inc. Fri Jul 14 07:33:53 2023 Page 1

ID:bcGHXsLhLjMpVeVc_4eeDgzAk?y-jrXiDdEiyHshFgbN5ZyDs4?_Hq11WLi6RICHBhyyE9S



Scale = 1:56.4

TOTAL WEIGHT = 68 lb

LUMBER

N. L. G. A. RULES

CHORDS SIZE

| CHORDS | SIZE | DRY | No.2 | DESCR. |
|--------|------|-----|------|--------|
| A - F | 2x4 | DRY | No.2 | SPF |
| F - K | 2x4 | DRY | No.2 | SPF |
| T - B | 2x4 | DRY | No.2 | SPF |
| L - J | 2x4 | DRY | No.2 | SPF |
| T - L | 2x4 | DRY | No.2 | SPF |

ALL WEBS 2x3 DRY No.2

ALL GABLE WEBS 2x3 DRY No.2

DRY: SEASONED LUMBER.

GABLE STUDS SPACED AT 2-0-0 OC.

PLATES (table is in inches)

| JT TYPE | PLATES | W | LEN | Y | X |
|---------------------|--------|-----|-----|------|------|
| B TMV+p | MT20 | 2.0 | 4.0 | | |
| C, D, E, G, H, I | | | | | |
| C TMW+w | MT20 | 2.0 | 4.0 | | |
| F TTW+p | MT20 | 3.0 | 4.0 | 2.50 | 1.50 |
| J TMV+p | MT20 | 2.0 | 4.0 | | |
| L BMV1+p | MT20 | 2.0 | 4.0 | | |
| M, N, O, P, Q, R, S | | | | | |
| M BMW1+w | MT20 | 2.0 | 4.0 | | |
| T BMV1+p | MT20 | 2.0 | 4.0 | | |

DIMENSIONS, SUPPORTS AND LOADINGS SPECIFIED BY FABRICATOR TO BE VERIFIED BY BUILDING DESIGNER**BEARINGS**

THIS TRUSS DESIGNED FOR CONTINUOUS BEARINGS.

THIS TRUSS REQUIRES RIGID SHEATHING ON EXPOSED FACE.

BEARING MATERIAL TO BE SPF NO.2 OR BETTER AT JOINT(S)

BRACINGTOP CHORD TO BE SHEATHED OR MAX. PURLIN SPACING = 6.25 FT.
MAX. UNBRACED BOTTOM CHORD LENGTH = 6.25 FT OR RIGID CEILING DIRECTLY APPLIED.

ALL PITCH BREAKS AND PERIMETER CORNER JOINTS MUST BE Laterally RESTRAINED.

LOADING

TOTAL LOAD CASES: (4)

| CHORDS | | | | WEBS | | | |
|--------|---------------------------|---------------------------|------------------------|----------|---------------------------|------------------------|----------|
| MEMB. | MAX. FACTORED FORCE (LBS) | FACTORED VERT. LOAD (PLF) | MAX. FACTORED CSI (LC) | MEMB. | MAX. FACTORED FORCE (LBS) | MAX. FACTORED CSI (LC) | |
| FR-TO | | FROM TO | LENGTH | FR-TO | | | |
| A-B | 0 / 53 | -119.4 -119.4 | 0.16 (1) | 10.00 | P-F | -301 / 0 | 0.30 (1) |
| B-C | -16 / 0 | -119.4 -119.4 | 0.11 (1) | 6.25 | Q-E | -243 / 0 | 0.13 (1) |
| C-D | 0 / 37 | -119.4 -119.4 | 0.06 (1) | 10.00 | R-D | -246 / 0 | 0.07 (1) |
| D-E | 0 / 37 | -119.4 -119.4 | 0.06 (1) | 10.00 | S-C | -101 / 0 | 0.02 (1) |
| E-F | 0 / 41 | -119.4 -119.4 | 0.07 (1) | 10.00 | O-G | -243 / 0 | 0.13 (1) |
| F-G | 0 / 41 | -119.4 -119.4 | 0.07 (1) | 10.00 | N-H | -246 / 0 | 0.07 (1) |
| G-H | 0 / 37 | -119.4 -119.4 | 0.06 (1) | 10.00 | M-I | -101 / 0 | 0.02 (1) |
| H-I | 0 / 37 | -119.4 -119.4 | 0.06 (1) | 10.00 | | | |
| I-J | -16 / 0 | -119.4 -119.4 | 0.11 (1) | 6.25 | | | |
| J-K | 0 / 53 | -119.4 -119.4 | 0.16 (1) | 10.00 | | | |
| T-B | -271 / 0 | 0.0 | 0.0 | 0.05 (1) | 7.81 | | |
| L-J | -271 / 0 | 0.0 | 0.0 | 0.05 (1) | 7.81 | | |
| T-S | -18 / 0 | -18.2 | -18.2 | 0.01 (1) | 6.25 | | |
| S-R | -22 / 0 | -18.2 | -18.2 | 0.02 (4) | 6.25 | | |
| R-Q | -28 / 0 | -18.2 | -18.2 | 0.02 (4) | 6.25 | | |
| Q-P | -33 / 0 | -18.2 | -18.2 | 0.01 (4) | 6.25 | | |
| P-O | -33 / 0 | -18.2 | -18.2 | 0.01 (4) | 6.25 | | |
| O-N | -28 / 0 | -18.2 | -18.2 | 0.02 (4) | 6.25 | | |
| N-M | -22 / 0 | -18.2 | -18.2 | 0.02 (4) | 6.25 | | |
| M-L | -18 / 0 | -18.2 | -18.2 | 0.01 (1) | 6.25 | | |

DESIGN CRITERIA

SPECIFIED LOADS:

| | | | |
|------------|------|------|-----|
| TOP CH. | LL = | 34.8 | PSF |
| | DL = | 6.0 | PSF |
| BOT CH. | LL = | 0.0 | PSF |
| | DL = | 7.3 | PSF |
| TOTAL LOAD | = | 48.1 | PSF |

SPACING = 24.0 IN. C/C

THIS TRUSS IS DESIGNED FOR RESIDENTIAL OR SMALL BUILDING REQUIREMENTS OF PART 9, NBCC 2015

THIS DESIGN COMPLIES WITH:

- PART 9 OF BCBC 2018 , NBC-2019AE
- PART 9 OF OBC 2012 (2019 AMENDMENT)
- CSA 086-14
- TPIC 2014

DESIGN ASSUMPTIONS

-OVERHANG NOT TO BE ALTERED OR CUT OFF.

(55 % OF 48.1 P.S.F. G.S.L. PLUS 8.4 P.S.F. RAIN LOAD) EQUALS 34.8 P.S.F. SPECIFIED ROOF LIVE LOAD

CSI: TC=0.16/0.97 (J-K:1) , BC=0.02/0.97 (Q-R:4) , WB=0.30/0.97 (F-P:1) , SSI=0.10/1.00 (J-K:1)

DOL LUMBER=1.00 NAIL=1.00 LS BEND=1.10 COMP=1.10 SHEAR=1.10 TENS= 1.10

COMPANION LIVE LOAD FACTOR = 1.00

TRUSS PLATE MANUFACTURER IS NOT RESPONSIBLE FOR QUALITY CONTROL IN THE TRUSS MANUFACTURING PLANT .

NAIL VALUES

| PLATE | GRIP(DRY) | SHEAR | SECTION |
|-------|-----------|-------|--------------------|
| | (PSI) | (PLI) | (PLI) |
| | MAX | MIN | MAX MIN |
| MT20 | 650 | 371 | 1747 788 1987 1873 |

PLATE PLACEMENT TOL. = 0.250 inches

PLATE ROTATION TOL. = 5.0 Deg.

JSI GRIP= 0.38 (F) (INPUT = 0.90)

JSI METAL= 0.13 (J) (INPUT = 1.00)




JULY 14, 2023

READ ALL NOTES ON THIS PAGE AND ON THE ENGINEERING NOTES: TRUSSES. THE NOTE PAGE IS AN INTEGRAL PART OF THIS DRAWING AS IT CONTAINS SPECIFICATIONS AND CRITERIA USED IN THE DESIGN OF THIS COMPONENT.



| | | | | | |
|------------|------------|----------|-----|-------------|-----------|
| JOB NAME | TRUSS NAME | QUANTITY | PLY | JOB DESC. | DRWG NO. |
| IM0723-092 | TRUSS NAME | 2 | 1 | TRUSS DESC. | MHP 23030 |

PER: 
CHIEF BUILDING OFFICIAL



Scale = 1:25.7

TOTAL WEIGHT = 2 X 10 = 20 lb

LUMBER

| N. L. G. A. RULES | CHORDS | SIZE | LUMBER | DESCR. |
|-------------------|--------|------|--------|--------|
| E - B | 2x4 | DRY | No.2 | SPF |
| A - C | 2x4 | DRY | No.2 | SPF |
| E - D | 2x4 | DRY | No.2 | SPF |

DRY: SEASONED LUMBER.

PLATES (table is in inches)

| JT | TYPE | PLATES | W | LEN | Y | X |
|----|--------|--------|-----|-----|---|---|
| B | TMV+p | MT20 | 2.0 | 4.0 | | |
| E | BMV1+p | MT20 | 2.0 | 4.0 | | |

DIMENSIONS, SUPPORTS AND LOADINGS SPECIFIED BY FABRICATOR TO BE VERIFIED BY BUILDING DESIGNER**BEARINGS**

| | FACTORED GROSS REACTION | MAXIMUM FACTORED GROSS REACTION | INPUT BRG | REQRD BRG |
|----|-------------------------|---------------------------------|-----------|-----------|
| JT | VERT | HORZ | DOWN | HORZ |
| E | 483 | 0 | 483 | 0 |
| C | 181 | 0 | 181 | 0 |
| D | 16 | 0 | 16 | 0 |

SEE MITEK STANDARD DETAIL MSD2015-H FOR CONNECTION TO JOINT(S) C, D

UNFACTORED REACTIONS

| JT | 1ST LCASE | MAX./MIN. | COMPONENT REACTIONS |
|----|-----------|-----------|---------------------|
| JT | COMBINED | SNOW | LIVE |
| E | 333 | 270 / 0 | 0 / 0 |
| C | 124 | 105 / 0 | 0 / 0 |
| D | 13 | 0 / 0 | 0 / 0 |

BEARING MATERIAL TO BE SPF NO.2 OR BETTER AT JOINT(S) E

BRACING

TOP CHORD TO BE SHEATHED OR MAX. PURLIN SPACING = 6.25 FT.
MAX. UNBRACED BOTTOM CHORD LENGTH = 10.00 FT OR RIGID CEILING DIRECTLY APPLIED.

ALL PITCH BREAKS AND PERIMETER CORNER JOINTS MUST BE Laterally RESTRAINED.

LOADING

TOTAL LOAD CASES: (4)

| MEMB. | MAX. FACTORED FORCE (LBS) | FACTORED VERT. LOAD (PLF) | LC1 MAX | MAX. UNBRACED LENGTH | MEMB. | MAX. FACTORED FORCE (LBS) | MAX. UNBRACED LENGTH |
|-------|---------------------------|---------------------------|---------|----------------------|-------|---------------------------|----------------------|
| FR-TO | | FROM | TO | | FR-TO | | |
| E-B | -463 / 0 | 0.0 | 0.0 | 0.01 (4) | 7.81 | | |
| A-B | 0 / 36 | -119.4 | -119.4 | 0.16 (1) | 10.00 | | |
| B-C | -27 / 0 | -119.4 | -119.4 | 0.33 (1) | 6.25 | | |
| E-D | 0 / 0 | -18.2 | -18.2 | 0.02 (4) | 10.00 | | |

DESIGN CRITERIA**SPECIFIED LOADS:**

| | | | | |
|------------|----|------|------|-----|
| TOP CH. | LL | = | 34.8 | PSF |
| | DL | = | 6.0 | PSF |
| BOT CH. | LL | = | 0.0 | PSF |
| | DL | = | 7.3 | PSF |
| TOTAL LOAD | = | 48.1 | PSF | |

SPACING = 24.0 IN. C/C

THIS TRUSS IS DESIGNED FOR RESIDENTIAL OR SMALL BUILDING REQUIREMENTS OF PART 9, NBCC 2015

THIS DESIGN COMPLIES WITH:

- PART 9 OF BCBC 2018, NBC-2019AE
- PART 9 OF OBC 2012 (2019 AMENDMENT)
- CSA 086-14
- TPIC 2014

DESIGN ASSUMPTIONS

-OVERHANG NOT TO BE ALTERED OR CUT OFF.

(55 % OF 48.1 P.S.F. G.S.L. PLUS 8.4 P.S.F. RAIN LOAD) EQUALS 34.8 P.S.F. SPECIFIED ROOF LIVE LOAD

ALLOWABLE DEFL.(LL)= L/360 (0.19")
CALCULATED VERT. DEFL.(LL) = L/ 999 (0.00")
ALLOWABLE DEFL.(TL)= L/360 (0.19")
CALCULATED VERT. DEFL.(TL) = L/ 999 (0.00")

CSI: TC=0.33/0.97 (B-C); BC=0.02/0.97 (D-E);
WB=0.00/0.97 (n/a:0); SSI=0.21/1.00 (B-C:1)

DOL LUMBER=1.00 NAIL=1.00 LS BEND=1.10
COMP=1.10 SHEAR=1.10 TENS=1.10

COMPANION LIVE LOAD FACTOR = 1.00

TRUSS PLATE MANUFACTURER IS NOT RESPONSIBLE FOR QUALITY CONTROL IN THE TRUSS MANUFACTURING PLANT.

NAIL VALUES

| PLATE | GRIP(DRY) (PSI) | SHEAR (PLI) | SECTION (PLI) |
|-------|-----------------|-------------|---------------|
| | MAX | MIN | MAX |
| MT20 | 650 | 371 | 1747 |

PLATE PLACEMENT TOL. = 0.250 inches

PLATE ROTATION TOL. = 5.0 Deg.

JSI GRIP= 0.26 (B) (INPUT = 0.90)
JSI METAL= 0.19 (B) (INPUT = 1.00)




JULY 14, 2023

READ ALL NOTES ON THIS PAGE AND ON THE ENGINEERING NOTES: TRUSSES. THE NOTE PAGE IS AN INTEGRAL PART OF THIS DRAWING AS IT CONTAINS SPECIFICATIONS AND CRITERIA USED IN THE DESIGN OF THIS COMPONENT.



| | | | | | |
|------------|------------|----------|-----|-------------|------------------|
| JOB NAME | TRUSS NAME | QUANTITY | PLY | JOB DESC. | DRWG NO. |
| IM0723-092 | JO A | 1 | 1 | TRUSS DESC. | MHP 23030 |

PER: 
CHIEF BUILDING OFFICIAL



Scale = 1:25.7

TOTAL WEIGHT = 8 lb

| LUMBER | | | | |
|-------------------|---------|--------|--------|--|
| N. L. G. A. RULES | SIZE | LUMBER | DESCR. | |
| CHORDS | | | SPF | |
| D - A | 2x4 DRY | No.2 | SPF | |
| A - B | 2x4 DRY | No.2 | SPF | |
| D - C | 2x4 DRY | No.2 | SPF | |

DRY: SEASONED LUMBER.

PLATES (table is in inches)

| JT | TYPE | PLATES | W | LEN | Y | X |
|----|--------|--------|-----|-----|---|---|
| A | TMV+p | MT20 | 2.0 | 4.0 | | |
| D | BMV1+p | MT20 | 2.0 | 4.0 | | |

DIMENSIONS, SUPPORTS AND LOADINGS SPECIFIED BY FABRICATOR TO BE VERIFIED BY BUILDING DESIGNER**BEARINGS**

| JT | FACTORED GROSS REACTION | MAXIMUM FACTORED GROSS REACTION | INPUT BRG | REQRD BRG |
|----|-------------------------|---------------------------------|-----------|-----------|
| | VERT | HORZ | DOWN | HORZ |
| D | 229 | 0 | 229 | 0 |
| B | 212 | 0 | 212 | 0 |
| C | 78 | 0 | 78 | 0 |

A SUITABLE HANGER/MECHANICAL CONNECTION IS REQUIRED AT JOINT D. MINIMUM BEARING LENGTH AT JOINT D = 1-8.

SEE MITEK STANDARD DETAIL MSD2015-H FOR CONNECTION TO JOINT(S) B , C

UNFACTORED REACTIONS

| JT | 1ST LCASE COMBINED | MAX./MIN. SNOW | LIVE | PERM.LIVE | WIND | DEAD | SOIL |
|----|--------------------|----------------|-------|-----------|-------|--------|-------|
| D | 159 | 123 / 0 | 0 / 0 | 0 / 0 | 0 / 0 | 36 / 0 | 0 / 0 |
| B | 145 | 123 / 0 | 0 / 0 | 0 / 0 | 0 / 0 | 22 / 0 | 0 / 0 |
| C | 55 | 35 / 0 | 0 / 0 | 0 / 0 | 0 / 0 | 20 / 0 | 0 / 0 |

BRACING

TOP CHORD TO BE SHEATHED OR MAX. PURLIN SPACING = 6.25 FT.
MAX. UNBRACED BOTTOM CHORD LENGTH = 10.00 FT OR RIGID CEILING DIRECTLY APPLIED.

ALL PITCH BREAKS AND PERIMETER CORNER JOINTS MUST BE Laterally RESTRAINED.

LOADING

TOTAL LOAD CASES: (4)

| CHORDS | | | | WEBS | | | |
|--------|---------------------------|---------------------------|---------------|----------|---------------------------|---------------|--|
| MEMB. | MAX. FACTORED FORCE (LBS) | FACTORED VERT. LOAD (PLF) | MAX. CSI (LC) | MEMB. | MAX. FACTORED FORCE (LBS) | MAX. CSI (LC) | |
| FR-TO | | FROM | TO | FR-TO | | | |
| D-A | -270 / 0 | 0.0 | 0.0 | 0.14 (1) | 7.81 | | |
| A-B | -13 / 0 | -119.4 | -119.4 | 0.24 (1) | 6.25 | | |
| D-C | 0 / 0 | -18.2 | -18.2 | 0.16 (1) | 10.00 | | |

DESIGN CRITERIA**SPECIFIED LOADS:**

| | | | | |
|------------|----|------|------|-----|
| TOP CH. | LL | = | 34.8 | PSF |
| | DL | = | 6.0 | PSF |
| BOT CH. | LL | = | 0.0 | PSF |
| | DL | = | 7.3 | PSF |
| TOTAL LOAD | = | 48.1 | PSF | |

SPACING = 24.0 IN. C/C

THIS TRUSS IS DESIGNED FOR RESIDENTIAL OR SMALL BUILDING REQUIREMENTS OF PART 9, NBCC 2015

THIS DESIGN COMPLIES WITH:

- PART 9 OF BCBC 2018 , NBC-2019AE
- PART 9 OF OBC 2012 (2019 AMENDMENT)
- CSA 086-14
- TPIC 2014

(55 % OF 48.1 P.S.F. G.S.L. PLUS 8.4 P.S.F. RAIN LOAD) EQUALS 34.8 P.S.F. SPECIFIED ROOF LIVE LOAD

ALLOWABLE DEFL.(LL)= L/360 (0.19")
CALCULATED VERT. DEFL.(LL) = L/ 999 (0.00")
ALLOWABLE DEFL.(TL)= L/360 (0.19")
CALCULATED VERT. DEFL.(TL) = L/ 999 (0.01")

CSI: TC=0.24/0.97 (A-B:1) , BC=0.16/0.97 (C-D:1) ,
WB=0.00/0.97 (n/a:0) , SSI=0.19/1.00 (A-B:1)

DOL LUMBER=1.00 NAIL=1.00 LS BEND=1.10
COMP=1.10 SHEAR=1.10 TENS= 1.10

COMPANION LIVE LOAD FACTOR = 1.00

TRUSS PLATE MANUFACTURER IS NOT RESPONSIBLE FOR QUALITY CONTROL IN THE TRUSS MANUFACTURING PLANT .

NAIL VALUES

| PLATE | GRIP(DRY) | SHEAR (PSI) | SECTION (PLI) |
|-------|-----------|-------------|---------------|
| MT20 | 650 | 371 | 1747 |

PLATE PLACEMENT TOL. = 0.250 inches

PLATE ROTATION TOL. = 5.0 Deg.

JSI GRIP= 0.15 (A) (INPUT = 0.90)
JSI METAL= 0.11 (A) (INPUT = 1.00)



JULY 14, 2023

READ ALL NOTES ON THIS PAGE AND ON THE ENGINEERING NOTES: TRUSSES. THE NOTE PAGE IS AN INTEGRAL PART OF THIS DRAWING AS IT CONTAINS SPECIFICATIONS AND CRITERIA USED IN THE DESIGN OF THIS COMPONENT.



| JOB NAME | TRUSS NAME | QUANTITY | PLY | JOB DESC. | DRWG NO. |
|------------|---------------------------|----------|-----|-------------|------------------|
| IM0723-092 | TRUSS NAME Oct 30 2023 | 2 | 1 | TRUSS DESC. | MHP 23030 |

Version 8.630 S Mar 22 2023 Mitek Industries, Inc. Fri Jul 14 07:33:56 2023 Page 1
ID:bcGHXsLhLjMpVeVc_4eeDgzAk?y-7QDreHbECEf67JynhVwUldVg23jmkY7jQxo0yyE9P

Scale = 1:18.7

TOTAL WEIGHT = 2 X 7 = 15 lb

| LUMBER | | | | DIMENSIONS, SUPPORTS AND LOADINGS SPECIFIED BY FABRICATOR TO BE VERIFIED BY BUILDING DESIGNER | | | | DESIGN CRITERIA | | | | | | | | | | | | |
|---|--------|--------|--------|---|---|---|--|------------------------|---------|-------|--|-------|--------|--|---------------------------------------|--|--|--|--|--|
| N. L. G. A. RULES | | | | BEARINGS | | | | SPECIFIED LOADS: | | | | | | | | | | | | |
| CHORDS | SIZE | LUMBER | DESCR. | FACTORED GROSS REACTION | | | | TOP CH. LL = 34.8 PSF | | | | | | | | | | | | |
| E - B | 2x4 | DRY | No.2 | MAXIMUM FACTORED GROSS REACTION | | | | DL = 6.0 PSF | | | | | | | | | | | | |
| A - C | 2x4 | DRY | No.2 | INPUT BRG | | | | BOT CH. LL = 0.0 PSF | | | | | | | | | | | | |
| E - D | 2x4 | DRY | No.2 | REQRD BRG | | | | DL = 7.3 PSF | | | | | | | | | | | | |
| DRY: SEASONED LUMBER. | | | | SEE MITEK STANDARD DETAIL MSD2015-H FOR CONNECTION TO JOINT(S) C, D | | | | TOTAL LOAD = 48.1 PSF | | | | | | | | | | | | |
| PLATES (table is in inches) | | | | UNFACTORED REACTIONS | | | | SPACING = 24.0 IN. C/C | | | | | | | | | | | | |
| JT | TYPE | PLATES | W | LEN | Y | X | 1ST LCASE MAX./MIN. COMPONENT REACTIONS | | | | THIS TRUSS IS DESIGNED FOR RESIDENTIAL OR SMALL BUILDING REQUIREMENTS OF PART 9, NBCC 2015 | | | | | | | | | |
| B | TMV+p | MT20 | 2.0 | 4.0 | | | JT | COMBINED | SNOW | LIVE | PERM.LIVE | WIND | DEAD | SOIL | THIS DESIGN COMPLIES WITH: | | | | | |
| E | BMV1+p | MT20 | 2.0 | 4.0 | | | E | 230 | 183 / 0 | 0 / 0 | 0 / 0 | 0 / 0 | 48 / 0 | 0 / 0 | - PART 9 OF BCBC 2018, NBC-2019AE | | | | | |
| | | | | | | | C | 63 | 54 / 0 | 0 / 0 | 0 / 0 | 0 / 0 | 9 / 0 | 0 / 0 | - PART 9 OF OBC 2012 (2019 AMENDMENT) | | | | | |
| | | | | | | | D | 13 | 0 / 0 | 0 / 0 | 0 / 0 | 0 / 0 | 13 / 0 | 0 / 0 | - CSA 086-14 | | | | | |
| BEARING MATERIAL TO BE SPF NO.2 OR BETTER AT JOINT(S) E | | | | | | | - TPIC 2014 | | | | | | | DESIGN ASSUMPTIONS | | | | | | |
| BRACING | | | | | | | TOP CHORD TO BE SHEATHED OR MAX. PURLIN SPACING = 6.25 FT. | | | | | | | - OVERHANG NOT TO BE ALTERED OR CUT OFF. | | | | | | |
| MAX. UNBRACED BOTTOM CHORD LENGTH = 10.00 FT OR RIGID CEILING DIRECTLY APPLIED. | | | | | | | ALL PITCH BREAKS AND PERIMETER CORNER JOINTS MUST BE Laterally RESTRAINED. | | | | | | | (55 % OF 48.1 P.S.F. G.S.L. PLUS 8.4 P.S.F. RAIN LOAD) EQUALS 34.8 P.S.F. SPECIFIED ROOF LIVE LOAD | | | | | | |
| LOADING | | | | | | | TOTAL LOAD CASES: (5) | | | | | | | ALLOWABLE DEFL.(LL)= L/360 (0.19") | | | | | | |
| CHORDS | | | | | | | W E B S | | | | | | | CALCULATED VERT. DEFL.(LL) = L/ 999 (0.00") | | | | | | |
| MEMB. MAX. FACTORED FORCE (LBS) | | | | | | | MEMB. MAX. FACTORED FORCE (LBS) | | | | | | | ALLOWABLE DEFL.(TL)= L/360 (0.19") | | | | | | |
| VERT. LOAD LC1 MAX | | | | | | | MAX. FACTORED | | | | | | | CALCULATED VERT. DEFL.(TL) = L/ 999 (0.00") | | | | | | |
| FROM TO | | | | | | | LENGTH FR-TO | | | | | | | CSI: TC=0.16/0.97 (A-B:1), BC=0.02/0.97 (D-E:4), WB=0.00/0.97 (n/a:0), SSI=0.11/1.00 (A-B:1) | | | | | | |
| E-B -313 / 0 | | | | | | | 0.0 0.0 0.01 (4) 7.81 | | | | | | | DOL LUMBER=1.00 NAIL=1.00 LS BEND=1.10 | | | | | | |
| A-B 0 / 36 | | | | | | | -119.4 -119.4 0.16 (1) 10.00 | | | | | | | COMP=1.10 SHEAR=1.10 TENS= 1.10 | | | | | | |
| B-C -13 / 0 | | | | | | | -119.4 -119.4 0.08 (1) 6.25 | | | | | | | COMPANION LIVE LOAD FACTOR = 1.00 | | | | | | |
| E-D 0 / 0 | | | | | | | -18.2 -18.2 0.02 (4) 10.00 | | | | | | | TRUSS PLATE MANUFACTURER IS NOT RESPONSIBLE FOR QUALITY CONTROL IN THE TRUSS MANUFACTURING PLANT . | | | | | | |
| CANTILEVER ANALYSIS HAS BEEN CONSIDERED IN THIS DESIGN | | | | | | | PATTERN-LOADING CHECK APPLIED TO THIS TRUSS. | | | | | | | NAIL VALUES | | | | | | |
| | | | | | | | | | | | | | | PLATE GRIP(DRY) SHEAR SECTION | | | | | | |
| | | | | | | | | | | | | | | (PSI) (PLI) (PLI) | | | | | | |
| | | | | | | | | | | | | | | MAX MIN MAX MIN MAX MIN | | | | | | |
| | | | | | | | | | | | | | | MT20 650 371 1747 788 1987 1873 | | | | | | |
| | | | | | | | | | | | | | | PLATE PLACEMENT TOL. = 0.250 inches | | | | | | |
| | | | | | | | | | | | | | | PLATE ROTATION TOL. = 5.0 Deg. | | | | | | |
| | | | | | | | | | | | | | | JSI GRIP= 0.18 (B) (INPUT = 0.90) | | | | | | |
| | | | | | | | | | | | | | | JSI METAL= 0.13 (B) (INPUT = 1.00) | | | | | | |


READ ALL NOTES ON THIS PAGE AND ON THE ENGINEERING NOTES: TRUSSES. THE NOTE PAGE IS AN INTEGRAL PART OF THIS DRAWING AS IT CONTAINS SPECIFICATIONS AND CRITERIA USED IN THE DESIGN OF THIS COMPONENT.

PROVINCE OF ONTARIO
JULY 14, 2023

KOTT

| | | | | | |
|------------|------------|----------|-----|-------------|------------------|
| JOB NAME | TRUSS NAME | QUANTITY | PLY | JOB DESC. | DRWG NO. |
| IM0723-092 | J02A | 1 | 1 | TRUSS DESC. | MHP 23030 |

PER: 
CHIEF BUILDING OFFICIAL



Scale = 1:18.7

TOTAL WEIGHT = 6 lb

LUMBER

| N. L. G. A. RULES | CHORDS | SIZE | LUMBER | DESCR. |
|-------------------|--------|------|--------|--------|
| D - A | 2x4 | DRY | No.2 | SPF |
| A - B | 2x4 | DRY | No.2 | SPF |
| D - C | 2x4 | DRY | No.2 | SPF |

DRY: SEASONED LUMBER.

PLATES (table is in inches)

| JT | TYPE | PLATES | W | LEN | Y | X |
|----|--------|--------|-----|-----|---|---|
| A | TMV+p | MT20 | 2.0 | 4.0 | | |
| D | BMV1+p | MT20 | 2.0 | 4.0 | | |

DIMENSIONS, SUPPORTS AND LOADINGS SPECIFIED BY FABRICATOR TO BE VERIFIED BY BUILDING DESIGNER**BEARINGS**

| JT | FACTORED GROSS REACTION | | MAXIMUM FACTORED GROSS REACTION | | INPUT BRG | REQRD BRG |
|----|-------------------------|------|---------------------------------|------|-----------|-----------|
| | DOWN | HORZ | DOWN | HORZ | | |
| D | 140 | 0 | 140 | 0 | 5-8 | 1-8 |
| B | 113 | 0 | 113 | 0 | 1-8 | 1-8 |
| C | 27 | 0 | 27 | 0 | 1-8 | 1-8 |

SEE MITEK STANDARD DETAIL MSD2015-H FOR CONNECTION TO JOINT(S) B , C

UNFACTORED REACTIONS

| JT | 1ST LCASE COMBINED | MAX./MIN. COMPONENT REACTIONS | | | | | |
|----|-----------------------|-------------------------------|-------|-----------|-------|--------|-------|
| | | SNOW | LIVE | PERM.LIVE | WIND | DEAD | SOIL |
| D | 98 | 71 / 0 | 0 / 0 | 0 / 0 | 0 / 0 | 27 / 0 | 0 / 0 |
| B | 77 | 65 / 0 | 0 / 0 | 0 / 0 | 0 / 0 | 12 / 0 | 0 / 0 |
| C | 21 | 6 / 0 | 0 / 0 | 0 / 0 | 0 / 0 | 15 / 0 | 0 / 0 |

BEARING MATERIAL TO BE SPF NO.2 OR BETTER AT JOINT(S) D

BRACING

TOP CHORD TO BE SHEATHED OR MAX. PURLIN SPACING = 10.00 FT.
MAX. UNBRACED BOTTOM CHORD LENGTH = 10.00 FT OR RIGID CEILING DIRECTLY APPLIED.

ALL PITCH BREAKS AND PERIMETER CORNER JOINTS MUST BE Laterally RESTRAINED.

LOADING

TOTAL LOAD CASES: (4)

| C H O R D S | | | | W E B S | | | |
|-------------|---------------------------|---------------------------|----------------------|----------------------------|-------|---------------------------|----------------------------|
| MEMB. | MAX. FACTORED FORCE (LBS) | FACTORED VERT. LOAD (PLF) | MAX LC1 MAX CSI (LC) | MAX. UNBRACED LENGTH FR-TO | MEMB. | MAX. FACTORED FORCE (LBS) | MAX. UNBRACED LENGTH FR-TO |
| FR-TO | | | | | FR-TO | | |
| D - A | -130 / 0 | 0.0 | 0.0 | 0.02 (1) | 7.81 | | |
| A - B | -4 / 0 | -119.4 | -119.4 | 0.06 (1) | 10.00 | | |
| D - C | 0 / 0 | -18.2 | -18.2 | 0.03 (1) | 10.00 | | |

DESIGN CRITERIA**SPECIFIED LOADS:**

| | | | |
|------------|------|------|-----|
| TOP CH. | LL = | 34.8 | PSF |
| | DL = | 6.0 | PSF |
| BOT CH. | LL = | 0.0 | PSF |
| | DL = | 7.3 | PSF |
| TOTAL LOAD | = | 48.1 | PSF |

SPACING = 24.0 IN. C/C

THIS TRUSS IS DESIGNED FOR RESIDENTIAL OR SMALL BUILDING REQUIREMENTS OF PART 9, NBCC 2015

THIS DESIGN COMPLIES WITH:

- PART 9 OF BCBC 2018 , NBC-2019AE
- PART 9 OF OBC 2012 (2019 AMENDMENT)
- CSA 086-14
- TPIC 2014

(55 % OF 48.1 P.S.F. G.S.L. PLUS 8.4 P.S.F. RAIN LOAD) EQUALS 34.8 P.S.F. SPECIFIED ROOF LIVE LOAD

ALLOWABLE DEFL.(LL)= L/360 (0.19")
CALCULATED VERT. DEFL.(LL) = L/ 999 (0.00")
ALLOWABLE DEFL.(TL)= L/360 (0.19")
CALCULATED VERT. DEFL.(TL) = L/ 999 (0.00")

CSI: TC=0.06/0.97 (A-B:1) , BC=0.03/0.97 (C-D:1) ,
WB=0.00/0.97 (n/a:0) , SSI=0.09/1.00 (A-B:1)

DOL LUMBER=1.00 NAIL=1.00 LS BEND=1.10
COMP=1.10 SHEAR=1.10 TENS= 1.10

COMPANION LIVE LOAD FACTOR = 1.00

TRUSS PLATE MANUFACTURER IS NOT RESPONSIBLE FOR QUALITY CONTROL IN THE TRUSS MANUFACTURING PLANT .

NAIL VALUES

| PLATE | GRIP(DRY) | SHEAR (PSI) | SECTION (PLI) |
|-------|-----------|-------------|--------------------|
| | MAX | MIN | MAX MIN |
| MT20 | 650 | 371 | 1747 788 1987 1873 |

PLATE PLACEMENT TOL. = 0.250 inches

PLATE ROTATION TOL. = 5.0 Deg.

JSI GRIP= 0.07 (A) (INPUT = 0.90)
JSI METAL= 0.05 (A) (INPUT = 1.00)



JULY 14, 2023

READ ALL NOTES ON THIS PAGE AND ON THE ENGINEERING NOTES: TRUSSES. THE NOTE PAGE IS AN INTEGRAL PART OF THIS DRAWING AS IT CONTAINS SPECIFICATIONS AND CRITERIA USED IN THE DESIGN OF THIS COMPONENT.

