

CONSTRUCTION SUMMARY - PARTIAL ONLY

Palmetto - Zadorra Estates Corp.

RECEIVED

PURCHASERS: Paramjyothi PANDI and Teja Sree MAREEDU

APR 02 2024

TEL: RES.: 647-861-0552

LOT NUMBER	PHASE	HOUSE TYPE	REG. PLAN #		
144	1	Villa 2 Elev 1	40M-2763		
INV#	QTY	EXTRA / CHANGE			

Offer	Note:
-------	-------

CABINETRY ACCESSORIES

29,631 15Mar24	1 - KITCHEN CABINETRY UPPER - FULL DEPTH ABOVE FRIDGE UPPER WITH GABLES - 650MM DEEP - PRICE IS EACH Note:
29,631 15Mar24	1 - KITCHEN CABINETRY - PANTRY UNIT UPGRADE - TO GO FROM 300MM TO 600MM DEEP - PRICE IS PER FOOT - STANDARD LEVEL Note:
29,631 15Mar24	1 - KITCHEN CABINETRY - BUILT-IN MICROWAVE WITH 2 BASE DOORS - STANDARD LEVEL NoteNOTE: EYE LEVEL HEIGHT

Appliance Specs Attached

ELECTRICAL

29,683 22Mar24	1 - ***DELETE*** - PRIMARY ENSUITE - SWITCH - DIMMER SWITCH IN LIEU OF EXISTING SWITCH - PRICE IS EACH Note:
29,683 22Mar24	1 - ***INSERT*** - PRIMARY BEDROOM - SWITCH - DIMMER SWITCH IN LIEU OF EXISTING SWITCH - PRICE IS EACH Note:
29,631 15Mar24	1 - ABOVE KITCHEN SINK - ADD LIGHT AND SWITCH - NO FIXTURE INCLUDED Note:
29,631 15Mar24	1 - LIGHT AND SWITCH - NO FIXTURE INCLUDED - LIVING ROOM Note:
29,631 15Mar24	1 - PLUG - ELECTRICAL PLUG - TO BE INSTALLED OVER FIREPLACE Note:
29,631 15Mar24	1 - ***DELETE*** - PRIMARY ENSUITE - SWITCH - DIMMER SWITCH IN LIEU OF EXISTING SWITCH - PRICE IS EACH Note:
29,631 15Mar24	1 - PLUG - ELECTRICAL PLUG - FOR BUILT-IN MICROWAVE Note:

This Document is Extremely Time Sensitive - Printed 2 Apr 24 at 10:32

Frigidaire Gallery

2.2 Cu. Ft. Built-In Microwave


GMBS3068AF, GMBS3068AD

Version : 01/22

CABINET OR WALL CUTOUT

Cutout Dimensions

Height (A)	Minimum	16" 3/4 (42.5 cm)
	Maximum	17" (43.2 cm)
Width (B)	Minimum	24 3/4" (62.9 cm)
	Maximum	25" (63.5 cm)
Depth (C)	Minimum	20" (50.8 cm)



30" TRIM KIT



~~30" STAINLESS TRIMKIT~~
(GMTK3068AF)

MICROWAVE (GMBS3068AF) PICTURED ABOVE PAIRED WITH STAINLESS STEEL TRIM KIT (GMTK3068AF / GMTK3068AD)

* Trim Kit Sold Separately

27" TRIM KIT



27" STAINLESS TRIMKIT
(GMTK2768AF)

30" TRIM KIT



~~30" DARK STAINLESS TRIMKIT~~
(GMTK3068AD)

MICROWAVE (GMBS3068AD) PICTURED ABOVE PAIRED WITH BLACK STAINLESS STEEL TRIM KIT (GMTK3068AD / GMTK2768AD)

* Trim Kit Sold Separately

27" TRIM KIT



~~27" DARK STAINLESS TRIMKIT~~
(GMTK2768AD)

Model Number	Color	Description
GMBS3068AF	SS	Microwave
GMBS3068AD	Black SS	Microwave
GMTK3068AF	SS	* 30" trim kit
GMTK2768AF	SS	* 27" trim kit
GMTK3068AD	Black SS	* 30" trim kit
GMTK2768AD	Black SS	* 27" trim kit

* Trim Kit Sold Separately

	Trim Kit Overall Dimensions	
	27"	30"
Height	18" (460.8 mm)	18" (460.8 mm)
Width	27" (685.8 mm)	30" (759 mm)
Depth	1 3/5" (40.9 mm)	1 3/5" (40.9 mm)

Note: For planning purposes only. Always consult local and national electric, gas and plumbing codes.
Refer to Product Installation Guide for detailed installation instructions on the web at frigidaire.com / frigidaire.ca
Specifications subject to change. Accessories information available on the web at frigidaire.com / frigidaire.ca

USA • 10200 David Taylor Drive • Charlotte, NC 28262 • 1-800-FRIGIDAIRE • frigidaire.com
CANADA • 5855 Terry Fox Way • Mississauga, ON L5V 3E4 • 1-800-265-8352 • frigidaire.ca

Frigidaire Gallery



Install Trim Kit Required. Multiple sizes available.

Built-In Microwave

2.2 Cu. Ft. Built-In Microwave

GMBS3068AF, GMBS3068AD

Available Colors : Stainless Steel, Black Stainless Steel

Version : 01/22

Cooking Controls	
Cooking Power	1100 Watts
Number of Power Levels	10

Microwave Cooking	
Auto Cook	Yes
Bacon	Yes
Beverage	Yes
Defrost	Yes
Melt / Soften	Yes
Popcorn	Yes
Potato	Yes
Reheat	Yes
Sensor Cooking	Yes
Sensor Reheat	Yes
Veggies	Yes

Microwave Control Features	
+ 10 Seconds	Yes - One Touch
+ 30 Seconds	Yes - One Touch
Quick Start	Yes

Additional Settings	
Child Lock	Yes
Demo On / Off	Yes
Language Options	English and French
Setting Turntable On / Off	No
Setting Weight Lb / Kg	Yes
Timer On / Off	Yes
Volume # of Settings	4 (Includes Off)

Internal Specifications	
Interior Color	White
Interior Light Quantity	1
Interior Light Type	LED
Interior Light Wattage	1.2 Watts

Turntable Diameter	16 1/2"
Turntable Material	Glass

Dimensions and Volume	
Height	13 5/8"
Width	24 7/16"
Depth	19 5/8"
Microwave Interior Height	11 1/4"
Microwave Interior Width	17 7/8"
Microwave Interior Depth	19 1/8"
Microwave Capacity	2.2 Cu. Ft.

Electrical Specifications	
Voltage Rating	120 V
Watts @ 120 Volts	1,100 Watts

Installation	
Power Supply Connection Location	Right Top

General Specifications	
Prop 65 Label	Yes
Warranty - Labor	1 Year
Warranty - Parts	1 Year

Safety Certifications and Approvals	
UL Listed	Yes
cUL Listed	Yes

Note: For planning purposes only. Always consult local and national electric, gas and plumbing codes.
Refer to Product Installation Guide for detailed installation instructions on the web at frigidaire.com / frigidaire.ca
Specifications subject to change. Accessories information available on the web at frigidaire.com / frigidaire.ca

USA • 10200 David Taylor Drive • Charlotte, NC 28262 • 1-800-FRIGIDAIRE • frigidaire.com
CANADA • 5855 Terry Fox Way • Mississauga, ON L5V 3E4 • 1-800-265-8352 • frigidaire.ca