

Appliance  
Specs  
Attached

|  |             |                     |
|--|-------------|---------------------|
| CONSTRUCTION SUMMARY                             |             |                     |
| Charisma Condominiums - Genazzano Highrises Inc. |             |                     |
| PURCHASER: Rita FIORINI                          | RECEIVED    | TEL:                |
| Unit 2, Level 23 (PH102-East)                    | JAN 17 2024 | Floor Plan<br>E1439 |

CABINETRY

|   |  |
|---|--|
| 1 - KITCHEN- ADD LIGHT VALANCE BELOW CABINETS<br>20Apr23 Note:                              |  |
| 1 - ALL BATH VANITIES UPGRADED HARDWARE-<br>20Apr23 Note:                                   |  |
| 1 - ALL BATH VANITIES TO BE RAISED TO 36"<br>20Apr23 Note:                                  |  |
| 1 - POWER ROOM -ENSUITE AND MAIN BATH VANITIES TO HAVE DRAWERS - UPGRADE 5<br>20Apr23 Note: |  |
| VANITIES ARE WITH CHEST OF DRAWERS  |  |
| 1 - KITCHEN- SEE REVISED LAYOUT- SINK ON ISLAND WITH DISHWASHER<br>20Apr23 Note:            |  |
| 1 - KITCHEN ADD CROWN AND HEADER ABOVE CABINETS<br>20Apr23 Note:                            |  |
| CM11- IF CONSTRUCTION PERMITS   |  |
| 3 - KITCHEN- ADD POT DRAWERS THROUGHT KITCHEN LAYOUT<br>20Apr23 Note:                       |  |
| 1 - KITCHEN ADD SPICE RACK-<br>20Apr23 Note:  |  |
| 1 - KITCHEN- ADD RECYCLE BIN - 4 BIN<br>20Apr23 Note:                                       |  |
| 1 - KITCHEN- ADD BUILT IN OVEN/MICROWAVE - UPGRADE 5<br>20Apr23 Note:                       |  |
| 1 - KITCHEN- ADD COOK TOP WITH POT DRAWERS UNDERNEATH-UPGRADE 5<br>20Apr23 Note:            |  |
| 1 - KITCHEN UPGRADE 5 CABINETS WITH 2 COLOUR<br>20Apr23 Note:                               |  |

CABINETRY ACCESSORIES

|   |  |
|---|--|
| 1 - KITCHEN AND BATH VANITIES ADD SOFT CLOSE DOORS AND DRAWERS<br>06Jun23 Note: |  |
| 1 - KITCHEN UPGRADE HARDWARE<br>20Apr23 Note:                                   |  |

CERAMIC TILE

|   |  |
|---|--|
| 1 - MAIN BATH- FLOOR AND SHOWER UPGRADED TILES-24X24 PORCELAIN TILES RECTIFIED<br>20Apr23 Note: |  |
| WITH UPGRADED MOSAIC SHOWER FLOOR TILES   |  |
| 1 - ENSUITE FLOOR AND SHOWER UPGRADED TILES-30X60 PORCELAIN RECTIFIED<br>20Apr23 Note:          |  |
| WITH UPGRADED SHOWER FLOOR MOSAICS-   |  |
| 1 - POWDER ROOM- UPGRADED TO MOSAIC TILE ON FLOOR ONLY-<br>20Apr23 Note:                        |  |



CONSTRUCTION SUMMARY

Charisma Condominiums - Genazzano Highrises Inc.

PURCHASER: Rita FIORINI

TEL:

Unit 2, Level 23 (PH102-East)

Floor Plan  
E1439

CONSTRUCTION

1 - ALL BATHROOM TOILETS ARE WALL HUNG---

20Apr23 Note:

3 - ADD SMOOTH CEILINGS THROUGHOUT ALL BEDROOMS

20Apr23 Note:

1 - ALL COFFERED CEILINGS TO HAVE KNIFE EDGE IN ORDER TO ACCOMMODATE LIGHTING- SEE ATTACHED

20Apr23 Note:

1 - SEE SKETCH FOR REVISIONS-

20Apr23 Note:

1 - SEE ATTACHED REVISED LAYOUTS AS PER SKETCH-

20Apr23 Note:

COUNTER TOP

1 - MASTER ENSUITE SHOWER SEAT- UPGRADED TO CEASERSTONE

20Apr23 Note:

BIANCO DRIFT

1 - POWDER ROOM, ENSUITE AND MAIN BATH COUNTERTOPS UPGRADED TO CEASERSTONE IN LIU OF STANDARD QUARTZ WITH UPGRADED EDGE

20Apr23 Note:

1 - KITCHEN- UPGRADED COUNTERTOP AND BACKSPLASH TO CEASERSTONE INLIU OF STANDARD QUARTZ AND UPGRADED EDGE IN COUNTERTOP

20Apr23 Note:

DOORS AND TRIM

2 - MASTER BEDROOM- ADD POCKET DOOR IN WALK IN CLOSET-AND MASTER BEDROOM DOOR

20Apr23 Note: CATCH AND CLOSE FROM KROWDER DOOR

ELECTRICAL

1 - KITCHEN- ELECTRICAL ROUGH IN FOR BUILT IN APPLIANCES-

20Apr23 Note:

1 - ALL UPGRADED ELECTRICAL POTS AND LIGHT FIXTURES AS PER ATTACHED LIST---

20Apr23 Note: TBD

1 - KITCHEN ADD LIGHT VALANCE UNDERCABINETS AND ABOVE CABINETS-

20Apr23 Note:

HARDWOOD FLOORING

1 - UPGRADED LOCK COLOUR HARDWOOD THROUGHT NON TILED AREAS

20Apr23 Note:

MIRRORS AND GLASS

1 - SHOWER ENCLOSURE - FRAMELESS CLEAR GLASS SHOWER DOOR WITH SIDE PANEL TO CEILING FOR 5 FOOT SHOWER - INCLUDES CHROME KNOB AND HINGES - ENSUITE BATHROOM - IN LIEU OF FRAMED

20Apr23 Note:

MAIN BATHROOM SHOWER

1 - MASTER ENSUITE- ADD FRAMELESS SHOWER GLASS WALLS AS PER SKETCH ATTACHED-

20Apr23 Note:



| CONSTRUCTION SUMMARY  |                     |  |      |
|---|---------------------|--|------|
| Charisma Condominiums - Genazzano Highrises Inc.  |                     |  |      |
| PURCHASER: Rita FIORINI   |                     |  | TEL: |
| Unit 2, Level 23 (PH102-East)   | Floor Plan<br>E1439 |  |      |
| 1 - CLOSET SLIDER - FRAMELESS MIRROR SLIDING DOOR WITH MIRRORED FASCIA IN LIEU OF STANDARD - BEDROOM 2<br>20Apr23 Note:         |                     |  |      |
| 1 - CLOSET SLIDER - FRAMELESS MIRROR SLIDING DOOR WITH MIRRORED FASCIA IN LIEU OF STANDARD<br>20Apr23 Note: IN FRONT FOYER----- |                     |  |      |

PAINTING

|  |  |
|--|--|
| 1 - ADD UPGRADED BENJAMIN MOORE PAINT- CHANTILLY LACE THROUGHOUT INCLUDING TRIM AND DOORS<br>20Apr23 Note: |  |
|--|--|

PLUMBING

|   |  |
|---|--|
| 1 - KITCHEN ADD THE WATER FILTER SYSTEM UNDER THE SINK CABINETS-<br>20Apr23 Note: ABSOLUTE WATER FILTRATION - IN CROME FAUCET |  |
| 1 - KITCHEN- ADD ROUGH IN FOR WATER LINE FOR FRIDGE<br>20Apr23 Note:  |  |
| 1 - ENSUITE , MAIN BATH AND POWDER ROOM- UPGRADED TO THE COLETTE UNDERMOUNT SINK<br>20Apr23 Note:                             |  |
| COLETTE- 4220CIY  |  |
| 1 - KITCHEN UNDERMOUNT SINK UPGRADED TO BLANCO QUARTUS R15-401519<br>20Apr23 Note:  |  |
| <del>1 - ALL BATHS UPGRADED TO THE WALL HUNG TOILET- EGLINTON CTL AVENUE - AVENAL 4772HNW</del><br>20Apr23 Note:              |  |
| WALL HUNG TOILET-AVENUE 3130A-WLFB110 WHITE   |  |
| 1 - MAIN BATH ADD THE 90 DEGREE FAUCET- TS6720/6900 FOR VANITY<br>20Apr23 Note:   |  |
| MOEN FAUCET   |  |
| 1 - MAIN BATH- ADD THE 90 DEGREE SHOWER FAUCET<br>20Apr23 Note:   |  |
| MOEN FAUCET   |  |
| 1 - POWDER ROOM ADD THE ALIGN 6190 CHROME FAUCET<br>20Apr23 Note:   |  |
| MOEN FAUCET   |  |
| 2 - ENSUITE VANITY FAUCETS- 90 DEGREE TS6720/6900 X2<br>20Apr23 Note:   |  |
| MOEN FAUCET   |  |
| 1 - ENSUITE SHOWER- ADD CEILING SHOWER HEAD WITH 90 DEGREE TS2712EP SLIDER BAR PACKAGE-<br>SEE SKETCH<br>20Apr23 Note:        |  |
| MOEN FAUCET   |  |
| 1 - KITCHEN- MOVE SINK TO ISLAND AND DISHWASHER<br>20Apr23 Note:  |  |





Specifications for Project

PH102 CHARISMA

Trifior Property Management Ltd, .

Location

Vaughan

905-303-6909

**i REMINDER:** To ensure a smooth project it is the responsibility of the homeowner / purchaser of appliances for this project to share all the attached specifications to ensure the cabinet provider, contractor, or any other tradesperson have all the information required to complete their work accurately.

Specifications are subject to change. If any tradesperson has questions regarding the attached specifications please contact our sales associate.

Powered by SteelCod



Full Spec Package

PH102 CHARISMA

Trifior Property Management Ltd, .

PH102 CHARISMA  
VAUGHAN, ON TBA TBA  
(905) 851-7901

| Contents   | Page no. |
|--|----------|
| <b>DET3650CIID/R</b><br>Sub-Zero Refrigeration<br><br>36" Designer Over-and-Under Refrigerator/Freezer with Ice Maker and Internal Dispenser - Panel Ready - Right Hinge | 4-8      |
| <b>DW2450</b><br>Cove Dishwasher   | 9-12     |
| <b>SU90227X</b><br>Sirius Ventilation<br><br>27" Hood Insert   | 13-14    |
| <b>CI30460C/B</b><br>Wolf Cooktop<br><br>30" Contemporary Induction Cooktop  | 15-18    |
| <b>SO3050CM/B</b><br>Wolf Wall Oven<br><br>30" M Series Contemporary Built-In Single Oven  | 19-20    |
| <b>WFW6605MC</b>   | 21-23    |



Coast Appliances  
coastappliances.com

Andrew Haidari  
Commercial Sales Representative  
905-303-6909

Inv **S03692443**  
Version 1.2

Wed, Jan 17, 2024  
10:36 AM EST

To ensure a smooth project it is the responsibility of the homeowner / purchaser of appliances for this project to share all the attached specifications to ensure the cabinet provider, contractor, or any other tradesperson have all the information required to complete their work accurately.

Specifications are subject to change. If any tradesperson has questions regarding the attached specifications please contact our sales associate.



[enterprise.steelcod.com/sp/csta/3JJEKXUJ](https://enterprise.steelcod.com/sp/csta/3JJEKXUJ)

**Note about page numbers:**  
Because the original manufacturer's documents are not altered in any way, the page numbers displayed on the page may not correspond to the page number within this package.

**All specifications are intended for initial planning purposes only.**  
Manufacturers reserve the right to change specifications at any time without notice. Always consult the installation instructions found on the manufacturer's website or included with the appliances before installation.



Full Spec Package

Whirlpool Washer  
5.8 Cu. Ft. Front Load Washer with Quick Wash Cycle

**YWED6605MC** 24-27

Whirlpool Dryer  
7.4 Cu. Ft. Electric Wrinkle Shield Dryer with Steam

**Note about page numbers:**  
Because the original manufacturer’s documents are not altered in any way, the page numbers displayed on the page may not correspond to the page number within this package.

**All specifications are intended for initial planning purposes only.**  
Manufacturers reserve the right to change specifications at any time without notice. Always consult the installation instructions found on the manufacturer’s website or included with the appliances before installation.



36" DESIGNER OVER-AND-UNDER REFRIGERATOR/FREEZER WITH ICE MAKER AND  
INTERNAL DISPENSER - PANEL READY

SUB-ZERO

DET3650CIID



FEATURES

- Split Climate™ intelligent cooling system revolutionizes Sub-Zero's already-superior preservation capabilities, keeping food even fresher for longer
- ClearSight™ LED lighting system fully illuminates the interior and reduces shadows
- Sleek stainless accents trim the interior, matching the sophistication of the exterior
- Easily customize settings—from lighting to humidity—with the tap of a finger via the conveniently accessible touch control panel
- Night Mode optimizes the interior lighting based on the detected ambient light, reducing the brightness by 90% in dim environments
- Lift the base of the flip-up dairy compartment to store taller items on the shelf below
- Delivers fresh-tasting, filtered water through an internal dispenser located discreetly within the refrigerator
- Fresh-tasting, filtered ice ready on-demand and activate Max Ice Mode to temporarily increase ice production
- Position adjustable door shelves at various heights to accommodate assorted items
- Nano coating lines the perimeter of each glass shelf to create a hydrophobic barrier that helps contain spills
- The easily accessible NASA-inspired air purification system scrubs the air of ethylene and odor every 20 minutes
- Wi-Fi enabled for convenient remote access using the Sub-Zero Group Owner's App
- Sub-Zero offers an industry-leading full two-year warranty on appliances, along with a full five-year sealed system warranty
- Accepts custom panels for an integrated look within cabinetry or stainless-steel accessory panels and handles to match other Sub-Zero, Wolf, and Cove products\*


ACCESSORIES

- Egg Container
- Reduced Toekick Divider
- Stainless Steel Side Panel
- Water Filter
- Dual Installation Kits
- Stainless Steel Dual Installation Kickplates
- Stainless Steel Door and Drawer Panels with Pro Handle
- Stainless Steel Door and Drawer Panels with Tubular Handle
- Stainless Steel Pro and Tubular Handles

Accessories are available through an authorized dealer.  
For local dealer information, visit [subzero-wolf.com/locator](https://subzero-wolf.com/locator).



HANDLE ACCESSORIES



PRODUCT DETAILS

REFRIGERATOR

- LED refrigerator and freezer lights
- 4 glass refrigerator shelves (3 adjustable; 1 stationary)
- Crisper drawer with adjustable dividers
- 3 door bins (2 adjustable; 1 stationary)
- 1 flip-up dairy compartment
- Internal water dispenser

FREEZER

- 2 full-extension roll-out freezer drawers; one with adjustable dividers
- Automatic ice maker with removable ice container

Specifications are subject to change without notice. This information was generated on January 2, 2024. Verify specifications prior to finalizing your cabinetry/enclosures.








Panel Specifications

Single Model: DET3650CIID



| PANEL          | WIDTH   | HEIGHT    | MIN THICKNESS | MAX WEIGHT |
|----------------|---------|-----------|---------------|------------|
| Door           | 35 3/4" | 49 3/8"   | 5/8"          | 60 lbs     |
| Drawer (Upper) | 35 3/4" | 13 9/16"  | 5/8"          | 15 lbs     |
| Drawer (Lower) | 35 3/4" | 16 11/16" | 5/8"          | 15 lbs     |



Panel Planning Notes

Single Model: DET3650CIID

For designer models, custom door panels and handle hardware must be provided.

The thickness of the custom panel can vary. A minimum 5/8" (16) thick panel is required, but the thickness can be increased provided it does not exceed the weight limit.

The depth of each designer model is 24" (610). Allow for panel thickness when planning the finished opening depth.

D-style handles are recommended. Door handles must be located near the edge of the panel opposite the hinge and should be centered top to bottom.

Typical panel dimensions are based on an 84" (2134) finished height for column and tall models and 1/8" (3) reveals. Panel dimensions must be adjusted accordingly for all other installations. Finish all sides of custom panels. They will be visible when the door/drawer is open.

Stainless steel tubular and pro handles are available through an authorized Sub-Zero dealer.

Drawer handles must be located near the top edge of each panel.

Minimum Panel Thickness

5/8"

Standard Handle Lengths (Optional)


| HANDLE             | TUBULAR | PRO     |
|--------------------|---------|---------|
| DET3650CIID Door   | 33 1/4" | 31 1/2" |
| DET3650CIID Drawer | 33 1/4" | 31 1/2" |



Door Panel Height

Typical panel dimensions are based on an 84" (2134) finished height for column and tall models and 34 1/2" (876) for drawer models, with a 4" (102) toe kick and 1/8" (3) reveals. Panel dimensions must be adjusted accordingly for all other installations.


The height of the custom door panel can extend beyond the typical panel height, provided it does not exceed the weight limit.



Upper valance—column and tall (side view).

Toe Kick Clearance

The height of the toe kick area can extend beyond the typical toe kick height, provided it does not exceed the dimensions in the illustration below. Toe kick heights from 2" (51) to 3 7/8" (98) require a reduced toe kick accessory available through an authorized Sub-Zero dealer.



Toe kick (side view).



24" DISHWASHER - PANEL READY



DW2450

FEATURES

Adapts easily to differently shaped dishes and glasses with a height-adjustable middle rack and fold-down tines

Removes food and grease with three powerful spray arms and custom wash and dry options for different soil levels

Filters food efficiently through fine mesh for cleaner water throughout every cycle

Dries every type of dish, utensil, and pan thoroughly with a hot rinse and fan-assist

Operates in near silence that never interrupts

Opt for a stainless-steel panel for a timeless, sophisticated look that coordinates with classic Wolf and Sub-Zero styles

Or, choose custom panels to integrate into any kitchen design

Provides better visibility with interior LED lights

Maintains clean lines with sleek control panel and floor status light

Marvel at the durability of the stainless-steel exterior and interior, built for decades of use

Monitor cycle progress, even start a new cycle, remotely. Receive alerts when rinse aid is low

Cove's leak protection system offers peace of mind in the rare event of a leak. A conductivity sensor in the base of the unit will automatically stop a cycle in progress if it detects a leak.

ACCESSORIES


24" Stainless Steel Door Panels

60cm Stainless Steel Door Panels


24" Stainless Steel Kickplates

60cm Stainless Steel Kickplates

Accessories are available through an authorized dealer.  
For local dealer information, visit [subzero-wolf.com/locator](http://subzero-wolf.com/locator).



HANDLE ACCESSORIES



PRODUCT DETAILS

DISHWASHER

- 4 LED lights (2 sides; 2 top)
- 43 spray jets across three spray arms
- Four-stage, fine mesh filter
- Adjustable stemware rail
- Adjustable cup shelf
- Height-adjustable middle rack
- Easy-glide bottom rack
- Upper silverware rack
- One large utensil basket




24" DISHWASHER - PANEL READY




PRODUCT SPECIFICATIONS

|                    |  |
|--------------------|--|
| Model              | DW2450   |
| Dimensions         | 23 5/8"W x 34 1/2"H x 23 1/4"D                         |
| Door Clearance     | 26 3/4"  |
| Sound Level        | 41 dBA (Model and cycle/option dependent)              |
| Electrical Supply  | 115 VAC, 60 Hz   |
| Electrical Service | 15 amp dedicated circuit                               |
| Receptacle         | 3-prong grounding-type                                 |
| Cord Length        | 6'   |
| Water Connection   | 5' braided tubing with 3/8" female compression fitting |
| Drain Connection   | 5' (1.5 m) corrugated tubing                           |
| Plumbing Pressure  | 30–140 psi   |

ELECTRICAL




PLUMBING



**COVE OPENING WIDTH** Cove dishwashers accommodate varying opening widths. A 23 5/8" (60 cm) width provides minimum reveals and is ideal for new construction. A 24" width is also common; however, reveals for a 24" opening will be larger than the reveals for a 23 5/8" opening unless the panel width is adjusted accordingly. 24" and 60 cm stainless steel panels are available and must be specified accordingly.


**PANEL SPECIFICATIONS** For complete panels specifications including width/height, weight requirements and thickness requirements visit [subzero-wolf.com/reveal](http://subzero-wolf.com/reveal).

INTERIOR VIEW




This illustration is intended for interior reference only and may not represent the exterior of the model being specified.


DIMENSIONS




\*34" (864) MIN TO 34 5/8" (880) MAX



24" INSTALLATION



NOTE: 3/2" (76) finished returns will be visible and should be finished to match cabinetry.





COVE DISHWASHERS

Door Panel

CUSTOM PANEL

**IMPORTANT NOTE:** The dishwasher opening width determines the custom panel width. The panel width should be 1/4" (6) less than the opening width to achieve minimum reveals.

The panel dimensions in the chart below are based on a 34 1/2" (876) opening, with a 4" (102) toe kick and 1/8" (3) top reveal. For all other opening and toe kick heights, adjust the panel accordingly. The minimum panel height is 28" (711). The minimum toe kick height is 4" (102).

Finish all sides of the custom panel. They may be visible when the door is open.

Locate the handle near the top of the door. Handle mounting hardware must be flush with the back of the door panel.

| PANEL DIMENSIONS        | W             | H             |
|-------------------------|---------------|---------------|
| 23 5/8" (60 cm) Opening | 23 3/8" (594) | 30 3/8" (772) |
| 24" (610) Opening       | 23 3/4" (603) | 30 3/8" (772) |

| PANEL REQUIREMENTS            |               |
|-------------------------------|---------------|
| Max Weight (including handle) | 20 lb (9 kg)* |
| Min Thickness                 | 1/2" (13)     |

\*Less than 16 lb (7 kg) is optimal.



Panel dimensions

STAINLESS STEEL PANEL

Stainless steel accessory door panels are available in two widths to accommodate a 23 5/8" (60 cm) or a 24" (610) opening. The panels are also available in two heights to accommodate a 4" (102) or 6" (152) toe kick. Refer to the chart below for panel dimensions. The panels are available through an authorized Cove dealer. For local dealer information, use the showroom, sales, and service search tool on [coveappliance.com](http://coveappliance.com).

| PANEL DIMENSIONS        |               |               |           |
|-------------------------|---------------|---------------|-----------|
| 4" (102) TOE KICK       | W             | H             | D         |
| 23 5/8" (60 cm) Opening | 23 3/8" (594) | 30 3/8" (772) | 3/4" (19) |
| 24" (610) Opening       | 23 3/4" (603) | 30 3/8" (772) | 3/4" (19) |
| 6" (152) TOE KICK       | W             | H             | D         |
| 23 5/8" (60 cm) Opening | 23 3/8" (594) | 28 3/8" (721) | 3/4" (19) |
| 24" (610) Opening       | 23 3/4" (603) | 28 3/8" (721) | 3/4" (19) |

STANDARD HANDLES

Optional stainless steel tubular and pro handles are available through an authorized Cove dealer. For local dealer information, use the showroom, sales, and service search tool on [coveappliance.com](http://coveappliance.com). Refer to the chart below for standard handle lengths for the dishwasher.

| HANDLE LENGTH |               |
|---------------|---------------|
| Tubular       | 21 1/4" (540) |
| Pro           | 19 1/2" (495) |




COVE DISHWASHERS

Door Panel

KICKPLATE CLEARANCE


It is possible to adhere a custom kickplate to the factory kickplate. The height and thickness can vary, provided it does not impede the door panel rotation. Refer to the illustration below.



Toe kick area (side view)

KICKPLATE

The upper right corner of any kickplate exceeding 3 3/8" (86) in height must be notched to allow for airflow. Refer to the illustration below.



Kickplate notch

Sub-Zero, Sub-Zero & Design, Sub-Zero & Snowflake Design, Dual Refrigeration, The Living Kitchen, Great American Kitchens The Fine Art of Kitchen Design, Wolf, Wolf & Design, Wolf Gourmet, W & Design, red colored knobs, Cove, and Cove & Design are registered trademarks and service marks of Sub-Zero Group, Inc. and its subsidiaries. All other trademarks are property of their respective owners in the United States and other countries.








SU90227X

SU 902  
stainless steel AISI 430



**note**  
- It is highly recommended that professional style cooking always be vented to the outside

|               |   |
|---------------|---|
| MOTOR         | 680 CFM Aluminium die-cast housing<br>Pressure: 680 Pa<br>Noise level: 64 dBA |
| LIGHTING      | 2X4W led spot   |
| CONTROL PANEL | 4 speed push-button + delay off timer + light switch                          |
| GREASE FILTER | Commercial style baffle filters   |
| AIR OUTLET    | 6" round  |
| DISCHARGE     | Vertical  |
| CUT OUT       | 26" 21/32 x 10" 25/64   |
| ACCESSORIES   | Charcoal filters: KF8 (order 2 pcs) code 60078099999                          |



30" CONTEMPORARY INDUCTION COOKTOP



C I30460C/B

FEATURES

Consistent, precise control and nearly instantaneous temperature response

More efficient heat transfer—energy is supplied directly to the cookware

Intuitive, full-color LCD touchscreen controls are sleek and easy to use

17 power settings enhance precision with half increment adjustments

Sensors regulate consistent low heat for simmering, melting, and warming without scorching

Independent cooking zone timers make it easy to prepare a variety of dishes at once

Boost Mode delivers rapid heat for 40% faster boil times, surpassing the speed of gas or electric

Bridge two cooking zones into one larger surface for induction-capable griddles, open roasters, and fish poachers

Sleek, subtle surface graphics make it easy to properly center cookware

The pause feature suspends the cooktop and all timers for up to 10 minutes


Turn off an individual cooking zone with two quick taps or power off the entire cooktop surface with one tap

Cooktop controls automatically lock when not in use for increased safety

Sleek black glass surface resists scratching, staining, impact, and heat

Because spills don't stick to the surface, cleanup is quick and easy

Frameless design installs flush against counter for a clean contemporary look



COOKTOP SPECIFICATIONS

- Unframed edge for flush installation
- Black ceramic glass surface
- Sensor based simmer, melt, and keep warm modes
- Boost Mode for rapid heat
- 1 - 6" 1,400 W Zone with 2,200 W Boost
- 2 - 8" 2,100 W Element with 3,700 W Boost
- 1 - 11" 2,600 W Zone with 3,700 W Boost

Specifications are subject to change without notice. This information was generated on January 2, 2024. Verify specifications prior to finalizing your cabinetry/enclosures.




30" CONTEMPORARY INDUCTION COOKTOP



PRODUCT SPECIFICATIONS


|                    |                            |
|--------------------|----------------------------|
| Model              | CI30460C/B                 |
| Dimensions         | 30"W x 2 1/2"H x 21"D      |
| Weight             | 49 lbs                     |
| Electrical Supply  | 3-wire, 240/208 VAC, 60 Hz |
| Electrical Service | 40 amp dedicated circuit   |
| Conduit Length     | 4 Feet                     |

ELECTRICAL




NOTE: Dimensions in parenthesis are in millimeters unless otherwise specified

DIMENSIONS



FLUSH INSTALLATION



NOTE: Shaded area above countertop indicates minimum clearance to combustible surfaces, combustible materials cannot be located within this area.  
Electrical supply location only applies to installations with built-in oven.  
Outside corner radius 7/16" (11).



30" CONTEMPORARY INDUCTION COOKTOP

WOLF

C130460C/B

FEATURES

Consistent, precise control and nearly instantaneous temperature response

More efficient heat transfer—energy is supplied directly to the cookware

Intuitive, full-color LCD touchscreen controls are sleek and easy to use

17 power settings enhance precision with half increment adjustments

Sensors regulate consistent low heat for simmering, melting, and warming without scorching

Independent cooking zone timers make it easy to prepare a variety of dishes at once

Boost Mode delivers rapid heat for 40% faster boil times, surpassing the speed of gas or electric

Bridge two cooking zones into one larger surface for induction-capable griddles, open roasters, and fish poachers

Sleek, subtle surface graphics make it easy to properly center cookware

The pause feature suspends the cooktop and all timers for up to 10 minutes


Turn off an individual cooking zone with two quick taps or power off the entire cooktop surface with one tap

Cooktop controls automatically lock when not in use for increased safety

Sleek black glass surface resists scratching, staining, impact, and heat

Because spills don't stick to the surface, cleanup is quick and easy

Frameless design installs flush against counter for a clean contemporary look



COOKTOP SPECIFICATIONS

- Unframed edge for flush installation
- Black ceramic glass surface
- Sensor based simmer, melt, and keep warm modes
- Boost Mode for rapid heat
- 1 - 6" 1,400 W Zone with 2,200 W Boost
- 2 - 8" 2,100 W Element with 3,700 W Boost
- 1 - 11" 2,600 W Zone with 3,700 W Boost




30" CONTEMPORARY INDUCTION COOKTOP



PRODUCT SPECIFICATIONS


|                    |                            |
|--------------------|----------------------------|
| Model              | CI30460C/B                 |
| Dimensions         | 30"W x 2 1/2"H x 21"D      |
| Weight             | 49 lbs                     |
| Electrical Supply  | 3-wire, 240/208 VAC, 60 Hz |
| Electrical Service | 40 amp dedicated circuit   |
| Conduit Length     | 4 Feet                     |

ELECTRICAL




NOTE: Dimensions in parenthesis are in millimeters unless otherwise specified


DIMENSIONS



STANDARD INSTALLATION



COUNTERTOP CUT-OUT



SIDE VIEW

FRONT VIEW

NOTE: Shaded area above countertop indicates minimum clearance to combustible surfaces. combustible materials cannot be located within this area.  
Electrical supply location only applies to installations with built-in oven.



30" M SERIES CONTEMPORARY BUILT-IN SINGLE OVEN



SO3050CM/B



FEATURES

Preheats faster and cooks more consistently across all racks due to its advanced Dual VertiFlow™ convection system

Assures predictably delicious results with a variety of modes, including Convection Roast, Proof, and Dehydrate

Prepares 50 popular dishes with the Gourmet feature that automatically adjusts cook times and temperatures

Handles multiple dishes simultaneously with our largest capacity oven (13 percent larger)

Insert a temperature probe to tell you exactly when it is done—and in Gourmet Mode, it will alert you the moment the dish is ready.

Uncomplicate cooking with innovative, interactive color touchscreen controls

Blends in with a sleek black glass, handleless design

Integrates beautifully into surrounding cabinetry with flush installation

Ensures excellent visibility via three bright halogen lights and large, triple-panel-glass door windows

Master your technique with tips and recipes from the Mastering the M Series Oven guide

ACCESSORIES

30" Broiler Pan

30" Full-Extension Ball-Bearing Oven Rack

30" Premier Baking Sheet

30" Standard Oven Rack

Bake Stone Kit


Dehydration Kit

Dual Installation Kit

Multi-Function Pan

Temperature Probe



Accessories available through an authorized dealer.  
For local dealer information, visit [subzero-wolf.com/locator](https://www.subzero-wolf.com/locator).







WOLF

## DIMENSIONS



## FLUSH INSTALLATION



SIDE VIEW

FRONT VIEW

\*1" (25) minimum depth. Shaded areas will be visible and should be finished to match cabinetry.  
 \*\*Dimension provides minimum reveals

NOTE: Location of electrical supply within opening may require additional cabinet depth.






## 5.8 Cu. Ft. Front Load Washer with Quick Wash Cycle

WFW6605MC

Available Finishes/Colours

 WFW6605MC  
Chrome Shadow

 WFW6605MW  
White

| Dimensions |        |
|------------|--------|
| Depth      | 33 1/4 |
| Height     | 40     |
| Width      | 27     |

| Exterior        |       |
|-----------------|-------|
| Adjustable Feet | Yes   |
| Lid/Door Finish | Glass |
| Lid/Door Lock   | Yes   |
| Lid/Door Swing  | Left  |
| Slow Close Lid  | No    |
| Window          | Yes   |

| Controls                   |   |
|----------------------------|---|
| Electronic Display Type    | Cycle indicator light with digital remaining time |
| End of Cycle Signal        | Yes   |
| LCD Touch Screen           | No  |
| Feedback-Status Indicators | Yes   |
| LED Color                  | White/Blue/White                                  |

| Details                                |     |
|--|-----|
| Advanced Vibration Control™            | Yes |
| Automatic Load Size Sensing Technology | Yes |

Clean regular-sized loads in as little as 25 minutes in this large capacity front load washer.\* Get help removing everyday stains with the washing machine Steam Clean Option. The Tumble Fresh Option keeps clean clothes fresh up to 12 hours after the wash cycle ends. And with the washing machine Sanitize Cycle, increased water temperature sanitizes items like towels. \*Based on a 10-lb load, Regular/Quick Cycle.

| Top Features        |
|---------------------|
| Quick Wash Cycle    |
| Intuitive Controls  |
| Tumble Fresh Option |

| Controls                       |           |
|--------------------------------|-----------|
| Automatic Temperature Controls | Yes       |
| Control Location               | Front     |
| Control Type                   | Tap Touch |

Manuals & Literature:


-  [Energy Guide](#)
-  [Use and Care Guide](#)
-  [Warranty Information](#)




Because Whirlpool Corporation policy includes a continuous commitment to improve our products, we reserve the right to change materials and specifications without notice. Dimensions are for planning purposes only. For complete details, see Installation Instructions packed with product. Specifications subject to change without notice.




**Recessed area or closet installation (stacked washer and dryer)**




**Custom under counter installation**



**Recessed area or closet installation (washer only)**



**Custom cabinet installation**




**Drain System**

It is the responsibility of the installer to install and secure the drain hose in to the provided plumbing/drain in a manner that will avoid the drain hose coming out of or leaking from the plumbing/drain.

Drain system can be installed using a floor drain, wall standpipe, floor standpipe, or laundry tub. Select the method you need.

**IMPORTANT:** To avoid siphoning, only 4.5" (114 mm) of drain hose should be inside standpipe. Always secure drain hose with cable tie.


**Floor standpipe drain system**



Minimum diameter for a standpipe drain: 2" (51 mm). Minimum carry-away capacity: 17 gallons (64 L) per minute. A 1/4" (6 mm) diameter to 1" (25 mm) diameter Standpipe Adapter Kit is available; refer to the Quick Start Guide for online ordering information. Top of standpipe must be at least 39" (762 mm) high; install no higher than 96" (2.4 m) from bottom of washer. If you have an overhead sewer and need to pump higher than 96" (2.4 m), a sump pump and associated hardware are needed. See "Alternate Parts."




### Wall standpipe drain system




See requirements in "Floor standpipe drain system."


### Laundry tub drain system



Minimum capacity: 20 gallons (76 L). Top of laundry tub must be at least 39" (991 mm) from the floor; install no higher than 96" (2.4 m) from bottom of washer.



### Floor drain system



Floor drain system requires a Siphon Break Kit, 2 Connector Kits, and an Extension Drain Hose that may be purchased separately; refer to the Quick Start Guide for online ordering information. Minimum siphon break height: 28" (710 mm) from bottom of washer. (Additional hoses may be needed.)

## Electrical Requirements

### ⚠ WARNING



#### Electrical Shock Hazard

**Plug into a grounded 3 prong outlet.**

**Do not remove ground prong.**

**Do not use an adapter.**

**Do not use an extension cord.**

**Failure to follow these instructions can result in death, fire, or electrical shock.**

- A 120 V, 60 Hz, AC only, 15 or 20 A, fused electrical supply is required. A time-delay fuse or circuit breaker is recommended. It is recommended that a separate circuit breaker serving only this appliance be provided.
- This washer is equipped with a power supply cord having a 3-prong grounding plug.
- To minimize possible shock hazard, the cord must be plugged into a mating, 3-prong, grounding-type outlet, grounded in accordance with local codes and ordinances. If a mating outlet is not available, it is the personal responsibility and obligation of the customer to have the properly grounded outlet installed by a qualified electrician.
- If codes permit and a separate ground wire is used, it is recommended that a qualified electrician determine that the ground path is adequate.
- Do not ground to a gas pipe.
- Check with a qualified electrician if you are not sure the washer is properly grounded.
- Do not have a fuse in the neutral or ground circuit.

### GROUNDING INSTRUCTIONS

#### For a grounded, cord-connected appliance:

This appliance must be grounded. In the event of a malfunction or breakdown, grounding will reduce the risk of electric shock by providing a path of least resistance for electric current. This appliance is equipped with a cord having an equipment-grounding conductor and a grounding plug. The plug must be plugged into an appropriate outlet that is properly installed and grounded in accordance with all local codes and ordinances.

#### WARNING: Improper connection of the equipment-

grounding conductor can result in a risk of electric shock. Check with a qualified electrician or serviceman if you are in doubt as to whether the appliance is properly grounded. Do not modify the plug provided with the appliance. If it will not fit the outlet, have a proper outlet installed by a qualified electrician.

#### For a permanently connected appliance:

This appliance must be connected to a grounded metal, permanent wiring system, or an equipment-grounding conductor must be run with the circuit conductors and connected to the equipment-grounding terminal or lead on the appliance.

### SAVE THESE INSTRUCTIONS





## 7.4 Cu. Ft. Electric Wrinkle Shield Dryer with Steam

YWED6605MC

Available Finishes/Colours

 YWED6605MC  
Chrome Shadow

 YWED6605MW  
White

| Dimensions |        |
|------------|--------|
| Depth      | 31     |
| Height     | 38 1/8 |
| Width      | 27     |





| Exterior        |       |
|-----------------|-------|
| Window          | Yes   |
| Door Opening    | Right |
| Reversible Door | Yes   |

| Controls                       |  |
|--------------------------------|--|
| Automatic Temperature Controls | Yes                                      |
| Control Location               | Front                                    |
| Control Type                   | Tap Touch                                |
| Feedback-Status Indicators     | Check Vent, Cool Down, Damp Sensing, Wet |
| Electronic Display Type        | Digital                                  |
| End of Cycle Signal            | Yes                                      |

| Features               |     |
|------------------------|-----|
| Lint Filter Indicator  | No  |
| Automatic Dry Control  | Yes |
| Moisture Sensor        | Yes |
| Sound Package          | No  |
| Cycle Time Remaining   | Yes |
| EcoBoost™/Energy Saver | Yes |
| LP Convertible         | No  |
| Secondary Lint Filter  | No  |

| Top Features                           |
|--|
| Wrinkle Shield™ Plus Option with Steam |
| 7.4 cu. ft. Capacity                   |
| Intuitive Controls                     |

| Exterior   |            |
|------------|------------|
| Door Style | Side Swing |

- Manuals & Literature:
-  [Dimension Guide](#)
  -  [Energy Guide](#)
  -  [Use and Care Guide](#)
  -  [Warranty Information](#)





Because Whirlpool Corporation policy includes a continuous commitment to improve our products, we reserve the right to change materials and specifications without notice. Dimensions are for planning purposes only. For complete details, see Installation Instructions packed with product. Specifications subject to change without notice.



DETAILED PLANNING DIMENSIONS

**WARNING:** To reduce the risk of fire, electric shock, or injury to persons, read the IMPORTANT SAFETY INSTRUCTIONS and INSTALLATION INSTRUCTIONS, located in your appliance's Owner's Manual, before installing and operating this appliance.


| Electrical Requirements         |   |               |
|---------------------------------|---|---------------|
| Fuel Type                       | Electric                                | Gas           |
| Minimum Circuit Amperage Rating | 30 A                                    | 15 A          |
| Maximum AMP Draw                | 24 A                                    | 6 A           |
| Operating Voltage               | 240 V AC only<br>230 V AC only (Canada) | 120 V AC only |
| Operating Frequency             | 60 Hz                                   |               |



| Product Dimensions |                             |                                 |                               |          |          |
|--------------------|-----------------------------|---------------------------------|-------------------------------|----------|----------|
|                    |                             | in (min)                        | in (max)                      | mm (min) | mm (max) |
| A                  | Height (with feet)          | 38 <sup>7</sup> / <sub>8</sub>  | 39                            | 968      | 989      |
| B                  | Width                       | 27                              | -                             | 686      | -        |
| C                  | Depth                       | 30 <sup>3</sup> / <sub>8</sub>  | -                             | 778      | -        |
| D                  | Side Vent Height (feet min) | 3 <sup>1</sup> / <sub>2</sub>   | 4 <sup>3</sup> / <sub>8</sub> | 89       | 111      |
| E                  | Side Vent (from back)       | 10 <sup>3</sup> / <sub>16</sub> | -                             | 258      | -        |



DETAILED PLANNING DIMENSIONS



| Product Dimensions |                                 |                                  |                                  |          |          |
|--------------------|---------------------------------|----------------------------------|----------------------------------|----------|----------|
|                    |                                 | in (min)                         | in (max)                         | mm (min) | mm (max) |
| F                  | Depth with Door Open            | 54 <sup>5</sup> / <sub>16</sub>  | -                                | 1,378    | -        |
| G                  | Strain Relief from Side (elec)  | 6 <sup>3</sup> / <sub>8</sub>    | -                                | 163      | -        |
| H                  | Strain Relief Height (elec)     | 29 <sup>7</sup> / <sub>8</sub>   | 30 <sup>11</sup> / <sub>16</sub> | 759      | 780      |
| G                  | Power Cord from Side (Canadian) | 6 <sup>3</sup> / <sub>8</sub>    | -                                | 163      | -        |
| H                  | Power Cord Height (Canadian)    | 29 <sup>7</sup> / <sub>8</sub>   | 30 <sup>11</sup> / <sub>16</sub> | 759      | 780      |
|                    | Power Cord Length (Canadian)    | 53 <sup>3</sup> / <sub>8</sub>   | -                                | 1,356    | -        |
| I                  | Power Cord from Side (gas)      | 3 <sup>13</sup> / <sub>16</sub>  | -                                | 96       | -        |
| J                  | Power Cord Height (gas)         | 31 <sup>13</sup> / <sub>16</sub> | 32 <sup>11</sup> / <sub>16</sub> | 808      | 829      |
|                    | Power Cord Length (gas)         | 72                               | -                                | 1,828    | -        |
| K                  | Gas Valve Height                | 5 <sup>5</sup> / <sub>8</sub>    | 6 <sup>3</sup> / <sub>8</sub>    | 142      | 163      |
| L                  | Gas Valve from Side             | 1 <sup>3</sup> / <sub>8</sub>    | -                                | 36       | -        |
| M                  | Exhaust Duct Height             | 3 <sup>1</sup> / <sub>2</sub>    | 4 <sup>3</sup> / <sub>8</sub>    | 90       | 111      |
| N                  | Exhaust Duct from Side          | 14 <sup>1</sup> / <sub>8</sub>   | -                                | 358      | -        |




## DETAILED PLANNING DIMENSIONS

### Spacing for recessed area or closet installation

The dimensions shown are for the recommended spacing allowed.

- Additional spacing should be considered for ease of installation and servicing.
- Additional clearances might be required for wall, door, and floor moldings.
- Additional spacing of 1" (25 mm) on all sides of the dryer is recommended to reduce noise transfer.
- For closet installation, with a door, minimum ventilation openings in the top and bottom of the door are required. Louvered doors with equivalent ventilations openings are acceptable.
- Companion appliance spacing should also be considered.



\*Recommended/Minimum spacing