

FROM PLAN DATED: FEB 2016

BUILDER:  
GREENPARK

SITE:  
STARTIME

MODEL: BRIDGEFORD 2

ELEVATION: 1

LOT:  
CITY: VAUGHAN

SALESMAN: MARIO  
DESIGNER: AJ  
REVISION:


NOTES:  
CERAMIC TILE APPLICATION  
AS PER O.B.C. 9.30.6.  
SQUASH BLOCKS  
2x4 OR 2x6 #2 S.P.F. REQ'D UNDER  
INTERIOR UNIFORM LOAD BEARING  
WALLS.  
MULTIPLE SQUASH BLOCKS REQ'D  
UNDER CONCENTRATED LOADS.  
CANTILEVERED JOISTS  
REQUIRE I-JOIST BLOCKING ALONG  
BEARING AND RIMBOARD CLOSURE  
AT  
ENDS.  
REFER TO THE NORDIC  
INSTALLATION GUIDE FOR PROPER  
STORAGE AND INSTALLATION.  
LOADING:

DESIGN LOADS: L/480.000  
LIVE LOAD: 40.0 lb/ft<sup>2</sup>  
DEAD LOAD: 15.0 lb/ft  
TILED AREAS: 20 lb/ft


SUBFLOOR: 3/4" GLUED AND NAILED

DATE: 5/2/2016

1st FLOOR



Products				
PlotID	Length	Product	Plies	Net Qty
J1	14-00-00	9 1/2" NI-40x	1	12
J2	12-00-00	9 1/2" NI-40x	1	48
J3	10-00-00	9 1/2" NI-40x	1	1
B2	12-00-00	1-3/4" x 9-1/2" VERSA-LAM® 2.0 3100 SP	2	2
B3	12-00-00	1-3/4" x 9-1/2" VERSA-LAM® 2.0 3100 SP	2	2
B1	10-00-00	1-3/4" x 9-1/2" VERSA-LAM® 2.0 3100 SP	2	2



FROM PLAN DATED: FEB 2016

BUILDER:  
GREENPARK

SITE:  
STARTIME

MODEL: BRIDGEFORD 2

ELEVATION: 1

LOT:  
CITY: VAUGHAN


SALESMAN: MARIO  
DESIGNER: AJ  
REVISION:

NOTES:  
CERAMIC TILE APPLICATION  
AS PER O.B.C. 9.30.6.  
SQUASH BLOCKS  
2x4 OR 2x6 #2 S.P.F. REQ'D UNDER  
INTERIOR UNIFORM LOAD BEARING  
WALLS.  
MULTIPLE SQUASH BLOCKS REQ'D  
UNDER CONCENTRATED LOADS.  
CANTILEVERED JOISTS  
REQUIRE I-JOIST BLOCKING ALONG  
BEARING AND RIMBOARD CLOSURE  
AT  
ENDS.  
REFER TO THE NORDIC  
INSTALLATION GUIDE FOR PROPER  
STORAGE AND INSTALLATION.  
LOADING:  
DESIGN LOADS: L/480.000  
LIVE LOAD: 40.0 lb/ft<sup>2</sup>  
DEAD LOAD: 15.0 lb/ft  
TILED AREAS: 20 lb/ft

SUBFLOOR: 5/8" GLUED AND NAILED


DATE: 5/2/2016

2nd FLOOR



Products				
PlotID	Length	Product	Plies	Net Qty
J1	14-00-00	9 1/2" NI-40x	1	19
J2	12-00-00	9 1/2" NI-40x	1	41
J3	10-00-00	9 1/2" NI-40x	1	17
J4	4-00-00	9 1/2" NI-40x	1	3
B11	14-00-00	1-3/4" x 9-1/2" VERSA-LAM® 2.0 3100 SP	2	2
B12	12-00-00	1-3/4" x 9-1/2" VERSA-LAM® 2.0 3100 SP	2	2
B5 DR	12-00-00	1-3/4" x 9-1/2" VERSA-LAM® 2.0 3100 SP	2	2
B8	10-00-00	1-3/4" x 9-1/2" VERSA-LAM® 2.0 3100 SP	1	1
B13	10-00-00	1-3/4" x 9-1/2" VERSA-LAM® 2.0 3100 SP	2	2
B4 DR	10-00-00	1-3/4" x 9-1/2" VERSA-LAM® 2.0 3100 SP	2	2
B9	10-00-00	1-3/4" x 9-1/2" VERSA-LAM® 2.0 3100 SP	2	2
B6	8-00-00	1-3/4" x 9-1/2" VERSA-LAM® 2.0 3100 SP	2	2
B10	4-00-00	1-3/4" x 9-1/2" VERSA-LAM® 2.0 3100 SP	1	1
B7	4-00-00	1-3/4" x 9-1/2" VERSA-LAM® 2.0 3100 SP	1	1

Connector Summary		
Qty	Manuf	Product
2	H1	HUS1.81/11.88
3	H1	IUS2.56/9.5
29	H1	IUS2.56/9.5
1	H2	HUS1.81/9.5
2	H2	HUS1.81/9.5
1	H3	HGUS410
1	H4	HUC410



FROM PLAN DATED: FEB 2016

BUILDER:  
GREENPARK

SITE:  
STARTIME

MODEL: BRIDGFORD 2

ELEVATION: 2

LOT:  
CITY: VAUGHAN

SALESMAN: MARIO  
DESIGNER: AJ  
REVISION:


NOTES:  
CERAMIC TILE APPLICATION  
AS PER O.B.C. 9.30.6.  
SQUASH BLOCKS  
2x4 OR 2x6 #2 S.P.F. REQ'D UNDER  
INTERIOR UNIFORM LOAD BEARING  
WALLS.  
MULTIPLE SQUASH BLOCKS REQ'D  
UNDER CONCENTRATED LOADS.  
CANTILEVERED JOISTS  
REQUIRE I-JOIST BLOCKING ALONG  
BEARING AND RIMBOARD CLOSURE  
AT  
ENDS.  
REFER TO THE NORDIC  
INSTALLATION GUIDE FOR PROPER  
STORAGE AND INSTALLATION.  
LOADING:

DESIGN LOADS: L/480.000  
LIVE LOAD: 40.0 lb/ft<sup>2</sup>  
DEAD LOAD: 15.0 lb/ft  
TILED AREAS: 20 lb/ft


SUBFLOOR: 3/4" GLUED AND NAILED

DATE: 5/2/2016

1st FLOOR



Products				
PlotID	Length	Product	Plies	Net Qty
J1	14-00-00	9 1/2" NI-40x	1	12
J2	12-00-00	9 1/2" NI-40x	1	48
J3	10-00-00	9 1/2" NI-40x	1	1
B2	12-00-00	1-3/4" x 9-1/2" VERSA-LAM® 2.0 3100 SP	2	2
B3	12-00-00	1-3/4" x 9-1/2" VERSA-LAM® 2.0 3100 SP	2	2
B1	10-00-00	1-3/4" x 9-1/2" VERSA-LAM® 2.0 3100 SP	2	2



FROM PLAN DATED: FEB 2016

BUILDER:  
GREENPARK

SITE:  
STARTIME

MODEL: BRIDGEFORD 2

ELEVATION: 2

LOT:  
CITY: VAUGHAN


SALESMAN: MARIO  
DESIGNER: AJ  
REVISION:

NOTES:  
CERAMIC TILE APPLICATION  
AS PER O.B.C. 9.30.6.  
SQUASH BLOCKS  
2x4 OR 2x6 #2 S.P.F. REQ'D UNDER  
INTERIOR UNIFORM LOAD BEARING  
WALLS.  
MULTIPLE SQUASH BLOCKS REQ'D  
UNDER CONCENTRATED LOADS.  
CANTILEVERED JOISTS  
REQUIRE I-JOIST BLOCKING ALONG  
BEARING AND RIMBOARD CLOSURE  
AT  
ENDS.  
REFER TO THE NORDIC  
INSTALLATION GUIDE FOR PROPER  
STORAGE AND INSTALLATION.  
LOADING:  
DESIGN LOADS: L/480.000  
LIVE LOAD: 40.0 lb/ft<sup>2</sup>  
DEAD LOAD: 15.0 lb/ft  
TILED AREAS: 20 lb/ft

SUBFLOOR: 5/8" GLUED AND NAILED


DATE: 5/2/2016

2nd FLOOR



Products				
PlotID	Length	Product	Plies	Net Qty
J1	14-00-00	9 1/2" NI-40x	1	19
J2	12-00-00	9 1/2" NI-40x	1	41
J3	10-00-00	9 1/2" NI-40x	1	17
J4	4-00-00	9 1/2" NI-40x	1	3
B11	14-00-00	1-3/4" x 9-1/2" VERSA-LAM® 2.0 3100 SP	2	2
B12	12-00-00	1-3/4" x 9-1/2" VERSA-LAM® 2.0 3100 SP	2	2
B5 DR	12-00-00	1-3/4" x 9-1/2" VERSA-LAM® 2.0 3100 SP	2	2
B8	10-00-00	1-3/4" x 9-1/2" VERSA-LAM® 2.0 3100 SP	1	1
B13	10-00-00	1-3/4" x 9-1/2" VERSA-LAM® 2.0 3100 SP	2	2
B4 DR	10-00-00	1-3/4" x 9-1/2" VERSA-LAM® 2.0 3100 SP	2	2
B9	10-00-00	1-3/4" x 9-1/2" VERSA-LAM® 2.0 3100 SP	2	2
B10	4-00-00	1-3/4" x 9-1/2" VERSA-LAM® 2.0 3100 SP	1	1
B7	4-00-00	1-3/4" x 9-1/2" VERSA-LAM® 2.0 3100 SP	1	1

Connector Summary		
Qty	Manuf	Product
2	H1	HUS1.81/11.88
3	H1	IUS2.56/9.5
29	H1	IUS2.56/9.5
1	H2	HUS1.81/9.5
2	H2	HUS1.81/9.5
1	H3	HGUS410
1	H4	HUC410



FROM PLAN DATED: FEB 2016

BUILDER:  
GREENPARK

SITE:  
STARTIME

MODEL: BRIDGEFORD 2

ELEVATION: 3

LOT:  
CITY: VAUGHAN

SALESMAN: MARIO  
DESIGNER: AJ  
REVISION:


NOTES:  
CERAMIC TILE APPLICATION  
AS PER O.B.C. 9.30.6.  
SQUASH BLOCKS  
2x4 OR 2x6 #2 S.P.F. REQ'D UNDER  
INTERIOR UNIFORM LOAD BEARING  
WALLS.  
MULTIPLE SQUASH BLOCKS REQ'D  
UNDER CONCENTRATED LOADS.  
CANTILEVERED JOISTS  
REQUIRE I-JOIST BLOCKING ALONG  
BEARING AND RIMBOARD CLOSURE  
AT  
ENDS.  
REFER TO THE NORDIC  
INSTALLATION GUIDE FOR PROPER  
STORAGE AND INSTALLATION.  
LOADING:

DESIGN LOADS: L/480.000  
LIVE LOAD: 40.0 lb/ft<sup>2</sup>  
DEAD LOAD: 15.0 lb/ft  
TILED AREAS: 20 lb/ft


SUBFLOOR: 3/4" GLUED AND NAILED

DATE: 5/2/2016

1st FLOOR



Products				
PlotID	Length	Product	Plies	Net Qty
J1	14-00-00	9 1/2" NI-40x	1	12
J2	12-00-00	9 1/2" NI-40x	1	48
J3	10-00-00	9 1/2" NI-40x	1	2
B2	12-00-00	1-3/4" x 9-1/2" VERSA-LAM® 2.0 3100 SP	2	2
B3	12-00-00	1-3/4" x 9-1/2" VERSA-LAM® 2.0 3100 SP	2	2
B1	10-00-00	1-3/4" x 9-1/2" VERSA-LAM® 2.0 3100 SP	2	2



FROM PLAN DATED: FEB 2016

BUILDER:  
GREENPARK

SITE:  
STARTIME

MODEL: BRIDGEFORD 2

ELEVATION: 3

LOT:  
CITY: VAUGHAN


SALESMAN: MARIO  
DESIGNER: AJ  
REVISION:

NOTES:  
CERAMIC TILE APPLICATION  
AS PER O.B.C. 9.30.6.  
SQUASH BLOCKS  
2x4 OR 2x6 #2 S.P.F. REQ'D UNDER  
INTERIOR UNIFORM LOAD BEARING  
WALLS.  
MULTIPLE SQUASH BLOCKS REQ'D  
UNDER CONCENTRATED LOADS.  
CANTILEVERED JOISTS  
REQUIRE I-JOIST BLOCKING ALONG  
BEARING AND RIMBOARD CLOSURE  
AT  
ENDS.  
REFER TO THE NORDIC  
INSTALLATION GUIDE FOR PROPER  
STORAGE AND INSTALLATION.  
LOADING:  
DESIGN LOADS: L/480.000  
LIVE LOAD: 40.0 lb/ft<sup>2</sup>  
DEAD LOAD: 15.0 lb/ft  
TILED AREAS: 20 lb/ft

SUBFLOOR: 5/8" GLUED AND NAILED

DATE: 5/2/2016

2nd FLOOR



Products				
PlotID	Length	Product	Plies	Net Qty
J1	14-00-00	9 1/2" NI-40x	1	19
J2	12-00-00	9 1/2" NI-40x	1	41
J3	10-00-00	9 1/2" NI-40x	1	17
J4	4-00-00	9 1/2" NI-40x	1	3
B11	14-00-00	1-3/4" x 9-1/2" VERSA-LAM® 2.0 3100 SP	2	2
B12	12-00-00	1-3/4" x 9-1/2" VERSA-LAM® 2.0 3100 SP	2	2
B5 DR	12-00-00	1-3/4" x 9-1/2" VERSA-LAM® 2.0 3100 SP	2	2
B8	10-00-00	1-3/4" x 9-1/2" VERSA-LAM® 2.0 3100 SP	1	1
B13	10-00-00	1-3/4" x 9-1/2" VERSA-LAM® 2.0 3100 SP	2	2
B4 DR	10-00-00	1-3/4" x 9-1/2" VERSA-LAM® 2.0 3100 SP	2	2
B9	10-00-00	1-3/4" x 9-1/2" VERSA-LAM® 2.0 3100 SP	2	2
B10	4-00-00	1-3/4" x 9-1/2" VERSA-LAM® 2.0 3100 SP	1	1
B7	4-00-00	1-3/4" x 9-1/2" VERSA-LAM® 2.0 3100 SP	1	1

Connector Summary		
Qty	Manuf	Product
2	H1	HUS1.81/11.88
3	H1	IUS2.56/9.5
29	H1	IUS2.56/9.5
1	H2	HUS1.81/9.5
2	H2	HUS1.81/9.5
1	H3	HGUS410
1	H4	HUC410

**BC CALC® Design Report**


Build 4340

Job Name:

Address:

City, Province, Postal Code:

Customer:

Code reports: CCMC 12472-R

File Name: BRIDGEFORD 2 EL-1.mmdl


Description: Designs\Flush Beams\1st Floor\Flush Beams\B13(i2885)

Specifier:

Designer: AJ

Company:

Misc:



Total Horizontal Product Length = 09-08-00

**Reaction Summary (Down / Uplift) (lbs)**

Bearing	Live	Dead	Snow	Wind
B0, 5-1/2"	386 / 0	616 / 0	493 / 0	
B1, 5-1/2"	387 / 0	602 / 0	497 / 0	

**Load Summary**

Tag	Description	Load Type	Ref.	Start	End	Live 1.00	Dead 0.65	Snow 1.00	Wind 1.15	Trib.
1	FC2 Floor Material	Unf. Lin. (lb/ft)	L	-00-00-00	09-08-00	26	10			n/a
2	User Load	Unf. Lin. (lb/ft)	L	00-05-08	03-05-08	55	150	105		n/a
3	User Load	Unf. Lin. (lb/ft)	L	06-07-08	09-02-08	55	150	105		n/a
4	User Load	Conc. Pt. (lbs)	L	03-05-08	03-05-08	105	96	202		n/a
5	User Load	Conc. Pt. (lbs)	L	06-07-08	06-07-08	105	96	202		n/a

**Controls Summary**

	Factored Demand	Factored Resistance	Demand / Resistance	Load Case	Location
Pos. Moment	3,314 ft-lbs	25,408 ft-lbs	13%	13	03-05-08
End Shear	1,360 lbs	11,571 lbs	11.8%	13	01-03-00
Total Load Defl.	L/999 (0.075")	n/a	n/a	45	04-10-02
Live Load Defl.	L/999 (0.042")	n/a	n/a	61	04-10-02
Max Defl.	0.075"	n/a	n/a	45	04-10-02
Span / Depth	11.2	n/a	n/a		00-00-00

Bearing Supports	Dim. (L x W)	Demand	Demand / Resistance Support	Demand / Resistance Member	Material
B0 Wall/Plate	5-1/2" x 3-1/2"	1,702 lbs	16.6%	7.2%	Unspecified
B1 Wall/Plate	5-1/2" x 3-1/2"	1,692 lbs	16.5%	7.2%	Unspecified

**Notes**

 DWG NO. TAN3/266 -18  
 STRUCTURAL  
 COMPONENT ONLY



Build 4340

Job Name:

Address:

City, Province, Postal Code:

Customer:

Code reports: CCMC 12472-R

File Name: BRIDGEFORD 2 EL-1.mmdl

Description: Designs\Flush Beams\1st Floor\Flush Beams\B13(i2885)

Specifier:

Designer: AJ

Company:

Misc:

Design meets Code minimum (L/240) Total load deflection criteria.

Design meets Code minimum (L/360) Live load deflection criteria.

Calculations assume Member is Fully Braced.

Resistance Factor phi has been applied to all presented results per CSA086.

BC CALC® analysis is based on Canadian Limit States Design, as per NBCC and CSA086.

Unbalanced snow loads determined from building geometry were used in selected product's verification.

Design based on Dry Service Condition.

Importance Factor: Normal Part code: Part 9

Deflections less than 1/8" were ignored in the results.


**CONFORMS TO OBC 2012**

### Disclosure

Completeness and accuracy of input must be verified by anyone who would rely on output as evidence of suitability for particular application. Output here based on building code-accepted design properties and analysis methods. Installation of BOISE engineered wood products must be in accordance with current Installation Guide and applicable building codes. To obtain Installation Guide or ask questions, please call 1-800-964-6999 before installation.

BC CALC®, BC FRAMER®, AJS™, ALLJOIST®, BC RIM BOARD™, BC®, BOISE GLULAM™, SIMPLE FRAMING SYSTEM®, VERSA-LAM®, VERSA-RIM PLUS®, VERSA-RIM®, VERSA-STRAND®, VERSA-STUD® are trademarks of Boise Cascade Wood Products L.L.C.

### Connection Diagram




a minimum = 1/2" c = 1-1/2"  
b minimum = 3" d = 6"

Connection design assumes point load is top-loaded. For connection design of side-loaded point loads, please consult a technical representative or professional of Record.

Member has no side loads.

Connectors are: 16d Nails

3 1/2" ARDOX SPIRAL



DWG NO. TAM3/266-16  
STRUCTURAL  
COMPONENT ONLY



Boise Cascade

**Double 1-3/4" x 9-1/2" VERSA-LAM® 2.0 3100 SP Basment\Flush Beams\B1(i2251)**

Dry | 1 span | No cantilevers | 0/12 slope (deg)

May 2, 2016 09:35:05

BC CALC® Design Report



Build 4340

Job Name:

Address:

City, Province, Postal Code:

Customer:

Code reports: CCMC 12472-R

File Name: BRIDGEFORD 2 EL-1.mmdl


Description: Designs\Flush Beams\Basment\Flush Beams\B1(i2251)

Specifier:

Designer: AJ

Company:

Misc:



Total Horizontal Product Length = 09-11-06

**Reaction Summary (Down / Uplift) (lbs)**

Bearing	Live	Dead	Snow	Wind
B0, 4-3/8"	260 / 0	178 / 0		
B1, 5-1/2"	781 / 0	439 / 0		

**Load Summary**

Tag	Description	Load Type	Ref.	Start	End	Live 1.00	Dead 0.65	Snow 1.00	Wind 1.15	Trib.
1	FC1 Floor Material	Unf. Lin. (lb/ft)	L	00-00-00	09-08-10	15	7			n/a
2	User Load	Unf. Lin. (lb/ft)	L	05-08-14	09-05-14	240	120			n/a

**Controls Summary**

	Factored Demand	Factored Resistance	Demand / Resistance	Load Case	Location
Pos. Moment	2,746 ft-lbs	25,408 ft-lbs	10.8%	1	06-04-10
End Shear	1,270 lbs	11,571 lbs	11%	1	08-08-06
Total Load Defl.	L/999 (0.054")	n/a	n/a	4	05-03-11
Live Load Defl.	L/999 (0.034")	n/a	n/a	5	05-03-11
Max Defl.	0.054"	n/a	n/a	4	05-03-11
Span / Depth	11.7	n/a	n/a		00-00-00

**Bearing Supports**

	Dim. (L x W)	Demand	Demand / Resistance Support	Demand / Resistance Member	Material
B0 Wall/Plate	4-3/8" x 3-1/2"	613 lbs	7.5%	3.3%	Unspecified
B1 Wall/Plate	5-1/2" x 3-1/2"	1,721 lbs	16.7%	7.3%	Unspecified

**Notes**

Design meets Code minimum (L/240) Total load deflection criteria.

Design meets Code minimum (L/360) Live load deflection criteria.

Calculations assume Member is Fully Braced.

Resistance Factor phi has been applied to all presented results per CSA 086.


BC CALC® analysis is based on Canadian Limit States Design, as per NBCC and CSA 086.

Design based on Dry Service Condition.

Importance Factor: Normal Part code: Part 9

Deflections less than 1/8" were ignored in the results.

CONFORMS TO OBC 2012



p6 1/2

DWG NO. TAM31267-16  
STRUCTURAL  
COMPONENT ONLY



Boise Cascade

**Double 1-3/4" x 9-1/2" VERSA-LAM® 2.0 3100 SP Basment\Flush Beams\B1(i2251)**

BC CALC® Design Report



Dry | 1 span | No cantilevers | 0/12 slope (deg)

May 2, 2016 09:35:05

Build 4340

Job Name:

Address:

City, Province, Postal Code:

Customer:

Code reports:

CCMC 12472-R

File Name: BRIDGEFORD 2 EL-1.mmdl


Description: Designs\Flush Beams\Basment\Flush Beams\B1(i225

Specifier:

Designer: AJ

Company:

Misc:

**Connection Diagram**

a minimum = 2" c = 5-1/2"

b minimum = 3" d = 2 6 4

Member has no side loads.

Connectors are: 16d Nails (0.14...)

7  
3 1/2" ARDOX SPIRAL**Disclosure**

Completeness and accuracy of input must be verified by anyone who would rely on output as evidence of suitability for particular application. Output here based on building code-accepted design properties and analysis methods. Installation of BOISE engineered wood products must be in accordance with current Installation Guide and applicable building codes. To obtain Installation Guide or ask questions, please call 1-800-964-6999 before installation.

BC CALC®, BC FRAMER®, AJS™, ALLJOIST®, BC RIM BOARD™, BC®, BOISE GLULAM™, SIMPLE FRAMING SYSTEM®, VERSA-LAM®, VERSA-RIM PLUS®, VERSA-RIM®, VERSA-STRAND®, VERSA-STUD® are trademarks of Boise Cascade Wood Products L.L.C.



DWG NO. TAM 31267 -16  
STRUCTURAL  
COMPONENT ONLY



Boise Cascade

## Double 1-3/4" x 9-1/2" VERSA-LAM® 2.0 3100 SP Basment\Flush Beams\B2(i2737)

Dry | 1 span | No cantilevers | 0/12 slope (deg)

May 2, 2016 09:35:06

BC CALC® Design Report



Build 4340

Job Name:

Address:

City, Province, Postal Code:

Customer:

Code reports: CCMC 12472-R

File Name: BRIDGEFORD 2 EL-1.mmdl


Description: Designs\Flush Beams\Basment\Flush Beams\B2(i2737)

Specifier:

Designer: AJ

Company:

Misc:



Total Horizontal Product Length = 11-02-02

## Reaction Summary (Down / Uplift) (lbs)

Bearing	Live	Dead	Snow	Wind
B0, 2-3/4"	665 / 0	442 / 0		
B1, 4-3/8"	474 / 0	318 / 0		

## Load Summary

Tag	Description	Load Type	Ref.	Start	End	Live 1.00	Dead 0.65	Snow 1.00	Wind 1.15	Trib.
1	FC1 Floor Material	Unf. Lin. (lb/ft)	L	-00-00-00	11-02-02	53	27			n/a
2	PBO1(i2374)	Conc. Pt. (lbs)	L	03-06-12	03-06-12	543	354			n/a

## Controls Summary

	Factored Demand	Factored Resistance	Demand / Resistance	Load Case	Location
Pos. Moment	4,472 ft-lbs	25,408 ft-lbs	17.6%	1	03-06-12
End Shear	1,423 lbs	11,571 lbs	12.3%	1	01-00-04
Total Load Defl.	L/999 (0.119")	n/a	n/a	4	05-03-05
Live Load Defl.	L/999 (0.071")	n/a	n/a	5	05-03-05
Max Defl.	0.119"	n/a	n/a	4	05-03-05
Span / Depth	13.5	n/a	n/a		00-00-00

## Bearing Supports

	Dim. (L x W)	Demand	Demand/ Resistance Support	Demand/ Resistance Member	Material
B0 Wall/Plate	2-3/4" x 3-1/2"	1,551 lbs	30.2%	13.2%	Unspecified
B1 Wall/Plate	4-3/8" x 3-1/2"	1,108 lbs	13.5%	5.9%	Unspecified

## Notes

Design meets Code minimum (L/240) Total load deflection criteria.

Design meets Code minimum (L/360) Live load deflection criteria.

Calculations assume Member is Fully Braced.

Resistance Factor phi has been applied to all presented results per CSA 086.


BC CALC® analysis is based on Canadian Limit States Design, as per NBCC and CSA 086.

Design based on Dry Service Condition.

Importance Factor: Normal Part code: Part 9

Deflections less than 1/8" were ignored in the results.

CONFORMS TO OBC 2012



p6A

DWG NO. TAM 3126B-16  
STRUCTURAL  
COMPONENT ONLY



Boise Cascade

**Double 1-3/4" x 9-1/2" VERSA-LAM® 2.0 3100 SP Basement\Flush Beams\B2(i2737)**

BC CALC® Design Report



Dry | 1 span | No cantilevers | 0/12 slope (deg)

May 2, 2016 09:35:06

Build 4340

Job Name:

Address:

City, Province, Postal Code:

Customer:

Code reports: CCMC 12472-R

File Name: BRIDGEFORD 2 EL-1.mmd


Description: Designs\Flush Beams\Basement\Flush Beams\B2(i273

Specifier:

Designer: AJ

Company:

Misc:

**Connection Diagram**

a minimum = 1/2" c = 1-1/2"  
 b minimum = 3" d = 6"

Connection design assumes point load is top-loaded. For connection design of side-loaded point loads, please consult a technical representative or professional of Record.

Member has no side loads.


Connectors are: 16d Nails (16d) 3 1/2" ARDOX SPIRAL

3 1/2" ARDOX SPIRAL

**Disclosure**

Completeness and accuracy of input must be verified by anyone who would rely on output as evidence of suitability for particular application. Output here based on building code-accepted design properties and analysis methods. Installation of BOISE engineered wood products must be in accordance with current Installation Guide and applicable building codes. To obtain Installation Guide or ask questions, please call 1-800-964-6999 before installation.

BC CALO®, BC FRAMER®, AJS™, ALLJOIST®, BC RIM BOARD™, BC®, BOISE GLULAM™, SIMPLE FRAMING SYSTEM®, VERSA-LAM®, VERSA-RIM PLUS®, VERSA-RIM®, VERSA-STRAND®, VERSA-STUD® are trademarks of Boise Cascade Wood Products L.L.C.



DWG NO. TAN 31168-16  
 STRUCTURAL  
 COMPONENT ONLY



# Double 1-3/4" x 9-1/2" VERSA-LAM® 2.0 3100 SP Basement\Flush Beams\B3(i2709)

Dry | 1 span | No cantilevers | 0/12 slope (deg)

May2, 2016 09:35:06

BC CALC® Design Report



Build 4340

Job Name:

Address:

City, Province, Postal Code:

Customer:

Code reports: CCMC 12472-R

File Name: BRIDGEFORD 2 EL-1.mmdl


Description: Designs\Flush Beams\Basement\Flush Beams\B3(i2709)

Specifier:

Designer: AJ

Company:

Misc:



Total Horizontal Product Length = 11-04-14

## Reaction Summary (Down / Uplift) (lbs)

Bearing	Live	Dead	Snow	Wind
B0, 5-1/2"	1,522 / 0	1,182 / 0		
B1, 4-3/8"	382 / 0	664 / 0		

## Load Summary

Tag	Description	Load Type	Ref.	Start	End	Live 1.00	Dead 0.65	Snow 1.00	Wind 1.15	Trib.
1	7(i2368)	Unf. Lin. (lb/ft)	L	00-00-00	11-00-08		81			n/a
2	7(i2368)	Unf. Lin. (lb/ft)	L	00-00-00	00-10-09	52				n/a
3	FC1 Floor Material	Unf. Lin. (lb/ft)	L	00-02-12	11-04-14	27	13			n/a
4	7(i2368)	Unf. Lin. (lb/ft)	L	01-08-04	11-00-08	15	8			n/a
5	7(i2368)	Conc. Pt. (lbs)	L	01-06-08	01-06-08	1,418	602			n/a

Controls Summary	Factored Demand	Factored Resistance	Demand / Resistance	Load Case	Location
Pos. Moment	4,777 ft-lbs	25,408 ft-lbs	18.8%	1	04-02-12
End Shear	3,514 lbs	11,571 lbs	30.4%	1	01-03-00
Total Load Defl.	L/871 (0.148")	0.535"	27.6%	4	05-05-03
Live Load Defl.	L/999 (0.065")	n/a	n/a	5	05-03-10
Max Defl.	0.148"	n/a	n/a	4	05-05-03
Span / Depth	13.5	n/a	n/a		00-00-00

Bearing Supports	Dim. (L x W)	Demand	Demand / Resistance Support	Demand / Resistance Member	Material
B0 Wall/Plate	5-1/2" x 3-1/2"	3,760 lbs	36.6%	16%	Unspecified
B1 Wall/Plate	4-3/8" x 3-1/2"	930 lbs	17.5%	7.7%	Unspecified

## Notes

Design meets Code minimum (L/240) Total load deflection criteria.

Design meets Code minimum (L/360) Live load deflection criteria.

Calculations assume Member is Fully Braced.

Resistance Factor phi has been applied to all presented results per CSA 086.

BC CALC® analysis is based on Canadian Limit States Design, as per NBCC and CSA 086.

Design based on Dry Service Condition.

Importance Factor: Normal Part code: Part 9

Deflections less than 1/8" were ignored in the results.

CONFORMS TO OBC 2012



DWG NO. TAM 3/269-16  
STRUCTURAL  
COMPONENT ONLY



Boise Cascade

**Double 1-3/4" x 9-1/2" VERSA-LAM® 2.0 3100 SP Basement\Flush Beams\B3(i2709)**

BC CALC® Design Report



Dry | 1 span | No cantilevers | 0/12 slope (deg)

May 2, 2016 09:35:06

Build 4340

Job Name:

Address:

City, Province, Postal Code:

Customer:

Code reports:

CCMC 12472-R

File Name: BRIDGEFORD 2 EL-1.mmdl


Description: Designs\Flush Beams\Basement\Flush Beams\B3(i270

Specifier:

Designer: AJ

Company:

Misc:

**Connection Diagram**

a minimum = 4"      c = 3-1/2"  
 b minimum = 3"      d = 6"

Connection design assumes point load is top-loaded. For connection design of side-loaded point loads, please consult a technical representative or professional of Record.

Member has no side loads.

Connectors are: 16d Nails (16d x 3 1/2")

3 1/2" ARDOX SPIRAL

**Disclosure**

Completeness and accuracy of input must be verified by anyone who would rely on output as evidence of suitability for particular application. Output here based on building code-accepted design properties and analysis methods.

Installation of BOISE engineered wood products must be in accordance with current Installation Guide and applicable building codes. To obtain Installation Guide or ask questions, please call 1-800-964-6999 before installation.

BC CALC®, BC FRAMER®, AJS™, ALLJOIST®, BC RIM BOARD™, BC®, BOISE GLULAM™, SIMPLE FRAMING SYSTEM®, VERSA-LAM®, VERSA-RIM PLUS®, VERSA-RIM®, VERSA-STRAND®, VERSA-STUD® are trademarks of Boise Cascade Wood Products L.L.C.



DWG NO. TAM3/269 -16  
 STRUCTURAL  
 COMPONENT ONLY



# Double 1-3/4" x 9-1/2" VERSA-LAM® 2.0 3100 SP 1st Floor\...\B4 DR(i2336)

Dry | 1 span | No cantilevers | 0/12 slope (deg)

May 2, 2016 09:35:06

BC CALC® Design Report



Build 4340

Job Name:

Address:

City, Province, Postal Code:

Customer:

Code reports: CCMC 12472-R

File Name: BRIDGEFORD 2 EL-1.mmdl


Description: Designs\Dropped Beams\1st Floor\Dropped Beams\B4 D

Specifier:

Designer: AJ

Company:

Misc:



Total Horizontal Product Length = 08-08-00

## Reaction Summary (Down / Uplift) (lbs)

Bearing	Live	Dead	Snow	Wind
B0, 4"	1,684 / 0	676 / 0		
B1, 4"	1,857 / 0	742 / 0		

## Load Summary

Tag	Description	Load Type	Ref.	Start	End	Live 1.00	Dead 0.65	Snow 1.00	Wind 1.15	Trib.
1	Smoothed Load	Unf. Lin. (lb/ft)	L	01-04-06	08-04-06	437	165			n/a
2	-	Conc. Pt. (lbs)	L	01-01-07	01-01-07	485	182			n/a

## Controls Summary

	Factored Demand	Factored Resistance	Demand / Resistance	Load Case	Location
Pos. Moment	7,391 ft-lbs	25,408 ft-lbs	29.1%	1	03-11-10
End Shear	3,225 lbs	11,571 lbs	27.9%	1	01-01-08
Total Load Defl.	L/999 (0.123")	n/a	n/a	4	04-03-11
Live Load Defl.	L/999 (0.088")	n/a	n/a	5	04-03-11
Max Defl.	0.123"	n/a	n/a	4	04-03-11
Span / Depth	10.3	n/a	n/a		00-00-00

## Bearing Supports

	Dim. (L x W)	Demand	Demand / Resistance Support	Demand / Resistance Member	Material
B0 Wall/Plate	4" x 3-1/2"	3,371 lbs	29.7%	19.7%	Unspecified
B1 Wall/Plate	4" x 3-1/2"	3,713 lbs	32.7%	21.7%	Unspecified

## Notes

Design meets Code minimum (L/240) Total load deflection criteria.

Design meets Code minimum (L/360) Live load deflection criteria.

Calculation assumes member is partially braced. See engineering report for the unbraced length.

Resistance Factor phi has been applied to all presented results per CSA 086.

BC CALC® analysis is based on Canadian Limit States Design, as per NBCC and CSA 086.

Design based on Dry Service Condition.

Importance Factor: Normal Part code: Part 9

Deflections less than 1/8" were ignored in the results.

CONFORMS TO OBC 2012



DWG NO. TAM 31220-16  
STRUCTURAL  
COMPONENT ONLY

BC CALC® Design Report



Build 4340

Job Name:

Address:

City, Province, Postal Code:

Customer:

Code reports:

CCMC 12472-R

File Name: BRIDGEFORD 2 EL-1.mmd

Description: Designs\Dropped Beams\1st Floor\Dropped Beams\B4


Specifier:

Designer: AJ

Company:

Misc:

## Connection Diagram



$\frac{1}{4}$ " 4 rows  
 $\frac{1}{2}$ " 4 rows  
 $\frac{1}{4}$ "

a minimum =  $\frac{1}{4}$ " c =  $3\frac{1}{2}$ "  
 b minimum = 3" d =  $4\frac{1}{2}$ "

Connection design assumes point load is top-loaded. For connection design of side-loaded point loads, please consult a technical representative or professional of Record.  
 Member has no side loads.


Connectors are: 16d Nails (16d) 16d

$3\frac{1}{2}$ " ARDOX SPIRAL

## Disclosure

Completeness and accuracy of input must be verified by anyone who would rely on output as evidence of suitability for particular application. Output here based on building code-accepted design properties and analysis methods. Installation of BOISE engineered wood products must be in accordance with current Installation Guide and applicable building codes. To obtain Installation Guide or ask questions, please call 1-800-964-6999 before installation.

BC CALC®, BC FRAMER®, AJS™, ALLJOIST®, BC RIM BOARD™, BCI®, BOISE GLULAM™, SIMPLE FRAMING SYSTEM®, VERSA-LAM®, VERSA-RIM PLUS®, VERSA-RIM®, VERSA-STRAND®, VERSA-STUD® are trademarks of Boise Cascade Wood Products L.L.C.



DWG NO. TAM31270-16  
 STRUCTURAL  
 COMPONENT ONLY



# Double 1-3/4" x 9-1/2" VERSA-LAM® 2.0 3100 SP 1st Floor...B5 DR(i2340)

Dry | 1 span | No cantilevers | 0/12 slope (deg)

May 2, 2016 09:35:07

BC CALC® Design Report



Build 4340

Job Name:

Address:

City, Province, Postal Code:

Customer:

Code reports: CCMC 12472-R

File Name: BRIDGEFORD 2 EL-1.mmdl


Description: Designs\Dropped Beams\1st Floor\Dropped Beams\B5 D

Specifier:

Designer: AJ

Company:

Misc:



Total Horizontal Product Length = 11-08-00

## Reaction Summary (Down / Uplift) (lbs)

Bearing	Live	Dead	Snow	Wind
B0, 4"	2,605 / 0	1,037 / 0		
B1, 4"	2,652 / 0	1,051 / 0		

## Load Summary

Tag	Description	Load Type	Ref.	Start	End	Live 1.00	Dead 0.65	Snow 1.00	Wind 1.15	Trib.
1	Smoothed Load	Unf. Lin. (lb/ft)	L	00-04-06	05-04-06	403	152			n/a
2	Smoothed Load	Unf. Lin. (lb/ft)	L	06-04-06	11-07-10	228	86			n/a
3	J2(i2534)	Conc. Pt. (lbs)	L	00-03-10	00-03-10	292	110			n/a
4	-	Conc. Pt. (lbs)	L	05-08-14	05-08-14	532	200			n/a
5	J2(i2495)	Conc. Pt. (lbs)	L	06-11-10	06-11-10	278	104			n/a
6	J2(i2536)	Conc. Pt. (lbs)	L	08-03-10	08-03-10	267	100			n/a
7	J2(i2617)	Conc. Pt. (lbs)	L	09-04-14	09-04-14	230	86			n/a
8	J2(i2620)	Conc. Pt. (lbs)	L	10-04-14	10-04-14	219	82			n/a
9	J2(i2622)	Conc. Pt. (lbs)	L	11-04-14	11-04-14	219	82			n/a

## Controls Summary

	Factored Demand	Factored Resistance	Demand / Resistance	Load Case	Location
Pos. Moment	13,831 ft-lbs	25,408 ft-lbs	54.4%	1	05-10-06
End Shear	4,524 lbs	11,571 lbs	39.1%	1	10-06-08
Total Load Defl.	L/311 (0.429")	0.556"	77.2%	4	05-10-06
Live Load Defl.	L/435 (0.307")	0.371"	82.8%	5	05-10-06
Max Defl.	0.429"	n/a	n/a	4	05-10-06
Span / Depth	14.1	n/a	n/a		00-00-00

## Bearing Supports

B0	Wall/Plate	4" x 3-1/2"	5,204 lbs	45.8%	30.5%	Unspecified
B1	Wall/Plate	4" x 3-1/2"	5,292 lbs	46.5%	31%	Unspecified

## Notes



DWG NO. TAM3/271-16  
STRUCTURAL  
COMPONENT ONLY

BC CALC® Design Report



Build 4340

Job Name:

Address:

City, Province, Postal Code:

Customer:

Code reports: CCMC 12472-R

File Name: BRIDGEFORD 2 EL-1.mmdl

Description: Designs\Dropped Beams\1st Floor\Dropped Beams\B5

Specifier:

Designer: AJ

Company:

Misc:

Design meets Code minimum (L/240) Total load deflection criteria.

Design meets Code minimum (L/360) Live load deflection criteria.

Calculation assumes member is partially braced. See engineering report for the unbraced length.

Resistance Factor phi has been applied to all presented results per CSA 086.

BC CALC® analysis is based on Canadian Limit States Design, as per NBCC and CSA 086.


Design based on Dry Service Condition.

Importance Factor : Normal Part code : Part 9

Deflections less than 1/8" were ignored in the results.

CONFORMS TO OBC 2012

Connection Diagram



a minimum = 1" c = 1-1/2"  
b minimum = 3" d = 4"

Connection design assumes point load is top-loaded. For connection design of side-loaded point loads, please consult a technical representative or professional of Record.

Member has no side loads.

Connectors are: 16d Common Nails (16d 20mm x 100mm)

3/4" ARDOX SPIRAL

Disclosure

Completeness and accuracy of input must be verified by anyone who would rely on output as evidence of suitability for particular application. Output here based on building code-accepted design properties and analysis methods. Installation of BOISE engineered wood products must be in accordance with current Installation Guide and applicable building codes. To obtain Installation Guide or ask questions, please call 1-800-964-6999 before installation.

BC CALC®, BC FRAMER®, AJS™, ALLJOIST®, BC RIM BOARD™, BCI®, BOISE GLULAM™, SIMPLE FRAMING SYSTEM®, VERSA-LAM®, VERSA-RIM PLUS®, VERSA-RIM®, VERSA-STRAND®, VERSA-STUD® are trademarks of Boise Cascade Wood Products L.L.C.



DWG NO. TAM 3121 -16  
STRUCTURAL  
COMPONENT ONLY

BC CALC® Design Report



Dry | 1 span | No cantilevers | 0/12 slope (deg)

May 2, 2016 09:35:07

Build 4340

Job Name:

Address:

City, Province, Postal Code:

Customer:

Code reports: CCMC 12472-R

File Name: BRIDGEFORD 2 EL-1.mmdl

Description: Designs\Dropped Beams\1st Floor\Dropped Beams\B6(12

Specifier:

Designer: AJ

Company:

**Misc:**

[illegible]

Total Horizontal Product Length = 07-10-00

**Reaction Summary (Down / Uplift) ( lbs )**

Bearing	Live	Dead	Snow	Wind
B0, 6"	136/0	108/0		
B1, 6"	136/0	108/0		

## Load Summary

Load Summary						Live	Dead	Snow	Wind	Trib.
Tag	Description	Load Type	Ref.	Start	End	1.00	0.65	1.00	1.15	
1	J1 (i2507)	Unf. Lin. (lb/ft)	L	00-00-00	07-10-00	31	14			n/a
2	R1 (i2646)	Unf. Lin. (lb/ft)	L	00-00-00	07-10-00	4	4			n/a

## Controls Summary

<b>Controls Summary</b>	<b>Factored Demand</b>	<b>Factored Resistance</b>	<b>Demand / Resistance</b>	<b>Load Case</b>	<b>Location</b>
Pos. Moment	523 ft-lbs	25,408 ft-lbs	2.1%	1	03-11-00
End Shear	227 lbs	11,571 lbs	2%	1	01-03-08
Total Load Defl.	L/999 (0.007")	n/a	n/a	4	03-11-00
Live Load Defl.	L/999 (0.004")	n/a	n/a	5	03-11-00
Max Defl.	0.007"	n/a	n/a	4	03-11-00
Span / Depth	8.8	n/a	n/a		00-00-00

## Bearing Supports

Bearing Supports		Dim. (L x W)	Demand	Demand/	Demand/	Material
				Resistance	Resistance	
				Support	Member	
B0	Wall/Plate	6" x 3-1/2"	339 lbs	2%	1.3%	Unspecified
B1	Wall/Plate	6" x 3-1/2"	339 lbs	2%	1.3%	Unspecified

## Notes

Design meets Code minimum (L/240) Total load deflection criteria.

Design meets Code minimum ( $L/360$ ) Live load deflection criteria.

Calculations assume Member is Fully Braced.


Resistance Factor  $\phi$  has been applied to all presented results per CSA 086. **CONFORMS TO OBC 2012**

BC CALC® analysis is based on Canadian Limit States Design, as per NBCC and CSA 086.

Design based on Dry Service Condition.

Importance Factor : Normal      Part code : Part 9

Deflections less than 1/8" were ignored in the results.



DWG NO. TAM 31272-16  
STRUCTURAL  
COMPONENT ONLY

BC CALC® Design Report



Build 4340

Job Name:

Address:

City, Province, Postal Code:

Customer:

Code reports:

CCMC 12472-R

File Name: BRIDGEFORD 2 EL-1.mmdl

Description: Designs\Dropped Beams\1st Floor\Dropped Beams\B6


Specifier:

Designer: AJ

Company:

Misc:

### Connection Diagram



a minimum = 2" c = 5-1/2"  
b minimum = 3" d = 4"

Member has no side loads.


Connectors are: 16d x 1 1/2" Nails

3 1/2" ARDOX SPIRAL

### Disclosure

Completeness and accuracy of input must be verified by anyone who would rely on output as evidence of suitability for particular application. Output here based on building code-accepted design properties and analysis methods. Installation of BOISE engineered wood products must be in accordance with current Installation Guide and applicable building codes. To obtain Installation Guide or ask questions, please call 1-800-964-6999 before installation.

BC CALC®, BC FRAMER®, AJS™, ALLJOIST®, BC RIM BOARD™, BC®, BOISE GLULAM™, SIMPLE FRAMING SYSTEM®, VERSA-LAM®, VERSA-RIM PLUS®, VERSA-RIM®, VERSA-STRAND®, VERSA-STUD® are trademarks of Boise Cascade Wood Products L.L.C.



DWG NO. TAM3/22-16  
STRUCTURAL  
COMPONENT ONLY



# Single 1-3/4" x 9-1/2" VERSA-LAM® 2.0 3100 SP 1st Floor\Flush Beams\B7(i2728)

Dry | 1 span | No cantilevers | 0/12 slope (deg)

May 2, 2016 09:35:07

BC CALC® Design Report



Build 4340

Job Name:

Address:

City, Province, Postal Code:

Customer:

Code reports: CCMC 12472-R

File Name: BRIDGEFORD 2 EL-1.mmdl


Description: Designs\Flush Beams\1st Floor\Flush Beams\B7(i2728)

Specifier:

Designer: AJ

Company:

Misc:



Total Horizontal Product Length = 03-06-13

## Reaction Summary (Down / Uplift) (lbs)

Bearing	Live	Dead	Snow	Wind
B0, 3-1/2"	472 / 0	235 / 0		
B1	447 / 0	222 / 0		

## Load Summary

Tag	Description	Load Type	Ref.	Start	End	Live 1.00	Dead 0.65	Snow 1.00	Wind 1.15	Trib.
1	J4(i2725)	Conc. Pt. (lbs)	L	00-05-07	00-05-07	230	110			n/a
2	J4(i2739)	Conc. Pt. (lbs)	L	01-07-06	01-07-06	360	172			n/a
3	J4(i2720)	Conc. Pt. (lbs)	L	02-11-06	02-11-06	329	157			n/a

## Controls Summary

	Factored Demand	Factored Resistance	Demand / Resistance	Load Case	Location
Pos. Moment	818 ft-lbs	12,704 ft-lbs	6.4%	1	01-07-06
End Shear	645 lbs	5,785 lbs	11.2%	1	02-07-05
Total Load Defl.	L/999 (0.004")	n/a	n/a	4	01-10-00
Live Load Defl.	L/999 (0.003")	n/a	n/a	5	01-10-00
Max Defl.	0.004"	n/a	n/a	4	01-10-00
Span / Depth	4.1	n/a	n/a		00-00-00

## Bearing Supports

	Dim. (L x W)	Demand	Demand / Resistance Support	Demand / Resistance Member	Material
B0 Post	3-1/2" x 1-3/4"	1,001 lbs	20.1%	13.4%	Unspecified
B1 Hanger	2" x 1-3/4"	947 lbs	n/a	22.2%	Hanger

## Notes

Design meets Code minimum (L/240) Total load deflection criteria.  
 Design meets Code minimum (L/360) Live load deflection criteria.  
 Calculations assume Member is Fully Braced.  
 Resistance Factor phi has been applied to all presented results per CSA 086.  
 BC CALC® analysis is based on Canadian Limit States Design, as per NBCC and CSA 086.  
 Design based on Dry Service Condition.  
 Importance Factor: Normal Part code: Part 9  
 Deflections less than 1/8" were ignored in the results.

CONFORMS TO OBC 2012

## Disclosure

Completeness and accuracy of input must be verified by anyone who would rely on output as evidence of suitability for particular application. Output here based on building code-accepted design properties and analysis methods. Installation of BOISE engineered wood products must be in accordance with current Installation Guide and applicable building codes. To obtain Installation Guide or ask questions, please call 1-800-964-6999 before installation.

BC CALC®, BC FRAMER®, AJS™, ALLJOIST®, BC RIM BOARD™, BCI®, BOISE GLULAM™, SIMPLE FRAMING SYSTEM®, VERSA-LAM®, VERSA-RIM PLUS®, VERSA-RIM®, VERSA-STRAND®, VERSA-STUD® are trademarks of Boise Cascade Wood Products L.L.C.



DWG NO. YAW3/273-16  
 STRUCTURAL  
 COMPONENT ONLY



# Single 1-3/4" x 9-1/2" VERSA-LAM® 2.0 3100 SP 1st Floor\Flush Beams\B8(i2706)

Dry | 1 span | No cantilevers | 0/12 slope (deg)

May 2, 2016 09:35:07

BC CALC® Design Report



Build 4340

Job Name:

Address:

City, Province, Postal Code:

Customer:

Code reports: CCMC 12472-R

File Name: BRIDGEFORD 2 EL-1.mmdl

Description: Designs\Flush Beams\1st Floor\Flush Beams\B8(i2706)

Specifier:

Designer: AJ

Company:

Misc:



09-09-12

B1

Total Horizontal Product Length = 09-09-12

## Reaction Summary (Down / Uplift) (lbs)

Bearing	Live	Dead	Snow	Wind
B0	326 / 0	185 / 0		
B1, 5-1/2"	93 / 0	71 / 0		

## Load Summary

Tag	Description	Load Type	Ref.	Start	End	Live 1.00	Dead 0.65	Snow 1.00	Wind 1.15	Trib.
1	B7(i2728)	Conc. Pt. (lbs)	L	02-02-02	02-02-02	419	208			n/a

Controls Summary	Factored Demand	Factored Resistance	Demand / Resistance	Load Case	Location
Pos. Moment	1,478 ft-lbs	12,704 ft-lbs	11.6%	1	02-02-02
End Shear	714 lbs	5,785 lbs	12.3%	1	00-11-08
Total Load Defl.	L/999 (0.05")	n/a	n/a	4	04-02-01
Live Load Defl.	L/999 (0.031")	n/a	n/a	5	04-02-01
Max Defl.	0.05"	n/a	n/a	4	04-02-01
Span / Depth	11.8	n/a	n/a		00-00-00

## Disclosure

Completeness and accuracy of input must be verified by anyone who would rely on output as evidence of suitability for particular application. Output here based on building code-accepted design properties and analysis methods. Installation of BOISE engineered wood products must be in accordance with current Installation Guide and applicable building codes. To obtain Installation Guide or ask questions, please call 1-800-964-6999 before installation.

## Bearing Supports

	Dim. (L x W)	Demand	Demand / Resistance Support	Demand / Resistance Member	Material
B0 Hanger	2" x 1-3/4"	719 lbs	n/a	16.8%	Hanger
B1 Wall/Plate	5-1/2" x 1-3/4"	228 lbs	4.4%	1.9%	Unspecified

## Notes

Design meets Code minimum (L/240) Total load deflection criteria.

Design meets Code minimum (L/360) Live load deflection criteria.

Calculations assume Member is Fully Braced.

Resistance Factor phi has been applied to all presented results per CSA 086.

BC CALC® analysis is based on Canadian Limit States Design, as per NBCC and CSA 086.

Design based on Dry Service Condition.

Importance Factor: Normal Part code: Part 9

Deflections less than 1/8" were ignored in the results.

CONFORMS TO OBC 2012



DWG NO. TAM 31274-16  
STRUCTURAL  
COMPONENT ONLY



# Double 1-3/4" x 9-1/2" VERSA-LAM® 2.0 3100 SP 1st Floor\Flush Beams\B9(i2748)

Dry | 1 span | No cantilevers | 0/12 slope (deg)

May 2, 2016 09:35:07

BC CALC® Design Report



Build 4340

Job Name:

Address:

City, Province, Postal Code:

Customer:

Code reports: CCMC 12472-R

File Name: BRIDGEFORD 2 EL-1.mmdl


Description: Designs\Flush Beams\1st Floor\Flush Beams\B9(i2748)

Specifier:

Designer: AJ

Company:

Misc:



Total Horizontal Product Length = 09-11-06

## Reaction Summary (Down / Uplift) (lbs)

Bearing	Live	Dead	Snow	Wind
B0, 5-1/8"	1,410 / 0	597 / 0		
B1	1,936 / 0	823 / 0		

## Load Summary

Tag	Description	Load Type	Ref.	Start	End	Live 1.00	Dead 0.65	Snow 1.00	Wind 1.15	Trib.
1	Smoothed Load	Unf. Lin. (lb/ft)	L	00-06-12	04-06-12	260	98			n/a
2	J4(i2725)	Conc. Pt. (lbs)	L	04-02-13	04-02-13	37	14			n/a
3	-	Conc. Pt. (lbs)	L	05-03-01	05-03-01	372	139			n/a
4	-	Conc. Pt. (lbs)	L	06-04-14	06-04-14	329	123			n/a
5	-	Conc. Pt. (lbs)	L	07-04-10	07-04-10	578	279			n/a
6	-	Conc. Pt. (lbs)	L	08-01-06	08-01-06	509	195			n/a
7	-	Conc. Pt. (lbs)	L	09-03-07	09-03-07	456	171			n/a

Controls Summary	Factored Demand	Factored Resistance	Demand / Resistance	Load Case	Location
Pos. Moment	8,066 ft-lbs	25,408 ft-lbs	31.7%	1	05-04-12
End Shear	3,587 lbs	11,571 lbs	31%	1	08-11-14
Total Load Defl.	L/619 (0.184")	0.474"	38.8%	4	05-02-12
Live Load Defl.	L/882 (0.129")	0.316"	40.8%	5	05-02-12
Max Defl.	0.184"	n/a	n/a	4	05-02-12
Span / Depth	12	n/a	n/a		00-00-00

Bearing Supports	Dim. (L x W)	Demand	Demand / Support Resistance	Demand / Member Resistance	Material
B0 Wall/Plate	5-1/8" x 3-1/2"	2,862 lbs	29.9%	13.1%	Unspecified
B1 Hanger	2" x 3-1/2"	3,933 lbs	n/a	46.1%	Hanger

## Notes

Design meets Code minimum (L/240) Total load deflection criteria.

Design meets Code minimum (L/360) Live load deflection criteria.

Calculations assume Member is Fully Braced.


Resistance Factor phi has been applied to all presented results per CSA 086.

BC CALC® analysis is based on Canadian Limit States Design, as per NBCC and CSA 086.

Design based on Dry Service Condition.

Importance Factor: Normal Part code: Part 9

Deflections less than 1/8" were ignored in the results.



CONFORMS TO OBC 2012

DWG NO. TAM31275-16  
STRUCTURAL  
COMPONENT ONLY



Boise Cascade

**Double 1-3/4" x 9-1/2" VERSA-LAM® 2.0 3100 SP 1st Floor\Flush Beams\B9(i2748)**

Dry | 1 span | No cantilevers | 0/12 slope (deg)

May 2, 2016 09:35:07

BC CALC® Design Report



Build 4340

Job Name:

Address:

City, Province, Postal Code:

Customer:

Code reports:

CCMC 12472-R

File Name: BRIDGEFORD 2 EL-1.mmdl


Description: Designs\Flush Beams\1st Floor\Flush Beams\B9(i2748

Specifier:

Designer: AJ

Company:

Misc:

**Connection Diagram**

a minimum = 2"      c = 2-3/4"  
 b minimum = 3"      d = 4"

Calculated Side Load = 482.9 lb/ft

Connection design assumes point load is top-loaded. For connection design of side-loaded point loads, please consult a technical representative or professional of Record.


Connectors are: 16d S&amp;W Nails (2 1/2 in.)

1 3/4" ARDOX SPIRAL

**Disclosure**

Completeness and accuracy of input must be verified by anyone who would rely on output as evidence of suitability for particular application. Output here based on building code-accepted design properties and analysis methods. Installation of BOISE engineered wood products must be in accordance with current Installation Guide and applicable building codes. To obtain Installation Guide or ask questions, please call 1-800-964-6999 before installation.

BC CALC®, BC FRAMER®, AJS™, ALLJOIST®, BC RIM BOARD™, BC®, BOISE GLULAM™, SIMPLE FRAMING SYSTEM®, VERSA-LAM®, VERSA-RIM PLUS®, VERSA-RIM®, VERSA-STRAND®, VERSA-STUD® are trademarks of Boise Cascade Wood Products L.L.C.



DWG NO. TAM 31275-16  
 STRUCTURAL  
 COMPONENT ONLY



Boise Cascade

## Single 1-3/4" x 9-1/2" VERSA-LAM® 2.0 3100 SP 1st Floor\Flush Beams\B10(i2712)

BC CALC® Design Report



Dry | 1 span | No cantilevers | 0/12 slope (deg)

May 2, 2016 09:35:08

Build 4340

Job Name:

Address:

City, Province, Postal Code:

Customer:

Code reports:

CCMC 12472-R

File Name: BRIDGEFORD 2 EL-1.mmdl


Description: Designs\Flush Beams\1st Floor\Flush Beams\B10(i2712)

Specifier:

Designer: AJ

Company:

Misc:



Total Horizontal Product Length = 02-01-04

## Reaction Summary (Down / Uplift) (lbs)

Bearing	Live	Dead	Snow	Wind
B0	10 / 0	9 / 0		
B1, 1-3/4"	42 / 0	25 / 0		

## Load Summary

Tag	Description	Load Type	Ref.	Start	End	Live 1.00	Dead 0.65	Snow 1.00	Wind 1.15	Trib.
1	FC2 Floor Material	Unf. Lin. (lb/ft)	L	-00-00-00	02-01-04	9	3			n/a
2	FC2 Floor Material	Conc. Pt. (lbs)	L	02-01-04	02-01-04	32	16			n/a

## Controls Summary

	Factored Demand	Factored Resistance	Demand / Resistance	Load Case	Location
Pos. Moment	11 ft-lbs	n/a	n/a	1	01-00-12
End Shear	2 lbs	n/a	n/a	1	00-11-08
Span / Depth	2.4	n/a	n/a		00-00-00

## Bearing Supports

	Dim. (L x W)	Demand	Demand / Resistance Support	Demand / Resistance Member	Material
B0 Hanger	2" x 1-3/4"	25 lbs	n/a	0.6%	Hanger
B1 Post	1-3/4" x 1-3/4"	93 lbs	3.7%	2.5%	Unspecified

## Notes

Calculations assume Member is Fully Braced.

Resistance Factor phi has been applied to all presented results per CSA 086.

BC CALC® analysis is based on Canadian Limit States Design, as per NBCC and CSA 086.

Design based on Dry Service Condition.

Importance Factor : Normal Part code : Part 9

Deflections less than 1/8" were ignored in the results.

CONFORMS TO OBC 2012

## Disclosure

Completeness and accuracy of input must be verified by anyone who would rely on output as evidence of suitability for particular application. Output here based on building code-accepted design properties and analysis methods. Installation of BOISE engineered wood products must be in accordance with current Installation Guide and applicable building codes. To obtain Installation Guide or ask questions, please call 1-800-964-6999 before installation.

BC CALC®, BC FRAMER®, AJS™, ALLJOIST®, BC RIM BOARD™, BCI®, BOISE GLULAM™, SIMPLE FRAMING SYSTEM®, VERSA-LAM®, VERSA-RIM PLUS®, VERSA-RIM®, VERSA-STRAND®, VERSA-STUD® are trademarks of Boise Cascade Wood Products L.L.C.



DWG NO. TAM 3/27616  
STRUCTURAL  
COMPONENT ONLY

BC CALC® Design Report



Build 4340

Job Name:

Address:

City, Province, Postal Code:

Customer:

Code reports: CCMC 12472-R

File Name: BRIDGEFORD 2 EL-1.mmdl


Description: Designs\Flush Beams\1st Floor\Flush Beams\B11(i2729)

Specifier:

Designer: AJ

Company:

Misc:



Total Horizontal Product Length = 12-11-06

## Reaction Summary (Down / Uplift) (lbs)

Bearing	Live	Dead	Snow	Wind
B0	1,634 / 0	747 / 0		
B1, 4-3/8"	632 / 0	323 / 0		

## Load Summary

Tag	Description	Load Type	Ref.	Start	End	Live 1.00	Dead 0.65	Snow 1.00	Wind 1.15	Trib.
1	FC2 Floor Material	Unf. Lin. (lb/ft)	L	00-00-00	12-11-06	9	4			n/a
2	FC2 Floor Material	Unf. Lin. (lb/ft)	L	00-00-00	03-01-00	15	6			n/a
3	FC2 Floor Material	Unf. Lin. (lb/ft)	L	03-01-00	12-11-06	17	6			n/a
4	B9(i2748)	Conc. Pt. (lbs)	L	03-01-00	03-01-00	1,928	819			n/a

## Controls Summary

	Factored Demand	Factored Resistance	Demand / Resistance	Load Case	Location
Pos. Moment	9,800 ft-lbs	25,408 ft-lbs	38.6%	1	03-01-00
End Shear	3,328 lbs	11,571 lbs	28.8%	1	00-11-08
Total Load Defl.	L/483 (0.312")	0.627"	49.7%	4	05-09-11
Live Load Defl.	L/708 (0.212")	0.418"	50.8%	5	05-08-00
Max Defl.	0.312"	n/a	n/a	4	05-09-11
Span / Depth	15.8	n/a	n/a		00-00-00

## Bearing Supports

	Dim. (L x W)	Demand	Demand / Resistance Support	Demand / Resistance Member	Material
B0 Hanger	2" x 3-1/2"	3,386 lbs	n/a	39.6%	Hanger
B1 Wall/Plate	4-3/8" x 3-1/2"	1,353 lbs	16.5%	7.2%	Unspecified

## Notes

Design meets Code minimum (L/240) Total load deflection criteria.

Design meets Code minimum (L/360) Live load deflection criteria.

Calculations assume Member is Fully Braced.

Resistance Factor phi has been applied to all presented results per CSA 086.

BC CALC® analysis is based on Canadian Limit States Design, as per NBCC and CSA 086.

Design based on Dry Service Condition.

Importance Factor : Normal Part code : Part 9

Deflections less than 1/8" were ignored in the results.

CONFORMS TO OBC 2012



DWG NO. YAM 3/277-16  
STRUCTURAL  
COMPONENT ONLY

BC CALC® Design Report



Build 4340

Job Name:

Address:

City, Province, Postal Code:

Customer:

Code reports:

CCMC 12472-R

File Name: BRIDGEFORD 2 EL-1.mmdl

Description: Designs\Flush Beams\1st Floor\Flush Beams\B11(i2729)

Specifier:

Designer: AJ


Company:

Misc:

### Connection Diagram

Concentrated side-load exceeds allowable magnitude for connection design. Please consult a technical representative or Professional Engineer for the design of the connection.

*OK WITH  
NAILING*



PROVIDE 4 ROWS OF 3 1/2" ARDOX SPIRAL NAILS @ 6" O/C FOR MULTI-PLY NAILING, MAINTAIN A MIN. 1" LUMBER EDGE/END DISTANCE. DO NOT USE AIR NAILS

### Disclosure

Completeness and accuracy of input must be verified by anyone who would rely on output as evidence of suitability for particular application. Output here based on building code-accepted design properties and analysis methods. Installation of BOISE engineered wood products must be in accordance with current Installation Guide and applicable building codes. To obtain Installation Guide or ask questions, please call 1-800-964-6999 before installation.

BC CALC®, BC FRAMER®, AJS™, ALLJOIST®, BC RIM BOARD™, BC®, BOISE GLULAM™, SIMPLE FRAMING SYSTEM®, VERSA-LAM®, VERSA-RIM PLUS®, VERSA-RIM®, VERSA-STRAND®, VERSA-STUD® are trademarks of Boise Cascade Wood Products L.L.C.



DWG NO. TAM 3/27-16  
STRUCTURAL  
COMPONENT ONLY

BC CALC® Design Report



Build 4340

Job Name:

Address:

City, Province, Postal Code:

Customer:

Code reports: CCMC 12472-R

File Name: BRIDGEFORD 2 EL-1.mmdl


Description: Designs\Flush Beams\1st Floor\Flush Beams\B12(i2742)

Specifier:

Designer: AJ

Company:

Misc:



Total Horizontal Product Length = 10-01-12

## Reaction Summary (Down / Uplift) (lbs)

Bearing	Live	Dead	Snow	Wind
B0, 3-1/2"	3,822 / 0	1,619 / 0		
B1, 4"	2,502 / 0	991 / 0		

## Load Summary

Tag	Description	Load Type	Ref.	Start	End	Live 1.00	Dead 0.65	Snow 1.00	Wind 1.15	Trib.
1	Smoothed Load	Unf. Lin. (lb/ft)	L	01-03-06	04-10-10	499	188			n/a
2	Smoothed Load	Unf. Lin. (lb/ft)	L	06-07-06	10-01-12	510	192			n/a
3	-	Conc. Pt. (lbs)	L	00-02-10	00-02-10	2,049	903			n/a
4	J3(i2648)	Conc. Pt. (lbs)	L	05-04-10	05-04-10	150	56			n/a
5	-	Conc. Pt. (lbs)	L	05-11-06	05-11-06	526	198			n/a

## Controls Summary

	Factored Demand	Factored Resistance	Demand / Resistance	Load Case	Location
Pos. Moment	10,370 ft-lbs	25,408 ft-lbs	40.8%	1	04-07-06
End Shear	3,797 lbs	11,571 lbs	32.8%	1	09-00-04
Total Load Defl.	L/477 (0.243")	0.482"	50.3%	4	05-00-00
Live Load Defl.	L/667 (0.174")	0.322"	54%	5	05-00-00
Max Defl.	0.243"	n/a	n/a	4	05-00-00
Span / Depth	12.2	n/a	n/a		00-00-00

## Bearing Supports

	Dim. (L x W)	Demand	Demand / Resistance Support	Demand / Resistance Member	Material
B0 Post	3-1/2" x 3-1/2"	7,756 lbs	78%	51.9%	Unspecified
B1 Wall/Plate	4" x 3-1/2"	4,993 lbs	66.8%	29.2%	Unspecified

## Notes

Design meets Code minimum (L/240) Total load deflection criteria.

Design meets Code minimum (L/360) Live load deflection criteria.

Calculations assume Member is Fully Braced.


Resistance Factor phi has been applied to all presented results per CSA 086.

BC CALC® analysis is based on Canadian Limit States Design, as per NBCC and CSA 086.

Design based on Dry Service Condition.

Importance Factor : Normal Part code : Part 9

Deflections less than 1/8" were ignored in the results.

**CONFORMS TO OBC 2012**

 DWG NO. TAM 31278-16  
 STRUCTURAL  
 COMPONENT ONLY

BC CALC® Design Report



Build 4340

Job Name:

Address:

City, Province, Postal Code:

Customer:

Code reports:

CCMC 12472-R

File Name: BRIDGEFORD 2 EL-1.mmdl

Description: Designs\Flush Beams\1st Floor\Flush Beams\B12(i274


Specifier:

Designer: AJ

Company:

Misc:

Connection Diagram



a minimum = 2" c = 3-1/2"  
b minimum = 3" d = 6"

Calculated Side Load = 872.0 lb/ft

Connection design assumes point load is top-loaded. For connection design of side-loaded point loads, please consult a technical representative or professional of Record.

Connectors are: 16d Nails (16d x 3-1/2")

3 1/2" ARDOX SPIRAL




Disclosure

Completeness and accuracy of input must be verified by anyone who would rely on output as evidence of suitability for particular application. Output here based on building code-accepted design properties and analysis methods. Installation of BOISE engineered wood products must be in accordance with current Installation Guide and applicable building codes. To obtain Installation Guide or ask questions, please call 1-800-964-6999 before installation.

BC CALC®, BC FRAMER®, AJS™, ALLJOIST®, BC RIM BOARD™, BC®, BOISE GLULAM™, SIMPLE FRAMING SYSTEM®, VERSA-LAM®, VERSA-RIM PLUS®, VERSA-RIM®, VERSA-STRAND®, VERSA-STUD® are trademarks of Boise Cascade Wood Products L.L.C.



DWG NO. TAM 312816  
STRUCTURAL  
COMPONENT ONLY



## Maximum Floor Spans

Live Load = 40 psf, Dead Load = 15 psf  
Simple Spans, L/480 Deflection Limit  
5/8" OSB G&N Sheathing

Depth	Series	Bare				1/2" Gypsum Ceiling			
		On Centre Spacing				On Centre Spacing			
		12"	16"	19.2"	24"	12"	16"	19.2"	24"
9-1/2"	NI-20	15'-1"	14'-2"	13'-9"	N/A	15'-7"	14'-8"	14'-2"	N/A
	NI-40x	16'-1"	15'-2"	14'-8"	N/A	16'-7"	15'-7"	15'-1"	N/A
	NI-60	16'-3"	15'-4"	14'-10"	N/A	16'-8"	15'-9"	15'-3"	N/A
	NI-70	17'-1"	16'-1"	15'-6"	N/A	17'-5"	16'-5"	15'-10"	N/A
	NI-80	17'-3"	16'-3"	15'-8"	N/A	17'-8"	16'-7"	16'-0"	N/A
11-7/8"	NI-20	16'-11"	16'-0"	15'-5"	N/A	17'-6"	16'-6"	16'-0"	N/A
	NI-40x	18'-1"	17'-0"	16'-5"	N/A	18'-9"	17'-6"	16'-11"	N/A
	NI-60	18'-4"	17'-3"	16'-7"	N/A	19'-0"	17'-8"	17'-1"	N/A
	NI-70	19'-6"	18'-0"	17'-4"	N/A	20'-1"	18'-7"	17'-9"	N/A
	NI-80	19'-9"	18'-3"	17'-6"	N/A	20'-4"	18'-10"	17'-11"	N/A
14"	NI-90x	20'-4"	18'-9"	17'-11"	N/A	20'-10"	19'-3"	18'-5"	N/A
	NI-40x	20'-1"	18'-7"	17'-10"	N/A	20'-10"	19'-4"	18'-6"	N/A
	NI-60	20'-5"	18'-11"	18'-1"	N/A	21'-2"	19'-7"	18'-9"	N/A
	NI-70	21'-7"	20'-0"	19'-1"	N/A	22'-3"	20'-7"	19'-8"	N/A
	NI-80	21'-11"	20'-3"	19'-4"	N/A	22'-7"	20'-11"	20'-0"	N/A
16"	NI-90x	22'-7"	20'-11"	19'-11"	N/A	23'-3"	21'-6"	20'-6"	N/A
	NI-60	22'-3"	20'-8"	19'-9"	N/A	23'-1"	21'-5"	20'-6"	N/A
	NI-70	23'-6"	21'-9"	20'-9"	N/A	24'-3"	22'-5"	21'-5"	N/A
	NI-80	23'-11"	22'-1"	21'-1"	N/A	24'-8"	22'-10"	21'-9"	N/A
	NI-90x	24'-8"	22'-9"	21'-9"	N/A	25'-4"	23'-5"	22'-4"	N/A

Depth	Series	Mid-Span Blocking				Mid-Span Blocking and 1/2" Gypsum Ceiling			
		On Centre Spacing				On Centre Spacing			
		12"	16"	19.2"	24"	12"	16"	19.2"	24"
9-1/2"	NI-20	16'-8"	15'-3"	14'-5"	N/A	16'-8"	15'-3"	14'-5"	N/A
	NI-40x	17'-11"	16'-11"	16'-1"	N/A	18'-5"	17'-1"	16'-1"	N/A
	NI-60	18'-2"	17'-1"	16'-4"	N/A	18'-7"	17'-4"	16'-4"	N/A
	NI-70	19'-2"	17'-10"	17'-2"	N/A	19'-7"	18'-3"	17'-7"	N/A
	NI-80	19'-5"	18'-0"	17'-4"	N/A	19'-10"	18'-5"	17'-8"	N/A
11-7/8"	NI-20	19'-6"	18'-1"	17'-3"	N/A	19'-11"	18'-3"	17'-3"	N/A
	NI-40x	21'-0"	19'-6"	18'-8"	N/A	21'-7"	20'-2"	19'-2"	N/A
	NI-60	21'-4"	19'-9"	18'-11"	N/A	21'-11"	20'-4"	19'-6"	N/A
	NI-70	22'-6"	20'-10"	19'-11"	N/A	23'-0"	21'-5"	20'-5"	N/A
	NI-80	22'-9"	21'-1"	20'-1"	N/A	23'-3"	21'-7"	20'-8"	N/A
14"	NI-90x	23'-4"	21'-8"	20'-8"	N/A	23'-10"	22'-2"	21'-2"	N/A
	NI-40x	23'-7"	21'-11"	20'-11"	N/A	24'-3"	22'-7"	21'-7"	N/A
	NI-60	24'-0"	22'-3"	21'-3"	N/A	24'-8"	22'-11"	21'-11"	N/A
	NI-70	25'-3"	23'-4"	22'-3"	N/A	25'-10"	24'-0"	22'-11"	N/A
	NI-80	25'-7"	23'-8"	22'-7"	N/A	26'-2"	24'-4"	23'-2"	N/A
16"	NI-90x	26'-4"	24'-4"	23'-3"	N/A	26'-10"	24'-11"	23'-9"	N/A
	NI-60	26'-5"	24'-6"	23'-4"	N/A	27'-2"	25'-3"	24'-2"	N/A
	NI-70	27'-9"	25'-8"	24'-6"	N/A	28'-5"	26'-5"	25'-2"	N/A
	NI-80	28'-2"	26'-1"	24'-10"	N/A	28'-10"	26'-9"	25'-6"	N/A
	NI-90x	29'-0"	26'-10"	25'-7"	N/A	29'-7"	27'-5"	26'-2"	N/A

- Maximum clear span applicable to simple-span residential floor construction with a design live load of 40 psf and dead load of 15 psf. The ultimate limit states are based on the factored loads of 1.50L + 1.25D. The serviceability limit states include the consideration for floor vibration, a live load deflection limit of L/480 and a total load deflection limit of L/240.
- Spans are based on a composite floor with glued-nailed oriented strand board (OSB) sheathing with a minimum thickness of 5/8 inch for a joist spacing of 19.2 inches or less. The composite floor may include 1/2 inch gypsum ceiling and/or one row of blocking at mid-span with strapping. Strapping shall be minimum 1x4 inch strap applied to underside of joists at blocking line or 1/2 inch gypsum ceiling attached to joists.
- Minimum bearing length shall be 1-3/4 inches for the end bearings.
- Bearing stiffeners are not required when I-joists are used with the spans and spacings given in this table, except as required for hangers.
- This span chart is based on uniform loads. For applications with other than uniformly distributed loads, an engineering analysis may be required based on the use of the design properties. Tables are based on Limit States Design per CSA O86-09, NBC 2010, and OBC 2012.
- Joists shall be laterally supported at supports and continuously along the compression edge. Refer to technical documentation for installation guidelines and construction details. Nordic I-joists are listed in CCMC evaluation report 13032-R and APA Product Report PR-L274C.



## Maximum Floor Spans



Live Load = 40 psf, Dead Load = 15 psf  
Simple Spans, L/480 Deflection Limit  
3/4" OSB G&N Sheathing

Depth	Series	Bare				1/2" Gypsum Ceiling			
		On Centre Spacing				On Centre Spacing			
		12"	16"	19.2"	24"	12"	16"	19.2"	24"
9-1/2"	NI-20	15'-10"	15'-0"	14'-5"	13'-5"	16'-4"	15'-5"	14'-6"	13'-5"
	NI-40x	17'-0"	16'-0"	15'-5"	14'-9"	17'-5"	16'-5"	15'-10"	15'-2"
	NI-60	17'-2"	16'-2"	15'-7"	14'-11"	17'-6"	16'-7"	15'-11"	15'-3"
	NI-70	18'-0"	16'-11"	16'-3"	15'-7"	18'-5"	17'-3"	16'-7"	15'-11"
	NI-80	18'-3"	17'-1"	16'-5"	15'-9"	18'-8"	17'-5"	16'-9"	16'-1"
11-7/8"	NI-20	17'-10"	16'-10"	16'-2"	15'-6"	18'-6"	17'-4"	16'-9"	16'-1"
	NI-40x	19'-4"	17'-11"	17'-3"	16'-6"	19'-11"	18'-6"	17'-9"	17'-0"
	NI-60	19'-7"	18'-2"	17'-5"	16'-9"	20'-2"	18'-9"	17'-11"	17'-2"
	NI-70	20'-9"	19'-2"	18'-3"	17'-5"	21'-4"	19'-9"	18'-10"	17'-10"
	NI-80	21'-1"	19'-5"	18'-6"	17'-7"	21'-7"	20'-0"	19'-0"	18'-0"
	NI-90x	21'-8"	20'-0"	19'-1"	18'-0"	22'-2"	20'-6"	19'-6"	18'-6"
14"	NI-40x	21'-5"	19'-10"	18'-11"	17'-11"	22'-1"	20'-6"	19'-7"	18'-7"
	NI-60	21'-10"	20'-2"	19'-3"	18'-2"	22'-5"	20'-10"	19'-11"	18'-10"
	NI-70	23'-0"	21'-3"	20'-3"	19'-2"	23'-8"	21'-11"	20'-10"	19'-9"
	NI-80	23'-5"	21'-7"	20'-7"	19'-5"	24'-0"	22'-3"	21'-2"	20'-0"
	NI-90x	24'-1"	22'-3"	21'-2"	20'-0"	24'-8"	22'-10"	21'-9"	20'-7"
16"	NI-60	23'-9"	22'-0"	20'-11"	19'-10"	24'-6"	22'-9"	21'-8"	20'-6"
	NI-70	25'-1"	23'-2"	22'-0"	20'-10"	25'-9"	23'-10"	22'-9"	21'-6"
	NI-80	25'-6"	23'-6"	22'-4"	21'-2"	26'-1"	24'-2"	23'-1"	21'-10"
	NI-90x	26'-4"	24'-3"	23'-1"	21'-10"	26'-11"	24'-11"	23'-8"	22'-5"

Depth	Series	Mid-Span Blocking				Mid-Span Blocking and 1/2" Gypsum Ceiling			
		On Centre Spacing				On Centre Spacing			
		12"	16"	19.2"	24"	12"	16"	19.2"	24"
9-1/2"	NI-20	16'-10"	15'-5"	14'-6"	13'-5"	16'-10"	15'-5"	14'-6"	13'-5"
	NI-40x	18'-8"	17'-2"	16'-3"	15'-2"	18'-10"	17'-2"	16'-3"	15'-2"
	NI-60	18'-11"	17'-6"	16'-6"	15'-5"	19'-2"	17'-6"	16'-6"	15'-5"
	NI-70	20'-0"	18'-7"	17'-9"	16'-7"	20'-5"	18'-11"	17'-10"	16'-7"
	NI-80	20'-3"	18'-10"	17'-11"	16'-10"	20'-8"	19'-3"	18'-2"	16'-10"
11-7/8"	NI-20	20'-1"	18'-5"	17'-5"	16'-2"	20'-1"	18'-5"	17'-5"	16'-2"
	NI-40x	21'-10"	20'-4"	19'-4"	17'-8"	22'-5"	20'-6"	19'-4"	17'-8"
	NI-60	22'-1"	20'-7"	19'-7"	18'-4"	22'-8"	20'-10"	19'-8"	18'-4"
	NI-70	23'-4"	21'-8"	20'-8"	19'-7"	23'-10"	22'-3"	21'-2"	19'-9"
	NI-80	23'-7"	21'-11"	20'-11"	19'-9"	24'-1"	22'-6"	21'-5"	20'-0"
	NI-90x	24'-3"	22'-6"	21'-6"	20'-4"	24'-8"	23'-0"	22'-0"	20'-9"
14"	NI-40x	24'-5"	22'-9"	21'-8"	19'-5"	25'-1"	23'-2"	21'-9"	19'-5"
	NI-60	24'-10"	23'-1"	22'-0"	20'-10"	25'-6"	23'-8"	22'-4"	20'-10"
	NI-70	26'-1"	24'-3"	23'-2"	21'-10"	26'-8"	24'-11"	23'-9"	22'-4"
	NI-80	26'-6"	24'-7"	23'-5"	22'-2"	27'-1"	25'-3"	24'-1"	22'-9"
	NI-90x	27'-3"	25'-4"	24'-1"	22'-9"	27'-9"	25'-11"	24'-8"	23'-4"
16"	NI-60	27'-3"	25'-5"	24'-2"	22'-10"	28'-0"	26'-2"	24'-9"	23'-1"
	NI-70	28'-8"	26'-8"	25'-4"	23'-11"	29'-3"	27'-4"	26'-1"	24'-8"
	NI-80	29'-1"	27'-0"	25'-9"	24'-4"	29'-8"	27'-9"	26'-5"	25'-0"
	NI-90x	29'-11"	27'-10"	26'-6"	25'-0"	30'-6"	28'-5"	27'-2"	25'-8"

- Maximum clear span applicable to simple-span residential floor construction with a design live load of 40 psf and dead load of 15 psf. The ultimate limit states are based on the factored loads of 1.50L + 1.25D. The serviceability limit states include the consideration for floor vibration, a live load deflection limit of L/480 and a total load deflection limit of L/240.
- Spans are based on a composite floor with glued-nailed oriented strand board (OSB) sheathing with a minimum thickness of 3/4 inch for a joist spacing of 24 inches or less. The composite floor may include 1/2 inch gypsum ceiling and/or one row of blocking at mid-span with strapping. Strapping shall be minimum 1x4 inch strap applied to underside of joists at blocking line or 1/2 inch gypsum ceiling attached to joists.
- Minimum bearing length shall be 1-3/4 inches for the end bearings.
- Bearing stiffeners are not required when I-joists are used with the spans and spacings given in this table, except as required for hangers.
- This span chart is based on uniform loads. For applications with other than uniformly distributed loads, an engineering analysis may be required based on the use of the design properties. Tables are based on Limit States Design per CSA O86-09, NBC 2010, and OBC 2012.
- Joists shall be laterally supported at supports and continuously along the compression edge. Refer to technical documentation for installation guidelines and construction details. Nordic I-joists are listed in CCMC evaluation report 13032-R and APA Product Report PR-L274C.



## Maximum Floor Spans



Live Load = 40 psf, Dead Load = 30 psf  
Simple Spans, L/480 Deflection Limit  
5/8" OSB G&N Sheathing

Depth	Series	Bare				1/2" Gypsum Ceiling			
		On Centre Spacing				On Centre Spacing			
		12"	16"	19.2"	24"	12"	16"	19.2"	24"
9-1/2"	NI-20	15'-1"	14'-1"	13'-3"	N/A	15'-7"	14'-1"	13'-3"	N/A
	NI-40x	16'-1"	15'-2"	14'-8"	N/A	16'-7"	15'-7"	15'-1"	N/A
	NI-60	16'-3"	15'-4"	14'-10"	N/A	16'-8"	15'-9"	15'-3"	N/A
	NI-70	17'-1"	16'-1"	15'-6"	N/A	17'-5"	16'-5"	15'-10"	N/A
	NI-80	17'-3"	16'-3"	15'-8"	N/A	17'-8"	16'-7"	16'-0"	N/A
11-7/8"	NI-20	16'-11"	16'-0"	15'-5"	N/A	17'-6"	16'-6"	16'-0"	N/A
	NI-40x	18'-1"	17'-0"	16'-5"	N/A	18'-9"	17'-6"	16'-11"	N/A
	NI-60	18'-4"	17'-3"	16'-7"	N/A	19'-0"	17'-8"	17'-1"	N/A
	NI-70	19'-6"	18'-0"	17'-4"	N/A	20'-1"	18'-7"	17'-9"	N/A
	NI-80	19'-9"	18'-3"	17'-6"	N/A	20'-4"	18'-10"	17'-11"	N/A
	NI-90x	20'-4"	18'-9"	17'-11"	N/A	20'-10"	19'-3"	18'-5"	N/A
14"	NI-40x	20'-1"	18'-7"	17'-10"	N/A	20'-10"	19'-4"	18'-6"	N/A
	NI-60	20'-5"	18'-11"	18'-1"	N/A	21'-2"	19'-7"	18'-9"	N/A
	NI-70	21'-7"	20'-0"	19'-1"	N/A	22'-3"	20'-7"	19'-8"	N/A
	NI-80	21'-11"	20'-3"	19'-4"	N/A	22'-7"	20'-11"	20'-0"	N/A
	NI-90x	22'-7"	20'-11"	19'-11"	N/A	23'-3"	21'-6"	20'-6"	N/A
16"	NI-60	22'-3"	20'-8"	19'-9"	N/A	23'-1"	21'-5"	20'-6"	N/A
	NI-70	23'-6"	21'-9"	20'-9"	N/A	24'-3"	22'-5"	21'-5"	N/A
	NI-80	23'-11"	22'-1"	21'-1"	N/A	24'-8"	22'-10"	21'-9"	N/A
	NI-90x	24'-8"	22'-9"	21'-9"	N/A	25'-4"	23'-5"	22'-4"	N/A

Depth	Series	Mid-Span Blocking				Mid-Span Blocking and 1/2" Gypsum Ceiling			
		On Centre Spacing				On Centre Spacing			
		12"	16"	19.2"	24"	12"	16"	19.2"	24"
9-1/2"	NI-20	15'-7"	14'-1"	13'-3"	N/A	15'-7"	14'-1"	13'-3"	N/A
	NI-40x	17'-9"	16'-1"	15'-1"	N/A	17'-9"	16'-1"	15'-1"	N/A
	NI-60	18'-1"	16'-4"	15'-4"	N/A	18'-1"	16'-4"	15'-4"	N/A
	NI-70	19'-2"	17'-10"	16'-9"	N/A	19'-7"	17'-10"	16'-9"	N/A
	NI-80	19'-5"	18'-0"	17'-1"	N/A	19'-10"	18'-3"	17'-1"	N/A
11-7/8"	NI-20	18'-9"	17'-0"	16'-0"	N/A	18'-9"	17'-0"	16'-0"	N/A
	NI-40x	21'-0"	19'-3"	17'-9"	N/A	21'-3"	19'-3"	17'-9"	N/A
	NI-60	21'-4"	19'-8"	18'-5"	N/A	21'-8"	19'-8"	18'-5"	N/A
	NI-70	22'-6"	20'-10"	19'-11"	N/A	23'-0"	21'-4"	20'-0"	N/A
	NI-80	22'-9"	21'-1"	20'-1"	N/A	23'-3"	21'-7"	20'-5"	N/A
	NI-90x	23'-4"	21'-8"	20'-8"	N/A	23'-10"	22'-2"	21'-2"	N/A
14"	NI-40x	23'-7"	21'-5"	19'-6"	N/A	24'-1"	21'-5"	19'-6"	N/A
	NI-60	24'-0"	22'-3"	21'-0"	N/A	24'-8"	22'-5"	21'-0"	N/A
	NI-70	25'-3"	23'-4"	22'-3"	N/A	25'-10"	24'-0"	22'-9"	N/A
	NI-80	25'-7"	23'-8"	22'-7"	N/A	26'-2"	24'-4"	23'-2"	N/A
	NI-90x	26'-4"	24'-4"	23'-3"	N/A	26'-10"	24'-11"	23'-9"	N/A
16"	NI-60	26'-5"	24'-6"	23'-4"	N/A	27'-2"	24'-10"	23'-4"	N/A
	NI-70	27'-9"	25'-8"	24'-6"	N/A	28'-5"	26'-5"	25'-2"	N/A
	NI-80	28'-2"	26'-1"	24'-10"	N/A	28'-10"	26'-9"	25'-6"	N/A
	NI-90x	29'-0"	26'-10"	25'-7"	N/A	29'-7"	27'-5"	26'-2"	N/A

- Maximum clear span applicable to simple-span residential floor construction with a design live load of 40 psf and dead load of 30 psf. The ultimate limit states are based on the factored loads of 1.50L + 1.25D. The serviceability limit states include the consideration for floor vibration, a live load deflection limit of L/480 and a total load deflection limit of L/240.
- Spans are based on a composite floor with glued-nailed oriented strand board (OSB) sheathing with a minimum thickness of 5/8 inch for a joist spacing of 19.2 inches or less. The composite floor may include 1/2 inch gypsum ceiling and/or one row of blocking at mid-span with strapping. Strapping shall be minimum 1x4 inch strap applied to underside of joists at blocking line or 1/2 inch gypsum ceiling attached to joists.
- Minimum bearing length shall be 1-3/4 inches for the end bearings.
- Bearing stiffeners are not required when I-joists are used with the spans and spacings given in this table, except as required for hangers.
- This span chart is based on uniform loads. For applications with other than uniformly distributed loads, an engineering analysis may be required based on the use of the design properties. Tables are based on Limit States Design per CSA O86-09, NBC 2010, and OBC 2012.
- Joists shall be laterally supported at supports and continuously along the compression edge. Refer to technical documentation for installation guidelines and construction details. Nordic I-joists are listed in CCMC evaluation report 13032-R and APA Product Report PR-L274C.




## Maximum Floor Spans

Live Load = 40 psf, Dead Load = 30 psf  
Simple Spans, L/480 Deflection Limit  
3/4" OSB G&N Sheathing



Depth	Series	Bare				1/2" Gypsum Ceiling			
		On Centre Spacing				On Centre Spacing			
		12"	16"	19.2"	24"	12"	16"	19.2"	24"
9-1/2"	NI-20	15'-7"	14'-2"	13'-4"	12'-4"	15'-7"	14'-2"	13'-4"	12'-4"
	NI-40x	17'-0"	16'-0"	15'-1"	13'-11"	17'-5"	16'-1"	15'-1"	13'-11"
	NI-60	17'-2"	16'-2"	15'-5"	14'-3"	17'-6"	16'-5"	15'-5"	14'-3"
	NI-70	18'-0"	16'-11"	16'-3"	15'-6"	18'-5"	17'-3"	16'-7"	15'-6"
	NI-80	18'-3"	17'-1"	16'-5"	15'-9"	18'-8"	17'-5"	16'-9"	15'-10"
11-7/8"	NI-20	17'-10"	16'-10"	16'-0"	14'-10"	18'-6"	17'-1"	16'-0"	14'-10"
	NI-40x	19'-4"	17'-11"	17'-3"	15'-10"	19'-11"	18'-6"	17'-9"	15'-10"
	NI-60	19'-7"	18'-2"	17'-5"	16'-9"	20'-2"	18'-9"	17'-11"	17'-1"
	NI-70	20'-9"	19'-2"	18'-3"	17'-5"	21'-4"	19'-9"	18'-10"	17'-10"
	NI-80	21'-1"	19'-5"	18'-6"	17'-7"	21'-7"	20'-0"	19'-0"	18'-0"
14"	NI-90x	21'-8"	20'-0"	19'-1"	18'-0"	22'-2"	20'-6"	19'-6"	18'-6"
	NI-40x	21'-5"	19'-10"	18'-11"	17'-5"	22'-1"	20'-6"	19'-6"	17'-5"
	NI-60	21'-10"	20'-2"	19'-3"	18'-2"	22'-5"	20'-10"	19'-11"	18'-10"
	NI-70	23'-0"	21'-3"	20'-3"	19'-2"	23'-8"	21'-11"	20'-10"	19'-9"
	NI-80	23'-5"	21'-7"	20'-7"	19'-5"	24'-0"	22'-3"	21'-2"	20'-0"
16"	NI-90x	24'-1"	22'-3"	21'-2"	20'-0"	24'-8"	22'-10"	21'-9"	20'-7"
	NI-60	23'-9"	22'-0"	20'-11"	19'-10"	24'-6"	22'-9"	21'-8"	20'-6"
	NI-70	25'-1"	23'-2"	22'-0"	20'-10"	25'-9"	23'-10"	22'-9"	21'-6"
	NI-80	25'-6"	23'-6"	22'-4"	21'-2"	26'-1"	24'-2"	23'-1"	21'-10"
	NI-90x	26'-4"	24'-3"	23'-1"	21'-10"	26'-11"	24'-11"	23'-8"	22'-5"

Depth	Series	Mid-Span Blocking				Mid-Span Blocking and 1/2" Gypsum Ceiling			
		On Centre Spacing				On Centre Spacing			
		12"	16"	19.2"	24"	12"	16"	19.2"	24"
9-1/2"	NI-20	15'-7"	14'-2"	13'-4"	12'-4"	15'-7"	14'-2"	13'-4"	12'-4"
	NI-40x	17'-9"	16'-1"	15'-1"	13'-11"	17'-9"	16'-1"	15'-1"	13'-11"
	NI-60	18'-1"	16'-5"	15'-5"	14'-3"	18'-1"	16'-5"	15'-5"	14'-3"
	NI-70	19'-10"	17'-11"	16'-9"	15'-6"	19'-10"	17'-11"	16'-9"	15'-6"
	NI-80	20'-2"	18'-3"	17'-1"	15'-10"	20'-2"	18'-3"	17'-1"	15'-10"
11-7/8"	NI-20	18'-10"	17'-1"	16'-0"	14'-10"	18'-10"	17'-1"	16'-0"	14'-10"
	NI-40x	21'-3"	19'-3"	17'-9"	15'-10"	21'-3"	19'-3"	17'-9"	15'-10"
	NI-60	21'-9"	19'-8"	18'-5"	17'-1"	21'-9"	19'-8"	18'-5"	17'-1"
	NI-70	23'-4"	21'-5"	20'-1"	18'-6"	23'-8"	21'-5"	20'-1"	18'-6"
	NI-80	23'-7"	21'-10"	20'-5"	18'-11"	24'-1"	21'-10"	20'-5"	18'-11"
14"	NI-90x	24'-3"	22'-6"	21'-3"	19'-7"	24'-8"	22'-7"	21'-3"	19'-7"
	NI-40x	24'-2"	21'-5"	19'-6"	17'-5"	24'-2"	21'-5"	19'-6"	17'-5"
	NI-60	24'-9"	22'-5"	21'-0"	19'-6"	24'-9"	22'-5"	21'-0"	19'-6"
	NI-70	26'-1"	24'-3"	22'-9"	21'-0"	26'-8"	24'-3"	22'-9"	21'-0"
	NI-80	26'-6"	24'-7"	23'-3"	21'-6"	27'-1"	24'-10"	23'-3"	21'-6"
16"	NI-90x	27'-3"	25'-4"	24'-1"	22'-4"	27'-9"	25'-10"	24'-3"	22'-4"
	NI-60	27'-3"	24'-11"	23'-5"	21'-7"	27'-6"	24'-11"	23'-5"	21'-7"
	NI-70	28'-8"	26'-8"	25'-3"	23'-4"	29'-3"	26'-11"	25'-3"	23'-4"
	NI-80	29'-1"	27'-0"	25'-9"	23'-10"	29'-8"	27'-6"	25'-10"	23'-10"
	NI-90x	29'-11"	27'-10"	26'-6"	24'-10"	30'-6"	28'-5"	26'-11"	24'-10"

- Maximum clear span applicable to simple-span residential floor construction with a design live load of 40 psf and dead load of 30 psf. The ultimate limit states are based on the factored loads of 1.50L + 1.25D. The serviceability limit states include the consideration for floor vibration, a live load deflection limit of L/480 and a total load deflection limit of L/240.
- Spans are based on a composite floor with glued-nailed oriented strand board (OSB) sheathing with a minimum thickness of 3/4 inch for a joist spacing of 24 inches or less. The composite floor may include 1/2 inch gypsum ceiling and/or one row of blocking at mid-span with strapping. Strapping shall be minimum 1x4 inch strap applied to underside of joists at blocking line or 1/2 inch gypsum ceiling attached to joists.
- Minimum bearing length shall be 1-3/4 inches for the end bearings.
- Bearing stiffeners are not required when I-joists are used with the spans and spacings given in this table, except as required for hangers.
- This span chart is based on uniform loads. For applications with other than uniformly distributed loads, an engineering analysis may be required based on the use of the design properties. Tables are based on Limit States Design per CSA O86-09, NBC 2010, and OBC 2012.
- Joists shall be laterally supported at supports and continuously along the compression edge. Refer to technical documentation for installation guidelines and construction details. Nordic I-joists are listed in CCMC evaluation report 13032-R and APA Product Report PR-L274C.



# INSTALLATION GUIDE FOR RESIDENTIAL FLOORS



Distributed by:



The mark of responsible forestry

N-C301 / November 2014

## SAFETY AND CONSTRUCTION PRECAUTIONS



Do not walk on I-joists until fully fastened and braced, or serious injuries can result.



Never stack building materials over unsheathed I-joists. Once sheathed, do not over-stress I-joist with concentrated loads from building materials.


**WARNING**  
I-joists are not stable until completely installed, and will not carry any load until fully braced and sheathed.

### Avoid Accidents by Following these Important Guidelines:

1. Brace and nail each I-joist as it is installed, using hangers, blocking panels, rim board, and/or cross-bridging at joist ends. When I-joists are applied continuously over interior supports and a load-bearing wall is planned at that location, blocking will be required at the interior support.
  2. When the building is completed, the floor sheathing will provide lateral support for the top flanges of the I-joists. Until this sheathing is applied, temporary bracing, often called struts, or temporary sheathing must be applied to prevent I-joist rollover or buckling.
    - Temporary bracing or struts must be 1x4 inch minimum, at least 8 feet long and spaced no more than 8 feet on centre, and must be secured with a minimum of two 2-1/2" nails fastened to the top surface of each I-joist. Nail the bracing to a lateral restraint at the end of each bay. Lap ends of adjoining bracing over at least two I-joists.
    - Or, sheathing (temporary or permanent) can be nailed to the top flange of the first 4 feet of I-joists at the end of the bay.
  3. For cantilevered I-joists, brace top and bottom flanges, and brace ends with closure panels, rim board, or cross-bridging.
  4. Install and fully nail permanent sheathing to each I-joist before placing loads on the floor system. Then, stack building materials over beams or walls only.
  5. Never install a damaged I-joist.
- Improper storage or installation, failure to follow applicable building codes, failure to follow span ratings for Nordic I-joists, failure to follow allowable hole sizes and locations, or failure to use web stiffeners when required can result in serious accidents. Follow these installation guidelines carefully.

## STORAGE AND HANDLING GUIDELINES

1. Bundle wrap can be slippery when wet. Avoid walking on wrapped bundles.
2. Store, stack, and handle I-joists vertically and level only.
3. Always stack and handle I-joists in the upright position only.
4. Do not store I-joists in direct contact with the ground and/or flatwise.
5. Protect I-joists from weather, and use spacers to separate bundles.
6. Bundled units should be kept intact until time of installation.
7. When handling I-joists with a crane on the job site, take a few simple precautions to prevent damage to the I-joists and injury to your work crew.
  - Pick I-joists in bundles as shipped by the supplier.
  - Orient the bundles so that the webs of the I-joists are vertical.
  - Pick the bundles at the 5th points, using a spreader bar if necessary.
8. Do not handle I-joists in a horizontal orientation.
9. NEVER USE OR TRY TO REPAIR A DAMAGED I-JOIST.



1. Maximum clear spans applicable to simple-span or multiple-span residential floor construction with a design live load of 40 psf and dead load of 15 psf. The ultimate limit states are based on the factored loads of 1.50L + 1.25D. The serviceability limit states include the consideration for floor vibration and a live load deflection limit of L/480. For multiple-span applications, the load spans shall be 40% or more of the adjacent spans.
2. Spans are based on a composite floor with glued-ndled oriented strand board (OSB) sheathing with a minimum thickness of 5/8 inch for a joist spacing of 19.2 inches or less, or 3/4 inch for joist spacing of 24 inches. Adhesive shall meet the requirements given in CGS8-71.26 Standard. No concrete topping or bridging element was assumed. Increased spans may be achieved with the use of gypsum and/or a row of blocking at mid-span.
3. Minimum bearing length shall be 1-3/4 inches for the end bearings, and 3-1/2 inches for the intermediate bearings.
4. Bearing stiffeners are not required when joists are used with the spans and spacings given in this table, except as required for hangars.
5. This span chart is based on uniform loads. For applications with other than uniform loads, an engineering analysis may be required based on the use of the design properties.
6. Tables are based on Limit States Design per CAN/CSA O88-09 Standard, and NBC 2010.
7. SI units conversion: 1 inch = 25.4 mm  
1 foot = 0.305 m

**RECOMMENDATIONS:**

- A **beaming stiffener** is required in all engineered applications with factored reactions greater than shown in the *Table of Beaming Stiffeners* in the *Steel Construction Guide* (C101). The gap between the stiffener and the flange is at the top.
- A **beaming stiffener** is required when the I-joist is supported in a hanger and the sides of the hanger do not extend up to, and stiffen, the top flange. The gap between the stiffener and flange is at the top.
- A **load stiffener** is required at locations where a factored concentrated load greater than 2,370 lbs. is applied to the top flange between supports, or in the case of a cantilever, anywhere between the cantilever tip and the support. These values are for standard term load duration, and may be adjusted for other load durations as permitted by the code. The gap between the stiffener and the flange is at the bottom.

Joint Depth	Joint Series	Simple spans				Multiple spans			
		12"	16"	19.2"	24"	12"	16"	19.2"	24"
17/2/6	N7-0	15.1	14.2	13.9	13.3	6.3	15.4	14.10	14.7
	N7-1	16.1	15.2	14.8	14.9	17.5	16.5	15.0	15.5
	N7-2	16.9	15.4	14.10	14.1	17.7	16.7	15.0	16.1
	N7-3	17.1	16.1	15.5	15.7	18.7	17.4	16.9	17.0
	N7-4	17.3	16.3	15.8	15.9	18.10	17.6	16.1	17.10
17/2/6	N7-5	16.2	16.0	15.9	15.7	18.4	17.3	16.8	16.7
	N7-6	18.1	17.0	16.5	16.6	20.4	18.4	17.9	17.7
	N7-7	18.4	17.3	16.9	16.9	20.3	18.9	18.0	18.1
	N7-8	19.6	18.0	17.4	17.5	21.6	19.1	19.0	19.1
	N7-9	19.9	18.5	17.8	17.7	21.9	20.2	19.3	19.4
17/2/6	N7-10	20.2	18.7	17.10	17.10	22.5	20.9	19.8	19.9
	N7-11	20.4	18.9	17.1	18.0	22.5	20.9	19.9	19.1
	N7-12	20.1	18.7	17.10	17.1	22.2	20.4	19.8	19.4
	N7-13	20.5	18.1	17.1	18.2	22.7	20.7	20.0	20.1
	N7-14	21.7	20.0	19.1	19.2	23.10	22.5	21.5	21.5
16	N6-0	21.1	20.3	19.4	19.5	22.5	21.1	20.5	20.6
	N6-1	21.7	20.3	19.4	19.5	22.5	21.1	20.5	20.6
	N6-2	21.5	20.8	19.9	19.10	21.9	21.0	20.10	21.10
	N6-3	21.8	19.9	19.11	20.0	21.9	20.1	20.0	21.0
	N6-4	22.9	20.8	19.9	19.10	24.7	22.7	21.8	21.10
16	N6-5	23.6	21.9	21.1	21.2	26.5	24.5	23.3	23.6
	N6-6	24.5	22.6	21.4	21.6	26.5	24.5	23.3	23.6
	N6-7	24.8	22.9	21.5	21.6	26.1	24.10	23.9	24.1
	N6-8	24.8	22.9	21.5	21.10	27.3	25.9	24.0	24.1
	N6-9	24.8	22.9	21.5	21.10	27.3	25.9	24.0	24.1


1. Hangers shown illustrate the three most commonly used metal hangers to support I-joists.
2. All nailing must meet the hanger manufacturer's recommendations.
3. Hangers should be selected based on the joist depth, flange width and load capacity based on the maximum spans.
4. Web stiffeners are required when the sides of the hangers do not laterally brace the top flange of the I-joist.



The diagram illustrates a beam under a concentrated load, supported by stiffeners. Key features include:

- Flange width:** Indicated as  $2-1/2"$  or  $3-1/2"$ .
- Stiffener Spacing:** Labeled as "Approx.  $2'$ ".
- Gap:** A gap of  $1/8"-1/4"$  is shown between the stiffeners.
- Fasteners:** A note specifies "(4)  $2-1/2"$  nails, 3" nails required for I-beams with  $3-1/2"$  flange width".
- End Bearing:** The bottom section shows the "END BEARING (bearing stiffener)" with a "Tight Joint" and a "Gap" between the stiffener and the beam.

Flange Width	Web Stiffener Size Each Side of Web
2-1/2"	1" x 2-5/16" minimum width
3-1/2"	1-1/2" x 2-5/16" minimum width



# NORDIC I-JOIST SERIES

S-P-F No.2	19501 MSR	2100F MSR	1950I MSR	2100F MSR	2400I MSR	NFG lumber
33 pieces per unit	33 pieces Per unit	33 pieces per unit	23 pieces per unit	23 pieces per unit	23 pieces per unit	23 pieces per unit


Nordic Engineered Wood I-joists use only finger-joined track splices lumber in their flanges, ensuring consistent quality, superior strength, longer span carrying capacity.

SI units conversion: 1 inch = 25.4 mm

## INSTALLING NORDIC I-JOISTS


1. Before laying out floor system components, verify that I-joist flange widths match hanger widths. If not, contact your supplier.
2. Except for cutting to length, I-joist flanges should **never** be cut, drilled, or notched.
3. Install I-joists so that top and bottom flanges are within 1/2 inch of true vertical alignment.
4. I-joists must be anchored securely to supports before floor sheathing is attached, and supports for multiple-span joists must be level.
5. Minimum bearing lengths: 1-3/4 inches for end bearings and 3-1/2 inches for intermediate bearings.
6. When using hangers, seat I-joists firmly in hanger bottoms to minimize settlement.
7. Leave a 1/16-inch gap between the I-joist end and a header.
8. Concentrated loads greater than those that can normally be expected in residential construction should **only** be applied to the top surface of the top flange. Normal concentrated loads include track lighting fixtures, audio equipment and security cameras. Never suspend unusual or heavy loads from the I-joist's bottom flange. Whenever possible, suspend all concentrated loads from the top of the I-joist. Or, attach the load to blocking that has been securely fastened to the I-joist webs.
9. Never install I-joists where they will be permanently exposed to weather, or where they will remain in direct contact with concrete or masonry.
10. Restrain ends of floor joists to prevent rollover. Use rim board, rim joists or I-joist blocking panels.
11. For I-joists installed over and beneath bearing walls, use full depth blocking panels, rim board, or squash blocks (cripple members) to transfer gravity loads through the floor system to the wall or foundation below.
12. Due to shrinkage, common framing lumber set on edge **may never** be used as blocking or rim boards. I-joist blocking panels or other engineered wood products – such as rim board – must be cut to fit between the I-joists, and an I-joist-compatible depth selected.
13. Provide permanent lateral support of the bottom flange of all I-joists at interior supports of multiple-span joists. Similarly, support the bottom flange of all cantilevered I-joists at the end support next to the cantilever extension. In the completed structure, the gypsum wallboard ceiling provides this lateral support. Until the final finished ceiling is applied, temporary bracing or struts must be used.
14. If square-edge panels are used, edges must be supported between I-joists with 2x4 blocking. Glue panels to blocking to minimize squeaks. Blocking is not required under structural finish flooring, such as wood strip flooring, or if a separate underlayment layer is installed.
15. Nail spacing: Space nails installed to the flange's top face in accordance with the applicable building code requirements or approved building plans.

2015-04-16



Blocking Panel or Rim Joist	Maximum Factored Uniform Vertical Load* (pl)
NI I-joists	3,300

\*The uniform vertical load is limited to a joist depth of 16 inches or less and is based on standard term load duration. It shall not be used in the design of a bending member, such as joist, header, or rafter. For concentrated vertical load transfer, see detail 1d.




Blocking Panel or Rim Joist	Maximum Factored Uniform Vertical Load* (pl)
1-1/8" Rim Board Plus	8,090



\*The uniform vertical load is limited to a rim board depth of 16 inches or less and is based on standard term load duration. It shall not be used in the design of a bending member, such as joist, header, or rafter. For concentrated vertical load transfer, see detail 1d.

FIGURE 1  
TYPICAL NORDIC I-JOIST FLOOR FRAMING AND CONSTRUCTION DETAILS

Some framing requirements such as erection bracing and blocking panels have been omitted for clarity.
















All nails shown in the above details are assumed to be common wire nails unless otherwise noted. 3" (0.122" dia.) common spiral nails may be substituted for 2-1/2" (0.128" dia.) common wire nails. Framing lumber assumed to be Spruce-Pine-Fir No. 2 or better. Individual components not shown to scale for clarity.



Pair of Squash Blocks	Maximum Factored Vertical per Pair of Squash Blocks (lbs)
2x Lumber	5,500
1-1/8" Rim Board Plus	4,300

Provide lateral bracing per detail 1a, 1b, or 1c



**Notes:**

- Support back of I-joist web during nailing to prevent damage to web/flange connection.
- Leave a 1/8 to 1/4-inch gap between top of filler block and bottom of top I-joist flange.
- Filler block is required between joists for full length of span.
- Nail joists together with two rows of 3" nails at 12 inches o.c. (clinched when possible) on each side of the double I-joist. Total of four nails per foot required. If nails are clinched, only two nails per foot are required.
- The maximum factored load that may be applied to one side of the double joist using this detail is 860 lb/ft. Verify double I-joist capacity.

**Notes:**

- Support back of I-joist web during nailing to prevent damage to web/flange connection.
- Leave a 1/8 to 1/4-inch gap between top of filler block and bottom of top I-joist flange.
- Filler block is required between joists for full length of span.
- Nail joists together with two rows of 3" nails at 12 inches o.c. (clinched when possible) on each side of the double I-joist. Total of four nails per foot required. If nails are clinched, only two nails per foot are required.
- The maximum factored load that may be applied to one side of the double joist using this detail is 860 lb/ft. Verify double I-joist capacity.

**Notes:**

- Support back of I-joist web during nailing to prevent damage to web/flange connection.
- Leave a 1/8 to 1/4-inch gap between top of filler block and bottom of top I-joist flange.
- Filler block is required between joists for full length of span.
- Nail joists together with two rows of 3" nails at 12 inches o.c. (clinched when possible) on each side of the double I-joist. Total of four nails per foot required. If nails are clinched, only two nails per foot are required.
- The maximum factored load that may be applied to one side of the double joist using this detail is 860 lb/ft. Verify double I-joist capacity.

**Notes:**

- Support back of I-joist web during nailing to prevent damage to web/flange connection.
- Leave a 1/8 to 1/4-inch gap between top of filler block and bottom of top I-joist flange.
- Filler block is required between joists for full length of span.
- Nail joists together with two rows of 3" nails at 12 inches o.c. (clinched when possible) on each side of the double I-joist. Total of four nails per foot required. If nails are clinched, only two nails per foot are required.
- The maximum factored load that may be applied to one side of the double joist using this detail is 860 lb/ft. Verify double I-joist capacity.

1p




**Notes:**

**FILLER BLOCK REQUIREMENTS FOR DOUBLE I-JOIST CONSTRUCTION**

Flange Size	Joist Depth	Filler Block Size
2-1/2" x 1-1/2"	9-1/2" x 11-7/8" x 14"	2-1/8" x 6" x 8"
2-1/2" x 1-1/2"	11-7/8" x 14"	2-1/8" x 8" x 10"
3-1/2" x 1-1/2"	9-1/2" x 11-7/8" x 14"	3" x 6" x 8"
3-1/2" x 1-1/2"	11-7/8" x 14"	3" x 8" x 10"
3-1/2" x 2"	11-7/8" x 14"	3" x 7" x 11"

1r

1s



**Notes:**

- Support back of I-joist web during nailing to prevent damage to web/flange connection.
- Leave a 1/8 to 1/4-inch gap between top of filler block and bottom of top I-joist flange.
- Filler block is required between joists for full length of span.
- Nail joists together with two rows of 3" nails at 12 inches o.c. (clinched when possible) on each side of the double I-joist. Total of four nails per foot required. If nails are clinched, only two nails per foot are required.
- The maximum factored load that may be applied to one side of the double joist using this detail is 860 lb/ft. Verify double I-joist capacity.

**Optional:** Minimum 1x4 inch strip applied to underside of joist at blocking line or 1/2 inch minimum gypsum ceiling attached to underside of joists.

**Notes:**


- In some local codes, blocking is prescriptively required in the first joist space (or first and second joist space) next to the starter joist. Where required, see local code requirements for spacing of the blocking.
- All nails are common spiral in this detail.

Flange Width	Material Thickness Required*	Minimum Depth**
2-1/2"	1"	5-1/2"
3-1/2"	1-1/2"	7-1/4"

\* Minimum grade for backer block material shall be S-P-F No. 2 or better for solid sawn lumber and wood structural panels conforming to CAN/CSA-O325 or CAN/CSA-Q437 Standard.

\*\* For face-mount hangers use net joist depth minus 3-1/4" for joists with 1-1/2" thick flanges. For 2" thick flanges use net depth minus 4-1/4".


For hanger capacity see hanger manufacturer's recommendations. Verify double I-joist capacity to support concentrated loads.




2015-04-16

## CANTILEVER DETAILS FOR BALCONIES (NO WALL LOAD)

### (30) I-JOIST CANTILEVER DETAIL FOR BALCONIES (No Wall Load)




### (35) LUMBER CANTILEVER DETAIL FOR BALCONIES (No Wall Load)




## CANTILEVER DETAILS FOR VERTICAL BUILDING OFFSET (CONCENTRATED WALL LOAD)

### (40) Method 1 — SHEATHING REINFORCEMENT ONE SIDE



### Method 2 — SHEATHING REINFORCEMENT TWO SIDES

- Use same installation as Method 1 but reinforce both sides of I-joist with sheathing.
- Use nailing pattern shown for Method 1 with opposite face nailing offset by 3".



Note: Canadian softwood plywood sheathing or equivalent (minimum thickness 3/4") required on sides of joist. Depth shall match the full height of the joist. Nail with 2-1/2" nails at 6" o.c., top and bottom flange. Install with face grain horizontal. Attach I-joist to plate at all supports per detail 1b. Verify reinforced I-joist capacity.

### (45) Alternate Method 2 — DOUBLE I-JOIST






FIGURE 4 (continued)




## CANTILEVER REINFORCEMENT METHODS ALLOWED

JOIST DEPTH (in.)	ROOF TRUSS		ROOF LOADING (UNFACTORED)			
	LL = 30 psf, DL = 15 psf	LL = 40 psf, DL = 15 psf	LL = 50 psf, DL = 15 psf	LL = 60 psf, DL = 15 psf	LL = 70 psf, DL = 15 psf	LL = 80 psf, DL = 15 psf
12	12	12	12	12	12	12
14	14	14	14	14	14	14
16	16	16	16	16	16	16
18	18	18	18	18	18	18
20	20	20	20	20	20	20
22	22	22	22	22	22	22
24	24	24	24	24	24	24
26	26	26	26	26	26	26
28	28	28	28	28	28	28
30	30	30	30	30	30	30
32	32	32	32	32	32	32
34	34	34	34	34	34	34
36	36	36	36	36	36	36
38	38	38	38	38	38	38
40	40	40	40	40	40	40
42	42	42	42	42	42	42
44	44	44	44	44	44	44
46	46	46	46	46	46	46
48	48	48	48	48	48	48
50	50	50	50	50	50	50
52	52	52	52	52	52	52
54	54	54	54	54	54	54
56	56	56	56	56	56	56
58	58	58	58	58	58	58
60	60	60	60	60	60	60

1. N = No reinforcement required.
2. NI = No reinforcement with 3/4" wood structural panel on one side only.
3. NI reinforced with 3/4" wood structural panel on both sides, or double I-joist.
4. For larger openings, or multiple 3'-0" wide openings spaced less than 6'-0" o.c., additional joists beneath the opening's cripple studs may be required.
5. Table applies to joists 12" to 24" o.c. that meet the floor span requirements for a design live load of 40 psf and dead load of 15 psf, and a live load deflection limit of L/480. Use 12" o.c. requirements for lesser spacing.
6. For conventional roof construction using a ridge beam, the Roof Truss Span column above is equivalent to the distance between the supporting wall and the ridge beam. When the roof is framed using a ridge board, the Roof Truss Span is equivalent to the distance between the supporting walls as if a truss is used.
7. Cantilevered joist supporting girder trusses or roof beams may require additional reinforcing.

### **RULES FOR CUTTING HOLES AND DUCT CHASE OPENINGS:**

- FIGURE 7**  
**FIELD-CUT HOLE LOCATOR**

[illegible]

## OPTIONAL:

$$D_{\text{reduced}} = \frac{I_{\text{actual}}}{x} D$$

Where:  $\text{SAF}_{\text{reduced}}$

**Lactual**

SAF  
D

Span Adjustment Factor given in this table.

The minimum distance from the inside face of any support to centre of hole from this table if  $\frac{\text{hole dia}}{\text{SAF}}$  is greater than 1, use 1 in the above calculation for  $\frac{\text{hole dia}}{\text{SAF}}$ .

SAF

2015-04-16

Joist Depth	Joist Series	Minimum distance from inside face of any support to centre of opening (ft.in.)											
		8	10	12	14	16	18	20	22	24			
9 1/2 in.	1	5 1/2	5 5/8	5 7/8	6 1/8	6 3/8	6 5/8	6 7/8	7 1/8	7 3/8	7 5/8	7 7/8	
	2	5 1/2	5 5/8	5 7/8	6 1/8	6 3/8	6 5/8	6 7/8	7 1/8	7 3/8	7 5/8	7 7/8	
	3	5 1/2	5 5/8	5 7/8	6 1/8	6 3/8	6 5/8	6 7/8	7 1/8	7 3/8	7 5/8	7 7/8	
	4	5 1/2	5 5/8	5 7/8	6 1/8	6 3/8	6 5/8	6 7/8	7 1/8	7 3/8	7 5/8	7 7/8	
	5	5 1/2	5 5/8	5 7/8	6 1/8	6 3/8	6 5/8	6 7/8	7 1/8	7 3/8	7 5/8	7 7/8	
	6	5 1/2	5 5/8	5 7/8	6 1/8	6 3/8	6 5/8	6 7/8	7 1/8	7 3/8	7 5/8	7 7/8	
	7	5 1/2	5 5/8	5 7/8	6 1/8	6 3/8	6 5/8	6 7/8	7 1/8	7 3/8	7 5/8	7 7/8	
	8	5 1/2	5 5/8	5 7/8	6 1/8	6 3/8	6 5/8	6 7/8	7 1/8	7 3/8	7 5/8	7 7/8	
	9	5 1/2	5 5/8	5 7/8	6 1/8	6 3/8	6 5/8	6 7/8	7 1/8	7 3/8	7 5/8	7 7/8	
	10	5 1/2	5 5/8	5 7/8	6 1/8	6 3/8	6 5/8	6 7/8	7 1/8	7 3/8	7 5/8	7 7/8	
11 3/4 in.	1	5 1/2	5 5/8	5 7/8	6 1/8	6 3/8	6 5/8	6 7/8	7 1/8	7 3/8	7 5/8	7 7/8	
	2	5 1/2	5 5/8	5 7/8	6 1/8	6 3/8	6 5/8	6 7/8	7 1/8	7 3/8	7 5/8	7 7/8	
	3	5 1/2	5 5/8	5 7/8	6 1/8	6 3/8	6 5/8	6 7/8	7 1/8	7 3/8	7 5/8	7 7/8	
	4	5 1/2	5 5/8	5 7/8	6 1/8	6 3/8	6 5/8	6 7/8	7 1/8	7 3/8	7 5/8	7 7/8	
	5	5 1/2	5 5/8	5 7/8	6 1/8	6 3/8	6 5/8	6 7/8	7 1/8	7 3/8	7 5/8	7 7/8	
	6	5 1/2	5 5/8	5 7/8	6 1/8	6 3/8	6 5/8	6 7/8	7 1/8	7 3/8	7 5/8	7 7/8	
	7	5 1/2	5 5/8	5 7/8	6 1/8	6 3/8	6 5/8	6 7/8	7 1/8	7 3/8	7 5/8	7 7/8	
	8	5 1/2	5 5/8	5 7/8	6 1/8	6 3/8	6 5/8	6 7/8	7 1/8	7 3/8	7 5/8	7 7/8	
	9	5 1/2	5 5/8	5 7/8	6 1/8	6 3/8	6 5/8	6 7/8	7 1/8	7 3/8	7 5/8	7 7/8	
	10	5 1/2	5 5/8	5 7/8	6 1/8	6 3/8	6 5/8	6 7/8	7 1/8	7 3/8	7 5/8	7 7/8	
13 1/4 in.	1	5 1/2	5 5/8	5 7/8	6 1/8	6 3/8	6 5/8	6 7/8	7 1/8	7 3/8	7 5/8	7 7/8	
	2	5 1/2	5 5/8	5 7/8	6 1/8	6 3/8	6 5/8	6 7/8	7 1/8	7 3/8	7 5/8	7 7/8	
	3	5 1/2	5 5/8	5 7/8	6 1/8	6 3/8	6 5/8	6 7/8	7 1/8	7 3/8	7 5/8	7 7/8	
	4	5 1/2	5 5/8	5 7/8	6 1/8	6 3/8	6 5/8	6 7/8	7 1/8	7 3/8	7 5/8	7 7/8	
	5	5 1/2	5 5/8	5 7/8	6 1/8	6 3/8	6 5/8	6 7/8	7 1/8	7 3/8	7 5/8	7 7/8	
	6	5 1/2	5 5/8	5 7/8	6 1/8	6 3/8	6 5/8	6 7/8	7 1/8	7 3/8	7 5/8	7 7/8	
	7	5 1/2	5 5/8	5 7/8	6 1/8	6 3/8	6 5/8	6 7/8	7 1/8	7 3/8	7 5/8	7 7/8	
	8	5 1/2	5 5/8	5 7/8	6 1/8	6 3/8	6 5/8	6 7/8	7 1/8	7 3/8	7 5/8	7 7/8	
	9	5 1/2	5 5/8	5 7/8	6 1/8	6 3/8	6 5/8	6 7/8	7 1/8	7 3/8	7		


1. Above table may be used for 4-foot spacing of 3/4 inches on centre or less.
2. Duct chase spanning location distance is measured from inside face of supports to centre of opening.
3. The above table is based on simple-span joists only. For other applications, contact your local distributor.
4. Distances are based on uniformly loaded floor joists that meet the span requirements for a design load of 40 psf and dead load of 15 psf, and a live load deflection limit of 1/480. For other applications, contact your local distributor.

# BRICK CANTILEVER DETAILS FOR VERTICAL BUILDING OFFSET (CONCENTRATED WALL LOAD)

## 5a SHEATHING REINFORCEMENT

Provide full depth blocking between joists over support (not shown)


Note: Canadian softwood plywood sheathing or equivalent (minimum thickness 3/4") required on sides of joist. Depth shall match the full height of the joist. Nail with 2-1/2" nails at 6" o.c., top and bottom flange. Install with face grain horizontal. Attach I-joist to plate at all supports per detail 1b. Verify reinforced I-joist capacity.



## 5b SET-BACK DETAIL


Rim board or wood structural panel closure (3/4" minimum thickness), attach per detail 1b.

Notes:  
- Provide full depth blocking between joists over support (not shown for clarity)  
- Attach I-joist to plate at all supports per detail 1b.  
- 3-1/2" minimum I-joist bearing required.





## 5c SET-BACK CONNECTION

Vertical solid sawn blocks (2x6 S-P-F No. 2 or better) nailed through joist web and web of girder using 2-1/2" nails.



Notes:  
- Verify girder joist capacity if the back span exceeds the joist spacing.  
- Attach double I-joist per detail 1p, if required.

FIGURE 5 (continued)



For hip roofs with the jack trusses running parallel to the cantilevered floor joists, the I-joist reinforcement requirements for a span of 26 ft. shall be permitted to be used.

## BRICK CANTILEVER REINFORCEMENT METHODS ALLOWED

JOIST DEPTH (in.)	ROOF TRUSS SPAN (ft)	ROOF LOADING (UNFACTORED)				LL = 50 psf, DL = 15 psf			
		LL = 30 psf, DL = 15 psf	JOIST SPACING (in.)	LL = 40 psf, DL = 15 psf	JOIST SPACING (in.)	LL = 50 psf, DL = 15 psf	JOIST SPACING (in.)	LL = 50 psf, DL = 15 psf	JOIST SPACING (in.)
16"	12	1	12	1	12	1	12	1	12
16"	16	1	16	1	16	1	16	1	16
16"	19.2	1	19.2	1	19.2	1	19.2	1	19.2
16"	24	1	24	1	24	1	24	1	24
14"	12	1	12	1	12	1	12	1	12
14"	16	1	16	1	16	1	16	1	16
14"	19.2	1	19.2	1	19.2	1	19.2	1	19.2
14"	24	1	24	1	24	1	24	1	24
12"	12	1	12	1	12	1	12	1	12
12"	16	1	16	1	16	1	16	1	16
12"	19.2	1	19.2	1	19.2	1	19.2	1	19.2
12"	24	1	24	1	24	1	24	1	24
10 7/8"	12	1	12	1	12	1	12	1	12
10 7/8"	16	1	16	1	16	1	16	1	16
10 7/8"	19.2	1	19.2	1	19.2	1	19.2	1	19.2
10 7/8"	24	1	24	1	24	1	24	1	24
9 1/2"	12	1	12	1	12	1	12	1	12
9 1/2"	16	1	16	1	16	1	16	1	16
9 1/2"	19.2	1	19.2	1	19.2	1	19.2	1	19.2
9 1/2"	24	1	24	1	24	1	24	1	24
8"	12	1	12	1	12	1	12	1	12
8"	16	1	16	1	16	1	16	1	16
8"	19.2	1	19.2	1	19.2	1	19.2	1	19.2
8"	24	1	24	1	24	1	24	1	24
6"	12	1	12	1	12	1	12	1	12
6"	16	1	16	1	16	1	16	1	16
6"	19.2	1	19.2	1	19.2	1	19.2	1	19.2
6"	24	1	24	1	24	1	24	1	24

1. N = No reinforcement required.
2. N = NI reinforced with 3/4" wood structural panel on one side only.
3. N = NI reinforced with 3/4" wood structural panel on both sides, or double I-joist.
4. For larger openings, or multiple 3'-0" width openings spaced less than 6'-0" o.c., additional joists beneath the opening's cripple studs may be required.
5. Table applies to joists 12" to 24" o.c. that meet the floor span requirements for a design live load of 40 psf and dead load of 15 psf, and a live load deflection limit of L/480. Use 12" o.c. requirements for lesser spacing.
6. For conventional roof construction using a ridge beam, the Roof Truss Span column above is equivalent to the distance between the supporting wall and the ridge beam.
7. When the roof is framed using a ridge beam, the Roof Truss Span is equivalent to the distance between the supporting walls as if a truss is used.
8. Cantilevered joists supporting girder trusses or roof beams may require additional reinforcing.

# INSTALLING THE GLUED FLOOR SYSTEM

1. Wipe any mud, dirt, water, or ice from I-joist flanges before gluing.
2. Snap a chalk line across the I-joists four feet in from the wall for panel edge alignment and as a boundary for spreading glue.
3. Spread only enough glue to lay one or two panels at a time, or follow specific recommendations from the glue manufacturer.
4. Lay the first panel with tongue side to the wall, and nail in place. This protects the tongue of the next panel from damage when topped into place with a block and sledgehammer.
5. Apply a continuous line of glue (about 1/4-inch diameter) to the top flange of a single I-joist. Apply glue in a winding pattern on wide areas, such as with double I-joists.
6. Apply two lines of glue on I-joists where panel ends butt to assure proper gluing of each end.
7. After the first row of panels is in place, spread glue in the groove of one or two panels at a time before laying the next row. Glue line may be continuous or spaced, but avoid squeeze-out by applying a thinner line (1/8 inch) than used on I-joist flanges.
8. Top the second row of panels into place, using a block to protect groove edges.
9. Stagger end joints in each succeeding row of panels. A 1/8-inch space between all end joints and 1/8-inch at all edges, including T&G edges, is recommended. (Use a spacer tool or an 2-1/2" common nail to assure accurate and consistent spacing.)
10. Complete all nailing of each panel before glue sets. Check the manufacturer's recommendations for cure time. (Warm weather accelerates glue setting.) Use 2" ring- or screw-shank nails for panels 3/4-inch thick or less, and 2-1/2" ring- or screw-shank nails for thicker panels. Space nails per the table below. Closer nail spacing may be required by some codes, or for diaphragm construction. The finished deck can be walked on right away and will carry construction loads without damage to the glue bond.

## FASTENERS FOR SHEATHING AND SUBFLOORING(1)

Maximum Joist Spacing (in.)	Minimum Panel Thickness (in.)	Common Wire or Spiral Nails	Nail Size and Type	Ring Thread or Screws	Staples	Maximum Spacing of Fasteners
16	5/8	2"	1-3/4"	2"	6"	12"
20	5/8	2"	1-3/4"	2"	6"	12"
24	3/4	2"	1-3/4"	2"	6"	12"


1. Fasteners of sheathing and subflooring shall conform to the above table.
2. Staples shall not be less than 1/16-inch in diameter or thickness, with not less than a 3/8-inch crown driven with the crown parallel to framing.
3. Flooring screws shall not be less than 1/8-inch in diameter.
4. Special conditions may impose heavy traffic and concentrated loads that require construction in excess of the minimums shown.
5. Use only adhesives conforming to CAN/CGSB-71.26 Standard, Adhesives for Field-Gluing Plywood to Lumber Framing for Floor System, applied in accordance with the manufacturer's recommendations. If OSB panels with sealed surfaces and edges are to be used, use only solvent-based glues, check with panel manufacturer.

Ref.: NRC-CNRC, National Building Code of Canada 2010, Table 9.23.3.5.


**IMPORTANT NOTE:**  
Floor sheathing must be field glued to the I-joist flanges in order to achieve the maximum spans shown in this document. If sheathing is nailed only, I-joist spans must be verified with your local distributor.

# RIM BOARD INSTALLATION DETAILS


## 8a ATTACHMENT DETAILS WHERE RIM BOARDS ABOUT



## 8b TOE-NAIL CONNECTION AT RIM BOARD



## 8c 2x LEDGER TO RIM BOARD ATTACHMENT DETAIL




2015-04-16


## PRODUCT WARRANTY

Champion Chalklines guarantees that its assemblies with our specifications. Your products are free from manufacturing defects in material and workmanship.

Furthermore, Champion Chalklines warrants that our products when utilized in accordance with our handling and installation instructions will meet or exceed our specifications for the lifetime of the structure.



LVL HEADER AND CONVENTIONAL LUMBER NAILING DETAILS		
DETAIL NUMBER	NUMBER OF ROWS	SPACING (INCHES o/c) "d"
A	2	12
B	2	8
C	2	6
D	2	4
1A	3	12
1B	3	8
1C	3	6
1D	3	4
2A	4	12
2B	4	8
2C	4	6
2D	4	4
3A	5	12
3B	5	8
3C	5	6
3D	5	4
4A	6	12
4B	6	8
4C	6	6
4D	6	4



### NOTES:

- (1) MINIMUM LUMBER EDGE DISTANCE "a" = 1"
- (2) MINIMUM LUMBER END DISTANCE "b" = 2"
- (3) MINIMUM NAIL ROW SPACING "c" = 2"
- (4) STAGGER NAILS "d/2" BETWEEN PLYS FOR MULTI-PLY MEMBERS (3 PLY OR MORE)
- (5) ALL NAILS ARE 3-1/2" ARDOX SPIRAL NAILS
- (6) DO NOT USE AIR-DRIVEN NAILS



DWG NO TAMN1001.14

STRUCTURAL

COMPONENT ONLY

TO BE USED ONLY  
WITH BEAM CALCS  
BEARING THE  
STAMP BELOWS

PROVIDE NAILING  
DETAIL N° X SEE  
DWG #TAMN1001-14