

ENGINEERING NOTE PAGE (ENP-1)
PLEASE READ PRIOR TO INSTALLATION

NE0618-006
GREEN YORK HOMES - GRANELLI
HOME CORP - LIANA 3 ELEV 2

RESPONSIBILITIES

THIS DESIGN IS FOR AN INDIVIDUAL BUILDING COMPONENT AND HAS BEEN BASED ON INFORMATION PROVIDED BY THE DESIGN OFFICE OF KOTT LUMBER. THE UNDERSIGNED ENGINEER DISCLAIMS ANY RESPONSIBILITY FOR DAMAGES AS A RESULT OF FAULTY OR INCORRECT INFORMATION, SPECIFICATION AND/OR DESIGNS FURNISHED TO THE ENGINEER. THE UNDERSIGNED ENGINEER IS ONLY RESPONSIBLE FOR THE STRUCTURAL INTEGRITY OF THIS BUILDING COMPONENT FOR THE CONDITIONS AND LOADS SHOWN ON THIS DRAWING. THE STRUCTURAL INTEGRITY OF THE BUILDING AND THE VERIFICATION OF THE DIMENSIONS AND THE DESIGN LOADS USED ARE THE RESPONSIBILITY OF THE BUILDING DESIGNER.

TRUSSES ARE DESIGNED IN CONFORMANCE WITH THE RELEVANT SECTIONS OF THE NATIONAL BUILDING CODE OF CANADA OR THE CANADIAN CODE FOR FARM BUILDINGS, WHICHEVER APPLIES TO THE BUILDING TYPE INDICATED ON THE DRAWING

IT IS THE RESPONSIBILITY OF KOTT LUMBER TO ENSURE THAT TRUSSES ARE MANUFACTURED IN CONFORMANCE WITH THESE DESIGNS AND WITH THE SPECIFICATIONS OUTLINED BELOW. THE UNDERSIGNED ENGINEER IS NOT RESPONSIBLE FOR QUALITY CONTROL IN THE TRUSS MANUFACTURING PLANT.

USE AND OCCUPANCY

- The building is of the type indicated on the drawing

LOADING

- The truss loading intensity and distribution as well as load transfer mechanism is that indicated on the drawing
- No buildings, trees, parapets or other projections higher than the roof for which the trusses are used are located within a distance less than ten (10) times the difference in height, or five metres (16 ft) whichever is greater, unless the drawing indicates that the snow drifting has been taken into account

HANDLING, INSTALLATION AND BRACING

- The trusses must be handled and installed by a qualified professional as per the supplied document titled *Information for Truss Installers* and the BCSI-B1 and BCSI-B3 Summary Sheets
- The compression chords are laterally braced by continuous rigid diaphragm sheathing or as specified on the drawing
- Temporary and permanent bracing must be installed as indicated on the truss drawing and according to the BCSI-B1 and BCSI-B3 Summary Sheets. Bracing for the lateral stability of the truss is to be provided by the building designer
- **It is recommended that a Professional Engineer's advice be obtained for the bracing of trusses spanning more than 12.37m (40'-7")**

SUPPORTS

- The trusses are to be supported at the bearing points indicated and anchored to the supports where considered necessary by the designer of the overall structure
- Bearing sizes shown are the minimum required to prevent crushing of the truss members and do not necessarily take into account stability of the overall building structure
- Elevation of bearings must be carefully checked and shimmed to alignment for solid bearings
- Adequate wood truss bearing is the responsibility of the building designer.

DIMENSIONS


- Geometry of the truss and dimensions indicated on the drawing are identical to those of the installed truss.

Layout based on plans provided by
Jardin Design Group Inc.
Revision #2 dated May 22, 2018

THIS CERTIFICATION IS FOR THE ENGINEERING REVIEW OF STRUCTURAL COMPONENTS SHOWN ON THIS DRAWING AND IS LIMITED TO THE COMPONENTS SUPPLIED BY KOTT LUMBER FOR THE LOADS AND CONDITIONS SHOWN ON THE CALCULATION PAGE OF EACH COMPONENT. THE PLACEMENT OF THESE COMPONENTS ON THIS LAYOUT IS SHOWN FOR REFERENCE ONLY. ROOF TRUSSES MUST BE INSTALLED ACCORDING TO MANUFACTURER'S GUIDELINES AT 24" C/C UNLESS NOTED OTHERWISE. CONVENTIONAL FRAMING SHOWN ON THE LAYOUT MUST BE DESIGNED AND APPROVED BY THE PROJECT ENGINEER. TEMPORARY AND PERMANENT BRACINGS OF THE ROOF AND BUILDING ARE THE RESPONSIBILITY OF THE PROJECT ENGINEER AND TO CONFORM TO BCSI GUIDELINES.



ENG.JOB:NE0618-006



ROOF TRUSS LAYOUT



CONVENTIONAL
FRAMING BY OTHERS

HANGER LEGEND

X - LUS24
- HGUS26

O - LJS26DS
% - HGUS26-2

DESIGN CRITERIA
SPECIFIED LOADS:
TOP CH. LL = 23.3 psf
DL = 3.0 psf
BOT CH. LL = 0.0 psf
DL = 7.0 psf
TOTAL LOAD = 33.3 psf

SPACING @ 24" CENTERS,
THIS TRUSS SYSTEM IS DESIGN FOR RESIDENTIAL
OR SMALL BUILDING REQUIREMENTS OF
PART 9, NBC 2010


THIS DESIGN COMPLIES WITH PART 9 OF OBC 2012,
BCBC 2012, ABC 2012, CSA 086-09, TPIC 2011

ALLOWABLE DEFLECTION OF EACH COMPONENT = L/360

Model:	LIANA 3 ELE 2
Customer:	GREEN YORK HOMES
Project:	GRANELLI HOME
Location:	BRAMPTON, ON
Drawn By:	DM
Date:	5/31/2018

SIZE AND LOCATION OF CONVENTIONAL FRAMING IS APPROXIMATE. ALL AREAS MAY NOT BE SHOWN. REFER TO ARCHITECTURAL PLANS FOR DETAILS.

ALL CONVENTIONAL FRAMING TO CONFORM WITH PART 9 OF THE O.B.C RAFTER THAT CROSS MEET OVER TRUSSES TO BE 2X4 SPF @ 24" O/C WITH 2X4 VERT POST TO THE TRUSS BELOW EA CROSS PT. VERT POS. THAN 6' TO HAVE A LATERAL BRACING SO THAT THE DISTANCE BETEN PT & VERT ROWS OF BRACING DOES NOT EXCEED 6'



										TOTAL WEIGHT = 130 lb	
										[M]	
LUMBER N. L. G. A. RULES				DIMENSIONS, SUPPORTS AND LOADINGS SPECIFIED BY FABRICATOR TO BE VERIFIED BY BUILDING DESIGNER						DESIGN CRITERIA	
CHORDS		SIZE	LUMBER	DESCR.	BEARINGS						
					FACTORED		MAXIMUM FACTORED	INPUT	REQRD		
					GROSS REACTION		GROSS REACTION	BRG	BRG		
A - D	2x4	DRY	No.2	SPF	JT	VERT	HORZ	DOWN	HORZ	UPLIFT	IN-SX
D - G	2x4	DRY	No.2	SPF	R	2248	0	2248	0	0	5-8
G - J	2x4	DRY	No.2	SPF	K	2499	0	2499	0	0	5-8
R - B	2x4	DRY	No.2	SPF							
K - I	2x4	DRY	No.2	SPF							
R - N	2x6	DRY	No.2	SPF							
N - K	2x6	DRY	No.2	SPF							
ALL WEBS		2x3	DRY	No.2	UNFACTORED REACTIONS						
EXCEPT				SPF							
					1ST LCASE		MAX./MIN. COMPONENT REACTIONS				
					JT	COMBINED	SNOW	LIVE	PERM.LIVE	WIND	DEAD
					R	1576	1110 / 0	0 / 0	0 / 0	0 / 0	466 / 0
					K	1755	1218 / 0	0 / 0	0 / 0	0 / 0	538 / 0

BEARING MATERIAL TO BE SPF NO.2 OR BETTER AT JOINT(S) R, K							SPACING = 24.0 IN. C/C																																																																																																																																																																																																																																																																																															
PLATES (table is in inches) <table><tr><th>JT</th><th>TYPE</th><th>PLATES</th><th>W</th><th>LEN</th><th>Y</th><th>X</th></tr><tr><td>B</td><td>TMVW-t</td><td>MT20</td><td>6.0</td><td>6.0</td><td>1.75</td><td>3.00</td></tr><tr><td>C</td><td>TMWW-t</td><td>MT20</td><td>3.0</td><td>4.0</td><td>1.50</td><td>1.50</td></tr><tr><td>D</td><td>TTWW+m</td><td>MT20</td><td>6.0</td><td>8.0</td><td>Edge</td><td>2.00</td></tr><tr><td>E</td><td>TMW+w</td><td>MT20</td><td>2.0</td><td>4.0</td><td></td><td></td></tr><tr><td>F</td><td>TMWW-t</td><td>MT20</td><td>3.0</td><td>4.0</td><td></td><td></td></tr><tr><td>G</td><td>TTWW+m</td><td>MT20</td><td>6.0</td><td>8.0</td><td>2.25</td><td>2.25</td></tr><tr><td>H</td><td>TMWW-t</td><td>MT20</td><td>3.0</td><td>4.0</td><td>1.50</td><td>1.50</td></tr><tr><td>I</td><td>TMVW-p</td><td>MT20</td><td>6.0</td><td>6.0</td><td>2.25</td><td>2.50</td></tr><tr><td>K</td><td>BMV1+p</td><td>MT20</td><td>3.0</td><td>4.0</td><td>2.00</td><td>0.25</td></tr><tr><td>L</td><td>BMWW-t</td><td>MT20</td><td>4.0</td><td>6.0</td><td>2.00</td><td>1.50</td></tr><tr><td>M</td><td>BMWW+t</td><td>MT20</td><td>3.0</td><td>4.0</td><td></td><td></td></tr><tr><td>N</td><td>BSWW+I</td><td>MT20</td><td>5.0</td><td>8.0</td><td>5.00</td><td>2.25</td></tr><tr><td>O</td><td>BMWW-t</td><td>MT20</td><td>5.0</td><td>8.0</td><td>2.50</td><td>3.50</td></tr><tr><td>P</td><td>BMWW+t</td><td>MT20</td><td>3.0</td><td>4.0</td><td></td><td></td></tr><tr><td>Q</td><td>BMWW-t</td><td>MT20</td><td>4.0</td><td>6.0</td><td>2.00</td><td>1.75</td></tr><tr><td>R</td><td>BMV1+p</td><td>MT20</td><td>3.0</td><td>4.0</td><td>2.00</td><td>0.50</td></tr></table> Edge - INDICATES REFERENCE CORNER OF PLATE TOUCHES EDGE OF CHORD.							JT	TYPE	PLATES	W	LEN	Y	X	B	TMVW-t	MT20	6.0	6.0	1.75	3.00	C	TMWW-t	MT20	3.0	4.0	1.50	1.50	D	TTWW+m	MT20	6.0	8.0	Edge	2.00	E	TMW+w	MT20	2.0	4.0			F	TMWW-t	MT20	3.0	4.0			G	TTWW+m	MT20	6.0	8.0	2.25	2.25	H	TMWW-t	MT20	3.0	4.0	1.50	1.50	I	TMVW-p	MT20	6.0	6.0	2.25	2.50	K	BMV1+p	MT20	3.0	4.0	2.00	0.25	L	BMWW-t	MT20	4.0	6.0	2.00	1.50	M	BMWW+t	MT20	3.0	4.0			N	BSWW+I	MT20	5.0	8.0	5.00	2.25	O	BMWW-t	MT20	5.0	8.0	2.50	3.50	P	BMWW+t	MT20	3.0	4.0			Q	BMWW-t	MT20	4.0	6.0	2.00	1.75	R	BMV1+p	MT20	3.0	4.0	2.00	0.50	BRACING TOP CHORD TO BE SHEATHED OR MAX. PURLIN SPACING = 2.87 FT. MAX. UNBRACED BOTTOM CHORD LENGTH = 10.00 FT OR RIGID CEILING DIRECTLY APPLIED. ALL PITCH BREAKS AND PERIMETER CORNER JOINTS MUST BE LATERALLY RESTRAINED. LOADING TOTAL LOAD CASES: (4) <table><tr><th colspan="4">CHORDS</th><th colspan="4">WEBS</th></tr><tr><th>MEMB.</th><th>MAX. FACTORED FORCE (LBS)</th><th>FACTORED VERT. LOAD (PLF)</th><th>MAX. FACTORED LC1 (LC)</th><th>MEMB.</th><th>MAX. FACTORED FORCE (LBS)</th><th>MAX. FACTORED LC1 (LC)</th></tr><tr><td>FR-TO</td><td></td><td>FROM TO</td><td></td><td>FR-TO</td><td></td><td></td></tr><tr><td>A-B</td><td>0 / 28</td><td>-77.4 -77.4</td><td>0.10 (1)</td><td>Q-C</td><td>-653 / 0</td><td>0.13 (1)</td></tr><tr><td>B-C</td><td>-2456 / 0</td><td>-77.4 -77.4</td><td>0.19 (1)</td><td>C-P</td><td>0 / 311</td><td>0.08 (1)</td></tr><tr><td>C-D</td><td>-2749 / 0</td><td>-77.4 -77.4</td><td>0.21 (1)</td><td>P-D</td><td>-59 / 30</td><td>0.02 (1)</td></tr><tr><td>D-E</td><td>-3530 / 0</td><td>-77.4 -77.4</td><td>0.51 (1)</td><td>D-O</td><td>0 / 1841</td><td>0.46 (1)</td></tr><tr><td>E-F</td><td>-3530 / 0</td><td>-145.9 -145.9</td><td>0.74 (1)</td><td>O-E</td><td>-509 / 0</td><td>0.21 (1)</td></tr><tr><td>F-G</td><td>-3457 / 0</td><td>-145.9 -145.9</td><td>0.74 (1)</td><td>O-F</td><td>0 / 108</td><td>0.03 (1)</td></tr><tr><td>G-H</td><td>-3038 / 0</td><td>-77.4 -77.4</td><td>0.22 (1)</td><td>N-F</td><td>-838 / 0</td><td>0.34 (1)</td></tr><tr><td>H-I</td><td>-2737 / 0</td><td>-77.4 -77.4</td><td>0.21 (1)</td><td>N-G</td><td>0 / 1383</td><td>0.34 (1)</td></tr><tr><td>I-J</td><td>0 / 28</td><td>-77.4 -77.4</td><td>0.10 (1)</td><td>M-G</td><td>-42 / 113</td><td>0.04 (4)</td></tr><tr><td>R-B</td><td>-2191 / 0</td><td>0.0 0.0</td><td>0.24 (1)</td><td>M-H</td><td>0 / 319</td><td>0.08 (1)</td></tr><tr><td>K-I</td><td>-2420 / 0</td><td>0.0 0.0</td><td>0.27 (1)</td><td>L-H</td><td>-662 / 0</td><td>0.14 (1)</td></tr><tr><td></td><td></td><td></td><td></td><td>B-Q</td><td>0 / 2145</td><td>0.53 (1)</td></tr><tr><td></td><td></td><td></td><td></td><td>L-I</td><td>0 / 2390</td><td>0.59 (1)</td></tr><tr><td>R-Q</td><td>0 / 0</td><td>-18.2 -18.2</td><td>0.06 (1)</td><td></td><td></td><td></td></tr><tr><td>Q-P</td><td>0 / 2053</td><td>-18.2 -18.2</td><td>0.33 (1)</td><td></td><td></td><td></td></tr><tr><td>P-O</td><td>0 / 2271</td><td>-18.2 -18.2</td><td>0.36 (1)</td><td></td><td></td><td></td></tr><tr><td>O-N</td><td>0 / 3457</td><td>-34.4 -34.4</td><td>0.54 (1)</td><td></td><td></td><td></td></tr><tr><td>N-M</td><td>0 / 2511</td><td>-34.4 -34.4</td><td>0.37 (1)</td><td></td><td></td><td></td></tr><tr><td>M-L</td><td>0 / 2287</td><td>-34.4 -34.4</td><td>0.35 (1)</td><td></td><td></td><td></td></tr></table>							CHORDS				WEBS				MEMB.	MAX. FACTORED FORCE (LBS)	FACTORED VERT. LOAD (PLF)	MAX. FACTORED LC1 (LC)	MEMB.	MAX. FACTORED FORCE (LBS)	MAX. FACTORED LC1 (LC)	FR-TO		FROM TO		FR-TO			A-B	0 / 28	-77.4 -77.4	0.10 (1)	Q-C	-653 / 0	0.13 (1)	B-C	-2456 / 0	-77.4 -77.4	0.19 (1)	C-P	0 / 311	0.08 (1)	C-D	-2749 / 0	-77.4 -77.4	0.21 (1)	P-D	-59 / 30	0.02 (1)	D-E	-3530 / 0	-77.4 -77.4	0.51 (1)	D-O	0 / 1841	0.46 (1)	E-F	-3530 / 0	-145.9 -145.9	0.74 (1)	O-E	-509 / 0	0.21 (1)	F-G	-3457 / 0	-145.9 -145.9	0.74 (1)	O-F	0 / 108	0.03 (1)	G-H	-3038 / 0	-77.4 -77.4	0.22 (1)	N-F	-838 / 0	0.34 (1)	H-I	-2737 / 0	-77.4 -77.4	0.21 (1)	N-G	0 / 1383	0.34 (1)	I-J	0 / 28	-77.4 -77.4	0.10 (1)	M-G	-42 / 113	0.04 (4)	R-B	-2191 / 0	0.0 0.0	0.24 (1)	M-H	0 / 319	0.08 (1)	K-I	-2420 / 0	0.0 0.0	0.27 (1)	L-H	-662 / 0	0.14 (1)					B-Q	0 / 2145	0.53 (1)					L-I	0 / 2390	0.59 (1)	R-Q	0 / 0	-18.2 -18.2	0.06 (1)				Q-P	0 / 2053	-18.2 -18.2	0.33 (1)				P-O	0 / 2271	-18.2 -18.2	0.36 (1)				O-N	0 / 3457	-34.4 -34.4	0.54 (1)				N-M	0 / 2511	-34.4 -34.4	0.37 (1)				M-L	0 / 2287	-34.4 -34.4	0.35 (1)				LOADING IN FLAT SECTION BASED ON A SLOPE OF 2.00/12 MINIMUM						
JT	TYPE	PLATES	W	LEN	Y	X																																																																																																																																																																																																																																																																																																
B	TMVW-t	MT20	6.0	6.0	1.75	3.00																																																																																																																																																																																																																																																																																																
C	TMWW-t	MT20	3.0	4.0	1.50	1.50																																																																																																																																																																																																																																																																																																
D	TTWW+m	MT20	6.0	8.0	Edge	2.00																																																																																																																																																																																																																																																																																																
E	TMW+w	MT20	2.0	4.0																																																																																																																																																																																																																																																																																																		
F	TMWW-t	MT20	3.0	4.0																																																																																																																																																																																																																																																																																																		
G	TTWW+m	MT20	6.0	8.0	2.25	2.25																																																																																																																																																																																																																																																																																																
H	TMWW-t	MT20	3.0	4.0	1.50	1.50																																																																																																																																																																																																																																																																																																
I	TMVW-p	MT20	6.0	6.0	2.25	2.50																																																																																																																																																																																																																																																																																																
K	BMV1+p	MT20	3.0	4.0	2.00	0.25																																																																																																																																																																																																																																																																																																
L	BMWW-t	MT20	4.0	6.0	2.00	1.50																																																																																																																																																																																																																																																																																																
M	BMWW+t	MT20	3.0	4.0																																																																																																																																																																																																																																																																																																		
N	BSWW+I	MT20	5.0	8.0	5.00	2.25																																																																																																																																																																																																																																																																																																
O	BMWW-t	MT20	5.0	8.0	2.50	3.50																																																																																																																																																																																																																																																																																																
P	BMWW+t	MT20	3.0	4.0																																																																																																																																																																																																																																																																																																		
Q	BMWW-t	MT20	4.0	6.0	2.00	1.75																																																																																																																																																																																																																																																																																																
R	BMV1+p	MT20	3.0	4.0	2.00	0.50																																																																																																																																																																																																																																																																																																
CHORDS				WEBS																																																																																																																																																																																																																																																																																																		
MEMB.	MAX. FACTORED FORCE (LBS)	FACTORED VERT. LOAD (PLF)	MAX. FACTORED LC1 (LC)	MEMB.	MAX. FACTORED FORCE (LBS)	MAX. FACTORED LC1 (LC)																																																																																																																																																																																																																																																																																																
FR-TO		FROM TO		FR-TO																																																																																																																																																																																																																																																																																																		
A-B	0 / 28	-77.4 -77.4	0.10 (1)	Q-C	-653 / 0	0.13 (1)																																																																																																																																																																																																																																																																																																
B-C	-2456 / 0	-77.4 -77.4	0.19 (1)	C-P	0 / 311	0.08 (1)																																																																																																																																																																																																																																																																																																
C-D	-2749 / 0	-77.4 -77.4	0.21 (1)	P-D	-59 / 30	0.02 (1)																																																																																																																																																																																																																																																																																																
D-E	-3530 / 0	-77.4 -77.4	0.51 (1)	D-O	0 / 1841	0.46 (1)																																																																																																																																																																																																																																																																																																
E-F	-3530 / 0	-145.9 -145.9	0.74 (1)	O-E	-509 / 0	0.21 (1)																																																																																																																																																																																																																																																																																																
F-G	-3457 / 0	-145.9 -145.9	0.74 (1)	O-F	0 / 108	0.03 (1)																																																																																																																																																																																																																																																																																																
G-H	-3038 / 0	-77.4 -77.4	0.22 (1)	N-F	-838 / 0	0.34 (1)																																																																																																																																																																																																																																																																																																
H-I	-2737 / 0	-77.4 -77.4	0.21 (1)	N-G	0 / 1383	0.34 (1)																																																																																																																																																																																																																																																																																																
I-J	0 / 28	-77.4 -77.4	0.10 (1)	M-G	-42 / 113	0.04 (4)																																																																																																																																																																																																																																																																																																
R-B	-2191 / 0	0.0 0.0	0.24 (1)	M-H	0 / 319	0.08 (1)																																																																																																																																																																																																																																																																																																
K-I	-2420 / 0	0.0 0.0	0.27 (1)	L-H	-662 / 0	0.14 (1)																																																																																																																																																																																																																																																																																																
				B-Q	0 / 2145	0.53 (1)																																																																																																																																																																																																																																																																																																
				L-I	0 / 2390	0.59 (1)																																																																																																																																																																																																																																																																																																
R-Q	0 / 0	-18.2 -18.2	0.06 (1)																																																																																																																																																																																																																																																																																																			
Q-P	0 / 2053	-18.2 -18.2	0.33 (1)																																																																																																																																																																																																																																																																																																			
P-O	0 / 2271	-18.2 -18.2	0.36 (1)																																																																																																																																																																																																																																																																																																			
O-N	0 / 3457	-34.4 -34.4	0.54 (1)																																																																																																																																																																																																																																																																																																			
N-M	0 / 2511	-34.4 -34.4	0.37 (1)																																																																																																																																																																																																																																																																																																			
M-L	0 / 2287	-34.4 -34.4	0.35 (1)																																																																																																																																																																																																																																																																																																			
							GIRDER TYPE: CPrimeHip SIDE SETBACK = 6-0-0 END SETBACK = 6-0-0 END WALL WIDTH = 5-8 CORNER FRAMING TYPE: CONVENTIONAL END JACK TYPE: CONVENTIONAL APPLIED TO FRONT SIDE - ADDTL LOADS BASED ON 55 % OF GSL. LOADS APPLIED TO FIRST 15-0-0 OF SPAN MEASURED FROM THE RIGHT.																																																																																																																																																																																																																																																																																															
							*** NON STANDARD GIRDER *** ADDTL USER-DEFINED LOADS APPLIED TO ALL LOAD CASES.																																																																																																																																																																																																																																																																																															
							THIS TRUSS IS DESIGNED FOR RESIDENTIAL OR SMALL BUILDING REQUIREMENTS OF PART 9, NBCC 2010																																																																																																																																																																																																																																																																																															
							THIS DESIGN COMPLIES WITH: - PART 9 OF OBC 2012 , BCBC 2012 , ABC 2014 - CSA 086-09 - TPIC 2011																																																																																																																																																																																																																																																																																															
							(55 % OF 27.2 P.S.F. G.S.L PLUS 8.4 P.S.F. RAIN LOAD) EQUALS 23.3 P.S.F. SPECIFIED ROOF LIVE LOAD																																																																																																																																																																																																																																																																																															
							ALLOWABLE DEFL.(LL)= L/360 (0.86")																																																																																																																																																																																																																																																																																															

READ ALL NOTES ON THIS PAGE AND ON ENGINEERING NOTE PAGE ENP-1. THIS NOTE PAGE IS AN INTEGRAL PART OF THIS DRAWING AS IT CONTAINS SPECIFICATIONS AND CRITERIA USED IN THE DESIGN OF THIS COMPONENT.

CONTINUED ON PAGE 2

JOB NAME	TRUSS NAME	QUANTITY	PLY	JOB DESC.	GREEN YORK HOMES - GRANELLI HOME CORP - LIANA 3 ELEV 2	DRWG NO.
NE0618-006	G01	1	1	TRUSS DESC.		PAGE 4 OF 42

Version 8.210 S Mar 12 2018 MiTek Industries, Inc. Sat Jun 2 15:02:02 2018 Page 2
ID:9_xLMwZ3WDKc3QXh8cyzSszB2V3-BzqJ4jxUO_DgnqwjqzFV7LpjMGfuXf0?dz94SlzAldJ

HANGERS NOTES
1) SPECIAL HANGER(S) OR CONNECTION(S) REQUIRED TO SUPPORT CONCENTRATED LOAD(S) 348.1 lbs FACTORED DOWN AT 19-10-0 ON TOP CHORD, AND 854.0 lbs FACTORED DOWN AT 10-5-4 ON BOTTOM CHORD. DESIGN FOR UNSPECIFIED CONNECTION(S) IS DELEGATED TO THE BUILDING DESIGNER.

READ ALL NOTES ON THIS PAGE AND ON ENGINEERING NOTE PAGE ENP-1. THIS NOTE PAGE IS AN INTEGRAL PART OF THIS DRAWING AS IT CONTAINS SPECIFICATIONS AND CRITERIA USED IN THE DESIGN OF THIS COMPONENT.

TRUSS PLATE MANUFACTURER IS NOT RESPONSIBLE FOR QUALITY CONTROL IN THE TRUSS MANUFACTURING PLANT .

NAIL VALUES
PLATE GRIP(DRY) SHEAR SECTION
(PSI) (PLI) (PLI)
MAX MIN MAX MIN MAX MIN
MT20 618 354 1667 822 2284 1656


PLATE PLACEMENT TOL. = 0.250 inches

PLATE ROTATION TOL. = 5.0 Deg.

JSI GRIP= 0.89 (O) (INPUT = 0.90)
JSI METAL= 0.64 (B) (INPUT = 1.00)



Version 8.210 S Mar 12 2018 MiTek Industries, Inc. Sat Jun 2 15:02:02 2018 Page 1
ID:9_xLMwZ3WDKc3QXh8cyzSnzB2V3-BzqJ4jxUO_DgnqwjzFV7LpnpGZzXeo?dz94SlzAldJ



TOTAL WEIGHT = 128 lb [M]

LUMBER
N. L. G. A. RULES

CHORDS	SIZE	DRY	LUMBER	DESCR.
A - C	2x4	DRY	No.2	SPF
C - F	2x6	DRY	No.2	SPF
F - H	2x6	DRY	No.2	SPF
H - J	2x4	DRY	No.2	SPF
R - B	2x4	DRY	No.2	SPF
K - I	2x4	DRY	No.2	SPF
R - N	2x4	DRY	No.2	SPF
N - K	2x4	DRY	No.2	SPF

ALL WEBS 2x3 DRY No.2 SPF
EXCEPT

DRY: SEASONED LUMBER.

PLATES (table is in inches)

JT	TYPE	PLATES	W	LEN	Y	X
B	TMVW-p	MT20	5.0	8.0	1.50	3.50
C	TTWW+m	MT20	8.0	8.0	4.00	3.00
D	TMWW-t	MT20	4.0	4.0		
E	TMW+w	MT20	2.0	4.0		
F	TS-t	MT20	4.0	6.0		
G	TMWW-t	MT20	4.0	4.0		
H	TTWW+m	MT20	8.0	8.0	4.00	3.00
I	TMVW-p	MT20	5.0	8.0	1.50	3.50
K	BMV1+p	MT20	3.0	5.0		
L	BMWW-t	MT20	4.0	8.0	2.00	3.00
M	BMWW-t	MT20	4.0	6.0	1.50	1.75
N	BS-t	MT20	4.0	8.0		
O	BMWW-t	MT20	3.0	8.0		
P	BMWW-t	MT20	4.0	6.0	1.50	1.75
Q	BMWW-t	MT20	4.0	8.0	2.00	3.00
R	BMV1+p	MT20	3.0	5.0		

HANGERS NOTES
1) SPECIAL HANGER(S) OR CONNECTION(S) REQUIRED TO SUPPORT CONCENTRATED LOAD(S) 241.8 lbs FACTORED DOWN AT 25-0-0, AND 241.8 lbs FACTORED DOWN AT 4-2-0 ON TOP CHORD. DESIGN FOR UNSPECIFIED CONNECTION(S) IS DELEGATED TO THE BUILDING DESIGNER.



READ ALL NOTES ON THIS PAGE AND ON ENGINEERING NOTE PAGE ENP-1. THIS NOTE PAGE IS AN INTEGRAL PART OF THIS DRAWING AS IT CONTAINS SPECIFICATIONS AND CRITERIA USED IN THE DESIGN OF THIS COMPONENT.

DIMENSIONS, SUPPORTS AND LOADINGS SPECIFIED BY FABRICATOR TO BE VERIFIED BY BUILDING DESIGNER

BEARINGS

JT	FACTORED GROSS REACTION		MAXIMUM FACTORED GROSS REACTION		INPUT BRG	REQRD BRG
	VERT	HORZ	DOWN	HORZ		
R	2685	0	2685	0	5-8	5-8
K	2685	0	2685	0	5-8	5-8

UNFACTORED REACTIONS

JT	1ST LCASE COMBINED		MAX./MIN. COMPONENT REACTIONS		WIND	DEAD	SOIL
	SNOW	LIVE	PERM.LIVE	WIND			
R	1885	1314 / 0	0 / 0	0 / 0	0 / 0	571 / 0	0 / 0
K	1885	1314 / 0	0 / 0	0 / 0	0 / 0	571 / 0	0 / 0

BEARING MATERIAL TO BE SPF NO.2 OR BETTER AT JOINT(S) R, K

BRACING
TOP CHORD TO BE SHEATHED OR MAX. PURLIN SPACING = 3.44 FT.
MAX. UNBRACED BOTTOM CHORD LENGTH = 10.00 FT OR RIGID CEILING DIRECTLY APPLIED.

ALL PITCH BREAKS AND PERIMETER CORNER JOINTS MUST BE Laterally RESTRAINED.

LOADING
TOTAL LOAD CASES: (4)

CHORDS				WEBS			
MEMB.	MAX. FACTORED FORCE (LBS)	FACTORED VERT. LOAD (PLF)	MAX. FACTORED VERT. LOAD (PLF)	MAX. FACTORED VERT. LOAD (PLF)	MEMB.	MAX. FACTORED FORCE (LBS)	MAX. FACTORED VERT. LOAD (PLF)
FR-TO		FROM	TO	LENGTH	FR-TO		
A-B	0 / 28	-77.4	-77.4	0.10 (1)	10.00	Q-C	-449 / 14
B-C	-3151 / 0	-77.4	-77.4	0.46 (1)	3.52	C-P	0 / 2539
C-D	-4680 / 0	-145.9	-145.9	0.43 (1)	3.63	P-D	-1309 / 0
D-E	-5292 / 0	-145.9	-145.9	0.43 (1)	3.44	D-O	0 / 757
E-F	-5292 / 0	-145.9	-145.9	0.43 (1)	3.44	O-E	-711 / 0
F-G	-5292 / 0	-145.9	-145.9	0.43 (1)	3.44	G-G	0 / 757
G-H	-4680 / 0	-145.9	-145.9	0.43 (1)	3.63	M-G	-1309 / 0
H-I	-3151 / 0	-77.4	-77.4	0.46 (1)	3.52	M-H	0 / 2539
I-J	0 / 28	-77.4	-77.4	0.10 (1)	10.00	L-H	-449 / 14
R-B	-2628 / 0	0.0	0.0	0.30 (1)	5.23	B-Q	0 / 2704
K-I	-2628 / 0	0.0	0.0	0.30 (1)	5.23	L-I	0 / 2704
R-Q	0 / 0	-34.4	-34.4	0.19 (4)	10.00		
Q-P	0 / 2617	-34.4	-34.4	0.57 (1)	10.00		
P-O	0 / 4680	-34.4	-34.4	0.92 (1)	10.00		
O-N	0 / 4680	-34.4	-34.4	0.92 (1)	10.00		
N-M	0 / 4680	-34.4	-34.4	0.92 (1)	10.00		
M-L	0 / 2617	-34.4	-34.4	0.57 (1)	10.00		
L-K	0 / 0	-34.4	-34.4	0.19 (4)	10.00		

FACTORED CONCENTRATED LOADS (LBS)

JT	LOC.	LC1	MAX-	MAX+	FACE	DIR.	TYPE
C	4-2-0	-242	-242	---	FRONT	VERT	TOTAL
H	25-0-0	-242	-242	---	FRONT	VERT	TOTAL

DESIGN CRITERIA

SPECIFIED LOADS:
TOP CH. LL = 23.3 PSF
DL = 3.0 PSF
BOT CH. LL = 0.0 PSF
DL = 7.3 PSF
TOTAL LOAD = 33.6 PSF

SPACING = 24.0 IN./C

LOADING IN FLAT SECTION BASED ON A SLOPE OF 2.00/12 MINIMUM

GIRDER TYPE: CPrimeHip
SIDE SETBACK = 4-2-0
END SETBACK = 6-0-0
END WALL WIDTH = 5-8
CORNER FRAMING TYPE: CONVENTIONAL
END JACK TYPE: CONVENTIONAL
APPLIED TO FRONT SIDE
- ADDTL LOADS BASED ON 55 % OF GSL.

THIS TRUSS IS DESIGNED FOR RESIDENTIAL OR SMALL BUILDING REQUIREMENTS OF PART 9, NBCC 2010

THIS DESIGN COMPLIES WITH:
- PART 9 OF OBC 2012, BCBC 2012, ABC 2014
- CSA 086-09
- TPIC 2011

(55 % OF 27.2 P.S.F. G.S.L. PLUS 8.4 P.S.F. RAIN LOAD) EQUALS 23.3 P.S.F. SPECIFIED ROOF LIVE LOAD

ALLOWABLE DEFL.(LL)= L/360 (0.97")
CALCULATED VERT. DEFL.(LL) = L/ 999 (0.23")
ALLOWABLE DEFL.(TL)= L/360 (0.97")
CALCULATED VERT. DEFL.(TL) = L/ 851 (0.41")

CSI: TC=0.46/1.00 (H-I:1), BC=0.92/1.00 (M-O:1), WB=0.67/1.00 (L-I:1), SSI=0.29/1.00 (C-D:1)

DOL LUMBER=1.00 NAIL=1.00 LBS BEND=1.00
COMP=1.00 SHEAR=1.00 TENS=1.00

COMPANION LIVE LOAD FACTOR = 0.50

TRUSS PLATE MANUFACTURER IS NOT RESPONSIBLE FOR QUALITY CONTROL IN THE TRUSS MANUFACTURING PLANT .

NAIL VALUES
PLATE GRIP(DRY) SHEAR SECTION
(PSI) (PLI) (PLI)
MAX MIN MAX MIN MAX MIN
MT20 618 354 1667 822 2284 1656

CONTINUED ON PAGE 2



JOB NAME	TRUSS NAME	QUANTITY	PLY	JOB DESC.	DRWG NO.
NE0618-006	G02	1	1	GREEN YORK HOMES - GRANELLI HOME CORP - LIANA 3 ELEV 2	PAGE 6 OF 42

Version 8.210 S Mar 12 2018 MiTek Industries, Inc. Sat Jun 2 15:02:03 2018 Page 2

ID:9_xLMwZ3WDKc3QXh8cyzSnzB2V3-f9OhH3y79HLXO_VwOgmkgZMyZfvCG528sdud?kzAld

PLATE PLACEMENT TOL. = 0.250 inches


PLATE ROTATION TOL. = 5.0 Deg.

JSI GRIP= 0.90 (Q) (INPUT = 0.90)

JSI METAL= 0.90 (N) (INPUT = 1.00)

READ ALL NOTES ON THIS PAGE AND ON
ENGINEERING NOTE PAGE ENP-1. THIS
NOTE PAGE IS AN INTEGRAL PART OF
THIS DRAWING AS IT CONTAINS
SPECIFICATIONS AND CRITERIA USED IN
THE DESIGN OF THIS COMPONENT.





TOTAL WEIGHT = 2 X 149 = 297 lb [M]

LUMBER			
N. L. G. A. RULES			
CHORDS	SIZE	LUMBER	DESCR.
A - C	2x4	DRY No.2	SPF
C - E	2x4	DRY No.2	SPF
E - G	2x4	DRY No.2	SPF
G - H	2x4	DRY No.2	SPF
H - J	2x4	DRY No.2	SPF
R - B	2x4	DRY No.2	SPF
K - I	2x6	DRY No.2	SPF
R - O	2x6	DRY No.2	SPF
O - K	2x6	DRY No.2	SPF
ALL WEBS EXCEPT	2x3	DRY No.2	SPF

DRY: SEASONED LUMBER.

DESIGN CONSISTS OF **2** TRUSSES BUILT SEPARATELY THEN FASTENED TOGETHER AS FOLLOWS:

CHORDS #ROWS	SURFACE SPACING (IN)	LOAD(PLF)
TOP CHORDS : (0.122"x3") SPIRAL NAILS		
A - C	12	TOP
C - E	12	TOP
E - G	12	TOP
G - H	12	TOP
H - J	12	TOP
R - B	12	TOP
K - I	12	TOP
BOTTOM CHORDS : (0.122"x3") SPIRAL NAILS		
R - O	12	TOP
O - K	12	SIDE(0.0)
WEBS : (0.122"x3") SPIRAL NAILS		
2x3	6	

NAILS TO BE DRIVEN FROM ONE SIDE ONLY.

GIRDER NAILING ASSUMES NAILED HANGERS ARE FASTENED WITH MIN. 3-0 INCH NAILS.

TOP - COMPONENTS ARE LOADED FROM THE TOP AND MUST BE PLACED ON TOP EDGE OF ALL PLIES FOR THE LOAD TO BE TRANSFERRED TO EACH PLY.

DIMENSIONS, SUPPORTS AND LOADINGS SPECIFIED BY FABRICATOR TO BE VERIFIED BY BUILDING DESIGNER

FACTORED GROSS REACTION		MAXIMUM FACTORED GROSS REACTION		INPUT BRG		REQRD BRG	
JT	VERT	JT	HORZ	JT	IN-SX	JT	IN-SX
R	1744	0	1744	0	5-8	5-8	5-8
K	3460	0	3460	0	5-8	5-8	5-8

UNFACTORED REACTIONS

1ST LCASE	MAX./MIN. COMPONENT REACTIONS						
JT	COMBINED	SNOW	LIVE	PERM.LIVE	WIND	DEAD	SOIL
R	1223	861 / 0	0 / 0	0 / 0	0 / 0	362 / 0	0 / 0
K	2429	1697 / 0	0 / 0	0 / 0	0 / 0	732 / 0	0 / 0

BEARING MATERIAL TO BE SPF NO.2 OR BETTER AT JOINT(S) R, K

BRACING

TOP CHORD TO BE SHEATHED OR MAX. PURLIN SPACING = 4.68 FT.
MAX. UNBRACED BOTTOM CHORD LENGTH = 10.00 FT OR RIGID CEILING DIRECTLY APPLIED.

ALL PITCH BREAKS AND PERIMETER CORNER JOINTS MUST BE Laterally RESTRAINED.

1 - 1x4 LATERAL BRACE(S) AT 1/2 LENGTH OF D-P. DBS = 20-0-0 . CBF = 53 LBS.

DBS = DIAGONAL BRACE SPACING (MAX). CBF = CUMULATIVE BRACING FORCE (PER BRACE). FASTEN LATERAL BRACE(S) TO EACH PLY USING (0.122"x3") SPIRAL NAILS : 1 NAIL FOR 2x3 BRACE(S), 2 FOR 1x4, 2x4, 2x5, 3 FOR 2x6, 4 FOR 2x8, 5 FOR 2x10, AND 6 FOR 2x12.

END VERTICAL(S) MUST BE SHEATHED OR HAVE BRACES AS INDICATED IN THE MAX. UNBRACED LENGTH COLUMN OF THE TABLE BELOW

LOADING

TOTAL LOAD CASES: (4)

CHORDS				WEBS			
MEMB.	MAX. FACTORED FORCE (LBS)	FACTORED VERT. LOAD (PLF)	MAX LC1 MAX CSI (LC)	MEMB.	MAX. FACTORED FORCE (LBS)	MAX UNBRACED LENGTH	MAX CSI (LC)
FR-TO		FROM TO		FR-TO			
A-B	0 / 28	-77.4 -77.4	0.05 (1)	Q-D	-134 / 72	10.00	0.03 (1)
B-C	-2032 / 0	-77.4 -77.4	0.36 (1)	D-P	-421 / 0	10.00	0.10 (1)
C-D	-2032 / 0	-77.4 -77.4	0.36 (1)	P-E	0 / 1545	5.76	0.19 (1)
D-E	-1711 / 0	-77.4 -77.4	0.34 (1)	P-F	-1377 / 0	6.15	0.89 (1)
E-F	-1699 / 0	-77.4 -77.4	0.15 (1)	N-F	0 / 1232	6.25	0.15 (1)
F-G	-2563 / 0	-77.4 -77.4	0.16 (1)	N-G	-1740 / 0	5.50	0.50 (1)
G-H	-3462 / 0	-77.4 -77.4	0.12 (1)	M-G	-558 / 0	4.93	0.07 (1)
H-I	-3798 / 0	-77.4 -77.4	0.20 (1)	M-H	0 / 404	4.68	0.05 (1)
I-J	0 / 28	-77.4 -77.4	0.05 (1)	L-H	0 / 1519	10.00	0.19 (1)
R-B	-1687 / 0	0.0 0.0	0.09 (1)	B-Q	0 / 1736	7.81	0.21 (1)
K-I	-3072 / 0	0.0 0.0	0.11 (1)	L-I	0 / 3231	7.81	0.40 (1)
R-Q	0 / 0	-18.2 -18.2	0.04 (4)			10.00	
Q-P	0 / 1718	-18.2 -18.2	0.14 (1)			10.00	
P-O	0 / 2154	-18.2 -18.2	0.17 (1)			10.00	
O-N	0 / 2154	-18.2 -18.2	0.17 (1)			10.00	
N-M	0 / 3477	-18.2 -18.2	0.30 (1)			10.00	
M-L	0 / 3197	-18.2 -18.2	0.46 (1)			10.00	
L-S	0 / 0	-18.2 -18.2	0.32 (1)			10.00	
S-T	0 / 0	-18.2 -18.2	0.32 (1)			10.00	
T-K	0 / 0	-18.2 -18.2	0.32 (1)			10.00	

FACTORED CONCENTRATED LOADS (LBS)

JT	LOC.	LC1	MAX-	MAX+	FACE	DIR.	TYPE
S	25-8-8	-1946	-1946	---	FRONT	VERT	TOTAL
T	27-1-4	-270	-270	---	FRONT	VERT	TOTAL

DESIGN CRITERIA

*** SPECIAL LOADS ANALYSIS ***
GEOMETRY AND/OR BASIC LOADS CHANGED BY USER.
LOADS WERE DERIVED FROM USER INPUT
NO FURTHER MODIFICATIONS WERE MADE

SPECIFIED LOADS:

TOP CH.	LL = 23.3	PSF
	DL = 3.0	PSF
BOT CH.	LL = 0.0	PSF
	DL = 7.3	PSF
TOTAL LOAD = 33.6 PSF		

SPACING = 24.0 IN./C

LOADING IN ALL FLAT SECTIONS BASED ON A SLOPE OF 2.00/12 MINIMUM

*** NON STANDARD GIRDER ***
ADD'L USER-DEFINED LOADS APPLIED TO ALL LOAD CASES.

THIS TRUSS IS DESIGNED FOR RESIDENTIAL OR SMALL BUILDING REQUIREMENTS OF PART 9, NBCC 2010

THIS DESIGN COMPLIES WITH:
- PART 9 OF OBC 2012 , BCBC 2012 , ABC 2014
- CSA 086-09
- TPIC 2011

(55 % OF 27.2 P.S.F. G.S.L. PLUS 8.4 P.S.F. RAIN LOAD) EQUALS 23.3 P.S.F. SPECIFIED ROOF LIVE LOAD

ALLOWABLE DEFL.(LL)= L/360 (0.97")
CALCULATED VERT. DEFL.(LL) = L/999 (0.07")
ALLOWABLE DEFL.(TL)= L/360 (0.97")
CALCULATED VERT. DEFL.(TL) = L/999 (0.12")

CSI: TC=0.36/1.00 (B-D:1) , BC=0.46/1.00 (L-M:1) ,
WB=0.89/1.00 (F-P:1) , SSI=0.63/1.00 (K-L:1)

DOL LUMBER=1.00 NAIL=1.00 LS BEND=1.00
COMP=1.00 SHEAR=1.00 TENS= 1.00

COMPANION LIVE LOAD FACTOR = 0.50

AUTOSOLVE LEFT HEEL ONLY

TRUSS PLATE MANUFACTURER IS NOT RESPONSIBLE FOR QUALITY CONTROL IN THE TRUSS MANUFACTURING PLANT .

NAIL VALUES
PLATE GRIP(DRY) SHEAR SECTION
(PSI) (PLI) (PLI)
MAX MIN MAX MIN MAX MIN
MT20 618 354 1667 822 2284 1656

CONTINUED ON PAGE 2



READ ALL NOTES ON THIS PAGE AND ON ENGINEERING NOTE PAGE ENP-1. THIS NOTE PAGE IS AN INTEGRAL PART OF THIS DRAWING AS IT CONTAINS SPECIFICATIONS AND CRITERIA USED IN THE DESIGN OF THIS COMPONENT.



PLATES (table is in inches)

JT	TYPE	PLATES	W	LEN	Y	X
B	TMVW-p	MT20	4.0	4.0	1.25	2.00
C	TS-t	MT20	3.0	6.0		
D	TMWW-t	MT20	3.0	4.0	1.50	1.50
E	TTW+p	MT20	3.0	5.0		
F	TMWW-t	MT20	3.0	5.0	1.50	2.00
G	TTWW+m	MT20	4.0	5.0		
H	TTWW-m	MT20	4.0	6.0	1.75	2.50
I	TMVW-p	MT20	5.0	6.0	1.50	3.00
K	BMV1+p	MT20	2.0	4.0		
L	BMWW-t	MT20	5.0	6.0	2.50	2.25
M	BMWW+t	MT20	3.0	4.0		
N	BMWW-t	MT20	4.0	4.0		
O	BS-t	MT20	4.0	6.0		
P	BMWWW-t	MT20	4.0	6.0		
Q	BMWW-t	MT20	4.0	4.0	2.00	1.75
R	BMV1+p	MT20	2.0	4.0		

HANGERS NOTES

1) SPECIAL HANGER(S) OR CONNECTION(S) REQUIRED TO SUPPORT CONCENTRATED LOAD(S) 1945.7 lbs FACTORED DOWN AT 25-8-8, AND 270.4 lbs FACTORED DOWN AT 27-1-4 ON BOTTOM CHORD. DESIGN FOR UNSPECIFIED CONNECTION(S) IS DELEGATED TO THE BUILDING DESIGNER.

PLATE PLACEMENT TOL. = 0.250 inches


PLATE ROTATION TOL. = 5.0 Deg.

JSI GRIP= 0.90 (G) (INPUT = 0.90)

JSI METAL= 0.40 (L) (INPUT = 1.00)

READ ALL NOTES ON THIS PAGE AND ON ENGINEERING NOTE PAGE ENP-1. THIS NOTE PAGE IS AN INTEGRAL PART OF THIS DRAWING AS IT CONTAINS SPECIFICATIONS AND CRITERIA USED IN THE DESIGN OF THIS COMPONENT.





Scale = 1:23.2

TOTAL WEIGHT = 2 X 31 = 61 lb [M]

LUMBER				
N. L. G. A. RULES				
CHORDS	SIZE	DRY	LUMBER	DESCR.
A - B	2x4	DRY	No.2	SPF
B - C	2x4	DRY	No.2	SPF
D - C	2x4	DRY	No.2	SPF
F - A	2x4	DRY	No.2	SPF
F - D	2x6	DRY	No.2	SPF
ALL WEBS EXCEPT	2x3	DRY	No.2	SPF

DRY: SEASONED LUMBER.

DESIGN CONSISTS OF 2 TRUSSES BUILT SEPARATELY THEN FASTENED TOGETHER AS FOLLOWS:

CHORDS #ROWS	SURFACE SPACING (IN)	LOAD(PLF)
TOP CHORDS : (0.122"x3") SPIRAL NAILS		
A - B	12	TOP
B - C	12	TOP
C - D	12	TOP
F - A	12	TOP
BOTTOM CHORDS : (0.122"x3") SPIRAL NAILS		
F - D	9	SIDE (276.4)
WEBS : (0.122"x3") SPIRAL NAILS		
2x3	6	

NAILS TO BE DRIVEN FROM ONE SIDE ONLY.

TOP - COMPONENTS ARE LOADED FROM THE TOP AND MUST BE PLACED ON TOP EDGE OF ALL PLIES FOR THE LOAD TO BE TRANSFERRED TO EACH PLY.

SIDE - PLF SHOWN IS THE EQUIVALENT UDL APPLIED TO ONE SIDE THAT THE CORRESPONDING NAILING PATTERN SHALL BE CAPABLE OF TRANSFERING. REMAINING PLF MUST BE APPLIED ON THE OPPOSITE SIDE OR ON THE TOP.

PLATES (table is in inches)

JT	TYPE	PLATES	W	LEN	Y	X
A	TMVW-t	MT20	3.0	5.0	1.50	2.25
B	TTWW+m	MT20	5.0	5.0	2.00	1.25
C	TMV+p	MT20	2.0	4.0		

DIMENSIONS, SUPPORTS AND LOADINGS SPECIFIED BY FABRICATOR TO BE VERIFIED BY BUILDING DESIGNER

BEARINGS

JT	FACTORED GROSS REACTION		MAXIMUM FACTORED GROSS REACTION		INPUT BRG UPLIFT	REQRD BRG IN-SX
	VERT	HORZ	DOWN	HORZ		
D	1945	0	1945	0	0	MECHANICAL
F	1945	0	1945	0	0	5-8

A SUITABLE MECHANICAL CONNECTION IS REQUIRED AT JOINT D TO RESIST THE MAX FACTORED REACTIONS.

UNFACTORED REACTIONS

JT	1ST LCASE COMBINED	MAX/MIN. SNOW	MAX/MIN. LIVE	MAX/MIN. PERM. LIVE	MAX/MIN. WIND	MAX/MIN. DEAD	MAX/MIN. SOIL
D	1367	947 / 0	0 / 0	0 / 0	0 / 0	419 / 0	0 / 0
F	1367	947 / 0	0 / 0	0 / 0	0 / 0	419 / 0	0 / 0

BEARING MATERIAL TO BE SPF NO.2 OR BETTER AT JOINT(S) F

BRACING

TOP CHORD TO BE SHEATHED OR MAX. PURLIN SPACING = 6.25 FT.
MAX. UNBRACED BOTTOM CHORD LENGTH = 10.00 FT OR RIGID CEILING DIRECTLY APPLIED.

ALL PITCH BREAKS AND PERIMETER CORNER JOINTS MUST BE Laterally RESTRAINED.

LOADING

TOTAL LOAD CASES: (4)

CHORDS				WEBS			
MEMB.	MAX. FACTORED FORCE (LBS)	FACTORED VERT. LOAD (PLF)	LC1 MAX CSI (LC)	MAX. UNBRACED LENGTH	MEMB.	MAX. FACTORED FORCE (LBS)	MAX. CSI (LC)
FR-TO		FROM	TO		FR-TO		
A-B	-932 / 0	-77.4	-77.4 0.18 (1)	6.25	E-B	0 / 2841	0.35 (1)
B-C	0 / 0	-77.4	-77.4 0.01 (1)	10.00	B-D	-2811 / 0	0.31 (1)
D-C	-43 / 0	0.0	0.0 0.00 (1)	7.81	A-E	0 / 842	0.10 (1)
F-A	-729 / 0	0.0	0.0 0.04 (1)	7.81			
F-E	0 / 0	-571.0	-571.0 0.48 (1)	10.00			
E-D	0 / 926	-571.0	-571.0 0.45 (1)	10.00			

DESIGN CRITERIA

SPECIFIED LOADS:

TOP CH.	LL	=	23.3	PSF
	DL	=	3.0	PSF
BOT CH.	LL	=	0.0	PSF
	DL	=	7.3	PSF
TOTAL LOAD		=	33.6	PSF

SPACING = 24.0 IN./C

LOADING IN FLAT SECTION BASED ON A SLOPE OF 2.00/12 MINIMUM

GIRDER TYPE: CstdGirder

START DISTANCE = 0-0

START SPAN CARRIED = 25-7-0

END DISTANCE = 6-0-0

END SPAN CARRIED = 25-7-0

END WALL WIDTH = 5-8

APPLIED TO BACK SIDE OF BOTTOM CHORD.

- ADDTL LOADS BASED ON 55 % OF GSL.

THIS TRUSS IS DESIGNED FOR RESIDENTIAL OR SMALL BUILDING REQUIREMENTS OF PART 9, NBCC 2010

THIS DESIGN COMPLIES WITH:

- PART 9 OF OBC 2012, BCBC 2012, ABC 2014
- CSA 086-09
- TPIC 2011

(55 % OF 27.2 P.S.F. G.S.L. PLUS 8.4 P.S.F. RAIN LOAD) EQUALS 23.3 P.S.F. SPECIFIED ROOF LIVE LOAD

ALLOWABLE DEFL.(LL)= L/360 (0.20")

CALCULATED VERT. DEFL.(LL) = L/999 (0.05")

ALLOWABLE DEFL.(TL)= L/360 (0.20")

CALCULATED VERT. DEFL.(TL) = L/822 (0.09")

CSI: TC=0.18/1.00 (A-B:1), BC=0.48/1.00 (E-F:1), WB=0.35/1.00 (B-E:1), SSI=0.54/1.00 (E-F:1)

DOL LUMBER=1.00 NAIL=1.00 LS BEND=1.00
COMP=1.00 SHEAR=1.00 TENS=1.00

COMPANION LIVE LOAD FACTOR = 0.50

TRUSS PLATE MANUFACTURER IS NOT RESPONSIBLE FOR QUALITY CONTROL IN THE TRUSS MANUFACTURING PLANT .

NAIL VALUES

PLATE	GRIP(DRY)	SHEAR	SECTION
	(PSI)	(PLI)	(PLI)
	MAX	MIN	MAX
MT20	618	354	1667
			822
			2284
			1656

CONTINUED ON PAGE 2

READ ALL NOTES ON THIS PAGE AND ON ENGINEERING NOTE PAGE ENP-1. THIS NOTE PAGE IS AN INTEGRAL PART OF THIS DRAWING AS IT CONTAINS SPECIFICATIONS AND CRITERIA USED IN THE DESIGN OF THIS COMPONENT.



PLATES (table is in inches)

JT	TYPE	PLATES	W	LEN	Y	X
D	BMVW1+p	MT20	4.0	5.0		
E	BMWW+t	MT20	3.0	8.0		
F	BMV1+p	MT20	2.0	4.0		

PLATE PLACEMENT TOL. = 0.250 inches


PLATE ROTATION TOL. = 5.0 Deg.

JSI GRIP= 0.79 (E) (INPUT = 0.90)

JSI METAL= 0.39 (B) (INPUT = 1.00)

READ ALL NOTES ON THIS PAGE AND ON
ENGINEERING NOTE PAGE ENP-1. THIS
NOTE PAGE IS AN INTEGRAL PART OF
THIS DRAWING AS IT CONTAINS
SPECIFICATIONS AND CRITERIA USED IN
THE DESIGN OF THIS COMPONENT.





TOTAL WEIGHT = 26 lb

LUMBER
N. L. G. A. RULES

CHORDS	SIZE	DRY	LUMBER	DESCR.
A - C	2x4	DRY	No.2	SPF
C - D	2x4	DRY	No.2	SPF
E - D	2x4	DRY	No.2	SPF
G - B	2x4	DRY	No.2	SPF
G - E	2x4	DRY	No.2	SPF
ALL WEBS EXCEPT	2x3	DRY	No.2	SPF

DRY: SEASONED LUMBER.

PLATES (table is in inches)

JT TYPE	PLATES	W	LEN	Y	X
B TMVW-t	MT20	3.0	4.0	1.50	1.25
C TTWW-m	MT20	4.0	5.0	1.75	1.25
D TMV+p	MT20	2.0	4.0		
E BMVW1-t	MT20	3.0	4.0		
F BMWW-t	MT20	3.0	4.0		
G BMV1+p	MT20	2.0	4.0		

HANGERS NOTES
1) SPECIAL HANGER(S) OR CONNECTION(S) REQUIRED TO SUPPORT CONCENTRATED LOAD(S) 20.0 lbs FACTORED DOWN AT 3-1-5 ON TOP CHORD. DESIGN FOR UNSPECIFIED CONNECTION(S) IS DELEGATED TO THE BUILDING DESIGNER.

DIMENSIONS, SUPPORTS AND LOADINGS SPECIFIED BY FABRICATOR TO BE VERIFIED BY BUILDING DESIGNER

BEARINGS

	FACTORED GROSS REACTION	MAXIMUM FACTORED GROSS REACTION	INPUT BRG	REQRD BRG
JT	VERT	HORZ	DOWN	UPLIFT
E	272	0	272	0
G	383	0	383	0

A SUITABLE MECHANICAL CONNECTION IS REQUIRED AT JOINT E TO RESIST THE MAX FACTORED REACTIONS.

UNFACTORED REACTIONS

1ST LCASE	MAX/MIN. COMPONENT REACTIONS	SNOW	LIVE	PERM. LIVE	WIND	DEAD	SOIL
JT	COMBINED						
E	190	134 / 0	0 / 0	0 / 0	0 / 0	56 / 0	0 / 0
G	266	201 / 0	0 / 0	0 / 0	0 / 0	65 / 0	0 / 0

BEARING MATERIAL TO BE SPF NO.2 OR BETTER AT JOINT(S) G

BRACING
TOP CHORD TO BE SHEATHED OR MAX. PURLIN SPACING = 6.25 FT.
MAX. UNBRACED BOTTOM CHORD LENGTH = 10.00 FT OR RIGID CEILING DIRECTLY APPLIED.

ALL PITCH BREAKS AND PERIMETER CORNER JOINTS MUST BE Laterally RESTRAINED.

LOADING
TOTAL LOAD CASES: (4)

CHORDS					WEBS				
MEMB.	MAX. FACTORED FORCE (LBS)	FACTORED VERT. LOAD (PLF)	LC1 MAX. (LC)	MAX. UNBRACED LENGTH	MEMB.	MAX. FACTORED FORCE (LBS)	FACTORED MAX. CSI (LC)		
FR-TO		FROM	TO		FR-TO				
A-B	0 / 22	-77.4	-77.4	0.10 (1)	10.00	F-C	0 / 52	0.02 (4)	
B-C	-209 / 0	-77.4	-77.4	0.14 (1)	6.25	C-E	-243 / 0	0.06 (1)	
C-D	0 / 0	-68.5	-68.5	0.11 (1)	10.00	B-F	0 / 193	0.05 (1)	
E-D	-99 / 0	0.0	0.0	0.01 (1)	7.81				
G-B	-360 / 0	0.0	0.0	0.04 (1)	7.81				
G-F	0 / 0	-16.2	-16.2	0.04 (4)	10.00				
F-E	0 / 187	-16.2	-16.2	0.06 (4)	10.00				

FACTORED CONCENTRATED LOADS (LBS)

JT	LOC.	LC1	MAX-	MAX+	FACE	DIR.	TYPE
C	3-1-5	-20	-20	---	FRONT	VERT	TOTAL

DESIGN CRITERIA

SPECIFIED LOADS:

TOP CH.	LL	PSF
LL	23.3	PSF
DL	3.0	PSF
BOT CH.	LL	PSF
LL	0.0	PSF
DL	7.3	PSF
TOTAL LOAD	33.6	PSF

SPACING = 24.0 IN. C/C

LOADING IN FLAT SECTION BASED ON A SLOPE OF 2.00/12 MINIMUM

GIRDER TYPE: CPrimeHip
LEFT SETBACK = 3-1-5
RIGHT SETBACK = 0-0
END SETBACK = 2-0-0
END WALL WIDTH = 5-8
CORNER FRAMING TYPE: CONVENTIONAL
END JACK TYPE: CONVENTIONAL
APPLIED TO FRONT SIDE
- ADDTL LOADS BASED ON 55 % OF GSL.

THIS TRUSS IS DESIGNED FOR RESIDENTIAL OR SMALL BUILDING REQUIREMENTS OF PART 9, NBCC 2010

THIS DESIGN COMPLIES WITH:
- PART 9 OF OBC 2012, BCBC 2012, ABC 2014
- CSA 086-09
- TPIC 2011

(55 % OF 27.2 P.S.F. G.S.L. PLUS 8.4 P.S.F. RAIN LOAD) EQUALS 23.3 P.S.F. SPECIFIED ROOF LIVE LOAD

ALLOWABLE DEFL.(LL)= L/360 (0.20")
CALCULATED VERT. DEFL.(LL)= L/ 999 (0.00")
ALLOWABLE DEFL.(TL)= L/360 (0.20")
CALCULATED VERT. DEFL.(TL)= L/ 999 (0.00")

CSI: TC=0.14/1.00 (B-C:1), BC=0.06/1.00 (E-F:4), WB=0.06/1.00 (C-E:1), SSI=0.09/1.00 (B-C:1)

DOL LUMBER=1.00 NAIL=1.00 LS BEND=1.00
COMP=1.00 SHEAR=1.00 TENS= 1.00

COMPANION LIVE LOAD FACTOR = 0.50

TRUSS PLATE MANUFACTURER IS NOT RESPONSIBLE FOR QUALITY CONTROL IN THE TRUSS MANUFACTURING PLANT .

NAIL VALUES

PLATE	GRIP(DRY)	SHEAR (PSI)	SECTION (PLI)
MT20	618	354	1667 822 2284 1656

CONTINUED ON PAGE 2

READ ALL NOTES ON THIS PAGE AND ON ENGINEERING NOTE PAGE ENP-1. THIS NOTE PAGE IS AN INTEGRAL PART OF THIS DRAWING AS IT CONTAINS SPECIFICATIONS AND CRITERIA USED IN THE DESIGN OF THIS COMPONENT.




JOB NAME	TRUSS NAME	QUANTITY	PLY	JOB DESC.	DRWG NO.
NE0618-006	G05	1	1	GREEN YORK HOMES - GRANELLI HOME CORP - LIANA 3 ELEV 2	PAGE 12 OF 42
TRUSS DESC.					

Version 8.210 S Mar 12 2018 MiTek Industries, Inc. Sat Jun 2 15:02:04 2018 Page 2
ID:9 xLMwZ3WDKc3QXh8cyzSnzB2V3-7My3UPzIwbTO0746yOHZDmvCE3Tu?isI5HeAXAzAldH

PLATE PLACEMENT TOL. = 0.250 inches
PLATE ROTATION TOL. = 5.0 Deg.
JSI GRIP= 0.49 (B) (INPUT = 0.90)
JSI METAL= 0.12 (B) (INPUT = 1.00)

READ ALL NOTES ON THIS PAGE AND ON
ENGINEERING NOTE PAGE ENP-1. THIS
NOTE PAGE IS AN INTEGRAL PART OF
THIS DRAWING AS IT CONTAINS
SPECIFICATIONS AND CRITERIA USED IN
THE DESIGN OF THIS COMPONENT.





TOTAL WEIGHT = 33 lb [M]

LUMBER
N. L. G. A. RULES

CHORDS	SIZE	DRY	LUMBER	DESCR.
A - C	2x4	DRY	No.2	SPF
D - C	2x4	DRY	No.2	SPF
F - A	2x4	DRY	No.2	SPF
F - D	2x6	DRY	No.2	SPF

ALL WEBS 2x3 DRY No.2 SPF EXCEPT

DRY: SEASONED LUMBER.

PLATES (table is in inches)

JT	TYPE	PLATES	W	LEN	Y	X
A	TMVW-t	MT20	3.0	5.0	1.50	2.00
B	TMVW-t	MT20	3.0	5.0	1.50	2.25
C	TMV+p	MT20	2.0	4.0		
D	BMVW1-t	MT20	4.0	4.0		
E	BMVW1-t	MT20	4.0	4.0		
F	BMV1+p	MT20	2.0	4.0		

DIMENSIONS, SUPPORTS AND LOADINGS SPECIFIED BY FABRICATOR TO BE VERIFIED BY BUILDING DESIGNER

BEARINGS

JT	FACTORED GROSS REACTION		MAXIMUM FACTORED GROSS REACTION		INPUT BRG	REQRD BRG
	VERT	HORZ	DOWN	HORZ		
D	855	0	855	0	MECHANICAL	
F	855	0	855	0	5-8	5-8

A SUITABLE MECHANICAL CONNECTION IS REQUIRED AT JOINT D TO RESIST THE MAX FACTORED REACTIONS.

UNFACTORED REACTIONS							
	1ST LCASE	MAX./MIN. COMPONENT REACTIONS					
JT	COMBINED	SNOW	LIVE	PERM.LIVE	WIND	DEAD	SOIL
D	600	416 / 0	0 / 0	0 / 0	0 / 0	184 / 0	0 / 0
F	600	416 / 0	0 / 0	0 / 0	0 / 0	184 / 0	0 / 0

BEARING MATERIAL TO BE SPF NO.2 OR BETTER AT JOINT(S) F

BRACING
TOP CHORD TO BE SHEATHED OR MAX. PURLIN SPACING = 6.25 FT.
MAX. UNBRACED BOTTOM CHORD LENGTH = 10.00 FT OR RIGID CEILING DIRECTLY APPLIED.

ALL PITCH BREAKS AND PERIMETER CORNER JOINTS MUST BE Laterally RESTRAINED.

LOADING
TOTAL LOAD CASES: (4)

MEMB.	CHORDS				WEBS			
	MAX. FACTORED FORCE (LBS)	FACTORED VERT. LOAD (PLF)	LC1 MAX	CS1 (LC)	MAX. MEMB. UNBRAC LENGTH	FR-TO	MAX. FACTORED FORCE (LBS)	MAX. CS1 (LC)
FR-TO		FROM	TO					
A-B	-605 / 0	-77.4	-77.4	0.12 (1)	6.25	E-B	0 / 565	0.14 (1)
B-C	-14 / 0	-77.4	-77.4	0.12 (1)	6.25	B-D	-721 / 0	0.21 (1)
D-C	-90 / 0	0.0	0.0	0.04 (1)	7.81	A-E	0 / 540	0.13 (1)
F-A	-596 / 0	0.0	0.0	0.07 (1)	7.81			
F-E	0 / 0	-207.5	-207.5	0.12 (1)	10.00			
E-D	0 / 515	-207.5	-207.5	0.19 (1)	10.00			

DESIGN CRITERIA

SPECIFIED LOADS:				
TOP	CH.	LL	=	23.3 PSF
		DL	=	3.0 PSF
BOT	CH.	LL	=	0.0 PSF
		DL	=	7.3 PSF
TOTAL LOAD			=	33.6 PSF

SPACING = 24.0 IN. C/C

GIRDER TYPE: CStd Girder
START DISTANCE = 0-0
START SPAN CARRIED = 10-4-8
END DISTANCE = 6-0-0
END SPAN CARRIED = 10-4-8
END WALL WIDTH = 5-8
APPLIED TO BACK SIDE OF BOTTOM CHORD.
- ADDTL LOADS BASED ON 55 % OF GSL.

THIS TRUSS IS DESIGNED FOR RESIDENTIAL OR SMALL BUILDING REQUIREMENTS OF PART 9, NBCC 2010

THIS DESIGN COMPLIES WITH:
- PART 9 OF OBC 2012, BCBC 2012, ABC 2014
- CSA 086-09
- TPIC 2011

(55 % OF 27.2 P.S.F. G.S.L. PLUS 8.4 P.S.F. RAIN LOAD) EQUALS 23.3 P.S.F. SPECIFIED ROOF LIVE LOAD

ALLOWABLE DEFL.(LL)= L/360 (0.20")
CALCULATED VERT. DEFL.(LL)= L/999 (0.01")
ALLOWABLE DEFL.(TL)= L/360 (0.20")
CALCULATED VERT. DEFL.(TL)= L/999 (0.01")

CSI: TC=0.12/1.00 (A-B:1), BC=0.19/1.00 (D-E:1), WB=0.21/1.00 (B-D:1), SSI=0.24/1.00 (E-F:1)

DOL LUMBER=1.00 NAIL=1.00 LS BEND=1.00
COMP=1.00 SHEAR=1.00 TENS= 1.00

COMPANION LIVE LOAD FACTOR = 0.50

TRUSS PLATE MANUFACTURER IS NOT RESPONSIBLE FOR QUALITY CONTROL IN THE TRUSS MANUFACTURING PLANT .

NAIL VALUES

PLATE	GRIP(DRY)	SHEAR (PSI)	SECTION (PLI)
MT20	618	354	1667 822 2284 1656

PLATE PLACEMENT TOL. = 0.250 inches

PLATE ROTATION TOL. = 5.0 Deg.

CONTINUED ON PAGE 2



READ ALL NOTES ON THIS PAGE AND ON ENGINEERING NOTE PAGE ENP-1. THIS NOTE PAGE IS AN INTEGRAL PART OF THIS DRAWING AS IT CONTAINS SPECIFICATIONS AND CRITERIA USED IN THE DESIGN OF THIS COMPONENT.




JOB NAME	TRUSS NAME	QUANTITY	PLY	JOB DESC.	GREEN YORK HOMES - GRANELLI HOME CORP - LIANA 3 ELEV 2	DRWG NO.
NE0618-006	G06	1	1	TRUSS DESC.		PAGE 14 OF 42

Version 8.210 S Mar 12 2018 MiTek Industries, Inc. Sat Jun 2 15:02:05 2018 Page 2
ID:9_xLMwZ3WDKc3QXh8cyzSszB2V3-bYVVRilzNhvbFeHfIV5pCI_ROHTn8k5nRjXNk3czAldG

JSI GRIP= 0.85 (B) (INPUT = 0.90)
JSI METAL= 0.20 (A) (INPUT = 1.00)

READ ALL NOTES ON THIS PAGE AND ON
ENGINEERING NOTE PAGE ENP-1. THIS
NOTE PAGE IS AN INTEGRAL PART OF
THIS DRAWING AS IT CONTAINS
SPECIFICATIONS AND CRITERIA USED IN
THE DESIGN OF THIS COMPONENT.





TOTAL WEIGHT = 36 lb [M]

LUMBER
N. L. G. A. RULES

CHORDS	SIZE	DRY	LUMBER	DESCR.
A - B	2x4	DRY	No.2	SPF
B - D	2x4	DRY	No.2	SPF
D - E	2x4	DRY	No.2	SPF
J - A	2x4	DRY	No.2	SPF
F - E	2x4	DRY	No.2	SPF
J - F	2x4	DRY	No.2	SPF

ALL WEBS EXCEPT 2x3 DRY No.2 SPF

DRY: SEASONED LUMBER.

PLATES (table is in inches)

JT	TYPE	PLATES	W	LEN	Y	X
A	TMVW+p	MT20	4.0	4.0	1.25	2.00
B	TTWW-m	MT20	4.0	6.0	1.75	1.50
C	TMW+w	MT20	2.0	4.0		
D	TTWW-m	MT20	4.0	6.0	1.75	1.50
E	TMVW+p	MT20	4.0	4.0	1.25	2.00
F	BMV1+p	MT20	2.0	4.0		
G	BMWW-t	MT20	3.0	4.0	1.50	1.75
H	BMWW-t	MT20	3.0	8.0		
I	BMWW-t	MT20	3.0	4.0	1.50	1.75
J	BMV1+p	MT20	2.0	4.0		

HANGERS NOTES
1) SPECIAL HANGER(S) OR CONNECTION(S) REQUIRED TO SUPPORT CONCENTRATED LOAD(S) 10.7 lbs FACTORED DOWN AT 7-8-0, AND 10.7 lbs FACTORED DOWN AT 1-8-0 ON TOP CHORD. DESIGN FOR UNSPECIFIED CONNECTION(S) IS DELEGATED TO THE BUILDING DESIGNER.

DIMENSIONS, SUPPORTS AND LOADINGS SPECIFIED BY FABRICATOR TO BE VERIFIED BY BUILDING DESIGNER

BEARINGS

	FACTORED GROSS REACTION	MAXIMUM FACTORED GROSS REACTION	INPUT BRG	REQRD BRG
JT	VERT HORZ	DOWN HORZ UPLIFT	IN-SX	IN-SX
J	853 0	853 0 0	5-8	5-8
F	853 0	853 0 0	5-8	5-8

UNFACTORED REACTIONS

	1ST LCASE	MAX./MIN. COMPONENT REACTIONS					
JT	COMBINED	SNOW	LIVE	PERM.LIVE	WIND	DEAD	SOIL
J	598	418 / 0	0 / 0	0 / 0	0 / 0	180 / 0	0 / 0
F	598	418 / 0	0 / 0	0 / 0	0 / 0	180 / 0	0 / 0

BEARING MATERIAL TO BE SPF NO.2 OR BETTER AT JOINT(S) J, F

BRACING
TOP CHORD TO BE SHEATHED OR MAX. PURLIN SPACING = 5.98 FT.
MAX. UNBRACED BOTTOM CHORD LENGTH = 10.00 FT OR RIGID CEILING DIRECTLY APPLIED.

ALL PITCH BREAKS AND PERIMETER CORNER JOINTS MUST BE Laterally RESTRAINED.

LOADING
TOTAL LOAD CASES: (4)

CHORDS				WEBS			
MEMB.	MAX. FACTORED FORCE (LBS)	FACTORED VERT. LOAD (PLF)	MAX. LC1 (LC)	MAX. UNBRACED LENGTH	MEMB.	MAX. FACTORED FORCE (LBS)	MAX. LC1 (LC)
FR-TO		FROM TO			FR-TO		
A-B	-775 / 0	-77.4	-77.4 0.05 (1)	6.25	I-B	-5 / 32	0.01 (4)
B-C	-1066 / 0	-68.5	-68.5 0.10 (1)	5.98	B-H	0 / 505	0.12 (1)
C-D	-1066 / 0	-68.5	-68.5 0.10 (1)	5.98	H-C	-230 / 0	0.04 (1)
D-E	-776 / 0	-77.4	-77.4 0.05 (1)	6.25	H-D	0 / 504	0.12 (1)
J-A	-790 / 0	0.0	0.0 0.09 (1)	7.81	G-D	-4 / 32	0.01 (4)
F-E	-790 / 0	0.0	0.0 0.09 (1)	7.81	A-I	0 / 705	0.17 (1)
					G-E	0 / 706	0.17 (1)
J-I	0 / 0	-108.8	-108.8 0.09 (1)	10.00			
I-H	0 / 642	-108.8	-108.8 0.20 (1)	10.00			
H-G	0 / 642	-108.8	-108.8 0.20 (1)	10.00			
G-F	0 / 0	-108.8	-108.8 0.09 (1)	10.00			

FACTORED CONCENTRATED LOADS (LBS)

JT	LOC.	LC1	MAX-	MAX+	FACE	DIR.	TYPE
B	1-8-0	-11	-11	---	FRONT	VERT	TOTAL
D	7-8-0	-11	-11	---	FRONT	VERT	TOTAL

DESIGN CRITERIA

SPECIFIED LOADS:
TOP CH. LL = 23.3 PSF
DL = 3.0 PSF
BOT CH. LL = 0.0 PSF
DL = 7.3 PSF
TOTAL LOAD = 33.6 PSF

SPACING = 24.0 IN./C

LOADING IN FLAT SECTION BASED ON A SLOPE OF 2.00/12 MINIMUM

GIRDER TYPE: CPrimeHip
SIDE SETBACK = 1-8-0
END SETBACK = 2-0-0
END WALL WIDTH = 5-8
CORNER FRAMING TYPE: CONVENTIONAL
END JACK TYPE: CONVENTIONAL
APPLIED TO FRONT SIDE
- ADDTL LOADS BASED ON 55 % OF GSL.

GIRDER TYPE: CStdGirder
START DISTANCE = 0-0
START SPAN CARRIED = 5-10-8
END DISTANCE = 9-4-0
END SPAN CARRIED = 5-10-8
END WALL WIDTH = 0-0
APPLIED TO BACK SIDE OF BOTTOM CHORD.
- ADDTL LOADS BASED ON 55 % OF GSL.

THIS TRUSS IS DESIGNED FOR RESIDENTIAL OR SMALL BUILDING REQUIREMENTS OF PART 9, NBCC 2010

THIS DESIGN COMPLIES WITH:
- PART 9 OF OBC 2012, BCBC 2012, ABC 2014
- CSA 086-09
- TPIC 2011

(55 % OF 27.2 P.S.F. G.S.L. PLUS 8.4 P.S.F. RAIN LOAD) EQUALS 23.3 P.S.F. SPECIFIED ROOF LIVE LOAD

ALLOWABLE DEFL.(LL)= L/360 (0.31")
CALCULATED VERT. DEFL.(LL) = L/999 (0.02")
ALLOWABLE DEFL.(TL)= L/360 (0.31")
CALCULATED VERT. DEFL.(TL) = L/999 (0.03")

CSI: TC=0.10/1.00 (B-C:1), BC=0.20/1.00 (G-H:1), WB=0.17/1.00 (E-G:1), SSI=0.14/1.00 (H-I:1)

DOL LUMBER=1.00 NAIL=1.00 LS BEND=1.00
COMP=1.00 SHEAR=1.00 TENS= 1.00

COMPANION LIVE LOAD FACTOR = 0.50



READ ALL NOTES ON THIS PAGE AND ON ENGINEERING NOTE PAGE ENP-1. THIS NOTE PAGE IS AN INTEGRAL PART OF THIS DRAWING AS IT CONTAINS SPECIFICATIONS AND CRITERIA USED IN THE DESIGN OF THIS COMPONENT.

CONTINUED ON PAGE 2



JOB NAME	TRUSS NAME	QUANTITY	PLY	JOB DESC.	DRWG NO.
NE0618-006	G07	1	1	GREEN YORK HOMES - GRANELLI HOME CORP - LIANA 3 ELEV 2	PAGE 16 OF 42

Version 8.210 S Mar 12 2018 MiTek Industries, Inc. Sat Jun 2 15:02:05 2018 Page 2
ID:9_xLMwZ3WDKc3QXh8cyzSnzB2V3-bYVRIzNhbvFeHflV5pCl ROITmsk6HRJxNk3czAldG

TRUSS PLATE MANUFACTURER IS NOT RESPONSIBLE FOR QUALITY CONTROL IN THE TRUSS MANUFACTURING PLANT .

NAIL VALUES

PLATE	GRIP(DRY)	SHEAR	SECTION
	(PSI)	(PLI)	(PLI)
	MAX	MIN	MAX MIN
MT20	618	354 1667	822 2284 1656

PLATE PLACEMENT TOL. = 0.250 inches


PLATE ROTATION TOL. = 5.0 Deg.

JSI GRIP= 0.89 (D) (INPUT = 0.90)

JSI METAL= 0.24 (I) (INPUT = 1.00)

READ ALL NOTES ON THIS PAGE AND ON ENGINEERING NOTE PAGE ENP-1. THIS NOTE PAGE IS AN INTEGRAL PART OF THIS DRAWING AS IT CONTAINS SPECIFICATIONS AND CRITERIA USED IN THE DESIGN OF THIS COMPONENT.





LUMBER
N. L. G. A. RULES

CHORDS	SIZE	DRY	LUMBER	DESCR.
E - B	2x4	DRY	No.2	SPF
A - C	2x4	DRY	No.2	SPF
E - D	2x4	DRY	No.2	SPF

DRY: SEASONED LUMBER.

PLATES (table is in inches)

JT	TYPE	PLATES	W	LEN	Y	X
B	TMV+p	MT20	2.0	4.0		
E	BMV1+p	MT20	2.0	4.0		

DIMENSIONS, SUPPORTS AND LOADINGS SPECIFIED BY FABRICATOR TO BE VERIFIED BY BUILDING DESIGNER

BEARINGS

JT	FACTORED GROSS REACTION		MAXIMUM FACTORED GROSS REACTION		INPUT BRG	REQD BRG
	VERT	HORZ	DOWN	HORZ		
E	256	0	256	0	5-8	5-8
C	56	0	56	0	1-8	1-8
D	46	0	51	0	1-8	1-8

SEE MITEK STANDARD DETAIL B37579H FOR CONNECTION TO JOINT(S) C , D

UNFACTORED REACTIONS

JT	1ST LCASE	MAX./MIN. COMPONENT REACTIONS					
	COMBINED	SNOW	LIVE	PERM.LIVE	WIND	DEAD	SOIL
E	181	115 / 0	0 / 0	0 / 0	0 / 0	66 / 0	0 / 0
C	38	34 / 0	0 / 0	0 / 0	0 / 0	4 / 0	0 / 0
D	37	0 / 0	0 / 0	0 / 0	0 / 0	37 / 0	0 / 0

BEARING MATERIAL TO BE SPF NO.2 OR BETTER AT JOINT(S) E, C

BRACING

TOP CHORD TO BE SHEATHED OR MAX. PURLIN SPACING = 10.00 FT.
MAX. UNBRACED BOTTOM CHORD LENGTH = 10.00 FT OR RIGID CEILING DIRECTLY APPLIED.

ALL PITCH BREAKS AND PERIMETER CORNER JOINTS MUST BE Laterally RESTRAINED.

LOADING

TOTAL LOAD CASES: (4)

MEMB.	MAX. FACTORED FORCE (LBS)	FACTORED VERT. LOAD (PLF)	CHORDS			MAX. UNBRACED LENGTH	MEMB. FORCE (LBS)	MAX. FACTORED FORCE (LBS)	MAX. FACTORED CSI (LC)
			FROM	TO	LC1				
FR-TO									
E-B	-192 / 0	0.0	0.0	0.11 (4)		7.81			
A-B	0 / 28	-77.4	-77.4	0.09 (1)		10.00			
B-C	-10 / 0	-77.4	-77.4	0.04 (1)		10.00			
E-D	0 / 0	-18.2	-18.2	0.13 (4)		10.00			

DESIGN CRITERIA

SPECIFIED LOADS:

TOP CH.	LL =	23.3	PSF
	DL =	3.0	PSF
BOT CH.	LL =	0.0	PSF
	DL =	7.3	PSF
TOTAL LOAD	=	33.6	PSF

SPACING = 24.0 IN. C/C

THIS TRUSS IS DESIGNED FOR RESIDENTIAL OR SMALL BUILDING REQUIREMENTS OF PART 9, NBCC 2010

THIS DESIGN COMPLIES WITH:
- PART 9 OF OBC 2012 , BCBC 2012 , ABC 2014
- CSA 086-09
- TPIC 2011

DESIGN ASSUMPTIONS
- OVERHANG NOT TO BE ALTERED OR CUT OFF.

(55 % OF 27.2 P.S.F. G.S.L. PLUS 8.4 P.S.F. RAIN LOAD) EQUALS 23.3 P.S.F. SPECIFIED ROOF LIVE LOAD

ALLOWABLE DEFL.(LL)= L/360 (0.20")
CALCULATED VERT. DEFL.(LL)= L/ 999 (0.00")
ALLOWABLE DEFL.(TL)= L/360 (0.20")
CALCULATED VERT. DEFL.(TL)= L/ 999 (0.04")

CSI: TC=0.11/1.00 (B-E:4) , BC=0.13/1.00 (D-E:4) , WB=0.00/1.00 (n/a:0) , SSI=0.09/1.00 (D-E:4)

DOL LUMBER=1.00 NAIL=1.00 LS BEND=1.10
COMP=1.10 SHEAR=1.10 TENS= 1.10

COMPANION LIVE LOAD FACTOR = 0.50

AUTOSOLVE RIGHT HEEL ONLY

TRUSS PLATE MANUFACTURER IS NOT RESPONSIBLE FOR QUALITY CONTROL IN THE TRUSS MANUFACTURING PLANT .

NAIL VALUES

PLATE	GRIP(DRY)	SHEAR (PSI)	SECTION (PLI)
MT20	618	354	1667
	822	2284	1656

PLATE PLACEMENT TOL. = 0.250 inches


PLATE ROTATION TOL. = 5.0 Deg.

JSI GRIP= 0.12 (B) (INPUT = 0.90)
JSI METAL= 0.05 (B) (INPUT = 1.00)



READ ALL NOTES ON THIS PAGE AND ON ENGINEERING NOTE PAGE ENP-1. THIS NOTE PAGE IS AN INTEGRAL PART OF THIS DRAWING AS IT CONTAINS SPECIFICATIONS AND CRITERIA USED IN THE DESIGN OF THIS COMPONENT.





TOTAL WEIGHT = 13 lb [M][F]

LUMBER				DESCR.	
N. L. G. A. RULES					
CHORDS	SIZE	LUMBER	DRY	No.2	SPF
D - A	2x4	DRY	No.2	SPF	
A - B	2x4	DRY	No.2	SPF	
D - C	2x4	DRY	No.2	SPF	

DRY: SEASONED LUMBER.

BEARINGS

JT	FACTORED GROSS REACTION		MAXIMUM FACTORED GROSS REACTION		INPUT BRG	REQRD BRG
	VERT	HORZ	DOWN	HORZ		
D	201	0	201	0	MECHANICAL	
B	143	0	143	0	1-8	1-8
C	56	0	56	0	1-8	1-8

A SUITABLE MECHANICAL CONNECTION IS REQUIRED AT JOINT D TO RESIST THE MAX FACTORED REACTIONS.

PLATES (table is in inches)

JT	TYPE	PLATES	W	LEN	Y	X
A	TMV+p	MT20	2.0	4.0		
D	BMV1+p	MT20	2.0	4.0		

SEE MITEK STANDARD DETAIL B37579H FOR CONNECTION TO JOINT(S) B , C

UNFACTORED REACTIONS

JT	1ST CASE COMBINED	MAX./MIN. COMPONENT REACTIONS					
		SNOW	LIVE	PERM. LIVE	WIND	DEAD	SOIL
D	143	91/0	0/0	0/0	0/0	52/0	0/0
B	98	81/0	0/0	0/0	0/0	18/0	0/0
C	44	5/0	0/0	0/0	0/0	39/0	0/0

BRACING

TOP CHORD TO BE SHEATHED OR MAX. PURLIN SPACING = 10.00 FT.

MAX. UNBRACED BOTTOM CHORD LENGTH = 10.00 FT OR RIGID CEILING DIRECTLY APPLIED.

ALL PITCH BREAKS AND PERIMETER CORNER JOINTS MUST BE Laterally RESTRAINED.

LOADING

TOTAL LOAD CASES: (4)

CHORDS				WEBS			
MEMB.	MAX. FACTORED FORCE (LBS)	FACTORED VERT. LOAD (PLF)	LC1 MAX	MEMB. UNBRAC LENGTH	MEMB. MAX. FACTORED FORCE (LBS)	MAX. FACTORED CSI (LC)	
FR-TO		FROM	TO		FR-TO		
D-A	-150/0	0.0	0.0	0.06 (4)	7.81		
A-B	-2/5	-77.4	-77.4	0.17 (1)	10.00		
D-C	0/0	-18.2	-18.2	0.15 (4)	10.00		

DESIGN CRITERIA

SPECIFIED LOADS:

TOP CH.	LL	=	23.3	PSF
	DL	=	3.0	PSF
BOT CH.	LL	=	0.0	PSF
	DL	=	7.3	PSF
TOTAL LOAD	=	33.6	PSF	

SPACING = 24.0 IN. C/C

THIS TRUSS IS DESIGNED FOR RESIDENTIAL OR SMALL BUILDING REQUIREMENTS OF PART 9, NBCC 2010

THIS DESIGN COMPLIES WITH:

- PART 9 OF OBC 2012, CBC 2012, ABC 2014
- CSA 086-09
- TPIC 2011

(55 % OF 27.2 P.S.F. G.S.L. PLUS 8.4 P.S.F. RAIN LOAD) EQUALS 23.3 P.S.F. SPECIFIED ROOF LIVE LOAD

ALLOWABLE DEFL.(LL)= L/360 (0.20")

CALCULATED VERT. DEFL.(LL) = L/999 (0.01")

ALLOWABLE DEFL.(TL)= L/360 (0.20")

CALCULATED VERT. DEFL.(TL) = L/999 (0.06")

CSI: TC=0.17/1.00 (A-B:1), BC=0.15/1.00 (C-D:4), WB=0.00/1.00 (n/a:0), SSI=0.10/1.00 (A-B:1)

DOL LUMBER=1.00 NAIL=1.00 LS BEND=1.10

COMP=1.10 SHEAR=1.10 TENS= 1.10

COMPANION LIVE LOAD FACTOR = 0.50

AUTOSOLVE RIGHT HEEL ONLY

TRUSS PLATE MANUFACTURER IS NOT RESPONSIBLE FOR QUALITY CONTROL IN THE TRUSS MANUFACTURING PLANT .

NAIL VALUES

PLATE	GRIP(DRY)	SHEAR	SECTION
	(PSI)	(PLI)	(PLI)
	MAX MIN	MAX MIN	MAX MIN
MT20	618 354	1667 822	2284 1656

PLATE PLACEMENT TOL. = 0.250 inches

PLATE ROTATION TOL. = 5.0 Deg.


JSI GRIP= 0.10 (A) (INPUT = 0.90)

JSI METAL= 0.04 (A) (INPUT = 1.00)



READ ALL NOTES ON THIS PAGE AND ON ENGINEERING NOTE PAGE ENP-1. THIS NOTE PAGE IS AN INTEGRAL PART OF THIS DRAWING AS IT CONTAINS SPECIFICATIONS AND CRITERIA USED IN THE DESIGN OF THIS COMPONENT.





TOTAL WEIGHT = 2 X 18 = 36 lb

LUMBER

N. L. G. A. RULES				
CHORDS	SIZE		LUMBER	DESCR.
E - B	2x4	DRY	No.2	SPF
A - C	2x4	DRY	No.2	SPF
E - D	2x4	DRY	No.2	SPF

DRY; SEASONED LUMBER.

PLATES (table is in inches)

JT	TYPE	PLATES	W	LEN	Y	X
B	TMV+p	MT20	2.0	4.0		
E	BMV1+p	MT20	2.0	4.0		

DIMENSIONS, SUPPORTS AND LOADINGS SPECIFIED BY FABRICATOR TO BE VERIFIED BY BUILDING DESIGNER

BUILDING BEARINGS

FACTORED GROSS REACTION			MAXIMUM FACTORED GROSS REACTION			INPUT BRG	REQD BRG
JT	VERT	HORZ	DOWN	HORZ	UPLIFT	IN-SX	IN-SX
E	454	0	454	0	0	5-8	5-8
C	174	0	174	0	0	1-8	1-8
D	46	0	51	0	0	1-8	1-8

SEE MITEK STANDARD DETAIL B37579H FOR CONNECTION TO JOINT(S) C, D

UNFACTORED REACTIONS

JT	1ST LCASE	MAX./MIN. COMPONENT REACTIONS					
	COMBINED	SNOW	LIVE	PERM.LIVE	WIND	DEAD	SOIL
E	316	235 / 0	0 / 0	0 / 0	0 / 0	81 / 0	0 / 0
C	118	105 / 0	0 / 0	0 / 0	0 / 0	14 / 0	0 / 0
D	37	0 / 0	0 / 0	0 / 0	0 / 0	37 / 0	0 / 0

BEARING MATERIAL TO BE SPF NO.2 OR BETTER AT JOINT(S) E

BRACING

BRACING
TOP CHORD TO BE SHEATHED OR MAX. PURLIN SPACING = 6.25 FT.
MAX. UNBRACED BOTTOM CHORD LENGTH = 10.00 FT OR RIGID CEILING DIRECTLY
APPLIED

ALL PITCH BREAKS AND PERIMETER CORNER JOINTS MUST BE LATERALLY RESTRAINED.

LOADING

TOTAL LOAD CASES: (4)

CHORDS				WEBS			
MEMB.	MAX. FACTORED FORCE (LBS)	FACTORED VERT. LOAD (PLF)	MAX LOAD CSI (LC)	MAX. UNBRAC LENGTH	MEMB.	MAX. FACTORED FORCE (LBS)	MAX LOAD CSI (LC)
FR-TO		FROM TO		FR-TO			
E-B	-390 / 0	0.0	0.0 0.11 (4)	7.81			
A-B	0 / 28	-77.4	-77.4 0.09 (1)	10.00			
B-C	-32 / 0	-77.4	-77.4 0.36 (1)	6.25			
E-D	0 / 0	-18.2	-18.2 0.13 (4)	10.00			

DESIGN CRITERIA

SPECIFIED LOADS:

TOP	CH.	LL =	23.3	PSF
		DL =	3.0	PSF
BOT	CH.	LL =	0.0	PSF
		DL =	7.3	PSF
TOTAL LOAD		=	33.6	PSF

SPACING = 24.0 IN. C/C

THIS TRUSS IS DESIGNED FOR RESIDENTIAL
OR SMALL BUILDING REQUIREMENTS OF
PART 9, NBCC 2010

THIS DESIGN COMPLIES WITH:
- PART 9 OF OBC 2012 , BCBC 2012 , ABC 2014
- CSA 086-09
- TPIC 2011

DESIGN ASSUMPTIONS

DESIGN ASSUMPTIONS
-OVERHANG NOT TO BE ALTERED OR CUT
OFF

(55 % OF 27.2 P.S.F. G.S.L. PLUS 8.4 P.S.F. RAIN LOAD) EQUALS 23.3 P.S.F. SPECIFIED ROOF LIVE LOAD

ALLOWABLE DEFL.(LL)= L/360 (0.20")
CALCULATED VERT. DEFL.(LL) = L/ 999 (0.00")
ALLOWABLE DEFL.(TL)= L/360 (0.20")
CALCULATED VERT. DEFL.(TL) = L/ 999 (0.04")

CSI: TC=0.36/1.00 (B-C:1) , BC=0.13/1.00 (D-E:4) ,
WB=0.00/1.00 (n/a:0) , SSI=0.19/1.00 (B-C:1)

DOL LUMBER=1.00 NAIL=1.00 LS BEND=1.10
COMP=1.10 SHEAR=1.10 TENS= 1.10

COMPANION LIVE LOAD FACTOR = 0.50

AUTOSOLVE RIGHT HEEL ONLY

TRUSS PLATE MANUFACTURER IS NOT RESPONSIBLE FOR QUALITY CONTROL IN THE TRUSS MANUFACTURING PLANT.

NAIL VALUES	GRIP(DRY)		SHEAR		SECTION	
	(PSI)		(PLI)		(PLI)	
	MAX	MIN	MAX	MIN	MAX	MIN
MT20	618	354	1667	822	2284	1656

PLATE PLACEMENT TOL. = 0.250 inches


PLATE ROTATION TOL. = 5.0 Deg

JSI GRIP= 0.25 (B) (INPUT = 0.90)
JSI METAL= 0.10 (B) (INPUT = 1.00)



**READ ALL NOTES ON THIS PAGE AND ON
ENGINEERING NOTE PAGE ENP-1. THIS
NOTE PAGE IS AN INTEGRAL PART OF
THIS DRAWING AS IT CONTAINS
SPECIFICATIONS AND CRITERIA USED IN
THE DESIGN OF THIS COMPONENT.**





Scale = 1:30.6

TOTAL WEIGHT = 3 X 16 = 48 lb

LUMBER
N. L. G. A. RULES
CHORDS SIZE LUMBER DESCR.
D - A 2x4 DRY No.2 SPF
A - B 2x4 DRY No.2 SPF
D - C 2x4 DRY No.2 SPF

DRY: SEASONED LUMBER.

PLATES (table is in inches)
JT TYPE PLATES W LEN Y X
A TMV+p MT20 2.0 4.0
D BMV1+p MT20 2.0 4.0

DIMENSIONS, SUPPORTS AND LOADINGS SPECIFIED BY FABRICATOR TO BE VERIFIED BY BUILDING DESIGNER

JT	FACTORED GROSS REACTION		MAXIMUM FACTORED GROSS REACTION		INPUT BRG	REQRD BRG
	VERT	HORZ	DOWN	HORZ		
D	281	0	281	0	MECHANICAL	
B	207	0	207	0	1-8	1-8
C	73	0	73	0	1-8	1-8

A SUITABLE MECHANICAL CONNECTION IS REQUIRED AT JOINT D TO RESIST THE MAX FACTORED REACTIONS.

SEE MITEK STANDARD DETAIL B37579H FOR CONNECTION TO JOINT(S) B , C

UNFACTORED REACTIONS

JT	1ST LCASE	MAX./MIN. COMPONENT REACTIONS				DEAD	SOIL
		COMBINED	SNOW	LIVE	PERM.LIVE		
D	197	137 / 0	0 / 0	0 / 0	0 / 0	61 / 0	0 / 0
B	142	122 / 0	0 / 0	0 / 0	0 / 0	20 / 0	0 / 0
C	56	15 / 0	0 / 0	0 / 0	0 / 0	41 / 0	0 / 0

BRACING

TOP CHORD TO BE SHEATHED OR MAX. PURLIN SPACING = 6.25 FT.
MAX. UNBRACED BOTTOM CHORD LENGTH = 10.00 FT OR RIGID CEILING DIRECTLY APPLIED.

ALL PITCH BREAKS AND PERIMETER CORNER JOINTS MUST BE Laterally RESTRAINED.

LOADING

TOTAL LOAD CASES: (4)

CHORDS				WEBS			
MEMB.	MAX. FACTORED FORCE (LBS)	FACTORED VERT. LOAD (PLF)	LC1 MAX CSI (LC)	MEMB. UNBRAC LENGTH	MEMB. MAX. FACTORED FORCE (LBS)	MAX. FACTORED CSI (LC)	
FR-TO		FROM	TO		FR-TO		
D-A	-247 / 0	0.0	0.0	0.14 (1)	7.81		
A-B	-11 / 2	-77.4	-77.4	0.39 (1)	6.25		
D-C	0 / 0	-18.2	-18.2	0.20 (1)	10.00		

DESIGN CRITERIA

SPECIFIED LOADS:
TOP CH. LL = 23.3 PSF
DL = 3.0 PSF
BOT CH. LL = 0.0 PSF
DL = 7.3 PSF
TOTAL LOAD = 33.6 PSF

SPACING = 24.0 IN. C/C

THIS TRUSS IS DESIGNED FOR RESIDENTIAL OR SMALL BUILDING REQUIREMENTS OF PART 9, NBCC 2010

THIS DESIGN COMPLIES WITH:
- PART 9 OF OBC 2012, BCBC 2012, ABC 2014
- CSA 086-09
- TPIC 2011

(55 % OF 27.2 P.S.F. G.S.L. PLUS 8.4 P.S.F. RAIN LOAD) EQUALS 23.3 P.S.F. SPECIFIED ROOF LIVE LOAD

ALLOWABLE DEFL.(LL)= L/360 (0.20")
CALCULATED VERT. DEFL.(LL) = L/ 999 (0.05")
ALLOWABLE DEFL.(TL)= L/360 (0.20")
CALCULATED VERT. DEFL.(TL) = L/ 662 (0.11")

CSI: TC=0.39/1.00 (A-B:1) , BC=0.20/1.00 (C-D:1) , WB=0.00/1.00 (n/a:0) , SSI=0.16/1.00 (A-B:1)

DOL LUMBER=1.00 NAIL=1.00 LS BEND=1.10
COMP=1.10 SHEAR=1.10 TENS= 1.10

COMPANION LIVE LOAD FACTOR = 0.50

AUTOSOLVE RIGHT HEEL ONLY

TRUSS PLATE MANUFACTURER IS NOT RESPONSIBLE FOR QUALITY CONTROL IN THE TRUSS MANUFACTURING PLANT .

NAIL VALUES
PLATE GRIP(DRY) SHEAR SECTION
(PSI) (PLI) (PLI)
MAX MIN MAX MIN MAX MIN
MT20 618 354 1667 822 2284 1656

PLATE PLACEMENT TOL. = 0.250 inches

PLATE ROTATION TOL. = 5.0 Deg.


JSI GRIP= 0.16 (A) (INPUT = 0.90)
JSI METAL= 0.06 (A) (INPUT = 1.00)



READ ALL NOTES ON THIS PAGE AND ON ENGINEERING NOTE PAGE ENP-1. THIS NOTE PAGE IS AN INTEGRAL PART OF THIS DRAWING AS IT CONTAINS SPECIFICATIONS AND CRITERIA USED IN THE DESIGN OF THIS COMPONENT.



Version 8.210 S Mar 12 2018 MITek Industries, Inc. Sat Jun 2 15:02:08 2018 Page 1
ID:9_xLMwZ3WDKc3QXh8cyzSnzB2V3-77BaKn0F_q_pVIOtBDMvNc3vGgqSxVkt0vcOgxzAldD



TOTAL WEIGHT = 8 lb [M]

LUMBER
N. L. G. A. RULES

CHORDS	SIZE	DRY	LUMBER	DESCR.
E - B	2x4	DRY	No.2	SPF
A - C	2x4	DRY	No.2	SPF
E - D	2x4	DRY	No.2	SPF

DRY: SEASONED LUMBER.

PLATES (table is in inches)

JT	TYPE	PLATES	W	LEN	Y	X
B	TMV+p	MT20	2.0	4.0		
E	BMV1+p	MT20	2.0	4.0		

DIMENSIONS, SUPPORTS AND LOADINGS SPECIFIED BY FABRICATOR TO BE VERIFIED BY BUILDING DESIGNER

BEARINGS

JT	FACTORED GROSS REACTION		MAXIMUM FACTORED GROSS REACTION		INPUT BRG	REQRD BRG
	VERT	HORZ	DOWN	HORZ		
E	212	0	212	0	5-8	5-8
C	56	0	56	0	1-8	1-8
D	16	0	18	0	1-8	1-8

SEE MITEK STANDARD DETAIL B37579H FOR CONNECTION TO JOINT(S) C, D

UNFACTORED REACTIONS

JT	1ST LCASE	MAX./MIN. COMPONENT REACTIONS					
		SNOW	LIVE	PERM.LIVE	WIND	DEAD	SOIL
E	146	115/0	0/0	0/0	0/0	31/0	0/0
C	38	34/0	0/0	0/0	0/0	4/0	0/0
D	13	0/0	0/0	0/0	0/0	13/0	0/0

BEARING MATERIAL TO BE SPF NO.2 OR BETTER AT JOINT(S) E, C

BRACING
TOP CHORD TO BE SHEATHED OR MAX. PURLIN SPACING = 10.00 FT.
MAX. UNBRACED BOTTOM CHORD LENGTH = 10.00 FT OR RIGID CEILING DIRECTLY APPLIED.
ALL PITCH BREAKS AND PERIMETER CORNER JOINTS MUST BE Laterally RESTRAINED.

LOADING
TOTAL LOAD CASES: (5)

MEMB.	CHORDS				WEBS			
	MAX. FACTORED FORCE (LBS)	FACTORED VERT. LOAD (PLF)	LC1	MAX. CSI (LC)	MAX. MEMB. UNBRACED LENGTH FR-TO	MAX. FACTORED FORCE (LBS)	FACTORED VERT. LOAD (PLF)	MAX. CSI (LC)
E-B	-192/0	0.0	0.0	0.01 (4)	7.81			
A-B	0/28	-77.4	-77.4	0.09 (1)	10.00			
B-C	-10/0	-77.4	-77.4	0.05 (1)	10.00			
E-D	0/0	-18.2	-18.2	0.02 (4)	10.00			

CANTILEVER ANALYSIS HAS BEEN CONSIDERED IN THIS DESIGN

DESIGN CRITERIA

SPECIFIED LOADS:
TOP CH. LL = 23.3 PSF
DL = 3.0 PSF
BOT CH. LL = 0.0 PSF
DL = 7.3 PSF
TOTAL LOAD = 33.6 PSF

SPACING = 24.0 IN. C/C

THIS TRUSS IS DESIGNED FOR RESIDENTIAL OR SMALL BUILDING REQUIREMENTS OF PART 9, NBCC 2010

THIS DESIGN COMPLIES WITH:
- PART 9 OF OBC 2012, BCBC 2012, ABC 2014
- CSA 086-09
- TPIC 2011

DESIGN ASSUMPTIONS
- OVERHANG NOT TO BE ALTERED OR CUT OFF.

(55 % OF 27.2 P.S.F. G.S.L. PLUS 8.4 P.S.F. RAIN LOAD) EQUALS 23.3 P.S.F. SPECIFIED ROOF LIVE LOAD

ALLOWABLE DEFL.(LL)= L/360 (0.19")
CALCULATED VERT. DEFL.(LL)= L/999 (0.00")
ALLOWABLE DEFL.(TL)= L/360 (0.19")
CALCULATED VERT. DEFL.(TL)= L/999 (0.00")

CSI: TC=0.09/1.00 (A-B:1), BC=0.02/1.00 (D-E:4), WB=0.00/1.00 (n/a:0), SSI=0.06/1.00 (A-B:1)

DOL LUMBER=1.00 NAIL=1.00 LS BEND=1.10
COMP=1.10 SHEAR=1.10 TENS= 1.10

COMPANION LIVE LOAD FACTOR = 0.50

AUTOSOLVE RIGHT HEEL ONLY

TRUSS PLATE MANUFACTURER IS NOT RESPONSIBLE FOR QUALITY CONTROL IN THE TRUSS MANUFACTURING PLANT .

NAIL VALUES
PLATE GRIP(DRY) SHEAR SECTION (PSI) (PLI) (PLI)
MAX MIN MAX MIN MAX MIN
MT20 618 354 1667 822 2284 1656

PLATE PLACEMENT TOL. = 0.250 inches


PLATE ROTATION TOL. = 5.0 Deg.

JSI GRIP= 0.12 (B) (INPUT = 0.90)
JSI METAL= 0.05 (B) (INPUT = 1.00)



READ ALL NOTES ON THIS PAGE AND ON ENGINEERING NOTE PAGE ENP-1. THIS NOTE PAGE IS AN INTEGRAL PART OF THIS DRAWING AS IT CONTAINS SPECIFICATIONS AND CRITERIA USED IN THE DESIGN OF THIS COMPONENT.





Scale = 1:23.1

TOTAL WEIGHT = 11 lb [M]

LUMBER
N. L. G. A. RULES

CHORDS	SIZE	DRY	LUMBER	DESCR.
E - B	2x4	DRY	No.2	SPF
A - C	2x4	DRY	No.2	SPF
E - D	2x4	DRY	No.2	SPF

DRY: SEASONED LUMBER.

PLATES (table is in inches)

JT	TYPE	PLATES	W	LEN	Y	X
B	TMV+p	MT20	2.0	4.0		
E	BMV1+p	MT20	2.0	4.0		

DIMENSIONS, SUPPORTS AND LOADINGS SPECIFIED BY FABRICATOR TO BE VERIFIED BY BUILDING DESIGNER

BEARINGS

JT	FACTORED GROSS REACTION		MAXIMUM FACTORED GROSS REACTION		INPUT BRG	REQD BRG
	VERT	HORZ	DOWN	HORZ		
E	309	0	309	0	5-8	5-8
C	114	0	114	0	1-8	1-8
D	16	0	18	0	1-8	1-8

SEE MITEK STANDARD DETAIL B37579H FOR CONNECTION TO JOINT(S) C , D

UNFACTORED REACTIONS							
	1ST LCASE	MAX./MIN. COMPONENT REACTIONS					
JT	COMBINED	SNOW	LIVE	PERM.LIVE	WIND	DEAD	SOIL
E	212	174 / 0	0 / 0	0 / 0	0 / 0	38 / 0	0 / 0
C	77	68 / 0	0 / 0	0 / 0	0 / 0	9 / 0	0 / 0
D	13	0 / 0	0 / 0	0 / 0	0 / 0	13 / 0	0 / 0

BEARING MATERIAL TO BE SPF NO.2 OR BETTER AT JOINT(S) E

BRACING
TOP CHORD TO BE SHEATHED OR MAX. PURLIN SPACING = 6.25 FT.
MAX. UNBRACED BOTTOM CHORD LENGTH = 10.00 FT OR RIGID CEILING DIRECTLY APPLIED.
ALL PITCH BREAKS AND PERIMETER CORNER JOINTS MUST BE Laterally RESTRAINED.

LOADING
TOTAL LOAD CASES: (4)

CHORDS					WEBS				
MEMB.	MAX. FORCE (LBS)	FACTORED VERT. LOAD (PLF)	LC1	MAX. CSI (LC)	MAX. UNBRAC LENGTH	MEMB. FR-TO	MAX. FORCE (LBS)	FACTORED VERT. LOAD (PLF)	MAX. CSI (LC)
FR-TO		FROM	TO						
E-B	-289 / 0	0.0	0.0	0.01 (4)	7.81				
A-B	0 / 28	-77.4	-77.4	0.09 (1)	10.00				
B-C	-21 / 0	-77.4	-77.4	0.20 (1)	6.25				
E-D	0 / 0	-18.2	-18.2	0.02 (4)	10.00				

DESIGN CRITERIA

SPECIFIED LOADS:
TOP CH. LL = 23.3 PSF
DL = 3.0 PSF
BOT CH. LL = 0.0 PSF
DL = 7.3 PSF
TOTAL LOAD = 33.6 PSF

SPACING = 24.0 IN. C/C

THIS TRUSS IS DESIGNED FOR RESIDENTIAL OR SMALL BUILDING REQUIREMENTS OF PART 9, NBCC 2010

THIS DESIGN COMPLIES WITH:
- PART 9 OF OBC 2012, BCBC 2012, ABC 2014
- CSA 086-09
- TPIC 2011

DESIGN ASSUMPTIONS
- OVERHANG NOT TO BE ALTERED OR CUT OFF.

(55 % OF 27.2 P.S.F. G.S.L. PLUS 8.4 P.S.F. RAIN LOAD) EQUALS 23.3 P.S.F. SPECIFIED ROOF LIVE LOAD

ALLOWABLE DEFL.(LL)= L/360 (0.19")
CALCULATED VERT. DEFL.(LL)= L/ 999 (0.00")
ALLOWABLE DEFL.(TL)= L/360 (0.19")
CALCULATED VERT. DEFL.(TL)= L/ 999 (0.00")

CSI: TC=0.20/1.00 (B-C:1), BC=0.02/1.00 (D-E:4), WB=0.00/1.00 (n/a:0), SSI=0.12/1.00 (B-C:1)

DOL LUMBER=1.00 NAIL=1.00 LS BEND=1.10
COMP=1.10 SHEAR=1.10 TENS= 1.10

COMPANION LIVE LOAD FACTOR = 0.50

AUTOSOLVE RIGHT HEEL ONLY

TRUSS PLATE MANUFACTURER IS NOT RESPONSIBLE FOR QUALITY CONTROL IN THE TRUSS MANUFACTURING PLANT .

NAIL VALUES

PLATE	GRIP(DRY)	SHEAR (PSI)	SECTION (PLI)
MT20	618	354	1667
	822	2284	1656

PLATE PLACEMENT TOL. = 0.250 inches

PLATE ROTATION TOL. = 5.0 Deg.

JSI GRIP= 0.19 (B) (INPUT = 0.90)
JSI METAL= 0.07 (B) (INPUT = 1.00)




READ ALL NOTES ON THIS PAGE AND ON ENGINEERING NOTE PAGE ENP-1. THIS NOTE PAGE IS AN INTEGRAL PART OF THIS DRAWING AS IT CONTAINS SPECIFICATIONS AND CRITERIA USED IN THE DESIGN OF THIS COMPONENT.



JOB NAME	TRUSS NAME	QUANTITY	PLY	JOB DESC.	GREEN YORK HOMES - GRANELLI HOME CORP - LIANA 3 ELEV 2	DRWG NO.
NE0618-006	J06	16	1	TRUSS DESC.		PAGE 23 OF 42

Version 8.210 S Mar 12 2018 MITek Industries, Inc. Sat Jun 2 15:02:09 2018 Page 1
ID:9_xLMwZ3WDKc3QXh8cyzSnzB2V3-TJlyY60ti76g6vz4kxt8wqc0V48ggy_1EZLxC0zAIdC



Scale = 1:23.4

TOTAL WEIGHT = 16 X 17 = 271 lb [M][F]

LUMBER					DESCR.
N. L. G. A. RULES	SIZE	LUMBER			
CHORDS	2x4	DRY	No.2		SPF
E - B	2x4	DRY	No.2		SPF
A - C	2x4	DRY	No.2		SPF
E - D	2x4	DRY	No.2		SPF

DRY: SEASONED LUMBER.

PLATES (table is in inches)					
JT	TYPE	PLATES	W	LEN	Y
B	TMV+p	MT20	2.0	4.0	X
E	BMV1+p	MT20	2.0	4.0	

DIMENSIONS, SUPPORTS AND LOADINGS SPECIFIED BY FABRICATOR TO BE VERIFIED BY BUILDING DESIGNER

BEARINGS		FACTORED		MAXIMUM FACTORED		INPUT		REQRD	
JT	GROSS REACTION	VERT	HORZ	DOWN	HORZ	UPLIFT	IN-SX	BRG	IN-SX
E	453	0	453	0	0	5-8	5-8		
C	174	0	174	0	0	1-8	1-8		
D	45	0	50	0	0	1-8	1-8		

SEE MITEK STANDARD DETAIL B37579H FOR CONNECTION TO JOINT(S) C , D

UNFACTORED REACTIONS		1ST LCASE		MAX./MIN. COMPONENT REACTIONS					
JT	COMBINED	SNOW	LIVE	PERM.LIVE	WIND	DEAD	SOIL		
E	316	234 / 0	0 / 0	0 / 0	0 / 0	82 / 0	0 / 0		
C	118	105 / 0	0 / 0	0 / 0	0 / 0	14 / 0	0 / 0		
D	36	0 / 0	0 / 0	0 / 0	0 / 0	36 / 0	0 / 0		

BEARING MATERIAL TO BE SPF NO.2 OR BETTER AT JOINT(S) E

BRACING
TOP CHORD TO BE SHEATHED OR MAX. PURLIN SPACING = 6.25 FT.
MAX. UNBRACED BOTTOM CHORD LENGTH = 10.00 FT OR RIGID CEILING DIRECTLY APPLIED.
ALL PITCH BREAKS AND PERIMETER CORNER JOINTS MUST BE Laterally RESTRAINED.

LOADING		TOTAL LOAD CASES: (4)							
CHORDS		MAX. FACTORED		FACTORED		WEBS		MAX. FACTORED	
MEMB.	FORCE (LBS)	VERT. LOAD (PLF)	LC1	MAX	CS1 (LC)	MEMB.	FORCE (LBS)	MAX	CS1 (LC)
FR-TO		FROM	TO			FR-TO			
E-B	-389 / 0	0.0	0.0	0.11 (4)	7.81				
A-B	0 / 22	-77.4	-77.4	0.09 (1)	10.00				
B-C	-26 / 0	-77.4	-77.4	0.36 (1)	6.25				
E-D	0 / 0	-18.2	-18.2	0.14 (4)	10.00				

DESIGN CRITERIA

SPECIFIED LOADS:
TOP CH. LL = 23.3 PSF
DL = 3.0 PSF
BOT CH. LL = 0.0 PSF
DL = 7.3 PSF
TOTAL LOAD = 33.6 PSF

SPACING = 24.0 IN. C/C

THIS TRUSS IS DESIGNED FOR RESIDENTIAL OR SMALL BUILDING REQUIREMENTS OF PART 9, NBCC 2010

THIS DESIGN COMPLIES WITH:
- PART 9 OF OBC 2012 , BCBC 2012 , ABC 2014
- CSA 086-09
- TPIC 2011

DESIGN ASSUMPTIONS
- OVERHANG NOT TO BE ALTERED OR CUT OFF.

(55 % OF 27.2 P.S.F. G.S.L. PLUS 8.4 P.S.F. RAIN LOAD) EQUALS 23.3 P.S.F. SPECIFIED ROOF LIVE LOAD

ALLOWABLE DEFL.(LL)= L/360 (0.20")
CALCULATED VERT. DEFL.(LL)= L/ 999 (0.00")
ALLOWABLE DEFL.(TL)= L/360 (0.20")
CALCULATED VERT. DEFL.(TL)= L/ 999 (0.03")

CSI: TC=0.36/1.00 (B-C:1) , BC=0.14/1.00 (D-E:4) , WB=0.00/1.00 (n/a:0) , SSI=0.20/1.00 (B-C:1)

DOL LUMBER=1.00 NAIL=1.00 LS BEND=1.10
COMP=1.10 SHEAR=1.10 TENS= 1.10

COMPANION LIVE LOAD FACTOR = 0.50

AUTOSOLVE RIGHT HEEL ONLY

TRUSS PLATE MANUFACTURER IS NOT RESPONSIBLE FOR QUALITY CONTROL IN THE TRUSS MANUFACTURING PLANT .

NAIL VALUES
PLATE GRIP(DRY) SHEAR SECTION
(PSI) (PLI) (PLI)
MAX MIN MAX MIN MAX MIN
MT20 618 354 1667 822 2284 1656

PLATE PLACEMENT TOL. = 0.250 inches


PLATE ROTATION TOL. = 5.0 Deg.

JSI GRIP= 0.22 (B) (INPUT = 0.90)
JSI METAL= 0.09 (B) (INPUT = 1.00)



READ ALL NOTES ON THIS PAGE AND ON ENGINEERING NOTE PAGE ENP-1. THIS NOTE PAGE IS AN INTEGRAL PART OF THIS DRAWING AS IT CONTAINS SPECIFICATIONS AND CRITERIA USED IN THE DESIGN OF THIS COMPONENT.





TOTAL WEIGHT = 2 X 8 = 16 lb
[M]

LUMBER
N. L. G. A. RULES

CHORDS	SIZE	DRY	LUMBER	DESCR.
E - B	2x4	DRY	No.2	SPF
A - C	2x4	DRY	No.2	SPF
E - D	2x4	DRY	No.2	SPF

DRY: SEASONED LUMBER.

PLATES (table is in inches)

JT	TYPE	PLATES	W	LEN	Y	X
B	TMV+p	MT20	2.0	4.0		
E	BMV1+p	MT20	2.0	4.0		

DIMENSIONS, SUPPORTS AND LOADINGS SPECIFIED BY FABRICATOR TO BE VERIFIED BY BUILDING DESIGNER

BEARINGS

JT	FACTORED GROSS REACTION		MAXIMUM FACTORED GROSS REACTION		INPUT BRG	REQRD BRG
	VERT	HORZ	DOWN	HORZ		
E	216	0	216	0	5-8	5-8
C	58	0	58	0	1-8	1-8
D	16	0	18	0	1-8	1-8

SEE MITEK STANDARD DETAIL B37579H FOR CONNECTION TO JOINT(S) C , D

UNFACTORED REACTIONS

JT	1ST LCASE	MAX./MIN. COMPONENT REACTIONS				
		COMBINED	SNOW	LIVE	PERM.LIVE	WIND
E	149	118 / 0	0 / 0	0 / 0	0 / 0	31 / 0
C	40	35 / 0	0 / 0	0 / 0	0 / 0	5 / 0
D	13	0 / 0	0 / 0	0 / 0	0 / 0	13 / 0

BEARING MATERIAL TO BE SPF NO.2 OR BETTER AT JOINT(S) E

BRACING

TOP CHORD TO BE SHEATHED OR MAX. PURLIN SPACING = 6.25 FT.
MAX. UNBRACED BOTTOM CHORD LENGTH = 10.00 FT OR RIGID CEILING DIRECTLY APPLIED.

ALL PITCH BREAKS AND PERIMETER CORNER JOINTS MUST BE Laterally RESTRAINED.

LOADING

TOTAL LOAD CASES: (5)

CHORDS					WEBS				
MEMB.	MAX. FACTORED FORCE (LBS)	FACTORED VERT. LOAD (PLF)	LC1	MAX. CSI (LC)	MAX. UNBRAC LENGTH	MEMB.	MAX. FACTORED FORCE (LBS)	MAX. CSI (LC)	
FR-TO		FROM	TO			FR-TO			
E-B	-196 / 0	0.0	0.0	0.01 (4)	7.81				
A-B	0 / 28	-77.4	-77.4	0.09 (1)	10.00				
B-C	-10 / 0	-77.4	-77.4	0.05 (1)	6.25				
E-D	0 / 0	-18.2	-18.2	0.02 (4)	10.00				

CANTILEVER ANALYSIS HAS BEEN CONSIDERED IN THIS DESIGN

DESIGN CRITERIA

SPECIFIED LOADS:
TOP CH. LL = 23.3 PSF
DL = 3.0 PSF
BOT CH. LL = 0.0 PSF
DL = 7.3 PSF
TOTAL LOAD = 33.6 PSF

SPACING = 24.0 IN. C/C

THIS TRUSS IS DESIGNED FOR RESIDENTIAL OR SMALL BUILDING REQUIREMENTS OF PART 9, NBCC 2010

THIS DESIGN COMPLIES WITH:
- PART 9 OF OBC 2012 , BCBC 2012 , ABC 2014
- CSA 086-09
- TPIC 2011

DESIGN ASSUMPTIONS
- OVERHANG NOT TO BE ALTERED OR CUT OFF.

(55 % OF 27.2 P.S.F. G.S.L. PLUS 8.4 P.S.F. RAIN LOAD) EQUALS 23.3 P.S.F. SPECIFIED ROOF LIVE LOAD

ALLOWABLE DEFL.(LL)= L/360 (0.19")
CALCULATED VERT. DEFL.(LL)= L/999 (0.00")
ALLOWABLE DEFL.(TL)= L/360 (0.19")
CALCULATED VERT. DEFL.(TL)= L/999 (0.00")

CSI: TC=0.09/1.00 (A-B:1) , BC=0.02/1.00 (D-E:4) ,
WB=0.00/1.00 (n/a:0) , SSI=0.06/1.00 (A-B:1)

DOL LUMBER=1.00 NAIL=1.00 LS BEND=1.10
COMP=1.10 SHEAR=1.10 TENS= 1.10

COMPANION LIVE LOAD FACTOR = 0.50

AUTOSOLVE RIGHT HEEL ONLY

TRUSS PLATE MANUFACTURER IS NOT RESPONSIBLE FOR QUALITY CONTROL IN THE TRUSS MANUFACTURING PLANT .

NAIL VALUES
PLATE GRIP(DRY) SHEAR SECTION
(PSI) (PLI) (PLI)
MAX MIN MAX MIN MAX MIN
MT20 618 354 1667 822 2284 1656

PLATE PLACEMENT TOL. = 0.250 inches


PLATE ROTATION TOL. = 5.0 Deg.

JSI GRIP= 0.13 (B) (INPUT = 0.90)
JSI METAL= 0.05 (B) (INPUT = 1.00)



READ ALL NOTES ON THIS PAGE AND ON ENGINEERING NOTE PAGE ENP-1. THIS NOTE PAGE IS AN INTEGRAL PART OF THIS DRAWING AS IT CONTAINS SPECIFICATIONS AND CRITERIA USED IN THE DESIGN OF THIS COMPONENT.





Scale = 1:14.2

TOTAL WEIGHT = 4 X 6 = 26 lb [M]

LUMBER
N. L. G. A. RULES

CHORDS	SIZE	DRY	LUMBER	DESCR.
E - B	2x4	DRY	No.2	SPF
A - C	2x4	DRY	No.2	SPF
E - D	2x4	DRY	No.2	SPF

DRY: SEASONED LUMBER.

PLATES (table is in inches)

JT	TYPE	PLATES	W	LEN	Y	X
B	TMV+p	MT20	2.0	4.0		
E	BMV1+p	MT20	2.0	4.0		

DIMENSIONS, SUPPORTS AND LOADINGS SPECIFIED BY FABRICATOR TO BE VERIFIED BY BUILDING DESIGNER

BEARINGS

JT	FACTORED GROSS REACTION		MAXIMUM FACTORED GROSS REACTION		INPUT BRG	REQRD BRG
	VERT	HORZ	DOWN	HORZ		
E	171	0	171	0	5-8	5-8
C	49	0	49	0	1-8	1-8
D	14	0	15	0	1-8	1-8

SEE MITEK STANDARD DETAIL B37579H FOR CONNECTION TO JOINT(S) C , D

UNFACTORED REACTIONS

JT	1ST LCASE	MAX./MIN. COMPONENT REACTIONS				
		SNOW	LIVE	PERM.LIVE	WIND	DEAD
E	118	93/0	0/0	0/0	0/0	25/0
C	33	29/0	0/0	0/0	0/0	4/0
D	11	0/0	0/0	0/0	0/0	11/0

BEARING MATERIAL TO BE SPF NO.2 OR BETTER AT JOINT(S) E

BRACING
TOP CHORD TO BE SHEATHED OR MAX. PURLIN SPACING = 10.00 FT.
MAX. UNBRACED BOTTOM CHORD LENGTH = 10.00 FT OR RIGID CEILING DIRECTLY APPLIED.

ALL PITCH BREAKS AND PERIMETER CORNER JOINTS MUST BE Laterally RESTRAINED.

LOADING									
TOTAL LOAD CASES: (5)									
C H O R D S					W E B S				
MAX. FACTORED		FACTORED		MAX. MEMB. FORCE (LBS)	MAX. FACTORED		MAX. MEMB. FORCE (LBS)	MAX. CSI (LC)	
MEMB.	FORCE (LBS)	VERT. LOAD (PLF)	LC1 MAX CSI (LC)		UNBRACED LENGTH	FR-TO			
FR-TO		FROM	TO						
E-B	-154 / 0	0.0	0.0	0.01 (4)	7.81				
A-B	0 / 21	-77.4	-77.4	0.05 (1)	10.00				
B-C	-9 / 0	-77.4	-77.4	0.04 (1)	10.00				
E-D	0 / 0	-18.2	-18.2	0.01 (4)	10.00				

CANTILEVER ANALYSIS HAS BEEN CONSIDERED IN THIS DESIGN

DESIGN CRITERIA

SPECIFIED LOADS:

TOP CH.	LL	PSF
DL	3.0	PSF
BOT CH.	LL	PSF
DL	7.3	PSF
TOTAL LOAD	33.6	PSF

SPACING = 24.0 IN. C/C

THIS TRUSS IS DESIGNED FOR RESIDENTIAL OR SMALL BUILDING REQUIREMENTS OF PART 9, NBCC 2010

THIS DESIGN COMPLIES WITH:
- PART 9 OF OBC 2012 , BCBC 2012 , ABC 2014
- CSA 086-09
- TPIC 2011

DESIGN ASSUMPTIONS
- OVERHANG NOT TO BE ALTERED OR CUT OFF.

(55 % OF 27.2 P.S.F. G.S.L. PLUS 8.4 P.S.F. RAIN LOAD) EQUALS 23.3 P.S.F. SPECIFIED ROOF LIVE LOAD

ALLOWABLE DEFL.(LL)= L/360 (0.19")
CALCULATED VERT. DEFL.(LL)= L/ 999 (0.00")
ALLOWABLE DEFL.(TL)= L/360 (0.19")
CALCULATED VERT. DEFL.(TL)= L/ 999 (0.00")

CSI: TC=0.05/1.00 (A-B:1) , BC=0.01/1.00 (D-E:4) , WB=0.00/1.00 (n/a:0) , SSI=0.05/1.00 (B-C:1)

DOL LUMBER=1.00 NAIL=1.00 LS BEND=1.10
COMP=1.10 SHEAR=1.10 TENS= 1.10

COMPANION LIVE LOAD FACTOR = 0.50

AUTOSOLVE RIGHT HEEL ONLY

TRUSS PLATE MANUFACTURER IS NOT RESPONSIBLE FOR QUALITY CONTROL IN THE TRUSS MANUFACTURING PLANT .

NAIL VALUES

PLATE	GRIP(DRY)	SHEAR (PSI)	SECTION (PLI)
MT20	618	354	1667
	822	2284	1656

PLATE PLACEMENT TOL. = 0.250 inches


PLATE ROTATION TOL. = 5.0 Deg.

JSI GRIP= 0.10 (B) (INPUT = 0.90)
JSI METAL= 0.04 (B) (INPUT = 1.00)



READ ALL NOTES ON THIS PAGE AND ON ENGINEERING NOTE PAGE ENP-1. THIS NOTE PAGE IS AN INTEGRAL PART OF THIS DRAWING AS IT CONTAINS SPECIFICATIONS AND CRITERIA USED IN THE DESIGN OF THIS COMPONENT.





TOTAL WEIGHT = 108 lb [M][F]

LUMBER				DIMENSIONS, SUPPORTS AND LOADINGS SPECIFIED BY FABRICATOR TO BE VERIFIED BY BUILDING DESIGNER			
N. L. G. A. RULES				BEARINGS			
CHORDS	SIZE	LUMBER	DESCR.	FACTORED GROSS REACTION	MAXIMUM FACTORED GROSS REACTION	INPUT BRG	REQRD BRG
A - D	2x4	DRY	No.2	VERT	DOWN	UPLIFT	IN-SX
D - F	2x4	DRY	No.2	N	1335	0	5-8
F - I	2x4	DRY	No.2	J	1335	0	5-8
N - B	2x4	DRY	No.2				
J - H	2x4	DRY	No.2				
N - L	2x4	DRY	No.2				
L - J	2x4	DRY	No.2				

LUMBER				UNFACTORED REACTIONS			
ALL WEBS EXCEPT	SIZE	LUMBER	DESCR.	1ST LCASE	MAX./MIN. COMPONENT REACTIONS	WIND	SOIL
2x3	DRY	No.2	SPF	JT	COMBINED	SNOW	LIVE
				N	935	662 / 0	0 / 0
				J	935	662 / 0	0 / 0

DRY: SEASONED LUMBER.

BEARING MATERIAL TO BE SPF NO.2 OR BETTER AT JOINT(S) N, J

BRACING
TOP CHORD TO BE SHEATHED OR MAX. PURLIN SPACING = 5.46 FT.
MAX. UNBRACED BOTTOM CHORD LENGTH = 10.00 FT OR RIGID CEILING DIRECTLY APPLIED.

ALL PITCH BREAKS AND PERIMETER CORNER JOINTS MUST BE Laterally RESTRAINED.

LOADING
TOTAL LOAD CASES: (4)

CHORDS				WEBS			
MEMB.	MAX. FACTORED FORCE (LBS)	FACTORED VERT. LOAD (PLF)	MAX. FACTORED LC1 (LC)	MAX. UNBRACED LENGTH	MEMB.	MAX. FACTORED FORCE (LBS)	MAX. FACTORED LC1 (LC)
FR-TO		FROM	TO		FR-TO		
A-B	0 / 28	-77.4	-77.4 0.09 (1)	10.00	C-M	-74 / 36	0.04 (1)
B-C	0 / 19	-77.4	-77.4 0.19 (1)	10.00	M-D	0 / 461	0.10 (1)
C-D	-1330 / 0	-77.4	-77.4 0.17 (1)	5.46	M-E	-291 / 0	0.39 (1)
D-E	-1097 / 0	-77.4	-77.4 0.25 (1)	5.75	E-K	-291 / 0	0.39 (1)
E-F	-1097 / 0	-77.4	-77.4 0.25 (1)	5.75	K-F	0 / 461	0.10 (1)
F-G	-1330 / 0	-77.4	-77.4 0.17 (1)	5.46	K-G	-74 / 36	0.04 (1)
G-H	0 / 19	-77.4	-77.4 0.19 (1)	10.00	N-C	-1558 / 0	0.75 (1)
H-I	0 / 28	-77.4	-77.4 0.09 (1)	10.00	G-J	-1558 / 0	0.75 (1)
N-B	-220 / 0	0.0	0.0 0.02 (1)	7.81			
J-H	-220 / 0	0.0	0.0 0.02 (1)	7.81			
N-M	0 / 1145	-18.2	-18.2 0.41 (4)	10.00			
M-L	0 / 1272	-18.2	-18.2 0.42 (4)	10.00			
L-K	0 / 1272	-18.2	-18.2 0.42 (4)	10.00			
K-J	0 / 1144	-18.2	-18.2 0.41 (4)	10.00			

DESIGN CRITERIA

SPECIFIED LOADS:
TOP CH. LL = 23.3 PSF
DL = 3.0 PSF
BOT CH. LL = 0.0 PSF
DL = 7.3 PSF
TOTAL LOAD = 33.6 PSF

SPACING = 24.0 IN. C/C

LOADING IN FLAT SECTION BASED ON A SLOPE OF 2.00/12 MINIMUM

THIS TRUSS IS DESIGNED FOR RESIDENTIAL OR SMALL BUILDING REQUIREMENTS OF PART 9, NBCC 2010

THIS DESIGN COMPLIES WITH:
- PART 9 OF OBC 2012, BCBC 2012, ABC 2014
- CSA 086-09
- TPIC 2011

(55 % OF 27.2 P.S.F. G.S.L. PLUS 8.4 P.S.F. RAIN LOAD) EQUALS 23.3 P.S.F. SPECIFIED ROOF LIVE LOAD

ALLOWABLE DEFL.(LL)= L/360 (0.86")
CALCULATED VERT. DEFL.(LL) = L/999 (0.05")
ALLOWABLE DEFL.(TL)= L/360 (0.86")
CALCULATED VERT. DEFL.(TL) = L/999 (0.16")

CSI: TC=0.25/1.00 (D-E:1), BC=0.42/1.00 (K-M:4), WB=0.75/1.00 (C-N:1), SSI=0.18/1.00 (D-E:1)

DOL LUMBER=1.00 NAIL=1.00 LS BEND=1.10
COMP=1.10 SHEAR=1.10 TENS= 1.10

COMPANION LIVE LOAD FACTOR = 0.50

TRUSS PLATE MANUFACTURER IS NOT RESPONSIBLE FOR QUALITY CONTROL IN THE TRUSS MANUFACTURING PLANT .


NAIL VALUES
PLATE GRIP(DRY) SHEAR SECTION
(PSI) (PLI) (PLI)
MAX MIN MAX MIN MAX MIN
MT20 618 354 1667 822 2284 1656

PLATE PLACEMENT TOL. = 0.250 inches

PLATE ROTATION TOL. = 5.0 Deg.


JSI GRIP= 0.88 (N) (INPUT = 0.90)

JSI METAL= 0.57 (G) (INPUT = 1.00)



READ ALL NOTES ON THIS PAGE AND ON ENGINEERING NOTE PAGE ENP-1. THIS NOTE PAGE IS AN INTEGRAL PART OF THIS DRAWING AS IT CONTAINS SPECIFICATIONS AND CRITERIA USED IN THE DESIGN OF THIS COMPONENT.





TOTAL WEIGHT = 114 lb
[M][F]

LUMBER
N. L. G. A. RULES

CHORDS	SIZE	DRY	LUMBER	DESCR.
A - D	2x4	DRY	No.2	SPF
D - E	2x4	DRY	No.2	SPF
E - H	2x4	DRY	No.2	SPF
N - B	2x4	DRY	No.2	SPF
I - G	2x4	DRY	No.2	SPF
N - K	2x4	DRY	No.2	SPF
K - I	2x4	DRY	No.2	SPF
ALL WEBS EXCEPT	2x3	DRY	No.2	SPF

DRY: SEASONED LUMBER.

PLATES (table is in inches)

JT	TYPE	PLATES	W	LEN	Y	X
B	TMVW-t	MT20	4.0	5.0	1.50	2.00
C	TMWW-t	MT20	3.0	4.0	1.50	1.50
D	TTWW-m	MT20	4.0	5.0	1.75	1.50
E	TTW+p	MT20	3.0	4.0	2.50	1.50
F	TMWW-t	MT20	3.0	4.0	1.50	1.50
G	TMVW-t	MT20	4.0	5.0	1.50	2.00
I	BMV1+p	MT20	2.0	4.0		
J	BMWW-t	MT20	4.0	4.0	1.75	1.50
K	BSWWW-I	MT20	5.0	6.0	3.00	3.00
L	BMWW-t	MT20	3.0	4.0		
M	BMWW-t	MT20	4.0	4.0	1.75	1.50
N	BMV1+p	MT20	2.0	4.0		

DIMENSIONS, SUPPORTS AND LOADINGS SPECIFIED BY FABRICATOR TO BE VERIFIED BY BUILDING DESIGNER

BEARINGS

JT	FACTORED GROSS REACTION		MAXIMUM FACTORED GROSS REACTION		INPUT BRG	REQRD BRG
	VERT	HORZ	DOWN	HORZ		
N	1335	0	1335	0	5-8	5-8
I	1335	0	1335	0	5-8	5-8

UNFACTORED REACTIONS							
	1ST LCASE	MAX./MIN. COMPONENT REACTIONS					
JT	COMBINED	SNOW	LIVE	PERM.LIVE	WIND	DEAD	SOIL
N	935	662 / 0	0 / 0	0 / 0	0 / 0	274 / 0	0 / 0
I	935	662 / 0	0 / 0	0 / 0	0 / 0	274 / 0	0 / 0

BEARING MATERIAL TO BE SPF NO.2 OR BETTER AT JOINT(S) N, I

BRACING
TOP CHORD TO BE SHEATHED OR MAX. PURLIN SPACING = 5.19 FT.
MAX. UNBRACED BOTTOM CHORD LENGTH = 10.00 FT OR RIGID CEILING DIRECTLY APPLIED.

ALL PITCH BREAKS AND PERIMETER CORNER JOINTS MUST BE Laterally RESTRAINED.

LOADING
TOTAL LOAD CASES: (4)

CHORDS				WEBS			
MEMB.	MAX. FACTORED FORCE (LBS)	FACTORED VERT. LOAD (PLF)	MAX. UNBRACED LENGTH (LC)	MEMB.	MAX. FACTORED FORCE (LBS)	MAX. UNBRACED LENGTH (LC)	
FR-TO		FROM TO		FR-TO			
A-B	0 / 28	-77.4 -77.4	0.09 (1)	10.00	M-C	-144 / 41	0.05 (1)
B-C	-1419 / 0	-77.4 -77.4	0.28 (1)	5.19	C-L	-291 / 0	0.24 (1)
C-D	-1211 / 0	-77.4 -77.4	0.27 (1)	5.52	L-D	0 / 291	0.07 (1)
D-E	-988 / 0	-77.4 -77.4	0.35 (1)	5.82	D-K	0 / 0	0.00 (1)
E-F	-1211 / 0	-77.4 -77.4	0.26 (1)	5.52	K-E	0 / 291	0.07 (1)
F-G	-1418 / 0	-77.4 -77.4	0.28 (1)	5.19	K-F	-289 / 0	0.24 (1)
G-H	0 / 28	-77.4 -77.4	0.09 (1)	10.00	J-F	-145 / 40	0.05 (1)
N-B	-1295 / 0	0.0 0.0	0.13 (1)	7.10	B-M	0 / 1226	0.28 (1)
I-G	-1295 / 0	0.0 0.0	0.13 (1)	7.10	J-G	0 / 1225	0.28 (1)
N-M	0 / 0	-18.2 -18.2	0.10 (4)	10.00			
M-L	0 / 1202	-18.2 -18.2	0.25 (1)	10.00			
L-K	0 / 988	-18.2 -18.2	0.22 (1)	10.00			
K-J	0 / 1201	-18.2 -18.2	0.25 (1)	10.00			
J-I	0 / 0	-18.2 -18.2	0.10 (4)	10.00			

DESIGN CRITERIA

SPECIFIED LOADS:

TOP CH.	LL	PSF
	23.3	PSF
BOT CH.	LL	PSF
	0.0	PSF
	7.3	PSF
TOTAL LOAD	33.6	PSF

SPACING = 24.0 IN./C

LOADING IN FLAT SECTION BASED ON A SLOPE OF 2.00/12 MINIMUM

THIS TRUSS IS DESIGNED FOR RESIDENTIAL OR SMALL BUILDING REQUIREMENTS OF PART 9, NBCC 2010

THIS DESIGN COMPLIES WITH:
- PART 9 OF OBC 2012, BCBC 2012, ABC 2014
- CSA 086-09
- TPIC 2011

(55 % OF 27.2 P.S.F. G.S.L. PLUS 8.4 P.S.F. RAIN LOAD) EQUALS 23.3 P.S.F. SPECIFIED ROOF LIVE LOAD

ALLOWABLE DEFL.(LL)= L/360 (0.86")
CALCULATED VERT. DEFL.(LL) = L/999 (0.04")
ALLOWABLE DEFL.(TL)= L/360 (0.86")
CALCULATED VERT. DEFL.(TL) = L/999 (0.09")

CSI: TC=0.35/1.00 (D-E:1), BC=0.25/1.00 (J-K:1), WB=0.28/1.00 (B-M:1), SSI=0.18/1.00 (D-E:1)

DOL LUMBER=1.00 NAIL=1.00 LS BEND=1.10
COMP=1.10 SHEAR=1.10 TENS= 1.10

COMPANION LIVE LOAD FACTOR = 0.50

TRUSS PLATE MANUFACTURER IS NOT RESPONSIBLE FOR QUALITY CONTROL IN THE TRUSS MANUFACTURING PLANT .

NAIL VALUES

PLATE	GRIP(DRY)	SHEAR	SECTION
(PSI)	(PLI)	(PLI)	
MAX	MIN	MAX	MIN
MT20	618	354	1667 822 2284 1656

PLATE PLACEMENT TOL. = 0.250 inches


PLATE ROTATION TOL. = 5.0 Deg.

JSI GRIP= 0.85 (B) (INPUT = 0.90)
JSI METAL= 0.47 (B) (INPUT = 1.00)



READ ALL NOTES ON THIS PAGE AND ON ENGINEERING NOTE PAGE ENP-1. THIS NOTE PAGE IS AN INTEGRAL PART OF THIS DRAWING AS IT CONTAINS SPECIFICATIONS AND CRITERIA USED IN THE DESIGN OF THIS COMPONENT.





TOTAL WEIGHT = 121 lb [M][F]

LUMBER
N. L. G. A. RULES

CHORDS	SIZE	DRY	LUMBER	DESCR.
A - C	2x4	DRY	No.2	SPF
C - E	2x4	DRY	No.2	SPF
E - F	2x4	DRY	No.2	SPF
F - H	2x4	DRY	No.2	SPF
H - J	2x4	DRY	No.2	SPF
Q - B	2x4	DRY	No.2	SPF
K - I	2x4	DRY	No.2	SPF
Q - M	2x4	DRY	No.2	SPF
M - K	2x4	DRY	No.2	SPF
ALL WEBS EXCEPT	2x3	DRY	No.2	SPF

DRY: SEASONED LUMBER.

PLATES (table is in inches)

JT	TYPE	PLATES	W	LEN	Y	X
B	TMVW-t	MT20	4.0	5.0	1.50	2.00
C	TS-t	MT20	3.0	6.0		
D	TMWW-t	MT20	3.0	4.0	1.50	1.50
E	TTWW+m	MT20	5.0	5.0	2.25	1.25
F	TTW+m	MT20	3.0	4.0	2.00	1.25
G	TMWW-t	MT20	3.0	4.0	1.50	1.50
H	TS-t	MT20	3.0	6.0		
I	TMVW-t	MT20	4.0	5.0	1.50	2.00
K	BMV1+p	MT20	2.0	4.0		
L	BMWW-t	MT20	4.0	4.0	1.75	1.50
M	BS-t	MT20	3.0	6.0		
N	BMWW-t	MT20	3.0	8.0		
O	BMWW-t	MT20	3.0	4.0		
P	BMWW-t	MT20	4.0	4.0	1.75	1.50
Q	BMV1+p	MT20	2.0	4.0		

DIMENSIONS, SUPPORTS AND LOADINGS SPECIFIED BY FABRICATOR TO BE VERIFIED BY BUILDING DESIGNER

BEARINGS

JT	FACTORED GROSS REACTION		MAXIMUM FACTORED GROSS REACTION		INPUT BRG	REQRD BRG
	VERT	HORZ	DOWN	HORZ		
Q	1335	0	1335	0	5-8	5-8
K	1335	0	1335	0	5-8	5-8

UNFACTORED REACTIONS							
	1ST LCASE	MAX./MIN. COMPONENT REACTIONS					
JT	COMBINED	SNOW	LIVE	PERM.LIVE	WIND	DEAD	SOIL
Q	935	662 / 0	0 / 0	0 / 0	0 / 0	274 / 0	0 / 0
K	935	662 / 0	0 / 0	0 / 0	0 / 0	274 / 0	0 / 0

BEARING MATERIAL TO BE SPF NO.2 OR BETTER AT JOINT(S) Q, K

BRACING
TOP CHORD TO BE SHEATHED OR MAX. PURLIN SPACING = 5.02 FT.
MAX. UNBRACED BOTTOM CHORD LENGTH = 10.00 FT OR RIGID CEILING DIRECTLY APPLIED.

ALL PITCH BREAKS AND PERIMETER CORNER JOINTS MUST BE Laterally RESTRAINED.

LOADING
TOTAL LOAD CASES: (4)

CHORDS				WEBS			
MEMB.	MAX. FACTORED FORCE (LBS)	FACTORED VERT. LOAD (PLF)	FACTORED LC1 MAX CSI (LC)	MAX. UNBRACED LENGTH	MEMB.	MAX. FACTORED FORCE (LBS)	MAX. FACTORED CSI (LC)
FR-TO		FROM	TO		FR-TO		
A-B	0 / 28	-77.4	-77.4 0.09 (1)	10.00	P-D	-76 / 84	0.03 (1)
B-C	-1422 / 0	-77.4	-77.4 0.41 (1)	5.02	D-O	-435 / 0	0.56 (1)
C-D	-1422 / 0	-77.4	-77.4 0.41 (1)	5.02	O-E	0 / 334	0.08 (1)
D-E	-1087 / 0	-77.4	-77.4 0.38 (1)	5.58	E-N	0 / 11	0.00 (1)
E-F	-883 / 0	-77.4	-77.4 0.04 (1)	6.25	N-F	0 / 346	0.08 (1)
F-G	-1089 / 0	-77.4	-77.4 0.38 (1)	5.58	N-G	-431 / 0	0.55 (1)
G-H	-1420 / 0	-77.4	-77.4 0.41 (1)	5.02	L-G	-80 / 82	0.04 (1)
H-I	-1420 / 0	-77.4	-77.4 0.41 (1)	5.02	B-P	0 / 1226	0.28 (1)
I-J	0 / 28	-77.4	-77.4 0.09 (1)	10.00	L-I	0 / 1224	0.28 (1)
Q-B	-1290 / 0	0.0	0.0 0.13 (1)	7.10			
K-I	-1289 / 0	0.0	0.0 0.13 (1)	7.10			
Q-P	0 / 0	-18.2	-18.2 0.17 (4)	10.00			
P-O	0 / 1209	-18.2	-18.2 0.28 (1)	10.00			
O-N	0 / 881	-18.2	-18.2 0.20 (1)	10.00			
N-M	0 / 1207	-18.2	-18.2 0.28 (1)	10.00			
M-L	0 / 1207	-18.2	-18.2 0.28 (1)	10.00			
L-K	0 / 0	-18.2	-18.2 0.17 (4)	10.00			

DESIGN CRITERIA

SPECIFIED LOADS:
TOP CH. LL = 23.3 PSF
DL = 3.0 PSF
BOT CH. LL = 0.0 PSF
DL = 7.3 PSF
TOTAL LOAD = 33.6 PSF

SPACING = 24.0 IN./C

LOADING IN FLAT SECTION BASED ON A SLOPE OF 2.00/12 MINIMUM

THIS TRUSS IS DESIGNED FOR RESIDENTIAL OR SMALL BUILDING REQUIREMENTS OF PART 9, NBCC 2010

THIS DESIGN COMPLIES WITH:
- PART 9 OF OBC 2012, BCBC 2012, ABC 2014
- CSA 086-09
- TPIC 2011

(55 % OF 27.2 P.S.F. G.S.L. PLUS 8.4 P.S.F. RAIN LOAD) EQUALS 23.3 P.S.F. SPECIFIED ROOF LIVE LOAD

ALLOWABLE DEFL.(LL)= L/360 (0.86")
CALCULATED VERT. DEFL.(LL)= L/999 (0.05")
ALLOWABLE DEFL.(TL)= L/360 (0.86")
CALCULATED VERT. DEFL.(TL)= L/999 (0.10")

CSI: TC=0.41/1.00 (B-D:1), BC=0.28/1.00 (O-P:1), WB=0.56/1.00 (D-O:1), SSI=0.19/1.00 (B-D:1)

DOL LUMBER=1.00 NAIL=1.00 LS BEND=1.10
COMP=1.10 SHEAR=1.10 TENS= 1.10

COMPANION LIVE LOAD FACTOR = 0.50

TRUSS PLATE MANUFACTURER IS NOT RESPONSIBLE FOR QUALITY CONTROL IN THE TRUSS MANUFACTURING PLANT .

NAIL VALUES
PLATE GRIP(DRY) SHEAR SECTION (PSI) (PLI) (PLI)
MAX MIN MAX MIN MAX MIN
MT20 618 354 1667 822 2284 1656

PLATE PLACEMENT TOL. = 0.250 inches


PLATE ROTATION TOL. = 5.0 Deg.

JSI GRIP= 0.87 (F) (INPUT = 0.90)
JSI METAL= 0.48 (B) (INPUT = 1.00)



READ ALL NOTES ON THIS PAGE AND ON ENGINEERING NOTE PAGE ENP-1. THIS NOTE PAGE IS AN INTEGRAL PART OF THIS DRAWING AS IT CONTAINS SPECIFICATIONS AND CRITERIA USED IN THE DESIGN OF THIS COMPONENT.





LUMBER
N. L. G. A. RULES

CHORDS	SIZE	DRY	LUMBER	DESCR.
A - C	2x4	DRY	No.2	SPF
C - E	2x4	DRY	No.2	SPF
E - G	2x4	DRY	No.2	SPF
M - B	2x4	DRY	No.2	SPF
H - G	2x4	DRY	No.2	SPF
M - J	2x4	DRY	No.2	SPF
J - H	2x4	DRY	No.2	SPF
ALL WEBS EXCEPT	2x3	DRY	No.2	SPF

DRY: SEASONED LUMBER.

PLATES (table is in inches)

JT	TYPE	PLATES	W	LEN	Y	X
B	TMVW-t	MT20	4.0	5.0	1.50	2.00
C	TS-t	MT20	3.0	6.0		
D	TMWW-t	MT20	3.0	4.0	1.50	1.50
E	TTW+p	MT20	3.0	5.0		
F	TMWW-t	MT20	3.0	4.0	1.50	1.50
G	TMVW-t	MT20	4.0	5.0	1.50	2.00
H	BMV1+p	MT20	2.0	4.0		
I	BMWW-t	MT20	4.0	4.0	1.75	1.50
J	BS-t	MT20	3.0	6.0		
K	BMWW-t	MT20	4.0	6.0		
L	BMWW-t	MT20	4.0	4.0	1.75	1.50
M	BMV1+p	MT20	2.0	4.0		

DIMENSIONS, SUPPORTS AND LOADINGS SPECIFIED BY FABRICATOR TO BE VERIFIED BY BUILDING DESIGNER

BEARINGS

JT	FACTORED GROSS REACTION		MAXIMUM FACTORED GROSS REACTION		INPUT BRG	REQRD BRG
	VERT	HORZ	DOWN	HORZ		
M	1335	0	1335	0	5-8	5-8
H	1235	0	1235	0	5-8	5-8

UNFACTORED REACTIONS							
	1ST LCASE	MAX./MIN. COMPONENT REACTIONS					
JT	COMBINED	SNOW	LIVE	PERM.LIVE	WIND	DEAD	SOIL
M	935	662 / 0	0 / 0	0 / 0	0 / 0	274 / 0	0 / 0
H	868	602 / 0	0 / 0	0 / 0	0 / 0	266 / 0	0 / 0

BEARING MATERIAL TO BE SPF NO.2 OR BETTER AT JOINT(S) M, H

BRACING
TOP CHORD TO BE SHEATHED OR MAX. PURLIN SPACING = 4.92 FT.
MAX. UNBRACED BOTTOM CHORD LENGTH = 10.00 FT OR RIGID CEILING DIRECTLY APPLIED.

ALL PITCH BREAKS AND PERIMETER CORNER JOINTS MUST BE Laterally RESTRAINED.

1 - 1x4 LATERAL BRACE(S) AT 1/2 LENGTH OF D-K, F-K. DBS = 20-0-0. CBF = 61 LBS.

DBS = DIAGONAL BRACE SPACING (MAX). CBF = CUMULATIVE BRACING FORCE (PER BRACE). FASTEN LATERAL BRACE(S) USING (0.122"x3") SPIRAL NAILS: 1 NAIL FOR 2x3 BRACE(S), 2 FOR 1x4, 2x4, 2x5, 3 FOR 2x6, 4 FOR 2x8, 5 FOR 2x10, AND 6 FOR 2x12.

END VERTICAL(S) MUST BE SHEATHED OR HAVE BRACES AS INDICATED IN THE MAX. UNBRACED LENGTH COLUMN OF THE TABLE BELOW

LOADING

TOTAL LOAD CASES: (4)

CHORDS				WEBS				
MEMB.	MAX. FACTORED FORCE (LBS)	FACTORED VERT. LOAD (PLF)	LC1 MAX (LC)	MAX. UNBRACED LENGTH	MEMB.	MAX. FACTORED FORCE (LBS)	FACTORED MAX CSI (LC)	
FR-TO		FROM	TO		FR-TO			
A-B	0 / 28	-77.4	-77.4	0.09 (1)	10.00	L-D	-57 / 94	0.03 (4)
B-C	-1415 / 0	-77.4	-77.4	0.48 (1)	4.92	D-K	-488 / 0	0.23 (1)
C-D	-1415 / 0	-77.4	-77.4	0.48 (1)	4.92	K-E	0 / 743	0.17 (1)
D-E	-1036 / 0	-77.4	-77.4	0.44 (1)	5.59	K-F	-487 / 0	0.23 (1)
E-F	-1036 / 0	-77.4	-77.4	0.44 (1)	5.59	I-F	-58 / 94	0.03 (4)
F-G	-1414 / 0	-77.4	-77.4	0.48 (1)	4.92	B-L	0 / 1219	0.27 (1)
M-B	-1285 / 0	0.0	0.0	0.13 (1)	7.11	I-G	0 / 1219	0.27 (1)
H-G	-1186 / 0	0.0	0.0	0.12 (1)	7.33			
M-L	0 / 0	-18.2	-18.2	0.18 (4)	10.00			
L-K	0 / 1205	-18.2	-18.2	0.29 (1)	10.00			
K-J	0 / 1204	-18.2	-18.2	0.29 (1)	10.00			
J-I	0 / 1204	-18.2	-18.2	0.29 (1)	10.00			
I-H	0 / 0	-18.2	-18.2	0.18 (4)	10.00			

DESIGN CRITERIA

SPECIFIED LOADS:
TOP CH. LL = 23.3 PSF
DL = 3.0 PSF
BOT CH. LL = 0.0 PSF
DL = 7.3 PSF
TOTAL LOAD = 33.6 PSF

SPACING = 24.0 IN./C

THIS TRUSS IS DESIGNED FOR RESIDENTIAL OR SMALL BUILDING REQUIREMENTS OF PART 9, NBCC 2010

THIS DESIGN COMPLIES WITH:
- PART 9 OF OBC 2012, BCBC 2012, ABC 2014
- CSA 086-09
- TPIC 2011

(55 % OF 27.2 P.S.F. G.S.L. PLUS 8.4 P.S.F. RAIN LOAD) EQUALS 23.3 P.S.F. SPECIFIED ROOF LIVE LOAD

ALLOWABLE DEFL.(LL)= L/360 (0.86")
CALCULATED VERT. DEFL.(LL) = L/999 (0.05")
ALLOWABLE DEFL.(TL)= L/360 (0.86")
CALCULATED VERT. DEFL.(TL) = L/999 (0.10")

CSI: TC=0.48/1.00 (B-D:1), BC=0.29/1.00 (K-L:1), WB=0.27/1.00 (B-L:1), SSI=0.20/1.00 (B-D:1)

DOL LUMBER=1.00 NAIL=1.00 LS BEND=1.10
COMP=1.10 SHEAR=1.10 TENS= 1.10

COMPANION LIVE LOAD FACTOR = 0.50

TRUSS PLATE MANUFACTURER IS NOT RESPONSIBLE FOR QUALITY CONTROL IN THE TRUSS MANUFACTURING PLANT .

NAIL VALUES
PLATE GRIP(DRY) SHEAR SECTION (PSI) (PLI) (PLI)
MAX MIN MAX MIN MAX MIN
MT20 618 354 1667 822 2284 1656

PLATE PLACEMENT TOL. = 0.250 inches


PLATE ROTATION TOL. = 5.0 Deg.

JSI GRIP= 0.86 (G) (INPUT = 0.90)
JSI METAL= 0.48 (B) (INPUT = 1.00)



READ ALL NOTES ON THIS PAGE AND ON ENGINEERING NOTE PAGE ENP-1. THIS NOTE PAGE IS AN INTEGRAL PART OF THIS DRAWING AS IT CONTAINS SPECIFICATIONS AND CRITERIA USED IN THE DESIGN OF THIS COMPONENT.





Scale = 1:57.6

TOTAL WEIGHT = 3 X 108 = 323 lb [M][F]

LUMBER			
N. L. G. A. RULES			
CHORDS	SIZE	LUMBER	DESCR.
A - C	2x4	DRY	No.2
C - E	2x4	DRY	No.2
E - G	2x4	DRY	No.2
M - B	2x4	DRY	No.2
H - G	2x4	DRY	No.2
M - J	2x4	DRY	No.2
J - H	2x4	DRY	No.2
ALL WEBS EXCEPT	2x3	DRY	No.2

DRY: SEASONED LUMBER.

PLATES (table is in inches)

JT	TYPE	PLATES	W	LEN	Y	X
B	TMVW-t	MT20	4.0	5.0	1.50	2.00
C	TS-t	MT20	3.0	6.0		
D	TMWW-t	MT20	3.0	4.0	1.50	1.50
E	TTW+p	MT20	3.0	5.0		
F	TMWW-t	MT20	3.0	4.0	1.50	1.50
G	TMVW-t	MT20	4.0	5.0	1.75	Edge
H	BMV1+p	MT20	2.0	4.0		
I	BMWW-t	MT20	4.0	4.0	1.75	1.50
J	BS-t	MT20	3.0	6.0		
K	BMWW-t	MT20	4.0	6.0		
L	BMWW-t	MT20	4.0	4.0	1.75	1.50
M	BMV1+p	MT20	2.0	4.0		

Edge - INDICATES REFERENCE CORNER OF PLATE TOUCHES EDGE OF CHORD.

DIMENSIONS, SUPPORTS AND LOADINGS SPECIFIED BY FABRICATOR TO BE VERIFIED BY BUILDING DESIGNER

BEARINGS

	FACTORED GROSS REACTION	MAXIMUM FACTORED GROSS REACTION	INPUT BRG	REQRD BRG
JT	VERT	HORZ	DOWN	UP
M	1323	0	1323	0
H	1223	0	1223	0

A SUITABLE MECHANICAL CONNECTION IS REQUIRED AT JOINT H TO RESIST THE MAX FACTORED REACTIONS.

UNFACTORED REACTIONS

JT	1ST LCASE	MAX/MIN. COMPONENT REACTIONS	PERM. LIVE	WIND	DEAD	SOIL
M	927	656 / 0	0 / 0	0 / 0	271 / 0	0 / 0
H	859	596 / 0	0 / 0	0 / 0	264 / 0	0 / 0

BEARING MATERIAL TO BE SPF NO.2 OR BETTER AT JOINT(S) M

BRACING

TOP CHORD TO BE SHEATHED OR MAX. PURLIN SPACING = 4.94 FT.
MAX. UNBRACED BOTTOM CHORD LENGTH = 10.00 FT OR RIGID CEILING DIRECTLY APPLIED.

ALL PITCH BREAKS AND PERIMETER CORNER JOINTS MUST BE Laterally RESTRAINED.

1 - 1x4 LATERAL BRACE(S) AT 1/2 LENGTH OF D-K, F-K. DBS = 20-0-0 . CBF = 61 LBS.

DBS = DIAGONAL BRACE SPACING (MAX). CBF = CUMULATIVE BRACING FORCE (PER BRACE). FASTEN LATERAL BRACE(S) USING (0.122"x3") SPIRAL NAILS : 1 NAIL FOR 2x3 BRACE(S), 2 FOR 1x4, 2x4, 2x5, 3 FOR 2x6, 4 FOR 2x8, 5 FOR 2x10, AND 6 FOR 2x12.

END VERTICAL(S) MUST BE SHEATHED OR HAVE BRACES AS INDICATED IN THE MAX. UNBRACED LENGTH COLUMN OF THE TABLE BELOW

LOADING

TOTAL LOAD CASES: (4)

CHORDS				WEBS			
MEMB.	MAX. FACTORED FORCE (LBS)	FACTORED VERT. LOAD (PLF)	MAX. FACTORED VERT. LOAD (LC1)	MEMB.	MAX. FACTORED FORCE (LBS)	MAX. FACTORED VERT. LOAD (LC1)	MAX. FACTORED VERT. LOAD (LC1)
FR-TO		FROM	TO	FR-TO		FROM	TO
A-B	0 / 28	-77.4	-77.4	0.09 (1)	L-D	-55 / 94	0.03 (4)
B-C	-1397 / 0	-77.4	-77.4	0.48 (1)	D-K	-490 / 0	0.23 (1)
C-D	-1397 / 0	-77.4	-77.4	0.48 (1)	K-E	0 / 719	0.16 (1)
D-E	-1016 / 0	-77.4	-77.4	0.44 (1)	K-F	-448 / 0	0.21 (1)
E-F	-1015 / 0	-77.4	-77.4	0.43 (1)	I-F	-91 / 81	0.05 (1)
F-G	-1359 / 0	-77.4	-77.4	0.45 (1)	B-L	0 / 1205	0.27 (1)
M-B	-1273 / 0	0.0	0.0	0.13 (1)	I-G	0 / 1179	0.27 (1)
H-G	-1176 / 0	0.0	0.0	0.12 (1)			
M-L	0 / 0	-18.2	-18.2	0.18 (4)			
L-K	0 / 1190	-18.2	-18.2	0.29 (1)			
K-J	0 / 1158	-18.2	-18.2	0.28 (1)			
J-I	0 / 1158	-18.2	-18.2	0.28 (1)			
I-H	0 / 0	-18.2	-18.2	0.18 (4)			

DESIGN CRITERIA

SPECIFIED LOADS:

TOP CH.	LL	=	23.3	PSF
	DL	=	3.0	PSF
BOT CH.	LL	=	0.0	PSF
	DL	=	7.3	PSF
TOTAL LOAD		=	33.6	PSF

SPACING = 24.0 IN./C

THIS TRUSS IS DESIGNED FOR RESIDENTIAL OR SMALL BUILDING REQUIREMENTS OF PART 9, NBCC 2010

THIS DESIGN COMPLIES WITH:
- PART 9 OF OBC 2012, BCBC 2012, ABC 2014
- CSA 086-09
- TPIC 2011

(55 % OF 27.2 P.S.F. G.S.L. PLUS 8.4 P.S.F. RAIN LOAD) EQUALS 23.3 P.S.F. SPECIFIED ROOF LIVE LOAD

ALLOWABLE DEFL.(LL)= L/360 (0.85")
CALCULATED VERT. DEFL.(LL) = L/999 (0.05")
ALLOWABLE DEFL.(TL)= L/360 (0.85")
CALCULATED VERT. DEFL.(TL) = L/999 (0.10")

CSI: TC=0.48/1.00 (B-D:1), BC=0.29/1.00 (K-L:1), WB=0.27/1.00 (B-L:1), SSI=0.20/1.00 (B-D:1)

DOL LUMBER=1.00 NAIL=1.00 LS BEND=1.10
COMP=1.10 SHEAR=1.10 TENS= 1.10

COMPANION LIVE LOAD FACTOR = 0.50

TRUSS PLATE MANUFACTURER IS NOT RESPONSIBLE FOR QUALITY CONTROL IN THE TRUSS MANUFACTURING PLANT .

NAIL VALUES

PLATE	GRIP(DRY)	SHEAR	SECTION
	(PSI)	(PLI)	(PLI)
	MAX MIN	MAX MIN	MAX MIN
MT20	618 354	1667 822	2284 1656

PLATE PLACEMENT TOL. = 0.250 inches


PLATE ROTATION TOL. = 5.0 Deg.

JSI GRIP= 0.89 (G) (INPUT = 0.90)
JSI METAL= 0.48 (B) (INPUT = 1.00)



READ ALL NOTES ON THIS PAGE AND ON ENGINEERING NOTE PAGE ENP-1. THIS NOTE PAGE IS AN INTEGRAL PART OF THIS DRAWING AS IT CONTAINS SPECIFICATIONS AND CRITERIA USED IN THE DESIGN OF THIS COMPONENT.





TOTAL WEIGHT = 116 lb [M]


L. N. L. G. A. RULES				BUILDING DESIGNER				DESIGN CRITERIA			
CHORDS SIZE				BEARINGS				SPECIFIED LOADS:			
A - C	2x4	DRY	No.2	SPF	FACTORED	MAXIMUM	FACTORED	INPUT	REQRD	TOP CH. LL = 23.3 PSF	
C - D	2x4	DRY	No.2	SPF	GROSS REACTION	GROSS REACTION	BRG	BRG		DL = 3.0 PSF	
D - G	2x4	DRY	No.2	SPF	JT VERT	HORZ	DOWN	HORZ	UPLIFT	BOT CH. LL = 0.0 PSF	
G - I	2x4	DRY	No.2	SPF	P 1494	0	1494	0	0	DL = 7.3 PSF	
P - B	2x4	DRY	No.2	SPF	J 1494	0	1494	0	0	TOTAL LOAD = 33.6 PSF	
J - H	2x4	DRY	No.2	SPF							
P - M	2x4	DRY	No.2	SPF							
M - J	2x4	DRY	No.2	SPF							
ALL WEBS 2x3 DRY No.2				SPF	UNFACTORED REACTIONS					SPACING = 24.0 IN. C/C	
EXCEPT					1ST LCASE MAX./MIN. COMPONENT REACTIONS					LOADING IN FLAT SECTION BASED ON A SLOPE OF 2.00/12 MINIMUM	
DRY: SEASONED LUMBER.					JT COMBINED	SNOW	LIVE	PERM.LIVE	WIND	DEAD	SOIL
					P 1047	739 / 0	0 / 0	0 / 0	0 / 0	308 / 0	0 / 0
					J 1047	739 / 0	0 / 0	0 / 0	0 / 0	308 / 0	0 / 0
BEARING MATERIAL TO BE SPF NO.2 OR BETTER AT JOINT(S) P, J											
BRACING											
TOP CHORD TO BE SHEATHED OR MAX. PURLIN SPACING = 4.21 FT.											
MAX. UNBRACED BOTTOM CHORD LENGTH = 10.00 FT OR RIGID CEILING DIRECTLY APPLIED.											
ALL PITCH BREAKS AND PERIMETER CORNER JOINTS MUST BE Laterally RESTRAINED.											
LOADING											
TOTAL LOAD CASES: (4)											
CHORDS WEBS											
MEMB. MAX. FACTORED FORCE (LBS) VERT. LOAD (PLF) MAX. UNBRACED LENGTH (LC) MAX. FACTORED FORCE (LBS) MAX. UNBRACED LENGTH (LC)											
FR-TO FROM TO FR-TO											
A-B 0 / 28 -77.4 -77.4 0.09 (1) 10.00 O-C -117 / 61 0.05 (1)											
B-C -1609 / 0 -77.4 -77.4 0.55 (1) 4.58 C-N 0 / 956 0.22 (1)											
C-D -2079 / 0 -77.4 -77.4 0.48 (1) 4.22 N-E -495 / 0 0.19 (1)											
D-E -2079 / 0 -77.4 -77.4 0.48 (1) 4.22 N-F -2 / 0 0.00 (1)											
E-F -2079 / 0 -77.4 -77.4 0.49 (1) 4.21 L-F -497 / 0 0.19 (1)											
F-G -2081 / 0 -77.4 -77.4 0.49 (1) 4.21 L-G 0 / 958 0.22 (1)											
G-H -1609 / 0 -77.4 -77.4 0.55 (1) 4.58 K-G -118 / 61 0.05 (1)											
H-I 0 / 28 -77.4 -77.4 0.09 (1) 10.00 B-O 0 / 1359 0.31 (1)											
P-B -1452 / 0 0.0 0.0 0.15 (1) 6.79 K-H 0 / 1358 0.31 (1)											
J-H -1452 / 0 0.0 0.0 0.15 (1) 6.79											
P-O 0 / 0 -18.2 -18.2 0.15 (4) 10.00											
O-N 0 / 1335 -18.2 -18.2 0.30 (1) 10.00											
N-M 0 / 2081 -18.2 -18.2 0.39 (1) 10.00											
M-L 0 / 2081 -18.2 -18.2 0.39 (1) 10.00											
L-K 0 / 1335 -18.2 -18.2 0.30 (1) 10.00											
K-J 0 / 0 -18.2 -18.2 0.15 (4) 10.00											

<



READ ALL NOTES ON THIS PAGE AND ON ENGINEERING NOTE PAGE ENP-1. THIS NOTE PAGE IS AN INTEGRAL PART OF THIS DRAWING AS IT CONTAINS SPECIFICATIONS AND CRITERIA USED IN THE DESIGN OF THIS COMPONENT.





TOTAL WEIGHT = 119 lb [M]

LUMBER
N. L. G. A. RULES

CHORDS	SIZE	DRY	LUMBER	DESCR.
A - D	2x4	DRY	No.2	SPF
D - F	2x4	DRY	No.2	SPF
F - I	2x4	DRY	No.2	SPF
O - B	2x4	DRY	No.2	SPF
J - H	2x4	DRY	No.2	SPF
O - L	2x4	DRY	No.2	SPF
L - J	2x4	DRY	No.2	SPF
ALL WEBS EXCEPT	2x3	DRY	No.2	SPF

DRY: SEASONED LUMBER.

PLATES (table is in inches)

JT	TYPE	PLATES	W	LEN	Y	X
B	TMV+p	MT20	2.0	4.0		
C	TMWW-t	MT20	4.0	5.0	1.75	2.25
D	TTWW+m	MT20	5.0	6.0	2.25	1.50
E	TMW+w	MT20	2.0	4.0		
F	TTWW+m	MT20	5.0	6.0	2.25	1.50
G	TMWW-t	MT20	4.0	5.0	1.75	2.25
H	TMV+p	MT20	2.0	4.0		
J	BMVW1-t	MT20	4.0	5.0	1.75	2.25
K	BMWW-t	MT20	3.0	4.0		
L	BS-t	MT20	3.0	6.0		
M	BMWW-t	MT20	3.0	8.0		
N	BMWW-t	MT20	3.0	4.0		
O	BMVW1-t	MT20	4.0	5.0	1.75	2.25

DIMENSIONS, SUPPORTS AND LOADINGS SPECIFIED BY FABRICATOR TO BE VERIFIED BY BUILDING DESIGNER

BEARINGS

JT	FACTORED GROSS REACTION		MAXIMUM FACTORED GROSS REACTION		INPUT BRG	REQRD BRG
	VERT	HORZ	DOWN	HORZ		
O	1494	0	1494	0	5-8	5-8
J	1494	0	1494	0	5-8	5-8

UNFACTORED REACTIONS

JT	1ST LCASE		MAX./MIN. COMPONENT REACTIONS				SOIL
	COMBINED	SNOW	LIVE	PERM.LIVE	WIND	DEAD	
O	1047	739 / 0	0 / 0	0 / 0	0 / 0	308 / 0	0 / 0
J	1047	739 / 0	0 / 0	0 / 0	0 / 0	308 / 0	0 / 0

BEARING MATERIAL TO BE SPF NO.2 OR BETTER AT JOINT(S) O, J

BRACING
TOP CHORD TO BE SHEATHED OR MAX. PURLIN SPACING = 3.60 FT.
MAX. UNBRACED BOTTOM CHORD LENGTH = 10.00 FT OR RIGID CEILING DIRECTLY APPLIED.

ALL PITCH BREAKS AND PERIMETER CORNER JOINTS MUST BE Laterally RESTRAINED.

LOADING
TOTAL LOAD CASES: (4)

CHORDS					WEBS				
MEMB.	MAX. FACTORED FORCE (LBS)	FACTORED VERT. LOAD (PLF)	LC1 (LC)	MAX. UNBRACED LENGTH	MEMB.	MAX. FACTORED FORCE (LBS)	LC1 (LC)		
FR-TO		FROM	TO		FR-TO				
A-B	0 / 28	-77.4	-77.4	0.09 (1)	10.00	C-N	0 / 59	0.02 (4)	
B-C	0 / 16	-77.4	-77.4	0.14 (1)	10.00	N-D	0 / 134	0.04 (4)	
C-D	-1595 / 0	-77.4	-77.4	0.18 (1)	5.06	D-M	0 / 672	0.15 (1)	
D-E	-1842 / 0	-77.4	-77.4	0.95 (1)	3.60	M-E	-706 / 0	0.42 (1)	
E-F	-1842 / 0	-77.4	-77.4	0.95 (1)	3.60	M-F	0 / 672	0.15 (1)	
F-G	-1595 / 0	-77.4	-77.4	0.18 (1)	5.06	K-F	0 / 134	0.04 (4)	
G-H	0 / 16	-77.4	-77.4	0.14 (1)	10.00	K-G	0 / 59	0.02 (4)	
H-I	0 / 28	-77.4	-77.4	0.09 (1)	10.00	O-C	-1785 / 0	0.70 (1)	
O-B	-209 / 0	0.0	0.0	0.02 (1)	7.81	G-J	-1785 / 0	0.70 (1)	
J-H	-209 / 0	0.0	0.0	0.02 (1)	7.81				
O-N	0 / 1292	-18.2	-18.2	0.34 (1)	10.00				
N-M	0 / 1314	-18.2	-18.2	0.35 (1)	10.00				
M-L	0 / 1314	-18.2	-18.2	0.35 (1)	10.00				
L-K	0 / 1314	-18.2	-18.2	0.35 (1)	10.00				
K-J	0 / 1292	-18.2	-18.2	0.34 (1)	10.00				

DESIGN CRITERIA

SPECIFIED LOADS:
TOP CH. LL = 23.3 PSF
DL = 3.0 PSF
BOT CH. LL = 0.0 PSF
DL = 7.3 PSF
TOTAL LOAD = 33.6 PSF

SPACING = 24.0 IN. C/C

LOADING IN FLAT SECTION BASED ON A SLOPE OF 2.00/12 MINIMUM

THIS TRUSS IS DESIGNED FOR RESIDENTIAL OR SMALL BUILDING REQUIREMENTS OF PART 9, NBCC 2010

THIS DESIGN COMPLIES WITH:
- PART 9 OF OBC 2012, BCBC 2012, ABC 2014
- CSA 086-09
- TPIC 2011

(55 % OF 27.2 P.S.F. G.S.L. PLUS 8.4 P.S.F. RAIN LOAD) EQUALS 23.3 P.S.F. SPECIFIED ROOF LIVE LOAD

ALLOWABLE DEFL.(LL)= L/360 (0.97")
CALCULATED VERT. DEFL.(LL)= L/ 999 (0.08")
ALLOWABLE DEFL.(TL)= L/360 (0.97")
CALCULATED VERT. DEFL.(TL)= L/ 999 (0.15")

CSI: TC=0.95/1.00 (D-E:1), BC=0.35/1.00 (K-M:1), WB=0.70/1.00 (G-J:1), SSI=0.28/1.00 (D-E:1)

DOL LUMBER=1.00 NAIL=1.00 LS BEND=1.10
COMP=1.10 SHEAR=1.10 TENS= 1.10

COMPANION LIVE LOAD FACTOR = 0.50

TRUSS PLATE MANUFACTURER IS NOT RESPONSIBLE FOR QUALITY CONTROL IN THE TRUSS MANUFACTURING PLANT .

NAIL VALUES

PLATE	GRIP(DRY) (PSI)	SHEAR (PLI)	SECTION (PLI)
MT20	618	354	1667

PLATE PLACEMENT TOL. = 0.250 inches


PLATE ROTATION TOL. = 5.0 Deg.

JSI GRIP= 0.89 (C) (INPUT = 0.90)
JSI METAL= 0.53 (C) (INPUT = 1.00)



READ ALL NOTES ON THIS PAGE AND ON ENGINEERING NOTE PAGE ENP-1. THIS NOTE PAGE IS AN INTEGRAL PART OF THIS DRAWING AS IT CONTAINS SPECIFICATIONS AND CRITERIA USED IN THE DESIGN OF THIS COMPONENT.






										TOTAL WEIGHT = 128 lb																																																																																
LUMBER N. L. G. A. RULES CHORDS SIZE DRY No.2 SPF A - D 2x4 DRY No.2 SPF D - F 2x4 DRY No.2 SPF F - I 2x4 DRY No.2 SPF Q - B 2x4 DRY No.2 SPF J - H 2x4 DRY No.2 SPF Q - M 2x4 DRY No.2 SPF M - J 2x4 DRY No.2 SPF ALL WEBS 2x3 DRY No.2 SPF EXCEPT DRY: SEASONED LUMBER. DIMENSIONS, SUPPORTS AND LOADINGS SPECIFIED BY FABRICATOR TO BE VERIFIED BY BUILDING DESIGNER BEARINGS <table><tr><td></td><td>FACTORED</td><td></td><td>MAXIMUM FACTORED</td><td>INPUT</td><td>REQRD</td></tr><tr><td></td><td>GROSS REACTION</td><td></td><td>GROSS REACTION</td><td>BRG</td><td>BRG</td></tr><tr><td>JT</td><td>VERT</td><td>HORZ</td><td>DOWN</td><td>HORZ</td><td>UPLIFT</td></tr><tr><td></td><td></td><td></td><td></td><td>IN-SX</td><td>IN-SX</td></tr><tr><td>Q</td><td>1494</td><td>0</td><td>1494</td><td>0</td><td>0</td></tr><tr><td></td><td></td><td></td><td></td><td>5-8</td><td>5-8</td></tr><tr><td>J</td><td>1494</td><td>0</td><td>1494</td><td>0</td><td>0</td></tr><tr><td></td><td></td><td></td><td></td><td>5-8</td><td>5-8</td></tr></table> UNFACTORED REACTIONS <table><tr><td></td><td>1ST LCASE</td><td colspan="5">MAX./MIN. COMPONENT REACTIONS</td></tr><tr><td>JT</td><td>COMBINED</td><td>SNOW</td><td>LIVE</td><td>PERM.LIVE</td><td>WIND</td><td>DEAD</td><td>SOIL</td></tr><tr><td>Q</td><td>1047</td><td>739 / 0</td><td>0 / 0</td><td>0 / 0</td><td>0 / 0</td><td>308 / 0</td><td>0 / 0</td></tr><tr><td>J</td><td>1047</td><td>739 / 0</td><td>0 / 0</td><td>0 / 0</td><td>0 / 0</td><td>308 / 0</td><td>0 / 0</td></tr></table>											FACTORED		MAXIMUM FACTORED	INPUT	REQRD		GROSS REACTION		GROSS REACTION	BRG	BRG	JT	VERT	HORZ	DOWN	HORZ	UPLIFT					IN-SX	IN-SX	Q	1494	0	1494	0	0					5-8	5-8	J	1494	0	1494	0	0					5-8	5-8		1ST LCASE	MAX./MIN. COMPONENT REACTIONS					JT	COMBINED	SNOW	LIVE	PERM.LIVE	WIND	DEAD	SOIL	Q	1047	739 / 0	0 / 0	0 / 0	0 / 0	308 / 0	0 / 0	J	1047	739 / 0	0 / 0	0 / 0	0 / 0	308 / 0	0 / 0	DESIGN CRITERIA SPECIFIED LOADS: TOP CH. LL = 23.3 PSF DL = 3.0 PSF BOT CH. LL = 0.0 PSF DL = 7.3 PSF TOTAL LOAD = 33.6 PSF SPACING = 24.0 IN. C/C LOADING IN FLAT SECTION BASED ON A SLOPE OF 2.00/12 MINIMUM	
	FACTORED		MAXIMUM FACTORED	INPUT	REQRD																																																																																					
	GROSS REACTION		GROSS REACTION	BRG	BRG																																																																																					
JT	VERT	HORZ	DOWN	HORZ	UPLIFT																																																																																					
				IN-SX	IN-SX																																																																																					
Q	1494	0	1494	0	0																																																																																					
				5-8	5-8																																																																																					
J	1494	0	1494	0	0																																																																																					
				5-8	5-8																																																																																					
	1ST LCASE	MAX./MIN. COMPONENT REACTIONS																																																																																								
JT	COMBINED	SNOW	LIVE	PERM.LIVE	WIND	DEAD	SOIL																																																																																			
Q	1047	739 / 0	0 / 0	0 / 0	0 / 0	308 / 0	0 / 0																																																																																			
J	1047	739 / 0	0 / 0	0 / 0	0 / 0	308 / 0	0 / 0																																																																																			

PLATES (table is in inches)						
JT	TYPE	PLATES	W	LEN	Y	X
B	TMVW-t	MT20	4.0	6.0	1.75	3.00
C	TMWW-t	MT20	3.0	4.0	1.50	1.50
D	TTWW+m	MT20	5.0	5.0	Edge	3.75
E	TMW+w	MT20	2.0	4.0		
F	TTWW+m	MT20	5.0	5.0	Edge	3.75
G	TMWW-t	MT20	3.0	4.0	1.50	1.50
H	TMVW-t	MT20	4.0	6.0	1.75	3.00
J	BMV1+p	MT20	2.0	4.0		
K	BMWW-t	MT20	3.0	6.0	1.50	2.25
L	BMWW-t	MT20	3.0	4.0		
M	BS-t	MT20	3.0	6.0		
N	BMWWWW-t	MT20	3.0	6.0		
O	BMWW-t	MT20	3.0	4.0		
P	BMWW-t	MT20	3.0	6.0	1.50	2.25
Q	BMV1+p	MT20	2.0	4.0		
Edge - INDICATES REFERENCE CORNER OF PLATE TOUCHES EDGE OF CHORD.						

BEARING MATERIAL TO BE SPF NO.2 OR BETTER AT JOINT(S) Q, J									
BRACING									
TOP CHORD TO BE SHEATHED OR MAX. PURLIN SPACING = 4.88 FT.									
MAX. UNBRACED BOTTOM CHORD LENGTH = 10.00 FT OR RIGID CEILING DIRECTLY APPLIED.									
ALL PITCH BREAKS AND PERIMETER CORNER JOINTS MUST BE Laterally RESTRAINED.									
LOADING									
TOTAL LOAD CASES: (4)									
CHORDS					WEBS				
MAX. FACTORED		FACTORED			MAX. FACTORED				
MEMB.	FORCE (LBS)	VERT. LOAD (PLF)	LC1 MAX (LC)	MAX. UNBRAC	MEMB.	FORCE (LBS)	MAX. FACTORED CSI (LC)		
FR-TO		FROM TO		LENGTH	FR-TO				
A-B	0 / 28	-77.4 -77.4	0.09 (1)	10.00	P-C	-237 / 0	0.07 (1)		
B-C	-1617 / 0	-77.4 -77.4	0.21 (1)	5.01	C-O	-154 / 0	0.09 (1)		
C-D	-1526 / 0	-77.4 -77.4	0.21 (1)	5.13	O-D	0 / 201	0.05 (1)		
D-E	-1542 / 0	-77.4 -77.4	0.38 (1)	4.88	D-N	0 / 443	0.10 (1)		
E-F	-1542 / 0	-77.4 -77.4	0.38 (1)	4.88	N-E	-560 / 0	0.49 (1)		
F-G	-1526 / 0	-77.4 -77.4	0.21 (1)	5.13	N-F	0 / 443	0.10 (1)		
G-H	-1617 / 0	-77.4 -77.4	0.21 (1)	5.01	L-F	0 / 201	0.05 (1)		
H-I	0 / 28	-77.4 -77.4	0.09 (1)	10.00	L-G	-154 / 0	0.09 (1)		
Q-B	-1458 / 0	0.0 0.0	0.15 (1)	6.77	K-G	-237 / 0	0.07 (1)		
J-H	-1458 / 0	0.0 0.0	0.15 (1)	6.77	B-P	0 / 1399	0.31 (1)		
					K-H	0 / 1399	0.31 (1)		
Q-P	0 / 0	-18.2 -18.2	0.07 (4)	10.00					
P-O	0 / 1363	-18.2 -18.2	0.28 (1)	10.00					
O-N	0 / 1252	-18.2 -18.2	0.27 (1)	10.00					
N-M	0 / 1252	-18.2 -18.2	0.27 (1)	10.00					

THIS TRUSS IS DESIGNED FOR RESIDENTIAL OR SMALL BUILDING REQUIREMENTS OF PART 9, NBCC 2010	
THIS DESIGN COMPLIES WITH: - PART 9 OF OBC 2012 , BCBC 2012 , ABC 2014 - CSA 086-09 - TPIC 2011	
(55 % OF 27.2 P.S.F. G.S.L. PLUS 8.4 P.S.F. RAIN LOAD) EQUALS 23.3 P.S.F. SPECIFIED ROOF LIVE LOAD	
ALLOWABLE DEFL.(LL)= L/360 (0.97") CALCULATED VERT. DEFL.(LL)= L/ 999 (0.06") ALLOWABLE DEFL.(TL)= L/360 (0.97") CALCULATED VERT. DEFL.(TL)= L/ 999 (0.12")	
CSI: TC=0.38/1.00 (E-F:1) , BC=0.28/1.00 (O-P:1) , WB=0.49/1.00 (E-N:1) , SSI=0.22/1.00 (E-F:1)	
DOL LUMBER=1.00 NAIL=1.00 LS BEND=1.10 COMP=1.10 SHEAR=1.10 TENS= 1.10	
COMPANION LIVE LOAD FACTOR = 0.50	
TRUSS PLATE MANUFACTURER IS NOT RESPONSIBLE FOR QUALITY CONTROL IN THE TRUSS MANUFACTURING PLANT .	
NAIL VALUES	

READ ALL NOTES ON THIS PAGE AND ON ENGINEERING NOTE PAGE ENP-1. THIS NOTE PAGE IS AN INTEGRAL PART OF THIS DRAWING AS IT CONTAINS SPECIFICATIONS AND CRITERIA USED IN THE DESIGN OF THIS COMPONENT.



TOTAL WEIGHT = 142 lb
[M][F]

LUMBER			
N. L. G. A. RULES	SIZE	LUMBER	DESCR.
A - D	2x4	DRY No.2	SPF
D - E	2x4	DRY No.2	SPF
E - F	2x4	DRY No.2	SPF
F - G	2x4	DRY No.2	SPF
G - J	2x4	DRY No.2	SPF
R - B	2x4	DRY No.2	SPF
K - I	2x4	DRY No.2	SPF
R - O	2x4	DRY No.2	SPF
O - K	2x4	DRY No.2	SPF
ALL WEBS EXCEPT	2x3	DRY No.2	SPF
DRY: SEASONED LUMBER.			

PLATES (table is in inches)					
JT	TYPE	PLATES	W	LEN	Y X
B	TMVW-t	MT20	4.0	6.0	1.75 3.00
C	TMWW-t	MT20	3.0	4.0	1.50 1.50
D	TTW-m	MT20	4.0	4.0	
E	TTW-m	MT20	4.0	4.0	2.00 1.75
F	TTWW+m	MT20	4.0	5.0	
G	TTWW+m	MT20	5.0	5.0	2.50 1.50
H	TMWW-t	MT20	3.0	4.0	1.50 1.50
I	TMVW-t	MT20	4.0	6.0	1.75 3.00
K	BMV1+p	MT20	2.0	4.0	
L	BMWW-t	MT20	4.0	4.0	1.50 1.50
M	BMWW-t	MT20	3.0	4.0	
N	BMWW+t	MT20	3.0	4.0	
O	BS-t	MT20	3.0	6.0	
P	BMWWWW+r	MT20	6.0	10.0	Edge
Q	BMWW-t	MT20	4.0	4.0	1.50 1.50
R	BMV1+p	MT20	2.0	4.0	

Edge - INDICATES REFERENCE CORNER OF PLATE TOUCHES EDGE OF CHORD.

DIMENSIONS, SUPPORTS AND LOADINGS SPECIFIED BY FABRICATOR TO BE VERIFIED BY BUILDING DESIGNER

BEARINGS		FACTORED GROSS REACTION	MAXIMUM FACTORED GROSS REACTION	INPUT BRG	REQRD BRG
JT	VERT	HORZ	DOWN	HORZ	UPLIFT
R	1494	0	1494	0	5-8
K	1494	0	1494	0	5-8

UNFACTORED REACTIONS		1ST LCASE	MAX./MIN. COMPONENT REACTIONS	DEAD	SOIL
JT	COMBINED	SNOW	LIVE	PERM.LIVE	WIND
R	1047	739 / 0	0 / 0	0 / 0	308 / 0
K	1047	739 / 0	0 / 0	0 / 0	308 / 0

BEARING MATERIAL TO BE SPF NO.2 OR BETTER AT JOINT(S) R, K

BRACING
TOP CHORD TO BE SHEATHED OR MAX. PURLIN SPACING = 4.89 FT.
MAX. UNBRACED BOTTOM CHORD LENGTH = 10.00 FT OR RIGID CEILING DIRECTLY APPLIED.

ALL PITCH BREAKS AND PERIMETER CORNER JOINTS MUST BE Laterally RESTRAINED.

2x4 DRY SPF No.2 T-BRACE AT F-P

FASTEN T AND I-BRACES TO NARROW EDGE OF WEB WITH ONE ROW PER PLY OF 3" COMMON WIRE NAILS @ 6" O.C. WITH 3" MINIMUM END DISTANCE. BRACE MUST COVER 90% OF WEB LENGTH.

END VERTICAL(S) MUST BE SHEATHED OR HAVE BRACES AS INDICATED IN THE MAX. UNBRACED LENGTH COLUMN OF THE TABLE BELOW

LOADING

TOTAL LOAD CASES: (4)

CHORDS		WEBS	
MEMB.	MAX. FACTORED FORCE (LBS)	MAX. FACTORED VERT. LOAD (PLF)	MAX. FACTORED VERT. LOAD (PLF)
FR-TO		FROM TO	LENGTH FR-TO
A-B	0 / 28	-77.4 -77.4	0.09 (1)
B-C	-1640 / 0	-77.4 -77.4	0.30 (1)
C-D	-1452 / 0	-77.4 -77.4	0.28 (1)
D-E	-1190 / 0	-77.4 -77.4	0.32 (1)
E-F	-1107 / 0	-77.4 -77.4	0.01 (1)
F-G	-1327 / 0	-77.4 -77.4	0.13 (1)
G-H	-1466 / 0	-77.4 -77.4	0.27 (1)
H-I	-1638 / 0	-77.4 -77.4	0.28 (1)
I-J	0 / 28	-77.4 -77.4	0.09 (1)
R-B	-1453 / 0	0.0 0.0	0.15 (1)
K-I	-1455 / 0	0.0 0.0	0.15 (1)
R-Q	0 / 0	-18.2 -18.2	0.10 (4)
Q-P	0 / 1386	-18.2 -18.2	0.29 (1)
P-O	0 / 1330	-18.2 -18.2	0.28 (1)
O-N	0 / 1330	-18.2 -18.2	0.28 (1)
N-M	0 / 1200	-18.2 -18.2	0.23 (1)
M-L	0 / 1383	-18.2 -18.2	0.27 (1)
L-K	0 / 0	-18.2 -18.2	0.11 (4)

DESIGN CRITERIA

SPECIFIED LOADS:
TOP CH. LL = 23.3 PSF
DL = 3.0 PSF
BOT CH. LL = 0.0 PSF
DL = 7.3 PSF
TOTAL LOAD = 33.6 PSF

SPACING = 24.0 IN./C

LOADING IN ALL FLAT SECTIONS BASED ON A SLOPE OF 2.00/12 MINIMUM

THIS TRUSS IS DESIGNED FOR RESIDENTIAL OR SMALL BUILDING REQUIREMENTS OF PART 9, NBCC 2010

THIS DESIGN COMPLIES WITH:
- PART 9 OF OBC 2012, BCBC 2012, ABC 2014
- CSA 086-09
- TPIC 2011

(55 % OF 27.2 P.S.F. G.S.L. PLUS 8.4 P.S.F. RAIN LOAD) EQUALS 23.3 P.S.F. SPECIFIED ROOF LIVE LOAD

ALLOWABLE DEFL.(LL)= L/360 (0.97")
CALCULATED VERT. DEFL.(LL)= L/999 (0.06")
ALLOWABLE DEFL.(TL)= L/360 (0.97")
CALCULATED VERT. DEFL.(TL)= L/999 (0.13")

CSI: TC=0.32/1.00 (D-E:1), BC=0.29/1.00 (P-Q:1), WB=0.49/1.00 (F-P:1), SSI=0.17/1.00 (D-E:1)

DOL LUMBER=1.00 NAIL=1.00 LS BEND=1.10 COMP=1.10 SHEAR=1.10 TENS=1.10

COMPANION LIVE LOAD FACTOR = 0.50

TRUSS PLATE MANUFACTURER IS NOT RESPONSIBLE FOR QUALITY CONTROL IN THE TRUSS MANUFACTURING PLANT .

NAIL VALUES
PLATE GRIP(DRY) SHEAR SECTION
(PSI) (PLI) (PLI)
MAX MIN MAX MIN MAX MIN
MT20 618 354 1667 822 2284 1656

PLATE PLACEMENT TOL. = 0.250 inches


PLATE ROTATION TOL. = 5.0 Deg.

JSI GRIP= 0.84 (L) (INPUT = 0.90)
JSI METAL= 0.52 (Q) (INPUT = 1.00)



READ ALL NOTES ON THIS PAGE AND ON ENGINEERING NOTE PAGE ENP-1. THIS NOTE PAGE IS AN INTEGRAL PART OF THIS DRAWING AS IT CONTAINS SPECIFICATIONS AND CRITERIA USED IN THE DESIGN OF THIS COMPONENT.





TOTAL WEIGHT = 146 lb
[M][F]

LUMBER
N. L. G. A. RULES

CHORDS	SIZE	LUMBER	DESCR.
A - D	2x4	DRY	No.2
D - E	2x4	DRY	No.2
E - F	2x4	DRY	No.2
F - G	2x4	DRY	No.2
G - J	2x4	DRY	No.2
S - B	2x4	DRY	No.2
K - I	2x4	DRY	No.2
S - O	2x4	DRY	No.2
O - K	2x4	DRY	No.2
ALL WEBS EXCEPT	2x3	DRY	No.2

DRY: SEASONED LUMBER.

PLATES (table is in inches)

JT	TYPE	PLATES	W	LEN	Y	X
B	TMVW-t	MT20	4.0	6.0	1.75	3.00
C	TMWW-t	MT20	3.0	4.0	1.50	1.50
D	TTWW-m	MT20	4.0	5.0	1.75	1.50
E	TTW+m	MT20	3.0	5.0	2.50	1.25
F	TTWW+m	MT20	4.0	5.0	2.50	1.75
G	TTWW+m	MT20	5.0	5.0	Edge	3.75
H	TMWW-t	MT20	3.0	4.0	1.50	1.50
I	TMVW-t	MT20	4.0	6.0	1.75	3.00
K	BMV1+p	MT20	2.0	4.0		
L	BMWW-t	MT20	3.0	6.0	1.50	2.25
M	BMWW-t	MT20	3.0	4.0		
N	BMWW-t	MT20	3.0	4.0		
O	BS-t	MT20	3.0	6.0		
P	BMWW-t	MT20	4.0	6.0		
Q	BMWW-t	MT20	3.0	4.0		
R	BMWW-t	MT20	4.0	4.0	1.50	1.50
S	BMV1+p	MT20	2.0	4.0		

Edge - INDICATES REFERENCE CORNER OF PLATE TOUCHES EDGE OF CHORD.

DIMENSIONS, SUPPORTS AND LOADINGS SPECIFIED BY FABRICATOR TO BE VERIFIED BY BUILDING DESIGNER

BEARINGS

JT	FACTORED GROSS REACTION		MAXIMUM FACTORED GROSS REACTION		INPUT BRG	REQRD BRG
	VERT	HORZ	DOWN	HORZ		
S	1494	0	1494	0	5-8	5-8
K	1494	0	1494	0	5-8	5-8

UNFACTORED REACTIONS

JT	1ST LCASE		MAX./MIN. COMPONENT REACTIONS				
	COMBINED	SNOW	LIVE	PERM.LIVE	WIND	DEAD	SOIL
S	1047	739 / 0	0 / 0	0 / 0	0 / 0	308 / 0	0 / 0
K	1047	739 / 0	0 / 0	0 / 0	0 / 0	308 / 0	0 / 0

BEARING MATERIAL TO BE SPF NO.2 OR BETTER AT JOINT(S) S, K

BRACING
TOP CHORD TO BE SHEATHED OR MAX. PURLIN SPACING = 4.75 FT.
MAX. UNBRACED BOTTOM CHORD LENGTH = 10.00 FT OR RIGID CEILING DIRECTLY APPLIED.

ALL PITCH BREAKS AND PERIMETER CORNER JOINTS MUST BE Laterally RESTRAINED.

LOADING
TOTAL LOAD CASES: (4)

CHORDS				WEBS			
MEMB.	MAX. FACTORED FORCE (LBS)	FACTORED VERT. LOAD (PLF)	MAX. FACTORED LC1 MAX (LC)	MAX. UNBRACED LENGTH	MEMB.	MAX. FACTORED FORCE (LBS)	MAX. FACTORED LC1 MAX (LC)
FR-TO		FROM	TO		FR-TO		
A-B	0 / 28	-77.4	-77.4 0.09 (1)	10.00	R-C	-120 / 67	0.05 (1)
B-C	-1650 / 0	-77.4	-77.4 0.40 (1)	4.75	C-Q	-383 / 0	0.46 (1)
C-D	-1362 / 0	-77.4	-77.4 0.37 (1)	5.15	Q-D	0 / 325	0.07 (1)
D-E	-1152 / 0	-77.4	-77.4 0.08 (1)	5.86	D-P	0 / 158	0.04 (1)
E-F	-1377 / 0	-77.4	-77.4 0.13 (1)	5.42	P-E	0 / 538	0.12 (1)
F-G	-1475 / 0	-77.4	-77.4 0.13 (1)	5.27	P-F	-722 / 0	0.79 (1)
G-H	-1538 / 0	-77.4	-77.4 0.19 (1)	5.13	N-F	-382 / 0	0.31 (1)
H-I	-1610 / 0	-77.4	-77.4 0.20 (1)	5.04	N-G	0 / 482	0.11 (1)
I-J	0 / 28	-77.4	-77.4 0.09 (1)	10.00	M-G	0 / 164	0.04 (1)
S-B	-1449 / 0	0.0	0.0 0.15 (1)	6.79	M-H	-131 / 0	0.07 (1)
K-I	-1459 / 0	0.0	0.0 0.15 (1)	6.77	L-H	-246 / 0	0.07 (1)
					B-R	0 / 1418	0.32 (1)
S-R	0 / 0	-18.2	-18.2 0.16 (4)	10.00	L-I	0 / 1395	0.31 (1)
R-Q	0 / 1398	-18.2	-18.2 0.30 (1)	10.00			
Q-P	0 / 1111	-18.2	-18.2 0.22 (1)	10.00			
P-O	0 / 1481	-18.2	-18.2 0.27 (1)	10.00			
O-N	0 / 1481	-18.2	-18.2 0.27 (1)	10.00			
N-M	0 / 1263	-18.2	-18.2 0.23 (1)	10.00			
M-L	0 / 1356	-18.2	-18.2 0.25 (1)	10.00			
L-K	0 / 0	-18.2	-18.2 0.07 (4)	10.00			

DESIGN CRITERIA

SPECIFIED LOADS:
TOP CH. LL = 23.3 PSF
DL = 3.0 PSF
BOT CH. LL = 0.0 PSF
DL = 7.3 PSF
TOTAL LOAD = 33.6 PSF

SPACING = 24.0 IN. C/C

LOADING IN ALL FLAT SECTIONS BASED ON A SLOPE OF 2.00/12 MINIMUM

THIS TRUSS IS DESIGNED FOR RESIDENTIAL OR SMALL BUILDING REQUIREMENTS OF PART 9, NBCC 2010

THIS DESIGN COMPLIES WITH:
- PART 9 OF OBC 2012, BCBC 2012, ABC 2014
- CSA 086-09
- TPIC 2011

(55 % OF 27.2 P.S.F. G.S.L. PLUS 8.4 P.S.F. RAIN LOAD) EQUALS 23.3 P.S.F. SPECIFIED ROOF LIVE LOAD

ALLOWABLE DEFL.(LL)= L/360 (0.97")
CALCULATED VERT. DEFL.(LL)= L/999 (0.07")
ALLOWABLE DEFL.(TL)= L/360 (0.97")
CALCULATED VERT. DEFL.(TL)= L/999 (0.12")

CSI: TC=0.40/1.00 (B-C:1), BC=0.30/1.00 (Q-R:1), WB=0.79/1.00 (F-P:1), SSI=0.18/1.00 (B-C:1)

DOL LUMBER=1.00 NAIL=1.00 LS BEND=1.10
COMP=1.10 SHEAR=1.10 TENS= 1.10

COMPANION LIVE LOAD FACTOR = 0.50

TRUSS PLATE MANUFACTURER IS NOT RESPONSIBLE FOR QUALITY CONTROL IN THE TRUSS MANUFACTURING PLANT .

NAIL VALUES
PLATE GRIP(DRY) SHEAR SECTION (PSI) (PLI) (PLI)
MAX MIN MAX MIN MAX MIN
MT20 618 354 1667 822 2284 1656

PLATE PLACEMENT TOL. = 0.250 inches


PLATE ROTATION TOL. = 5.0 Deg.

JSI GRIP= 0.87 (G) (INPUT = 0.90)
JSI METAL= 0.52 (R) (INPUT = 1.00)



READ ALL NOTES ON THIS PAGE AND ON ENGINEERING NOTE PAGE ENP-1. THIS NOTE PAGE IS AN INTEGRAL PART OF THIS DRAWING AS IT CONTAINS SPECIFICATIONS AND CRITERIA USED IN THE DESIGN OF THIS COMPONENT.





TOTAL WEIGHT = 129 lb [M][F]

LUMBER
N. L. G. A. RULES

CHORDS	SIZE	DRY	LUMBER	DESCR.
A - C	2x4	DRY	No.2	SPF
C - E	2x4	DRY	No.2	SPF
E - F	2x4	DRY	No.2	SPF
F - G	2x4	DRY	No.2	SPF
G - J	2x4	DRY	No.2	SPF
Q - B	2x4	DRY	No.2	SPF
K - I	2x4	DRY	No.2	SPF
Q - N	2x4	DRY	No.2	SPF
N - K	2x4	DRY	No.2	SPF
ALL WEBS EXCEPT	2x3	DRY	No.2	SPF

DRY: SEASONED LUMBER.

PLATES (table is in inches)

JT	TYPE	PLATES	W	LEN	Y	X
B	TMVW-t	MT20	4.0	6.0	1.75	3.00
C	TS-t	MT20	3.0	6.0		
D	TMWW-t	MT20	3.0	4.0	1.50	1.50
E	TTW+p	MT20	3.0	5.0		
F	TTWW+m	MT20	4.0	5.0	2.50	1.75
G	TTWW+m	MT20	5.0	6.0	Edge	1.75
H	TMWW-t	MT20	4.0	5.0	1.75	2.25
I	TMV+p	MT20	2.0	4.0		
K	BMVW1-t	MT20	4.0	5.0	1.75	2.25
L	BMWW-t	MT20	3.0	4.0		
M	BMWW+t	MT20	3.0	4.0	1.75	1.50
N	BS-t	MT20	3.0	6.0		
O	BMWWW-t	MT20	4.0	6.0		
P	BMWW-t	MT20	4.0	4.0	1.50	1.50
Q	BMV1+p	MT20	2.0	4.0		

Edge - INDICATES REFERENCE CORNER OF PLATE TOUCHES EDGE OF CHORD.

DIMENSIONS, SUPPORTS AND LOADINGS SPECIFIED BY FABRICATOR TO BE VERIFIED BY BUILDING DESIGNER

BEARINGS

	FACTORED GROSS REACTION	MAXIMUM FACTORED GROSS REACTION	INPUT BRG	REQRD BRG
	VERT	HORZ	DOWN	UP
JT	1494	0	0	5-8
Q	1494	0	0	5-8
K	1494	0	0	5-8

UNFACTORED REACTIONS

	1ST LCASE	MAX./MIN. COMPONENT REACTIONS	DEAD	SOIL
	COMBINED	SNOW	LIVE	PERM.LIVE
JT	1047	739 / 0	0 / 0	0 / 0
Q	1047	739 / 0	0 / 0	0 / 0
K	1047	739 / 0	0 / 0	0 / 0

BEARING MATERIAL TO BE SPF NO.2 OR BETTER AT JOINT(S) Q, K

BRACING
TOP CHORD TO BE SHEATHED OR MAX. PURLIN SPACING = 4.62 FT.
MAX. UNBRACED BOTTOM CHORD LENGTH = 10.00 FT OR RIGID CEILING DIRECTLY APPLIED.

ALL PITCH BREAKS AND PERIMETER CORNER JOINTS MUST BE Laterally RESTRAINED.

2x4 DRY SPF No.2 T-BRACE AT D-O, F-O

FASTEN T AND I-BRACES TO NARROW EDGE OF WEB WITH ONE ROW PER PLY OF 3" COMMON WIRE NAILS @ 6" O.C. WITH 3" MINIMUM END DISTANCE. BRACE MUST COVER 90% OF WEB LENGTH.

END VERTICAL(S) MUST BE SHEATHED OR HAVE BRACES AS INDICATED IN THE MAX. UNBRACED LENGTH COLUMN OF THE TABLE BELOW

LOADING

TOTAL LOAD CASES: (4)

CHORDS				WEBS			
MEMB.	MAX. FACTORED FORCE (LBS)	FACTORED VERT. LOAD (PLF)	MAX. UNBRACED LENGTH (LC)	MEMB.	MAX. FACTORED FORCE (LBS)	MAX. UNBRACED LENGTH (LC)	
FR-TO		FROM TO		FR-TO			
A-B	0 / 28	-77.4 -77.4	0.09 (1)	10.00	P-D	-90 / 82	0.05 (1)
B-C	-1646 / 0	-77.4 -77.4	0.50 (1)	4.62	D-O	-459 / 0	0.24 (1)
C-D	-1646 / 0	-77.4 -77.4	0.50 (1)	4.62	O-E	0 / 974	0.22 (1)
D-E	-1293 / 0	-77.4 -77.4	0.46 (1)	5.12	O-F	-822 / 0	0.43 (1)
E-F	-1258 / 0	-77.4 -77.4	0.41 (1)	5.26	M-F	-505 / 0	0.27 (1)
F-G	-1644 / 0	-77.4 -77.4	0.14 (1)	5.05	M-G	0 / 653	0.15 (1)
G-H	-1599 / 0	-77.4 -77.4	0.13 (1)	5.12	L-G	0 / 88	0.03 (4)
H-I	0 / 15	-77.4 -77.4	0.12 (1)	10.00	L-H	0 / 64	0.02 (4)
I-J	0 / 28	-77.4 -77.4	0.09 (1)	10.00	B-P	0 / 1414	0.32 (1)
Q-B	-1444 / 0	0.0 0.0	0.15 (1)	6.80	H-K	-1777 / 0	0.64 (1)
K-I	-205 / 0	0.0 0.0	0.02 (1)	7.81			
Q-P	0 / 0	-18.2 -18.2	0.18 (4)	10.00			
P-O	0 / 1397	-18.2 -18.2	0.31 (1)	10.00			
O-N	0 / 1653	-18.2 -18.2	0.35 (1)	10.00			
N-M	0 / 1653	-18.2 -18.2	0.35 (1)	10.00			
M-L	0 / 1317	-18.2 -18.2	0.31 (1)	10.00			
L-K	0 / 1277	-18.2 -18.2	0.31 (1)	10.00			

DESIGN CRITERIA

SPECIFIED LOADS:
TOP CH. LL = 23.3 PSF
DL = 3.0 PSF
BOT CH. LL = 0.0 PSF
DL = 7.3 PSF
TOTAL LOAD = 33.6 PSF

SPACING = 24.0 IN./C

LOADING IN ALL FLAT SECTIONS BASED ON A SLOPE OF 2.00/12 MINIMUM

THIS TRUSS IS DESIGNED FOR RESIDENTIAL OR SMALL BUILDING REQUIREMENTS OF PART 9, NBCC 2010

THIS DESIGN COMPLIES WITH:
- PART 9 OF OBC 2012, BCBC 2012, ABC 2014
- CSA 086-09
- TPIC 2011

(55 % OF 27.2 P.S.F. G.S.L. PLUS 8.4 P.S.F. RAIN LOAD) EQUALS 23.3 P.S.F. SPECIFIED ROOF LIVE LOAD

ALLOWABLE DEFL.(LL)= L/360 (0.97")
CALCULATED VERT. DEFL.(LL) = L/999 (0.08")
ALLOWABLE DEFL.(TL)= L/360 (0.97")
CALCULATED VERT. DEFL.(TL) = L/999 (0.16")

CSI: TC=0.50/1.00 (B-D:1), BC=0.35/1.00 (M-O:1), WB=0.64/1.00 (H-K:1), SSI=0.20/1.00 (B-D:1)

DOL LUMBER=1.00 NAIL=1.00 LS BEND=1.10
COMP=1.10 SHEAR=1.10 TENS=1.10

COMPANION LIVE LOAD FACTOR = 0.50

TRUSS PLATE MANUFACTURER IS NOT RESPONSIBLE FOR QUALITY CONTROL IN THE TRUSS MANUFACTURING PLANT .

NAIL VALUES
PLATE GRIP(DRY) SHEAR SECTION (PSI) (PLI) (PLI)
MAX MIN MAX MIN MAX MIN
MT20 618 354 1667 822 2284 1656

PLATE PLACEMENT TOL. = 0.250 inches


PLATE ROTATION TOL. = 5.0 Deg.

JSI GRIP= 0.90 (H) (INPUT = 0.90)
JSI METAL= 0.53 (H) (INPUT = 1.00)



READ ALL NOTES ON THIS PAGE AND ON ENGINEERING NOTE PAGE ENP-1. THIS NOTE PAGE IS AN INTEGRAL PART OF THIS DRAWING AS IT CONTAINS SPECIFICATIONS AND CRITERIA USED IN THE DESIGN OF THIS COMPONENT.





LUMBER
N. L. G. A. RULES

CHORDS	SIZE	DRY	LUMBER	DESCR.
A - C	2x4	DRY	No.2	SPF
C - E	2x4	DRY	No.2	SPF
E - G	2x4	DRY	No.2	SPF
G - H	2x4	DRY	No.2	SPF
H - J	2x4	DRY	No.2	SPF
K - B	2x4	DRY	No.2	SPF
K - I	2x4	DRY	No.2	SPF
Q - N	2x4	DRY	No.2	SPF
N - K	2x4	DRY	No.2	SPF
ALL WEBS EXCEPT	2x3	DRY	No.2	SPF

DRY: SEASONED LUMBER.

PLATES (table is in inches)

JT	TYPE	PLATES	W	LEN	Y	X
B	TMVW-t	MT20	4.0	6.0	1.75	3.00
C	TS-t	MT20	3.0	6.0		
D	TMWW-t	MT20	3.0	4.0	1.50	1.50
E	TTW+p	MT20	3.0	5.0		
F	TMWW-t	MT20	4.0	4.0	2.00	1.25
G	TTW-h	MT20	4.0	6.0	2.25	3.00
H	TTWW+m	MT20	5.0	6.0	2.50	1.50
I	TMVW-t	MT20	4.0	6.0	1.75	3.00
K	BMV1+p	MT20	2.0	4.0		
L	BMWW-t	MT20	4.0	4.0	1.50	1.50
M	BMWWW-t	MT20	4.0	6.0	1.50	3.00
N	BS-t	MT20	3.0	6.0		
O	BMWWW-t	MT20	4.0	6.0	1.75	3.00
P	BMWW-t	MT20	4.0	4.0	1.50	1.50
Q	BMV1+p	MT20	2.0	4.0		



DIMENSIONS, SUPPORTS AND LOADINGS SPECIFIED BY FABRICATOR TO BE VERIFIED BY BUILDING DESIGNER

BEARINGS

JT	FACTORED GROSS REACTION		MAXIMUM FACTORED GROSS REACTION		INPUT BRG	REQRD BRG
	VERT	HORZ	DOWN	HORZ		
Q	1494	0	1494	0	5-8	5-8
K	1494	0	1494	0	5-8	5-8

UNFACTORED REACTIONS

JT	1ST LCASE		MAX./MIN. COMPONENT REACTIONS				
	COMBINED	SNOW	LIVE	PERM.LIVE	WIND	DEAD	SOIL
Q	1047	739 / 0	0 / 0	0 / 0	0 / 0	308 / 0	0 / 0
K	1047	739 / 0	0 / 0	0 / 0	0 / 0	308 / 0	0 / 0

BEARING MATERIAL TO BE SPF NO.2 OR BETTER AT JOINT(S) Q, K

BRACING
TOP CHORD TO BE SHEATHED OR MAX. PURLIN SPACING = 4.41 FT.
MAX. UNBRACED BOTTOM CHORD LENGTH = 10.00 FT OR RIGID CEILING DIRECTLY APPLIED.

ALL PITCH BREAKS AND PERIMETER CORNER JOINTS MUST BE LATERALLY RESTRAINED.

2x4 DRY SPF No.2 T-BRACE AT D-O, F-O

FASTEN T AND I-BRACES TO NARROW EDGE OF WEB WITH ONE ROW PER PLY OF 3" COMMON WIRE NAILS @ 6" O.C. WITH 3" MINIMUM END DISTANCE. BRACE MUST COVER 90% OF WEB LENGTH.

END VERTICAL(S) MUST BE SHEATHED OR HAVE BRACES AS INDICATED IN THE MAX. UNBRACED LENGTH COLUMN OF THE TABLE BELOW

LOADING
TOTAL LOAD CASES: (4)

CHORDS				WEBS			
MEMB.	MAX. FACTORED FORCE (LBS)	FACTORED VERT. LOAD (PLF)	MAX. UNBRACED LENGTH (LC)	MEMB.	MAX. FACTORED FORCE (LBS)	MAX. UNBRACED LENGTH (LC)	
FR-TO		FROM TO		FR-TO			
A-B	0 / 28	-77.4 -77.4	0.09 (1)	10.00	P-D	-96 / 77	0.05 (1)
B-C	-1645 / 0	-77.4 -77.4	0.50 (1)	4.63	D-O	-454 / 0	0.24 (1)
C-D	-1645 / 0	-77.4 -77.4	0.50 (1)	4.63	O-E	0 / 1105	0.25 (1)
D-E	-1296 / 0	-77.4 -77.4	0.46 (1)	5.12	O-F	-761 / 0	0.37 (1)
E-F	-1282 / 0	-77.4 -77.4	0.16 (1)	5.53	F-M	0 / 968	0.22 (1)
F-G	-2230 / 0	-77.4 -77.4	0.21 (1)	4.41	M-G	-1483 / 0	0.52 (1)
G-H	-1842 / 0	-77.4 -77.4	0.15 (1)	4.82	M-H	0 / 888	0.20 (1)
H-I	-1606 / 0	-77.4 -77.4	0.33 (1)	4.89	L-H	-168 / 10	0.06 (1)
I-J	0 / 28	-77.4 -77.4	0.09 (1)	10.00	B-P	0 / 1413	0.32 (1)
Q-B	-1443 / 0	0.0 0.0	0.15 (1)	6.81	L-I	0 / 1358	0.31 (1)
K-I	-1451 / 0	0.0 0.0	0.15 (1)	6.79			
Q-P	0 / 0	-18.2 -18.2	0.17 (4)	10.00			
P-O	0 / 1396	-18.2 -18.2	0.35 (1)	10.00			
O-N	0 / 1409	-18.2 -18.2	0.35 (1)	10.00			
N-M	0 / 1409	-18.2 -18.2	0.35 (1)	10.00			
M-L	0 / 1331	-18.2 -18.2	0.27 (1)	10.00			
L-K	0 / 0	-18.2 -18.2	0.12 (4)	10.00			

DESIGN CRITERIA

SPECIFIED LOADS:				
TOP	CH.	LL	=	23.3 PSF
		DL	=	3.0 PSF
BOT	CH.	LL	=	0.0 PSF
		DL	=	7.3 PSF
TOTAL LOAD			=	33.6 PSF

SPACING = 24.0 IN./C

LOADING IN ALL FLAT SECTIONS BASED ON A SLOPE OF 2.00/12 MINIMUM

THIS TRUSS IS DESIGNED FOR RESIDENTIAL OR SMALL BUILDING REQUIREMENTS OF PART 9, NBCC 2010

THIS DESIGN COMPLIES WITH:
- PART 9 OF OBC 2012, BCBC 2012, ABC 2014
- CSA 086-09
- TPIC 2011

(55 % OF 27.2 P.S.F. G.S.L. PLUS 8.4 P.S.F. RAIN LOAD) EQUALS 23.3 P.S.F. SPECIFIED ROOF LIVE LOAD

ALLOWABLE DEFL.(LL) = L/360 (0.97")
CALCULATED VERT. DEFL.(LL) = L/999 (0.10")
ALLOWABLE DEFL.(TL) = L/360 (0.97")
CALCULATED VERT. DEFL.(TL) = L/999 (0.23")

CSI: TC=0.50/1.00 (B-D:1), BC=0.35/1.00 (M-O:1), WB=0.52/1.00 (G-M:1), SSI=0.20/1.00 (B-D:1)

DOL LUMBER=1.00 NAIL=1.00 LS BEND=1.10
COMP=1.10 SHEAR=1.10 TENS=1.10

COMPANION LIVE LOAD FACTOR = 0.50

TRUSS PLATE MANUFACTURER IS NOT RESPONSIBLE FOR QUALITY CONTROL IN THE TRUSS MANUFACTURING PLANT.

NAIL VALUES

PLATE	GRIP(DRY)	SHEAR	SECTION
(PSI)	(PLI)	(PLI)	(PLI)
MAX MIN	MAX MIN	MAX MIN	MAX MIN
MT20	618 354	1667 822	2284 1656


PLATE PLACEMENT TOL. = 0.250 inches

PLATE ROTATION TOL. = 5.0 Deg.

JSI GRIP= 0.89 (M) (INPUT = 0.90)
JSI METAL= 0.55 (G) (INPUT = 1.00)

READ ALL NOTES ON THIS PAGE AND ON ENGINEERING NOTE PAGE ENP-1. THIS NOTE PAGE IS AN INTEGRAL PART OF THIS DRAWING AS IT CONTAINS SPECIFICATIONS AND CRITERIA USED IN THE DESIGN OF THIS COMPONENT.





TOTAL WEIGHT = 44 lb [M][F]

LUMBER			
N. L. G. A. RULES			
CHORDS	SIZE	DRY	LUMBER
A - C	2x4	DRY	No.2
C - E	2x4	DRY	No.2
H - B	2x4	DRY	No.2
F - D	2x4	DRY	No.2
H - F	2x4	DRY	No.2
ALL WEBS EXCEPT	2x3	DRY	No.2

DRY: SEASONED LUMBER.

PLATES (table is in inches)

JT	TYPE	PLATES	W	LEN	Y	X
B	TMVW-t	MT20	3.0	5.0	1.50	2.00
C	TTW+p	MT20	3.0	4.0	2.25	1.50
D	TMVW-t	MT20	3.0	5.0	1.50	2.00
F	BMV1+p	MT20	2.0	4.0		
G	BMWW-t	MT20	3.0	6.0		
H	BMV1+p	MT20	2.0	4.0		

DIMENSIONS, SUPPORTS AND LOADINGS SPECIFIED BY FABRICATOR TO BE VERIFIED BY BUILDING DESIGNER

BEARINGS		FACTORED GROSS REACTION	MAXIMUM FACTORED GROSS REACTION	INPUT BRG	REQRD BRG
JT		VERT	HORZ	UPLIFT	IN-SX
H		602	0	0	5-8
F		602	0	0	5-8

UNFACTORED REACTIONS

JT	1ST LCASE	MAX./MIN. COMPONENT REACTIONS	SNOW	LIVE	PERM.LIVE	WIND	DEAD	SOIL
H	COMBINED	420	305 / 0	0 / 0	0 / 0	0 / 0	116 / 0	0 / 0
F	COMBINED	420	305 / 0	0 / 0	0 / 0	0 / 0	116 / 0	0 / 0

BEARING MATERIAL TO BE SPF NO.2 OR BETTER AT JOINT(S) H, F

BRACING

TOP CHORD TO BE SHEATHED OR MAX. PURLIN SPACING = 6.25 FT.
MAX. UNBRACED BOTTOM CHORD LENGTH = 10.00 FT OR RIGID CEILING DIRECTLY APPLIED.

ALL PITCH BREAKS AND PERIMETER CORNER JOINTS MUST BE Laterally RESTRAINED.

LOADING

TOTAL LOAD CASES: (4)

CHORDS				WEBS			
MEMB.	MAX. FACTORED FORCE (LBS)	FACTORED VERT. LOAD (PLF)	FACTORED LC1 MAX CSI (LC)	MEMB.	MAX. FACTORED FORCE (LBS)	FACTORED VERT. LOAD (PLF)	FACTORED LC1 MAX CSI (LC)
FR-TO		FROM	TO	FR-TO		FROM	TO
A-B	0 / 28	-77.4	-77.4 0.09 (1)	10.00	G-C	0 / 93	0.03 (4)
B-C	-365 / 0	-77.4	-77.4 0.27 (1)	6.25	B-G	0 / 310	0.07 (1)
C-D	-365 / 0	-77.4	-77.4 0.27 (1)	6.25	G-D	0 / 310	0.07 (1)
D-E	0 / 28	-77.4	-77.4 0.09 (1)	10.00			
H-B	-565 / 0	0.0	0.0 0.06 (1)	7.81			
F-D	-565 / 0	0.0	0.0 0.06 (1)	7.81			
H-G	0 / 0	-18.2	-18.2 0.14 (4)	10.00			
G-F	0 / 0	-18.2	-18.2 0.14 (4)	10.00			

DESIGN CRITERIA

SPECIFIED LOADS:

TOP CH.	LL	=	23.3	PSF
	DL	=	3.0	PSF
BOT CH.	LL	=	0.0	PSF
	DL	=	7.3	PSF
TOTAL LOAD		=	33.6	PSF

SPACING = 24.0 IN. C/C

THIS TRUSS IS DESIGNED FOR RESIDENTIAL OR SMALL BUILDING REQUIREMENTS OF PART 9, NBCC 2010

THIS DESIGN COMPLIES WITH:
- PART 9 OF OBC 2012, BCBC 2012, ABC 2014
- CSA 086-09
- TPIC 2011

(55 % OF 27.2 P.S.F. G.S.L. PLUS 8.4 P.S.F. RAIN LOAD) EQUALS 23.3 P.S.F. SPECIFIED ROOF LIVE LOAD

ALLOWABLE DEFL.(LL)= L/360 (0.35")
CALCULATED VERT. DEFL.(LL) = L/ 999 (0.00")
ALLOWABLE DEFL.(TL)= L/360 (0.35")
CALCULATED VERT. DEFL.(TL) = L/ 999 (0.02")

CSI: TC=0.27/1.00 (C-D:1), BC=0.14/1.00 (F-G:4), WB=0.07/1.00 (B-G:1), SSI=0.13/1.00 (C-D:1)

DOL LUMBER=1.00 NAIL=1.00 LS BEND=1.10
COMP=1.10 SHEAR=1.10 TENS= 1.10

COMPANION LIVE LOAD FACTOR = 0.50

TRUSS PLATE MANUFACTURER IS NOT RESPONSIBLE FOR QUALITY CONTROL IN THE TRUSS MANUFACTURING PLANT .

NAIL VALUES

PLATE	GRIP(DRY)	SHEAR	SECTION
(PSI)	(PLI)	(PLI)	(PLI)
MAX	MIN	MAX	MIN
MT20	618	354	1667
	822	2284	1656

PLATE PLACEMENT TOL. = 0.250 inches


PLATE ROTATION TOL. = 5.0 Deg.

JSI GRIP= 0.68 (G) (INPUT = 0.90)
JSI METAL= 0.16 (D) (INPUT = 1.00)



READ ALL NOTES ON THIS PAGE AND ON ENGINEERING NOTE PAGE ENP-1. THIS NOTE PAGE IS AN INTEGRAL PART OF THIS DRAWING AS IT CONTAINS SPECIFICATIONS AND CRITERIA USED IN THE DESIGN OF THIS COMPONENT.





TOTAL WEIGHT = 3 X 42 = 125 lb

LUMBER			
CHORDS	SIZE	DRY	LUMBER
A - C	2x4	DRY	No.2
C - D	2x4	DRY	No.2
G - B	2x4	DRY	No.2
E - D	2x4	DRY	No.2
G - E	2x4	DRY	No.2
ALL WEBS EXCEPT	2x3	DRY	No.2

DRY: SEASONED LUMBER.

PLATES (table is in inches)

JT	TYPE	PLATES	W	LEN	Y	X
B	TMVW-t	MT20	3.0	5.0	1.50	2.00
C	TTW+p	MT20	3.0	4.0	2.25	1.50
D	TMVW-t	MT20	3.0	5.0	1.50	2.00
E	BMV1+p	MT20	2.0	4.0		
F	BMVWW-t	MT20	4.0	6.0		
G	BMV1+p	MT20	2.0	4.0		

DIMENSIONS, SUPPORTS AND LOADINGS SPECIFIED BY FABRICATOR TO BE VERIFIED BY BUILDING DESIGNER

BEARINGS

JT	FACTORED GROSS REACTION	MAXIMUM FACTORED GROSS REACTION	INPUT BRG	REQRD BRG
	VERT	HORZ	DOWN	HORZ
G	596	0	596	0
E	496	0	496	0

A SUITABLE MECHANICAL CONNECTION IS REQUIRED AT JOINT E TO RESIST THE MAX FACTORED REACTIONS.

UNFACTORED REACTIONS

JT	1ST LCASE	MAX/MIN. COMPONENT REACTIONS	SNOW	LIVE	PERM.LIVE	WIND	DEAD	SOIL
G	416	302 / 0	0 / 0	0 / 0	0 / 0	0 / 0	115 / 0	0 / 0
E	348	242 / 0	0 / 0	0 / 0	0 / 0	0 / 0	107 / 0	0 / 0

BEARING MATERIAL TO BE SPF NO.2 OR BETTER AT JOINT(S) G

BRACING

TOP CHORD TO BE SHEATHED OR MAX. PURLIN SPACING = 6.25 FT.
MAX. UNBRACED BOTTOM CHORD LENGTH = 10.00 FT OR RIGID CEILING DIRECTLY APPLIED.

ALL PITCH BREAKS AND PERIMETER CORNER JOINTS MUST BE Laterally RESTRAINED.

LOADING

TOTAL LOAD CASES: (4)

CHORDS				WEBS			
MEMB.	MAX. FACTORED FORCE (LBS)	FACTORED VERT. LOAD (PLF)	MAX. CSI (LC)	MEMB.	MAX. FACTORED FORCE (LBS)	MAX. CSI (LC)	
FR-TO		FROM	TO	FR-TO			
A-B	0 / 28	-77.4	-77.4 0.09 (1)	10.00	F-C	-6 / 90	0.03 (4)
B-C	-357 / 0	-77.4	-77.4 0.27 (1)	6.25	B-F	0 / 302	0.07 (1)
C-D	-357 / 0	-77.4	-77.4 0.26 (1)	6.25	F-D	0 / 304	0.07 (1)
G-B	-559 / 0	0.0	0.0 0.06 (1)	7.81			
E-D	-460 / 0	0.0	0.0 0.05 (1)	7.81			
G-F	0 / 0	-18.2	-18.2 0.14 (4)	10.00			
F-E	0 / 0	-18.2	-18.2 0.14 (4)	10.00			

DESIGN CRITERIA

SPECIFIED LOADS:

TOP CH.	LL	=	23.3	PSF
DL	=	3.0	PSF	
BOT CH.	LL	=	0.0	PSF
DL	=	7.3	PSF	
TOTAL LOAD	=	33.6	PSF	

SPACING = 24.0 IN./C

THIS TRUSS IS DESIGNED FOR RESIDENTIAL OR SMALL BUILDING REQUIREMENTS OF PART 9, NBCC 2010

THIS DESIGN COMPLIES WITH:
- PART 9 OF OBC 2012, BCBC 2012, ABC 2014
- CSA 086-09
- TPIC 2011

(55 % OF 27.2 P.S.F. G.S.L. PLUS 8.4 P.S.F. RAIN LOAD) EQUALS 23.3 P.S.F. SPECIFIED ROOF LIVE LOAD

ALLOWABLE DEFL.(LL)= L/360 (0.35")
CALCULATED VERT. DEFL.(LL) = L/ 999 (0.00")
ALLOWABLE DEFL.(TL)= L/360 (0.35")
CALCULATED VERT. DEFL.(TL) = L/ 999 (0.02")

CSI: TC=0.27/1.00 (B-C:1) , BC=0.14/1.00 (E-F:4) , WB=0.07/1.00 (D-F:1) , SSI=0.13/1.00 (B-C:1)

DOL LUMBER=1.00 NAIL=1.00 LS BEND=1.10
COMP=1.10 SHEAR=1.10 TENS= 1.10

COMPANION LIVE LOAD FACTOR = 0.50

TRUSS PLATE MANUFACTURER IS NOT RESPONSIBLE FOR QUALITY CONTROL IN THE TRUSS MANUFACTURING PLANT .

NAIL VALUES

PLATE	GRIP(DRY)	SHEAR	SECTION
(PSI)	(PLI)	(PLI)	(PLI)
MAX	MIN	MAX	MIN
MT20	618	354	1667
	822	2284	1656

PLATE PLACEMENT TOL. = 0.250 inches

PLATE ROTATION TOL. = 5.0 Deg.

JSI GRIP= 0.51 (B) (INPUT = 0.90)
JSI METAL= 0.16 (B) (INPUT = 1.00)



READ ALL NOTES ON THIS PAGE AND ON ENGINEERING NOTE PAGE ENP-1. THIS NOTE PAGE IS AN INTEGRAL PART OF THIS DRAWING AS IT CONTAINS SPECIFICATIONS AND CRITERIA USED IN THE DESIGN OF THIS COMPONENT.





BEARING ANCHORAGE BY TOE-NAILS FOR LATERAL CAPACITY

B37579H1

NAIL TYPE	LENGTH (IN)	DIAMETER (IN)	NAIL LATERAL CAPACITY (LB)	
			S-P-F	D. FIR
COMMON WIRE	3.00	0.144	132	147
	3.25	0.144	132	147
	3.50	0.160	159	177

NOTES:

1. Rafter and ceiling members may be anchored to top and bottom chords of girder truss by toe-nailing rafter and ceiling members to girder chords provided the reaction does not exceed the lateral capacities in the table. Hangers (specified by others) are required for reactions higher than the maximum toe-nail capacity. Reactions are based on factored loads.
2. Toe nail capacities shown in the table are for **one** toe-nail. For additional toe-nails multiply values in table by the number of toe-nails used. Toe-nail capacities take into account toe-nailing factor J_A in CSA O86-09, section 10.9.4.1.
3. For 9- 3/4 gauge 3.25" common wire gun nails (diameter = 0.120") use 3" common spiral nail values.
4. Maximum number of toe-nails allowed depends on the lumber size & species to be toe-nailed to supporting member and nail diameter, as shown in tables below.
5. Nail values in table are based on the following relative lumber densities: G = 0.42 (SPF), G = 0.49 (D. Fir).
6. Toe-nails shall be driven at approximately 1/3 the nail length from the edge of the joist/truss chord and driven at an angle of 30° to the grain of the member (See next page for nailing on bearing plate).
7. For loads due to **wind** the nail lateral capacity in this table may be multiplied by 1.15 (K_D factor).
8. Lumber must be dry (< 19% moisture content) at the time of nail installation.
9. Nail values in this table comply with CSA O86-09, section 10.9.4
10. This design is not valid after April 30, 2019.



Nail type	Common wire	Common spiral	Common wire
Nail dia. (in)	0.160	0.152	0.144
	(3.5" nail)		(3" and 3.25" nail)
LUMBER SIZE	MAXIMUM NUMBER OF TOE-NAILS		
2X4 SPF	2	2	3
2X4 D. Fir	2	2	2
2X6 SPF	4	4	4
2X6 D. Fir	3	3	3



MiTek Canada Inc
100 Industrial Rd.
Bradford, Ontario L3Z 3G7

PEO
Certificate No. 10889485



April 26, 2017

BEARING ANCHORAGE BY TOE-NAILS FOR WIND LOADING

B37579H2



NAIL TYPE	LENGTH (IN)	DIAMETER (IN)	NAIL WITHDRAWAL CAPACITY (LB)	
			S-P-F	D. FIR
COMMON WIRE	3.00	0.144	30	42
	3.25	0.144	32	45
	3.50	0.160	38	52

Note: If using truss with D. Fir lumber and S-P-F bearing plate, use values in table for S-P-F.



NOTES:

1. Truss chord, rafter, or ceiling members may be anchored to bearing plate by toe-nails, provided that the actual factored uplift force due to **wind or earthquake** load does not exceed the withdrawal capacities in the table. Hangers (specified by others) are required for uplift forces that are higher than the maximum toe-nail withdrawal capacity.
2. Toe nail capacities shown in the table are for **one** toe-nail. For additional toe-nails multiply values in table by the number of toe-nails used. Toe-nail capacities take into account toe-nailing factor J_A in CSA O86-09, section 10.9.5.2.
3. For 9- 3/4 gauge 3.25" common wire gun nails (diameter = 0.120") use 3" common spiral nail values.
4. Maximum number of toe-nails allowed depends on the lumber size & species to be toe-nailed to supporting member and nail diameter, as shown in table above.
5. Nail values in table are based on the following relative lumber densities: $G = 0.42$ (SPF), $G = 0.49$ (D. Fir).
6. Toe-nails shall be driven at approximately 1/3 the nail length from the edge of the joist/truss chord and driven at an angle of 30° to the grain of the member (See drawing on detail B37579H1).
7. Lumber must be dry (< 19% moisture content) at the time of nail installation.
8. Nail values in this table comply with CSA O86-09, section 10.9.5
9. This design is not valid after April 30, 2019

Toe-nailing on 2x6 Bearing Plate



Toe-nailing on 2x4 Bearing Plate



MiTek Canada Inc
100 Industrial Rd.
Bradford, Ontario L3Z 3G7

PEO
Certificate No. 10889485



April 26, 2017