

Sales Selection Sheet
Checklist

1 of 57

LOT 62 Model: 28-2660 C THE LEMONGRASS

PURCHASERS: FOLARIN, OPEOLUWA KOMAIYA/OMOTOLA, FLORENCE KOMAIYA

VENDOR: Heathwood Homes (Williamsburg) Limited

OPTIONAL COFFERED CEILING IN GREAT ROOM

- ☐ WOB
- ☐ DECK
- ☒ FINISHED LOWER LEVEL (STD)

UPGRADED / MODIFIED ELEVATION

- ☐ CORNER UPGRADE
- ☐ REAR UPGRADE
- ☐ SIDE UPGRADE

CEILING UPGRADE - SMOOTH

- ☒ MAIN FLOOR (SITE STD)
- ☐ SECOND FLOOR
- ☐ SECOND FLOOR UPPER HALLWAY ONLY
- ☐ FINISHED LOWER LEVEL

ADDITIONAL ROUGH-INS

- ☒ 200 AMP SERVICE (SITE STD)
- ☐ WET BAR ROUGH-IN
- ☐ HUMIDIFIER
- ☒ HEAT PUMP / AIR CONDITIONING (SITE STD)

GAS ROUGH-IN

- ☐ STOVE
- ☐ DRYER
- ☐ BBQ
- ☐ ADDITIONAL GAS FIREPLACE

KITCHEN HOODFAN VENTING SIZE

- ☒ 6 IN ROUND DUCT
- ☐ 7 IN ROUND DUCT

FULL LOWER LEVEL STAIRS	Carpet Grade
UPPER LOWER LEVEL STAIRS	N/A
LOWER LOWER LEVEL STAIRS	N/A
MAIN STAIRS	All Oak

Sept 18/23 *Signatures on file*

Date Purchaser:

by email

Date Purchaser:

Locked Date:

Sept 18/23 IRIT SALEM

Date Decor Consultant:

[Stamp]

-09- 18 2023 *mRosen*

Date Heathwood Homes (Williamsburg)

Approved Limited


Customer Colours

FOLARIN, OPEOLUWA KOMAIYA/OMOTOLA, FLORENCE KOMAIYA
Project: Williamsburg Green
Unit: 62, Phase: 1
Model: 28-2660 C THE LEMONGRASS

Created: 10/17/2023 13:36:53
Locked:
Closed:

Kitchen

Cabinet Colour/Style	9111	Viking III-SIMCOE ORCHID 3DL ***STD***
Island Cabinet Colour/Style	9111	Viking III-SIMCOE ORCHID 3DL ***STD***
Cabinet Hardware	2098	12801-HARDWARE ***STD***
Countertop	9814	Group 2-Quartz-Caesarstone-ASHEN MARBLE # 7512-3/4 inch B/U MITERED EDGE ***2***
Island Countertop	9814	Group 2-Quartz-Caesarstone-ASHEN MARBLE # 7512-3/4 inch B/U MITERED EDGE ***2***
Countertop Edge	4006	GROUP 2 - DOUBLE MITRE 1 1/2 INCH ***UPG***



- Please note some islands may require a seam as per manufacturer and fabricator discretions.

Opt. Crumb Vac Colour	1111	N/A *****	
Kitchen Sink	9557	BLANCO SILGRANIT PRECIS U SUPER SINGLE 400890 ANTHRACITE (min cabinet 36 in)	PG 25
HoodFan	9068	KVWB606HBS KITCHEN AID 36 BLACK STAINLESS STEEL CHIMNEY HOOD	PG 38-41
Opt. Backsplash	1111	N/A *****	
Opt. Backsplash Grout	1111	N/A *****	
Opt. Backsplash Tile Pattern	1111	N/A *****	
Flooring	9554	Red Oak Pearl-Vintage Engineered-SHALE-3/4 inch x 3 1/4 inch ***UPG***	
Floor Tile Grout	1111	N/A *****	
Floor Tile Pattern	1111	N/A *****	

- Purchasers have been advised: standard fridge opening is a minimum 37 3/8 x 73 3/8 inches. Ice Waterline Rough-In is included.
- Standard stove opening is 30 inches and standard dishwasher opening is 24 inches. Any gas stove will require backsplash or stainless steel backing to avoid fire hazards.
- Purchasers acknowledge: Heathwood Homes and its contractors will not be responsible for any kitchen cabinet changes due to appliances dimension changes after sign-off.

Comment

Hall and Closet (from Mud to Kitchen)

Flooring	9106	GE.MD.WHT.1818.MT Madison Series White Matte 18 X 18 Matte ***1***
Floor Tile Grout	2225	Grout-(27) Silver ***STD***

- F.K O.K

FOLARIN, OPEOLUWA KOMAIYA/OMOTOLA, FLORENCE KOMAIYA
Project: Williamsburg Green
Unit: 62, Phase: 1
Model: 28-2660 C THE LEMONGRASS

Created: 10/17/2023 13:56:53
Locked:
Closed:

Floor Tile Pattern	3000	STANDARD SQUARE ***STD***									
<table><tr><td></td><td></td><td></td></tr><tr><td></td><td></td><td></td></tr><tr><td></td><td></td><td></td></tr></table>											
Comment											

Foyer

Flooring	9106	GE.MD.WHT.1818.MT Madison Series White Matte 18 X 18 Matte ***1***									
Floor Tile Grout	2225	Grout-(27) Silver ***STD***									
Floor Tile Pattern	3000	STANDARD SQUARE ***STD***									
<table><tr><td></td><td></td><td></td></tr><tr><td></td><td></td><td></td></tr><tr><td></td><td></td><td></td></tr></table>											
Comment											

Powder Room

Flooring	9106	GE.MD.WHT.1818.MT Madison Series White Matte 18 X 18 Matte ***1***									
Floor Tile Grout	2225	Grout-(27) Silver ***STD***									
Floor Tile Pattern	3000	STANDARD SQUARE ***STD***									
<table><tr><td></td><td></td><td></td></tr><tr><td></td><td></td><td></td></tr><tr><td></td><td></td><td></td></tr></table>											
Plumbing Fixture (Colour)	1737	Plumbing Fixtures-WHITE ***STD***									
Opt. Vanity	1111	N/A *****									
Opt. Vanty Hardware	1111	N/A *****									
Opt. Vanity Countertop	1111	N/A *****									

Mud Room

Floor Tile	9106	GE.MD.WHT.1818.MT Madison Series White Matte 18 X 18 Matte ***1***									
Floor Tile Grout	2225	Grout-(27) Silver ***STD***									
Floor Tile Pattern	3000	STANDARD SQUARE ***STD***									
<table><tr><td></td><td></td><td></td></tr><tr><td></td><td></td><td></td></tr><tr><td></td><td></td><td></td></tr></table>											
Comment											

FOLARIN, OPEOLUWA KOMAIYA/OMOTOLA, FLORENCE KOMAIYA
Project: Williamsburg Green
Unit: 62, Phase: 1
Model: 28-2660 C THE LEMONGRASS

Created: 10/17/2023 13:36:53
Locked:
Closed:

Dining Room

Flooring 9554 Red Oak Pearl-Vintage Engineered-SHALE-3/4 inch x 3 1/4 inch ***STD***

Comment

Great Room

Flooring 9554 Red Oak Pearl-Vintage Engineered-SHALE-3/4 inch x 3 1/4 inch ***STD***

Comment

Great Room Fireplace

Type 8869 Majestic MERC32 ***STD***

Mantle 8891 NF-17-Paint Grade Mantle- Cabinet (Per Plan)-WHITE ***STD***

Opt. Surround 1111 N/A *****

- Purchasers have been advised: heat from the FP can damage TV above a FP and items placed on mantle.

- Heathwood and its contractors will not be liable for any damage on items placed and / or installed above a FP after closing.

Comment

Main Hall (from Foyer to Dining)

Flooring 9554 Red Oak Pearl-Vintage Engineered-SHALE-3/4 inch x 3 1/4 inch ***STD***

Comment

Upper Hall

Flooring 9507 DY 89418-MINOTAUR-BLACK ICE-40 oz Poly ***STD***


Comment

Laundry Room

Floor Tile 9106 GE.MD.WHT.1818.MT Madison Series White Matte 18 X 18 Matte ***1***

Floor Tile Grout 2225 Grout-(27) Silver ***STD***

Floor Tile Pattern 3000 STANDARD SQUARE ***STD***



Cabinet Colour/Style - Uppers 9111 Viking III-SIMCOE ORCHID 3DL ***STD***

Cabinet Hardware - Uppers 2098 12801-HARDWARE ***STD***

F.K O.K

Customer Colours

FOLARIN, OPEOLUWA KOMAIYA/OMOTOLA, FLORENCE KOMAIYA
Project: Williamsburg Green
Unit: 62, Phase: 1
Model: 28-2660 C THE LEMONGRASS

Created: 10/17/2023 13:36:53
Locked:
Closed:

Cabinet Colour/Style - Base	9111	Viking III-SIMCOE ORCHID 3DL ***STD***
Cabinet Hardware - Base	2098	12801-HARDWARE ***STD***
Countertop	8822	4924-38-Countertop-WHITE CARRARA-Wilsonart ***STD***
Opt. Countertop Edge	1111	N/A *****

Comment

Principal Suite and Walk-in Closets

Flooring	9507	DY 89418-MINOTAUR-BLACK ICE-40 oz Poly ***STD***
----------	------	--

Comment

Bedroom 2 and Walk-in Closet

Flooring	9507	DY 89418-MINOTAUR-BLACK ICE-40 oz Poly ***STD***
----------	------	--

Comment

Bedroom 3

Flooring	9507	DY 89418-MINOTAUR-BLACK ICE-40 oz Poly ***STD***
----------	------	--

Comment


Bedroom 4

Flooring	9507	DY 89418-MINOTAUR-BLACK ICE-40 oz Poly ***STD***
----------	------	--

Comment

Principal Ensuite

Cabinet Colour/Style	9111	Viking III-SIMCOE ORCHID 3DL ***STD***
Cabinet Hardware	2098	12801-HARDWARE ***STD***
Countertop	9806	Group 1-Quartz-Caesarstone-WHITE SAND # 7041-3/4 inch ***STD IN PRINCIPLAL ENSUITE ONLY***
Countertop Edge	4010	SINGLE POLISHED STRAIGHT EDGE 3/4 INCH ***STD***



Floor Tile	9760	NA.SP.WHC.1224-Spendid-White Cloud-12 x 24 ***3***
------------	------	--

S 7

Floor Tile Grout	2225	Grout (27) Silver ***STD***
------------------	------	-----------------------------

F.K O.K

Customer Colours

FOLARIN, OPEOLUWA KOMAIYA/OMOTOLA, FLORENCE KOMAIYA
Project: Williamsburg Green
Unit: 62, Phase: 1
Model: 28-2660 C THE LEMONGRASS

Created: 10/17/2023 13:38:53

Locked:

Closed:

Floor Tile Grout	2225	Grout-(27) Silver ***STD***
Floor Tile Pattern	3050	SIDE TO SIDE ***STD***
Shower Wall and Ceiling Tile	9760	NA.SP.WHC.1224-Spendid-White Cloud-12 x 24 ***3***
Shower Wall and Ceiling Tile Grout	2226	Grout-(00) White ***STD***
Shower Wall and Ceiling Tile Pattern	3090	VERTICAL STACKED ***STD***
Shower Floor Tile	8109	OD.ON.BLK.02.HEX.MT-ONTARIO HEXAGON MATTE-BLACK ***UG2***
Shower Floor Tile Grout	2221	Grout-(47) Charcoal ***UPG***
Shower Floor Tile Pattern	3120	VERTICAL HEX ***STD***
Shower Jamb(s) and Sill(s)	8927	Shower Jamb / Sill-Moonlight Black ***Upg***
Plumbing Fixture (colour)	1737	Plumbing Fixtures-WHITE ***STD***
Comment		

Ensuite 4

Cabinet Colour/Style	9120	VIKING III-GEORGIAN-ORCHID 3DL ***STD***
Cabinet Hardware	2098	12801-HARDWARE ***STD***
Countertop	9806	Group 1-Quartz-Caesarstone-WHITE SAND # 7041-3/4 inch ***STD IN PRINCIPLAL ENSUITE ONLY***
Opt. Countertop Edge	4010	GROUP 1 - SINGLE POLISHED STRAIGHT EDGE 3/4 INCH ***1***
Floor Tile	9071	GE.BY.AZR.1313 New Byzantine Azzuro 13x13 ***STD***
Floor Tile Grout	2225	Grout-(27) Silver ***STD***
Floor Tile Pattern	3000	STANDARD SQUARE ***STD***
Wall and Ceiling Tile	5411	QT.SP.WHT.0810-Splendour-White-8 inch x 10 inch ***STD***
Wall and Ceiling Tile Grout	2226	Grout-(00) White ***STD***
Wall and Ceiling Tile Pattern	3090	VERTICAL STACKED ***STD***

F.K O-K

FOLARIN, OPEOLUWA KOMAIYA/OMOTOLA, FLORENCE KOMAIYA
Project: Williamsburg Green
Unit: 62, Phase: 1
Model: 28-2660 C THE LEMONGRASS

Created: 10/17/2023 13:36:53
Locked:
Closed:

Shower Floor Tile	8661	OD.ON.SWT.0202.MT.N-Ontario Series Mosaic-Snow White Matte-2 x 2 ***STD***		
Shower Floor Tile Grout	2226	Grout-(00) White ***STD***		
Shower Floor Tile Pattern	3000	STANDARD SQUARE ***STD***		
Shower Jamb(s) and Sill(s)	8923	Shower Jamb / Sill-Thassos White ***STD***		
Plumbing Fixture (colour)	1737	Plumbing Fixtures-WHITE ***STD***		
Comment				

Shared Bath

Cabinet Colour/Style	9533	Viking III-TRINITY LPL-FREE SPIRIT L580K ***STD***		
Lower Level Recreation Room	1111	N/A *****		
Cabinet Hardware	2098	12801-HARDWARE ***STD***		
Countertop	9806	Group 1-Quartz-Caesarstone-WHITE SAND # 7041-3/4 inch ***STD IN PRINCIPLAL ENSUITE ONLY***		
Opt. Countertop Edge	4010	GROUP 1 - SINGLE POLISHED STRAIGHT EDGE 3/4 INCH ***1***		
Floor Tile	8261	TR.ST.BYZ.1313-Serpentine-Beyaz/White-13x13 ***STD***		
Floor Tile Grout	2225	Grout-(27) Silver ***STD***		
Floor Tile Pattern	3000	STANDARD SQUARE ***STD***		
Wall Tile	8257	TR.ST.BYZ.0810-Serpentine-Beyaz/White-8 x 10 ***STD***		
Wall Tile Grout	2226	Grout-(00) White ***STD***		
Wall Tile Pattern	3090	VERTICAL STACKED ***STD***		
Opt. Shower Floor Tile	1111	N/A *****		
Opt. Shower Floor Tile Grout	1111	N/A *****		
Opt. Shower Floor Tile Pattern	1111	N/A *****		

FOLARIN, OPEOLUWA KOMAIYA/OMOTOLA, FLORENCE KOMAIYA
Project: Williamsburg Green
Unit: 62, Phase: 1
Model: 28-2660 C THE LEMONGRASS

Created: 10/17/2023 13:36:53
Locked:
Closed:

Opt. Shower Jamb(s) and Sill(s)	1111	N/A *****
Opt. Wall and Ceiling Tile	1111	N/A *****
Opt. Wall and Ceiling Tile Grout	1111	N/A *****
Opt. Wall and Ceiling Tile Pattern	1111	N/A *****

Plumbing Fixture (colour)	1737	Plumbing Fixtures-WHITE ***STD***
Comment		

Lower Level Recreation Room

Flooring	9507	DY 89418-MINOTAUR-BLACK ICE-40 oz Poly ***STD***
Comment		

Lower Level Recreation Room Fireplace

Type	8865	Dimplex-Electric Fireplace-PF3033HL ***STD***
Mantle	8892	NF-17-Paint Grade Mantle-6 inch Deep Mantle (TV above Fireplace-WHITE) ***Upg***
Opt. Surround	1111	N/A *****

PG 24

- Purchasers have been advised: heat from the FP can damage TV above a FP and items placed on mantle.

- Heathwood and its contractors will not be liable for any damage on items placed and / or installed above a FP after closing.

Comment

Lower Level Bathroom

Cabinet Colour/Style	9120	VIKING III-GEORGIAN-ORCHID 3DL ***STD***
Cabinet Hardware	2098	12801-HARDWARE ***STD***
Countertop	9806	Group 1-Quartz-Caesarstone-WHITE SAND # 7041-3/4 inch ***STD IN PRINCIPAL ENSUITE ONLY***
Opt. Countertop Edge	4010	GROUP 1 - SINGLE POLISHED STRAIGHT EDGE 3/4 INCH ***1***
Floor Tile	9071	GE.BY.AZR.1313 New Byzantine Azzuro 13x13 ***STD***
Floor Tile Grout	2225	Grout-(27) Silver ***STD***
Floor Tile Pattern	3000	STANDARD SQUARE ***STD***

Shower Wall and Ceiling Tile	5111	OT SP-WHT 0010- Solid White 8 inch x 10 inch
------------------------------	------	--

F.K O.K

FOLARIN, OPEOLUWA KOMAIYA/OMOTOLA, FLORENCE KOMAIYA
Project: Williamsburg Green
Unit: 62, Phase: 1
Model: 28-2660 C THE LEMONGRASS

Created: 10/17/2023 13:36:53
Locked:
Closed:

Shower wall and Ceiling Tile	3411	QT.SP.WHT.0810-Splendour-white-8 inch x 10 inch ***STD***
Shower Wall and Ceiling Grout	2226	Grout-(00) White ***STD***
Shower Wall and Ceiling Pattern	3090	VERTICAL STACKED ***STD***
Shower Floor Tile	8661	OD.ON.SWT.0202.MT.N-Ontario Series Mosaic-Snow White Matte-2 x 2 ***STD***
Shower Floor Tile Grout	2226	Grout-(00) White ***STD***
Shower Floor Tile Pattern	3000	STANDARD SQUARE ***STD***
Shower Jamb(s) and Sill(s)	8923	Shower Jamb / Sill-Thassos White ***STD***
Plumbing Fixture (colour)	1737	Plumbing Fixtures-WHITE ***STD***
Comment		

Main Stairs

Type	1714	Oak Stairs ***STD MAIN STAIRS***
Colour	1111	N/A *****
Colour	1111	STAIN TO COMPLIMENT SHALE
Handrail/Pickets/Posts Type	8148	Single Collar Alt. Plain w/ Shoes with 3 1/2 Square/Cap Post(s)-BLACK ***2***
Handrail/Pickets/Posts Location	7761	Oak Grade-Stain handrail,stringers,treads,risers,nosingpost
Custom Stain/Paint	1111	N/A *****
Landing(s)	9554	Red Oak Pearl-Vintage Engineered-SHALE-3/4 inch x 3 1/4 inch ***STD***
Opt. Carpet Runner	1111	N/A *****
Comment		

Lower Level Stairs

Type		
Colour	9507	89418-MINOTAUR-BLACK ICE-40 oz Poly ***STD***
Type		Carpet Grade
Handrail/Pickets/Posts Type	9119	Handrail only on closed walls (one or two sides per building code) ***STD***
Handrail/Pickets/Posts Location	7762	Carpet Grade-Stain handrail, stringers, nosing_post(s). (Me
Custom Stain/Paint	1111	N/A *****

Customer Colours

FOLARIN, OPEOLUWA KOMAIYA/OMOTOLA, FLORENCE KOMAIYA
Project: Williamsburg Green
Unit: 62, Phase: 1
Model: 28-2660 C THE LEMONGRASS

Created: 10/17/2023 13:36:53
Locked:
Closed:

Landing(s)	9554	Red Oak Pearl-Vintage Engineered-SHALE-3/4 inch x 3 1/4 inch ***UPG***
Opt. Carpet Runner	1111	N/A *****
Comment	UPPER BASEMENT LANDING - HARDWOOD	

Throughout

Switches and Plug	5796	Decora White Switches and Plugs ***STD***
Thresholds	2232	Metal Thresholds ***STD***
Underpad	1079	500 Series-Underpad ***STD***
Trim Size	8705	4 1/4 Baseboard and 2 3/4 Casings ***STD***
Trim - Paint Colour	1716	Trim-WHITE ***STD***
Walls - Paint Colour	1717	22-Wall-WARM GREY ***STD***
Comment		

Purchaser:		NOV 6, 2023		Nov. 8 23
	FOLARIN, OPEOLUWA KOMAIYA	Date	Decor Consultant	Date

Purchaser:		NOV 6 2023		-11- 15 2023
	OMOTOLA, FLORENCE KOMAIYA	Date	Williamsburg Green	Date Approved

F.K O.K



CONSTRUCTION SUMMARY

Lot: 62
Model: 28-2660 C THE LEMONGRASS
Project/Phase: Williamsburg Green / 1

Offer	Finished Lower Level Complete with Finished Bathroom.
Worksheet	Note:

Offer	Ten Thousand Dollars (\$10,000) At D?cor. (No Cash Value) Singles
Worksheet	Note:



CONSTRUCTION SUMMARY

Lot: 62
Model: 28-2660 C THE LEMONGRASS
Project/Phase: Williamsburg Green / 1

APPLIANCES

Invoice	Qty.	Description
1572 362,466 06Dec23	1	- APPLIANCES-KITCHENAID 36 INCH CHIMNEY HOOD BLACK SS-KVWB606HBS CABINETRY-delete stove uppers; ELECTRICAL-delete std range hood; HEATING/AIR CONDITIONING-Duct S change to 6 in

CABINETRY

Invoice	Qty.	Description
1572 362,522 06Dec23	1	KITCHEN - CABINETRY-B18-PER UNIT 60CM WIDE PULL-OUT DOOR BASE CABINET WASTE/RECYCLE CENTRE WITH SOFT-CLOSE ([4] BINS TOTAL, INCLUDING [2] 35L) (AVAILABLE ONLY WITH 60CM WIDE CABINET) VIKING TO BE INSTALLED IN THE ISLAND BESIDE THE SINK SEE SKETCH # 3
1572 375,631 06Dec23	1	KITCHEN - CABINETRY - OPT.BUILT IN CABINET (SEE SEPARATE CHARGE ON COOKTOP CUTOUT) - VIKING - UPG SKETCH # 3 SEE SPECS DRYWAL-Notify; FRAMING-Modify Bulkhead; GRANITE-delete partial countertop due to Built-in; PAINTING-
1572 363,163 06Dec23 **	1	KITCHEN - PLUMBING-BLANCO-SILGRANIT PRECIS U SUPER SINGLE MODEL 400890-ANTHRACITE CABINETRY-see specs for upgraded kitchen sink; GRANITE-see specs for upgraded kitchen sink
1572 06Dec23 ** NoCat	1	KITCHEN - KITCHEN - RED OAK PEARL VITAGE ENGINEERED SHALE 3/4 INCH X 3 1/4 INCH CABINETRY-Raise Cabinet; CERAMICS-Delete Std Ceramics; Interior Stairs-Adjust riser height where applicabl
1572 362,466 06Dec23 **	1	- APPLIANCES-KITCHENAID 36 INCH CHIMNEY HOOD BLACK SS-KVWB606HBS CABINETRY-delete stove uppers; ELECTRICAL-delete std range hood; HEATING/AIR CONDITIONING-Duct S change to 6 in
1572 362,508 06Dec23	3	KITCHEN - CABINETRY-B07-ADDITIONAL KITCHEN TOP DRAWER (PER DRAWER) VIKING SEE SKETCH # 3
1572 364,363 06Dec23 **	1	Opt. Lower Bath - GRANITE-GROUP 1-OPT. LOWER BATH-UPG CABINETRY-delete std countertop; GRANITE-see upgraded single hole faucet and undermount sink specs
1572 364,371 06Dec23 **	1	Opt. Shared Bath - GRANITE-GROUP 1-OPT. SHARED BATH-UPG CABINETRY-delete std countertop; GRANITE-see upgraded single hole faucet and undermount sink specs
1572 364,379 06Dec23 **	1	Opt. Bed 4 ensuite - GRANITE-GROUP 1-OPT. BED 4 ENSUITE-UPG CABINETRY-delete std countertop; GRANITE-see upgraded single hole faucet and undermount sink specs



CONSTRUCTION SUMMARY

Lot: 62
Model: 28-2660 C THE LEMONGRASS
Project/Phase: Williamsburg Green / 1

CABINETRY

Invoice	Qty.	Description
1572	1	LAUNDRY ROOM - PURCHASER IS INSTALLING STACKED WASHER/DRYER BESIDE BASE CABINET. INSTALL STANDARD LAUNDRY UPPER CABINETS ABOVE BASE CABINET ONLY- DELETE OTHER UPPER CABINETS
06Dec23 NoCat		SKETCH # 5 SEE SPEC FOR STACKED LG WASHER/DRYER ELECTRICAL-Relocation; HEATING/AIR CONDITIONING-Notify; PLUMBING-Relocation

SEE REVISED COLOUR PGS 58-59

CERAMIC

Invoice	Qty.	Description
1572 371,540 06Dec23	1	FOYER - CERAMICS-FLOOR -UG 1-FOYER
1572 371,560 06Dec23	1	MUDROOM and Hallway in Front of Powder - CERAMICS-FLOOR -UG 1-MUDROOM AND HALLWAY IN FRONT OF POWDER
1572 371,550 06Dec23	1	POWDER ROOM - CERAMICS-FLOOR -UG 1-POWDER ROOM
1572 371,600 06Dec23	1	LAUNDRY - CERAMICS-FLOOR -UG 1-LAUNDRY
1572 371,592 06Dec23	1	PRINCIPAL ENSUITE - CERAMICS-FLOOR -UG 3-PRINCIPAL ENSUITE
1572 371,645 06Dec23	1	PRINCIPAL ENSUITE SHOWER INCLUDING CEILING - CERAMICS-FLOOR ON WALL-UG 3-PRINCIPAL ENSUITE SHOWER INCLUDING CEILING
1572 371,679 06Dec23	1	PRINCIPAL ENSUITE SHOWER - CERAMICS-SHOWER FLOOR-GROUT-PRINCIPAL ENSUITE SHOWER
1572 371,673 06Dec23	1	PRINCIPAL ENSUITE SHOWER - CERAMICS-SHOWER FLOOR-UG 2-PRINCIPAL ENSUITE SHOWER

CERAMICS

Invoice	Qty.	Description
1572	1	KITCHEN - KITCHEN - RED OAK PEARL VITAGE ENGINEERED SHALE 3/4 INCH X 3 1/4 INCH
06Dec23 ** NoCat		CABINETRY-Raise Cabinet; CERAMICS-Delete Std Ceramics; Interior Stairs-Adjust riser height where applicab
1572 362,726 06Dec23	1	MASTER ENSUITE - CERAMICS-UPGRADED SHOWER JAMB/SILL COLOUR MOONLIGHT BLACK #8927



CONSTRUCTION SUMMARY

Lot: 62
Model: 28-2660 C THE LEMONGRASS
Project/Phase: Williamsburg Green / 1

COFFERED CEILING

Invoice	Qty.	Description
1552 363,402 16Nov23	1	GREAT ROOM - COFFERED CEILING - OPT. COFFERED CEILING - GREAT ROOM - UPG SKETCH # 2 DRYWALL-Notify; FRAMING-Notify; PAINTING-Notify

DRYWALL

Invoice	Qty.	Description
1552 363,402 16Nov23 **	1	GREAT ROOM - COFFERED CEILING - OPT. COFFERED CEILING - GREAT ROOM - UPG SKETCH # 2 DRYWALL-Notify; FRAMING-Notify; PAINTING-Notify
1552 363,410 16Nov23 **	1	- CLASSIC COLLECTION SCHEDULE A - Choice of 20 LED pot lights in finished areas (Second Floor Potlight(s) Require Smooth Ceiling) DRYWALL-Drywall Ceiling cutouts for potlights FRAMING-Frame to accommodate potlights 8 X IN GREAT ROOM,- USE SEPARATE SWITCH 8 X IN KITCHEN- USE EXSITING 4 WAY SWITCH, RELOCATE STD. LIGHTS (x3) ON A SEPARATE SWITCH 4 X IN DINING ROOM - USE SEPARATE SWITCH. KEEP STD. LIGHT WITH SWITCH SEE SKETCH # 2
1572 375,631 06Dec23 **	1	KITCHEN - CABINETRY - OPT.BUILT IN CABINET (SEE SEPARATE CHARGE ON COOKTOP CUTOUT) - VIKING - UPG SKETCH # 3 SEE SPECS DRYWAL-Notify; FRAMING-Modify Bulkhead; GRANITE-delete partial countertop due to Built-in; PAINTING-



CONSTRUCTION SUMMARY

Lot: 62
Model: 28-2660 C THE LEMONGRASS
Project/Phase: Williamsburg Green / 1

ELECTRICAL

Invoice	Qty.	Description
1552 363,261 16Nov23	3	KITCHEN - ELECTRICAL-RELOCATION OF SWITCHES/LIGHTS RELOCATE 3 X STD. KITCHEN LIGHTS TO BE CAPPED CEILING ABOVE THE BREAKFAST BAR-FOR FUTURE PENDANT LIGHTS USE SEPARATE SWITCH (FROM THE POT LIGHT PACKAGE. SWITCH) SEE SKETCH # 2
1552 363,222 16Nov23	2	THROUGHOUT - ELECTRICAL-INTERIOR DUPLEX OUTLET ON EXISTING CIRCUIT 1X GREAT ROOM- TO BE INSTALLED ABOVE THE GREAT ROOM FIRE PLACE 70"-+ FROM FLOOR 1X REC. ROOM 70"-+ FROM FLOOR SKETCH #S 1 AND 2
1552 363,410 16Nov23	1	- CLASSIC COLLECTION SCHEDULE A - Choice of 20 LED pot lights in finished areas (Second Floor Potlight(s) Require Smooth Ceiling) DRYWALL-Drywall Ceiling cutouts for potlights FRAMING-Frame to accommodate potlights 8 X IN GREAT ROOM,- USE SEPARATE SWITCH 8 X IN KITCHEN- USE EXSITING 4 WAY SWITCH, RELOCATE STD. LIGHTS (x3) ON A SEPARATE SWITCH 4 X IN DINING ROOM - USE SEPARATE SWITCH. KEEP STD. LIGHT WITH SWITCH SEE SKETCH # 2
1572 362,466 06Dec23 **	1	- APPLIANCES-KITCHENAID 36 INCH CHIMNEY HOOD BLACK SS-KVWB606HBS CABINETRY-delete stove uppers; ELECTRICAL-delete std range hood; HEATING/AIR CONDITIONING-Duct S change to 6 in
1572 363,230 06Dec23	1	KITCHEN - ELECTRICAL-ADDITIONAL 240V 40AMP DIRECT LINE FOR ADDITIONAL APPLIANCE TO BE USED FOR THE BUILT IN WALL OVEN / MICROWAVE SKETCH # 3 SEE SPECS
1572 06Dec23 ** NoCat	1	LAUNDRY ROOM - PURCHASER IS INSTALLING STACKED WASHER/DRYER BESIDE BASE CABINET. INSTALL STANDARD LAUNDRY UPPER CABINETS ABOVE BASE CABINET ONLY- DELETE OTHER UPPER CABINETS SKETCH # 5 SEE SPEC FOR STACKED LG WASHER/DRYER ELECTRICAL-Relocation; HEATING/AIR CONDITIONING-Notify; PLUMBING-Relocation

FRAMING

Invoice	Qty.	Description
1552 363,402 16Nov23 **	1	GREAT ROOM - COFFERED CEILING - OPT. COFFERED CEILING - GREAT ROOM - UPG SKETCH # 2 DRYWALL-Notify; FRAMING-Notify; PAINTING-Notify
1552 363,410 16Nov23 **	1	- CLASSIC COLLECTION SCHEDULE A - Choice of 20 LED pot lights in finished areas (Second Floor Potlight(s) Require Smooth Ceiling) DRYWALL-Drywall Ceiling cutouts for potlights FRAMING-Frame to accommodate potlights 8 X IN GREAT ROOM,- USE SEPARATE SWITCH 8 X IN KITCHEN- USE EXSITING 4 WAY SWITCH, RELOCATE STD. LIGHTS (x3) ON A SEPARATE SWITCH 4 X IN DINING ROOM - USE SEPARATE SWITCH. KEEP STD. LIGHT WITH SWITCH SEE SKETCH # 2
1572 375,631 06Dec23 **	1	KITCHEN - CABINETRY - OPT.BUILT IN CABINET (SEE SEPARATE CHARGE ON COOKTOP CUTOUT) - VIKING - UPG SKETCH # 3 SEE SPECS DRYWAL-Notify; FRAMING-Modify Bulkhead; GRANITE-delete partial countertop due to Built-in; PAINTING-



CONSTRUCTION SUMMARY

Lot: 62
Model: 28-2660 C THE LEMONGRASS
Project/Phase: Williamsburg Green / 1

GLASS PRODUCTS / MIRRORS

Invoice	Qty.	Description
1572 375,667 06Dec23	1	MASTER ENSUITE - MIRRORS/GLASS PRODUCTS - CHANGE THE HARDWARE FOR 10MM FRAMELESS SHOWERS TO MATTE BLACK

GRANITE

Invoice	Qty.	Description
1572 362,792 06Dec23	1	KITCHEN - GRANITE-GRANITE CUTOUT W/ STRAIGHT EDGE POLISH TO ACCOMMODATE COOK TOP SKETCH # 3 SEE SPECS FOR 36" INDUCTION COOKTOP
1572 375,631 06Dec23 **	1	KITCHEN - CABINETRY - OPT.BUILT IN CABINET (SEE SEPARATE CHARGE ON COOKTOP CUTOUT) - VIKING - UPG SKETCH # 3 SEE SPECS DRYWAL-Notify; FRAMING-Modify Bulkhead; GRANITE-delete partial countertop due to Built-in; PAINTING-
1572 364,350 06Dec23	1	Kitchen - GRANITE-GROUP 2 WITH 1 1/2 IN MITER EDGE-KITCHEN-UPG
1572 363,163 06Dec23 **	1	KITCHEN - PLUMBING-BLANCO-SILGRANIT PRECIS U SUPER SINGLE MODEL 400890-ANTHRACITE CABINETRY-see specs for upgraded kitchen sink; GRANITE-see specs for upgraded kitchen sink
1572 364,363 06Dec23	1	Opt. Lower Bath - GRANITE-GROUP 1-OPT. LOWER BATH-UPG CABINETRY-delete std countertop; GRANITE-see upgraded single hole faucet and undermount sink specs
1572 364,371 06Dec23	1	Opt. Shared Bath - GRANITE-GROUP 1-OPT. SHARED BATH-UPG CABINETRY-delete std countertop; GRANITE-see upgraded single hole faucet and undermount sink specs
1572 364,379 06Dec23	1	Opt. Bed 4 ensuite - GRANITE-GROUP 1-OPT. BED 4 ENSUITE-UPG CABINETRY-delete std countertop; GRANITE-see upgraded single hole faucet and undermount sink specs
1572 362,794 06Dec23	3	THROUGHOUT - GRANITE-GRANITE CUTOUT WITH STRAIGHT EDGE POLISH TO ACCOMMODATE UNDER MOUNT VANITY SINK SHARED, ENS 4 AND BASEMENT BATHROOM SEE SINK SPECS

HARDWOOD

Invoice	Qty.	Description
1572 06Dec23 NoCat	1	KITCHEN - KITCHEN - RED OAK PEARL VITAGE ENGINEERED SHALE 3/4 INCH X 3 1/4 INCH CABINETRY-Raise Cabinet; CERAMICS-Delete Std Ceramics; Interior Stairs-Adjust riser height where applicab



CONSTRUCTION SUMMARY

Lot: 62
Model: 28-2660 C THE LEMONGRASS
Project/Phase: Williamsburg Green / 1

HEATING / AIR CONDITIONING

Invoice	Qty.	Description
1572 362,466 06Dec23 **	1	- APPLIANCES-KITCHENAID 36 INCH CHIMNEY HOOD BLACK SS-KVWB606HBS CABINETRY-delete stove uppers; ELECTRICAL-delete std range hood; HEATING/AIR CONDITIONING-Duct S change to 6 in
1572 06Dec23 ** NoCat	1	LAUNDRY ROOM - PURCHASER IS INSTALLING STACKED WASHER/DRYER BESIDE BASE CABINET. INSTALL STANDARD LAUNDRY UPPER CABINETS ABOVE BASE CABINET ONLY- DELETE OTHER UPPER CABINETS SKETCH # 5 SEE SPEC FOR STACKED LG WASHER/DRYER ELECTRICAL-Relocation; HEATING/AIR CONDITIONING-Notify; PLUMBING-Relocation

INTERIOR RAILINGS

Invoice	Qty.	Description
1572 375,522 06Dec23	1	- INTERIOR RAILING-SINGLE COLLAR ALT. PLAIN W/ SHOES WITH 3 1/2 IN SQUARE/CAP POST(S)-BLACK METAL-UPG 2 PAINTING-Notify

INTERIOR TRIM AND DOORS

Invoice	Qty.	Description
1572 375,522 06Dec23 **	1	- INTERIOR RAILING-SINGLE COLLAR ALT. PLAIN W/ SHOES WITH 3 1/2 IN SQUARE/CAP POST(S)-BLACK METAL-UPG 2 PAINTING-Notify

PAINTING

Invoice	Qty.	Description
1552 363,402 16Nov23 **	1	GREAT ROOM - COFFERED CEILING - OPT. COFFERED CEILING - GREAT ROOM - UPG SKETCH # 2 DRYWALL-Notify; FRAMING-Notify; PAINTING-Notify
1572 375,631 06Dec23 **	1	KITCHEN - CABINETRY - OPT.BUILT IN CABINET (SEE SEPARATE CHARGE ON COOKTOP CUTOUT) - VIKING - UPG SKETCH # 3 SEE SPECS DRYWAL-Notify; FRAMING-Modify Bulkhead; GRANITE-delete partial countertop due to Built-in; PAINTING-
1572 375,522 06Dec23 **	1	- INTERIOR RAILING-SINGLE COLLAR ALT. PLAIN W/ SHOES WITH 3 1/2 IN SQUARE/CAP POST(S)-BLACK METAL-UPG 2 PAINTING-Notify



CONSTRUCTION SUMMARY

Lot: 62
Model: 28-2660 C THE LEMONGRASS
Project/Phase: Williamsburg Green / 1

PLUMBING

Invoice	Qty.	Description
1572 363,163 06Dec23	1	KITCHEN - PLUMBING-BLANCO-SILGRANIT PRECIS U SUPER SINGLE MODEL 400890-ANTHRACITE CABINETRY-see specs for upgraded kitchen sink; GRANITE-see specs for upgraded kitchen sink
1572 363,115 06Dec23	1	- PLUMBING-MOEN-ALIGN SINGLE HANDLE PULLDOWN KITCHEN FAUCET MODEL 7565 BG-BRUSHED GOLD
1572 363,034 06Dec23	1	- PLUMBING-MOEN -RIZON- POSI-TEMP TUB/SHOWER WITH 3 FUNCTION DIVERTER VALVE, SLIDE BAR WITH HANDHELD AND SHOWERHEAD MATTE BLACK (MODEL: T2813EPBL/U361CI/UT2081BL/62320/3669EPBL/A725WR)
1572 363,054 06Dec23	1	MASTER ENSUITE - PLUMBING-MOEN -RIZON-ROMAN TUB-3 PIECE MATTE BLACK (MODEL: 4796/T935 BL) - STANDARD CHATEAU CHROME FAUCETS TO BE INSTALLED
1572 362,901 06Dec23	3	THROUGHOUT - PLUMBING-AMERICAN STANDARD-SINK OPTIONS-UNDERMOUNT SINK-OVALYN MODEL 0496 221 020 (19 INCH X 16 INCH) - SHARED , ENS.4 AND BASEMENT BATHROOM SEE SPEC
1572 06Dec23 ** NoCat	1	LAUNDRY ROOM - PURCHASER IS INSTALLING STACKED WASHER/DRYER BESIDE BASE CABINET. INSTALL STANDARD LAUNDRY UPPER CABINETS ABOVE BASE CABINET ONLY- DELETE OTHER UPPER CABINETS SKETCH # 5 SEE SPEC FOR STACKED LG WASHER/DRYER ELECTRICAL-Relocation; HEATING/AIR CONDITIONING-Notify; PLUMBING-Relocation


SECURITY

Invoice	Qty.	Description
1552 363,190 16Nov23	1	MUD ROOM - SECURITY-SECURITY KEY PAD ROUGH-IN SKETCH # 2
1552 363,189 16Nov23	1	- SECURITY-SECURITY CAMERA ROUGH-IN 1X TO BE INSTALLED ON THE REAR EXTERIOR WALL SKETCH # 2

Sketch #1

THE LEMONGRASS
ELEVATION A | 3,526 SQ. FT.
Including 866 sq. ft. of Finished Lower Level

28-2660 ELEV. C
Finished Lower Level



LOWER LEVEL
ELEVATION C

Changes made to match Architectural Plan:

- 1 Proposed electrical panel location adjusted

* Floor plan may vary due to grading conditions.

THE LEMONGRASS

ELEVATION A | 3,526 SQ. FT.

Including 866 sq. ft. of Finished Lower Level

28-2660 ELEV. C

Main Level

Sketch #2



SECURITY CAMERA ROUGH-IN

ELECTRICAL PLUG ABOVE THE GREAT ROOM FIRE PLACE 70"++ FROM FLOOR

8 X POTLIGHTS IN GREAT ROOM,- USE SEPARATE SWITCH


OPT. COFFERED CEILING

RELOCATE 3 X STD. KITCHEN LIGHTS TO BE CAPPED CEILING ABOVE THE BREAKFAST BAR-FOR FUTURE PENDANT LIGHTS USE SEPARATE SWITCH

8 X POTLIGHTS IN KITCHEN- USE EXSITING 4 WAY SWITCH

4 X POTLIGHTS IN DINING ROOM - USE SEPARATE SWITCH. KEEP STD. LIGHT WITH SWITCH

SECURITY KEY PAD ROUGH-IN



MAIN LEVEL ELEVATION C







* Floor plan may vary due to grading conditions.

KITCHEN – GROUND FLR

UPGRADE KITCHEN

- 30" COOKTOP POTS & PANS
- 30" TALL BUILT-IN OVEN

SKETCH #3



F R E N D E L
K I T C H E N S L I M I T E D
1350 Shawson Drive, Mississauga, ON L4W 1G5

HEATHWOOD HOMES
WILLIAMSBURG
MODEL: LEMONGRASS
28-2660 (3404)

STANDARD CONTRACT INCLUDES:

Appliance Openings

- Hood: 30"W Builder Hood
- Fridge Opening: 37 3/8 "W X 73 3/8"
- Fridge cabinet & gables: 66cm Deep
- Stove Opening: 30" Freestanding
- Dishwasher Opening: 24"

Standard Scope Kitchen, Vanity, Laundry:

- 100cm H wall Cabinets
- Base Pie Cut Corner Cabinets
- Std. Blumotion Hinges-**Soft Close Doors**
- Std. Metabox Drawers-**Not Soft Close**
- Top Drawer In Principal Ensuite (Qty x1)
- Std. Laundry Uppers - 61cm H
- Std. Laundry Base
- Std. Basement Baths
- Backing on All - Except Sink Cabinets
- Countertop by Others for Kitchen & Principal Ensuite

Drawn By: Sepideh B
Date: August 25, 2023
Scale: Not To Scale

This sketch is for DESIGN PURPOSES ONLY – It is not meant to be an exact rendition.

THIS DRAWING IS FOR DESIGN PURPOSES ONLY.
IT IS NOT AN EXACT RENDITION.

SKETCH #4

THE LEMONGRASS

ELEVATION A | 3,526 SQ. FT.

Including 866 sq. ft. of Finished Lower Level


28-2660 ELEV. C

Second Level



12 X 24 TILE INSTALL
DIRECTION

BLACK TRIM FRAMELESS




STACKED WASHER/DRYER
UPPER CABINETS ABOVE
BASE CABINETS ONLY

SECOND LEVEL
ELEVATION C


* Floor plan may vary due to grading conditions.

2ND FLOOR CABINETRY


PRINCIPAL ENSUITE



ENSUITE 4




SHARED BATH




LAUNDRY

STD. LAUNDRY BASE
STD. LAUNDRY UPPERS



BASEMENT

FINISHED BASEMENT



F R E N D E L
K I T C H E N S L I M I T E D
1350 Shawson Drive, Mississauga, ON L4W 1C5

HEATHWOOD HOMES
WILLIAMSBURG
MODEL: LEMONGRASS
28-2660 (3404)

STANDARD CONTRACT INCLUDES:

Appliance Openings

- Hood: 30"W Builder Hood
- Fridge Opening: 37 3/8 "W X 73 3/8"
- Fridge cabinet & gables: 66cm Deep
- Stove Opening: 30" Freestanding
- Dishwasher Opening: 24"


Standard Scope Kitchen, Vanity, Laundry:

- 100cm H wall Cabinets
- Base Pie Cut Corner Cabinets
- Std. Blumotion Hinges-**Soft Close Doors**
- Std. Metabox Drawers-**Not Soft Close**
- Top Drawer In Principal Ensuite (Qty x1)
- Std. Laundry Uppers - 61 cm H
- Std. Laundry Base
- Std. Basement Baths
- Backing on All - Except Sink Cabinets
- Countertop by Others for Kitchen & Principal Ensuite

Drawn By: Sepideh B
Date: August 25, 2023
Scale: Not To Scale

This sketch is for DESIGN PURPOSES ONLY – It is not meant to be an exact rendition.

THIS DRAWING IS FOR DESIGN PURPOSES ONLY.
IT IS NOT AN EXACT RENDITION.



NFAS NF17 Mantel


O.K. F.K.

BLANCO

Sink Specifications

Colour	SKU
Café	400889
Anthracite	400890
Truffle	401143
Cinder	401397
Metallic Grey	401683
White	401820
Concrete Grey	402266
Coal Black	402660

PRECIS U SUPER SINGLE
SILGRANIT



Design and planning tips

- Min cabinet size: 36 in (915 mm)
- Bowl Depth: 9,5 in (240.0 mm)

Specifications:
Mounting clips, Sink template, Installation instructions, 3½" (90 mm) stainless steel strainer(s), Limited Lifetime Warranty

To protect from damage, this model should be shipped on a pallet.
Depending on cabinet construction, a different cabinet size may be required. Consult the cabinet manufacturer.
Codes/Standards: CSA B45.8-18/ IAPMO Z403-2018

Optional Accessories

CapFlow Strainer Cover	517666
Floating Grid	406535
Sink Grid	406446
Mesh Basket	406399

Warranty
Limited lifetime warranty on all sinks and faucets. One-year warranty on all accessories and soap dispensers.

Code/Standards Compliance
BLANCO sinks and faucets are third-party tested and certified to CSA, cUPC, ANSI/ASME, IAPMO and NSF standards and listed by applicable certification bodies. For more information on individual product listings, contact our office or listing organization.

 Need support? Learn more by watching our sink & faucet How-to videos:
<https://www.blanco.com/ca-en/support/how-to-videos/how-to-videos-for-sinks/>

	BLANCO Canada Inc 100 Corporation Drive Brampton ON L6S 6B5	Tel & Fax Tel: 905-494-2400 Toll free: 1-877-425-2626 Fax: 905-494-2425 Toll free: 1-877-825-2626
---	---	---

While BLANCO strives to provide accurate information, all images and dimensions in this document are intended for reference only and are subject to change at any time without notice. This document is not intended for use as an installation guide. For technical installation details, refer to installation instructions provided with the product. BLANCO assumes no responsibility for the use of superseded or voided specifications.

G.K F.K

*** BRUSH GOLD

MOEN®

Specifications

FAUCET DESCRIPTION

- Reflex™ pulldown system offers smooth operation, easy movement and secure docking
- Power Clean™ spray technology
- Metal construction with various finishes identified by suffix
- Quick connect installation
- Pulldown spray with 68" braided hose
- Flexible supply lines with 3/8" compression fittings
- High arc spout provides height and reach to fill or clean large pots while pulldown wand provides the maneuverability for cleaning or rinsing
- 360° rotating spout
- Faucet designed for handle to be mounted on right side only

OPERATION

- Lever style handle
- Temperature controlled by 100° arc of handle travel
- Operates with less than 5 lbs. of force
- Operates in stream or spray mode in the pullout or retracted position

FLOW

- Flow is limited to 1.5 gpm (5.7 L/min) max at 60 psi

CARTRIDGE


- 1255™ Duralast™ cartridge

STANDARDS

- Third party certified to IAPMO Green, ASME A112.18.1/CSA B125.1 and all applicable requirements therein including NSF 61/9G & 372
- Meets CalGreen and Georgia SB370 requirements
- Complies with California Proposition 65 and with the Federal Safe Drinking Water Act
- The backflow protection system in the device consists of two independently operating check valves, a primary and a secondary which prevent backflow
- ADA ♿ for lever handle

WARRANTY

- Lifetime limited warranty against leaks, drips and finish defects to the original homeowner
 - 10 year limited warranty when used in a multifamily installation
 - 5 year limited warranty when used in a commercial installation
- Visit www.moen.com/support for complete details and limitations




ALIGN™

Single Handle High Arc
Pulldown Kitchen Faucet

Models: 7565 series

*** BRUSH GOLD

NOTE: THIS FAUCET IS DESIGNED TO BE INSTALLED
THROUGH 1 HOLE, 1-1/2" (38mm) MIN. DIA.
(OPTIONAL 3-HOLE ESCUTCHEON 141002 AVAILABLE)



BRUSH GOLD

CRITICAL DIMENSIONS
(DO NOT SCALE)

Rev. 6/20

FOR MORE INFORMATION CALL: 1-800-BUY-MOEN
www.moen.com

OK F.K.



BARRIER FREE (ABOVE COUNTER OR DROP-IN ONLY)

BOULEVARD®
PEDESTAL SINK
VITREOUS CHINA

BOULEVARD® PEDESTAL SINK


- STD ☒ ~~0641.800~~ Faucet holes on 8" (203mm) centers (Illustrated)
- ☒ **0641.400** Faucet holes on 4" (102mm) centers
- ☒ ~~0641.100~~ Center hole only
- Classic styled rectangular pedestal lavatory
 - Vitreous china
 - Rear overflow
 - Supplied with mounting kit
 - Right Height® for greater comfort during use
 - Faucet ledge with large deck area (faucet not included)
 - **Design coordinates with Boulevard® Toilet**
 - Basin has flat bottom to also allow use as an **above counter** sink or a **drop-in** sink (with u-shaped cut out)

Nominal Dimensions:
24" x 19" x 35-1/2"
(610 x 483 x 902mm)

- ☐ **0641.008** Pedestal top-8" (203mm) centers
- ☐ **0641.004** Pedestal top-4" (102mm) centers
- ☒ **0641.001** Pedestal top-center hole only
- ☐ **0010.000** Pedestal only

Bowl sizes:
17" (432mm) wide,
12-1/2" (318mm) front to back,
5" (127mm) deep

Compliance Certifications -
Meets or Exceeds the Following Specifications:
• ASME A112.19.2 - 2008/CSA B45.1-08



SEE REVERSE FOR ROUGHING-IN DIMENSIONS

To Be Specified:

☐ Color: ☐ White ☐ Linen

☐ Faucet Finish:

☐ Supplies:

☐ 1-1/4" Trap:

☐ Nipple:

* See faucet section for additional models available


O.K F.k

American
Standard

 BARRIER FREE (ABOVE COUNTER OR DROP-IN ONLY)



BOULEVARD®
PEDESTAL SINK
VITREOUS CHINA

TOP VIEW (ALL THREE CONFIGURATIONS)



PEDESTAL CONFIGURATION
(NOT ADA COMPLIANT)

ABOVE COUNTER CONFIGURATION



DROP-IN SINK CONFIGURATION



ABOVE COUNTER AND DROP-IN SINK CONFIGURATIONS
MEET THE AMERICANS WITH DISABILITIES ACT GUIDELINES
AND ANSI A117.1 ACCESSIBLE AND USABLE
BUILDINGS AND FACILITIES - CHECK LOCAL CODES.

Top of sink installed at 34" (864mm) height from finished floor.
Sink installed 5" (127mm) minimum from front edge of countertop.
Provide 27" (686mm) knee clearance area.

NOTES:


- * DIMENSIONS SHOWN FOR LOCATION OF SUPPLIES AND "P" TRAPS ARE SUGGESTED.
- ▼ PEDESTAL ANCHORING SCREWS NOT INCLUDED.
- SUITABLE FOR REINFORCEMENT ONLY. ACTUAL DIMENSIONS MUST BE TAKEN FROM FIXTURE.
- FITTING NOT INCLUDED AND MUST BE ORDERED SEPARATELY.
- PROVIDE SUITABLE REINFORCEMENT FOR ALL WALL SUPPORTS.
- INSTALLATION INSTRUCTIONS SUPPLIED WITH LAVATORY.

IMPORTANT: Dimensions of fixtures are nominal and may vary within the range of tolerance established by ANSI Standard A112.19.2
These measurements are subject to change or cancellation. No responsibility is assumed for use of superseded or voided pages.

O.K F.K.



DEMI™
Product Specification Sheet



Two Piece Freestanding Collection


CF2007	Two Piece Freestanding Soaker
Size:	60" x 32" x 22" 1524 mm x 813 mm x 559 mm

PRODUCT FEATURES & BENEFITS


- Vacuum formed acrylic reinforced with fiberglass
- Scratch, stain and fade resistant high gloss finish
- Installation friendly two piece design
- Accepts deck mounted faucet
- Includes integral pop up drain and rectangular overflow
- Includes levelling feet

TWO PIECE ASSEMBLY


FRONT VIEW



END VIEW



TOP VIEW



GENERAL SPECIFICATIONS		
Average Weight	90 lb	41 kg
Bathing Well at bottom	43"x 20"	1092 x 508 mm
Capacity Drain to Overflow		195 litres
Water Depth Drain to Overflow	16"	406 mm
Drain Opening (dia.)	2"	51 mm
Overflow Opening	2 1/4"x 1 1/2"	57 x 13 mm
Drain to Floor Clearance	3 1/4"	83 mm

NOTES: Please confirm measurements on actual product to ensure proper identification. Bathtub to be installed on the floor supported by 5 self levelling feet. Adjust if required to level the bathtub for adequate drainage. Refer to installation instructions for additional information.

IMPORTANT: Dimensions of fixtures are nominal and may vary $\pm 1/4"$ (6 mm). Weight may vary ± 5 lb (2.3 kg). Drawing is not to scale. These measurements are subject to change at manufacturer's discretion.

Compliance Certifications -
Meets or Exceeds the following Specifications:
• CAN/CSA - B45 Series



O-K F-K

VORMAX® UHET
RIGHT HEIGHT® ELONGATED TOILET

 BARRIER FREE

VITREOUS CHINA

VORMAX® UHET
RIGHT HEIGHT® ELONGATED TOILET

- ❑ 238AA.114
 - VorMax flushing technology cleans two times better than conventional toilets**
 - Combination bowl and tank, less seat
 - 12" (305 mm) rough-in
 - Right Height elongated siphon action bowl
 - Ultra-high efficiency toilet (UHET) 1.0 gpf/3.8 Lpf
 - Meets EPA WaterSense® and MaP Premium criteria
 - EverClean® Antimicrobial Surface
 - Transitional styling
 - Includes EZ-Install Tools
 - CleanCurve™ rim eliminates rim area where dirt and build-up hide
 - 16-1/2" (419 mm) rim height for accessible applications
 - 2-1/16" (52 mm) trapway
 - Dual injection flush valves
 - Chrome trip lever
 - Two color-matched bolt caps
 - 10 year warranty

- ❑ 238AA.115 Same as above except trip lever on right hand side
- ❑ 3385A.101 Right Height® Elongated Bowl
- ❑ 4385A.114 UHET Tank

Nominal Dimensions:
30-3/16" x 17-7/8" x 32-1/4"
(767 x 453 x 820mm)

Fixture only, seat and supply sold separately

- Alternative Tank Configuration Available:
- ❑ 4385A.115 Tank complete with trip lever located on right side

- Compliance Certifications -
Meets or Exceeds the Following Specifications:
- ASME A112.19.2/CSA B45.1 for Vitreous China Fixtures
 - US EPA WaterSense® Specification for UHETs

To Be Specified:


☐ Color: ☐ White

☐ Seat: #5055A.65C Elongated Slow Close solid plastic seat and cover

☐ Supply with stop:

**Source: IAPMO R&T Labs Test Report No. 109-141486-002, comparing VorMax against conventional under-the-rim-water-dispersal toilets from major retailers.

 MEETS THE AMERICANS WITH DISABILITIES ACT GUIDELINES AND ICC ANSI A117.1 REQUIREMENTS FOR ACCESSIBLE AND USABLE BUILDING FACILITIES-CHECK LOCAL CODES.



NOTES:
THIS TOILET IS DESIGNED TO ROUGH-IN AT A MINIMUM DIMENSION OF 305MM (12") FROM FINISHED WALL TO C/L OF OUTLET.
SUPPLY NOT INCLUDED WITH FIXTURE AND MUST BE ORDERED SEPARATELY.
* DIMENSION SHOWN FOR LOCATION OF SUPPLY IS SUGGESTED.

IMPORTANT: Dimensions of fixtures are nominal and may vary within the range of tolerances established by ANSI Standard A112.19.2. These measurements are subject to change or cancellation. No responsibility is assumed for use of superseded or voided pages.

EVERCLEAN®
Surface



o-k f.k



Specifications

DESCRIPTION

- Metal construction with various finishes identified by suffix
- 16" long 3/8" tubing connections
- Includes metal or 50/50 pop-up type waste assembly where noted

OPERATION

- Pivot action lever style handle
- Temperature controlled through 180° degree arc of handle travel

FLOW

- Flow is limited to 1.5 gpm max (5.7L/min) at 60 psi

CARTRIDGE

- 1225 cartridge design
- Nonmetallic/nonferrous and stainless steel material
- Can accommodate reversed piping and back to back installations


STANDARDS

- Third party certified to WaterSense®, CSA B-125.1, ASME A112.18.1 and all applicable requirements referenced therein including NSF61/9
- Complies with California Proposition 65 and with the Federal Safe Drinking Water Act

- ADA  for lever handle

WARRANTY

- Lifetime limited warranty against leaks, drips and finish defects to the original consumer purchaser
- 5 year warranty if used in commercial installations



CHATEAU®
Single-Handle Lavatory Faucet

with Metal Waste Assembly

Model: L4625 series

L4631BC


Bulk Packed (12 per carton):
L64624 series

with 50/50 Waste Assembly

Bulk Packed (12 per carton):
L64625 series

Less Waste
Bulk Packed (12 per carton):
L64600 series

NOTE: THIS FAUCET IS DESIGNED TO BE
INSTALLED THRU 3-1" DIA. HOLES, 2" ON CENTER



CRITICAL DIMENSIONS
(DO NOT SCALE)

O.K. F.K.

SHARED, ENSUITE 4 AND BASEMENT BATHROOM



Buy it for looks. Buy it for life.®

There is more than 1 version of this model.
Page down to identify the version you have.

DESCRIPTION

- Metal construction with various finishes identified by suffix
- Includes non-metallic showerhead, arm, flange and non-metallic diverter tub spout

OPERATION

- Handle operates counterclockwise through a 270° arc with off at 6 o'clock and maximum hot at the 9 o'clock position. Shut off in clockwise direction
- Adjustable temperature limit stop to control maximum hot water temperature
- Pressure balancing mechanism maintains selected discharge temperature to ± 3°

FLOW

- Showerhead is limited to 2.5 gpm (9.5 L/min) at 80 psi
- EP suffix models are limited to 1.75 gpm (6.6 L/min) at 80 psi
- NH suffix models contain no showerhead

CARTRIDGE

- 1222 cartridge design
- Accommodates back to back installations
- Nonmetallic/nonferrous and stainless steel material

STANDARDS

- Third party certified to meet ASME A112.18.1/CSA B125.1 and all applicable requirements referenced therein
- EP suffix models are third party certified to WaterSense®

- ADA  for lever handle

WARRANTY

- Lifetime limited warranty against leaks, drips and finish defects to the original consumer purchaser
- 5 year warranty if used in commercial installations


Specifications



CHATEAU® POSI-TEMP®
Single-Handle Tub/Shower Trim Kit

Models: TL181 series - valve trim only
(Bulk Packed 12 per carton)
TL182 series - shower trim only
(Bulk Packed 12 per carton)
TL183 series - tub/shower trim
(Bulk Packed 12 per carton)

Valves: 62300 series
2500 series



O-K F.M

ALL BATHROOMS

American Standard
Style That Works Better

 BARRIER FREE

OVALYN™
UNDERCOUNTER SINK
VITREOUS CHINA

OVALYN™ UNDERCOUNTER SINK

- Classic oval undermount sink
- Made from vitreous china
- Front overflow
- Supplied with mounting kit (047194-0070A) and template

☐ **0495.221 Unglazed rim**
435 x 359mm
(17-1/8" x 14-1/8")

☐ **0495.300 Glazed underside**

Bowl size:

382mm (15-1/16") wide
306mm (12-1/16") front to back
140mm (5-1/2") deep

☒ **0496.221 Unglazed rim**
489 x 413mm
(19-1/4" x 16-1/4")

☐ **0496.300 Glazed underside**

Bowl size:

432mm (17") wide
356mm (14") front to back
140mm (5-1/2") deep

☐ **0497.221 Unglazed rim**
546 x 441mm
(21-1/2" x 17-3/8")

☐ **0497.300 Glazed underside**

Bowl size:

483mm (19") wide
391mm (15-3/8") front to back
140mm (5-1/2") deep

Compliance Certifications -


Meets or Exceeds the Following Specifications:

- ASME A112.19.2M for Vitreous China Fixtures
- CAN/CSA B45 series

To Be Specified:

- ☐ Color: ☐ White ☐ Bone ☐ Linen
☐ Silver ☐ Fawn Beige ☐ Black
- ☐ Faucet*:
☐ Faucet Finish:
☐ Supplies:
☐ 1-1/4" Trap:

* See faucet section for additional models available




SEE REVERSE FOR ROUGHING-IN DIMENSIONS

O.K. F.K.

American Standard
Style That Works Better

BARRIER FREE


OVALYN™
UNDERCOUNTER SINK
VITREOUS CHINA



NOTES:
* DIMENSIONS SHOWN FOR LOCATION OF SUPPLIED AND "P" TRAP ARE SUGGESTED.
▼ UNDERCOUNTER MOUNTING KIT SUPPLIED WITH SINK.
PLEASE NOTE MINIMUM INTERIOR CLEARANCE DIMENSION (K). FITTINGS NOT INCLUDED AND MUST BE ORDERED SEPARATELY. USE ENCLOSED TEMPLATE FOR COUNTERTOP CUTOUT SEALING COMPOUND SUPPLIED BY OTHERS.
IMPORTANT: Dimensions of fixtures are nominal and may vary within the range of tolerances established by ANSI Standard A112.19.2. These measurements are subject to change or cancellation. No responsibility is assumed for use of superseded or voided pages.

MEETS THE AMERICANS WITH DISABILITIES ACT GUIDELINES AND ANSI A117.1 ACCESSIBLE AND USEABLE BUILDINGS AND FACILITIES - CHECK LOCAL CODES.
Countertop 864mm (34") from finished floor. Lavatory installed 76mm (3") from front edge of countertop. Countertop thickness to be 25mm (1") maximum.

CAT. NO.	E	F	G	H	C	D	J	K
0496.221	489mm (19-1/4)	413mm (16-1/4)	432mm (17)	356mm (14)	103mm (4-1/16)	182mm (7-3/16)	16mm (5/8)	500mm (19-11/16)
0497.221	546mm (21-1/2)	441mm (17-3/8)	483mm (19)	391mm (15-3/8)	95mm (3-3/4)	191mm (7-1/2)	19mm (3/4)	534mm (21-1/16)



NOTES:
USE ENCLOSED TEMPLATE FOR COUNTER TOP CUTOUT. FITTINGS NOT INCLUDED WITH FIXTURE AND MUST BE ORDERED SEPARATELY.
* DIMENSIONS SHOWN FOR LOCATION OF SUPPLIED AND "P" TRAP ARE SUGGESTED.
▼ UNDERCOUNTER MOUNTING KIT SUPPLIED WITH SINK.
PLEASE NOTE MINIMUM INTERIOR CLEARANCE DIMENSION (K). SEALING COMPOUND SUPPLIED BY OTHERS.
IMPORTANT: Dimensions of fixtures are nominal and may vary within the range of tolerances established by ANSI Standard A112.19.2. These measurements are subject to change or cancellation. No responsibility is assumed for use of superseded or voided pages


MEETS THE AMERICANS WITH DISABILITIES ACT GUIDELINES AND ANSI A117.1 ACCESSIBLE AND USABLE BUILDINGS AND FACILITIES - CHECK LOCAL CODES.
Countertop 864mm (34") from finished floor. Lavatory installed 51mm (2") from front edge of countertop. Countertop thickness to be 25mm (1") maximum.

O.K F.K

INCLUDING PRINCIPAL ENSUITE

MOEN®

Specifications




Single-Handle Lavatory Faucet

L4631BC

Bulk Packed (12 per carton):
L64600 series

NOTE: THIS FAUCET IS DESIGNED TO BE
INSTALLED THRU 3-1" DIA. HOLES, 2" ON CENTER



PRINCIPAL ENSUITE TUB AND SHOWER ONLY (STD CHARTEAU CHROME FAUCETS)

Rizon™

Traditional | Transitional | Modern

Polished smooth with clean, horizontal lines, the Rizon collection features a modern style with simple edges and soft curves.




Single Handle Vessel Lav Faucet with Push-Button Drain without Overflow ±
Not available in BL
Model 6911 / 140780

Chrome
Other



Single Handle Lav Faucet with Lift Rod Drain -
NEW! Available in BL*
Model 6900

Chrome
Other



Two Handle Adjustable Widespread (8" - 16") Lav Faucet with Lift Rod Drain
NEW! Available in BL*
Model T6920 / 69000

Chrome
Other



NEW!

Two Handle Roman Tub Faucet
Available in BL*
Model T935 / 4796

Chrome
Other **BL**



Two Handle Roman Tub Faucet with Hand Shower
Not available in BL
Model T936 / 9796

Chrome
Other



One Handle Roman Tub Faucet with Hand Shower
Not available in BL
Model T937 / 4791


Chrome



Tub Drain Half Kits Available**

Chrome
Other

FINISH OPTIONS:



To order, combine the model number with one of these finish letter(s):
LifeShine® Brushed Nickel (BN) & Matte Black (BL)

To order Chrome (C) model, use model number only.

- Deckplate sold separately - 165006 series ± Single hole installation only

** T90331 / 140680

* BL Finish Ships Q2


O.K. F.K.

PRINCIPAL ENSUITE ONLY

Rizon™

Traditional | Transitional | Modern

Polished smooth with clean, horizontal lines, the Rizon collection features a modern style with simple edges and soft curves.




Posi-Temp® Tub/Shower Faucet with 3 Function Transfer Valve/Trim and Slide Bar with Hand Shower *

Available in BL*
Model T2813EP / 3372 / 128284 / 62320 / T2081 / 3669EP / A725

Chrome

Other

BL



Posi-Temp® Shower Only with 3 Function Transfer Valve/Trim and Slide Bar with Hand Shower *

Available in BL*
Model T2812EP / 3372 / T2081 / 62320 / 3669EP / A725

Chrome

Other

FINISH OPTIONS:



C

BN

BL

To order, combine the model number with one of these finish letter(s):
LifeShine® Brushed Nickel (BN) & Matte Black (BL)

To order Chrome (C) model, use model number only.

- Please see vertical spa guide for installation #700106
- * BL Finish Ships Q2

O.K

F.K



Home > Major Kitchen Appliances > Hoods & Vents > Wall Mount Hoods and Vents > KVWB606HBS

36" Wall-Mount, 3-Speed Canopy Hood

Model: KVWB606HBS



Key Features

- 4-Speed Electronic Glass Touch Control
- Power Boost Function
- Auto Speed Setting
- Automatic Turn On
- Removable Filters

Color

Black Stainless Steel with PrintShield™ Finish



OK F.K.

INSTALLATION REQUIREMENTS

Tools and Parts

Gather the required tools and parts before starting installation.
Read and follow the instructions provided with any tools listed here.

Tools Needed

- Level
- Drill with 1¼" (3.0 cm), ⅝" (9.5 mm), and ⅜" (7.9 mm) drill bits
- Pencil
- Wire stripper or utility knife
- Tape measure or ruler
- Pliers
- Caulking gun and weatherproof caulking compound
- Vent clamps
- Jigsaw or keyhole saw
- Flat-blade screwdriver
- Metal snips
- Phillips screwdriver

Parts Needed

- Home power supply cable
- ½" (12.7 mm) UL listed or CSA approved strain relief
- UL listed wire connectors (3)

For Vented Installations, You Will Also Need:

- 1 wall or roof cap
- Metal vent system

For Non-Vented (Recirculating) Installations, You Will Also Need:

- Recirculation Kit Part Number W10692908 for non-vented (recirculating) installations only. See "Assistance or Service" section to order.
- 6" (15.2 cm) diameter round metal vent duct - length required is determined by ceiling height.

Parts Supplied

Remove parts from packages. Check that all parts are included.

- Hood canopy assembly with ventilator and LED and halogen lights installed
- Vent transition with back draft dampers installed
- Metal grease filter(s)—depending on model and size
- Vent cover support bracket
- Mounting template
- 2-piece vent cover
- 4.2 x 8 screws (4)
- 5 x 45 mm mounting screws (6)
- D6.4 x 18 mm washers (2)
- 8 x 40 mm wall anchors (2)
- 10 x 60 mm wall anchors (4)
- 5.4 x 75 mm screws (for 10 x 60 mm wall anchors) (4)
- 3.5 x 9.5 mm sheet metal screws (2)
- T10 TORX®† adapter

†®TORX is a registered trademark of Acument Intellectual Properties, LLC.

Location Requirements

IMPORTANT: Observe all governing codes and ordinances.

Have a qualified technician install the range hood. It is the installer's responsibility to comply with installation clearances specified on the model/serial/rating plate. The model/serial/rating plate is located behind the left filter on the rear wall of the vent hood.

Canopy hood location should be away from strong draft areas, such as windows, doors and strong heating vents.

Cabinet opening dimensions that are shown must be used. Given dimensions provide minimum clearance.

This range hood is recommended for use with cooktops with a maximum total rating of 65,000 BTUs or less.

Grounded electrical outlet is required. See "Electrical Requirements" section.


The canopy hood is factory-set for venting through the roof or wall. For non-vented (recirculating) installation see "For non-vented (recirculating) installation only" in the "Connect Vent System" section. Recirculation Kit Part Number W10692908 is available from your dealer or an authorized parts distributor.

All openings in ceiling and wall where canopy hood will be installed must be sealed.

For Mobile Home Installations

The installation of this range hood must conform to the Manufactured Home Construction Safety Standards, Title 24 CFR, Part 328 (formerly the Federal Standard for Mobile Home Construction and Safety, Title 24, HUD, Part 280) or when such standard is not applicable, the standard for Manufactured Home Installation 1982 (Manufactured Home Sites, Communities and Setups) ANSI A225.1/NFPA 501A, or latest edition, or with local codes.

Product Dimensions




*For non-vented (recirculating) installations

**For vented installations

O.K F.K.

Cabinet Dimensions



*For non-vented (recirculating) installations

IMPORTANT:

Minimum distance "X": 24" (61.0 cm) from electric cooking surface.

Minimum distance "X": 27" (68.6 cm) from gas cooking surfaces.

Suggested maximum distance "X": 36" (91.4 cm)

The chimneys can be adjusted for different ceiling heights. See the following chart.

Vented Installations		
	Min. ceiling height	Max. ceiling height
Electric cooking surface	7' 1" (2.16 m)	9' 2" (2.79 m)
Gas cooking surface	7' 4" (2.23 m)	9' 2" (2.79 m)

Non-vented (recirculating) Installations		
	Min. ceiling height	Max. ceiling height
Electric cooking surface	7' 1" (2.16 m)	9' 6" (2.9 m)
Gas cooking surface	7' 4" (2.23 m)	9' 6" (2.9 m)

NOTE: The range hood chimneys are adjustable and designed to meet varying ceiling or soffit heights depending on the distance "X" between the bottom of the range hood and the cooking surface. For higher ceilings, a Chimney Extension Kit is available from your dealer or an authorized parts distributor. The chimney extension replaces the chimney shipped with the range hood. To order, see the "Assistance or Service" section.

Venting Requirements
(Vented Models Only)

- Vent system must terminate to the outdoors except for non-vented (recirculating) installations.
- Do not terminate the vent system in an attic or other enclosed area.
- Do not use 4" (10.2 cm) laundry-type wall caps.
- Use metal vent only. Rigid metal vent is recommended. Plastic or metal foil vent is not recommended.
- The length of vent system and number of elbows should be kept to a minimum to provide efficient performance.

For the Most Efficient and Quiet Operation:

- Use no more than three 90° elbows.
- Make sure there is a minimum of 24" (61.0 cm) of straight vent between the elbows if more than 1 elbow is used.
- Do not install 2 elbows together.
- Use clamps to seal all joints in the vent system.
- The vent system must have a damper. If the roof or wall cap has a damper, do not use the damper supplied with the range hood.
- Use caulking to seal exterior wall or roof opening around the cap.
- The size of the vent should be uniform.

Cold Weather Installations

An additional back draft damper should be installed to minimize backward cold air flow and a thermal break should be installed to minimize conduction of outside temperatures as part of the vent system. The damper should be on the cold air side of the thermal break.

The break should be as close as possible to where the vent system enters the heated portion of the house.

Makeup Air

Local building codes may require the use of makeup air systems when using ventilation systems greater than specified CFM of air movement. The specified CFM varies from locale to locale. Consult your HVAC professional for specific requirements in your area.

Venting Methods

This canopy range hood is factory set for venting through the roof or through the wall.

A 6" (15.2 cm) round vent system is needed for installation (not included). The hood exhaust opening is 6" (15.2 cm) round.

NOTE: Flexible vent is not recommended. Flexible vent creates back pressure and air turbulence that greatly reduce performance.

Vent system can terminate either through the roof or wall. To vent through a wall, a 90° elbow is needed.


Rear Discharge

A 90° elbow may be installed immediately above the hood.

O.K F.K

For Non-Vented (Recirculating) Installations

If it is not possible to vent cooking fumes and vapors to the outside, the hood can be used in the non-vented (recirculating) version, using a Recirculation Kit (which includes charcoal filters and a deflector). To order, see the "Assistance or Service" section.




Calculating Vent System Length

To calculate the length of the system you need, add the equivalent feet (meters) for each vent piece used in the system.

Vent Piece	6" (15.2 cm) Round	
45° elbow	2.5 ft (0.8 m)	
90° elbow	5.0 ft (1.5 m)	

Maximum equivalent vent length is 35 ft (10.7 m).

Example Vent System



The following example falls within the maximum recommended vent length of 35 ft (10.7 m).

1 - 90° elbow	= 5.0 ft (1.5 m)
1 - wall cap	= 0.0 ft (0.0 m)
8 ft (2.4 m) straight	= 8.0 ft (2.4 m)
Length of system	= 13.0 ft (3.9 m)

Electrical Requirements

Observe all governing codes and ordinances.

Ensure that the electrical installation is adequate and in conformance with National Electrical Code, ANSI/NFPA 70 (latest edition), or CSA Standards C22.1-94, Canadian Electrical Code, Part 1 and C22.2 No. 0-M91 (latest edition) and all local codes and ordinances.

If codes permit and a separate ground wire is used, it is recommended that a qualified electrician determine that the ground path is adequate.

A copy of the above code standards can be obtained from:

National Fire Protection Association
1 Batterymarch Park
Quincy, MA 02169-7471
CSA International
8501 East Pleasant Valley Road
Cleveland, OH 44131-5575

- A 120 volt, 60 Hz., AC only, 15-amp, fused electrical circuit is required.
- If the house has aluminum wiring, follow the procedure below:
 - Connect a section of solid copper wire to the pigtail leads.
 - Connect the aluminum wiring to the added section of copper wire using special connectors and/or tools designed and UL listed for joining copper to aluminum.Follow the electrical connector manufacturer's recommended procedure. Aluminum/copper connection must conform with local codes and industry accepted wiring practices.
- Wire sizes and connections must conform with the rating of the appliance as specified on the model/serial/rating plate. The model/serial/rating plate is located behind the left filter on the rear wall of the range hood.
- Wire sizes must conform to the requirements of the National Electrical Code, ANSI/NFPA 70 (latest edition), or CSA Standards C22. 1-94, Canadian Electrical Code, Part 1 and C22.2 No. 0-M91 (latest edition) and all local codes and ordinances.

G.K F.K.

Sponsored

BEST BUY


Stores

Cart


Home > Appliances > Major Appliances > Refrigerators & Freezers > Refrigerators > French Door Refrigerators > Product Details

Samsung Family Hub 36" 22.8 Cu. Ft. French Door Refrigerator (RF23A9771SG) - Black Stainless

Model Number: RF23A9771SG
Web Code: 15308372
★★★★★ 4.7 (100 Reviews)
Write your review >
Sold and shipped by Best Buy



2 of 2



O.K F.K

\$3,899⁹⁹

BEST BUY Financing
\$325.00/mo.
Suggested monthly payment for 12 months, plus \$69.99 admin fee and applicable taxes. [How it works.](#)

1 special offer available!
• [Free delivery and haul away on select major appliances \\$699.99 and above.*](#)

Add to Cart

Pick Up at Store

Sponsored

Save 200
on 2



Home > Appliances > Major Appliances > Ranges, Cooking & Ventilation > Cooktops > Product Details

KitchenAid 36" 5-Element Induction Cooktop (KCIG556JSS) - Stainless Steel


Model Number: KCIG556JSS

Web Code: 15973746

☆☆☆☆☆

No reviews yet. Be the first! >

Sold and shipped by Best Buy



1 of 19



OK Fick

\$2,699⁹⁹

Financing

\$225.00/mo.

2699

Suggested monthly payment for 12 months, plus \$69.99 admin fee and applicable taxes. How it works.

1 special offer available!

- Free delivery and haul away on select major appliances \$699.99 and above.*

Add to Cart


Pick Up at Store

DIMENSIONS

1 of 21

INDUCTION COOKTOP
PRODUCT DIMENSIONS

MODEL #	30" Cooktop KCIG550JBL/SS KCIG950JBL/SS		36" Cooktop KCIG556JBL/SS ✓ KCIG956JBL/SS	
	in	cm	in	cm
Overall Width with Frame (A)	31 ³ / ₁₆	79.2	36 ¹¹ / ₁₆	93.2
Depth with Frame (B)	21 ²³ / ₃₂	55.1	21 ²³ / ₃₂	55.1
Overall Width without Frame (C)	30 ³ / ₄	78.2	36 ⁵ / ₁₆	92.2
Depth without Frame (D)	21 ¹ / ₄	54.1	21 ⁵ / ₁₆	54.1



TOP VIEW

IMPORTANT: Dimensional specifications are provided for planning purposes only.
Do not make any cutouts based on this information. Refer to the Installation Guide before selecting cabinetry, verifying electrical/gas connections, making cutouts or beginning installation.
All KitchenAid® appliances are appropriately UL, CUL or CSA approved.



DIMENSIONS

2 of 21

INDUCTION COOKTOP
PRODUCT DIMENSIONS

MODEL #	30" Cooktop KCIG550JBL/SS KCIG950JBL/SS		36" Cooktop KCIG556JBL/SS KCIG956JBL/SS	
	in	cm	in	cm
Glass Width (E)*	30 ³⁵ / ₃₂	78.2	36 ⁵ / ₁₆	92.2
Electric Inlet to Surface (F)	3 ²⁹ / ₃₂	9.9	3 ²⁹ / ₃₂	9.9
Center to Electric Inlet (G)	13 ³ / ₃₂	33.2	13 ²⁵ / ₃₂	35.0
Recessed Cooktop Width (H)	29 ¹¹ / ₃₂	74.5	35 ⁵ / ₁₆	89.7

*Includes width of grates and griddle.



IMPORTANT: Dimensional specifications are provided for planning purposes only.
Do not make any cutouts based on this information. Refer to the Installation Guide before selecting cabinetry, verifying electrical/gas connections, making cutouts or beginning installation.
All KitchenAid® appliances are appropriately UL, CUL or CSA approved.

KitchenAid®


DIMENSIONS

3 of 21

INDUCTION COOKTOP
PRODUCT DIMENSIONS

MODEL #	30" Cooktop KCIG550JBL/SS KCIG950JBL/SS		36" Cooktop KCIG556JBL/SS KCIG956JBL/SS	
	in	cm	in	cm
Unit of Measurement				
Height with Grates (I)	2 ⁵ / ₁₆	7.1	2 ⁵ / ₁₆	7.1
Control Panel Height (J)	3 ⁹ / ₁₆	9	3 ⁹ / ₁₆	9.0
Recessed Cooktop Height (K)	3 ²³ / ₃₂	9.4	3 ²³ / ₃₂	9.4
Cooking Surface Height (L)	20 ¹ / ₄	51.4	20 ¹ / ₄	51.4
Recessed Cooktop Depth (M)	21 ¹ / ₄	54.1	21 ¹ / ₄	54.1
Depth with Front Edge (M)	22	55.9	22	55.9

IMPORTANT: Supplied regulator does not come preattached and is pictured for reference purposes only.



IMPORTANT: Dimensional specifications are provided for planning purposes only.
Do not make any cutouts based on this information. Refer to the Installation Guide before selecting cabinetry, verifying electrical/gas connections, making cutouts or beginning installation.
All KitchenAid® appliances are appropriately UL, CUL or CSA approved.

KitchenAid®


DIMENSIONS

4 of 21

INDUCTION COOKTOP
OPENING/CLEARANCE DIMENSIONS

MODEL #	30" Cooktop KCIG550JBL/SS KCIG950JBL/SS		36" Cooktop KCIG556JBL/SS KCIG956JBL/SS	
	in	cm	in	cm
Combustible Area above Cooking Surface Width (minimum) (A)	30	76.2	36	91.4
Bottom of Cabinet Height above Cooking Surface (minimum) (B)*	30	76.2	30	76.2
Bottom of Cabinet Height above Countertop (minimum) (C)	18	45.7	18	45.7
Distance to Fixed Wall or Combustible Material (D)	1	2.5	1	2.5

*If installing a hood above the cooktop, follow the hood instructions for dimensional clearances above the cooking surface.



FRONT VIEW

IMPORTANT: Dimensional specifications are provided for planning purposes only.
Do not make any cutouts based on this information. Refer to the Installation Guide before selecting cabinetry, verifying electrical/gas connections, making cutouts or beginning installation.
All KitchenAid® appliances are appropriately UL, CUL or CSA approved.

KitchenAid®

DIMENSIONS


5 of 21

INDUCTION COOKTOP
OPENING/CLEARANCE DIMENSIONS

MODEL #	30" Cooktop KCIG550JBL/SS KCIG950JBL/SS		36" Cooktop KCIG556JBL/SS KCIG956JBL/SS	
	in	cm	in	cm
Recommended Upper Cabinet Depth (E)	13	33	13	33
Cutout to Wall Depth (if backwall is constructed of non-combustible material) (F)*	1	2.5	1	2.5
Cutout to Wall Depth (if backwall is constructed of combustible material) (F)*	1	2.5	1	2.5
Cabinet to Countertop Height (G)**	3 ¹⁵ / ₁₆	10	3 ¹⁵ / ₁₆	10
Cabinet Depth (H)	23 ⁹ / ₃₂	59.1	23 ⁹ / ₃₂	59.1

*If the back wall is constructed of a combustible material and a backsplash is not installed, a 7¼" (19.7 cm) minimum clearance is required from the cutout or 6" (15.2 cm) minimum clearance from the back edge of the cooktop.

**The bottom of the cutout supports the product. Unlike many cooktops, these models do not hang from the side flanges, but rather sit on the floor of the cutout.



SIDE VIEW

IMPORTANT: Dimensional specifications are provided for planning purposes only.
Do not make any cutouts based on this information. Refer to the Installation Guide before selecting cabinetry, verifying electrical/gas connections, making cutouts or beginning installation.
All KitchenAid® appliances are appropriately UL, CUL or CSA approved.




DIMENSIONS

6 of 21

INDUCTION COOKTOP
OPENING/CLEARANCE DIMENSIONS

MODEL #	30" Cooktop KCIG550JBL/SS KCIG950JBL/SS		36" Cooktop KCIG556JBL/SS KCIG956JBL/SS	
	in	cm	in	cm
Countertop and Cabinet Cutout Width (I)	29 ⁹ / ₁₆	75.1	35 ⁹ / ₁₆	90.3
Countertop and Cutout Depth (J)	20 ³ / ₄	52.7	20 ³ / ₄	52.7

NOTE: Due to manufacturing factory tolerances, these are nominal dimensions. You may need to readjust to meet your clearance.



TOP VIEW

IMPORTANT: Dimensional specifications are provided for planning purposes only.
Do not make any cutouts based on this information. Refer to the Installation Guide before selecting cabinetry, verifying electrical/gas connections, making cutouts or beginning installation.
All KitchenAid® appliances are appropriately UL, CUL or CSA approved.

KitchenAid®

Certifications

Prop 65	Standard
ADA Compliant	ADA Height and Operation Compliant
UL	Yes

Description

Combinations with Oven	KOSE500,KOSE507,KOSE900,KOST100,KOST107
Cooktop Type	Standard
Fuel Type	Electric Induction
Size (in.)	36

Features

Hot Surface Indicator Light	Yes
Automatic Pan Detection	Yes
Digital Display	Yes
Downdraft Vent	No
Heating Element On Indicator Light	Yes
Automatic Pan Size Adjustment	Yes
Installs Over Built-In Oven	Yes
Power Boost	Yes
Griddle	NA
LP Convertible	No
Power Outage Compatible	No

Controls

Control Location	Front
Control Type	Tap Touch
Infinite Heat Controls	No

Cooktop Details

Cooktop Element Style	Induction
Cooktop Surface Color	Black
Number of Cooking Element-Burners	5
Center Front Element-Burner Size	12"
Ignition Type	Electronic Button
Left Front Element-Burner Size	8"
Number of Open Bays	NA
Right Front Element-Burner Size	6"
Left Front Element-Burner Power	2300W/ 3000W Boost
Center Front Element-Burner Power	3600W/ 4000W Boost
Right Rear Element-Burner Size	8"
Left Front Element-Burner Type	Round
Left Rear Element-Burner Size	6"
Left Rear Element-Burner Power	1500W/ 1800W Boost
Center Front Element-Burner Type	Round
Left Rear Element-Burner Type	Round
Right Front Element-Burner Type	Round
Right Front Element-Burner Power	1500W/ 1800W Boost
Right Rear Element-Burner Type	Round
Right Rear Element-Burner Power	2300W/3000W
Cooktop Configuration	All Burners

Details

Cooktop Surface Material	Glass
--------------------------	-------

Electrical

Amps	40
Volts	240
208V Compatible	Yes
Watts	11880
Hz	60
Power Cord Included	Yes

Refinement

Style	Cooktops
-------	----------

Certifications	
ADA Compliant	ADA Height and Operation Compliant
UL	Yes
prop65	Standard
Controls	
Control Location	Front
Control Type	Tap Touch
Infinite Heat Controls	No
Cooktop Details	
Cooktop Surface Material	Glass
Digital Display	Yes
Griddle Included	N/A
Heating Element On Indicator Light	Yes
Hot Surface Indicator Light	Yes
Ignition Type	Electronic Button
Number of Open Bays	N/A
Details	
Automatic Pan Detection	Yes
Automatic Pan Size Adjustment	Yes
Cooktop Configuration	All Burners
Fuel Type	Electric Induction
Installs Over Built-In Oven	Yes
LP Convertible	No
Power Outage Compatible	No
True Flush Installation	Yes
Dimensions	
Cutout Depth Min	20.75
Cutout Width Min	35.563
carton depth	25.28
carton height	7.64
carton width	40.45
gross weight	64
net weight	49
Electrical	
208V Compatible	Yes
Power Cord Included	Yes
Element/Burner Details	
Center Front Element-Burner Power	2100W/3600W Boost
Center Front Element-Burner Size	12in.
Center Front Element-Burner Type	Round
Cooktop Element Style	Induction
Cooktop Type	Standard
Left Front Element-Burner Power	2100W/ 3000W Boost
Left Front Element-Burner Size	8in.
Left Front Element-Burner Type	Round
Left Rear Element-Burner Power	1200W/ 1600W Boost
Left Rear Element-Burner Size	6in.
Left Rear Element-Burner Type	Round
Number of Cooking Element-Burners	5
Power Boost	Yes
Right Front Element-Burner Power	1200W/ 1600W Boost
Right Front Element-Burner Size	6in.
Right Front Element-Burner Type	Round
Right Rear Element-Burner Power	2100W/ 3000W Boost
Right Rear Element-Burner Size	8in.
Right Rear Element-Burner Type	Round
Ventilation Details	
Downdraft Vent	No

Dimensions	
Depth	21 23/32
Width	36 11/16
Height	2 5/16
Carton Depth	25 5/16
Carton Height	7 11/16
Carton Width	40 1/2

\$3,894

Description & Features

Specs

Manuals

Video

Rebate

Review

Warranty

Financing

Install

FAQ

Dimensions

Capacity	6-2/5
Depth	68.90 cm, 27-1/8 in
Height	107.95 cm, 42-1/2 in
Microwave Capacity	39.62 l, 1.4 cu. ft.
Oven Capacity	141.50 l, 5.0 cu. ft.
Width	76.20 cm, 30 in

Configuration and Overview

Fuel Type	Electric
Oven Type	Combination
Size	76.20 cm, 30 in

Features

Automatic Shut-Off	Yes
Broiler Location	Top of Oven
Convection Functions	Bake, Broil, Roast
Door Broil Position	Closed
Door Lock	Yes
Door Removable	Yes
Hidden Bake Element	Yes
Color	5 OFFERS AVAILABLE Black

Sponsored

[Stores](#) [Account](#) [Cart](#)

Home > Appliances > Major Appliances > Ranges, Cooking & Ventilation > Wall Ovens > Product Details


KitchenAid 30" 5 Cu. Ft./1.4 Cu. Ft. True Convection Electric Combination Wall Oven - Black SS

Model Number: KOCE500EBS

Web Code: 10649317

★★★★☆ 4.5 (2270 Reviews)
[Write your review >](#)

Sold and shipped by Best Buy



1 of 9



O.K F.K

Sale ends: November 15, 2023*

5699

SAVE \$500
\$5,699⁹⁹

BEST BUY Financing
\$475.00/mo.

Suggested monthly payment for 12 months, plus \$69.99 admin fee and applicable taxes. [How it works.](#)

1 special offer available!

- Free delivery and haul away on select major appliances \$699.99 and above.*

Add to Cart


Pick Up at Store

- Electrical supply junction box should be located 3" (7.6 cm) maximum below the support surface when the oven is installed in a wall cabinet. A 1" (2.5 cm) minimum diameter hole should have been drilled in the left rear corner of the support surface to pass the appliance cable through to the junction box.
- Oven support surface must be solid, level and flush with bottom of cabinet cutout. Floor must be able to support a total weight (microwave and built-in oven) of 208 lbs (95 kg) for 27" (68.6 cm) models or 249 lbs (113 kg) for 30" (76.2 cm) models.

IMPORTANT: To avoid damage to your cabinets, check with your builder or cabinet supplier to make sure that the materials used will not discolor, delaminate or sustain other damage. This oven has been designed in accordance with the requirements of UL and CSA International and complies with the maximum allowable wood cabinet temperatures of 194°F (90°C).

Product Dimensions

27" and 30" (68.6 cm and 76.2 cm) Ovens



27" (68.6 cm) models


- A. 42 3/8" (108.0 cm) overall height
- B. 25 7/8" (64.6 cm) recessed width
- C. 41" (104.1 cm) recessed height
- D. 23 1/4" (59.1 cm) max. recessed depth
- E. 27" (68.6 cm) overall width
- F. 48" (121.9 cm) flexible conduit length measured from the conduit clamp located at the rear of the oven. Do not remove the conduit clamp.

30" (76.2 cm) models

- A. 42 3/8" (108.0 cm) overall height
- B. 28 7/8" (72.2 cm) recessed width
- C. 41" (104.1 cm) recessed height
- D. 23 1/4" (59.1 cm) max. recessed depth
- E. 30" (76.2 cm) overall width
- F. 48" (121.9 cm) flexible conduit length measured from the conduit clamp located at the rear of the oven. Do not remove the conduit clamp.

Cabinet Dimensions

27" and 30" (68.6 cm and 76.2 cm) Ovens



27" (68.6 cm) models

- A. 27" (68.6 cm) min. cabinet width
- B. 1" (2.5 cm) top of cutout to bottom of upper cabinet door
- C. 19 1/4" (48.9 cm) bottom of cutout to floor is recommended. 4"-19 1/4" (10.2-48.9 cm) bottom of cutout to floor is acceptable.
- D. 25 1/2" (64.8 cm) cutout width
- E. 1 1/2" (3.8 cm) min. bottom of cutout to top of cabinet door
- F. 41 3/8" (105 cm)* recommended cutout height
- G. 24" (60.7 cm) cutout depth

30" (76.2 cm) models

- A. 30" (76.2 cm) min. cabinet width
- B. 1" (2.5 cm) top of cutout to bottom of upper cabinet door
- C. 19 1/4" (48.9 cm) bottom of cutout to floor is recommended. 4"-19 1/4" (10.2-48.9 cm) bottom of cutout to floor is acceptable.
- D. 28 1/2" (72.4 cm) cutout width
- E. 1 1/2" (3.8 cm) min. bottom of cutout to top of cabinet door
- F. 41 3/8" (105 cm)* recommended cutout height
- G. 24" (60.7 cm) cutout depth

***NOTE:** The cutout height can be between 41" and 41 1/2" (104.1 cm and 105.6 cm) for microwave/oven combination.

Electrical Requirements

If codes permit and a separate ground wire is used, it is recommended that a qualified electrical installer determine that the ground path and wire gauge are in accordance with local codes.

Check with a qualified electrical installer if you are not sure the oven is properly grounded.

This oven must be connected to a grounded metal, permanent wiring system.

Be sure that the electrical connection and wire size are adequate and in conformance with the National Electrical Code, ANSI/NFPA 70-latest edition or CSA Standards C22.1-94, Canadian Electrical Code, Part 1 and C22.2 No. O-M91-latest edition, and all local codes and ordinances.

A copy of the above code standards can be obtained from:


National Fire Protection Association
1 Batterymarch Park
Quincy, MA 02169-7471

CSA International
8501 East Pleasant Valley Road
Cleveland, OH 44131-5575

Electrical Connection

To properly install your oven, you must determine the type of electrical connection you will be using and follow the instructions provided for it here.

- Oven must be connected to the proper electrical voltage, amperage, and frequency as specified on the model/serial/rating plate. See the following illustration.



A. Model/serial/rating plate

- Models rated from 7.3 to 9.6 kW at 240 volts (5.4 to 7.4 kW at 208 volts) require a separate 40-amp circuit. Models rated at 4.8 kW and below at 240 volts (3.6 kW and below at 208 volts) require a separate 30-amp circuit.
- A circuit breaker is recommended.
- Connect directly to the fused disconnect (or circuit breaker box) through flexible, armored or nonmetallic sheathed, copper cable (with grounding wire). See “Make Electrical Connection” section.

- Flexible conduit from the oven should be connected directly to the junction box.
- Do not cut the conduit. The length of conduit provided is for serviceability of the oven.
- A UL listed or CSA approved conduit connector must be provided.
- If the house has aluminum wiring, follow the procedure below:
 1. Connect a section of solid copper wire to the ends of the flexible conduit leads.
 2. Connect the aluminum wiring to the added section of copper wire using special connectors and/or tools designed and UL listed for joining copper to aluminum.

Follow the electrical connector manufacturer’s recommended procedure. Aluminum/copper connection must conform with local codes and industry accepted wiring practices.

For power requirements, refer to the following table.

Model	Voltage	Amperage (L1)*	Amperage (L2)*	Rating (W)
KOCE507E/ KOCE500E	120/240	32	30	8000
KOCE507E/ KOCE500E	120/208	30	28	6600

*Amperage values noted above are for information purposes only: The units are rated in watts.

INSTALLATION INSTRUCTIONS

Prepare Built-In Microwave/Oven Combination

1. Decide on the final location for the oven. Locate existing wiring to avoid drilling into or severing wiring during installation.

⚠ WARNING

Excessive Weight Hazard


Use two or more people to move and install oven.
Failure to do so can result in back or other injury.

2. To avoid floor damage, set the oven onto cardboard prior to installation. Do not use handle or any portion of the front frame for lifting.
3. Remember to remove bottom vent from the foam packing on top of oven.
4. Remove the shipping materials and tape from the oven.
5. Remove the hardware package from inside the bag containing literature.
6. Remove and set aside racks and other parts from inside the oven.
7. Move oven and cardboard close to the oven’s final location.


Remove Oven Door(s)

IMPORTANT: Use two hands to remove oven door.

1. Prior to removing the oven door, prepare a surface where you will place it. This surface should be flat and covered with a soft blanket, or use the corner posts from your packaging material.
2. Open the oven door.
3. Locate the oven door hinge locks in both corners of the oven door, and then rotate the hinge locks toward the oven door to the unlocked position. If the door hinge lock is not rotated fully (see illustration B), the door will not remove properly.



A. Oven door hinge lock in locked position



B. Oven door hinge lock in unlocked position

Sponsored



Home > Appliances > Major Appliances > Dishwashers > Built-In Dishwashers > Product Details

LG 24" 44dB Built-In Dishwasher with Stainless Steel Tub & Third Rack (LDPS6762D) -Black Stainless Steel


Model Number: LDPS6762D

Web Code: 16653777


★★★★★ 4.7 (197 Reviews)

Write your review >

Sold and shipped by Best Buy



1 of 8



O.K Fik

Sale ends: November 8, 2023¹

SAVE \$100

\$1,199⁹⁹

Financing

\$100.00/mo.

Suggested monthly payment for 12 months, plus \$69.99 admin fee and applicable taxes. [How it works.](#)

1 special offer available!

- Free delivery and haul away on select major appliances \$699.99 and above.*

Add to Cart

Pick Up at Store

1199

HOME APPLIANCES



LG LAUNDRY

Single Unit LG WashTower™ with Center Control™
4.5 cu. ft. Front Load Washer and 7.4 cu. ft. Dryer

KEY FEATURES

Ultra Large Capacity 4.5 cu.ft. Washer and 7.4 cu.ft. Dryer
Single Unit WashTower™ Design
Built-In Intelligence - AI Fabric Sensors/Smart Learner/Smart Pairing™
Advanced Washing & Drying - TurboWash™ 360°/Allergiene™ wash cycle/
TurboSteam™
ThinQ® Technology / Proactive Customer Care
Tempered Glass Door

SMART APPLIANCE


Enjoy new ways to control your home with LG smart appliances

- Use the ThinQ® app to start the laundry while you're out
- Get alerts when the cycle is finished
- With Smart Pairing™, the washer can tell the dryer to select a compatible drying cycle


LG ThinQ®

works with the Google Assistant

WORKS WITH alexa



AVAILABLE COLORS



PRODUCT FEATURES

SUMMARY		Washer	Dryer	Drying Levels		ThinQ® TECHNOLOGY		Washer	Dryer
Type		Front Load Washer	Front Load Dryer			Very, More, Normal, Less, Damp	SmartDiagnosis™ (v3.0)		Yes
Capacity (cu.ft.)		4.5 cu. ft.	7.4 cu. ft.			60 min., 50 min., 40 min., 30 min., 20 min.	Wi-Fi		Yes
Color		Black Steel (B), White (W)		Manual Dry Times			Remote Start and Cycle Monitor		Yes
APPEARANCE		Washer	Dryer	FABRIC CARE FEATURES		Washer	Dryer	Energy Monitoring	
Hard Buttons		Yes		AI DD		Yes	-	Tub Clean Coach	Yes
Touch Buttons		Yes		TurboWash™ 360 Technology		Yes	-	MOTOR AND AGITATOR	
Full Touch Electronic Control Panel with LED Display		Yes		Steam Technology		Yes	-	Motor Type	Inverter Direct Drive Motor
Unified Center Control		Yes		Allergiene™ Cycle		Yes	-	Axis	Horizontal
Reversible Door		No		Sanitary Cycle		Yes	-	MATERIALS AND FINISHES	
ENERGY		Washer	Dryer	SenseClean™ System		Yes	-	NeveRust™ Stainless Steel Drum	Yes
ENERGY STAR® Qualified		Yes		AI Dry		-	Yes	Cabinet	PCM
CEE Tier		Tier2	-	Sensor Dry		-	Yes	Control Panel	Plastic
IMEF		2.92	-	Precise Temperature Control with Variable Heater		-	Yes	Top Plate	Painted
IWF		2.9	-	Steam Technology		-	Yes (TurboSteam™)	NeveRust™ Stainless Steel Drum	-
CEF		-	Electric: 3.94 Gas: 3.49	CONVENIENCE FEATURES		Washer	Dryer	Tub Rear	Painted
PROGRAMS		Washer	Dryer	TrueBalance™ Anti-Vibration System		Yes	-	CERTIFICATION	
No. of Programs		6	6			Prewash, Main Wash (with liquid detergent cup), Bleach, Fabric Softener	-	AAFA	Yes
OPTIONS	No. of Options	Normal, Bedding, Delicates, Heavy Duty, Speed Wash, Downloaded	Normal, Bedding, Delicates, Heavy Duty, Speed Wash, Downloaded	4 Tray Dispenser		Yes	-	POWER SOURCE	
		Washer	Dryer	LoDecibel™ Quiet Operation		Yes	-	Ratings	UL Listed
		TurboWash®, Steam, Extra Rinse, Pre-wash, Sanitary, Tub Clean, Drum Light, Child Lock, Signal, Wi-Fi / Remote Start	Wrinkle Care, TurboSteam™, Reduce Static, Energy Saver, Steam Fresh*, Drum Light*, Child Lock*, Signal*, Wi-Fi* / Remote Start*	End of Cycle Signal		Yes	-	Electrical Requirements	120V, 10 Amps
				LoadSense		Yes	-	Type	Electric
DETAILS	No. of Wash/Rinse Temps	Hot, Warm/Hot, Warm, Cold/Warm, Cold	-	Child Lock		Yes	-	Ratings	CSA Listed
				Auto Suds Removal		Yes	-	Electrical Requirements	120V, 15 Amps (Gas)
				Leveling Legs		Yes	-	Type	Gas / Electric
				Easy Loading TiITub™		Yes	-	BTU Rating	10,000 Feet
	No. of Spin Speeds	High,Medium/Low, No Spin	-	Drum Light		Yes	-	LP Conversion Kit	383EEL3002D
				Remaining Time Display/Status Indicator(s)		Yes	-	Side Venting Kit	383EEL9001B
				3 Minute Installation Check		-	Yes	DIMENSIONS	
				LoDecibel™ Quiet Operation		-	Yes	Product (WxHxD)	27" x 74 3/8" x 30 3/8"
	Spin Speeds	High,Medium/Low, No Spin	-	End of Cycle Signal		-	Yes	Depth with Door Open	55" D with door open
				Drum Light		-	Yes	Carton (WxHxD)	30 1/16" x 79 11/32" x 32"
				FlowSense™ Duct Clogging Indicator		-	Yes	Weight (Product/Carton)	Electric: (326 lb / 361 lb) Gas: (329 lb / 364 lb)
				Wrinkle Care Option		-	Yes	LIMITED WARRANTY	
	Max RPM	1300	-	Child Lock		-	Yes	Parts and Labor	1 Year
				Venting Option		-	Yes	Direct Drive Motor	10 Years
				4 Adjustable Legs		-	Yes	Drum	3 Years
				Remaining Time Display/Status Indicator(s)		-	Yes	UPC CODES	
	Water Levels	Load Sensing	-					WKEX200HBA (Black Steel)	048231028486
								WKGX201HBA (Black Steel)	048231029254
								WKEX200HWA (White)	048231028462
								WKGX201HWA (White)	048231029261
	No. of Soil Levels	5	-						
	Temperature Settings	-	High, Medium/High, Medium, Low/Medium, Low						

© 2020 LG Electronics USA, Inc. All rights reserved. "LG Life's Good" is a registered trademark of LG Corp. All other product and brand names are trademarks or registered trademarks of their respective owners. Design, features and specifications are subject to change without notice. Non-metric weights and measurements are approximate. Some features may require Internet access. Content and services may vary by product and are subject to change without notice. 10/19/20