



Heathwood Homes (Whitby) Limited

245 Yorkland Blvd., Suite 100

Toronto, Ontario

M2J 4W9

Ph: (416) 490-1400

Fax: (416) 490-1401

**** Pending ****

PO# DE-TR-7-765-29349

Vendor PO: DE-TR-7-765-29349

Created: 01Aug24

Created By: Bonijen Santos

Approved By: Unauthorized

Required Date: 01Aug24

Vendor

Practical Electric Contracting Inc.

527 Edgeley Blvd. Unit 12

Concord, Ontario

L4K 4G6

Ph: (416) 663-1500

Fax: (416) 663-1502

Ship To

Reference

Re: Lot 765 Phase 7

Model: 30-2794 D The Willowglen

Site: Country Lane

Quantity	Account	Description	Unit Price	Ext. Price
1.00	0704	SKETCH # 2 - ELECTRICAL-CAR CHARGER- ADDITIONAL OUTLET 30AMP/240V 2 POLE BREAKER AND FEMALE OUTLET FOR FUTURE ELECTRICAL CAR CHARGER, PLEASE SPECIFY LOCATION -	\$420.00	\$420.00
1.00	0704	FOR COOKTOP STOVE SKETCH # 3 SEE 36" INDUCTION COOKTOP SPECS - ELECTRICAL- OUTLET-50AMP/240V ADDITIONAL, PLEASE SPECIFY LOCATION -	\$680.00	\$680.00
2.00	0704	1 X ADDITIONAL ON SIDE OF ISLAND 1 X ABOVE COUNTER IN SERVERY SKETCH # 3 - ELECTRICAL-OUTLET-EXTRA WALL INTERIOR OUTLET (120V/15A) ON A SEPARATE CIRCUIT (ON ARCFault) -	\$195.00	\$390.00
5.00	0704	SKETCH #'S 1 , 2 AND 4 - ELECTRICAL-OUTLET- EXTRA WALL INTERIOR OUTLET ON EXISTING CIRCUIT (DOES NOT INCLUDE KITCHEN OUTLETS) - 1 X OVER FIREPLACE IN GREAT RM 70" +/- FROM FLOOR 1 X DINING RM - ADDITIONAL - STD HEIGHT 1 X PRIMARY BDRM - 66" FROM FLOOR 1 X OVER FIREPLACE IN FINISHED RECROOM 70" +/- FROM FLOOR 1 X BDRM 5 (BSMT) ADDITIONAL PLUG - STD HEIGHT ON BEDROOM WALL ADJACENT TO REC ROOM	\$45.00	\$225.00
4.00	0704	SKETCH # 2 - ELECTRICAL-RELOCATION OF SWITCHES/LIGHTS (MUST SPECIFY LOCATION) RELOCATE STD 240 PLUG TO BUILT IN OVEN / MICRO SKETCH # 3 RELOCATE KITCHEN, BRKFST & SERVERY STD CEILING LIGHTS TO OVER ISLAND	\$0.00	\$0.00
1.00	0704	SKETCH # 2 - CLASSIC COLLECTION SCHEDULE A - Choice of 20 LED (3000K) pot	\$0.00	\$0.00

		lights in finished areas (Second Floor Potlight(s) Require Smooth Ceiling)		
			Total:	\$1,715.00

Notes

- All above amounts are net of taxes.
- All invoices must quote a PO# and delivery address.
- All deliveries must be authorized by the site superintendent.
- All materials and/or work must comply with all applicable building codes and regulations.