


LOT 12 SMS

American Standard

Style That Works Better



CADET® 3 RIGHT HEIGHT™ 14" ROUGH-IN ELONGATED TOILET

VITREOUS CHINA

CADET® 3 RIGHT HEIGHT™ 14" ROUGH-IN ELONGATED TOILET

☐ 2386.014

- Vitreous china
- Low-consumption (6.0 Lpf/1.6 gpf)
- EverClean® surface inhibits the growth of stain- and odor-causing bacteria, mold, and mildew on the surface
- Features the **Cadet® 3 Flushing System**
- 16-1/2" rim height for accessible application
- Elongated siphon action jetted bowl
- Fully-glazed 2-1/8" trapway with 2" ball pass
- Generous 9" x 8" water surface area
- Close-coupled tank with flat tank cover for superior storage
- Oversized 3" flush valve with chemical resistant flapper
- Chrome trip lever
- Speed Connect® tank-to-bowl coupling system
- Sanitary dam on bowl with four point tank stabilization
- 2 color-matched bolt caps
- 100% factory flush tested
- 5 year warranty

☐ 3016.016 Right Height™ Elongated Bowl

☐ 3016.001 Right Height™ Elongated Universal Bowl

☐ 4027.016 Tank

Nominal Dimensions:

819 x 445 x 775mm (32-1/4" x 17-1/2" x 30-1/2")

Fixture only, seat and supply by others

Alternative Tank Configurations Available:

- ☐ **4027.600** Tank complete with tank cover locking device
- ☐ **4027.800** Tank complete with trip lever on right side
- ☐ **4027.900** Tank complete with tank cover locking device and trip lever on right side

Compliance Certifications -


- Meets or Exceeds the Following Specifications:**
- ASME A112.19.2-2008/CSA B45.1-08 for Vitreous China Fixtures

MAIN ENCLAVE

ENG #2
POUNDER
BASEMENT

To Be Specified:

- ☐ Color: ☒ White ☐ Bone ☐ Linen ☐ Black
- ☐ Seat: #5325.010 Elongated Champion® Slow Close solid plastic seat and cover with easy lift off feature
- ☐ Seat: #5284.016 Elongated EverClean® solid plastic seat and cover
- ☐ Seat: #5321.110 EverClean® Elongated Seat with Slow Close Snap-Off Hinges
- ☐ Supply with stop:



NOTES:

THIS TOILET IS DESIGNED TO ROUGH-IN AT A MINIMUM DIMENSION OF 356MM (14") FROM FINISHED WALL TO C/L OF OUTLET. SUPPLY NOT INCLUDED WITH FIXTURE AND MUST BE ORDERED SEPARATELY.
* DIMENSION SHOWN FOR LOCATION OF SUPPLY IS SUGGESTED.

IMPORTANT: Dimensions of fixtures are nominal and may vary within the range of tolerances established by ANSI Standard A112.19.2. These measurements are subject to change or cancellation. No responsibility is assumed for use of superseded or voided pages.






MEETS THE AMERICANS WITH DISABILITIES ACT GUIDELINES AND ANSI A117.1 REQUIREMENTS FOR ACCESSIBLE AND USABLE BUILDING FACILITIES-CHECK LOCAL CODES.

CADET® 3
Flushing System

BATHROOM SINKS

American Standard
Style That Works Better

Above Counter Glass Sinks	FIXTURE NO.	DESCRIPTION	WEIGHT PTS.	CU. FT./ CTN. PLT. QTY.	LIST PRICE	AVAILABLE COLOURS
AFFINITY OVAL GLASS SINK 	0976 000	- Contemporary oval above-counter sink - Tempered 5/8" (16mm) glass for durability - Sink riser and chrome grid drain included - Recommended for use with Cardiff 9445 100 Cabinet or other countertop installation - Recommended faucet - SERIN 2064 151 Nominal Dimensions: 14" x 20-1/2" diameter (256mm x 521mm) Bowl Dimensions: 12-3/4" x 19-1/4" (324mm x 489mm) diameter 4-1/2" (114mm) deep	12 kg 1.4	3.6	357.00	321 Frosted 200 Clear
			(26 lbs)	16		
XEN GLASS VESSEL 	0990 000	- Squared design glass above vessel counter sink - Tempered 5/8" (16mm) glass for durability - Sink riser and chrome grid drain included - Recommended for use with Cardiff 9445 100 Cabinet or other countertop installation - Recommended faucet - SERIN 2064 151 Nominal Dimensions: 17" x 17" diameter (432mm x 432mm) Bowl Dimensions: 15-3/4" x 15-3/4" diameter (400mm x 400mm) 5" (127mm) deep	12 kg 1.4	3.6	255.00	321 Frosted 200 Clear
			(26 lbs)	16		
BAR ABOVE COUNTER SINK 	0969 000	- Contemporary glass above-counter sink - Tempered 5/8" (16mm) glass for durability - Sink riser and chrome grid drain included - Recommended for use with Cardiff 9445 100 Cabinet or other countertop installation - Recommended faucet - SERIN 2064 151 Nominal Dimensions: 17" (432mm) diameter Bowl Dimensions: 15-3/4" (400mm) diameter 4-1/2" (114mm) deep	12 kg 1.4	3.6	255.00	321 Frosted 200 Clear 160 Midnight Blue LOT 12 SM 5 POWDER ? BASEMENT BATH.
			(26 lbs)	16		

Bathroom Sinks



see what Delta can do™

LOT 12 SM5


POWDER ? BASEMENT BATH

DRYDEN

Single Handle Centerset Lavatory Faucet - Less Pop-Up

Model #: 751-SS-DST
What does this model number mean?

Finish Shown: Stainless



Product Features and Benefits

The clean, geometric lines of the Dryden™ line are reminiscent of the Art Deco period of the 1920's and 30's

- The Dryden collection offers a full complement of coordinating products to create the perfect look.
- Single Handle operation
- Extended height for vessel bowl mounting
- Features water efficient aerator
- Available in chrome, Aged Pewter, Brilliance® Stainless or Venetian Bronze®
- Lifetime Faucet and Finish Warranty

Smart Features:

- ADA Compliant
- WaterSense® Labeled Product
- DIAMOND™ Seal Technology
- Water-Efficient Product meeting CALGreen standards



Certified by
CSA International

This product meets EPA
criteria for WaterSense



BARRIER FREE

STUDIO UNDERCOUNTER SINK

- Vitreous china
- Rectangular undercounter mount sink
- Unglazed rim
- Front overflow
- Supplied with mounting kit (047194-0070A) and template (Faucet shown not included)



0614 000 Unglazed Rim

540 x 387mm (21-1/4" x 15-1/4")

Bowl size:

464mm (18-1/4") wide,
308mm (12-1/8") front to back,
171mm (6-3/4") deep



0618 000 Unglazed Rim

600 x 422mm (23-5/8" x 16-5/8")

Bowl size:

537mm (21-1/8") wide,
356mm (14") front to back,
152mm (6") deep

COMPLIANCE CERTIFICATIONS -

Meets or exceeds the following Specifications:

- ASME A112.19.2M for Vitreous China Fixtures.
- CAN/CSA B45 Series.

To Be Specified

- ☐ Colour:
- ☐ Faucet*:
- ☐ Faucet Finish:
- ☐ Supplies & Stops:
- ☐ Trap 1-1/4" (32 mm):

* See faucet section for additional models available







- Countertop 864mm (34") from finished floor. Sink installed 102mm (4") from front edge of countertop. Countertop thickness to be 25mm (1") maximum.

**MEETS THE AMERICAN DISABILITIES ACT GUIDELINES
AND ANSI A117.1 ACCESSIBLE AND USEABLE
BUILDINGS AND FACILITIES - CHECK LOCAL CODES.**

NOTES:

WE RECOMMEND USING SINK AS A TEMPLATE TO DETERMINE PROPER CONTOUR. CUT COUNTERTOP 38MM (1-1/2") INSIDE SINK CONTOUR. FAUCETS NOT INCLUDED AND MUST BE ORDERED SEPARATELY.

- * DIMENSIONS SHOWN FOR LOCATION OF SUPPLIES AND "P" TRAP ARE SUGGESTED.
- ▼ UNDERCOUNT MOUNTING KIT SUPPLIED WITH SINK.
- IMPORTANT: Dimensions of fixtures are nominal and may vary within the range of tolerances established by ANSI Standard A112.19.2. These measurements are subject to change or cancellation. No responsibility is assumed for use of superseded or voided pages.



	A	B
FAUCET		
CENTRESET	1-1/8 (29mm)	4 (102mm)
SPREAD	1-3/8 (35mm)	8 (203mm)

CAT. NO.	E	F	G	H	C	D
0614 000	540mm (21-1/4)	337mm (15-1/4)	464mm (18-1/4)	308mm (12-1/8)	114mm (4-1/2)	209mm (8-1/4)
0618 000	600mm (23-3/8)	422mm (16-5/8)	537mm (21-1/8)	358mm (14)	188mm (4-4)	209mm (8-1/4)

Trim Options




Dual-Function Pressure-Balanced Valve Cartridge


Allows the user to control the temperature and volume independently. Temperature can be set in order to remain consistent shower after shower. Constant temperature ($\pm 3.6^\circ$) is achieved by balancing the pressures of both the hot and cold water.* Offered for all Monitor 17 Series Delta brand tub/showers.

131

MULTI-CHOICE UNIVERSAL



VERO
MONITOR
17 Series
T17253



ARZO
MONITOR
17 Series
T17286-SS



RIZU
MONITOR
17 Series
T17282-SS




DRYDEN
MONITOR
17 Series
T17251




VICTORIAN
MONITOR
17 Series
T17255-SS




GRAIL
MONITOR
17 Series
T17285-SS




ADDISON
MONITOR
17 Series
T17292




INNOVATIONS
MONITOR
17 Series
T17230



LAHARA
MONITOR
17 Series
T17238-SS



LELAND
MONITOR
17 Series
T17278



LINDEN
MONITOR
17 Series
T17294-I

*When the inlet temperature limit stop is set correctly and the water inlet temperature remains constant.


MAIN, ENSURE,
ENSURE #2

Trim Options



Dual-Function Thermostatic Valve Cartridge


Our newest innovative valve cartridge for an enhanced shower experience. Keeps water temperature consistent ($\pm 3.6^\circ$) by actually measuring and monitoring the temperature of the water and automatically adjusting the water mix to maintain a more precise water temperature. Allows the user to control the temperature and volume independently. Temperature can be set in order to remain consistent shower after shower. Offered for all TempAssure® 17T Series Delta brand tub/showers.




VERO
TEMPASSURE
17T Series
T17T253




ARZO
TEMPASSURE
17T Series
T17T286



RIZU
TEMPASSURE
17T Series
T17T282-SS




DRYDEN
TEMPASSURE
17T Series
T17T251



VICTORIAN
TEMPASSURE
17T Series
T17T255-SS




GRAIL
TEMPASSURE
17T Series
T17T285-SS



ADDISON
TEMPASSURE
17T Series
T17T292



INNOVATIONS
TEMPASSURE
17T Series
T17T230










LAHARA
TEMPASSURE
17T Series
T17T238-SS



LELAND
TEMPASSURE
17T Series
T17T278


Two-Handle Centerset Lavatory




LOT 12 SAS
NANA, ENROUTE, ENROUTE #2

TWO-HANDLE CENTERSET LAVATORY


More styles and finishes are available.
For our complete product offering, visit deltafaucet.com.




SINGLE-HOLE WITH
TOUCH2O® TECHNOLOGY
538T-RB-DST
*Optional escutcheon
included*




SINGLE-HOLE
538-RBMPUL-DST
*Optional escutcheon
included*




4" CENTERSET
2538LF-RB



4" MINI-WIDESPREAD
4538-RB



8" WIDESPREAD
3538LF-RB




3-HOLE ROMAN TUB
T2738-RB R2707



4-HOLE ROMAN TUB
T4738-RB-R4707




73818-RB 18" TOWEL BAR
73824-RB 24" TOWEL BAR
73835-RB SINGLE ROBE HOOK
73846-RB TOWEL RING
73850-RB TISSUE HOLDER




Lot 12 SWS
EN suite.

The faucets and accessories on this page are shown in Venetian Bronze®.


Trinsic™ Pull-Down



SINGLE-HANDLE PULL-DOWN
9159T-DST
1 or 3-hole installation
Order RP64070 for
optional escutcheon




SINGLE-HANDLE PULL-DOWN
9159T-DST WITH RP1002
SOAP DISPENSER
2 or 4-hole installation
Order RP64070 for
optional escutcheon




SINGLE-HANDLE PULL-DOWN
BAR/PREP
9959T-DST
1 or 3-hole installation
Order RP64070 for
optional escutcheon




Addison® Pull-Down



SINGLE-HANDLE PULL-DOWN
9192T-DST
1 or 3-hole installation
Optional escutcheon included



SINGLE-HANDLE PULL-DOWN
9192T-DST WITH RP1002
SOAP DISPENSER
2 or 4-hole installation
Optional escutcheon included




SINGLE-HANDLE PULL-DOWN
BAR/PREP
9992T-DST
1 or 3-hole installation
Order RP63198 for
optional escutcheon




Pilar® Pull-Down


LOT 12 SWS
KITCHEN



SINGLE-HANDLE PULL-DOWN
980T-DST
2-hole installation




SINGLE-HANDLE PULL-DOWN
980T-DST WITH RP50781
SOAP DISPENSER
3-hole installation




SINGLE-HANDLE BAR/PREP
1980T-DST
2-hole installation




Pilar® Waterfall®



SINGLE-HANDLE
4380T-DST
3-hole installation



SINGLE-HANDLE
4380T-DST WITH RP50781
SOAP DISPENSER
4-hole installation



SINGLE-HANDLE BAR/PREP
1980T-DST
2-hole installation



The faucets on this page
are shown in Chrome.