

INSERTS



**FISAB28B3SS** — 280 cfm  
**FIMAR28B6SS** — 600 cfm  
*Falmec® 28" Hood Insert*




**FIVAL28B5SS-1**  
*Falmec® 500 cfm*  
*28" & 34" Valentina Hood Insert*




**CRIS30SSH300**  
*Faber® 300 cfm 30" Pullout Hood*

WALL CHIMNEYS




**WWV51UC0FS**  
*Whirlpool® 400 cfm*  
*30" & 36" Wall Canopy*

➤ Available in Stainless & Black Stainless



**WWV53UC0FS**  
*Whirlpool® 400 cfm*  
*30" & 36" Wall Canopy*

➤ Available in Stainless & Black Stainless



**WWV57UC0FS**  
*Whirlpool® 400 cfm*  
*30" & 36" Wall Canopy*


➤ Available in Stainless




*Faber® 300 cfm & 600 cfm*  
*30" & 36" Tender Chimney*



*Faber® 300 cfm & 600 cfm*  
*30" & 36" Synthesis Chimney*



*Faber® 300 cfm & 600 cfm*  
*30" & 36" Glassy Chimney*



*Falmec® 280 cfm & 600 cfm*  
*30" & 36" Vulcano Chimney*



*Falmec® 280 cfm & 600 cfm*  
*30" & 36" Mercurio Chimney*



*Falmec® 600 cfm & 1000 cfm*  
*Pro Pyramid Chimney*  
*30" — 600 cfm*  
*36" — 1000 cfm*

Are you browsing the correct region?

Current region: Canada | Change to: USA




Taymor

/ Barcelona

BARCELONA

Knob — Matte Black — SKU: 30-D006124BLK



THE

PREMIER

LINE

PRODUCT FEATURES

- Fully reversible lock
- Universal 6-in-1 latches offer a guaranteed fit
- Push button auto-release on privacy function
- Concealed screw mount for a streamlined look
- Premium all metal construction
- Fits standard doors
- ANSI Grade 3
- Fire Rating Available
- Extension Kit Available

FINISH



FUNCTION

PRIVACY

Taymor Celebrates 70th Anniversary

Since 1948, Taymor has proudly designed and manufactured architectural hardware products of exceptional design, quality and value.



DS

AJ

DS

OJ




TRINSIC®

# Monitor 14 Series H<sub>2</sub>Okinetic Shower Trim

MODEL#: T14259-BL

- Featuring Delta H2Okinetic Technology for 3X the coverage



WaterSense® Labeled

Finish: Matte Black



## Rough Valve



MultiChoice Universal  
Tub / Shower Rough -  
Universal Inlets /  
Outlets

MODEL#: R10000-UNBX

▼ SHOW MORE OPTION

## Base Part



Monitor 14 Series  
H<sub>2</sub>Okinetic Shower  
Trim

MODEL#: T14259-BL



DS DS  
AJ OT





TRINSIC®

# Roman Tub Trim

MODEL#: T2759-BL



- Valve is not included, must purchase separately
- 3-hole 8-16" installation
- Backed by Delta Faucet's Lifetime Limited Warranty

Finish: Matte Black



## Rough Valve



Two Handle Flexible Mount  
MODEL#: R2700

▼ SHOW MORE OPTION

## Base Part



Roman Tub Trim  
MODEL#: T2759-BL

DS DS  
AJ OT





TRINSIC®

# Single Handle Pull-Down Kitchen Faucet

MODEL#: 9159-BL-DST

- Delta MagnaTite Docking holds spray wand firmly in place

Finish: **Matte Black**



DS DS  
AJ OT



**KitchenAid®**  
FOR THE WAY IT'S MADE.®

**PRODUCT MODEL NUMBERS**

KRFC302E


**Electrical:** A 115 volt, 60 Hz, AC only 15- or 20-amp fused, grounded electrical supply is required. It is recommended that a separate circuit serving only your refrigerator and approved accessories be provided. Use an outlet that cannot be turned off by a switch. Do not use an extension cord.

**Water:** A cold water supply with water pressure of between 35 and 120 psi (241 and 827 kPa) is required to operate the water dispenser and ice maker. If you have questions about your water pressure, call a licensed, qualified plumber.

**Reverse Osmosis Water Supply:**  
**IMPORTANT:** The pressure of the water supply coming out of a reverse osmosis system going to the water inlet valve of the refrigerator needs to be between 35 and 120 psi (241 and 827 kPa).


**Bottom Mount Refrigerator**

**PRODUCT DIMENSIONS**



Model Size	Height - Overall "A"	Height - Top of Cabinet "B"	Depth - Doors Open 90° "C"	Depth - Drawer Open "D"	Depth - With Handles "E"	Depth - Without Handles "F"	Depth - Cabinet Only "G"	Width - Cabinet "H"
21.9	72" (182.9 cm)	71 1/8" (181.3 cm)	44 1/8" (112.1 cm)	45 1/2" (114.9 cm)	30 1/2" (76.8 cm)	27 3/4" (70.5 cm)	24 5/8" (62.5 cm)	35 1/4" (90.8 cm)

**LOCATION REQUIREMENTS**



**IMPORTANT:** This refrigerator is designed for indoor, household use only.

To ensure proper ventilation for your refrigerator, allow for 1/2" (1.25 cm) of space on each side and at the top. Allow for 1" (2.54 cm) of space behind the refrigerator. If your refrigerator has an ice maker, allow extra space at the back for the water line connections. When installing your refrigerator next to a fixed wall, leave 2 1/2" (6.3 cm) minimum on the hinge side (some models require more) to allow for the door to swing open.

**NOTE:** This refrigerator is intended for use in a location where the temperature ranges from a minimum of 55°F (13°C) to a maximum of 110°F (43°C). The preferred room temperature range for optimum performance, which reduces electricity usage and provides superior cooling, is between 60°F (15°C) and 90°F (32°C). It is recommended that you do not install the refrigerator near a heat source, such as an oven or radiator.





**KitchenAid**

Authorized Dealer


# KitchenAid KCES556HSS

KitchenAid KCES556HSS Cooktop, 36 inch Exterior Width, Electric Cooktop, 5 Burners, 3200W, Stainless Steel colour

Availability:  
☒ \*3-10 Business Days

Save up to \$100 in multiple offers!

Up to 3 years  
FREE extended  
warranty!  
i



DS DS  
AJ OT

Specifications

Dimensions

Cutout Depth Max	5222.88 cm, 20-9/16 in
Cutout Depth Min	5175.25 cm, 20-3/8 in
Cutout Width Max	9032.88 cm, 35-9/16 in
Cutout Width Min	8778.88 cm, 34-9/16 in
Depth	5492.75 cm, 21-5/8 in
Height	1333.50 cm, 5-1/4 in
Maximum Height	1333.50 cm, 5-1/4 in
Width	9112.25 cm, 35-7/8 in

COOKTOP

Configuration and Overview

Cooktop Type	Standard
Fuel Type	Electric
Installs Over Built-In Oven	Yes
LP Convertible	No
Power Boost	No
Size	9144.00 cm, 36 in

Controls

Control Location	Front
Infinite Heat Controls	Yes
Knob Type	Metal

Cooktop Details

Automatic Pan Detection	No
Center Rear Element-Burner Size	8"
Cooktop Configuration	All Burners
Cooktop Element Style	Radiant
Cooktop Surface Color	Black
Downdraft Vent	No

DS DS  
AJOT



**KitchenAid® 27" (68.6 cm) and 30" (76.2 cm) Electric Built-In Microwave/Oven Combination**

**PRODUCT MODEL NUMBERS**

KEMS309E      KOCE500E      KOCE507E

**ELECTRICAL CONNECTION**


If codes permit and a separate ground wire is used, it is recommended that a qualified electrical installer determine that the ground path and the wire gauge are in accordance with local codes. Check with a qualified electrical installer if you are not sure the oven is properly grounded.

This oven must be connected to a grounded metal, permanent wiring system.

Be sure that the electrical connection and wire size are adequate and in conformance with the National Electrical Code, ANSI/NFPA 70-latest edition or CSA Standards C22.1-94, Canadian Electrical Code, Part 1 and C22.2 No. O-M91-latest edition, and all local codes and ordinances.

To properly install your oven, you must determine the type of electrical connection you will be using and follow the instructions provided for it here.

- Oven must be connected to the proper electrical voltage and frequency as specified on the model/serial/rating plate. See the following illustration.



A. Model/serial/rating plate

- Models rated from 7.3 to 9.6 kW at 240 volts (5.4 to 7.4 kW at 208 volts) require a separate 40-amp circuit. Models rated at 4.8 kW and below at 240 volts (3.6 kW and below at 208 volts) require a separate 30-amp circuit.
- A circuit breaker is recommended.
- Connect directly to the fused disconnect (or circuit breaker box) through flexible, armored or nonmetallic sheathed, copper cable (with grounding wire). See "Make Electrical Connection" section.
- Flexible conduit from the oven should be connected directly to the junction box.
- Do not cut the conduit. The length of conduit provided is for serviceability of the oven.
- A UL listed or CSA approved conduit connector must be provided.
- If the house has aluminum wiring, follow the procedure below:
  1. Connect a section of solid copper wire to the pigtail leads.
  2. Connect the aluminum wiring to the added section of copper wire using special connectors and/or tools designed and UL listed for joining copper to aluminum.

Follow the electrical connector manufacturer's recommended procedure. Aluminum/copper connection must conform with local codes and industry accepted wiring practices.

For power requirements, refer to the following table.

Model	Voltage	Amperage (L1)*	Amperage (L2)*	Rating (W)
KOCE507E/KOCE500E	120/240	32	30	8000
KOCE507E/KOCE500E	120/208	30	28	6600

\*Amperage values noted above are for information purposes only: the units are rated in watts.

Because Whirlpool Corporation includes a continues commitment to improve our products, we reserve the right to change materials and specifications without notice.

**PRODUCT DIMENSIONS**

**27" (68.6 cm) models**  
A. 42<sup>1</sup>/<sub>16</sub>" (108.0 cm) overall height  
B. 25<sup>7</sup>/<sub>16</sub>" (64.6 cm) recessed width  
C. 41" (104.1 cm) recessed height  
D. 23<sup>1</sup>/<sub>4</sub>" (59.1 cm) max. recessed depth  
E. 27" (68.6 cm) overall width  
F. 48" (121.9 cm) flexible conduit length measured from the conduit clamp located at the rear of the oven. Do not remove the conduit clamp.

**30" (76.2 cm) models**  
A. 42<sup>1</sup>/<sub>16</sub>" (108.0 cm) overall height  
B. 28<sup>7</sup>/<sub>16</sub>" (72.3 cm) recessed width  
C. 41" (104.1 cm) recessed height  
D. 23<sup>1</sup>/<sub>4</sub>" (59.1 cm) max. recessed depth  
E. 30" (76.2 cm) overall width  
F. 48" (121.9 cm) flexible conduit length measured from the conduit clamp located at the rear of the oven. Do not remove the conduit clamp.

**Cabinet Dimensions**

**27" (68.6 cm) models**  
A. 27" (68.6 cm) min. cabinet width  
B. 1" (2.5 cm) top of cutout to bottom of upper cabinet door  
C. 19<sup>1</sup>/<sub>4</sub>" (48.9 cm) bottom of cutout to floor is recommended. 4"-19<sup>1</sup>/<sub>4</sub>" (10.2-48.9 cm) bottom of cutout to floor is acceptable.  
D. 25<sup>1</sup>/<sub>4</sub>" (64.8 cm) cutout width  
E. 1<sup>1</sup>/<sub>2</sub>" (3.8 cm) min. bottom of cutout to top of cabinet door  
F. 41<sup>1</sup>/<sub>16</sub>" (105 cm)\* recommended cutout height  
G. 24" (60.7 cm) cutout depth

**30" (76.2 cm) models**  
A. 30" (76.2 cm) min. cabinet width  
B. 1" (2.5 cm) top of cutout to bottom  
C. 19<sup>1</sup>/<sub>4</sub>" (48.9 cm) bottom of cutout to floor is recommended. 4"-19<sup>1</sup>/<sub>4</sub>" (10.2-48.9 cm) bottom of cutout to floor is acceptable.  
D. 28<sup>1</sup>/<sub>4</sub>" (72.4 cm) cutout width  
E. 1<sup>1</sup>/<sub>2</sub>" (3.8 cm) min. bottom of cutout  
F. 41<sup>1</sup>/<sub>16</sub>" (105 cm)\* recommended cutout  
G. 24" (60.7 cm) cutout depth

\* NOTE: The cabinet height can be between 41" (104.1 cm) and 41<sup>1</sup>/<sub>2</sub>" (105.6 cm) for microwave/oven combination.

Dimensions are for planning purposes only. For complete details, see Installation Instructions packed with product. Specifications subject to change without notice.

Ref. W10725683B  
2/10/15




Kitchen / Accessories

TRINSIC®

# Metal Soap Dispenser

MODEL#: RP100734BL

Finish: **Matte Black**



<sup>DS</sup> AJ <sup>DS</sup> OT



The sleek elegance of modern design is embodied in the Trinsic Kitchen Collection. Increase the functionality of your kitchen with a deck-mounted soap dispenser. You can install with confidence, knowing that this Delta soap dispenser is backed by our Lifetime Limited Warranty.

- Metal construction to increase product quality and performance
- Slimmer metal soap heads with better design
- Uses the existing soap bottle and pump mechanism
- Refillable from above deck
- 13 oz. capacity
- Includes refill funnel
- 3 in. maximum deck thickness

**Special Features**

 FltSoapDispenser ⓘ







PURCHASER'S ESTIMATE REQUEST  
Pathways at Findlay Creek

PURCHASER: Atiqur Sikder TEL:

LOT NUMBER	PHASE	HOUSE TYPE	
315	2	ROSEMERE ELEV E 4 BEDROOM	

ITEM	QTY	EXTRA / CHANGE	PRICE	INTERNAL USE
1	1	S/I 3 piece rough-in for future bathroom in basement, in standard location	\$ 0.00	Each
144130		Note: as per B-1		(1/74/0)
2	1	Optional Alternate Kitchen/Family/Dining room	\$ 0.00	Each
144132		Note: as per B-1		(1/45/0)
3	1	9' Basement pour	\$ 11,000.00	Each
144133		Note:		(1/16/11000)
4	1	9' Second floor	\$ 11,000.00	Each
144134		Note:		(1/15/11000)
5	1	S/I (1) standard Laundry tub in basement	\$ 660.00	Each
144135		Note:		(1/40/660)
6	1	S/I (3) American Standard Studio 3075120.020 toilet - right height, dual flush, elongated bowl - lieu of standard - in Ensuite, powder room and main bathroom	\$ 2,475.00	Each
144136		Note:		(1/157/2475)
7	1	S/I Humidifier - General Aire 1042 - 2800 Sq. Ft.	\$ 970.00	Each
144137		Note:		(1/49/970)
8	1	S/I Goodman - 13 Seer R410A GSX 13024 2.0 Ton Air Conditioner	\$ 4,760.00	Each
144138		Note:		(1/61/4760)
9	1	S/I Complete central vac system c/w accessories kit and installation - includes joining and extending vac rough-in and (1) 15 AMP separate circuit plug	\$ 2,010.00	Each
144139		Note:		(1/151/2010)
10	1	S/I (1) Vac pan c/w plate, wiring and flex piping - black - Located under Kitchen sink	\$ 220.00	Each
144140		Note:		(1/86/220)
11	1	S/I Gas line for future BBQ - on ground level	\$ 800.00	Each
144141		Note: as per plan		(1/45/800)
12	1	S/I Terminated gas line c/w 110 Decora outlet for gas stove and photo electric smoke detector	\$ 800.00	Each
144142		Note:		(1/93/800)
13	1	Raise standard gas fireplace 12" above finished floor	\$ 400.00	Each
144143		Note:		(1/53/400)
14	3	Upgrade all closet doors to mirrored sliders in lieu of standard vinyl closet doors - Bedroom 2, Bedroom 3, Bedroom 4- as per plan	\$ 900.00	
144144		Note:		(3/130/300)
15	1	ALT option - Enlarge ensuite shower from 36"x36" to 48"x36" (includes standard wall tiles and standard shower doors)	\$ 750.00	Each
144146		Note:		(1/116/750)
16	1	Enlarge existing bedroom windows from 32"x48" to 48"x48"	\$ 0.00	Each
144147		Note: as per B-1		(1/56/0)

Initials:\_\_\_\_\_

PREPARED BY: Kayleigh Chipman

PE 8951 - 1

CONSTRUCTION SCHEDULING APPROVAL	
PER:	_____
DATE:	_____



PURCHASER'S ESTIMATE REQUEST  
Pathways at Findlay Creek

PURCHASER: Atiqur Sikder TEL:

LOT NUMBER 315	PHASE 2	HOUSE TYPE ROSEMERE ELEV E 4 BEDROOM	
-------------------	------------	---	--

ITEM	QTY	EXTRA / CHANGE	PRICE	INTERNAL USE
17 144148	1	Enlarge patio door from 6' wide to 8' wide- as per plan Note:	\$ 1,250.00	Each (1/55/1250)
18 144149	1	S/I (1) Additional standard sink and faucet in vanity - additional vanity light fixture priced separately Note:	\$ 1,265.00	Each (1/105/1265)
19 144150	1	S/I (1) 4-Light chrome vanity fixture (A16014-CH) - vanities larger than 36" - connected to existing switch - in Ensuite Note:	\$ 240.00	Each (1/120/240)
20 144152	1	S/I Finished 3-piece basement bathroom- c/w Standard tub, toilet, vanity and laminate countertops, plumbing and light fixtures with ceramic floor and wall tiles- as per plan Note: **Standard colour selections**	\$ 11,000.00	Each (1/173/11000)

Initials: \_\_\_\_\_

PREPARED BY: Kayleigh Chipman  
PE 8951 - 2

CONSTRUCTION SCHEDULING APPROVAL	
PER:	_____
DATE:	_____



PURCHASER'S ESTIMATE REQUEST  
Pathways at Findlay Creek

PURCHASER: Atiqur Sikder TEL:

LOT NUMBER	PHASE	HOUSE TYPE	
315	2	ROSEMERE ELEV E 4 BEDROOM	

ITEM	QTY	EXTRA / CHANGE	PRICE	INTERNAL USE
------	-----	----------------	-------	--------------

\$50,500.00 Sub Total  
\$6,565.00 HST  
\$57,065.00 Total

This is your direction to install the above extras in accordance with the following terms and conditions:

- In the event the work on the house has progressed beyond the point where the items covered by this extra cannot be installed without entailing any unusual expense, then this order is to be cancelled and any deposit paid in connection with the same is to be refunded to the purchaser.
- The Vendor will undertake to incorporate the work covered by the sales extra in the construction of the house but will not be liable to the purchaser in any way, if for any reason the work covered by the extra is not carried out. In that event, any monies paid in connection with the same shall be returned to the purchaser.
- It is understood and agreed that if for any reason whatsoever the transaction of Purchase and Sale is not completed, the total cost of extras ordered are not refundable to the Purchaser(s).
- Extras or changes will not be processed unless signed by the Vendor.
- These extras may not be amended without the written consent of 2588824 Ontario Inc.
- The purchaser(s) and the builder acknowledge and agree that this "Purchaser's Extra" form shall not be deemed to be part of the agreement of purchase and sale entered into between them, nor an addendum thereto.
- Prices are estimates only and guaranteed for a period of 5 days only.
- No post dated cheques will be accepted.
- No Estimates or orders will be accepted once construction has commenced.
- Should a refund be requested on any extras purchased, an 80% reimbursement of the purchase price will be given. (A \$50.00 minimum charge and a maximum \$250.00 charge will apply.)
- No estimates will be considered official orders until resubmitted on a signed Purchaser Extras Form, accompanied by payment in full.

PE 8.951-3

PURCHASER: Atiqur Sikder 14-Jul-21  
DATE

VENDOR: PER: 2588824 Ontario Inc.

PREPARED BY: Kayleigh Chipman  
PE 8951 - 3

CONSTRUCTION SCHEDULING APPROVAL	
PER:	
DATE:	