



Fireplace Design Studio

Ascent™ Linear 46
(BL46)



Glass Media Kits
Topaz Glass Embers

Safety Barrier
Standard Black

Surround
Classic Black

DS
NDK

DS
gmk

DV2- 33



BACK



Masonite
Expo™
Heritage®
Series
Logan™
Moulded
Panel Door



WHERE TO BUY

Door • Molded Panel Door •
Masonite Expo™ Heritage® Series



DETAILS

INSTALLATION

CARE & FINISHING





Combines the classic lines of a wood door with the durability of molded panel engineering. The smooth, primed surface is perfect for painting to match or accent your interior. Resists warping, shrinking and cracking.

DV2- 33

Available in passage and bifold doors

- 6'8", 7'0" and 8'0" heights
- Passage widths up to 3'0"
- Bifold widths up to 6'0"
- 1-3/4" 20-minute fire door
- Hollow and solid core constructions
- Emerald® "green" specification offered



Ask an in-store professional about this upgrade



Exhibit 6032 IFS DTF Acrylic Alcove Bathtub

DV2- 33- Main Bathroom

Model number:	105549
---------------	--------

Dimensions:59.75" x 31.875" x 20"

Installation:Alcove

Material:Acrylic



Standard Features:

- Unique feature: minimalist look with discreet armrests and textured bottom
- Integrated apron with access panel when equipped with a system
- Alcove installation
- Double tiling flange

Product characteristics:

- Made in Canada
- Elegant Design
- Integrated Tiling Flange and Skirt

Systems:

- Whirlpool
- Combined Whirlpool/Aeroeffect
- Aeroeffect

Warranty:

25 Years

Standard Colors:

White (001)

Bone (004)

Biscuit (007)

Certifications

UL

ICC

ES

PMG

ne or more of the following certifications:

Recommended products (Visit our website for a complete list of our recommended products)

No	Description
☐ 138760	Inverto 56-59 x 55 ½-59 in. 8mm Sliding Tub Door for Alcove Installation
☐ 139398	Halo 56 ½-59 x 59 in. 8 mm Sliding Tub Door for Alcove Installation
☐ 138480	Vela 56 ½-59 x 59 in. 8 mm Sliding Tub Door for Alcove Installation



DS

DS



Exhibit 6032 IFS DTF Acrylic Alcove Bathtub

Model number:	105549
---------------	--------

Dimensions:	59.75" x 31.875" x 20"	Installation:	Alcove	Material:	Acrylic
-------------	------------------------	---------------	--------	-----------	---------



Wood support design may vary.
Single Integrated tiling flange: 1" height x 1/4" thickness (shown)
Double Integrated tiling flange: 2 3/8" height (not shown)
All dimensions are approximate.
Structure measurement must be verified against the unit to ensure proper fit.



Dimensions
59 3/4 x 32 x 20 In. (1518 x 810 x 508 mm)
Water Capacity
46 gallons - 173 liters
Weight
78 lbs - 35.37 kg
Bathing Well
53 1/4 In. x 26 In. (1353 mm x 657 mm)
Deep Sump Height
16.25 In. - 413 mm
Deck Width
4.125 In. - 105 mm
Drain location:
Left
Right

Project: _____

Contractor: _____

Representative: _____

Date: _____

El: _____

Notes: _____

DS
JDK

DS
JDK

Jazz F 66 x 36 Acrylic Freestanding Bathtub

DV2- 33- Master Ensuite

Model number:	105359
---------------	--------

Dimensions:	66" x 36" x 24"	Installation:	FreeStanding	Material:	Acrylic
-------------	-----------------	---------------	--------------	-----------	---------



Standard Features:

- Deep soak bathing for ultimate relaxation
- 2-piece freestanding bathtub with concealed seam
- Comfortable backrest and ample deck space for faucet installation
- MAAX innovative leveling legs for easy installation
- Above-the-Floor Rough (AFR) and F² Drain compatible
- Center drain

Product characteristics:

- Made in Canada
- Deck Space for Faucet
- Chromatherapy Available

Systems:

Aerofeel

Warranty:

25 Years

Standard Colors:



White (001)



Bone (004)



Biscuit (007)

Certifications



ne or more of the following certifications:

^{DS}

^{DS}

Jazz F 66 x 36 Acrylic Freestanding Bathtub


DV2- 33- Master Ensuite

Model number:	105359
---------------	--------

Dimensions: 66" x 36" x 24"

Installation: FreeStanding

Material: Acrylic



(●) : Indicates Aerofeel airjets positioning
(■) : Indicates chromatherapy light positioning
(■) : Recommended faucet area 2 sections of 12" (L) x 3 1/2" (W)

Blower must be installed at a distance.

All dimensions are approximate. Structure measurements must be verified against the unit to ensure proper fit.

Dimensions
66 x 36 x 24 In. (1676 x 914 x 610 mm)
Water Capacity
76 gallons - 286 liters
Weight
149 lbs - 67.57 kg
Bathing Well
57 3/4 In. x 24 1/4 In. (1464 mm x 616 mm)
Deep Sump Height
19.25 In. - 489 mm
Deck Width
5.875 In. - 149 mm
Drain location:
Center

Project: _____

Contractor: _____

Representative: _____

Date: _____

Rel: _____

Notes: _____

DS
JDK

DS
JDK