



KINDRED

STEEL QUEEN


SINGLE BOWL 20 GAUGE UNDERMOUNT

MODEL: QSUA1914-7

- ✓ Resilient finish offers lasting durability
- ✓ Rear off-set drain maximizes the usable bottom surface of the bowl while also creating extra cabinet space beneath the sink
- ✓ Sound dampening system that reduces excess noise from running water and disposal vibration
- ✓ Undermount installation creates a seamless profile to bring sleek style to any kitchen



Steel Queen
Undermount



TECHNICAL FEATURES

OVERALL SINK SIZE (OD)	18 3/4" FB x 13 3/4" LR
BOWL SIZE (ID)	17" FB x 12" LR x 7" DP
MINIMUM CABINET SIZE	18"
MATERIAL	20 Gauge
CORNER RADIUS	50 mm
STAINLESS STEEL FINISH	Satin Finish Bowl with Silk Finished Rim
DRAIN HOLE LOCATION	Rear
INSTALLATION TYPE	Undermount
SOUND COATING	Undercoating
WEIGHT	6.7 lbs
WARRANTY	Limited Lifetime
COUNTRY OF ORIGIN	Canada

INCLUDED / OPTIONAL ACCESSORIES

STRAINER BASKET	1135 - INCLUDED
BOTTOM GRID	BGA1217S
CUTTING BOARD	MB100
COLANDER	CA1W _s






27W431


Submitted Model No.: _____

Specific Features: _____




FEATURES	MODEL 27W431LF
Compression	x
Direct copper inlets	x
Flexible supply inlets	
Crown handles	x
Lever handles	

BRASS STEM – COMPRESSION	
1	Acme threads engaged at all times for long life. Lubrication lasts and water is sealed out
2	Replaceable radial seal “O” ring
3	Replaceable seat washer
4	Stainless steel screw
5	Nickel chrome-plated renewable brass seats



BAR FAUCETS



SUGGESTED SPECIFICATIONS:

- Two handle deck faucet for exposed mounting.
- 10.2 cm (4") centres with 15.24 cm (6") gooseneck swing spout.
- Valve mechanisms are of the rotating compression type.
- Hot and cold stem units are interchangeable.
- All operating parts must be replaceable from above the deck.
- Valves shall be used with replaceable chrome-plated brass seats.
- All exposed metal surfaces are chrome-plated.

Aerator

- Flow restricting, 2.2 gpm maximum (8.3 L/min), chrome-plated brass housing.



COMPLIES WITH:


- ASME A112.18.1/CSA B125.1
- “LF” suffix indicates model is verified to <0.25% Pb average wetted surface regulation.

Waltec reserves the right (1) to make changes in specifications and materials, and (2) to change or discontinue models, both without notice or obligation. Dimensions are for reference only.




Numéro du modèle soumis : _____

Caractéristiques spécifiques : _____



DISPOSITIFS	MODÈLE 27W431LF
Compression	x
Conduits d'eau en cuivre directe	x
Conduits d'eau flexibles	
Manettes rondes	x
Manettes à levier	


TIGE DE LAITON – COMPRESSION	
1	Filetages Acme engagés en tout temps pour une longue durée de vie. La lubrification perdue et l'étanchéité demeure
2	Joint torique d'étanchéité radiale remplaçable
3	Rondelle de siège remplaçable
4	Vis d'acier inoxydable
5	Sièges de laiton et nickel plaqué chrome renouvelables



Waltec se réserve le droit (1) d'apporter des modifications aux spécifications et aux matériaux;
(2) de modifier ou de discontinuer certains modèles, sans avis ni obligation. Les dimensions ne sont fournies qu'à titre de référence seulement.



ROBINETS DE BAR



SPÉCIFICATIONS SUGGÉRÉES :

- Robinet à deux manettes pour le montage exposé.
- Entraxe de 10,2 cm (4 po) avec bec pivotant de 15,24 cm (6 po) en col de cygne.
- Les mécanismes du clapet doivent être de type rotatif à compression.
- Les tiges chaud et froid sont interchangeables.
- Toutes les pièces sujettes à usure doivent être remplaçables par le dessus.
- Les soupapes doivent être utilisées avec des sièges en laiton chromé remplaçables.
- Toutes les surfaces métalliques exposées doivent être chromées.

Aérateur

- Boîtier en laiton chromé, à restriction de débit, d'un débit de 8,3 L/min (2,2 gal./min).



CONFORMES AUX NORMES SUIVANTES :

- ASME A112.18.1/CSA B125.1
- Le suffixe « LF » indique que la modèle est vérifiée avec les règlements concernant le poids moyen de 0,25 % du contenu en Pb.

Waltec
Masco Canada Limited
350 South Edgeware Road
St. Thomas, ON N5P 4L1

www.waltecfaucets.ca
© 2018 Masco Canada Limited