



APPLIANCE CHECKLIST

It may seem early to be thinking about appliances, but they are an important part of your kitchen design and may require upgrades to your HVAC, plumbing and electrical plans. It’s important that we are provided with your appliance information during the structural and foundation part of the Design Process, so that these upgrades can be included on your invoice, if required.

ITEM	BRAND	MODEL NUMBER
FRIDGE	KITCHENAID	KRFF577KPS
DISHWASHER	KITCHENAID	KDTE204KPS
RANGE	FRIGIDAIRE	CGIH3047VF
Type: Gas <input type="checkbox"/> Electric <input type="checkbox"/> Induction <input checked="" type="checkbox"/> Waterline Required <input type="checkbox"/> Electrical: 15 Amp <input type="checkbox"/> 40 Amp <input checked="" type="checkbox"/> 50 Amp <input type="checkbox"/>		
WALL OVEN	NA	
Type: Gas <input type="checkbox"/> Electric <input type="checkbox"/> Waterline Required <input type="checkbox"/> Electrical: 30 Amp <input type="checkbox"/> 40 Amp <input type="checkbox"/>		
WARMING DRAWER	NA	
Electrical: 15 Amp <input type="checkbox"/> Other: Specify		
COOKTOP	NA	
Type: Gas <input type="checkbox"/> Electric <input type="checkbox"/> Induction <input type="checkbox"/> Electrical: 15 Amp <input type="checkbox"/> 40 Amp <input type="checkbox"/> 50 Amp <input type="checkbox"/>		
BUILT IN MICROWAVE	PANASONIC	
Electrical: 15 Amp <input type="checkbox"/> 20 Amp <input type="checkbox"/> 240 Volt <input type="checkbox"/> 120 Volt <input type="checkbox"/>		
MICROWAVE TRIM KIT	NA	
OTR MICROWAVE	NA	
WASHING MACHINE	ELECTROLUX	ELFW7637AT
DRYER	ELECTROLUX	ELFE763CAT
Type: Gas <input type="checkbox"/> Electric <input checked="" type="checkbox"/> Stacked <input type="checkbox"/>		
OTHER: WAHER/DRYER PEDISTALS	ELECTROLUX	EPWD257UTT
OTHER: HOODFAN	AIR KING	AV1308
OTHER:		

Hood Fans must be purchased through Phoenix Homes, and will require an upgrade to a make up air system for any hood fans above 300CFM. Standard hood fan vent pipe is 6”.

A make up air system is a required upgraded for all gas stoves/cooktops.

Any changes from the standard kitchen plan and/or standard electrical, plumbing and electrical specifications/plans may be subject to additional fees.

Community: WHITETAIL (4)

Lot #: 137

Purchaser Signature:

DocuSigned by:  
Alexandra Raeli  
41273A11C5554F5...

Purchaser Signature:


DocuSigned by:  
  
6085EB25FB8D455...

WT4 LOT 137 - FRIDGE KRFF577KPS



**KitchenAid®**

Product Dimension Guide for models KRFF577




Because Whirlpool Corporation policy includes a continuous commitment to improve our products, we reserve the right to change materials and specifications without notice. Dimensions are for planning purposes only. For complete details, see Installation Instructions packed with product. Specifications subject to change without notice.

W11640023A



Product Dimension Guide for models KRFF577



Electrical Requirements

**⚠ WARNING**

**Electrical Shock Hazard**

Plug into a grounded 3 prong outlet.

Do not remove ground prong.

Do not use an adapter.

Do not use an extension cord.

Failure to follow these instructions can result in death, fire, or electrical shock.

	Power chord		
	Type	Length	
		Inches	mm
	Standard	75 <sup>5</sup> / <sub>8</sub>	1920


**Electrical:** A 115 V, 60 Hz AC only, 15 A or 20 A fused, grounded electrical supply is required. It is recommended that a separate circuit serving only your refrigerator be provided. Use an outlet that cannot be turned off by a switch. Do not use an extension cord.

**Water:** A cold water supply with water pressure of between 30 psi and 120 psi (207 kPa and 827 kPa) is required to operate the water dispenser and ice maker. If you have questions about your water pressure, call a licensed, qualified plumber.

Because Whirlpool Corporation policy includes a continuous commitment to improve our products, we reserve the right to change materials and specifications without notice. Dimensions are for planning purposes only. For complete details, see Installation Instructions packed with product. Specifications subject to change without notice.

**KitchenAid®**

Product Dimension Guide for models KRFF577




Description		Inches	mm
A	Depth without doors	29¾	755.27
B	Depth with doors	33⅙	861.37
C	Depth with handles	36⅝	930.77
D	Space required for water lines and power chord	2	50.8

Because Whirlpool Corporation policy includes a continuous commitment to improve our products, we reserve the right to change materials and specifications without notice. Dimensions are for planning purposes only. For complete details, see Installation Instructions packed with product. Specifications subject to change without notice.

**KitchenAid®**

Product Dimension Guide for models KRFF577




Description		Inches	mm
A	Width from RC side of refrigerator to handle - door fully open 135°	13 <sup>7</sup> / <sub>8</sub>	352.63
B	Width from side RC side of refrigerator to handle - door open 90°	4	100.9
C	Depth with RC doors open 90°	48 <sup>7</sup> / <sub>8</sub>	1240.87
D	Space required for water lines and power chord	2	50.8

Because Whirlpool Corporation policy includes a continuous commitment to improve our products, we reserve the right to change materials and specifications without notice. Dimensions are for planning purposes only. For complete details, see Installation Instructions packed with product. Specifications subject to change without notice.

**KitchenAid®**

Product Dimension Guide for models KRFF577




Description		Inches	mm
A	Depth with FC door fully open	54 <sup>5</sup> / <sub>8</sub>	1387.92
B	Space required for water lines and power chord	2	50.8

Because Whirlpool Corporation policy includes a continuous commitment to improve our products, we reserve the right to change materials and specifications without notice. Dimensions are for planning purposes only. For complete details, see Installation Instructions packed with product. Specifications subject to change without notice.




Product Dimension Guide for models KRFF577



Description		Inches	mm
A	Height of recessed refrigerator	68 <sup>11</sup> / <sub>16</sub>	1744.6
B	Height to top of hinges	69 <sup>15</sup> / <sub>16</sub>	1776.6
C	Total Height	70 <sup>1</sup> / <sub>16</sub>	1780.4
D	Depth to back of hinges	25 <sup>3</sup> / <sub>8</sub>	643.77
E	Depth without doors	29 <sup>3</sup> / <sub>4</sub>	755.27
F	Depth with doors	33 <sup>15</sup> / <sub>16</sub>	861.37
G	Depth with handles	36 <sup>5</sup> / <sub>8</sub>	930.77

Interior dimensions	Width Inches (mm)	Height Inches (mm)
Refrigerator Compartment	32 <sup>9</sup> / <sub>16</sub> " (827.2)	40 <sup>1</sup> / <sub>8</sub> " (1019.4)
Freezer Compartment	31 <sup>1</sup> / <sub>8</sub> " (790.4)	17 <sup>15</sup> / <sub>16</sub> " (454.8)

Location Requirements



**⚠ WARNING**

**Explosion Hazard**  
Keep flammable materials and vapors, such as gasoline, away from refrigerator.  
Failure to do so can result in death, explosion, or fire.

To ensure proper ventilation for your refrigerator, allow for 1/2" (1.27 cm) of space on each side and at the top. Allow for 1" (2.54 cm) of space behind the refrigerator. If your refrigerator has an ice maker, allow extra space at the back for the water line connections. When installing your refrigerator next to a fixed wall, leave a 2" (5.08 cm) minimum space on each side (depending on your model) to allow the doors to swing open.


NOTES:

- This refrigerator is intended for use in a location where the temperature ranges from a minimum of 55°F (13°C) to a maximum of 110°F (43°C). The preferred room temperature range for optimum performance, which reduces electricity usage and provides superior cooling, is between 60°F (15°C) and 90°F (32°C). It is recommended that you do not install the refrigerator near a heat source, such as an oven or radiator.
- Normal minimum cabinet cut-out width required for product installation is 36" (91.44 cm). However, if the product is placed against an extended wall and the ability to remove the crisper pans is desired, an additional 18" (45.72 cm) of cabinet width is required, so a total cabinet opening width of 54" (137.16 cm) is recommended.


Because Whirlpool Corporation policy includes a continuous commitment to improve our products, we reserve the right to change materials and specifications without notice. Dimensions are for planning purposes only. For complete details, see Installation Instructions packed with product. Specifications subject to change without notice.

**KitchenAid®**


Product Dimension Guide for models KRFF577



Pantry



Crisper Drawer




Shelf Plater

Refrigerator Compartment Features			
Description	A Width Inches (mm)	B Height Inches (mm)	C Depth Inches (mm)
Pantry	32 <sup>7</sup> / <sub>16</sub> " (823.2)	5 <sup>5</sup> / <sub>8</sub> " (142.8)	20 <sup>3</sup> / <sub>16</sub> " (512.7)
Crisper Drawer	32 <sup>5</sup> / <sub>16</sub> " (821.3)	7 <sup>7</sup> / <sub>8</sub> " (199.6)	18 <sup>3</sup> / <sub>4</sub> " (475.9)
Shelf Plater	31 <sup>13</sup> / <sub>16</sub> " (350.8)	2 <sup>7</sup> / <sub>16</sub> " (61.1)	15 <sup>3</sup> / <sub>16</sub> " (386)




**KitchenAid®**

Product Dimension Guide for models KRFF577



Tuck Shelf




Shelf


Refrigerator Compartment Features			
Description	A Width Inches (mm)	B Height Inches (mm)	C Depth Inches (mm)
Tuck Shelf	15 <sup>5</sup> / <sub>8</sub> " (397)	3 <sup>1</sup> / <sub>2</sub> " (88.9)	19" (482.3)
Shelf	15 <sup>1</sup> / <sub>2</sub> " (394)	3 <sup>3</sup> / <sub>8</sub> " (85.4)	19 <sup>3</sup> / <sub>16</sub> " (487.2)

**KitchenAid®**

Product Dimension Guide for models KRFF577




Pan Lower



Pan Upper

Refrigerator Compartment Features			
Description	A Width Inches (mm)	B Height Inches (mm)	C Depth Inches (mm)
Pan Lower	29 <sup>7</sup> / <sub>8</sub> " (759.4)	11 <sup>1</sup> / <sub>16</sub> " (281.6)	21 <sup>7</sup> / <sub>8</sub> " (555.9)
Pan Upper	29 <sup>7</sup> / <sub>8</sub> " (759.4)	8 <sup>1</sup> / <sub>8</sub> " (206.7)	19 <sup>5</sup> / <sub>8</sub> " (498.5)

WT4 LOT 137 - DISHWASHER KDTE204KPS




**KitchenAid®**

# 24" Dishwasher

## DETAILED PLANNING DIMENSIONS GUIDE

Applies to all model numbers starting with;  
KDFE104K, KDTE104K, KDFE204K, KDTE204K, KDTE304LPA,  
KDFM404K, KDTM404K, KDPM604K, KDTM604K, KDPM704K,  
KDTM704K, KDTM704LPA, KDPM804K, KDTM804K

PRODUCT DIMENSIONS




\*Dishwasher can be raised 1 7/16" (3.7 cm) with feet fully extended.

Because Whirlpool Corporation policy includes a continuous commitment to improve our products, we reserve the right to change materials and specifications without notice.

Dimensions are for planning purposes only. For complete details, see Installation Instructions packed with product. Specifications subject to change without notice.

**KitchenAid®** **24" Dishwasher**  
DETAILED PLANNING DIMENSIONS GUIDE

## PRODUCT DIMENSIONS (CONTD.)



	DESCRIPTION	DIMENSIONS
A	Width of door	23½" (59.7 cm)
B*	Height to top of handle	30⅓" (78.3 cm)
C	Height of adjustable toe kick	3⅝" (8.4 cm) - min. 4⅞" (11.8 cm) - max.
D	Width of recessed dishwasher	22⅝" (57.4 cm)
E†	Depth without door	22⅝" ( 57.5 cm)
F***	Depth with Towel Bar Handle	26⅞" (68.3 cm)
	Depth with Pocket Handle	24½" (62.6 cm)
	Depth of Panel-Ready Models	24" (61.0 cm)
G*	Height to bottom of door (min.)	3⅝" (8.4 cm)
H*	Height to top of door (min.)	33⅞" (84.9 cm)
I†*	Height of recessed dishwasher (min.)	33⅝" (85.4 cm)
J†	Depth with door fully open (min.)	50⅞" (127.4 cm)
K†	Depth with toe kick (min.)	20⅓" (52.9 cm)

†Insulation blanket thickness not included, can be crushed up to 1/8" (0.3 cm), or removed along the top perforate section for additional clearance.

\*Dishwasher can be raised 1 $\frac{7}{16}$ " (3.7 cm) with feet fully extended.

**\*\*For panel-ready models, dishwasher depth is 24" (61.0 cm), not including the 3/4" (1.9 cm) custom door panel.**

Because Whirlpool Corporation policy includes a continuous commitment to improve our products, we reserve the right to change materials and specifications without notice.


Dimensions are for planning purposes only. For complete details, see Installation Instructions packed with product. Specifications subject to change without notice.

**KitchenAid®**

**24" Dishwasher**  
DETAILED PLANNING DIMENSIONS GUIDE

OPENING/CLEARANCE DIMENSIONS

**IMPORTANT:** Check that all surfaces have no protrusions that would prohibit dishwasher installation.




- A. Measured from the lowest point on the underside of the countertop. May be reduced to 33 3/8" min. (85.4 cm) min. by removing the feet and perforated area of insulation (blanket) on dishwasher.
- B. Minimum, measured from narrowest point of opening.
- NOTE:** Corner locations require a 2" (5.1 cm) minimum clearance between the side of the dishwasher door and the wall or cabinet.

Because Whirlpool Corporation policy includes a continuous commitment to improve our products, we reserve the right to change materials and specifications without notice.

Dimensions are for planning purposes only. For complete details, see Installation Instructions packed with product. Specifications subject to change without notice.

DRAIN REQUIREMENTS

- A new drain hose is supplied with your dishwasher. If drain hose is not long enough, use a new drain hose with a maximum length of 12 ft (3.7 m) that meets all current AHAM/ IAPMO test standards, is resistant to heat and detergent, and fits the 1" (2.5 cm) drain connector of the dishwasher.
- NOTE:** Do not connect multiple drain hoses together.
- Make sure to connect drain hose to waste tee or disposer inlet above drain trap in house plumbing and 20" (50.8 cm) minimum above the floor. It is recommended that the drain hose either be looped up and securely fastened to the underside of the counter or be connected to an air gap.
- Make sure to use an air gap if the drain hose is connected to house plumbing lower than 20" (50.8 cm) above subfloor or floor.



- If required, the air gap should be installed in accordance with the air gap installation instructions. When you are connecting the air gap, a rubber hose (not provided) will be needed to connect to the waste tee or disposer inlet.
- Use 1/2" (1.3 cm) minimum I.D. drain line fittings.

WATER SUPPLY REQUIREMENTS

- This dishwasher has a water heating feature and also requires a connection to a hot water supply line.
- A hot water line with 20 psi to 120 psi (138 kPa to 862 kPa) water pressure can be verified by a licensed plumber.
- 120°F (49°C) water at dishwasher.
- 3/8" (0.95 cm) O.D. copper tubing with compression fitting or flexible braided water supply line.
- NOTE:** 1/2" (1.3 cm) minimum plastic tubing is not recommended.
- A 90° elbow with 3/4" (0.95 cm) hose connection with rubber washer.
- Do not solder within 6" (15.2 cm) of the water inlet valve.
- If installed in new construction, make sure the house water supply lines have been flushed prior to connecting the dishwasher to remove any debris that may exist in the supply line.
- NOTE:** If replacing an existing dishwasher, it is recommended to install a new water line and drain hose (supplied) with the new dishwasher.

ELECTRICAL REQUIREMENTS

**WARNING**

**Electrical Shock Hazard**

**Plug into a grounded 3 prong outlet.**

**Do not remove ground prong.**

**Do not use an adapter.**

**Do not use an extension cord.**

**Failure to follow these instructions can result in death, fire, or electrical shock.**

Be sure that the electrical connection and wire size are adequate and in conformance with the National Electrical Code, ANSI/NFPA 70 - latest edition, and all local codes and ordinances.

A copy of the above code standards can be obtained from:

National Fire Protection Association  
1 Batterymarch Park  
Quincy, MA 02169-7471

You Must Have:

- 120 V, 60 Hz, AC only, 15 A or 20 A, fused electrical supply
- Copper wire only
- A maximum of 2 field wiring supply conductors (12 AWG largest size) plus 1 grounding conductor are permitted in the terminal box.

We Recommend:

- A time-delay fuse or circuit breaker.

Circuit Requirements:

- The dishwasher may be installed on the same circuit as a garbage disposal providing that the branch circuit cannot exceed rated circuit load and must comply with all governing codes and regulations such as but not limited to National Electrical Code, ANSI/NFPA 70 - latest edition.
- No electrical connections other than the dishwasher power and ground connections can be made inside of the dishwasher terminal box.

If connecting dishwasher with a power supply cord:

- Use UL Listed power cord kit marked for use with dishwasher.
- Plug into a grounded 3 prong outlet. Outlet must meet all local codes and ordinances.



If connecting dishwasher with direct wiring:

- Use flexible, armored, or nonmetallic sheathed copper wire with grounding wire that meets the wiring requirements for your home and local codes and ordinances.
- Use a UL Listed/CSA Approved metallic strain relief.



WT4 LOT 137 - INDUCTION RANGE   CGIH3047VF

FRIGIDAIRE  
GALLERY



30" Front Control Induction Range with Air Fry

Induction Range

Available Products: CGIH3047VD, CGIH3047VF

Available Colors: Black Stainless Steel, Stainless Steel

Version: 08/22



Product Specifications

Cooktop

Cooking Surface Type	Smooth
Hot-Surface Indicator Light	Yes

Cooking Controls

Air Fry	Yes
Bake	Yes
Broil	Yes
Cancel	Yes
Cooktop Lockout	Yes
Delay Clean	Yes
Door Lock	Yes
Kitchen Timer	Yes
Lockout	Yes
My Favorite	No
Off	Yes
Oven Light	Yes
Preheat	Yes
Probe	No
Quick Bake	Yes
Self Clean	Yes
Set Clock	Yes
Start	Yes
Temperature Display	Yes

Drawer

Drawer Type	Storage
-------------	---------

Display

Display Interface Color	White
Display Type	Capacitive Touch
Control Location	Front

Electrical Specifications

Minimum Circuit Required	40 Amps
Voltage Rating	240 V

General Specifications

Prop 65 Label	Yes
Warranty - Labor	1 Year
Warranty - Parts	1 Year

Cooktop Performance

Right Front Element Burner Size	8 3/10"
Right Rear Element Burner Size	5 1/2"
Left Front Element Burner Size	7"
Left Rear Element Burner Size	7"
Right Front Element Burner	3,600 Watts
Right Rear Element Burner	2,500 Watts
Left Front Element Burner	2,800 Watts
Left Rear Element Burner	2,800 Watts

Oven

Bake System	Yes
Bake Element Type	Hidden
Bake Element	3,500 Watts
Broil System	Yes
Broil Element	3,900 Watts
Convection Element	900 Watts
Rack Position Type	Nickel Ladder
Number of Rack Positions	6
Rack Type 1	Handle
Rack Type 1 Quantity	3
Window Type	Extra Large Visual

Controls

Control Lock	Yes
Sabbath Mode	Yes

Dimensions and Volume

Height	36 5/8"
Width	29 7/8"
Depth	26 3/4"
Depth With Door 90° Open	47"
Depth With Handle	29"
Oven Interior Height	19 3/4"
Oven Interior Width	24 3/8"
Oven Interior Depth	19 1/8"
Oven Capacity	5.4 Cu. Ft.

Installation

Adjustable Leveling Legs	Yes
--------------------------	-----

Certifications and Approvals

ADA Compliant	Yes
---------------	-----

For planning purposes only. We reserve the right to change specifications or discontinue models without notice.  
Refer to Product Installation Guide for detailed installation instructions on the web at [frigidaire.com](http://frigidaire.com) / [frigidaire.ca](http://frigidaire.ca)  
Electrolux Major Appliances, N.A.  
USA • 10200 David Taylor Drive •Charlotte, NC 28262 • Charlotte, NC 28262 • 1-877-4electrolux (1-877-435-3287) • [frigidaire.com](http://frigidaire.com)  
CANADA • 5855 Terry Fox Way • Mississauga, ON L5V 3E4 • 1-800-265-8352 • [frigidaire.ca](http://frigidaire.ca)

30" Front Control Induction Range with Air Fry	Induction Range
Available Products: CGIH3047VD, CGIH3047VF	Available Colors: Black Stainless Steel, Stainless Steel
Version: 08/22	

Safety Certifications and Approvals

CSA Listed	Yes
UL Listed	Yes
ETL Listed	No

Awards

Reviewed.com Best of Year Award	2017
---------------------------------	------







Family Size Microwave Oven with Cyclonic Inverter NN-ST77LS



Capacity

1.6cft

Power Supply

Cyclonic Inverter

Power

Microwave	1200W
-----------	-------

Color (Material)

Face of Door/Base	Stainless Steel (Normal)
-------------------	--------------------------

Cabinet Body	Silver
--------------	--------

Dial / Button	-
---------------	---

Plastic part of Door/Base	Black
---------------------------	-------

Oven Interior

Color (Material)	Paint Grey
------------------	------------

Oven Lamp

LED

Door

Door Design	Top/Bottom Separate / Side Open
-------------	---------------------------------

Door Open	Push Open
-----------	-----------

Screen	Smoke Glass
--------	-------------

Display

Type	New 4 Digit+icon
------	------------------

Color	White
-------	-------

Back Light	Yes
------------	-----

Word Prompting	No
Power Level etc.	
MW Power Level	11 ( P0-P10 )
Cooking Time	99min 99sec
Kitchen Timer	Yes ( 99min 99sec )
Standing Time	Yes ( 99min 99sec )
Delay Start	Yes ( 99min 99sec )
Clock	12H
Child Lock	Yes
Stage Cooking	3 stage
Menu	
Sensor	Yes
Turbo Defrost	Yes ( 0.1-3.0kg )
Popcorn	Yes ( 1.5/2.75/3.2oz )
Keep Warm	Yes in MW power (P0) (up to 30min)
Steam Clean	No
Quick Min	Quick 30 ( up to 5min )
Serving/Weight	-
More/Less	Yes
Recipe Store	No
Auto Reheat	Sensor Reheat
Number of Auto Cook	15
Turntable Size	
380mm	
Accessory	
Glass Tray	
Trim Kit	
Yes	
Power Consumption	
Microwave	1460W

Cooking Power

1200W

Dimensions

Outside (HxWxD) 304 x 555 x 493 mm  
11 15/16 x 21 7/8 x 19 7/16 "

Oven (HxWxD) 210 x 398 x 470 mm  
8 1/4 x 15 11/16 x 18 1/2 "

Weight

Net 32,0 lb / 14,3 kg

Shipping 16,7 kg

WT4 LOT 137 - WASHER ELFW7637AT



Electrolux



Front Load Washer

4.5 Cu.Ft. Front Load Washer

ELFW7637AT, ELFW7637AW

Available Colors : Titanium, White

Version : 06/21

Washer	
Drum Light	Yes
Drum Material	Stainless Steel
Maximum Spin Speed	1,300 RPM
Water Heater	Yes
Water Level Adjustment	Yes

Washer Cycles	
Activewear	Yes
Clean Washer	Yes
Colors	Yes
Cycle Count	11
Delicates	Yes
Fast Wash	Yes
Hand Wash	Yes
Heavy Duty	Yes
Normal	Yes
Optic Whites	Yes
Rinse and Spin	Yes
Towels	Yes
Allergen	Yes

Washer Options	
Delay Start Time	1-12 Hours
Extended Refresh	Yes
Extra Rinse	Yes
Perfect Steam	Yes
Pure Rinse	Yes
Stain Soak	Yes
Steam	Yes

Soil Levels	
Extra Light	Yes
Light	Yes
Normal	Yes
Heavy	Yes

Solid Soil	Yes
------------	-----

Temperature Settings	
Eco Cold	Yes
Cool	Yes
Warm	Yes
Hot	Yes
Sanitize	Yes

Washer Spin Speeds	
Spin Speed Selections	5
Max	Yes
High	Yes
Medium	Yes
Low	Yes
No Spin	Yes

Controls	
Cancel	Yes
Cycle Status Lights	Yes
Delay Start	Yes
Control Lock	Yes
Pause Function	Yes
Power On/Off	Yes
Start	Yes

Dispenser	
Bleach Dispenser	Yes
Detergent Dispenser	Yes
Fabric Softener Dispenser	Yes
Prewash Detergent Dispenser	Yes
PODs Dispenser	Yes

Exterior	
Door Latch	Yes
Reversible Door	Yes

High standards of quality at Electrolux Home Products, Inc. mean we are constantly working to improve our products. We reserve the right to change specifications or discontinue models without notice.

Electrolux Major Appliances, N.A.  
USA • 10200 David Taylor Drive •Charlotte, NC 28262 • Charlotte, NC 28262 • 1-877-4electrolux (1-877-435-3287) • [electroluxappliances.com](http://electroluxappliances.com)  
CANADA • 5855 Terry Fox Way • Mississauga, ON L5V 3E4 • 1-800-265-8352 • [electroluxappliances.ca](http://electroluxappliances.ca)

Electrolux

4.5 Cu.Ft. Front Load Washer

ELFW7637AT, ELFW7637AW

Version : 06/21

Dimensions and Volume

Height	38"
Width	27"
Depth	32"
Washer Drum Capacity	4.5 Cu. Ft.

Electrical Specifications

Minimum Circuit Required	15 Amps
Voltage Rating	120 V

Energy Data

Integrated Water Factor	3.2
kWh/year	85 kWh
Modified Energy Factor	2.92
Water Usage/Year	4,248 Gallons

Installation

Optional Pedestal	Yes
Stackable	Yes

General Specifications

Chime On / Chime Off	Yes
Leveling Legs	Yes
Product Weight	217 lbs
Prop 65 Label	No
Warranty - Labor	1 Year
Warranty - Parts	1 Year

Performance Certifications and Approvals

CEE Tier	Tier 2
ENERGY STAR Certified	Yes
ENERGY STAR Most Efficient	Yes
High Efficiency	Yes

Safety Certifications and Approvals

UL Listed	Yes
NSF Certified	Yes
Sanitization and Allergy Reduction	Yes

High standards of quality at Electrolux Home Products, Inc. mean we are constantly working to improve our products. We reserve the right to change specifications or discontinue models without notice.


Electrolux Major Appliances, N.A.  
USA • 10200 David Taylor Drive •Charlotte, NC 28262 • Charlotte, NC 28262 • 1-877-4electrolux (1-877-435-3287) • [electroluxappliances.com](http://electroluxappliances.com)  
CANADA • 5855 Terry Fox Way • Mississauga, ON L5V 3E4 • 1-800-265-8352 • [electroluxappliances.ca](http://electroluxappliances.ca)

Electrolux

4.5 Cu.Ft. Front Load Washer

ELFW7637AT, ELFW7637AW

Version : 06/21



WT4 LOT 137 - ELECTRIC DRYER ELFE763CAT



Electrolux



Dryer

Electric 8.0 Cu. Ft. Front Load Dryer

ELFE763CAT, ELFE763CAW

Available Colors : Titanium, White

Version : 07/21

Dryer

Air Flow	200 CFM
Balanced Dry	Yes
Drum Back Type	Painted Steel
Drum Material	Stainless Steel
Dryness Level Selections	Yes
Lint Filter	Yes
Predictive Dry	No

Dryer Cycles

Cycle Count	11
Activewear	Yes
Air Dry	Yes
Allergen	Yes
Delicates	Yes
Fast Dry	Yes
Heavy Duty	Yes
Instant Refresh	Yes
Mixed Load	Yes
Normal	Yes
Timed Dry Time	Yes
Towels	Yes

Dryer Options

Anti Static	Yes
Delay Start Time	1-12 Hours
Drum Light	Yes
Dry Boost	Yes
Extended Tumble	Yes
Perfect Steam	Yes
Wrinkle Release	Yes

Drying Temperatures

Low	Yes
Normal	Yes
High	Yes

Sanitize	Yes
Eco Dry	Yes

Dryness Level

Max	Yes
High	Yes
Normal	Yes
Low	Yes
Damp	Yes

Controls

Cancel	Yes
Cycle Status Lights	Yes
Delay Start	Yes
Estimated Time Remaining	Yes
Control Lock	Yes
Pause Function	Yes
Power On/Off	Yes
Start	Yes

Exterior

Door Latch	Yes
Reversible Door	Yes

Dimensions and Volume

Height	38"
Width	27"
Depth	32"
Dryer Drum Capacity	8 Cu. Ft.

Electrical Specifications

Minimum Circuit Required	30 Amps
Voltage Rating	208/240v

Energy Data

kWh/cycle	2.5 kWh
-----------	---------

High standards of quality at Electrolux Home Products, Inc. mean we are constantly working to improve our products. We reserve the right to change specifications or discontinue models without notice.

Electrolux Major Appliances, N.A.  
USA • 10200 David Taylor Drive •Charlotte, NC 28262 • Charlotte, NC 28262 • 1-877-4electrolux (1-877-435-3287) • [electroluxappliances.com](http://electroluxappliances.com)  
CANADA • 5855 Terry Fox Way • Mississauga, ON L5V 3E4 • 1-800-265-8352 • [electroluxappliances.ca](http://electroluxappliances.ca)



Electrolux

Electric 8.0 Cu. Ft. Front Load Dryer		ELFE763CAT, ELFE763CAW	
		Version : 07/21	
kWh/year		710 kWh	
Installation			
Optional Pedestal		Yes	
General Specifications			
Chime On / Chime Off		Yes	
Leveling Legs		Yes	
Product Weight		126 lbs	
Prop 65 Label		No	
Warranty - Labor		1 Year	
Warranty - Parts		1 Year	
Performance Certifications and Approvals			
ENERGY STAR Certified		Yes	
Safety Certifications and Approvals			
UL Listed		Yes	

High standards of quality at Electrolux Home Products, Inc. mean we are constantly working to improve our products. We reserve the right to change specifications or discontinue models without notice.


Electrolux Major Appliances, N.A.  
USA • 10200 David Taylor Drive •Charlotte, NC 28262 • Charlotte, NC 28262 • 1-877-4electrolux (1-877-435-3287) • [electroluxappliances.com](http://electroluxappliances.com)  
CANADA • 5855 Terry Fox Way • Mississauga, ON L5V 3E4 • 1-800-265-8352 • [electroluxappliances.ca](http://electroluxappliances.ca)

Electrolux

Electric 8.0 Cu. Ft. Front Load Dryer

ELFE763CAT, ELFE763CAW

Version : 07/21



High standards of quality at Electrolux Home Products, Inc. mean we are constantly working to improve our products. We reserve the right to change specifications or discontinue models without notice.

Electrolux Major Appliances, N.A.  
USA • 10200 David Taylor Drive •Charlotte, NC 28262 • Charlotte, NC 28262 • 1-877-4electrolux (1-877-435-3287) • [electroluxappliances.com](http://electroluxappliances.com)  
CANADA • 5855 Terry Fox Way • Mississauga, ON L5V 3E4 • 1-800-265-8352 • [electroluxappliances.ca](http://electroluxappliances.ca)

WT4 LOT 137 - WASHER/DRYER PEDISTAL EPWD257UTT



Luxury-Glide® Pedestal with Spacious Storage Drawer

Pedestal

Available Products: EPWD257UIW, EPWD257UTT

Available Colors: White, Titanium

Version: 08/22



Product Specifications

Dimensions and Volume		General Specifications	
Height	15"	Prop 65 Label	No
Width	27"	Warranty - Labor	1 Year
Depth	26 7/16"	Warranty - Parts	1 Year

We reserve the right to change specifications or discontinue models without notice.

Electrolux Major Appliances, N.A.

USA • 10200 David Taylor Drive •Charlotte, NC 28262 • Charlotte, NC 28262 • 1-877-4electrolux (1-877-435-3287) • electrolux.com/en

CANADA • 5855 Terry Fox Way • Mississauga, ON L5V 3E4 • 1-800-265-8352 • electrolux.ca

WT4 LOT 137 - STANDARD UNDERCABINET HOODFAN AV1308



SPECIFICATIONS  
**AV SERIES**  
RANGE HOODS

**180 CFM/7.0 Sones @ 0.10" SP. Horizontal**  
**180 CFM/7.5 Sones @ 0.10" SP. Vertical**

• **Dimensions**

Overall bottom projection - 18<sup>3</sup>/<sub>8</sub>"  
Overall top projection -12"  
Height - 6"  
Available widths: 24", 30", 36" & 42"

• **Hood Body**

Stainless Steel: 24 gauge, grade 430 stainless steel.  
Painted: 23 gauge cold rolled commercial grade (CRCQ) steel, auto welded, coated with a baked enamel finish.

• **Motor**

2 speed, single coil, thermally protected, permanently lubricated.  
Rated 120 volts, 60 hz. Complete with 200°C lead wires.

• **Lighting**

Single 60 watt cook light capacity (bulb not included).

• **Ducting Options**


Horizontal ducting: 3<sup>1</sup>/<sub>4</sub>"x10" (duct adapter and damper included).  
Vertical ducting: 3<sup>1</sup>/<sub>4</sub>"x10" (duct adapter and damper included).  
Vertical ducting: 7" round (duct adapter and damper not included).  
Ductless: removable front vent (charcoal filter not included).

• **Fan Blade**


One piece polymeric, electronically balanced blade. 6<sup>5</sup>/<sub>8</sub>" diameter with 5 paddles.

• **Electrical connection**

Hood top - 7/8" knockout hole for use with 1/2" cable clamp  
Hood back - 7/8" knockout hole for use with 1/2" cable clamp



**AV SERIES**



• **Filters**

UL rated, class 2 filter.  
Grease Filter: RF35 - 8<sup>7</sup>/<sub>8</sub>"x10<sup>3</sup>/<sub>8</sub>" (included).  
Charcoal Filter: RF34 (not included).  
Combo Grease/Charcoal: RF55 (not included).

• **Available Finishes**

White, Black & Stainless Steel.

EXPANDED PERFORMANCE										
Air Flow - CFM	Static Pressure (inches of w.g.)						Sones @ .1 SP	Fan Speed RPM	Power Watts	Amps
	0	0.05	0.1	0.15	0.2	0.25				
Vertical Ducting High	246	232	218	203	181	147	7.5	2973	87.0	2.1
Horizontal Ducting High	225	210	180	175	155	120	7.0	3024	87.0	2.1

PROJECT							ARCHITECT			
LOCATION							ENGINEER			
CONTRACTOR							SUBMITTED BY		DATE	
FAN NUMBER	MODEL NUMBER	CFM	IN W.C.	RPM	WATTS	AMPS	SONES	QTY	OPTIONAL EQUIPMENT & REMARKS	



**Air King:** 820 Lincoln Avenue  
West Chester, Pennsylvania 19380-4466  
Tel: (610) 692-7400 • 877-304-3785  
Fax: (610) 696-8048

**Canada:**  
Brampton, Ontario  
Tel: 905-456-2033  
Fax: (905) 456-1015