



ADDENDUM TO CONSTRUCTION CONTRACT

SCHEDULE "A" **(Revised: Aug. 16, 2018)** **Forestside Towns VI**

The materials and labour to be furnished and the work to be performed by the contractor under the terms of this agreement are as set out below:

POURED BASEMENT WALLS:

- Ø Basement walls 7'10" high, including party wall.
- Ø Garage walls full height.
- Ø Supply: anchor bolts and 2 x 5 plates
- Ø Brush coat and beam pockets included.
- Ø Clean up debris
- Ø Cracked basement and rod holes to have a two year warranty
- Ø Labour and material all included
- Ø All walls shall be level and square
- Ø Before commencing work the site foreman shall check with the site super for any changes, extras, re-location of windows, location of hydro, all cuts and veneers.
- Ø Two prices must be included in this quote summer and winter.
- Ø If for any reason there occurs extra concrete to footings, walls, base conditions, a P.O. must be assigned by the superintendent and or project manager and must also require a signature to the quantities of materials and labour involved.
- Ø **Included in quote:**
Labour to install reinforced rebars for engineered filled lots in accordance with site supers direction and specifications. (2 bars for footings, 2 bars for walls).

EXPIRY DATE: DECEMBER 31, 2019