





ASPHALT SHINGLES
FINISHED OVERHANG: 12"
2x6 EXTERIOR WALLS
2x6 FASCIA BOARD
HEEL: R.T.M.C.

DESIGN CONFORMS WITH OBC 2012
OCCUPANCY: RESIDENTIAL | PART: 9
Ss = 31.4 psf | Sr = 8.4 psf

DESIGN LOADS:
TCSL = 25.6 psf
TCDL = 6.0 psf
BCLL = 0.0 psf
BCDL = 7.4 psf

 DENOTES:
CONVENTIONAL
FRAMING

HARDWARE:
LUS24 - (O)
LJS26DS - (V)
HGUS26-2 - (XX)
HGUS26-3 - (XXX)
H2.5T - (/)
LGT3 - (@)

All conventional framing to conform with Part 9 of O.B.C. 2012. Rof rafters that cross over or meet trusses to be min. 2x4 SPF #2 @ 24" o/c with a vertical post to the truss at each cross point. Vertical posts longer than 6' to have lateral bracing so that the distance between the post end points and lateral bracing does not exceed 6'.



Job Track: **51012**
Plan Log: **203549**
Layout ID: **413086**


Builder / Location:
ROYAL PINE HOMES / RICHMOND HILL
Project: **CENTREFIELD**
Date: 2021-07-01 Sales: **Mario DiCano** Designer: AC

Model / Elevation:
BLOCK 58 / UNITS 17 - 21

Mitek ver 8.4.2.286

THESE DRAWINGS CONSTITUTE THE PROPERTY OF TAMARACK ROOF TRUSSES INC., SHALL NOT BE REPRODUCED, PUBLISHED, OR REDISTRIBUTED IN ANY MANNER OR UTILIZED FOR ANY PURPOSE OTHER THAN THE MANUFACTURE OF TRUSSES BY TAMARACK ROOF TRUSSES INC AND WILL BE RETRACTED BY TAMARACK ROOF TRUSSES INC IF UTILIZED FOR ANY OTHER PURPOSE.



DELIVERY SHIPLIST




Lumber Yard: TAMARACK LUMBER
 Builder: ROYAL PINE HOMES
 Project: CENTREFIELD
 Location: RICHMOND HILL
 Model: BLOCK 58
 Lot #:
 Elevation: B / UNIT21BLK284

Job Track: 51012
 PlanLog: 203549
 Layout ID: 413119
 Ref #
 Page: 1 of 2
 Date: 07-08-2021
 Designer: Andrew Conway
 Sales Rep: Mario DiCano

Roof Trusses

PROFILE	QTY PLY	MARK TYPE	PITCH	SPAN	HEIGHT	LUMBER	OVERHANG LEFT RIGHT	HEEL HEIGHT LEFT RIGHT	LBS. BFT.	BUNDLE # STACK #	LOAD BY REMARKS
	2	T10G GABLE	6 /12	22-08-08	8-01-04	2 x 4	1-05-00	1-02-00 8-01-04	243.75 153.67		
	1 2-ply	T101 Half Hip Girder	6 /12	19-05-08	4-01-04	2 x 4 2 x 6	1-03-08	1-02-00 4-01-04	182.72 116.00		
	1 2-ply	T101Z Half Hip Girder	6 /12	19-05-08	4-01-04	2 x 4 2 x 6	1-03-08	1-02-00 4-01-04	182.72 116.00		
	2	T102 Half Hip	6 /12	19-05-08	5-01-04	2 x 4	1-03-08	1-02-00 5-01-04	159.13 101.33		
	2	T103 Half Hip	6 /12	19-05-08	6-01-04	2 x 4	1-03-08	1-02-00 6-01-04	172.24 109.67		
	2	T104 Half Hip	6 /12	19-05-08	7-01-04	2 x 4	1-03-08	1-02-00 7-01-04	173.04 108.00		
	8	T105 Half Hip	6 /12	19-05-08	8-01-04	2 x 4	1-03-08	1-02-00 8-01-04	689.37 434.67		
	2	T106 Half Hip	6 /12	19-05-08	9-01-04	2 x 4	1-03-08	1-02-00 9-01-04	181.02 114.00		
	1	T107 Hip Girder	6 /12	9-06-00	2-04-12	2 x 4	1-03-08 1-03-08	1-02-00 1-02-00	37.9 25.50		
	2	T108 Hip	6 /12	9-06-00	4-10-12	2 x 4	1-03-08 1-03-08	2-08-00 2-08-00	99.25 67.00		
	1	T109 Hip	6 /12	9-06-00	3-10-12	2 x 4	1-03-08 1-03-08	2-08-00 2-08-00	45.71 31.67		
	1 2-ply	T110 Monopitch Girder	6 /12	5-10-08	4-01-04	2 x 4 2 x 6		1-02-00 4-01-04	58.39 37.67		
	2	PB101 Piggyback	6 /12	5-07-00	2-00-00	2 x 4		2-00-00	32.19 22.67		
	4	PB102 Piggyback	6 /12	5-07-00	2-09-08	2 x 4		2-09-08	58.98 40.00		

DELIVERY SHIPLIST



Lumber Yard: TAMARACK LUMBER
 Builder: ROYAL PINE HOMES
 Project: CENTREFIELD
 Location: RICHMOND HILL
 Model: BLOCK 58
 Lot #:
 Elevation: B / UNIT21BLK284

Job Track: 51012
 PlanLog: 203549
 Layout ID: 413119
 Ref #
 Page: 2 of 2
 Date: 07-08-2021
 Designer: Andrew Conway
 Sales Rep: Mario DiCano

Roof Trusses

PROFILE	QTY PLY	MARK TYPE	PITCH	SPAN	HEIGHT	LUMBER	OVERHANG LEFT RIGHT	HEEL HEIGHT LEFT RIGHT	LBS. BFT.	BUNDLE # STACK #	LOAD BY REMARKS
	2	PB103G GABLE	6 / 12	8-10-00	2-09-08	2 x 4		2-09-08	51.18 35.33		
	11	J01 Jack-Open	6 / 12	5-10-08	4-01-04	2 x 4	1-03-08	1-02-00 4-01-04	184.74 117.33		
	5	J03 Jack-Open	4 / 12	3-07-00	1-11-03	2 x 4	1-03-08	3-15 1-03-04	50.28 33.33		
	2	J11 Jack-Open	6 / 12	1-10-15	2-01-08	2 x 4	1-03-08 6-09	1-02-00 2-01-08	15.69 10.67		
	2	J12 Jack-Open	6 / 12	2-05-08	2-04-12	2 x 4	1-03-08	1-02-00 2-04-12	17.09 12.00		
	3	J13 Jack-Open	6 / 12	1-10-15	2-01-08	2 x 4	1-03-08 1-01	1-02-00 2-01-08	21.97 14.00		
	1	J14 Jack-Open	6 / 12	2-00-00	3-01-08	2 x 4	1-03-08 1-10-15	1-02-00 2-02-00	9.87 6.00		
	1	J15 Jack-Open	6 / 12	1-10-15	2-01-08	2 x 4	1-03-08 3-11-09	1-02-00 2-01-08	11.74 7.33		
	1	J16 Jack-Open	6 / 12	3-10-15	3-01-08	2 x 4	1-03-08 1-11-09	1-02-00 3-01-08	14.29 8.67		


TOTAL # TRUSS= 62 TOTAL BFT OF ALL TRUSSES= 1722.51 BFT. TOTAL WEIGHT OF ALL TRSSES 2693.27 LBS

HARDWARE

QTY	TYPE	MODEL	LENGTH
3	Hardware	LUS24	
1	Hardware	HGUS26-2	

TOTAL NUMBER OF ITEMS= 4

DELIVERY SHIPLIST




Lumber Yard: TAMARACK LUMBER
 Builder: ROYAL PINE HOMES
 Project: CENTREFIELD
 Location: RICHMOND HILL
 Model: BLOCK 58
 Lot #:
 Elevation: B1 / UNIT20BLK284

Job Track: 51012
 PlanLog: 203549
 Layout ID: 413120
 Ref #
 Page: 1 of 2
 Date: 07-08-2021
 Designer: Andrew Conway
 Sales Rep: Mario DiCano

Roof Trusses

PROFILE	QTY PLY	MARK TYPE	PITCH	SPAN	HEIGHT	LUMBER	OVERHANG LEFT RIGHT	HEEL HEIGHT LEFT RIGHT	LBS. BFT.	BUNDLE # STACK #	LOAD BY REMARKS
	5	T11 Piggyback Base	6 /12	45-05-00	8-01-04	2 x 6	1-03-08 1-03-08	1-02-00 1-02-00	1279.34 775.00		
	4	T11B Piggyback Base	6 /12	45-00-08	8-01-04	2 x 6	1-03-08	1-02-00 1-02-00	1007.58 617.33		
	1	T11G GABLE	6 /12	45-05-00	8-01-04	2 x 6	1-03-08 1-03-08	1-02-00 1-02-00	272.06 169.67		
	1	T11GC GABLE	6 /12	38-11-00	8-01-04	2 x 6	1-03-08	1-02-00 1-02-00	247.87 155.83		
	1	T122 Hip Girder	6 /12	8-07-00	2-04-12	2 x 4	1-03-08 1-03-08	1-02-00 1-02-00	35.14 23.67		
	1 3-ply	T127 Common Girder	6 /12	8-05-08	4-09-12	2 x 4 2 x 6		2-08-00 2-08-12	124.02 84.50		
	1	T141 Common	6 /12	8-07-00	3-03-12	2 x 4	1-03-08 1-03-08	1-02-00 1-02-00	34.58 22.17		
	2	J11 Jack-Open	6 /12	1-10-15	2-01-08	2 x 4	1-03-08 6-09	1-02-00 2-01-08	15.69 10.67		
	2	J12 Jack-Open	6 /12	2-05-08	2-04-12	2 x 4	1-03-08	1-02-00 2-04-12	17.09 12.00		
	2	J13 Jack-Open	6 /12	1-10-15	2-01-08	2 x 4	1-03-08 1-01	1-02-00 2-01-08	14.65 9.33		
	8	PB06 Piggyback	6 /12	17-08-00	4-05-00	2 x 4			410.9 256.00		
	1	PB06G GABLE	6 /12	17-08-00	4-05-00	2 x 4			50.76 31.00		
	1	PB104 Piggyback	6 /12	17-08-00	3-11-04	2 x 4			57.06 37.00		
	1	PB105G Piggyback	6 /12	8-10-00	2-08-00	2 x 4		2-09-08	25.27 17.67		

 TAMARACK ROOF TRUSSES INC. ALFA LUMBER GROUP	DELIVERY SHIPLIST			
	Lumber Yard:	TAMARACK LUMBER	Job Track:	51012
	Builder:	ROYAL PINE HOMES	PlanLog:	203549
	Project:	CENTREFIELD	Layout ID:	413120
	Location:	RICHMOND HILL	Ref #	
	Model:	BLOCK 58	Page:	2 of 2
Lot #:		Date:	07-08-2021	
Elevation:	B1 / UNIT20BLK284	Designer:	Andrew Conway	
		Sales Rep:	Mario DiCano	

Roof Trusses


PROFILE	QTY PLY	MARK TYPE	PITCH	SPAN	HEIGHT	LUMBER	OVERHANG LEFT RIGHT	HEEL HEIGHT LEFT RIGHT	LBS. BFT.	BUNDLE # STACK #	LOAD BY REMARKS
---------	------------	--------------	-------	------	--------	--------	---------------------------	------------------------------	--------------	---------------------	--------------------

TOTAL # TRUSS= 33
TOTAL BFT OF ALL TRUSSES= 2221.84
BFT.
TOTAL WEIGHT OF ALL TRSSES 3592
LBS


HARDWARE

QTY	TYPE	MODEL	LENGTH
4	Hardware	LJS26DS	
14	Hardware	H2.5T	
2	Hardware	LGT3	

TOTAL NUMBER OF ITEMS= 20

DELIVERY SHIPLIST				
 TAMARACK ROOF TRUSSES INC. ALPA LUMBER GROUP	Lumber Yard:	TAMARACK LUMBER	Job Track:	51012
	Builder:	ROYAL PINE HOMES	PlanLog:	203549
	Project:	CENTREFIELD	Layout ID:	413121
	Location:	RICHMOND HILL	Ref #	
	Model:	BLOCK 58	Page:	1 of 2
	Lot #:		Date:	07-08-2021
	Elevation:	B / UNIT19BLK284	Designer:	
		Sales Rep:	Mario DiCano	

Roof Trusses

PROFILE	QTY PLY	MARK TYPE	PITCH	SPAN	HEIGHT	LUMBER	OVERHANG LEFT RIGHT	HEEL HEIGHT LEFT RIGHT	LBS. BFT.	BUNDLE # STACK #	LOAD BY REMARKS
	5	T11 Piggyback Base	6 /12	45-05-00	8-01-04	2 x 6	1-03-08 1-03-08	1-02-00 1-02-00	1279.34 775.00		
	4	T11B Piggyback Base	6 /12	45-00-08	8-01-04	2 x 6	1-03-08	1-02-00 1-02-00	1007.58 617.33		
	1	T11G GABLE	6 /12	45-05-00	8-01-04	2 x 6	1-03-08 1-03-08	1-02-00 1-02-00	272.06 169.67		
	1	T11GB GABLE	6 /12	37-03-00	8-01-04	2 x 6	1-03-08	1-02-00 5-03-00	236.81 147.83		
	1	T122 Hip Girder	6 /12	8-07-00	2-04-12	2 x 4	1-03-08 1-03-08	1-02-00 1-02-00	35.14 23.67		
	1	T123 Common	6 /12	8-03-08	3-03-12	2 x 4	1-03-08	1-02-00 1-03-12	32.19 20.83		
	1 3-ply	T127 Monopitch Girder	6 /12	8-05-08	4-09-12	2 x 4 2 x 6		2-08-00 2-08-12	124.02 84.50		
	9	PB06 Piggyback	6 /12	17-08-00	4-05-00	2 x 4			462.27 288.00		
	2	PB06G GABLE	6 /12	17-08-00	4-05-00	2 x 4			101.52 62.00		
	2	J11 Jack-Open	6 /12	1-10-15	2-01-08	2 x 4	1-03-08 6-09	1-02-00 2-01-08	15.69 10.67		
	2	J12 Jack-Open	6 /12	2-05-08	2-04-12	2 x 4	1-03-08	1-02-00 2-04-12	17.09 12.00		
	1	J13 Jack-Open	6 /12	1-10-15	2-01-08	2 x 4	1-03-08 1-01	1-02-00 2-01-08	7.32 4.67		

TOTAL # TRUSS= 32


TOTAL BFT OF ALL TRUSSES= 2216.17

BFT.

TOTAL WEIGHT OF ALL TRSSES 3591.01 LBS

HARDWARE


QTY	TYPE	MODEL	LENGTH
4	Hardware	LJS26DS	
14	Hardware	H2.5T	

 TAMARACK ROOF TRUSSES INC. ALPA LUMBER GROUP	DELIVERY SHIPLIST	
	Lumber Yard:	TAMARACK LUMBER
	Builder:	ROYAL PINE HOMES
	Project:	CENTREFIELD
	Location:	RICHMOND HILL
	Model:	BLOCK 58
	Lot #:	
	Elevation:	B / UNIT19BLK284
Job Track:	51012	
PlanLog:	203549	
Layout ID:	413121	
Ref #		
Page:	2 of 2	
Date:	07-08-2021	
Designer:		
Sales Rep:	Mario DiCano	




HARDWARE


QTY	TYPE	MODEL	LENGTH
2	Hardware	LGT3	

TOTAL NUMBER OF ITEMS= 20

DELIVERY SHIPLIST				
 TAMARACK ROOF TRUSSES INC. ALPHA LUMBER GROUP	Lumber Yard:	TAMARACK LUMBER	Job Track:	51012
	Builder:	ROYAL PINE HOMES	PlanLog:	203549
	Project:	CENTREFIELD	Layout ID:	413122
	Location:	RICHMOND HILL	Ref #	
	Model:	BLOCK 58	Page:	1 of 2
	Lot #:		Date:	07-08-2021
	Elevation:	B / UNIT18BLK284	Designer:	Andrew Conway
		Sales Rep:	Mario DiCano	

Roof Trusses

PROFILE	QTY PLY	MARK TYPE	PITCH	SPAN	HEIGHT	LUMBER	OVERHANG LEFT RIGHT	HEEL HEIGHT LEFT RIGHT	LBS. BFT.	BUNDLE # STACK #	LOAD BY REMARKS
	5	T11 Piggyback Base	6 /12	45-05-00	8-01-04	2 x 6	1-03-08 1-03-08	1-02-00 1-02-00	1279.34 775.00		
	4	T11A Piggyback Base	6 /12	38-03-00	8-01-04	2 x 6	1-03-08	1-02-00 1-02-00	886.16 540.00		
	1	T11G GABLE	6 /12	45-05-00	8-01-04	2 x 6	1-03-08 1-03-08	1-02-00 1-02-00	272.06 169.67		
	1	T11GB GABLE	6 /12	37-03-00	8-01-04	2 x 6	1-03-08	1-02-00 5-03-00	236.81 147.83		
	1 3-ply	T111 Piggyback Base Girder	6 /12	45-05-00	8-01-04	2 x 6	1-03-08 1-03-08	1-02-00 1-02-00	843.15 519.00		
	1	T117 Half Hip Girder	6 /12	8-04-08	2-04-12	2 x 4	1-03-08	1-02-00 2-04-12	34.08 22.83		
	1	T118 Half Hip	6 /12	8-04-08	4-10-12	2 x 4		2-08-00 4-10-12	39.12 26.00		
	1	T119 Half Hip	6 /12	8-04-08	5-10-12	2 x 4		2-08-00 5-10-12	45.3 29.67		
	1	T120 Monopitch	6 /12	8-04-08	6-10-04	2 x 4		2-08-00 6-10-04	41.6 27.33		
	1 3-ply	T121 Jack-Closed Girder	6 /12	8-06-08	6-11-04	2 x 4 2 x 6		2-08-00 6-11-04	141.44 94.00		
	8	PB06 Piggyback	6 /12	17-08-00	4-05-00	2 x 4			410.9 256.00		
	1	PB06G GABLE	6 /12	17-08-00	4-05-00	2 x 4			50.76 31.00		
	1 3-ply	PB06Z Piggyback	6 /12	17-08-00	4-05-00	2 x 4			154.09 96.00		
	1	PB104 Piggyback	6 /12	17-08-00	3-11-04	2 x 4			57.06 37.00		

DELIVERY SHIPLIST				
 TAMARACK ROOF TRUSSES INC. ALPA LUMBER GROUP	Lumber Yard:	TAMARACK LUMBER	Job Track:	51012
	Builder:	ROYAL PINE HOMES	PlanLog:	203549
	Project:	CENTREFIELD	Layout ID:	413122
	Location:	RICHMOND HILL	Ref #	
	Model:	BLOCK 58	Page:	2 of 2
	Lot #:		Date:	07-08-2021
	Elevation:	B / UNIT18BLK284	Designer:	Andrew Conway
		Sales Rep:	Mario DiCano	

Roof Trusses

PROFILE	QTY PLY	MARK TYPE	PITCH	SPAN	HEIGHT	LUMBER	OVERHANG LEFT RIGHT	HEEL HEIGHT LEFT RIGHT	LBS. BFT.	BUNDLE # STACK #	LOAD BY REMARKS
	1	PB105G Piggyback	6 /12	8-10-00	2-08-00	2 x 4		2-09-08	25.27 17.67		
	5	J03 Jack-Open	4 /12	3-07-00	1-11-03	2 x 4	1-03-08	3-15 1-03-04	50.28 33.33		
	1	J11 Jack-Open	6 /12	1-10-15	2-01-08	2 x 4	1-03-08 6-09	1-02-00 2-01-08	7.85 5.33		
	3	J12 Jack-Open	6 /12	2-05-08	2-04-12	2 x 4	1-03-08	1-02-00 2-04-12	25.63 18.00		
	1	J13 Jack-Open	6 /12	1-10-15	2-01-08	2 x 4	1-03-08 1-01	1-02-00 2-01-08	7.32 4.67		


TOTAL # TRUSS= 45 TOTAL BFT OF ALL TRUSSES= 2850.33 BFT. TOTAL WEIGHT OF ALL TRSSES 4608.21 LBS

HARDWARE

QTY	TYPE	MODEL	LENGTH
3	Hardware	LUS24	
4	Hardware	LJS26DS	
1	Hardware	HGUS26-3	
14	Hardware	H2.5T	

TOTAL NUMBER OF ITEMS= 22

DELIVERY SHIPLIST




Lumber Yard: TAMARACK LUMBER
 Builder: ROYAL PINE HOMES
 Project: CENTREFIELD
 Location: RICHMOND HILL
 Model: BLOCK 58
 Lot #:
 Elevation: B / UNIT17BLK284




Job Track: 51012
 PlanLog: 203549
 Layout ID: 413123
 Ref #
 Page: 1 of 2
 Date: 07-08-2021
 Designer: Andrew Conway
 Sales Rep: Mario DiCano

Roof Trusses

PROFILE	QTY PLY	MARK TYPE	PITCH	SPAN	HEIGHT	LUMBER	OVERHANG LEFT RIGHT	HEEL HEIGHT LEFT RIGHT	LBS. BFT.	BUNDLE # STACK #	LOAD BY REMARKS
	2	T10G GABLE	6 /12	22-08-08	8-01-04	2 x 4	1-05-00	1-02-00 8-01-04	243.75 153.67		
	1 2-ply	T101 Half Hip Girder	6 /12	19-05-08	4-01-04	2 x 4 2 x 6	1-03-08	1-02-00 4-01-04	182.72 116.00		
	1 2-ply	T101Z Half Hip Girder	6 /12	19-05-08	4-01-04	2 x 4 2 x 6	1-03-08	1-02-00 4-01-04	182.72 116.00		
	2	T102 Half Hip	6 /12	19-05-08	5-01-04	2 x 4	1-03-08	1-02-00 5-01-04	159.13 101.33		
	2	T103 Half Hip	6 /12	19-05-08	6-01-04	2 x 4	1-03-08	1-02-00 6-01-04	172.24 109.67		
	2	T104 Half Hip	6 /12	19-05-08	7-01-04	2 x 4	1-03-08	1-02-00 7-01-04	173.04 108.00		
	8	T105 Half Hip	6 /12	19-05-08	8-01-04	2 x 4	1-03-08	1-02-00 8-01-04	689.37 434.67		
	2	T106 Half Hip	6 /12	19-05-08	9-01-04	2 x 4	1-03-08	1-02-00 9-01-04	181.02 114.00		
	1	T107 Hip Girder	6 /12	9-06-00	2-04-12	2 x 4	1-03-08 1-03-08	1-02-00 1-02-00	37.9 25.50		
	2	T108 Hip	6 /12	9-06-00	4-10-12	2 x 4	1-03-08 1-03-08	2-08-00 2-08-00	99.25 67.00		
	1	T109 Hip	6 /12	9-06-00	3-10-12	2 x 4	1-03-08 1-03-08	2-08-00 2-08-00	45.71 31.67		
	1 2-ply	T110 Monopitch Girder	6 /12	5-10-08	4-01-04	2 x 4 2 x 6		1-02-00 4-01-04	58.39 37.67		
	2	PB101 Piggyback	6 /12	5-07-00	2-00-00	2 x 4		2-00-00	32.19 22.67		
	4	PB102 Piggyback	6 /12	5-07-00	2-09-08	2 x 4		2-09-08	58.98 40.00		

 TAMARACK ROOF TRUSSES INC. ALPHA LUMBER GROUP	DELIVERY SHIPLIST	
	Lumber Yard: TAMARACK LUMBER Builder: ROYAL PINE HOMES Project: CENTREFIELD Location: RICHMOND HILL Model: BLOCK 58 Lot #: Elevation: B / UNIT17BLK284	Job Track: 51012 PlanLog: 203549 Layout ID: 413123 Ref # Page: 2 of 2 Date: 07-08-2021 Designer: Andrew Conway Sales Rep: Mario DiCano

Roof Trusses

PROFILE	QTY PLY	MARK TYPE	PITCH	SPAN	HEIGHT	LUMBER	OVERHANG LEFT RIGHT	HEEL HEIGHT LEFT RIGHT	LBS. BFT.	BUNDLE # STACK #	LOAD BY REMARKS
	2	PB103G GABLE	6 /12	8-10-00	2-09-08	2 x 4		2-09-08	51.18 35.33		
	11	J01 Jack-Open	6 /12	5-10-08	4-01-04	2 x 4	1-03-08	1-02-00 4-01-04	184.74 117.33		
	5	J03 Jack-Open	4 /12	3-07-00	1-11-03	2 x 4	1-03-08	3-15 1-03-04	50.28 33.33		
	2	J11 Jack-Open	6 /12	1-10-15	2-01-08	2 x 4	1-03-08 6-09	1-02-00 2-01-08	15.69 10.67		
	2	J12 Jack-Open	6 /12	2-05-08	2-04-12	2 x 4	1-03-08	1-02-00 2-04-12	17.09 12.00		
	3	J13 Jack-Open	6 /12	1-10-15	2-01-08	2 x 4	1-03-08 1-01	1-02-00 2-01-08	21.97 14.00		
	1	J14 Jack-Open	6 /12	2-00-00	3-01-08	2 x 4	1-03-08 1-10-15	1-02-00 2-02-00	9.87 6.00		
	1	J15 Jack-Open	6 /12	1-10-15	2-01-08	2 x 4	1-03-08 3-11-09	1-02-00 2-01-08	11.74 7.33		
	1	J16 Jack-Open	6 /12	3-10-15	3-01-08	2 x 4	1-03-08 1-11-09	1-02-00 3-01-08	14.29 8.67		

TOTAL # TRUSS= 62 TOTAL BFT OF ALL TRUSSES= 1722.51 BFT. TOTAL WEIGHT OF ALL TRSSES 2693.27 LBS


HARDWARE

QTY	TYPE	MODEL	LENGTH
3	Hardware	LUS24	
1	Hardware	HGUS26-2	

TOTAL NUMBER OF ITEMS= 4

JOB NAME 412868	TRUSS NAME T10G	QUANTITY 4	PLY 1	JOB DESC. ROYAL PINE HOMES	DRWG NO.
Tamarack Roof Truss, Burlington					

Version 8.420 S Jan 21 2021 MiTek Industries, Inc. Thu Jul 1 10:22:39 2021 Page 1
ID:U6yi?rbeFFwxf_UFm_koDybSsJ-R8Izrke7RKetFAUC3nbSg0rZCUXPq?LTSBvRz0TvE



Scale = 1:44.7

TOTAL WEIGHT = 4 X 122 = 488 lb

LUMBER			
N. L. G. A. RULES	CHORDS	SIZE	LUMBER
AC - B	2x4	DRY	No.2
A - G	2x4	DRY	No.2
G - J	2x4	DRY	No.2
J - O	2x4	DRY	No.2
P - O	2x4	DRY	No.2
AC - T	2x4	DRY	No.2
T - P	2x4	DRY	No.2
ALL WEBS	2x3	DRY	No.2
ALL GABLE WEBS	2x3	DRY	No.2
DRY: SEASONED LUMBER			
GABLE STUDS SPACED AT 2-0-0 OC.			

PLATES (table is in inches)				
JT TYPE	PLATES	W	LEN	Y X
B TMV+p	MT20	3.0	4.0	
C, D, E, F, H, I, K, L, M, N				
C TMW+w	MT20	2.0	4.0	
G TS-t	MT20	3.0	6.0	
J TTW-m	MT20	4.0	4.0	
O TMVW-t	MT20	4.0	4.0	
P BMV1+p	MT20	3.0	4.0	
Q BMWV1-t	MT20	4.0	4.0	
R, S, U, V, W, X, Y, Z, AA, AB				
R BMW1+w	MT20	2.0	4.0	
T BS-t	MT20	3.0	6.0	
AC BMV1+p	MT20	3.0	4.0	

DIMENSIONS, SUPPORTS AND LOADINGS SPECIFIED BY FABRICATOR TO BE VERIFIED BY BUILDING DESIGNER

BEARINGS
THIS TRUSS DESIGNED FOR CONTINUOUS BEARINGS.
THIS TRUSS REQUIRES RIGID SHEATHING ON EXPOSED FACE.
BEARING MATERIAL TO BE SPF NO.2 OR BETTER AT JOINT(S)

BRACING
TOP CHORD TO BE SHEATHED OR MAX. PURLIN SPACING = 6.25 FT.
MAX. UNBRACED BOTTOM CHORD LENGTH = 6.25 FT OR RIGID CEILING DIRECTLY APPLIED.
ALL PITCH BREAKS AND PERIMETER CORNER JOINTS MUST BE Laterally RESTRAINED.

LOADING

TOTAL LOAD CASES: (4)

CHORDS				WEBS			
MEMB.	MAX. FACTORED FORCE (LBS)	VERT. LOAD (PLF)	MAX. FACTORED CS1 (LC)	MEMB.	MAX. FACTORED FORCE (LBS)	MAX. FACTORED CS1 (LC)	
FR-TO		FROM TO		FR-TO			
AC-B	-271 / 0	0.0	0.0 0.03 (1)	Q-N	-200 / 0	0.25 (1)	
A-B	0 / 30	-91.8	-91.8 0.14 (1)	R-M	-182 / 0	0.23 (1)	
B-C	-21 / 0	-91.8	-91.8 0.14 (1)	S-L	-190 / 0	0.24 (1)	
C-D	0 / 10	-91.8	-91.8 0.05 (1)	U-K	-149 / 0	0.19 (1)	
D-E	0 / 9	-91.8	-91.8 0.05 (1)	V-J	-95 / 0	0.12 (1)	
E-F	0 / 14	-91.8	-91.8 0.04 (1)	AB-C	-118 / 0	0.02 (1)	
F-G	0 / 16	-91.8	-91.8 0.04 (1)	AA-D	-196 / 0	0.04 (1)	
G-H	0 / 16	-91.8	-91.8 0.04 (1)	Z-E	-179 / 0	0.05 (1)	
H-I	0 / 19	-91.8	-91.8 0.05 (1)	Y-F	-183 / 0	0.07 (1)	
I-J	0 / 13	-91.8	-91.8 0.05 (1)	X-H	-180 / 0	0.11 (1)	
J-K	0 / 20	-91.8	-91.8 0.03 (1)	W-I	-200 / 0	0.18 (1)	
K-L	0 / 20	-91.8	-91.8 0.05 (1)	Q-O	-79 / 0	0.11 (1)	
L-M	0 / 20	-91.8	-91.8 0.05 (1)				
M-N	0 / 20	-91.8	-91.8 0.05 (1)				
N-O	0 / 20	-91.8	-91.8 0.05 (1)				
P-O	0 / 0	0.0	0.0 0.00 (1)				
AC-AB	0 / 0	-18.5	-18.5 0.02 (4)				
AB-AA	-4 / 0	-18.5	-18.5 0.02 (4)				
AA-Z	-9 / 0	-18.5	-18.5 0.01 (4)				
Z-Y	-12 / 0	-18.5	-18.5 0.01 (4)				
Y-X	-14 / 0	-18.5	-18.5 0.01 (4)				
X-W	-16 / 0	-18.5	-18.5 0.02 (4)				
W-V	-18 / 0	-18.5	-18.5 0.02 (4)				
V-U	-20 / 0	-18.5	-18.5 0.01 (4)				
U-T	-20 / 0	-18.5	-18.5 0.02 (4)				
T-S	-20 / 0	-18.5	-18.5 0.02 (4)				
S-R	-20 / 0	-18.5	-18.5 0.02 (4)				
R-Q	-20 / 0	-18.5	-18.5 0.02 (4)				
Q-P	0 / 0	-18.5	-18.5 0.02 (4)				

DESIGN CRITERIA

SPECIFIED LOADS:
TOP CH. LL = 25.6 PSF
DL = 6.0 PSF
BOT CH. LL = 0.0 PSF
DL = 7.4 PSF
TOTAL LOAD = 39.0 PSF

SPACING = 24.0 IN C/C

LOADING IN FLAT SECTION BASED ON A SLOPE OF 2.00/12 MINIMUM

THIS TRUSS IS DESIGNED FOR RESIDENTIAL OR SMALL BUILDING REQUIREMENTS OF PART 9, NBC 2015

THIS DESIGN COMPLIES WITH:
- PART 9 OF CBC 2018, ABC 2019
- PART 9 OF CBC 2012 (2019 AMENDMENT)
- CSA 086-14
- TPIC 2014

DESIGN ASSUMPTIONS
- OVERHANG NOT TO BE ALTERED OR CUT OFF.

(55 % OF 31.3 P.S.F. G.S.L. PLUS 8.4 P.S.F. RAIN LOAD) EQUALS 25.6 P.S.F. SPECIFIED ROOF LIVE LOAD

CSI: TC=0.14/1.00 (A-B:1), BC=0.02/1.00 (Q-R:4), WB=0.25/1.00 (N-Q:1), SS=0.09/1.00 (A-B:1)

DOL LUMBER=1.00 NAIL=1.00 LS BEND=1.10
COMP=1.10 SHEAR=1.10 TENS=1.10

COMPANION LIVE LOAD FACTOR = 1.00

TRUSS PLATE MANUFACTURER IS NOT RESPONSIBLE FOR QUALITY CONTROL IN THE TRUSS MANUFACTURING PLANT.

NAIL VALUES
PLATE GRIP(DRY) SHEAR SECTION (PSI) (PLI) (PLI)
MAX MIN MAX MIN MAX MIN
MT20 650 371 1747 788 1987 1873

PLATE PLACEMENT TOL = 0.250 inches

PLATE ROTATION TOL = 5.0 Deg.

JSI GRIP= 0.59 (J) (INPUT = 0.90)
JSI METAL= 0.08 (I) (INPUT = 1.00)



Structural component only
DWG# T-2121161

JOB NAME 412868	TRUSS NAME T11	QUANTITY 15	PLY 1	JOB DESC. ROYAL PINE HOMES	DRWG NO.
Tamarack Roof Truss, Burlington				TRUSS DESC.	


Version 8.420 S Jan 21 2021 MiTek Industries, Inc. Thu Jul 1 10:22:40 2021 Page 2
ID:U6yi?rbeFFwxf UFm koDybSsJ-vKsL24fCdmjtK3PdU7hDENfqLeB8A1V16wSCbz0TvD

TRUSS HAS BEEN CHECKED FOR UNBALANCED LOADING
AS PER NBCC 4.1.6.2.(8)

WIND LOAD APPLIED IS DERIVED FROM REFERENCE VELOCITY PRESSURE OF { 9.2} PSF AT {31-0-0} FT-IN-SX REFERENCE HEIGHT ABOVE GRADE AND USING EXTERNAL PEAK COEFFICIENTS, CpCg, BASED ON THE {MAIN WIND FORCE RESISTING SYSTEM}. INTERNAL WIND PRESSURE IS BASED ON DESIGN {CATEGORY 2}. BUILDING MAY BE LOCATED ON {OPEN TERRAIN}, AND TRUSS IS DESIGNED TO BE LOCATED AT LEAST {0-0} FT-IN-SX AWAY FROM EAVE. TRUSS UPLIFT IS BASED ON TOP AND BOTTOM CHORD DEAD LOADS OF 5.0 PSF AND 5.0 PSF RESPECTIVELY.



Structural component only
DWG# T-2121162 *ML*

Scale = 1:75.7

CONTINUED ON PAGE 2

JOB NAME 412868	TRUSS NAME T11G	QUANTITY 2	PLY 1	JOB DESC. ROYAL PINE HOMES	DRWG NO.
Tamarack Roof Truss, Burlington				TRUSS DESC.	

Version 8.420 S Jan 21 2021 MiTek Industries, Inc. Thu Jul 1 10:22:42 2021 Page 2
ID:U6yi?rbeFFwkxf UFm koDybSsJ-riz6Tmg?kF0R6eCnkV99lfT5g8V3cBMo9QPZGTz0TvB

LOADING
TOTAL LOAD CASES: (4)


CHORDS				WEBS			
MEMB.	MAX. FACTORED FORCE (LBS)	FACTORED VERT. LOAD (PLF)	LC1 MAX (LC)	MAX. UNBRAC LENGTH	MEMB.	MAX. FACTORED FORCE (LBS)	MAX. CSI (LC)
FR-TO		FROM	TO		FR-TO		
AI-AH	0 / 8	-18.5	-18.5 0.01 (4)	10.00			
AI-AG	0 / 12	-18.5	-18.5 0.01 (4)	10.00			
AG-AF	0 / 17	-18.5	-18.5 0.01 (4)	10.00			
AF-AE	0 / 25	-18.5	-18.5 0.01 (1)	10.00			
AE-AD	0 / 33	-18.5	-18.5 0.03 (1)	10.00			



Structural component only
DWG# T-2121163 *mm*

JOB NAME 413139	TRUSS NAME T11B	QUANTITY 8	PLY 1	JOB DESC. ROYAL PINE HOMES	DRWG NO.
Tamarack Roof Truss, Burlington					

Version 8.420 S Jan 21 2021 MiTek Industries, Inc. Thu Jul 1 16:03:38 2021 Page 1
ID:U6yir?rbeFFwxf_UFm_koDybSsJ-u6?JkNEKJLfzEH1G4189MPho24xcUhtk?zd?Epz0OvZ



LUMBER			
N. L. G. A. RULES	CHORDS	SIZE	LUMBER
A - D	2x6	DRY	No.2
D - F	2x6	DRY	No.2
F - H	2x6	DRY	No.2
H - J	2x6	DRY	No.2
J - M	2x6	DRY	No.2
U - A	2x6	DRY	No.2
U - R	2x6	DRY	No.2
R - P	2x6	DRY	No.2
P - L	2x6	DRY	No.2

REINFORCING MEMBERS			
HW2	2x8	DRY	No.2
ALL WEBS EXCEPT			
U - B	2x6	DRY	No.2

DRY: SEASONED LUMBER.

PLATES (table is in inches)

JT	TYPE	PLATES	W	LEN	Y	X
A	TMV+p	MT20	4.0	4.0		
B	TMVW-t	MT20	6.0	10.0		
C	TMVW-t	MT20	5.0	6.0		
D	TTW+p	MT20	5.0	8.0		
E	TMVW-t	MT20	4.0	6.0		
F	TS-t	MT20	5.0	6.0		
G	TMVW-t	MT20	4.0	6.0		
H	TTW+p	MT20	5.0	8.0		
I	TMVW-t	MT20	5.0	6.0		
J	TS-t	MT20	5.0	6.0		
K	TMVW-t	MT20	6.0	9.0		
L	TBMW-t	MT20	10.0	12.0	4.00	Edge
N, Q, T						
N	BMVW-t	MT20	4.0	6.0		
O	BMVW-t	MT20	5.0	8.0		
P	BS-t	MT20	5.0	6.0		
R	BS-t	MT20	5.0	6.0		
S	BMVW-t	MT20	5.0	8.0		
U	BMVW-t	MT20	8.0	12.0	5.50	Edge

Edge - INDICATES REFERENCE CORNER OF PLATE TOUCHES EDGE OF CHORD.

DIMENSIONS, SUPPORTS AND LOADINGS SPECIFIED BY FABRICATOR TO BE VERIFIED BY BUILDING DESIGNER

FACTORED		MAXIMUM FACTORED		INPUT		REQD	
GROSS REACTION		GROSS REACTION		BRG		BRG	
JT VERT	HORZ	DOWN	HORZ	UPLIFT	IN-SX	IN-SX	
U	3485	0	3487	-196	-1004	MECHANICAL	
L	3646	0	3690	0	-1065	5-8	5-8

A SUITABLE HANGER/MECHANICAL CONNECTION IS REQUIRED AT JOINT U. MINIMUM BEARING LENGTH AT JOINT U = 3-8.

PROVIDE ANCHORAGE AT BEARING JOINT U FOR 1004 LBS. FACTORED UPLIFT
PROVIDE ANCHORAGE AT BEARING JOINT L FOR 1065 LBS. FACTORED UPLIFT

PROVIDE FOR 196 LBS. FACTORED HORIZONTAL REACTION AT JOINT U

UNFACTORED REACTIONS

JT	COMBINED	SNOW	LIVE	PERM. LIVE	WIND	DEAD	SOIL
U	2582	1508 / 0	473 / 0	0 / 0	0 / -1007	604 / 0	0 / 0
L	2692	1628 / 0	473 / 0	0 / 0	59 / -1059	620 / 0	0 / 0

HORIZONTAL REACTIONS									
U	—	0 / 0	0 / 0	0 / 0	120 / -140	0 / 0	0 / 0	0 / 0	0 / 0

BEARING MATERIAL TO BE SPF NO.2 OR BETTER AT JOINT(S) L

BRACING

MAX. UNBRACED TOP CHORD LENGTH = 3.56 FT.
MAX. UNBRACED BOTTOM CHORD LENGTH = 6.25 FT. OR RIGID CEILING DIRECTLY APPLIED.

ALL PITCH BREAKS AND PERIMETER CORNER JOINTS MUST BE Laterally RESTRAINED.

1 LATERAL BRACE(S) AT 1/2 LENGTH OF E-S, G-O, B-U.

END VERTICAL(S) MUST BE SHEATHED OR HAVE BRACES AS INDICATED IN THE MAX. UNBRACED LENGTH COLUMN OF THE TABLE BELOW

LOADING

TOTAL LOAD CASES: (18)

CHORDS				WEBS			
MEMB.	MAX. FACTORED FORCE (LBS)	FACTORED VERT. LOAD (PLF)	MAX. FACTORED CSI (LC)	MEMB.	MAX. FACTORED FORCE (LBS)	MAX. FACTORED CSI (LC)	
FR-TO		FROM TO		FR-TO			
A-B	-15 / 90	-115.2 -115.2	0.18 (2)	6.25	B-T	-48 / 520	0.08 (3)
B-C	-5244 / 1613	-115.2 -115.2	0.29 (2)	3.66	T-C	-193 / 181	0.07 (10)
C-D	-4868 / 1551	-115.2 -115.2	0.27 (2)	3.78	C-S	-695 / 340	0.45 (2)
D-E	-4364 / 1456	-115.2 -115.2	0.36 (1)	3.87	S-D	-455 / 1675	0.36 (13)
E-F	-5141 / 1615	-115.2 -115.2	0.40 (1)	3.56	S-E	-1471 / 495	0.66 (3)
F-G	-5141 / 1615	-115.2 -115.2	0.40 (1)	3.56	E-Q	-142 / 477	0.14 (9)
G-H	-4431 / 1478	-115.2 -115.2	0.36 (1)	3.85	Q-G	-185 / 424	0.18 (10)
H-I	-4943 / 1574	-115.2 -115.2	0.29 (3)	3.75	G-O	-1409 / 476	0.63 (2)
I-J	-5473 / 1687	-115.2 -115.2	0.32 (3)	3.56	O-H	-464 / 1703	0.37 (14)
J-K	-5473 / 1687	-115.2 -115.2	0.32 (3)	3.56	O-I	-813 / 384	0.53 (3)
K-W	-2810 / 889	-115.2 -115.2	0.15 (3)	4.88	I-N	-117 / 259	0.04 (9)
W-L	-4259 / 1142	-115.2 -115.2	0.18 (3)	4.08	N-K	-31 / 366	0.06 (2)
L-M	0 / 1	-115.2 -115.2	0.09 (3)	10.00	U-B	-5485 / 1539	0.54 (1)
U-A	-267 / 147	0.0	0.02 (13)	7.81	K-V	-2931 / 816	0.49 (1)
					V-W	-377 / 1904	0.00 (1)
U-T	-1416 / 4506	-39.5 -39.5	0.66 (1)	6.25			
T-S	-1357 / 4690	-39.5 -39.5	0.69 (1)	6.25			
S-R	-1339 / 5063	-39.5 -39.5	0.74 (1)	6.25			
R-Q	-1339 / 5063	-39.5 -39.5	0.74 (1)	6.25			
Q-P	-1292 / 5085	-39.5 -39.5	0.75 (1)	6.25			
P-O	-1292 / 5085	-39.5 -39.5	0.75 (1)	6.25			
O-N	-1220 / 4842	-39.5 -39.5	0.71 (1)	6.25			
N-V	-1311 / 4828	-39.5 -39.5	0.68 (1)	6.25			
V-L	-660 / 2510	-39.5 -39.5	0.30 (3)	6.25			

DESIGN CRITERIA

SPECIFIED LOADS:

TOP CH.	LL	=	33.4	PSF
	DL	=	6.0	PSF
BOT CH.	LL	=	10.5	PSF
	DL	=	7.4	PSF
TOTAL LOAD	=	57.3	PSF	

SPACING = 24.0 IN/C

LOADING IN FLAT SECTION BASED ON A SLOPE OF 2.00/12

THIS TRUSS IS DESIGNED FOR COMMERCIAL OR INDUSTRIAL BUILDING REQUIREMENTS OF PART 4, NBCC 2015

THIS DESIGN COMPLIES WITH:

- PART 4 OF BCBC 2018, ABC 2019
- PART 4 OF OBC 2012 (2019 AMENDMENT)
- CSA 086-14
- TPIC 2014

DESIGN ASSUMPTIONS

- SLOPE REDUCTION FACTOR NOT USED
- PERCENTAGE OF GROUND SNOW LOAD IS USER-DEFINED.

(80 % OF 31.3 P.S.F. G.S.L. PLUS 8.4 P.S.F. RAIN LOAD) TIMES IMPORTANCE FACTOR. EQUALS 33.4 P.S.F. SPECIFIED ROOF LIVE LOAD

ALLOWABLE DEFL. (LL) = L/360 (1.50")
CALCULATED VERT. DEFL. (LL) = L/999 (0.24")
ALLOWABLE DEFL. (TL) = L/180 (3.00")
CALCULATED VERT. DEFL. (TL) = L/999 (0.34")

CSI: TC=0.40/1.00 (E-G-1), BC=0.75/1.00 (O-Q-1), WB=0.66/1.00 (E-S-3), SS=0.24/1.00 (D-E-3)

DOL LUMBER=1.00 NAIL=1.00 LS BEND=1.10 COMP=1.10 SHEAR=1.10 TENS=1.10

SNOW LOAD IMPORTANCE FACTOR = 1.00
WIND LOAD IMPORTANCE FACTOR = 1.00
LIVE LOAD IMPORTANCE FACTOR = 1.00
COMPANION LIVE LOAD FACTOR = 1.00

AUTOSOLVE RIGHT HEEL ONLY

TRUSS PLATE MANUFACTURER IS NOT RESPONSIBLE FOR QUALITY CONTROL IN THE TRUSS MANUFACTURING PLANT.

NAIL VALUES

PLATE	GRIP (DRY)	SHEAR	SECTION
(PSI)	(PLI)	(PLI)	
MT20	650	371	1747 788 1987 1873

PLATE PLACEMENT TOL. = 0.250 inches

PLATE ROTATION TOL. = 5.0 Deg.

JSI GRIP = 0.87 (B) (INPUT = 0.90)
JSI METAL = 0.93 (R) (INPUT = 1.00)

JOB NAME	TRUSS NAME	QUANTITY	PLY	JOB DESC.	ROYAL PINE HOMES	DRWG NO.
413139	T11B	8	1	TRUSS DESC.		

Tamarack Roof Truss, Burlington

TRUSS HAS BEEN CHECKED FOR UNBALANCED LOADING
AS PER NBCC 4.1.6.2.(8)


WIND LOAD APPLIED IS DERIVED FROM REFERENCE VELOCITY PRESSURE OF { 9.2} PSF AT
{30-0-0} FT-IN-SX REFERENCE HEIGHT ABOVE GRADE AND USING EXTERNAL PEAK
COEFFICIENTS, CpCg, BASED ON THE (MAIN WIND FORCE RESISTING SYSTEM). INTERNAL
WIND PRESSURE IS BASED ON DESIGN (CATEGORY 2). BUILDING MAY BE LOCATED ON
(OPEN TERRAIN), AND TRUSS IS DESIGNED TO BE LOCATED AT LEAST (0-0) FT-IN-SX AWAY
FROM EAVE. TRUSS UPLIFT IS BASED ON TOP AND BOTTOM CHORD DEAD LOADS OF 5.0 PSF
AND 5.0 PSF RESPECTIVELY.



Structural component only
DWG# T-2121238 *mm*

JOB NAME 412865	TRUSS NAME T11GB	QUANTITY 2	PLY 1	JOB DESC. ROYAL PINE HOMES	DRWG NO.
Tamarack Roof Truss, Burlington				TRUSS DESC.	

Version 8.420 S Jan 21 2021 MITek Industries, Inc. Thu Jul 1 12:26:26 2021 Page 1
ID:hEKUVWZApjnyW9leD6V_jMya4z_-TzZhcHWPNGM3nYmce4L6BDxp6plE3qzXISnPrAz0S5B



TOTAL WEIGHT = 2 X 238 = 475 lb [M]

LUMBER				DESCR.	
N. L. G. A. RULES	SIZE	LUMBER			
CHORDS					
AR - B	2x6	DRY	No.2	SPF	
A - F	2x6	DRY	No.2	SPF	
F - J	2x6	DRY	No.2	SPF	
J - O	2x6	DRY	No.2	SPF	
O - T	2x6	DRY	No.2	SPF	
T - W	2x6	DRY	No.2	SPF	
X - W	2x4	DRY	No.2	SPF	
AR- AK	2x6	DRY	No.2	SPF	
AK- AF	2x6	DRY	No.2	SPF	
AF- X	2x6	DRY	No.2	SPF	
ALL WEBS	2x3	DRY	No.2	SPF	
ALL GABLE WEBS	2x3	DRY	No.2	SPF	
DRY: SEASONED LUMBER.					

GABLE STUDS SPACED AT 2-0-0 OC.

PLATES (table is in inches)					
JT TYPE	PLATES	W	LEN	Y	X
B, AE, AF, AR					
C, D, E, G, H, I, U, V					
C	TMW+w	MT20	4.0	4.0	
F	TS-t	MT20	5.0	6.0	Edge 2.75
J	TTW+m	MT20	5.0	6.0	
K, L, M, N, P, Q, R, S					
K	TMW+w	MT20	3.0	6.0	
O	TS-t	MT20	5.0	6.0	
T	TTW+m	MT20	5.0	6.0	
W	TMVW+p	MT20	4.0	6.0	
X	BMV1+p	MT20	3.0	6.0	
Y	BMVW1-t	MT20	5.0	6.0	
Z, AA, AB, AC, AD, AG, AH, AI, AJ, AL, AM, AN, AO, AP, AQ					
Z	BMV1+w	MT20	3.0	6.0	
AE	BBW1+h	MT20	5.0	8.0	
AK	BSW1+h	MT20	5.0	8.0	4.50 2.50
AR	TMBMV1+p	MT20	3.0	8.0	2.75 0.25

Edge - INDICATES REFERENCE CORNER OF PLATE TOUCHES EDGE OF CHORD.

DIMENSIONS, SUPPORTS AND LOADINGS SPECIFIED BY FABRICATOR TO BE VERIFIED BY BUILDING DESIGNER

BEARINGS

THIS TRUSS DESIGNED FOR CONTINUOUS BEARINGS.

THIS TRUSS REQUIRES RIGID SHEATHING ON EXPOSED FACE.

BEARING MATERIAL TO BE SPF NO.2 OR BETTER AT JOINT(S)

BRACING

TOP CHORD TO BE SHEATHED OR MAX. PURLIN SPACING = 6.25 FT.

MAX. UNBRACED BOTTOM CHORD LENGTH = 6.25 FT OR RIGID CEILING DIRECTLY APPLIED.

ALL PITCH BREAKS AND PERIMETER CORNER JOINTS MUST BE Laterally RESTRAINED.

LOADING

TOTAL LOAD CASES: (7)

CHORDS		FACTORED		WEBS		FACTORED	
MEMB.	MAX. FORCE (LBS)	VERT. LOAD (PLF)	MAX. CSI (LC)	MEMB.	MAX. FORCE (LBS)	MAX. CSI (LC)	
FR-TO		FROM TO		FR-TO			
AR-B	-255 / 0	0.0	0.0 0.02 (1)	AA-T	-170 / 0	0.19 (1)	
A-B	0 / 29	-91.8	-91.8 0.06 (1)	AB-S	-206 / 0	0.23 (1)	
B-C	-18 / 0	-91.8	-91.8 0.06 (1)	AC-R	-183 / 0	0.21 (1)	
C-D	0 / 14	-91.8	-91.8 0.02 (1)	AD-Q	-183 / 0	0.21 (1)	
D-E	0 / 16	-91.8	-91.8 0.02 (1)	AE-P	-184 / 0	0.21 (1)	
E-F	0 / 23	-91.8	-91.8 0.02 (1)	AG-N	-183 / 0	0.21 (1)	
F-G	0 / 23	-91.8	-91.8 0.02 (1)	AH-M	-184 / 0	0.21 (1)	
G-H	0 / 27	-91.8	-91.8 0.02 (1)	AI-L	-186 / 0	0.21 (1)	
H-I	0 / 31	-91.8	-91.8 0.02 (1)	AJ-K	-178 / 0	0.20 (1)	
I-J	0 / 27	-91.8	-91.8 0.02 (1)	Z-U	-206 / 0	0.16 (1)	
J-K	0 / 33	-91.8	-91.8 0.02 (1)	Y-V	-173 / 0	0.09 (1)	
K-L	0 / 33	-91.8	-91.8 0.02 (1)	AK-J	-146 / 0	0.16 (1)	
L-M	0 / 33	-91.8	-91.8 0.02 (1)	AQ-C	-122 / 0	0.02 (1)	
M-N	0 / 33	-91.8	-91.8 0.02 (1)	AP-D	-193 / 0	0.03 (1)	
N-O	0 / 33	-91.8	-91.8 0.02 (1)	AO-E	-179 / 0	0.04 (1)	
O-P	0 / 33	-91.8	-91.8 0.02 (1)	AN-G	-181 / 0	0.06 (1)	
P-Q	0 / 33	-91.8	-91.8 0.02 (1)	AM-H	-182 / 0	0.09 (1)	
Q-R	0 / 33	-91.8	-91.8 0.03 (1)	AL-I	-198 / 0	0.15 (1)	
R-S	0 / 33	-91.8	-91.8 0.03 (1)	Y-W	-68 / 0	0.03 (1)	
S-T	0 / 33	-91.8	-91.8 0.03 (1)				
T-U	0 / 26	-91.8	-91.8 0.03 (1)				
U-V	0 / 34	-91.8	-91.8 0.03 (1)				
V-W	0 / 32	-91.8	-91.8 0.02 (1)				
X-W	0 / 9	0.0	0.0 0.00 (1)				

AR-AQ	0 / 0	-18.5	-18.5 0.01 (4)	10.00
AQ-AP	-8 / 0	-18.5	-18.5 0.01 (4)	10.00
AP-AO	-15 / 0	-18.5	-18.5 0.01 (4)	6.25
AO-AN	-20 / 0	-18.5	-18.5 0.01 (4)	6.25
AN-AM	-24 / 0	-18.5	-18.5 0.01 (4)	6.25
AM-AL	-28 / 0	-18.5	-18.5 0.01 (4)	6.25
AL-AK	-31 / 0	-18.5	-18.5 0.01 (4)	6.25
AK-AJ	-33 / 0	-18.5	-18.5 0.01 (4)	6.25
AJ-AI	-33 / 0	-18.5	-18.5 0.01 (4)	6.25
AI-AH	-33 / 0	-18.5	-18.5 0.01 (4)	6.25
AH-AG	-33 / 0	-18.5	-18.5 0.01 (4)	6.25
AG-AF	-33 / 0	-18.5	-18.5 0.01 (4)	6.25
AF-AE	-33 / 0	-18.5	-18.5 0.01 (4)	6.25
AE-AD	-33 / 0	-18.5	-18.5 0.01 (4)	6.25
AD-AC	-33 / 0	-18.5	-18.5 0.01 (4)	6.25
AC-AB	-33 / 0	-18.5	-18.5 0.01 (4)	6.25
AB-AA	-33 / 0	-18.5	-18.5 0.01 (4)	6.25
AA-Z	-30 / 0	-18.5	-18.5 0.01 (4)	6.25
Z-Y	-27 / 0	-18.5	-18.5 0.01 (4)	6.25
Y-X	0 / 0	-18.5	-18.5 0.01 (4)	10.00

DESIGN CRITERIA

SPECIFIED LOADS:

TOP CH.	LL	= 25.6	PSF
	DL	= 6.0	PSF
BOT CH.	LL	= 0.0	PSF
	DL	= 7.4	PSF
TOTAL LOAD	=	39.0	PSF

SPACING = 24.0 IN/C

LOADING IN FLAT SECTION BASED ON A SLOPE OF 2.00/12 MINIMUM

THIS TRUSS IS DESIGNED FOR RESIDENTIAL OR SMALL BUILDING REQUIREMENTS OF PART 9, NBC 2015

THIS DESIGN COMPLIES WITH:

- PART 9 OF BCBC 2018, ABC 2019
- PART 9 OF OBC 2012 (2019 AMENDMENT)
- CSA 086-14
- TPIC 2014

DESIGN ASSUMPTIONS

- OVERHANG NOT TO BE ALTERED OR CUT OFF.

(55 % OF 31.3 P.S.F. G.S.L. PLUS 8.4 P.S.F. RAIN LOAD) EQUALS 25.6 P.S.F. SPECIFIED ROOF LIVE LOAD

CSI: TC=0.06/1.00 (A-B:1), BC=0.01/1.00 (AK-AL:4), WB=0.23/1.00 (S-AB:1), SS=0.07/1.00 (A-B:1)

DOL LUMBER=1.00 NAIL=1.00 LS BEND=1.10 COMP=1.10 SHEAR=1.10 TENS=1.10

COMPANION LIVE LOAD FACTOR = 1.00

AUTOSOLVE RIGHT HEEL ONLY

TRUSS PLATE MANUFACTURER IS NOT RESPONSIBLE FOR QUALITY CONTROL IN THE TRUSS MANUFACTURING PLANT.

NAIL VALUES

PLATE GRIP(DRY)	SHEAR	SECTION
(PSI)	(PLI)	(PLI)
MAX MIN	MAX MIN	MAX MIN
MT20	650 371 1747 788 1987 1873	

PLATE PLACEMENT TOL = 0.250 inches

PLATE ROTATION TOL = 5.0 Deg.

JSI GRIP = 0.38 (Y) (INPUT = 0.90)
JSI METAL = 0.07 (AR) (INPUT = 1.00)




Structural component only
DWG# T-2121205

JOB NAME	TRUSS NAME	QUANTITY	PLY	JOB DESC.	ROYAL PINE HOMES	DRWG NO.
413139	T11A	8	1	TRUSS DESC.		

Tamarack Roof Truss, Burlington

Version 8.420 S Jan 21 2021 MITek Industries, Inc. Thu Jul 1 12:42:59 2021 Page 1
ID:U6yi?rbeFFwxf_Ufm_koDybSsJ-u?340qXhWNTAP9ATJ7tZxdaPb562Dr5leRqRB6z0Rrg



LUMBER	N. L. G. A. RULES	CHORDS	SIZE	LUMBER	DESCR.
A - F	2x6 DRY	No.2	SPF		
F - G	2x6 DRY	No.2	SPF		
G - I	2x6 DRY	No.2	SPF		
I - K	2x6 DRY	No.2	SPF		
K - L	2x6 DRY	No.2	SPF		
M - L	2x6 DRY	No.2	SPF		
B - Q	2x6 DRY	No.2	SPF		
Q - O	2x6 DRY	No.2	SPF		
O - M	2x6 DRY	No.2	SPF		

REINFORCING MEMBERS	SIZE	LUMBER	DESCR.
HW1	2x6 DRY	No.2	SPF
ALL WEBS EXCEPT	2x4 DRY	No.2	SPF

DRY: SEASONED LUMBER.

PLATES (table is in inches)	JT TYPE	PLATES	W	LEN	Y	X
B	TMBMR1-I	MT20	8.0	9.0	5.00	
B	RT-t	MT20	4.0	6.0		
B	RT-t	MT20	4.0	6.0		
D	TMW-w	MT20	3.0	6.0		
E, H, J						
F	TMWW-t	MT20	5.0	6.0		
F	TS-t	MT20	5.0	6.0		
G	TTW+m	MT20	5.0	6.0		
I	TS-t	MT20	5.0	6.0		
K	TTW+m	MT20	5.0	6.0		
L	TMWV-p	MT20	4.0	6.0	1.00	3.75
M	BMV1+p	MT20	3.0	6.0		
N	BMVWV-t	MT20	6.0	9.0		
O	BS-t	MT20	5.0	6.0		
P	BMVWV-t	MT20	5.0	6.0		
Q	BS-t	MT20	5.0	6.0		
R	BMVWVW-t	MT20	5.0	8.0		
S	BMVWV-t	MT20	5.0	6.0		

DIMENSIONS, SUPPORTS AND LOADINGS SPECIFIED BY FABRICATOR TO BE VERIFIED BY BUILDING DESIGNER

BEARINGS	FACTORED GROSS REACTION	MAXIMUM FACTORED GROSS REACTION	INPUT	REQD
JT	VERT	HORZ	DOWN	HORZ
B	2237	0	2237	0
M	2109	0	2109	0

A SUITABLE HANGER/MECHANICAL CONNECTION IS REQUIRED AT JOINT M. MINIMUM BEARING LENGTH AT JOINT M = 3-8.

UNFACTORED REACTIONS

1ST LCASE	MAX/MIN. COMPONENT REACTIONS	JT	COMBINED	SNOW	LIVE	PERM. LIVE	WIND	DEAD	SOIL
B	1579	1050 / 0	0 / 0	0 / 0	0 / 0	0 / 0	0 / 0	529 / 0	0 / 0
M	1491	979 / 0	0 / 0	0 / 0	0 / 0	0 / 0	0 / 0	513 / 0	0 / 0

BEARING MATERIAL TO BE SPF NO.2 OR BETTER AT JOINT(S) B

BRACING

TOP CHORD TO BE SHEATHED OR MAX. PURLIN SPACING = 4.60 FT.
MAX. UNBRACED BOTTOM CHORD LENGTH = 10.00 FT OR RIGID CEILING DIRECTLY APPLIED.

ALL PITCH BREAKS AND PERIMETER CORNER JOINTS MUST BE Laterally RESTRAINED.

1 LATERAL BRACE(S) AT 1/2 LENGTH OF H-R, J-N.

END VERTICAL(S) MUST BE SHEATHED OR HAVE BRACES AS INDICATED IN THE MAX. UNBRACED LENGTH COLUMN OF THE TABLE BELOW

LOADING

TOTAL LOAD CASES: (4)

CHORDS	MAX. FACTORED FORCE (LBS)	FACTORED VERT. LOAD (PLF)	MAX. FACTORED VERT. LOAD (LBS)	MAX. FACTORED VERT. LOAD (LBS)	MAX. FACTORED VERT. LOAD (LBS)	MAX. FACTORED VERT. LOAD (LBS)	MAX. FACTORED VERT. LOAD (LBS)	MAX. FACTORED VERT. LOAD (LBS)	MAX. FACTORED VERT. LOAD (LBS)
FR-TO									
A-B	0 / 0	-91.8	-91.8	0.06 (1)	10.00	D-S	0 / 69	0.02 (4)	
B-U	-2908 / 0	-91.8	-91.8	0.05 (1)	4.91	S-E	0 / 65	0.02 (4)	
U-C	-2227 / 0	-91.8	-91.8	0.40 (1)	5.00	E-R	-550 / 0	0.36 (1)	
C-D	-2227 / 0	-91.8	-91.8	0.40 (1)	5.00	R-G	0 / 854	0.14 (1)	
D-E	-3092 / 0	-91.8	-91.8	0.23 (1)	4.60	R-H	-332 / 0	0.15 (1)	
E-F	-2766 / 0	-91.8	-91.8	0.17 (1)	4.89	H-P	-338 / 0	0.33 (1)	
F-G	-2766 / 0	-91.8	-91.8	0.17 (1)	4.89	P-J	0 / 506	0.08 (1)	
G-H	-2465 / 0	-91.8	-91.8	0.20 (1)	5.08	J-N	-1328 / 0	0.80 (1)	
H-I	-2543 / 0	-91.8	-91.8	0.19 (1)	5.04	N-K	0 / 252	0.04 (4)	
I-J	-2543 / 0	-91.8	-91.8	0.19 (1)	5.04	N-L	0 / 1836	0.30 (1)	
J-K	-1563 / 0	-91.8	-91.8	0.18 (1)	6.07	T-U	0 / 2337	0.00 (1)	
K-L	-1744 / 0	-91.8	-91.8	0.28 (1)	5.89	T-C	-2249 / 0	0.17 (1)	
M-L	-2080 / 0	0.0	0.0	0.44 (1)	7.06				

B-T	0 / 1311	-18.5	-18.5	0.32 (1)	10.00
T-S	0 / 2770	-18.5	-18.5	0.49 (1)	10.00
S-R	0 / 2810	-18.5	-18.5	0.41 (1)	10.00
R-Q	0 / 2684	-18.5	-18.5	0.39 (1)	10.00
Q-P	0 / 2684	-18.5	-18.5	0.39 (1)	10.00
P-O	0 / 2361	-18.5	-18.5	0.35 (1)	10.00
O-N	0 / 2361	-18.5	-18.5	0.35 (1)	10.00
N-M	0 / 0	-18.5	-18.5	0.12 (4)	10.00

DESIGN CRITERIA

SPECIFIED LOADS:

TOP CH. LL = 25.6 PSF
DL = 6.0 PSF
BOT CH. LL = 0.0 PSF
DL = 7.4 PSF
TOTAL LOAD = 39.0 PSF

SPACING = 24.0 IN. C/C

LOADING IN FLAT SECTION BASED ON A SLOPE OF 2.00/12 MINIMUM

THIS TRUSS IS DESIGNED FOR RESIDENTIAL OR SMALL BUILDING REQUIREMENTS OF PART 9, NBC 2015

THIS DESIGN COMPLIES WITH:

- PART 9 OF CBC 2018, ABC 2019
- PART 9 OF OBC 2012 (2019 AMENDMENT)
- CSA 086-14
- TPIC 2014

(55 % OF 31.3 P.S.F. G.S.L. PLUS 8.4 P.S.F. RAIN LOAD) EQUALS 25.6 P.S.F. SPECIFIED ROOF LIVE LOAD

ALLOWABLE DEFL.(LL) = L/360 (1.27")
CALCULATED VERT. DEFL.(LL) = L/999 (0.11")
ALLOWABLE DEFL.(TL) = L/360 (1.27")
CALCULATED VERT. DEFL.(TL) = L/999 (0.21")

CSI: TC=0.44/1.00 (L-M:1), BC=0.49/1.00 (S-T:1), WB=0.60/1.00 (J-N:1), SSI=0.31/1.00 (B-T:1)

DOL LUMBER=1.00 NAIL=1.00 LS BEND=1.10 COMP=1.10 SHEAR=1.10 TENS=1.10

COMPANION LIVE LOAD FACTOR = 1.00

AUTOSOLVE LEFT HEEL ONLY

TRUSS PLATE MANUFACTURER IS NOT RESPONSIBLE FOR QUALITY CONTROL IN THE TRUSS MANUFACTURING PLANT


NAIL VALUES

PLATE GRIP(DRY)	SHEAR (PSI)	SECTION (PLI)	MAX MIN	MAX MIN	MAX MIN
MT20	650	371	1747	788	1987 1873

PLATE PLACEMENT TOL = 0.250 inches

PLATE ROTATION TOL = 5.0 Deg.


JSI GRIP= 0.82 (L) (INPUT = 0.90)
JSI METAL= 0.78 (B) (INPUT = 1.00)



Structural component only
DWG# T-2121237

JOB NAME 412865	TRUSS NAME T101	QUANTITY 2	PLY 2	JOB DESC. ROYAL PINE HOMES	DRWG NO.
Tamarack Roof Truss, Burlington					

Version 8.420 S Jan 21 2021 MiTek Industries, Inc. Thu Jul 1 12:26:27 2021 Page 1
ID:hEKUVWZApjnyW9leD6V_jMya4z_x973pdXR8aUwOikPcosLkRUwoCowoG5hX6XyNcz0S5A



TOTAL WEIGHT = 4 X 91 = 365 lb

LUMBER	N. L. G. A. RULES	CHORDS	SIZE	LUMBER	DESCR.
A - D	2x4	DRY	No.2	SPF	
D - G	2x4	DRY	No.2	SPF	
H - J	2x4	DRY	No.2	SPF	
M - B	2x6	DRY	No.2	SPF	
M - J	2x6	DRY	No.2	SPF	
J - H	2x6	DRY	No.2	SPF	

ALL WEBS 2x3 DRY No.2 SPF

DRY: SEASONED LUMBER.

DESIGN CONSISTS OF 2 TRUSSES BUILT SEPARATELY THEN FASTENED TOGETHER AS FOLLOWS:

CHORDS #ROWS	SURFACE SPACING (IN)	LOAD (PLF)
TOP CHORDS : (0.122"x3") SPIRAL NAILS		
A - D 1	12	SIDE(61.0)
D - G 1	12	SIDE(61.0)
G - H 1	12	TOP
M - B 2	12	TOP
BOTTOM CHORDS : (0.122"x3") SPIRAL NAILS		
M - J 2	12	SIDE(183.1)
J - H 2	12	SIDE(0.0)
WEBS : (0.122"x3") SPIRAL NAILS		
2x3 1	6	

NAILS TO BE DRIVEN FROM ONE SIDE ONLY.

GIRDER NAILING ASSUMES NAILED HANGERS ARE FASTENED WITH MIN. 3-0 INCH NAILS.

TOP - COMPONENTS ARE LOADED FROM THE TOP AND MUST BE PLACED ON TOP EDGE OF ALL PLIES FOR THE LOAD TO BE TRANSFERRED TO EACH PLY.

SIDE - PLF SHOWN IS THE EQUIVALENT UDL APPLIED TO ONE SIDE THAT THE CORRESPONDING NAILING PATTERN SHALL BE CAPABLE OF TRANSFERRING. REMAINING PLF MUST BE APPLIED ON THE OPPOSITE SIDE OR ON THE TOP.

DIMENSIONS, SUPPORTS AND LOADINGS SPECIFIED BY FABRICATOR TO BE VERIFIED BY BUILDING DESIGNER

JT	FACTORED GROSS REACTION		MAXIMUM FACTORED GROSS REACTION		INPUT BRG	REQRD BRG
	VERT	HORZ	DOWN	UPLIFT		
H	1774	0	1774	0	1-8	1-8
M	1855	0	1855	0	5-8	5-8

UNFACTORED REACTIONS

1ST LCASE	COMBINED	SNOW	LIVE	PERM.LIVE	WIND	DEAD	SOIL
JT	1255	820 / 0	0 / 0	0 / 0	0 / 0	435 / 0	0 / 0
M	1311	867 / 0	0 / 0	0 / 0	0 / 0	444 / 0	0 / 0

BEARING MATERIAL TO BE SPF NO.2 OR BETTER AT JOINT(S) H, M

BRACING

TOP CHORD TO BE SHEATHED OR MAX. PURLIN SPACING = 5.42 FT. MAX. UNBRACED BOTTOM CHORD LENGTH = 10.00 FT OR RIGID CEILING DIRECTLY APPLIED.

ALL PITCH BREAKS AND PERIMETER CORNER JOINTS MUST BE Laterally RESTRAINED.

LOADING

TOTAL LOAD CASES: (4)

CHORDS				WEBS				
MEMB.	MAX. FACTORED FORCE (LBS)	FACTORED VERT. LOAD (PLF)	LC1 MAX CSI (LC)	MAX. UNBRAC LENGTH	MEMB.	MAX. FACTORED FORCE (LBS)	MAX FACTORED CSI (LC)	
FR-TO		FROM	TO		FR-TO			
A-B	0 / 28	-91.8	-91.8	0.07 (1)	10.00	C-L	0 / 214	0.03 (1)
B-C	0 / 9	-91.8	-91.8	0.05 (1)	10.00	L-D	0 / 151	0.03 (4)
C-D	-2488 / 0	-91.8	-91.8	0.07 (1)	5.69	M-C	-2546 / 0	0.30 (1)
D-N	-2488 / 0	-91.8	-91.8	0.23 (1)	5.46	I-G	0 / 2332	0.29 (1)
N-O	-2488 / 0	-91.8	-91.8	0.23 (1)	5.46	D-K	0 / 375	0.05 (1)
O-E	-2488 / 0	-91.8	-91.8	0.23 (1)	5.46	I-F	-1302 / 0	0.17 (1)
E-P	-2488 / 0	-91.8	-91.8	0.26 (1)	5.42	K-E	-702 / 0	0.09 (1)
P-Q	-2488 / 0	-91.8	-91.8	0.26 (1)	5.42	K-F	0 / 880	0.11 (1)
Q-F	-2488 / 0	-91.8	-91.8	0.26 (1)	5.42			
F-R	-1814 / 0	-91.8	-91.8	0.25 (1)	6.13			
R-S	-1814 / 0	-91.8	-91.8	0.25 (1)	6.13			
S-G	-1814 / 0	-91.8	-91.8	0.25 (1)	6.13			
H-G	-1712 / 0	0.0	0.0	0.21 (1)	7.81			
M-B	-239 / 0	0.0	0.0	0.01 (1)	7.81			
M-T	0 / 2025	-18.5	-18.5	0.17 (1)	10.00			
T-U	0 / 2025	-18.5	-18.5	0.17 (1)	10.00			
U-L	0 / 2025	-18.5	-18.5	0.17 (1)	10.00			
L-V	0 / 2198	-18.5	-18.5	0.17 (1)	10.00			
V-W	0 / 2198	-18.5	-18.5	0.17 (1)	10.00			
W-K	0 / 2198	-18.5	-18.5	0.17 (1)	10.00			
K-J	0 / 1814	-18.5	-18.5	0.15 (1)	10.00			
J-X	0 / 1814	-18.5	-18.5	0.15 (1)	10.00			
X-I	0 / 1814	-18.5	-18.5	0.15 (1)	10.00			
I-Y	0 / 0	-18.5	-18.5	0.04 (4)	10.00			
Y-Z	0 / 0	-18.5	-18.5	0.04 (4)	10.00			
Z-H	0 / 0	-18.5	-18.5	0.04 (4)	10.00			

SPECIFIED CONCENTRATED LOADS (LBS)

JT	LOC.	LC1	MAX.	FACE	DIR.	TYPE	HEEL	CONN.
D	5-10-8	-317	-317	---	BACK	VERT	---	C1
J	11-11-4	-21	-21	---	BACK	VERT	---	C1
L	5-11-4	-21	-21	---	BACK	VERT	---	C1
N	7-11-4	-76	-76	---	BACK	VERT	---	C1
O	9-11-4	-76	-76	---	BACK	VERT	---	C1
P	11-11-4	-76	-76	---	BACK	VERT	---	C1
Q	13-11-4	-76	-76	---	BACK	VERT	---	C1
R	15-11-4	-76	-76	---	BACK	VERT	---	C1
S	17-11-4	-76	-76	---	BACK	VERT	---	C1
T	2-0-12	-21	-21	---	BACK	VERT	---	C1
U	4-0-12	-21	-21	---	BACK	VERT	---	C1
V	7-11-4	-21	-21	---	BACK	VERT	---	C1
W	9-11-4	-21	-21	---	BACK	VERT	---	C1

DESIGN CRITERIA

SPECIFIED LOADS:

TOP CH. LL = 25.6 PSF
DL = 6.0 PSF
BOT CH. LL = 0.0 PSF
DL = 7.4 PSF
TOTAL LOAD = 39.0 PSF

SPACING = 24.0 IN. C/C

LOADING IN FLAT SECTION BASED ON A SLOPE OF 2.00/12 MINIMUM

THIS TRUSS IS DESIGNED FOR RESIDENTIAL OR SMALL BUILDING REQUIREMENTS OF PART 9, NBCC 2015

THIS DESIGN COMPLIES WITH:

- PART 9 OF BCBC 2018, ABC 2019
- PART 9 OF OBC 2012 (2019 AMENDMENT)
- CSA 086-14
- TPIC 2014

(55 % OF 31.3 P.S.F. G.S.L. PLUS 8.4 P.S.F. RAIN LOAD) EQUALS 25.6 P.S.F. SPECIFIED ROOF LIVE LOAD

ALLOWABLE DEFL.(LL)= L/360 (0.65")
CALCULATED VERT. DEFL.(LL) = L/999 (0.04")
ALLOWABLE DEFL.(TL)= L/360 (0.65")
CALCULATED VERT. DEFL.(TL) = L/999 (0.07")

CSI: TC=0.26/1.00 (E-F:1), BC=0.17/1.00 (L-M:1),
WB=0.30/1.00 (C-M:1), SS=0.18/1.00 (D-E:1)

DOL LUMBER=1.00 NAIL=1.00 LS BEND=1.00
COMP=1.00 SHEAR=1.00 TENS=1.00

COMPANION LIVE LOAD FACTOR = 1.00

AUTOSOLVE RIGHT HEEL ONLY

TRUSS PLATE MANUFACTURER IS NOT RESPONSIBLE FOR QUALITY CONTROL IN THE TRUSS MANUFACTURING PLANT.

NAIL VALUES

PLATE	GRIP(DRY)	SHEAR (PSI)	SECTION (PLI)
MT20	650	371	1747
	788	1987	1873

PLATE PLACEMENT TOL. = 0.250 inches

PLATE ROTATION TOL. = 5.0 Deg.

JSI GRIP= 0.69 (G) (INPUT = 0.90)

JSI METAL= 0.30 (C) (INPUT = 1.00)



Structural component only
DWG# T-2121206 1/12

CONTINUED ON PAGE 2

JOB NAME 412865	TRUSS NAME T101	QUANTITY 2	PLY 2	JOB DESC. ROYAL PINE HOMES	DRWG NO.
				TRUSS DESC.	

Tamarack Roof Truss, Burlington

Version 8.420 S Jan 21 2021 MiTek Industries, Inc. Thu Jul 1 12:26:27 2021 Page 2

ID:hEKUVWZApinyW9leD6V iMya4z -x973pdXR8aUwOiKpCosLkRUwoCcwG5hX6XyNcz0S5A

PLATES (table is in inches)

JT	TYPE	PLATES	W	LEN	Y	X
B	TMV+p	MT20	4.0	4.0		
C	TMWW-t	MT20	4.0	6.0		
D	TTWW-m	MT20	5.0	6.0	2.25	2.00
E	TMW+w	MT20	2.0	4.0		
F	TMWW-t	MT20	4.0	4.0		
G	TMVW-t	MT20	4.0	6.0		
H	BMV1+p	MT20	3.0	6.0		
I	BMWW-t	MT20	5.0	6.0		
J	BS-t	MT20	5.0	6.0		
K	BMWWW-t	MT20	5.0	8.0		
L	BMWW-t	MT20	5.0	6.0		
M	BMVW1-t	MT20	5.0	6.0		

SPECIFIED CONCENTRATED LOADS (LBS)

JT	LOC.	LC1	MAX-	MAX+	FACE	DIR.	TYPE	HEEL	CONN.
X	13-11-4	-21	-21	--	BACK	VERT	TOTAL	--	C1
Y	15-11-4	-21	-21	--	BACK	VERT	TOTAL	--	C1
Z	17-11-4	-21	-21	--	BACK	VERT	TOTAL	--	C1

CONNECTION REQUIREMENTS

- 1) C1: A SUITABLE HANGER/MECHANICAL CONNECTION IS REQUIRED.




Structural component only
DWG# T-2121206 *M*

JOB NAME 412865	TRUSS NAME T101Z	QUANTITY 1	PLY 2	JOB DESC. ROYAL PINE HOMES	DRWG NO.
TRUSS DESC.					

Tamarack Roof Truss, Burlington

Version 8.420 S Jan 21 2021 MiTek Industries, Inc. Thu Jul 1 12:26:28 2021 Page 1
ID:hEKUVWZApjnyW9leD6V_jMya4z_-PMhR1zY3vucn0sv?mVNaGe15wcuNXiKqmmGWv2z0S59



TOTAL WEIGHT = 2 X 91 = 183 lb

LUMBER	N. L. G. A. RULES	CHORDS	SIZE	LUMBER	DESCR.
A - D	2x4	DRY	No.2	SPF	
D - G	2x4	DRY	No.2	SPF	
H - G	2x4	DRY	No.2	SPF	
M - B	2x6	DRY	No.2	SPF	
M - J	2x6	DRY	No.2	SPF	
J - H	2x6	DRY	No.2	SPF	

ALL WEBS 2x3 DRY No.2 SPF
EXCEPT

DRY: SEASONED LUMBER.

DESIGN CONSISTS OF 2 TRUSSES BUILT SEPARATELY THEN FASTENED TOGETHER AS FOLLOWS:

CHORDS #ROWS	SURFACE SPACING (IN)	LOAD (PLF)
TOP CHORDS : (0.122"x3") SPIRAL NAILS		
A - D 1 12	TOP	
D - G 1 12	SIDE(0.0)	
G - H 1 12	TOP	
M - B 2 12	TOP	
BOTTOM CHORDS : (0.122"x3") SPIRAL NAILS		
M - J 2 12	SIDE(0.0)	
J - H 2 12	SIDE(0.0)	
WEBS : (0.122"x3") SPIRAL NAILS		
2x3 1 6		

NAILS TO BE DRIVEN FROM ONE SIDE ONLY.

GIRDER NAILING ASSUMES NAILED HANGERS ARE FASTENED WITH MIN. 3-0 INCH NAILS.

TOP - COMPONENTS ARE LOADED FROM THE TOP AND MUST BE PLACED ON TOP EDGE OF ALL PLIES FOR THE LOAD TO BE TRANSFERRED TO EACH PLY.

SIDE - PLF SHOWN IS THE EQUIVALENT UDL APPLIED TO ONE SIDE THAT THE CORRESPONDING NAILING PATTERN SHALL BE CAPABLE OF TRANSFERRING. REMAINING PLF MUST BE APPLIED ON THE OPPOSITE SIDE OR ON THE TOP.

DIMENSIONS, SUPPORTS AND LOADINGS SPECIFIED BY FABRICATOR TO BE VERIFIED BY BUILDING DESIGNER

FACTORED	MAXIMUM FACTORED	INPUT	REQRD
GROSS REACTION	GROSS REACTION	BRG	BRG
JT VERT	DOWN	IN-SX	IN-SX
H 2170	0	1-8	1-8
M 2037	0	5-8	5-8

UNFACTORED REACTIONS

1ST LCASE	MAX/MIN. COMPONENT REACTIONS						
JT COMBINED	SNOW	LIVE	PERM. LIVE	WIND	DEAD	SOIL	
H 1531	1022 / 0	0 / 0	0 / 0	0 / 0	509 / 0	0 / 0	
M 1434	977 / 0	0 / 0	0 / 0	0 / 0	458 / 0	0 / 0	

BEARING MATERIAL TO BE SPF NO.2 OR BETTER AT JOINT(S) H, M

BRACING

TOP CHORD TO BE SHEATHED OR MAX. PURLIN SPACING = 4.66 FT.
MAX. UNBRACED BOTTOM CHORD LENGTH = 10.00 FT OR RIGID CEILING DIRECTLY APPLIED.

ALL PITCH BREAKS AND PERIMETER CORNER JOINTS MUST BE Laterally RESTRAINED.

LOADING

TOTAL LOAD CASES: (4)

CHORDS	MAX. FACTORED	FACTORED	MAX	MAX.	WEBS	MAX. FACTORED	MAX
MEMB.	FORCE (LBS)	VERT. LOAD (PLF)	CSI (LC)	UNBRAC LENGTH	MEMB.	FORCE (LBS)	CSI (LC)
FR-TO		FROM TO			FR-TO		
A-B	0 / 28	-91.8 -91.8	0.07 (1)	10.00	C-L	0 / 295	0.04 (1)
B-C	0 / 9	-91.8 -91.8	0.06 (1)	10.00	L-D	0 / 176	0.02 (4)
C-D	-2873 / 0	-91.8 -91.8	0.08 (1)	5.35	M-C	-2920 / 0	0.35 (1)
D-E	-3565 / 0	-91.8 -91.8	0.19 (1)	4.80	I-G	0 / 2975	0.37 (1)
E-N	-3565 / 0	-91.8 -91.8	0.30 (1)	4.66	D-K	0 / 1296	0.16 (1)
N-O	-3565 / 0	-91.8 -91.8	0.30 (1)	4.66	I-F	-1812 / 0	0.23 (1)
O-F	-3565 / 0	-91.8 -91.8	0.30 (1)	4.66	K-E	-529 / 0	0.07 (1)
F-P	-2315 / 0	-91.8 -91.8	0.27 (1)	5.56	K-F	0 / 1635	0.20 (1)
P-Q	-2315 / 0	-91.8 -91.8	0.27 (1)	5.56			
Q-G	-2315 / 0	-91.8 -91.8	0.27 (1)	5.56			
H-G	-2095 / 0	0.0 0.0	0.26 (1)	7.65			
M-B	-241 / 0	0.0 0.0	0.01 (1)	7.81			
M-L	0 / 2322	-18.5 -18.5	0.22 (1)	10.00			
L-R	0 / 2564	-18.5 -18.5	0.41 (1)	10.00			
R-K	0 / 2564	-18.5 -18.5	0.41 (1)	10.00			
K-S	0 / 2315	-18.5 -18.5	0.25 (1)	10.00			
S-J	0 / 2315	-18.5 -18.5	0.25 (1)	10.00			
J-T	0 / 2315	-18.5 -18.5	0.25 (1)	10.00			
T-I	0 / 2315	-18.5 -18.5	0.25 (1)	10.00			
I-U	0 / 0	-18.5 -18.5	0.04 (4)	10.00			
U-V	0 / 0	-18.5 -18.5	0.04 (4)	10.00			
V-H	0 / 0	-18.5 -18.5	0.04 (4)	10.00			

SPECIFIED CONCENTRATED LOADS (LBS)

JT	LOC.	LC1	MAX-	MAX+	FACE	DIR.	TYPE	HEEL	CONN.
N	11-6-12	-76	-76	---	FRONT	VERT	TOTAL	---	C1
O	13-6-12	-76	-76	---	FRONT	VERT	TOTAL	---	C1
P	15-6-12	-76	-76	---	FRONT	VERT	TOTAL	---	C1
Q	17-6-12	-76	-76	---	FRONT	VERT	TOTAL	---	C1
R	9-7-8	-974	-974	---	FRONT	VERT	TOTAL	---	C1
S	11-6-12	-21	-21	---	FRONT	VERT	TOTAL	---	C1
T	13-6-12	-21	-21	---	FRONT	VERT	TOTAL	---	C1
U	15-6-12	-21	-21	---	FRONT	VERT	TOTAL	---	C1
V	17-6-12	-21	-21	---	FRONT	VERT	TOTAL	---	C1

CONNECTION REQUIREMENTS

1) C1: A SUITABLE HANGER/MECHANICAL CONNECTION IS REQUIRED.

DESIGN CRITERIA

SPECIFIED LOADS:

TOP CH.	LL	= 25.6	PSF
	DL	= 6.0	PSF
BOT CH.	LL	= 0.0	PSF
	DL	= 7.4	PSF
TOTAL LOAD		= 39.0	PSF

SPACING = 24.0 IN. C/C

LOADING IN FLAT SECTION BASED ON A SLOPE OF 2.00/12 MINIMUM

THIS TRUSS IS DESIGNED FOR RESIDENTIAL OR SMALL BUILDING REQUIREMENTS OF PART 9, NBC 2015

THIS DESIGN COMPLIES WITH:

- PART 9 OF BCBC 2018, ABC 2019
- PART 9 OF OBC 2012 (2019 AMENDMENT)
- CSA 086-14
- TPIC 2014

(55% OF 31.3 P.S.F. G.S.L. PLUS 8.4 P.S.F. RAIN LOAD) EQUALS 25.6 P.S.F. SPECIFIED ROOF LIVE LOAD

ALLOWABLE DEFL.(LL) = L/360 (0.65")
CALCULATED VERT. DEFL.(LL) = L/999 (0.06")
ALLOWABLE DEFL.(TL) = L/360 (0.65")
CALCULATED VERT. DEFL.(TL) = L/999 (0.11")

CSI: TC=0.30/1.00 (E-F:1), BC=0.41/1.00 (K-L:1), WB=0.37/1.00 (G-I:1), SSI=0.40/1.00 (K-L:1)

DOL LUMBER=1.00 NAIL=1.00 LS BEND=1.00
COMP=1.00 SHEAR=1.00 TENS=1.00

COMPANION LIVE LOAD FACTOR = 1.00

AUTOSOLVE RIGHT HEEL ONLY

TRUSS PLATE MANUFACTURER IS NOT RESPONSIBLE FOR QUALITY CONTROL IN THE TRUSS MANUFACTURING PLANT.


NAIL VALUES

PLATE GRIP(DRY)	SHEAR	SECTION
(PSI)	(PLI)	(PLI)
MAX MIN	MAX MIN	MAX MIN
MT20	650 371	1747 788
	1987	1873

PLATE PLACEMENT TOL. = 0.250 inches

PLATE ROTATION TOL. = 5.0 Deg.

JSI GRIP= 0.88 (G) (INPUT = 0.90)
JSI METAL= 0.34 (C) (INPUT = 1.00)



Structural component only
DWG# T-2121207

CONTINUED ON PAGE 2

JOB NAME	TRUSS NAME	QUANTITY	PLY	JOB DESC.	ROYAL PINE HOMES	DRWG NO.
412865	T101Z	1	2	TRUSS DESC.		

Tamarack Roof Truss, Burlington

Version 8.420 S Jan 21 2021 MITek Industries, Inc. Thu Jul 1 12:26:28 2021 Page 2

ID:hEKUVWZApinyW9leD6V_iMya4z -PMhR1zY3vucn0sv?mVNaGe15wcuNXiKqmmGWv2z0S59

PLATES (table is in inches)

JT	TYPE	PLATES	W	LEN	Y	X
B	TMV+p	MT20	4.0	4.0		
C	TMWW-t	MT20	4.0	6.0		
D	TTWW-m	MT20	5.0	6.0	2.25	2.00
E	TMW+w	MT20	2.0	4.0		
F	TMWW-t	MT20	4.0	4.0		
G	TMVW-t	MT20	4.0	6.0		
H	BMV1+p	MT20	3.0	6.0		
I	BMWW-t	MT20	5.0	6.0		
J	BS-t	MT20	5.0	6.0		
K	BMWWW-t	MT20	5.0	8.0		
L	BMWW-t	MT20	5.0	6.0		
M	BMVW1-t	MT20	5.0	6.0		




Structural component only
DWG# T-2121207 *M*

JOB NAME 412865	TRUSS NAME T102	QUANTITY 3	PLY 1	JOB DESC. ROYAL PINE HOMES	DRWG NO.
---------------------------	---------------------------	----------------------	-----------------	--------------------------------------	----------

Tamarack Roof Truss, Burlington

Version 8.420 S Jan 21 2021 MITek Industries, Inc. Thu Jul 1 12:26:29 2021 Page 1
ID:hEKUVWZApjnyW9leD6V_jMya4z_tYFpEjYigBkeq0UBJCvppsZCg0FqG6O_?Q03RVz0S58



TOTAL WEIGHT = 3 X 80 = 239 lb [M]

LUMBER	CHORDS	SIZE	LUMBER	DESCR.
N. L. G. A. RULES				
A - D	2x4	DRY	No.2	SPF
D - F	2x4	DRY	No.2	SPF
K - B	2x4	DRY	No.2	SPF
K - I	2x4	DRY	No.2	SPF
I - G	2x4	DRY	No.2	SPF

ALL WEBS	2x3	DRY	No.2	SPF
EXCEPT				

DRY: SEASONED LUMBER.

PLATES (table is in inches)	JT	TYPE	PLATES	W	LEN	Y	X
B	TMV+p	MT20	3.0	4.0			
C	TMWV-t	MT20	4.0	6.0			
D	TTWW-m	MT20	5.0	6.0	2.25	2.00	
E	TMW+w	MT20	2.0	4.0			
F	TMVW-t	MT20	4.0	6.0			
G	BMV1+p	MT20	3.0	4.0			
H	BMWVW-t	MT20	4.0	9.0			
I	BS-t	MT20	3.0	6.0			
J	BMWV-t	MT20	4.0	4.0			
K	BMVW1-t	MT20	4.0	6.0			

DIMENSIONS, SUPPORTS AND LOADINGS SPECIFIED BY FABRICATOR TO BE VERIFIED BY BUILDING DESIGNER

BEARINGS	FACTORED GROSS REACTION	MAXIMUM FACTORED GROSS REACTION	INPUT BRG	REQD BRG
JT	VERT	HORZ	DOWN	HORZ
G	1073	0	1073	0
K	1197	0	1197	0

UNFACTORED REACTIONS

1ST LCASE	MAX/MIN. COMPONENT REACTIONS	1ST LCASE	MAX/MIN. COMPONENT REACTIONS
JT	COMBINED	SNOW	LIVE
G	759	498 / 0	0 / 0
K	844	567 / 0	0 / 0

BEARING MATERIAL TO BE SPF NO.2 OR BETTER AT JOINT(S) G, K

BRACING

TOP CHORD TO BE SHEATHED OR MAX. PURLIN SPACING = 5.39 FT.
MAX. UNBRACED BOTTOM CHORD LENGTH = 10.00 FT. OR RIGID CEILING DIRECTLY APPLIED.

ALL PITCH BREAKS AND PERIMETER CORNER JOINTS MUST BE Laterally RESTRAINED.

LOADING

TOTAL LOAD CASES: (4)

CHORDS	MEMB.	FORCE	FACTORED	VERT. LOAD	LC1	MAX	CS1 (LC)	UNBRAC	MEMB.	FORCE	FACTORED	VERT. LOAD	LC1	MAX	CS1 (LC)
FR-TO								LENGTH	FR-TO						
A-B	0 / 28	-91.8	-91.8	0.12	(1)	10.00	C-J	-182 / 2	0.07	(1)					
B-C	0 / 18	-91.8	-91.8	0.21	(1)	10.00	J-D	0 / 253	0.06	(4)					
C-D	-1207 / 0	-91.8	-91.8	0.24	(1)	5.54	D-H	-94 / 0	0.10	(1)					
D-E	-996 / 0	-91.8	-91.8	0.55	(1)	5.39	H-E	-658 / 0	0.25	(1)					
E-F	-996 / 0	-91.8	-91.8	0.56	(1)	5.39	H-F	0 / 1291	0.29	(1)					
G-F	-1026 / 0	0.0	0.0	0.45	(1)	7.74	K-C	-1491 / 0	0.57	(1)					
K-B	-266 / 0	0.0	0.0	0.03	(1)	7.81									
K-J	0 / 1212	-18.5	-18.5	0.34	(4)	10.00									
J-I	0 / 1068	-18.5	-18.5	0.34	(4)	10.00									
I-H	0 / 1068	-18.5	-18.5	0.34	(4)	10.00									
H-G	0 / 0	-18.5	-18.5	0.13	(4)	10.00									

DESIGN CRITERIA

SPECIFIED LOADS:

TOP CH.	LL = 25.6	PSF
DL = 6.0	PSF	
BOT CH.	LL = 0.0	PSF
DL = 7.4	PSF	
TOTAL LOAD	= 39.0	PSF

SPACING = 24.0 IN. C/C

LOADING IN FLAT SECTION BASED ON A SLOPE OF 2.00/12 MINIMUM

THIS TRUSS IS DESIGNED FOR RESIDENTIAL OR SMALL BUILDING REQUIREMENTS OF PART 9, NBC 2015

THIS DESIGN COMPLIES WITH:

- PART 9 OF CBC 2018, ABC 2019
- PART 9 OF OBC 2012 (2019 AMENDMENT)
- CSA 086-14
- TPIC 2014

(55 % OF 31.3 P.S.F. G.S.L. PLUS 8.4 P.S.F. RAIN LOAD) EQUALS 25.6 P.S.F. SPECIFIED ROOF LIVE LOAD

ALLOWABLE DEFL.(LL) = L/360 (0.65")
CALCULATED VERT. DEFL.(LL) = L/999 (0.04")
ALLOWABLE DEFL.(TL) = L/360 (0.65")
CALCULATED VERT. DEFL.(TL) = L/999 (0.15")

CSI: TC=0.56/1.00 (E-F:1), BC=0.34/1.00 (H-J:4),
WB=0.57/1.00 (C-K:1), SSI=0.26/1.00 (E-F:1)

DOL LUMBER=1.00 NAIL=1.00 LS BEND=1.10
COMP=1.10 SHEAR=1.10 TENS=1.10

COMPANION LIVE LOAD FACTOR = 1.00

TRUSS PLATE MANUFACTURER IS NOT RESPONSIBLE FOR QUALITY CONTROL IN THE TRUSS MANUFACTURING PLANT.

NAIL VALUES

PLATE GRIP(DRY)	SHEAR	SECTION
(PSI)	(PLI)	(PLI)
MAX	MIN	MAX
MT20	650	371
	1747	788
	1987	1873

PLATE PLACEMENT TOL. = 0.250 inches

PLATE ROTATION TOL. = 5.0 Deg.

JSI GRIP= 0.78 (F) (INPUT = 0.90)
JSI METAL= 0.32 (C) (INPUT = 1.00)




Structural component only
DWG# T-2121208

JOB NAME 412865	TRUSS NAME T103	QUANTITY 3	PLY 1	JOB DESC. ROYAL PINE HOMES	DRWG NO.
---------------------------	---------------------------	----------------------	-----------------	--------------------------------------	----------

Tamarack Roof Truss, Burlington

Version 8.420 S Jan 21 2021 MTEK Industries, Inc. Thu Jul 1 12:26:30 2021 Page 1
ID:hEKUVWZApjnyW9leD6V_jMya4z_MkoBSZKQVsVF93OtwQ2L36JRQdS?db7D4lc_xz0S557



TOTAL WEIGHT = 3 X 86 = 258 lb

LUMBER	N. L. G. A. RULES	CHORDS	SIZE	LUMBER	DESCR.
A - D	2x4	DRY	No.2	SPF	
D - F	2x4	DRY	No.2	SPF	
G - F	2x4	DRY	No.2	SPF	
L - B	2x4	DRY	No.2	SPF	
L - I	2x4	DRY	No.2	SPF	
I - G	2x4	DRY	No.2	SPF	

ALL WEBS 2x3 DRY No.2 SPF

EXCEPT

DRY: SEASONED LUMBER.

PLATES (table is in inches)	JT	TYPE	PLATES	W	LEN	Y	X
B	TMVW-t	MT20	4.0	6.0			
C	TMVW-t	MT20	4.0	4.0	2.00	1.75	
D	TTWW-m	MT20	5.0	6.0	2.25	2.00	
E	TMVW-t	MT20	2.0	4.0			
F	TMVW-t	MT20	4.0	6.0			
G	BMV1-p	MT20	3.0	4.0			
H	BMVW-t	MT20	4.0	9.0			
I	BS-t	MT20	3.0	6.0			
J	BMVW-t	MT20	4.0	4.0			
K	BMVW-t	MT20	4.0	6.0			
L	BMV1-p	MT20	3.0	4.0			

DIMENSIONS, SUPPORTS AND LOADINGS SPECIFIED BY FABRICATOR TO BE VERIFIED BY BUILDING DESIGNER

JT	FACTORED GROSS REACTION		MAXIMUM FACTORED GROSS REACTION		INPUT BRG	REQD BRG
	VERT	HORZ	DOWN	HORZ		
G	1073	0	1073	0	1-8	1-8
L	1197	0	1197	0	5-8	5-8

UNFACTORED REACTIONS

JT	1ST LCASE		MAX./MIN. COMPONENT REACTIONS		WIND	DEAD	SOIL
	COMBINED	SNOW	LIVE	PERM.LIVE			
G	759	498 / 0	0 / 0	0 / 0	0 / 0	261 / 0	0 / 0
L	844	567 / 0	0 / 0	0 / 0	0 / 0	277 / 0	0 / 0

BEARING MATERIAL TO BE SPF NO.2 OR BETTER AT JOINT(S) G, L

BRACING

TOP CHORD TO BE SHEATHED OR MAX. PURLIN SPACING = 5.17 FT.
MAX. UNBRACED BOTTOM CHORD LENGTH = 10.00 FT OR RIGID CEILING DIRECTLY APPLIED.

ALL PITCH BREAKS AND PERIMETER CORNER JOINTS MUST BE Laterally RESTRAINED.

LOADING

TOTAL LOAD CASES: (4)

CHORDS				WEBS			
MEMB.	MAX. FACTORED FORCE (LBS)	FACTORED VERT. LOAD (PLF)	MAX LC1 (LC)	MEMB.	MAX. FACTORED FORCE (LBS)	MAX LC1 (LC)	
FR-TO		FROM TO		FR-TO			
A-B	0 / 28	-91.8 -91.8	0.12 (1)	K-C	-118 / 43	0.03 (1)	
B-C	-1400 / 0	-91.8 -91.8	0.31 (1)	C-J	-454 / 0	0.28 (1)	
C-D	-1030 / 0	-91.8 -91.8	0.29 (1)	J-D	0 / 343	0.08 (1)	
D-E	-720 / 0	-91.8 -91.8	0.27 (1)	D-H	-292 / 0	0.32 (1)	
E-F	-720 / 0	-91.8 -91.8	0.27 (1)	H-E	-543 / 0	0.32 (1)	
G-F	-1035 / 0	0.0 0.0	0.75 (1)	H-F	0 / 1126	0.25 (1)	
L-B	-1157 / 0	0.0 0.0	0.12 (1)	B-K	0 / 1291	0.29 (1)	
L-K	0 / 0	-18.5 -18.5	0.10 (4)				
K-J	0 / 1273	-18.5 -18.5	0.25 (1)				
J-I	0 / 905	-18.5 -18.5	0.19 (1)				
I-H	0 / 905	-18.5 -18.5	0.19 (1)				
H-G	0 / 0	-18.5 -18.5	0.10 (4)				

DESIGN CRITERIA

SPECIFIED LOADS:

TOP CH. LL = 25.6 PSF
DL = 6.0 PSF
BOT CH. LL = 0.0 PSF
DL = 7.4 PSF
TOTAL LOAD = 39.0 PSF

SPACING = 24.0 IN. C/C

LOADING IN FLAT SECTION BASED ON A SLOPE OF 2.00/12 MINIMUM

THIS TRUSS IS DESIGNED FOR RESIDENTIAL OR SMALL BUILDING REQUIREMENTS OF PART 9, NBC 2015

THIS DESIGN COMPLIES WITH:

- PART 9 OF CBC 2018, ABC 2019
- PART 9 OF CBC 2012 (2019 AMENDMENT)
- CSA 086-14
- TPIC 2014

(55% OF 31.3 P.S.F. G.S.L. PLUS 8.4 P.S.F. RAIN LOAD) EQUALS 25.6 P.S.F. SPECIFIED ROOF LIVE LOAD

ALLOWABLE DEFL.(LL) = L/360 (0.65")
CALCULATED VERT. DEFL.(LL) = L/999 (0.04")
ALLOWABLE DEFL.(TL) = L/360 (0.65")
CALCULATED VERT. DEFL.(TL) = L/999 (0.07")

CSI: TC=0.75/1.00 (F-G:1), BC=0.25/1.00 (J-K:1), WB=0.32/1.00 (E-H:1), SS=0.21/1.00 (E-F:1)

DOL LUMBER=1.00 NAIL=1.00 LS BEND=1.10
COMP=1.10 SHEAR=1.10 TENS=1.10

COMPANION LIVE LOAD FACTOR = 1.00

TRUSS PLATE MANUFACTURER IS NOT RESPONSIBLE FOR QUALITY CONTROL IN THE TRUSS MANUFACTURING PLANT.


NAIL VALUES

PLATE	GRIP(DRY)	SHEAR	SECTION
(PSI)	(PLI)	(PLI)	(PLI)
MT20	650	371	1747 788 1987 1873

PLATE PLACEMENT TOL. = 0.250 inches

PLATE ROTATION TOL. = 5.0 Deg.

JSI GRIP= 0.87 (F) (INPUT = 0.90)
JSI METAL= 0.35 (B) (INPUT = 1.00)




Structural component only
DWG# T-2121209

JOB NAME 412865	TRUSS NAME T104	QUANTITY 3	PLY 1	JOB DESC. ROYAL PINE HOMES	DRWG NO.
TRUSS DESC.					

Tamarack Roof Truss, Burlington

Version 8.420 S Jan 21 2021 MiTek Industries, Inc. Thu Jul 1 12:26:31 2021 Page 1
ID:hEKUVWZApinyW9leD6V_jMya4z_-qwMaf_ayBo_MtJeaRdxHuHfYnqxOk?LHskVAWNz0S56



LUMBER			
N. L. G. A. RULES	CHORDS	SIZE	LUMBER
A - D	2x4	DRY	No.2
D - F	2x4	DRY	No.2
G - F	2x4	DRY	No.2
K - B	2x4	DRY	No.2
K - I	2x4	DRY	No.2
I - G	2x4	DRY	No.2

ALL WEBS	2x3	DRY	No.2	SPF
----------	-----	-----	------	-----

EXCEPT

DRY: SEASONED LUMBER.

PLATES (table is in inches)					
JT	TYPE	PLATES	W	LEN	Y X
B	TMVW-t	MT20	4.0	6.0	
C	TMVW-t	MT20	4.0	4.0	2.00 1.75
D	TTW-m	MT20	4.0	4.0	
E	TMVW-t	MT20	4.0	4.0	
F	TMV-p	MT20	3.0	4.0	
G	BMVW1-t	MT20	4.0	4.0	
H	BMVW1-t	MT20	4.0	9.0	
I	BS-t	MT20	3.0	6.0	
J	BMVW-t	MT20	4.0	6.0	
K	BMV1-p	MT20	3.0	4.0	

DIMENSIONS, SUPPORTS AND LOADINGS SPECIFIED BY FABRICATOR TO BE VERIFIED BY

BUILDING DESIGNER		FACTORED		MAXIMUM FACTORED		INPUT		REQRD	
BEARINGS		GROSS REACTION		GROSS REACTION		BRG		BRG	
JT	VERT	HORZ	DOWN	HORZ	UPLIFT	IN-SX	IN-SX	IN-SX	IN-SX
G	1073	0	1073	0	0	1-8	1-8		
K	1197	0	1197	0	0	5-8	5-8		

UNFACTORED REACTIONS		1ST LCASE		MAX./MIN. COMPONENT REACTIONS	
JT	COMBINED	SNOW	LIVE	PERM. LIVE	WIND
G	759	498 / 0	0 / 0	0 / 0	0 / 0
K	844	567 / 0	0 / 0	0 / 0	0 / 0

BEARING MATERIAL TO BE SPF NO.2 OR BETTER AT JOINT(S) G, K

BRACING
TOP CHORD TO BE SHEATHED OR MAX. PURLIN SPACING = 4.99 FT.
MAX. UNBRACED BOTTOM CHORD LENGTH = 10.00 FT OR RIGID CEILING DIRECTLY APPLIED.

ALL PITCH BREAKS AND PERIMETER CORNER JOINTS MUST BE Laterally RESTRAINED.

1 LATERAL BRACE(S) AT 1/2 LENGTH OF F-G, E-G.

END VERTICAL(S) MUST BE SHEATHED OR HAVE BRACES AS INDICATED IN THE MAX. UNBRACED LENGTH COLUMN OF THE TABLE BELOW

LOADING		TOTAL LOAD CASES: (4)	
CHORDS		FACTORED	
MEMB.	MAX. FACTORED FORCE (LBS)	VERT. LOAD (PLF)	MAX. UNBRACED LENGTH (LC)
FR-TO			
A-B	0 / 28	-91.8 -91.8	0.12 (1) 10.00
B-C	-1384 / 0	-91.8 -91.8	0.45 (1) 4.99
C-D	-855 / 0	-91.8 -91.8	0.42 (1) 6.02
D-E	-738 / 0	-91.8 -91.8	0.17 (1) 6.25
E-F	0 / 0	-91.8 -91.8	0.22 (1) 10.00
G-F	-134 / 0	0.0 0.0	0.03 (1) 6.25
K-B	-1148 / 0	0.0 0.0	0.12 (1) 7.42
K-J	0 / 0	-18.5 -18.5	0.14 (4) 10.00
J-I	0 / 1264	-18.5 -18.5	0.33 (1) 10.00
I-H	0 / 1264	-18.5 -18.5	0.33 (1) 10.00
H-G	0 / 496	-18.5 -18.5	0.26 (4) 10.00

DESIGN CRITERIA

SPECIFIED LOADS:
TOP CH. LL = 25.6 PSF
DL = 6.0 PSF
BOT CH. LL = 0.0 PSF
DL = 7.4 PSF
TOTAL LOAD = 39.0 PSF

SPACING = 24.0 IN. C/C

LOADING IN FLAT SECTION BASED ON A SLOPE OF 2.00/12 MINIMUM

THIS TRUSS IS DESIGNED FOR RESIDENTIAL OR SMALL BUILDING REQUIREMENTS OF PART 9, NBCC 2015

THIS DESIGN COMPLIES WITH:
- PART 9 OF CBC 2018, ABC 2019
- PART 9 OF OBC 2012 (2019 AMENDMENT)
- CSA 086-14
- TPIC 2014

(55% OF 31.3 P.S.F. G.S.L. PLUS 8.4 P.S.F. RAIN LOAD) EQUALS 25.6 P.S.F. SPECIFIED ROOF LIVE LOAD

ALLOWABLE DEFL.(LL) = L/360 (0.65")
CALCULATED VERT. DEFL.(LL) = L/999 (0.04")
ALLOWABLE DEFL.(TL) = L/360 (0.65")
CALCULATED VERT. DEFL.(TL) = L/999 (0.11")

CSI: TC=0.45/1.00 (B-C:1), BC=0.33/1.00 (H-J:1), WB=0.61/1.00 (C-H:1), SSI=0.24/1.00 (B-C:1)

DOL LUMBER=1.00 NAIL=1.00 LS BEND=1.10
COMP=1.10 SHEAR=1.10 TENS=1.10

COMPANION LIVE LOAD FACTOR = 1.00

TRUSS PLATE MANUFACTURER IS NOT RESPONSIBLE FOR QUALITY CONTROL IN THE TRUSS MANUFACTURING PLANT.

NAIL VALUES
PLATE GRIP(DRY) SHEAR SECTION
(PSI) (PLI) (PLI)
MAX MIN MAX MIN MAX MIN
MT20 650 371 1747 788 1987 1873

PLATE PLACEMENT TOL. = 0.250 inches

PLATE ROTATION TOL. = 5.0 Deg.


JSI GRIP= 0.74 (J) (INPUT = 0.90)
JSI METAL= 0.37 (I) (INPUT = 1.00)



Structural component only
DWG# T-2121210

JOB NAME 412865	TRUSS NAME T105	QUANTITY 11	PLY 1	JOB DESC. ROYAL PINE HOMES	DRWG NO.
Tamarack Roof Truss, Burlington				TRUSS DESC.	

Version 8.420 S Jan 21 2021 MITek Industries, Inc. Thu Jul 1 12:26:33 2021 Page 1
ID:hEKUVWZApjnyW9leD6V_jMya4z_-mJUK4gcCjQE36dozY2zIziksOdd1CzSZv2_HaGz0S54



TOTAL WEIGHT = 11 X 86 = 948 lb
(M/F)

LUMBER			
N. L. G. A. RULES	CHORDS	SIZE	LUMBER
A - D	2x4	DRY	No.2
D - E	2x4	DRY	No.2
E - F	2x4	DRY	No.2
G - F	2x4	DRY	No.2
K - B	2x4	DRY	No.2
K - I	2x4	DRY	No.2
I - G	2x4	DRY	No.2
ALL WEBS EXCEPT	2x3	DRY	No.2
DRY: SEASONED LUMBER.			

PLATES (table is in inches)					
JT	TYPE	PLATES	W	LEN	Y X
B	TMVW-t	MT20	4.0	6.0	
C	TMVW-t	MT20	4.0	4.0	2.00 1.75
D	TS-t	MT20	3.0	6.0	
E	TTW-m	MT20	4.0	4.0	
F	TMVW-t	MT20	4.0	6.0	
G	BMV1+p	MT20	3.0	4.0	
H	BMVWW-t	MT20	4.0	9.0	
I	BS-t	MT20	3.0	6.0	
J	BMVW-t	MT20	4.0	6.0	
K	BMV1+p	MT20	3.0	4.0	

DIMENSIONS, SUPPORTS AND LOADINGS SPECIFIED BY FABRICATOR TO BE VERIFIED BY BUILDING DESIGNER

BEARINGS		FACTORED GROSS REACTION	MAXIMUM FACTORED GROSS REACTION	INPUT BRG	REQRD BRG
JT	VERT	HORZ	DOWN	HORZ	UPLIFT
G	1073	0	1073	0	1-8
K	1197	0	1197	0	5-8

UNFACTORED REACTIONS

JT	1ST LCASE	MAX/MIN. COMPONENT REACTIONS	2ND LCASE	MAX/MIN. COMPONENT REACTIONS
G	759	498 / 0	0 / 0	0 / 0
K	844	567 / 0	0 / 0	0 / 0

BEARING MATERIAL TO BE SPF NO.2 OR BETTER AT JOINT(S) G, K

BRACING

TOP CHORD TO BE SHEATHED OR MAX. PURLIN SPACING = 4.69 FT.
MAX. UNBRACED BOTTOM CHORD LENGTH = 10.00 FT. OR RIGID CEILING DIRECTLY APPLIED.

ALL PITCH BREAKS AND PERIMETER CORNER JOINTS MUST BE Laterally RESTRAINED.

1 LATERAL BRACE(S) AT 1/2 LENGTH OF F-G, C-H.

END VERTICAL(S) MUST BE SHEATHED OR HAVE BRACES AS INDICATED IN THE MAX. UNBRACED LENGTH COLUMN OF THE TABLE BELOW

LOADING

TOTAL LOAD CASES: (4)

CHORDS		FACTORED		WEBS	
MEMB.	FORCE (LBS)	VERT. LOAD	LC1 MAX	MEMB.	FORCE (LBS)
FR-TO		FROM	TO	FR-TO	
A-B	0 / 28	-91.8	-91.8 0.12 (1)	J-C	-8 / 113
B-C	-1355 / 0	-91.8	-91.8 0.64 (1)	C-H	-821 / 0
C-D	-649 / 0	-91.8	-91.8 0.58 (1)	H-E	-216 / 6
D-E	-649 / 0	-91.8	-91.8 0.58 (1)	E-F	0 / 951
E-F	-546 / 0	-91.8	-91.8 0.37 (1)	F-J	0 / 1252
F-G	-1034 / 0	0.0	0.0 0.31 (1)		
G-K	-1144 / 0	0.0	0.0 0.12 (1)		
K-J	0 / 0	-18.5	-18.5 0.22 (4)		
J-I	0 / 1243	-18.5	-18.5 0.32 (4)		
I-H	0 / 1243	-18.5	-18.5 0.32 (4)		
H-G	0 / 0	-18.5	-18.5 0.15 (4)		

DESIGN CRITERIA

SPECIFIED LOADS:

TOP CH.	LL = 25.6 PSF
	DL = 6.0 PSF
BOT CH.	LL = 0.0 PSF
	DL = 7.4 PSF
TOTAL LOAD	= 39.0 PSF

SPACING = 24.0 IN. C/C

LOADING IN FLAT SECTION BASED ON A SLOPE OF 2.00/12 MINIMUM

THIS TRUSS IS DESIGNED FOR RESIDENTIAL OR SMALL BUILDING REQUIREMENTS OF PART 9, NBC 2015

THIS DESIGN COMPLIES WITH:

- PART 9 OF CBC 2018, ABC 2019
- PART 9 OF OBC 2012 (2019 AMENDMENT)
- CSA 086-14
- TPIC 2014

(55% OF 31.3 P.S.F. G.S.L. PLUS 8.4 P.S.F. RAIN LOAD) EQUALS 25.6 P.S.F. SPECIFIED ROOF LIVE LOAD

ALLOWABLE DEFL. (LL) = $L/360$ (0.65")
CALCULATED VERT. DEFL. (LL) = $L/999$ (0.04")
ALLOWABLE DEFL. (TL) = $L/360$ (0.65")
CALCULATED VERT. DEFL. (TL) = $L/999$ (0.10")

CSI: TC=0.64/1.00 (B-C:1), BC=0.32/1.00 (H-J:4), WB=0.38/1.00 (C-H:1), SSI=0.28/1.00 (B-C:1)

DOL LUMBER=1.00 NAIL=1.00 LS BEND=1.10
COMP=1.10 SHEAR=1.10 TENS=1.10

COMPANION LIVE LOAD FACTOR = 1.00

TRUSS PLATE MANUFACTURER IS NOT RESPONSIBLE FOR QUALITY CONTROL IN THE TRUSS MANUFACTURING PLANT.

NAIL VALUES

PLATE GRIP (DRY)	SHEAR	SECTION
(PSI)	(PLI)	(PLI)
MAX	MIN	MAX MIN
MT20	650 371	1747 788 1987 1873

PLATE PLACEMENT TOL. = 0.250 inches

PLATE ROTATION TOL. = 5.0 Deg.


JSI GRIP = 0.84 (F) (INPUT = 0.90)
JSI METAL = 0.41 (I) (INPUT = 1.00)



Structural component only
DWG# T-2121212

JOB NAME 412865	TRUSS NAME T107	QUANTITY 1	PLY 1	JOB DESC. ROYAL PINE HOMES	DRWG NO.
Tamarack Roof Truss, Burlington				TRUSS DESC.	

Version 8.420 S Jan 21 2021 Mitek Industries, Inc. Thu Jul 1 12:26:36 2021 Page 1
ID:hEKUVWZApjnyW9leD6VjMya4z_AuATie50LdeZ4WXBXSbMKrkhQPMa0c?CxBbz0S51



Scale = 1:21.5

LUMBER			
N. L. G. A. RULES	CHORDS	SIZE	LUMBER
A - C	2x4	DRY	No.2
C - D	2x4	DRY	No.2
D - F	2x4	DRY	No.2
J - B	2x4	DRY	No.2
G - E	2x4	DRY	No.2
J - G	2x4	DRY	No.2

ALL WEBS 2x3 DRY No.2
EXCEPT

DRY: SEASONED LUMBER.

PLATES (table is in inches)

JT	TYPE	PLATES	W	LEN	Y	X
B	TMVW+p	MT20	4.0	4.0	1.50	2.00
C	TTWW-m	MT20	5.0	6.0	2.00	2.00
D	TTW-m	MT20	4.0	4.0		
E	TMVW+p	MT20	4.0	4.0	1.50	2.00
G	BMV1+p	MT20	3.0	4.0		
H	BMVWW-t	MT20	4.0	9.0		
I	BMVWW-t	MT20	4.0	6.0		
J	BMV1+p	MT20	3.0	4.0		

DIMENSIONS, SUPPORTS AND LOADINGS SPECIFIED BY FABRICATOR TO BE VERIFIED BY BUILDING DESIGNER

FACTORED		MAXIMUM FACTORED		INPUT		REQRD	
JT	GROSS REACTION	JT	GROSS REACTION	JT	BRG	JT	BRG
J	VERT	J	DOWN	J	IN-SX	J	IN-SX
G	762	G	762	G	5-8	G	5-8
	0		0		4-4		4-4

UNFACTORED REACTIONS

1ST LCASE	MAX./MIN. COMPONENT REACTIONS	1ST LCASE	MAX./MIN. COMPONENT REACTIONS
JT	COMBINED	JT	COMBINED
J	535	J	535
G	535	G	535

BEARING MATERIAL TO BE SPF NO.2 OR BETTER AT JOINT(S) J, G

BRACING

TOP CHORD TO BE SHEATHED OR MAX. PURLIN SPACING = 6.25 FT.
MAX. UNBRACED BOTTOM CHORD LENGTH = 10.00 FT OR RIGID CEILING DIRECTLY APPLIED.

ALL PITCH BREAKS AND PERIMETER CORNER JOINTS MUST BE Laterally RESTRAINED.

LOADING

TOTAL LOAD CASES: (4)

CHORDS				WEBS			
MEMB.	MAX. FACTORED FORCE (LBS)	FACTORED VERT. LOAD (PLF)	MAX. CSI (LC)	MEMB.	MAX. FACTORED FORCE (LBS)	MAX. CSI (LC)	
FR-TO		FROM TO		FR-TO			
A-B	0 / 28	-91.8 -91.8	0.13 (1)	I-C	-126 / 22	0.02 (1)	
B-C	-678 / 0	-91.8 -91.8	0.11 (1)	C-H	0 / 0	0.00 (1)	
C-K	-598 / 0	-91.8 -91.8	0.37 (1)	H-D	-127 / 21	0.02 (1)	
K-L	-598 / 0	-91.8 -91.8	0.37 (1)	B-I	0 / 638	0.16 (1)	
L-D	-598 / 0	-91.8 -91.8	0.37 (1)	H-E	0 / 638	0.16 (1)	
D-E	-677 / 0	-91.8 -91.8	0.11 (1)				
E-F	0 / 28	-91.8 -91.8	0.13 (1)				
J-B	-745 / 0	0.0 0.0	0.08 (1)				
G-E	-744 / 0	0.0 0.0	0.08 (1)				
J-M	0 / 0	-18.5 -18.5	0.06 (4)				
M-I	0 / 0	-18.5 -18.5	0.06 (4)				
I-N	0 / 599	-18.5 -18.5	0.15 (1)				
N-O	0 / 599	-18.5 -18.5	0.15 (1)				
O-H	0 / 599	-18.5 -18.5	0.15 (1)				
H-P	0 / 0	-18.5 -18.5	0.06 (4)				
P-G	0 / 0	-18.5 -18.5	0.06 (4)				

SPECIFIED CONCENTRATED LOADS (LBS)

JT	LOC.	LC1	MAX.	MAX+	FACE	DIR.	TYPE	HEEL	CONN.
C	2-5-8	-74	-74	---	FRONT	VERT	TOTAL	---	C1
D	7-0-8	-74	-74	---	FRONT	VERT	TOTAL	---	C1
K	3-5-4	1	1	---	FRONT	VERT	TOTAL	---	C1
L	5-5-4	1	1	---	FRONT	VERT	TOTAL	---	C1
M	2-0-12	-3	-3	---	FRONT	VERT	TOTAL	---	C1
N	3-5-4	-1	-1	---	FRONT	VERT	TOTAL	---	C1
O	5-5-4	-1	-1	---	FRONT	VERT	TOTAL	---	C1
P	7-5-4	-3	-3	---	FRONT	VERT	TOTAL	---	C1

CONNECTION REQUIREMENTS

1) C1: A SUITABLE HANGER/MECHANICAL CONNECTION IS REQUIRED.

DESIGN CRITERIA

SPECIFIED LOADS:

TOP CH.	LL	=	25.6	PSF
DL	=	6.0	PSF	
BOT CH.	LL	=	0.0	PSF
DL	=	7.4	PSF	
TOTAL LOAD	=	39.0	PSF	

SPACING = 24.0 IN. C/C

LOADING IN FLAT SECTION BASED ON A SLOPE OF 2.00/12 MINIMUM

THIS TRUSS IS DESIGNED FOR RESIDENTIAL OR SMALL BUILDING REQUIREMENTS OF PART 9, NBC 2015

THIS DESIGN COMPLIES WITH:

- PART 9 OF BCBC 2018, ABC 2019
- PART 9 OF OBC 2012 (2019 AMENDMENT)
- CSA 086-14
- TPIC 2014

(55% OF 31.3 P.S.F. G.S.L. PLUS 8.4 P.S.F. RAIN LOAD) EQUALS 25.6 P.S.F. SPECIFIED ROOF LIVE LOAD

ALLOWABLE DEFL. (LL) = $L/360$ (0.32")
CALCULATED VERT. DEFL. (LL) = $L/999$ (0.01")
ALLOWABLE DEFL. (TL) = $L/360$ (0.32")
CALCULATED VERT. DEFL. (TL) = $L/999$ (0.02")

CSI: TC=0.37/1.00 (C-D:1), BC=0.15/1.00 (H-I:1), WB=0.16/1.00 (B-I:1), SS=0.18/1.00 (C-D:1)

DOL LUMBER=1.00 NAIL=1.00 LS BEND=1.00
COMP=1.00 SHEAR=1.00 TENS=1.00

COMPANION LIVE LOAD FACTOR = 1.00

TRUSS PLATE MANUFACTURER IS NOT RESPONSIBLE FOR QUALITY CONTROL IN THE TRUSS MANUFACTURING PLANT.

NAIL VALUES

PLATE GRIP (DRY)	SHEAR	SECTION
(PSI)	(PL)	(PL)
MAX	MIN	MAX
650	371	1747
788	1987	1873

PLATE PLACEMENT TOL. = 0.250 inches

PLATE ROTATION TOL. = 5.0 Deg.


JSI GRIP= 0.65 (B) (INPUT = 0.90)
JSI METAL= 0.20 (B) (INPUT = 1.00)



Structural component only
DWG# T-2121216

JOB NAME 412865	TRUSS NAME T108	QUANTITY 2	PLY 1	JOB DESC. ROYAL PINE HOMES	DRWG NO.
Tamarack Roof Truss, Burlington				TRUSS DESC.	

Version 8.420 S Jan 21 2021 MITek Industries, Inc. Thu Jul 1 12:26:36 2021 Page 1
ID:hEKUVWZApjnyW9leD6V_jMya4z_-AuATie50Ldez4WXEBXSbKMTxri6PNy0c?CxBbz0S51



TOTAL WEIGHT = 2 X 50 = 99 lb
[M/F]

LUMBER			
N. L. G. A. RULES	CHORDS	SIZE	LUMBER
A - C	2x4	DRY	No.2
C - D	2x6	DRY	No.2
D - F	2x4	DRY	No.2
J - B	2x4	DRY	No.2
G - E	2x4	DRY	No.2
J - G	2x4	DRY	No.2

ALL WEBS 2x3 DRY No.2
EXCEPT

DRY: SEASONED LUMBER.

PLATES (table is in inches)

JT	TYPE	PLATES	W	LEN	Y	X
B	TMVW-t	MT20	4.0	4.0	2.00	1.25
C	TTWW+m	MT20	4.0	6.0	2.25	1.75
D	TTW-h	MT20	4.0	6.0		
E	TMVW-t	MT20	4.0	4.0	2.00	1.25
G	BMV1+p	MT20	3.0	4.0		
H	BMWW-t	MT20	4.0	6.0	2.00	1.50
I	BMWW-t	MT20	4.0	4.0		
J	BMV1+p	MT20	3.0	4.0		

DIMENSIONS, SUPPORTS AND LOADINGS SPECIFIED BY FABRICATOR TO BE VERIFIED BY BUILDING DESIGNER

BEARINGS		FACTORED	MAXIMUM FACTORED	INPUT	REQRD
JT	GROSS REACTION	DOWN	GROSS REACTION	BRG	BRG
J	648	0	648	0	5-8
G	648	0	648	0	5-8

A SUITABLE HANGER/MECHANICAL CONNECTION IS REQUIRED AT JOINT G. MINIMUM BEARING LENGTH AT JOINT G = 1-8.

UNFACTORED REACTIONS

JT	COMBINED	SNOW	LIVE	PERM.LIVE	WIND	DEAD	SOIL
J	456	312/0	0/0	0/0	0/0	144/0	0/0
G	456	312/0	0/0	0/0	0/0	144/0	0/0

BEARING MATERIAL TO BE SPF NO.2 OR BETTER AT JOINT(S) J

BRACING

TOP CHORD TO BE SHEATHED OR MAX. PURLIN SPACING = 6.25 FT.
MAX. UNBRACED BOTTOM CHORD LENGTH = 10.00 FT OR RIGID CEILING DIRECTLY APPLIED.

ALL PITCH BREAKS AND PERIMETER CORNER JOINTS MUST BE Laterally RESTRAINED.

LOADING

TOTAL LOAD CASES: (4)

CHORDS				WEBS			
MEMB.	MAX. FACTORED FORCE (LBS)	FACTORED VERT. LOAD (PLF)	MAX. UNBRACED LENGTH (LC)	MEMB.	MAX. FACTORED FORCE (LBS)	MAX. UNBRACED LENGTH (LC)	
FR-TO		FROM TO		FR-TO			
A-B	0/28	-91.8 -91.8	0.12 (1)	10.00	I-C	-88/7	0.03 (1)
B-C	-309/0	-91.8 -91.8	0.23 (1)	6.25	H-D	-96/7	0.03 (1)
C-D	-278/0	-91.8 -91.8	0.00 (1)	6.25	B-I	0/315	0.07 (1)
D-E	-307/0	-91.8 -91.8	0.23 (1)	6.25	H-E	0/314	0.07 (1)
E-F	0/28	-91.8 -91.8	0.12 (1)	10.00	C-H	-7/0	0.00 (1)
J-B	-615/0	0.0 0.0	0.09 (1)	7.81			
G-E	-614/0	0.0 0.0	0.09 (1)	7.81			
J-I	0/0	-18.5 -18.5	0.08 (4)	10.00			
I-H	0/279	-18.5 -18.5	0.10 (4)	10.00			
H-G	0/0	-18.5 -18.5	0.08 (4)	10.00			

DESIGN CRITERIA

SPECIFIED LOADS:

TOP CH.	LL = 25.6	PSF
	DL = 6.0	PSF
BOT CH.	LL = 0.0	PSF
	DL = 7.4	PSF
TOTAL LOAD	= 39.0	PSF

SPACING = 24.0 IN. C/C

LOADING IN FLAT SECTION BASED ON A SLOPE OF 2.00/12 MINIMUM

THIS TRUSS IS DESIGNED FOR RESIDENTIAL OR SMALL BUILDING REQUIREMENTS OF PART 9, NBC 2015

THIS DESIGN COMPLIES WITH:

- PART 9 OF BCBC 2018, ABC 2019
- PART 9 OF OBC 2012 (2019 AMENDMENT)
- CSA 086-14
- TPIC 2014

(55% OF 31.3 P.S.F. G.S.L. PLUS 8.4 P.S.F. RAIN LOAD) EQUALS 25.6 P.S.F. SPECIFIED ROOF LIVE LOAD

ALLOWABLE DEFL. (LL) = $L/360$ (0.32")
CALCULATED VERT. DEFL. (LL) = $L/999$ (0.00")
ALLOWABLE DEFL. (TL) = $L/360$ (0.32")
CALCULATED VERT. DEFL. (TL) = $L/999$ (0.01")

CSI: TC=0.23/1.00 (B-C:1), BC=0.10/1.00 (H-I:4), WB=0.07/1.00 (B-I:1), SS=0.14/1.00 (D-E:1)

DOL LUMBER=1.00 NAIL=1.00 LS BEND=1.10
COMP=1.10 SHEAR=1.10 TENS=1.10

COMPANION LIVE LOAD FACTOR = 1.00

TRUSS PLATE MANUFACTURER IS NOT RESPONSIBLE FOR QUALITY CONTROL IN THE TRUSS MANUFACTURING PLANT.

NAIL VALUES

PLATE GRIP (DRY)	SHEAR	SECTION
(PSI)	(PLI)	(PLI)
MAX MIN	MAX MIN	MAX MIN
MT20	650 371	1747 788 1987 1873

PLATE PLACEMENT TOL. = 0.250 inches

PLATE ROTATION TOL. = 5.0 Deg.


JSI GRIP= 0.45 (B) (INPUT = 0.90)
JSI METAL= 0.16 (B) (INPUT = 1.00)



Structural component only
DWG# T-2121217

JOB NAME 412865	TRUSS NAME T109	QUANTITY 1	PLY 1	JOB DESC. ROYAL PINE HOMES	DRWG NO.
Tamarack Roof Truss, Burlington		TRUSS DESC.		Version 8.420 S Jan 21 2021 MITek Industries, Inc. Thu Jul 1 12:26:37 2021 Page 1	

ID:hEKUVWZApjnyW9leD6V_iMya4z_f4jrw2fjneVbE5knu2h7YveUE2h8qz9qfyUj1z0S50



TOTAL WEIGHT = 46 lb [M/F]

LUMBER				DESCR.	
N. L. G. A. RULES	SIZE	DRY	No.2	SPF	SPF
CHORDS					
A - C	2x4	DRY	No.2	SPF	SPF
C - D	2x4	DRY	No.2	SPF	SPF
D - F	2x4	DRY	No.2	SPF	SPF
J - B	2x4	DRY	No.2	SPF	SPF
G - E	2x4	DRY	No.2	SPF	SPF
J - G	2x4	DRY	No.2	SPF	SPF
ALL WEBS EXCEPT	2x3	DRY	No.2	SPF	SPF

DRY: SEASONED LUMBER.

PLATES (table is in inches)					
JT	TYPE	PLATES	W	LEN	Y X
B	TMVW-t	MT20	4.0	4.0	2.00 1.25
C	TTWW-m	MT20	5.0	6.0	2.25 2.00
D	TTW-m	MT20	4.0	4.0	
E	TMVW-t	MT20	4.0	4.0	2.00 1.25
G	BMV1+p	MT20	3.0	4.0	
H	BMVWW-t	MT20	4.0	4.0	9.0
I	BMVW-t	MT20	4.0	4.0	
J	BMV1+p	MT20	3.0	4.0	

DIMENSIONS, SUPPORTS AND LOADINGS SPECIFIED BY FABRICATOR TO BE VERIFIED BY BUILDING DESIGNER

BEARINGS		FACTORED	MAXIMUM FACTORED	INPUT	REQD
JT	GROSS REACTION	GROSS REACTION	DOWN	BRG	BRG
J	648 0	648 0	0 0	5-8	5-8
G	648 0	648 0	0 0	MECHANICAL	

A SUITABLE HANGER/MECHANICAL CONNECTION IS REQUIRED AT JOINT G. MINIMUM BEARING LENGTH AT JOINT G = 1-8.

UNFACTORED REACTIONS

1ST LCASE	MAX./MIN. COMPONENT REACTIONS						
JT	COMBINED	SNOW	LIVE	PERM. LIVE	WIND	DEAD	SOIL
J	456	312 / 0	0 / 0	0 / 0	0 / 0	144 / 0	0 / 0
G	456	312 / 0	0 / 0	0 / 0	0 / 0	144 / 0	0 / 0

BEARING MATERIAL TO BE SPF NO.2 OR BETTER AT JOINT(S) J

BRACING

TOP CHORD TO BE SHEATHED OR MAX. PURLIN SPACING = 6.25 FT. MAX. UNBRACED BOTTOM CHORD LENGTH = 10.00 FT. OR RIGID CEILING DIRECTLY APPLIED.

ALL PITCH BREAKS AND PERIMETER CORNER JOINTS MUST BE Laterally RESTRAINED.

LOADING

TOTAL LOAD CASES: (4)

CHORDS				WEBS			
MEMB.	MAX. FACTORED FORCE (LBS)	FACTORED VERT. LOAD (PLF)	MAX. UNBRACED LENGTH (LC)	MEMB.	MAX. FACTORED FORCE (LBS)	MAX. UNBRACED LENGTH (LC)	
FR-TO		FROM TO		FR-TO			
A-B	0 / 28	-91.8 -91.8	0.12 (1)	10.00	I-C	-183 / 0	0.04 (1)
B-C	-311 / 0	-91.8 -91.8	0.07 (1)	6.25	C-H	0 / 0	0.00 (1)
C-D	-272 / 0	-91.8 -91.8	0.25 (1)	6.25	H-D	-183 / 0	0.04 (1)
D-E	-311 / 0	-91.8 -91.8	0.07 (1)	6.25	B-I	0 / 378	0.09 (1)
E-F	0 / 28	-91.8 -91.8	0.12 (1)	10.00	H-E	0 / 377	0.08 (1)
J-B	-633 / 0	0.0 0.0	0.09 (1)	7.81			
G-E	-632 / 0	0.0 0.0	0.09 (1)	7.81			
J-I	0 / 0	-18.5 -18.5	0.06 (4)	10.00			
I-H	0 / 273	-18.5 -18.5	0.08 (4)	10.00			
H-G	0 / 0	-18.5 -18.5	0.06 (4)	10.00			

DESIGN CRITERIA

SPECIFIED LOADS:
TOP CH. LL = 25.6 PSF
DL = 6.0 PSF
BOT CH. LL = 0.0 PSF
DL = 7.4 PSF
TOTAL LOAD = 39.0 PSF

SPACING = 24.0 IN. C/C

LOADING IN FLAT SECTION BASED ON A SLOPE OF 2.00/12 MINIMUM

THIS TRUSS IS DESIGNED FOR RESIDENTIAL OR SMALL BUILDING REQUIREMENTS OF PART 9, NBCC 2015

THIS DESIGN COMPLIES WITH:
- PART 9 OF CBC 2018, ABC 2019
- PART 9 OF OBC 2012 (2019 AMENDMENT)
- CSA 086-14
- TPIC 2014

(55 % OF 31.3 P.S.F. G.S.L. PLUS 8.4 P.S.F. RAIN LOAD) EQUALS 25.6 P.S.F. SPECIFIED ROOF LIVE LOAD

ALLOWABLE DEFL.(LL)= L/360 (0.32")
CALCULATED VERT. DEFL.(LL) = L/999 (0.00")
ALLOWABLE DEFL.(TL)= L/360 (0.32")
CALCULATED VERT. DEFL.(TL) = L/999 (0.01")

CSI: TC=0.25/1.00 (C-D:1), BC=0.08/1.00 (H-I:4), WB=0.09/1.00 (B-I:1), SS=0.16/1.00 (C-D:1)

DOL LUMBER=1.00 NAIL=1.00 LS BEND=1.10
COMP=1.10 SHEAR=1.10 TENS= 1.10

COMPANION LIVE LOAD FACTOR = 1.00

TRUSS PLATE MANUFACTURER IS NOT RESPONSIBLE FOR QUALITY CONTROL IN THE TRUSS MANUFACTURING PLANT.

NAIL VALUES			
PLATE	GRIP(DRY)	SHEAR	SECTION
(PSI)	(PLI)	(PLI)	
MAX	MIN	MAX	MIN
MT20	650	371	1747 788 1987 1873

PLATE PLACEMENT TOL. = 0.250 inches

PLATE ROTATION TOL. = 5.0 Deg.


JSI GRIP= 0.52 (B) (INPUT = 0.90)
JSI METAL= 0.14 (B) (INPUT = 1.00)



Structural component only
DWG# T-2121218

JOB NAME 412865	TRUSS NAME T110	QUANTITY 1	PLY 2	JOB DESC. ROYAL PINE HOMES	DRWG NO.
Tamarack Roof Truss, Burlington					

Version 8.420 S Jan 21 2021 MITek Industries, Inc. Thu Jul 1 12:26:38 2021 Page 1
ID:hEKUVWZApinyW9leD6V_jMya4z_-7HHD7OfLYytMDOgwLbZwglRs9eM2tGvJ3Jh1GTz0S5?



TOTAL WEIGHT = 2 X 29 = 58 lb

LUMBER				
N. L. G. A. RULES	CHORDS	SIZE	LUMBER	DESCR.
A - C	2x4	DRY	No.2	SPF
D - C	2x4	DRY	No.2	SPF
F - A	2x6	DRY	No.2	SPF
F - D	2x6	DRY	No.2	SPF

ALL WEBS 2x3 DRY No.2 SPF
EXCEPT

DRY: SEASONED LUMBER.

DESIGN CONSISTS OF 2 TRUSSES BUILT SEPARATELY THEN FASTENED TOGETHER AS FOLLOWS:

CHORDS #ROWS	SURFACE SPACING (IN)	LOAD(PLF)
TOP CHORDS : (0.122"x3") SPIRAL NAILS		
A - C 1	12	TOP
C - D 1	12	TOP
F - A 2	12	TOP
BOTTOM CHORDS : (0.122"x3") SPIRAL NAILS		
F - D 2	12	SIDE(183.1)
WEBS : (0.122"x3") SPIRAL NAILS		
2x3 1	6	

NAILS TO BE DRIVEN FROM ONE SIDE ONLY.

GIRDER NAILING ASSUMES NAILED HANGERS ARE FASTENED WITH MIN. 3-0 INCH NAILS.

TOP - COMPONENTS ARE LOADED FROM THE TOP AND MUST BE PLACED ON TOP EDGE OF ALL PLIES FOR THE LOAD TO BE TRANSFERRED TO EACH PLY.

SIDE - PLF SHOWN IS THE EQUIVALENT UDL APPLIED TO ONE SIDE THAT THE CORRESPONDING NAILING PATTERN SHALL BE CAPABLE OF TRANSFERRING. REMAINING PLF MUST BE APPLIED ON THE OPPOSITE SIDE OR ON THE TOP.

DIMENSIONS, SUPPORTS AND LOADINGS SPECIFIED BY FABRICATOR TO BE VERIFIED BY BUILDING DESIGNER

	FACTORED GROSS REACTION	MAXIMUM FACTORED GROSS REACTION	INPUT BRG	REQRD BRG
JT	VERT	HORZ	DOWN	HORZ
D	1408	0	1408	0
F	1130	0	1130	0

A SUITABLE HANGER/MECHANICAL CONNECTION IS REQUIRED AT JOINT D. MINIMUM BEARING LENGTH AT JOINT D = 4-0.

UNFACTORED REACTIONS

1ST LCASE	MAX. MIN. COMPONENT REACTIONS
JT COMBINED	SNOW LIVE PERM. LIVE WIND DEAD SOIL
D	989 688 / 0 0 / 0 0 / 0 0 / 0 301 / 0 0 / 0
F	794 550 / 0 0 / 0 0 / 0 0 / 0 244 / 0 0 / 0

BEARING MATERIAL TO BE SPF NO.2 OR BETTER AT JOINT(S) F

BRACING

TOP CHORD TO BE SHEATHED OR MAX. PURLIN SPACING = 6.25 FT.
MAX. UNBRACED BOTTOM CHORD LENGTH = 10.00 FT OR RIGID CEILING DIRECTLY APPLIED.

ALL PITCH BREAKS AND PERIMETER CORNER JOINTS MUST BE Laterally RESTRAINED.

LOADING

TOTAL LOAD CASES: (4)

CHORDS	MAX. FACTORED MEMB. FORCE (LBS)	FACTORED VERT. LOAD (PLF)	MAX. VERT. LOAD LC1 (LO)	MAX. VERT. LOAD LC2 (LO)	MAX. VERT. LOAD LC3 (LO)	MAX. VERT. LOAD LC4 (LO)	MAX. VERT. LOAD LC5 (LO)	MAX. VERT. LOAD LC6 (LO)	MAX. VERT. LOAD LC7 (LO)	MAX. VERT. LOAD LC8 (LO)	MAX. VERT. LOAD LC9 (LO)	MAX. VERT. LOAD LC10 (LO)
FR-TO												
A-B	-1250 / 0	-91.8	-91.8	0.06 (1)	6.25	E-B	0 / 1106	0.14 (1)				
B-C	-11 / 0	-91.8	-91.8	0.05 (1)	6.25	B-D	-1419 / 0	0.17 (1)				
D-C	-110 / 0	0.0	0.0	0.01 (1)	7.81	A-E	0 / 1166	0.14 (1)				
F-A	-971 / 0	0.0	0.0	0.03 (1)	7.81							
F-G	0 / 0	-18.5	-18.5	0.11 (1)	10.00							
G-E	0 / 0	-18.5	-18.5	0.11 (1)	10.00							
E-H	0 / 1128	-18.5	-18.5	0.20 (1)	10.00							
H-D	0 / 1128	-18.5	-18.5	0.20 (1)	10.00							

SPECIFIED CONCENTRATED LOADS (LBS)

JT	LOC.	LC1	MAX-	MAX+	FACE	DIR.	TYPE	HEEL	CONN.
E	3-0-12	-441	-441	---	BACK	VERT	TOTAL	---	C1
G	2-1-4	-441	-441	---	BACK	VERT	TOTAL	---	C1
H	5-0-12	-443	-443	---	BACK	VERT	TOTAL	---	C1

CONNECTION REQUIREMENTS

- 1) C1: A SUITABLE HANGER/MECHANICAL CONNECTION IS REQUIRED.

DESIGN CRITERIA

SPECIFIED LOADS:

TOP CH.	LL = 25.6 PSF
	DL = 6.0 PSF
BOT CH.	LL = 0.0 PSF
	DL = 7.4 PSF
TOTAL LOAD	= 39.0 PSF

SPACING = 24.0 IN C/C

THIS TRUSS IS DESIGNED FOR RESIDENTIAL OR SMALL BUILDING REQUIREMENTS OF PART 9, NBCC 2015

THIS DESIGN COMPLIES WITH:

- PART 9 OF BCBC 2018, ABC 2019
- PART 9 OF OBC 2012 (2019 AMENDMENT)
- CSA 086-14
- TPIC 2014

(55 % OF 31.3 P.S.F. G.S.L. PLUS 8.4 P.S.F. RAIN LOAD) EQUALS 25.6 P.S.F. SPECIFIED ROOF LIVE LOAD

ALLOWABLE DEFL.(LL) = L/360 (0.20")
CALCULATED VERT. DEFL.(LL) = L/999 (0.01")
ALLOWABLE DEFL.(TL) = L/360 (0.20")
CALCULATED VERT. DEFL.(TL) = L/999 (0.01")

CSI: TC=0.08/1.00 (A-B:1), BC=0.20/1.00 (D-E:1),
WB=0.17/1.00 (B-D:1), SSI=0.17/1.00 (E-F:1)

DOL LUMBER=1.00 NAIL=1.00 LS BEND=1.00
COMP=1.00 SHEAR=1.00 TENS=1.00

COMPANION LIVE LOAD FACTOR = 1.00

AUTOSOLVE RIGHT HEEL ONLY

TRUSS PLATE MANUFACTURER IS NOT RESPONSIBLE FOR QUALITY CONTROL IN THE TRUSS MANUFACTURING PLANT.

NAIL VALUES

PLATE	GRIP(DRY)	SHEAR	SECTION
	(PSI)	(PLI)	(PLI)
MT20	650	371	1747
	788	1987	1873

PLATE PLACEMENT TOL = 0.250 inches

PLATE ROTATION TOL = 5.0 Deg.

JSI GRIP= 0.72 (B) (INPUT = 0.90)
JSI METAL= 0.25 (D) (INPUT = 1.00)



Structural component only
DWG# T-2121219

CONTINUED ON PAGE 2

JOB NAME 412865	TRUSS NAME T110	QUANTITY 1	PLY 2	JOB DESC. ROYAL PINE HOMES	DRWG NO.
Tamarack Roof Truss, Burlington				TRUSS DESC.	

Version 8.420 S Jan 21 2021 MiTek Industries, Inc. Thu Jul 1 12:26:38 2021 Page 2
ID:hEKUVWZApinyW9leD6V iMya4z -7HHD7OfLYtMDOgwLbZwglRs9eM2tGvJ3Jh1GTz0S5?

PLATES (table is in inches)

JT	TYPE	PLATES	W	LEN	Y	X
D	BMVW1+p	MT20	4.0	6.0		
E	BMVW-t	MT20	5.0	6.0		
F	BMV1+p	MT20	3.0	6.0		



Structural component only
DWG# T-2121219 *3/12*

JOB NAME 412865	TRUSS NAME T111	QUANTITY 1	PLY 3	JOB DESC. ROYAL PINE HOMES	DRWG NO.
Tamarack Roof Truss, Burlington				TRUSS DESC.	

Version 8.420 S Jan 21 2021 Mitek Industries, Inc. Thu Jul 1 12:26:40 2021 Page 2
ID:hEKUVWZApinyW9leD6V jMya4z -3fPzY3hb4Z74SiqJT0bOIAx9YSwcL4bWdA8JMz0S4z

PLATES (table is in inches)

JT	TYPE	PLATES	W	LEN	Y	X
B	TMBMW1+	MT20	10.0	12.0	3.75	
C	TMWW+	MT20	4.0	9.0	4.50	1.00
D	TMWW-	MT20	5.0	6.0		
E, I, K						
E	TS-	MT20	5.0	6.0		
F	TTW+m	MT20	5.0	8.0		
G	TMWW+	MT20	4.0	6.0		
H	TMWW+	MT20	4.0	6.0		
J	TTW+m	MT20	5.0	8.0		
L	TMWW-	MT20	5.0	6.0		
M	TMWW+	MT20	4.0	9.0	4.50	1.00
N	TMBMW1+	MT20	10.0	12.0	3.75	Edge
P	BMWW+	MT20	6.0	9.0		
Q	BMWW-	MT20	5.0	8.0	2.50	2.00
R	BS-	MT20	5.0	6.0		
S	BMWW+	MT20	4.0	6.0		
T	BS-	MT20	5.0	6.0		
U	BMWW-	MT20	5.0	8.0	2.50	2.50
V	BMWW+	MT20	6.0	9.0		

Edge - INDICATES REFERENCE CORNER OF PLATE TOUCHES EDGE OF CHORD.

SPECIFIED CONCENTRATED LOADS (LBS)

JT	LOC.	LC1	MAX-	MAX+	FACE	DIR.	TYPE	HEEL	CONN.
P	38-5-4	-2896	-2896	---	BACK	VERT	TOTAL	---	C1
AA	39-3-12	-312	-312	---	BACK	VERT	TOTAL	---	C1
AB	41-3-12	-312	-312	---	BACK	VERT	TOTAL	---	C1
AC	43-3-12	-312	-312	---	BACK	VERT	TOTAL	---	C1

CONNECTION REQUIREMENTS

- 1) C1: A SUITABLE HANGER/MECHANICAL CONNECTION IS REQUIRED.

TRUSS HAS BEEN CHECKED FOR UNBALANCED LOADING
AS PER NBCC 4.1.6.2.(8)


WIND LOAD APPLIED IS DERIVED FROM REFERENCE VELOCITY PRESSURE OF (9.2) PSF AT (30-0-0) FT-IN-SX REFERENCE HEIGHT ABOVE GRADE AND USING EXTERNAL PEAK COEFFICIENTS, C_{pe} , BASED ON THE (MAIN WIND FORCE RESISTING SYSTEM) INTERNAL WIND PRESSURE IS BASED ON DESIGN (CATEGORY 2). BUILDING MAY BE LOCATED ON (OPEN TERRAIN), AND TRUSS IS DESIGNED TO BE LOCATED AT LEAST (0-0) FT-IN-SX AWAY FROM EAVE. TRUSS UPLIFT IS BASED ON TOP AND BOTTOM CHORD DEAD LOADS OF 5.0 PSF AND 5.0 PSF RESPECTIVELY.



Structural component only
DWG# T-2121220 *ML*

JOB NAME 412865	TRUSS NAME T117	QUANTITY 1	PLY 1	JOB DESC. ROYAL PINE HOMES	DRWG NO.
Tamarack Roof Truss, Burlington					

Version 8.420 S Jan 21 2021 MiTek Industries, Inc. Thu Jul 1 12:26:46 2021 Page 1
ID:hEKUVWZApjnyW9leD6V_jMya4z_-upmFp7mMFPtDAdHSpHio?RmBxt6Qlu5UvZdTX?z0S4t



Scale = 1:17.3

LUMBER					DESCR.
N. L. G. A. RULES	SIZE	LUMBER			
CHORDS					
A - C	2x4	DRY	No.2	SPF	
C - E	2x4	DRY	No.2	SPF	
F - E	2x4	DRY	No.2	SPF	
I - B	2x4	DRY	No.2	SPF	
I - F	2x4	DRY	No.2	SPF	
ALL WEBS	2x3	DRY	No.2	SPF	
EXCEPT					

DRY: SEASONED LUMBER.

PLATES (table is in inches)

JT	TYPE	PLATES	W	LEN	Y	X
B	TMVW-t	MT20	4.0	4.0	2.00	1.25
C	TTWW-m	MT20	5.0	6.0	2.25	2.00
D	TMVW-w	MT20	2.0	4.0		
E	TMVW-t	MT20	4.0	4.0		
F	BMV1+p	MT20	3.0	4.0		
G	BMVWW-t	MT20	4.0	9.0		
H	BMVWW-t	MT20	4.0	6.0		
I	BMV1+p	MT20	3.0	4.0		

DIMENSIONS, SUPPORTS AND LOADINGS SPECIFIED BY FABRICATOR TO BE VERIFIED BY BUILDING DESIGNER

BEARINGS

	FACTORED GROSS REACTION	MAXIMUM FACTORED GROSS REACTION	INPUT BRG	REQD BRG
JT	VERT	HORZ	DOWN	HORZ
F	527	0	527	0
I	668	0	668	0

UNFACTORED REACTIONS

JT	COMBINED	SNOW	LIVE	PERM.LIVE	WIND	DEAD	SOIL
F	373	245 / 0	0 / 0	0 / 0	0 / 0	128 / 0	0 / 0
I	469	327 / 0	0 / 0	0 / 0	0 / 0	142 / 0	0 / 0

BEARING MATERIAL TO BE SPF NO.2 OR BETTER AT JOINT(S) F, I

BRACING

TOP CHORD TO BE SHEATHED OR MAX. PURLIN SPACING = 6.25 FT.
MAX. UNBRACED BOTTOM CHORD LENGTH = 10.00 FT OR RIGID CEILING DIRECTLY APPLIED.

ALL PITCH BREAKS AND PERIMETER CORNER JOINTS MUST BE Laterally RESTRAINED.

LOADING

TOTAL LOAD CASES: (4)

CHORDS				WEBS			
MEMB.	MAX. FACTORED FORCE (LBS)	FACTORED VERT. LOAD (PLF)	MAX. FACTORED CSI (LC)	MEMB.	MAX. FACTORED FORCE (LBS)	MAX. FACTORED CSI (LC)	
FR-TO		FROM TO		FR-TO			
A-B	0 / 28	-91.8 -91.8	0.13 (1)	10.00	H-C	-106 / 11	0.02 (1)
B-C	-546 / 0	-91.8 -91.8	0.11 (1)	6.25	C-G	0 / 44	0.01 (1)
C-J	-518 / 0	-91.8 -91.8	0.14 (1)	6.25	G-D	-332 / 0	0.06 (1)
J-D	-518 / 0	-91.8 -91.8	0.14 (1)	6.25	G-E	0 / 633	0.16 (1)
D-K	-518 / 0	-91.8 -91.8	0.14 (1)	6.25	B-H	0 / 515	0.13 (1)
K-L	-518 / 0	-91.8 -91.8	0.14 (1)	6.25			
L-E	-518 / 0	-91.8 -91.8	0.14 (1)	6.25			
F-E	-494 / 0	0.0 0.0	0.07 (1)	7.81			
I-B	-646 / 0	0.0 0.0	0.07 (1)	7.81			
I-M	0 / 0	-18.5 -18.5	0.03 (4)	10.00			
M-H	0 / 0	-18.5 -18.5	0.03 (4)	10.00			
H-N	0 / 483	-18.5 -18.5	0.11 (1)	10.00			
N-G	0 / 483	-18.5 -18.5	0.11 (1)	10.00			
G-O	0 / 0	-18.5 -18.5	0.04 (4)	10.00			
O-P	0 / 0	-18.5 -18.5	0.04 (4)	10.00			
P-F	0 / 0	-18.5 -18.5	0.04 (4)	10.00			

SPECIFIED CONCENTRATED LOADS (LBS)

JT	LOC.	LC1	MAX-	MAX+	FACE	DIR.	TYPE	HEEL	CONN.
C	2-5-8	-74	1	---	FRONT	VERT	TOTAL	---	C1
J	4-0-12	1	1	---	FRONT	VERT	TOTAL	---	C1
K	6-0-12	1	1	---	FRONT	VERT	TOTAL	---	C1
L	8-0-12	-17	-17	---	FRONT	VERT	TOTAL	---	C1
M	2-0-12	-3	-3	---	FRONT	VERT	TOTAL	---	C1
N	4-0-12	-1	-1	---	FRONT	VERT	TOTAL	---	C1
O	6-0-12	-1	-1	---	FRONT	VERT	TOTAL	---	C1
P	8-0-12	-6	-6	---	FRONT	VERT	TOTAL	---	C1

CONNECTION REQUIREMENTS

1) C1: A SUITABLE HANGER/MECHANICAL CONNECTION IS REQUIRED.

DESIGN CRITERIA

SPECIFIED LOADS:

TOP CH.	LL = 25.6	PSF
	DL = 6.0	PSF
BOT CH.	LL = 0.0	PSF
	DL = 7.4	PSF
TOTAL LOAD	= 39.0	PSF

SPACING = 24.0 IN./C

LOADING IN FLAT SECTION BASED ON A SLOPE OF 2.00/12 MINIMUM

THIS TRUSS IS DESIGNED FOR RESIDENTIAL OR SMALL BUILDING REQUIREMENTS OF PART 9, NBCC 2015

THIS DESIGN COMPLIES WITH:

- PART 9 OF CBC 2018, ABC 2019
- PART 9 OF OBC 2012 (2019 AMENDMENT)
- CSA 086-14
- TPIC 2014

(55 % OF 31.3 P.S.F. G.S.L. PLUS 8.4 P.S.F. RAIN LOAD) EQUALS 25.6 P.S.F. SPECIFIED ROOF LIVE LOAD

ALLOWABLE DEFL.(LL) = L/360 (0.28")
CALCULATED VERT. DEFL.(LL) = L/999 (0.01")
ALLOWABLE DEFL.(TL) = L/360 (0.28")
CALCULATED VERT. DEFL.(TL) = L/999 (0.01")

CSI: TC=0.14/1.00 (D-E:1), BC=0.11/1.00 (G-H:1), WB=0.16/1.00 (E-G:1), SSI=0.15/1.00 (D-E:1)

DOL LUMBER=1.00 NAIL=1.00 LS BEND=1.00
COMP=1.00 SHEAR=1.00 TENS=1.00

COMPANION LIVE LOAD FACTOR = 1.00

TRUSS PLATE MANUFACTURER IS NOT RESPONSIBLE FOR QUALITY CONTROL IN THE TRUSS MANUFACTURING PLANT.


NAIL VALUES

PLATE GRIP(DRY)	SHEAR (PSI)	SECTION (PLI)
MAX MIN	MAX MIN	MAX MIN
MT20	650 371	1747 788

PLATE PLACEMENT TOL. = 0.250 inches

PLATE ROTATION TOL. = 5.0 Deg.


JSI GRIP = 0.79 (B) (INPUT = 0.90)
JSI METAL = 0.22 (B) (INPUT = 1.00)



Structural component only
DWG# T-2121226

JOB NAME 412865	TRUSS NAME T118	QUANTITY 1	PLY 1	JOB DESC. ROYAL PINE HOMES	DRWG NO.
Tamarack Roof Truss, Burlington					

Version 8.420 S Jan 21 2021 MiTek Industries, Inc. Thu Jul 1 12:26:47 2021 Page 1
ID:hEKUJVWZApjnyW9leD6V_jMya4z_-M?Kd0Tm_Qj?4onsfN_D1XfJL9GSsUMHd7DN03S20S4s



Scale = 1/28.5

TOTAL WEIGHT = 39 lb

LUMBER			
N. L. G. A. RULES	SIZE	LUMBER	DESCR.
CHORDS			
A - B	2x4 DRY	No.2	SPF
B - C	2x4 DRY	No.2	SPF
D - C	2x4 DRY	No.2	SPF
F - A	2x4 DRY	No.2	SPF
F - D	2x4 DRY	No.2	SPF

ALL WEBS 2x3 DRY No.2
EXCEPT

DRY: SEASONED LUMBER.

PLATES (table is in inches)

JT	TYPE	PLATES	W	LEN	Y	X
A	TMVW-t	MT20	4.0	4.0	2.00	1.25
B	TTW-m	MT20	4.0	4.0		
C	TMVW-t	MT20	4.0	4.0		
D	BMV1+p	MT20	4.0	4.0		
E	BMVWW-t	MT20	4.0	9.0		
F	BMV1+p	MT20	3.0	4.0		

DIMENSIONS, SUPPORTS AND LOADINGS SPECIFIED BY FABRICATOR TO BE VERIFIED BY BUILDING DESIGNER

BEARINGS		FACTORED	MAXIMUM FACTORED	INPUT	REQRD
JT	VERT	GROSS REACTION	GROSS REACTION	BRG	BRG
D	462	0	462	0	1-8
F	462	0	462	0	1-8

A SUITABLE HANGER/MECHANICAL CONNECTION IS REQUIRED AT JOINT F. MINIMUM BEARING LENGTH AT JOINT F = 1-8.

UNFACTORED REACTIONS

JT	1ST LCASE	MAX. MIN. COMPONENT REACTIONS	SNOW	LIVE	PERM. LIVE	WIND	DEAD	SOIL
D	326	214 / 0	0 / 0	0 / 0	0 / 0	0 / 0	112 / 0	0 / 0
F	326	214 / 0	0 / 0	0 / 0	0 / 0	0 / 0	112 / 0	0 / 0

BEARING MATERIAL TO BE SPF NO.2 OR BETTER AT JOINT(S) D

BRACING

TOP CHORD TO BE SHEATHED OR MAX. PURLIN SPACING = 6.25 FT.
MAX. UNBRACED BOTTOM CHORD LENGTH = 10.00 FT. OR RIGID CEILING DIRECTLY APPLIED.

ALL PITCH BREAKS AND PERIMETER CORNER JOINTS MUST BE Laterally RESTRAINED.

LOADING

TOTAL LOAD CASES: (4)

CHORDS		FACTORED		WEBS	
MEMB.	MAX. FACTORED FORCE (LBS)	VERT. LOAD (PLF)	LC1 MAX (CSI (LC))	MEMB.	MAX. FACTORED FORCE (LBS)
FR-TO		FROM	TO	FR-TO	
A-B	-245 / 0	-91.8	-91.8 0.23 (1)	E-B	-275 / 0
B-C	-212 / 0	-91.8	-91.8 0.18 (1)	E-C	0 / 333
D-C	-436 / 0	0.0	0.0 0.17 (1)	A-E	0 / 246
F-A	-427 / 0	0.0	0.0 0.06 (1)		
F-E	0 / 0	-18.5	-18.5 0.09 (4)		
E-D	0 / 0	-18.5	-18.5 0.09 (4)		

DESIGN CRITERIA

SPECIFIED LOADS:

TOP CH.	LL = 25.6 PSF
	DL = 6.0 PSF
BOT CH.	LL = 0.0 PSF
	DL = 7.4 PSF
TOTAL LOAD	= 39.0 PSF

SPACING = 24.0 IN/C

LOADING IN FLAT SECTION BASED ON A SLOPE OF 2.00/12 MINIMUM

THIS TRUSS IS DESIGNED FOR RESIDENTIAL OR SMALL BUILDING REQUIREMENTS OF PART 9, NBCC 2015

THIS DESIGN COMPLIES WITH:

- PART 9 OF BCBC 2018, ABC 2019
- PART 9 OF OBC 2012 (2019 AMENDMENT)
- CSA 086-14
- TPIC 2014

(55 % OF 31.3 P.S.F. G.S.L. PLUS 8.4 P.S.F. RAIN LOAD) EQUALS 25.6 P.S.F. SPECIFIED ROOF LIVE LOAD

ALLOWABLE DEFL.(LL)= L/360 (0.28")
CALCULATED VERT. DEFL.(LL) = L/999 (0.00")
ALLOWABLE DEFL.(TL)= L/360 (0.28")
CALCULATED VERT. DEFL.(TL) = L/999 (0.01")

CSI: TC=0.23/1.00 (A-B:1), BC=0.09/1.00 (E-F:4), WB=0.10/1.00 (B-E:1), SS=0.14/1.00 (A-B:1)

DOL LUMBER=1.00 NAIL=1.00 LS BEND=1.10
COMP=1.10 SHEAR=1.10 TENS= 1.10

COMPANION LIVE LOAD FACTOR = 1.00

TRUSS PLATE MANUFACTURER IS NOT RESPONSIBLE FOR QUALITY CONTROL IN THE TRUSS MANUFACTURING PLANT.


NAIL VALUES

PLATE	GRIP(DRY)	SHEAR	SECTION
(PSI)	(PLI)	(PLI)	(PLI)
MT20	650	371	1747
	788	1987	1873

PLATE PLACEMENT TOL. = 0.250 inches


PLATE ROTATION TOL. = 5.0 Deg.

JSI GRIP= 0.36 (A) (INPUT = 0.90)
JSI METAL= 0.11 (A) (INPUT = 1.00)



Structural component only
DWG# T-2121227

JOB NAME 412865	TRUSS NAME T119	QUANTITY 1	PLY 1	JOB DESC. ROYAL PINE HOMES	DRWG NO.
Tamarack Roof Truss, Burlington					



Scale = 1:33.8

LUMBER	N. L. G. A. RULES	CHORDS	SIZE	LUMBER	DESCR.
A - C	2x4	DRY	No.2	SPF	
C - D	2x4	DRY	No.2	SPF	
E - D	2x4	DRY	No.2	SPF	
G - A	2x4	DRY	No.2	SPF	
G - E	2x4	DRY	No.2	SPF	

ALL WEBS 2x3 DRY No.2
EXCEPT

DRY: SEASONED LUMBER.

PLATES (table is in inches)

JT	TYPE	PLATES	W	LEN	Y	X
A	TMV+p	MT20	3.0	4.0		
B	TMVW-t	MT20	4.0	4.0		
C	TTW-m	MT20	4.0	4.0		
D	TMVW-t	MT20	4.0	4.0		
E	BMV1+p	MT20	3.0	4.0		
F	BMVW-t	MT20	4.0	9.0		
G	BMVW1-t	MT20	4.0	4.0		

DIMENSIONS, SUPPORTS AND LOADINGS SPECIFIED BY FABRICATOR TO BE VERIFIED BY BUILDING DESIGNER

BEARINGS	FACTORED	MAXIMUM FACTORED	INPUT	REQRD
GROSS REACTION	GROSS REACTION	BRG	BRG	
JT	VERT	HORZ	UPLIFT	IN-SX
E	462	0	462	0
G	462	0	462	0

A SUITABLE HANGER/MECHANICAL CONNECTION IS REQUIRED AT JOINT G. MINIMUM BEARING LENGTH AT JOINT G = 1-8.

UNFACTORED REACTIONS

JT	COMBINED	SNOW	LIVE	PERM.LIVE	WIND	DEAD	SOIL
E	326	214 / 0	0 / 0	0 / 0	0 / 0	112 / 0	0 / 0
G	326	214 / 0	0 / 0	0 / 0	0 / 0	112 / 0	0 / 0

BEARING MATERIAL TO BE SPF NO.2 OR BETTER AT JOINT(S) E

BRACING

TOP CHORD TO BE SHEATHED OR MAX. PURLIN SPACING = 6.25 FT.
MAX. UNBRACED BOTTOM CHORD LENGTH = 10.00 FT OR RIGID CEILING DIRECTLY APPLIED.

ALL PITCH BREAKS AND PERIMETER CORNER JOINTS MUST BE Laterally RESTRAINED.

LOADING

TOTAL LOAD CASES: (4)

CHORDS				WEBS			
MEMB.	MAX. FACTORED FORCE (LBS)	FACTORED VERT. LOAD (PLF)	MAX. UNBRACED LENGTH	MEMB.	MAX. FACTORED FORCE (LBS)	MAX. UNBRACED LENGTH	
FR-TO		FROM TO		FR-TO			
A-B	0 / 16	-91.8 -91.8	0.16 (1)	10.00	B-F	-175 / 0	0.08 (1)
B-C	-162 / 0	-91.8 -91.8	0.12 (1)	6.25	F-C	-135 / 0	0.07 (1)
C-D	-128 / 0	-91.8 -91.8	0.04 (1)	6.25	F-D	0 / 416	0.09 (1)
E-D	-483 / 0	0.0 0.0	0.32 (1)	7.81	G-B	-385 / 0	0.16 (1)
G-A	-113 / 0	0.0 0.0	0.02 (1)	7.81			
G-F	0 / 243	-18.5 -18.5	0.19 (4)	10.00			
F-E	0 / 0	-18.5 -18.5	0.18 (4)	10.00			

TOTAL WEIGHT = 45 lb [M] [F]

DESIGN CRITERIA

SPECIFIED LOADS:

TOP CH.	LL	=	25.6	PSF
	DL	=	6.0	PSF
BOT CH.	LL	=	0.0	PSF
	DL	=	7.4	PSF
TOTAL LOAD		=	39.0	PSF

SPACING = 24.0 IN C/C

LOADING IN FLAT SECTION BASED ON A SLOPE OF 2.00/12 MINIMUM

THIS TRUSS IS DESIGNED FOR RESIDENTIAL OR SMALL BUILDING REQUIREMENTS OF PART 9, NBCC 2015

THIS DESIGN COMPLIES WITH:

- PART 9 OF BCBC 2018, ABC 2019
- PART 9 OF OBC 2012 (2019 AMENDMENT)
- CSA 086-14
- TPIC 2014

(55 % OF 31.3 P.S.F. G.S.L. PLUS 8.4 P.S.F. RAIN LOAD) EQUALS 25.6 P.S.F. SPECIFIED ROOF LIVE LOAD

ALLOWABLE DEFL.(LL)= L/360 (0.28")
CALCULATED VERT. DEFL.(LL) = L/999 (0.01")
ALLOWABLE DEFL.(TL)= L/360 (0.28")
CALCULATED VERT. DEFL.(TL) = L/999 (0.05")

CSI: TC=0.32/1.00 (D-E:1), BC=0.19/1.00 (F-G:4), WB=0.16/1.00 (B-G:1), SSI=0.13/1.00 (A-B:1)

DOL LUMBER=1.00 NAIL=1.00 LS BEND=1.10
COMP=1.10 SHEAR=1.10 TENS= 1.10

COMPANION LIVE LOAD FACTOR = 1.00

TRUSS PLATE MANUFACTURER IS NOT RESPONSIBLE FOR QUALITY CONTROL IN THE TRUSS MANUFACTURING PLANT.

NAIL VALUES
PLATE GRIP(DRY) SHEAR SECTION
(PSI) (PLI) (PLI)
MAX MIN MAX MIN MAX MIN
MT20 650 371 1747 788 1987 1873

PLATE PLACEMENT TOL. = 0.250 inches


PLATE ROTATION TOL. = 5.0 Deg.

JSI GRIP = 0.55 (D) (INPUT = 0.90)
JSI METAL = 0.12 (D) (INPUT = 1.00)



Structural component only
DWG# T-2121228

JOB NAME 412865	TRUSS NAME T120	QUANTITY 1	PLY 1	JOB DESC. ROYAL PINE HOMES	DRWG NO.
Tamarack Roof Truss, Burlington					



TOTAL WEIGHT = 42 lb
[M/F]

LUMBER			
N. L. G. A. RULES	SIZE	LUMBER	DESCR.
CHORDS			
A - C	2x4 DRY	No.2	SPF
D - C	2x4 DRY	No.2	SPF
F - A	2x4 DRY	No.2	SPF
F - D	2x4 DRY	No.2	SPF
ALL WEBS	2x3 DRY	No.2	SPF
EXCEPT			

DRY: SEASONED LUMBER.

PLATES (table is in inches)

JT	TYPE	PLATES	W	LEN	Y	X
A	TMVW-t	MT20	4.0	4.0	2.00	1.25
B	TMVW-t	MT20	4.0	4.0	2.00	1.75
C	TMV+p	MT20	3.0	4.0		
D	BMVW1-t	MT20	4.0	4.0		
E	BMVW-t	MT20	4.0	4.0		
F	BMV1+p	MT20	3.0	4.0		

DIMENSIONS, SUPPORTS AND LOADINGS SPECIFIED BY FABRICATOR TO BE VERIFIED BY BUILDING DESIGNER

BEARINGS		FACTORED	MAXIMUM FACTORED	INPUT	REQRD
JT	VERT	GROSS REACTION	GROSS REACTION	BRG	BRG
D	462	0	462	0	1-8
F	462	0	462	0	MECHANICAL

A SUITABLE HANGER/MECHANICAL CONNECTION IS REQUIRED AT JOINT F. MINIMUM BEARING LENGTH AT JOINT F = 1-8.

UNFACTORED REACTIONS

JT	COMBINED	1ST CASE	SNOW	LIVE	PERM. LIVE	WIND	DEAD	SOIL
D	326	214 / 0	0 / 0	0 / 0	0 / 0	0 / 0	112 / 0	0 / 0
F	326	214 / 0	0 / 0	0 / 0	0 / 0	0 / 0	112 / 0	0 / 0

BEARING MATERIAL TO BE SPF NO.2 OR BETTER AT JOINT(S) D

BRACING

TOP CHORD TO BE SHEATHED OR MAX. PURLIN SPACING = 6.25 FT.
MAX. UNBRACED BOTTOM CHORD LENGTH = 10.00 FT OR RIGID CEILING DIRECTLY APPLIED.

ALL PITCH BREAKS AND PERIMETER CORNER JOINTS MUST BE Laterally RESTRAINED.

LOADING

TOTAL LOAD CASES: (4)

CHORDS		WEBS	
MEMB.	MAX. FACTORED FORCE (LBS)	FACTORED VERT. LOAD (PLF)	MAX. FACTORED FORCE (LBS)
FR-TO		FROM TO	FR-TO
A-B	-280 / 0	-91.8 -91.8 0.21 (1)	6.25 E-B -58 / 56
B-C	-21 / 0	-91.8 -91.8 0.21 (1)	6.25 B-D -393 / 0
D-C	-145 / 0	0.0 0.0 0.14 (1)	7.81 A-E 0 / 309
F-A	-431 / 0	0.0 0.0 0.06 (1)	7.81
F-E	0 / 0	-18.5 -18.5 0.09 (4)	10.00
E-D	0 / 269	-18.5 -18.5 0.11 (4)	10.00

DESIGN CRITERIA

SPECIFIED LOADS:

TOP CH.	LL = 25.6 PSF
	DL = 6.0 PSF
BOT CH.	LL = 0.0 PSF
	DL = 7.4 PSF
TOTAL LOAD	= 39.0 PSF

SPACING = 24.0 IN. C/C

THIS TRUSS IS DESIGNED FOR RESIDENTIAL OR SMALL BUILDING REQUIREMENTS OF PART 9, NBCC 2015

THIS DESIGN COMPLIES WITH:

- PART 9 OF BCBC 2018, ABC 2019
- PART 9 OF OBC 2012 (2019 AMENDMENT)
- CSA 086-14
- TPIC 2014

(55 % OF 31.3 P.S.F. G.S.L. PLUS 8.4 P.S.F. RAIN LOAD) EQUALS 25.6 P.S.F. SPECIFIED ROOF LIVE LOAD

ALLOWABLE DEFL.(LL) = $L/360$ (0.28")
CALCULATED VERT. DEFL.(LL) = $L/999$ (0.00")
ALLOWABLE DEFL.(TL) = $L/360$ (0.28")
CALCULATED VERT. DEFL.(TL) = $L/999$ (0.01")

CSI: TC=0.21/1.00 (A-B:1), BC=0.11/1.00 (D-E:4),
WB=0.24/1.00 (B-D:1), SS=0.17/1.00 (A-B:1)

DOL LUMBER=1.00 NAIL=1.00 LS BEND=1.10
COMP=1.10 SHEAR=1.10 TENS=1.10

COMPANION LIVE LOAD FACTOR = 1.00

TRUSS PLATE MANUFACTURER IS NOT RESPONSIBLE FOR QUALITY CONTROL IN THE TRUSS MANUFACTURING PLANT.

NAIL VALUES

PLATE GRIP(DRY)	SHEAR	SECTION
(PSI)	(PLI)	(PLI)
MAX	MIN	MAX MIN
MT20	650 371	1747 788 1987 1873

PLATE PLACEMENT TOL. = 0.250 inches


PLATE ROTATION TOL. = 5.0 Deg.

JSI GRIP= 0.44 (A) (INPUT = 0.90)
JSI METAL= 0.12 (A) (INPUT = 1.00)



Structural component only
DWG# T-2121229

JOB NAME 412865	TRUSS NAME T121	QUANTITY 1	PLY 3	JOB DESC. ROYAL PINE HOMES	DRWG NO.
Tamarack Roof Truss, Burlington					



LUMBER				DESCR.	
N. L. G. A. RULES	CHORDS	SIZE	LUMBER	SPF	
F - A	2x4	DRY	No.2	SPF	
A - C	2x4	DRY	No.2	SPF	
D - C	2x4	DRY	No.2	SPF	
F - D	2x6	DRY	No.2	SPF	

ALL WEBS 2x3 DRY
DRY: SEASONED LUMBER.

DESIGN CONSISTS OF 3 TRUSSES BUILT SEPARATELY THEN FASTENED TOGETHER AS FOLLOWS:

CHORDS #ROWS	SURFACE SPACING (IN)	LOAD (PLF)
TOP CHORDS : (0.122"x3") SPIRAL NAILS		
F-A 1	12	TOP
A-C 1	12	TOP
C-D 1	12	TOP
BOTTOM CHORDS : (0.122"x3") SPIRAL NAILS		
F-D 2	6	SIDE(545.9)
WEBS : (0.122"x3") SPIRAL NAILS		
2x3 1	6	

STAGGER NAILS BY HALF THE SURFACE SPACING IN ADJACENT PLIES.

GIRDER NAILING ASSUMES NAILED HANGERS ARE FASTENED WITH MIN. 3-0 INCH NAILS.

TOP - COMPONENTS ARE LOADED FROM THE TOP AND MUST BE PLACED ON TOP EDGE OF ALL PLIES FOR THE LOAD TO BE TRANSFERRED TO EACH PLY.

SIDE - PLF SHOWN IS THE EQUIVALENT UDL APPLIED TO ONE SIDE THAT THE CORRESPONDING NAILING PATTERN SHALL BE CAPABLE OF TRANSFERING. REMAINING PLF MUST BE APPLIED ON THE OPPOSITE SIDE OR ON THE TOP.

PLATES (table is in inches)					
JT	TYPE	PLATES	W	LEN	Y X
A	TMVW-p	MT20	4.0	4.0	1.50 2.00
B	TMVW-t	MT20	5.0	6.0	
C	TMV-p	MT20	3.0	4.0	
D	BMVW1+p	MT20	4.0	6.0	

DIMENSIONS, SUPPORTS AND LOADINGS SPECIFIED BY FABRICATOR TO BE VERIFIED BY BUILDING DESIGNER

BEARINGS		FACTORED GROSS REACTION	MAXIMUM FACTORED GROSS REACTION	INPUT BRG	REQRD BRG
JT	VERT	HORZ	DOWN	HORZ	UPLIFT
F	4121	0	4121	0	0
D	5184	0	5184	0	0

A SUITABLE HANGER/MECHANICAL CONNECTION IS REQUIRED AT JOINT F. MINIMUM BEARING LENGTH AT JOINT F = 4-0.

UNFACTORED REACTIONS							
JT	COMBINED	SNOW	LIVE	PERM.LIVE	WIND	DEAD	SOIL
F	2911	1927 / 0	0 / 0	0 / 0	0 / 0	984 / 0	0 / 0
D	3662	2424 / 0	0 / 0	0 / 0	0 / 0	1238 / 0	0 / 0

BEARING MATERIAL TO BE SPF NO.2 OR BETTER AT JOINT(S) D

BRACING
TOP CHORD TO BE SHEATHED OR MAX. PURLIN SPACING = 5.99 FT.
MAX. UNBRACED BOTTOM CHORD LENGTH = 10.00 FT OR RIGID CEILING DIRECTLY APPLIED.

ALL PITCH BREAKS AND PERIMETER CORNER JOINTS MUST BE Laterally RESTRAINED.

LOADING

TOTAL LOAD CASES: (4)

CHORDS				WEBS			
MEMB.	MAX. FACTORED FORCE (LBS)	FACTORED VERT. LOAD (PLF)	MAX LC1 (LC)	MEMB.	MAX. FACTORED FORCE (LBS)	MAX LC1 (LC)	
FR-TO		FROM TO		FR-TO			
F-A	-3150 / 0	0.0	0.0 0.14 (1)	A-E	0 / 3284	0.25 (1)	
A-B	-3223 / 0	-91.8	-91.8 0.10 (1)	E-B	0 / 3972	0.30 (1)	
B-C	-18 / 0	-91.8	-91.8 0.08 (1)	B-D	-4167 / 0	0.85 (1)	
D-C	-156 / 0	0.0	0.0 0.05 (1)				
F-G	0 / 0	-18.5	-18.5 0.47 (1)				
G-H	0 / 0	-18.5	-18.5 0.47 (1)				
H-E	0 / 0	-18.5	-18.5 0.47 (1)				
E-I	0 / 2899	-18.5	-18.5 0.59 (1)				
I-J	0 / 2899	-18.5	-18.5 0.59 (1)				
J-D	0 / 2899	-18.5	-18.5 0.59 (1)				

SPECIFIED CONCENTRATED LOADS (LBS)							
JT	LOC.	LC1	MAX.	FACE	DIR.	TYPE	HEEL
G	1-9-12	-1476	-1476	---	BACK	VERT	TOTAL
H	3-9-12	-1476	-1476	---	BACK	VERT	TOTAL
I	5-9-12	-1476	-1476	---	BACK	VERT	TOTAL
J	7-9-12	-1476	-1476	---	BACK	VERT	TOTAL

CONNECTION REQUIREMENTS

1) C1: A SUITABLE HANGER/MECHANICAL CONNECTION IS REQUIRED.

DESIGN CRITERIA

SPECIFIED LOADS:
TOP CH. LL = 25.6 PSF
DL = 6.0 PSF
BOT CH. LL = 0.0 PSF
DL = 7.4 PSF
TOTAL LOAD = 39.0 PSF

SPACING = 24.0 IN. C/C

THIS TRUSS IS DESIGNED FOR RESIDENTIAL OR SMALL BUILDING REQUIREMENTS OF PART 9, NBCC 2015

THIS DESIGN COMPLIES WITH:
- PART 9 OF BCBC 2018, ABC 2019
- PART 9 OF OBC 2012 (2019 AMENDMENT)
- CSA 086-14
- TPIC 2014

(55% OF 31.3 P.S.F. G.S.L. PLUS 8.4 P.S.F. RAIN LOAD) EQUALS 25.6 P.S.F. SPECIFIED ROOF LIVE LOAD

ALLOWABLE DEFL. (LL) = L/360 (0.28")
CALCULATED VERT. DEFL. (LL) = L/999 (0.03")
ALLOWABLE DEFL. (TL) = L/360 (0.28")
CALCULATED VERT. DEFL. (TL) = L/999 (0.06")

CSI: TC=0.14/1.00 (A-F:1), BC=0.59/1.00 (D-E:1), WB=0.85/1.00 (B-D:1), SSI=0.66/1.00 (E-F:1)

DOL LUMBER=1.00 NAIL=1.00 LS BEND=1.10
COMP=1.10 SHEAR=1.10 TENS=1.10

COMPANION LIVE LOAD FACTOR = 1.00

TRUSS PLATE MANUFACTURER IS NOT RESPONSIBLE FOR QUALITY CONTROL IN THE TRUSS MANUFACTURING PLANT.

NAIL VALUES					
PLATE	GRIP(DRY)	SHEAR	SECTION	(PSI)	(PLI)
MT20	650	371	1747	788	1987

PLATE PLACEMENT TOL. = 0.250 inches

PLATE ROTATION TOL. = 5.0 Deg.

JSI GRIP= 0.86 (A) (INPUT = 0.90)
JSI METAL= 0.44 (D) (INPUT = 1.00)



Structural component only
DWG# T-2121230

JOB NAME 412865	TRUSS NAME T121	QUANTITY 1	PLY 3	JOB DESC. ROYAL PINE HOMES	DRWG NO.
Tamarack Roof Truss, Burlington				TRUSS DESC.	

Version 8.420 S Jan 21 2021 MiTek Industries, Inc. Thu Jul 1 12:26:49 2021 Page 2
ID:5hmlqDWy3rdQ?RwMW_6szaya40M-IOSNR8oEyKFo1401UPGVd4OI940dy42wbXs78Kz0S4g

PLATES (table is in inches)


JT	TYPE	PLATES	W	LEN	Y	X
E	BMWw+t	MT20	5.0	8.0	4.25	2.50
F	BMV1+p	MT20	3.0	6.0		



Structural component only
DWG# T-2121230 *ML*

JOB NAME 412865	TRUSS NAME T122	QUANTITY 1	PLY 1	JOB DESC. ROYAL PINE HOMES	DRWG NO.
Tamarack Roof Truss, Burlington				TRUSS DESC.	

Version 8.420 S Jan 21 2021 MITek Industries, Inc. Thu Jul 1 12:26:50 2021 Page 1
ID:hEKUVWZApjnyW9leD6V_jMya4z_ma0leUptjeOffEbE27nk9HxsFUU3hiH4qBbggnz0S4p



Scale = 1:20.0

LUMBER				DESCR.	
N. L. G. A. RULES	CHORDS	SIZE	LUMBER		
A - C	2x4	DRY	No.2	SPF	
C - D	2x4	DRY	No.2	SPF	
D - F	2x4	DRY	No.2	SPF	
J - B	2x4	DRY	No.2	SPF	
G - E	2x4	DRY	No.2	SPF	
J - G	2x4	DRY	No.2	SPF	
ALL WEBS				2x3	DRY
EXCEPT				No.2	SPF
DRY: SEASONED LUMBER.					

PLATES (table is in inches)					
JT	TYPE	PLATES	W	LEN	Y X
B	TMVW-t	MT20	4.0	4.0	2.00 1.25
C	TTWW-m	MT20	5.0	6.0	2.25 2.00
D	TTW-m	MT20	4.0	4.0	
E	TMVW-t	MT20	4.0	4.0	2.00 1.25
G	BMV1+p	MT20	3.0	4.0	
H	BMVW-t	MT20	4.0	9.0	
I	BMVW-t	MT20	4.0	6.0	
J	BMV1+p	MT20	3.0	4.0	

DIMENSIONS, SUPPORTS AND LOADINGS SPECIFIED BY FABRICATOR TO BE VERIFIED BY BUILDING DESIGNER

BEARINGS		FACTORED		MAXIMUM FACTORED		INPUT		REQRD	
JT	GROSS REACTION	VERT	HORZ	DOWN	HORZ	BRG	IN-SX	BRG	IN-SX
J	720	0	0	720	0	5-8	5-8	5-8	5-8
G	716	0	0	716	0	5-8	5-8	5-8	5-8

UNFACTORED REACTIONS

1ST LCASE		MAX./MIN. COMPONENT REACTIONS						
JT	COMBINED	SNOW	LIVE	PERM.LIVE	WIND	DEAD	SOIL	
J	505	354 / 0	0 / 0	0 / 0	0 / 0	151 / 0	0 / 0	
G	502	352 / 0	0 / 0	0 / 0	0 / 0	150 / 0	0 / 0	

BEARING MATERIAL TO BE SPF NO.2 OR BETTER AT JOINT(S) J, G

BRACING

TOP CHORD TO BE SHEATHED OR MAX. PURLIN SPACING = 6.25 FT.
MAX. UNBRACED BOTTOM CHORD LENGTH = 10.00 FT OR RIGID CEILING DIRECTLY APPLIED.

ALL PITCH BREAKS AND PERIMETER CORNER JOINTS MUST BE Laterally RESTRAINED.

LOADING

TOTAL LOAD CASES: (4)

CHORDS				WEBS			
MEMB.	MAX. FACTORED FORCE (LBS)	FACTORED VERT. LOAD (PLF)	MAX. CSI (LC)	MEMB.	MAX. FACTORED FORCE (LBS)	MAX. CSI (LC)	
FR-TO		FROM TO		FR-TO			
A-B	0 / 28	-91.8 -91.8	0.13 (1)	I-C	-119 / 16	0.02 (1)	
B-C	-617 / 0	-91.8 -91.8	0.11 (1)	C-H	-6 / 0	0.00 (1)	
C-K	-540 / 0	-91.8 -91.8	0.24 (1)	H-D	-116 / 17	0.02 (1)	
K-L	-540 / 0	-91.8 -91.8	0.24 (1)	B-I	0 / 582	0.14 (1)	
L-D	-540 / 0	-91.8 -91.8	0.24 (1)	H-E	0 / 576	0.14 (1)	
D-E	-611 / 0	-91.8 -91.8	0.11 (1)				
E-F	0 / 28	-91.8 -91.8	0.13 (1)				
J-B	-700 / 0	0.0 0.0	0.08 (1)				
G-E	-695 / 0	0.0 0.0	0.08 (1)				
J-M	0 / 0	-18.5 -18.5	0.04 (4)				
M-I	0 / 0	-18.5 -18.5	0.04 (4)				
I-N	0 / 546	-18.5 -18.5	0.12 (1)				
N-O	0 / 546	-18.5 -18.5	0.12 (1)				
O-H	0 / 546	-18.5 -18.5	0.12 (1)				
H-P	0 / 0	-18.5 -18.5	0.04 (4)				
P-G	0 / 0	-18.5 -18.5	0.04 (4)				

SPECIFIED CONCENTRATED LOADS (LBS)

JT	LOC.	LC1	MAX.	MAX+	FACE	DIR.	TYPE	HEEL	CONN.
C	2-5-8	-74	-74	---	BACK	VERT	TOTAL	---	C1
D	6-1-8	-74	-74	---	BACK	VERT	TOTAL	---	C1
K	3-0-4	-9	-9	---	BACK	VERT	TOTAL	---	C1
L	4-6-4	1	1	---	BACK	VERT	TOTAL	---	C1
M	2-0-12	-3	-3	---	BACK	VERT	TOTAL	---	C1
N	3-0-4	-1	-1	---	BACK	VERT	TOTAL	---	C1
O	4-6-4	-1	-1	---	BACK	VERT	TOTAL	---	C1
P	6-6-4	-3	-3	---	BACK	VERT	TOTAL	---	C1

CONNECTION REQUIREMENTS

1) C1: A SUITABLE HANGER/MECHANICAL CONNECTION IS REQUIRED.

DESIGN CRITERIA

SPECIFIED LOADS:

TOP CH. LL = 25.6 PSF
DL = 6.0 PSF
BOT CH. LL = 0.0 PSF
DL = 7.4 PSF
TOTAL LOAD = 39.0 PSF

SPACING = 24.0 IN. C/C

LOADING IN FLAT SECTION BASED ON A SLOPE OF 2.00/12 MINIMUM

THIS TRUSS IS DESIGNED FOR RESIDENTIAL OR SMALL BUILDING REQUIREMENTS OF PART 9, NBCC 2015

THIS DESIGN COMPLIES WITH:
- PART 9 OF BCBC 2018, ABC 2019
- PART 9 OF OBC 2012 (2019 AMENDMENT)
- CSA 086-14
- TPIC 2014

(55 % OF 31.3 P.S.F. G.S.L PLUS 8.4 P.S.F. RAIN LOAD) EQUALS 25.6 P.S.F. SPECIFIED ROOF LIVE LOAD

ALLOWABLE DEFL.(LL)= L/360 (0.29")
CALCULATED VERT. DEFL.(LL) = L/999 (0.01")
ALLOWABLE DEFL.(TL)= L/360 (0.29")
CALCULATED VERT. DEFL.(TL) = L/999 (0.02")

CSI: TC=0.24/1.00 (C-D:1), BC=0.12/1.00 (H-I:1), WB=0.14/1.00 (B-I:1), SSI=0.15/1.00 (C-D:1)

DOL LUMBER=1.00 NAIL=1.00 LS BEND=1.00
COMP=1.00 SHEAR=1.00 TENS=1.00

COMPANION LIVE LOAD FACTOR = 1.00

TRUSS PLATE MANUFACTURER IS NOT RESPONSIBLE FOR QUALITY CONTROL IN THE TRUSS MANUFACTURING PLANT.


NAIL VALUES

PLATE GRIP(DRY) SHEAR	SECTION
(PSI)	(PLI)
MAX MIN MAX MIN MAX MIN	
MT20	650 371 1747 788 1987 1873

PLATE PLACEMENT TOL. = 0.250 inches

PLATE ROTATION TOL. = 5.0 Deg.


JSI GRIP= 0.90 (B) (INPUT = 0.90)
JSI METAL= 0.25 (B) (INPUT = 1.00)



Structural component only
DWG# T-2121231

JOB NAME 412865	TRUSS NAME T123	QUANTITY 1	PLY 1	JOB DESC. ROYAL PINE HOMES	DRWG NO.
Tamarack Roof Truss, Burlington					

Version 8.420 S Jan 21 2021 MITek Industries, Inc. Thu Jul 1 12:26:51 2021 Page 1
ID:hEKUVWZApjnyW9leD6V_jMya4z_-Ena8sqgVUyWWHOAQqqlziVU1 PuptQABd2rLDCDz0S4o



TOTAL WEIGHT = 32 lb
[M][F]

LUMBER			
N. L. G. A. RULES	CHORDS	SIZE	LUMBER
A - C	2x4	DRY	No.2
C - B	2x4	DRY	No.2
G - B	2x4	DRY	No.2
E - D	2x4	DRY	No.2
G - E	2x4	DRY	No.2
ALL WEBS EXCEPT	2x3	DRY	No.2
SPF			
DRY: SEASONED LUMBER.			

PLATES (table is in inches)

JT	TYPE	PLATES	W	LEN	Y	X
B	TMVW-t	MT20	4.0	4.0	2.00	1.25
C	TTW-p	MT20	4.0	4.0		
D	TMVW-t	MT20	4.0	4.0	2.00	1.25
E	BMV1+p	MT20	3.0	4.0		
F	BMVWW-t	MT20	4.0	9.0		
G	BMV1+p	MT20	3.0	4.0		

DIMENSIONS, SUPPORTS AND LOADINGS SPECIFIED BY FABRICATOR TO BE VERIFIED BY BUILDING DESIGNER

BEARINGS		FACTORED	MAXIMUM FACTORED	INPUT	REQD
JT	GROSS REACTION	GROSS REACTION	DOWN	UP	BRG
G	582	0	582	0	5-8
E	457	0	457	0	1-8

UNFACTORED REACTIONS

JT	1ST LCASE	MAX./MIN. COMPONENT REACTIONS	SNOW	LIVE	PERM.LIVE	WIND	DEAD	SOIL
G	409	282 / 0	0 / 0	0 / 0	0 / 0	0 / 0	127 / 0	0 / 0
E	323	212 / 0	0 / 0	0 / 0	0 / 0	0 / 0	111 / 0	0 / 0

BEARING MATERIAL TO BE SPF NO.2 OR BETTER AT JOINT(S) G, E

BRACING

TOP CHORD TO BE SHEATHED OR MAX. PURLIN SPACING = 6.25 FT.
MAX. UNBRACED BOTTOM CHORD LENGTH = 10.00 FT OR RIGID CEILING DIRECTLY APPLIED.

ALL PITCH BREAKS AND PERIMETER CORNER JOINTS MUST BE Laterally RESTRAINED.

LOADING

TOTAL LOAD CASES: (4)

CHORDS		MAX. FACTORED	FACTORED	VERT. LOAD	LC1	MAX	MAX. FACTORED	WEBS	MAX. FACTORED	FACTORED	VERT. LOAD	LC1	MAX
MEMB.	FORCE (LBS)	FROM	TO	PLF	CSI (LC)	UNBRAC LENGTH	FR-TO	MEMB.	FORCE (LBS)	FROM	TO	PLF	CSI (LC)
A-B	0 / 28	-91.8	-91.8	0.12 (1)	10.00	F-C	-54 / 52	0.02 (4)					
B-C	-364 / 0	-91.8	-91.8	0.22 (1)	6.25	B-F	0 / 332	0.07 (1)					
C-D	-364 / 0	-91.8	-91.8	0.19 (1)	6.25	F-D	0 / 336	0.08 (1)					
G-B	-550 / 0	0.0	0.0	0.06 (1)	7.81								
E-D	-428 / 0	0.0	0.0	0.04 (1)	7.81								
G-F	0 / 0	-18.5	-18.5	0.09 (4)	10.00								
F-E	0 / 0	-18.5	-18.5	0.09 (4)	10.00								

DESIGN CRITERIA

SPECIFIED LOADS:
TOP CH. LL = 25.6 PSF
DL = 6.0 PSF
BOT CH. LL = 0.0 PSF
DL = 7.4 PSF
TOTAL LOAD = 39.0 PSF

SPACING = 24.0 IN./C

THIS TRUSS IS DESIGNED FOR RESIDENTIAL OR SMALL BUILDING REQUIREMENTS OF PART 9, NBCC 2015

THIS DESIGN COMPLIES WITH:

- PART 9 OF BCBC 2018, ABC 2019
- PART 9 OF OBC 2012 (2019 AMENDMENT)
- CSA 086-14
- TPIC 2014

(55 % OF 31.3 P.S.F. G.S.L. PLUS 8.4 P.S.F. RAIN LOAD) EQUALS 25.6 P.S.F. SPECIFIED ROOF LIVE LOAD

ALLOWABLE DEFL.(LL) = L/360 (0.28")
CALCULATED VERT. DEFL.(LL) = L/999 (0.00")
ALLOWABLE DEFL.(TL) = L/360 (0.28")
CALCULATED VERT. DEFL.(TL) = L/999 (0.01")

CSI: TC=0.22/1.00 (B-C:1), BC=0.09/1.00 (F-G:4),
WB=0.08/1.00 (D-F:1), SSI=0.14/1.00 (B-C:1)

DOL LUMBER=1.00 NAIL=1.00 LS BEND=1.10
COMP=1.10 SHEAR=1.10 TENS=1.10

COMPANION LIVE LOAD FACTOR = 1.00

TRUSS PLATE MANUFACTURER IS NOT RESPONSIBLE FOR QUALITY CONTROL IN THE TRUSS MANUFACTURING PLANT.

NAIL VALUES

PLATE	GRIP(DRY)	SHEAR	SECTION
(PSI)	(PLI)	(PLI)	(PLI)
MAX	MIN	MAX	MIN
MT20	650	371	1747
	788	1987	1873

PLATE PLACEMENT TOL = 0.250 inches

PLATE ROTATION TOL = 5.0 Deg.

JSI GRIP= 0.56 (B) (INPUT = 0.90)

JSI METAL= 0.17 (B) (INPUT = 1.00)



Structural component only
DWG# T-2121232

JOB NAME 412865	TRUSS NAME T127	QUANTITY 1	PLY 3	JOB DESC. ROYAL PINE HOMES	DRWG NO.
Tamarack Roof Truss, Burlington				TRUSS DESC.	

Version 8.420 S Jan 21 2021 MiTek Industries, Inc. Thu Jul 1 15:50:49 2021 Page 2

ID:4yza9PaaQpgU0dqb94LAvFyZ5Xk-wA2clQwzQ4N5U6kTX1sqiFLQk5U4oy5YAqrpkuZ0P5a

PLATES (table is in inches)

JT	TYPE	PLATES	W	LEN	Y	X
A	TMVW-t	MT20	5.0	6.0		Edge
B	TTW+p	MT20	4.0	6.0		Edge
C	TMVW-p	MT20	5.0	6.0		Edge
D	BMV1+p	MT20	3.0	6.0		
E	BMVWW-t	MT20	8.0	9.0	4.25	4.50
F	BMV1+t	MT20	4.0	9.0		5.50

Edge - INDICATES REFERENCE CORNER OF PLATE
TOUCHES EDGE OF CHORD.




Structural component only
DWG# T-2121233 *3/1*

JOB NAME 413086	TRUSS NAME T141	QUANTITY 1	PLY 1	JOB DESC. ROYAL PINE HOMES	DRWG NO.
Tamarack Roof Truss, Burlington				TRUSS DESC.	

Version 8.420 S Jan 21 2021 MITek Industries, Inc. Thu Jul 1 12:32:50 2021 Page 1

ID:hEKUVWZApjnyW9leD6V_jMya4z_-ErnrCaAhxKfz6Q8kE9CrOobLm1XO3cBoJvz0S?B



TOTAL WEIGHT = 35 lb

LUMBER			
N. L. G. A. RULES	CHORDS	SIZE	LUMBER
A - C	2x4	DRY	No.2
C - E	2x4	DRY	No.2
H - B	2x4	DRY	No.2
F - D	2x4	DRY	No.2
H - F	2x4	DRY	No.2
ALL WEBS EXCEPT	2x3	DRY	No.2

DRY: SEASONED LUMBER.

PLATES (table is in inches)

JT	TYPE	PLATES	W	LEN	Y	X
B	TMVW-t	MT20	4.0	4.0	2.00	1.25
C	TTW-p	MT20	4.0	4.0		
D	TMVW-t	MT20	4.0	4.0	2.00	1.25
F	BMV1+p	MT20	3.0	4.0		
G	BMVWW-t	MT20	4.0	9.0		
H	BMV1+p	MT20	3.0	4.0		

DIMENSIONS, SUPPORTS AND LOADINGS SPECIFIED BY FABRICATOR TO BE VERIFIED BY BUILDING DESIGNER

BEARINGS		FACTORED GROSS REACTION	MAXIMUM FACTORED GROSS REACTION	INPUT	REQD
JT	VERT	HORZ	DOWN	HORZ	UPLIFT
H	598	0	598	0	5-8
F	598	0	598	0	5-8

UNFACTORED REACTIONS

JT	1ST LCASE	MAX. MIN. COMPONENT REACTIONS	SNOW	LIVE	PERM. LIVE	WIND	DEAD	SOIL
H	420	289 / 0	0 / 0	0 / 0	0 / 0	0 / 0	131 / 0	0 / 0
F	420	289 / 0	0 / 0	0 / 0	0 / 0	0 / 0	131 / 0	0 / 0

BEARING MATERIAL TO BE SPF NO.2 OR BETTER AT JOINT(S) H, F

BRACING

TOP CHORD TO BE SHEATHED OR MAX. PURLIN SPACING = 6.25 FT.
MAX. UNBRACED BOTTOM CHORD LENGTH = 10.00 FT. OR RIGID CEILING DIRECTLY APPLIED.

ALL PITCH BREAKS AND PERIMETER CORNER JOINTS MUST BE Laterally RESTRAINED.

LOADING

TOTAL LOAD CASES: (4)

CHORDS				WEBS			
MEMB.	MAX. FACTORED FORCE (LBS)	FACTORED VERT. LOAD (PLF)	MAX. LC1 MAX (LC)	MEMB.	MAX. FACTORED FORCE (LBS)	MAX. UNBRACED LENGTH	MAX. FACTORED FORCE (LBS)
FR-TO		FROM	TO	FR-TO			
A-B	0 / 28	-91.8	-91.8 0.12 (1)	10.00	G-C	44 / 58	0.02 (4)
B-C	-391 / 0	-91.8	-91.8 0.22 (1)	6.25	B-G	0 / 357	0.08 (1)
C-D	-391 / 0	-91.8	-91.8 0.22 (1)	6.25	G-D	0 / 357	0.08 (1)
D-E	0 / 28	-91.8	-91.8 0.12 (1)	10.00			
H-B	-566 / 0	0.0	0.0 0.06 (1)	7.81			
F-D	-566 / 0	0.0	0.0 0.06 (1)	7.81			
H-G	0 / 0	-18.5	-18.5 0.09 (4)	10.00			
G-F	0 / 0	-18.5	-18.5 0.09 (4)	10.00			

DESIGN CRITERIA

SPECIFIED LOADS:

TOP CH.	LL	=	25.6	PSF
	DL	=	6.0	PSF
BOT CH.	LL	=	0.0	PSF
	DL	=	7.4	PSF
TOTAL LOAD		=	39.0	PSF

SPACING = 24.0 IN. C/C

THIS TRUSS IS DESIGNED FOR RESIDENTIAL OR SMALL BUILDING REQUIREMENTS OF PART 9, NBC 2015

THIS DESIGN COMPLIES WITH:

- PART 9 OF CBC 2018, ABC 2019
- PART 9 OF OBC 2012 (2019 AMENDMENT)
- CSA 086-14
- TPIC 2014

(55% OF 31.3 P.S.F. G.S.L. PLUS 8.4 P.S.F. RAIN LOAD) EQUALS 25.6 P.S.F. SPECIFIED ROOF LIVE LOAD

ALLOWABLE DEFL.(LL) = $L/360$ (0.29")
CALCULATED VERT. DEFL.(LL) = $L/999$ (0.00")
ALLOWABLE DEFL.(TL) = $L/360$ (0.29")
CALCULATED VERT. DEFL.(TL) = $L/999$ (0.01")

CSI: TC=0.22/1.00 (C-D:1), BC=0.09/1.00 (F-G:4), WB=0.08/1.00 (B-G:1), SSI=0.14/1.00 (C-D:1)

DOL LUMBER=1.00 NAIL=1.00 LS BEND=1.10
COMP=1.10 SHEAR=1.10 TENS=1.10

COMPANION LIVE LOAD FACTOR = 1.00

TRUSS PLATE MANUFACTURER IS NOT RESPONSIBLE FOR QUALITY CONTROL IN THE TRUSS MANUFACTURING PLANT.

NAIL VALUES

PLATE	GRIP(DRY)	SHEAR	SECTION
	(PSI)	(PLI)	(PLI)
MAX	MIN	MAX	MIN
MT20	650	371	1747
	788	1987	1873

PLATE PLACEMENT TOL. = 0.250 inches

PLATE ROTATION TOL. = 5.0 Deg.


JSI GRIP = 0.60 (D) (INPUT = 0.90)
JSI METAL = 0.18 (D) (INPUT = 1.00)



Structural component only
DWG# T-2121235

JOB NAME 412868	TRUSS NAME PB06	QUANTITY 18	PLY 1	JOB DESC. ROYAL PINE HOMES	DRWG NO.
Tamarack Roof Truss, Burlington				TRUSS DESC.	

Version 8.420 S Jan 21 2021 Mitek Industries, Inc. Thu Jul 1 10:22:28 2021 Page 1
ID:U6yi?rbeFFwxf_UFm_koDybSsJ-F07pXzVD1xFQRU85wzvkiufSViPKu3kxF0pmHz0TvP



LUMBER	N. L. G. A. RULES	CHORDS	SIZE	DRY	LUMBER	DESCR.
A - D	2x4	DRY	No.2	SPF		
D - G	2x4	DRY	No.2	SPF		
B - F	2x4	DRY	No.2	SPF		
ALL WEBS	2x3	DRY	No.2	SPF		
DRY: SEASONED LUMBER.						

PLATES (table is in inches)	JT	TYPE	PLATES	W	LEN	Y	X
B	TMB1-I	MT20	3.0	4.0			
C	TMW-w	MT20	2.0	4.0			
D	TTWW+p	MT20	4.0	6.0	Edge		
E	TMW-w	MT20	2.0	4.0			
F	TMB1-I	MT20	3.0	4.0			
H	BMWW1-I	MT20	4.0	4.0			
I	BMWW1-I	MT20	4.0	4.0			

Edge - INDICATES REFERENCE CORNER OF PLATE TOUCHES EDGE OF CHORD.

DIMENSIONS, SUPPORTS AND LOADINGS SPECIFIED BY FABRICATOR TO BE VERIFIED BY BUILDING DESIGNER

JT	FACTORED GROSS REACTION		MAXIMUM FACTORED GROSS REACTION		INPUT BRG	REQRD BRG
	VERT	HORZ	DOWN	HORZ		
B	340	0	340	0	15-9-6	15-9-6
F	340	0	340	0	15-9-6	15-9-6
H	610	0	610	0	15-9-6	15-9-6
I	610	0	610	0	15-9-6	15-9-6

UNFACTORED REACTIONS

JT	1ST LCASE		MAX./MIN. COMPONENT REACTIONS				
	COMBINED	SNOW	LIVE	PERM. LIVE	WIND	DEAD	SOIL
B	239	166 / 0	0 / 0	0 / 0	0 / 0	73 / 0	0 / 0
F	239	166 / 0	0 / 0	0 / 0	0 / 0	73 / 0	0 / 0
H	432	283 / 0	0 / 0	0 / 0	0 / 0	149 / 0	0 / 0
I	432	283 / 0	0 / 0	0 / 0	0 / 0	149 / 0	0 / 0

BEARING MATERIAL TO BE SPF NO.2 OR BETTER AT JOINT(S) B, F, H, I

BRACING

TOP CHORD TO BE SHEATHED OR MAX. PURLIN SPACING = 6.25 FT.
MAX. UNBRACED BOTTOM CHORD LENGTH = 10.00 FT OR RIGID CEILING DIRECTLY APPLIED.

ALL PITCH BREAKS AND PERIMETER CORNER JOINTS MUST BE Laterally RESTRAINED.

LOADING

TOTAL LOAD CASES: (4)

CHORDS				WEBS				
MEMB.	MAX. FACTORED FORCE (LBS)	FACTORED VERT. LOAD (PLF)		LC1 MAX CSI (LC)	MAX. UNBRAC LENGTH	MEMB.	MAX. FACTORED FORCE (LBS)	MAX CSI (LC)
FR-TO		FROM	TO			FR-TO		
A-B	0 / 17	-91.8	-91.8	0.05 (1)	10.00	D-H	-197 / 0	0.07 (1)
B-K	-199 / 0	-91.8	-91.8	0.06 (4)	6.25	H-E	-396 / 0	0.07 (1)
K-C	-143 / 0	-91.8	-91.8	0.23 (1)	6.25	I-D	-197 / 0	0.07 (1)
C-D	0 / 54	-91.8	-91.8	0.24 (1)	10.00	C-I	-396 / 0	0.07 (1)
D-E	0 / 54	-91.8	-91.8	0.24 (1)	10.00	J-K	-69 / 58	0.00 (1)
E-M	-143 / 0	-91.8	-91.8	0.23 (1)	6.25	L-M	-69 / 58	0.00 (1)
M-F	-199 / 0	-91.8	-91.8	0.06 (4)	6.25			
F-G	0 / 17	-91.8	-91.8	0.05 (1)	10.00			
B-J	0 / 149	-18.5	-18.5	0.08 (1)	10.00			
J-I	0 / 149	-18.5	-18.5	0.12 (4)	10.00			
I-H	0 / 40	-18.5	-18.5	0.11 (4)	10.00			
H-L	0 / 149	-18.5	-18.5	0.12 (4)	10.00			
L-F	0 / 149	-18.5	-18.5	0.08 (1)	10.00			

TOTAL WEIGHT = 18 X 51 = 925 lb

DESIGN CRITERIA

SPECIFIED LOADS:

TOP CH. LL = 25.6 PSF
DL = 6.0 PSF
BOT CH. LL = 0.0 PSF
DL = 7.4 PSF
TOTAL LOAD = 39.0 PSF

SPACING = 24.0 IN. C/C

THIS TRUSS IS DESIGNED FOR RESIDENTIAL OR SMALL BUILDING REQUIREMENTS OF PART 9, NBCC 2015

THIS DESIGN COMPLIES WITH:

- PART 9 OF BCBC 2018, ABC 2019
- PART 9 OF OBC 2012 (2019 AMENDMENT)
- CSA 086-14
- TPIC 2014

(55% OF 31.3 P.S.F. G.S.L. PLUS 8.4 P.S.F. RAIN LOAD) EQUALS 25.6 P.S.F. SPECIFIED ROOF LIVE LOAD

CSI: TC=0.24/1.00 (C-D:1), BC=0.12/1.00 (I-J:4), WB=0.07/1.00 (D-H:1), SSI=0.15/1.00 (C-D:1)

DOL LUMBER=1.00 NAIL=1.00 LS BEND=1.10
COMP=1.10 SHEAR=1.10 TENS=1.10

COMPANION LIVE LOAD FACTOR = 1.00

TRUSS PLATE MANUFACTURER IS NOT RESPONSIBLE FOR QUALITY CONTROL IN THE TRUSS MANUFACTURING PLANT.

NAIL VALUES

PLATE GRIP(DRY) SHEAR SECTION
(PSI) (PLI) (PLI)
MAX MIN MAX MIN MAX MIN
MT20 650 371 1747 788 1987 1873

PLATE PLACEMENT TOL. = 0.250 inches

PLATE ROTATION TOL. = 5.0 Deg.

JSI GRIP= 0.24 (B) (INPUT = 0.90)


JSI METAL= 0.08 (E) (INPUT = 1.00)



Structural component only
DWG# T-2121149

JOB NAME 412868	TRUSS NAME PB06G	QUANTITY 4	PLY 1	JOB DESC. ROYAL PINE HOMES	DRWG NO.
Tamarack Roof Truss, Burlington					

Version 8.420 S Jan 21 2021 MiTek Industries, Inc. Thu Jul 1 10:22:29 2021 Page 1
ID:U6yi?rbeFFwxf_UFm_koDybSsJ-jChBIJWroFNH2ejHTgQ6GvQrtv2s3MitAvmNjz0TvO



LUMBER				
N. L. G. A. RULES	CHORDS	SIZE	LUMBER	DESCR.
A - E	2x4	DRY	No.2	SPF
E - I	2x4	DRY	No.2	SPF
B - H	2x4	DRY	No.2	SPF
ALL WEBS	2x3	DRY	No.2	SPF
ALL GABLE WEBS	2x3	DRY	No.2	SPF
DRY: SEASONED LUMBER.				

GABLE STUDS SPACED AT 2'-0" OC.

PLATES (table is in inches)				
JT TYPE	PLATES	W	LEN	Y X
B TMB1-I	MT20	3.0	4.0	
C, D, F, G				
C TMW+w	MT20	2.0	4.0	
E TTW-p	MT20	4.0	4.0	
H TMB1-I	MT20	3.0	4.0	
J, K, L, M, N				
J BMW1+w	MT20	2.0	4.0	

DIMENSIONS, SUPPORTS AND LOADINGS SPECIFIED BY FABRICATOR TO BE VERIFIED BY BUILDING DESIGNER

BEARINGS

THIS TRUSS DESIGNED FOR CONTINUOUS BEARINGS.

THIS TRUSS REQUIRES RIGID SHEATHING ON EXPOSED FACE.

BEARING MATERIAL TO BE SPF NO.2 OR BETTER AT JOINT(S)

BRACING

TOP CHORD TO BE SHEATHED OR MAX. PURLIN SPACING = 6.25 FT.

MAX. UNBRACED BOTTOM CHORD LENGTH = 10.00 FT OR RIGID CEILING DIRECTLY APPLIED.

ALL PITCH BREAKS AND PERIMETER CORNER JOINTS MUST BE Laterally RESTRAINED.

LOADING

TOTAL LOAD CASES: (4)

CHORDS				WEBS			
MEMB.	MAX. FACTORED FORCE (LBS)	VERT. LOAD (PLF)	MAX. FACTORED CSI (LC)	MEMB.	MAX. FACTORED FORCE (LBS)	MAX. FACTORED CSI (LC)	UNBRACED LENGTH
FR-TO		FROM TO		FR-TO			
A-B	0 / 17	-91.8 -91.8	0.05 (1)	L-E	-131 / 0	0.04 (1)	10.00
B-P	-44 / 0	-91.8 -91.8	0.02 (4)	M-D	-160 / 0	0.03 (1)	6.25
P-C	-44 / 0	-91.8 -91.8	0.13 (1)	N-C	-306 / 0	0.05 (1)	6.25
C-D	-60 / 0	-91.8 -91.8	0.13 (1)	K-F	-160 / 0	0.03 (1)	6.25
D-E	-45 / 0	-91.8 -91.8	0.05 (1)	J-G	-306 / 0	0.05 (1)	6.25
E-F	-45 / 0	-91.8 -91.8	0.05 (1)	O-P	-171 / 5	0.00 (1)	6.25
F-G	-60 / 0	-91.8 -91.8	0.13 (1)	Q-R	-171 / 5	0.00 (1)	6.25
G-R	-44 / 0	-91.8 -91.8	0.13 (1)				6.25
R-H	-44 / 0	-91.8 -91.8	0.02 (4)				6.25
H-I	0 / 17	-91.8 -91.8	0.05 (1)				10.00
B-O	0 / 49	-18.5 -18.5	0.10 (1)				10.00
O-N	0 / 49	-18.5 -18.5	0.10 (1)				10.00
N-M	0 / 39	-18.5 -18.5	0.07 (1)				10.00
M-L	0 / 36	-18.5 -18.5	0.02 (4)				10.00
L-K	0 / 36	-18.5 -18.5	0.02 (4)				10.00
K-J	0 / 39	-18.5 -18.5	0.07 (1)				10.00
J-Q	0 / 49	-18.5 -18.5	0.10 (1)				10.00
Q-H	0 / 49	-18.5 -18.5	0.10 (1)				10.00

TOTAL WEIGHT = 4 X 51 = 203 lb

DESIGN CRITERIA

SPECIFIED LOADS:

TOP CH.	LL	=	25.6	PSF
	DL	=	6.0	PSF
BOT CH.	LL	=	0.0	PSF
	DL	=	7.4	PSF
TOTAL LOAD	=	39.0	PSF	

SPACING = 24.0 IN./C

THIS TRUSS IS DESIGNED FOR RESIDENTIAL OR SMALL BUILDING REQUIREMENTS OF PART 9, NBCC 2015

THIS DESIGN COMPLIES WITH:

- PART 9 OF BCBC 2018, ABC 2019
- PART 9 OF OBC 2012 (2019 AMENDMENT)
- CSA 086-14
- TPIC 2014

(55 % OF 31.3 P.S.F. G.S.L. PLUS 8.4 P.S.F. RAIN LOAD) EQUALS 25.6 P.S.F. SPECIFIED ROOF LIVE LOAD

CSI: TC=0.13/1.00 (G-R:1), BC=0.10/1.00 (H-Q:1), WB=0.05/1.00 (G-J:1), SSI=0.14/1.00 (B-O:1)

DOL LUMBER=1.00 NAIL=1.00 LS BEND=1.10
COMP=1.10 SHEAR=1.10 TENS=1.10

COMPANION LIVE LOAD FACTOR = 1.00

TRUSS PLATE MANUFACTURER IS NOT RESPONSIBLE FOR QUALITY CONTROL IN THE TRUSS MANUFACTURING PLANT.

NAIL VALUES

PLATE GRIP(DRY)	SHEAR (PSI)	SECTION (PL)
MAX	MIN	MAX
MT20	650	371
	1747	788
	1987	1873

PLATE PLACEMENT TOL. = 0.250 inches

PLATE ROTATION TOL. = 5.0 Deg.


JSI GRIP= 0.21 (B) (INPUT = 0.90)
JSI METAL= 0.13 (G) (INPUT = 1.00)



Structural component only
DWG# T-2121150

JOB NAME 412865	TRUSS NAME PB06Z	QUANTITY 1	PLY 3	JOB DESC. ROYAL PINE HOMES	DRWG NO.
Tamarack Roof Truss, Burlington				TRUSS DESC.	

Version 8.420 S Jan 21 2021 Mitek Industries, Inc. Thu Jul 1 12:26:20 2021 Page 1
ID:U6yi?rbeFFwxf_UFm_koDybSsJ-epCPLES2nQcw3dITpEixyimNOFM9jfwWK4dWz0S5H



TOTAL WEIGHT = 3 X 51 = 154 lb [M]

LUMBER			
N. L. G. A. RULES	CHORDS	SIZE	LUMBER
A - D	2x4	DRY	No.2
D - G	2x4	DRY	No.2
B - F	2x4	DRY	No.2
ALL WEBS	2x3	DRY	No.2
DRY: SEASONED LUMBER.			

DESIGN CONSISTS OF 3 TRUSSES BUILT SEPARATELY THEN FASTENED TOGETHER AS FOLLOWS:

CHORDS #ROWS	SURFACE SPACING (IN)	LOAD(PLF)
TOP CHORDS : (0.122"x3") SPIRAL NAILS		
A - D 1 12		TOP
D - G 1 12		TOP
BOTTOM CHORDS : (0.122"x3") SPIRAL NAILS		
B - F 1 12		TOP
WEBS : (0.122"x3") SPIRAL NAILS		
2x3 1 6		

STAGGER NAILS BY HALF THE SURFACE SPACING IN ADJACENT PLIES.

TOP - COMPONENTS ARE LOADED FROM THE TOP AND MUST BE PLACED ON TOP EDGE OF ALL PLIES FOR THE LOAD TO BE TRANSFERRED TO EACH PLY.

PLATES (table is in inches)

JT	TYPE	PLATES	W	LEN	Y	X
B	TMB1-I	MT20	3.0	4.0		
C	TMW+W	MT20	2.0	4.0		
D	TTWW+p	MT20	4.0	6.0	Edge	
E	TMW+W	MT20	2.0	4.0		
F	TMB1-I	MT20	3.0	4.0		
H	BMWW1-I	MT20	4.0	4.0		
I	BMWW1-I	MT20	4.0	4.0		

Edge - INDICATES REFERENCE CORNER OF PLATE TOUCHES EDGE OF CHORD.

DIMENSIONS, SUPPORTS AND LOADINGS SPECIFIED BY FABRICATOR TO BE VERIFIED BY BUILDING DESIGNER

JT	FACTORED GROSS REACTION		MAXIMUM FACTORED GROSS REACTION		INPUT BRG	REQRD BRG
	VERT	HORZ	DOWN	HORZ		
B	340	0	340	0	15-9-6	15-9-6
F	340	0	340	0	15-9-6	15-9-6
H	610	0	610	0	15-9-6	15-9-6
I	610	0	610	0	15-9-6	15-9-6

UNFACTORED REACTIONS

1ST LCASE		MAX./MIN. COMPONENT REACTIONS					
JT	COMBINED	SNOW	LIVE	PERM.LIVE	WIND	DEAD	SOIL
B	239	166 / 0	0 / 0	0 / 0	0 / 0	73 / 0	0 / 0
F	239	166 / 0	0 / 0	0 / 0	0 / 0	73 / 0	0 / 0
H	432	283 / 0	0 / 0	0 / 0	0 / 0	149 / 0	0 / 0
I	432	283 / 0	0 / 0	0 / 0	0 / 0	149 / 0	0 / 0

BEARING MATERIAL TO BE SPF NO.2 OR BETTER AT JOINT(S) B, F, H, I

BRACING

TOP CHORD TO BE SHEATHED OR MAX. PURLIN SPACING = 6.25 FT.
MAX. UNBRACED BOTTOM CHORD LENGTH = 10.00 FT OR RIGID CEILING DIRECTLY APPLIED.

ALL PITCH BREAKS AND PERIMETER CORNER JOINTS MUST BE Laterally RESTRAINED.

LOADING

TOTAL LOAD CASES: (4)

MEMB.	CHORDS MAX. FACTORED FORCE (LBS)		FACTORED VERT. LOAD LC1 MAX (PLF)		MAX. UNBRAC LENGTH	MEMB.	WEBS MAX. FACTORED FORCE (LBS)		MAX. CSI (LC)
	FR-TO	FROM TO	FR-TO	FROM TO			FR-TO	FROM TO	
A-B	0 / 17	-91.8	-91.8	0.02 (1)	10.00	D-H	-197 / 0	0.02 (1)	
B-K	-199 / 0	-91.8	-91.8	0.02 (4)	6.25	H-E	-396 / 0	0.02 (1)	
K-C	-144 / 0	-91.8	-91.8	0.08 (1)	6.25	I-D	-197 / 0	0.02 (1)	
C-D	0 / 54	-91.8	-91.8	0.08 (1)	10.00	C-I	-396 / 0	0.02 (1)	
D-E	0 / 54	-91.8	-91.8	0.08 (1)	10.00	J-K	-68 / 57	0.00 (1)	
E-M	-144 / 0	-91.8	-91.8	0.08 (1)	6.25	L-M	-68 / 57	0.00 (1)	
M-F	-199 / 0	-91.8	-91.8	0.02 (4)	6.25				
F-G	0 / 17	-91.8	-91.8	0.02 (1)	10.00				
B-J	0 / 149	-18.5	-18.5	0.03 (1)	10.00				
J-I	0 / 149	-18.5	-18.5	0.04 (4)	10.00				
I-H	0 / 40	-18.5	-18.5	0.04 (4)	10.00				
H-L	0 / 149	-18.5	-18.5	0.04 (4)	10.00				
L-F	0 / 149	-18.5	-18.5	0.03 (1)	10.00				

DESIGN CRITERIA

SPECIFIED LOADS:

TOP CH.	LL = 25.6 PSF
	DL = 6.0 PSF
BOT CH.	LL = 0.0 PSF
	DL = 7.4 PSF
TOTAL LOAD	= 39.0 PSF

SPACING = 24.0 IN. C/C

THIS TRUSS IS DESIGNED FOR RESIDENTIAL OR SMALL BUILDING REQUIREMENTS OF PART 9, NBCC 2015

THIS DESIGN COMPLIES WITH:

- PART 9 OF CBC 2018, ABC 2019
- PART 9 OF OBC 2012 (2019 AMENDMENT)
- CSA 086-14
- TPIC 2014

(55% OF 31.3 P.S.F. G.S.L. PLUS 8.4 P.S.F. RAIN LOAD) EQUALS 25.6 P.S.F. SPECIFIED ROOF LIVE LOAD

CSI: TC=0.08/1.00 (C-D:1), BC=0.04/1.00 (I-J:4), WB=0.02/1.00 (D-I:1), SSI=0.05/1.00 (C-D:1)

DOL LUMBER=1.00 NAIL=1.00 LS BEND=1.10 COMP=1.10 SHEAR=1.10 TENS=1.10

COMPANION LIVE LOAD FACTOR = 1.00

TRUSS PLATE MANUFACTURER IS NOT RESPONSIBLE FOR QUALITY CONTROL IN THE TRUSS MANUFACTURING PLANT.


NAIL VALUES

PLATE GRIP(DRY) SHEAR SECTION	(FSI)	(PLI)	(PLI)
MAX MIN MAX MIN MAX MIN	650	371	1747
MT20	788	1987	1873

PLATE PLACEMENT TOL. = 0.250 inches

PLATE ROTATION TOL. = 5.0 Deg.

JSI GRIP= 0.08 (F) (INPUT = 0.90)
JSI METAL= 0.03 (C) (INPUT = 1.00)




Structural component only
DWG# T-2121199

JOB NAME 412865	TRUSS NAME PB101	QUANTITY 4	PLY 1	JOB DESC. ROYAL PINE HOMES	TRUSS DESC.	DRWG NO.
---------------------------	----------------------------	----------------------	-----------------	--------------------------------------	-------------	----------

Tamarack Roof Truss, Burlington

Version 8.420 S Jan 21 2021 MiTek Industries, Inc. Thu Jul 1 12:26:21 2021 Page 1
ID:hEKUVWZApjnyW9leD6V_jMya4z_6?moZaSgYkmgntfrXlxUAEExnoalOcyo9A4e9yz0S5G



Scale = 1:12.5

TOTAL WEIGHT = 4 X 16 = 64 lb [M]

LUMBER			
N. L. G. A. RULES	CHORDS	SIZE	LUMBER
A - C	2x4	DRY	No.2
C - D	2x4	DRY	No.2
E - D	2x4	DRY	No.2
B - E	2x4	DRY	No.2
ALL WEBS	2x3	DRY	No.2
DRY: SEASONED LUMBER.			

PLATES (table is in inches)					
JT	TYPE	PLATES	W	LEN	Y X
B	TMB1-t	MT20	3.0	4.0	
C	TTW-m	MT20	4.0	4.0	
D	TMVW-t	MT20	4.0	4.0	
E	BMV1+p	MT20	3.0	4.0	
F	BMVW1-t	MT20	4.0	4.0	

DIMENSIONS, SUPPORTS AND LOADINGS SPECIFIED BY FABRICATOR TO BE VERIFIED BY BUILDING DESIGNER

JT	FACTORED GROSS REACTION		MAXIMUM FACTORED GROSS REACTION		INPUT BRG	REQRD BRG
	VERT	HORZ	DOWN	HORZ		
E	76	0	76	0	4-7-11	4-7-11
B	252	0	252	0	4-7-11	4-7-11
F	264	0	264	0	4-7-11	4-7-11

UNFACTORED REACTIONS

JT	1ST LCASE COMBINED	MAX./MIN. COMPONENT REACTIONS				
		SNOW	LIVE	PERM. LIVE	WIND	DEAD
E	53	39 / 0	0 / 0	0 / 0	0 / 0	14 / 0
B	177	126 / 0	0 / 0	0 / 0	0 / 0	50 / 0
F	188	118 / 0	0 / 0	0 / 0	0 / 0	70 / 0

BEARING MATERIAL TO BE SPF NO.2 OR BETTER AT JOINT(S) E, B, F

BRACING

TOP CHORD TO BE SHEATHED OR MAX. PURLIN SPACING = 6.25 FT.
MAX. UNBRACED BOTTOM CHORD LENGTH = 10.00 FT OR RIGID CEILING DIRECTLY APPLIED.

ALL PITCH BREAKS AND PERIMETER CORNER JOINTS MUST BE Laterally RESTRAINED.

LOADING

TOTAL LOAD CASES: (4)

CHORDS				WEBS			
MEMB.	MAX. FACTORED FORCE (LBS)	FACTORED VERT. LOAD (PLF)	MAX. UNBRACED LENGTH (LC)	MEMB.	MAX. FACTORED FORCE (LBS)	MAX. UNBRACED LENGTH (LC)	
FR-TO		FROM TO		FR-TO			
A-B	0 / 17	-91.8 -91.8	0.05 (1)	10.00	F-C	-176 / 0	
B-H	-18 / 0	-91.8 -91.8	0.02 (1)	6.25	F-D	0 / 24	
H-C	-33 / 0	-91.8 -91.8	0.10 (1)	6.25	G-H	-170 / 0	
C-D	-16 / 0	-91.8 -91.8	0.04 (1)	6.25			
E-D	-90 / 0	0.0 0.0	0.01 (1)	7.81			
B-G	0 / 28	-18.5 -18.5	0.09 (1)	10.00			
G-F	0 / 28	-18.5 -18.5	0.09 (1)	10.00			
F-E	0 / 0	-18.5 -18.5	0.06 (1)	10.00			

DESIGN CRITERIA

SPECIFIED LOADS:

TOP CH.	LL	= 25.6	PSF
	DL	= 6.0	PSF
BOT CH.	LL	= 0.0	PSF
	DL	= 7.4	PSF
TOTAL LOAD = 39.0 PSF			

SPACING = 24.0 IN. C/C

LOADING IN FLAT SECTION BASED ON A SLOPE OF 2.00/12 MINIMUM

THIS TRUSS IS DESIGNED FOR RESIDENTIAL OR SMALL BUILDING REQUIREMENTS OF PART 9, NBC 2015

THIS DESIGN COMPLIES WITH:

- PART 9 OF BCBC 2018, ABC 2019
- PART 9 OF OBC 2012 (2019 AMENDMENT)
- CSA 086-14
- TPIC 2014

(55 % OF 31.3 P.S.F. G.S.L. PLUS 8.4 P.S.F. RAIN LOAD) EQUALS 25.6 P.S.F. SPECIFIED ROOF LIVE LOAD

CSI: TC=0.10/1.00 (C-H:1), BC=0.09/1.00 (F-G:1), WB=0.03/1.00 (C-F:1), SSI=0.13/1.00 (B-G:1)

DOL LUMBER=1.00 NAIL=1.00 LS BEND=1.10
COMP=1.10 SHEAR=1.10 TENS=1.10

COMPANION LIVE LOAD FACTOR = 1.00

TRUSS PLATE MANUFACTURER IS NOT RESPONSIBLE FOR QUALITY CONTROL IN THE TRUSS MANUFACTURING PLANT.


NAIL VALUES

PLATE GRIP(DRY)	SHEAR (PSI)	SECTION (PLI)
MT20	650	371
	1747	788
	1987	1873

PLATE PLACEMENT TOL. = 0.250 inches

PLATE ROTATION TOL. = 5.0 Deg.


JSI GRIP= 0.20 (B) (INPUT = 0.90)
JSI METAL= 0.06 (C) (INPUT = 1.00)



Structural component only
DWG# T-2121200

JOB NAME 412865	TRUSS NAME PB102	QUANTITY 8	PLY 1	JOB DESC. ROYAL PINE HOMES	DRWG NO.
Tamarack Roof Truss, Burlington				TRUSS DESC.	

Version 8.420 S Jan 21 2021 MiTek Industries, Inc. Thu Jul 1 12:26:22 2021 Page 1
ID:hEKUVWZApjnyW9leD6V_jMya4z_bCJAmyTJJ2sdlxSrPEHA1Nn47Bvd73byOqpBiOz0SS5F



LUMBER			
N. L. G. A. RULES	CHORDS	SIZE	LUMBER
A - C	2x4	DRY	No.2
D - C	2x4	DRY	No.2
B - D	2x4	DRY	No.2

DRY: SEASONED LUMBER.

PLATES (table is in inches)					
JT	TYPE	PLATES	W	LEN	Y X
B	TMB1-I	MT20	3.0	4.0	
C	TMV+p	MT20	3.0	4.0	
D	BMV1+p	MT20	3.0	4.0	

DIMENSIONS, SUPPORTS AND LOADINGS SPECIFIED BY FABRICATOR TO BE VERIFIED BY BUILDING DESIGNER

FACTORED		MAXIMUM FACTORED		INPUT		REQD	
GROSS REACTION		GROSS REACTION		BRG		BRG	
JT	VERT	HORZ	DOWN	HORZ	UPLIFT	IN-SX	IN-SX
D	256	0	256	0	0	4-7-11	4-7-11
B	336	0	336	0	0	4-7-11	4-7-11

UNFACTORED REACTIONS

1ST LCASE		MAX./MIN. COMPONENT REACTIONS					
JT	COMBINED	SNOW	LIVE	PERM. LIVE	WIND	DEAD	SOIL
D	181	119 / 0	0 / 0	0 / 0	0 / 0	62 / 0	0 / 0
B	236	164 / 0	0 / 0	0 / 0	0 / 0	73 / 0	0 / 0

BEARING MATERIAL TO BE SPF NO.2 OR BETTER AT JOINT(S) D, B

BRACING

TOP CHORD TO BE SHEATHED OR MAX. PURLIN SPACING = 6.25 FT.
MAX. UNBRACED BOTTOM CHORD LENGTH = 10.00 FT. OR RIGID CEILING DIRECTLY APPLIED.

ALL PITCH BREAKS AND PERIMETER CORNER JOINTS MUST BE Laterally RESTRAINED.

LOADING

TOTAL LOAD CASES: (4)

CHORDS				WEBS			
MEMB.	MAX. FACTORED FORCE (LBS)	FACTORED VERT. LOAD (PLF)	MAX. CSI (LC)	MEMB.	MAX. FACTORED FORCE (LBS)	MAX. CSI (LC)	
FR-TO		FROM TO		FR-TO			
A-B	0 / 17	-91.8 -91.8	0.05 (1)	E-F	-310 / 7	0.00 (1)	
B-F	-21 / 45	-91.8 -91.8	0.06 (1)				
F-C	-4 / 2	-91.8 -91.8	0.26 (1)				
D-C	-186 / 0	0.0 0.0	0.02 (1)				
B-E	0 / 0	-18.5 -18.5	0.18 (1)				
E-D	0 / 0	-18.5 -18.5	0.18 (1)				

TOTAL WEIGHT = 8 X 15 = 118 lb

DESIGN CRITERIA

SPECIFIED LOADS:

TOP CH.	LL	= 25.6	PSF
	DL	= 6.0	PSF
BOT CH.	LL	= 0.0	PSF
	DL	= 7.4	PSF
TOTAL LOAD	=	39.0	PSF

SPACING = 24.0 IN. C/C

THIS TRUSS IS DESIGNED FOR RESIDENTIAL OR SMALL BUILDING REQUIREMENTS OF PART 9, NBCC 2015

THIS DESIGN COMPLIES WITH:

- PART 9 OF CBC 2018, ABC 2019
- PART 9 OF OBC 2012 (2019 AMENDMENT)
- CSA 086-14
- TPIC 2014

(55 % OF 31.3 P.S.F. G.S.L. PLUS 8.4 P.S.F. RAIN LOAD) EQUALS 25.6 P.S.F. SPECIFIED ROOF LIVE LOAD

CSI: TC=0.26/1.00 (C-F:1), BC=0.18/1.00 (D-E:1), WB=0.00/1.00 (E-F:1), SS=0.25/1.00 (B-E:1)

DOL LUMBER=1.00 NAIL=1.00 LS BEND=1.10 COMP=1.10 SHEAR=1.10 TENS=1.10

COMPANION LIVE LOAD FACTOR = 1.00

TRUSS PLATE MANUFACTURER IS NOT RESPONSIBLE FOR QUALITY CONTROL IN THE TRUSS MANUFACTURING PLANT.


NAIL VALUES

PLATE	GRIP(DRY)	SHEAR	SECTION
	(PSI)	(PLI)	(PLI)
	MAX	MIN	MAX
MT20	650	371	1747
			788
			1987
			1873

PLATE PLACEMENT TOL. = 0.250 inches

PLATE ROTATION TOL. = 5.0 Deg.


JSI GRIP = 0.26 (B) (INPUT = 0.90)
JSI METAL = 0.05 (B) (INPUT = 1.00)



Structural component only
DWG# T-2121201

JOB NAME 412865	TRUSS NAME PB103G	QUANTITY 4	PLY 1	JOB DESC. ROYAL PINE HOMES	DRWG NO.
Tamarack Roof Truss, Burlington				TRUSS DESC.	

Version 8.420 S Jan 21 2021 MiTek Industries, Inc. Thu Jul 1 12:26:23 2021 Page 1
ID:hEKUVWZApinyW9leD6V_jMya4z_-3OtY_FUX4L_Uw512zyoPZbJF6bEYsWJ5cUZIErz0S5E



TOTAL WEIGHT = 4 X 26 = 102 lb [M]

LUMBER				DESCR.	
N. L. G. A. RULES	CHORDS	SIZE	LUMBER		
A - O	2x4	DRY	No.2	SPF	
O - m	2x4	DRY	No.2	SPF	
T - m	2x4	DRY	No.2	SPF	
B - T	2x4	DRY	No.2	SPF	
ALL WEBS 2x3 DRY No.2 SPF					
ALL GABLE WEBS 2x3 DRY No.2 SPF					
DRY: SEASONED LUMBER.					
GABLE STUDS SPACED AT 2'-0" OC.					

PLATES (table is in inches)					
JT	TYPE	PLATES	W	LEN	Y X
B	TMB1-I	MT20	3.0	4.0	
C	TTW-m	MT20	4.0	4.0	
D	TMW-w	MT20	2.0	4.0	
E	TMV-p	MT20	3.0	4.0	
F	BMV1-p	MT20	3.0	4.0	
G	BMW1-w	MT20	2.0	4.0	
H	BMW1-w	MT20	2.0	4.0	

DIMENSIONS, SUPPORTS AND LOADINGS SPECIFIED BY FABRICATOR TO BE VERIFIED BY BUILDING DESIGNER

BEARINGS
THIS TRUSS DESIGNED FOR CONTINUOUS BEARINGS.
THIS TRUSS REQUIRES RIGID SHEATHING ON EXPOSED FACE.
BEARING MATERIAL TO BE SPF NO.2 OR BETTER AT JOINT(S)

BRACING
TOP CHORD TO BE SHEATHED OR MAX. PURLIN SPACING = 6.25 FT.
MAX. UNBRACED BOTTOM CHORD LENGTH = 10.00 FT OR RIGID CEILING DIRECTLY APPLIED.
ALL PITCH BREAKS AND PERIMETER CORNER JOINTS MUST BE Laterally RESTRAINED.

LOADING

TOTAL LOAD CASES: (4)

CHORDS				WEBS			
MEMB.	MAX. FACTORED FORCE (LBS)	FACTORED VERT. LOAD (PLF)	MAX. UNBRACED LENGTH (LC)	MEMB.	MAX. FACTORED FORCE (LBS)	MAX. UNBRACED LENGTH (LC)	
FR-TO		FROM TO		FR-TO			
A-B	0 / 17	-91.8 -91.8	0.05 (1)	10.00	G-D	-193 / 0	0.03 (1)
B-J	-9 / 65	-91.8 -91.8	0.09 (1)	10.00	H-C	-206 / 0	0.03 (1)
J-C	-17 / 0	-91.8 -91.8	0.24 (1)	6.25	I-J	-374 / 0	0.00 (1)
C-D	0 / 0	-91.8 -91.8	0.05 (1)	10.00			
D-E	0 / 0	-91.8 -91.8	0.05 (1)	10.00			
F-E	-75 / 0	0.0 0.0	0.01 (1)	7.81			
B-I	0 / 9	-18.5 -18.5	0.20 (1)	10.00			
I-H	0 / 9	-18.5 -18.5	0.20 (1)	10.00			
I-G	0 / 0	-18.5 -18.5	0.14 (1)	10.00			
G-F	0 / 0	-18.5 -18.5	0.02 (4)	10.00			

DESIGN CRITERIA

SPECIFIED LOADS:
TOP CH. LL = 25.6 PSF
DL = 6.0 PSF
BOT CH. LL = 0.0 PSF
DL = 7.4 PSF
TOTAL LOAD = 39.0 PSF

SPACING = 24.0 IN. C/C

LOADING IN FLAT SECTION BASED ON A SLOPE OF 2.00/12 MINIMUM

THIS TRUSS IS DESIGNED FOR RESIDENTIAL OR SMALL BUILDING REQUIREMENTS OF PART 9, NBCC 2015

THIS DESIGN COMPLIES WITH:
- PART 9 OF CBC 2018, ABC 2019
- PART 9 OF OBC 2012 (2019 AMENDMENT)
- CSA 086-14
- TPIC 2014

(55 % OF 31.3 P.S.F. G.S.L. PLUS 8.4 P.S.F. RAIN LOAD) EQUALS 25.6 P.S.F. SPECIFIED ROOF LIVE LOAD

CSI: TC=0.24/1.00 (C-J:1), BC=0.20/1.00 (B-I:1), WB=0.03/1.00 (C-H:1), SS=0.28/1.00 (B-I:1)

DOL LUMBER=1.00 NAIL=1.00 LS BEND=1.10
COMP=1.10 SHEAR=1.10 TENS=1.10

COMPANION LIVE LOAD FACTOR = 1.00


TRUSS PLATE MANUFACTURER IS NOT RESPONSIBLE FOR QUALITY CONTROL IN THE TRUSS MANUFACTURING PLANT

NAIL VALUES
PLATE GRIP(DRY) SHEAR SECTION (PSI) (PLI) (PLI)
MAX MIN MAX MIN MAX MIN
MT20 650 371 1747 788 1987 1873

PLATE PLACEMENT TOL. = 0.250 inches

PLATE ROTATION TOL. = 5.0 Deg.

JSI GRIP= 0.26 (B) (INPUT = 0.90)
JSI METAL= 0.11 (C) (INPUT = 1.00)



Structural component only
DWG# T-2121202

Scale = 1:28.



DIMENSIONS, SUPPORTS AND LOADINGS SPECIFIED BY CARRIAGES TO BE EXAMINED

BEARING MATERIAL TO BE SPF NO.2 OR BETTER AT JOINT(S) B, G, K, J, L, I

BRACING
TOP CHORD TO BE SHEATHED OR MAX. PURLIN SPACING = 6.25 FT.
MAX. UNBRACED BOTTOM CHORD LENGTH = 10.00 FT OR RIGID CEILING DIRECTLY APPLIED.

ALL PITCH BREAKS AND PERIMETER CORNER JOINTS MUST BE Laterally RESTRAINED

LOADING
TOTAL LOAD CASES: (4)

DESIGN CRITERIA

SPECIFIED LOADS:

TOP	CH.	LL	=	25.6	PSF
		DL	=	6.0	PSF
BOT	CH.	LL	=	0.0	PSF
		DL	=	7.4	PSF
TOTAL LOAD				=	39.0 PSF

SPACING = 24.0 IN. C/C

LOADING IN FLAT SECTION BASED ON A SLOPE
OF 2.00/12 MINIMUM

THIS TRUSS IS DESIGNED FOR RESIDENTIAL OR
SMALL BUILDING REQUIREMENTS OF PART 9,
NBCC 2015

THIS DESIGN COMPLIES WITH:

- PART 9 OF BCBC 2018 , ABC 2019
- PART 9 OF OBC 2012 (2019 AMENDMENT)
- CSA 086-14
- TPIC 2014

(55 % OF 31.3 P.S.F. G.S.L. PLUS 8.4 P.S.F. RAIN LOAD) EQUALS 25.6 P.S.F. SPECIFIED ROOF LIVE LOAD.

CSI: TC=0.19/1.00 (F-P:1), BC=0.06/1.00 (K-L:4), WB=0.05/1.00 (E-J:1), SSI=0.15/1.00 (E-F:1)

DOL LUMBER=1.00 NAIL=1.00 LS BEND=1.10
COMP=1.10 SHEAR=1.10 TENS= 1.10

COMPANION LIVE LOAD FACTOR = 1.00

TRUSS PLATE MANUFACTURER IS NOT RESPONSIBLE FOR QUALITY CONTROL IN THE TRUSS MANUFACTURING PLANT

NAIL VALUES						
PLATE	GRIP(DRY)		SHEAR		SECTION	
	(PSI)		(PLI)		(PLI)	
	MAX	MIN	MAX	MIN	MAX	MIN
MT20	650	371	1747	788	1987	1873

PLATE PLACEMENT TOL. = 0.250 inches


PLATE ROTATION TOL. = 5.0 Deg.

JSI GRIP= 0.30 (C) (INPUT = 0.90)
JSI METAL= 0.09 (E) (INPUT = 1.00)



JOB NAME 412865	TRUSS NAME PB105G	QUANTITY 2	PLY 1	JOB DESC. ROYAL PINE HOMES	DRWG NO.
Tamarack Roof Truss, Burlington				TRUSS DESC.	

Version 8.420 S Jan 21 2021 MiTek Industries, Inc. Thu Jul 1 12:26:24 2021 Page 1
ID:hEKUVWZApjnyW9leD6V_jMya4z_-XaRwBbVZrf6LXEcEXfJe6osP7?ZKbzOf8lImHz0S5D



LUMBER					DESCR.
N. L. G. A. RULES	CHORDS	SIZE	LUMBER		
A - B	2x4	DRY	No.2	SPF	
B - D	2x4	DRY	No.2	SPF	
E - D	2x4	DRY	No.2	SPF	
A - E	2x4	DRY	No.2	SPF	
ALL WEBS 2x3 DRY					No.2
DRY: SEASONED LUMBER.					SPF

PLATES (table is in inches)					
JT	TYPE	PLATES	W	LEN	Y X
A	TBM1-h	MT20	3.0	4.0	
B	TTW-m	MT20	4.0	4.0	
C	TMW-w	MT20	2.0	4.0	
D	TMV-p	MT20	3.0	4.0	
E	BMV1-p	MT20	3.0	4.0	
F	BMW1-w	MT20	2.0	4.0	
G	BMW1-w	MT20	2.0	4.0	

DIMENSIONS, SUPPORTS AND LOADINGS SPECIFIED BY FABRICATOR TO BE VERIFIED BY BUILDING DESIGNER

BEARINGS		FACTORED		MAXIMUM FACTORED		INPUT		REQ'D	
JT	GROSS REACTION	VERT	HORZ	DOWN	HORZ	UPLIFT	IN-SX	BRG	IN-SX
A	272	0	272	0	0	8-6-8	-8-6-8	8-6-8	8-6-8
E	65	0	65	0	0	8-6-8	8-6-8	8-6-8	8-6-8
G	502	0	502	0	0	8-6-8	8-6-8	8-6-8	8-6-8
F	103	0	103	0	0	8-6-8	8-6-8	8-6-8	8-6-8

UNFACTORED REACTIONS

1ST LCASE		MAX./MIN. COMPONENT REACTIONS						
JT	COMBINED	SNOW	LIVE	PERM. LIVE	WIND	DEAD	SOIL	
A	192	128 / 0	0 / 0	0 / 0	0 / 0	64 / 0	0 / 0	
E	46	27 / 0	0 / 0	0 / 0	0 / 0	19 / 0	0 / 0	
G	357	224 / 0	0 / 0	0 / 0	0 / 0	132 / 0	0 / 0	
F	71	57 / 0	0 / 0	0 / 0	0 / 0	14 / 0	0 / 0	

BEARING MATERIAL TO BE SPF NO.2 OR BETTER AT JOINT(S) A, E, G, F

BRACING

TOP CHORD TO BE SHEATHED OR MAX. PURLIN SPACING = 6.25 FT.
MAX. UNBRACED BOTTOM CHORD LENGTH = 6.25 FT OR RIGID CEILING DIRECTLY APPLIED.

ALL PITCH BREAKS AND PERIMETER CORNER JOINTS MUST BE Laterally RESTRAINED.

LOADING

TOTAL LOAD CASES: (4)

CHORDS				WEBS			
MEMB.	MAX. FACTORED FORCE (LBS)	FACTORED VERT. LOAD (PLF)	MAX LC1 MAX CSI (LC)	MEMB.	MAX. FACTORED FORCE (LBS)	MAX LC1 MAX CSI (LC)	
FR-TO		FROM TO		FR-TO			
A-I	-14 / 0	-91.8 -91.8	0.05 (4)	G-B	-270 / 0	0.04 (1)	
I-B	-13 / 0	-91.8 -91.8	0.29 (1)	F-C	-199 / 0	0.03 (1)	
B-C	0 / 0	-91.8 -91.8	0.05 (1)	H-I	-238 / 0	0.00 (1)	
C-D	0 / 0	-91.8 -91.8	0.05 (1)				
E-D	-20 / 0	0.0 0.0	0.00 (1)				
A-H	-17 / 0	-18.5 -18.5	0.29 (1)				
H-G	0 / 12	-18.5 -18.5	0.29 (1)				
G-F	0 / 0	-18.5 -18.5	0.20 (1)				
F-E	0 / 0	-18.5 -18.5	0.05 (1)				

DESIGN CRITERIA

SPECIFIED LOADS:

TOP CH.	LL = 25.6 PSF
	DL = 6.0 PSF
BOT CH.	LL = 0.0 PSF
	DL = 7.4 PSF
TOTAL LOAD	= 39.0 PSF

SPACING = 24.0 IN. C/C

LOADING IN FLAT SECTION BASED ON A SLOPE OF 2.00/12 MINIMUM

THIS TRUSS IS DESIGNED FOR RESIDENTIAL OR SMALL BUILDING REQUIREMENTS OF PART 9, NBCC 2015

THIS DESIGN COMPLIES WITH:

- PART 9 OF BCBC 2018, ABC 2019
- PART 9 OF OBC 2012 (2019 AMENDMENT)
- CSA 086-14
- TPIC 2014

(55 % OF 31.3 P.S.F. G.S.L. PLUS 8.4 P.S.F. RAIN LOAD) EQUALS 25.6 P.S.F. SPECIFIED ROOF LIVE LOAD

CSI: TC=0.29/1.00 (B-I:1), BC=0.29/1.00 (G-H:1), WB=0.04/1.00 (B-G:1), SS=0.17/1.00 (A-H:1)

DOL LUMBER=1.00 NAIL=1.00 LS BEND=1.10 COMP=1.10 SHEAR=1.10 TENS=1.10

COMPANION LIVE LOAD FACTOR = 1.00

TRUSS PLATE MANUFACTURER IS NOT RESPONSIBLE FOR QUALITY CONTROL IN THE TRUSS MANUFACTURING PLANT

NAIL VALUES

PLATE GRIP(DRY)	SHEAR (PSI)	SECTION (PLI)
MAX MIN	MAX MIN	MAX MIN
MT20	650 371	1747 788

PLATE PLACEMENT TOL. = 0.250 inches

PLATE ROTATION TOL. = 5.0 Deg.

JSI GRIP= 0.22 (B) (INPUT = 0.90)


JSI METAL= 0.12 (B) (INPUT = 1.00)



Structural component only
DWG# T-2121204

JOB NAME 412868	TRUSS NAME J01	QUANTITY 20	PLY 1	JOB DESC. ROYAL PINE HOMES	DRWG NO.
Tamarack Roof Truss, Burlington				TRUSS DESC.	

Version 8.420 S Jan 21 2021 MITek Industries, Inc. Thu Jul 1 10:22:22 2021 Page 1
ID:U6yi?rbeFFwxf_UFm_koDybSsJ-QsmYHwRSR5VHjZhXZioTureZH4eowBkrZJZVZdz0Tvv



TOTAL WEIGHT = 20 X 17 = 336 lb

LUMBER			
N. L. G. A. RULES	CHORDS	SIZE	LUMBER
E - B	2x4	DRY	No.2
A - C	2x4	DRY	No.2
E - D	2x4	DRY	No.2

DRY: SEASONED LUMBER.

PLATES (table is in inches)

JT	TYPE	PLATES	W	LEN	Y	X
B	TMV+p	MT20	3.0	4.0		
E	BMV1+p	MT20	3.0	4.0		

DIMENSIONS, SUPPORTS AND LOADINGS SPECIFIED BY FABRICATOR TO BE VERIFIED BY BUILDING DESIGNER

JT	FACTORED GROSS REACTION		MAXIMUM FACTORED GROSS REACTION		INPUT BRG		REQD BRG	
	VERT	HORZ	DOWN	HORZ	UPLIFT	IN-SX	IN-SX	
E	525	0	525	0	0	5-8	5-8	
C	202	0	202	0	0	1-8	1-8	
D	45	0	50	0	0	1-8	1-8	

SEE MITEK STANDARD DETAIL B97791H FOR CONNECTION TO JOINT(S) C, D

UNFACTORED REACTIONS

JT	1ST LOASE	MAX./MIN. COMPONENT REACTIONS	PERM. LIVE	WIND	DEAD	SOIL
E	369	257 / 0	0 / 0	0 / 0	111 / 0	0 / 0
C	139	113 / 0	0 / 0	0 / 0	26 / 0	0 / 0
D	36	0 / 0	0 / 0	0 / 0	36 / 0	0 / 0

BEARING MATERIAL TO BE SPF NO.2 OR BETTER AT JOINT(S) E, C

BRACING

TOP CHORD TO BE SHEATHED OR MAX. PURLIN SPACING = 6.25 FT.
MAX. UNBRACED BOTTOM CHORD LENGTH = 10.00 FT OR RIGID CEILING DIRECTLY APPLIED.

ALL PITCH BREAKS AND PERIMETER CORNER JOINTS MUST BE Laterally RESTRAINED.

LOADING

TOTAL LOAD CASES: (4)

MEMB.	CHORDS		FACTORED		WEBS		MAX. FACTORED	
	FORCE (LBS)	VERT. LOAD (PLF)	LC1	MAX	MEMB. UNBRAC LENGTH	FR-TO	FORCE (LBS)	MAX
FR-TO		FROM	TO	CSI (LC)				
E-B	-461 / 0	0.0	0.0	0.13 (4)	7.81			
A-B	0 / 28	-91.8	-91.8	0.12 (1)	10.00			
B-C	-30 / 0	-91.8	-91.8	0.54 (1)	6.25			
E-D	0 / 0	-18.5	-18.5	0.13 (4)	10.00			

DESIGN CRITERIA

SPECIFIED LOADS:

TOP CH.	LL = 25.6 PSF
DL = 6.0 PSF	
BOT CH.	LL = 0.0 PSF
DL = 7.4 PSF	
TOTAL LOAD = 39.0 PSF	

SPACING = 24.0 IN/C/C

THIS TRUSS IS DESIGNED FOR RESIDENTIAL OR SMALL BUILDING REQUIREMENTS OF PART 9, NBCC 2015

THIS DESIGN COMPLIES WITH:

- PART 9 OF BCBC 2018, ABC 2019
- PART 9 OF OBC 2012 (2019 AMENDMENT)
- CSA 086-14
- TPIC 2014

DESIGN ASSUMPTIONS

- OVERHANG NOT TO BE ALTERED OR CUT OFF.

(55 % OF 31.3 P.S.F. G.S.L. PLUS 8.4 P.S.F. RAIN LOAD) EQUALS 25.6 P.S.F. SPECIFIED ROOF LIVE LOAD

ALLOWABLE DEFL.(LL)= L/360 (0.20")
CALCULATED VERT. DEFL.(LL) = L/999 (0.00")
ALLOWABLE DEFL.(TL)= L/360 (0.20")
CALCULATED VERT. DEFL.(TL) = L/999 (0.03")

CSI: TC=0.54/1.00 (B-C:1), BC=0.13/1.00 (D-E:4),
WB=0.00/1.00 (n/a:0), SSI=0.24/1.00 (B-C:1)

DOL LUMBER=1.00 NAIL=1.00 LS BEND=1.10
COMP=1.10 SHEAR=1.10 TENS=1.10

COMPANION LIVE LOAD FACTOR = 1.00

AUTOSOLVE RIGHT HEEL ONLY

TRUSS PLATE MANUFACTURER IS NOT RESPONSIBLE FOR QUALITY CONTROL IN THE TRUSS MANUFACTURING PLANT.

NAIL VALUES

PLATE	GRIP(DRY)	SHEAR	SECTION
(PSI)	(PLI)	(PLI)	
MAX	MIN	MAX	MIN
MT20	650	371	1747
		788	1987
			1873

PLATE PLACEMENT TOL. = 0.250 inches

PLATE ROTATION TOL. = 5.0 Deg.

JSI GRIP = 0.18 (E) (INPUT = 0.90)


JSI METAL = 0.13 (B) (INPUT = 1.00)



Structural component only
DWG# T-2121142

JOB NAME 412868	TRUSS NAME J02	QUANTITY 20	PLY 1	JOB DESC. ROYAL PINE HOMES	DRWG NO.
Tamarack Roof Truss, Burlington		TRUSS DESC.			

Version 8.420 S Jan 21 2021 Mitek Industries, Inc. Thu Jul 1 10:22:23 2021 Page 1
ID:U6yi?rbeFFwxf_UFm_koDybSsJ-v3KwUGR4CPd8KJF77QJi1eAm9Uyafe?nzJ354z0TvU



LUMBER
N. L. G. A. RULES
CHORDS SIZE LUMBER
A - C 2x4 DRY No.2
B - D 2x4 DRY No.2
DRY: SEASONED LUMBER.

PLATES (table is in inches)
JT TYPE PLATES W LEN Y X
B TMB1-I MT20 3.0 4.0

DIMENSIONS, SUPPORTS AND LOADINGS SPECIFIED BY FABRICATOR TO BE VERIFIED BY BUILDING DESIGNER

JT	FACTORED GROSS REACTION		MAXIMUM FACTORED GROSS REACTION		INPUT BRG IN-SX	REQD BRG IN-SX
	VERT	HORZ	DOWN	HORZ - UPLIFT		
C	233	0	233	121	-113	1-8
B	444	0	444	0	-308	5-8
D	88	0	88	0	-107	5-8

SEE MITEK STANDARD DETAIL B97791H FOR CONNECTION TO JOINT(S) C

PROVIDE ANCHORAGE AT BEARING JOINT C FOR 150 LBS FACTORED UPLIFT
PROVIDE ANCHORAGE AT BEARING JOINT B FOR 308 LBS FACTORED UPLIFT
PROVIDE ANCHORAGE AT BEARING JOINT D FOR 150 LBS FACTORED UPLIFT

PROVIDE FOR 121 LBS FACTORED HORIZONTAL REACTION AT JOINT C

UNFACTORED REACTIONS

JT	1ST CASE COMBINED		MAX./MIN. COMPONENT REACTIONS		WIND	DEAD	SOIL
	SNOW	LIVE	PERM. LIVE	WIND			
C	181	125 / 0	0 / 0	0 / 0	0 / -104	36 / 0	0 / 0
B	312	217 / 0	0 / 0	0 / 0	0 / -281	94 / 0	0 / 0
D	66	24 / 0	0 / 0	0 / 0	0 / -103	42 / 0	0 / 0

HORIZONTAL REACTIONS

C	0 / 0	0 / 0	0 / 0	86 / 0	0 / 0	0 / 0
---	-------	-------	-------	--------	-------	-------

BEARING MATERIAL TO BE SPF NO.2 OR BETTER AT JOINT(S) B, D

BRACING

TOP CHORD TO BE SHEATHED OR MAX. PURLIN SPACING = 6.25 FT.
MAX. UNBRACED BOTTOM CHORD LENGTH = 10.00 FT OR RIGID CEILING DIRECTLY APPLIED.

ALL PITCH BREAKS AND PERIMETER CORNER JOINTS MUST BE Laterally RESTRAINED.

LOADING

TOTAL LOAD CASES: (12)

MEMB.	CHORDS MAX. FACTORED FORCE (LBS)		FACTORED VERT. LOAD LC1 MAX (PLF)		MAX. UNBRACED LENGTH FR-TO	WEBS MAX. FACTORED FORCE (LBS)		MAX. UNBRACED LENGTH FR-TO
	FR-TO	TO	FR-TO	TO		FR-TO	TO	
A-B	0 / 16	-91.8	-91.8	0.11 (1)	10.00	E-F	-308 / 100	0.00 (1)
B-F	-17 / 44	-91.8	-91.8	0.08 (12)	6.25			
F-C	0 / 77	-91.8	-91.8	0.40 (1)	10.00			
B-E	0 / 0	-18.5	-18.5	0.29 (1)	10.00			
E-D	0 / 0	-18.5	-18.5	0.29 (1)	10.00			

WIND LOAD APPLIED IS DERIVED FROM REFERENCE VELOCITY PRESSURE OF (9.2) PSF AT (15-0-0) FT-IN-SX REFERENCE HEIGHT ABOVE GRADE AND USING EXTERNAL PEAK COEFFICIENTS, CpCg, BASED ON THE (MAIN WIND FORCE RESISTING SYSTEM). INTERNAL WIND PRESSURE IS BASED ON DESIGN (CATEGORY 2). BUILDING MAY BE LOCATED ON (OPEN TERRAIN), AND TRUSS IS DESIGNED TO BE LOCATED AT LEAST (0-0) FT-IN-SX AWAY FROM EAVE. TRUSS UPLIFT IS BASED ON TOP AND BOTTOM CHORD DEAD LOADS OF 6.0 PSF AND 7.4 PSF RESPECTIVELY.

DESIGN CRITERIA

SPECIFIED LOADS:

TOP CH. LL = 25.6 PSF
DL = 6.0 PSF
BOT CH. LL = 0.0 PSF
DL = 7.4 PSF
TOTAL LOAD = 39.0 PSF

SPACING = 24.0 IN./C

THIS TRUSS IS DESIGNED FOR RESIDENTIAL OR SMALL BUILDING REQUIREMENTS OF PART 9, NBCC 2015

THIS DESIGN COMPLIES WITH:

- PART 9 OF BCBC 2018, ABC 2019
- PART 9 OF OBC 2012 (2019 AMENDMENT)
- CSA 086-14
- TPIC 2014

(55% OF 31.3 P.S.F. G.S.L. PLUS 8.4 P.S.F. RAIN LOAD) EQUALS 25.6 P.S.F. SPECIFIED ROOF LIVE LOAD

ALLOWABLE DEFL.(LL) = L/360 (0.19")
CALCULATED VERT. DEFL.(LL) = L/684 (0.10")
ALLOWABLE DEFL.(TL) = L/360 (0.19")
CALCULATED VERT. DEFL.(TL) = L/496 (0.14")

CSI: TC=0.40/1.00 (C-F:1), BC=0.29/1.00 (D-E:1), WB=0.00/1.00 (E-F:1), SS=0.24/1.00 (B-E:1)

DOL LUMBER=1.00 NAIL=1.00 LS BEND=1.10
COMP=1.10 SHEAR=1.10 TENS=1.10

COMPANION LIVE LOAD FACTOR = 1.00

TRUSS PLATE MANUFACTURER IS NOT RESPONSIBLE FOR QUALITY CONTROL IN THE TRUSS MANUFACTURING PLANT.

NAIL VALUES

PLATE GRIP(DRY) SHEAR SECTION (PSI) (PLI) (PLI)
MAX MIN MAX MIN MAX MIN
MT20 650 371 1747 788 1987 1873

PLATE PLACEMENT TOL. = 0.250 inches

PLATE ROTATION TOL. = 5.0 Deg.

JSI GRIP= 0.28 (B) (INPUT = 0.90)
JSI METAL= 0.08 (B) (INPUT = 1.00)




Structural component only
DWG# T-2121143

JOB NAME 412868	TRUSS NAME J03	QUANTITY 15	PLY 1	JOB DESC. ROYAL PINE HOMES	DRWG NO.
Tamarack Roof Truss, Burlington				TRUSS DESC.	

Version 8.420 S Jan 21 2021 MITek Industries, Inc. Thu Jul 1 10:22:24 2021 Page 1
ID:U6yi?rbeFFwxf_UFm_koDybSsJ-NFulicSizl?ytqKh7qxZsj_uuLTO5E80d2cdWz0TvT

Scale = 1:10.3



TOTAL WEIGHT = 15 X 10 = 151 lb [M]

LUMBER				
N. L. G. A. RULES				
CHORDS	SIZE	DRY	LUMBER	DESCR.
A - C	2x4	DRY	No.2	SPF
B - D	2x4	DRY	No.2	SPF
DRY: SEASONED LUMBER.				

PLATES (table is in inches)				
JT TYPE	PLATES	W	LEN	Y X
B TMB1-1	MT20	3.0	4.0	

DIMENSIONS, SUPPORTS AND LOADINGS SPECIFIED BY FABRICATOR TO BE VERIFIED BY BUILDING DESIGNER

BEARINGS		FACTORED GROSS REACTION	MAXIMUM FACTORED GROSS REACTION	INPUT BRG	REQD BRG
JT	VERT	HORZ	DOWN	HORZ	UPLIFT
C	141	0	141	0	0
B	320	0	320	0	0
D	57	0	57	0	0

VALUE IN PARENTHESIS INDICATES EFFECTIVE BEARING LENGTH

BEVELED PLATE OR SHIM REQUIRED TO PROVIDE FULL BEARING SURFACE WITH TRUSS CHORD AT JT(S): C

UNFACTORED REACTIONS

JT	1ST LCASE	MAX. MIN. COMPONENT REACTIONS	SNOW	LIVE	PERM. LIVE	WIND	DEAD	SOIL
C	98	76 / 0	0 / 0	0 / 0	0 / 0	0 / 0	22 / 0	0 / 0
B	224	160 / 0	0 / 0	0 / 0	0 / 0	0 / 0	64 / 0	0 / 0
D	42	16 / 0	0 / 0	0 / 0	0 / 0	0 / 0	26 / 0	0 / 0

BEARING MATERIAL TO BE SPF NO.2 OR BETTER AT JOINT(S) C, B, D

BRACING

TOP CHORD TO BE SHEATHED OR MAX. PURLIN SPACING = 6.25 FT.
MAX. UNBRACED BOTTOM CHORD LENGTH = 10.00 FT OR RIGID CEILING DIRECTLY APPLIED.

ALL PITCH BREAKS AND PERIMETER CORNER JOINTS MUST BE Laterally RESTRAINED.

LOADING

TOTAL LOAD CASES: (5)

CHORDS		WEBS	
MEMB.	MAX. FACTORED FORCE (LBS)	FACTORED VERT. LOAD (PLF)	MAX. FACTORED UNBRACED LENGTH (FT)
FR-TO			
A-B	0 / 18	-91.8 -91.8 0.13 (5)	10.00
B-F	-10 / 0	-91.8 -91.8 0.04 (4)	6.25
F-C	0 / 2	-91.8 -91.8 0.15 (1)	10.00
B-E	0 / 0	-18.5 -18.5 0.12 (1)	10.00
E-D	0 / 0	-18.5 -18.5 0.12 (1)	10.00

CANTILEVER ANALYSIS HAS BEEN CONSIDERED IN THIS DESIGN

DESIGN CRITERIA

SPECIFIED LOADS:

TOP CH.	LL = 25.6 PSF
DL = 8.0 PSF	
BOT CH.	LL = 0.0 PSF
DL = 7.4 PSF	
TOTAL LOAD = 39.0 PSF	

SPACING = 24.0 IN. C/C

THIS TRUSS IS DESIGNED FOR RESIDENTIAL OR SMALL BUILDING REQUIREMENTS OF PART 9, NBCC 2015

THIS DESIGN COMPLIES WITH:

- PART 9 OF CBC 2018, ABC 2019
- PART 9 OF OBC 2012 (2019 AMENDMENT)
- CSA 086-14
- TPIC 2014

(55% OF 31.3 P.S.F. G.S.L. PLUS 8.4 P.S.F. RAIN LOAD) EQUALS 25.6 P.S.F. SPECIFIED ROOF LIVE LOAD

ALLOWABLE DEFL.(LL) = L/360 (0.19")
CALCULATED VERT. DEFL.(LL) = L/999 (0.01")
ALLOWABLE DEFL.(TL) = L/360 (0.19")
CALCULATED VERT. DEFL.(TL) = L/999 (0.02")

CSI: TC=0.15/1.00 (C-F:1), BC=0.12/1.00 (B-E:1),
WB=0.00/1.00 (E-F:1), SS=0.11/1.00 (B-E:1)

DOL LUMBER=1.00 NAIL=1.00 LS BEND=1.10
COMP=1.10 SHEAR=1.10 TENS=1.10

COMPANION LIVE LOAD FACTOR = 1.00

TRUSS PLATE MANUFACTURER IS NOT RESPONSIBLE FOR QUALITY CONTROL IN THE TRUSS MANUFACTURING PLANT.

NAIL VALUES

PLATE	GRIP(DRY)	SHEAR	SECTION
(PSI)	(PLI)	(PLI)	
MAX	MIN	MAX	MIN
MT20	650	371	1747
	788	1987	1873

PLATE PLACEMENT TOL. = 0.250 inches

PLATE ROTATION TOL. = 5.0 Deg.

JSI GRIP= 0.20 (B) (INPUT = 0.90)
JSI METAL= 0.05 (B) (INPUT = 1.00)




Structural component only
DWG# T-2121144

JOB NAME 412865	TRUSS NAME J11	QUANTITY 5	PLY 1	JOB DESC. ROYAL PINE HOMES	TRUSS DESC.	DRWG NO.
---------------------------	--------------------------	----------------------	-----------------	--------------------------------------	-------------	----------

Tamarack Roof Truss, Burlington

Version 8.420 S Jan 21 2021 Mitek Industries, Inc. Thu Jul 1 12:26:13 2021 Page 1
ID:hEKUVWZApjnyW9leD6V_iMya4z_LTHmtrMfRHjvYg7Nrc39UvZMZsxW?MdJw8DtQz0S50



TOTAL WEIGHT = 5 X 8 = 39 lb [M]

LUMBER			
N. L. G. A. RULES	SIZE	DRY	LUMBER
E - B	2x4	DRY	No.2
A - C	2x4	DRY	No.2
E - D	2x4	DRY	No.2

DRY: SEASONED LUMBER.

PLATES (table is in inches)

JT	TYPE	PLATES	W	LEN	Y	X
B	TMV+p	MT20	3.0	4.0		
E	BMV1+p	MT20	3.0	4.0		

DIMENSIONS, SUPPORTS AND LOADINGS SPECIFIED BY FABRICATOR TO BE VERIFIED BY BUILDING DESIGNER

BEARINGS							
JT	FACTORED GROSS REACTION		MAXIMUM FACTORED GROSS REACTION			INPUT BRG	REQRD BRG
	VERT	HORZ	DOWN	HORZ	UPLIFT	IN-SX	IN-SX
E	260	0	260	0	0	5-8	5-8
C	66	0	66	0	0	1-8	1-8
D	23	0	26	0	0	1-8	1-8

SEE MITEK STANDARD DETAIL B97791H FOR CONNECTION TO JOINT(S) C, D

UNFACTORED REACTIONS

JT	1ST LCASE COMBINED	MAX./MIN. COMPONENT REACTIONS					SOIL
		SNOW	LIVE	PERM. LIVE	WIND	DEAD	
E	182	130 / 0	0 / 0	0 / 0	0 / 0	52 / 0	0 / 0
C	46	37 / 0	0 / 0	0 / 0	0 / 0	9 / 0	0 / 0
D	18	0 / 0	0 / 0	0 / 0	0 / 0	18 / 0	0 / 0

BEARING MATERIAL TO BE SPF NO.2 OR BETTER AT JOINT(S) E, C

BRACING

TOP CHORD TO BE SHEATHED OR MAX. PURLIN SPACING = 10.00 FT.
MAX. UNBRACED BOTTOM CHORD LENGTH = 10.00 FT OR RIGID CEILING DIRECTLY APPLIED.

ALL PITCH BREAKS AND PERIMETER CORNER JOINTS MUST BE Laterally RESTRAINED.

LOADING

TOTAL LOAD CASES: (5)

CHORDS				WEBS			
MEMB.	MAX. FACTORED FORCE (LBS)	FACTORED VERT. LOAD (PLF)	MAX. FACTORED UNBRACED LENGTH (LC)	MEMB.	MAX. FACTORED FORCE (LBS)	MAX. FACTORED UNBRACED LENGTH (LC)	
FR-TO		FROM	TO	FR-TO			
E-B	-234 / 0	0.0	0.0	0.02 (4)	7.81		
A-B	0 / 28	-91.8	-91.8	0.13 (5)	10.00		
B-C	-10 / 0	-91.8	-91.8	0.06 (1)	10.00		
E-F	0 / 0	-18.5	-18.5	0.03 (4)	10.00		
F-D	0 / 0	-18.5	-18.5	0.03 (4)	10.00		

SPECIFIED CONCENTRATED LOADS (LBS)

JT	LOC.	LC1	MAX-	MAX+	FACE	DIR.	TYPE	HEEL	CONN.
F	2-0-12	-3	-3	---	BACK	VERT	TOTAL	---	C1

CONNECTION REQUIREMENTS

1) C1: A SUITABLE HANGER/MECHANICAL CONNECTION IS REQUIRED.

CANTILEVER ANALYSIS HAS BEEN CONSIDERED IN THIS DESIGN

DESIGN CRITERIA

SPECIFIED LOADS:

TOP CH. LL = 25.6 PSF
DL = 6.0 PSF
BOT CH. LL = 0.0 PSF
DL = 7.4 PSF
TOTAL LOAD = 39.0 PSF

SPACING = 24.0 IN/C

THIS TRUSS IS DESIGNED FOR RESIDENTIAL OR SMALL BUILDING REQUIREMENTS OF PART 9, NBCC 2015

THIS DESIGN COMPLIES WITH:

- PART 9 OF BCBC 2018, ABC 2019
- PART 9 OF OBC 2012 (2019 AMENDMENT)
- CSA 086-14
- TPIC 2014

DESIGN ASSUMPTIONS

- OVERHANG NOT TO BE ALTERED OR CUT OFF.

(55 % OF 31.3 P.S.F. G.S.L. PLUS 8.4 P.S.F. RAIN LOAD) EQUALS 25.6 P.S.F. SPECIFIED ROOF LIVE LOAD

ALLOWABLE DEFL.(LL)= L/360 (0.19")
CALCULATED VERT. DEFL.(LL) = L/999 (0.00")
ALLOWABLE DEFL.(TL)= L/360 (0.19")
CALCULATED VERT. DEFL.(TL) = L/999 (0.00")

CSI: TC=0.13/1.00 (A-B-5), BC=0.03/1.00 (D-E-4),
WB=0.00/1.00 (n/a-0), SSI=0.09/1.00 (A-B-5)

DOL LUMBER=1.00 NAIL=1.00 LS BEND=1.10
COMP=1.10 SHEAR=1.10 TENS= 1.10

COMPANION LIVE LOAD FACTOR = 1.00

AUTOSOLVE RIGHT HEEL ONLY

TRUSS PLATE MANUFACTURER IS NOT RESPONSIBLE FOR QUALITY CONTROL IN THE TRUSS MANUFACTURING PLANT.

NAIL VALUES

PLATE	GRIP(DRY)	SHEAR	SECTION
(PSI)	(PLI)	(PLI)	(PLI)
MAX	MIN	MAX	MIN
MT20	650	371	1747
		788	1987

PLATE PLACEMENT TOL = 0.250 inches

PLATE ROTATION TOL = 5.0 Deg.

JSI GRIP= 0.09 (E) (INPUT = 0.90)


JSI METAL= 0.06 (B) (INPUT = 1.00)



Structural component only
DWG# T-2121191

JOB NAME 412865	TRUSS NAME J12	QUANTITY 7	PLY 1	JOB DESC. ROYAL PINE HOMES	DRWG NO.
Tamarack Roof Truss, Burlington				TRUSS DESC.	

Version 8.420 S Jan 21 2021 MiTek Industries, Inc. Thu Jul 1 12:26:14 2021 Page 1
ID:hEKUVWZApjnyW9leD6V_jMya4z_qfr85ANHCarmlirJxZ7lihSkBzCBFScmYatmPsz0SSN



TOTAL WEIGHT = 7 X 9 = 60 lb

LUMBER			
N. L. G. A. RULES			
CHORDS	SIZE	DRY	LUMBER
E - B	2x4	DRY	No.2
A - C	2x4	DRY	No.2
E - D	2x4	DRY	No.2

DRY: SEASONED LUMBER.

PLATES (table is in inches)				
JT	TYPE	PLATES	W	LEN Y X
B	TMV+p	MT20	3.0	4.0
E	BMV1+p	MT20	3.0	4.0

DIMENSIONS, SUPPORTS AND LOADINGS SPECIFIED BY FABRICATOR TO BE VERIFIED BY BUILDING DESIGNER

JT	FACTORED GROSS REACTION		MAXIMUM FACTORED GROSS REACTION		INPUT BRG		REQD BRG	
	VERT	HORZ	DOWN	HORZ	UPLIFT	IN-SX	IN-SX	
E	291	0	291	0	0	5-8	5-8	
C	85	0	85	0	0	1-8	1-8	
D	20	0	22	0	0	1-8	1-8	

SEE MITEK STANDARD DETAIL B97791H FOR CONNECTION TO JOINT(S) C, D

UNFACTORED REACTIONS

JT	1ST LCASE		MAX/MIN. COMPONENT REACTIONS		WIND	DEAD	SOIL
	COMBINED	SNOW	LIVE	PERM. LIVE			
E	203	148 / 0	0 / 0	0 / 0	0 / 0	55 / 0	0 / 0
C	58	47 / 0	0 / 0	0 / 0	0 / 0	11 / 0	0 / 0
D	16	0 / 0	0 / 0	0 / 0	0 / 0	16 / 0	0 / 0

BEARING MATERIAL TO BE SPF NO.2 OR BETTER AT JOINT(S) E

BRACING

TOP CHORD TO BE SHEATHED OR MAX. PURLIN SPACING = 6.25 FT.
MAX. UNBRACED BOTTOM CHORD LENGTH = 10.00 FT OR RIGID CEILING DIRECTLY APPLIED.

ALL PITCH BREAKS AND PERIMETER CORNER JOINTS MUST BE Laterally RESTRAINED.

LOADING

TOTAL LOAD CASES: (5)

MEMB.	CHORDS		WEBS	
	MAX. FACTORED FORCE (LBS)	FACTORED VERT. LOAD (PLF)	MAX. FACTORED FORCE (LBS)	FACTORED VERT. LOAD (PLF)
FR-TO		FROM TO	FR-TO	FROM TO
E-B	-265 / 0	0.0 0.0 0.02 (4)	7.81	
A-B	0 / 28	-91.8 -91.8 0.12 (5)	10.00	
B-C	-12 / 0	-91.8 -91.8 0.09 (1)	6.25	
E-D	0 / 0	-18.5 -18.5 0.03 (4)	10.00	

CANTILEVER ANALYSIS HAS BEEN CONSIDERED IN THIS DESIGN

DESIGN CRITERIA

SPECIFIED LOADS:
TOP CH. LL = 25.6 PSF
DL = 6.0 PSF
BOT CH. LL = 0.0 PSF
DL = 7.4 PSF
TOTAL LOAD = 39.0 PSF

SPACING = 24.0 IN/C/C

THIS TRUSS IS DESIGNED FOR RESIDENTIAL OR SMALL BUILDING REQUIREMENTS OF PART 9, NBCC 2015

THIS DESIGN COMPLIES WITH:
- PART 9 OF BCBC 2018, ABC 2019
- PART 9 OF OBC 2012 (2019 AMENDMENT)
- CSA 086-14
- TPIC 2014

DESIGN ASSUMPTIONS

- OVERHANG NOT TO BE ALTERED OR CUT OFF.
(55 % OF 31.3 P.S.F. G.S.L. PLUS 8.4 P.S.F. RAIN LOAD) EQUALS 25.6 P.S.F. SPECIFIED ROOF LIVE LOAD

ALLOWABLE DEFL.(LL)= L/360 (0.19")
CALCULATED VERT. DEFL.(LL) = L/999 (0.00")
ALLOWABLE DEFL.(TL)= L/360 (0.19")
CALCULATED VERT. DEFL.(TL) = L/999 (0.00")

CSI: TC=0.12/1.00 (A-B:5), BC=0.03/1.00 (D-E:4), WB=0.00/1.00 (n/a:0), SSI=0.10/1.00 (B-C:1)

DOL LUMBER=1.00 NAIL=1.00 LS BEND=1.10 COMP=1.10 SHEAR=1.10 TENS= 1.10

COMPANION LIVE LOAD FACTOR = 1.00

AUTOSOLVE RIGHT HEEL ONLY

TRUSS PLATE MANUFACTURER IS NOT RESPONSIBLE FOR QUALITY CONTROL IN THE TRUSS MANUFACTURING PLANT.

NAIL VALUES

PLATE	GRIP(DRY)	SHEAR	SECTION
(PSI)	(PLI)	(PLI)	
MAX	MIN	MAX	MIN
MT20	650	371	1747 788 1987 1873

PLATE PLACEMENT TOL. = 0.250 inches

PLATE ROTATION TOL. = 5.0 Deg.

JSI GRIP= 0.11 (E) (INPUT = 0.90)
JSI METAL= 0.07 (B) (INPUT = 1.00)




Structural component only
DWG# T-2121192

Version 8.420 S Jan 21 2021 MiTek Industries, Inc. Thu Jul 1 12:26:15 2021 Page 1
ID:hEKUVVWZApjnyW9leD6V_jMya4z_-lrOWIWOWwzuzdysQVVGeXEv_v0NYX_vswEdKylz0S5M




JSI GRIP= 0.09 (E) (INPUT = 0.90)
JSI METAL= 0.06 (B) (INPUT = 1.00)



JOB NAME 412865	TRUSS NAME J14	QUANTITY 2	PLY 1	JOB DESC. ROYAL PINE HOMES	DRWG NO.
Tamarack Roof Truss, Burlington				TRUSS DESC.	

Version 8.420 S Jan 21 2021 MiTek Industries, Inc. Thu Jul 1 12:26:16 2021 Page 1
ID:hEKUVWZApjnyW9leD6V_iMya4z_-m2yvWsOYjC5Ua0?h3_Amn6X2vnmjM53?uMtUiz0S5L



Scale = 1:18.6

LUMBER					DESCR.	SPF
N. L. G. A. RULES	CHORDS	SIZE	DRY	LUMBER		
E - B	2x4	DRY	No.2			
A - C	2x4	DRY	No.2			
E - D	2x4	DRY	No.2			

DRY: SEASONED LUMBER.

PLATES (table is in inches)					
JT	TYPE	PLATES	W	LEN	Y X
B	TMV+p	MT20	3.0	4.0	
E	BMV1+p	MT20	3.0	4.0	

DIMENSIONS, SUPPORTS AND LOADINGS SPECIFIED BY FABRICATOR TO BE VERIFIED BY BUILDING DESIGNER

JT	FACTORED GROSS REACTION		MAXIMUM FACTORED GROSS REACTION		INPUT BRG		REQD BRG	
	VERT	HORZ	DOWN	HORZ	UPLIFT	IN-SX	IN-SX	
E	369	0	369	0	0	5-8	5-8	
C	135	0	135	0	0	1-8	1-8	
D	16	0	18	0	0	1-8	1-8	

SEE MITEK STANDARD DETAIL B97791H FOR CONNECTION TO JOINT(S) C, D

UNFACTORED REACTIONS

JT	1ST LCASE		MAX/MIN. COMPONENT REACTIONS		WIND	DEAD	SOIL
	COMBINED	SNOW	LIVE	PERM. LIVE			
E	256	194 / 0	0 / 0	0 / 0	0 / 0	62 / 0	0 / 0
C	93	75 / 0	0 / 0	0 / 0	0 / 0	18 / 0	0 / 0
D	13	0 / 0	0 / 0	0 / 0	0 / 0	13 / 0	0 / 0

BEARING MATERIAL TO BE SPF NO.2 OR BETTER AT JOINT(S) E

BRACING

TOP CHORD TO BE SHEATHED OR MAX. PURLIN SPACING = 6.25 FT.
MAX. UNBRACED BOTTOM CHORD LENGTH = 10.00 FT OR RIGID CEILING DIRECTLY APPLIED.

ALL PITCH BREAKS AND PERIMETER CORNER JOINTS MUST BE Laterally RESTRAINED.

LOADING

TOTAL LOAD CASES: (5)

MEMB.	CHORDS		W E B S	
	MAX. FACTORED FORCE (LBS)	FACTORED VERT. LOAD (PLF)	MAX. FACTORED UNBRAC LENGTH FR-TO	MAX. FACTORED FORCE (LBS)
FR-TO		FROM TO		
E-B	-349 / 0	0.0 0.0 0.01 (4)	7.81	
A-B	0 / 28	-91.8 -91.8 0.13 (5)	10.00	
B-C	-20 / 0	-91.8 -91.8 0.24 (1)	6.25	
E-D	0 / 0	-18.5 -18.5 0.02 (4)	10.00	

CANTILEVER ANALYSIS HAS BEEN CONSIDERED IN THIS DESIGN

TOTAL WEIGHT = 2 X 10 = 20 lb [M]

DESIGN CRITERIA

SPECIFIED LOADS:

TOP CH.	LL = 25.6 PSF
DL = 6.0 PSF	
BOT CH.	LL = 0.0 PSF
DL = 7.4 PSF	
TOTAL LOAD = 39.0 PSF	

SPACING = 24.0 IN. C/C

THIS TRUSS IS DESIGNED FOR RESIDENTIAL OR SMALL BUILDING REQUIREMENTS OF PART 9, NBCC 2015

THIS DESIGN COMPLIES WITH:

- PART 9 OF BCBC 2018, ABC 2019
- PART 9 OF OBC 2012 (2019 AMENDMENT)
- CSA 086-14
- TPIC 2014

DESIGN ASSUMPTIONS

- OVERHANG NOT TO BE ALTERED OR CUT OFF.

(55 % OF 31.3 P.S.F. G.S.L. PLUS 8.4 P.S.F. RAIN LOAD) EQUALS 25.6 P.S.F. SPECIFIED ROOF LIVE LOAD

ALLOWABLE DEFL.(LL) = $L/360$ (0.19")
CALCULATED VERT. DEFL.(LL) = $L/999$ (0.00")
ALLOWABLE DEFL.(TL) = $L/360$ (0.19")
CALCULATED VERT. DEFL.(TL) = $L/999$ (0.00")

CSI: TC=0.24/1.00 (B-C:1), BC=0.02/1.00 (D-E:4), WB=0.00/1.00 (n/a:0), SSI=0.16/1.00 (B-C:1)

DOL LUMBER=1.00 NAIL=1.00 LS BEND=1.10
COMP=1.10 SHEAR=1.10 TENS=1.10

COMPANION LIVE LOAD FACTOR = 1.00

AUTOSOLVE RIGHT HEEL ONLY

TRUSS PLATE MANUFACTURER IS NOT RESPONSIBLE FOR QUALITY CONTROL IN THE TRUSS MANUFACTURING PLANT.


NAIL VALUES

PLATE GRIP(DRY)	SHEAR (PSI)	SECTION (PLI)
MAX MIN	MAX MIN	MAX MIN
MT20	650 371	1747 788 1987 1873

PLATE PLACEMENT TOL. = 0.250 inches

PLATE ROTATION TOL. = 5.0 Deg.


JSI GRIP= 0.14 (E) (INPUT = 0.90)
JSI METAL= 0.10 (B) (INPUT = 1.00)



Structural component only
DWG# T-2121194

JOB NAME 412865	TRUSS NAME J15	QUANTITY 2	PLY 1	JOB DESC. ROYAL PINE HOMES	DRWG NO.
Tamarack Roof Truss, Burlington				TRUSS DESC.	

Version 8.420 S Jan 21 2021 Mitek Industries, Inc. Thu Jul 1 12:26:17 2021 Page 1
ID:hEKUVWZApjnyW9leD6V_iMya4z_-EEWHjCPAUVDLc9auchh?KK4ELACESoLDEY6Q0Bz0S5K



TOTAL WEIGHT = 2 X 12 = 23 lb [M]

LUMBER			
N. L. G. A. RULES	CHORDS	SIZE	LUMBER
E - B	2x4	DRY	No.2
A - C	2x4	DRY	No.2
E - D	2x4	DRY	No.2

DRY: SEASONED LUMBER.

DIMENSIONS, SUPPORTS AND LOADINGS SPECIFIED BY FABRICATOR TO BE VERIFIED BY BUILDING DESIGNER							
BEARINGS							
JT	FACTORED GROSS REACTION	MAXIMUM FACTORED GROSS REACTION	INPUT BRG	REQD BRG			
	VERT	HORZ	DOWN	HORZ	UPLIFT	IN-SX	IN-SX
E	297	0	297	0	0	5-8	5-8
C	66	0	66	0	0	1-8	1-8
D	45	0	50	0	0	1-8	1-8

SEE MITEK STANDARD DETAIL B97791H FOR CONNECTION TO JOINT(S) C, D

UNFACTORED REACTIONS							
JT	1ST LCASE	SNOW	LIVE	PERM. LIVE	WIND	DEAD	SOIL
E	212	130 / 0	0 / 0	0 / 0	0 / 0	82 / 0	0 / 0
C	46	37 / 0	0 / 0	0 / 0	0 / 0	9 / 0	0 / 0
D	36	0 / 0	0 / 0	0 / 0	0 / 0	36 / 0	0 / 0

BEARING MATERIAL TO BE SPF NO.2 OR BETTER AT JOINT(S) E, C

BRACING
TOP CHORD TO BE SHEATHED OR MAX. PURLIN SPACING = 10.00 FT.
MAX. UNBRACED BOTTOM CHORD LENGTH = 10.00 FT. OR RIGID CEILING DIRECTLY APPLIED.
ALL PITCH BREAKS AND PERIMETER CORNER JOINTS MUST BE Laterally RESTRAINED.

LOADING
TOTAL LOAD CASES: (4)

CHORDS				WEBS			
MEMB.	MAX. FACTORED FORCE (LBS)	FACTORED VERT. LOAD (PLF)	MAX. CSI (LC)	MEMB.	MAX. FACTORED FORCE (LBS)	MAX. CSI (LC)	
FR-TO		FROM TO		FR-TO			
E-B	-234 / 0	0.0	0.0 0.13 (4)	7.81			
A-B	0 / 28	-91.8	-91.8 0.12 (1)	10.00			
B-C	-10 / 0	-91.8	-91.8 0.06 (1)	10.00			
E-F	0 / 0	-18.5	-18.5 0.13 (4)	10.00			
F-G	0 / 0	-18.5	-18.5 0.13 (4)	10.00			
G-D	0 / 0	-18.5	-18.5 0.13 (4)	10.00			

SPECIFIED CONCENTRATED LOADS (LBS)							
JT	LOC.	LC1	MAX.	MAX+	FACE	DIR.	TYPE
F	2-0-12	1	1	---	FRONT	VERT	TOTAL
G	4-0-12	1	1	---	FRONT	VERT	TOTAL

CONNECTION REQUIREMENTS

- 1) C1: A SUITABLE HANGER/MECHANICAL CONNECTION IS REQUIRED.

DESIGN CRITERIA

SPECIFIED LOADS:
TOP CH. LL = 25.6 PSF
DL = 6.0 PSF
BOT CH. LL = 0.0 PSF
DL = 7.4 PSF
TOTAL LOAD = 39.0 PSF

SPACING = 24.0 IN. C/C

THIS TRUSS IS DESIGNED FOR RESIDENTIAL OR SMALL BUILDING REQUIREMENTS OF PART 9, NBCC 2015

THIS DESIGN COMPLIES WITH:
- PART 9 OF BCBC 2018, ABC 2019
- PART 9 OF OBC 2012 (2019 AMENDMENT)
- CSA 086-14
- TPIC 2014

DESIGN ASSUMPTIONS
- OVERHANG NOT TO BE ALTERED OR CUT OFF.

(55 % OF 31.3 P.S.F. G.S.L. PLUS 8.4 P.S.F. RAIN LOAD) EQUALS 25.6 P.S.F. SPECIFIED ROOF LIVE LOAD

ALLOWABLE DEFL.(LL) = L/360 (0.20")
CALCULATED VERT. DEFL.(LL) = L/999 (0.00")
ALLOWABLE DEFL.(TL) = L/360 (0.20")
CALCULATED VERT. DEFL.(TL) = L/999 (0.03")

CSI: TC=0.13/1.00 (B-E:4), BC=0.13/1.00 (D-E:4), WB=0.00/1.00 (n/a:0), SSI=0.09/1.00 (A-B:1)

DOL LUMBER=0.99 NAIL=0.99 LS BEND=1.10
COMP=1.10 SHEAR=1.10 TENS=1.10

COMPANION LIVE LOAD FACTOR = 1.00

AUTOSOLVE RIGHT HEEL ONLY

TRUSS PLATE MANUFACTURER IS NOT RESPONSIBLE FOR QUALITY CONTROL IN THE TRUSS MANUFACTURING PLANT.

NAIL VALUES
PLATE GRIP(DRY) SHEAR SECTION
(PSI) (PLI) (PLI)
MAX MIN MAX MIN MAX MIN
MT20 650 371 1747 788 1987 1873

PLATE PLACEMENT TOL. = 0.250 inches

PLATE ROTATION TOL. = 5.0 Deg.


JSI GRIP = 0.09 (E) (INPUT = 0.90)
JSI METAL = 0.07 (B) (INPUT = 1.00)



Structural component only
DWG# T-2121195

JOB NAME 412865	TRUSS NAME J16	QUANTITY 2	PLY 1	JOB DESC. ROYAL PINE HOMES	DRWG NO.
Tamarack Roof Truss, Burlington		TRUSS DESC.			

Version 8.420 S Jan 21 2021 MiTek Industries, Inc. Thu Jul 1 12:26:18 2021 Page 1
ID:hEKUVWZApjnyW9leD6V_jMya4z_-iQ4fwYQoFpMCpJ84APCEsXcOPaYTBfBMTCr_Ydz0S5u



Scale = 1:18.4

LUMBER				DESCR.	
N. L. G. A. RULES	CHORDS	SIZE	LUMBER	SPF	SPF
E - B	2x4	DRY	No.2	SPF	SPF
A - C	2x4	DRY	No.2	SPF	SPF
E - D	2x4	DRY	No.2	SPF	SPF

DRY: SEASONED LUMBER.

PLATES (table is in inches)					
JT	TYPE	PLATES	W	LEN	Y X
B	TMV+p	MT20	3.0	4.0	
E	BMV1+p	MT20	3.0	4.0	

DIMENSIONS, SUPPORTS AND LOADINGS SPECIFIED BY FABRICATOR TO BE VERIFIED BY BUILDING DESIGNER

JT	FACTORED GROSS REACTION		MAXIMUM FACTORED GROSS REACTION		INPUT BRG	REQRD BRG
	VERT	HORZ	DOWN	HORZ		
E	412	0	412	0	5-8	5-8
C	135	0	135	0	1-8	1-8
D	45	0	50	0	1-8	1-8

SEE MITEK STANDARD DETAIL B97791H FOR CONNECTION TO JOINT(S) C, D

UNFACTORED REACTIONS

JT	1ST CASE		MAX./MIN. COMPONENT REACTIONS				DEAD	SOIL
	COMBINED	SNOW	LIVE	PERM. LIVE	WIND			
E	291	194 / 0	0 / 0	0 / 0	0 / 0		97 / 0	0 / 0
C	93	75 / 0	0 / 0	0 / 0	0 / 0		18 / 0	0 / 0
D	36	0 / 0	0 / 0	0 / 0	0 / 0		36 / 0	0 / 0

BEARING MATERIAL TO BE SPF NO.2 OR BETTER AT JOINT(S) E, C

BRACING

TOP CHORD TO BE SHEATHED OR MAX. PURLIN SPACING = 6.25 FT.
MAX. UNBRACED BOTTOM CHORD LENGTH = 10.00 FT OR RIGID CEILING DIRECTLY APPLIED.

ALL PITCH BREAKS AND PERIMETER CORNER JOINTS MUST BE Laterally RESTRAINED.

LOADING

TOTAL LOAD CASES: (4)

MEMB.	CHORDS		FACTORED				WEBS	
	MAX. FACTORED	FORCE	VERT. LOAD	LC1	MAX	MAX.	MEMB.	MAX. FACTORED
	(LBS)	(LBS)	(PLF)	CS1 (LC)	UNBRAC	LENGTH		(LBS)
FR-TO			FROM	TO		FR-TO		
E-B	-349 / 0		0.0	0.0	0.13 (4)	7.81		
A-B	0 / 28		-91.8	-91.8	0.12 (1)	10.00		
B-C	-20 / 0		-91.8	-91.8	0.24 (1)	6.25		
E-D	0 / 0		-18.5	-18.5	0.13 (4)	10.00		

TOTAL WEIGHT = 2 X 14 = 29 lb

DESIGN CRITERIA

SPECIFIED LOADS:

TOP CH.	LL =	25.6	PSF
	DL =	6.0	PSF
BOT CH.	LL =	0.0	PSF
	DL =	7.4	PSF
TOTAL LOAD	=	39.0	PSF

SPACING = 24.0 IN. C/C

THIS TRUSS IS DESIGNED FOR RESIDENTIAL OR SMALL BUILDING REQUIREMENTS OF PART 9, NBCC 2015

THIS DESIGN COMPLIES WITH:

- PART 9 OF CBC 2018, ABC 2019
- PART 9 OF OBC 2012 (2019 AMENDMENT)
- CSA 086-14
- TPIC 2014

DESIGN ASSUMPTIONS

-OVERHANG NOT TO BE ALTERED OR CUT OFF.

(55 % OF 31.3 P.S.F. G.S.L. PLUS 8.4 P.S.F. RAIN LOAD) EQUALS 25.6 P.S.F. SPECIFIED ROOF LIVE LOAD

ALLOWABLE DEFL.(LL)= $L/360$ (0.20")
CALCULATED VERT. DEFL.(LL) = $L/999$ (0.00")
ALLOWABLE DEFL.(TL)= $L/360$ (0.20")
CALCULATED VERT. DEFL.(TL) = $L/999$ (0.03")

CSI: TC=0.24/1.00 (B-C:1), BC=0.13/1.00 (D-E:4),
WB=0.00/1.00 (n/a:0), SSI=0.16/1.00 (B-C:1)

DOL LUMBER=1.00 NAIL=1.00 LS BEND=1.10
COMP=1.10 SHEAR=1.10 TENS=1.10

COMPANION LIVE LOAD FACTOR = 1.00

AUTOSOLVE RIGHT HEEL ONLY

TRUSS PLATE MANUFACTURER IS NOT RESPONSIBLE FOR QUALITY CONTROL IN THE TRUSS MANUFACTURING PLANT.

NAIL VALUES

PLATE GRIP(DRY)	SHEAR	SECTION
(PSI)	(PL)	(PL)
MAX	MIN	MAX
MT20	650	371
	1747	788
	1987	1873


PLATE PLACEMENT TOL. = 0.250 inches

PLATE ROTATION TOL. = 5.0 Deg.

JSI GRIP= 0.14 (E) (INPUT = 0.90)
JSI METAL= 0.10 (B) (INPUT = 1.00)



Structural component only
DWG# T-2121196



Alves Engineering Services Inc.

5208 Easton road
Burlington, Ontario L7L 6N6
(289) 259 5455

RESPONSABILITIES

- 1-Alves Engineering Services Inc. is responsible for the design of trusses as individual components
- 2-It is the responsibility of others to ascertain that the design loads utilized on this drawing meet or exceed the actual dead load imposed by the structure and the live load imposed by the local building code or the authorities having jurisdictions.
- 3- All dimensions are to be verified by owner, contractor, architect or other authority before manufacture.
- 4- Alves Engineering Services Inc. bears no responsibility for the erection of the trusses. Persons erecting trusses are cautioned to seek professional advice regarding temporary and permanent bracing system. Bracing shown on Alves Engineering Services Inc. drawings is specified for the truss as a single component and forms an integral part of the truss design, but is not meant to represent the only required bracing for that truss when trusses are installed in a series of trusses forming a roof truss system.
- 5- It is the manufactures responsibility to ensure that the trusses are manufactured in conformance with Alves Engineering Services Inc. specifications outlined below.

SPECIFICATIONS

- 1-Truss components sealed by Alves Engineering Services Inc. conform to the relevant sections of the current Building Code of Ontario and Canada (part 4 or part 9) or the current Canadian code for Farm Buildings in accordance with the application specified on the sealed truss component drawing. All truss component design procedures must conform to the current design standard issued by the truss plate institute of Canada (TPIC). All lumber and nailing stresses to conform to the current CSA wood design standard identified on the current Building Code and TPIC.
- 2- Lumber is to be the sizes and grade specified on the truss drawing.
- 3- Moist content of lumber is not to exceed 19% in service unless otherwise specified.
- 4- Plates shall be applied to both faces of the each truss joint and shall be positioned as shown on the truss drawings
- 5- Lumber used on manufacture of trusses is not to be treated with chemicals unless otherwise specified on the truss drawings.
- 6- The top chord is assumed to be continuously laterally braced by the roof sheathing or purlins at intervals specified on the truss drawing but not exceeding 24" c/c for (part 9) and not exceeding 48" for (part 4 or farm design)
- 7- When rigid ceiling is not attached directly to the bottom chord, lateral bracing is required and it should not exceed more than 3m or 10' intervals.
- 8-Refer to Mitek sheet MII7473C REV.10-08 attached for information on symbols, numbering system and General Safety notes.

T-1900213

Feb 09, 2018



BEARING ANCHORAGE BY TOE-NAILS FOR LATERAL CAPACITY

B97791H1

NAIL TYPE	LENGTH (IN)	DIAMETER (IN)	NAIL LATERAL CAPACITY (LB)	
			S-P-F	D. FIR
COMMON WIRE	3.00	0.144	132	147
	3.25	0.144	132	147
	3.50	0.160	159	177
COMMON SPIRAL	3.00	0.122	97	108
	3.25	0.122	97	108
	3.50	0.152	145	162

NOTES:

1. Rafter and ceiling members may be anchored to top and bottom chords of girder truss by toe-nailing rafter and ceiling members to girder chords provided the reaction does not exceed the lateral capacities in the table. Hangers (specified by others) are required for reactions higher than the maximum toe-nail capacity. Reactions are based on factored loads.
2. Toe nail capacities shown in the table are for **one** toe-nail. For additional toe-nails multiply values in table by the number of toe-nails used. Toe-nail capacities take into account toe-nailing factor J_A in CSA O86-14, section 12.9.4.1.
3. For 9- 3/4 gauge 3.25" common wire gun nails (diameter = 0.120") use 3" common spiral nail values.
4. Maximum number of toe-nails allowed depends on the lumber size & species to be toe-nailed to supporting member and nail diameter, as shown in tables below.
5. Nail values in table are based on the following relative lumber densities: G = 0.42 (SPF), G = 0.49 (D. Fir).
6. Toe-nails shall be driven at approximately 1/3 the nail length from the edge of the joist/truss chord and driven at an angle of 30° to the grain of the member (See next page for nailing on bearing plate).
7. For loads due to **wind** the nail lateral capacity in this table may be multiplied by 1.15 (K_D factor).
8. Lumber must be dry (< 19% moisture content) at the time of nail installation.
9. Nail values in this table comply with CSA O86-14, section 12.9.4
10. This design is not valid after April 30, 2021.



TOE-NAIL INSTALLATION

Nail type	Common wire	Common spiral	Common wire	Common spiral
Nail dia. (in)	0.160	0.152	0.144	0.122
	(3.5" nail)		(3" and 3.25" nail)	
LUMBER SIZE	MAXIMUM NUMBER OF TOE-NAILS			
2X4 SPF	2	2	3	3
2X4 D. Fir	2	2	2	2
2X6 SPF	4	4	4	5
2X6 D. Fir	3	3	3	4

MiTek® MiTek Canada Inc
100 Industrial Rd.
Bradford, Ontario L3Z 3G7

PEO
Certificate No. 10889485



April 2, 2020

BEARING ANCHORAGE BY TOE-NAILS FOR WIND LOADING

B97791H2



NAIL TYPE	LENGTH (IN)	DIAMETER (IN)	NAIL WITHDRAWAL CAPACITY (LB)	
			S-P-F	D. FIR
COMMON WIRE	3.00	0.144	30	42
	3.25	0.144	32	45
	3.50	0.160	38	52
COMMON SPIRAL	3.00	0.122	26	36
	3.25	0.122	28	40
	3.50	0.152	36	50

Note: If using truss with D. Fir lumber and S-P-F bearing plate, use values in table for S-P-F.



NOTES:

1. Truss chord, rafter, or ceiling members may be anchored to bearing plate by toe-nails, provided that the actual factored uplift force due to **wind** or **earthquake** load does not exceed the withdrawal capacities in the table. Hangers (specified by others) are required for uplift forces that are higher than the maximum toe-nail withdrawal capacity.
2. Toe nail capacities shown in the table are for **one** toe-nail. For additional toe-nails multiply values in table by the number of toe-nails used. Toe-nail capacities take into account toe-nailing factor J_A in CSA O86-14, section 12.9.5.2.
3. For 9- 3/4 gauge 3.25" common wire gun nails (diameter = 0.120") use 3" common spiral nail values.
4. Maximum number of toe-nails allowed depends on the lumber size & species to be toe-nailed to supporting member and nail diameter, as shown in table above.
5. Nail values in table are based on the following relative lumber densities: $G = 0.42$ (SPF), $G = 0.49$ (D. Fir).
6. Toe-nails shall be driven at approximately 1/3 the nail length from the edge of the joist/truss chord and driven at an angle of 30° to the grain of the member (See drawing on detail B37579H1).
7. Lumber must be dry (< 19% moisture content) at the time of nail installation.
8. Nail values in this table comply with CSA O86-14, section 12.9.5
9. This design is not valid after April 30, 2021.

Toe-nailing on 2x6 Bearing Plate



Toe-nailing on 2x4 Bearing Plate



MiTek®

MiTek Canada Inc
100 Industrial Rd.
Bradford, Ontario L3Z 3G7

April 2, 2020

PEO
Certificate No. 10889485



HUS/LJS – Double Shear Joist Hangers

SIMPSON
Strong-Tie

All hangers have double shear nailing. This patented innovation distributes the load through two points on each joist nail for greater strength. It also allows the use of fewer nails, faster installation and the use of common nails for all connections. Do not bend or remove tabs.

Material: See table

Finish: G90 galvanized

Design:


- Factored resistances are in accordance with CSA O86 -14.
- Uplift resistances have been increased 15%. No further increase is permitted.
- Wood shear is not considered in the factored resistances given. The specifier must ensure that the joist and header capacities are capable of withstanding these loads.

Installation:


- Use all specified fasteners
- Nails: 16d = 0.162" dia. x 3½" long common wire
- Double shear nails must be driven at an angle through the joist or truss into the header to achieve the table loads
- Not designed for welded or nailer applications

Options:


- See current catalogue for options




LJS26DS




HUS210
(HUS26, HUS28, similar)



Typical LJS26DS
Installation




Typical HUS
Installation



Typical HUS Installation
(Truss Designer to provide fastener quantity for connecting multiple members together)


Model No.	Ga.	Dimensions (in.)				Fasteners		Factored Resistance (lb.)			
		W	H	B	d _g ¹	Face	Joist	D.Fir-L		S-P-F	
								Uplift (K _p =1.15) lb.	Normal (K _p =1.00) lb.	Uplift (K _p =1.15) lb.	Normal (K _p =1.00) lb.
LJS26DS	18	1½	5	3½	4⅞	(16) 16d	(6) 16d	2055	4265	1460	4115
HUS26	16	1⅝	5⅞	3	3⅝	(14) 16d	(6) 16d	2705	4940	2065	3875
HUS28	16	1⅝	7⅝	3	6⅜	(22) 16d	(8) 16d	3605	5365	2675	4345
HUS210	16	1⅝	9⅝	3	7⅜	(30) 16d	(10) 16d	4505	5795	4010	4740
HUS1.81/10	16	1⅝	9	3	8	(30) 16d	(10) 16d	4505	6450	4010	5200

1. d_g is the distance from the seat of the hanger to the highest joist nail.




Dome Double Shear Nailing prevents tabs breaking off (available on some models).


U.S. Patent
5,603,580



Double Shear Nailing Side View. Do not bend tab back.



Double Shear Nailing Top View.



(800) 999-5099
strongtie.com

HGUS – Double Shear Joist Hangers

SIMPSON
Strong-Tie

All HGUS hangers have double shear nailing. This patented innovation distributes the load through two points on each joist nail for greater strength. It also allows the use of fewer nails, faster installation and the use of common nails for all connections. Do not bend or remove tabs.

Material: 12 gauge

Finish: G90 galvanized

Design:


- Factored resistances are in accordance with CSA O86-14.
- Uplift resistances have been increased 15%.
No further increase is permitted.
- Wood shear is not considered in the factored resistances given. The specifier must ensure that the joist and header capacities are capable of withstanding these loads.

Installation:


- Use all specified fasteners
- Nails: 16d = 0.162" dia x 3½" long common wire
- Double shear nails must be driven at an angle through the joist or truss into the header to achieve the table loads
- Not designed for welded or nailer applications

Options:


- See current catalogue for options



HGUS28-2




Typical HGUS
Installation




Typical HGUS Installation
(Truss Designer to
provide fastener quantity
for connecting multiple
members together)

Model No.	Ga.	Dimensions (in.)				Fasteners		Factored Resistance (lb.)			
		W	H	B	d _e ¹	Face	Joist	D.Fir-L		S-P-F	
								Uplift (K _p =1.15)	Normal (K _p =1.00)	Uplift (K _p =1.15)	Normal (K _p =1.00)
HGUS26	12	1⅝	5⅝	5	4⅞	(20) 16d	(8) 16d	2685	6625	2685	5700
HGUS26-2	12	3⅝	5⅝	4	4⅞	(20) 16d	(8) 16d	4385	8950	3100	6355
HGUS26-3	12	4⅝	5⅝	4	4⅞	(20) 16d	(8) 16d	4385	8950	3100	6355
HGUS26-4	12	6⅝	5⅝	4	4⅞	(20) 16d	(8) 16d	4385	8950	3100	6355
HGUS28	12	1⅝	7⅝	5	6⅞	(36) 16d	(12) 16d	3310	7675	3100	6900
HGUS28-2	12	3⅝	7⅝	4	6⅞	(36) 16d	(12) 16d	6070	12980	4310	9215
HGUS28-3	12	4⅝	7⅝	4	6⅞	(36) 16d	(12) 16d	6070	12980	4310	9215
HGUS28-4	12	6⅝	7⅝	4	6⅞	(36) 16d	(12) 16d	6070	12980	4310	9215
HGUS210	12	1⅝	9⅝	5	7⅞	(46) 16d	(16) 16d	3535	11070	2510	8090
HGUS210-2	12	3⅝	9⅝	4	8⅞	(46) 16d	(16) 16d	6840	14015	4855	10270
HGUS210-3	12	4⅝	9⅝	4	8⅞	(46) 16d	(16) 16d	6840	14645	4855	10400
HGUS210-4	12	6⅝	9⅝	4	8⅞	(46) 16d	(16) 16d	6840	14645	4855	10400
HGUS212-4	12	6⅝	10⅝	4	10⅞	(56) 16d	(20) 16d	7640	14995	5425	10645
HGUS214-4	12	6⅝	12⅝	4	11⅞	(66) 16d	(22) 16d	10130	16400	7195	11645


1. d_e is the distance from the seat of the hanger to the highest joist nail.




Dome Double
Shear Nailing
prevents tabs
breaking off
(available on
some models).
U.S. Patent
5,603,580



Double
Shear
Nailing
Side View.
Do not
bend tab
back.



Double
Shear
Nailing
Top View.



(800) 999-5099
strongtie.com

H – Seismic and Hurricane Ties

SIMPSON
Strong-Tie

The H connector series provides wind and seismic ties for trusses and rafters.

Material: 18 gauge **Finish:** G90 galvanized

Design: • Factored resistances are in accordance with CSA O86-14


- Factored resistances have been increased 15%. No further increase is permitted.

Installation: • Use all specified fasteners


- Nails: 8d = 0.131" dia. x 2½" long common wire, 8d x 1½" = 0.131" x 1½" long, 10d x 1½" = 0.146" x 1½" long
- H1 can be installed with flanges facing outwards
- Hurricane ties do not replace solid blocking

Factored resistances for more than one direction for a single connection cannot be added together. A factored load which can be divided into components in the directions given must be evaluated as follows: Factored Shear/Resisting Shear + Factored Tension/Resisting Tension ≤ 1.0.


Hurricane Tie Installations to Achieve Twice the Load (Top View)




Install diagonally across from each other for minimum 2x truss.




Nailing into both sides of a single ply 2x truss may cause the wood to split.




H1




H1 Installation




H2A




H2A Installation




H2.5A




H2.5A Installation




H2.5T




H2.5T Installation
(Nails into both top plates)




H3



H3 Installation



H10A



H10A Installation

Model No.	Ga.	Fasteners			Factored Resistance (lb.)					
					D.Fir-L			S-P-F		
		To Rafter	To Plates	To Studs	Uplift	Normal		Uplift	Normal	
						F ₁	F ₂		F ₁	F ₂
						(K _b =1.15)			(K _b =1.15)	
H1	18	(6) 8d x 1½"	(4) 8d	—	740	685	300	680	485	215
H2A	18	(5) 8d x 1½"	(2) 8d x 1½"	(5) 8d x 1½"	830	220	75	590	155	55
H2.5A	18	(5) 8d	(5) 8d	—	805	160	160	755	160	160
H2.5T	18	(5) 8d	(5) 8d	—	835	175	240	740	160	210
H3	18	(4) 8d	(4) 8d	—	740	180	265	615	125	190
H10A	18	(9) 10d x 1½"	(9) 10d x 1½"	—	1735	795	410	1505	565	290

1. Factored resistances have been increased 15% for earthquake or wind loading with no further increase allowed.

2. Factored resistances are for one anchor. A minimum rafter thickness of 2½" must be used when framing anchors are installed on each side of the joist and on the same side of the plate.

3. When cross-grain bending or cross-grain tension cannot be avoided, mechanical reinforcement to resist such forces should be considered.

4. Hurricane ties are shown installed on the outside of the wall for clarity. Installation on the inside of the wall is acceptable. For a Continuous Load Path, connections must be on same side of the wall.



(800) 999-5099
strongtie.com

LUS – Double Shear Joist Hangers

SIMPSON
Strong-Tie

All LUS hangers have double shear nailing. This patented innovation distributes the load through two points on each joist nail for greater strength. It also allows the use of fewer nails, faster installation and the use of common nails for all connections.

Material: 18 gauge


Finish: G90 galvanized

Design:


- Factored resistances are in accordance with CSA O86-14.
- Uplift resistances have been increased 15%. No further increase is permitted.
- Wood shear is not considered in the factored resistances given. The specifier must ensure that the joist and header capacities are capable of withstanding these loads.

Installation:

- Use all specified fasteners.
- Nails: 16d = 0.162" dia. x 3½" long common wire,
10d = 0.148" x 3" long common wire.
- Double shear nails must be driven at an angle through the joist or truss into the header to achieve the table loads.
- Not designed for welded or nailer applications.




Typical LUS
Installation



LUS28


Model No.	Ga.	Dimensions (in.)				Fasteners		Factored Resistance (lb.)			
		W	H	B	d _e ¹	Face	Joist	D.Fir-L		S-P-F	
								Uplift (K _o =1.15)	Normal (K _o =1.00)	Uplift (K _o =1.15)	Normal (K _o =1.00)
LUS24	18	1⅞	3⅞	1¾	1 15/16	(4) 10d	(2) 10d	710	1630	645	1155
LUS24-2	18	3⅞	3⅞	2	1 13/16	(4) 16d	(2) 16d	835	2020	590	1435
LUS26	18	1⅞	4¾	1¾	3⅞	(4) 10d	(4) 10d	1420	2170	1290	1630
LUS26-2	18	3⅞	4¾	2	4	(4) 16d	(4) 16d	1720	2595	1545	1920
LUS26-3	18	4⅞	4¾	2	3¼	(4) 16d	(4) 16d	1720	2595	1545	2340
LUS28	18	1⅞	6⅞	1¾	3¾	(6) 10d	(6) 10d	1420	2520	1290	1790
LUS28-2	18	3⅞	7	2	4	(6) 16d	(4) 16d	1720	3325	1545	2575
LUS28-3	18	4⅞	6¼	2	3¼	(6) 16d	(4) 16d	1720	3325	1545	2375
LUS210	18	1⅞	7 13/16	1¾	3⅞	(8) 10d	(4) 10d	1420	2785	1290	2210
LUS210-2	18	3⅞	9	2	6	(8) 16d	(6) 16d	2580	4500	2320	3195
LUS210-3	18	4⅞	8 3/16	2	5¼	(8) 16d	(6) 16d	2580	3345	2320	2375

1. d_e is the distance from the seat of the hanger to the highest joist nail.



Double Shear Nailing prevents tabs breaking off (available on some models).

U.S. Patent
5,603,580



Double Shear Nailing
Top View.




(800) 999-5099
strongtie.com

Overview:

Where piggybacks are connected ovetop of base trusses, 2x4 purlins must be first added to the flat portion of the base truss at a spacing no more than 24" o/c. These purlins not only provide support for the piggyback trusses above, but are required to laterally support the top chord of the base truss which will not have the sheathing directly connected to the flat portion of the base truss. This ensures the top chord, most often in compression, will not buckle laterally.

Further, the purlins in the plane of the flat portion require diagonal bracing to prevent lateral displacement of the purlins themselves where under certain conditions, the trusses may in fact all buckle in the same direction if this additional bracing is not added in the plane of the purlins.

Detail:



NOTE: THE SLOPED PORTION OF THE TOP CHORD OF THE BASE TRUSS AND PIGGYBACK TRUSS IN THIS SKETCH IS ASSUMED TO BE SHEATHED IN ACCORDANCE WITH THE OBC.

SKETCH FROM BCSI-CANADA 2013


Disclaimer:

OWTFA Tech Notes are intended to provide guidance to the design community both within the membership as well as to third party designers who might benefit from the information. The details have been developed by the OWTFA technical committee and although there may be professional engineers involved in development, the information contained in the tech-note are not intended to be used without having a professional engineer review the information for a specific application. The OWTFA takes no responsibility with respect to the information provided but has developed this tech-note to offer guidance where it is not currently readily available.

Symbols

PLATE LOCATION AND ORIENTATION

Center plate on joint unless x, y offsets are indicated. Dimensions are in ft-in-sixteenths or mm. Apply plates to both sides of truss and fully embed teeth.



This symbol indicates the required direction of slots in connector plates.



* Plate location details available in MiTek software or upon request.

PLATE SIZE

4 X 4


The first dimension is the plate width measured perpendicular to slots. Second dimension is the length parallel to slots.

LATERAL BRACING LOCATION



Indicated by symbol shown and/or by text in the bracing section of the output. Use T, I or Eliminator bracing if indicated.

BEARING




Indicates location where bearings (supports) occur. Icons vary but reaction section indicates joint number where bearings occur.

Industry Standards:

TPIC: Truss Design Procedures and Specifications for Light Metal Plate Connected Wood Trusses
DSB-89: Design Standard for Bracing.
BCSI: Building Component Safety Information, Guide to Good Practice for Handling, Installing & Bracing of Metal Plate Connected Wood Trusses.

Numbering System

6-4-8 dimensions shown in ft-in-sixteenths or mm (Drawings not to scale)



JOINTS ARE GENERALLY NUMBERED/LETTERED CLOCKWISE AROUND THE TRUSS STARTING AT THE JOINT FARTHEST TO THE LEFT.


CHORDS AND WEBS ARE IDENTIFIED BY END JOINT NUMBERS/LETTERS.

PRODUCT CODE APPROVALS

CCMC Reports:

11996-L, 10319-L, 13270-L, 12691-R

© 2007 MiTek® All Rights Reserved



MiTek Engineering Reference Sheet: MI-7473C rev. 10-'08

General Safety Notes

Failure to Follow Could Cause Property Damage or Personal Injury

1. Additional stability bracing for truss system, e.g. diagonal or X-bracing, is always required. See BCSi.
2. Truss bracing must be designed by an engineer. For wide truss spacing, individual lateral braces themselves may require bracing, or alternative T, I, or Eliminator bracing should be considered.
3. Never exceed the design loading shown and never stack materials on inadequately braced trusses.
4. Provide copies of this truss design to the building designer, erection supervisor, property owner and all other interested parties.
5. Cut members to bear tightly against each other.
6. Place plates on each face of truss at each joint and embed fully. Knots and waste at joint locations are regulated by TPIC.
7. Design assumes trusses will be suitably protected from the environment in accord with TPIC.
8. Unless otherwise noted, moisture content of lumber shall not exceed 19% at time of fabrication.
9. Unless expressly noted, this design is not applicable for use with fire retardant, preservative treated, or green lumber.
10. Camber is a non-structural consideration and is the responsibility of truss fabricator. General practice is to camber for dead load deflection.
11. Plate type, size, orientation and location dimensions indicated are minimum plating requirements.
12. Lumber used shall be of the species and size, and in all respects, equal to or better than that specified.
13. Top chords must be sheathed or purlins provided at spacing indicated on design.
14. Bottom chords require lateral bracing at 10 ft. spacing, or less, if no ceiling is installed, unless otherwise noted.
15. Connections not shown are the responsibility of others.
16. Do not cut or alter truss member or plate without prior approval of an engineer.
17. Install and load vertically unless indicated otherwise.
18. Use of green or treated lumber may pose unacceptable environmental, health or performance risks. Consult with project engineer before use.
19. Review all portions of this design (front, back, words and pictures) before use. Reviewing pictures alone is not sufficient.
20. Design assumes manufacture in accordance with TPIC Quality Criteria.