

FROM PLAN DATED:

BUILDER: ROYAL PINE HOMES

SITE: CENTREFIELD WEST GORMLEY

MODEL: 2009 END

ELEVATION: A,B

LOT:

CITY: RICHMOND HILL

SALESMAN: MARIO DICIANO

DESIGNER: AJ

REVISION:

NOTES:

REFER TO THE **NORDIC INSTALLATION** GUIDE FOR PROPER STORAGE AND INSTALLATION.

**SQUASH BLOCKS** OF 2x4, 2x6, 2x8 #2 S.P.F REQ'D UNDER INTERIOR UNIFORM LOAD BEARING WALLS. **MULTIPLE SQUASH BLOCKS** REQ'D UNDER CONCENTRATED LOADS. SEE FIGURE 1. **CANTILEVERED JOISTS** INCLUDING **CANT' OVER BRICK REI** I-JOIST BLOCKING ALONG BEARING AND RIMBOARD CLOSURE AT ENDS. SEE FIGURES 4 & 5 FOR REINFORCEMENT REQUIREMENTS. FOR **HOLES** INCLUDING **DUCT CHASE** AND **FIELD CUT OPENINGS** SEE FIGURE 7, TABLES 1 & 2. **CERAMIC TIL** APPLICATION AS PER O.B.C 9.30.6.

LOADING:

DESIGN LOADS: L/480.000


LIVE LOAD: 40.0 lb/ft<sup>2</sup>

DEAD LOAD: 20.0 lb/ft<sup>2</sup>

SUBFLOOR: 3/4" GLUED AND NAILED


DATE: 2020-08-06

1st FLOOR




Products				
PlotID	Length	Product	Plies	Net Qty
J1	20-00-00	11 7/8" NI-40x	1	2
J1DJ	20-00-00	11 7/8" NI-40x	2	4
J2	12-00-00	11 7/8" NI-40x	1	2
J3	10-00-00	11 7/8" NI-40x	1	3
J3DJ	10-00-00	11 7/8" NI-40x	2	2
J4	6-00-00	11 7/8" NI-40x	1	7
J5	4-00-00	11 7/8" NI-40x	1	4
J6	2-00-00	11 7/8" NI-40x	1	4
J7	20-00-00	11 7/8" NI-80	1	15
B3	20-00-00	1-3/4" x 11-7/8" VERSA-LAM® 2.0 3100 SP	2	2
B6	12-00-00	1-3/4" x 11-7/8" VERSA-LAM® 2.0 3100 SP	2	2
B1	10-00-00	1-3/4" x 11-7/8" VERSA-LAM® 2.0 3100 SP	1	1
B2	10-00-00	1-3/4" x 11-7/8" VERSA-LAM® 2.0 3100 SP	2	2
B4	10-00-00	1-3/4" x 11-7/8" VERSA-LAM® 2.0 3100 SP	2	2
B5	6-00-00	1-3/4" x 11-7/8" VERSA-LAM® 2.0 3100 SP	1	1
B8	6-00-00	1-3/4" x 11-7/8" VERSA-LAM® 2.0 3100 SP	1	1
B9	6-00-00	1-3/4" x 11-7/8" VERSA-LAM® 2.0 3100 SP	1	1
B7	4-00-00	1-3/4" x 11-7/8" VERSA-LAM® 2.0 3100 SP	1	1

Connector Summary		
Qty	Manuf	Product
8	H1	IUS2.56/11.88
7	H1	IUS2.56/11.88
6	H1	IUS2.56/11.88
2	H1	IUS2.56/11.88
2	H2	HUS1.81/10
3	H2	HUS1.81/10
1	H4	HGUS410



Products				
PlotID	Length	Product	Plies	Net Qty
J1	20-00-00	11 7/8" NI-40x	1	7
J2	16-00-00	11 7/8" NI-40x	1	2
J3	12-00-00	11 7/8" NI-40x	1	11
J4	10-00-00	11 7/8" NI-40x	1	4
J5	4-00-00	11 7/8" NI-40x	1	7
J6	20-00-00	11 7/8" NI-80	1	21
B11	20-00-00	1-3/4" x 11-7/8" VERSA-LAM® 2.0 3100 SP	2	2
B13	14-00-00	1-3/4" x 11-7/8" VERSA-LAM® 2.0 3100 SP	1	1
B12	10-00-00	1-3/4" x 11-7/8" VERSA-LAM® 2.0 3100 SP	1	1
B14	10-00-00	1-3/4" x 11-7/8" VERSA-LAM® 2.0 3100 SP	2	2
B10	4-00-00	1-3/4" x 11-7/8" VERSA-LAM® 2.0 3100 SP	2	2

Connector Summary		
Qty	Manuf	Product
9	H1	IUS2.56/11.88
1	H1	IUS2.56/11.88
1	H2	HUS1.81/10
1	H2	HUS1.81/10



FROM PLAN DATED:

BUILDER: ROYAL PINE HOMES

SITE: CENTREFIELD WEST GORMLEY

MODEL: 2009 END

ELEVATION: A,B

LOT:

CITY: RICHMOND HILL

SALESMAN: MARIO DICIANO

DESIGNER: AJ

REVISION:

NOTES:

REFER TO THE NORDIC **INSTALLATION GUIDE** FOR PROPER STORAGE AND INSTALLATION. **SQUASH BLOCKS** OF 2x4, 2x6, 2x8 #2 S.P.F. REQ'D UNDER INTERIOR UNIFORM LOAD BEARING WALLS. **MULTIPLE SQUASH BLOCKS** REQ'D UNDER CONCENTRATED LOADS. SEE FIGURE 1. **CANTILEVERED JOISTS** INCLUDING **CANT' OVER BRICK** REQ. I-JOIST BLOCKING ALO BEARING AND RIMBOARD CLOSURE AT ENDS. SEE FIGURE 7 TABLES 4 & 5 FOR REINFORCEMENT REQUIREMENTS. FOR **HOLES** INCLUDING **DUCT CHASE** AND **FIEL CUT OPENINGS** SEE FIGURE 7 TABLES 1 & OF THE INSTALLATION GUIDE. **CERAMIC T** APPLICATION AS PER O.B.C. 9.30.6

LOADING:

DESIGN LOADS: L/480.000


LIVE LOAD: 40.0 lb/ft²

DEAD LOAD: 20.0 lb/ft²

SUBFLOOR: 5/8" GLUED AND NAILED

DATE: 2020-08-06

2nd FLOOR



FROM PLAN DATED:

BUILDER: ROYAL PINE HOMES

SITE: CENTREFIELD WEST GORMLEY

MODEL: 2009

ELEVATION: A,B

LOT:

CITY: RICHMOND HILL

SALESMAN: MARIO DICIANO

DESIGNER: AJ

REVISION:

NOTES:

REFER TO THE **NORDIC INSTALLATION** GUIDE FOR PROPER STORAGE AND INSTALLATION.

**SQUASH BLOCKS** OF 2x4, 2x6, 2x8 #2 S.P. REQ'D UNDER INTERIOR UNIFORM LOAD BEARING WALLS. **MULTIPLE SQUASH BLOCKS** REQ'D UNDER CONCENTRATED LOADS. SEE FIGURE 1. **CANTILEVERED JOISTS** INCLUDING **CANT' OVER BRICK** RI I-JOIST BLOCKING ALONG BEARING AND RIMBOARD CLOSURE AT ENDS. SEE FIGURES 4 & 5 FOR REINFORCEMENT REQUIREMENTS. FOR **HOLES** INCLUDING **DUCT CHASE** AND **FIELD CUT OPENINGS** SEE FIGURE 7, TABLES 1 & 2. **CERAMIC T** APPLICATION AS PER O.B.C 9.30.6.

LOADING:


DESIGN LOADS: L/480.000

LIVE LOAD: 40.0 lb/ft²

DEAD LOAD: 20.0 lb/ft²

SUBFLOOR: 3/4" GLUED AND NAILED


DATE: 2020-07-22



Products				
PlotID	Length	Product	Plies	Net Qty
J1	12-00-00	11 7/8" NI-40x	1	2
J2	10-00-00	11 7/8" NI-40x	1	3
J2DJ	10-00-00	11 7/8" NI-40x	2	2
J3	6-00-00	11 7/8" NI-40x	1	7
J4	4-00-00	11 7/8" NI-40x	1	3
J5	2-00-00	11 7/8" NI-40x	1	4
J6	20-00-00	11 7/8" NI-80	1	18
B3	20-00-00	1-3/4" x 11-7/8" VERSA-LAM® 2.0 3100 SP	2	2
B6	12-00-00	1-3/4" x 11-7/8" VERSA-LAM® 2.0 3100 SP	2	2
B1	10-00-00	1-3/4" x 11-7/8" VERSA-LAM® 2.0 3100 SP	1	1/
B2	10-00-00	1-3/4" x 11-7/8" VERSA-LAM® 2.0 3100 SP	2	2/
B4	10-00-00	1-3/4" x 11-7/8" VERSA-LAM® 2.0 3100 SP	2	2/
B5	6-00-00	1-3/4" x 11-7/8" VERSA-LAM® 2.0 3100 SP	1	1.
B8	6-00-00	1-3/4" x 11-7/8" VERSA-LAM® 2.0 3100 SP	1	1
B9	6-00-00	1-3/4" x 11-7/8" VERSA-LAM® 2.0 3100 SP	1	1
B7	4-00-00	1-3/4" x 11-7/8" VERSA-LAM® 2.0 3100 SP	1	1

Connector Summary		
Qty	Manuf	Product
8	H1	IUS2.56/11.88
7	H1	IUS2.56/11.88
4	H1	IUS2.56/11.88
2	H2	HUS1.81/10
3	H2	HUS1.81/10
1	H4	HGUS410

1st FLOOR



FROM PLAN DATED:

BUILDER: ROYAL PINE HOMES

SITE: CENTREFIELD WEST GORMLEY

MODEL: 2009

ELEVATION: A,B

LOT:

CITY: RICHMOND HILL

SALESMAN: MARIO DICIANO

DESIGNER: AJ


REVISION:

NOTES:  
REFER TO THE NORDIC **INSTALLATION GUIDE** FOR PROPER STORAGE AND INSTALLATION. **SQUASH BLOCKS** OF 2x4, 2x6, 2x8 #2 S.P.F. REQ'D UNDER INTERIOR UNIFORM LOAD BEARING WALLS. **MULTIPLY SQUASH BLOCKS** REQ'D UNDER CONCENTRATED LOADS. SEE FIGURE 1. **CANTILEVERED JOISTS** INCLUDING **CANT' OVER BRICK** REQ. I-JOIST BLOCKING ALSO BEARING AND RIMBOARD CLOSURE AT ENDS. SEE FIGURE 7 TABLES 4 & 5 FOR REINFORCEMENT REQUIREMENTS. FOR **HOLES** INCLUDING **DUCT CHASE** AND **FIEL CUT OPENINGS** SEE FIGURE 7 TABLES 1 & 2 OF THE INSTALLATION GUIDE. **CERAMIC T** APPLICATION AS PER O.B.C. 9.30.6

LOADING:  
DESIGN LOADS: L/480.000  
LIVE LOAD: 40.0 lb/ft²  
DEAD LOAD: 20.0 lb/ft²  
SUBFLOOR: 5/8" GLUED AND NAILED


DATE: 2020-07-27

2nd FLOOR



Products				
PlotID	Length	Product	Plies	Net Qty
J1	20-00-00	11 7/8" NI-40x	1	7
J2	16-00-00	11 7/8" NI-40x	1	2
J3	12-00-00	11 7/8" NI-40x	1	11
J4	10-00-00	11 7/8" NI-40x	1	4
J5	4-00-00	11 7/8" NI-40x	1	7
J6	20-00-00	11 7/8" NI-80	1	21
B11	20-00-00	1-3/4" x 11-7/8" VERSA-LAM® 2.0 3100 SP	2	2
B15	18-00-00	1-3/4" x 11-7/8" VERSA-LAM® 2.0 3100 SP	2	2
B13	14-00-00	1-3/4" x 11-7/8" VERSA-LAM® 2.0 3100 SP	1	1
B14	10-00-00	1-3/4" x 11-7/8" VERSA-LAM® 2.0 3100 SP	2	2
B12	8-00-00	1-3/4" x 11-7/8" VERSA-LAM® 2.0 3100 SP	1	1
B10	4-00-00	1-3/4" x 11-7/8" VERSA-LAM® 2.0 3100 SP	2	2

Connector Summary		
Qty	Manuf	Product
9	H1	IUS2.56/11.88
2	H1	IUS2.56/11.88
1	H2	HUS1.81/10
2	H2	HUS1.81/10
1	H3	IUS3.56/11.88
1	H4	HGUS410




The mark of  
responsible forestry

SI units conversion: 1 inch = 25.4 mm

See table below for web stiffener size requirements:

Flange Width	Web Stiffener Size Each Side of Web
2-1/2"	1" x 2-5/16" minimum width
3-1/2"	1-1/2" x 2-5/16" minimum width



Ni-20	Ni-40x	Ni-40	Ni-70	Ni-8D	Ni-90	Ni-90x
S-RF No.2	1950I MSR	2100I MSR	1950I MSR	2100I MSR	2400I MSR	NPG Lumber
33 pieces per unit	33 pieces per unit	33 pieces per unit	23 pieces per unit	23 pieces per unit	23 pieces per unit	23 pieces per unit


Nordic Engineered Wood I-joists use only finger-jointed black spruce lumber in their flanges, ensuring consistent quality, superior strength and longer span carrying capacity.

1. Before laying out floor system components, verify that I-joint flange widths match larger widths. If not, engineer's approval is required.
2. Except for cutting to length, I-joint flanges should **never** be cut, drilled, or notched.
3. Install I-joists so that top and bottom flanges are within 1/2 inch of true vertical alignment.
4. I-joists must be anchored securely to supports before floor sheathing is attached, and supports for multiple-span joists must be level.
5. Minimum bearing lengths: 1-3/4 inches for end bearings and 3-1/2 inches for intermediate bearings.
6. When using hangers, seat I-joists firmly in hanger bottoms to minimize settlement.
7. Leave a 1/16-inch gap between the I-joint end and a header.
8. Concentrated loads greater than those that can normally be expected in residential construction should only be applied to the top surface of the top flange. Normal concentrated loads include track lighting fixtures, audio equipment and security cameras. Never suspend unusual or heavy loads from the I-joint's bottom flange. Whenever possible, suspend all concentrated loads from the top of the I-joint. Or, attach the load to blocking that has been securely fastened to the I-joint webs.
9. Never install I-joists where they will be permanently exposed to weather, or where they will remain in direct contact with concrete or masonry.
10. Restrain ends of floor joists to prevent rollover. Use rim board, rim joists or I-joint blocking panels.
11. For I-joists installed over and beneath bearing walls, use full depth blocking panels, rim board, or squash blocks (cripple members) to transfer gravity loads from the floor system to the wall or foundation below.
12. Due to shrinkage, common framing lumber set on edge **may never** be used as blocking or rim boards. I-joint blocking panels or other engineered wood products – such as rim board – must be cut to fit between the I-joists, and an I-joint-compatible depth selected.
13. Provide permanent lateral support of the bottom flange of all I-joists at interior supports of multiple-span joists. Similarly, support the bottom flange of all cantilevered I-joists at the end support next to the cantilever extension. In the completed structure, the gypsum wallboard ceiling provides this lateral support. Until the final finished ceiling is applied, temporary bracing or struts must be used.
14. If square-edge panels are used, edges must be supported between I-joists with 2x4 blocking. Glue panels to blocking to minimize squeaks. Blocking is not required under structural finish flooring, such as wood strip flooring, or if a separate underlayment layer is installed.
15. Nail spacing: Space nails installed to the flange's top face in accordance with the applicable building code requirements or approved building plans.


Figure 3 is an isometric view of a floor joist assembly. The diagram shows a network of joists and cross-bracing. Labels with leader lines point to various parts:
 

- 1d, 1e**: Point to the top surface of a joist.
- 1g**: Points to a vertical hanger or support.
- Nordic Lam or Structural Composite Lumber (SCL)**: Points to the main joist members.
- 1b, 1c**: Point to the bottom surface of a joist.
- 1j**: Points to a cross-bracing member.
- 1p**: Points to a small vertical support or clip.
- 1a, 1n**: Point to the bottom edge of the assembly.
- 1f**: Points to the side of a joist.
- 1h, 1j, 1k, 1m**: Point to different types of hangers or fasteners.
- NOTE**: A box containing the text "NOTE: Never cut or notch flanges." with a leader pointing to a joist flange.
- Figures 3, 4 or 5**: Points to a specific hanger type.
- Use hangers recognized in current code evaluation reports**: A text box with a leader pointing to a hanger.
- Holes may be cut in webs for plumbing, wiring or duct work. See Tables and Figure 7.**: A text box at the top right.

All nails shown in the above details are assumed to be common wire nails unless otherwise noted. 3" (0.122" dia.) common spiral nails may be substituted for 2-1/2" (0.128" dia.) common wire nails. Framing lumber assumed to be Spruce-Pine-Fir No. 2 or better. Individual components not shown to scale for clarity.




Transfer load from above to bearing below. Install squash blocks per detail 1d. Match bearing area of blocks below to post above.




Wall sheathing, if required, is used.

Rim board may be used in lieu of I-joists. Backer is not required when rim board is used. Bracing per code shall be carried to the foundation.




2-1/2" nails at  
6" o.c. to top plate

Ni blocking post  
per detail




2015-04-16



Blocking Panel or Rim Joist	Maximum Factored Uniform Vertical Load* (plf)
N/ Joists	3.300


\*The uniform vertical load is limited to a joist depth of 16 inches or less and is based on standard term load duration. It shall not be used in the design of a bending member, such as joist, header, or rafter. For concentrated vertical load transfer, see detail 1d.



Blocking Panel or Rim Joist	Maximum Factored Uniform Vertical Load* (plf)
--------------------------------	--

1-1/8" Rim Board Plus	8,090
-----------------------	-------

The uniform vertical load is limited to a rim board depth of 16" or less and is based on standard term load duration. It shall be used in the design of a bending member, such as joist, headed after. For concentrated vertical load transfer, see detail 1D.




NI rim joist per detail 1a

Attach I-joist per detail 1b

Attach rim joist to top plate per detail 1a


Minimum 1-3/4" bearing required



Pair of Squash Blocks	Maximum Factored Vertical per Pair of Squash Blocks (lbs)	
	2.1/20 in. wide	5.1/20 in. wide

	3-1/2" wide	5-1/2" wide
Number	5,500	8,500
1/8" Rim Board Plus	4,300	6,600


See lateral bracing per detail 1a, 1b, or 1c



**Notes:**

1. Support back of I-joist web during nailing to prevent damage to web/flange connection.
2. Leave a 1/8 to 1/4-inch gap between top of filler block and bottom of top I-joist flange.
3. Filler block is required between joists for full length of span.
4. Nail joists together with two rows of 3" nails at 12 inches o.c. (climbed when possible) on each side of the double I-joist. Total of four nails per foot required. If nails can be clinched, only two nails per foot are required.
5. The maximum factored load that may be applied to one side of the double joist using this detail is 860 lb/ft. Verify double I-joist capacity.

Flange Size	Joist Depth	Filler Block Size
2-1/2" x 1-1/2"	9-1/2" 11-7/8" 14" 16"	2-1/8" x 6" 2-1/8" x 8" 2-1/8" x 10" 2-1/8" x 12"
3-1/2" x 1-1/2"	9-1/2" 11-7/8" 14" 16"	3" x 6" 3" x 8" 3" x 10" 3" x 12"
3-1/2" x 2"	11-7/8" 14" 16"	3" x 7" 3" x 9" 3" x 11"



**(Tr)**

Lumber 2x4 min., extend block to face of adjacent web.

Two 2-1/2" spiral nails from each web to lumber piece, alternate on opposite side.

NI blocking panel

**Optional:** Minimum 1x4 inch strip applied to underside of joist or blocking line or 1/2 inch minimum gypsum ceiling attached to underside of joists.




Diagram illustrating the nailing schedule for blocking:

- One 2-1/2" nails at top and bottom flange
- Two 2-1/2" nails from each web to lumber piece
- Rim board
- 2x4 min. (1/8" gap minimum)
- Two 2-1/2" nails from each web to lumber piece
- 1-joist blocking panel
- 1.5"
- One 2-1/2" nails one side only
- 2-1/2" nails at 6' o.c.

Notes:

- For local codes, blocking is prescriptively required in first joist space (for first and second joist space) next to starter joist. Where required, see local code requirements for spacing of the blocking.
- For more information, consult with your local building department.

**3a I-JOIST CANTILEVER DETAIL FOR BALCONIES (No Wall Load)**

Labels for 3a: Cantilever extension supporting uniform floor loads only; Rim board or wood structural panel closure; attach per detail 1b; Attach I-joists to plate at all supports per detail 1b; I-joist, or rim board; 3-1/2" min. bearing required; # minimum where L is less than 10 ft. span; CAUTION: Cantilevers formed this way must be carefully detailed to prevent moisture intrusion into the structure and potential decay of untreated I-joist extensions; Note: This detail is applicable to cantilevers supporting a maximum specified uniform live load of 60 psf.

**3b LUMBER CANTILEVER DETAIL FOR BALCONIES (No Wall Load)**

Labels for 3b: Full depth backer block with 1/8" gap between block and top flange of I-joist. See detail 1h. Nail with 2 rows of 3" nails at 6" o.c. and clinch.; 2x8 min. Nail to backer block and joist with 2 rows of 3" nails at 6" o.c. and clinch. (Cantilever nails may be used to attach backer block if length of nail is sufficient to allow clinching.); Cantilever extension supporting uniform floor loads only; Lumber or wood structural panel closure; 3-1/2" min. bearing required; I-joist, or rim board; Attach I-joists to plate at all supports per detail 1b; # minimum where L is less than 10 ft. span of cantilever; 1-1/2" + L

**(4a) Method 1 — SHEATHING REINFORCEMENT TWO SIDES**

Rim board or wood structural panel closure (3/4\" minimum thickness); attach per detail 1b

6\" o.c.

2-1/2\" nails

3-1/2\" min. bearing required

12\" maximum

4\" minimum

NI blocking panel or rim board blocking, attach per detail 1g

Attach I-joist to plate per detail 1b

**Method 2 — SHEATHING REINFORCEMENT TWO SIDES**

- Use same installation as Method 1 but reinforce both sides of I-joist with sheathing.
- Use nailing pattern shown for Method 1 with opposite face nailing offset by 3\".

**Note:** Canadian softwood plywood sheathing or equivalent (minimum thickness 3/4\") required on sides of joist. Depth shall match the full height of the joist. Nail with 2-1/2\" nails at 6\" o.c., top and bottom flange. Install with face grain horizontal. Attach I-joist to plate at all supports per detail 1b. Verify reinforced I-joist capacity.

**(4b) Alternate Method 2 — DOUBLE I-JOIST**

Rim board, or wood structural panel closure (3/4\" minimum thickness); attach per detail 1b

2-1/2\" nails

3-1/2\" min. bearing required

12\" maximum

4\" minimum

NI blocking panel or rim board blocking, attach per detail 1g

Face nail two rows of 3\" nails at 12\" o.c. each side through one I-joist web and the filler block to other I-joist web. Offset nails from opposite face by 6\".

Clinch if possible (four nails per foot required, except two nails per foot required if clinched).

Block I-joists together with filler blocks for the full length of the reinforcement.

For I-joist lengths greater than 3 inches place an additional row of 3\" nails along the centreline of the reinforcing panel from each side. Clinch when possible.

FIGURE 4 (continued)

See table below for NI reinforcement requirements at cantilever.

Roof truss span

2-0\" maximum cantilever

Roof trusses

Roof truss span

13-0\" maximum

Jack trusses

2-0\" maximum cantilever

For hip roofs with the jack trusses running parallel to the confluent floor joists, the I-joist reinforcement requirements for a span of 26 ft. shall be permitted to be used.

**CANTILEVER REINFORCEMENT METHODS ALLOWED**

JOIST DEPTH (in.)	ROOF TRUSS SPAN (ft.)	ROOF LOADING (UNFACTORED)											
		LL = 30 psf, DL = 15 psf				LL = 40 psf, DL = 15 psf				LL = 50 psf, DL = 15 psf			
		JOIST SPACING (in.)				JOIST SPACING (in.)				JOIST SPACING (in.)			
		12	16	19.2	24	12	16	19.2	24	12	16	19.2	24
9-1/2"	26	N	N	1	2	N	N	1	2	N	N	1	2
	28	N	N	1	X	N	1	2	X	N	2	X	X
	30	N	1	1	X	N	1	2	X	1	2	X	X
	32	N	1	2	X	N	2	X	X	1	X	X	X
	34	N	1	2	X	N	2	X	X	1	X	X	X
11-7/8"	26	N	1	2	X	1	2	X	X	1	X	X	X
	28	N	N	N	1	N	N	1	2	N	N	1	2
	30	N	N	1	1	N	N	1	2	N	1	2	X
	32	N	N	1	2	N	1	1	X	N	1	2	X
	36	N	N	1	2	N	1	2	X	N	1	2	X
14"	26	N	N	1	2	N	1	2	X	N	2	X	X
	28	N	N	N	N	N	N	N	1	N	N	N	1
	30	N	N	N	N	N	N	N	1	N	N	1	2
	32	N	N	N	1	N	N	N	1	N	N	1	2
	34	N	N	N	1	N	1	1	N	N	N	1	2
16"	36	N	N	N	1	N	N	1	2	N	1	1	2
	38	N	N	N	1	N	N	1	2	N	1	1	X
	40	N	N	N	1	N	N	1	2	N	1	2	X
	26	N	N	N	N	N	N	N	N	N	N	N	1
	28	N	N	N	N	N	N	N	1	N	N	N	1
16"	30	N	N	N	N	N	N	N	1	N	N	N	1
	32	N	N	N	N	N	N	N	1	N	N	1	1
	34	N	N	N	N	N	N	N	1	N	N	1	2
	36	N	N	N	1	N	N	1	N	N	N	1	2
	38	N	N	N	1	N	N	1	2	N	N	1	2
16"	40	N	N	N	1	N	N	1	2	N	N	1	X
	42	N	N	N	1	N	N	1	2	N	N	1	X

1. N = No reinforcement required.

### 5a SHEATHING REINFORCEMENT

**Note:** Canadian softwood plywood sheathing or equivalent (minimum thickness 3/4") required on sides of joist. Depth shall match the full height of the joist. Nail with 2-1/2" nails at 6" o.c., top and bottom flange. Install with face grain horizontal. Attach l-joint to plate at all supports per detail 1b. Verify reinforced l-joint capacity.

### FIGURE 4 (continued)

Roof truss span  
2'-0" maximum cantilever  
5" maximum

Girder truss  
Roof truss span  
13'-0" maximum  
2'-0" maximum cantilever  
5" maximum

For hip roofs with the jack trusses running parallel to the cantilevered floor joists, the l-joint reinforcement requirements for a span of 26 ft. shall be permitted to be used.

### 5b SET-BACK DETAIL

**Notes:**

- Provide full depth blocking between joists over support (not shown for clarity)
- Attach l-joint to plate at all supports per detail 1b.
- 3-1/2" minimum l-joint bearing required.

### 5c SET-BACK CONNECTION

**Notes:**

- Verify girder joist capacity if the back span exceeds the joist spacing.
- Attach double l-joint per detail 1p, if required.

### BRICK CANTILEVER REINFORCEMENT METHODS ALLOWED

JOIST DEPTH (in)	ROOF TRUSS SPAN (ft)	ROOF LOADING (UNFACTORED)														
		U = 60 psf, DLE = 16 psf						U = 40 psf, DLE = 16 psf								
		JOIST SPACING (in)						JOIST SPACING (in)								
		12	16	19.2	24		12	16	19.2	24		12	16	19.2	24	
9-1/2"	26	N	1	X	X	X	2	X	X	X	2	X	X	X	X	
	28	1	X	X	X	2	X	X	X	2	X	X	X	X		
	30	1	X	X	X	2	X	X	X	2	X	X	X	X		
	32	2	X	X	X	2	X	X	X	2	X	X	X	X		
	34	2	X	X	X	2	X	X	X	2	X	X	X	X		
11-7/8"	26	N	2	X	X	X	N	2	X	X	1	X	X	X		
	28	N	2	X	X	1	X	X	1	X	1	X	X			
	30	1	2	X	X	1	X	X	1	X	2	X	X			
	32	1	2	X	X	1	X	X	1	X	2	X	X			
	34	1	2	X	X	2	X	X	2	X	2	X	X			
14"	26	N	2	X	X	2	N	2	X	X	2	X	X	X		
	28	N	2	X	X	1	X	X	1	X	2	X	X			
	30	N	2	X	X	1	X	X	1	X	2	X	X			
	32	N	2	X	X	1	X	X	1	X	2	X	X			
	34	N	2	X	X	1	X	X	1	X	2	X	X			
16"	26	N	2	X	X	2	N	2	X	X	2	X	X	X		
	28	N	2	X	X	1	X	X	1	X	2	X	X			
	30	N	2	X	X	1	X	X	1	X	2	X	X			
	32	N	2	X	X	1	X	X	1	X	2	X	X			
	34	N	2	X	X	1	X	X	1	X	2	X	X			

**1. N = No reinforcement required.**

**1. = Nl reinforced with 3/4" wood structural panel on one side only.**

**2. = Nl reinforced with 3/4" wood structural panel on both sides, or double l-joint.**

**X = Try a deeper joist or closer spacing.**

**2. Maximum design load shall be: 15 psf roof dead load, 35 psf floor total load, and 80 psf wall load. Wall load is based on 3'-0" maximum width window or door openings.**

**For larger openings, or multiple 3'-0" width openings spaced less than 6'-0" o.c., additional joists beneath the opening's cripple studs may be required.**

**3. Table applies to joists 12" to 24" o.c. that meet the floor span requirements for a design live load of 40 psf and dead load of 15 psf, and a live load deflection limit of L/480. Use 12" o.c. requirements for lesser spacing.**

**4. For conventional roof construction using a ridge beam, the Roof Truss Span column above is equivalent to the distance between the supporting wall and the ridge beam. When the roof is framed using a ridge board, the Roof Truss Span is equivalent to the distance between the supporting walls as if a truss is used.**

**5. Cantilevered joists supporting girder trusses or roof beams may require additional reinforcing.**

See Table 1 for minimum distance from bearing

2x diameter of larger hole

2x duct chase length or hole diameter, whichever is larger

Duct chase opening (see Table 2 for minimum distance from bearing)

3/4x diameter

Knockouts

See rule 12

Maintain minimum 1/8" space between top and bottom flange — all duct chase openings and holes

A knockout is **NOT** considered a hole, may be utilized wherever it occurs and may be ignored for purposes of calculating minimum distances between holes.

**IMPORTANT NOTE:**  
Floor sheathing must be field glued to the I-joist flanges in order to achieve the maximum spans shown in this document. If sheathing is nailed only, I-joist spans must be verified with your local distributor.

Where:

- $D_{\text{reduced}} = \frac{\text{actual}}{\text{SAF}} \times D$
- $D_{\text{reduced}}$  = Distance from the inside face of any support to centre of hole, reduced for less-than-maximum span applications (ft). The reduced distance shall not be less than 6 inches from the face of the support to edge of the hole.
- $\text{actual}$  = The actual measured span distance between the inside faces of supports (ft).
- $\text{SAF}$  = Span Adjustment Factor given in this table.
- $D$  = The minimum distance from the inside face of any support to centre of hole from this table.

If  $\frac{\text{actual}}{\text{SAF}}$  is greater than 1, use 1 in the above calculation for  $\frac{\text{actual}}{\text{SAF}}$ .

1. Above table may be used for I-joist spacing of 24 inches on centre or less.
2. Duct chase opening location distance is measured from inside face of supports to centre of opening.
3. The above table is based on simple-span joists only. For other applications, contact your local distributor.
4. Distances are based on uniformly loaded floor joists that meet the span requirements for a design live load of 40 psf and dead load of 15 psf, and a live load deflection limit of L/480. For other applications, contact your local distributor.

Technical drawing showing the connection of a ledger board to an existing wall and joist system. The drawing includes a side elevation and a cross-section.

**Side Elevation Labels:**

- Rim board
- Top or sole plate
- 30°
- $\frac{l}{3}$
- $\frac{l}{2}$

**Cross-section Labels:**

- Existing stud wall
- Rim board
- Floor sheathing
- 1-joist
- Existing foundation wall
- Exterior sheathing
- Remove siding at ledger prior to installation
- Continuous flashing extending at least 3" past joist hanger
- Staggered 1/2" diameter log screws or thru-balls with washers
- Deck joist
- Joist hanger

**Dimensions:**

- 1'-5/8" min.
- 5" max.
- 2" min.

**Notes:**

- 2x ledger board (preservative-treated); must be greater than or equal to the depth of the deck joist

Chattler Chibugamau guarantees that, in accordance with our specifications, Nordic products are free from manufacturing defects in material and workmanship.

Furthermore, Chattler Chibugamau warrants that our products, when utilized in accordance with our handling and installation instructions, will meet or exceed our specifications for the lifetime of the structure.





	NI-20	NI-40x	NI-60	NI-70	NI-80	NI-90	NI-90x
S-R-F No.2	OSB 3/8"	OSB 3/8"	OSB 3/8"	OSB 3/8"	OSB 3/8"	OSB 3/8"	OSB 3/8"
1950f MSR	1950f MSR	2100f MSR	1950f MSR	2100f MSR	2400f MSR	2400f MSR	NPG Lumber
33 pieces per unit	33 pieces per unit	33 pieces per unit	23 pieces per unit	23 pieces per unit	23 pieces per unit	23 pieces per unit	23 pieces per unit

## WEB HOLE SPECIFICATIONS

### RULES FOR CUTTING HOLES AND DUCT CHASE OPENINGS:

- The distance between the inside edge of the support and the centreline of any hole or duct chase opening shall be in compliance with the requirements of Table 1 or 2, respectively.
- I-joist top and bottom flanges must NEVER be cut, notched, or otherwise modified.
- Whenever possible, field-cut holes should be centred on the middle of the web.
- The maximum size hole or the maximum depth of a duct chase opening that can be cut into an I-joist web shall equal the clear distance between the flanges of the I-joist minus 1/4 inch. A minimum of 1/8 inch should always be maintained between the top or bottom of the hole or opening and the adjacent I-joist flange.

- The sides of square holes or longest sides of rectangular holes should not exceed 3/4 of the diameter of the maximum round hole permitted at that location.
- Where more than one hole is necessary, the distance between adjacent hole edges shall exceed twice the diameter of the largest round hole or twice the size of the largest square hole (or twice the length of the longest side of the longest rectangular hole or duct chase opening) and each hole and duct chase opening shall be sized and located in compliance with the requirements of Tables 1 and 2, respectively.
- A knockout is not considered a hole, may be utilized anywhere it occurs, and may be ignored for purposes of calculating minimum distances between holes and/or duct chase openings.
- Holes measuring 1-1/2 inches or smaller are permitted anywhere in a cantilevered section of a joist. Holes of greater size may be permitted subject to verification.

- A 1-1/2 inch hole or smaller can be placed anywhere in the web provided that it meets the requirements of rule number 6 above.
- All holes and duct chase openings shall be cut in a workman-like manner in accordance with the restrictions listed above and as illustrated in Figure 7.
- Limit three maximum size holes per span, of which one may be a duct chase opening.
- A group of round holes at approximately the same location shall be permitted if they meet the requirements for a single round hole circumscribed around them.

TABLE 1  
LOCATION OF CIRCULAR HOLES IN JOIST WEBS  
Simple or Multiple Span for Dead Loads up to 15 psf and Live Loads up to 40 psf

Joist Depth	Joist Series	Minimum Distance from Inside Face of Any Support to Centre of Hole (ft - in.)											
		Round Hole Diameter (in.)											
		2	3	4	5	6	6-1/4	7	8	8-5/8	9	10	10-3/4
9-1/2"	NI-20	0-7"	1-6"	2-10"	4-3"	5-8"	6-0"	---	---	---	---	---	---
	NI-40x	0-7"	1-6"	3-0"	4-4"	6-0"	6-4"	---	---	---	---	---	---
	NI-60	1-3"	2-6"	4-0"	5-4"	7-0"	7-5"	---	---	---	---	---	---
	NI-70	2-0"	3-4"	4-9"	6-3"	8-0"	8-4"	---	---	---	---	---	---
	NI-80	2-3"	3-6"	5-0"	6-6"	8-2"	8-8"	---	---	---	---	---	---
11-7/8"	NI-20	0-7"	0-8"	1-0"	2-4"	3-8"	4-0"	5-0"	6-6"	7-9"	---	---	---
	NI-40x	0-7"	0-8"	1-3"	2-8"	4-0"	4-4"	5-5"	7-0"	8-4"	---	---	---
	NI-60	0-7"	1-8"	3-0"	4-3"	5-9"	6-0"	7-3"	8-10"	10-0"	---	---	---
	NI-70	1-3"	2-6"	4-0"	5-4"	6-9"	7-2"	8-4"	10-0"	11-2"	---	---	---
	NI-80	1-6"	2-10"	4-2"	5-6"	7-0"	7-5"	8-6"	10-3"	11-4"	---	---	---
14"	NI-20	0-7"	0-8"	1-5"	3-2"	4-10"	5-4"	6-9"	8-9"	10-2"	---	---	---
	NI-40x	0-7"	0-8"	0-9"	2-5"	4-4"	4-9"	6-3"	---	---	---	---	---
	NI-60	0-7"	0-8"	0-8"	1-0"	2-4"	2-9"	3-9"	5-2"	6-0"	6-6"	8-3"	10-2"
	NI-70	0-7"	0-8"	1-8"	3-0"	4-3"	4-8"	5-8"	7-2"	8-0"	8-8"	10-4"	11-9"
	NI-80	0-7"	0-8"	1-10"	3-0"	4-5"	5-10"	6-2"	7-3"	8-9"	9-9"	10-4"	12-0"
16"	NI-20	0-7"	0-8"	0-8"	1-6"	2-10"	3-2"	4-2"	5-6"	6-4"	7-0"	8-5"	9-8"
	NI-40x	0-7"	0-8"	0-8"	1-6"	2-10"	3-2"	4-2"	5-6"	6-4"	7-0"	8-5"	9-8"
	NI-60	0-7"	0-8"	1-8"	3-0"	4-3"	4-8"	5-8"	7-2"	8-0"	8-8"	10-4"	11-9"
	NI-70	0-7"	0-8"	1-10"	3-0"	4-5"	5-10"	6-2"	7-3"	8-9"	9-9"	10-4"	12-0"
	NI-80	0-7"	0-8"	1-10"	3-0"	4-5"	5-10"	6-2"	7-3"	8-9"	9-9"	10-4"	12-0"



- Above table may be used for I-joist spacing of 24 inches on centre or less.
- Hole location distance measured from inside face of supports to centre of hole.
- Distances in this chart are based on uniformly loaded joists.
- The above table is based on the I-joists being used at their maximum spans. The minimum distance as given above may be reduced for shorter spans; contact your local distributor.

TABLE 2  
DUCT CHASE OPENING SIZES AND LOCATIONS  
Simple Span Only

Joist Depth	Joist Series	Minimum distance from inside face of supports to centre of opening (ft - in.)											
		Duct Chase Length (in.)											
		8	10	12	14	16	18	20	22	24			
9-1/2"	NI-20	4-1"	4-5"	4-10"	5-4"	5-8"	6-1"	6-6"	7-1"	7-5"			
	NI-40x	5-3"	5-8"	6-0"	6-5"	6-10"	7-3"	7-8"	8-2"	8-6"			
	NI-60	5-4"	5-9"	6-2"	6-7"	7-1"	7-5"	8-0"	8-3"	8-9"			
	NI-70	5-1"	5-5"	5-10"	6-3"	6-7"	7-1"	7-6"	8-1"	8-4"			
	NI-80	5-3"	5-8"	6-0"	6-5"	6-10"	7-3"	7-8"	8-2"	8-6"			
11-7/8"	NI-20	5-9"	6-2"	6-6"	7-1"	7-5"	7-9"	8-3"	8-9"	9-4"			
	NI-40x	6-8"	7-2"	7-6"	8-1"	8-6"	9-1"	9-6"	10-1"	10-9"			
	NI-60	7-3"	7-8"	8-0"	8-6"	9-0"	9-3"	9-9"	10-3"	11-0"			
	NI-70	7-1"	7-4"	7-9"	8-3"	8-7"	9-1"	9-6"	10-1"	10-4"			
	NI-80	7-2"	7-7"	8-0"	8-5"	8-10"	9-3"	9-8"	10-2"	10-8"			
14"	NI-20	7-6"	7-11"	8-4"	8-9"	9-2"	9-7"	10-1"	10-7"	10-11"			
	NI-40x	7-7"	8-1"	8-5"	8-10"	9-4"	9-8"	10-2"	10-8"	11-2"			
	NI-60	8-1"	8-7"	9-0"	9-6"	10-1"	10-6"	11-1"	11-6"	12-0"			
	NI-70	8-9"	9-3"	9-8"	10-1"	10-6"	11-1"	11-6"	12-1"	12-3"			
	NI-80	8-7"	9-1"	9-5"	10-1"	10-4"	10-8"	11-2"	11-7"	12-3"			
16"	NI-20	9-0"	9-3"	9-9"	10-1"	10-7"	11-1"	11-6"	12-1"	12-6"			
	NI-40x	9-2"	9-8"	10-0"	10-6"	10-11"	11-5"	11-9"	12-4"	12-11"			
	NI-60	9-4"	9-9"	10-3"	10-7"	11-1"	11-7"	12-1"	12-7"	13-2"			
	NI-70	10-3"	10-8"	11-2"	11-6"	12-1"	12-6"	13-2"	14-1"	14-10"			
	NI-80	10-1"	10-5"	11-0"	11-4"	11-10"	12-3"	12-8"	13-3"	14-0"			

- Above table may be used for I-joist spacing of 24 inches on centre or less.
- Duct chase opening location distance is measured from inside face of supports to centre of opening.
- The above table is based on simple-span joists only. For other applications, contact your local distributor.
- Distances are based on uniformly loaded floor joists that meet the span requirements for a design live load of 40 psf and dead load of 15 psf, and a live load deflection limit of L/480.
- The above table is based on the I-joists being used at their maximum spans. The minimum distance as given above may be reduced for shorter spans; contact your local distributor.

FIGURE 7  
FIELD-CUT HOLE LOCATOR



Knockouts are prescored holes provided for the contractor's convenience to install electrical or small plumbing lines. They are 1-1/2 inches in diameter, and are spaced 15 inches on centre along the length of the I-joist. Where possible, it is preferable to use knockouts instead of field-cut holes.

Never drill, cut or notch the flange, or over-cut the web.


Holes in webs should be cut with a sharp saw.

For rectangular holes, avoid over-cutting the corners, as this can cause unnecessary stress concentrations. Slightly rounding the corners is recommended. Starting the rectangular hole by drilling a 1-inch diameter hole in each of the four corners and then making the cuts between the holes is another good method to minimize damage to the I-joist.

## SAFETY AND CONSTRUCTION PRECAUTIONS



Do not walk on I-joists until fully fastened and braced, or serious injuries can result.



Never stack building materials over unshathed I-joists. Once sheathed, do not over-stress I-joists with concentrated loads from building materials.

WARNING: I-joists are not stable until completely installed, and will not carry any load until fully braced and sheathed.

### AVOID ACCIDENTS BY FOLLOWING THESE IMPORTANT GUIDELINES:

- Brace and nail each I-joist as it is installed, using hangers, blocking panels, rim board, and/or cross-bridging at joist ends. When I-joists are applied continuous over interior supports and a load-bearing wall is planned at that location, blocking will be required at the interior support.
- When the building is completed, the floor sheathing will provide lateral support for the top flanges of the I-joists. Until this sheathing is applied, temporary bracing, often called struts, or temporary sheathing must be applied to prevent I-joist rollover or buckling.
  - Temporary bracing or struts must be 1x4 inch minimum, at least 8 feet long and spaced no more than 8 feet on centre, and must be secured with a minimum of two 2-1/2" nails fastened to the top surface of each I-joist. Nail the bracing to a lateral restraint at the end of each bay. Lap ends of adjoining bracing over at least two I-joists.
  - Or, sheathing (temporary or permanent) can be nailed to the top flange of the first 4 feet of I-joists at the end of the bay.
- For cantilevered I-joists, brace top and bottom flanges, and brace ends with closure panels, rim board, or cross-bridging.
- Install and fully nail permanent sheathing to each I-joist before placing loads on the floor system. Then, stack building materials over beams or walls only.
- Never install a damaged I-joist.


Improper storage or installation, failure to follow applicable building codes, failure to follow span ratings for Nordic I-joists, failure to follow allowable hole sizes and locations, or failure to use web stiffeners when required can result in serious accidents. Follow these installation guidelines carefully.



## PRODUCT WARRANTY

Chantiers Chibougamau guarantees that, in accordance with our specifications, Nordic products are free from manufacturing defects in material and workmanship.


Furthermore, Chantiers Chibougamau warrants that our products, when utilized in accordance with our handling and installation instructions, will meet or exceed our specifications for the lifetime of the structure.



Blocking Panel or Rim Joist	Maximum Factored Uniform Vertical Load* (plf)
NI Joists	3,300


\*The uniform vertical load is limited to a joist depth of 16 inches or less and is based on standard term load duration. It shall not be used in the design of a bending member, such as joist, header, or rafter. For concentrated vertical load transfer, see detail 1d.

2-1/2" nails at 6" o.c. to top plate (when used for lateral shear transfer, nail to bearing plate with same nailing as required for decking)



Pair of Squash Blocks	Maximum Factored Vertical Load per Pair of Squash Blocks (lbs)	
	3-1/2" wide	5-1/2" wide
2x Lumber	5,500	8,500
1-1/8" Rim Board Plus	4,300	6,600

Provide lateral bracing per detail 1a or 1b



Blocking Panel or Rim Joist	Maximum Factored Uniform Vertical Load* (plf)
1-1/8" Rim Board Plus	8,090

\*The uniform vertical load is limited to a rim board depth of 16 inches or less and is based on standard term load duration. It shall not be used in the design of a bending member, such as joist, header, or rafter. For concentrated vertical load transfer, see detail 1d.


One 2-1/2" face nail at each side at bearing

Attach rim board to top plate using 2-1/2" wire or spiral toe-nails at 6" o.c.

To avoid splitting flange, start nails at least 1-1/2" from end of I-joist.

Nails may be driven at an angle to avoid splitting of bearing plate.

Minimum bearing length shall be 1-3/4" for the end bearings, and 3-1/2" for the intermediate bearings when applicable.




BACKER BLOCKS (Blocks must be long enough to permit required nailing without splitting)


Flange Width	Material Thickness Required*	Minimum Depth**
2-1/2"	1"	5-1/2"
3-1/2"	1-1/2"	7-1/4"

\* Minimum grade for backer block material shall be S-R-F No. 2 or better for solid sawn lumber and wood structural panels conforming to CAN/CSA-O325 or CAN/CSA-O437 Standard.


\*\* For face-mount hangers use net joist depth minus 3-1/4" for joists with 1-1/2" thick flanges. For 2" thick flanges use net depth minus 4-1/4".




For hanger capacity see hanger manufacturer's recommendations. Verify double I-joist capacity to support concentrated loads.




NOTE: Unless hanger sides laterally support the top flange, bearing stiffeners shall be used.




NOTE: Unless hanger sides laterally support the top flange, bearing stiffeners shall be used.




Maximum support capacity = 1,620 lbs.



NOTE: Blocking required at bearing for lateral support, not shown for clarity.




OPTIONAL: Minimum 1x4 inch strap applied to underside of joist at blocking line or 1/2 inch minimum gypsum ceiling attached to underside of joists.



- Support back of I-joist web during nailing to prevent damage to web/flange connection.
- Leave a 1/8 to 1/4-inch gap between top of filler block and bottom of top I-joist flange.
- Filler block is required between joists for full length of span.
- Nail joists together with two rows of 3" nails at 12 inches o.c. (clinch when possible) on each side of the double I-joist. Total of four nails per foot required. If nails can be clinched, only two nails per foot are required.
- The maximum factored load that may be applied to one side of the double joist using this detail is 860 lb/ft. Verify double I-joist capacity.

Flange Size	Net Depth	Filler Block Size
2-1/2" x 1-1/2"	9-1/2"	2-1/8" x 6"
	11-7/8"	2-1/8" x 8"
	14"	2-1/8" x 10"
	16"	2-1/8" x 12"
3-1/2" x 1-1/2"	9-1/2"	3" x 6"
	11-7/8"	3" x 8"
	14"	3" x 10"
	16"	3" x 12"
3-1/2" x 2"	11-7/8"	3" x 7"
	14"	3" x 9"
	16"	3" x 11"



NOTE: In some local codes, blocking is prescriptively required in the first joist space (or first and second joist space) next to the starter joist. Where required, see local code requirements for spacing of the blocking. All nails are common spiral in this detail.


All nails shown in the above details are assumed to be common wire nails unless otherwise noted. 3" (0.122" dia.) common spiral nails may be substituted for 2-1/2" (0.128" dia.) common wire nails. Framing lumber assumed to be Spruce-Pine-Fir No. 2 or better. Individual components not shown to scale for clarity.

## WEB STIFFENERS

### RECOMMENDATIONS:

- A bearing stiffener is required in all engineered applications with factored reactions greater than shown in the I-joist properties table found in the I-joist Construction Guide (C101). The gap between the stiffener and the flange is at the top.
- A bearing stiffener is required when the I-joist is supported in a hanger and the sides of the hanger do not extend up to, and support, the top flange. The gap between the stiffener and flange is at the top.
- A load stiffener is required at locations where a factored concentrated load greater than 2,370 lbs is applied to the top flange between supports, or in the case of a cantilever, anywhere between the cantilever tip and the support. These values are for standard term load duration, and may be adjusted for other load durations as permitted by the code. The gap between the stiffener and the flange is at the bottom.


FIGURE 2  
WEB STIFFENER INSTALLATION DETAILS




STIFFENER SIZE REQUIREMENTS	
Flange Width	Web Stiffener Size Each Side of Web
2-1/2"	1" x 2-5/16" minimum width
3-1/2"	1-1/2" x 2-5/16" minimum width

## CANTILEVER DETAILS FOR VERTICAL BUILDING OFFSET

### Method 1 — SHEATHING REINFORCEMENT ONE SIDE



### Method 2 — SHEATHING REINFORCEMENT TWO SIDES



# NORDIC STRUCTURES

**COMPANY**  
July 22, 2020 16:57

**PROJECT**  
J6 1ST FLOOR.wwb


## Design Check Calculation Sheet

Nordic Sizer – Canada 7.2

### Loads:

Load	Type	Distribution	Pat- tern	Location [ft] Start End	Magnitude Start End	Unit
Load1	Dead	Full Area			20.00	psf
Load2	Live	Full Area			40.00	psf

### Maximum Reactions (lbs) and Support Bearing (in):



Unfactored:			
Dead	191		191
Live	383		383
Factored:			
Total	814		814
Bearing:			
Capacity			
Joist	2188		2188
Support	5573		5573
Des ratio			
Joist	0.37		0.37
Support	0.15		0.15
Load case	#2		#2
Length	2-3/8		2-3/8
Min req'd	1-3/4		1-3/4
Stiffener	No		No
KD	1.00		1.00
KB support	1.00		1.00
fcp sup	769		769
Kzcp sup	1.09		1.09

### Nordic 11-7/8" NI-80 Floor joist @ 12" o.c.

Supports: All - Lumber Sill plate, No.1/No.2

Total length: 19' 4-3/4"; Clear span: 19'; 3/4" nailed and glued OSB sheathing

**This section PASSES the design code check.**

### Limit States Design using CSA O86-14 and Vibration Criterion:

Criterion	Analysis Value	Design Value	Unit	Analysis/Design
Shear	Vf = 814	Vr = 2336	lbs	Vf/Vr = 0.35
Moment (+)	Mf = 3894	Mr = 11609	lbs-ft	Mf/Mr = 0.34
Perm. Defl'n	0.11 = < L/999	0.64 = L/360	in	0.17
Live Defl'n	0.22 = < L/999	0.48 = L/480	in	0.46
Total Defl'n	0.33 = L/690	0.96 = L/240	in	0.35
Bare Defl'n	0.25 = L/920	0.64 = L/360	in	0.39
Vibration	Lmax = 19'-1.8	Lv = 21'-2.7	ft	0.90
Defl'n	= 0.026	= 0.033	in	0.78



8666  
DWG NO. TAN 9129 -21  
STRUCTURAL  
COMPONENT ONLY



**Additional Data:**

FACTORS:	f/E	KD	KH	KZ	KL	KT	KS	KN	LC#
Vr	2336	1.00	1.00	-	-	-	-	-	#2
Mr+	11609	1.00	1.00	-	1.000	-	-	-	#2
EI	547.1 million	-	-	-	-	-	-	-	#2

**CRITICAL LOAD COMBINATIONS:**

Shear : LC #2 = 1.25D + 1.5L

Moment(+) : LC #2 = 1.25D + 1.5L

Deflection: LC #1 = 1.0D (permanent)

LC #2 = 1.0D + 1.0L (live)

LC #2 = 1.0D + 1.0L (total)

LC #2 = 1.0D + 1.0L (bare joist)

Bearing : Support 1 - LC #2 = 1.25D + 1.5L

Support 2 - LC #2 = 1.25D + 1.5L

Load Types: D=dead W=wind S=snow H=earth,groundwater E=earthquake

L=live(use,occupancy) Ls=live(storage,equipment) f=fire

Load Patterns: s=S/2 L=L+Ls \_=no pattern load in this span

All Load Combinations (LCs) are listed in the Analysis output

**CALCULATIONS:**EI<sub>eff</sub> = 625.37 lb-in<sup>2</sup> K= 6.18e06 lbs"Live" deflection is due to all non-dead loads (live, wind, snow...) **CONFORMS TO NBC 2012****Design Notes:****AMENDED 2020**

1. WoodWorks analysis and design are in accordance with the 2015 National Building Code of Canada (NBC), Division B, Part 4, and the CSA O86-14 Engineering Design in Wood standard, Update No. 2 (June 2017).
2. Please verify that the default deflection limits are appropriate for your application.
3. Refer to Nordic Structures technical documentation for installation guidelines and construction details.
4. Nordic I-joists are listed in CCMC evaluation report 13032-R.
5. Joists shall be laterally supported at supports and continuously along the compression edge.
6. The design assumptions and specifications have been provided by the client. Any damages resulting from faulty or incorrect information, specifications, and/or designs furnished, and the correctness or accuracy of this information is their responsibility. This analysis does not constitute a record of the structural integrity of the building nor suitability of the design assumptions made. Nordic Structures is responsible only for the structural adequacy of this component based on the design criteria and loadings shown.



10/2/20  
 DWG NO. TAM 9/29 -21  
 STRUCTURAL  
 COMPONENT ONLY

# NORDIC STRUCTURES

COMPANY  
July 22, 2020 08:26


PROJECT  
J5 2ND FLOOR.wwb

## Design Check Calculation Sheet Nordic Sizer – Canada 7.2

### Loads:

Load	Type	Distribution	Pat- tern	Location [ft] Start End	Magnitude Start End	Unit
Load1	Dead	Full Area			20.00	psf
Load2	Live	Full Area			40.00	psf

### Maximum Reactions (lbs) and Support Bearing (in):



Unfactored:			
Dead	188		188
Live	376		376
Factored:			
Total	800		800
Bearing:			
Capacity			
Joist	2336		2336
Support	10841		10841
Des ratio			
Joist	0.34		0.34
Support	0.07		0.07
Load case	#2		#2
Length	4-3/8		4-3/8
Min req'd	1-3/4		1-3/4
Stiffener	No		No
KD	1.00		1.00
KB support	-		-
fcp sup	769		769
Kzcp sup	-		-

Bearing for wall supports is perpendicular-to-grain bearing on top plate. No stud design included.

### Nordic Joist 11-7/8" NI-80 Floor joist @ 12" o.c.


Supports: All - Lumber Wall, No.1/No.2

Total length: 19' 4-3/4"; Clear span: 18' 8"; 5/8" nailed and glued OSB sheathing with 1/2" gypsum ceiling

This section PASSES the design code check.

### Limit States Design using CSA O86-14 and Vibration Criterion:

Criterion	Analysis Value	Design Value	Unit	Analysis/Design
Shear	Vf = 800	Vr = 2336	lbs	Vf/Vr = 0.34
Moment(+)	Mf = 3760	Mr = 11609	lbs-ft	Mf/Mr = 0.32
Perm. Defl'n	0.11 = < L/999	0.63 = L/360	in	0.17
Live Defl'n	0.21 = < L/999	0.47 = L/480	in	0.45
Total Defl'n	0.32 = L/712	0.94 = L/240	in	0.34
Bare Defl'n	0.23 = L/966	0.63 = L/360	in	0.37
Vibration	Lmax = 18'-9.8	Lv = 20'-5.8	ft	0.92
Defl'n	= 0.027	= 0.033	in	0.81



DWG NO. TAM 9130 -21  
STRUCTURAL  
COMPONENT ONLY

**Additional Data:**

FACTORS:	f/E	KD	KH	KZ	KL	KT	KS	KN	LC#
Vr	2336	1.00	1.00	-	-	-	-	-	#2
Mr+	11609	1.00	1.00	-	1.000	-	-	-	#2
EI	547.1 million	-	-	-	-	-	-	-	#2

**CRITICAL LOAD COMBINATIONS:**

Shear : LC #2 = 1.25D + 1.5L

Moment(+) : LC #2 = 1.25D + 1.5L

Deflection: LC #1 = 1.0D (permanent)

LC #2 = 1.0D + 1.0L (live)

LC #2 = 1.0D + 1.0L (total)

LC #2 = 1.0D + 1.0L (bare joist)

Bearing : Support 1 - LC #2 = 1.25D + 1.5L

Support 2 - LC #2 = 1.25D + 1.5L

Load Types: D=dead W=wind S=snow H=earth,groundwater E=earthquake  
L=live(use,occupancy) Ls=live(storage,equipment) f=fire

Load Patterns: s=S/2 L=L+Ls \_=no pattern load in this span

All Load Combinations (LCs) are listed in the Analysis output

**CALCULATIONS:**EI<sub>eff</sub> = 613.27 lb-in<sup>2</sup> K= 6.18e06 lbs

"Live" deflection is due to all non-dead loads (live, wind, snow...)

**CONFORMS TO OBC 2012****Design Notes:****AMENDED 2020**

1. WoodWorks analysis and design are in accordance with the 2015 National Building Code of Canada (NBC), Division B, Part 4, and the CSA O86-14 Engineering Design in Wood standard, Update No. 2 (June 2017).
2. Please verify that the default deflection limits are appropriate for your application.
3. Refer to Nordic Structures technical documentation for installation guidelines and construction details.
4. Nordic I-joists are listed in CCMC evaluation report 13032-R.
5. Joists shall be laterally supported at supports and continuously along the compression edge.
6. The design assumptions and specifications have been provided by the client. Any damages resulting from faulty or incorrect information, specifications, and/or designs furnished, and the correctness or accuracy of this information is their responsibility. This analysis does not constitute a record of the structural integrity of the building nor suitability of the design assumptions made. Nordic Structures is responsible only for the structural adequacy of this component based on the design criteria and loadings shown.



PC42  
 DWG NO. TAM 9/30-21  
 STRUCTURAL  
 COMPONENT ONLY

BC CALC® Member Report

Build 7493

Job name:

Address:

City, Province, Postal Code:

Customer:

Code reports:

CCMC 12472-R


File name: UNIT 2009 EL A,B.mmdl

Description: 1ST FLR FRAMING\Flush Beams\B1(i333)

Specifier:

Designer:

Company:



Total Horizontal Product Length = 08-04-06

### Reaction Summary (Down / Uplift) (lbs)

Bearing	Live	Dead	Snow	Wind
B1, 3-1/2"	1392 / 240	1276 / 0		
B2, 4-3/8"	112 / 0	82 / 0		

### Load Summary

Tag	Description	Load Type	Ref.	Start	End	Loc.	Live 1.00	Dead 0.65	Snow 1.00	Wind 1.15	Tributary
0	Self-Weight	Unf. Lin. (lb/ft)	L	00-00-00	08-04-06	Top		6			00-00-00
1	FC1 Floor Material	Unf. Lin. (lb/ft)	L	00-00-00	08-04-06	Top	27	13			n/a
2	E1(i185)	Conc. Pt. (lbs)	L	00-02-12	00-02-12	Top	1281	1196			n/a
3	E1(i185)	Conc. Pt. (lbs)	L	00-02-12	00-02-12	Top	-240				n/a

### Controls Summary

	Factored Demand	Factored Resistance	Demand/Resistance	Case	Location
Pos. Moment	492 ft-lbs	17696 ft-lbs	2.8%	1	04-01-12
End Shear	184 lbs	7232 lbs	2.5%	1	01-03-06
Total Load Deflection	L/999 (0.008")	n/a	n/a	6	04-01-12
Live Load Deflection	L/999 (0.005")	n/a	n/a	8	04-01-12
Max Defl.	0.008"	n/a	n/a	6	04-01-12
Span / Depth	7.9				


Bearing Supports	Dim. (LxW)	Demand	Demand/Resistance Support	Demand/Resistance Member	Material
B1	Wall/Plate 3-1/2" x 1-3/4"	3683 lbs	97.7%	49.3%	Spruce-Pine-Fir
B2	Wall/Plate 4-3/8" x 1-3/4"	271 lbs	5.7%	2.9%	Spruce-Pine-Fir

### Notes

Design meets Code minimum (L/240) Total load deflection criteria.  
 Design meets Code minimum (L/360) Live load deflection criteria.  
 Calculations assume member is fully braced.  
 Resistance Factor phi has been applied to all presented results per CSA O86.  
 BC CALC® analysis is based on Canadian Limit States Design, as per NBCC 2015 and CSA O86.  
 Design based on Dry Service Condition.  
 Importance Factor : Normal Part code : Part 9

CONFORMS TO CBC 2012

AMENDED 2020



OWG NO. TAM 9131 -21

STRUCTURAL

COMPONENT ONLY

### Disclosure

Use of the Boise Cascade Software is subject to the terms of the End User License Agreement (EULA). Completeness and accuracy of input must be reviewed and verified by a qualified engineer or other appropriate expert to assure its adequacy, prior to anyone relying on such output as evidence of suitability for a particular application. The output here is based on building code-accepted design properties and analysis methods. Installation of Boise Cascade engineered wood products must be in accordance with current Installation Guide and applicable building codes. To obtain Installation Guide or ask questions, please call (800)232-0788 before installation.

BC CALC®, BC FRAMER®, AJST™, ALLJOIST®, BC RIM BOARD™, BCI®, BOISE GLULAM™, BC FloorValue®, VERSA-LAM®, VERSA-RIM PLUS®,

BC CALC® Member Report

Build 7493

Job name:

File name: UNIT 2009 EL A,B.mmdl

Address:

Description: 1ST FLR FRAMING\Flush Beams\B2(i348)

City, Province, Postal Code:

Specifier:


Customer:

Designer:

Code reports:

CCMC 12472-R

Company:



### Reaction Summary (Down / Uplift) (lbs)

Bearing	Live	Dead	Snow	Wind
B1, 2-3/8"	700 / 0	431 / 0		
B2, 4-3/8"	506 / 0	333 / 0		

### Load Summary

Tag	Description	Load Type	Ref.	Start	End	Loc.	Live 1.00	Dead 0.65	Snow 1.00	Wind 1.15	Tributary
0	Self-Weight	Unf. Lin. (lb/ft)	L	00-00-00	08-03-04	Top		12			00-00-00
1	FC1 Floor Material	Unf. Lin. (lb/ft)	L	00-00-00	08-03-04	Top	27	13			n/a
2	FC1 Floor Material	Unf. Lin. (lb/ft)	L	00-00-00	03-08-10	Top	6	3			n/a
3	STAIR	Unf. Lin. (lb/ft)	L	00-02-06	03-11-03	Top	120	60			n/a
4	FC1 Floor Material	Unf. Lin. (lb/ft)	L	03-08-10	08-03-04	Top	27	13			n/a
5	B4(i304)	Conc. Pt. (lbs)	L	03-10-06	03-10-06	Top	395	258			n/a

### Controls Summary

	Factored Demand	Factored Resistance	Demand/Resistance	Case	Location
Pos. Moment	3583 ft-lbs	35392 ft-lbs	10.1%	1	03-10-06
End Shear	1236 lbs	14464 lbs	8.5%	1	01-02-04
Total Load Deflection	L/999 (0.026")	n/a	n/a	4	03-11-03
Live Load Deflection	L/999 (0.016")	n/a	n/a	5	03-11-03
Max Defl.	0.026"	n/a	n/a	4	03-11-03
Span / Depth	7.9				

### Bearing Supports

	Dim. (LxW)	Demand	Demand/Resistance Support	Demand/Resistance Member	Material
B1	Wall/Plate 2-3/8" x 3-1/2"	1589 lbs	31.1%	15.7%	Spruce-Pine-Fir
B2	Wall/Plate 4-3/8" x 3-1/2"	1176 lbs	12.5%	6.3%	Spruce-Pine-Fir

### Notes

Design meets Code minimum (L/240) Total load deflection criteria.

Design meets Code minimum (L/360) Live load deflection criteria.

Calculations assume member is fully braced.

Resistance Factor phi has been applied to all presented results per CSA O86.


BC CALC® analysis is based on Canadian Limit States Design, as per NBCC 2015 and CSA O86.

Design based on Dry Service Condition.

Importance Factor : Normal Part code : Part 9

CONFORMS TO OBC 2012

AMENDED 2020



SWG NO. TAM 9/32-21  
STRUCTURAL  
COMPONENT ONLY





# Double 1-3/4" x 11-7/8" VERSA-LAM® 2.0 3100 SP

PASSED

## 1ST FLR FRAMING\Flush Beams\B2(i348) (Flush Beam)

Dry | 1 span | No cant.

July 22, 2020 16:20:19

BC CALC® Member Report

Build 7493

Job name:

File name: UNIT 2009 EL A,B.mmdl

Address:

Description: 1ST FLR FRAMING\Flush Beams\B2(i348)

City, Province, Postal Code:

Specifier:

Customer:


Designer:

Code reports:

CCMC 12472-R

Company:

### Connection Diagram: Full Length of Member



a minimum = 2"

c = 7-7/8"

b minimum = 3"

d = 10 6/11"

Calculated Side Load = 457.5 lb/ft

Connectors are: 1 Nails

3 1/2" ARDOX SPIRAL



OWG NO. YAM 2132-28  
STRUCTURAL  
COMPONENT ONLY

### Disclosure

Use of the Boise Cascade Software is subject to the terms of the End User License Agreement (EULA). Completeness and accuracy of input must be reviewed and verified by a qualified engineer or other appropriate expert to assure its adequacy, prior to anyone relying on such output as evidence of suitability for a particular application. The output here is based on building code-accepted design properties and analysis methods. Installation of Boise Cascade engineered wood products must be in accordance with current Installation Guide and applicable building codes. To obtain Installation Guide or ask questions, please call (800)232-0788 before installation.

BC CALC®, BC FRAMER®, AJST™, ALLJOIST®, BC RIM BOARD™, BCI®, BOISE GLULAM™, BC FloorValue®, VERSA-LAM®, VERSA-RIM PLUS®,

BC CALC® Member Report

Build 7493

Job name:

File name: UNIT 2009 EL A,B.mmdl

Address:

Description: 1ST FLR FRAMING\Flush Beams\B3(i332)

City, Province, Postal Code:

Specifier:


Customer:

Designer:

Code reports:

CCMC 12472-R

Company:



Total Horizontal Product Length = 19-04-12

**Reaction Summary (Down / Uplift) (lbs)**

Bearing	Live	Dead	Snow	Wind
B1, 2-3/8"	289 / 0	294 / 0		
B2, 2-3/8"	256 / 0	282 / 0		

**Load Summary**

Tag	Description	Load Type	Ref.	Start	End	Loc.	Live 1.00	Dead 0.65	Snow 1.00	Wind 1.15	Tributary
0	Self-Weight	Unf. Lin. (lb/ft)	L	00-00-00	19-04-12	Top		12			00-00-00
1	FC1 Floor Material	Unf. Lin. (lb/ft)	L	00-00-00	19-04-12	Top	10	5			n/a
2	FC1 Floor Material	Unf. Lin. (lb/ft)	L	00-00-00	10-04-06	Top	15	7			n/a
3	FC1 Floor Material	Unf. Lin. (lb/ft)	L	10-04-06	19-04-12	Top	6	3			n/a
4	B7(i331)	Conc. Pt. (lbs)	L	10-03-08	10-03-08	Top	155	147			n/a

**Controls Summary**

	Factored Demand	Factored Resistance	Demand/ Resistance	Case	Location
Pos. Moment	4616 ft-lbs	35392 ft-lbs	13.0%	1	10-03-08
End Shear	722 lbs	14464 lbs	5.0%	1	01-02-04
Total Load Deflection	L/1102 (0.208")	n/a	21.8%	4	09-08-10
Live Load Deflection	L/999 (0.102")	n/a	n/a	5	09-08-10
Max Defl.	0.208"	n/a	n/a	4	09-08-10
Span / Depth	19.3				

**Bearing Supports**

	Dim. (LxW)	Demand	Demand/ Resistance Support	Demand/ Resistance Member	Material
B1	Wall/Plate 2-3/8" x 3-1/2"	801 lbs	15.7%	7.9%	Spruce-Pine-Fir
B2	Wall/Plate 2-3/8" x 3-1/2"	736 lbs	14.4%	7.3%	Spruce-Pine-Fir

**Notes**

Design meets Code minimum (L/240) Total load deflection criteria.

Design meets Code minimum (L/360) Live load deflection criteria.

Calculations assume member is fully braced.

Resistance Factor phi has been applied to all presented results per CSA O86.


BC CALC® analysis is based on Canadian Limit States Design, as per NBCC 2015 and CSA O86.

Design based on Dry Service Condition.

Importance Factor : Normal Part code : Part 9

CONFORMS TO OBC 2012

AMENDED 2020


 UWG NO. TAM 9133-21  
 STRUCTURAL  
 COMPONENT ONLY



# Double 1-3/4" x 11-7/8" VERSA-LAM® 2.0 3100 SP

PASSED

## 1ST FLR FRAMING\Flush Beams\B3(i332) (Flush Beam)

Dry | 1 span | No cant.

July 22, 2020 16:20:19

BC CALC® Member Report  
Build 7493

Job name:

File name: UNIT 2009 EL A,B.mmdl

Address:

Description: 1ST FLR FRAMING\Flush Beams\B3(i332)

City, Province, Postal Code:

Specifier:

Customer:


Designer:

Code reports:

CCMC 12472-R

Company:

### Connection Diagram: Full Length of Member



a minimum = 2"

c = 7-7/8"

b minimum = 3"

d = 2-1/2"

Calculated Side Load = 208.1 lb/ft

Connectors are: *A* Nails

**3 1/2" ARDOX SPIRAL**



OWB NO. TAM 9133-21  
STRUCTURAL  
COMPONENT ONLY

### Disclosure

Use of the Boise Cascade Software is subject to the terms of the End User License Agreement (EULA). Completeness and accuracy of input must be reviewed and verified by a qualified engineer or other appropriate expert to assure its adequacy, prior to anyone relying on such output as evidence of suitability for a particular application. The output here is based on building code-accepted design properties and analysis methods. Installation of Boise Cascade engineered wood products must be in accordance with current Installation Guide and applicable building codes. To obtain Installation Guide or ask questions, please call (800)232-0788 before installation.

BC CALC®, BC FRAMER®, AJS™, ALLJOIST®, BC RIM BOARD™, BCi®, BOISE GLULAM™, BC FloorValue®, VERSA-LAM®, VERSA-RIM PLUS®

BC CALC® Member Report

Build 7493

Job name:

File name: UNIT 2009 EL A,B.mmdl

Address:

Description: 1ST FLR FRAMING\Flush Beams\B4(i304)

City, Province, Postal Code:

Specifier:


Customer:

Designer:

Code reports:

CCMC 12472-R

Company:



Total Horizontal Product Length = 09-10-06

### Reaction Summary (Down / Uplift) (lbs)

Bearing	Live	Dead	Snow	Wind
B1, 4"	407 / 0	266 / 0		
B2, 1-3/4"	416 / 0	268 / 0		

### Load Summary

Tag	Description	Load Type	Ref.	Start	End	Loc.	Live	Dead	Snow	Wind	Tributary
0	Self-Weight	Unf. Lin. (lb/ft)	L	00-00-00	09-10-06	Top	1.00	0.65	1.00	1.15	00-00-00
1	Smoothed Load	Unf. Lin. (lb/ft)	L	00-06-04	08-06-04	Top	91	46			n/a
2	J4(i314)	Conc. Pt. (lbs)	L	09-02-04	09-02-04	Top	90	45			n/a

### Controls Summary

	Factored Demand	Factored Resistance	Demand/Resistance	Case	Location
Pos. Moment	2374 ft-lbs	35392 ft-lbs	6.7%	1	05-02-04
End Shear	888 lbs	14464 lbs	6.1%	1	01-03-14
Total Load Deflection	L/999 (0.028")	n/a	n/a	4	05-00-04
Live Load Deflection	L/999 (0.017")	n/a	n/a	5	05-00-04
Max Defl.	0.028"	n/a	n/a	4	05-00-04
Span / Depth	9.6				

Bearing Supports	Dim. (LxW)	Demand	Demand/Resistance Support	Demand/Resistance Member	Material
B1 Hanger	4" x 3-1/2"	943 lbs	n/a	5.5%	HGUS410
B2 Column	1-3/4" x 3-1/2"	959 lbs	19.3%	12.8%	Unspecified

### Cautions

Header for the hanger HGUS410 is a Double 1-3/4" x 11-7/8" LVL Beam.

Hanger model HGUS410 and seat length were input by the user. Hanger has not been analyzed for adequate capacity.

### Notes

Design meets Code minimum (L/240) Total load deflection criteria.

Design meets Code minimum (L/360) Live load deflection criteria.

Calculations assume member is fully braced.

Hanger Manufacturer: Unassigned

Resistance Factor phi has been applied to all presented results per CSA O86.

BC CALC® analysis is based on Canadian Limit States Design, as per NBCC 2015 and CSA O86.

Design based on Dry Service Condition.

Importance Factor : Normal Part code : Part 9

CONFORMS TO OBC 2012

AMENDED 2020



OWN NO. TAM 9134 -21  
STRUCTURAL  
COMPONENT ONLY



# Double 1-3/4" x 11-7/8" VERSA-LAM® 2.0 3100 SP

PASSED

## 1ST FLR FRAMING\Flush Beams\B4(i304) (Flush Beam)

Dry | 1 span | No cant.

July 22, 2020 16:20:19

BC CALC® Member Report  
Build 7493

Job name:

File name: UNIT 2009 EL A,B.mmdl

Address:

Description: 1ST FLR FRAMING\Flush Beams\B4(i304)

City, Province, Postal Code:

Specifier:

Customer:


Designer:

Code reports:

CCMC 12472-R

Company:


### Connection Diagram: Full Length of Member



a minimum = 2"      c = 7-7/8" "  
b minimum = 3"      d = 2-1/2" "

Calculated Side Load = 257.8 lb/ft

Connectors are: 3 Nails  
3 1/2" ARDOX SPIRAL



DWG NO. YAM 9134-21  
STRUCTURAL  
COMPONENT ONLY

### Disclosure

Use of the Boise Cascade Software is subject to the terms of the End User License Agreement (EULA). Completeness and accuracy of input must be reviewed and verified by a qualified engineer or other appropriate expert to assure its adequacy, prior to anyone relying on such output as evidence of suitability for a particular application. The output here is based on building code-accepted design properties and analysis methods. Installation of Boise Cascade engineered wood products must be in accordance with current Installation Guide and applicable building codes. To obtain Installation Guide or ask questions, please call (800)232-0788 before installation.

BC CALC®, BC FRAMER®, AJS™, ALLJOIST®, BC RIM BOARD™, BCI®, BOISE GLULAM™, BC FloorValue®, VERSA-LAM®, VERSA-RIM PLUS®,



BC CALC® Member Report  
Build 7493

Job name:

File name: UNIT 2009 EL A,B.mmdl

Address:

Description: 1ST FLR FRAMING\Flush Beams\B5(i315)

City, Province, Postal Code:

Specifier:


Customer:

Designer:

Code reports:

CCMC 12472-R

Company:



Total Horizontal Product Length = 04-06-10

### Reaction Summary (Down / Uplift) (lbs)

Bearing	Live	Dead	Snow	Wind
B1, 3-1/2"	444 / 0	249 / 0		
B2, 4-3/8"	179 / 0	115 / 0		

### Load Summary

Tag	Description	Load Type	Ref.	Start	End	Loc.	Live 1.00	Dead 0.65	Snow 1.00	Wind 1.15	Tributary
0	Self-Weight	Unf. Lin. (lb/ft)	L	00-00-00	04-06-10	Top		6			00-00-00
1	FC1 Floor Material	Unf. Lin. (lb/ft)	L	00-03-08	04-06-10	Top	15	7			n/a
2	FC1 Floor Material	Unf. Lin. (lb/ft)	L	00-03-08	03-11-12	Top	12	6			n/a
3	B9(i317)	Conc. Pt. (lbs)	L	00-04-06	00-04-06	Top	381	203			n/a
4	B8(i165)	Conc. Pt. (lbs)	L	03-10-14	03-10-14	Top	136	80			n/a

### Controls Summary

	Factored Demand	Factored Resistance	Demand/Resistance	Case	Location
Pos. Moment	186 ft-lbs	17696 ft-lbs	1.1%	1	02-07-14
End Shear	142 lbs	7232 lbs	2.0%	1	03-02-06
Total Load Deflection	L/999 (0.001")	n/a	n/a	4	02-04-05
Live Load Deflection	L/999 (0")	n/a	n/a	5	02-04-05
Max Defl.	0.001"	n/a	n/a	4	02-04-05
Span / Depth	4.1				

Bearing Supports	Dim. (LxW)	Demand	Demand/Resistance Support	Demand/Resistance Member	Material
B1 Column	3-1/2" x 1-3/4"	978 lbs	19.7%	13.1%	Unspecified
B2 Wall/Plate	4-3/8" x 1-3/4"	412 lbs	8.8%	4.4%	Spruce-Pine-Fir

### Notes

Design meets Code minimum (L/240) Total load deflection criteria.

Design meets Code minimum (L/360) Live load deflection criteria.

Calculations assume member is fully braced.

Resistance Factor phi has been applied to all presented results per CSA O86.

BC CALC® analysis is based on Canadian Limit States Design, as per NBCC 2015 and CSA O86.

Design based on Dry Service Condition.

Importance Factor : Normal Part code : Part 9

CONFORMS TO OBC 2012

AMENDED 2020



DWG NO. YAW 8135-21

STRUCTURAL

COMPONENT ONLY

### Disclosure

Use of the Boise Cascade Software is subject to the terms of the End User License Agreement (EULA). Completeness and accuracy of input must be reviewed and verified by a qualified engineer or other appropriate expert to assure its adequacy, prior to anyone relying on such output as evidence of suitability for a particular application. The output here is based on building code-accepted design properties and analysis methods. Installation of Boise Cascade engineered wood products must be in accordance with current Installation Guide and applicable building codes. To obtain Installation Guide or ask questions, please call (800)232-0788 before installation.

BC CALC®, BC FRAMER®, AJS™, ALLJOIST®, BC RIM BOARD™, BCI®, BOISE GLULAM™, BC FloorValue®, VERSA-LAM®, VERSA-RIM PLUS®,

BC CALC® Member Report

Build 7493

Job name:

File name: UNIT 2009 EL A,B.mmdl

Address:

Description: 1ST FLR FRAMING\Flush Beams\B6(i340)

City, Province, Postal Code:

Specifier:


Customer:

Designer:

Code reports:

CCMC 12472-R

Company:



B1

10-02-10

B2

Total Horizontal Product Length = 10-02-10

**Reaction Summary (Down / Uplift) (lbs)**

Bearing	Live	Dead	Snow	Wind
B1, 2-3/8"	334 / 0	258 / 0		
B2, 1-3/4"	319 / 0	362 / 0		

**Load Summary**

Tag	Description	Load Type	Ref.	Start	End	Loc.	Live 1.00	Dead 0.65	Snow 1.00	Wind 1.15	Tributary
0	Self-Weight	Unf. Lin. (lb/ft)	L	00-00-00	10-02-10	Top		12			00-00-00
1	FC1 Floor Material	Unf. Lin. (lb/ft)	L	00-00-00	07-08-06	Top	5	3			n/a
2	FC1 Floor Material	Unf. Lin. (lb/ft)	L	00-00-00	04-00-02	Top	6	3			n/a
3	FC1 Floor Material	Unf. Lin. (lb/ft)	L	04-00-02	07-08-06	Top	21	11			n/a
4	WALL	Unf. Lin. (lb/ft)	L	07-07-10	10-00-14	Top		60			n/a
5	FC1 Floor Material	Unf. Lin. (lb/ft)	L	07-08-06	10-02-10	Top	8	4			n/a
6	B9(i317)	Conc. Pt. (lbs)	L	04-01-00	04-01-00	Top	367	196			n/a
7	B8(i165)	Conc. Pt. (lbs)	L	07-07-08	07-07-08	Top	121	73			n/a

**Controls Summary**

	Factored Demand	Factored Resistance	Demand/Resistance	Case	Location
Pos. Moment	2925 ft-lbs	35392 ft-lbs	8.3%	1	04-01-00
End Shear	820 lbs	14464 lbs	5.7%	1	09-01-00
Total Load Deflection	L/999 (0.036")	n/a	n/a	4	05-00-15
Live Load Deflection	L/999 (0.02")	n/a	n/a	5	05-00-15
Max Defl.	0.036"	n/a	n/a	4	05-00-15
Span / Depth	10.1				

**Bearing Supports**

	Dim. (LxW)	Demand	Demand/Resistance Support	Demand/Resistance Member	Material
B1	Wall/Plate 2-3/8" x 3-1/2"	823 lbs	16.1%	8.1%	Spruce-Pine-Fir
B2	Column 1-3/4" x 3-1/2"	931 lbs	18.7%	12.5%	Unspecified

**Notes**

Design meets Code minimum (L/240) Total load deflection criteria.

Design meets Code minimum (L/360) Live load deflection criteria.

Calculations assume unbraced length of Top: 00-00-00, Bottom: 00-00-00.

Resistance Factor phi has been applied to all presented results per CSA O86.

BC CALC® analysis is based on Canadian Limit States Design, as per NBCC 2015 and CSA O86.

Design based on Dry Service Condition.

Importance Factor : Normal Part code : Part 9

CONFORMS TO OBC 2012

AMENDED 2020


 006 NO. TAM 9136 -21  
 STRUCTURAL  
 COMPONENT ONLY



# Double 1-3/4" x 11-7/8" VERSA-LAM® 2.0 3100 SP

PASSED

## 1ST FLR FRAMING\Flush Beams\B6(i340) (Flush Beam)

Dry | 1 span | No cant.

July 22, 2020 16:20:19

BC CALC® Member Report

Build 7493

Job name:

Address:

City, Province, Postal Code:

Customer:

Code reports:

CCMC 12472-R

File name: UNIT 2009 EL A,B.mmdl


Description: 1ST FLR FRAMING\Flush Beams\B6(i340)

Specifier:

Designer:

Company:

### Connection Diagram: Full Length of Member



a minimum = 2"

c = 7-7/8"


b minimum = 3"

d = 2'-3"

Calculated Side Load = 397.8 lb/ft

Connectors are: 16d Nails

**3 1/2" ARDOX SPIRAL**



OWG NO. YAM 9136 -21

**STRUCTURAL  
COMPONENT ONLY**

### Disclosure

Use of the Boise Cascade Software is subject to the terms of the End User License Agreement (EULA). Completeness and accuracy of input must be reviewed and verified by a qualified engineer or other appropriate expert to assure its adequacy, prior to anyone relying on such output as evidence of suitability for a particular application. The output here is based on building code-accepted design properties and analysis methods. Installation of Boise Cascade engineered wood products must be in accordance with current Installation Guide and applicable building codes. To obtain Installation Guide or ask questions, please call (800)232-0788 before installation.

BC CALC®, BC FRAMER®, AJS™, ALLJOIST®, BC RIM BOARD™, BCI®, BOISE GLULAM™, BC FloorValue®, VERSA-LAM®, VERSA-RIM PLUS®,

BC CALC® Member Report  
Build 7493

Dry | 1 span | No cant.

July 22, 2020 16:20:19

Job name:

File name: UNIT 2009 EL A,B.mmdl

Address:

Description: 1ST FLR FRAMING\Flush Beams\B7(i331) (Flush Beam)

City, Province, Postal Code:

Specifier:


Customer:

Designer:

Code reports:

CCMC 12472-R

Company:



B1

Total Horizontal Product Length = 02-04-00

B2

### Reaction Summary (Down / Uplift) (lbs)

Bearing	Live	Dead	Snow	Wind
B1, 3-1/2"	209 / 0	186 / 0		
B2, 2"	179 / 0	162 / 0		

### Load Summary

Tag	Description	Load Type	Ref.	Start	End	Loc.	Live 1.00	Dead 0.65	Snow 1.00	Wind 1.15	Tributary
0	Self-Weight	Unf. Lin. (lb/ft)	L	00-00-00	02-04-00	Top		6			00-00-00
1	WALL	Unf. Lin. (lb/ft)	L	00-00-00	02-04-00	Top		60			n/a
2	J1(i325)	Conc. Pt. (lbs)	L	00-05-00	00-05-00	Top	174	87			n/a
3	J1(i328)	Conc. Pt. (lbs)	L	01-09-00	01-09-00	Top	214	107			n/a

### Controls Summary

	Factored Demand	Factored Resistance	Demand/Resistance	Case	Location
Pos. Moment	212 ft-lbs	17696 ft-lbs	1.2%	1	01-09-00
End Shear	116 lbs	7232 lbs	1.6%	1	01-03-06
Total Load Deflection	L/999 (0")	n/a	n/a	4	01-03-06
Live Load Deflection	L/999 (0")	n/a	n/a	5	01-03-06
Max Defl.	0"	n/a	n/a	4	01-03-06
Span / Depth	2.0				

Bearing Supports	Dim. (LxW)	Demand	Demand/Resistance Support	Demand/Resistance Member	Material
B1 Column	3-1/2" x 1-3/4"	545 lbs	11.0%	7.3%	Unspecified
B2 Hanger	2" x 1-3/4"	472 lbs	n/a	11.0%	HUS1.81/10

### Cautions

Header for the hanger HUS1.81/10 is a Double 1-3/4" x 11-7/8" LVL Beam.  
Hanger model HUS1.81/10 and seat length were input by the user. Hanger has not been analyzed for adequate capacity.

### Notes

Design meets Code minimum (L/240) Total load deflection criteria.  
Design meets Code minimum (L/360) Live load deflection criteria.  
Calculations assume member is fully braced.  
Hanger Manufacturer: Unassigned  
Resistance Factor phi has been applied to all presented results per CSA O86.  
BC CALC® analysis is based on Canadian Limit States Design, as per NBCC 2015 and CSA O86.  
Design based on Dry Service Condition.  
Importance Factor : Normal Part code : Part 9

CONFORMS TO CBC 2012

AMENDED 2020



DWG NO. TAM 9137 -21

STRUCTURAL

COMPONENT ONLY

### Disclosure

Use of the Boise Cascade Software is subject to the terms of the End User License Agreement (EULA). Completeness and accuracy of input must be reviewed and verified by a qualified engineer or other appropriate expert to assure its adequacy, prior to anyone relying on such output as evidence of suitability for a particular application. The output here is based on building code-accepted design properties and analysis methods. Installation of Boise Cascade engineered wood products must be in accordance with current Installation Guide and applicable building codes. To obtain Installation Guide or ask questions, please call (800)232-0788 before installation.

BC CALC®, BC FRAMER®, AJS™, ALLJOIST®, BC RIM BOARD™, BCI®, BOISE GLULAM™, BC FloorValue®, VERSA-LAM®, VERSA-RIM PLUS®,



# Single 1-3/4" x 11-7/8" VERSA-LAM® 2.0 3100 SP

PASSED

## 1ST FLR FRAMING\Flush Beams\B8(i165) (Flush Beam)

BC CALC® Member Report  
Build 7493

Dry | 1 span | No cant.

July 22, 2020 16:20:19

Job name:

File name: UNIT 2009 EL A,B.mmdl

Address:

Description: 1ST FLR FRAMING\Flush Beams\B8(i165)

City, Province, Postal Code:

Specifier:


Customer:

Designer:

Code reports:

CCMC 12472-R

Company:



### Reaction Summary (Down / Uplift) (lbs)

Bearing	Live	Dead	Snow	Wind
B1, 2"	136 / 0	80 / 0		
B2, 2"	121 / 0	73 / 0		

### Load Summary

Tag	Description	Load Type	Ref.	Start	End	Loc.	Live	Dead	Snow	Wind	Tributary
0	Self-Weight	Unf. Lin. (lb/ft)	L	00-00-00	04-01-02	Top	1.00	0.65	1.00	1.15	00-00-00
1	J5(i174)	Conc. Pt. (lbs)	L	00-06-02	00-06-02	Top	71	35			n/a
2	J5(i150)	Conc. Pt. (lbs)	L	01-10-02	01-10-02	Top	98	49			n/a
3	J5(i126)	Conc. Pt. (lbs)	L	03-02-02	03-02-02	Top	88	44			n/a

### Controls Summary

	Factored Demand	Factored Resistance	Demand/Resistance	Case	Location
Pos. Moment	316 ft-lbs	17696 ft-lbs	1.8%	1	01-10-02
End Shear	218 lbs	7232 lbs	3.0%	1	02-11-04
Total Load Deflection	L/999 (0.001")	n/a	n/a	4	02-00-09
Live Load Deflection	L/999 (0.001")	n/a	n/a	5	02-00-09
Max Defl.	0.001"	n/a	n/a	4	02-00-09
Span / Depth	3.9				

### Bearing Supports

	Dim. (LxW)	Demand	Demand/Resistance Support	Demand/Resistance Member	Material
B1	Hanger 2" x 1-3/4"	304 lbs	n/a	7.1%	HUS1.81/10
B2	Hanger 2" x 1-3/4"	272 lbs	n/a	6.4%	HUS1.81/10

### Cautions

Header for the hanger HUS1.81/10 is a Single 1-3/4" x 11-7/8" LVL Beam.

Hanger model HUS1.81/10 and seat length were input by the user. Hanger has not been analyzed for adequate capacity.

Header for the hanger HUS1.81/10 is a Double 1-3/4" x 11-7/8" LVL Beam.

### Notes

Design meets Code minimum (L/240) Total load deflection criteria.

Design meets Code minimum (L/360) Live load deflection criteria.

Calculations assume member is fully braced.

Hanger Manufacturer: Unassigned

Resistance Factor phi has been applied to all presented results per CSA O86.


BC CALC® analysis is based on Canadian Limit States Design, as per NBCC 2015 and CSA O86.

Design based on Dry Service Condition.

Importance Factor : Normal Part code : Part 9

CONFORMS TO CBC 2012

AMENDED 2020



UWG NO. TAM 9138 -21

STRUCTURAL

COMPONENT ONLY

### Disclosure

Use of the Boise Cascade Software is subject to the terms of the End User License Agreement (EULA). Completeness and accuracy of input must be reviewed and verified by a qualified engineer or other appropriate expert to assure its adequacy, prior to anyone relying on such output as evidence of suitability for a particular application. The output here is based on building code-accepted design properties and analysis methods. Installation of Boise Cascade engineered wood products must be in accordance with current Installation Guide and applicable building codes. To obtain Installation Guide or ask questions, please call (800)232-0788 before installation.

BC CALC®, BC FRAMER®, AJS™, ALLJOIST®, BC RIM BOARD™, BCI®, BOISE GLULAM™, BC FloorValue®, VERSA-LAM®, VERSA-RIM PLUS®,



BC CALC® Member Report

Build 7493

Job name:

File name: UNIT 2009 EL A,B.mmdl

Address:

Description: 1ST FLR FRAMING\Flush Beams\B9(i317)

City, Province, Postal Code:

Specifier:


Customer:

Designer:

Code reports:

CCMC 12472-R

Company:



B1

Total Horizontal Product Length = 04-01-02

B2

### Reaction Summary (Down / Uplift) (lbs)

Bearing	Live	Dead	Snow	Wind
B1, 2"	382 / 0	203 / 0		
B2, 2"	367 / 0	196 / 0		

### Load Summary

Tag	Description	Load Type	Ref.	Start	End	Loc.	Live	Dead	Snow	Wind	Tributary
0	Self-Weight	Unf. Lin. (lb/ft)	L	00-00-00	04-01-02	Top	1.00	0.65	1.00	1.15	00-00-00
1	STAIR	Unf. Lin. (lb/ft)	L	00-00-00	04-01-02	Top	120	60			n/a
2	J5(i174)	Conc. Pt. (lbs)	L	00-06-02	00-06-02	Top	71	35			n/a
3	J5(i150)	Conc. Pt. (lbs)	L	01-10-02	01-10-02	Top	98	49			n/a
4	J5(i126)	Conc. Pt. (lbs)	L	03-02-02	03-02-02	Top	88	44			n/a

### Controls Summary

	Factored Demand	Factored Resistance	Demand/Resistance	Case	Location
Pos. Moment	792 ft-lbs	17696 ft-lbs	4.5%	1	01-10-02
End Shear	445 lbs	7232 lbs	6.2%	1	02-11-04
Total Load Deflection	L/999 (0.003")	n/a	n/a	4	02-00-09
Live Load Deflection	L/999 (0.002")	n/a	n/a	5	02-00-09
Max Defl.	0.003"	n/a	n/a	4	02-00-09
Span / Depth	3.9				

Bearing Supports	Dim. (LxW)	Demand	Demand/Resistance Support	Demand/Resistance Member	Material
B1 Hanger	2" x 1-3/4"	826 lbs	n/a	19.3%	HUS1.81/10
B2 Hanger	2" x 1-3/4"	794 lbs	n/a	18.6%	HUS1.81/10

### Cautions

Header for the hanger HUS1.81/10 is a Single 1-3/4" x 11-7/8" LVL Beam.  
Hanger model HUS1.81/10 and seat length were input by the user. Hanger has not been analyzed for adequate capacity.  
Header for the hanger HUS1.81/10 is a Double 1-3/4" x 11-7/8" LVL Beam.

### Notes

Design meets Code minimum (L/240) Total load deflection criteria.  
Design meets Code minimum (L/360) Live load deflection criteria.  
Calculations assume unbraced length of Top: 00-00-00, Bottom: 00-00-00. **CONFORMS TO OBC 2012**  
Hanger Manufacturer: Unassigned **AMENDED 2020**  
Resistance Factor phi has been applied to all presented results per CSA O86.  
BC CALC® analysis is based on Canadian Limit States Design, as per NBCC 2015 and CSA O86.  
Design based on Dry Service Condition.  
Importance Factor : Normal Part code : Part 9



OWG NO. TAM 2139 -21  
**STRUCTURAL COMPONENT ONLY**

### Disclosure

Use of the Boise Cascade Software is subject to the terms of the End User License Agreement (EULA). Completeness and accuracy of input must be reviewed and verified by a qualified engineer or other appropriate expert to assure its adequacy, prior to anyone relying on such output as evidence of suitability for a particular application. The output here is based on building code-accepted design properties and analysis methods. Installation of Boise Cascade engineered wood products must be in accordance with current Installation Guide and applicable building codes. To obtain Installation Guide or ask questions, please call (800)232-0788 before installation.

BC CALC®, BC FRAMER®, AJST™, ALLJOIST®, BC RIM BOARD™, BCI®, BOISE GLULAM™, BC FloorValue®, VERSA-LAM®, VERSA-RIM PLUS®



Boise Cascade

**Double 1-3/4" x 11-7/8" VERSA-LAM® 2.0 3100 SP****2ND FLR FRAMING\Flush Beams\B10(i326) (Flush Beam)****PASSED**BC CALC® Member Report  
Build 7493

Dry | 2 spans | No cant.

July 22, 2020 16:20:19

Job name:

File name: UNIT 2009 EL A,B.mmdl

Address:

Description: 2ND FLR FRAMING\Flush Beams\B10(i326)

City, Province, Postal Code:

Specifier:


Customer:

Designer:

Code reports:

CCMC 12472-R

Company:

**Reaction Summary (Down / Uplift) (lbs)**

Bearing	Live	Dead	Snow	Wind
B1, 3-1/2"	0 / 6	25 / 0	0 / 4	
B2, 5-1/2"	216 / 0	333 / 0	191 / 0	
B3, 5-1/2"	186 / 0	229 / 0	188 / 0	

**Load Summary**

Tag	Description	Load Type	Ref.	Start	End	Loc.	Live 1.00	Dead 0.65	Snow 1.00	Wind 1.15	Tributary
0	Self-Weight	Unf. Lin. (lb/ft)	L	00-00-00	08-09-00	Top		12			00-00-00
1	E10(i260)	Unf. Lin. (lb/ft)	L	05-10-08	08-03-08	Top	55	131	130		n/a
2	FC2 Floor Material	Unf. Lin. (lb/ft)	L	07-02-08	08-06-08	Top	6				n/a
3	J4(i344)	Conc. Pt. (lbs)	L	07-02-08	07-02-08	Top	229	115			n/a
4	E9(i258)	Conc. Pt. (lbs)	L	08-06-04	08-06-04	Top	25	47	60		n/a

**Controls Summary**

	Factored Demand	Factored Resistance	Demand/ Resistance	Case	Location
Pos. Moment	434 ft-lbs	29611 ft-lbs	1.5%	18	07-02-08
Neg. Moment	-180 ft-lbs	-29611 ft-lbs	0.6%	1	06-01-04
End Shear	187 lbs	14464 lbs	1.3%	43	07-03-10
Cont. Shear	239 lbs	14464 lbs	1.7%	43	07-03-14
Total Load Deflection	L/999 (0")	n/a	n/a	126	07-03-01
Live Load Deflection	L/999 (-0")	n/a	n/a	178	03-07-12
Total Neg. Defl.	L/999 (-0")	n/a	n/a	126	04-03-03
Max Defl.	0"	n/a	n/a	126	07-03-01
Span / Depth	5.9				

Bearing Supports	Dim. (LxW)	Demand	Demand/ Resistance Support	Demand/ Resistance Member	Material
B1 Column	3-1/2" x 3-1/2"	35 lbs	0.5%	0.4%	Unspecified
B2 Wall/Plate	5-1/2" x 3-1/2"	931 lbs	7.9%	4.0%	Spruce-Pine-Fir
B3 Wall/Plate	5-1/2" x 3-1/2"	754 lbs	6.4%	3.2%	Spruce-Pine-Fir

**Notes**

Design meets Code minimum (L/240) Total load deflection criteria.

Design meets Code minimum (L/360) Live load deflection criteria.

Calculations assume unbraced length of Top: 05-10-08, Bottom: 05-10-08.

Resistance Factor phi has been applied to all presented results per CSA O86.

BC CALC® analysis is based on Canadian Limit States Design, as per NBCC 2015 and CSA O86.

Unbalanced snow loads determined from building geometry were used in selected product's verification.

Design based on Dry Service Condition.

Importance Factor : Normal Part code : Part 9

CONFORMS TO OBC 2012

AMENDED 2020



OWR NO. TAM 9140 -21  
STRUCTURAL  
COMPONENT ONLY



# Double 1-3/4" x 11-7/8" VERSA-LAM® 2.0 3100 SP

PASSED

## 2ND FLR FRAMING\Flush Beams\B10(i326) (Flush Beam)

Dry | 2 spans | No cant.

July 22, 2020 16:20:19

BC CALC® Member Report

Build 7493

Job name:

Address:

City, Province, Postal Code:

Customer:

Code reports: CCMC 12472-R

File name: UNIT 2009 EL A,B.mmdl


Description: 2ND FLR FRAMING\Flush Beams\B10(i326)

Specifier:

Designer:

Company:

### Connection Diagram: Full Length of Member




a minimum = 2"      c = 7-7/8"  
b minimum = 3"      d = 2-1/2"

Calculated Side Load = 243.6 lb/ft

Connectors are: 3/4" ARDOX SPIRAL Nails

3/4" ARDOX SPIRAL



ENG NO. YAM 9140 -21  
STRUCTURAL  
COMPONENT ONLY

### Disclosure

Use of the Boise Cascade Software is subject to the terms of the End User License Agreement (EULA). Completeness and accuracy of input must be reviewed and verified by a qualified engineer or other appropriate expert to assure its adequacy, prior to anyone relying on such output as evidence of suitability for a particular application. The output here is based on building code-accepted design properties and analysis methods. Installation of Boise Cascade engineered wood products must be in accordance with current Installation Guide and applicable building codes. To obtain Installation Guide or ask questions, please call (800)232-0788 before installation.

BC CALC®, BC FRAMER®, AJS™, ALLJOIST®, BC RIM BOARD™, BCI®, BOISE GLULAM™, BC FloorValue®, VERSA-LAM®, VERSA-RIM PLUS®,

Build 7493

Job name:

File name: UNIT 2009 EL A,B.mmdl

Address:

Description: 2ND FLR FRAMING\Flush Beams\B14(i289)

City, Province, Postal Code:

Specifier:


Customer:

Designer:

Code reports:

CCMC 12472-R

Company:



Total Horizontal Product Length = 08-10-14

### Reaction Summary (Down / Uplift) (lbs)

Bearing	Live	Dead	Snow	Wind
B1, 5-1/2"	1281 / 0	1546 / 0	2814 / 0	
B2, 4-3/8"	1249 / 0	1509 / 0	2743 / 0	

### Load Summary

Tag	Description	Load Type	Ref.	Start	End	Loc.	Live 1.00	Dead 0.65	Snow 1.00	Wind 1.15	Tributary
0	Self-Weight	Unf. Lin. (lb/ft)	L	00-00-00	08-10-14	Top		12			00-00-00
1	FC2 Floor Material	Unf. Lin. (lb/ft)	L	00-00-00	08-10-14	Top	20	10			n/a
2	E12(i261)	Unf. Lin. (lb/ft)	L	00-00-00	03-10-00	Top		81			n/a
3	E12(i261)	Unf. Lin. (lb/ft)	L	00-00-00	03-06-00	Top	264	240	624		n/a
4	E13(i262)	Unf. Lin. (lb/ft)	L	03-10-00	05-10-00	Top		61			n/a
5	E14(i263)	Unf. Lin. (lb/ft)	L	05-10-00	08-10-14	Top		81			n/a
6	E14(i263)	Unf. Lin. (lb/ft)	L	06-02-00	08-10-14	Top	264	240	624		n/a
7	E12(i261)	Conc. Pt. (lbs)	L	03-09-00	03-09-00	Top	362	349	856		n/a
8	E14(i263)	Conc. Pt. (lbs)	L	05-11-00	05-11-00	Top	342	331	808		n/a

### Controls Summary

	Factored Demand	Factored Resistance	Demand/Resistance	Case	Location
Pos. Moment	13516 ft-lbs	35392 ft-lbs	38.2%	13	03-09-00
End Shear	5047 lbs	14464 lbs	34.9%	13	01-05-06
Total Load Deflection	L/769 (0.128")	n/a	31.2%	35	04-05-08
Live Load Deflection	L/999 (0.093")	n/a	n/a	51	04-05-08
Max Defl.	0.128"	n/a	n/a	35	04-05-08
Span / Depth	8.3				

### Bearing Supports

	Dim. (LxW)	Demand	Demand/Resistance Support	Demand/Resistance Member	Material
B1	Wall/Plate 5-1/2" x 3-1/2"	7434 lbs	62.8%	31.7%	Spruce-Pine-Fir
B2	Wall/Plate 4-3/8" x 3-1/2"	7249 lbs	77.0%	38.8%	Spruce-Pine-Fir

### Notes

Design meets Code minimum (L/240) Total load deflection criteria.

Design meets Code minimum (L/360) Live load deflection criteria.

Calculations assume member is fully braced.

Resistance Factor phi has been applied to all presented results per CSA O86.

BC CALC® analysis is based on Canadian Limit States Design, as per NBCC 2015 and CSA O86.

Unbalanced snow loads determined from building geometry were used in selected product's verification.

Design based on Dry Service Condition.


Importance Factor : Normal Part code : Part 9

CONFORMS TO OBC 2012

AMENDED 2020



ENG NO. TAM 9141-21  
STRUCTURAL  
COMPONENT ONLY



# Double 1-3/4" x 11-7/8" VERSA-LAM® 2.0 3100 SP

PASSED

## 2ND FLR FRAMING\Flush Beams\B14(i289) (Flush Beam)

Dry | 1 span | No cant.

July 22, 2020 16:20:19

BC CALC® Member Report  
Build 7493

Job name:

File name: UNIT 2009 EL A,B.mmdl

Address:

Description: 2ND FLR FRAMING\Flush Beams\B14(i289)

City, Province, Postal Code:

Specifier:

Customer:


Designer:

Code reports:

CCMC 12472-R

Company:

### Connection Diagram: Full Length of Member



a minimum = 2"

c = 7-7/8"

b minimum = 3"

d = 24 6"

Connectors are:

3 1/2" ARDOX SPIRAL Nails



SWG NO. TAM 9141 -20  
STRUCTURAL  
COMPONENT ONLY

### Disclosure

Use of the Boise Cascade Software is subject to the terms of the End User License Agreement (EULA). Completeness and accuracy of input must be reviewed and verified by a qualified engineer or other appropriate expert to assure its adequacy, prior to anyone relying on such output as evidence of suitability for a particular application. The output here is based on building code-accepted design properties and analysis methods. Installation of Boise Cascade engineered wood products must be in accordance with current Installation Guide and applicable building codes. To obtain Installation Guide or ask questions, please call (800)232-0788 before installation.

BC CALC®, BC FRAMER®, AJS™, ALLJOIST®, BC RIM BOARD™, BCI®, BOISE GLULAM™, BC FloorValue®, VERSA-LAM®, VERSA-RIM PLUS®,



BC CALC® Member Report

Dry | 1 span | No cant.

July 22, 2020 16:20:19

Build 0

Job name:

File name: UNIT 2009 EL A,B.mmdl

Address:

Description: 2ND FLR FRAMING\Flush Beams\B15(i313)

City, Province, Postal Code:

Specifier:


Customer:

Designer:

Code reports:

CCMC 12472-R

Company:



### Load Summary

Tag	Description	Load Type	Ref.	Start	End	Loc.	Live 1.00	Dead 0.65	Snow 1.00	Wind 1.15	Tributary
0	Self-Weight	Unf. Lin. (lb/ft)	L	00-00-00	16-02-12	Top					00-00-00
1	J1(i227)	Conc. Pt. (lbs)	L	00-09-00	00-09-00	Top	183	62			n/a
2	J1(i227)	Conc. Pt. (lbs)	L	00-09-00	00-09-00	Top	-60				n/a
3	B12(i306)	Conc. Pt. (lbs)	L	01-09-12	01-09-12	Top	354	238			n/a
4	B12(i306)	Conc. Pt. (lbs)	L	01-09-12	01-09-12	Top	-429				n/a
5	B11(i310)	Conc. Pt. (lbs)	L	15-01-04	15-01-04	Top	1240	820			n/a
6	B11(i310)	Conc. Pt. (lbs)	L	15-01-04	15-01-04	Top	-436				n/a
7	J5(i211)	Conc. Pt. (lbs)	L	15-08-00	15-08-00	Top	309	155			n/a


### Controls Summary

	Factored Demand	Factored Resistance	Demand/ Resistance	Case	Location
Dist. Load	13.28 lb/ft	57645.00 lb/ft	n/a		
Conc. Load	2885 lbs	16813 lbs	17.2%		

### Cautions

Concentrated side load(s) 7 are closer than 18" from end of member. Please consult a technical representative or Professional of Record.


### Connection Diagram: Full Length of Member



a minimum = 2"      c = 7-7/8"  
b minimum = 3"      d = 12"

Calculated Side Load = 328.6 lb/ft  
Connectors are: 16d, 1 Nails

3 1/2" ARDOX SPIRAL



CONFORMS TO OBC 2012  
AMENDED 2020  
STRUCTURAL  
COMPONENT ONLY

### Disclosure

Use of the Boise Cascade Software is subject to the terms of the End User License Agreement (EULA). Completeness and accuracy of input must be reviewed and verified by a qualified engineer or other appropriate expert to assure its adequacy, prior to anyone relying on such output as evidence of suitability for a particular application. The output here is based on building code-accepted design properties and analysis methods. Installation of Boise Cascade engineered wood products must be in accordance with current Installation Guide and applicable building codes. To obtain Installation Guide or ask questions, please call (800)232-0788 before installation.

BC CALC®, BC FRAMER®, AJS™, ALLJOIST®, BC RIM BOARD™, BCI®, BOISE GLULAM™, BC FloorValue®, VERSA-LAM®, VERSA-RIM PLUS®,



Boise Cascade

**Double 1-3/4" x 11-7/8" VERSA-LAM® 2.0 3100 SP****2ND FLR FRAMING\Flush Beams\B10(i599) (Flush Beam)****PASSED**

BC CALC® Member Report

Dry | 1 span | No cant.

July 27, 2020 08:46:28

Build 7493

Job name:

File name: UNIT 2009 EL A,B.mmdl

Address:

Description: 2ND FLR FRAMING\Flush Beams\B10(i599)

City, Province, Postal Code: RICHMOND HILL


Specifier:

Customer:

Designer: AJ

Code reports: CCMC 12472-R

Company:



B1

Total Horizontal Product Length = 02-10-08

B2

**Reaction Summary (Down / Uplift) (lbs)**

Bearing	Live	Dead	Snow	Wind
B1, 5-1/2"	100 / 181	125 / 0	187 / 0	
B2, 5-1/2"	101 / 148	129 / 0	187 / 0	

**Load Summary**

Tag	Description	Load Type	Ref.	Start	End	Loc.	Live 1.00	Dead 0.65	Snow 1.00	Wind 1.15	Tributary
0	Self-Weight	Unf. Lin. (lb/ft)	L	00-00-00	02-10-08	Top		12			00-00-00
1	E10(i260)	Unf. Lin. (lb/ft)	L	00-00-00	02-05-00	Top	55	131	130		n/a
2	FC2 Floor Material	Unf. Lin. (lb/ft)	L	01-04-00	02-08-00	Top	6	3			n/a
3	J4(i344)	Conc. Pt. (lbs)	L	01-04-00	01-04-00	Top	35	-147			n/a
4	J4(i344)	Conc. Pt. (lbs)	L	01-04-00	01-04-00	Top	-329				n/a
5	E9(i258)	Conc. Pt. (lbs)	L	02-07-12	02-07-12	Top	25	47	60		n/a

**Controls Summary**


	Factored Demand	Factored Resistance	Demand/ Resistance	Case	Location
Pos. Moment	171 ft-lbs	35392 ft-lbs	0.5%	25	01-07-03
Neg. Moment	-253 ft-lbs	-35392 ft-lbs	0.7%	24	01-04-00
End Shear	309 lbs	14464 lbs	2.1%	2	01-05-02
Total Load Deflection	L/999 (0")	n/a	n/a	58	01-05-06
Live Load Deflection	L/999 (-0")	n/a	n/a	84	01-04-13
Total Neg. Defl.	L/999 (-0")	n/a	n/a	57	01-04-09
Max Defl.	0"	n/a	n/a	58	01-05-06
Span / Depth	2.1				

**Bearing Supports**

	Dim. (LxW)	Demand	Demand/ Resistance Support	Demand/ Resistance Member	Material
B1	Wall/Plate 5-1/2" x 3-1/2"	537 lbs	4.5%	2.3%	Spruce-Pine-Fir
B1	Uplift	158 lbs			
B2	Wall/Plate 5-1/2" x 3-1/2"	543 lbs	4.6%	2.3%	Spruce-Pine-Fir
B2	Uplift	106 lbs			

**Cautions**

Uplift of 158 lbs found at bearing B1. (SIMPSON 2-H2-5A @ B1).



OWG NO. YAM 9143 -21  
STRUCTURAL  
COMPONENT ONLY



**Double 1-3/4" x 11-7/8" VERSA-LAM® 2.0 3100 SP**  
**2ND FLR FRAMING\Flush Beams\B10(i599) (Flush Beam)**

**PASSED**

BC CALC® Member Report

Dry | 1 span | No cant.

July 27, 2020 08:46:28

Build 7493

Job name:

File name: UNIT 2009 EL A,B.mmdl

Address:

Description: 2ND FLR FRAMING\Flush Beams\B10(i599)

City, Province, Postal Code: RICHMOND HILL

Specifier:

Customer:

Designer: AJ

Code reports:

CCMC 12472-R

Company:

**Notes**

Design meets Code minimum (L/240) Total load deflection criteria.

Design meets Code minimum (L/360) Live load deflection criteria.

Calculations assume member is fully braced.

Resistance Factor phi has been applied to all presented results per CSA O86.

BC CALC® analysis is based on Canadian Limit States Design, as per NBCC 2015 and CSA O86.

Unbalanced snow loads determined from building geometry were used in selected product's verification.


Design based on Dry Service Condition.

Importance Factor : Normal Part code : Part 9

CONFORMS TO OBC 2012

AMENDED 2020

**Connection Diagram: Full Length of Member**




a minimum = 2"  
b minimum = 3"

c = 7-7/8"  
d = 6"

Calculated Side Load = 338.6 lb/ft

Connectors are: 16d Nails

**3 1/2" ARDOX SPIRAL**



ENG NO. TAM 9143 -21  
**STRUCTURAL  
COMPONENT ONLY**

**Disclosure**

Use of the Boise Cascade Software is subject to the terms of the End User License Agreement (EULA). Completeness and accuracy of input must be reviewed and verified by a qualified engineer or other appropriate expert to assure its adequacy, prior to anyone relying on such output as evidence of suitability for a particular application. The output here is based on building code-accepted design properties and analysis methods. Installation of Boise Cascade engineered wood products must be in accordance with current Installation Guide and applicable building codes. To obtain Installation Guide or ask questions, please call (800)232-0788 before installation.

BC CALC®, BC FRAMER®, AJST™, ALLJOIST®, BC RIM BOARD™, BCI®, BOISE GLULAM™, BC FloorValue®, VERSA-LAM®, VERSA-RIM PLUS®,



# Double 1-3/4" x 11-7/8" VERSA-LAM® 2.0 3100 SP

## 2ND FLR FRAMING\Flush Beams\B11(i597) (Flush Beam)

**PASSED**


BC CALC® Member Report  
Build 7493

Dry | 1 span | No cant.

July 27, 2020 08:46:28

Job name:  
Address:  
City, Province, Postal Code: RICHMOND HILL  
Customer:  
Code reports: CCMC 12472-R

File name: UNIT 2009 EL A,B.mmdl  
Description: 2ND FLR FRAMING\Flush Beams\B11(i597)  
Specifier:  
Designer: AJ  
Company:



B1 19-00-06 B2  
Total Horizontal Product Length = 19-00-06

### Reaction Summary (Down / Uplift) (lbs)

Bearing	Live	Dead	Snow	Wind
B1, 4"	1254 / 0	1020 / 0		
B2, 2-3/8"	631 / 0	469 / 0		

### Load Summary

Tag	Description	Load Type	Ref.	Start	End	Loc.	Live 1.00	Dead 0.65	Snow 1.00	Wind 1.15	Tributary
0	Self-Weight	Unf. Lin. (lb/ft)	L	00-00-00	19-00-06	Top		12			00-00-00
1	WALL	Unf. Lin. (lb/ft)	L	00-00-00	04-07-04	Top		60			n/a
2	FC2 Floor Material	Unf. Lin. (lb/ft)	L	00-00-00	04-04-00	Top	14	7			n/a
3	FC2 Floor Material	Unf. Lin. (lb/ft)	L	04-04-00	19-00-06	Top	38	19			n/a
4	B13(i590)	Conc. Pt. (lbs)	L	04-04-14	04-04-14	Top	1261	671			n/a

### Controls Summary

	Factored Demand	Factored Resistance	Demand/ Resistance	Case	Location
Pos. Moment	11889 ft-lbs	35392 ft-lbs	33.6%	1	04-04-14
End Shear	2998 lbs	14464 lbs	20.7%	1	01-03-14
Total Load Deflection	L/454 (0.492")	n/a	52.8%	4	08-11-06
Live Load Deflection	L/777 (0.288")	n/a	46.3%	5	08-11-06
Max Defl.	0.492"	n/a	n/a	4	08-11-06
Span / Depth	18.8				

Bearing Supports	Dim. (LxW)	Demand	Demand/ Resistance Support	Demand/ Resistance Member	Material
B1 Hanger	4" x 3-1/2"	3157 lbs	n/a	18.5%	HGUS410
B2 Wall/Plate	2-3/8" x 3-1/2"	1533 lbs	30.0%	15.1%	Spruce-Pine-Fir

### Cautions

Header for the hanger HGUS410 is a Double 1-3/4" x 11-7/8" LVL Beam.  
Hanger model HGUS410 and seat length were input by the user. Hanger has not been analyzed for adequate capacity.

### Notes

Design meets Code minimum (L/240) Total load deflection criteria.  
Design meets Code minimum (L/360) Live load deflection criteria.  
Calculations assume member is fully braced.  
Hanger Manufacturer: Unassigned  
Resistance Factor phi has been applied to all presented results per CSA O86.  
BC CALC® analysis is based on Canadian Limit States Design, as per NBCC 2015 and CSA O86.  
Design based on Dry Service Condition.  
Importance Factor : Normal Part code : Part 9

CONFORMS TO OBC 2012

AMENDED 2020



946 NO. TAM 9/144-21  
STRUCTURAL  
COMPONENT ONLY



# Double 1-3/4" x 11-7/8" VERSA-LAM® 2.0 3100 SP

## 2ND FLR FRAMING\Flush Beams\B11(i597) (Flush Beam)

**PASSED**

BC CALC® Member Report  
Build 7493


Dry | 1 span | No cant.

July 27, 2020 08:46:28

Job name:  
Address:  
City, Province, Postal Code: RICHMOND HILL  
Customer:  
Code reports: CCMC 12472-R

File name: UNIT 2009 EL A,B.mmdl  
Description: 2ND FLR FRAMING\Flush Beams\B11(i597)  
Specifier:  
Designer: AJ  
Company:

### Connection Diagram: Full Length of Member




a minimum = 2"  
b minimum = 3"  
c = 7-7/8"  
d = 24"

Connectors are: 1 Nails

**3 1/2" ARDOX SPIRAL**


### Connection Diagrams: Concentrated Side Loads

Connection Tag: A Applies to load tag(s): 4



a minimum = 2"  
b minimum = 4"  
c minimum = 4"  
d maximum = 12"  
e minimum = 4"  
Connectors are: 16d Nails

**3 1/2" ARDOX SPIRAL**



### Disclosure

Use of the Boise Cascade Software is subject to the terms of the End User License Agreement (EULA). Completeness and accuracy of input must be reviewed and verified by a qualified engineer or other appropriate expert to assure its adequacy, prior to anyone relying on such output as evidence of suitability for a particular application. The output here is based on building code-accepted design properties and analysis methods. Installation of Boise Cascade engineered wood products must be in accordance with current Installation Guide and applicable building codes. To obtain Installation Guide or ask questions, please call (800)232-0788 before installation.

BC CALC®, BC FRAMER®, AJS™, ALLJOIST®, BC RIM BOARD™, BCI®, BOISE GLULAM™, BC FloorValue®, VERSA-LAM®, VERSA-RIM PLUS®,



# Single 1-3/4" x 11-7/8" VERSA-LAM® 2.0 3100 SP 2ND FLR FRAMING\Flush Beams\B12(i595) (Flush Beam)

**PASSED**


BC CALC® Member Report  
Build 7493

Dry | 1 span | No cant.

July 27, 2020 08:46:28

Job name:  
Address:  
City, Province, Postal Code: RICHMOND HILL  
Customer:  
Code reports: CCMC 12472-R

File name: UNIT 2009 EL A,B.mmdl  
Description: 2ND FLR FRAMING\Flush Beams\B12(i595)  
Specifier:  
Designer: AJ  
Company:



B1  
Total Horizontal Product Length = 08-00-00  
B2

## Reaction Summary (Down / Uplift) (lbs)

Bearing	Live	Dead	Snow	Wind
B1, 2"	342 / 0	409 / 0		
B2, 5-1/2"	469 / 0	367 / 0		

## Load Summary

Tag	Description	Load Type	Ref.	Start	End	Loc.	Live 1.00	Dead 0.65	Snow 1.00	Wind 1.15	Tributary
0	Self-Weight	Unf. Lin. (lb/ft)	L	00-00-00	08-00-00	Top		6			00-00-00
1	WALL	Unf. Lin. (lb/ft)	L	00-00-00	04-08-09	Top		60			n/a
2	FC2 Floor Material	Unf. Lin. (lb/ft)	L	00-00-00	04-04-00	Top	24	12			n/a
3	FC2 Floor Material	Unf. Lin. (lb/ft)	L	04-04-00	07-09-04	Top	47	23			n/a
4	B13(i590)	Conc. Pt. (lbs)	L	04-04-14	04-04-14	Top	545	313			n/a

## Controls Summary

	Factored Demand	Factored Resistance	Demand/ Resistance	Case	Location
Pos. Moment	3105 ft-lbs	17696 ft-lbs	17.5%	1	04-04-14
End Shear	1030 lbs	7232 lbs	14.2%	1	06-06-10
Total Load Deflection	L/999 (0.04")	n/a	n/a	4	03-11-04
Live Load Deflection	L/999 (0.021")	n/a	n/a	5	04-00-07
Max Defl.	0.04"	n/a	n/a	4	03-11-04
Span / Depth	7.6				

## Bearing Supports

	Dim. (LxW)	Demand	Demand/ Resistance Support	Demand/ Resistance Member	Material
B1	Hanger 2" x 1-3/4"	1024 lbs	n/a	24.0%	HUS1.81/10
B2	Wall/Plate 5-1/2" x 1-3/4"	1162 lbs	19.6%	9.9%	Spruce-Pine-Fir


## Cautions

Header for the hanger HUS1.81/10 is a Double 1-3/4" x 11-7/8" LVL Beam.  
Hanger model HUS1.81/10 and seat length were input by the user. Hanger has not been analyzed for adequate capacity.

## Notes

Design meets Code minimum (L/240) Total load deflection criteria.  
Design meets Code minimum (L/360) Live load deflection criteria.  
Calculations assume member is fully braced.  
Hanger Manufacturer: Unassigned  
Resistance Factor phi has been applied to all presented results per CSA O86.  
BC CALC® analysis is based on Canadian Limit States Design, as per NBCC 2015 and CSA O86.  
Design based on Dry Service Condition.  
Importance Factor : Normal Part code : Part 9

CONFORMS TO OBC 2012  
AMENDED 2020



## Disclosure

Use of the Boise Cascade Software is subject to the terms of the End User License Agreement (EULA).  
Completeness and accuracy of input must be reviewed and verified by a qualified engineer or other appropriate expert to assure its adequacy, prior to anyone relying on such output as evidence of suitability for a particular application. The output here is based on building code-accepted design properties and analysis methods.  
Installation of Boise Cascade engineered wood products must be in accordance with current Installation Guide and applicable building codes. To obtain Installation Guide or ask questions, please call (800)232-0788 before installation.

BC CALC®, BC FRAMER®, AJS™, ALLJOIST®, BC RIM BOARD™, BCi®, BOISE GLULAM™, BC FloorValue®, VERSA-LAM®, VERSA-RIM PLUS®,



**Single 1-3/4" x 11-7/8" VERSA-LAM® 2.0 3100 SP**  
**2ND FLR FRAMING\Flush Beams\B13(i590) (Flush Beam)**

**PASSED**

BC CALC® Member Report

Dry | 1 span | No cant.

July 27, 2020 08:46:28

Build 7493

Job name:

File name: UNIT 2009 EL A,B.mmdl

Address:

Description: 2ND FLR FRAMING\Flush Beams\B13(i590)

City, Province, Postal Code: RICHMOND HILL


Specifier:

Customer:

Designer: AJ

Code reports: CCMC 12472-R

Company:



**Reaction Summary (Down / Uplift) (lbs)**

Bearing	Live	Dead	Snow	Wind
B1, 2"	539 / 0	310 / 0		
B2, 2"	1267 / 0	674 / 0		

**Load Summary**

Tag	Description	Load Type	Ref.	Start	End	Loc.	Live 1.00	Dead 0.65	Snow 1.00	Wind 1.15	Tributary
0	Self-Weight	Unf. Lin. (lb/ft)	L	00-00-00	13-00-00	Top		6			00-00-00
1	Smoothed Load	Unf. Lin. (lb/ft)	L	01-09-08	09-09-08	Top	68	34			n/a
2	STAIR	Unf. Lin. (lb/ft)	L	09-06-11	13-00-00	Top	120	60			n/a
3	J5(i523)	Conc. Pt. (lbs)	L	01-01-08	01-01-08	Top	87	43			n/a
4	J2(i465)	Conc. Pt. (lbs)	L	10-05-08	10-05-08	Top	364	182			n/a
5	J2(i404)	Conc. Pt. (lbs)	L	11-09-08	11-09-08	Top	396	198			n/a

**Controls Summary**

	Factored Demand	Factored Resistance	Demand/ Resistance	Case	Location
Pos. Moment	5152 ft-lbs	17696 ft-lbs	29.1%	1	07-09-08
End Shear	2440 lbs	7232 lbs	33.7%	1	11-10-02
Total Load Deflection	L/693 (0.222")	n/a	34.7%	4	06-09-08
Live Load Deflection	L/1077 (0.143")	n/a	33.4%	5	06-09-08
Max Defl.	0.222"	n/a	n/a	4	06-09-08
Span / Depth	12.9				

**Bearing Supports**


	Dim. (LxW)	Demand	Demand/ Resistance Support	Demand/ Resistance Member	Material
B1 Hanger	2" x 1-3/4"	1196 lbs	n/a	28.0%	HUS1.81/10
B2 Hanger	2" x 1-3/4"	2743 lbs	n/a	64.2%	HUS1.81/10

**Cautions**

Header for the hanger HUS1.81/10 is a Single 1-3/4" x 11-7/8" LVL Beam.

Hanger model HUS1.81/10 and seat length were input by the user. Hanger has not been analyzed for adequate capacity. *OK*

Header for the hanger HUS1.81/10 is a Double 1-3/4" x 11-7/8" LVL Beam.



OWN NO. TAM 9146 -21  
**STRUCTURAL  
 COMPONENT ONLY**



Boise Cascade

**Single 1-3/4" x 11-7/8" VERSA-LAM® 2.0 3100 SP****2ND FLR FRAMING\Flush Beams\B13(i590) (Flush Beam)****PASSED**

BC CALC® Member Report

Dry | 1 span | No cant.

July 27, 2020 08:46:28

Build 7493

Job name:

File name: UNIT 2009 EL A,B.mmdl

Address:

Description: 2ND FLR FRAMING\Flush Beams\B13(i590)

City, Province, Postal Code: RICHMOND HILL

Specifier:

Customer:

Designer: AJ

Code reports: CCMC 12472-R

Company:

**Notes**

Design meets Code minimum (L/240) Total load deflection criteria.

Design meets Code minimum (L/360) Live load deflection criteria.

Calculations assume member is fully braced.

Hanger Manufacturer: Unassigned

Resistance Factor phi has been applied to all presented results per CSA O86.

BC CALC® analysis is based on Canadian Limit States Design, as per NBCC 2015 and CSA O86.

Design based on Dry Service Condition.

Importance Factor : Normal Part code : Part 9

CONFORMS TO OBC 2012

AMENDED 2020





OWN NO. TAM 9/46 -21  
**STRUCTURAL  
 COMPONENT ONLY**

**Disclosure**

Use of the Boise Cascade Software is subject to the terms of the End User License Agreement (EULA). Completeness and accuracy of input must be reviewed and verified by a qualified engineer or other appropriate expert to assure its adequacy, prior to anyone relying on such output as evidence of suitability for a particular application. The output here is based on building code-accepted design properties and analysis methods. Installation of Boise Cascade engineered wood products must be in accordance with current Installation Guide and applicable building codes. To obtain Installation Guide or ask questions, please call (800)232-0788 before installation.

BC CALC®, BC FRAMER®, AJS™, ALLJOIST®, BC RIM BOARD™, BCI®, BOISE GLULAM™, BC FloorValue®, VERSA-LAM®, VERSA-RIM PLUS®







## Maximum Floor Spans

Live Load = 40 psf, Dead Load = 15 psf  
Simple Spans, L/480 Deflection Limit  
5/8" OSB G&N Sheathing

Depth	Series	Bare				1/2" Gypsum Ceiling			
		On Centre Spacing				On Centre Spacing			
		12"	16"	19.2"	24"	12"	16"	19.2"	24"
9-1/2"	NI-20	15'-1"	14'-2"	13'-9"	N/A	15'-7"	14'-8"	14'-2"	N/A
	NI-40x	16'-1"	15'-2"	14'-8"	N/A	16'-7"	15'-7"	15'-1"	N/A
	NI-60	16'-3"	15'-4"	14'-10"	N/A	16'-8"	15'-9"	15'-3"	N/A
	NI-70	17'-1"	16'-1"	15'-6"	N/A	17'-5"	16'-5"	15'-10"	N/A
	NI-80	17'-3"	16'-3"	15'-8"	N/A	17'-8"	16'-7"	16'-0"	N/A
11-7/8"	NI-20	16'-11"	16'-0"	15'-5"	N/A	17'-6"	16'-6"	16'-0"	N/A
	NI-40x	18'-1"	17'-0"	16'-5"	N/A	18'-9"	17'-6"	16'-11"	N/A
	NI-60	18'-4"	17'-3"	16'-7"	N/A	19'-0"	17'-8"	17'-1"	N/A
	NI-70	19'-6"	18'-0"	17'-4"	N/A	20'-1"	18'-7"	17'-9"	N/A
	NI-80	19'-9"	18'-3"	17'-6"	N/A	20'-4"	18'-10"	17'-11"	N/A
	NI-90x	20'-4"	18'-9"	17'-11"	N/A	20'-10"	19'-3"	18'-5"	N/A
14"	NI-40x	20'-1"	18'-7"	17'-10"	N/A	20'-10"	19'-4"	18'-6"	N/A
	NI-60	20'-5"	18'-11"	18'-1"	N/A	21'-2"	19'-7"	18'-9"	N/A
	NI-70	21'-7"	20'-0"	19'-1"	N/A	22'-3"	20'-7"	19'-8"	N/A
	NI-80	21'-11"	20'-3"	19'-4"	N/A	22'-7"	20'-11"	20'-0"	N/A
	NI-90x	22'-7"	20'-11"	19'-11"	N/A	23'-3"	21'-6"	20'-6"	N/A
16"	NI-60	22'-3"	20'-8"	19'-9"	N/A	23'-1"	21'-5"	20'-6"	N/A
	NI-70	23'-6"	21'-9"	20'-9"	N/A	24'-3"	22'-5"	21'-5"	N/A
	NI-80	23'-11"	22'-1"	21'-1"	N/A	24'-8"	22'-10"	21'-9"	N/A
	NI-90x	24'-8"	22'-9"	21'-9"	N/A	25'-4"	23'-5"	22'-4"	N/A

Depth	Series	Mid-Span Blocking				Mid-Span Blocking and 1/2" Gypsum Ceiling			
		On Centre Spacing				On Centre Spacing			
		12"	16"	19.2"	24"	12"	16"	19.2"	24"
9-1/2"	NI-20	16'-8"	15'-3"	14'-5"	N/A	16'-8"	15'-3"	14'-5"	N/A
	NI-40x	17'-11"	16'-11"	16'-1"	N/A	18'-5"	17'-1"	16'-1"	N/A
	NI-60	18'-2"	17'-1"	16'-4"	N/A	18'-7"	17'-4"	16'-4"	N/A
	NI-70	19'-2"	17'-10"	17'-2"	N/A	19'-7"	18'-3"	17'-7"	N/A
	NI-80	19'-5"	18'-0"	17'-4"	N/A	19'-10"	18'-5"	17'-8"	N/A
11-7/8"	NI-20	19'-6"	18'-1"	17'-3"	N/A	19'-11"	18'-3"	17'-3"	N/A
	NI-40x	21'-0"	19'-6"	18'-8"	N/A	21'-7"	20'-2"	19'-2"	N/A
	NI-60	21'-4"	19'-9"	18'-11"	N/A	21'-11"	20'-4"	19'-6"	N/A
	NI-70	22'-6"	20'-10"	19'-11"	N/A	23'-0"	21'-5"	20'-5"	N/A
	NI-80	22'-9"	21'-1"	20'-1"	N/A	23'-3"	21'-7"	20'-8"	N/A
	NI-90x	23'-4"	21'-8"	20'-8"	N/A	23'-10"	22'-2"	21'-2"	N/A
14"	NI-40x	23'-7"	21'-11"	20'-11"	N/A	24'-3"	22'-7"	21'-7"	N/A
	NI-60	24'-0"	22'-3"	21'-3"	N/A	24'-8"	22'-11"	21'-11"	N/A
	NI-70	25'-3"	23'-4"	22'-3"	N/A	25'-10"	24'-0"	22'-11"	N/A
	NI-80	25'-7"	23'-8"	22'-7"	N/A	26'-2"	24'-4"	23'-2"	N/A
	NI-90x	26'-4"	24'-4"	23'-3"	N/A	26'-10"	24'-11"	23'-9"	N/A
16"	NI-60	26'-5"	24'-6"	23'-4"	N/A	27'-2"	25'-3"	24'-2"	N/A
	NI-70	27'-9"	25'-8"	24'-6"	N/A	28'-5"	26'-5"	25'-2"	N/A
	NI-80	28'-2"	26'-1"	24'-10"	N/A	28'-10"	26'-9"	25'-6"	N/A
	NI-90x	29'-0"	26'-10"	25'-7"	N/A	29'-7"	27'-5"	26'-2"	N/A

- Maximum clear span applicable to simple-span residential floor construction with a design live load of 40 psf and dead load of 15 psf. The ultimate limit states are based on the factored loads of 1.50L + 1.25D. The serviceability limit states include the consideration for floor vibration, a live load deflection limit of L/480 and a total load deflection limit of L/240.
- Spans are based on a composite floor with glued-nailed oriented strand board (OSB) sheathing with a minimum thickness of 5/8 inch for a joist spacing of 19.2 inches or less. The composite floor may include 1/2 inch gypsum ceiling and/or one row of blocking at mid-span with strapping. Strapping shall be minimum 1x4 inch strap applied to underside of joists at blocking line or 1/2 inch gypsum ceiling attached to joists.
- Minimum bearing length shall be 1-3/4 inches for the end bearings.
- Bearing stiffeners are not required when I-joists are used with the spans and spacings given in this table, except as required for hangers.
- This span chart is based on uniform loads. For applications with other than uniformly distributed loads, an engineering analysis may be required based on the use of the design properties. Tables are based on Limit States Design per CSA O86-09, NBC 2010, and OBC 2012.
- Joists shall be laterally supported at supports and continuously along the compression edge. Refer to technical documentation for installation guidelines and construction details. Nordic I-joists are listed in CCMC evaluation report 13032-R and APA Product Report PR-L274C.



## Maximum Floor Spans

Live Load = 40 psf, Dead Load = 15 psf  
Simple Spans, L/480 Deflection Limit  
3/4" OSB G&N Sheathing



Depth	Series	Bare				1/2" Gypsum Ceiling			
		On Centre Spacing				On Centre Spacing			
		12"	16"	19.2"	24"	12"	16"	19.2"	24"
9-1/2"	NI-20	15'-10"	15'-0"	14'-5"	13'-5"	16'-4"	15'-5"	14'-6"	13'-5"
	NI-40x	17'-0"	16'-0"	15'-5"	14'-9"	17'-5"	16'-5"	15'-10"	15'-2"
	NI-60	17'-2"	16'-2"	15'-7"	14'-11"	17'-6"	16'-7"	15'-11"	15'-3"
	NI-70	18'-0"	16'-11"	16'-3"	15'-7"	18'-5"	17'-3"	16'-7"	15'-11"
	NI-80	18'-3"	17'-1"	16'-5"	15'-9"	18'-8"	17'-5"	16'-9"	16'-1"
11-7/8"	NI-20	17'-10"	16'-10"	16'-2"	15'-6"	18'-6"	17'-4"	16'-9"	16'-1"
	NI-40x	19'-4"	17'-11"	17'-3"	16'-6"	19'-11"	18'-6"	17'-9"	17'-0"
	NI-60	19'-7"	18'-2"	17'-5"	16'-9"	20'-2"	18'-9"	17'-11"	17'-2"
	NI-70	20'-9"	19'-2"	18'-3"	17'-5"	21'-4"	19'-9"	18'-10"	17'-10"
	NI-80	21'-1"	19'-5"	18'-6"	17'-7"	21'-7"	20'-0"	19'-0"	18'-0"
14"	NI-90x	21'-8"	20'-0"	19'-1"	18'-0"	22'-2"	20'-6"	19'-6"	18'-6"
	NI-40x	21'-5"	19'-10"	18'-11"	17'-11"	22'-1"	20'-6"	19'-7"	18'-7"
	NI-60	21'-10"	20'-2"	19'-3"	18'-2"	22'-5"	20'-10"	19'-11"	18'-10"
	NI-70	23'-0"	21'-3"	20'-3"	19'-2"	23'-8"	21'-11"	20'-10"	19'-9"
	NI-80	23'-5"	21'-7"	20'-7"	19'-5"	24'-0"	22'-3"	21'-2"	20'-0"
16"	NI-90x	24'-1"	22'-3"	21'-2"	20'-0"	24'-8"	22'-10"	21'-9"	20'-7"
	NI-60	23'-9"	22'-0"	20'-11"	19'-10"	24'-6"	22'-9"	21'-8"	20'-6"
	NI-70	25'-1"	23'-2"	22'-0"	20'-10"	25'-9"	23'-10"	22'-9"	21'-6"
	NI-80	25'-6"	23'-6"	22'-4"	21'-2"	26'-1"	24'-2"	23'-1"	21'-10"
	NI-90x	26'-4"	24'-3"	23'-1"	21'-10"	26'-11"	24'-11"	23'-8"	22'-5"

Depth	Series	Mid-Span Blocking				Mid-Span Blocking and 1/2" Gypsum Ceiling			
		On Centre Spacing				On Centre Spacing			
		12"	16"	19.2"	24"	12"	16"	19.2"	24"
9-1/2"	NI-20	16'-10"	15'-5"	14'-6"	13'-5"	16'-10"	15'-5"	14'-6"	13'-5"
	NI-40x	18'-8"	17'-2"	16'-3"	15'-2"	18'-10"	17'-2"	16'-3"	15'-2"
	NI-60	18'-11"	17'-6"	16'-6"	15'-5"	19'-2"	17'-6"	16'-6"	15'-5"
	NI-70	20'-0"	18'-7"	17'-9"	16'-7"	20'-5"	18'-11"	17'-10"	16'-7"
	NI-80	20'-3"	18'-10"	17'-11"	16'-10"	20'-8"	19'-3"	18'-2"	16'-10"
11-7/8"	NI-20	20'-1"	18'-5"	17'-5"	16'-2"	20'-1"	18'-5"	17'-5"	16'-2"
	NI-40x	21'-10"	20'-4"	19'-4"	17'-8"	22'-5"	20'-6"	19'-4"	17'-8"
	NI-60	22'-1"	20'-7"	19'-7"	18'-4"	22'-8"	20'-10"	19'-8"	18'-4"
	NI-70	23'-4"	21'-8"	20'-8"	19'-7"	23'-10"	22'-3"	21'-2"	19'-9"
	NI-80	23'-7"	21'-11"	20'-11"	19'-9"	24'-1"	22'-6"	21'-5"	20'-0"
14"	NI-90x	24'-3"	22'-6"	21'-6"	20'-4"	24'-8"	23'-0"	22'-0"	20'-9"
	NI-40x	24'-5"	22'-9"	21'-8"	19'-5"	25'-1"	23'-2"	21'-9"	19'-5"
	NI-60	24'-10"	23'-1"	22'-0"	20'-10"	25'-6"	23'-8"	22'-4"	20'-10"
	NI-70	26'-1"	24'-3"	23'-2"	21'-10"	26'-8"	24'-11"	23'-9"	22'-4"
	NI-80	26'-6"	24'-7"	23'-5"	22'-2"	27'-1"	25'-3"	24'-1"	22'-9"
16"	NI-90x	27'-3"	25'-4"	24'-1"	22'-9"	27'-9"	25'-11"	24'-8"	23'-4"
	NI-60	27'-3"	25'-5"	24'-2"	22'-10"	28'-0"	26'-2"	24'-9"	23'-1"
	NI-70	28'-8"	26'-8"	25'-4"	23'-11"	29'-3"	27'-4"	26'-1"	24'-8"
	NI-80	29'-1"	27'-0"	25'-9"	24'-4"	29'-8"	27'-9"	26'-5"	25'-0"
	NI-90x	29'-11"	27'-10"	26'-6"	25'-0"	30'-6"	28'-5"	27'-2"	25'-8"

- Maximum clear span applicable to simple-span residential floor construction with a design live load of 40 psf and dead load of 15 psf. The ultimate limit states are based on the factored loads of 1.50L + 1.25D. The serviceability limit states include the consideration for floor vibration, a live load deflection limit of L/480 and a total load deflection limit of L/240.
- Spans are based on a composite floor with glued-nailed oriented strand board (OSB) sheathing with a minimum thickness of 3/4 inch for a joist spacing of 24 inches or less. The composite floor may include 1/2 inch gypsum ceiling and/or one row of blocking at mid-span with strapping. Strapping shall be minimum 1x4 inch strap applied to underside of joists at blocking line or 1/2 inch gypsum ceiling attached to joists.
- Minimum bearing length shall be 1-3/4 inches for the end bearings.
- Bearing stiffeners are not required when I-joists are used with the spans and spacings given in this table, except as required for hangers.
- This span chart is based on uniform loads. For applications with other than uniformly distributed loads, an engineering analysis may be required based on the use of the design properties. Tables are based on Limit States Design per CSA O86-09, NBC 2010, and OBC 2012.
- Joists shall be laterally supported at supports and continuously along the compression edge. Refer to technical documentation for installation guidelines and construction details. Nordic I-joists are listed in CCMC evaluation report 13032-R and APA Product Report PR-L274C.

## Maximum Floor Spans



Live Load = 40 psf, Dead Load = 30 psf  
Simple Spans, L/480 Deflection Limit  
5/8" OSB G&N Sheathing



Depth	Series	Bare				1/2" Gypsum Ceiling			
		On Centre Spacing				On Centre Spacing			
		12"	16"	19.2"	24"	12"	16"	19.2"	24"
9-1/2"	NI-20	15'-1"	14'-1"	13'-3"	N/A	15'-7"	14'-1"	13'-3"	N/A
	NI-40x	16'-1"	15'-2"	14'-8"	N/A	16'-7"	15'-7"	15'-1"	N/A
	NI-60	16'-3"	15'-4"	14'-10"	N/A	16'-8"	15'-9"	15'-3"	N/A
	NI-70	17'-1"	16'-1"	15'-6"	N/A	17'-5"	16'-5"	15'-10"	N/A
	NI-80	17'-3"	16'-3"	15'-8"	N/A	17'-8"	16'-7"	16'-0"	N/A
11-7/8"	NI-20	16'-11"	16'-0"	15'-5"	N/A	17'-6"	16'-6"	16'-0"	N/A
	NI-40x	18'-1"	17'-0"	16'-5"	N/A	18'-9"	17'-6"	16'-11"	N/A
	NI-60	18'-4"	17'-3"	16'-7"	N/A	19'-0"	17'-8"	17'-1"	N/A
	NI-70	19'-6"	18'-0"	17'-4"	N/A	20'-1"	18'-7"	17'-9"	N/A
	NI-80	19'-9"	18'-3"	17'-6"	N/A	20'-4"	18'-10"	17'-11"	N/A
14"	NI-90x	20'-4"	18'-9"	17'-11"	N/A	20'-10"	19'-3"	18'-5"	N/A
	NI-40x	20'-1"	18'-7"	17'-10"	N/A	20'-10"	19'-4"	18'-6"	N/A
	NI-60	20'-5"	18'-11"	18'-1"	N/A	21'-2"	19'-7"	18'-9"	N/A
	NI-70	21'-7"	20'-0"	19'-1"	N/A	22'-3"	20'-7"	19'-8"	N/A
	NI-80	21'-11"	20'-3"	19'-4"	N/A	22'-7"	20'-11"	20'-0"	N/A
16"	NI-90x	22'-7"	20'-11"	19'-11"	N/A	23'-3"	21'-6"	20'-6"	N/A
	NI-60	22'-3"	20'-8"	19'-9"	N/A	23'-1"	21'-5"	20'-6"	N/A
	NI-70	23'-6"	21'-9"	20'-9"	N/A	24'-3"	22'-5"	21'-5"	N/A
	NI-80	23'-11"	21'-1"	21'-1"	N/A	24'-8"	22'-10"	21'-9"	N/A
	NI-90x	24'-8"	22'-9"	21'-9"	N/A	25'-4"	23'-5"	22'-4"	N/A

Depth	Series	Mid-Span Blocking				Mid-Span Blocking and 1/2" Gypsum Ceiling			
		On Centre Spacing				On Centre Spacing			
		12"	16"	19.2"	24"	12"	16"	19.2"	24"
9-1/2"	NI-20	15'-7"	14'-1"	13'-3"	N/A	15'-7"	14'-1"	13'-3"	N/A
	NI-40x	17'-9"	16'-1"	15'-1"	N/A	17'-9"	16'-1"	15'-1"	N/A
	NI-60	18'-1"	16'-4"	15'-4"	N/A	18'-1"	16'-4"	15'-4"	N/A
	NI-70	19'-2"	17'-10"	16'-9"	N/A	19'-7"	17'-10"	16'-9"	N/A
	NI-80	19'-5"	18'-0"	17'-1"	N/A	19'-10"	18'-3"	17'-1"	N/A
11-7/8"	NI-20	18'-9"	17'-0"	16'-0"	N/A	18'-9"	17'-0"	16'-0"	N/A
	NI-40x	21'-0"	19'-3"	17'-9"	N/A	21'-3"	19'-3"	17'-9"	N/A
	NI-60	21'-4"	19'-8"	18'-5"	N/A	21'-8"	19'-8"	18'-5"	N/A
	NI-70	22'-6"	20'-10"	19'-11"	N/A	23'-0"	21'-4"	20'-0"	N/A
	NI-80	22'-9"	21'-1"	20'-1"	N/A	23'-3"	21'-7"	20'-5"	N/A
14"	NI-90x	23'-4"	21'-8"	20'-8"	N/A	23'-10"	22'-2"	21'-2"	N/A
	NI-40x	23'-7"	21'-5"	19'-6"	N/A	24'-1"	21'-5"	19'-6"	N/A
	NI-60	24'-0"	22'-3"	21'-0"	N/A	24'-8"	22'-5"	21'-0"	N/A
	NI-70	25'-3"	23'-4"	22'-3"	N/A	25'-10"	24'-0"	22'-9"	N/A
	NI-80	25'-7"	23'-8"	22'-7"	N/A	26'-2"	24'-4"	23'-2"	N/A
16"	NI-90x	26'-4"	24'-4"	23'-3"	N/A	26'-10"	24'-11"	23'-9"	N/A
	NI-60	26'-5"	24'-6"	23'-4"	N/A	27'-2"	24'-10"	23'-4"	N/A
	NI-70	27'-9"	25'-8"	24'-6"	N/A	28'-5"	26'-5"	25'-2"	N/A
	NI-80	28'-2"	26'-1"	24'-10"	N/A	28'-10"	26'-9"	25'-6"	N/A
	NI-90x	29'-0"	26'-10"	25'-7"	N/A	29'-7"	27'-5"	26'-2"	N/A

- Maximum clear span applicable to simple-span residential floor construction with a design live load of 40 psf and dead load of 30 psf. The ultimate limit states are based on the factored loads of 1.50L + 1.25D. The serviceability limit states include the consideration for floor vibration, a live load deflection limit of L/480 and a total load deflection limit of L/240.
- Spans are based on a composite floor with glued-nailed oriented strand board (OSB) sheathing with a minimum thickness of 5/8 inch for a joist spacing of 19.2 inches or less. The composite floor may include 1/2 inch gypsum ceiling and/or one row of blocking at mid-span with strapping. Strapping shall be minimum 1x4 inch strap applied to underside of joists at blocking line or 1/2 inch gypsum ceiling attached to joists.
- Minimum bearing length shall be 1-3/4 inches for the end bearings.
- Bearing stiffeners are not required when I-joists are used with the spans and spacings given in this table, except as required for hangers.
- This span chart is based on uniform loads. For applications with other than uniformly distributed loads, an engineering analysis may be required based on the use of the design properties. Tables are based on Limit States Design per CSA O86-09, NBC 2010, and OBC 2012.
- Joists shall be laterally supported at supports and continuously along the compression edge. Refer to technical documentation for installation guidelines and construction details. Nordic I-joists are listed in CCMC evaluation report 13032-R and APA Product Report PR-L274C.



## Maximum Floor Spans

Live Load = 40 psf, Dead Load = 30 psf  
Simple Spans, L/480 Deflection Limit  
3/4" OSB G&N Sheathing

Depth	Series	Bare				1/2" Gypsum Ceiling			
		On Centre Spacing				On Centre Spacing			
		12"	16"	19.2"	24"	12"	16"	19.2"	24"
9-1/2"	NI-20	15'-7"	14'-2"	13'-4"	12'-4"	15'-7"	14'-2"	13'-4"	12'-4"
	NI-40x	17'-0"	16'-0"	15'-1"	13'-11"	17'-5"	16'-1"	15'-1"	13'-11"
	NI-60	17'-2"	16'-2"	15'-5"	14'-3"	17'-6"	16'-5"	15'-5"	14'-3"
	NI-70	18'-0"	16'-11"	16'-3"	15'-6"	18'-5"	17'-3"	16'-7"	15'-6"
	NI-80	18'-3"	17'-1"	16'-5"	15'-9"	18'-8"	17'-5"	16'-9"	15'-10"
11-7/8"	NI-20	17'-10"	16'-10"	16'-0"	14'-10"	18'-6"	17'-1"	16'-0"	14'-10"
	NI-40x	19'-4"	17'-11"	17'-3"	15'-10"	19'-11"	18'-6"	17'-9"	15'-10"
	NI-60	19'-7"	18'-2"	17'-5"	16'-9"	20'-2"	18'-9"	17'-11"	17'-1"
	NI-70	20'-9"	19'-2"	18'-3"	17'-5"	21'-4"	19'-9"	18'-10"	17'-10"
	NI-80	21'-1"	19'-5"	18'-6"	17'-7"	21'-7"	20'-0"	19'-0"	18'-0"
	NI-90x	21'-8"	20'-0"	19'-1"	18'-0"	22'-2"	20'-6"	19'-6"	18'-6"
14"	NI-40x	21'-5"	19'-10"	18'-11"	17'-5"	22'-1"	20'-6"	19'-6"	17'-5"
	NI-60	21'-10"	20'-2"	19'-3"	18'-2"	22'-5"	20'-10"	19'-11"	18'-10"
	NI-70	23'-0"	21'-3"	20'-3"	19'-2"	23'-8"	21'-11"	20'-10"	19'-9"
	NI-80	23'-5"	21'-7"	20'-7"	19'-5"	24'-0"	22'-3"	21'-2"	20'-0"
	NI-90x	24'-1"	22'-3"	21'-2"	20'-0"	24'-8"	22'-10"	21'-9"	20'-7"
16"	NI-60	23'-9"	22'-0"	20'-11"	19'-10"	24'-6"	22'-9"	21'-8"	20'-6"
	NI-70	25'-1"	23'-2"	22'-0"	20'-10"	25'-9"	23'-10"	22'-9"	21'-6"
	NI-80	25'-6"	23'-6"	22'-4"	21'-2"	26'-1"	24'-2"	23'-1"	21'-10"
	NI-90x	26'-4"	24'-3"	23'-1"	21'-10"	26'-11"	24'-11"	23'-8"	22'-5"

Depth	Series	Mid-Span Blocking				Mid-Span Blocking and 1/2" Gypsum Ceiling			
		On Centre Spacing				On Centre Spacing			
		12"	16"	19.2"	24"	12"	16"	19.2"	24"
9-1/2"	NI-20	15'-7"	14'-2"	13'-4"	12'-4"	15'-7"	14'-2"	13'-4"	12'-4"
	NI-40x	17'-9"	16'-1"	15'-1"	13'-11"	17'-9"	16'-1"	15'-1"	13'-11"
	NI-60	18'-1"	16'-5"	15'-5"	14'-3"	18'-1"	16'-5"	15'-5"	14'-3"
	NI-70	19'-10"	17'-11"	16'-9"	15'-6"	19'-10"	17'-11"	16'-9"	15'-6"
	NI-80	20'-2"	18'-3"	17'-1"	15'-10"	20'-2"	18'-3"	17'-1"	15'-10"
11-7/8"	NI-20	18'-10"	17'-1"	16'-0"	14'-10"	18'-10"	17'-1"	16'-0"	14'-10"
	NI-40x	21'-3"	19'-3"	17'-9"	15'-10"	21'-3"	19'-3"	17'-9"	15'-10"
	NI-60	21'-9"	19'-8"	18'-5"	17'-1"	21'-9"	19'-8"	18'-5"	17'-1"
	NI-70	23'-4"	21'-5"	20'-1"	18'-6"	23'-8"	21'-5"	20'-1"	18'-6"
	NI-80	23'-7"	21'-10"	20'-5"	18'-11"	24'-1"	21'-10"	20'-5"	18'-11"
	NI-90x	24'-3"	22'-6"	21'-3"	19'-7"	24'-8"	22'-7"	21'-3"	19'-7"
14"	NI-40x	24'-2"	21'-5"	19'-6"	17'-5"	24'-2"	21'-5"	19'-6"	17'-5"
	NI-60	24'-9"	22'-5"	21'-0"	19'-6"	24'-9"	22'-5"	21'-0"	19'-6"
	NI-70	26'-1"	24'-3"	22'-9"	21'-0"	26'-8"	24'-3"	22'-9"	21'-0"
	NI-80	26'-6"	24'-7"	23'-3"	21'-6"	27'-1"	24'-10"	23'-3"	21'-6"
	NI-90x	27'-3"	25'-4"	24'-1"	22'-4"	27'-9"	25'-10"	24'-3"	22'-4"
16"	NI-60	27'-3"	24'-11"	23'-5"	21'-7"	27'-6"	24'-11"	23'-5"	21'-7"
	NI-70	28'-8"	26'-8"	25'-3"	23'-4"	29'-3"	26'-11"	25'-3"	23'-4"
	NI-80	29'-1"	27'-0"	25'-9"	23'-10"	29'-8"	27'-6"	25'-10"	23'-10"
	NI-90x	29'-11"	27'-10"	26'-6"	24'-10"	30'-6"	28'-5"	26'-11"	24'-10"

1. Maximum clear span applicable to simple-span residential floor construction with a design live load of 40 psf and dead load of 30 psf. The ultimate limit states are based on the factored loads of 1.50L + 1.25D. The serviceability limit states include the consideration for floor vibration, a live load deflection limit of L/480 and a total load deflection limit of L/240.

2. Spans are based on a composite floor with glued-nailed oriented strand board (OSB) sheathing with a minimum thickness of 3/4 inch for a joist spacing of 24 inches or less. The composite floor may include 1/2 inch gypsum ceiling and/or one row of blocking at mid-span with strapping. Strapping shall be minimum 1x4 inch strap applied to underside of joists at blocking line or 1/2 inch gypsum ceiling attached to joists.

3. Minimum bearing length shall be 1-3/4 inches for the end bearings.

4. Bearing stiffeners are not required when I-joists are used with the spans and spacings given in this table, except as required for hangers.

5. This span chart is based on uniform loads. For applications with other than uniformly distributed loads, an engineering analysis may be required based on the use of the design properties. Tables are based on Limit States Design per CSA O86-09, NBC 2010, and OBC 2012.


6. Joists shall be laterally supported at supports and continuously along the compression edge. Refer to technical documentation for installation guidelines and construction details. Nordic I-joists are listed in CCMC evaluation report 13032-R and APA Product Report PR-L274C.

## Allowance for Piping (Installation Notes)


The floor layouts have usually not been checked for heating and/or plumbing interference. On-site adjustment of joists of up to 3 inches is permitted to avoid interferences. When moving a joist, the subfloor thickness shall be checked with code requirements when the joist spacing exceeds 19.2 inches. Except for cutting to length, I-joist flanges should never be cut, drilled, or notched.

Installation of Nordic I-joists shall be as per *Nordic Joist Installation Guide for Residential Floors*. Refer to Tables 1 and 2 for maximum web hole and duct chase openings, respectively. These tables are based on the I-joists being used at their maximum spans. The minimum distance given may be reduced for shorter spans; contact your distributor for additional information.

The detail below shows the 3-inch allowance for piping. Every third joist may be shifted up to 3 inches to avoid heating/plumbing interference. For other applications, please contact your distributor.



Revised April 12, 2012



#### Notes:

1. Blocking required at bearing for lateral support, not shown for clarity.
2. The maximum dimensions for a notch on the side of the top flange are 4-inch width by 1/2-inch depth for flange width of 2-1/2 inches, and 4-inch width by 1-inch depth for flange width of 3-1/2 inches.
3. This detail applies to simple-span joists and multiple-span joists where the notch is located at the end half-span.
4. For other applications, contact Nordic Structures.

This document supersedes all previous versions. If the document has been in effect for more than one year, consult [nordic.ca](http://nordic.ca) or contact Nordic Structures.

All nails shown in the details are assumed to be common nails unless otherwise noted. Nails shall have a diameter not less than 0.128 inch for 2-1/2-inch nails, or 0.144 inch for 3-inch nails. Individual components not shown to scale for clarity.

<b>NORDIC</b> <b>STRUCTURES</b>	T 514-871-8526 1 866 817-3418 <a href="http://nordic.ca">nordic.ca</a>	TITLE Notch in I-joist for Heat Register	DOCUMENT -
	CATEGORY I-joist - Typical Floor Framing and Construction Details	DATE 2018-04-10	NUMBER 1w-1