


Products				
PlotID	Length	Product	Plies	Net Qty
J1	20-00-00	11 7/8" NI-40x	2	2
J2	10-00-00	11 7/8" NI-40x	1	7
J3	6-00-00	11 7/8" NI-40x	1	10
J4	2-00-00	11 7/8" NI-40x	1	4
J5	20-00-00	11 7/8" NI-80	1	19
B1	20-00-00	1-3/4" x 11-7/8" VERSA-LAM® 2.0 3100 SP	2	2
B3	10-00-00	1-3/4" x 11-7/8" VERSA-LAM® 2.0 3100 SP	1	1
B4	10-00-00	1-3/4" x 11-7/8" VERSA-LAM® 2.0 3100 SP	1	1
B5	10-00-00	1-3/4" x 11-7/8" VERSA-LAM® 2.0 3100 SP	1	1
B2	6-00-00	1-3/4" x 11-7/8" VERSA-LAM® 2.0 3100 SP	1	1
B6	6-00-00	1-3/4" x 11-7/8" VERSA-LAM® 2.0 3100 SP	1	1
B7	4-00-00	1-3/4" x 11-7/8" VERSA-LAM® 2.0 3100 SP	1	1

Connector Summary		
Qty	Manuf	Product
13	H1	IUS2.56/11.88
4	H1	IUS2.56/11.88
3	H2	HUS1.81/10
2	H2	HUS1.81/10



FROM PLAN DATED:

BUILDER: ROYAL PINE HOMES

SITE: CENTREFIELD WEST GORMLEY

MODEL: UNIT 2008

ELEVATION: A,B

LOT:

CITY: RICHMOND HILL

SALESMAN: MARIO DICIANO

DESIGNER: AJ

REVISION:

NOTES:

REFER TO THE **NORDIC INSTALLATION** GUIDE FOR PROPER STORAGE AND INSTALLATION.

SQUASH BLOCKS OF 2x4, 2x6, 2x8 #2 S.P.F REQ'D UNDER INTERIOR UNIFORM LOAD BEARING WALLS. **MULTIPLE SQUASH BLOCKS** REQ'D UNDER CONCENTRATED LOADS. SEE FIGURE 1. **CANTILEVERED JOISTS** INCLUDING **CANT' OVER BRICK** RE I-JOIST BLOCKING ALONG BEARING AND RIMBOARD CLOSURE AT ENDS. SEE FIGURES 4 & 5 FOR REINFORCEMENT REQUIREMENTS. FOR **HOLES** INCLUDING **DUCT CHASE** AND **FIELD CUT OPENINGS** SEE FIGURE 7, TABLES 1 & 2. **CERAMIC TIL** APPLICATION AS PER O.B.C 9.30.6.

LOADING:

DESIGN LOADS: L/480.000

LIVE LOAD: 40.0 lb/ft²

DEAD LOAD: 20.0 lb/ft²

SUBFLOOR: 3/4" GLUED AND NAILED

DATE: 2020-07-27


1st FLOOR

CITY OF RICHMOND HILL
BUILDING DIVISION

07/20/2021


RECEIVED

Per: jocelyn.aguilar



Products				
PlotID	Length	Product	Plies	Net Qty
J1	20-00-00	11 7/8" NI-40x	1	9
J2	14-00-00	11 7/8" NI-40x	1	6
J3	12-00-00	11 7/8" NI-40x	1	6
J4	10-00-00	11 7/8" NI-40x	1	4
J5	4-00-00	11 7/8" NI-40x	1	6
J6	20-00-00	11 7/8" NI-80	1	21
B8	20-00-00	1-3/4" x 11-7/8" VERSA-LAM® 2.0 3100 SP	2	2
B11	18-00-00	1-3/4" x 11-7/8" VERSA-LAM® 2.0 3100 SP	2	2
B10	14-00-00	1-3/4" x 11-7/8" VERSA-LAM® 2.0 3100 SP	1	1
B12	10-00-00	1-3/4" x 11-7/8" VERSA-LAM® 2.0 3100 SP	2	2
B9	8-00-00	1-3/4" x 11-7/8" VERSA-LAM® 2.0 3100 SP	1	1

Connector Summary		
Qty	Manuf	Product
12	H1	IUS2.56/11.88
3	H1	IUS2.56/11.88
1	H2	HUS1.81/10
2	H2	HUS1.81/10
1	H3	IUS3.56/11.88
1	H4	HGUS410



FROM PLAN DATED:

BUILDER: ROYAL PINE HOMES

SITE: CENTREFIELD WEST GORMLEY

MODEL: UNIT 2008

ELEVATION: A

LOT:

CITY: RICHMOND HILL

SALESMAN: MARIO DICIANO

DESIGNER: AJ

REVISION:

NOTES:
REFER TO THE NORDIC INSTALLATION GUIDE FOR PROPER STORAGE AND INSTALLATION. **SQUASH BLOCKS** OF 2x4, 2x6, 2x8 #2 S.P.F. REQ'D UNDER INTERIOR UNIFORM LOAD BEARING WALLS. **MULTIPLY SQUASH BLOCKS** REQ'D UNDER CONCENTRATED LOADS. SEE FIGURE 1. **CANTILEVERED JOISTS** INCLUDING **CANT' OVER BRICK** REQ. I-JOIST BLOCKING ALO BEARING AND RIMBOARD CLOSURE AT ENDS. SEE FIGURE 7 TABLES 4 & 5 FOR REINFORCEMENT REQUIREMENTS. FOR **HOLES** INCLUDING **DUCT CHASE** AND **FIEL CUT OPENINGS** SEE FIGURE 7 TABLES 1 & OF THE INSTALLATION GUIDE. **CERAMIC T** APPLICATION AS PER O.B.C. 9.30.6


LOADING:
DESIGN LOADS: L/480.000
LIVE LOAD: 40.0 lb/ft²
DEAD LOAD: 20.0 lb/ft²

SUBFLOOR: 5/8" GLUED AND NAILED

DATE: 2020-07-27

2nd FLOOR





FROM PLAN DATED:

BUILDER: ROYAL PINE HOMES

SITE: CENTREFIELD WEST GORMLEY

MODEL: UNIT 2008

ELEVATION: B

LOT:

CITY: RICHMOND HILL

SALESMAN: MARIO DICIANO

DESIGNER: AJ

REVISION:

NOTES:

REFER TO THE NORDIC INSTALLATION GUIDE FOR PROPER STORAGE AND INSTALLATION. **SQUASH BLOCKS** OF 2x4, 2x6, 2x8 #2 S.P.F. REQ'D UNDER INTERIOR UNIFORM LOAD BEARING WALLS. **MULTIPI SQUASH BLOCKS** REQ'D UNDER CONCENTRATED LOADS. SEE FIGURE 1. **CANTILEVERED JOISTS** INCLUDING **CANT' OVER BRICK** REQ. I-JOIST BLOCKING ALO BEARING AND RIMBOARD CLOSURE AT ENDS. SEE FIGURE 7 TABLES 4 & 5 FOR REINFORCEMENT REQUIREMENTS. FOR **HOLES** INCLUDING **DUCT CHASE** AND **FIEL CUT OPENINGS** SEE FIGURE 7 TABLES 1 & 2 OF THE INSTALLATION GUIDE. **CERAMIC T** APPLICATION AS PER O.B.C. 9.30.6

LOADING:

DESIGN LOADS: L/480.000


LIVE LOAD: 40.0 lb/ft²

DEAD LOAD: 20.0 lb/ft²

SUBFLOOR: 5/8" GLUED AND NAILED

DATE: 2020-07-27

2nd FLOOR



Products				
PlotID	Length	Product	Plies	Net Qty
J1	20-00-00	11 7/8" NI-40x	1	9
J2	14-00-00	11 7/8" NI-40x	1	6
J3	12-00-00	11 7/8" NI-40x	1	6
J4	10-00-00	11 7/8" NI-40x	1	4
J5	4-00-00	11 7/8" NI-40x	1	6
J6	20-00-00	11 7/8" NI-80	1	21
B8	20-00-00	1-3/4" x 11-7/8" VERSA-LAM® 2.0 3100 SP	2	2
B11	18-00-00	1-3/4" x 11-7/8" VERSA-LAM® 2.0 3100 SP	2	2
B10	14-00-00	1-3/4" x 11-7/8" VERSA-LAM® 2.0 3100 SP	1	1
B12	10-00-00	1-3/4" x 11-7/8" VERSA-LAM® 2.0 3100 SP	2	2
B9	8-00-00	1-3/4" x 11-7/8" VERSA-LAM® 2.0 3100 SP	1	1

Connector Summary		
Qty	Manuf	Product
12	H1	IUS2.56/11.88
3	H1	IUS2.56/11.88
1	H2	HUS1.81/10
2	H2	HUS1.81/10
1	H3	IUS3.56/11.88
1	H4	HGUS410

CITY OF RICHMOND HILL
BUILDING DIVISION


07/20/2021

RECEIVED

Per: jocelyn.aguilar



INSTALLATION GUIDE FOR RESIDENTIAL FLOORS




Distributed by:




N-CSD1 / November 2014

SAFETY AND CONSTRUCTION PRECAUTIONS



Do not walk on I-joists until fully braced and braced, or serious injuries can result.



Never stack building materials over unbraced I-joists. Once sheathed, do not over-stress I-joist with concentrated loads from building materials.

WARNING

I-joists are not stable until completely installed, and will not carry any load until fully braced and sheathed.


Avoid Accidents by Following these Important Guidelines:

1. Brace and nail each I-joist as it is installed, using hangers, blocking panels, rim board, and/or cross-briding at joist ends. When I-joists are applied continuous over interior supports and a load-bearing wall is planned at that location, blocking will be required at the interior support.
2. When the building is completed, the floor sheathing will provide lateral support for the top flanges of the I-joists. Until this sheathing is applied, temporary bracing, often called struts, or temporary sheathing must be applied to prevent I-joist rollover or buckling.
 - Temporary bracing or struts must be 1x4 inch minimum, at least 8 feet long and spaced no more than 8 feet on center, and must be secured with a minimum of two 2-1/2" nails fastened to the top surface of each I-joist. Nail the bracing to a lateral restraint at the end of each bay. Top ends of adjoining bracing over at least two I-joists.
 - Or, sheathing (temporary or permanent) can be nailed to the top flange of the first 4 feet of I-joists at the end of the bay.
3. For cantilevered I-joists, brace top and bottom flanges, and brace ends with closure panels, rim board, or cross-briding.
4. Install and fully nail permanent sheathing to each I-joist before placing loads on the floor system. Then, stack building materials over beams or walls only.
5. Never install a damaged I-joist.

Improper storage or installation, failure to follow applicable building codes, failure to follow span ratings for Nordic I-joists, failure to follow allowable hole sizes and locations, or failure to use web stiffeners when required can result in serious accidents. Follow these installation guidelines carefully.

STORAGE AND HANDLING GUIDELINES

1. Bundle wrap can be slippery when wet. Avoid walking on wrapped bundles.
2. Store, stack, and handle I-joists vertically and level only.
3. Always stack and handle I-joists in the upright position only.
4. Do not store I-joists in direct contact with the ground and/or flatwise.
5. Protect I-joists from weather, and use spacers to separate bundles.
6. Bundled units should be kept intact until time of installation.
7. When handling I-joists with a crane on the job site, take a few simple precautions to prevent damage to the I-joists and injury to your work crew.
 - Pick I-joists in bundles as shipped by the supplier.
 - Orient the bundles so that the webs of the I-joists are vertical.
 - Pick the bundles at the 5th points, using a spreader bar if necessary.
8. Do not handle I-joists in a horizontal orientation.
9. NEVER USE OR TRY TO REPAIR A DAMAGED I-JOIST.



MAXIMUM FLOOR SPANS

1. Maximum clear spans applicable to simple-span or multiple-span residential floor construction with a design live load of 40 psf and dead load of 15 psf. The ultimate limit states are based on the factored loads of 1.50L + 1.25D. The serviceability limit states include the consideration for floor vibration and a live load deflection limit of L/480. For multiple-span applications, the end spans shall be 40% or more of the adjacent span.
2. Spans are based on a composite floor with glued-nailed oriented strand board (OSB) sheathing with a minimum thickness of 5/8 inch for a joist spacing of 19.2 inches or less, or 3/4 inch for joist spacing of 24 inches. Adhesive shall meet the requirements given in CGS-71.26. Standard. No concrete topping or bridging element was assumed. Increased spans may be achieved with the use of gypsum and/or a row of blocking at mid-span.
3. Minimum bearing length shall be 1-3/4 inches for the end bearings, and 3-1/2 inches for the intermediate bearings.
4. Bearing stiffeners are not required when I-joists are used with the spans and spacings given in this table, except as required for hangers.
5. This span chart is based on uniform loads. For applications with other than uniform loads, an engineering analysis may be required based on the use of the design properties.
6. Tables are based on Limit States Design per CAN/CSA O86-09 Standard, and NBC 2010.
7. SI units conversion: 1 inch = 25.4 mm
1 foot = 0.305 m


MAXIMUM FLOOR SPANS FOR NORDIC I-JOISTS SIMPLE AND MULTIPLE SPANS

Joist Depth	Joist Spacing	Simple Span				Multiple Span			
		19.2"	24"	30"	36"	19.2"	24"	30"	36"
9-1/2"	NI-20	15'-1"	14'-2"	13'-9"	13'-5"	16'-3"	15'-4"	14'-10"	14'-7"
	NI-40x	16'-1"	15'-2"	14'-8"	14'-9"	17'-5"	16'-5"	15'-10"	15'-5"
	NI-60	16'-3"	15'-4"	14'-10"	14'-11"	17'-7"	16'-7"	16'-0"	15'-7"
	NI-70	17'-1"	16'-1"	15'-6"	15'-7"	18'-7"	17'-4"	16'-9"	16'-10"
	NI-80	17'-3"	16'-3"	15'-8"	15'-9"	18'-10"	17'-6"	16'-11"	17'-0"
11-7/8"	NI-20	16'-11"	16'-0"	15'-5"	15'-6"	18'-4"	17'-3"	16'-8"	16'-7"
	NI-40x	18'-1"	17'-0"	16'-5"	16'-6"	20'-0"	18'-6"	17'-7"	17'-7"
	NI-60	18'-4"	17'-3"	16'-7"	16'-9"	20'-3"	18'-9"	18'-0"	18'-1"
	NI-70	19'-6"	18'-0"	17'-4"	17'-5"	21'-6"	19'-11"	19'-0"	19'-1"
	NI-80	19'-9"	18'-3"	17'-6"	17'-7"	21'-9"	20'-2"	19'-3"	19'-4"
14"	NI-20	20'-2"	18'-7"	17'-11"	17'-11"	22'-3"	20'-7"	19'-8"	19'-9"
	NI-40x	20'-4"	18'-9"	17'-11"	18'-0"	22'-5"	20'-9"	19'-10"	19'-11"
	NI-60	20'-1"	18'-7"	17'-10"	17'-11"	22'-2"	20'-6"	19'-8"	19'-4"
	NI-70	20'-5"	18'-11"	18'-1"	18'-2"	22'-7"	20'-11"	20'-0"	20'-1"
	NI-80	21'-7"	20'-0"	19'-1"	19'-2"	23'-10"	22'-1"	21'-1"	21'-2"
16"	NI-20	22'-5"	20'-8"	19'-9"	19'-10"	24'-9"	22'-10"	21'-10"	21'-6"
	NI-40x	22'-7"	20'-11"	19'-11"	20'-0"	25'-0"	23'-1"	22'-0"	22'-0"
	NI-60	22'-3"	20'-8"	19'-9"	19'-10"	24'-7"	22'-9"	21'-9"	21'-10"
	NI-70	23'-6"	21'-9"	20'-9"	20'-10"	26'-0"	24'-0"	23'-11"	23'-0"
	NI-80	23'-11"	22'-1"	21'-1"	21'-2"	26'-5"	24'-5"	23'-3"	23'-4"

CCMC EVALUATION REPORT 13032-R

I-JOIST HANGERS

1. Hangers shown illustrate the three most commonly used metal hangers to support I-joists.
2. All nailing must meet the hanger manufacturer's recommendations.
3. Hangers should be selected based on the joist depth, flange width and load capacity based on the maximum spans.
4. Web stiffeners are required when the sides of the hangers do not laterally brace the top flange of the I-joist.



NORDIC I-JOIST SERIES


Series	Material	Length	Weight
NI-20	2x4 S-PF No. 2	16'-0"	33 pieces per unit
NI-40x	2x6 S-PF No. 2	16'-0"	33 pieces per unit
NI-60	2x8 S-PF No. 2	16'-0"	33 pieces per unit
NI-70	2x10 S-PF No. 2	16'-0"	23 pieces per unit
NI-80	2x12 S-PF No. 2	16'-0"	23 pieces per unit
NI-90	2x14 S-PF No. 2	16'-0"	23 pieces per unit
NI-90x	2x16 S-PF No. 2	16'-0"	23 pieces per unit

Chantiers Chibougamou Ltd. harvests its own trees, which enables Nordic products to adhere to strict quality control procedures throughout the manufacturing process. Every phase of the operation, from logging to the finished product, reflects our commitment to quality.

Nordic Engineered Wood I-joists use only finger-jointed black spruce lumber in their flanges, ensuring consistent quality, superior strength, and longer span carrying capacity.


INSTALLING NORDIC I-JOISTS

1. Before laying out floor system components, verify that I-joist flange widths match hanger widths. If not, consult your supplier.
2. Except for cutting to length, I-joist flanges should never be cut, drilled, or notched.
3. Install I-joists so that top and bottom flanges are within 1/2 inch of true vertical alignment.
4. I-joists must be anchored securely to supports before floor sheathing is attached, and supports for multiple-span applications must be level.
5. Minimum bearing lengths: 1-3/4 inches for end bearings and 3-1/2 inches for intermediate bearings.
6. When using hangers, seat I-joists firmly in hanger bottoms to minimize settlement.
7. Leave a 1/16-inch gap between the I-joist end and a header.
8. Concentrated loads greater than those that can normally be expected in residential construction should only be applied to the top surface of the top flange. Normal concentrated loads include track lighting fixtures, audio equipment and security cameras. Never suspend unusual or heavy loads from the I-joist's bottom flange. Whenever possible, suspend all concentrated loads from the top of the I-joist. Or, attach the load to blocking that has been securely fastened to the I-joist webs.
9. Never install I-joists where they will be permanently exposed to weather, or where they will remain in direct contact with concrete or masonry.
10. Restrain ends of floor joists to prevent rollover. Use rim board, rim joists or I-joist blocking panels.
11. For I-joists installed over and beneath bearing walls, use full depth blocking panels, rim board, or squash blocks (cripple members) to transfer gravity loads through the floor system to the wall or foundation below.
12. Due to shrinkage, common framing lumber set on edge may never be used as blocking or rim boards. I-joist blocking panels or other engineered wood products - such as rim board - must be cut to fit between the I-joists, and an I-joist-compatible depth selected.
13. Provide permanent lateral support of the bottom flange of all I-joists at interior supports of multiple-span joists. Similarly, support the bottom flange of all cantilevered I-joists at the end support next to the cantilever extension. In the completed structure, the gypsum wallboard ceiling provides this lateral support. Until the final finished ceiling is applied, temporary bracing or struts must be used.
14. If square-edge panels are used, edges must be supported between I-joists with 2x4 blocking. Glue panels to blocking to minimize squeaks. Blocking is not required under structural finish flooring, such as wood strip flooring, or if a separate underlayment layer is installed.
15. Nail spacing: Space nails installed to the flange's top face in accordance with the applicable building code requirements or approved building plans.




Blocking Panel or Rim Joist	Maximum Factored Uniform Vertical Load* (plf)
NI Joists	3,300

*The uniform vertical load is limited to a joist depth of 16 inches or less and is based on standard term load duration. It shall not be used in the design of a bending member, such as joist, header, or rafter. For concentrated vertical load transfer, see detail 1d.




Blocking Panel or Rim Joist	Maximum Factored Uniform Vertical Load* (plf)
1-1/8" Rim Board Plus	8,090

*The uniform vertical load is limited to a rim board depth of 16 inches or less and is based on standard term load duration. It shall not be used in the design of a bending member, such as joist, header, or rafter. For concentrated vertical load transfer, see detail 1d.




All nails shown in the above details are assumed to be common wire nails unless otherwise noted. 3" (0.122" dia.) common spiral nails may be substituted for 2-1/2" (0.128" dia.) common wire nails. Framing lumber assumed to be Spruce-Pine-Fir No. 2 or better. Individual components not shown to scale for clarity.





Pair of Squash Blocks	Maximum Factored Vertical per Pair of Squash Blocks (lbs)
3-1/2" wide	5,500
5-1/2" wide	8,500

Provide lateral bracing per detail 1a, 1b, or 1c




Pair of Squash Blocks	Maximum Factored Vertical per Pair of Squash Blocks (lbs)
2x Lumber	5,500
1-1/8" Rim Board Plus	4,300
	6,600



Provide lateral bracing per detail 1a, 1b, or 1c




For nailing schedules for multiple beams, see the manufacturer's recommendations.





Note: Unless hanger sides laterally support the top flange, bearing stiffeners shall be used.




Maximum support capacity = 1,620 lbs.





For nailing schedules for multiple beams, see the manufacturer's recommendations.




Maximum support capacity = 1,620 lbs.



Maximum support capacity = 1,620 lbs.





Note: Blocking required at bearing for lateral support, not shown for clarity.




Notes:

- 1. Support back of I-joist web during nailing to prevent damage to web/flange connection.
- 2. Leave a 1/8 to 1/4-inch gap between top of filler block and bottom of top I-joist flange.
- 3. Filler block is required between joists for full length of span.
- 4. Nail joists together with two rows of 3 inch nails at 12 inches o.c. (clinch when possible) on each side of the double I-joist. Total of four nails per foot required. If nails can be clinched, only two nails per foot are required.
- 5. The maximum factored load that may be applied to one side of the double I-joist using this detail is 860 lbs/ft. Verify double I-joist capacity.



For hanger capacity see hanger manufacturer's recommendations. Verify double I-joist capacity to support concentrated loads.



Notes:

- In some local codes, blocking is prescriptively required in the first joist space (or first and second joist space) next to the starter joist. Where required, see local code requirements for spacing of the blocking.
- All nails are common spiral in this detail.

CITY OF RICHMOND HILL
BUILDING DIVISION

07/20/2021

RECEIVED
Per: jocelyn.aguiar

CANTILEVER DETAILS FOR BALCONIES (NO WALL LOAD)

3a) I-JOIST CANTILEVER DETAIL FOR BALCONIES (No Wall Load)

Cantilever extension supporting uniform floor loads only

Rim board or wood structural panel closure; attach per detail 1b

Attach I-joists to plate at all supports per detail 1b

I-joist, or rim board

3-1/2" min. bearing required

CAUTION: Cantilevers formed this way must be carefully detailed to prevent moisture intrusion into the structure and potential decay of untreated I-joist extensions.

Note: This detail is applicable to cantilevers supporting a maximum specified uniform live load of 60 psf.

3b) LUMBER CANTILEVER DETAIL FOR BALCONIES (No Wall Load)

Full depth backer block with 1/8" gap between block and top flange of I-joist. See detail 1h. Nail with 2 rows of 3" nails at 6" o.c. and clinch.

2x8 min. Nail to backer block and joist with 2 rows of 3" nails at 6" o.c. and clinch. (Cantilever nails may be used to attach backer block if length of nail is sufficient to allow clinching.)

Cantilever extension supporting uniform floor loads only

Lumber or wood structural panel closure

3-1/2" min. bearing required

I-joist, or rim board

Note: This detail is applicable to cantilevers supporting a maximum specified uniform live load of 60 psf.

CANTILEVER DETAILS FOR VERTICAL BUILDING OFFSET (CONCENTRATED WALL LOAD)

3a) Method 1 — SHEATHING REINFORCEMENT ONE SIDE

Rim board or wood structural panel closure (3/4" minimum thickness); attach per detail 1b

NI blocking panel or rim board blocking; attach per detail 1g

Attach I-joist to plate per detail 1b

2-1/2" nails

3-1/2" min. bearing required

Method 2 — SHEATHING REINFORCEMENT TWO SIDES

- Use same installation as Method 1 but reinforce both sides of I-joist with sheathing.
- Use nailing pattern shown for Method 1 with opposite face nailing offset by 3".

Note: Canadian softwood plywood sheathing or equivalent (minimum thickness 3/4") required on sides of joist. Depth shall match the full height of the joist. Nail with 2-1/2" nails at 6" o.c., top and bottom flange. Install with face grain horizontal. Attach I-joist to plate at all supports per detail 1b. Verify reinforced I-joist capacity.

3b) Alternate Method 2 — DOUBLE I-JOIST

Rim board, or wood structural panel closure (3/4" minimum thickness); attach per detail 1b

NI blocking panel or rim board blocking; attach per detail 1g

Face nail two rows of 3" nails at 12" o.c. each side through one I-joist web and the filler block to other I-joist web. Offset nails from opposite face by 6". Clinch if possible (four nails per foot required, except two nails per foot required if clinched).

Attach I-joists to top plate at all supports per detail 1b, 3-1/2" min. bearing required

Block I-joists together with filler blocks for the full length of the reinforcement. For I-joist flange widths greater than 3 inches place an additional row of 3" nails along the centreline of the reinforcing panel from each side. Clinch when possible.

FIGURE 4 (continued)

See table below for NI reinforcement requirements at cantilever.

Roof truss span

2'-0" maximum cantilever

Roof trusses

13'-0" maximum

Jack trusses

2'-0" maximum cantilever

For hip roofs with the jack trusses running parallel to the cantilevered floor joists, the I-joist reinforcement requirements for a span of 26 ft. shall be permitted to be used.

CANTILEVER REINFORCEMENT METHODS ALLOWED

JOIST DEPTH (in)	JOIST TRUSS SPAN (ft)	ROOF LOADING (UNFACTORED)												
		LL = 30 psf, DL = 15 psf				LL = 40 psf, DL = 15 psf				LL = 50 psf, DL = 15 psf				
		12	16	19/2	24	12	16	19/2	24	12	16	19/2	24	
9-1/2"	26	N	N	N	1	2	N	1	2	X	N	2	X	X
	28	N	N	N	1	2	X	N	1	2	X	N	2	X
	30	N	1	1	X	N	1	2	X	1	2	X	X	
	32	N	1	2	X	N	2	X	X	1	X	X	X	
11-7/8"	34	N	1	2	X	N	2	X	X	1	X	X	X	
	36	N	1	2	X	1	2	X	X	1	X	X	X	
	28	N	N	N	1	N	N	1	2	N	1	1	2	
	30	N	N	N	1	N	N	1	2	N	1	2	X	
14'	32	N	N	N	1	N	N	1	2	N	1	2	X	
	34	N	N	N	1	N	N	1	2	N	1	2	X	
	36	N	N	N	1	N	N	1	2	N	1	2	X	
	40	N	N	N	1	N	N	1	2	N	2	X	X	
16'	26	N	N	N	N	N	N	N	1	N	N	N	1	
	28	N	N	N	N	N	N	N	1	N	N	1	1	
	30	N	N	N	N	N	N	N	1	N	N	1	2	
	32	N	N	N	N	N	N	N	1	N	N	1	2	
16'	34	N	N	N	N	N	N	1	N	N	1	2		
	36	N	N	N	N	N	N	1	N	N	1	2		
	38	N	N	N	N	N	N	1	N	N	1	2		
	40	N	N	N	N	N	N	1	N	N	1	2		
16'	42	N	N	N	N	N	N	1	N	N	1	2	X	
	26	N	N	N	N	N	N	N	N	N	N	N	1	
	28	N	N	N	N	N	N	N	1	N	N	N	1	
	30	N	N	N	N	N	N	N	1	N	N	N	1	
16'	32	N	N	N	N	N	N	1	N	N	1	2		
	34	N	N	N	N	N	N	1	N	N	1	2		
	36	N	N	N	N	N	N	1	N	N	1	2		
	38	N	N	N	N	N	N	1	N	N	1	2		
16'	40	N	N	N	N	N	N	1	N	N	1	2		
	42	N	N	N	N	N	N	1	N	N	1	2	X	

1. N = No reinforcement required.
1 = NI reinforced with 3/4" wood structural panel on one side only.
2 = NI reinforced with 3/4" wood structural panel on both sides, or double I-joist.
X = Try a deeper joist or closer spacing.
2. Maximum design load shall be: 15 psf roof dead load, 55 psf floor total load, and 80 psf wall load. Wall load is based on 3'-0" maximum width window or door openings.
3. Table applies to joists 12" to 24" o.c. that meet the floor span requirements for a design live load of 40 psf and dead load of 15 psf, and a live load deflection limit of L/480. Use 12" o.c. requirements for lesser spacing.
4. For conventional roof construction using a ridge beam, the Roof Truss Span column above is equivalent to the distance between the supporting walls and the ridge beam. When the roof is framed using a ridge beam, the Roof Truss Span is equivalent to the live load of 40 psf and dead load of 15 psf, and a live load deflection limit of L/480. Use 12" o.c. requirements for lesser spacing.
5. Cantilevered joists supporting girder trusses or roof beams may require additional reinforcing.

BRICK CANTILEVER DETAILS FOR VERTICAL BUILDING OFFSET (CONCENTRATED WALL LOAD)

3a) SHEATHING REINFORCEMENT

Provide full depth blocking between joists over support (not shown)

12" minimum length of sheathing reinforcement

Nail reinforcement to top and bottom joist flanges with 2-1/2" nails at 6" o.c. (offset opposite face nailing by 3" when using reinforcement on both sides of I-joist)

Note: Canadian softwood plywood sheathing or equivalent (minimum thickness 3/4") required on sides of joist. Depth shall match the full height of the joist. Nail with 2-1/2" nails at 6" o.c., top and bottom flange. Install with face grain horizontal. Attach I-joist to plate at all supports per detail 1b. Verify reinforced I-joist capacity.

3b) SET-BACK DETAIL

Rim board or wood structural panel closure (3/4" minimum thickness); attach per detail 1b.

Bearing walls

5" max.

Back span

Attach joists to girder joist per detail 3c.

3c) SET-BACK CONNECTION

Vertical solid sawn blocks (2x6 S-P-F No. 2 or better) nailed through joist web and web of girder using 2-1/2" nails.

Alternates for opposite side.

Hangar may be used in lieu of solid sawn blocks

FIGURE 5 (continued)

See table below for NI reinforcement requirements at cantilever.

Roof truss span

2'-0" maximum cantilever

Roof trusses

13'-0" maximum

Jack trusses

2'-0" maximum cantilever

5" maximum

For hip roofs with the jack trusses running parallel to the cantilevered floor joists, the I-joist reinforcement requirements for a span of 26 ft. shall be permitted to be used.

BRICK CANTILEVER REINFORCEMENT METHODS ALLOWED

JOIST DEPTH (in)	JOIST TRUSS SPAN (ft)	ROOF LOADING (UNFACTORED)											
		LL = 30 psf, DL = 15 psf				LL = 40 psf, DL = 15 psf				LL = 50 psf, DL = 15 psf			
		12	16	19/2	24	12	16	19/2	24	12	16	19/2	24
9-1/2"	26	1	X	X	X	2	X	X	X	2	X	X	X
	28	1	X	X	X	2	X	X	X	2	X	X	X
	30	1	X	X	X	2	X	X	X	2	X	X	X
	32	2	X	X	X	2	X	X	X	2	X	X	X
11-7/8"	34	2	X	X	X	2	X	X	X	2	X	X	X
	36	2	X	X	X	2	X	X	X	2	X	X	X
	28	N	2	X	X	1	X	X	X	1	X	X	X
	30	N	2	X	X	1	X	X	X	1	X	X	X
14'	32	N	2	X	X	1	X	X	X	1	X	X	X
	34	N	2	X	X	1	X	X	X	1	X	X	X
	36	N	2	X	X	1	X	X	X	1	X	X	X
	38	N	2	X	X	1	X	X	X	1	X	X	X
16'	40	N	2	X	X	1	X	X	X	1	X	X	X
	26	N	1	2	X	N	1	2	X	N	2	X	X
	28	N	1	2	X	N	1	2	X	N	2	X	X
	30	N	1	2	X	N	1	2	X	N	2	X	X
16'	32	N	1	2	X	N	1	2	X	N	2	X	X
	34	N	1	2	X	N	1	2	X	N	2	X	X
	36	N	1	2	X	N	1	2	X	N	2	X	X
	38	N	1	2	X	N	1	2	X	N	2	X	X
16'	40	N	1	2	X	N	1	2	X	N	2	X	X
	42	N	1	2	X	N	1	2	X	N	2	X	X

1. N = No reinforcement required.
1 = NI reinforced with 3/4" wood structural panel on one side only.
2 = NI reinforced with 3/4" wood structural panel on both sides, or double I-joist.
X = Try a deeper joist or closer spacing.
2. Maximum design load shall be: 15 psf roof dead load, 55 psf floor total load, and 80 psf wall load. Wall load is based on 3'-0" maximum width window or door openings.
3. Table applies to joists 12" to 24" o.c. that meet the floor span requirements for a design live load of 40 psf and dead load of 15 psf, and a live load deflection limit of L/480. Use 12" o.c. requirements for lesser spacing.
4. For conventional roof construction using a ridge beam, the Roof Truss Span column above is equivalent to the distance between the supporting wall and the ridge beam. When the roof is framed using a ridge beam, the Roof Truss Span is equivalent to the live load of 40 psf and dead load of 15 psf, and a live load deflection limit of L/480. Use 12" o.c. requirements for lesser spacing.
5. Cantilevered joists supporting girder trusses or roof beams may require additional reinforcing.

WEB HOLES

RULES FOR CUTTING HOLES AND DUCT CHASE OPENINGS:

- The distance between the inside edge of the support and the centreline of any hole or duct chase opening shall be in compliance with the requirements of Table 1 or 2, respectively.
- I-joist top and bottom flanges must NEVER be cut, notched, or otherwise modified.
- Whenever possible, field-cut holes should be centred on the middle of the web.
- The maximum size hole or the maximum depth of a duct chase opening that can be cut into an I-joist web shall equal the clear distance between the flanges of the I-joist minus 1/4 inch. A minimum of 1/8 inch should always be maintained between the top or bottom of the hole or opening and the adjacent I-joist flange.
- The sides of square holes or longest sides of rectangular holes should not exceed 3/4 of the diameter of the maximum round hole permitted at that location.
- Where more than one hole is necessary, the distance between adjacent hole edges shall exceed twice the diameter of the largest round hole or twice the size of the largest square hole (or twice the length of the longest side of the longest rectangular hole or duct chase opening) and each hole and duct chase opening shall be sized and located in compliance with the requirements of Tables 1 and 2, respectively.
- A knockout is NOT considered a hole, may be utilized anywhere it occurs, and may be ignored for purposes of calculating minimum distances between holes and/or duct chase openings.
- Holes measuring 1-1/2 inches or smaller shall be permitted anywhere in a cantilevered section of a joist. Holes of greater size may be permitted subject to verification.
- A 1-1/2 inch hole or smaller can be placed anywhere in the web provided that it meets the requirements of rule number 6 above.
- All holes and duct chase openings shall be cut in a workman-like manner in accordance with the restrictions listed above and as illustrated in Figure 7.
- Limit three maximum size holes per span, of which one may be a duct chase opening.
- A group of round holes of approximately the same location shall be permitted if they meet the requirements for a single round hole circumscribed around them.

FIGURE 7 FIELD-CUT HOLE LOCATOR

See Table 1 for minimum distance from bearing

2x diameter of larger hole

Duct chase opening (see Table 2 for minimum distance from bearing)

Knockouts

See rule 12

Maintain minimum 1/8" space between top and bottom flange — all duct chase openings and holes

For rectangular holes, avoid over-cutting the corners, as this can cause unnecessary stress concentrations. Slightly rounding the corners is recommended. Starting the rectangular hole by drilling a 1-inch diameter hole in each of the four corners and then making the cuts between the holes is another good method to minimize damage to the I-joist.

A knockout is NOT considered a hole, may be utilized wherever it occurs and may be ignored for purposes of calculating minimum distances between holes.

TABLE 1 LOCATION OF CIRCULAR HOLES IN JOIST WEBS

Simple or Multiple Span for Dead Loads up to 15 psf and Live Loads up to 40 psf

JOIST DEPTH (in)	JOIST TRUSS SPAN (ft)	Minimum distance from inside face of any support to centre of hole (in)												Span (ft)	
		0	3	6	9	12	15	18	21	24	27	30	33		
9-1/2"	Ni-20	0.7	1.0	2.0	3.0	4.0	5.0	6.0	7.0	8.0	9.0	10.0	11.0	12.0	13.0
	Ni-40	0.7	1.0	2.0	3.0	4.0	5.0	6.0	7.0	8.0	9.0	10.0	11.0	12.0	13.0
	Ni-60	1.2	2.0	3.0	4.0	5.0	6.0	7.0	8.0	9.0	10.0	11.0	12.0	13.0	14.0
	Ni-80	2.0	3.0	4.0	5.0	6.0	7.0	8.0	9.0	10.0	11.0	12.0	13.0	14.0	15.0
11-7/8"	Ni-20	0.7	1.0	2.0	3.0	4.0	5.0	6.0	7.0	8.0	9.0	10.0	11.0	12.0	13.0
	Ni-40	0.7	1.0	2.0	3.0	4.0	5.0	6.0	7.0	8.0	9.0	10.0	11.0	12.0	13.0
	Ni-60	1.2	2.0	3.0	4.0	5.0	6.0	7.0	8.0	9.0	10.0	11.0	12.0	13.0	14.0
	Ni-80	2.0	3.0	4.0	5.0	6.0	7.0	8.0	9.0	10.0	11.0	12.0	13.0	14.0	15.0
14'	Ni-20	0.7	1.0	2.0	3.0	4.0	5.0	6.0	7.0	8.0	9.0	10.0	11.0	12.0	13.0
	Ni-40	0.7	1.0	2.0	3.0	4.0	5.0	6.0	7.0	8.0	9.0	10.0	11.0	12.0	13.0
	Ni-60	1.2	2.0	3.0	4.0	5.0	6.0	7.0	8.0	9.0	10.0	11.0	12.0	13.0	14.0
	Ni-80	2.0	3.0	4.0	5.0	6.0	7.0	8.0	9.0	10.0	11.0	12.0	13.0	14.0	15.0
16'	Ni-20	0.7	1.0	2.0	3.0	4.0	5.0	6.0	7.0	8.0	9.0	10.0	11.0	12.0	13.0
	Ni-40	0.7	1.0	2.0	3.0	4.0	5.0	6.0	7.0	8.0	9.0	10.0	11.0	12.0	13.0
	Ni-60	1.2	2.0	3.0	4.0	5.0	6.0	7.0	8.0	9.0	10.0	11.0	12.0	13.0	14.0
	Ni-80	2.0	3.0	4.0	5.0	6.0	7.0	8.0	9.0	10.0	11.0	12.0	13.0	14.0	15.0

1. Above table may be used for I-joist spacing of 24 inches on centre or less.
2. Hole location distance is measured from inside face of supports to centre of hole.
3. Distances in this chart are based on uniformly loaded joists.

OPTIONAL:

The above table is based on the I-joists used at their maximum span. If the I-joists are placed at less than their full maximum span (see Maximum Span Table), the minimum distance from the centreline of the hole to the face of any support (S) as given above may be reduced as follows:

Deducted = $\frac{S}{S_{max}} \times D$

Where: $\frac{S}{S_{max}}$ = Distance from the inside face of any support to centre of hole, reduced for less-than-maximum span applications (S). The reduced distance shall not be less than 6 inches from the face of the support to edge of the hole.
D = The actual measured span distance between the inside faces of supports (ft).
S = Span Adjustment Factor given in this table.
D = The minimum distance from the inside face of any support to centre of hole from this table.
If $\frac{S}{S_{max}}$ is greater than 1, use 1 in the above calculation for Deducted.

INSTALLING THE GLUED FLOOR SYSTEM

- Wipe any mud, dirt, water, or ice from I-joist flanges before gluing.
- Snap a chalk line across the I-joists four feet in from the wall for panel edge alignment and as a boundary for spreading glue.
- Spread only enough glue to lay one or two panels at a time, or follow specific recommendations from the glue manufacturer.
- Lay the first panel with tongue side to the wall, and nail in place. This protects the tongue of the next panel from damage when tapped into place with a block and sledgehammer.
- Apply a continuous line of glue (about 1/4-inch diameter) to the top flange of a single I-joist. Apply glue in a winding pattern on wide areas, such as with double I-joists.
- Apply two lines of glue on I-joists where panel ends butt to assure proper gluing of each end.
- After the first row of panels is in place, spread glue in the groove of one or two panels at a time before laying the next row. Glue line may be continuous or spaced, but avoid squeeze-out by applying a thinner line (1/8 inch) than used on I-joist flanges.
- Tap the second row of panels into place, using a block to protect groove edges.
- Stagger end joints in each succeeding row of panels. A 1/8-inch space between all end joints and 1/8-inch at all edges, including T&G edges, is recommended. (Use a spacer tool or an 1/8" common nail to assure accurate and consistent spacing.)
- Complete all nailing of each panel before glue sets. Check the manufacturer's recommendations for cure time. (Warm weather accelerates glue setting.) Use 2" ring- or screw-shank nails for panels 3/4-inch thick or less, and 2-1/2" ring- or screw-shank nails for thicker panels. Space nails per the table below. Closer nail spacing may be required by some codes, or for diaphragm construction. The finished deck can be walked on right away and will carry construction loads without damage to the glue bond.

FASTENERS FOR SHEATHING AND SUBFLOORING⁽¹⁾

Maximum Joist Spacing (in)	Minimum Panel Thickness (in)	Nail Size and Type			Maximum Spacing of Fasteners	
		Common Nails or Staples	Ring-Thread Nails or Screws	Staples	Edges	Uniform Spacing
16	5/8	2"	1-3/4"	2"	6"	12"
20	5/8	2"	1-3/4"	2"	6"	12"
24	3/4	2"	1-3/4"	2"	6"	12"

1. Fasteners of sheathing and subflooring shall conform to the above table.
2. Staples shall not be less than 1/16-inch in diameter or thickness, with not less than a 3/8-inch crown driven with the crown parallel to framing.
3. Flooring screws shall not be less than 1/8-inch in diameter.
4. Special conditions may impose heavy traffic and concentrated loads that require construction in excess of the minimums shown.
5. Use only adhesives conforming to CAN/CGSB-71.26 Standard, Adhesives for Field-Gluing Plywood to Lumber Framing for Floor System, applied in accordance with the manufacturer's recommendations. If OSB panels with sealed surfaces and edges are to be used, use only solvent-based glues; check with panel manufacturer.

Ref.: NRC-CNRC, National Building Code of Canada 2010, Table 9.23.3.5.

FASTENERS FOR SHEATHING AND SUBFLOORING⁽¹⁾

Maximum Joist Spacing (in)	Minimum Panel Thickness (in)	Nail Size and Type			Maximum Spacing of Fasteners	
		Common Nails or Staples	Ring-Thread Nails or Screws	Staples	Edges	Uniform Spacing
16	5/8	2"	1-3/4"	2"	6"	12"
20	5/8	2"	1-3/4"	2"	6"	12"
24	3/4	2"	1-3/4"	2"	6"	12"

1. Fasteners of sheathing and subflooring shall conform to the above table.
2. Staples shall not be less than 1/16-inch in diameter or thickness, with not less than a 3/8-inch crown driven with the crown parallel to framing.
3. Flooring screws shall not be less than 1/8-inch in diameter.
4. Special conditions may impose heavy traffic and concentrated loads that require construction in excess of the minimums shown.
5. Use only adhesives conforming to CAN/CGSB-71.26 Standard, Adhesives for Field-Gluing Plywood to Lumber Framing for Floor System, applied in accordance with the manufacturer's recommendations. If OSB panels with sealed surfaces and edges are to be used, use only solvent-based glues; check with panel manufacturer.

Ref.: NRC-CNRC, National Building Code of Canada 2010, Table 9.23.3.5.

IMPORTANT NOTE:

Floor sheathing must be field glued to the I-joist flanges in order to achieve the maximum spans shown in this document. If sheathing is nailed only, I-joist spans must be verified with your local distributor.

TABLE 2 DUCT CHASE OPENING SIZES AND LOCATIONS — Simple Span Only


JOIST DEPTH (in)	JOIST TRUSS SPAN (ft)	Minimum distance from inside face of any support to centre of opening (in)											
		0	3	6	9	12	15	18	21	24	27	30	33
9-1/2"	Ni-20	4.1	4.5	4.10	5.4	5.8	6.1	6.4	7.1	7.5	7.8	8.2	8.5
	N												

07/20/2021

RECEIVED

Per: jocelyn.aguilar**NORDIC**
STRUCTURESCOMPANY
July 22, 2020 10:56PROJECT
J4 2ND FLOOR.wwb**Design Check Calculation Sheet**
Nordic Sizer – Canada 7.2**Loads:**

Load	Type	Distribution	Pat-tern	Location [ft] Start End	Magnitude Start End	Unit
Load1	Dead	Full Area			20.00	psf
Load2	Live	Full Area			40.00	psf

Maximum Reactions (lbs) and Support Bearing (in):

Unfactored:			
Dead	188		188
Live	376		376
Factored:			
Total	800		800
Bearing:			
Capacity			
Joist	2336		2336
Support	10841		10841
Des ratio			
Joist	0.34		0.34
Support	0.07		0.07
Load case	#2		#2
Length	4-3/8		4-3/8
Min req'd	1-3/4		1-3/4
Stiffener	No		No
KD	1.00		1.00
KB support	-		-
fcp sup	769		769
Kzcp sup	-		-

Bearing for wall supports is perpendicular-to-grain bearing on top plate. No stud design included.

Nordic Joist 11-7/8" NI-80 Floor joist @ 12" o.c.

Supports: All - Lumber Wall, No.1/No.2

Total length: 19' 4-3/4"; Clear span: 18' 8"; 5/8" nailed and glued OSB sheathing with 1/2" gypsum ceiling

This section PASSES the design code check.**Limit States Design using CSA O86-14 and Vibration Criterion:**

Criterion	Analysis Value	Design Value	Unit	Analysis/Design
Shear	Vf = 800	Vr = 2336	lbs	Vf/Vr = 0.34
Moment (+)	Mf = 3760	Mr = 11609	lbs-ft	Mf/Mr = 0.32
Perm. Defl'n	0.11 = < L/999	0.63 = L/360	in	0.17
Live Defl'n	0.21 = < L/999	0.47 = L/480	in	0.45
Total Defl'n	0.32 = L/712	0.94 = L/240	in	0.34
Bare Defl'n	0.23 = L/966	0.63 = L/360	in	0.37
Vibration	Lmax = 18'-9.8	Lv = 20'-5.8	ft	0.92
Defl'n	= 0.027	= 0.033	in	0.81

DWG NO. TAM9162 -21
STRUCTURAL
COMPONENT ONLY

Additional Data:

FACTORS:	f/E	KD	KH	KZ	KL	KT	KS	KN	LC#
Vr	2336	1.00	1.00	-	-	-	-	-	#2
Mr+	11609	1.00	1.00	-	1.000	-	-	-	#2
EI	547.1 million	-	-	-	-	-	-	-	#2

CRITICAL LOAD COMBINATIONS:

Shear : LC #2 = 1.25D + 1.5L

Moment(+) : LC #2 = 1.25D + 1.5L

Deflection: LC #1 = 1.0D (permanent)

LC #2 = 1.0D + 1.0L (live)

LC #2 = 1.0D + 1.0L (total)

LC #2 = 1.0D + 1.0L (bare joist)

Bearing : Support 1 - LC #2 = 1.25D + 1.5L

Support 2 - LC #2 = 1.25D + 1.5L

Load Types: D=dead W=wind S=snow H=earth,groundwater E=earthquake

L=live(use,occupancy) Ls=live(storage,equipment) f=fire

Load Patterns: s=S/2 L=L+Ls _=no pattern load in this span

All Load Combinations (LCs) are listed in the Analysis output


CALCULATIONS:E_Ieff = 613.27 lb-in² K= .618e06 lbs"Live" deflection is due to all non-dead loads (live, wind, snow...) **CONFORMS TO OBC 2012****AMENDED 2020****Design Notes:**

1. WoodWorks analysis and design are in accordance with the 2015 National Building Code of Canada (NBC), Division B, Part 4, and the CSA O86-14 Engineering Design in Wood standard, Update No. 2 (June 2017).
2. Please verify that the default deflection limits are appropriate for your application.
3. Refer to Nordic Structures technical documentation for installation guidelines and construction details.
4. Nordic I-joists are listed in CCMC evaluation report 13032-R.
5. Joists shall be laterally supported at supports and continuously along the compression edge.
6. The design assumptions and specifications have been provided by the client. Any damages resulting from faulty or incorrect information, specifications, and/or designs furnished, and the correctness or accuracy of this information is their responsibility. This analysis does not constitute a record of the structural integrity of the building nor suitability of the design assumptions made. Nordic Structures is responsible only for the structural adequacy of this component based on the design criteria and loadings shown.

CITY OF RICHMOND HILL
BUILDING DIVISION

07/20/2021

RECEIVED

Per: jocelyn.aguilar

P64
DWG NO. TAM9162 -21
STRUCTURAL
COMPONENT ONLY

NORDIC STRUCTURES

COMPANY
July 22, 2020 08:23


PROJECT
J5 1ST FLOOR.wwb

Design Check Calculation Sheet Nordic Sizer – Canada 7.2

Loads:

Load	Type	Distribution	Pat- tern	Location [ft] Start End	Magnitude Start End	Unit
Load1	Dead	Full Area			20.00	psf
Load2	Live	Full Area			40.00	psf

Maximum Reactions (lbs) and Support Bearing (in):



Unfactored:			
Dead	191		191
Live	383		383
Factored:			
Total	814		814
Bearing:			
Capacity			
Joist	2188		2188
Support	5573		5573
Des ratio			
Joist	0.37		0.37
Support	0.15		0.15
Load case	#2		#2
Length	2-3/8		2-3/8
Min req'd	1-3/4		1-3/4
Stiffener	No		No
KD	1.00		1.00
KB support	1.00		1.00
fcg sup	769		769
Kzcp sup	1.09		1.09

Nordic 11-7/8" NI-80 Floor joist @ 12" o.c.

Supports: All - Lumber Sill plate, No.1/No.2

Total length: 19' 4-3/4"; Clear span: 19'; 3/4" nailed and glued OSB sheathing

This section PASSES the design code check.

CITY OF RICHMOND HILL
BUILDING DIVISION

07/20/2021

RECEIVED

Per: jocelyn.aguilar



8664
DWG NO. YAM 9/163 -21
STRUCTURAL
COMPONENT ONLY

Limit States Design using CSA O86-14 and Vibration Criterion:

Criterion	Analysis Value	Design Value	Unit	Analysis/Design
Shear	Vf = 814	Vr = 2336	lbs	Vf/Vr = 0.35
Moment (+)	Mf = 3894	Mr = 11609	lbs-ft	Mf/Mr = 0.34
Perm. Defl'n	0.11 = < L/999	0.64 = L/360	in	0.17
Live Defl'n	0.22 = < L/999	0.48 = L/480	in	0.46
Total Defl'n	0.33 = L/690	0.96 = L/240	in	0.35
Bare Defl'n	0.25 = L/920	0.64 = L/360	in	0.39
Vibration	Lmax = 19'-1.8	Lv = 21'-2.7	ft	0.90
Defl'n	= 0.026	= 0.033	in	0.78

Additional Data:

FACTORS:	f/E	KD	KH	KZ	KL	KT	KS	KN	LC#
Vr	2336	1.00	1.00	-	-	-	-	-	#2
Mr+	11609	1.00	1.00	-	1.000	-	-	-	#2
EI	547.1 million	-	-	-	-	-	-	-	#2

CRITICAL LOAD COMBINATIONS:

Shear : LC #2 = 1.25D + 1.5L
 Moment (+) : LC #2 = 1.25D + 1.5L
 Deflection: LC #1 = 1.0D (permanent)
 LC #2 = 1.0D + 1.0L (live)
 LC #2 = 1.0D + 1.0L (total)
 LC #2 = 1.0D + 1.0L (bare joist)
 Bearing : Support 1 - LC #2 = 1.25D + 1.5L
 Support 2 - LC #2 = 1.25D + 1.5L
 Load Types: D=dead W=wind S=snow H=earth,groundwater E=earthquake
 L=live(use,occupancy) Ls=live(storage,equipment) f=fire
 Load Patterns: s=S/2 L=L+Ls _=no pattern load in this span
 All Load Combinations (LCs) are listed in the Analysis output

CALCULATIONS:

E_{leff} = 625.37 lb-in² K= 6.18e06 lbs

"Live" deflection is due to all non-dead loads (live, wind, snow...) **CONFORMS TO OBC 2012**

AMENDED 2020**Design Notes:**


1. WoodWorks analysis and design are in accordance with the 2015 National Building Code of Canada (NBC), Division B, Part 4, and the CSA O86-14 Engineering Design in Wood standard, Update No. 2 (June 2017).
2. Please verify that the default deflection limits are appropriate for your application.
3. Refer to Nordic Structures technical documentation for installation guidelines and construction details.
4. Nordic I-joists are listed in CCMC evaluation report 13032-R.
5. Joists shall be laterally supported at supports and continuously along the compression edge.
6. The design assumptions and specifications have been provided by the client. Any damages resulting from faulty or incorrect information, specifications, and/or designs furnished, and the correctness or accuracy of this information is their responsibility. This analysis does not constitute a record of the structural integrity of the building nor suitability of the design assumptions made. Nordic Structures is responsible only for the structural adequacy of this component based on the design criteria and loadings shown.

CITY OF RICHMOND HILL
BUILDING DIVISION

07/20/2021

RECEIVED

Per: jocelyn.aguilar



OWB NO. TAM 8/63 -21
STRUCTURAL
COMPONENT ONLY

BC CALC® Member Report

Build 7493

Job name:

Address:

City, Province, Postal Code: RICHMOND HILL

Customer:

Code reports: CCMC 12472-R


File name: UNIT 2008 EL A,.mmdl

Description: 2ND FLR FRAMING\Flush Beams\B10(i582)

Specifier:

Designer: AJ

Company:



13-06-12
B1 Total Horizontal Product Length = 13-06-12 B2

Reaction Summary (Down / Uplift) (lbs)

Bearing	Live	Dead	Snow	Wind
B1, 2"	528 / 131	241 / 0		
B2, 2"	1452 / 227	654 / 0		

Load Summary

Tag	Description	Load Type	Ref.	Start	End	Loc.	Live 1.00	Dead 0.65	Snow 1.00	Wind 1.15	Tributary
0	Self-Weight	Unf. Lin. (lb/ft)	L	00-00-00	13-06-12	Top		6			00-00-00
1	Smoothed Load	Unf. Lin. (lb/ft)	L	01-02-04	06-06-04	Top	52	26			n/a
2	Smoothed Load	Unf. Lin. (lb/ft)	L	09-05-12	12-05-12	Top	274	137			n/a
3	STAIR	Unf. Lin. (lb/ft)	L	09-10-12	13-06-12	Top	120	60			n/a
4	J5(i542)	Conc. Pt. (lbs)	L	00-06-04	00-06-04	Top	50	25			n/a
5	J5(i622)	Conc. Pt. (lbs)	L	07-02-04	07-02-04	Top	61	30			n/a
6	J2(i629)	Conc. Pt. (lbs)	L	08-02-04	08-02-04	Top	47	-66			n/a
7	J2(i629)	Conc. Pt. (lbs)	L	08-02-04	08-02-04	Top	-179				n/a
8	J2(i630)	Conc. Pt. (lbs)	L	08-11-12	08-11-12	Top	47	-66			n/a
9	J2(i630)	Conc. Pt. (lbs)	L	08-11-12	08-11-12	Top	-179				n/a
10	J2(i636)	Conc. Pt. (lbs)	L	12-11-12	12-11-12	Top	237	119			n/a

Controls Summary

	Factored Demand	Factored Resistance	Demand/Resistance	Case	Location
Pos. Moment	5479 ft-lbs	17696 ft-lbs	31.0%	1	09-11-12
Neg. Moment	-760 ft-lbs	-17696 ft-lbs	4.3%	4	08-02-04
End Shear	2400 lbs	7232 lbs	33.2%	1	12-04-14
Total Load Deflection	L/679 (0.236")	n/a	35.4%	6	07-02-04
Live Load Deflection	L/941 (0.17")	n/a	38.3%	8	07-02-04
Max Defl.	0.236"	n/a	n/a	6	07-02-04
Span / Depth	13.5				

Bearing Supports

	Dim. (LxW)	Demand	Demand/Resistance Support	Demand/Resistance Member	Material
B1 Hanger	2" x 1-3/4"	1093 lbs	n/a	25.6%	HUS1.81/10
B2 Hanger	2" x 1-3/4"	2996 lbs	n/a	70.2%	HUS1.81/10

Cautions

Header for the hanger HUS1.81/10 is a Single 1-3/4" x 11-7/8" LVL Beam.

Hanger model HUS1.81/10 and seat length were input by the user. Hanger has not been analyzed for adequate capacity.


Header for the hanger HUS1.81/10 is a Double 1-3/4" x 11-7/8" LVL Beam.

CITY OF RICHMOND HILL
BUILDING DIVISION

07/20/2021

RECEIVED

Per: jocelyn.aguilar



DWG NO. TAM 9164 -21
STRUCTURAL
COMPONENT ONLY



Single 1-3/4" x 11-7/8" VERSA-LAM® 2.0 3100 SP

PASSED

2ND FLR FRAMING\Flush Beams\B10(i582) (Flush Beam)

Dry | 1 span | No cant.

July 27, 2020 08:56:58

BC CALC® Member Report

Build 7493

Job name:

Address:

City, Province, Postal Code: RICHMOND HILL

Customer:

Code reports: CCMC 12472-R

File name: UNIT 2008 EL A,.mmdl

Description: 2ND FLR FRAMING\Flush Beams\B10(i582)

Specifier:

Designer: AJ

Company:

Notes

Design meets Code minimum (L/240) Total load deflection criteria.

Design meets Code minimum (L/360) Live load deflection criteria.

Calculations assume member is fully braced.

Hanger Manufacturer: Unassigned

Resistance Factor phi has been applied to all presented results per CSA O86.


BC CALC® analysis is based on Canadian Limit States Design, as per NBCC 2015 and CSA O86.

Design based on Dry Service Condition.

Importance Factor : Normal Part code : Part 9

CONFORMS TO OBC 2012

AMENDED 2020



Disclosure

Use of the Boise Cascade Software is subject to the terms of the End User License Agreement (EULA). Completeness and accuracy of input must be reviewed and verified by a qualified engineer or other appropriate expert to assure its adequacy, prior to anyone relying on such output as evidence of suitability for a particular application. The output here is based on building code-accepted design properties and analysis methods. Installation of Boise Cascade engineered wood products must be in accordance with current Installation Guide and applicable building codes. To obtain Installation Guide or ask questions, please call (800)232-0788 before installation.

CITY OF RICHMOND HILL
BUILDING DIVISION

07/20/2021

RECEIVED

Per: jocelyn.aguilar

BC CALC®, BC FRAMER®, AJS™, ALLJOIST®, BC RIM BOARD™, BCI®, BOISE GLULAM™, BC FloorValue®, VERSA-LAM®, VERSA-RIM PLUS®,

**Double 1-3/4" x 11-7/8" VERSA-LAM® 2.0 3100 SP****PASSED****2ND FLR FRAMING\Flush Beams\B11(i561) (Flush Beam)**

Dry | 1 span | No cant.

July 27, 2020 08:56:58

BC CALC® Member Report

Build 0

Job name:

File name: UNIT 2008 EL A,.mmdl

Address:

Description: 2ND FLR FRAMING\Flush Beams\B11(i561)

City, Province, Postal Code: RICHMOND HILL

Specifier:


Customer:

Designer: AJ

Code reports:

CCMC 12472-R

Company:

**Load Summary**

Tag	Description	Load Type	Ref.	Start	End	Loc.	Live	Dead	Snow	Wind	Tributary
0	Self-Weight	Unf. Lin. (lb/ft)	L	00-00-00	16-10-00	Top	1.00	0.65	1.00	1.15	00-00-00
1	J1(i528)	Conc. Pt. (lbs)	L	01-00-08	01-00-08	Top	155	47			n/a
2	J1(i528)	Conc. Pt. (lbs)	L	01-00-08	01-00-08	Top	-60				n/a
3	B9(i553)	Conc. Pt. (lbs)	L	01-09-06	01-09-06	Top	242	136			n/a
4	B9(i553)	Conc. Pt. (lbs)	L	01-09-06	01-09-06	Top	-42				n/a
5	-	Conc. Pt. (lbs)	L	15-07-12	15-07-12	Top	1493	808			n/a
6	-	Conc. Pt. (lbs)	L	15-07-12	15-07-12	Top	-164				n/a

Controls Summary


	Factored Demand	Factored Resistance	Demand/Resistance	Case	Location
Dist. Load	13.28 lb/ft	57645.00 lb/ft	n/a		
Conc. Load	3250 lbs	16813 lbs	19.3%		

CONFORMS TO OBC 2012

AMENDED 2020

Cautions

Concentrated side load(s) 7 are closer than 18" from end of member. Please consult a technical representative or Professional of Record.

Connection Diagram: Full Length of Member

a minimum = 2" c = 7-7/8"
b minimum = 3" d = 24" 12"

Calculated Side Load = 301.0 lb/ft

Connectors are: 16d 1 : Nails

3 1/2" ARDOX SPIRAL

DWG NO. TAM 9165 -21
STRUCTURAL
COMPONENT ONLY

Disclosure

Use of the Boise Cascade Software is subject to the terms of the End User License Agreement (EULA). Completeness and accuracy of input must be reviewed and verified by a qualified engineer or other appropriate expert to assure its adequacy, prior to anyone relying on such output as evidence of suitability for a particular application. The output here is based on building code-accepted design properties and analysis methods. Installation of Boise Cascade engineered wood products must be in accordance with current Installation Guide and applicable building codes. To obtain Installation Guide or ask questions, please call (800)232-0788 before installation.

CITY OF RICHMOND HILL
BUILDING DIVISION

07/20/2021

RECEIVED

Per: jocelyn.aguiar

BC CALC®, BC FRAMER®, AJS™, ALLJOIST®, BC RIM BOARD™, BCI®, BOISE GLULAM™, BC FloorValue®, VERSA-LAM®, VERSA-RIM PLUS®,

BC CALC® Member Report

Build 7493

Job name:

File name: UNIT 2008 EL A,.mmdl

Address:

Description: 2ND FLR FRAMING\Flush Beams\B12(i560)

City, Province, Postal Code: RICHMOND HILL


Specifier:

Customer:

Designer: AJ

Code reports: CCMC 12472-R

Company:



Total Horizontal Product Length = 08-10-10

Reaction Summary (Down / Uplift) (lbs)

Bearing	Live	Dead	Snow	Wind
B1, 3-1/2"	84 / 0	137 / 0	49 / 0	
B2, 5-1/8"	442 / 0	536 / 0	303 / 0	

Load Summary

Tag	Description	Load Type	Ref.	Start	End	Loc.	Live 1.00	Dead 0.65	Snow 1.00	Wind 1.15	Tributary
0	Self-Weight	Unf. Lin. (lb/ft)	L	00-00-00	08-10-10	Top		12			00-00-00
1	E11(i509)	Unf. Lin. (lb/ft)	L	05-10-08	08-10-10	Top	50	126	117		n/a
2	FC2 Floor Material	Unf. Lin. (lb/ft)	L	05-10-08	08-05-08	Top	6	3			n/a
3	FC2 Floor Material	Unf. Lin. (lb/ft)	L	05-10-08	06-04-14	Top	16				n/a
4	J4(i602)	Conc. Pt. (lbs)	L	06-04-14	06-04-14	Top	141	70			n/a
5	J4(i544)	Conc. Pt. (lbs)	L	07-07-14	07-07-14	Top	208	104			n/a

Controls Summary

	Factored Demand	Factored Resistance	Demand/ Resistance	Case	Location
Pos. Moment	1773 ft-lbs	29611 ft-lbs	6.0%	1	06-04-14
End Shear	1018 lbs	14464 lbs	7.0%	1	07-05-10
Total Load Deflection	L/999 (0.014")	n/a	n/a	35	04-10-07
Live Load Deflection	L/999 (0.008")	n/a	n/a	51	04-10-07
Max Defl.	0.014"	n/a	n/a	35	04-10-07
Span / Depth	8.4				

Bearing Supports

	Dim. (LxW)	Demand	Demand/ Resistance Support	Demand/ Resistance Member	Material
B1	Column 3-1/2" x 3-1/2"	346 lbs	3.5%	2.3%	Unspecified
B2	Wall/Plate 5-1/8" x 3-1/2"	1637 lbs	14.8%	7.5%	Spruce-Pine-Fir

Notes

Design meets Code minimum (L/240) Total load deflection criteria.

Design meets Code minimum (L/360) Live load deflection criteria.

Calculations assume unbraced length of Top: 05-10-08, Bottom: 05-10-08.

Resistance Factor phi has been applied to all presented results per CSA O86.

BC CALC® analysis is based on Canadian Limit States Design, as per NBCC 2015 and CSA O86.

Unbalanced snow loads determined from building geometry were used in selected product's verification.

Design based on Dry Service Condition.

Importance Factor : Normal Part code : Part 9


CONFORMS TO OBC 2012

AMENDED 2020

 CITY OF RICHMOND HILL
BUILDING DIVISION

07/20/2021

RECEIVED

 Per: jocelyn.aguilar

 DWG NO. TAM 9166 -21
STRUCTURAL
COMPONENT ONLY



Double 1-3/4" x 11-7/8" VERSA-LAM® 2.0 3100 SP

2ND FLR FRAMING\Flush Beams\B12(i560) (Flush Beam)

Dry | 1 span | No cant.

PASSED

July 27, 2020 08:56:58

BC CALC® Member Report

Build 7493

Job name:

Address:

City, Province, Postal Code: RICHMOND HILL

Customer:

Code reports: CCMC 12472-R

File name: UNIT 2008 EL A,.mmdl


Description: 2ND FLR FRAMING\Flush Beams\B12(i560)

Specifier:

Designer: AJ

Company:

Connection Diagram: Full Length of Member



a minimum = 2"

b minimum = 3"

c = 7-7/8"

d = 22" 8"

Calculated Side Load = 221.0 lb/ft

Connectors are: Nails

3 1/2" ARDOX SPIRAL



OWG NO. 74W 9/66 -21
STRUCTURAL
COMPONENT ONLY

Disclosure

Use of the Boise Cascade Software is subject to the terms of the End User License Agreement (EULA). Completeness and accuracy of input must be reviewed and verified by a qualified engineer or other appropriate expert to assure its adequacy, prior to anyone relying on such output as evidence of suitability for a particular application. The output here is based on building code-accepted design properties and analysis methods. Installation of Boise Cascade engineered wood products must be in accordance with current Installation Guide and applicable building codes. To obtain Installation Guide or ask questions, please call (800)232-0788 before installation.

CITY OF RICHMOND HILL
BUILDING DIVISION

07/20/2021

RECEIVED

Per: jocelyn.aguilar

BC CALC®, BC FRAMER®, AJS™,
ALLJOIST®, BC RIM BOARD™, BCI®,
BOISE GLULAM™, BC FloorValue®,
VERSA-LAM®, VERSA-RIM PLUS®,


BC CALC® Member Report
Build 7493

Dry | 1 span | No cant.

July 27, 2020 08:56:58

Job name:
Address:
City, Province, Postal Code: RICHMOND HILL
Customer:
Code reports: CCMC 12472-R

File name: UNIT 2008 EL A,.mmdl
Description: 2ND FLR FRAMING\Flush Beams\B8(i611)
Specifier:
Designer: AJ
Company:



Reaction Summary (Down / Uplift) (lbs)

Bearing	Live	Dead	Snow	Wind
B1, 4"	1220 / 166	672 / 0		
B2, 4-3/8"	599 / 61	395 / 0		

Load Summary

Tag	Description	Load Type	Ref.	Start	End	Loc.	Live 1.00	Dead 0.65	Snow 1.00	Wind 1.15	Tributary
0	Self-Weight	Unf. Lin. (lb/ft)	L	00-00-00	19-00-06	Top		12			00-00-00
1	FC2 Floor Material	Unf. Lin. (lb/ft)	L	00-00-00	05-02-00	Top	11	6			n/a
2	FC2 Floor Material	Unf. Lin. (lb/ft)	L	05-02-00	19-00-06	Top	23	11			n/a
3	B10(i582)	Conc. Pt. (lbs)	L	05-02-14	05-02-14	Top	1443	650			n/a
4	B10(i582)	Conc. Pt. (lbs)	L	05-02-14	05-02-14	Top	-227				n/a

Controls Summary

	Factored Demand	Factored Resistance	Demand/ Resistance	Case	Location
Pos. Moment	12726 ft-lbs	35392 ft-lbs	36.0%	1	05-02-14
End Shear	2618 lbs	14464 lbs	18.1%	1	01-03-14
Total Load Deflection	L/467 (0.474")	n/a	51.4%	6	08-08-14
Live Load Deflection	L/731 (0.303")	n/a	49.2%	8	08-08-14
Max Defl.	0.474"	n/a	n/a	6	08-08-14
Span / Depth	18.7				

Bearing Supports

	Dim. (LxW)	Demand	Demand/ Resistance Support	Demand/ Resistance Member	Material
B1	Hanger 4" x 3-1/2"	2669 lbs	n/a	15.6%	HGUS410
B2	Wall/Plate 4-3/8" x 3-1/2"	1393 lbs	14.8%	7.5%	Spruce-Pine-Fir

Cautions


Header for the hanger HGUS410 is a Double 1-3/4" x 11-7/8" LVL Beam.
Hanger model HGUS410 and seat length were input by the user. Hanger has not been analyzed for adequate capacity.

Notes

Design meets Code minimum (L/240) Total load deflection criteria.
Design meets Code minimum (L/360) Live load deflection criteria.
Calculations assume member is fully braced.
Hanger Manufacturer: Unassigned
Resistance Factor phi has been applied to all presented results per CSA O86.
BC CALC® analysis is based on Canadian Limit States Design, as per NBCC 2015 and CSA O86.
Design based on Dry Service Condition.
Importance Factor : Normal Part code : Part 9

CONFORMS TO OBC 2012

AMENDED 2020



866 NO. 7AM 9167-21
STRUCTURAL
COMPONENT ONLY

BC CALC® Member Report

Build 7493

Job name:

Address:

City, Province, Postal Code: RICHMOND HILL

Customer:

Code reports: CCMC 12472-R

File name: UNIT 2008 EL A,,mmdl


Description: 2ND FLR FRAMING\Flush Beams\B8(i611)

Specifier:

Designer: AJ

Company:

Connection Diagram: Full Length of Member




a minimum = 2" c = 7-7/8"
b minimum = 3" d = 2-0" @ "

Connectors are: 16d Nails

3 1/2" ARDOX SPIRAL

Connection Diagrams: Concentrated Side Loads


Connection Tag: A Applies to load tag(s): 3+4



a minimum = 2"
b minimum = 4"
c minimum = 4"
d maximum = 12"
e minimum = 4"

Connectors are: 16d Nails

3 1/2" ARDOX SPIRAL



41621
S. KATSOUKAKOS
PROVINCE OF ONTARIO
P64
ENG NO. TAM 9/16 = 21
**STRUCTURAL
COMPONENT ONLY**

Disclosure

Use of the Boise Cascade Software is subject to the terms of the End User License Agreement (EULA). Completeness and accuracy of input must be reviewed and verified by a qualified engineer or other appropriate expert to assure its adequacy, prior to anyone relying on such output as evidence of suitability for a particular application. The output here is based on building code-accepted design properties and analysis methods. Installation of Boise Cascade engineered wood products must be in accordance with current Installation Guide and applicable building codes. To obtain Installation Guide or ask questions, please call (800)232-0788 before installation.

BC CALC®, BC FRAMER®, AJST®, ALLJOIST®, BC RIM BOARD™, BCI®, BOISE GLULAM™, BC FloorValue®, VERSA-LAM®, VERSA-RIM PLUS®,

**CITY OF RICHMOND HILL
BUILDING DIVISION**

07/20/2021

RECEIVED

Per: jocelyn.aguilar

BC CALC® Member Report

Build 7493

Job name:

File name: UNIT 2008 EL A,.mmdl

Address:

Description: 2ND FLR FRAMING\Flush Beams\B9(i553)

City, Province, Postal Code: RICHMOND HILL


Specifier:

Customer:

Designer: AJ

Code reports: CCMC 12472-R

Company:



Total Horizontal Product Length = 08-00-00

Reaction Summary (Down / Uplift) (lbs)

Bearing	Live	Dead	Snow	Wind
B1, 2"	236 / 41	134 / 0		
B2, 5-1/2"	454 / 90	236 / 0		

Load Summary

Tag	Description	Load Type	Ref.	Start	End	Loc.	Live 1.00	Dead 0.65	Snow 1.00	Wind 1.15	Tributary
0	Self-Weight	Unf. Lin. (lb/ft)	L	00-00-00	08-00-00	Top		6			00-00-00
1	FC2 Floor Material	Unf. Lin. (lb/ft)	L	00-00-00	05-02-00	Top	16	8			n/a
2	FC2 Floor Material	Unf. Lin. (lb/ft)	L	05-02-00	07-09-04	Top	27	13			n/a
3	B10(i582)	Conc. Pt. (lbs)	L	05-02-14	05-02-14	Top	537	245			n/a
4	B10(i582)	Conc. Pt. (lbs)	L	05-02-14	05-02-14	Top	-131				n/a

Controls Summary

	Factored Demand	Factored Resistance	Demand/ Resistance	Case	Location
Pos. Moment	2101 ft-lbs	17696 ft-lbs	11.9%	1	05-02-14
End Shear	896 lbs	7232 lbs	12.4%	1	06-06-10
Total Load Deflection	L/999 (0.025")	n/a	n/a	6	04-01-15
Live Load Deflection	L/999 (0.017")	n/a	n/a	8	04-01-15
Max Defl.	0.025"	n/a	n/a	6	04-01-15
Span / Depth	7.6				



OWG NO. TAM 9168-21
STRUCTURAL
COMPONENT ONLY

Bearing Supports	Dim. (LxW)	Demand	Demand/ Resistance Support	Demand/ Resistance Member	Material
B1 Hanger	2" x 1-3/4"	521 lbs	n/a	12.2%	HUS1.81/10
B2 Wall/Plate	5-1/2" x 1-3/4"	976 lbs	16.5%	8.3%	Spruce-Pine-Fir

Cautions

Header for the hanger HUS1.81/10 is a Double 1-3/4" x 11-7/8" LVL Beam.

Hanger model HUS1.81/10 and seat length were input by the user. Hanger has not been analyzed for adequate capacity.

Notes

Design meets Code minimum (L/240) Total load deflection criteria.

Design meets Code minimum (L/360) Live load deflection criteria.

Calculations assume member is fully braced.

Hanger Manufacturer: Unassigned

Resistance Factor phi has been applied to all presented results per CSA O86.

BC CALC® analysis is based on Canadian Limit States Design, as per NBCC 2015 and CSA O86.

Design based on Dry Service Condition.

Importance Factor : Normal Part code : Part 9

CONFORMS TO OBC 2012

AMENDED 2020

RICHMOND HILL
BUILDING DIVISION

07/20/2021

RECEIVED

Per: jocelyn.aguilar

Disclosure

Use of the Boise Cascade Software is subject to the terms of the End User License Agreement (EULA). Completeness and accuracy of input must be reviewed and verified by a qualified engineer or other appropriate expert to assure its adequacy, prior to anyone relying on such output as evidence of suitability for a particular application. The output here is based on building code-accepted design properties and analysis methods. Installation of Boise Cascade engineered wood products must be in accordance with current Installation Guide and applicable building codes. To obtain Installation Guide or ask questions, please call (800)232-0788 before installation.

BC CALC®, BC FRAMER®, AJS™, ALLJOIST®, BC RIM BOARD™, BCI®, BOISE GLULAM™, BC FloorValue®, VERSA-LAM®, VERSA-RIM PLUS®,

BC CALC® Member Report

Dry | 1 span | No cant.

July 27, 2020 08:56:58

Build 7493

Job name:

File name: UNIT 2008 EL A,.mmdl

Address:

Description: 1ST FLR FRAMING\Flush Beams\B1(i537) (Flush Beam)

City, Province, Postal Code: RICHMOND HILL


Specifier:

Customer:

Designer: AJ

Code reports: CCMC 12472-R

Company:



Total Horizontal Product Length = 19-04-12

Reaction Summary (Down / Uplift) (lbs)

Bearing	Live	Dead	Snow	Wind
B1, 2-3/8"	738 / 0	501 / 0		
B2, 2-3/8"	470 / 0	360 / 0		

Load Summary

Tag	Description	Load Type	Ref.	Start	End	Loc.	Live 1.00	Dead 0.65	Snow 1.00	Wind 1.15	Tributary
0	Self-Weight	Unf. Lin. (lb/ft)	L	00-00-00	19-04-12	Top		12			00-00-00
1	FC1 Floor Material	Unf. Lin. (lb/ft)	L	00-00-00	19-04-12	Top	10	5			n/a
2	FC1 Floor Material	Unf. Lin. (lb/ft)	L	00-00-00	04-00-06	Top	6	3			n/a
3	FC1 Floor Material	Unf. Lin. (lb/ft)	L	04-00-06	09-06-06	Top	24	12			n/a
4	FC1 Floor Material	Unf. Lin. (lb/ft)	L	09-06-06	19-04-12	Top	6	3			n/a
5	B7(i660)	Conc. Pt. (lbs)	L	04-01-04	04-01-04	Top	389	206			n/a
6	B2(i632)	Conc. Pt. (lbs)	L	09-05-08	09-05-08	Top	421	223			n/a

Controls Summary

	Factored Demand	Factored Resistance	Demand/Resistance	Case	Location
Pos. Moment	8958 ft-lbs	35392 ft-lbs	25.3%	1	09-05-08
End Shear	1676 lbs	14464 lbs	11.6%	1	01-02-04
Total Load Deflection	L/578 (0.397")	n/a	41.5%	4	09-03-08
Live Load Deflection	L/969 (0.237")	n/a	37.1%	5	09-03-08
Max Defl.	0.397"	n/a	n/a	4	09-03-08
Span / Depth	19.3				

Bearing Supports

	Dim. (LxW)	Demand	Demand/Resistance Support	Demand/Resistance Member	Material
B1	Wall/Plate 2-3/8" x 3-1/2"	1733 lbs	33.9%	17.1%	Spruce-Pine-Fir
B2	Wall/Plate 2-3/8" x 3-1/2"	1155 lbs	22.6%	11.4%	Spruce-Pine-Fir

Notes

Design meets Code minimum (L/240) Total load deflection criteria.

Design meets Code minimum (L/360) Live load deflection criteria.

Calculations assume member is fully braced.

Resistance Factor phi has been applied to all presented results per CSA O86.

BC CALC® analysis is based on Canadian Limit States Design, as per NBCC 2015 and CSA O86.

Design based on Dry Service Condition.

Importance Factor : Normal Part code : Part 9

CONFORMS TO OBC 2012


AMENDED 2020

CITY OF RICHMOND HILL
BUILDING DIVISION

07/20/2021

RECEIVED

Per: jocelyn.aguilar





Double 1-3/4" x 11-7/8" VERSA-LAM® 2.0 3100 SP

PASSED

1ST FLR FRAMING\Flush Beams\B1(i537) (Flush Beam)

Dry | 1 span | No cant.

July 27, 2020 08:56:58

BC CALC® Member Report

Build 7493

Job name:

Address:

City, Province, Postal Code: RICHMOND HILL

Customer:

Code reports: CCMC 12472-R

File name: UNIT 2008 EL A,.mmdl


Description: 1ST FLR FRAMING\Flush Beams\B1(i537)

Specifier:

Designer: AJ

Company:

Connection Diagram: Full Length of Member



a minimum = 2"
b minimum = 3"

c = 7-7/8"
d = 12 8"

Calculated Side Load = 455.1 lb/ft

Connectors are: 1 Nails

3 1/2" ARDOX SPIRAL



DWG NO. TAM 9169-21
STRUCTURAL
COMPONENT ONLY

Disclosure

Use of the Boise Cascade Software is subject to the terms of the End User License Agreement (EULA). Completeness and accuracy of input must be reviewed and verified by a qualified engineer or other appropriate expert to assure its adequacy, prior to anyone relying on such output as evidence of suitability for a particular application. The output here is based on building code-accepted design properties and analysis methods. Installation of Boise Cascade engineered wood products must be in accordance with current Installation Guide and applicable building codes. To obtain Installation Guide or ask questions, please call (800)232-0788 before installation.

BC CALC®, BC FRAMER®, AJS™, ALLJOIST®, BC RIM BOARD™, BCi®, BOISE GLULAM™, BC FloorValue®, VERSA-LAM®, VERSA-RIM PLUS®,

CITY OF RICHMOND HILL
BUILDING DIVISION

07/20/2021

RECEIVED

Per: jocelyn.aguilar

BC CALC® Member Report

Build 7493

Job name:

File name: UNIT 2008 EL A,.mmdl

Address:

Description: 1ST FLR FRAMING\Flush Beams\B2(i632)

City, Province, Postal Code: RICHMOND HILL


Specifier:

Customer:

Designer: AJ

Code reports: CCMC 12472-R

Company:



Reaction Summary (Down / Uplift) (lbs)

Bearing	Live	Dead	Snow	Wind
B1, 4-3/8"	525 / 0	293 / 0		
B2, 2"	431 / 0	228 / 0		

Load Summary

Tag	Description	Load Type	Ref.	Start	End	Loc.	Live 1.00	Dead 0.65	Snow 1.00	Wind 1.15	Tributary
0	Self-Weight	Unf. Lin. (lb/ft)	L	00-00-00	04-04-14	Top		6			00-00-00
1	STAIR	Unf. Lin. (lb/ft)	L	00-00-10	04-04-14	Top	120	60			n/a
2	-	Conc. Pt. (lbs)	L	00-07-02	00-07-02	Top	148	91			n/a
3	J3(i185)	Conc. Pt. (lbs)	L	02-00-06	02-00-06	Top	147	73			n/a
4	J3(i661)	Conc. Pt. (lbs)	L	03-04-06	03-04-06	Top	139	69			n/a

Controls Summary

	Factored Demand	Factored Resistance	Demand/Resistance	Case	Location
Pos. Moment	982 ft-lbs	17696 ft-lbs	5.5%	1	02-00-06
End Shear	593 lbs	7232 lbs	8.2%	1	03-03-00
Total Load Deflection	L/999 (0.004")	n/a	n/a	4	02-03-09
Live Load Deflection	L/999 (0.003")	n/a	n/a	5	02-03-09
Max Defl.	0.004"	n/a	n/a	4	02-03-09
Span / Depth	4.0				

Bearing Supports	Dim. (LxW)	Demand	Demand/Resistance Support	Demand/Resistance Member	Material
B1 Wall/Plate	4-3/8" x 1-3/4"	1155 lbs	24.5%	12.4%	Spruce-Pine-Fir
B2 Hanger	2" x 1-3/4"	931 lbs	n/a	21.8%	HUS1.81/10

Cautions

Header for the hanger HUS1.81/10 is a Triple 1-3/4" x 11-7/8" LVL Beam.
Hanger model HUS1.81/10 and seat length were input by the user. Hanger has not been analyzed for adequate capacity.

Notes

Design meets Code minimum (L/240) Total load deflection criteria.
Design meets Code minimum (L/360) Live load deflection criteria.
Calculations assume unbraced length of Top: 00-00-00, Bottom: 00-00-00.
Hanger Manufacturer: Unassigned
Resistance Factor phi has been applied to all presented results per CSA O86.
BC CALC® analysis is based on Canadian Limit States Design, as per NBCC 2015 and CSA O86.
Design based on Dry Service Condition.
Importance Factor : Normal Part code : Part 9

CONFORMS TO CBC 2012


AMENDED 2020

CITY OF RICHMOND HILL
BUILDING DIVISION

07/20/2021

RECEIVED

Per: jocelyn.aguilar



STRUCTURAL
COMPONENT ONLY

Disclosure

Use of the Boise Cascade Software is subject to the terms of the End User License Agreement (EULA).
Completeness and accuracy of input must be reviewed and verified by a qualified engineer or other appropriate expert to assure its adequacy, prior to anyone relying on such output as evidence of suitability for a particular application. The output here is based on building code-accepted design properties and analysis methods.
Installation of Boise Cascade engineered wood products must be in accordance with current Installation Guide and applicable building codes. To obtain Installation Guide or ask questions, please call (800)232-0788 before installation.

BC CALC®, BC FRAMER®, AJST™, ALLJOIST®, BC RIM BOARD™, BCI®, BOISE GLULAM™, BC FloorValue®, VERSA-LAM®, VERSA-RIM PLUS®,

BC CALC® Member Report

Build 7493

Job name:

File name: UNIT 2008 EL A,.mmdl

Address:

Description: 1ST FLR FRAMING\Flush Beams\B3(i599)

City, Province, Postal Code: RICHMOND HILL


Specifier:

Customer:

Designer: AJ

Code reports: CCMC 12472-R

Company:



Total Horizontal Product Length = 08-03-04

Reaction Summary (Down / Uplift) (lbs)

Bearing	Live	Dead	Snow	Wind
B1, 2-3/8"	194 / 0	121 / 0		
B2, 4-3/8"	722 / 0	386 / 0		

Load Summary

Tag	Description	Load Type	Ref.	Start	End	Loc.	Live	Dead	Snow	Wind	Tributary
0	Self-Weight	Unf. Lin. (lb/ft)	L	00-00-00	08-03-04	Top	1.00	0.65	1.00	1.15	00-00-00
1	FC1 Floor Material	Unf. Lin. (lb/ft)	L	00-00-00	08-03-04	Top	9	5			n/a
2	STAIR	Unf. Lin. (lb/ft)	L	04-09-04	08-03-04	Top	240	120			n/a

Controls Summary

	Factored Demand	Factored Resistance	Demand/Resistance	Case	Location
Pos. Moment	1834 ft-lbs	17696 ft-lbs	10.4%	1	05-04-08
End Shear	839 lbs	7232 lbs	11.6%	1	06-11-00
Total Load Deflection	L/999 (0.026")	n/a	n/a	4	04-05-03
Live Load Deflection	L/999 (0.017")	n/a	n/a	5	04-05-03
Max Defl.	0.026"	n/a	n/a	4	04-05-03
Span / Depth	7.9				

Bearing Supports

	Dim. (LxW)	Demand	Demand/Resistance Support	Demand/Resistance Member	Material
B1	Wall/Plate 2-3/8" x 1-3/4"	442 lbs	17.3%	8.7%	Spruce-Pine-Fir
B2	Wall/Plate 4-3/8" x 1-3/4"	1566 lbs	33.2%	16.8%	Spruce-Pine-Fir

Notes

Design meets Code minimum (L/240) Total load deflection criteria.

Design meets Code minimum (L/360) Live load deflection criteria.

Calculations assume member is fully braced.

Resistance Factor phi has been applied to all presented results per CSA O86.

BC CALC® analysis is based on Canadian Limit States Design, as per NBCC 2015 and CSA O86.

Design based on Dry Service Condition.

Importance Factor : Normal Part code : Part 9

CONFORMS TO OBC 2012

AMENDED 2020



ENG NO. TAM 9171 -21
STRUCTURAL
COMPONENT ONLY

Disclosure

Use of the Boise Cascade Software is subject to the terms of the End User License Agreement (EULA). Completeness and accuracy of input must be reviewed and verified by a qualified engineer or other appropriate expert to assure its adequacy, prior to anyone relying on such output as evidence of suitability for a particular application. The output here is based on building code-accepted design properties and analysis methods. Installation of Boise Cascade engineered wood products must be in accordance with current Installation Guide and applicable building codes. To obtain Installation Guide or ask questions, please call (800)232-0788 before installation.

BC CALC®, BC FRAMER®, AJS™, ALLJOIST®, BC RIM BOARD™, BCI®, BOISE GLULAM™, BC FloorValue®, VERSA-LAM®, VERSA-RIM PLUS®,

CITY OF RICHMOND HILL
BUILDING DIVISION

07/20/2021

RECEIVED

Per: jocelyn.aguiar



Single 1-3/4" x 11-7/8" VERSA-LAM® 2.0 3100 SP

PASSED

1ST FLR FRAMING\Flush Beams\B4(i615) (Flush Beam)

Dry | 1 span | No cant.

July 27, 2020 08:56:58

BC CALC® Member Report

Build 7493

Job name:

Address:

City, Province, Postal Code: RICHMOND HILL

Customer:

Code reports: CCMC 12472-R


File name: UNIT 2008 EL A,.mmdl

Description: 1ST FLR FRAMING\Flush Beams\B4(i615)

Specifier:

Designer: AJ

Company:



Total Horizontal Product Length = 08-03-04

Reaction Summary (Down / Uplift) (lbs)

Bearing	Live	Dead	Snow	Wind
B1, 2-3/8"	960 / 0	520 / 0		
B2, 4-3/8"	500 / 0	289 / 0		

Load Summary

Tag	Description	Load Type	Ref.	Start	End	Loc.	Live 1.00	Dead 0.65	Snow 1.00	Wind 1.15	Tributary
0	Self-Weight	Unf. Lin. (lb/ft)	L	00-00-00	08-03-04	Top		6			00-00-00
1	FC1 Floor Material	Unf. Lin. (lb/ft)	L	00-00-00	08-03-04	Top	16	8			n/a
2	STAIR	Unf. Lin. (lb/ft)	L	00-02-06	03-09-14	Top	240	120			n/a
3	FC1 Floor Material	Unf. Lin. (lb/ft)	L	03-08-10	08-03-04	Top	11	5			n/a
4	B5(i610)	Conc. Pt. (lbs)	L	03-09-08	03-09-08	Top	398	229			n/a

Controls Summary

	Factored Demand	Factored Resistance	Demand/ Resistance	Case	Location
Pos. Moment	4005 ft-lbs	17696 ft-lbs	22.6%	1	03-09-08
End Shear	1528 lbs	7232 lbs	21.1%	1	01-02-04
Total Load Deflection	L/999 (0.058")	n/a	n/a	4	03-09-14
Live Load Deflection	L/999 (0.037")	n/a	n/a	5	03-09-14
Max Defl.	0.058"	n/a	n/a	4	03-09-14
Span / Depth	7.9				

			Demand/ Resistance Support	Demand/ Resistance Member	
Bearing Supports	Dim. (LxW)	Demand			Material
B1	Wall/Plate	2-3/8" x 1-3/4"	2090 lbs	81.7%	41.2%
B2	Wall/Plate	4-3/8" x 1-3/4"	1112 lbs	23.6%	11.9%
					Spruce-Pine-Fir

Notes

Design meets Code minimum (L/240) Total load deflection criteria.

Design meets Code minimum (L/360) Live load deflection criteria.

Calculations assume member is fully braced.

Resistance Factor phi has been applied to all presented results per CSA O86. AMENDED 2020

BC CALC® analysis is based on Canadian Limit States Design, as per NBCC 2015 and CSA O86.

Design based on Dry Service Condition.

Importance Factor : Normal Part code : Part 9

CONFORMS TO OBC 2012



OWG NO. YAM 9172-21

STRUCTURAL

COMPONENT ONLY

Disclosure

Use of the Boise Cascade Software is subject to the terms of the End User License Agreement (EULA).

Completeness and accuracy of input must be reviewed and verified by a qualified engineer or other appropriate expert to assure its adequacy, prior to anyone relying on such output as evidence of suitability for a particular application. The output here is based on building code-accepted design properties and analysis methods. Installation of Boise Cascade engineered wood products must be in accordance with current Installation Guide and applicable building codes. To obtain Installation Guide or ask questions, please call (800)232-0788 before installation.

BC CALC®, BC FRAMER®, AJST™, ALLJOIST®, BC RIM BOARD™, BCI®, BOISE GLULAM™, BC FloorValue®, VERSA-LAM®, VERSA-RIM PLUS®,

CITY OF RICHMOND HILL
BUILDING DIVISION

07/20/2021

RECEIVED

Per: jocelyn.aguilar

BC CALC® Member Report

Build 7493

Job name:

Address:

City, Province, Postal Code: RICHMOND HILL

Customer:

Code reports: CCMC 12472-R


File name: UNIT 2008 EL A,.mmdl

Description: 1ST FLR FRAMING\Flush Beams\B5(i610)

Specifier:

Designer: AJ

Company:



B1

Total Horizontal Product Length = 09-07-12

B2

Reaction Summary (Down / Uplift) (lbs)

Bearing	Live	Dead	Snow	Wind
B1, 2"	402 / 0	231 / 0		
B2, 3-1/2"	383 / 0	222 / 0		

Load Summary

Tag	Description	Load Type	Ref.	Start	End	Loc.	Live 1.00	Dead 0.65	Snow 1.00	Wind 1.15	Tributary
0	Self-Weight	Unf. Lin. (lb/ft)	L	00-00-00	09-07-12	Top	6				00-00-00
1	Smoothed Load	Unf. Lin. (lb/ft)	L	01-01-08	07-09-08	Top	88	44			n/a
2	FC1 Floor Material	Unf. Lin. (lb/ft)	L	08-05-08	09-07-12	Top	12	6			n/a
3	J3(i555)	Conc. Pt. (lbs)	L	00-05-08	00-05-08	Top	82	41			n/a
4	J3(i613)	Conc. Pt. (lbs)	L	08-05-08	08-05-08	Top	103	51			n/a

Controls Summary

	Factored Demand	Factored Resistance	Demand/Resistance	Case	Location
Pos. Moment	2110 ft-lbs	17696 ft-lbs	11.9%	1	04-05-08
End Shear	814 lbs	7232 lbs	11.3%	1	08-04-06
Total Load Deflection	L/999 (0.047")	n/a	n/a	4	04-09-08
Live Load Deflection	L/999 (0.03")	n/a	n/a	5	04-09-08
Max Defl.	0.047"	n/a	n/a	4	04-09-08
Span / Depth	9.4				

Bearing Supports

	Dim. (LxW)	Demand	Demand/Resistance Support	Demand/Resistance Member	Material
B1	Hanger 2" x 1-3/4"	891 lbs	n/a	20.9%	HUS1.81/10
B2	Column 3-1/2" x 1-3/4"	852 lbs	17.1%	11.4%	Unspecified

Cautions

Header for the hanger HUS1.81/10 is a Single 1-3/4" x 11-7/8" LVL Beam.
Hanger model HUS1.81/10 and seat length were input by the user. Hanger has not been analyzed for adequate capacity.

Notes

Design meets Code minimum (L/240) Total load deflection criteria.
Design meets Code minimum (L/360) Live load deflection criteria.
Calculations assume member is fully braced.
Hanger Manufacturer: Unassigned
Resistance Factor phi has been applied to all presented results per CSA O86.
BC CALC® analysis is based on Canadian Limit States Design, as per NBCC 2015 and CSA O86.
Design based on Dry Service Condition.
Importance Factor : Normal Part code : Part 9

CONFORMS TO OBC 2012


AMENDED 2020

CITY OF RICHMOND HILL
BUILDING DIVISION

07/20/2021

RECEIVED

Per: jocelyn.aguilar



SWG NO. TAM 9173 -21
STRUCTURAL
COMPONENT ONLY

Disclosure

Use of the Boise Cascade Software is subject to the terms of the End User License Agreement (EULA).
Completeness and accuracy of input must be reviewed and verified by a qualified engineer or other appropriate expert to assure its adequacy, prior to anyone relying on such output as evidence of suitability for a particular application. The output here is based on building code-accepted design properties and analysis methods.
Installation of Boise Cascade engineered wood products must be in accordance with current Installation Guide and applicable building codes. To obtain Installation Guide or ask questions, please call (800)232-0788 before installation.

BC CALC®, BC FRAMER®, AJSTM®, ALLJOIST®, BC RIM BOARD™, BC1®, BOISE GLULAM™, BC FloorValue®, VERSA-LAM®, VERSA-RIM PLUS®,

BC CALC® Member Report

Build 7493

Job name:

File name: UNIT 2008 EL A,.mmdl

Address:

Description: 1ST FLR FRAMING\Flush Beams\B6(i659)

City, Province, Postal Code: RICHMOND HILL

Specifier:


Customer:

Designer: AJ

Code reports:

CCMC 12472-R

Company:



Total Horizontal Product Length = 05-06-04

Reaction Summary (Down / Uplift) (lbs)

Bearing	Live	Dead	Snow	Wind
B1, 1-3/4"	499 / 0	278 / 0		
B2, 2"	77 / 0	55 / 0		

Load Summary

Tag	Description	Load Type	Ref.	Start	End	Loc.	Live 1.00	Dead 0.65	Snow 1.00	Wind 1.15	Tributary
0	Self-Weight	Unf. Lin. (lb/ft)	L	00-00-00	05-06-04	Top		6			00-00-00
1	FC1 Floor Material	Unf. Lin. (lb/ft)	L	00-02-00	05-06-04	Top	4	2			n/a
2	FC1 Floor Material	Unf. Lin. (lb/ft)	L	00-02-00	04-06-00	Top	22	11			n/a
3	FC1 Floor Material	Unf. Lin. (lb/ft)	L	04-06-00	05-06-04	Top	11	6			n/a
4	B7(i660)	Conc. Pt. (lbs)	L	00-02-14	00-02-14	Top	444	234			n/a

Controls Summary

	Factored Demand	Factored Resistance	Demand/ Resistance	Case	Location
Pos. Moment	306 ft-lbs	17696 ft-lbs	1.7%	1	02-03-09
End Shear	219 lbs	7232 lbs	3.0%	1	01-01-10
Total Load Deflection	L/999 (0.002")	n/a	n/a	4	02-07-13
Live Load Deflection	L/999 (0.001")	n/a	n/a	5	02-07-03
Max Defl.	0.002"	n/a	n/a	4	02-07-13
Span / Depth	5.4				

Bearing Supports

	Dim. (LxW)	Demand	Demand/ Resistance Support	Demand/ Resistance Member	Material
B1 Column	1-3/4" x 1-3/4"	1096 lbs	44.1%	29.3%	Unspecified
B2 Hanger	2" x 1-3/4"	184 lbs	n/a	4.3%	HUS1.81/10

Cautions

Header for the hanger HUS1.81/10 is a Single 1-3/4" x 11-7/8" LVL Beam.
Hanger model HUS1.81/10 and seat length were input by the user. Hanger has not been analyzed for adequate capacity.

Notes

Design meets Code minimum (L/240) Total load deflection criteria.
Design meets Code minimum (L/360) Live load deflection criteria.
Calculations assume unbraced length of Top: 00-00-00, Bottom: 00-00-00.
Hanger Manufacturer: Unassigned
Resistance Factor phi has been applied to all presented results per CSA O86.
BC CALC® analysis is based on Canadian Limit States Design, as per NBCC 2015 and CSA O86.
Design based on Dry Service Condition.
Importance Factor : Normal Part code : Part 9



OWG NO. YAM 9174-21

STRUCTURAL

COMPONENT ONLY

Disclosure

Use of the Boise Cascade Software is subject to the terms of the End User License Agreement (EULA).
Completeness and accuracy of input must be reviewed and verified by a qualified engineer or other appropriate expert to assure its adequacy, prior to anyone relying on such output as evidence of suitability for a particular application. The output here is based on building code-accepted design properties and analysis methods.
Installation of Boise Cascade engineered wood products must be in accordance with current Installation Guide and applicable building codes. To obtain Installation Guide or ask questions, please call (800)232-0788 before installation.

BC CALC®, BC FRAMER®, AJSTM®, ALLJOIST®, BC RIM BOARD™, BCI®, BOISE GLULAM™, BC FloorValue®, VERSA-LAM®, VERSA-RIM PLUS®,

CONFORMS TO OBC 2012

AMENDED 2020

CITY OF RICHMOND HILL
BUILDING DIVISION

07/20/2021

RECEIVED

Per: iocelvn.aquilar

BC CALC® Member Report

Build 7493

Job name:

File name: UNIT 2008 EL A,.mmdl

Address:

Description: 1ST FLR FRAMING\Flush Beams\B7(i660)

City, Province, Postal Code: RICHMOND HILL


Specifier:

Customer:

Designer: AJ

Code reports: CCMC 12472-R

Company:



B1

Total Horizontal Product Length = 03-10-04

B2

Reaction Summary (Down / Uplift) (lbs)

Bearing	Live	Dead	Snow	Wind
B1, 2"	444 / 0	233 / 0		
B2, 2"	390 / 0	206 / 0		

Load Summary

Tag	Description	Load Type	Ref.	Start	End	Loc.	Live 1.00	Dead 0.65	Snow 1.00	Wind 1.15	Tributary
0	Self-Weight	Unf. Lin. (lb/ft)	L	00-00-00	03-10-04	Top		6			00-00-00
1	STAIR	Unf. Lin. (lb/ft)	L	00-00-00	03-10-04	Top	120	60			n/a
2	J3(i187)	Conc. Pt. (lbs)	L	00-01-12	00-01-12	Top	85	43			n/a
3	J3(i185)	Conc. Pt. (lbs)	L	01-05-12	01-05-12	Top	147	73			n/a
4	J3(i661)	Conc. Pt. (lbs)	L	02-09-12	02-09-12	Top	139	69			n/a

Controls Summary

	Factored Demand	Factored Resistance	Demand/Resistance	Case	Location
Pos. Moment	792 ft-lbs	17696 ft-lbs	4.5%	1	01-09-07
End Shear	505 lbs	7232 lbs	7.0%	1	02-08-06
Total Load Deflection	L/999 (0.003")	n/a	n/a	4	01-11-04
Live Load Deflection	L/999 (0.002")	n/a	n/a	5	01-11-04
Max Defl.	0.003"	n/a	n/a	4	01-11-04
Span / Depth	3.7				


Bearing Supports	Dim. (LxW)	Demand	Demand/Resistance Support	Demand/Resistance Member	Material
B1 Hanger	2" x 1-3/4"	957 lbs	n/a	22.4%	HUS1.81/10
B2 Hanger	2" x 1-3/4"	842 lbs	n/a	19.7%	HUS1.81/10

Cautions

Header for the hanger HUS1.81/10 is a Single 1-3/4" x 11-7/8" LVL Beam.
Hanger model HUS1.81/10 and seat length were input by the user. Hanger has not been analyzed for adequate capacity.
Header for the hanger HUS1.81/10 is a Triple 1-3/4" x 11-7/8" LVL Beam.

Notes

Design meets Code minimum (L/240) Total load deflection criteria.
Design meets Code minimum (L/360) Live load deflection criteria.
Calculations assume member is fully braced.
Hanger Manufacturer: Unassigned
Resistance Factor phi has been applied to all presented results per CSA O86.
BC CALC® analysis is based on Canadian Limit States Design, as per NBCC 2015 and CSA O86.
Design based on Dry Service Condition.
Importance Factor : Normal Part code : Part 9



STRUCTURAL COMPONENT ONLY

Disclosure

Use of the Boise Cascade Software is subject to the terms of the End User License Agreement (EULA). Completeness and accuracy of input must be reviewed and verified by a qualified engineer or other appropriate expert to assure its adequacy, prior to anyone relying on such output as evidence of suitability for a particular application. The output here is based on building code-accepted design properties and analysis methods. Installation of Boise Cascade engineered wood products must be in accordance with current Installation Guide and applicable building codes. To obtain Installation Guide or ask questions, please call (800)232-0788 before installation.

CONFORMS TO OBC 2012

AMENDED 2020



CITY OF RICHMOND HILL
BUILDING DIVISION

07/20/2021

RECEIVED

Per: jocelyn.aguiar

BC CALC®, BC FRAMER®, AJST™, ALLJOIST®, BC RIM BOARD™, BCI®, BOISE GLULAM™, BC FloorValue®, VERSA-LAM®, VERSA-RIM PLUS®,



Maximum Floor Spans

Live Load = 40 psf, Dead Load = 15 psf



Simple Spans, L/480 Deflection Limit

5/8" OSB G&N Sheathing

Depth	Series	Bare				1/2" Gypsum Ceiling			
		On Centre Spacing				On Centre Spacing			
		12"	16"	19.2"	24"	12"	16"	19.2"	24"
9-1/2"	NI-20	15'-1"	14'-2"	13'-9"	N/A	15'-7"	14'-8"	14'-2"	N/A
	NI-40x	16'-1"	15'-2"	14'-8"	N/A	16'-7"	15'-7"	15'-1"	N/A
	NI-60	16'-3"	15'-4"	14'-10"	N/A	16'-8"	15'-9"	15'-3"	N/A
	NI-70	17'-1"	16'-1"	15'-6"	N/A	17'-5"	16'-5"	15'-10"	N/A
	NI-80	17'-3"	16'-3"	15'-8"	N/A	17'-8"	16'-7"	16'-0"	N/A
11-7/8"	NI-20	16'-11"	16'-0"	15'-5"	N/A	17'-6"	16'-6"	16'-0"	N/A
	NI-40x	18'-1"	17'-0"	16'-5"	N/A	18'-9"	17'-6"	16'-11"	N/A
	NI-60	18'-4"	17'-3"	16'-7"	N/A	19'-0"	17'-8"	17'-1"	N/A
	NI-70	19'-6"	18'-0"	17'-4"	N/A	20'-1"	18'-7"	17'-9"	N/A
	NI-80	19'-9"	18'-3"	17'-6"	N/A	20'-4"	18'-10"	17'-11"	N/A
14"	NI-90x	20'-4"	18'-9"	17'-11"	N/A	20'-10"	19'-3"	18'-5"	N/A
	NI-40x	20'-1"	18'-7"	17'-10"	N/A	20'-10"	19'-4"	18'-6"	N/A
	NI-60	20'-5"	18'-11"	18'-1"	N/A	21'-2"	19'-7"	18'-9"	N/A
	NI-70	21'-7"	20'-0"	19'-1"	N/A	22'-3"	20'-7"	19'-8"	N/A
	NI-80	21'-11"	20'-3"	19'-4"	N/A	22'-7"	20'-11"	20'-0"	N/A
16"	NI-90x	22'-7"	20'-11"	19'-11"	N/A	23'-3"	21'-6"	20'-6"	N/A
	NI-60	22'-3"	20'-8"	19'-9"	N/A	23'-1"	21'-5"	20'-6"	N/A
	NI-70	23'-6"	21'-9"	20'-9"	N/A	24'-3"	22'-5"	21'-5"	N/A
	NI-80	23'-11"	22'-1"	21'-1"	N/A	24'-8"	22'-10"	21'-9"	N/A
	NI-90x	24'-8"	22'-9"	21'-9"	N/A	25'-4"	23'-5"	22'-4"	N/A

Depth	Series	Mid-Span Blocking				Mid-Span Blocking and 1/2" Gypsum Ceiling			
		On Centre Spacing				On Centre Spacing			
		12"	16"	19.2"	24"	12"	16"	19.2"	24"
9-1/2"	NI-20	16'-8"	15'-3"	14'-5"	N/A	16'-8"	15'-3"	14'-5"	N/A
	NI-40x	17'-11"	16'-11"	16'-1"	N/A	18'-5"	17'-1"	16'-1"	N/A
	NI-60	18'-2"	17'-1"	16'-4"	N/A	18'-7"	17'-4"	16'-4"	N/A
	NI-70	19'-2"	17'-10"	17'-2"	N/A	19'-7"	18'-3"	17'-7"	N/A
	NI-80	19'-5"	18'-0"	17'-4"	N/A	19'-10"	18'-5"	17'-8"	N/A
11-7/8"	NI-20	19'-6"	18'-1"	17'-3"	N/A	19'-11"	18'-3"	17'-3"	N/A
	NI-40x	21'-0"	19'-6"	18'-8"	N/A	21'-7"	20'-2"	19'-2"	N/A
	NI-60	21'-4"	19'-9"	18'-11"	N/A	21'-11"	20'-4"	19'-6"	N/A
	NI-70	22'-6"	20'-10"	19'-11"	N/A	23'-0"	21'-5"	20'-5"	N/A
	NI-80	22'-9"	21'-1"	20'-1"	N/A	23'-3"	21'-7"	20'-8"	N/A
14"	NI-90x	23'-4"	21'-8"	20'-8"	N/A	23'-10"	22'-2"	21'-2"	N/A
	NI-40x	23'-7"	21'-11"	20'-11"	N/A	24'-3"	22'-7"	21'-7"	N/A
	NI-60	24'-0"	22'-3"	21'-3"	N/A	24'-8"	22'-11"	21'-11"	N/A
	NI-70	25'-3"	23'-4"	22'-3"	N/A	25'-10"	24'-0"	22'-11"	N/A
	NI-80	25'-7"	23'-8"	22'-7"	N/A	26'-2"	24'-4"	23'-2"	N/A
16"	NI-90x	26'-4"	24'-4"	23'-3"	N/A	26'-10"	24'-11"	23'-9"	N/A
	NI-60	26'-5"	24'-6"	23'-4"	N/A	27'-2"	25'-3"	24'-2"	N/A
	NI-70	27'-9"	25'-8"	24'-6"	N/A	28'-5"	26'-5"	25'-2"	N/A
	NI-80	28'-2"	26'-1"	24'-10"	N/A	28'-10"	26'-9"	25'-6"	N/A
	NI-90x	29'-0"	26'-10"	25'-7"	N/A	29'-7"	27'-5"	26'-2"	N/A

- Maximum clear span applicable to simple-span residential floor construction with a design live load of 40 psf and dead load of 15 psf. The ultimate limit states are based on the factored loads of 1.50L + 1.25D. The serviceability limit states include the consideration for floor vibration, a live load deflection limit of L/480 and a total load deflection limit of L/240.
- Spans are based on a composite floor with glued-nailed oriented strand board (OSB) sheathing with a minimum thickness of 5/8 inch for a joist spacing of 19.2 inches or less. The composite floor may include 1/2 inch gypsum ceiling and/or one row of blocking at mid-span with strapping. Strapping shall be minimum 1x4 inch strap applied to underside of joists at blocking line or 1/2 inch gypsum ceiling attached to joists.
- Minimum bearing length shall be 1-3/4 inches for the end bearings.
- Bearing stiffeners are not required when I-joists are used with the spans and spacings given in this table, except as required for hangers.
- This span chart is based on uniform loads. For applications with other than uniformly distributed loads, an engineering analysis may be required based on the use of the design properties. Tables are based on Limit States Design per CSA O86-09, NBC 2010, and OBC 2012.
- Joists shall be laterally supported at supports and continuously along the compression edge. Refer to technical documentation for installation guidelines and construction details. Nordic I-joists are listed in CCMC evaluation report 13032-R and APA Product Report PR-L274C.






Maximum Floor Spans

Live Load = 40 psf, Dead Load = 15 psf
Simple Spans, L/480 Deflection Limit
3/4" OSB G&N Sheathing

Depth	Series	Bare				1/2" Gypsum Ceiling			
		On Centre Spacing				On Centre Spacing			
		12"	16"	19.2"	24"	12"	16"	19.2"	24"
9-1/2"	NI-20	15'-10"	15'-0"	14'-5"	13'-5"	16'-4"	15'-5"	14'-6"	13'-5"
	NI-40x	17'-0"	16'-0"	15'-5"	14'-9"	17'-5"	16'-5"	15'-10"	15'-2"
	NI-60	17'-2"	16'-2"	15'-7"	14'-11"	17'-6"	16'-7"	15'-11"	15'-3"
	NI-70	18'-0"	16'-11"	16'-3"	15'-7"	18'-5"	17'-3"	16'-7"	15'-11"
	NI-80	18'-3"	17'-1"	16'-5"	15'-9"	18'-8"	17'-5"	16'-9"	16'-1"
11-7/8"	NI-20	17'-10"	16'-10"	16'-2"	15'-6"	18'-6"	17'-4"	16'-9"	16'-1"
	NI-40x	19'-4"	17'-11"	17'-3"	16'-6"	19'-11"	18'-6"	17'-9"	17'-0"
	NI-60	19'-7"	18'-2"	17'-5"	16'-9"	20'-2"	18'-9"	17'-11"	17'-2"
	NI-70	20'-9"	19'-2"	18'-3"	17'-5"	21'-4"	19'-9"	18'-10"	17'-10"
	NI-80	21'-1"	19'-5"	18'-6"	17'-7"	21'-7"	20'-0"	19'-0"	18'-0"
14"	NI-90x	21'-8"	20'-0"	19'-1"	18'-0"	22'-2"	20'-6"	19'-6"	18'-6"
	NI-40x	21'-5"	19'-10"	18'-11"	17'-11"	22'-1"	20'-6"	19'-7"	18'-7"
	NI-60	21'-10"	20'-2"	19'-3"	18'-2"	22'-5"	20'-10"	19'-11"	18'-10"
	NI-70	23'-0"	21'-3"	20'-3"	19'-2"	23'-8"	21'-11"	20'-10"	19'-9"
	NI-80	23'-5"	21'-7"	20'-7"	19'-5"	24'-0"	22'-3"	21'-2"	20'-0"
16"	NI-90x	24'-1"	22'-3"	21'-2"	20'-0"	24'-8"	22'-10"	21'-9"	20'-7"
	NI-60	23'-9"	22'-0"	20'-11"	19'-10"	24'-6"	22'-9"	21'-8"	20'-6"
	NI-70	25'-1"	23'-2"	22'-0"	20'-10"	25'-9"	23'-10"	22'-9"	21'-6"
	NI-80	25'-6"	23'-6"	22'-4"	21'-2"	26'-1"	24'-2"	23'-1"	21'-10"
	NI-90x	26'-4"	24'-3"	23'-1"	21'-10"	26'-11"	24'-11"	23'-8"	22'-5"

Depth	Series	Mid-Span Blocking				Mid-Span Blocking and 1/2" Gypsum Ceiling			
		On Centre Spacing				On Centre Spacing			
		12"	16"	19.2"	24"	12"	16"	19.2"	24"
9-1/2"	NI-20	16'-10"	15'-5"	14'-6"	13'-5"	16'-10"	15'-5"	14'-6"	13'-5"
	NI-40x	18'-8"	17'-2"	16'-3"	15'-2"	18'-10"	17'-2"	16'-3"	15'-2"
	NI-60	18'-11"	17'-6"	16'-6"	15'-5"	19'-2"	17'-6"	16'-6"	15'-5"
	NI-70	20'-0"	18'-7"	17'-9"	16'-7"	20'-5"	18'-11"	17'-10"	16'-7"
	NI-80	20'-3"	18'-10"	17'-11"	16'-10"	20'-8"	19'-3"	18'-2"	16'-10"
11-7/8"	NI-20	20'-1"	18'-5"	17'-5"	16'-2"	20'-1"	18'-5"	17'-5"	16'-2"
	NI-40x	21'-10"	20'-4"	19'-4"	17'-8"	22'-5"	20'-6"	19'-4"	17'-8"
	NI-60	22'-1"	20'-7"	19'-7"	18'-4"	22'-8"	20'-10"	19'-8"	18'-4"
	NI-70	23'-4"	21'-8"	20'-8"	19'-7"	23'-10"	22'-3"	21'-2"	19'-9"
	NI-80	23'-7"	21'-11"	20'-11"	19'-9"	24'-1"	22'-6"	21'-5"	20'-0"
14"	NI-90x	24'-3"	22'-6"	21'-6"	20'-4"	24'-8"	23'-0"	22'-0"	20'-9"
	NI-40x	24'-5"	22'-9"	21'-8"	19'-5"	25'-1"	23'-2"	21'-9"	19'-5"
	NI-60	24'-10"	23'-1"	22'-0"	20'-10"	25'-6"	23'-8"	22'-4"	20'-10"
	NI-70	26'-1"	24'-3"	23'-2"	21'-10"	26'-8"	24'-11"	23'-9"	22'-4"
	NI-80	26'-6"	24'-7"	23'-5"	22'-2"	27'-1"	25'-3"	24'-1"	22'-9"
16"	NI-90x	27'-3"	25'-4"	24'-1"	22'-9"	27'-9"	25'-11"	24'-8"	23'-4"
	NI-60	27'-3"	25'-5"	24'-2"	22'-10"	28'-0"	26'-2"	24'-9"	23'-1"
	NI-70	28'-8"	26'-8"	25'-4"	23'-11"	29'-3"	27'-4"	26'-1"	24'-8"
	NI-80	29'-1"	27'-0"	25'-9"	24'-4"	29'-8"	27'-9"	26'-5"	25'-0"
	NI-90x	29'-11"	27'-10"	26'-6"	25'-0"	30'-6"	28'-5"	27'-2"	25'-8"

- Maximum clear span applicable to simple-span residential floor construction with a design live load of 40 psf and dead load of 15 psf. The ultimate limit states are based on the factored loads of 1.50L + 1.25D. The serviceability limit states include the consideration for floor vibration, a live load deflection limit of L/480 and a total load deflection limit of L/240.
- Spans are based on a composite floor with glued-nailed oriented strand board (OSB) sheathing with a minimum thickness of 3/4 inch for a joist spacing of 24 inches or less. The composite floor may include 1/2 inch gypsum ceiling and/or one row of blocking at mid-span with strapping. Strapping shall be minimum 1x4 inch strap applied to underside of joists at blocking line or 1/2 inch gypsum ceiling attached to joists.
- Minimum bearing length shall be 1-3/4 inches for the end bearings.
- Bearing stiffeners are not required when I-joists are used with the spans and spacings given in this table, except as required for hangers.
- This span chart is based on uniform loads. For applications with other than uniformly distributed loads, an engineering analysis may be required based on the use of the design properties. Tables are based on Limit States Design per CSA O86-09, NBC 2010, and OBC 2012.
- Joists shall be laterally supported at supports and continuously along the compression edge. Refer to technical documentation for installation guidelines and construction details. Nordic I-joists are listed in CCMC evaluation report 13032-R and APA Product Report PR-L274C.



Maximum Floor Spans

Live Load = 40 psf, Dead Load = 30 psf
Simple Spans, L/480 Deflection Limit
5/8" OSB G&N Sheathing



Depth	Series	Bare				1/2" Gypsum Ceiling			
		On Centre Spacing				On Centre Spacing			
		12"	16"	19.2"	24"	12"	16"	19.2"	24"
9-1/2"	NI-20	15'-1"	14'-1"	13'-3"	N/A	15'-7"	14'-1"	13'-3"	N/A
	NI-40x	16'-1"	15'-2"	14'-8"	N/A	16'-7"	15'-7"	15'-1"	N/A
	NI-60	16'-3"	15'-4"	14'-10"	N/A	16'-8"	15'-9"	15'-3"	N/A
	NI-70	17'-1"	16'-1"	15'-6"	N/A	17'-5"	16'-5"	15'-10"	N/A
	NI-80	17'-3"	16'-3"	15'-8"	N/A	17'-8"	16'-7"	16'-0"	N/A
11-7/8"	NI-20	16'-11"	16'-0"	15'-5"	N/A	17'-6"	16'-6"	16'-0"	N/A
	NI-40x	18'-1"	17'-0"	16'-5"	N/A	18'-9"	17'-6"	16'-11"	N/A
	NI-60	18'-4"	17'-3"	16'-7"	N/A	19'-0"	17'-8"	17'-1"	N/A
	NI-70	19'-6"	18'-0"	17'-4"	N/A	20'-1"	18'-7"	17'-9"	N/A
	NI-80	19'-9"	18'-3"	17'-6"	N/A	20'-4"	18'-10"	17'-11"	N/A
14"	NI-90x	20'-4"	18'-9"	17'-11"	N/A	20'-10"	19'-3"	18'-5"	N/A
	NI-40x	20'-1"	18'-7"	17'-10"	N/A	20'-10"	19'-4"	18'-6"	N/A
	NI-60	20'-5"	18'-11"	18'-1"	N/A	21'-2"	19'-7"	18'-9"	N/A
	NI-70	21'-7"	20'-0"	19'-1"	N/A	22'-3"	20'-7"	19'-8"	N/A
	NI-80	21'-11"	20'-3"	19'-4"	N/A	22'-7"	20'-11"	20'-0"	N/A
16"	NI-90x	22'-7"	20'-11"	19'-11"	N/A	23'-3"	21'-6"	20'-6"	N/A
	NI-60	22'-3"	20'-8"	19'-9"	N/A	23'-1"	21'-5"	20'-6"	N/A
	NI-70	23'-6"	21'-9"	20'-9"	N/A	24'-3"	22'-5"	21'-5"	N/A
	NI-80	23'-11"	22'-1"	21'-1"	N/A	24'-8"	22'-10"	21'-9"	N/A
	NI-90x	24'-8"	22'-9"	21'-9"	N/A	25'-4"	23'-5"	22'-4"	N/A

Depth	Series	Mid-Span Blocking				Mid-Span Blocking and 1/2" Gypsum Ceiling			
		On Centre Spacing				On Centre Spacing			
		12"	16"	19.2"	24"	12"	16"	19.2"	24"
9-1/2"	NI-20	15'-7"	14'-1"	13'-3"	N/A	15'-7"	14'-1"	13'-3"	N/A
	NI-40x	17'-9"	16'-1"	15'-1"	N/A	17'-9"	16'-1"	15'-1"	N/A
	NI-60	18'-1"	16'-4"	15'-4"	N/A	18'-1"	16'-4"	15'-4"	N/A
	NI-70	19'-2"	17'-10"	16'-9"	N/A	19'-7"	17'-10"	16'-9"	N/A
	NI-80	19'-5"	18'-0"	17'-1"	N/A	19'-10"	18'-3"	17'-1"	N/A
11-7/8"	NI-20	18'-9"	17'-0"	16'-0"	N/A	18'-9"	17'-0"	16'-0"	N/A
	NI-40x	21'-0"	19'-3"	17'-9"	N/A	21'-3"	19'-3"	17'-9"	N/A
	NI-60	21'-4"	19'-8"	18'-5"	N/A	21'-8"	19'-8"	18'-5"	N/A
	NI-70	22'-6"	20'-10"	19'-11"	N/A	23'-0"	21'-4"	20'-0"	N/A
	NI-80	22'-9"	21'-1"	20'-1"	N/A	23'-3"	21'-7"	20'-5"	N/A
14"	NI-90x	23'-4"	21'-8"	20'-8"	N/A	23'-10"	22'-2"	21'-2"	N/A
	NI-40x	23'-7"	21'-5"	19'-6"	N/A	24'-1"	21'-5"	19'-6"	N/A
	NI-60	24'-0"	22'-3"	21'-0"	N/A	24'-8"	22'-5"	21'-0"	N/A
	NI-70	25'-3"	23'-4"	22'-3"	N/A	25'-10"	24'-0"	22'-9"	N/A
	NI-80	25'-7"	23'-8"	22'-7"	N/A	26'-2"	24'-4"	23'-2"	N/A
16"	NI-90x	26'-4"	24'-4"	23'-3"	N/A	26'-10"	24'-11"	23'-9"	N/A
	NI-60	26'-5"	24'-6"	23'-4"	N/A	27'-2"	24'-10"	23'-4"	N/A
	NI-70	27'-9"	25'-8"	24'-6"	N/A	28'-5"	26'-5"	25'-2"	N/A
	NI-80	28'-2"	26'-1"	24'-10"	N/A	28'-10"	26'-9"	25'-6"	N/A
	NI-90x	29'-0"	26'-10"	25'-7"	N/A	29'-7"	27'-5"	26'-2"	N/A

- Maximum clear span applicable to simple-span residential floor construction with a design live load of 40 psf and dead load of 30 psf. The ultimate limit states are based on the factored loads of 1.50L + 1.25D. The serviceability limit states include the consideration for floor vibration, a live load deflection limit of L/480 and a total load deflection limit of L/240.
- Spans are based on a composite floor with glued-nailed oriented strand board (OSB) sheathing with a minimum thickness of 5/8 inch for a joist spacing of 19.2 inches or less. The composite floor may include 1/2 inch gypsum ceiling and/or one row of blocking at mid-span with strapping. Strapping shall be minimum 1x4 inch strap applied to underside of joists at blocking line or 1/2 inch gypsum ceiling attached to joists.
- Minimum bearing length shall be 1-3/4 inches for the end bearings.
- Bearing stiffeners are not required when I-joists are used with the spans and spacings given in this table, except as required for hangers.
- This span chart is based on uniform loads. For applications with other than uniformly distributed loads, an engineering analysis may be required based on the use of the design properties. Tables are based on Limit States Design per CSA O86-09, NBC 2010, and OBC 2012.
- Joists shall be laterally supported at supports and continuously along the compression edge. Refer to technical documentation for installation guidelines and construction details. Nordic I-joists are listed in CCMC evaluation report 13032-R and APA Product Report PR-L274C.

Maximum Floor Spans

Live Load = 40 psf, Dead Load = 30 psf
Simple Spans, L/480 Deflection Limit
3/4" OSB G&N Sheathing



Depth	Series	Bare				1/2" Gypsum Ceiling			
		On Centre Spacing				On Centre Spacing			
		12"	16"	19.2"	24"	12"	16"	19.2"	24"
9-1/2"	NI-20	15'-7"	14'-2"	13'-4"	12'-4"	15'-7"	14'-2"	13'-4"	12'-4"
	NI-40x	17'-0"	16'-0"	15'-1"	13'-11"	17'-5"	16'-1"	15'-1"	13'-11"
	NI-60	17'-2"	16'-2"	15'-5"	14'-3"	17'-6"	16'-5"	15'-5"	14'-3"
	NI-70	18'-0"	16'-11"	16'-3"	15'-6"	18'-5"	17'-3"	16'-7"	15'-6"
	NI-80	18'-3"	17'-1"	16'-5"	15'-9"	18'-8"	17'-5"	16'-9"	15'-10"
11-7/8"	NI-20	17'-10"	16'-10"	16'-0"	14'-10"	18'-6"	17'-1"	16'-0"	14'-10"
	NI-40x	19'-4"	17'-11"	17'-3"	15'-10"	19'-11"	18'-6"	17'-9"	15'-10"
	NI-60	19'-7"	18'-2"	17'-5"	16'-9"	20'-2"	18'-9"	17'-11"	17'-1"
	NI-70	20'-9"	19'-2"	18'-3"	17'-5"	21'-4"	19'-9"	18'-10"	17'-10"
	NI-80	21'-1"	19'-5"	18'-6"	17'-7"	21'-7"	20'-0"	19'-0"	18'-0"
14"	NI-90x	21'-8"	20'-0"	19'-1"	18'-0"	22'-2"	20'-6"	19'-6"	18'-6"
	NI-40x	21'-5"	19'-10"	18'-11"	17'-5"	22'-1"	20'-6"	19'-6"	17'-5"
	NI-60	21'-10"	20'-2"	19'-3"	18'-2"	22'-5"	20'-10"	19'-11"	18'-10"
	NI-70	23'-0"	21'-3"	20'-3"	19'-2"	23'-8"	21'-11"	20'-10"	19'-9"
	NI-80	23'-5"	21'-7"	20'-7"	19'-5"	24'-0"	22'-3"	21'-2"	20'-0"
16"	NI-90x	24'-1"	22'-3"	21'-2"	20'-0"	24'-8"	22'-10"	21'-9"	20'-7"
	NI-60	23'-9"	22'-0"	20'-11"	19'-10"	24'-6"	22'-9"	21'-8"	20'-6"
	NI-70	25'-1"	23'-2"	22'-0"	20'-10"	25'-9"	23'-10"	22'-9"	21'-6"
	NI-80	25'-6"	23'-6"	22'-4"	21'-2"	26'-1"	24'-2"	23'-1"	21'-10"
	NI-90x	26'-4"	24'-3"	23'-1"	21'-10"	26'-11"	24'-11"	23'-8"	22'-5"

Depth	Series	Mid-Span Blocking				Mid-Span Blocking and 1/2" Gypsum Ceiling			
		On Centre Spacing				On Centre Spacing			
		12"	16"	19.2"	24"	12"	16"	19.2"	24"
9-1/2"	NI-20	15'-7"	14'-2"	13'-4"	12'-4"	15'-7"	14'-2"	13'-4"	12'-4"
	NI-40x	17'-9"	16'-1"	15'-1"	13'-11"	17'-9"	16'-1"	15'-1"	13'-11"
	NI-60	18'-1"	16'-5"	15'-5"	14'-3"	18'-1"	16'-5"	15'-5"	14'-3"
	NI-70	19'-10"	17'-11"	16'-9"	15'-6"	19'-10"	17'-11"	16'-9"	15'-6"
	NI-80	20'-2"	18'-3"	17'-1"	15'-10"	20'-2"	18'-3"	17'-1"	15'-10"
11-7/8"	NI-20	18'-10"	17'-1"	16'-0"	14'-10"	18'-10"	17'-1"	16'-0"	14'-10"
	NI-40x	21'-3"	19'-3"	17'-9"	15'-10"	21'-3"	19'-3"	17'-9"	15'-10"
	NI-60	21'-9"	19'-8"	18'-5"	17'-1"	21'-9"	19'-8"	18'-5"	17'-1"
	NI-70	23'-4"	21'-5"	20'-1"	18'-6"	23'-8"	21'-5"	20'-1"	18'-6"
	NI-80	23'-7"	21'-10"	20'-5"	18'-11"	24'-1"	21'-10"	20'-5"	18'-11"
14"	NI-90x	24'-3"	22'-6"	21'-3"	19'-7"	24'-8"	22'-7"	21'-3"	19'-7"
	NI-40x	24'-2"	21'-5"	19'-6"	17'-5"	24'-2"	21'-5"	19'-6"	17'-5"
	NI-60	24'-9"	22'-5"	21'-0"	19'-6"	24'-9"	22'-5"	21'-0"	19'-6"
	NI-70	26'-1"	24'-3"	22'-9"	21'-0"	26'-8"	24'-3"	22'-9"	21'-0"
	NI-80	26'-6"	24'-7"	23'-3"	21'-6"	27'-1"	24'-10"	23'-3"	21'-6"
16"	NI-90x	27'-3"	25'-4"	24'-1"	22'-4"	27'-9"	25'-10"	24'-3"	22'-4"
	NI-60	27'-3"	24'-11"	23'-5"	21'-7"	27'-6"	24'-11"	23'-5"	21'-7"
	NI-70	28'-8"	26'-8"	25'-3"	23'-4"	29'-3"	26'-11"	25'-3"	23'-4"
	NI-80	29'-1"	27'-0"	25'-9"	23'-10"	29'-8"	27'-6"	25'-10"	23'-10"
	NI-90x	29'-11"	27'-10"	26'-6"	24'-10"	30'-6"	28'-5"	26'-11"	24'-10"

- Maximum clear span applicable to simple-span residential floor construction with a design live load of 40 psf and dead load of 30 psf. The ultimate limit states are based on the factored loads of 1.50L + 1.25D. The serviceability limit states include the consideration for floor vibration, a live load deflection limit of L/480 and a total load deflection limit of L/240.
- Spans are based on a composite floor with glued-nailed oriented strand board (OSB) sheathing with a minimum thickness of 3/4 inch for a joist spacing of 24 inches or less. The composite floor may include 1/2 inch gypsum ceiling and/or one row of blocking at mid-span with strapping. Strapping shall be minimum 1x4 inch strap applied to underside of joists at blocking line or 1/2 inch gypsum ceiling attached to joists.
- Minimum bearing length shall be 1-3/4 inches for the end bearings.
- Bearing stiffeners are not required when I-joists are used with the spans and spacings given in this table, except as required for hangers.
- This span chart is based on uniform loads. For applications with other than uniformly distributed loads, an engineering analysis may be required based on the use of the design properties. Tables are based on Limit States Design per CSA O86-09, NBC 2010, and OBC 2012.
- Joists shall be laterally supported at supports and continuously along the compression edge. Refer to technical documentation for installation guidelines and construction details. Nordic I-joists are listed in CCMC evaluation report 13032-R and APA Product Report PR-L274C.

CITY OF RICHMOND HILL
BUILDING DIVISION

07/20/2021

2014-01-18 / Page 1 of 1

RECEIVED

Per: jocelyn.aguiar



Construction Detail


Limit States Design

Allowance for Piping (Installation Notes)


The floor layouts have usually not been checked for heating and/or plumbing interference. On-site adjustment of joists of up to 3 inches is permitted to avoid interferences. When moving a joist, the subfloor thickness shall be checked with code requirements when the joist spacing exceeds 19.2 inches. Except for cutting to length, I-joist flanges should never be cut, drilled, or notched.

Installation of Nordic I-joists shall be as per *Nordic Joist Installation Guide for Residential Floors*. Refer to Tables 1 and 2 for maximum web hole and duct chase openings, respectively. These tables are based on the I-joists being used at their maximum spans. The minimum distance given may be reduced for shorter spans; contact your distributor for additional information.

The detail below shows the 3-inch allowance for piping. Every third joist may be shifted up to 3 inches to avoid heating/plumbing interference. For other applications, please contact your distributor.



Revised April 12, 2012



1W-1

CITY OF RICHMOND HILL
BUILDING DIVISION
07/20/2021
RECEIVED
Per: jocelyn.aguilar

Notes:

1. Blocking required at bearing for lateral support, not shown for clarity.
2. The maximum dimensions for a notch on the side of the top flange are 4-inch width by 1/2-inch depth for flange width of 2-1/2 inches, and 4-inch width by 1-inch depth for flange width of 3-1/2 inches.
3. This detail applies to simple-span joists and multiple-span joists where the notch is located at the end half-span.
4. For other applications, contact Nordic Structures.

This document supersedes all previous versions. If the document has been in effect for more than one year, consult nordic.ca or contact Nordic Structures.

All nails shown in the details are assumed to be common nails unless otherwise noted. Nails shall have a diameter not less than 0.128 inch for 2-1/2-inch nails, or 0.144 inch for 3-inch nails. Individual components not shown to scale for clarity.

NORDIC STRUCTURES T 514-871-8526 1 866 817-3418 nordic.ca	TITLE Notch in I-joist for Heat Register CATEGORY I-joist - Typical Floor Framing and Construction Details	DOCUMENT - DATE 2018-04-10 NUMBER 1W-1
--	---	---