

VALECRAFT HOMES LIMITED

SCHEDULE 'B'

A-6 PLUMBING

Revised: April 1, 2019

Contractor is to supply all labour and material to do all "plumbing" work, to include but not necessarily be limited to the following items. All work to be carried out in accordance with the General Conditions (Schedule "A") of the contract, the site specifications (Schedule B of Agreement of Purchase and Sale), drawings, and product schedule, to the satisfaction of the Builder and/or his representative, and to all codes and authorities having jurisdiction.

PLUMBING:

1. This Contractor shall supply and install white plumbing fixtures in all bathrooms, ensuite, and powder room as per the Interior Colour Chart provided by the Builder.
2. This Contractor shall supply and install one vitreous china pedestal sink and base in each Powder room unless otherwise noted in the specifications or by the Interior Colour Chart provided by the Builder.
3. This Contractor shall supply and install one moulded plastic laundry tub per household excluding condominiums as indicated on the drawings and make this level to floor. Black tubs are installed in basements, and White tubs in "Laundry Rooms" where adjacent white appliances.
4. This Contractor shall supply and install a double stainless-steel sink with ledge in kitchen unless otherwise noted by the Interior Colour Chart provided by the Builder.
5. This Contractor shall hook up one rental gas-fired water heater to the requirements of the Ontario Building Code including piping insulation with a minimum value of RSI 0.62 on the first 2.5m of the hot water outlet.
6. This Contractor shall supply and install two (2) exterior hose bibs per unit as per locations on Drawings excluding condominiums. (Stop drain in unit). This Contractor shall install access panels for hose bibs in basement ceilings @ 12" from exterior wall or as close as possible.
7. This Contractor shall supply and install one mechanical drain in each basin.
8. This Contractor shall supply and install one automatic washer water connection and separate waste as noted on Drawings, complete with trim kit where required.
9. The Contractor shall supply and install one Drain Water Heat Recovery unit in all singles and town homes. This unit is to receive drain water from all showers. This drain water heat recovery unit shall comply with SB-12 3.1.1.12.
10. This Contractor shall install spl valve for Furnace Humidifier.
11. Water pipes shall not be installed in any exterior partitions or near the top and bottom of beams/joists where they are susceptible to be damaged by fasteners.
12. This Contractor shall ensure that all water supply lines and drain pipes being installed to service a washing machine are contained within a washer box inside a finished wall in all finished areas of the home, except in an unfinished basement area.
13. This Contractor shall install basement bathroom rough-ins (pipes) in all house types where indicated on the plans. Not applicable to condominiums.
14. All water pipes to be pressure tested to 1034.2 KPA prior to drywall installation and it is this Contractor's responsibility to drain said water pipe until finishing's are installed.
15. This Contractor shall supply and install steel protective plates over top and bottom wood plates and studs where water lines occur.
16. This Contractor is responsible for all plumbing inspections from the Municipality on or before scheduled dates issued by the Site Superintendent.
17. This Contractor shall supply and install all required flashings where vent pipes protrude through roof proper. These flashings are to be securely fastened.

Contractor Initials: _____

Valecraft Initials: _____

VALECRAFT HOMES LIMITED
SCHEDULE 'B'

18. This Contractor shall repair or replace any bridging ribbon strips or damaged joists caused by his operation.
19. This Contractor shall connect on 19mm water service inside the foundation wall and a 100mm storm sewer and sanitary service to a point inside the foundation wall.
20. This Contractor shall supply and install a storm sewer connection with backwater valve and a sanitary sewer connection with check valve in each unit.
21. Supply and install one 75mm basement floor drain per unit. Contractor must confirm the location and install as indicated on the architectural drawings.
22. a) This Contractor shall supply and install one 38mm furnace condensate drain pipe (flush with concrete slab) adjacent to furnace as indicated on the architectural drawings.

b) This Contractor shall supply & install one 1-1/2" ABS floor drain adjacent to any hot water on demand gas fired system (i.e. Rinnai Tankless.)
23. Supply and install rough-in only for future dishwasher. This includes a shut off valve on hot supply under kitchen sink.
24. It shall be the responsibility of this Contractor to ensure all one piece shower stalls and roman tubs are installed properly as per the Manufacturer's instructions. Any framing irregularities are to be reported immediately to the Site Superintendent prior to installation.
25. This Contractor shall remove all excess material generated by his operations daily and place it in the waste disposal container provided by the Builder. All cardboard boxes must be cut and flattened before placing in the bin.
26. Under no circumstances are any open flames or soldering permitted within any unit under construction. All water pipes are to be connected using "PEX READY" fittings.
27. This Contractor shall guarantee all materials and workmanship for a period of two years after occupancy.
28. This Contractor shall ensure that all required stack vent pipes which protrude through roof proper are located at the rear of the building. This contractor shall also secure this stack properly to trusses.
29. All houses are to receive one "master mixing valve" at the hot water tank in accordance with the revised Ontario Plumbing Code (not reflected in Schedule 'C').
30. This contractor shall install shut off valves at all plumbing fixtures including all sinks.
31. This Contractor shall install a sleeve for future waterline to all refrigerators.
32. This Contractor shall install a Pressure Booster Pump in Deerfield Village 2 only as per the manufacturer's specifications.

WATER METERS:

33. This Contractor shall supply & install one approved water meter with remote per household to a minimum specification as set forth in the Authority having jurisdictions specifications for water meter installations.
34. This Contractor is expected to carry out his duties in a professional and workmanlike manner at all times while on a Valecraft Site.
35. This Contractor shall guarantee all material and workmanship for a period of one year after occupancy.

Contractor Initials: _____

Valecraft Initials: _____