

CONSTRUCTION SUMMARY OF EXTRAS  
Printed 2019-05-31 / 2:54 PM / Page 1 of 1

Site: INNISFIL PHASE 2  
Lot: 202  
Model: LUNAR 50-09 (B) CORNER  
Purchaser: TRUNG DUNG LY & LE HAO HA  
Phone/Email: 705-977-2666  
Appointment: **STRUCTURALS & COLOURS**




| DESCRIPTION |  | DATE SELECTED |
|-------------|--|---------------|
| #1          | SMOOTH CEILINGS ON MAIN FLOOR  | MAY 9 2019    |
| #2          | SMOOTH CEILINGS ON SECOND FLOOR  | MAY 9 2019    |
| #3          | KITCHEN - BUILT IN FRIDGE *NO PANEL REQUIRED   | MAY 9 2019    |
| #4          | KITCHEN - BUILT IN INDUCTION COOKTOP WITH BUILT IN WALL OVEN BELOW   | MAY 9 2019    |
| #5          | KITCHEN - BUILT IN MICROWAVE DRAWER *IN ISLAND   | MAY 9 2019    |
| #6          | ELECTRICAL FOR APPLIANCES <i>* SEE SPECS</i>   | MAY 9 2019    |
| #7          | PLASTER MOULDING ON MAIN FLOOR ***INDIRECT MOULDING FOR FUTURE LIGHTING IN FAMILY ROOM, STANDARD MOULDING IN DINING, LIVING, MAIN HALL, FOYER AND MUD, KITCHEN & BREAKFAST | MAY 9 2019    |
| #9          | FIREPLACE - MARBLE SURROUND  | MAY 9 2019    |
| #10         | KITCHEN - 6 INCH RISER IN KITCHEN  | MAY 9 2019    |
| #11         | KITCHEN - MATCHING VALANCE   | MAY 9 2019    |
| #12         | KITCHEN SINK - BLANCO QUATRUS R15 SUPER SINGLE (401515)  | MAY 9 2019    |
| #13         | ELECTRICAL - KITCHEN RELOCATE STANDARD LIGHT TO BE CENTRED OVER ISLAND   | MAY 9 2019    |
| #14         | ELECTRICAL - KITCHEN ROUGHIN ONLY WITH SWITCH FOR FUTURE VALANCE LIGHTING BY PURCHASER   | MAY 9 2019    |
| #15         | WATERLINE TO FRIDGE  | MAY 9 2019    |
| #16         | ELECTRICAL - ADD CAPPED LIGHT FOR MASTER ENSUITE ***STD CENTRED OVER SINK, ADDITIONAL CENTRED OVER SINK  | MAY 9 2019    |
| #17         | ELECTRICAL - ADD CAPPED LIGHT FOR TWIN BATH **STD CENTRED OVER SINK, ADDITIONAL CENTRED OVER SINK  | MAY 9 2019    |
| #18         | RAILINGS - UPGRADE 5   | MAY 9 2019    |
| #19         | HARDWOOD - UPGRADE COLOUR ON MAIN FLOOR  | MAY 9 2019    |
| #20         | HARDWOOD - IN UPPER HALL IN LIEU OF CARPET   | MAY 9 2019    |
| #21         | TILES - KITCHEN BREAKFAST - UPGRADE 4  | MAY 9 2019    |
| #22         | TILES - MUD ROOM UPGRADE 4   | MAY 9 2019    |
| #23         | TILES - POWDER ROOM UPGRADE 4  | MAY 9 2019    |
| #24         | TILES - FOYER - UPGRADE 4 WITH 6 INCH BORDER   | MAY 9 2019    |
| #25         | MASTER ENSUITE FLOOR TILES - UPGRADE 4   | MAY 9 2019    |
| #26         | MASTER ENSUITE SHOWER WALLS - INSTALL FLOOR TILES ON WALL WITH 6 INCH BORDER **INSTALL TOP OF BOARDER 16 INCHES DOWN FROM THE CEILING                                      | MAY 9 2019    |
| #27         | MASTER ENSUITE - SHOWER NICHE ***HORIZONTAL ON LARGE BACK WALL ***TILES INSIDE NICHE TO BE THE SAME BLACK AS THE BOARDER   | MAY 9 2019    |
| #28         | FRAMELESS GLASS SHOWER IN MASTER ENSUITE   | MAY 9 2019    |
| #29         | MASTER ENSUITE SHOWER FLOOR - MARBLE 5/8" X 5/8"   | MAY 9 2019    |
| #30         | KITCHEN COUNTERTOP - UPGRADE 6   | MAY 9 2019    |
| #31         | KITCHEN - CUTOUT FOR COOKTOP   | MAY 9 2019    |
| #32         | MASTER ENSUITE COUNTERTOP - UPGRADE 1 MARBLE **INCLUDE OVAL UNDERMOUNT SINK  | MAY 9 2019    |
| #33         | 8 FOOT HIGH INTERIOR DOORS (X5)  | MAY 9 2019    |
| #34         | STAIN STAIRS TO MATCH HARDWOOD AS CLOSE AS POSSIBLE  | MAY 9 2019    |
| #35         | ELECTRICAL - FAMILY ROOM INSTALL PLUG ON WALL BEHIND PLASTER MOULDING  | MAY 9 2019    |
| #36         | TRAY CEILING MASTER BEDROOM  | MAY 9 2019    |


ZANCOR HOMES COLOUR CHART

| CABINETRY / COUNTERTOPS  |  |                     |                       |        |
|--|--|---------------------|-----------------------|--------|
|  | DOOR STYLE                                     | HARDWARE            | COUNTERTOP            | EDGE   |
| Kitchen  | 400 SERIES MEL - WHITE                         | H500P               | ANTIQUE BROWN (6)     |        |
| Island   | 400 SERIES MEL - WHITE                         | H500P               | ANTIQUE BROWN (6)     |        |
| Powder Room  | N/A  |                     | N/A                   |        |
| Master Ensuite   | SHAKER MEL - TUXEDO                            | H500P               | BIANCO CARRARA MARBLE |        |
| Twin 2/3   | SHAKER MEL - TUXEDO                            | H500P               | 4925K-07              |        |
| Ensuite 4  | SHAKER MEL - TUXEDO                            | H500P               | 4925K-07              |        |
| Laundry  | N/A  |                     | N/A                   |        |
| TILES  |  |                     |                       |        |
| Main Foyer   | TIMELESS WHITE POLISHED 12 X 24 (4)            |                     |                       |        |
| MAIN FOYER BORDER  | UNICOLOUR JET BLACK 6 INCHES                   |                     | (SUPERBLACK)          |        |
| Powder Room  | TIMELESS WHITE POLISHED 12 X 24 (4)            |                     |                       |        |
| Mud Room   | TIMELESS WHITE POLISHED 12 X 24 (4)            |                     |                       |        |
| Kitchen  | TIMELESS WHITE POLISHED 12 X 24 (4)            |                     |                       |        |
| Breakfast  | TIMELESS WHITE POLISHED 12 X 24 (4)            |                     |                       |        |
| Kitchen Bk.Splash  | N/A  |                     |                       |        |
| Laundry  | BELLINA GREY 13 X 13                           |                     |                       |        |
| Mstr Ensuite Floor   | TIMELESS WHITE POLISHED 12 X 24 (4)            |                     |                       |        |
| Mstr Ensuite Shower WALL   | TIMELESS WHITE POLISHED 12 X 24 (4)            |                     |                       |        |
| Master shower BORDER   | NERO MARQUINA 5/8 X 5/8 MARBLE *POLISHED       |                     |                       |        |
| INSIDE NICHE   | NERO MARQUINA 5/8 X 5/8 MARBLE *POLISHED       |                     |                       |        |
| Master Shower Floor  | NERO MARQUINA 5/8 X 5/8 MARBLE *POLISHED       |                     |                       |        |
| Master Shower JAMB   | BIANCO CARRARA                                 |                     |                       |        |
| Twin 2/3 Floor   | BELLINA GREY 13 X 13                           |                     |                       |        |
| Twin 2/3 Tub Wall  | BELLINA GREY 8 X 10                            |                     |                       |        |
| Ensuite 4 Floor  | BELLINA GREY 13 X 13                           |                     |                       |        |
| Ensuite 4 Tub Wall   | BELLINA GREY 8 X 10                            |                     |                       |        |
| HARDWOOD / CARPET  |  |                     |                       |        |
| TILES  |  |                     |                       |        |
| Kitchen/ Breakfast   | VINTAGE OAK - 5 INCH GOTHAM SMOOTH (2)         |                     |                       |        |
| Family Room  | VINTAGE OAK - 5 INCH GOTHAM SMOOTH (2)         |                     |                       |        |
| Dining Room  | VINTAGE OAK - 5 INCH GOTHAM SMOOTH (2)         |                     |                       |        |
| Main hall  | VINTAGE OAK - 5 INCH GOTHAM SMOOTH (2)         |                     |                       |        |
| Living Room  | VINTAGE OAK - 5 INCH GOTHAM SMOOTH (2)         |                     |                       |        |
| Upper Hall   | VINTAGE OAK - 5 INCH GOTHAM SMOOTH (2)         |                     |                       |        |
| Master Bedroom   | OPENING NIGHT - COLOUR T03 / STANDARD UNDERPAD |                     |                       |        |
| Bedroom 2  | OPENING NIGHT - COLOUR T03 / STANDARD UNDERPAD |                     |                       |        |
| Bedroom 3  | OPENING NIGHT - COLOUR T03 / STANDARD UNDERPAD |                     |                       |        |
| Bedroom 4  | OPENING NIGHT - COLOUR T03 / STANDARD UNDERPAD |                     |                       |        |
| FIREPLACES   |  |                     |                       |        |
| LOCATION   | FAMILY ROOM                                    | MANTLE              | NF8                   |        |
| MIRRORS & ACCESSORIES  |  | PLASTER MOULDING    |                       |        |
| Mirrors  | YES  | Opt. Crown Moulding | 675 & IL IN FAMILY    |        |
| Bathroom Accessories   | DELETE   | Location            | SEE EXTRAS            |        |
| Purchaser has reviewed the colour chart  |  |                     | SITE & LOT            |        |
| ***FOR TRADE USE***  |  |                     | INNISFIL              | 202    |
| Any upgrades in the colour chart must be accompanied with a PES. It is the responsibility of all Trades to inform the builder of any discrepancies on sketches, PES and/or colour charts <u>PRIOR</u> to installation. |  |                     |                       |        |
| ** PAGE 1 OF 2 **  |  |                     | Purchaser Initial     | Vendor |

## ZANCOR HOMES COLOUR CHART

| STAIRS, RAILING & PICKETS & STAIR STAIN  |                            |  |                         |          |  |
|--|----------------------------|--|-------------------------|----------|--|
| Stair Stain / Species:   |                            | STAIN STAIRS TO MATCH HARDWOOD AS CLOSE AS POSSIBLE              |                         |          |  |
| Main to 2nd Railing Details:   |                            | STAMPED SINGLE COLLAR ALT. DOUBLE, SQUARE POST, GROOVED HANDRAIL |                         |          |  |
| Main to Basement Railing Details:  |                            | N/A  |                         |          |  |
| TRIM   |                            |  |                         |          |  |
| Casing/Baseboards  |                            | STANDARD   |                         |          |  |
| Interior Doors   |                            | STANDARD   |                         |          |  |
| Interior Door Hardware   |                            | STANDARD   |                         |          |  |
| Exterior Door Hardware   |                            | STANDARD   |                         |          |  |
| PAINT  |                            |  |                         |          |  |
| THROUGHOUT   |                            | CAMEO WHITE  |                         |          |  |
| PLUMBING- UPGRADES TO BE DETAILED ON PES   |                            |  |                         |          |  |
|  | FIXTURES                   | FAUCETS  | NOTES                   |          |  |
| Kitchen  | UPGRADE                    | STANDARD   | UPGRADED SINK           |          |  |
| Island   | STANDARD                   | STANDARD   |                         |          |  |
| Powder room  | STANDARD                   | STANDARD   |                         |          |  |
| Master Ensuite   | UPGRADE                    | STANDARD   | UNDERMOUNT SINKS (OVAL) |          |  |
| Twin 2/3   | STANDARD                   | STANDARD   |                         |          |  |
| Ensuite 3  | STANDARD                   | STANDARD   |                         |          |  |
| ZANCOR APPLIANCE REQUIREMENTS-UPGRADES TO BE DETAILED ON PES   |                            |  |                         |          |  |
| Appliance Package received in 'Schedule E'   |                            | YES / NO    Package Name:  |                         |          |  |
| GAS LINE   | UPG (SEE PES)              | DECLINED   | NOTES                   |          |  |
| WATERLINE to Fridge  | NO                         |  |                         |          |  |
| Hood Fan Venting SIZE  | YES                        |  |                         |          |  |
| ELECTRICAL for Built-in Oven   | 6 INCH                     |  |                         |          |  |
| ELECTRICAL for Built-in Micro / OTR  | YES                        |  |                         |          |  |
| ELECTRICAL for Gas Stove / Cooktop   | YES                        |  | INDUCTION               |          |  |
| ELECTRICAL for Bar Fridge  | NO                         |  |                         |          |  |
| DISCLAIMER   |                            |  |                         | INITIALS |  |
| Colours of all materials are as close as possible to Builders selection but not necessarily identical due to dye lot variances in manufacturing/manufacturers. Due to construction progress some items may have been pre-selected or installed. In this event the Vendor's selection must be accepted by the purchaser |                            |  |                         |          |  |
| Any changes to the colour chart after signing are subject to a \$5000 administration fee plus costs  |                            |  |                         |          |  |
| Purchaser has checked and acknowledged accuracy of colour and selections before signing.   |                            |  |                         |          |  |
| SITE:  | INNISFIL                   | LOT: 202   |                         |          |  |
| PURCHASER(S):  | TRUNG DUNG LY<br>LE HAO HA |  |                         |          |  |
| HOME #/CELL #  | 705-977-2666               |  |                         |          |  |
| EMAIL:   |                            |  |                         |          |  |
| DÉCOR NOTES  |                            |  |                         |          |  |
| ***FOR TRADE USE ***   |                            |  |                         |          |  |
| Any upgrades in the colour chart must be accompanied with a PES.   |                            |  |                         |          |  |
| It is the responsibility of all Trades to inform the builder of any discrepancies on sketches, PES and/or colour charts PRIOR to installation.   |                            |  |                         |          |  |
| *** PAGE 2 OF 2 ***  |                            |  |                         |          |  |
|   |                            |  |                         |          |  |
| D décor Consultant Signature   |                            |  | Date                    |          |  |
| Vendor Signature   |                            |  | Date                    |          |  |





# Ground Floor Elevation B


202

CT  
LH

#SMOOTH CEILING  
#8'00" Doors

LUNAR 50-09

Second Floor  
Elevation B



24 SMOOTH CEILINGS




Drawn by: MGER  
Reviewed:

Drawn by: MGER  
Reviewed:

Drawing number

Doctor w/  
Bulimia Nervosa



5 17

202

|                         |              |                 |  |
|-------------------------|--------------|-----------------|--|
| New Image Kitchens Inc. |              |                 |  |
| Scale:                  | Approved by: | Drawn by: MCE-R |  |
| Date: 24/02/17          |              | Revised:        |  |

BELLE AIR SHORES, INNISFIL

Drawing number:

MODEL: 50-09



57 202



STANDARD PAINT GRADE FIREPLACE MANTILES

NF8



WITH  
NEW  
MANTLE  
MANTLE

LD

NF23




LD1

NF17



202 Instl



202  
Innistr 1

INNOVATIVE CAST INC.  
N. SOLESA  
08/12/14.

FULL SCALE










147

G

ZANCOR HOMES  
EDGE PROFILES (INTERSTONE / REDSTONE)

STANDARD  
KITCHENS

STANDARD  
VANITIES












CJ

LA1

UPGRADE  
KITCHENS

UPGRADE  
VANITIES



INNISFIL - LOT 202  
MAY 9 2019

LOT / SITE

PURCHASER SIGNATURE



APPLIANCE ACKNOWLEDGEMENT

- ▶ NOTE: Any upgraded appliances are to be paid by the Purchaser, directly to the appliances company.
- ▶ Additional charges to the Purchaser may apply for cabinetry, electrical and plumbing in order to accommodate the specs given by the homeowner.
- ▶ It is the Purchaser's responsibility to provide Zancor Homes with the correct specification for each appliance where it exceeds the standard openings. Zancor Homes will not be responsible for appliances not fitting due to late changes.
- ▶ It is the Purchaser's responsibility to coordinate delivery, installation and hook up of appliances and to ensure they are installed as per Manufacturer's specifications after closing.
- ▶ Standard appliance openings are approximate and the minimum required. Sizes may vary due to onsite condition and/or when modifications have been made to the cabinetry.

STANDARD OPENINGS ACCEPTED BY PURCHASER:

HOMEOWNER SIGNATURE

Fridge ▶ 36" (+/-) x 74" (+/-)

\*\*Space above the fridge is required due to proper air flow

Stove ▶ 30"

Dishwasher ▶ 24"

Hood Fan Opening ▶ 30"

Hood fan Vent ▶ 6"

Appliance Specs are DUE (if not received during appointment)  
2 WEEKS FROM SIGNED DATE ABOVE  
\*\*\* Specs that require changes/modifications after this date will not be accepted \*\*\*

UPGRADE APPLIANCE OPENING REQUIREMENTS:

HOMEOWNER SIGNATURE

- FRIDGE
- ☒ Built-In
  - ☐ Paneled / Integrated
  - ☐ Flush Inset
  - ☐ Water Line Required

- RANGE
- ☐ 36"
  - ☐ 48"
  - ☐ Gas
  - ☒ Induction
  - ☐ Cooktop (Apron front)
  - ☒ Cooktop (Dropin)
- \*\*Cut-out charge required for cooktop

- HOOD FAN & VENT
- ☒ Under Cabinet
  - ☐ Chimney (centre vent)
  - ☐ Insert / Liner
  - ☒ 6 Inch
  - ☐ 8 Inch
  - ☐ 10 Inch

- WALL OVEN & MICRO
- ☒ Single Oven
  - ☐ Double Oven
  - ☐ Steam Oven
  - ☐ Warming Drawer
  - ☐ Over the Range Microwave
  - ☒ Built-in Microwave (\*trim kit required)
- DAVIDE

DATE MAY 9 2019 SITE INNISFIL PHASE 2 LOT 202

\*\* Any upgrades checked in this appliance form must be accompanied with specs provided by the Purchaser.  
It is the responsibility of the trades to inform the Builder of any discrepancies with specs, sketches, extras and/or colour chart PRIOR to production/installation. \*\*



INTERIOR FINISHES ACKNOWLEDGEMENT / WAIVER

Purchaser accepts and acknowledges that the Builder reserves the right to substitute materials with those of equal or better quality where the manufacture, scheduling or delivery of materials may directly impact the Builder's ability to meet its' contractual obligations under the Agreement of Purchase and Sale.

**UPGRADES/EXTRAS:** All upgrades and additional selections indicated on the colour chart must be accompanied by an upgrades/extras sheet (PES) and full payment otherwise the selection will be invalid. All colour charts and upgrades/extras will not proceed until verified and signed by an authorized signing officer at the Vendor's head office.  
**CHANGES WILL NOT BE PERMITTED UPON COMPLETION AND SUBMISSION OF THE COLOUR CHART.**

**PORCELAIN & NATURAL STONES:** Due to the properties of natural stones including but not limited to **marble, granite, quartz**, no two pieces are exactly the same. Variations in colour, tone, granularity (pitting, fissures) and pattern are to be expected, including various lighting may affect the overall finished look. Stone tops are sealed at time of installation and should never be cleaned with lemon oil or vinegar. Stones are porous materials, therefore any spilled substance require immediate attention. Stone countertops require regular seal re-application as part of home maintenance. Purchaser acknowledges colour and product variations as well as natural imperfections may exist with the selection of natural stone materials and shall not hold the Vendor liable for provision of same.

**STONE COUNTERTOP JOINTS:** Purchaser is aware that one joint will be at each corner and on either side of slide-in-range (if applicable). It will also be where the length of the counter top exceeds the length of a stone slab. Slabs are usually approximately 5' x 8'.

**CERAMIC TILES:** Due to manufacturing, shade (dye lots), product variations may exist that can affect the overall look of the finished product. Although every effort will be made to ensure the colours and materials selected are as close as possible to the samples, the purchaser acknowledges that the sample tiles supplied in the Design Centre may not be identical to the materials installed in the home.

**STAIR STAINS:** Due to the natural properties of wood, many variables can affect the overall look of the finished product. Factors including but not limited to wood type, knotting, graining, density, age, humidity, and air temperature can result in substantial variations in stain intensity. The purchaser accepts that although the Vendor will do their best to match stain the unfinished stairs as close as possible to the pre-finished floors, it is not possible to have an identical match and that there MAY be shade differences between the two products.

**CABINETRY:** Due to the natural properties of wood, slight variations apparent with cabinetry are to be expected. This includes but not limited to wood species, wood grain, colour, finish, product variations, and natural imperfections are all factors that may affect the overall look of the finished product. Such factors make exact colour matching impossible. The type and intensity of lighting in the areas of designated cabinetry placement may also highlight characteristics of cabinetry finish. All cabinets shall be finished with a white melamine interior box unless a finished interior is upgraded. Due to building specifications and/or on-site conditions, certain cabinetry upgrades may not be possible. The purchaser acknowledges that the Builder cannot guarantee the cabinetry finish or provision of certain upgrades and shall not hold the Builder liable for provision of same.

**UPGRADES/EXTRAS:** All upgrades and additional selections indicated on the colour chart must be accompanied by an upgrades/extras sheet (PES) and full payment otherwise the selection will be invalid. All colour charts and upgrades/extras will not proceed until verified and signed by an authorized signing officer at the Vendor's head office.  
**CHANGES WILL NOT BE PERMITTED UPON COMPLETION AND SUBMISSION OF THE COLOUR CHART.**

**HARDWOOD / LAMINATE FLOORING:** Due to the properties of wood and laminate, many variables can affect the overall look of the finished product. Variations include but not limited to wood type or laminate finish, colour/stain and wood grain are significant factors that make exact colour matching impossible. The purchaser acknowledges that the hardwood flooring is a pre-finished product in a controlled environment. Expansion, compression and cupping are characteristics of hardwood flooring once installed in the home. The purchaser acknowledges these may become apparent over time and despite the Builders' efforts to install the hardwood flooring materials in keeping with good workmanship, the Builder shall not be responsible nor held liable for minor variances of fluctuation in hardwood flooring materials.

**HARDWOOD / LAMINATE WAIVER:**

I/We understand hardwood flooring is classified as a porous material and as such not recommended by the Builder in certain areas. I/We understand there is a concern due to possible water and other substances being frequently splashed or spilled onto the floor and in contravention of Ontario Building Code Section 9.30.1.2(1).

***"Finished flooring bathrooms, kitchens, public entrance halls, laundry & general storage areas shall consist of resilient flooring, felted-synthetic-fibre floor coverings, concrete, terrazzo, ceramic tile, mastic or other types of flooring providing similar degrees of water resistance."***

I/We are prepared to assume full responsibility for any damage caused to the hardwood floor or subfloor due to moisture absorbency in the mentioned areas, and agree to waive any claims against the Township of residence, TARION and/or the Builder in relation to the matter.

**\*\*SEE COLOUR CHART FOR LOCATIONS\*\***

SITE **INNISFIL PHASE 2** LOT **202** DATE **MAY 9 2019**



**Trung Ly**

Lot 202 Belle Aire Shores, Innisfil

202  
Innisfil  
May 9/19


Prepared by  
Wayne Wanmaker  
COAST APPLIANCES  
[wwanmaker@coastappliances.com](mailto:wwanmaker@coastappliances.com)

**Whirlpool**  
CANADA



# Jenn-Air® 48-Inch Built-In Side-by-Side Refrigerator with Water Dispenser

JS48SSDUDE



This Jenn-Air® built-in side-by-side refrigerator features our exclusive Obsidian interior that complements the convenient side-by-side design and exceptional food preservation. It also features an in-door water dispenser for ice and filtered water. This model is available in Euro-Style Stainless (JS48SSDUDE) and Pro-Style Stainless (JS48PPDUDE) exterior design styles.

## Top Features

**Obsidian Interior**  
Exclusive Obsidian interior dazzles guests as food item colors "pop", even in matching crisp drawers and the freezer.

**Integrated Cubed/Crushed Ice and Water Dispenser**  
Delivers the convenience of through-the-door ice and water with a design that complements the refrigerator's built-in exterior.

**Precision Temperature Management™ System**  
A sensor-controlled system that uses a variable-speed compressor with an independent sensor in each compartment to monitor and adjust temperatures.

**Advanced Climate Control Drawer**  
A dedicated storage drawer with electronic control which provides precise, independent temperature control for sensitive foods.

**Produce Preserver**  
Delays over-ripening\* of certain fruits and vegetables by absorbing ethylene gas. \*Based on commonly purchased produce.

| Dimensions                     |          | Performance                    |   |
|--------------------------------|----------|--------------------------------|---|
| Depth                          | 27 3/4   | Freezer Capacity               | 10.30                                       |
| Height                         | 83 3/8   | Refrigerator Capacity          | 19.20                                       |
| Width                          | 48 3/8   | Energy Star® Qualified         | ENERGY STAR® Qualified                      |
| Cutout Depth                   | 24       | Refrigerator Features          |   |
| Cutout Height                  | 84       |                                |   |
| Cutout Width                   | 47 1/2   |                                |   |
| Height To Top Of Cabinet       | 83 3/8   | Humidity-Controlled Drawers    | No  |
| Depth With Door Open 90 Degree | 50 13/16 | Number of Interior Shelf(s)    | 4   |
| Depth Excluding Handles        | 25 1/8   | Temperature-Controlled Drawers | 1 Full-Width                                |
| Depth Closed Including Handles | 27 3/4   | Door Bins                      | 1 Fixed Full-Width, 3 Adjustable Full-Width |
| Width with Doors Closed        | 48 3/8   |                                |   |

Available Finishes/Colours



Manuals & Literature:

- Use and Care
- Energy Guide
- Warranty
- Dimension Guide
- Installation Instructions

COAST APPLIANCES  
Wayne Wanamaker  
wwanamaker@coastappliances.com

#1-1748 Creditstone Rd  
Vaughan, ON L4K 5V8

2022  
May 9/19



Because Whirlpool Corporation policy includes a continuous commitment to improve our products, we reserve the right to change materials and specifications without notice. Dimensions are for planning purposes only. For complete details, see Installation Instructions packed with product. Specifications subject to change without notice.



Jenn-Air® Euro-Style 36" Induction Cooktop

JIC4536XS

This induction cooktop offers precise temperature control and heats up more quickly than a traditional gas or electric cooktop. Energy transfers heat directly to cookware, turning it into the heat source, while the surface remains cool to the touch. This cooktop pairs beautifully with appliances in our Euro Style suite.

Top Features

**Industry's Most Powerful Induction Element<sup>1</sup>**  
Our newest induction cooktops feature the industry's most powerful induction element<sup>1</sup>, delivery fast & consistent results.

**Induction Technology**  
Cooks like gas, looks like electric, outperforms both. By converting cookware into the heat source, induction technology gives you fast, efficient and outstanding cooking power.

**Sensor Bolt Function**  
This intuitive option selects the optimal power level to quickly bring water to a boil, beeps when it reaches the boiling point, then adjusts the power level to minimize the possibility of boiling over.

**Keep Warm™ Function**  
One of the Low Settings, each element features a Keep Warm™ Function which may be used to keep cooked food or delicate sauces warm until you're ready to serve. Having the function available on each element allows you to cook and warm food on the same element.

Dimensions

|              |         |
|--------------|---------|
| Depth        | 21 5/16 |
| Height       | 3 3/8   |
| Width        | 36 5/16 |
| Cutout Depth | 19 1/4  |
| Cutout Width | 33 1/8  |


Performance

|                       |                    |
|-----------------------|--------------------|
| Fuel Type             | Electric Induction |
| Design                |                    |
| Hot Surface Indicator | Yes                |

Available Finishes/Colours

-  JIC4536XB  
Black
-  JIC4536XS  
Stainless Steel

Manuals & Literature:

-  CAD Image
-  Dimension Guide
-  Installation Instructions
-  Warranty
-  Use and Care
-  Google Sketch
-  Other

50 MW

2022  
May 9/19

COAST APPLIANCES

Wayne Wanamaker  
wwanamaker@coastappliances.com

#1-1748 Creditstone Rd  
Vaughan, ON L4K 5V8






JENN-AIR® DETAILED PLANNING DIMENSIONS

36" INDUCTION COOKTOP  
JIC4536X – 36<sup>5</sup>/<sub>16</sub>" x 4<sup>1</sup>/<sub>8</sub>" x 21<sup>3</sup>/<sub>16</sub>"

PRODUCT DIMENSIONS




TOP VIEW

| MODEL # |  | JIC4536X   |      |
|---------|--|--|------|
| A       | Overall width  | in   | cm   |
| B       | Overall depth  | 36 <sup>5</sup> / <sub>16</sub>                                    | 92.0 |
| C       | Width of recessed cooktop  | 21 <sup>3</sup> / <sub>16</sub>                                    | 54.1 |
| D       | Height of recessed cooktop   | 32 <sup>1</sup> / <sub>2</sub>                                     | 82.6 |
| E       | Recessed height including front flange                             | 3 <sup>1</sup> / <sub>8</sub>                                      | 8.0  |
| F       | Height of cooking surface<br>Euro-Style Stainless (including trim) | 3 <sup>7</sup> / <sub>8</sub>                                      | 9.8  |
| G       | Depth of recessed cooktop  | Height of cooking surface<br>Euro-Style Stainless (including trim) |      |
|         |  | 1 <sup>1</sup> / <sub>4</sub>                                      | 0.6  |
| H       | Recessed height including electrical conduit                       | 1 <sup>1</sup> / <sub>8</sub>                                      | 0.4  |
| G       | Depth of recessed cooktop  | 18 <sup>7</sup> / <sub>8</sub>                                     | 47.9 |
|         |  | 4 <sup>1</sup> / <sub>8</sub>                                      | 10.5 |



FRONT VIEW



SIDE VIEW


**IMPORTANT:** Dimensional specifications are provided for planning purposes only.  
Do not make any cutouts based on this information. Refer to the Installation or Use & Care Guide before selecting cabinetry, verifying electrical/gas connections, making cutouts or beginning installation.  
All Jenn-Air® appliances are appropriately UL, CUL or CSA approved.

202

JENN-AIR® DETAILED PLANNING DIMENSIONS

36" INDUCTION COOKTOP  
JIC4536X – 36<sup>5</sup>/<sub>16</sub>" x 4<sup>1</sup>/<sub>8</sub>" x 21<sup>5</sup>/<sub>16</sub>"

OPENING/CLEARANCE DIMENSIONS



| MODEL # | JIC4536X  |     |      |
|---------|---|-----|------|
|         | in  | cm  |      |
| A       | Width of combustible area above cooking surface (min.)  | 33⅓ | 84.0 |
| B       | Width from cooktop to fixed wall or other combustible material (min.)   | 1   | 2.5  |
| C       | Width to outer edge of outlet (min.)  | 10  | 25.4 |
| D*      | Height to bottom of uncovered wood or metal cabinet above cooking surface (min.)  | 30  | 76.2 |
| E       | Height to bottom of uncovered wood or metal cabinet (min.)  | 18  | 45.7 |
| F       | Required height of ventilation opening in front cabinet under countertop for proper ventilation – full width of cooktop | ¾   | 0.5  |
| G       | Height to top edge of outlet (min.)   | 12  | 30.5 |
| H       | Depth of upper cabinet (recommended)  | 13  | 33.0 |
| I       | Depth from cutout to wall (min.)  | 1   | 2.5  |
| J       | Width of cutout   | 33⅓ | 84.0 |
| K       | Depth of cutout   | 19⅓ | 49.0 |
| L       | Depth from cutout to front of countertop  | 2   | 5.1  |
| e       | Recommended electrical access location  |     |      |

\*Dimension can be reduced by 6" (15.2 cm) when bottom of wood or metal cabinet is covered by not less than 1/4" (0.6 cm) flame retardant millboard covered with not less than No. 28 MSG sheet metal, 0.015" (0.4 mm) stainless steel, 0.024" (0.6 mm) aluminum or 0.020" (0.5 mm) copper.


If installing a hood or microwave hood combination above the cooktop, follow the hood or microwave hood combination instructions for dimensional clearances above the cooking surface.

ELECTRICAL REQUIREMENTS


240 volt, 60 Hz, AC only, 50-amp fused, grounded circuit is required. A dedicated circuit is recommended. The length of conduit provided is for serviceability to the cooktop.

LOCATION REQUIREMENTS

- To ensure cooktop base clearance, cabinet side walls need to be wider than the cutout.
- If cabinet has a drawer, allow a 5<sup>1</sup>/<sub>16</sub>" (13.0 cm) minimum clearance between countertop and top of drawer.



SIDE VIEW



TOP VIEW – CUTOUT


**IMPORTANT:** Dimensional specifications are provided for planning purposes only. Do not make any cutouts based on this information. Refer to the Installation or Use & Care Guide before selecting cabinetry, verifying electrical/gas connections, making cutouts or beginning installation. All Jenn-Air® appliances are appropriately UL, CUL or CSA approved.

50 AMP



Jenn-Air® 30" Single Wall Oven with  
MultiMode® Convection System

JJW2430DS



Offering 5.0 cubic feet of oven capacity, this Jenn-Air® single wall oven achieves beautiful baking, broiling and roasting results with the MultiMode® convection system. A 4.3-inch full color menu-driven LCD display effortlessly guides through oven settings, and rapid preheat allows for a fast preheat when cooking with two oven racks. This wall oven pairs beautifully with appliances in our Euro Style suite.

Top Features

**MultiMode® Convection System**  
Three radiant elements provide consistent heat on every rack for evenly browned, perfectly cooked dishes.

**4.3-Inch (10.9cm) Full Color Menu-Driven LCD Display**  
Allow the oven to guide you through its modes and functions with a brilliant, 4.3-inch full-color display. Controls outside of the LCD display light up or darken to show you relevant selections for intuitive navigation during use.

**Telescoping Glide Rack**  
This roll-out rack lets you easily position and remove dishes.

**Rapid Preheat**  
This convenient oven mode reduces the amount of preheat time while allowing you to bake on up to two oven racks.

**Common Cutout¹**  
Our double and single wall ovens fit into the existing cutout for nearly every competitor's wall oven. Each oven fits into the smallest cutout, while its overall height also allows you to cover the remaining gap in the tallest cutout.

Manuals & Literature:

- CAD Image
- Dimension Guide
- Installation Instructions
- Use and Care
- Google Sketch
- Warranty

Dimensions

|               |        |
|---------------|--------|
| Depth         | 23 1/8 |
| Height        | 29 7/8 |
| Width         | 30     |
| Cutout Depth  | 24     |
| Cutout Height | 28     |
| Cutout Width  | 28 1/2 |

Oven Features

|                          |            |
|--------------------------|------------|
| Bake Element Power       | 2800W      |
| Broiler Element Power    | 4000W      |
| Convection Element Type  | Single-Fan |
| Convection Element Power | 3200       |
| Number of Oven Lights    | 2          |

Configuration and Overview

|                     |            |
|---------------------|------------|
| Oven Type           | Single     |
| Fuel Type           | Electric   |
| Oven Cooking System | Convection |

|                     |           |
|---------------------|-----------|
| Door Broil Position | Closed    |
| Interior Coating    | Porcelain |
| Interior Color      | Black     |
| Oven Rack 1 Type    | Standard  |

|       |     |
|-------|-----|
| CUL   | Yes |
| UL    | UL  |
| Amps  | 20  |
| Hz    | 60  |
| Volts | 240 |

Oven Features

|                     |     |
|---------------------|-----|
| Hidden Bake Element | Yes |
|---------------------|-----|

2020/01/19  
Mark

COAST APPLIANCES  
Wayne Wanamaker  
wwanamaker@coastappliances.com

#1-1748 Creditstone Rd  
Vaughan, ON L4K 5V8




Because Whirlpool Corporation policy includes a continuous commitment to improve our products, we reserve the right to change materials and specifications without notice. Dimensions are for planning purposes only. For complete details, see Installation Instructions packed with product. Specifications subject to change without notice.


JENN-AIR® DETAILED PLANNING DIMENSIONS

30" SINGLE WALL OVENS  
~~JMW3430D~~, JMW2430D – 30" x 29<sup>5</sup>/<sub>16</sub>" x 25<sup>5</sup>/<sub>16</sub>"

PRODUCT DIMENSIONS



FRONT VIEW



TOP VIEW

| MODEL # |  | JMW3430D<br>JMW2430D            |       |
|---------|--|---------------------------------|-------|
|         |  | in                              | cm    |
| A       | Overall width                                |                                 |       |
|         | Pro-Style® Stainless or Euro-Style Stainless | 30                              | 76.2  |
|         | Floating Glass                               | 29 <sup>5</sup> / <sub>16</sub> | 76.1  |
| B       | Height of control panel                      | 5 <sup>1</sup> / <sub>2</sub>   | 14.0  |
| C       | Space between control panel and door         | 7 <sup>1</sup> / <sub>16</sub>  | 1.1   |
| D       | Height to top of handle                      |                                 |       |
|         | Pro-Style® Stainless                         | 21 <sup>1</sup> / <sub>16</sub> | 55.0  |
|         | Euro-Style (color-coordinating)              | 21 <sup>7</sup> / <sub>16</sub> | 54.4  |
| E       | Height of door                               | 22 <sup>1</sup> / <sub>16</sub> | 56.2  |
| F       | Height of trim                               | 1 <sup>1</sup> / <sub>16</sub>  | 4.3   |
| G       | Overall height                               | 29 <sup>7</sup> / <sub>16</sub> | 75.8  |
| H       | Width of recessed oven                       | 28 <sup>7</sup> / <sub>16</sub> | 72.2  |
| I       | Width of conduit channel                     | 3 <sup>5</sup> / <sub>16</sub>  | 8.8   |
| J       | Depth of recessed oven                       | 23 <sup>1</sup> / <sub>16</sub> | 58.7  |
| K       | Depth with door                              | 24 <sup>5</sup> / <sub>16</sub> | 61.8  |
| L       | Depth with handle                            |                                 |       |
|         | Pro-Style® Stainless                         | 26 <sup>5</sup> / <sub>16</sub> | 66.9  |
|         | Euro-Style (color-coordinating)              | 25 <sup>5</sup> / <sub>16</sub> | 64.3  |
| M       | Depth with door fully open                   | 45 <sup>3</sup> / <sub>16</sub> | 115.3 |

702


**IMPORTANT:** Dimensional specifications are provided for planning purposes only.  
Do not make any cutouts based on this information. Refer to the Installation Guide before selecting cabinetry, verifying electrical/gas connections, making cutouts or beginning installation.  
All Jenn-Air® appliances are appropriately UL, CUL or CSA approved.



JENN-AIR® DETAILED PLANNING DIMENSIONS

30" SINGLE WALL OVENS  
~~JJW3430D~~ JJW2430D – 30" x 29<sup>7</sup>/<sub>8</sub>" x 25<sup>5</sup>/<sub>16</sub>"

DIMENSIONS AS INSTALLED



| MODEL # |   | JJW3430D                        | JJW2430D |
|---------|---|---------------------------------|----------|
| A       | Height to top of handle<br>Pro-Style® Stainless                       | 22 <sup>3</sup> / <sub>4</sub>  | 57.8     |
|         | Euro-Style<br>(color-coordinating)                                    | 22 <sup>9</sup> / <sub>16</sub> | 57.3     |
| B       | Height of trim extending<br>below cutout                              | 1 <sup>1</sup> / <sub>8</sub>   | 2.9      |
| C       | Height from top of recessed<br>oven to top of control panel           | 2 <sup>1</sup> / <sub>2</sub>   | 6.3      |
|         | JJW2430D  | 2 <sup>15</sup> / <sub>16</sub> | 7.4      |
| D       | Height from bottom of<br>recessed oven foot to bottom<br>of oven vent | 3 <sup>1</sup> / <sub>8</sub>   | 0.5      |
| E       | Height of recessed oven   | 26 <sup>3</sup> / <sub>4</sub>  | 67.9     |
| F       | Height to top of control panel  | 29 <sup>7</sup> / <sub>8</sub>  | 75.8     |
| G       | Depth with door fully open  | 45 <sup>3</sup> / <sub>8</sub>  | 115.3    |
| H       | Depth with handle<br>Pro-Style® Stainless                             | 26 <sup>5</sup> / <sub>16</sub> | 66.9     |
|         | Euro-Style<br>(color-coordinating)                                    | 25 <sup>5</sup> / <sub>16</sub> | 64.3     |
| I       | Depth with door   | 24 <sup>3</sup> / <sub>16</sub> | 61.8     |
| J       | Depth of recessed oven  | 23 <sup>1</sup> / <sub>16</sub> | 58.6     |

202


**IMPORTANT:** Dimensional specifications are provided for planning purposes only.  
Do not make any cutouts based on this information. Refer to the Installation Guide before  
selecting cabinetry, verifying electrical/gas connections, making cutouts or beginning installation.  
All Jenn-Air® appliances are appropriately UL, CUL or CSA approved.

JENN-AIR® DETAILED PLANNING DIMENSIONS

30" SINGLE WALL OVENS

~~JJW3430D~~, JJW2430D – 30" x 29⅞" x 25⅝"

OPENING/CLEARANCE DIMENSIONS



| MODEL # | <del>JJW3430D</del><br>JJW2430D                      |                |
|---------|--|----------------|
| A       | Width of cabinet (min.)                              | 30 in 76.2 cm  |
| B       | Width of cutout                                      | 28⅞ in 72.4 cm |
| C*      | Height of cutout (recommended)                       | 28 in 71.2 cm  |
| D       | Top of cutout to bottom of upper cabinet door (min.) | 2⅜ in 5.5 cm   |
| E       | Bottom of cutout to top of lower cabinet door (min.) | 1½ in 3.8 cm   |
| F       | Bottom of cutout to floor                            | 32 in 81.3 cm  |
| G       | Depth of cutout (min.)                               | 24 in 61.0 cm  |
| H       | Top of countertop to bottom of cutout (min.)         | 30⅜ in 76.7 cm |
| I       | Top of cutout to underside of countertop (min.)      | 1½ in 3.8 cm   |
| J       | Bottom of cutout to floor                            | 4⅝ in 11.0 cm  |
| e       | Recommended junction box location                    |                |

\*Will fit cutout height from 26⅜" (68.4 cm) to 29⅞" (74.8 cm).

ELECTRICAL REQUIREMENTS



240 volt, 20-amp fused, grounded circuit is required. A dedicated circuit is required.

The length of conduit provided is for serviceability. Do not cut the conduit. The junction box should be located 3" (7.6 cm) maximum below the support surface. Drill a 1" (2.5 cm) minimum diameter hole in the right rear or left rear corner of the support surface for access to the junction box.

NOTE: For under counter installation, the junction box should be located in the adjacent right or left cabinet. Drill a 1" (2.5 cm) minimum diameter hole in an upper corner of the side wall for access to the junction box.

CABINET REQUIREMENTS

NOTE: When using under counter installation, check cabinet manufacturer's specifications to verify fit.



UNDER COUNTER INSTALLATION  
(without cooktop installed above)

BACK VIEW


**IMPORTANT:** Dimensional specifications are provided for planning purposes only. Do not make any cutouts based on this information. Refer to the Installation Guide before selecting cabinetry, verifying electrical/gas connections, making cutouts or beginning installation. All Jenn-Air® appliances are appropriately UL, CUL or CSA approved.

202

JENN-AIR® DETAILED PLANNING DIMENSIONS

30" SINGLE WALL OVENS – FLUSH INSTALLATION  
JMW3430D, JWW2430D – 30" x 29 7/8" x 24 3/16" (depth without handle)

OPENING/CLEARANCE DIMENSIONS



| MODEL # | JMW3430D<br>JWW2430D                        | in        | cm         |
|---------|---|-----------|------------|
| A       | Width of flush inset cutout (min.)          | 30 1/4    | 76.8       |
| B       | Width of opening (min.)                     | 28 7/8    | 73.3       |
| C       | Height of flush inset cutout (min.)         | 30 7/16   | 77.3       |
| D       | Height of opening (min.)                    | 29 11/16  | 75.4       |
| E       | Bottom of cutout to floor                   | 4 5/8- 32 | 11.7- 81.3 |
| F       | Depth of cutout (min.)                      | 25        | 63.5       |
| G       | Bottom of cutout to floor for under counter | 4 1/16    | 10.3       |
| e       | Recommended junction box location           |           |            |

ELECTRICAL REQUIREMENTS

240 volt, 20-amp fused, grounded circuit is required. A dedicated circuit is required.  
The length of conduit provided is for serviceability. Do not cut the conduit. The junction box should be located 3" (7.6 cm) maximum below the support surface. Drill a 1" (2.5 cm) minimum diameter hole in the right rear or left rear corner of the support surface for access to the junction box.


NOTE: For under counter installation, the junction box should be located in the adjacent right or left cabinet. Drill a 1" (2.5 cm) minimum diameter hole in an upper corner of the side wall for access to the junction box.

FLUSH INSTALLATION REQUIREMENTS



A 25" (63.5 cm) minimum cutout depth is required. These dimensions will result in a 1/8" (0.6 cm) reveal on the top, a 1/4" (0.6 cm) reveal on the sides and a 1/8" (0.3 cm) reveal on the bottom of the wall oven.  
The front face of the cleats and spacers will be visible and should be treated as a finished surface.

CABINET REQUIREMENTS

NOTE: When using under counter installation, check cabinet manufacturer's specifications to verify fit.



UNDER COUNTER INSTALLATION  
(without cooktop installed above)



\* Cleats and spacers must be recessed 1 3/8" (3.5 cm) from the front of the cabinet.

**IMPORTANT:** Dimensional specifications are provided for planning purposes only. Do not make any cutouts based on this information. Refer to the Installation Guide before selecting cabinetry, verifying electrical/gas connections, making cutouts or beginning installation. All Jenn-Air® appliances are appropriately UL, CUL or CSA approved.

2022



## Jenn-Air® 36" Professional Low Profile Under Cabinet Hood

JXU9136HP

Target cooking grease, smoke and odors with a vent that fits the way you cook. Professional Stainless wall-mount hoods feature commercial styling and performance and are designed to meet the demand of high-powered commercial-style cooking surfaces/burners.



### Available Finishes/Colours

- JXU9136HP
- Stainless Steel

### Top Features

**Velocity Blower**  
Encounter an aura of clean air as smoke and steam are vanquished by the power of the 600 CFM blower.

**3 1/4" x 10" Rectangular Exterior Venting**  
The 3 1/4" x 10" rectangular exterior ventilation system allows ductwork to extend through an outer wall or the roof of a home.

**Radiant Until Ready**  
Dishes stay primed under restaurant-inspired lamps. Intensity visual impact by pairing with our professional-style backslashes, including those with shelves.

**Dishwasher-Safe Stainless Steel Baffle Filters**  
These stainless steel baffle filters, which effectively capture smoke, grease and cooking odors as they're drawn through the hood, can be easily cleaned in the dishwasher.

**Dual Lighting Levels**  
For precision. For ambience. Two brightness options let you control the mood as you cook.

### Dimensions

|        |      |
|--------|------|
| Depth  | 23   |
| Height | 10   |
| Width  | 3036 |

### Configuration and Overview

|              |               |
|--------------|---------------|
| Hood Type    | Under Cabinet |
| Fan CFM      | 600           |
| Venting Type | Exterior      |

### Controls

|                  |         |
|------------------|---------|
| Number of Speeds | 4       |
| Task Light       | Halogen |

as per 6" Vent.  
Coast

202  
May 9/17

**COAST APPLIANCES**  
Wayne Wanamaker  
wwanamaker@coastappliances.com

#1-1748 Creditstone Rd  
Vaughan, ON L4K 5V8

Page 6 of 6



Because Whirlpool Corporation policy includes a continuous commitment to improve our products, we reserve the right to change materials and specifications without notice. Dimensions are for planning purposes only. For complete details, see installation instructions packed with product. Specifications subject to change without notice.





Jenn-Air® 24" Euro-Style TriFecta™  
Dishwasher, 38 dBA

JDTSS244GS

Inside, a storm rages, as relentless power and technology bring every dish and glass to a state of refined clean. Outside, tranquility, with sleek lines wrapped in high design. Experiential ease. Tech connected. This is the quietest luxury dishwasher brand—period.


Top Features

**38 dBA Tranquility¹**  
Listen to the hush. At 38 dBA, JennAir is the quietest luxury dishwasher brand, all without sacrificing performance.

**TriFecta™ Wash System**  
No need to choose between brilliant cleaning, energy efficiency or quiet operation because our dishwashers deliver all three. Three-stage filtration, pressurized wash arms and alternating wash action in two zones work together to wash dishes with clean water.

**Remote Access**  
Remote start, Cycle monitoring. Connect to WiFi for real-time notifications and control your dishwasher from anywhere. Even download custom wash cycles directly to your appliance. Tap and swipe on both iOS and Android devices.²

**Smart Integration (U.S. Only)**  
(U.S. Only)



Available Finishes/Colours

JDTSS244GS  
Stainless Steel

Manuals & Literature:

- Use and Care
- Energy Guide
- Warranty
- Dimension Guide
- Installation Instructions

| Dimensions                     |                  |
|--------------------------------|------------------|
| Depth                          | 24 1/2           |
| Height                         | 34 1/2           |
| Width                          | 23 7/8           |
| Depth With Door Open 90 Degree | 49 1/2           |
| Carton Depth                   | 26 1/2           |
| Carton Height                  | 36 5/8           |
| Carton Width                   | 24 1/2           |
| Configuration and Overview     |                  |
| Number of Place Settings       | 14               |
| Control Type                   | Electronic Touch |
| Exterior Status Light          | White            |
| Sensor                         | Yes              |

| Configuration and Overview          |                         |
|-------------------------------------|-------------------------|
| Decibel Level (dBA)                 | 38                      |
| Dispensers                          | Detergent and Rinse Aid |
| Number of Wash Levels               | 5                       |
| Rinse Aid Dispenser Level Indicator | Yes                     |
| Sound Package                       | Yes                     |
| Controls                            |                         |
| Number of Wash Cycles               | 7                       |
| Adjustable Rack                     | 2 Position              |
| Cushion-Tip Trims                   | Yes                     |


2022  
May 9/11/19

COAST APPLIANCES  
Wayne Wanamaker  
wwanamaker@coastappliances.com

#1-1748 Creditstone Rd  
Vaughan, ON L4K 5V8



Because Whirlpool Corporation policy includes a continuous commitment to improve our products, we reserve the right to change materials and specifications without notice. Dimensions are for planning purposes only. For complete details, see Installation Instructions packed with product. Specifications subject to change without notice.



SHARP

SMD2477ASC  
24-INCH MICROWAVE DRAWER® OVEN

## TAKE YOUR MICROWAVE TO A BETTER PLACE

It's your kitchen, your design and your lifestyle. Sharp's Microwave Drawer Oven allows you to focus on the design elements you prefer by removing the microwave from sightlines and enabling more design versatility. The Microwave Drawer offers flexible placement options below an island, peninsula, or standard cabinetry and can also be installed adjacent to your wall oven. The Microwave Drawer allows you to showcase your design savvy and create a kitchen that flows with your lifestyle.

Sharp introduces the next generation of this successful appliance—model SMD2477ASC - a 24" microwave drawer with a simpler and a sleeker design to match more built-in appliances.

### Design Flexibility

Sharp's Microwave Drawer product expands the option for microwave placement in almost any kitchen plan—it's a perfect choice for open-plan kitchens, islands, peninsulas, and a great addition to wet bars, family rooms and home theatres.

### Location and Counter Space Saving

You may place the drawer under a counter, cooktop or wall oven or above a warming drawer without a built-in kit, additional trim or venting. Sharp microwave drawer provides the best solution for a cleaner, uncluttered counter space.

## Specifications

### TECHNICAL SPECIFICATIONS

|                                       |                      |
|---------------------------------------|----------------------|
| Size                                  | 24" wide             |
| Microwave Capacity                    | 1.2 cu.ft            |
| Microwave Power                       | 950 watts            |
| Control Panel                         | Digital LCD Display  |
| Control Type                          | Hidden Control Panel |
| Drawer Opening                        | AutoTouch™ System    |
| Power Level                           | 11                   |
| Sensor Cook, Reheat, Popcorn Settings | 13                   |
| Reheat Auto Settings                  | 2                    |
| Defrost Auto Settings                 | 6                    |
| Keep Warm Setting                     | Yes, up to 30 min.   |
| Melt / Soften / Settings              | Yes                  |
| Beverage Setting                      | Yes                  |
| Programmable Stages                   | Yes, 4               |
| Digital Clock                         | Yes                  |
| Kitchen Timer                         | Yes                  |
| Child Lock                            | Yes                  |
| +30 sec                               | Yes                  |
| Interior Oven Light                   | Yes                  |

### SHARP's Exclusive AutoTouch™ System

Sharp's exclusive AutoTouch™ system allows you to open and close the drawer automatically at one-finger operation by pressing a button on the control panel.

### New Hidden Control Panel

The new SMD2477ASC model features a hidden control panel which gives a more integrated look and feel within the kitchen. The new tall control panel, angled at 45° degrees, is easy to see, easy to access and easy to use.

### TECHNICAL SPECIFICATIONS CONTINUED

|                                |  |
|--------------------------------|--|
| Demonstration Mode             | Yes  |
| Built-In Ready                 | Yes  |
| Available Colour               | Stainless Steel  |
| Accessory                      | SKMD24F0AS   |
| DIMENSIONS/WEIGHT(inches/lbs.) |  |
| Cut-out Dimension              | 22 1/8" x 15 9/16"   |
| Product Dimension              | 23 1/8" x 23 1/4" x 15 7/8"  |
| Box Dimension                  | 29.8" w x 27.9" x 21.9"  |
| Net Weight                     | .74 lb.  |
| Gross Weight                   | 85.8 lb.   |
| POWER/SAFETY                   |  |
| Power / Ratings                | 120V, 60Hz   |
| Ratings                        | 1.67Kw, 14.5Amps   |
| Safety Compliance              | FCC, DHS, cUL  |
| WARRANTY/UPC                   |  |
| Warranty                       | 1 year parts & labour with in-home service; 4 additional years for magnetron tube only |

UPC


15044

074000619944

# SHARP

## SMD2477ASC

### Installation Guide



202  
May 9/19